



at a glance

RIEGL VMX-2HA



General Technical Data

VMX-CU Power Supply Input Voltage	11 - 15 V DC powered by on-board source (e.g. alternator) 11 - 15 V DC backup power
VMX-MH Input Voltage	24 V DC (powered via VMX-CU)
Typ. Power Consumption system operation without cameras additional power consumption per camera	typ. 250 W / max. 1020 W typ. 6 W / max. 34 W
Protection Class VMX-MH with camera system	IP64
Temperature Range VMX-MH with camera system Temperature Range VMX-CU	-10°C up to +40°C (operation) / -20°C up to +50°C (storage) 0°C up to +40°C (operation) / -20°C up to +50°C (storage)
Interface VMX-CU to VMX-MH	single main cable for power & data interface with robust Harting® connectors
Humidity	max. 80% non condensing @ +31°C
Weight (approx.)	
VMX-MH Measuring Head (without cameras)	39 kg
VMX-RM Roof Mount (including Thule wing bars with Thule mountings)	17.3 kg
VMX-2RM Roof Mount (including Thule wing bars with Thule mountings)	34 kg
VMX-MC Main Cable (5m length)	5 kg
VMX-CU Control Unit	25 kg
<i>RIEGL</i> cameras	
12 MP camera	1.65 kg
5 MP camera	1.25 kg
camera extension mounting pole	1.2 kg
FLIR Ladybug® 5+ camera (with cabling and mounting)	9 kg

Data Interfaces

VMX-MH Measuring Head
9 x multi-purpose ports supporting complementary camera systems and additional devices, each with - trigger pulse - precise time stamping of exposure pulse - NMEA data - PPS - LAN 1GigE - power 24V DC, max. 34 W
VMX-CU Control Unit
1 x DMI input (for distance measuring indicator; odometer) 1 x NAV RS-232 (COM port for IMU/GNSS for RTK, SBAS) 1 x AUX +12V DC 1 x touch screen incl. USB (for system operation) 1 x HDMI (additional video output) 1 x Display Port (additional video output) 2 x LAN, 1000 Mbit/sec (e.g. connect additional computer) 4 x USB 3.0 2 x USB 3.0 specific configuration for FLIR Ladybug® 5+ 4 x removable double SSD drive carrier with a of total 6TB swappable disc space wireless communication via Bluetooth, WLAN and LTE
VMX-MC Main Cable (single cable connection between VMX-MH and VMX-CU) with 10 GigE Link

Further Information



Copyright RIEGL Laser Measurement Systems GmbH © 2021 – All rights reserved. Use of this data sheet other than for personal purposes requires RIEGL's written consent. This data sheet is compiled with care. However, errors cannot be fully excluded and alternations might be necessary.

www.riegl.com

RIEGL VMX[®]-2HA



High-Speed 10 GigE Link
for acquisition of
2 million measurements/sec
and image data of up to
9 different high-end cameras

The RIEGL VMX-2HA is a High Speed, High Performance Dual Scanner Mobile Mapping System which provides dense, accurate, and feature-rich data at highway speeds. With 2 million measurements and 500 scan lines per second, this turn-key solution is ideally suited for survey-grade mobile mapping applications.

This powerful technology comprises two RIEGL VUX-1HA High Accuracy LiDAR Sensors and a high performance INS/GNSS unit, housed in an aerodynamically-shaped protective cover. A camera interface for up to 9 optional cameras enables complementation of the LiDAR data with precisely geo-referenced images.



High Speed, High Performance Dual Scanner Mobile Mapping System

Typical Applications

- Transportation Infrastructure Mapping
- Road Surface Measurement
- HD mapping for autonomous vehicles
- City Modeling
- Rapid Capture of Construction Sites and Bulk Material
- Open-Pit Mine Surveying
- GIS Mapping and Asset Management
- As-Built Surveying



www.riegl.com



RIEGL VMX-2HA Key Features

Proven System

The RIEGL VMX-2HA is the consistent further development of the compact RIEGL VMX Mobile Mapping System.

The alignment and placement of the two VUX-1HA (High Accuracy) scanners keeps within the proven VMX tradition with a simultaneous forward/backward looking to reduce scan shadows.

A compact dual scanner platform carries both, LiDAR sensors and a high-grade IMU/GNSS subsystem and provides an accurate and long-term stable system calibration.



VMX-2HA Scan Pattern

1 MHz program	pattern @ 3m distance		pattern @ 10m distance		pattern @ 50m distance		
platform speed	line spacing of a single scanner (mm)	point spacing within a scan-line of a single scanner (mm)	VMX-2HA point density (pts/m2)	point spacing within a scan-line of a single scanner (mm)	VMX-2HA point density (pts/m2)	point spacing within a scan-line of a single scanner (mm)	VMX-2HA point density (pts/m2)
platform speed 50km/h	56	4.7	7640	15.7	2300	78.5	458
platform speed 80km/h	89	4.7	4774	15.7	1432	78.5	286
platform speed 120km/h	133	4.7	3184	15.7	954	78.5	190

New Camera System and Features

The VMX-2HA impresses with an extremely enhanced camera performance and a number of new features. Camera interface and SYNC of up to 9 external devices are included in the basic system configuration. Multiple high-resolution RIEGL cameras allow for unique capture angles and a high degree of details in the images. The interface between the VMX-MH (Measuring Head) with scanners and cameras and the VMX-CU (Control Unit) was completely re-designed.



The VMX-CU (equipped with a high performance 7th generation Intel Core i7 processor) precisely controls management of power, data acquisition, and operation of the laser scanners, INS/GNSS sensors and the optional cameras.

A 10 GigE network and a set of SSD storage media with a total of 6 TB disk space enable big data handling for uninterrupted data recording of comprehensive missions.




The modular design of the system provides unique flexibility to meet a diversity of project requirements. Ready to be mounted on road and off-road vehicles, as well as on trains and boats, it provides the user with the technology and tools to ensure full data capturing for transportation infrastructure, facades, overhead structures, power lines, bridges, tunnels etc.

Seamless RIEGL Workflow

A handy touch-screen and the RIEGL data acquisition software facilitate the operator's task in the field by providing real-time visualization of acquired scan data and imagery. The RIEGL software packages also offer comprehensive features in data processing. This covers enhanced scan data adjustment to merge overlapping mobile scan data. Furthermore it enables the scan data to be fitted to specific control objects which results in a consistent point cloud of enhanced precision and increased geo-referenced accuracy. Finally, the precise geo-referenced scan data and high resolution (panorama) images can be exported to well-known file formats, or interfaced directly with third-party software.



RIEGL VMX-2HA Dimensions



RIEGL VMX-2HA Technical Data

- max. measurement range
- pulse repetition rate (peak)
- optional digital camera
- multiple target capability
- online waveform processing
- eye safe operation at Laser Class 1

VMX-2HA Scanner Performance

Laser Class	Laser Class 1 (Class 1 Laser Product according to IEC 60825-1:2014)			
Effective Measurement Rate ¹⁾	600 kHz	1 MHz	1.5 MHz	2 MHz
Max. Range, Target Reflectivity $\rho \geq 80\%$ ^{2) 3)}	420 m	330 m	270 m	235 m
Max. Range, Target Reflectivity $\rho \geq 10\%$ ^{2) 3)}	150 m	120 m	100 m	85 m
Max. Number of Targets per Pulse	practically unlimited (details on request)			
Minimum Range	1.2 m			
Accuracy ^{4) 6)} / Precision ^{5) 6)}	5 mm / 3 mm			
Field of View	360° "full circle"			
Scan Speed (selectable)	up to 500 scans/sec			

1) Rounded values, selectable by measurement program.
 2) Typical values for average conditions. Maximum range is specified for flat targets with size in excess of the laser beam diameter, perpendicular angle of incidence, and for atmospheric visibility of 23 km. In bright sunlight, the max. range is shorter than under overcast sky.
 3) Ambiguity to be resolved by post-processing with RIUNITE software.
 4) Accuracy is the degree of conformity of a measured quantity to its actual (true) value.
 5) Precision, also called reproducibility or repeatability, is the degree to which further measurements show the same result.
 6) One sigma @ 30 m range under RIEGL test conditions.

IMU/GNSS Performance ⁷⁾

Position Accuracy (absolute)	typ. 20 - 50 mm
Roll & Pitch Accuracy	0.005°
Heading Accuracy	0.015°

7) One sigma values, no GNSS outage, with DMI option, post-processed using base station data.