

**ENGINEERING AND DESIGN REPORT**  
**B-18 CLASS I LANDFILL PHASE III EXPANSION AND FINAL CLOSURE**

**KETTLEMAN HILLS FACILITY**  
**KETTLEMAN CITY, CALIFORNIA**



**Prepared for:**  
**Chemical Waste Management, Inc.**  
**Kettleman Hills Facility**  
**35251 Old Skyline Road**  
**Kettleman City, California 93239**

**Prepared by:**



**230 Commerce, Suite 200**  
**Irvine, California 92602**

**November 2008**  
**Revision 1: February 2010**  
**Revision 2: August 2011**  
**083-91887**

**Golder Associates Inc.**

230 Commerce, Suite 200  
Irvine, California 92602  
Telephone (714) 508-4400  
Fax (714) 508-4401  
www.golder.com



**ENGINEERING AND DESIGN REPORT  
LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY  
KETTLEMAN CITY, CALIFORNIA**

*Prepared for:*

Chemical Waste Management, Inc.  
Kettleman Hills Facility  
35251 Old Skyline Road  
Kettleman City, California 93239

*Prepared by:*

Golder Associates Inc.  
230 Commerce, Suite 200  
Irvine, California 92602

Distribution:

10 copies – Chemical Waste Management, Inc.  
2 copies – Golder Associates Inc.

November 2008  
Revision 1: February 2010  
Revision 2: August 2011



Project No.: 083-91887

## TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 INTRODUCTION .....	1
1.1 Purpose of Report and Background Information.....	1
1.2 Landfill B-18 Design.....	1
1.3 Report Organization .....	3
2.0 SITE DESCRIPTION .....	5
2.1 General.....	5
2.2 Current Site Layout and Conditions.....	5
2.3 Pre-Development Site Conditions.....	6
2.4 Geologic Conditions.....	6
2.5 Design Ground Motions .....	7
2.5.1 General .....	7
2.5.2 Ground Motions Used in the Original Design.....	7
2.5.3 Ground Motions Used in the Current Design.....	7
2.6 Hydrogeology.....	8
3.0 GEOTECHNICAL INVESTIGATIONS.....	9
3.1 General.....	9
3.2 Field Investigations .....	9
3.2.1 Geotechnical Exploration Program .....	9
3.2.2 Clay Liner Test Pads .....	11
3.3 Site Subsurface Conditions.....	11
3.3.1 Surficial Soils .....	11
3.3.2 Bedrock Lithology, Structure, and Stratigraphy .....	12
3.4 Laboratory Investigations .....	13
3.4.1 Sample and Testing Selection Process .....	13
3.4.2 Prior (Pre-1990) Geotechnical Data .....	14
3.4.3 Laboratory Testing for Landfill Design .....	14
3.4.4 Special Testing of the Phases I and II Clay Borrow Material .....	15
3.5 Laboratory Testing Results.....	16
3.5.1 General .....	16
3.5.2 Index Property Tests.....	16
3.5.3 Compaction Tests.....	17
3.5.4 Strength Tests on Relatively Undisturbed Samples .....	18
3.5.5 Strength Tests on Remolded Samples .....	19
3.5.6 Permeability Tests .....	19
3.5.7 Consolidation Tests .....	20
3.5.8 Shrink/Swell Potential Tests .....	20
3.5.9 Geochemical Tests .....	20
3.6 Method 9090 (Liner/Leachate Compatibility Testing .....	21
4.0 LANDFILL B-18 DESCRIPTION.....	23
4.1 General.....	23
4.2 Phase I.....	26

**TABLE OF CONTENTS (continued)**

<u>SECTION</u>		<u>PAGE</u>
4.3	Phase II.....	28
4.4	Phase III.....	29
4.5	Final Closure.....	30
4.6	Clay Borrow Operations.....	32
	4.6.1 Phases I and II.....	32
	4.6.2 Phase III.....	33
4.7	Liner Systems.....	33
	4.7.1 General.....	33
	4.7.2 Liner System Configurations.....	34
	4.7.2.1 Base Liner.....	34
	4.7.2.2 Vadose Zone Trench.....	36
	4.7.2.3 Phases I and II Sideslope Liner.....	36
	4.7.2.4 Phase III Sideslope Liner.....	37
	4.7.2.5 Base to Sideslope Liner Transition.....	38
	4.7.2.6 Final Cover Liner.....	38
	4.7.3 Special Liner Details.....	38
	4.7.3.1 Sideslope Liner Anchor Trenches.....	38
	4.7.3.2 Temporary Phase I/II Transition Anchors.....	39
	4.7.3.3 Phases I and II Access Ramp Liner.....	40
4.8	Leachate Collection and Recovery System (LCRS).....	40
	4.8.1 General.....	40
	4.8.2 Primary LCRS.....	42
	4.8.3 Secondary LCRS.....	43
	4.8.4 Vadose Zone Collection System.....	44
	4.8.5 Leachate Storage.....	45
4.9	Surface Water Control.....	45
	4.9.1 Off-site Diversion of Run-On.....	46
	4.9.2 Active Area Run-Off Control for Phase I Operations.....	47
	4.9.3 Phase I Direct Rainfall Control.....	48
	4.9.4 Active Area Run-Off Control for Phase II Operations.....	48
	4.9.5 Phase II Direct Rainfall Control.....	49
	4.9.6 Run-Off Control During the Above Grade Filling Period.....	49
	4.9.7 Phase III Direct Rainfall Control.....	50
	4.9.8 Run-Off Control at Closure.....	50
4.10	Utilities.....	50
5.0	ENGINEERING ANALYSES.....	51
	5.1 General.....	51
	5.2 Settlement Analyses.....	51
	5.2.1 Conditions Evaluated.....	51
	5.2.2 Foundation Settlement.....	51
	5.2.3 Degree of Consolidation of Clay Liners.....	52
	5.2.4 Magnitude of Clay Liner Consolidation.....	52
	5.2.5 Post-Closure Waste Settlement.....	53

**TABLE OF CONTENTS (continued)**

<u>SECTION</u>	<u>PAGE</u>
5.3	Stability Analyses..... 54
5.3.1	General ..... 54
5.3.2	Temporary Rock Cut Slopes ..... 55
5.3.3	Compacted Fill Slopes ..... 56
5.3.4	Temporary Phase I Intermediate Fill Slopes ..... 56
5.3.5	Temporary Phase IIIA Intermediate Fill Slope ..... 57
5.3.6	Final Closure Conditions..... 58
5.4	Cover Soil Erosion ..... 60
5.5	Surface Water Drainage..... 60
5.5.1	General ..... 60
5.5.2	Phases I and II Run-On Control ..... 62
5.5.3	Phases I and II Run-Off Control..... 62
5.5.4	Phase III Run-on Control ..... 62
5.5.5	Phase III Run-Off Control..... 63
5.5.6	Closure Drainage..... 64
5.6	Leachate Collection and Removal ..... 64
5.7	Riser Pipe Designs..... 65
5.8	Cover Infiltration..... 66
5.9	Frost and Biotic Protection..... 67
6.0	REFERENCES ..... 68


## LIST OF TABLES

Table 3.1	Key Boring Information
Table 3.2	Matrix of Investigation Activity vs. Rock Structure
Table 3.3	Geotechnical Parameters from Prior (Pre-1990) Investigations
Table 3.4	Laboratory Tests of Boring Samples
Table 3.5	Laboratory Tests of Test Pit Samples
Table 3.6	Geotechnical/Geochemical Analysis Methods
Table 3.7	Summary of Plasticity Index Data by Stratigraphic Unit
Table 3.8	Percent Passing No. 200 Sieve
Table 3.9	Compaction Test Results (Modified Proctor)
Table 3.10	Summary of Permeability Tests
Table 3.11	Summary of Swell Test Results (Undisturbed Samples)
Table 3.12	Summary of Swell Test Results (Remolded Samples)
Table 3.13	Summary of Clay Source Evaluation – Pecten Claystone
Table 5.1	Material and Interface Properties Used for Stability Calculations
Table 5.2	Summary of Slope Stability Analyses
Table 5.3	Perimeter Run-On Diversion Ditch Flow and Capacity Summary
Table 5.4	Active Road Run-Off Control Summary
Table 5.5	Summary of Containment Basin Capacities
Table 5.6	Final Closure Run-Off Control Summary

## LIST OF FIGURES

Figure 1.1	Site Vicinity Map
Figure 2.1	Landfill B-18 Pre-Development Topography
Figure 2.2	Area Geologic Map
Figure 2.3	Site Geologic Map
Figure 3.1	Site Geologic and Exploration Map
Figure 3.2	Geologic Cross Sections
Figure 3.3	Plasticity Chart, Stratigraphic Unit 18-8
Figure 3.4	Grain Size Curve Envelopes
Figure 3.5	Material Water Content vs. Plasticity Index, Stratum 18-8
Figure 3.6	Summary of Direct Shear Test Results
Figure 5.1	Stability Considerations for Rock Cut Slopes
Figure 5.2	Stability Considerations for Phase I Intermediate Fill Slope
Figure 5.3	Potential Sliding Mechanisms for Phase IIIA Intermediate Fill Slope and Final Closure
Figure 5.4	Surface Water Drainage Area Map for Phases I and II
Figure 5.5	Surface Water Drainage Area Map for Phase III and Closure

## LIST OF APPENDICES

Appendix A	Construction Drawings
	A.1 Phase I and II
	A.2 Phase III
Appendix B	Boring Logs
Appendix C	Trench and Test Pit Logs
Appendix D	Laboratory Data
Appendix E	Clay Liner Test Pad Data
Appendix F	Liner System Material Data
Appendix G	Settlement Analyses
Appendix H	Stability Analyses
Appendix I	Soil Erosion Analyses
Appendix J	Surface Water Damage Analyses
Appendix K	LCRS Analyses 
Appendix L	Riser Pipe Analyses
Appendix M	Cover Infiltration Analyses
Appendix N	Frost and Biotic Protection Evaluation
Appendix O	Technical Specifications
Appendix P	CQA Plan

## 1.0 INTRODUCTION

### 1.1 Purpose of Report and Background Information

This report provides engineering data and analyses to support the Construction Drawings (Drawings), the Technical Specifications (Specifications), and the Construction Quality Assurance (CQA) Plans for Landfill Unit B-18 (B-18) at the Kettleman Hills Facility (KHF) in Kettleman City, Kings County, California. B-18 is located in the southeast portion of the KHF, as shown on Figure 1.1 and on the Site Location Map portion of Sheet T-1<sup>1</sup> in Appendix A.1.2

B-18 is an existing active Class I/II landfill that has been accepting waste continually since 1992. The existing B-18 landfill was constructed in two phases (Phases I and II), both of which were completed in the early 1990s. The design of Phases I and II of B-18 was completed by Environmental Solutions, Inc. (ESI) and was presented in the original Engineering and Design Report for B-18 (ESI, 1990a)<sup>2</sup>.

Chemical Waste Management, Inc. (CWM), the owner and operator of B-18, wishes to construct Phase III to expand B-18 to provide additional waste capacity. Hence, this report has been prepared to supersede and serve as an updated revision to the original ESI (1990a) Engineering and Design Report for B-18. The updates contained in this report pertain primarily to the proposed Phase III expansion of B-18 and to the revised final closure design for B-18. The contents of the original ESI (1990a) Engineering and Design Report have been preserved herein - as appropriate - such that this report should be used as a stand-alone reference for the entirety of the Landfill B-18 engineering and design.

Reduced-size copies of the Drawings for Phases I through III and final closure are included in Appendix A. The Specifications and CQA Plan for Phases I and II of B-18 were prepared as a separate document by ESI (1990b). The Specifications and CQA Plans for Phase III and final closure are included in Appendices O and P, respectively.

### 1.2 Landfill B-18 Design

As described in Section 1.1, ESI (1990a) designed the existing Phases I and II of B-18 while Golder Associates Inc. (Golder) designed the proposed Phase III expansion and the revised final closure configuration. Golder's design of Phase III and the final closure of B-18 is based largely on the design of the existing B-18 Phases I and II completed by ESI (1990a).

The design of B-18 described in this report follows the master plan for the KHF, including the approved Kings County Conditional Use Permit (CUP) requirements. A Subsequent Environmental Impact Report (SEIR) has been prepared in accordance with the California Environmental Quality Act (CEQA). The SEIR is currently under review and certification of the SEIR will be required prior to construction of B-18 Phase III. The B-18 design generally follows procedures used for prior KHF

---

<sup>1</sup> The term "Sheet" refers to the specific page of the Drawings in Appendix A

<sup>2</sup> References are provided in Section 6



waste management units (WMU) for land disposal and complies with the following regulatory documents:

- United States Environmental Protection Agency (USEPA) Draft Minimum Technology Guidance on Double Liner Systems (USEPA, 1985)<sup>3</sup>.
- USEPA Resource Conservation and Recovery Act (RCRA) Hazardous Waste Facility Permit, Part B (USEPA, 1990)<sup>4</sup>.
- USEPA PCB regulations for Chemical Waste Landfills, Code of Federal Regulations, Title 40, Section 761.75.
- California Department of Toxic Substances Control (DTSC) Hazardous Waste Facility (Part B) Permit (DTSC, 2003).
- DTSC Environmental Health Standards for the Management of Hazardous Waste, Title 22, Division 4.5 of the California Code of Regulations (CCR).
- California Regional Water Quality Control Board (RWQCB), Central Valley Region, Waste Discharge Requirements No. 98-058 (RWQCB, 1998).
- California State Water Resources Control Board and RWQCBs, Discharges of Hazardous Waste to Land, Title 23, Division 3, Chapter 15 of the CCR.
- Kings County Conditional Use Permit (CUP) No. 1412, Administrative Approval Nos. 90-23 and 90-24 for the B-18 Landfill Phases I and II (Kings County, 1990).
- Kings County CUP No. 05-10 (application under review).

The primary differences between the B-18 design and the design of prior (i.e., pre-1990) KHF landfill units are the use of textured high density polyethylene (HDPE) geomembrane and the avoidance of operating waste slopes directly on the base liner system. These changes improve stability conditions throughout the operating period. These design concepts were initiated in Phase I and continue through Phase III and Closure.

Key aspects of the B-18 design are:

- The facility is developed in three phases (see Sheet 2 in Appendix A.1 and Sheet C-3 in Appendix A.2). Phase I is located on the west side of the existing landfill and was constructed in 1990 thru 1992 (ECS, 1992f). Phase II is located on the east side of the existing landfill and was constructed in 1992 thru 1993 (GCS, 1993h). Phase III will include a vertical expansion primarily over the western half (approximately) of the existing landfill as well as a lateral expansion up the existing rock cut slope along the west side of the landfill. Phase III is anticipated to be constructed in 2010/2011 and operational in 2010/2011.

---

<sup>3</sup> This reference is applicable only to Phases I and II.

<sup>4</sup> This reference is applicable only to Phases I and II.

- Phases I and II each have two independent sump areas for leachate collection, detection, and removal. No other sumps will be installed for Phase III since only sideslope liner systems will be constructed for this phase. The existing portions of each phase draining to the separate sumps are designated as Areas IA and IB for Phase I and Areas IIA and IIB for Phase II. The Phase III sideslope liner will drain to all four of the existing Areas (IA, IB, IIA, and IIB).
- The source of clay for the existing Phase I and Phase II liners was from an overburden claystone stratum (herein referred to as Stratum 18-8) that was excavated from the Phase II footprint. The primary source of clay for the Phase III liner is anticipated to be from the Landfill Unit B-17 excavation. The clay borrowing and preparation procedures that were used for Phases I and II as well as the procedures to be used for Phase III are described in Section 4.6.

### 1.3 Report Organization

This report is organized into the following sections that provide detailed descriptions and background information for the design of B-18:

- Section 2.0 – Site Description;
- Section 3.0 – Geotechnical Investigations;
- Section 4.0 – Landfill B-18 Description;
- Section 5.0 – Engineering Analyses; and
- Section 6.0 – References.

Supporting information on the B-18 engineering and design is provided in the following appendices to this report:

- Appendix A – Construction Drawings;
- Appendix B – Boring Logs;
- Appendix C – Trench and Test Pit Logs;
- Appendix D – Laboratory Data;
- Appendix E – Clay Liner Test Pad Data;
- Appendix F – Liner System Material Data;
- Appendix G – Settlement Analyses;
- Appendix H – Stability Analyses;
- Appendix I – Soil Erosion Analyses;

- Appendix J – Surface Water Drainage Analyses;
- Appendix K – LCRS Analyses;
- Appendix L – Riser Pipe Analyses;
- Appendix M – Cover Infiltration Analyses;
- Appendix N – Frost and Biotic Protection Evaluation;
- Appendix O – Technical Specifications; and
- Appendix P – CQA Plan.

## 2.0 SITE DESCRIPTION

### 2.1 General

This section describes the general location of B-18 as well as its pre-development and existing conditions. Sections 2.2 and 2.3 describe the current and pre-development B-18 site conditions, respectively. Sections 2.4 to 2.6 provide brief descriptions of the B-18 site's geologic, seismic, and hydrogeologic conditions, respectively.

### 2.2 Current Site Layout and Conditions

The KHF is located approximately midway between San Francisco and Los Angeles (see the Regional Location Map on Sheet T-1 in Appendix A.1) along the western edge of the San Joaquin Valley in central California. The KHF property consists of approximately 1,600 acres that occupies 2.5 Sections (1/2 of Section 33 and all of Section 34, R18E, T22S, and all of Section 3, R18E, T23S, Mount Diablo Base and Meridian). Landfill B-18 is located in the southeast portion of the KHF (see Figure 1.1) and currently has a footprint area of approximately 53 acres. The proposed final footprint area of B-18 will be approximately 68 acres.

Figure 1.1 shows the KHF in relation to the west side of the San Joaquin Valley floor. The KHF is located in the Kettleman Hills, approximately four miles from the valley's edge. The existing ground surface elevations (USGS Datum) at the KHF range from approximately 750 to 1,010 feet above mean sea level, making the KHF approximately 600 feet higher than the adjacent portion of the valley floor. The most recent (March 28, 2008) topographic survey of the KHF indicates that, as of March 28, 2008, the top deck waste elevations of B-18 range between 885 and 905 feet above mean sea level (see Sheet C-2 in Appendix A.2).

Access to the KHF is from State Route 41 and Interstate 5, located along the west side of the San Joaquin Valley as shown on Figure 1.1. The entrance to the KHF is approximately three miles west of Interstate 5 and 60 miles northeast of San Luis Obispo, California. Within the KHF, access to the B-18 area is through the existing Guard Station at the Main Gate, northwestward past Landfill Unit B-15, westward along the road that is south of Surface Impoundment P-9, and southward past Surface Impoundments P-10 and P-11 and past the Final Stabilization Unit (FSU), which is located immediately north of B-18 (see Sheet C-1 in Appendix A.2). Waste trucks currently enter at the northwest corner of the B-18 area; as waste elevations increase, the trucks will use the western access road and closure cover access road as shown on Sheet C-4 in Appendix A.2.

The layout of the existing Phases I and II of B-18 was based on the August 1990 CUP Facilities Boundary during the original design of B-18 (see Sheet 2 in Appendix A.1). Physical constraints for the Phases I and II areas included the following:

- The existing FSU facility to the north of Phase I.
- The existing KHF truck access road surface water control basin located along the northeast portion of Phase II.
- The requirement for a B-18 surface water containment basin (referred to as the Northeast Containment Basin herein) near the northeast corner of Phase II. This surface water basin was constructed as part of Phase II in 1992 thru 1993 and is shown on Sheet 2 in Appendix A.1.

The layout of Phase III of B-18 was developed based on the proposed modified CUP Facility Boundary the three above-mentioned physical constraints, and the following additional physical constraints:

- The existing Phases I and II geometry.
- The requirement for a second surface water containment basin (referred to as the South Containment Basin herein) to the south of B-18, as shown on Sheet C-3 in Appendix A.2.

The clean soil stockpile from the Phases I and II excavation is located outside of the immediate B-18 area as shown on Sheet C-1 in Appendix A.2. The “B-17 Borrow Area,” within the boundary of Landfill B-17, to the northwest of B-18 is used for clay borrow and processing activities, but is primarily utilized as the source of daily and final cover soil.

No major KHF utilities are located within the B-18 area. Power for the existing light poles that surround B-18 and for the B-18 leachate control pumps is currently provided from an electrical transformer located along the north side of B-18 (see Sheet C-2 in Appendix A.2). For the Phase III construction, this electrical transformer will be removed and relocated to the north. The existing lighting system that surrounds B-18 is no longer required and will be removed during the Phase III construction.

### 2.3 Pre-Development Site Conditions

Figure 2.1 shows the B-18 site topography prior to the construction of B-18. This area was defined by a central, east/northeast-draining dry wash (i.e., swale) flanked on either side by several roughly northwest-trending ridge spurs. A former elongated, northeast-facing ridge slope formed the southwest boundary between Phases I and II and was used to develop these phases. In the Phase I area, two former tributary swales drained (northwest and southeast, respectively) along the toe of this slope into the former central swale. Another former swale drained northward through the south portion of the Phase II area, joining the former central swale near the northeast corner of the B-18 area. Typical relief between the former swales and adjacent ridge tops varied up to about 100 feet; however, the long ridge that currently borders B-18 on its southwest side rises over 250 feet above the lower portion of the former central swale. Former slopes in the B-18 footprint were gentle to moderate, ranging from nearly flat up to inclinations of about 3H:1V (horizontal:vertical). Locally steep (2H:1V) former slopes occurred on the east/northeast side of the former ridge spur in the south-central portion of B-18.

### 2.4 Geologic Conditions

Geologic conditions at the KHF are well-documented in the many studies completed for previous site activities. In general, subsurface conditions are relatively straightforward and consistent in comparison with other sites in California.

Figure 2.2 shows the general geologic conditions in the vicinity of the KHF, based on the work of Woodring, et al. (1940). The KHF is located along the southwest limb of North Dome, which is a broad northwest-trending anticline that forms the north portion of the Kettleman Hills. The bedrock in the vicinity of B-18 mainly consists of the stratigraphically lowest units of the Upper and Lower San Joaquin Formation, which are comprised of discrete beds of sandstone, siltstone, and claystone. The

prevailing strike of these beds in the KHF area is about N45°W, with dips ranging from 25° to 35° southwest.

Figure 2.3 summarizes the geologic conditions at the KHF based on data from a variety of prior investigations. The most important characteristic of the site geology with respect to the B-18 site investigation program (Section 3) was the continuity and uniformity of the bedrock strata. Of special importance was the thick claystone stratum which passes through the western portion of the B-18 Phase II area. This material served as the clay source for the Phases I and II liner. Additionally, for the Phase III area, the dip of the bedrock strata is to the southwest, representing the most favorable bedding orientation for stability of the excavation.

Neither Figure 2.2 nor 2.3 indicates the existence of faults within the KHF, which would disrupt the general bedrock strike and dip trends and/or the continuity of the individual sandstone, siltstone, and claystone strata. Two studies by Roger Foott and Associates (1990a and 1990b) concluded that there is no surface or recent (i.e., Holocene) faulting in the B-18 area. This conclusion was corroborated by geologic mapping of the completed landfill subgrades during the construction of Phases I and II (Golder, 1992; GCS, 1993b).

## 2.5 Design Ground Motions

### 2.5.1 General

CCR Titles 22 and 23 require Class I landfills to be designed and maintained to withstand the Maximum Credible Earthquake (MCE) event. Hence, the design ground motions used in the analyses of B-18 were based on the MCE event(s), as described in the following two sections.

### 2.5.2 Ground Motions Used in the Original Design

In the original design of B-18, ESI (1990a) used the MCE event and associated ground motion parameters that had been developed by Golder (1988). The Golder (1988) MCE event for the KHF corresponded to a moment magnitude ( $M_w$ ) 7.0 earthquake occurring at a depth of 10 km below the site on the Ramp Thrust Kettleman Hills North Dome segment of the blind Ramp Thrust Faults. The deterministic peak horizontal ground acceleration (PHGA) associated with this MCE event was calculated to be 0.43g (Golder, 1988), where g is the acceleration due to gravity.

### 2.5.3 Ground Motions Used in the Current Design

Hushmand Associates, Inc. (HAI), under subcontract to Golder, updated the design ground motions for the KHF as part of the current B-18 design. Appendix H.5 contains HAI's slope stability report that explains the methods used to develop the updated design ground motions. HAI performed deterministic seismic hazard analyses to evaluate the MCE ground motions for the controlling near-field and far-field events using a variety of state-of-the-practice attenuation relationships. Based on their analyses, HAI has developed the following deterministic MCE ground motion parameters for the KHF that were used in the current design of B-18:

- *Near-Field Event:* The controlling near-field MCE event is considered to be a  $M_w$  7 earthquake occurring 10 km from the site on the Ramp Thrust Kettleman Hills North Dome segment. The PHGA associated with this event was calculated to be 0.62g.

- *Far-Field Event:* The controlling far-field MCE event is considered to be a  $M_w$  8 earthquake occurring 35 km from the site on the San Andreas Fault. The PHGA associated with this event was calculated to be 0.16g.

## 2.6 Hydrogeology

Groundwater conditions are extensively monitored at several existing monitoring wells located throughout the KHF site. Sheet C-2, C-3 and C-4 in Appendix A.2 shows the locations of monitoring wells in the vicinity of B-18. Recent data from these wells indicate that the depth to groundwater is about 250 feet below the bottom of the existing B-18 base liner system. No shallow perched groundwater or perennial springs are known to occur in the B-18 area.

Because groundwater conditions do not affect the design or construction of B-18, an extensive evaluation of hydrogeology is not provided in this report. A report by EMCON (1986) contains a detailed description of the hydrogeological conditions at the KHF. The current Groundwater Monitoring Plan for the KHF was prepared by Geosyntec (2001).

### 3.0 GEOTECHNICAL INVESTIGATIONS

#### 3.1 General

This section describes the geotechnical field and laboratory investigations previously undertaken by ESI and others to characterize the B-18 subsurface conditions and to evaluate soil and rock properties necessary for the geotechnical design of B-18. No additional field or laboratory investigations were performed by Golder in the preparation of this report. Field and laboratory testing on the proposed clay source for Phase III of B-18 was performed by Geosyntec (2008), as discussed in Section 3.2.2.

Section 3.2 describes the main field investigation activities associated with the design of B-18 and the evaluation of on-site claystone for use in the B-18 liner construction. Section 3.3 summarizes the subsurface conditions for B-18 based on the results of the geotechnical investigations. Section 3.4 describes the procedures used to select the soil and rock samples for laboratory testing in order to evaluate the required geotechnical design parameters. Results of the laboratory tests, including prior KHF data not directly associated with the design of B-18, are discussed in Section 3.5.

#### 3.2 Field Investigations

##### 3.2.1 Geotechnical Exploration Program

The locations of geotechnical field exploration activities are shown in plan view on Figure 3.1 and in sectional views on Figure 3.2. The field explorations were undertaken in several phases designed to verify the anticipated site geologic characteristics and to obtain representative soil and rock samples.

The initial phase of B-18 field exploration activities was conducted from February 20 through 27, 1990, and consisted of the following:

- Excavating long dozer trenches DT-A to DT-F to observe the thickness of colluvium, identify stratum contacts, and measure the strike and dip of rock discontinuities/bedding. These dozer trenches were generally between about 3 and 10 feet deep.
- Excavating test pits TP-1 through TP-21 to penetrate colluvium at the base of the dozer trenches and to observe soil and rock conditions throughout the B-18 area. These test pits were generally about 6 to 18 feet deep.

Several disturbed bulk samples of representative colluvium and rock materials were collected for general laboratory analyses during this initial program.

The second phase of B-18 field exploration activities was conducted from March 12 through 23, 1990, and consisted of the following:

- Drilling nine geotechnical borings (L18-A through L18-I) to further verify the depth of contacts between individual rock strata and to collect relatively undisturbed samples of the rock materials to be encountered during excavation and/or to be used as embankment borrow material. These borings were advanced to depths ranging between approximately 18.5 and 89 feet below ground surface.



- Excavating test pits TP-22 through TP-28 to confirm colluvium thicknesses and characteristics of bedrock strata at locations between the borings. These test pits were excavated to depths of approximately 5.5 to 13.5 feet.

Table 3.1 summarizes the purpose for and key information about each boring. The borings were drilled using a Pitcher Barrel rig so that core samples could be recovered at the various intervals shown in Table 3.1. A total of 65 Pitcher Barrel samples of bedrock and 6 drive samples of colluvium were collected from the initial borings (L18-A through L18-I).

Data from the two initial field exploration phases were used to develop the preliminary versions of the geologic cross sections shown in Figure 3.2. Existing monitoring well logs were also reviewed to confirm interpretations of rock strike and dip. These data consistently verified the relatively uniform site conditions and indicated that site characterization for the purposes of the B-18 design was complete. However, it was concluded that additional clay samples were required to complete the characterization of Stratum 18-8 for use as the onsite clay source for the Phases I and II liner.

Therefore, the third and final phase of B-18 field exploration activities was conducted from May 8 through 11, 1990, and consisted of the following:

- Drilling boring L18-J to penetrate the entire Stratum 18-8 (clay borrow source) thickness to confirm uniformity of the claystone throughout this stratum. Sampling was accomplished by collecting approximately 2.5 feet of relatively undisturbed sample for each 5 feet of penetration. This boring was drilled to a depth of approximately 172.5 feet below ground surface.
- Drilling boring L18-K through the entire thickness of Stratum 18-9 and into the underlying Stratum 18-8. Stratum 18-9 was excavated concurrently with the Stratum 18-8 claystone during the construction of Phases I and II. This boring was also sampled by collecting approximately 2.5 feet of relatively undisturbed sample for each 5-foot penetration interval. This boring was drilled to a depth of approximately 97.5 feet below ground surface.
- Excavating test pits TP-29 through TP-43 to obtain larger bag samples of materials from Strata 18-8, 18-9, 18-10, 18-11, 18-12, and 18-13. These larger samples were used to evaluate properties of compacted borrow materials that could be mixed with the clay. These test pits were excavated to depths of approximately 3.5 to 16 feet.

Appendix B contains the logs of the above-described borings. Logs of the dozer trenches and test pits are included in Appendix C.

The information contained in Table 3.2 demonstrates that the colluvium and rock strata of interest to the design of B-18 have been adequately investigated by the above-described field exploration activities. Table 3.2 also includes the existing and previous monitoring wells which pass/passed through each geologic stratum underlying B-18.

Supplemental geologic field investigations were undertaken by Roger Foott and Associates (1990a and 1990b) to evaluate the potential for recent faulting in the vicinity of B-18. The findings of these investigations are discussed in Section 3.3.2.

### 3.2.2 Clay Liner Test Pads

In 1991, a clay liner test pad was constructed to evaluate the B-18 Phases I and II clay borrow source (i.e., Stratum 18-8). A sealed double-ring infiltrometer (SDRI) test was conducted on this test pad. Results of the SDRI test confirmed that the Stratum 18-8 clay source met the permeability requirements under actual field conditions. The construction of the 1991 clay liner test pad and the SDRI testing are discussed in detail in the test fill and infiltrometer report by ESI (1992), which is provided in Appendix E.1. CQA testing of the clay liner material during construction of Phases I and II of B-18 (ECS, 1992a, 1992b, and 1992d; GCS, 1993a, 1993d, and 1993f) verified the results of the SDRI test and indicated that the as-built clay liners for Phases I and II have permeabilities that do not exceed the specified maximum of  $1 \times 10^{-7}$  cm/s.

The clay source for the Phase III liner is anticipated to be the on-site Pecten Claystone stratum that lies along the eastern boundary of Landfill Unit B-17 (see Sheet C-1 in Appendix A.2). Geosyntec (2008) performed laboratory testing on samples of this stratum of Pecten Claystone. Results of Geosyntec's laboratory tests indicate that the Pecten Claystone stratum is a suitable clay borrow source for the Phase III liner. The Geosyntec (2008) report on the Pecten Claystone testing is summarized in Table 3.13 and presented in Appendix E.2. A clay liner test pad consisting of Pecten Claystone was constructed in July 2008. A SDRI test was conducted by Geosyntec (2008a) on this test pad to further evaluate the Pecten Claystone and validate its use as the clay borrow source for the Phase III liner. The SDRI test report was completed in December 2008 and is presented in Appendix E.3. The report concludes the Pecten clay is suitable for Phase III clay liner.

## 3.3 Site Subsurface Conditions

### 3.3.1 Surficial Soils

The majority of the B-18 site was blanketed with colluvial soils prior to its development. These deposits consisted of low to moderately plastic, silty and/or sandy clays and very fine-grained clayey sands. The colluvium was generally stiff to very stiff and dry to slightly damp when encountered during the field explorations. Occasional laminated lenses of fine-grained sand, probably representative of intermittent alluvial deposits within the colluvium, were encountered in some swale areas. The colluvium varied in thickness from less than 1 foot along the uppermost ridge slopes to over 18 feet within the swales, as shown in Figure 3.2. Considerable variation in the thickness of colluvium beneath uniform slopes was indicative of differential weathering of the underlying San Joaquin Formation bedrock and surficial soil compaction.

During the Phases I and II construction, the colluvium was excavated from the vast majority of foundation areas within the B-18 footprint due to its shallow depths. The only areas where colluvium was left in place were at the crest of the 2H:1V slope along the western boundary of Phase I. The colluvium that remained in these areas was less than 5 feet thick (GCS, 1993h). Areas where colluvium remained above landfill cut slopes outside of the waste footprint (e.g., the steep northeast facing slope above the southwestern edge of B-18) were graded to control soil erosion and/or sloughing.

Prior to the development of B-18, minor portions of the B-18 footprint were covered with fill. The northern portion of the Phase I area included the toe of a fill slope associated with the FSU construction. Several small fills in the Phase II area were apparently associated with drilling pads and a former access road that traversed the area. These fill materials were removed during the Phases I and II excavations.

### 3.3.2 Bedrock Lithology, Structure, and Stratigraphy

The San Joaquin Formation underlying B-18 is similar to the other portions of this formation found throughout the KHF area. The San Joaquin Formation consists of three major lithologic units: sandstone, siltstone, and claystone. Principal variants include silty sandstone and sandy siltstone. These units of the San Joaquin Formation were relatively easy to excavate using conventional earthmoving equipment (e.g., scrapers and dozers) during the Phases I and II construction. The physical characteristics of each of the discrete lithologic units, as well as qualities common to the overall San Joaquin Formation, are:

- *Sandstone:* Beds of both clean and silty sandstone occur within the B-18 area. The sandstones are variably white, gray, tan, and orange-brown. They are typically slightly weathered, soft, friable, very fine- to fine-grained, thick-bedded, and uncemented to weakly cemented. Occasional thin beds are moderately- to well-cemented. Numerous veins of gypsum and thin, orange interbeds of hard, cemented, iron-rich material occur along bedding planes and joints within the sandstones, as well as within the other lithologic units. The sandstone excavations generated fine, loose, clean, and silty sand. Several fossiliferous, well-cemented sandstone beds (including “Trachycardium” and “Mya”) occur at various stratigraphic positions within the B-18 area, as shown on Figures 2.3, 3.1, and 3.2. These fossil beds are generally excavated as hard, gravel- to boulder-sized blocks.
- *Siltstone:* The siltstone units within the B-18 area are of variable character and include siltstone, sandy siltstone, and occasionally clayey siltstone. Each siltstone type is typically slightly weathered, soft, and laminated to thin-bedded. The siltstones vary from non- to low-plastic materials. Atterberg limits of selected samples, visually classified as siltstone, indicate that some “siltstones” consist of silty clays that plot just above the A-line on the plasticity chart. The siltstones are usually light brown or gray. Excavation of siltstone generates thin, angular fragments or slabs ranging from about 1/2 inch to 1 foot in largest dimension.
- *Claystone:* The claystone is usually either light gray, gray-brown, or dark olive-gray. It is typically slightly weathered, soft, laminated to thin-bedded, highly plastic, and frequently exhibits pronounced slickensides (striations) along glossy or waxy-appearing fracture and bedding surfaces. Dozer excavation of the claystone opposite the direction of dip yielded generally uniform, angular gravel-sized fragments, while excavation in the direction of dip yielded gravel- and larger-sized blocks and slabs in the range of 12 to 18 inches in maximum size. The largest slabs of claystone generated during the initial excavation tended to break down after repeated passes with the dozer.

The prevailing structural characteristic of the bedrock is its consistent bedding, which trends generally N30°W to N50°W and dips about 24 to 45°SW throughout the B-18 area (Golder, 1992; GCS, 1993b). Most measured joints dip steeper than the bedding and trend both across and generally parallel to the bedding (bedding and joint attitudes are shown on Figure 3.2). As shown on the cross sections in Figure 3.2, the cut slopes required for the Phases I and II construction were excavated shallower than the bedding plane angles to prevent adverse daylight conditions (e.g., along generally southwest-facing cut slopes).

Anomalous and contorted bedding (measured at N55°E, 73°SE) was encountered in dozer trench DT-C (Figure 3.1) within the thick Stratum 18-8 claystone. The length of the dozer trench characterized by this feature was logged as trench T-3 (see Appendix C). A detailed examination of the geologic units along this portion of DT-C suggest that the anomalous bedding was a result of old, intraformational deformation (e.g., localized folding, faulting, or slumping). The colluvium that overlaid this feature appeared undisturbed and displayed no evidence of offset or displacement that would be indicative of recent slope instability or faulting. Excavations for the construction of Phases I and II confirmed that the contorted bedding observed in DT-C was a localized, anomalous feature.

Contorted beds of cemented sandstone, appearing to be folded or compressed in a down-dip direction, were encountered immediately beneath colluvial soils in dozer trench DT-B (Figure 3.1). The contorted bedding is apparently related to settlement of the near-surface, cemented bedrock following erosion or animal burrowing of underlying, softer, uncemented sandstone (refer to the log of trench T-1 in Appendix C). The disturbed, near-surface bedrock was removed during the excavations for Phases I and II.

Stratigraphically, the San Joaquin Formation beds underlying B-18 have been grouped into a sequence of 13 stratigraphic units. Each unit is defined according to either a discrete lithology or a distinctive interbedding of various lithologic units. The units are designated 18-1 through 18-13, from northeast (oldest) units to southwest (youngest) units. The approximate contacts of these units are depicted in plan on Figure 3.1 and in profile on Figure 3.2. The stratigraphy shown in Figures 3.1 and 3.2 was based on the results of the dozer trenching, exploration drilling, air photo analysis, mapping of cut exposures prior to the development of B-18, and excavation of test pits. Comparisons were also made with logs of existing and previous monitoring wells in the B-18 area. In general, the geologic conditions in the B-18 area were found to be straightforward and consistent. Geologic mapping of the B-18 subgrades performed during the construction of Phases I and II revealed 15 units within the Phase I area (Golder, 1992) and 26 units within the Phase II area (GCS, 1993b). The results of this mapping confirmed the general geologic conditions shown on Figures 3.1 and 3.2 with the only significant discrepancies being local adjustments of some of the contact locations.

Geologic field investigations undertaken by Roger Foott and Associates (1990a and 1990b) indicated that recent (i.e., Holocene) faulting has not occurred in the vicinity of B-18. Additionally, geologic mapping of the completed B-18 subgrades during the construction of Phases I and II did not reveal any evidence of recent faulting (Golder, 1992; GCS, 1993b).

### **3.4 Laboratory Investigations**

#### **3.4.1 Sample and Testing Selection Process**

This section describes the approach for selecting appropriate geotechnical laboratory tests to evaluate the necessary geotechnical design parameters and to establish geochemical background data for the on-site materials.

Initially, the large amount of existing geotechnical data available from pre-1990 KHF landfill designs was evaluated to assess the usefulness of this data for the B-18 design. Also, index property tests were initially conducted on many of the B-18 samples for comparison with properties of materials previously tested and to characterize the range of material types which may be important for design. Representative samples for strength, consolidation, compaction, shrink/swell, permeability, and geochemical testing were selected based on the results of index property tests, past data, and the importance of specific strata to the design analyses.

### 3.4.2 Prior (Pre-1990) Geotechnical Data

The most pertinent pre-1990 KHF geotechnical data used in the design of B-18 is summarized in Table 3.3 and is based on the results of investigations reported for the following activities:

- The design of Phases II and III of Landfill Unit B-19 (Donohue and Associates, 1988a);
- The slope failure investigation for Phase IA of Landfill Unit B-19 (Seed et al., 1988); and
- Generic investigations of closure alternatives for various landfills at the KHF (Golder, 1988b, 1989c, and 1989a).

Table 3.3 also summarizes reported properties from published literature and vendor data on geosynthetic liner interface testing.

### 3.4.3 Laboratory Testing for Landfill Design

Tables 3.4 and 3.5 summarize the B-18 geotechnical laboratory testing program and show the samples collected from the borings and test pits/trenches, respectively. An “X” is provided in each table to indicate the types of tests conducted on each sample. The analysis methods used for the various tests are summarized in Table 3.6.

A large number of index tests were initially conducted to evaluate the consistency of characteristics for the various rock and soil types. The index tests performed on a particular sample were selected based on the type of material. For example, plasticity index testing was conducted only on fine-grained claystone or siltstone samples. Index property comparisons were then used to select representative samples to be tested for the various engineering properties (e.g., compaction, strength, settlement, permeability).

Tests that were conducted under conditions to simulate the B-18 site-specific conditions are indicated by the footnotes in Tables 3.4 and 3.5. These included:

- Conducting unconsolidated undrained (UU) triaxial tests at confining pressures ranging between 4 and 16 kips per square foot (ksf) to represent the anticipated range of overburden pressures due to the weight of the overlying waste.
- Conducting most of the clay permeability tests at a dry unit weight equal to 90 percent of the Modified Proctor (ASTM D1557) maximum dry density and at water contents ranging from 2 to 6 percent above the optimum moisture content to represent clay liner material that has been compacted in accordance with the Specifications.

All of the compaction tests except two were conducted using the Modified Proctor procedures (ASTM D1557), which are specified for the B-18 construction. Standard Proctor procedures (ASTM D698) were conducted on one sandstone sample from Boring L18-K and one claystone sample from test pit TP-37 for comparison purposes only.

Table 3.4 also shows that background geochemistry was analyzed for three rock samples (one each from borings L18-A, L18-C, and L18-F) representing a range of the claystone, siltstone, and sandstone. The geochemical analyses conducted are listed in Table 3.6. These are the same background analyses conducted for prior KHF landfill investigations.

#### 3.4.4 Special Testing of the Phases I and II Clay Borrow Material

Plasticity and unit weight/water content tests were conducted on 15 samples of Stratum 18-8 claystone collected from Boring L18-J to assess the uniformity of the claystone. Hydrometer tests were then conducted on five of the 15 samples that were considered representative of the range of conditions in the stratum to compare grain size characteristics. Shrinkage tests were conducted on four of the five samples to quantify the clay shrink/swell characteristics. Plasticity index and hydrometer tests were also conducted on shallow claystone samples from dozer trenches DT-A and DT-C and from test pits TP-36, TP-38, and TP-40 to provide a comparison of conditions derived from the shallow weathered rock.

Modified Proctor (ASTM D1557) compaction tests were conducted on three “pure” claystone composites of borehole samples to determine their water content-dry density relationship. Permeability tests were also performed on each of these three Modified Proctor composite samples using material compacted at approximately 90 percent relative compaction and water contents ranging from 0 to 2 percent above optimum. Unconsolidated-undrained (UU) triaxial and consolidation tests were conducted on one Modified Proctor test sample from dozer trench DT-A that was considered to be representative of the clay material.

The above-described tests on “pure” claystone samples provided conservative characteristics of strength and consolidation parameters for the clay materials. In order to assess the potential for mixing the claystone with other rock materials, an additional series of tests was conducted on mixtures of claystone from Stratum 18-8 and sandstone/siltstone from the adjacent Stratum 18-9. Mix ratios of 70:30 and 50:50 (claystone:sandstone/siltstone) percent were used.

Long-term leachate compatibility testing for the B-18 clay was not conducted in light of the results of an extensive testing program by EMCON (1989) using on-site claystone materials. That program included soil/waste compatibility tests performed consistent with the California Administrative Code, Title 23, Chapter 3, Subchapter 15, Section 2541(b) and (c); the United States Environmental Protection Agency (USEPA) regulations in 40 CFR 270.17(b)(1), 270.21(b)(1), 264.221(a)(1), and 264.301(a)(1)(i); and the Resource Conservation and Recovery Act (RCRA) Method 9100.

The EMCON (1989) compatibility tests showed no significant increase in clay permeability after displacing two volumes of pore water with a representative leachate obtained from another hazardous waste site operated by CWM EMCON (1989) therefore concluded that the leachate did not have a significant effect on the permeability of the clay. EMCON (1989) also considered this conclusion to be consistent with findings reported by others in published literature, which indicate that dilute organic liquids do not adversely affect the permeability of clay soils.

### 3.5 Laboratory Testing Results

#### 3.5.1 General

This section summarizes the B-18-specific laboratory testing results in the following order:

1. Index properties.
2. Compaction tests.
3. Strength tests.
4. Permeability tests.
5. Consolidation tests.
6. Shrink/swell potential tests.
7. Geochemical analyses.

The complete laboratory test results and supporting information are presented in Appendices D and E.

The laboratory test results described in this section were performed prior to the development of B-18 and provided the necessary information that guided the B-18 design. CQA reports prepared for the Phases I and II construction (see Section 4.1) contain additional laboratory and field test results that were performed as part of the Phases I and II CQA program. These CQA test results generally confirmed that the actual properties of the various as-built materials met or exceeded the material properties that were assumed during design. Hence, no attempt has been made to fully incorporate the CQA test data into the discussions in this report. Rather, CQA test results are only mentioned herein when deemed appropriate to reinforce an earlier assumption or finding. More recent testing, Geosyntec 2008a and b, has been conducted on proposed clay liner materials. Test results indicate the clay liner is similar to that used for Phase I and II and it will be suitable for use as a clay liner in Phase III. Test results that are included in Appendix E.2 and E.3 are summarized herein.

#### 3.5.2 Index Property Tests

Plasticity index tests (i.e., Atterberg limits tests) were performed on claystone samples from Strata 18-2 through 18-5, 18-7, 18-8 (the clay borrow source for Phases I and II), 18-9, 18-10, and 18-12. Table 3.7 summarizes the plasticity index data and indicates that the majority of the claystone is classified as high-plasticity clay (CH) having a liquid limit ranging from about 55 to 90 and a plasticity index ranging from about 30 to 60. One sample from Stratum 18-8 and several samples from other fine-grained strata were classified as low-plasticity clay (CL). These materials have a liquid limit ranging from about 30 to 49 and a plasticity index ranging from about 6 to 29. In addition, one of the plasticity index tests performed on a minor claystone/siltstone sample of Stratum 18-3 showed the characteristics of a low plasticity silt (ML).

Figure 3.3 shows a plasticity chart with plotted data points for the majority of the Stratum 18-8 samples that were tested. It can be seen from this figure that the Stratum 18-8 claystone material consistently lies in the CH (i.e., high-plasticity clay) range. Additional plasticity charts containing plotted data for the other strata that were tested are included in Appendix D.1.

Table 3.8 summarizes the tests performed to evaluate the percentage of material passing the U.S. No. 200 sieve (i.e., fine-grained silt and clay) for the various samples tested. The colluvial soil samples generally have a fairly high percentage (about 33 to 81 percent) of fine-grained materials. This variation apparently relates to the origin of the colluvial materials with the highest percentage of fines being derived from siltstone or claystone. The data in Table 3.8 for sandstone shows a relatively low

percentage of fines that ranges from about 11 to 37 percent. Clayey and silty sandstone samples showed the largest variation of percent fines (from about 21 to 73 percent) which reflects the varying amount of fine-grained laminations in these samples.

Figure 3.4 presents the grain size envelopes obtained from sieve analyses on sandstone samples from Stratum 18-9 and hydrometer tests on claystones from Stratum 18-8. Individual test results for samples from these strata and other rock units are included in Appendix D.2. These results further show the relative uniformity of the various rock types at B-18. The sandstones have relatively uniform grain sizes that fall mostly in the 4 to 0.1 millimeter diameter range. The percentage fines in the sandstones is approximately 10 to 40 percent. The claystone is well-graded with at least 80 percent fines and about 5 to 30 percent of the particles being smaller than 0.001 millimeters. The clay-size fraction (particles with a diameter less than 0.002 millimeters) varies between about 12 and 40 percent.

Natural moisture contents and dry densities for samples tested are presented on the boring logs in Appendix B. Typically, the sandstone materials have a natural moisture content varying between about 8 and 20 percent and a natural dry density varying between about 95 and 121 pounds per cubic foot (pcf). The claystone material's natural moisture content typically varies between about 15 and 30 percent and its dry density range is approximately 90 to 105 pcf.

Figure 3.5 contains a plot showing the relationship of the natural water content to the Atterberg limits for claystone samples from Stratum 18-8. This relationship is useful for qualitatively evaluating the compressibility and strength behavior of the claystone. The data in Figure 3.5 show that the natural water content of the Stratum 18-8 claystone is typically less than or roughly equal to its plastic limit. This condition is indicative of a material with relatively low compressibility and high strength. The importance of this condition is that it allowed the settlements of the B-18 foundation to be calculated based on the theory of elasticity. Other interesting features that can be seen from Figure 3.5 are the following:

- The natural water content of the Stratum 18-8 claystone is relatively close to its optimum moisture content as determined from Modified Proctor compaction tests (see Section 3.5.3); and
- The Stratum 18-8 claystone plasticity characteristics are relatively uniform throughout its entire depth, although a lower-plasticity zone was encountered in the 70- to 90-foot depth range.
- Recent testing on the proposed clay liner material, summarized in Table 3.13, indicates the plasticity index data of the claystone is generally classified as high-plasticity clay (CH) having a liquid limit ranging from about 58 to 105 and a plasticity index ranging from about 29 to 72. The fines content of the claystone ranged from 76 percent to nearly 100 percent. This is consistent with clay liner materials used for Phases I and II.

### 3.5.3 Compaction Tests

Table 3.9 summarizes the results of compaction tests conducted on a variety of composited samples and on individual bag samples from test pit TP-42 and dozer trenches DT-A and DT-C. With the exception of composite Samples No. 4 and No. 11, all of the tests were performed using the Modified Proctor test method (ASTM D1557), which is the method that was specified for the Phases I and II



construction (ESI, 1990b) and is specified for the Phase III and final closure construction (see Appendix O). The Standard Proctor test method (ASTM D698) was utilized for Samples No. 4 and No. 11 in order to assess the differences in densities resulting from the use of a lower compactive energy (the Modified Proctor method utilizes an energy of 56,000 foot-pounds per cubic foot as compared to an energy of only 12,400 foot-pounds per cubic foot for the Standard Proctor method). Individual plots for the Modified and Standard Proctor tests are provided in Appendices D.3 and D.4, respectively.

The Modified Proctor compaction data indicate that the optimum water content for the claystone is on the order of 21 to 25 percent and the corresponding maximum dry density is approximately 96 to 104 pcf. As the percentage of sandstone increases, the optimum moisture content is expected to decrease and the maximum dry density to increase. The recent testing by Geosyntec, presented in Appendix E.2, indicates lower optimum moisture contents and higher maximum dry density than previous testing. The optimum moisture content and maximum dry density ranged from 12.5 to 20.1 percent and 105.5 to 122.0 pcf, respectively. These variations are not significant and do not necessarily indicate a change in the clay quality.

The compaction tests using the Standard Proctor method indicate that the claystone's optimum water content for this lower compactive energy increases to about 30 percent while the maximum dry density decreases to below 90 pcf. A similar amount of change was also observed for the mixture of sandstone and claystone tested.

#### 3.5.4 Strength Tests on Relatively Undisturbed Samples

Strength properties of the in-situ rock materials that form the sidewalls of the majority of B-18 were evaluated by the following two types of tests:

1. Unconsolidated–undrained (UU) triaxial compression tests performed on relatively undisturbed samples of silty sandstone and claystone as summarized in Appendix D.5. These tests allowed failure to occur on the weakest plane in the sample and provided representative data for evaluating the stability of slopes in which failure along bedding planes may occur.
2. Direct shear tests performed on relatively undisturbed samples of sandstone and claystone, as summarized in Figure 3.6 and Appendix D.8. The direct shear samples were oriented such that failure occurred across bedding planes. These test results were then used for the stability evaluation of slopes which are not parallel or nearly parallel to the bedding.

Figure 3.6 also includes direct shear test data from the previous B-19 Phases II and III investigation (Golder, 1988b) for comparison.

The in-situ rock strengths along bedding planes obtained from the UU triaxial tests were consistently higher than the minimum strengths obtained for similar conditions for the design of B-19 Phases II and III (Golder, 1988b). Therefore, in order to be conservative for B-18 cut slopes in the west-facing direction, it was concluded that the appropriate rock strength along bedding planes should be represented by a friction angle ( $\phi$ ) = 36 degrees and a cohesion intercept ( $c$ ) = 0, as recommended by Golder (1988b).

As shown on Figure 3.6, the shear strength parameters for evaluating slope stability for crossbed conditions was evaluated to be  $\phi = 40$  degrees and  $c = 800$  pounds per square foot (psf). As can be seen in Figure 3.6, these strength parameters provide an approximately lower-bound limit of the direct shear test data conducted for the B-18 and B-19 (Golder, 1988b) investigations.

### 3.5.5 Strength Tests on Remolded Samples

The following two types of tests were performed to evaluate the strength of the clay liner for use in assessing the stability of B-18 at different times throughout its life:

1. UU triaxial compression tests were conducted on remolded sandstone and claystone samples to provide strength parameters to assess landfill stability for short-term conditions (i.e., prior to significant clay liner consolidation occurring due to the weight of the overlying waste).
2. Consolidated-undrained (CU) triaxial compression tests were conducted on remolded claystone samples for use in evaluating the long-term stability of B-18 (i.e., after the clay liner consolidation is essentially complete).

The results of the UU and CU triaxial tests are included in Appendices D.6 and D.7, respectively.

The UU triaxial test results indicate that the short-term strength of the clay liner can be represented by  $\phi = 8$  degrees and  $c = 3,600$  psf. After consolidation is essentially complete, the clay liner is significantly stronger and can be represented by  $\phi = 15$  degrees and  $c = 1,500$  psf.

CU triaxial compression tests conducted on silty sandstone materials from Stratum 18-9 indicate that the shear strength of these materials when compacted to 95 percent relative compaction can be represented by  $\phi = 30$  degrees and  $c = 3,000$  psf. These strength parameters are considered appropriate for evaluating the stability of structural fill and embankments constructed from low plasticity borrow materials.

### 3.5.6 Permeability Tests

The five permeability tests summarized in Table 3.10 were conducted on clay samples derived from the Stratum 18-8 claystone. These tests show that the anticipated permeability under laboratory conditions varies between about  $2 \times 10^{-8}$  and  $2 \times 10^{-9}$  cm/s. For comparison, the field SDRI test performed by ESI (1992) indicated that the permeability of a clay liner constructed of Stratum 18-8 claystone is on the order of approximately  $5 \times 10^{-8}$  cm/s.

The laboratory permeability tests were conducted under a variety of conditions to evaluate the degree to which the particle size and weathering of the claystone may affect its permeability. The first two tests in Table 3.10 were conducted using a maximum particle size of 3/8-inches in the Proctor mold. Although small with respect to field compaction equipment, the 3/8-inch particle size is relatively large for small-scale laboratory permeability tests. The second two tests in Table 3.10 were conducted using a 1/4-inch maximum particle size, which corresponds to the ASTM procedures. The final test in Table 3.10 was designed to simulate the field conditions anticipated for B-18. This test was conducted by allowing the material to weather over a two-week period and without controlling the particle size. This procedure best represents the conditions which are realized in the field as the clay borrow material is mixed, worked, stockpiled, and recovered with wetting operations at various times

during these activities. Experience from the Phases I and II construction indicates that adequate permeabilities are realized if a maximum particle size of 1 to 2 inches is maintained.

Recent permeability tests, Geosyntec 2008, indicate the proposed clay liner material has a permeability of less than  $1 \times 10^{-7}$  cm/sec. The tests show that the anticipated permeability under laboratory conditions varies between about  $9 \times 10^{-8}$  and  $4 \times 10^{-9}$  cm/s, and  $4.2 \times 10^{-8}$  cm/s based on the field SDRI (see Appendix E.2 and E.3).

### 3.5.7 Consolidation Tests

Consolidation tests were conducted on two samples of the Stratum 18-8 clay that were compacted to conditions similar to those specified for construction. These tests provided information for:

- Estimating the amount of settlement that will occur in the clay liners as a result of the waste loading; and
- Estimating the rate at which pore pressures will dissipate from the clay liner in order to evaluate if there is a potential for excess pore pressure build-up.

The two consolidation tests showed similar compressive stress versus void ratio relationships. The results of the consolidation tests are included in Appendix D.9.

### 3.5.8 Shrink/Swell Potential Tests

Tables 3.11 and 3.12 summarize the shrink/swell test results for relatively undisturbed and remolded Stratum 18-8 claystone samples, respectively. The test results for the relatively undisturbed samples in Table 3.11 indicate that the in-situ claystone has low to moderate swell potential under low confining pressures. At high confining pressures, such as those on the base liner system, the swelling potential of the claystone is considered negligible based on the test results in Table 3.11.

The data in Table 3.12 shows that remolded Stratum 18-8 clay has a moderate to high swelling potential under low confining pressures. This indicates that it is important to keep the clay liner materials wet after placement and prior to deployment of the overlying geosynthetics in order to prevent significant desiccation cracking. Appropriate steps were taken to prevent excessive drying of the clay liner during the Phases I and II construction. Similar preventative procedures are specified for the Phase III clay liner construction (see Appendix O.1).

### 3.5.9 Geochemical Tests

Background geochemical analyses were conducted on representative claystone, siltstone, and sandstone samples prior to the development of B-18. These test results are presented in Appendix D.10.

Additional geochemical analyses were performed on seven bedrock samples collected from the B-18 excavations during the construction of Phases I and II (Golder, 1992; GCS, 1993b). The results of these tests were consistent with the typical natural background composition (in terms of analytes and concentrations) of the San Joaquin Formation bedrock.

### 3.6 Method 9090 (Liner/Leachate Compatibility Testing)

As a condition of the Hazardous Waste Facility Permit (DTSC, 2003) “the Permittee shall test all components of landfill liners for waste/leachate compatibility using EPA Method 9090 or other more appropriate methods approved by DTSC. The liner components include seamed portions of 60-mil [HDPE], [HDPE] geomembrane material, [HDPE] geonet, geotextiles fabric, graded gravel used as drainage material, and [HDPE] piping used in the leachate collection systems.”

For Landfill B-18 Phases I and II, leachate samples from an on-site hazardous waste landfill were used to test compatibility with the liner components. The following reports were submitted to the agencies, confirming the acceptability of the materials:

- Chemical Compatibility Testing of National Seal 60 mil Geomembrane with Kettleman Hills Waste Leachate, Soltex Resin, NSC#CO2A, Final Report (TRI/Environmental, Inc., October 14, 1991)
- Leachate Compatibility of Geosynthetic Materials – Kettleman Hills Facility, Final Report (J&L Testing Company, November 4, 1991)
- Geotechnical Laboratory Test Results Aggregate/Leachate Compatibility Testing, Kettleman Hills Facility, (J&L Testing Company, November 7, 1991)
- NSC 60 mil Textured HDPE Chemical Compatibility Testing EPA Method 9090 – Kettleman Hills Facility, (J&L Testing Company, September 8, 1992)

The materials that were tested in 1991 and 1992 (during the B-18 construction) by J&L Testing Company included:

Gundle XL-14 Geonet  
NSC PN-3000 Geonet  
Trevira 1125 Geotextile  
Gundle 60mil HDPE Geomembrane  
Gundle 60mil Textured HDPE Geomembrane (New Resin)  
NSC 60 mil Textured HDPE Geomembrane (1992 testing)  
PVC Pipe  
HDPE Pipe  
LCRS Gravel

Testing was conducted in accordance with the Test Protocol and Methodology for Compatibility Testing (CWMI, May 31, 1988, revised August 31, 1989). This Test Protocol was approved with the issuance of EPA Permit Modification #2 and DTSC Permit Modification #1. Results of the testing indicate that the liner components, when exposed to leachate, would function satisfactorily and had no adverse cumulative effect on the physical and/or engineering properties.

Phase III will utilize similar materials for the construction of the liner components. The previous test results as well as industry-wide testing of liner materials with leachate (see Appendix F, Attachment 3), indicate that the proposed materials will function without adverse effect due to the exposure to leachate. Based on these data, no additional compatibility testing is proposed for materials to be used in the construction of Phase III. As allowed by the Hazardous Waste Facility Permit, the “existing

test data from similar studies, and manufacturer supplied specifications [may be] used as an alternative [to testing].”

## 4.0 LANDFILL B-18 DESCRIPTION

### 4.1 General

This section describes the B-18 design configuration, the key elements of B-18, and the supporting reasoning for the B-18 design.

B-18 development includes the following three phases:

- Phase I, which was constructed from October 1990 to February 1992 and has a footprint area of approximately 21 acres as shown on Sheet 2 in Appendix A.1.
- Phase II, which was constructed from August 1992 to November 1993 and has a footprint area of approximately 32 acres as shown on Sheet 2 in Appendix A.1.
- Phase III, which is anticipated to be constructed in 2012 and will have a footprint area of approximately 13.8 acres as shown on Sheet C-3 in Appendix A.2.

The landfill components and construction procedures for the three phases and final closure of B-18 are described in the following documents:

1. The Drawings for Phases I and II provided in Appendix A.1. It is noted that the original final closure design of B-18 shown on the Drawings in Appendix A.1 is superseded by the final closure design shown on the Drawings in Appendix A.2 and discussed herein.
2. The Drawings for Phase III and final closure provided in Appendix A.2.
3. The Specifications and CQA Plan for Phases I and II (ESI, 1990b).
4. The Specifications for Phase III and final closure contained in Appendices O.1 and O.2, respectively.
5. The CQA Plans for Phase III and final closure presented in Appendices P.1 and P.2, respectively.
6. The CQA Reports prepared for Phase I, which consist of the following:
  - a. Volume 1 – Subgrade Geologic Mapping Report (Golder, 1992).
  - b. Volume 2 – Clay Liner Source Report (ECS, 1992a).
  - c. Volume 3 – Secondary Clay Liner Construction Report (ECS, 1992b).
  - d. Volume 4 – Secondary HDPE Liner and Leachate Collection System Construction Report (ECS, 1992c).
  - e. Volume 5 – Primary Clay Liner Construction Report (ECS, 1992d).

- f. Volume 6 – Primary HDPE Liner and Leachate Collection System Construction Report (ECS, 1992e).
  - g. Volume 7 – Summary Construction Observation Report (ECS, 1992f).
  - h. Volume 8 – Operational Features Report (ECS, 1992g).
  - i. Volume 9 – Design Changes and Design Clarifications Report (ECS, 1992h).
7. The CQA Reports prepared for Phase II, which consist of the following:
- a. Volume 1 – Clay Liner Source Report (GCS, 1993a).
  - b. Volume 2 – Subgrade Geologic Mapping Report (GCS, 1993b).
  - c. Volume 3 – Excavation and Structural Fill Placement Construction Report (GCS, 1993c).
  - d. Volume 4 – Secondary Clay Liner Construction Report (GCS, 1993d).
  - e. Volume 5 – Secondary and Vadose HDPE Liner and Leachate Collection System Construction Report (GCS, 1993e).
  - f. Volume 6 – Primary Clay Liner Construction Report (GCS, 1993f).
  - g. Volume 7 – Primary HDPE Liner and Leachate Collection System Construction Report (GCS, 1993g).
  - h. Volume 8 – Summary Construction Observation Report (GCS, 1993h).
  - i. Volume 9 – Operational Features Report (GCS, 1993i).

An overview of the existing Phases I and II of B-18 is provided on the following sheets in Appendix A.1:

- Sheet 2 shows the Phases I and II areas and the former stockpile areas that were used for temporary storage of excavated materials during the construction of Phases I and II.
- Sheet 3 shows the Phase I subgrade elevations and the initial Phases I and II clay borrow area configuration in the Stratum 18-8 claystone described in Section 3 (see Figures 3.1 and 3.2).
- Sheet 7 generally shows how the Phases I and II clay borrow area was expanded after completion of Phase I but prior to the construction of Phase II. However, the grades shown on Sheet 7 were adjusted such that overexcavation below the Phase II subgrade was avoided.
- Sheet 8 shows the interim closure of Phase I and the Phase II subgrade elevations.

An overview of the proposed Phase III and final closure of B-18 is provided on the following sheets in Appendix A.2:

- Sheet C-1 and C-2 show the existing conditions of the B-18 area (as of March 28, 2008) and the location of the Phase III clay borrow area (borrow is within Landfill B-17).
- Sheet C-3 shows the subgrade elevations for all of B-18.
- Sheet C-4 illustrates the configuration of the B-18 closure cover final development grades (including benches, drainage, and access roads) for B-18.
- Sheets C-5 and C-6 show critical cross sections that further detail the development of B-18
- Sheet C-7 provides critical details for the liner cross section, liner termination, liner tie-in, and other items required for development of B-18.
- Sheet C-8 provides critical details for the extension of the existing leachate riser system as well as development of a replacement leachate riser and tank station.
- Sheet C-9 provides details to convey drainage into the new southern retention basin.
- Sheet C-10 provides additional drainage bench details and the final cover profile.

Detailed descriptions of the B-18 design are provided in the following sections:

- Section 4.2 – Phase I;
- Section 4.3 – Phase II;
- Section 4.4 – Phase III;
- Section 4.5 – Final Closure;
- Section 4.6 – Clay Borrow Operations;
- Section 4.7 – Liner Systems;
- Section 4.8 – Leachate Collection and Recovery Systems;
- Section 4.9 – Surface Water Control; and
- Section 4.10 – Utilities.



## 4.2 Phase I

Phase I comprises the western 40 percent (approximately) of the existing B-18 area (see Sheets 2 to 6 in Appendix A.1). Phase I of B-18 was configured so that:

- Disposed wastes are located within the 1990 CUP Facilities Boundary (Kings County, 1990).
- The number of boundary curves, which complicate excavation and liner construction, were minimized.
- Approximately 1,000,000 cubic yards of waste (including daily cover) were disposed of in Phase I.
- The waste is adequately stable under the operating and interim fill conditions.

The north, south, and west sides of Phase I form the originally-planned ultimate B-18 limits and were constructed as the final waste containment boundary. However, the proposed Phase III expansion will extend the ultimate limits of B-18 such that the Phase I area will be bordered by Phase III along the full length of its north, south, and west sides. The entire east side of Phase I is bordered by Phase II. Prior to the construction of Phase II, the east boundary of Phase I consisted of a berm (the Phase I/II Berm) that rises approximately 40 to 45 feet above the landfill base (see Sheets 3 and 8 in Appendix A.1). The Phase I/II Berm allowed waste to be filled in horizontal lifts in Phase I without having a laterally-unsupported waste slope on the Phase I base liner system. This minimized the risk of slope instability during Phase I disposal operations. The Phase I/II Berm is a permanent feature of the B-18 floor.

Almost all of Phase I is within excavated rock of the San Joaquin Formation. The only significant areas that required structural fill during the construction of Phase I were along the B-18 Perimeter Road near the northwest and southwest corners of B-18, as shown on Sheet 3A and in Section A-3A/15 on Sheet 15 in Appendix A.1.

The former access route into the Phase I area during its initial filling is illustrated on Sheet 5 in Appendix A.1. The main waste truck access included the following segments:

- Entering B-18 near the northwest corner of Phase I.
- Proceeding southward along the northern two-thirds (approximately) of the B-18 Perimeter Road on the west side of B-18.
- Proceeding down the 35-foot-wide access ramp on the west, south, and east Phase I waste area slopes. Special liner and road construction details for this access ramp are discussed in Section 4.7.3.3.

The Phase I waste area access ramp discussed above was aligned to intersect the top of the Phase I/II Berm near the southeast corner of Phase I. This allowed operations personnel to move landfill equipment and daily soil cover into the Phase I waste area along a temporary road on top of the Phase I/II Berm without impacting the main waste truck access. The appropriate manner for handling site traffic was refined on an on-going basis as operational experience was gained.

The existing B-18 Perimeter Road (see Section A-3,8/15 on Sheet 15 and Section A on Sheet 17 in Appendix A.1) is typically set back approximately 20 feet from the waste disposal limit to allow for the future construction of the final closure cover (Section 4.5). This separation is wider at two locations along the western portion of the B-18 Perimeter Road to accommodate the leachate collection and recovery system (LCRS) riser pads.

The base of Phase I is subdivided into two separate leachate collection zones that are referred to as Areas IA and IB, as shown on Sheets 2 through 5 in Appendix A.1. These areas are sloped toward two separate leachate sumps. This arrangement reduces the flow length for leachate to be collected as compared to an arrangement with only one sump at either end of the Phase I base. The sump areas are described in Section 4.8.

Waste was placed in nearly level, 10-foot-thick lifts across the entire Phase I area. This filling method avoided the condition of having interim waste slopes that were supported directly on the liner system. The interim waste surface was sloped slightly toward the north to allow for collection of surface water at a single location away from the waste fill access ramp.

Sheet 6 in Appendix A.1 shows the Phase I Intermediate Closure configuration that provided approximately 1,000,000 cubic yards of initial airspace in the Phase I area. The intermediate closure was primarily an operational condition to allow time for the then newly constructed Phase II to be filled to an elevation above the Phase I/II berm. Design considerations for this intermediate fill plan consisted of the following:

- A maximum waste elevation of approximately 810 feet to provide the 1,000,000 cubic yards of airspace.
- The east-facing intermediate closure slope was configured to provide adequate stability against a potential wedge failure occurring along the liner system. This stability consideration is discussed in Section 5.3.4.
- The south-facing intermediate closure slope was configured such that the access ramp to the Phase I waste area was maintained to provide access into the Phase II disposal area.
- The north-facing intermediate closure slope was provided to avoid having any laterally-unsupported portion of the waste fill directly on the liner system.

The Phase I Intermediate Closure top deck included a run-off collection sump to temporarily collect direct rainfall run-off from the top deck area. Control of this run-off is described in Section 4.9.3.

Once the Phase I Intermediate Closure elevations were reached, the flatter portions of the intermediate closure slopes (i.e., the top deck slopes) were temporarily covered by a nominal soil foundation layer and an overlying temporary 40-mil HDPE geomembrane for infiltration control. The temporary run-off collection sump in the top deck area was also lined with a 40-mil HDPE geomembrane to minimize infiltration during the infrequent periods when surface water was temporarily retained in this sump. The sideslope portions of the Phase I Intermediate Closure area were covered with soil as shown in Section A-6/23 on Sheet 23 in Appendix A.1 to provide stability and infiltration control. This soil was recovered and used for daily cover when waste disposal in the Phase I area resumed. Additionally, the 40-mil HDPE geomembrane was removed prior to covering the interim Phase I top deck with additional waste.

### 4.3 Phase II

Phase II comprises the eastern 60 percent (approximately) of the existing B-18 area (see Sheets 2, 8, 9, and 10 in Appendix A.1). This area encompasses the initial Phases I and II clay borrow area (excavated during the Phase I construction), the Phases I and II clay mixing area shown on the Drawings in Appendix A.1, and the Phase II clay borrow area expansion shown on Sheet 7 in Appendix A.1 (excavated prior to the construction of Phase II). Phase II of B-18 was configured so that:

- Disposed wastes are located within the 1990 CUP Facilities Boundary (Kings County, 1990).
- The number of boundary curves, which complicate construction, were minimized.
- The waste is adequately stable under the operating and interim fill conditions.

The eastern portion of Phase II was located to allow for the construction of the Northeast Containment Basin (see Sheet C-2 and C-3 in Appendix A.2).

Most of the Phase II area was also formed by excavation into rock of the San Joaquin Formation. A fill embankment was constructed along the eastern portion of Phase II where the former main natural drainage channel formed a low spot in the B-18 perimeter (see Figure 2.1). This fill embankment contains waste on its western (Phase II) side and forms the western sideslope of the Northeast Containment Basin on its eastern side. A cross-section of this embankment is shown in Section A-8/23 on Sheet 23 in Appendix A.1. Fill was also placed along the southern portion of the B-18 Perimeter Road (see Section D-8/15 on Sheet 15 in Appendix A.1) and to form the remaining upper sideslopes of the Northeast Containment Basin.

Waste truck access into Phase II occurred along the previously-described (see Section 4.2) access route into Phase I. This was accomplished by extending the Phase I access ramp across the Phase I/II Berm and then constructing an access ramp down the southern Phase II sideslope, as shown on Sheet 9 in Appendix A.1. This access ramp was 44 feet wide (see Section A on Sheet 16A in Appendix A.1) to provide adequate room for waste truck and operations equipment traffic.

As with Phase I, the existing B-18 Perimeter Road (see Section A-3,8/15 on Sheet 15 and Section A on Sheet 17 in Appendix A.1) is typically set back approximately 20 feet from the Phase II waste disposal limit to allow for the future construction of the final closure cover (Section 4.5). This separation is wider at two locations along the northeastern and southeastern portions of the B-18 Perimeter Road to accommodate the Phase II LCRS riser pads.

Phase II is also provided with two separated sumps (see Sheets 8, 9, and 10 in Appendix A.1) serving areas designated as Areas IIA and IIB. These sumps are located to optimize drainage distances within the Phase II LCRS and to provide access for the leachate pump and storage facilities along the Phase II perimeter.

Waste placement in the Phase II area also occurred in nearly level lifts to avoid laterally-unsupported slopes against the liner system. A slight slope on the waste surface was maintained toward one or two low areas during filling to allow for collection of direct rainfall run-off in the Phase II area. Procedures that were used for handling this run-off are described in Section 4.9.5.

When the waste elevation in Phase II reached the Phase I/II berm height, the entire existing B-18 Landfill began operating as a single contiguous disposal area.

#### 4.4 Phase III

The proposed Phase III vertical and lateral expansion of B-18 will increase the footprint area of the landfill by approximately 14 acres. Most of the lateral expansion area will be along the existing western, northwestern, and southern edges of B-18. Sheet C-3 in Appendix A.2 shows the limit of the existing B-18 liner system and the limit of the Phase III expansion area. Phase III of B-18 is configured so that:

- Disposed wastes are located within the modified CUP Facilities Boundary.
- The number of boundary curves, which complicate construction, will be minimized.
- The maximum waste elevation is increased from 965 feet to 1,018 feet, which provides B-18 with a total airspace of approximately 15,700,000 cubic yards. Of this total airspace capacity (volume between base grades and final grades which includes lining and final cover systems), the expansion of B-18 accounts for approximately 5,000,000 cubic yards of airspace.
- The waste is adequately stable under the operating, interim, and final fill conditions.

Construction of the Phase III liner system will be completed in one continuous construction sequence in accordance with the certified EIR. However, to facilitate early use of a portion of the expansion area, KHF will submit a CQA certification report for the 3.5-acre Phase IIIA area in the northwestern portion of the Phase III expansion area. Once approval from the regulatory agencies is obtained, the site will begin placement of waste within the approved Phase IIIA limits. Construction of the Phase IIIB liner system will continue and would be expected to be completed within 6 months of the initiation of waste placement in Phase IIIA. A separate CQA certification report will be prepared and submitted for Phase IIIB.

The configuration of the Phase IIIA waste fill is shown on Sheet C-4A in Appendix A.2. As can be seen on Sheet C-4A, the waste placement in Phase IIIA will involve filling to final design grades along the north, east, and west portions of the landfill. The south limit of waste in Phase IIIA will terminate in a 2H:1V interim waste fill slope. A lined temporary stormwater containment berm will be provided a minimum of 10 feet from the toe of the Phase IIIA interim waste slope as shown in Detail 1 on Sheet C-4A. This temporary berm will prevent stormwater run-off from the 24-hour PMP storm event from leaving the Phase IIIA area and will also prevent stormwater run-on from entering the Phase IIIA area from the south, as discussed in Sections 5.5.5 and 5.5.4, respectively. The Phase IIIA area will not involve the construction of any leachate controls; the temporary stormwater containment berm will also serve to contain leachate and direct this leachate to the adjacent Phase IA leachate collection system.

The southern limits of Phase III are located to allow for the construction of a second surface water run-off containment basin for B-18, herein referred to as the South Containment Basin, which will be built during the construction of Phase IIIB. The layout of Phase III and the South Containment Basin also allows two of the existing groundwater monitoring wells along the south side of B-18 (K-51 and K-32R) to be protected during the construction of Phase III. Monitoring well K-68 will be extended due to soil fill placement in the vicinity of this well.

The Phase III expansion will involve the construction of an additional sideslope liner system only (i.e., no additional base liner will be installed). Most of the Phase III sideslope liner will be constructed over either the existing B-18 Perimeter Road or the existing rock cut slopes located above the existing B-18 Perimeter Road. The existing rock cut slope will be regraded to the proposed design subgrade for Phase III. A fill embankment will be required along much of the southern and southeastern boundary of the Phase III limits to build this area up to the design subgrade elevations. This fill embankment will contain the waste on its northern (Phase III) side and will form the northern sideslope of the South Containment Basin on its southern side. A cross-section of this embankment is shown in Section D on Sheet C-5 in Appendix A.2.

Waste truck access into the Phase III disposal area will be initially through the existing entry point into B-18 at its northwest corner. Access to B-18 will eventually be relocated to the west side perimeter access road as the waste fill is extended above the surrounding topography.

The new B-18 Perimeter Road (see Sheet C-3 and C-4 in Appendix A.2) will typically be set back a minimum of 20 feet from the Phase III waste disposal limit to allow for the future construction of the final closure cover (Section 4.5). This separation will be wider at the locations of the three LCRS riser pads (the riser pads for Areas IA, IB, and IIB) that will be relocated up to the new B-18 Perimeter Road during the Phase III construction.

Phase III will not include any additional floor areas. Hence, no new LCRS sumps will be constructed as part of Phase III. Depending upon where leachate originates within Phase III, it will flow to one of the four existing sumps (IA, IB, IIA, and IIB).

Similar to Phases I and II, waste will be placed in the Phase III area in nearly level lifts to avoid laterally-unsupported slopes against the liner system. A slight waste surface slope will be maintained toward one or two low areas during operations to allow for collection of direct rainfall run-off in the Phase III area. Procedures that will be used for handling this run-off are described in Section 4.9.7.

#### 4.5 Final Closure

Sheet C-4 in Appendix A.2 shows the proposed B-18 final closure configuration, which is based on the following parameters:

- Overall closure slope inclinations of 4H:1V.
- Approximately 25-foot wide benches at maximum vertical intervals of 50 feet.
- Approximately 3.5H:1V slope inclinations between the individual benches.

Access to each final cover bench and the top deck will be provided by either the new B-18 Perimeter Road or the Cover Access Road that will run up the west sideslope of B-18 at the approximate location shown on Sheet C-4 in Appendix A.2. This Cover Access Road will be developed during operations to haul waste onto the above-grade disposal areas.

The final cover benches will be sloped to direct surface water flow to the Cover Access Road and/or the new B-18 Perimeter Road. The longitudinal slope of the benches will generally be about 2 percent to control flow velocities and to allow adjustment for differential settlement of the waste. The Cover Access Road and the new B-18 Perimeter Road will both be sloped at about 8 percent in most locations.

Each final cover bench will be configured as a trapezoidal drainage ditch to provide the necessary capacity to adequately convey surface water flows resulting from the 6-hour Probable Maximum Precipitation (PMP) storm event. The 6-hour PMP is used to design conveyance structures (e.g. channels) since the rainfall intensity is greater than the 24-hour PMP, and is therefore conservative. The Cover Access Road will be configured with a lined V-ditch to convey surface water flows from the 100-year 24-hour storm event. In the event of the 6-hour PMP storm event, the flow will be contained within the road width.

In accordance with the current Hazardous Waste Facility Permit for the KHF (DTSC, 2003), the final cover system for B-18 will consist of the following components (from bottom to top):

- Intermediate soil cover (minimum of 1 foot) over the last lift of waste.
- A foundation layer consisting of a minimum of 1 foot of compacted soil having a maximum permeability of  $1 \times 10^{-5}$  cm/s.
- 40-mil textured HDPE geomembrane.
- A 12 oz/sy nonwoven geotextile.
- A minimum 2.5-foot-thick vegetative cover soil layer. The top surface of the vegetative cover soil layer will be vegetated with plants having shallow root depths. Seed types for the final cover vegetation are provided in Section 02924 of the final closure Specifications in Appendix O.2.

The portions of the geomembrane located under the Cover Access Road and benches will be sloped at a minimum of 2 percent toward the outside of the landfill so that any water in the geotextile drainage layer can flow toward the toe of the cover system around the perimeter of the landfill.

Detail 4 on Sheet C-7 in Appendix A.2 shows the typical perimeter detail of how the final cover system will be terminated and toed out onto the B-18 Perimeter Road. The HDPE geomembrane and geotextile of the cover system will be terminated approximately 5-feet out beyond the limit of the foundation layer.

In accordance with 22 CCR 66264.111 and 66264.310, B-18 has been designed to be closed in a manner that will:

- Minimize the need for further maintenance;
- Control, minimize or eliminate, to the extent necessary, to protect human health and the environment, post-closure escape of hazardous waste, hazardous constituents, leachate, contaminated rainfall or run-off, or waste decomposition products to groundwater, surface water or the atmosphere;
- Prevent the downward entry of water into the closed landfill throughout a period of at least 100 years;
- Promote drainage;
- Accommodate settling and subsidence so that the cover's integrity is maintained; and

- Accommodate lateral and vertical shear forces generated by the MCE.

After waste acceptance ceases in B-18, the intermediate cover/foundation layer will be graded per the final closure grading plan, as shown on Sheet C-4. A 40 mil HDPE geomembrane, geotextiles and vegetative cover will be constructed over the foundation layer. The entire cover will be vegetated for erosion control. The final cover has been designed to avoid ponding, control run-off, minimize erosion and withstand the MCE event. Therefore the cover will function with minimum maintenance. The base liner and closure cover will provide barriers to protect human health and the environment.

Post-closure inspections will be performed and post-closure maintenance will occur in accordance with the Hazardous Waste Facility Permit (DTSC, 2003).

## 4.6 Clay Borrow Operations

### 4.6.1 Phases I and II

The initial Phases I and II clay borrow area excavation was completed during the Phase I excavation as shown on Sheet 3 in Appendix A.1. Sheet 7 in Appendix A.1 shows how the Phases I and II clay borrow area was extended toward the southeast before the Phase II construction began. The cross-sections on Figure 3.2 illustrate how the area was excavated to borrow clay from the thick Stratum 18-8 claystone in the Phase II footprint.

The west-facing sideslope of the clay borrow area was excavated along the rock's dip as the claystone was recovered down to the underlying stratum. This sideslope had an inclination of approximately 25 to 30 degrees on average. The other sideslopes of the clay borrow area cut across bedding planes and were inclined at 2H:1V.

A bench was provided around the initial borrow area (see Sheet 3 in Appendix A.1) at an elevation of approximately 720 feet. This bench was used to anchor the 40-mil HDPE geomembrane (see Section B on Sheet 13 in Appendix A.1) in the bottom of the borrow area. This lined area served as an interim containment basin for run-off from the Phase I access roads.

Sheet 3 in Appendix A.1 also shows how the eastern portion of the Phase II area was initially graded to create a relatively flat clay mixing area. KHF construction crews prepared the claystone in this area to achieve the required engineering properties for clay liner material. The clay preparation procedures used for the Phases I and II construction included the following activities:

- Ripping and excavation of the claystone in a manner that reduced the friable material to relatively small particle sizes;
- Mechanical breakdown of the excavated material to further reduce particle sizes; and
- Moisture conditioning of the clay liner material on mixing tables.

The clay liner test pad described in Appendix E.1 was constructed of Stratum 18-8 clay from the Phases I and II borrow source. This clay liner test pad program demonstrated that the Stratum 18-8 clay was suitable for use as clay liner material under field conditions.

#### 4.6.2 Phase III

The Phase III clay borrow area will be located adjacent and north of Landfill Unit B-17 (i.e., northwest of B-18), as shown on Sheet C-1 in Appendix A.2. This clay borrow source consists of a thick bed of the Pecten Claystone (see Appendix E.2). The contractor will be responsible for excavating and processing all of the required clay liner material for Phase III. Excavation and processing of the Pecten Claystone may be performed as part of the construction of various phases of Landfill B-17. KHF personnel will instruct the contractor on the appropriate excavation configurations to be used when mining the Pecten Claystone from the borrow area.

Sheet C-1 in Appendix A.2 also shows the designated clay mixing area that will be used by the contractor to process and prepare the clay liner material. This mixing area will be located adjacent to the clay borrow area (i.e., northwest of B-18). The final clay preparation procedures, to be determined by the contractor, may include combinations of the following activities:

- Ripping and excavation of the claystone in a manner that reduces the friable material to relatively small particle sizes;
- Crushing of the excavated material to further reduce particle sizes;
- Blending different portions of the claystone by the use of a pugmill or discing the material in lifts; and
- Pre-wetting stockpiled clay material with fresh water and/or a weak dispersant solution to accelerate weathering prior to re-excavation of the stockpiled clay.

A clay liner test pad was constructed from the Pecten Claystone material at the end of July 2008. The SDRI test report was completed in December 2008 (Geosyntec, 2008a). This clay liner test pad program verified the adequacy of the clay material from the Phase III borrow source when placed and compacted under actual field conditions. Based on laboratory testing and the SDRI test by Geosyntec (see Appendices E.2 and E.3), the Pecten Claystone material meets the requirements for use as clay liner. Additional pre-construction testing will be performed to confirm materials used for the construction meet the specified properties.

For Phase III, the compacted clay liner will be constructed using the same specifications as were used for the Phases I and II clay liner (see Section 4.7.2.1). Similar construction equipment will be used to compact the Phase III clay liner as was used to construct the Phases I and II clay liner test pad.

### 4.7 Liner Systems

#### 4.7.1 General

Liner system details and sections for Phases I and II are shown on Sheets 16 through 22A in Appendix A.1. The Phase III and final closure liner system details and sections are shown on Sheets C-7 through C-10 in Appendix A.2. The B-18 liner configurations are generally the same as those successfully used for prior KHF disposal WMUs. The primary modifications to the B-18 liner system design compared to KHF landfills designed prior to 1990 are:

- The use of textured HDPE geomembranes throughout B-18 and the use of geocomposites and geotextiles on the sideslope areas to improve the stability of B-18.



- The use of protective liner material on the B-18 sideslopes to provide temporary ultraviolet protection to the underlying geotextile component of the geocomposite. This protective liner is removed as the operations layer soil is periodically extended up the slope in advance of the waste mass.

Each of the basic liner systems used in B-18 are described in Section 4.7.2. Special liner construction details (e.g., anchor trenches) are described in Section 4.7.3. Appendix F.1 contains data sheets that list representative properties of the geosynthetic materials used in the construction of Phases I and II. Similarly, Appendix F.2 contains data sheets that list typical properties of the geosynthetic materials that will be used in the construction of Phase III and the final cover. The CQA reports for Phases I and II contain detailed information on the properties of the existing B-18 liner systems.

#### 4.7.2 Liner System Configurations

##### 4.7.2.1 *Base Liner*

The existing base (i.e., floor) areas of B-18 were each graded to drain toward a sump where leachate is monitored and collected in the three separate zones (primary, secondary, and vadose) described in Section 4.8. The entire base of each of the four areas (IA, IB, IIA, and IIB) was graded at 2 percent toward a central flow line. The central flow line in each area was sloped at 2.4 percent toward that area's respective collection sump. No new base area will be constructed for Phase III.

Detail 2 on Sheet 16 in Appendix A.1 shows the general B-18 base liner system configuration, which consists of the following components (from top to bottom):

- A 2-foot-thick (minimum) base soil operations layer. This operations layer was constructed from on-site granular material with a maximum particle size of 6 inches. The purpose of this layer was to provide a working surface for waste trucks and landfill equipment while protecting the underlying liner system components.
- A 1-foot-thick (minimum) primary LCRS consisting of the following components (from top to bottom):
  - An 8 oz/sy nonwoven geotextile (Trevira 1125) to function as a filter below the operations layer soil.
  - A 12-inch-thick (minimum) drainage gravel layer. A single-sided geocomposite filter/drainage layer consisting of an 8 oz/sy nonwoven geotextile (Trevira 1125) thermally-bonded to one side of a Polynet 3000 geonet. The geocomposite was placed with the geotextile facing up.
  - An 8 oz/sy nonwoven geotextile (Trevira 1125) to provide increased interface shear strength.
- A composite primary liner consisting of the following components (from top to bottom):
  - A 60-mil textured HDPE geomembrane.

A 1.5-foot-thick (minimum) layer of compacted clay having a maximum permeability of  $1 \times 10^{-7}$  cm/s.

- A secondary LCRS consisting of the following components (from top to bottom):

A 16-oz/sy nonwoven geotextile (Trevira 1155) to function as a filter below the primary clay liner.

An approximately 12-inch-thick layer of drainage gravel.

A single-sided geocomposite filter/drainage layer consisting of a 16-oz/sy nonwoven geotextile (Trevira 1155) thermally-bonded to one side of a Polynet 3000 geonet. The geocomposite was placed with the geotextile facing up.

An 80-foot-wide layer of Polynet 3000 geonet centered along the entire secondary LCRS flow line above the vadose trench.

A 16-oz/sy nonwoven geotextile (Trevira 1155) to provide increased interface shear strength.

- A composite secondary liner consisting of the following components (from top to bottom):

A 60-mil textured HDPE geomembrane.

A 3.5-foot-thick (minimum) layer of compacted clay having a maximum permeability of  $1 \times 10^{-7}$  cm/s.

- A prepared subgrade that was graded smooth and proof-rolled to assure that soft or loose zones did not exist.

Both of the clay liners (primary and secondary) were placed in 8-inch-thick (maximum) loose lifts before compaction. The Phases I and II Specifications (ESI, 1990b) required the clay to be compacted to a dry density of at least 90 percent of its Modified Proctor maximum dry density (ASTM D1557) at a water content wet of optimum (ASTM D1557). During the Phase I construction, the clay liner placement specifications were modified to allow the compacted clay's dry density and moisture content to lie within the window defined by the following four points on a moisture-dry density plot:

- Two (2) percent above the optimum moisture content for a dry density equal to 90 percent of the Modified Proctor maximum dry density.
- Five (5) percent above the optimum moisture content for a dry density equal to 90 percent of the Modified Proctor maximum dry density.
- One (1) percent above the optimum moisture content for a dry density equal to 98 percent of the Modified Proctor maximum dry density.
- Three (3) percent above the optimum moisture content for a dry density equal to 97 percent of the Modified Proctor maximum dry density.

This window, which allowed a lower water content for higher compactive efforts, was established to:

- Assure that both the required strength and permeability characteristics of the clay were achieved; and
- Provide the flexibility needed for controlling the clay's moisture content in an arid environment.

It should be noted that an allowance was made for up to 20 percent of the clay moisture-density test results to be slightly outside the above-described compaction window by  $\pm 0.5$  percent for moisture content and -0.5 percent for relative compaction as long as the average of all acceptable tests for the day fell within the compaction window. The above-described compaction window (along with the allowance for outliers) was used for both the Phases I and II clay liner construction and was formally documented in two design change letters prepared by ESI and contained in the CQA reports for Phases I and II (ECS, 1992h; GCS, 1993h). Copies of both of these ESI letters are included in Appendix E.4.

#### 4.7.2.2 *Vadose Zone Trench*

Section C on Sheet 16 in Appendix A.1 shows the 12-foot-wide vadose trench that is located directly below the secondary clay liner and along the flow line of the LCRS. Key elements of the vadose trench are:

- An 80-mil smooth HDPE geomembrane, which extends approximately 2.5 feet beyond both sides of the trench; and
- A 1-foot-thick layer of drainage gravel wrapped in a 16-oz/sy nonwoven geotextile (Trevira 1155).

#### 4.7.2.3 *Phases I and II Sideslope Liner*

Detail 1 on Sheet 16 in Appendix A.1 shows the typical existing Phases I and II sideslope liner system configuration. This system includes each basic component of the base liner system except the drainage gravel layers and the primary clay liner, none of which are required due to the relatively steep inclination of the sideslope liner system and the resulting rapid drainage of any liquids in the LCRS. The Phases I and II sideslope liner system consists of the following components (from top to bottom):

- A 2-foot-thick (minimum) soil operations layer to protect the liner system from the disposal operations. A 1-inch maximum particle size criterion was established for the slope operations layer because this material was placed directly against the geosynthetic layers. The slope operations layer was placed in increments at least 3 feet but not more than 10 feet above the rising waste level.
- A temporary protective liner to protect the underlying geotextile component of the geocomposite from ultraviolet light prior to placement of the operations layer. This protective liner consisted of white 40-mil smooth HDPE geomembrane and was removed as the operations layer was placed.

- A primary LCRS consisting of a single-sided geocomposite underlain by an 8 oz/sy nonwoven geotextile (Trevira 1125). The single-sided geocomposite consisted of an 8 oz/sy nonwoven geotextile (Trevira 1125) thermally-bonded to a Polynet 3000 geonet and was placed with the geotextile facing up. In construction of Phase II the components were combined in a double-sided geocomposite.
- A primary liner consisting of a 60-mil textured HDPE geomembrane.
- A secondary LCRS consisting of a single-sided geocomposite underlain by an 8 oz/sy nonwoven geotextile (Trevira 1125). The single-sided geocomposite consisted of an 8 oz/sy nonwoven geotextile (Trevira 1125) thermally-bonded to a Polynet 3000 geonet and was placed with the geotextile facing up. In construction of Phase II the components were combined in a double-sided geocomposite.
- A composite secondary liner that is the same as that used in the base liner system and consists of the following components (from top to bottom):
  - A 60-mil textured HDPE geomembrane.
  - A 3.5-foot-thick (minimum) layer of compacted clay having a maximum permeability of  $1 \times 10^{-7}$  cm/s.
- The sideslope subgrade that was prepared differently than the subgrade for the base liner in order to increase stability of the clay liner. The sloped subgrade surface was scarified to a depth of approximately 4 inches as the clay liner was placed to create a rough interface between these two soil layers.

#### 4.7.2.4 Phase III Sideslope Liner

Detail 1 on Sheet C-7 in Appendix A.2 shows the typical Phase III sideslope liner system configuration. This system is the same as the existing sideslope liner system for Phases I and II except the secondary clay liner will have a minimum thickness of 3 feet instead of 3.5 feet and double-sided geocomposites will be used instead of single-sided geocomposites with an underlying geotextile. The Phase III sideslope liner system will consist of the following components (from top to bottom):

- A 2-foot-thick (minimum) soil operations layer with a 1-inch maximum particle size criterion. The slope operations layer will be placed in increments at least 3 feet but not more than 10 feet above the rising waste level.
- Prior to the placement of the 2-foot-thick operations layer on the slope, a temporary 40 mil thick white HDPE protective liner will be installed. The protective liner will be removed as the operations layer is placed.
- A primary LCRS consisting of a double-sided geocomposite.
- A primary liner consisting of a 60-mil textured HDPE geomembrane.
- A secondary LCRS consisting of a double-sided geocomposite.

- A composite secondary liner consisting of the following components (from top to bottom):
  - A 60-mil textured HDPE geomembrane.
  - A 3-foot-thick (minimum) layer of compacted clay having a maximum permeability of  $1 \times 10^{-7}$  cm/s.
- A prepared subgrade that will be scarified to a depth of approximately 4 inches as the clay liner is placed to create a rough interface between these two soil layers.

#### 4.7.2.5 *Base to Sideslope Liner Transition*

Details 4 and 5 on Sheet 16 in Appendix A.1 show how geotextiles were wrapped around the ends of the drainage gravel and clay layers where the existing base and sideslope liner systems meet. Since there will be no connection between the new Phase III side slope liner and any of the base liner areas of Phases I and II, this does not apply to construction of the Phase III area.

#### 4.7.2.6 *Final Cover Liner*

The final closure cover liner system for B-18 will be similar to the final cover liner system approved in the Part B Permit and which has been used for closure of several other WMUs at KHF. The final closure cover liner system is described in Section 4.5.

#### 4.7.3 Special Liner Details

##### 4.7.3.1 *Sideslope Liner Anchor Trenches*

Detail 3 on Sheet 16 in Appendix A.1 shows the typical existing sideslope liner system anchor trench around the perimeter of the existing landfill. The primary requirements of the anchor trench are to prevent the geosynthetic components of the liner system from being pulled down the slope and to minimize the potential for surface water to enter the LCRSs. A vertical separation of 0.5 feet was maintained between the individual geosynthetic components in the anchor trench to provide soil friction against each of these geosynthetics. A 3-foot-tall soil berm was installed above the anchor trench to increase the frictional resistance on the geosynthetic components and to control surface water drainage.

The construction of Phase III will result in some of the existing anchor trenches being removed, as shown in Detail 5 on Sheet C-7 in Appendix A.2. The new anchor trenches for the Phase III sideslope liner system will typically have the configuration shown in Detail 2 on Sheet C-7 in Appendix A.2. The new anchor trenches will be configured similar to the existing anchor trenches except that the 0.5-foot vertical separation between geosynthetic components in the anchor trench is not required and the depth and width of the Phase III anchor trench are slightly less than that of the existing anchor trench.

The final closure cover system will be installed above the perimeter anchor trench as shown in Detail 4 on Sheet C-7 in Appendix A.2. This detail was described in Section 4.5.

#### 4.7.3.2 Temporary Phase I/II Transition Anchors

The B-18 liner system was temporarily terminated along the eastern edge of Phase I prior to the construction of Phase II. During the construction of Phase II, the Phases I and II liner systems were spliced together at the following locations:

- Along the top of the Phase I/II Berm.
- Along the north and south sideslopes above the Phase I/II Berm.

Section B-5,15,23/17 on Sheet 17 in Appendix A.1 shows the temporary liner system configuration at the top of the Phase I/II Berm at the end of the Phase I construction. The temporary anchor trench at the Phase I/II Berm was relatively far from the slope (12 feet) to provide room for the splicing of the Phases I and II liner systems. Also, the portion of the liner system on top of the Phase I/II Berm was sloped 2 percent toward Phase I to assure that leachate ponding did not occur. A small soil berm was constructed on top of the temporary anchor trench to increase frictional resistance of the geosynthetics, control surface water drainage, and provide a foundation for the temporary lights as shown in Section B on Sheet 23 in Appendix A.1.

The procedure that was used to splice the Phases I and II liner systems at the Phase I/II Berm included the following steps:

- The temporary small soil berm, drainage ditches, and light poles were removed.
- The liner system was cut a minimum of 3 feet back (i.e., toward Phase I) from the temporary anchor trench and then this anchor trench was removed.
- The east side of the Phase I/II Berm was graded to match the base of the existing clay liner while maintaining the 2 percent slope toward Phase I.
- The existing 4-foot-thick secondary clay liner on top of the Phase I/II Berm was extended to connect with the clay liner on the west sideslope of Phase II.
- Each individual geosynthetic component was spliced at the cut location, resulting in a continuous liner system over the top of the Phase I/II Berm as shown in Section B-9,10/17 on Sheet 17 in Appendix A.1.

Section B-4,5/16 on Sheet 16 in Appendix A.1 shows the temporary anchoring procedure that was used for the Phase I/II transition on the south and north sideslopes above the Phase I/II Berm. The temporary anchors at these locations were different than those at the tops of the sideslopes since there are no significant liner stresses acting perpendicular to the anchoring. The temporary edge of the Phase I sideslope liner was anchored by:

- Securing approximately 6 feet of the secondary 60-mil HDPE geomembrane beneath 2 feet of compacted clay. Clay was used to provide increased erosion resistance on the slope.
- Cutting and welding the primary 60-mil HDPE geomembrane and temporary protective liner to the secondary 60-mil HDPE geomembrane above the temporary

anchor trench. The geocomposites and geotextiles were also cut to end just inside these welds.

Section B-4,5/16 on Sheet 16 in Appendix A.1 also shows how clay was used to contain a temporary 18-inch diameter corrugated metal pipe (CMP) on the southside slope only. This pipe was used to convey surface water run-off from the B-18 Perimeter Road to the temporary drainage ditch along the top of the Phase I/II Berm.

The splicing of the Phases I and II liner systems on the north and south sideslopes was similar to that described above for the liner system splice at the top of Phase I/II Berm. Section B-9,10/16 on Sheet 16 in Appendix A.1 shows how the Phases I and II sideslope liner systems were spliced together.

#### 4.7.3.3 *Phases I and II Access Ramp Liner*

Section D-4,5/17 on Sheet 17 in Appendix A.1 shows a typical cross-section through the 35-foot-wide access ramp along the Phase I sideslopes. Key aspects of the design of this access ramp are:

- Both the primary and secondary LCRSs were sloped 2 percent toward the landfill to promote drainage without the need for water to flow the entire length of the ramp.
- An extra layer of 16 oz/sy nonwoven geotextile (Trevira 1155) was placed over the primary LCRS geocomposite to provide added cushioning under traffic loading.
- Three feet of operations layer soil (1-inch maximum particle size) was placed above the extra 16 oz/sy geotextile to further protect the liner system. The operations layer was also extended at least 10 feet up the sideslope areas adjacent to the access ramp to avoid the potential for traffic to accidentally drive onto the liner system.
- The roadway was finished with 1 foot of Class 2 aggregate base to provide all-weather access. Note that this aggregate base layer was used instead of the 4-inch-thick asphalt pavement shown in Section D-4,5/17 on Sheet 17 in Appendix A.1.

A special detail to weld the secondary 60-mil HDPE geomembrane was provided to facilitate continuous access along the ramp during construction and to minimize the potential for the liner to lift off of the ramp before the other materials and operations layer were placed. This was accomplished by anchoring the secondary HDPE geomembrane from the bottom sideslope in a trench about 15 feet from the toe of the upper sideslope. This 15-foot zone was then used for access until the upper sideslope portion of the secondary HDPE geomembrane was installed.

Section A on Sheet 16A in Appendix A.1 shows the arrangement of the Phase II access ramp. This ramp into the Phase II area was 44 feet wide to provide adequate space for the waste trucks and landfill equipment. The special liner details and protection details for the Phase II access ramp were similar to those described above for the Phase I access ramp.

## 4.8 Leachate Collection and Recovery System (LCRS)

### 4.8.1 General

The main features of the B-18 LCRS are the collection sumps where leachate is detected and removed. Phases I and II have two sumps each (see Sheets 5 and 10 in Appendix A.1), which

subdivide these phases into Areas IA and IB and Areas IIA and IIB, respectively. Phase III will utilize the existing sumps for Phases I and II and, therefore, no additional sumps will be installed.

Phase IIIA will be constructed such that leachate from Phase IIIA will be able to flow directly into the Phase IA LCRS. No interim control measures, except a temporary lined containment berm at the edge of Phase IIIA/IIIB (see Sheet C-4A in Appendix A.2) will be required. Stormwater contained on the north side of this temporary berm (i.e., between the berm and the Phase IIIA waste mass) will be treated as leachate and will be handled in the same manner as leachate that is collected in the existing B-18 leachate storage tanks (located on the concrete riser pads). The temporary berm has been sized such that stormwater run-off from the 24-hour PMP event will be fully contained on the north side of the berm with greater than 1 foot of freeboard.

The layout of the sumps in Areas IA and IB are shown on Sheet 18 in Appendix A.1. The layout of the sumps for Areas IIA and IIB are shown on Sheet 18A in Appendix A.1. Representative cross-sections through the sumps are provided on Sheets 19, 19A, 20, 20A, 22, and 22A in Appendix A.1. Sheet 21 in Appendix A.1 provides typical details for the vertical riser pipe that was installed at each of the four primary sump locations. Sheets 22 and 22A in Appendix A.1 also show details for the existing four riser pads (one riser pad is above each sump) that enable the removal and handling of the leachate. Of the four existing riser pads, three of them (the pads for Areas IA, IB, and IIB) will be removed during the construction of Phase III to allow for the expansion of the B-18 waste footprint in these areas. Three new riser pads will be constructed during Phase III as replacements for the three pads to be removed as shown on Sheet C-3 in Appendix A.2. Typical details for the new riser pads to be constructed during Phase III are shown on Sheet C-8 in Appendix A.2. These new riser pads will be very similar to the existing ones.

Each B-18 sump includes the following three leachate (or leak detection) collection and recovery zones (from top to bottom):

- The primary LCRS, which collects liquids that have infiltrated through the overlying waste and operations layer. The design of the primary LCRS is based on providing adequate pump capacity so that the liquids level in each sump will not exceed the height of that sump, which is taken to be the elevation of the landfill base at the sump perimeter.
- The secondary LCRS, which is typically not expected to be affected by liquids infiltration but drains consolidation water from the overlying clay liner and any seepage that may pass through leaks in the primary liner system.
- The vadose zone collection system, which is located in a 12-foot-wide trench below the secondary liner system. The purpose of this zone is to detect any seepage through leaks in the secondary liner system. Some clay consolidation water may also be collected in the vadose zone as increasing amounts of waste are placed within B-18.

Each of the four sump areas is located so that leachate pumps are lowered into the respective gravel collection zones through sideslope riser pipes. The primary LCRS design also includes a vertical riser pipe in each sump area that is extended upward in segments as the surrounding waste is placed. Details of the individual systems are described in the following three subsections.



#### 4.8.2 Primary LCRS

The maximum operating liquid level for each of the four primary LCRSs is 1 foot above the top of each sump, where the top of a sump corresponds to the lowest point where the 5H:1V sump sideslope meets the toe of the landfill sideslope. The liquid level in each sump is currently maintained as low as possible using a pump, which is lowered to the sump through an existing 8-inch diameter steel riser pipe that lies on a 60-mil HDPE rub sheet (see Section A on Sheet 22 in Appendix A.1). The bottom portion of this riser pipe consists of Type 304 stainless steel to resist corrosion. Above the level of normal liquids exposure, the existing riser pipe is carbon steel that is double-wrapped to protect against corrosion. During the Phase III construction, the primary sideslope riser pipes in Areas IA, IB, and IIB will be extended up the new Phase III sideslopes by connecting a 10-inch diameter HDPE pipe to the existing 8" diameter steel pipe as shown in Detail 3 on Sheet C-8 in Appendix A.2. The existing pumps and controls will be replaced with a system capable of reaching the extended length of the riser and providing a pumping capacity that will maintain the liquid level below the allowable limit.

At each sump, the primary leachate pump is lowered through the sideslope riser pipe into a 4-foot by 8-foot by 1.5-foot-deep gravel-filled pumping zone. This arrangement maximizes the pumping effectiveness of the system. Pumping is controlled manually as required. The pumping need is determined by a water level control bubbler system or equivalent system that provides liquid level sensing at the top of the riser pipe when sufficient liquids for pumping exist in the sump.

As shown in Section A and Detail 1 on Sheet 18 in Appendix A.1, the bottom of each sideslope riser pipe is connected to a perforated collection tee that is also made of stainless steel. This tee lies on and against 2-inch-thick HDPE flatstock to protect the primary liner system from impact and pipe movements as the pumps are operated and periodically removed for maintenance and repair.

Historically (January 2001 to December 2007), the primary LCRS has removed an average of 360 gallons per day from the 4 sumps. During this period, the peak flow in a primary LCRS sump was 98,000 gallons (Phase IB) during January 2006, or 3,300 gallons per day. The volume of liquids removed during Phase III waste placement and after closure is expected to remain the same or diminish after closure.

In addition to the sideslope riser pipes, each of the four sumps has a redundant vertical riser pipe that can also be used to pump leachate from the primary LCRS. Each of the four vertical riser pipes is extended upward in about 10-foot increments as the level of the surrounding waste rises. The design of the vertical riser pipes includes several features, shown on Sheet 21 in Appendix A.1, to control the drag loads transmitted to the pipe as the surrounding waste settles. These features include the following:

- The bottom 7 feet (approximately) consists of perforated, 18-inch diameter stainless steel pipe founded in the small pumping sump adjacent to the perforated tee for the sideslope riser pipe. This bottom pipe telescopes into the main vertical riser pipe through a concrete footing such that drag loads are not transmitted to the pumping area.
- The main 24-inch diameter carbon steel vertical riser pipe is surrounded by a thin-walled corrugated HDPE pipe. This corrugated pipe, which is very flexible in the longitudinal direction, deforms as the adjacent wastes settle, thereby reducing the potential for large drag loads to act on the steel vertical riser pipe.

- A 6-foot by 6-foot reinforced concrete footing provides support for the 24-inch diameter carbon steel pipe and any drag loads that may act on the steel pipe.

The corrugated HDPE pipe has a diameter of 30 inches to provide an annular space for lateral deformation to occur around the 24-inch steel pipe. Spacers were provided inside the corrugated pipe to keep the riser pipe alignment nearly vertical at the time of its initial installation.

As shown in Detail 6 on Sheet C-7 in Appendix A.2, slip connections will be installed in the Area IA and IB vertical risers due to the increased height of waste that will be placed over these areas during the Phase III expansion. These slip connections will be placed at an elevation of between 900 and 910 feet and will reduce the potential drag loads transmitted to the existing 24-inch diameter vertical riser pipes. Analysis of the existing concrete pad at the base of the liner to withstand the additional vertical force related to the expansion was performed and is contained in Appendix L. As shown, the existing pads can satisfactorily carry the additional load related to the extended risers and the down-drag forces related to waste settlement.

Initially, a backup 350 gpm, 20 horsepower submersible pump was installed through each vertical riser pipe and into the primary pumping sump. However, these backup pumps were never used and are no longer provided since they presented difficulties when extending the vertical riser pipes. In the future, backup pumps can be provided through the vertical risers on an as-needed basis.

During the Phase III construction, there will be a period of approximately 6 months between the demolition of the existing LCRS riser pads and the installation of the new riser pads. The primary LCRS will continue to be monitored on a daily basis for liquid level and liquids will be removed in accordance with site protocol during this period by placing pumps down the existing vertical riser pipes (which will not be disturbed during the Phase III construction) and/or by placing pumps down the sideslope risers that will be cut off at the existing riser pads. As the sideslope risers are extended, but before the new riser pads are constructed, a wye fitting will be installed in each sideslope pipe close to the locations of the demolished riser pads (i.e., near the bottom of Phase III). Pumps and level monitoring equipment can be inserted through the wye and then lowered down the sideslope riser. Once the new riser pads are completed, the wyes will be removed and the sideslope risers repaired at those locations.

#### 4.8.3 Secondary LCRS

The existing secondary LCRS is provided with two 8-inch diameter sideslope riser pipes as shown in Section A-18/19 and Detail 2 on Sheet 19 in Appendix A.1 and in Section C-18/20 on Sheet 20 in Appendix A.1. The bottom portion of one of these pipes is Type 304 stainless steel connected to a perforated stainless steel tee. The portion of this existing pipe above the level of normal liquids exposure is double-wrapped carbon steel. The other riser pipe is SDR 8.3 HDPE pipe for its entire length. During the Phase III construction, the secondary sideslope riser pipes in Areas IA, IB, and IIB will be extended up the new Phase III sideslopes. The existing HDPE riser pipe will be extended by splicing to a similar diameter pipe while the existing steel riser pipe will be extended by splicing to a 10-inch diameter HDPE pipe as shown in Detail 3 on Sheet C-8 in Appendix A.2.

A 4-foot by 4-foot by 1.5-foot-deep pumping zone was provided for the secondary LCRS. The perforated tee lies on and against a 2-inch-thick HDPE flatstock to protect the underlying HDPE geomembrane. The HDPE riser pipe terminates against the tee.

Both secondary sideslope riser pipes are sized to contain a pump and a bubbler liquid level control gauge. However, the current operating configuration has the pump in the steel riser pipe and the level control gauge in the HDPE riser pipe.

Historically (January 2001 to December 2007), there has been very little liquid in the secondary LCRS, averaging less than 10 gallons per day from B-18 sumps. Peak flow in the secondary LCRS approached 150 gallons per day in January 2006. This peak resulted from damage to the primary liner system that allowed rainfall to enter the secondary LCRS. The damage was subsequently repaired and leachate volumes have reduced to zero since March 2007.

The existing pumps and controls will be replaced with a system capable of reaching the extended length of the riser and providing a pumping capacity that will maintain the liquid level below the allowable limit. The maximum operating liquid level is 1 foot above the top of each secondary LCRS sump.

During the Phase III construction, there will be a period of approximately 6 months between the demolition of the existing LCRS riser pads and the installation of the new riser pads. The secondary LCRS will continue to be monitored on a daily basis for liquid level and liquids will be removed in accordance with site protocol during this period by placing pumps down the sideslope risers that will be cut off at the existing riser pads. As the sideslope risers are extended, but before the new riser pads are constructed, a wye fitting will be installed in each sideslope pipe close to the locations of the demolished riser pads (i.e., near the bottom of Phase III). Pumps can be inserted through the wye and then lowered down the sideslope riser. Once the new riser pads are completed, the wyes will be removed and the sideslope risers repaired at those locations.

#### 4.8.4 Vadose Zone Collection System

Section B-18A/19A on Sheet 19A in Appendix A.1 shows the configuration of the existing sideslope riser pipe used for pumping liquids from the vadose zone collection sump. A single 8-inch diameter pipe is provided since only a small volume of liquids (e.g., clay liner consolidation water) was expected to be removed from this sump. Historic (January 2001 to December 2010) LCRS pumping data indicate no liquids have been removed from the vadose LCRS. The bottom portion of the vadose riser pipe is stainless steel. During the Phase III construction, the vadose sideslope riser pipes in Areas IA, IB, and IIB will be extended up the new Phase III sideslopes by splicing a 10-inch diameter HDPE pipe to the existing steel pipe as shown in Detail 3 on Sheet C-8 in Appendix A.2.

A 4-foot by 4-foot by 1.5-foot-deep pumping zone is provided below the main 12-foot-wide vadose trench in the sump areas. The 80-mil smooth HDPE geomembrane at the bottom of the main vadose trench extends below the pumping sump to provide continuous containment. Two-inch-thick HDPE flatstock was provided as impact protection above the 80-mil geomembrane.

A pump is currently installed through the vadose sideslope riser pipe and into the vadose sump. A bubbler level control device is also provided through the 8-inch pipe. The maximum operating liquid level is 1 foot above the top of the vadose trench at each sump. During the period of January 2001 to December 2007 no liquids have been detected in the vadose sumps.

The existing pumps and controls will be replaced with a system capable of reaching the extended length of the riser and providing a pumping capacity that will maintain the liquid level below the allowable limit.

During the Phase III construction, there will be a period of approximately 6 months between the demolition of the existing LCRS riser pads and the installation of the new riser pads. Since no liquids have been detected in the vadose zone in the last 10 years, monitoring of the three vadose sumps whose riser pads are to be removed will be suspended for the duration of the Phase III construction. Once the new riser pads are constructed, monitoring of the vadose zones will resume.

#### 4.8.5 Leachate Storage

The following discussion of the leachate tank system provides information peripheral to the permitted unit's design, but supports the operational needs for understanding. Sheets 22 and 22A in Appendix A.1 show the existing top-of-slope riser pads above each sump area where liquids from the three (primary, secondary, and vadose) collection zones are handled. Flows from each pumping zone are monitored individually by a totalizer on each of the four (one primary, two secondary, and one vadose) pump discharge pipes. These pipes are then individually discharged into the top portion of a 6,000-gallon, double-walled, HDPE tank.

The double-walled tank is provided with a centrifugal pump for transferring liquids into vacuum trucks. The removed liquids are treated in on-site treatment facilities located away from B-18.

A curbed concrete slab (i.e., a concrete riser pad) is provided at each pump collection and storage tank area to contain any spilled liquids. A collection sump is provided in each concrete slab for removal of spilled liquids or rainwater.

As discussed in Section 4.8.1, three of the existing concrete riser pads (the pads for Areas IA, IB, and IIB) will be removed during the construction of Phase III. Three new riser pads will be constructed as replacements for the three pads to be removed. These new riser pads will be very similar to the existing ones and it is anticipated that the existing HDPE tanks and appurtenances will be salvaged and re-used for the new system or replaced with similar components.

### 4.9 Surface Water Control

The B-18 design includes surface water control features for the following conditions described in the indicated sections:

- Section 4.9.1 - Offsite Diversion of Run-on
- Section 4.9.2 - Active Area Run-off Control for Phase I Operations
- Section 4.9.3 - Phase I Direct Rainfall Control
- Section 4.9.4 - Active Area Run-off Control for Phase II Operations
- Section 4.9.5 - Phase II Direct Rainfall Control
- Section 4.9.6 - Run-off Control During the Above Grade Filling Period
- Section 4.9.7 - Phase III Direct Rainfall Control
- Section 4.9.8 - Run-off Control at Closure

Run-on is surface water that originates outside of the B-18 limits and it can therefore be discharged into natural stream channels. Active area run-off is surface water that flows from roads used for waste truck and/or landfill equipment access or from portions of the landfill with intermediate cover. This run-off does not come into direct contact with the waste disposal area.

The primary surface water design criteria for B-18 are the following:

- Precipitation falling directly into the disposal area must be contained within the waste prism. Resulting ponding on the waste surface must be managed as stipulated in the existing KHF permits.
- Active area run-off must be contained in surface water retention (i.e., containment) basins.

The permanent surface water controls that are used for conveying peak flows are designed based on rainfall intensity and duration relationships for the PMP storm event. The 24-hour PMP rainfall event for the site is 10.3 inches as reported by the National Oceanic and Atmospheric Administration (NOAA, 1998). The original design of B-18 (ESI, 1990a), used a 24-hour PMP storm event for the site of 7.4 inches, based on data from the California Department of Water Resources (CDWR, 1976). The CDWR used a statistical method, based on historic rainfall data, to determine the PMP rainfall depth. The CDWR no longer publishes data pertaining to PMP events as they apparently now defer to the PMP data provided by NOAA. The NOAA value is “theoretically, the greatest depth of precipitation for a given duration that is physically possible over a given storm area at a particular geographical location at a certain time of the year.” Hence, the current design PMP storm event of 10.3 inches has increased substantially from the 7.4 inches used in the original design.

#### 4.9.1 Off-site Diversion of Run-On

Sheets 5 and 10 in Appendix A.1 show the existing configuration for diverting run-on away from the B-18 area. This is accomplished by providing run-on collection ditches outside of the entire existing B-18 Perimeter Road that are capable of diverting run-on from the PMP storm event. These run-on collection ditches begin near the northwest corner of Phase I. One of these ditches diverts run-on flows along the outside of the B-18 Perimeter Road along the north side of the existing landfill. The other ditch diverts run-on flows along the outside of the B-18 Perimeter Road along the west and south sides of the existing landfill. These V-shaped run-on collection ditches are 5-foot-wide, earthen, and vary in depth from one to three feet. Sheets 5 and 10 in Appendix A.1 show the locations where changes in the depths of these ditches occur.

A buried culvert is used to convey flows from the southern-most run-on collection ditch under the B-18 Stockpile access road. This culvert is a 24-inch diameter corrugated metal pipe (CMP) that is capable of conveying the 25-year storm event. Larger storms can be safely conveyed over a swale at this road intersection. This swale is graded to maintain the entire surface water flow from the PMP storm event in the run-on collection ditch system.

Upon the completion of the Phase I construction (Sheet 5 in Appendix A.1), the run-on collection ditches were discharged into the natural drainage channel at the northeast corner of the B-18 area, near the limit of the Phases I and II clay mixing area. Upon the completion of Phase II (Sheet 10 in Appendix A.1), the run-on collection ditches were directed to an existing culvert under the KHF main access road. That culvert is capable of conveying flows from most of the storms that may be expected

to occur during the B-18 operations. Surface water from large, infrequent storms is allowed to flow across the KHF main access road with no potential for drainage to the existing waste disposal areas.

The final elements of the existing run-on collection ditch system are smaller V-ditches (brow ditches) along the tops of the existing B-18 Perimeter Road cuts. These brow ditches divert run-on from the natural hill slopes into drop inlets that discharge into the collection ditches that run along the outside

of the B-18 Perimeter Road. Due to the relatively steep slopes along the tops of these road cuts, the brow ditches are lined with asphalt to reduce erosion. The locations of the brow ditches and drop inlets are shown on Sheets 5 and 10 in Appendix A.1.

During the Phase III construction, most of the existing collection ditches along the outside edge of the existing B-18 Perimeter Road as well as the smaller brow ditches at the tops of the existing B-18 Perimeter Road cuts on the north, south, and west sides of B-18 will be removed and relocated to accommodate the expanded landfill footprint. The new collection ditches and brow ditches generally have a similar or increased capacity design as those of the existing ditches and they will be located along the outside edge of the new B-18 Perimeter Road (collection ditches) and at the tops of the cuts along the new B-18 Perimeter Road (brow ditches), as shown on Sheet C-3 in Appendix A.2. The permanent stormwater controls for B-18 are designed to convey the design PMP storm event. To be conservative, the stormwater controls were designed to convey the flow of the 6-hour PMP. The 6-hour PMP has a higher rainfall intensity and therefore greater peak flow than the 24-hour PMP event. During a PMP storm event, the drainage channels will reach capacity and some flows extend into the roadway. This design approach maintains reasonable size channels that convey a majority of storm events, however, flows from the PMP are controlled within the roadway assuming trafficable conditions would not need to be maintained during such an event.

During operation of Phase IIIA (while Phase IIIB is being constructed), there will be no potential for stormwater run-on into Phase IIIA from the adjacent portion of Phase IIIB due to the presence of the lined temporary Phase IIIA stormwater containment berm that will be constructed along the Phases IIIA-IIIB interface (see Detail 1 on Sheet C-4A in Appendix A.2). The top of this berm will be approximately 8 feet higher than the nearby high point on the Phase IIIB “bench liner” area, meaning that stormwater run-on from Phase IIIB will flow to the existing Northeast Containment Basin before it could overtop the temporary Phase IIIA berm. It is estimated that a maximum of approximately 2 feet of stormwater run-on could accumulate on the south side of the temporary Phase IIIA berm; this stormwater would be clean and would therefore be pumped by site personnel to just south of the nearby high point, where it could then flow to the Northeast Containment Basin. Once Phase IIIB is completed, the need for conveying stormwater run-on will be eliminated.

#### 4.9.2 Active Area Run-Off Control for Phase I Operations

Sheets 5 and 6 in Appendix A.1 shows how surface water run-off from active areas for the PMP storm event was controlled during the Phase I disposal operations. The main aspects of this control were:

- Active area roads were sloped inward to a ditch system that was separate from the run-on ditch system described in Section 4.9.1.
- The active area run-off was directed to a lined retention basin located in the bottom of the initial clay borrow pit.

The west and south portions of the B-18 Perimeter Road adjacent to Phase I slope inward to an asphalt-lined V-ditch as shown in Section A-3,8/15 on Sheet 15 in Appendix A.1. This ditch flows in

the south and east direction to a former culvert inlet on the south portion of the B-18 Perimeter Road approximately 12.5 feet beyond the limit of the sideslope liner system for Phase I. The former culvert was an 18-inch diameter CMP that dropped down the south sideslope (see Section B-4,5/16 on Sheet 16 in Appendix A.1) and into an 18-inch diameter, concrete-encased CMP culvert beneath the entrance of the Phase I/II Berm road to the Phase I access ramp. This culvert then discharged into a V-ditch (see Section B-5,15,23/17 on Sheet 17 in Appendix A.1) that flowed along the west side of the Phase I/II Berm to a drop inlet. This drop inlet discharged into a 30-inch diameter CMP that passed beneath the Phase I/II Berm crest and down its eastern embankment slope and into the lined basin in the clay borrow pit. The V-ditch and culvert also collected run-off from the road on top of the Phase I/II Berm, which sloped at two percent toward the west for its entire length.

An additional concrete-encased, 12-inch diameter CMP culvert was provided where the Phase I access ramp met the west portion of the existing B-18 Perimeter Road. This culvert drained the small flow from the northern part of this portion of the B-18 Perimeter Road and was concrete-encased to support waste truck traffic.

The north portion of the B-18 Perimeter Road adjacent to Phase I and the access road around the top of the initial clay borrow pit were also considered to have active area run-off because of the daily cover and landfill equipment that used these roads. Hence, these roads were also sloped toward an inside ditch that conveyed surface water flows to an 18-inch diameter CMP culvert along the southeast corner of the initial clay pit slope.

The clay pit retention basin was lined with 40-mil HDPE geomembrane from a bench at an elevation of 720 feet to its base at an elevation of 680 feet. Although not normally required for retention basins of this type, the liner was provided to avoid saturation of the clay borrow area because this area would later form part of Phase II floor. The retention basin and its liner system were completely removed when Phase II was constructed. The capacity of this temporary containment basin was sufficient to contain the 24-hour PMP run-off from the areas discussed above. Section A on Sheet 13 in Appendix A.1 shows a cross-section through this retention basin.

#### 4.9.3 Phase I Direct Rainfall Control

The control of direct rainfall into the Phase I disposal area consisted of sloping the waste surface toward a low spot where the collected surface water was removed by vacuum trucks (or other appropriate means) and transported to the appropriate storage, treatment, and/or disposal facilities.

The amount of water that was handled by vacuum trucks was reduced by installing slope gutters on the temporary liner portions of the slopes. Water collected in these gutters drained into a clean tank and was then pumped into the run-on collection ditch system discussed in Section 4.9.1.

Initially, the low spot on the waste surface was located in the northern portion of Phase I to minimize interference with traffic at the Phase I access ramp. As the waste level in Phase I rose, the low spot was moved to best suit operational conditions. Once the waste height rose above the top of the Phase I/II Berm, it was necessary to keep the low spot away from the east-facing Phase I waste slope to avoid localized instability of this slope.

#### 4.9.4 Active Area Run-Off Control for Phase II Operations

Sheet 10 in Appendix A.1 shows the configuration that was used for containing active area run-off during the Phase II operations. The collection system for this period consisted of an extension of the

Phase I ditches located along the inside of the B-18 Perimeter Road as described in Section 4.9.2. These ditches sloped toward the east-northeast portion of Phase II and conveyed run-off into the lined Northeast Containment Basin that was constructed in conjunction with Phase II. This basin is sized to contain run-off from both the existing B-18 Perimeter Road and from waste slopes with interim cover that are located above the level of the existing B-18 Perimeter Road. Surface water from the inside ditches flows into either of two culverts (one culvert is a 30-inch diameter CMP while the other culvert is a 24-inch diameter CMP) at the eastern portion of the B-18 Perimeter Road above the Northeast Containment Basin. These culverts discharge into asphalt-lined swales in the corners of the Northeast Containment Basin. For very large storms, the roadway profile above the culverts is depressed to direct flows across the road and into the asphalt-lined containment basin swales.

#### 4.9.5 Phase II Direct Rainfall Control

Direct rainfall into the Phase II waste disposal area was handled using procedures similar to those described in Section 4.9.3 for the Phase I operations.

#### 4.9.6 Run-Off Control During the Above Grade Filling Period

Currently, the B-18 waste mass is in the above grade filling period. As the waste mass rose above the level of the existing B-18 Perimeter Road, rainfall run-off began to be handled in the following two ways:

- The top deck area, where waste disposal is ongoing, is graded to direct surface water toward a low spot (with temporary earthen berms, as needed) where the collected surface water is removed as discussed for the Phase I and II areas in Sections 4.9.3 and 4.9.5, respectively.
- Surface water from sloped areas with interim cover is handled as run-off water. This run-off is collected from the sideslopes of the existing landfill and conveyed into the inside B-18 Perimeter Road ditches, which ultimately direct the run-off into the Northeast Containment Basin.

The asphalt-paved ditches on the inside of the existing B-18 Perimeter Road contain run-off from storms with recurrence intervals less than 100 years (based on original design storm event). During larger storms and up to the PMP event, the flow may extend outside of these paved ditches but is maintained within the larger channel formed by the inward-sloping perimeter road. Flows up to the PMP storm condition are currently directed into the Northeast Containment Basin. During operations within Phase IIIA (while Phase IIIB is still being constructed), stormwater run-off from the north, east, and west facing Phase IIIA waste slopes will be diverted to the Northeast Containment Basin. A temporary lined containment berm will be constructed at the interface of Phases IIIA and IIIB (see Sheet C-4A in Appendix A.2) to provide containment of stormwater run-off from the lower portions of the south-facing temporary Phase IIIA waste slope. This temporary berm has been sized to contain the entire run-off volume generated by the 24-hour PMP event (while maintaining a freeboard of greater than 1 foot); this run-off will be contained on the north side of the temporary berm. Therefore, no pumping will be required to prevent the overtopping of the temporary berm. Site personnel will treat the stormwater run-off contained on the north side of the temporary berm as leachate. Accordingly, the impounded stormwater run-off will be pumped into tanker trucks and transported to the appropriate on-site facility for treatment as leachate.



The Phase III expansion of B-18 will involve the construction of a new B-18 Perimeter Road around most of the landfill. Similar to the existing configuration, the new B-18 Perimeter Road will be sloped inward toward the landfill during the above grade filling period. Also, asphalt or shotcrete-lined V-ditches will run along the entire inside edge of the new B-18 Perimeter Road to convey run-off to containment basins in a similar manner as is currently done.

Due to the change in the PMP storm event (see the discussion at the beginning of Section 4.9) and the increased landfill area after the construction of Phase III, a second stormwater basin, the South Containment Basin, will be required to provide adequate run-off storage capacity for the PMP storm event after Phase III is completed. The new South Containment Basin will be constructed as part of the Phase IIIB expansion as shown on Sheet C-3 in Appendix A.2. The surface water flow patterns around the expanded landfill will be such that all run-off will be directed to and contained in the South and Northeast Containment Basins.

#### 4.9.7 Phase III Direct Rainfall Control

Direct rainfall into the Phase III waste disposal area will be handled using procedures similar to those described in Section 4.9.3 for the Phase I operations.

#### 4.9.8 Run-Off Control at Closure

The surface water drainage capacities of the final benches, Cover Access Road, and the new B-18 Perimeter Road are designed to be capable of conveying the 6-hour PMP storm water run-off without damage to the landfill. This storm water flow will drain to either the existing Northeast Containment Basin or the new South Containment Basin, as shown on Sheet C-4 in Appendix A.2. The stormwater containment basins are designed to contain the runoff from the 24-hour PMP storm event. After site closure, the basins may be modified to release the stormwater run-off in a controlled manner.

### 4.10 Utilities

The existing utilities for B-18 consist of the following:

- A perimeter lighting system that currently serves the existing B-18 Perimeter Road and that formerly served the waste disposal area before the waste mass grew to its current level above the lights.
- Electrical power to operate the various leachate control pumps and the perimeter lighting system.

As part of the B-18 Phases I and II construction, permanent lighting fixtures were placed around the entire existing B-18 Perimeter Road as illustrated in Section A-5,10/23 on Sheet 23 in Appendix A.1. However, this existing lighting system is no longer needed and it will be removed as part of the Phase III construction.

Power for the existing lighting system and leachate pumps is provided by an electrical transformer located along the northern boundary of B-18, as shown on Sheet C-2 in Appendix A.2. During the Phase III construction, this transformer will be removed and relocated to allow for the construction of the Phase III expansion.

## 5.0 ENGINEERING ANALYSES

### 5.1 General

This section describes the engineering analyses that were performed to support the design of B-18. The B-18 analyses are discussed in Sections 5.2 through 5.9 with calculations provided in Appendices G through N for Settlement, Stability, Cover Soil Erosion, Surface water drainage, leachate collection and removal, riser pipes, cover infiltration, and frost and biotic protection, respectively.

### 5.2 Settlement Analyses

#### 5.2.1 Conditions Evaluated

The following four settlement conditions were analyzed for B-18:

1. The elastic settlement of the landfill's foundation to assess the minimum slope of the LCRSs. Ideally, the post-settlement slopes of the LCRSs should be maintained at 2 percent or greater.
2. Evaluation of the degree of consolidation of the primary and secondary clay liners at interim and final closure to assign appropriate strength properties for these materials for use in the stability analyses.
3. Estimation of the magnitude of settlements of the primary and secondary clay liners to assure that adequate thicknesses (i.e., 3 feet or more) will be maintained after compression and consolidation of the liners are completed.
4. Estimation of the post-closure waste settlements to assure positive drainage of the cover, benches, and the Cover Access Road.

The settlement calculations are provided in Appendix G and described in the following sections.

#### 5.2.2 Foundation Settlement

The rock strata beneath B-18 have and will continue to settle in an approximately elastic manner as each layer of waste is placed. Therefore, essentially all of the foundation settlement is anticipated to occur prior to closure and, hence, foundation settlement will not be a factor with regard to the closure cover configuration or drainage control. The foundation settlement will, however, result in slope changes at the base of the landfill that will impact the LCRS. These settlements will not cause abrupt changes on the base (e.g., large differential settlements over short distances), but they could potentially reduce the slopes of the LCRS to below the desired minimum of 2 percent. A minimum LCRS slope of 2 percent is desired to assure positive leachate drainage to the sumps.

The foundation settlement estimates presented in Appendix G.1 were calculated using Boussinesq's stress distribution theory in conjunction with the elastic properties of the foundation materials. Elastic properties of the claystone and siltstone were conservatively considered to be the same and were estimated based on the measured plasticity index and strength characteristics of the undisturbed claystone samples using the procedure described by Duncan and Buchignani (1976). The elastic modulus and Poisson's ratio of these fine-grained rocks were estimated to be 6,000 ksf and 0.38, respectively. The sandstone was assumed to be incompressible since information obtained from the boring logs and laboratory test data indicate that deformation of the coarse-grained rock strata (i.e., sandstone) would be negligible in comparison to that of the claystone and siltstone.

In Appendix G.1, landfill base settlement profiles are estimated for four representative cross-sections through the waste mass to evaluate both the total and differential settlements. The total estimated settlements range up to about 15 inches. According to the computed settlements, the resulting slope of the base of the landfill will be greater than 2 percent. Hence, it is concluded that the LCRS will remain sloped at a minimum of 2 percent.

### 5.2.3 Degree of Consolidation of Clay Liners

Calculations of the time rate of consolidation of the clay liners due to placement of the overlying waste are provided in Appendix G.2. These calculations were carried out in order to evaluate the appropriate clay strength parameters for use in the stability analyses. Shortly after clay liner construction, UU triaxial strength parameters are appropriate. After “complete” consolidation (i.e., an average degree of consolidation greater than about 95 percent) of the clay due to the weight of the overlying waste has occurred, CU triaxial strength parameters are appropriate. The selection of clay strength parameters to assess stability at a certain stage of waste disposal is based on the expected degree of consolidation of the clay liner at that particular time.

The clay liners will be continually consolidating during waste placement such that the undrained shear strength of the clay liners will be continually increasing. Based on the consolidation test data for compacted (remolded) clay discussed in Section 3.5.7, it is estimated that the average degree of consolidation for both the primary and secondary clay liners will be greater than 95 percent by the time the final closure cover is installed. Therefore, the undrained shear strength of the clay liners for long-term, post-closure conditions should be based on its fully-consolidated strength as evaluated from the CU triaxial tests.

Another calculation was performed to evaluate the degree of consolidation of the clay liners when the Phase I Intermediate Closure was completed about two years after initial clay liner construction. This calculation shows that approximately 30 percent of clay consolidation will have occurred at that time, resulting in a modest gain in strength. To be conservative, the UU triaxial test data were used in the stability analyses for the Phase I Intermediate Closure condition. Also, because all of the excess porewater pressures were not dissipated at that time, the friction angle ( $\phi$ ) portion of the UU triaxial test data was not relied upon in the Phase I Intermediate Closure stability evaluation.

### 5.2.4 Magnitude of Clay Liner Consolidation

The clay liner consolidation calculations in Appendix G.3 were performed to estimate the clay liner thickness reductions once “complete” consolidation of the clay had occurred under the weight of the overlying waste mass. Calculations are provided for the following:

1. A primary and secondary clay liner thickness of 1.5 feet and 3.5 feet, respectively, at the landfill base and a maximum waste thickness of about 300 feet (compared to a maximum waste thickness of 230 feet without Phase III).
2. A clay liner thickness of 5 feet beneath the vertical riser pipe, where additional load will be applied to the clay liner by the vertical riser pipe foundation (see Section 5.7).

The calculations show that the maximum consolidation settlement of the primary and secondary clay liners at the landfill base will be approximately 0.1 and 0.3 feet, respectively, under loading from 300 feet of waste (similar to the result for Phase I and II). Therefore, it is concluded that the primary and

secondary clay liner's required minimum thickness of 1 and 3 feet, respectively, will be maintained after consolidation settlement is complete.

The maximum primary and secondary clay liner settlements beneath the vertical riser pipe foundation were calculated to be about 0.4 and 0.7 feet, respectively, under loading from 300 feet of waste. These magnitudes of settlement are acceptable because the original clay liner thicknesses in this area were about 3 and 5 feet for the primary and secondary clay liners, respectively.

#### 5.2.5 Post-Closure Waste Settlement

Appendix G.4 contains the post-closure waste settlement calculations that were performed in order to assess the minimum closure cover slopes for positive drainage. It was assumed that the primary consolidation of waste material will fully occur during waste placement. Therefore, the post-closure waste settlements were estimated based on the following factors:

- Crushing of disposed drums and the related settlements due to:
  - Closure of void spaces in the drums within the waste mass; and
  - Consolidation of loosely-placed materials in the drums.
- Secondary consolidation (or creep) settlement of the main, soil-like waste matrix.

It is anticipated that settlement of waste within B-18 will be less than prior WMUs at the KHF because of more restrictive disposal regulations, especially since a significant portion of the waste has been and will continue to be solidified prior to disposal. The waste settlement estimates discussed below do not fully account for these changes and are therefore considered to be conservative.

The waste settlement calculations were based on KHF's estimate that 15 percent of the waste volume within B-18 consists of drums that are distributed randomly throughout the waste. The drums are conservatively assumed to contain 10 percent voids and the wastes within the drums were calculated to consolidate an additional 30 percent. Long-term creep settlement of the waste was estimated based on characteristics for normally-consolidated soft to medium stiff clay.

By analyzing representative cross-sections through the entire B-18 waste mass, it is estimated that the post-closure waste settlements will vary from approximately zero at the edge of the landfill to a maximum of about 27 feet where the waste thickness is greatest. On the basis of the calculations in Appendix G.4, it is concluded that the proposed final cover grades shown on Sheet C-4 in Appendix A.2 will be adequate to assure appropriate drainage after waste settlement is complete.

It is recommended that survey monuments be monitored at areas with interim cover on the landfill sideslopes once these areas are filled to their final elevation. As this settlement data is obtained, it may be appropriate to re-evaluate whether or not a portion of the primary settlement may occur during the post-closure period and to re-assess the final cover grading plan.

### 5.3 Stability Analyses

#### 5.3.1 General

Appendix H includes static and seismic slope stability analyses for the conditions discussed in the following sections:

- Section 5.3.2 - Temporary Rock Cut Slopes;
- Section 5.3.3 - Compacted Fill Slopes;
- Section 5.3.4 - Temporary Phase I Intermediate Fill Slopes;
- Section 5.3.5 - Temporary Phase IIIA Intermediate Fill Slope; and
- Section 5.3.6 - Final Closure Conditions.

Table 5.1 summarizes the shear strength and unit weight parameters assigned to each of the materials and material interfaces modeled in the stability analyses. The right-hand column in Table 5.1 identifies the data sources for these parameters, which include the site-specific laboratory testing discussed in Section 3, prior KHF landfill investigations, and published data and information.

Table 5.2 summarizes the results of the stability analyses and lists the criteria used to evaluate acceptability. For static conditions, the minimum acceptable factor of safety is considered to be 1.5. This criterion was satisfied for all of the critical conditions analyzed. For seismic conditions, acceptability is evaluated based on a design displacement during the MCE event (see Section 2.5.1). A maximum design displacement of 6 inches was established for all cases where the failure plane could intersect the base liner system, based on the recommendations of Seed and Bonaparte (1992). This minimizes the potential for large displacements that could potentially disrupt the HDPE geomembrane/clay composite liner or the LCRS. As shown in Table 5.2, the estimated displacement for most of the cases considered is less than 1 inch for the applicable MCE event.

The following seismic displacements during the MCE event were considered maximum acceptable values for locations where permanent liner systems are not affected:

- A 6-inch seismic displacement for the Northeast Containment Basin embankment, primarily to minimize the potential of overall embankment instability occurring.
- A 12-inch displacement entirely within the waste mass for the Phase I intermediate fill slope because it is temporary and regrading improvements could easily be made without exposing the underlying liner systems.
- A 12-inch displacement would be allowable for the geotextile/HDPE geomembrane and vegetative cover soil/geotextile interfaces of the final cover system. This maximum displacement minimizes the potential for damage to the HDPE geomembrane and any resulting near-surface cracking could be repaired relatively easily.

The static factors of safety were calculated using:

1. The STABL5 computer program, developed by Purdue University (1986), for the stability analyses performed during the original design of B-18 (ESI, 1990a).
2. The computer program GSTABL7 version 2.003, developed by Gregory Geotechnical Software, for the stability analyses performed for the current design.

Displacement estimates for the seismic conditions were calculated using the following procedures:

1. Newmark (1965), as modified by Franklin and Chang (1977), for temporary rock cut slopes, compacted fill slopes, and the Phase I intermediate waste fill conditions. A conservative velocity-to-acceleration ratio of 30 was used for the Newmark and Franklin and Chang methods for these cases, based on measured velocity/acceleration ratios published by Donovan (1983). The maximum acceleration of the waste mass for these cases was assumed to be 80 percent of the PHGA, based on comparisons with site response analyses performed by Woodward-Clyde (1987) for the OII Landfill in Monterey Park, California. However, no attenuation was allowed for very shallow potential failure surfaces because the lower portions of the slide mass were close to the ground surface.
2. Makdisi and Seed (1978), which is based on the Newmark (1965) method, for the final closure configuration. In order to evaluate the average acceleration time histories of the critical slide mass, two-dimensional dynamic finite element analyses were performed using the computer program QUAD4M (Hudson et al., 1994).
3. Bray et al. (1998) for the final cover veneer stability analyses. Two-dimensional site response analyses were also performed for this case using QUAD4M to evaluate the average acceleration of the cover system.

The PHGAs corresponding to the MCE events (near-field and far-field) used in the current design are discussed in Section 2.5.3. These PHGAs and MCEs were used in the stability analyses of the final closure configuration and in the cover veneer analyses. During the original design of B-18 (ESI, 1990a), a single MCE event was considered, as discussed in Section 2.5.2. This MCE event and its associated PHGA differ from those used in the current design due to advances in geotechnical earthquake engineering since the time of the original design. The temporary rock cut slopes, compacted fill slopes, and Phase I intermediate waste fill conditions were not re-analyzed for the current design since these conditions no longer exist due to the placement of overlying waste. The rock cut slope on the west side of B-18 will be flattened and will be more stable than the current configuration. Hence, the computed seismic displacements for these conditions correspond to the MCE event from the original design (ESI, 1990a), as discussed in Section 2.5.2.

### 5.3.2 Temporary Rock Cut Slopes

Appendix H.2 provides stability analyses for the two rock cut slope conditions illustrated in Figure 5.1. East-, south-, and north-facing slopes were excavated at a 2H:1V inclination across bedding planes. West-facing slopes, which were in the general direction of the weaker bedding planes, were excavated at a shallower 3H:1V inclination. Table 5.2 shows that the static factors of safety for these two conditions are 2.4 and 2.2 for the 2H:1V and 3H:1V slopes, respectively. Table 5.2 also shows that essentially no displacement of either slope configuration is anticipated during the original design's MCE event (Section 2.5.2). Therefore, the designed temporary rock cut slopes were adequate for both the static and seismic criteria for Phases I and II and are considered to be adequate for the comparatively minor proposed Phase III temporary rock cut slopes.

### 5.3.3 Compacted Fill Slopes

Phases I and II of B-18 were formed primarily by excavation into rock and there were no large fill embankments required. A relatively small fill embankment was necessary in the former natural drainage area at the northeast edge of Phase II. This fill embankment forms a portion of the eastern Phase II sideslope and also forms one of the sideslopes for the Northeast Containment Basin. A cross-section through this embankment is shown in Section A-8/23 on Sheet 23 in Appendix A.1. Stability analyses were performed for this fill embankment.

Table 5.2 shows that the Phase II/Northeast Containment Basin fill embankment is satisfactory for both static and seismic conditions. The static factor of safety for this embankment is 2.2 and essentially no displacement was projected for this slope during the original design's MCE event (Section 2.5.2). Appendix H.3 contains the detailed stability computations for this condition.

Phase III will require some relatively small fill embankments along the south side of the existing landfill. The slopes of these fill embankments will have inclinations equal to or less than those of the existing Phase II/Northeast Containment Basin fill embankment. Based on the stability analysis results for the Phase II/Northeast Containment Basin fill embankment, the proposed fill embankments for Phase III are considered to be adequately stable for both the static and seismic conditions.

### 5.3.4 Temporary Phase I Intermediate Fill Slopes

The typical configuration of the temporary Phase I intermediate waste fill slopes is shown in Section A-6/23 on Sheet 23 in Appendix A.1. This slope condition existed from the time that initial filling of Phase I was completed until the Phase II area was filled to the top of the Phase I/II Berm. This temporary waste slope was constructed at the relatively steep 1.5H:1V inclination because the stability analyses showed that the factor of safety along the critical liner interface is higher when the waste slope is steeper due to the added frictional resistance along the toe portion of the potential sliding wedge.

Appendix H.4 presents the detailed results of the stability analyses conducted for the Phase I intermediate fill slopes. Figure 5.2 illustrates the various potential failure mechanisms considered for the Phase I temporary fill slopes. The most important potential sliding mechanism (Cases A1 and A2 in Figure 5.2) involved shearing through the waste, along the base liner of the landfill, and up the lined Phase I/II Berm sideslope, resulting in a wedge-shaped slide mass. This mechanism is critical because the liner interface strengths are much lower than those of the underlying foundation or the overlying waste materials. Also, a failure at this location could damage the liner and LCRSs. Figure 5.2 shows the following two potential shear surfaces for this sliding mechanism:

- Case A1: A shear surface that would occur entirely along the liner interface, including at the intersection of the landfill base and the Phase I/II Berm sideslope.
- Case A2: A shear surface that would include an approximately 50-foot-long diagonal shear zone through the waste near the base/berm intersection to simulate a circular failure surface across that intersection angle.

The results in Table 5.2 for these cases show a static factor of safety of at least 2.5 and essentially no displacement during the original design's MCE event (Section 2.5.2). These results are acceptable for this important stability condition.

The potential for a shallow circular failure (Case B in Figure 5.2) to occur through the intermediate fill slope without intersecting the liner system was an additional consideration for the Phase I temporary waste slope. This condition was less important than Cases A1 or A2 because, if some movement were to occur along the potential sliding surface, the underlying liner system would not be damaged. Table 5.2 shows that the static factor of safety for Case B is approximately 1.5 and the estimated displacement for the original design's MCE event (Section 2.5.2) is about half an inch. These results are based on shallow waste strength parameters of  $\phi = 27$  degrees and  $c = 300$  psf as compared to  $\phi = 31$  degrees and  $c = 0$  used for deeper zones of the landfill. Use of the cohesionless waste strength parameters would result in a lower static factor of safety (approximately 1.3) for very shallow potential failure surfaces. However, it is reasonable to assume that the waste will have a small degree of cohesion. Therefore, the factor of safety and estimated MCE displacement discussed above were considered to be appropriate and the intermediate slope was acceptable for this temporary and non-critical condition.

During the preliminary stability analyses, calculations were also performed to evaluate whether a failure could potentially occur along the entire Phase I liner interface (i.e., along the west sideslope, the landfill base, and the Phase I/II Berm sideslope). The factor of safety for this condition was found to be much higher than for the Cases A1 and A2 conditions.

Finally, because of prior experience at the KHF, an evaluation was made as to whether or not it would be appropriate to analyze the Phase I intermediate fill slope for a three-dimensional potential failure surface. However, because of the designed configuration, it was concluded that such an analysis was not necessary. Phase I was purposely configured to avoid three-dimensional driving forces that were significantly different than those realized for the two-dimensional (Cases A1 and A2) condition. Therefore, the factor of safety for a three-dimensional case would essentially be the same as the acceptable values for the two-dimensional cases discussed above.

#### 5.3.5 Temporary Phase IIIA Intermediate Fill Slope

The configuration of the temporary Phase IIIA intermediate waste fill slope is shown on Sheet C-4A in Appendix A.2. As can be seen on Sheet C-4A, the Phase IIIA interim waste slope is a south-facing, 2H:1V slope that contains an approximately 30-foot wide bench to allow for access to the landfill during waste placement operations. This interim slope condition will exist for only a short time, if at all, as it is anticipated that no more than 6 months of waste will be placed in Phase IIIA before waste placement in Phase IIIB begins. After waste placement in Phase IIIB commences, the interim Phase IIIA waste slope will be covered with waste relatively quickly. The north, east, and west facing Phase IIIA waste slopes will be built to the final cover grades (i.e., 3.5H:1V inclination between benches); therefore, these waste slopes were analyzed as part of the final closure configuration (Section 5.3.6).

Appendix H.4 presents the detailed results of the stability analyses conducted for the south-facing 2H:1V Phase IIIA intermediate fill slope. Due to its temporary nature, only static stability analyses were conducted for the Phase IIIA intermediate waste slope. Also, as can be seen in Appendix H.4, the shear strength parameters of the Phase IIIA liner system were assumed to lie between its peak and residual values since the slope will be temporary and the portion of the Phase IIIA liner modeled in the stability analyses will be graded at only 10 percent, thereby making it similar to a base liner from a shear strength standpoint.

Figure 5.3 illustrates the potential failure mechanism considered for the south-facing 2H:1V Phase IIIA temporary fill slope. This critical potential sliding mechanism involves shearing down through



the waste and then along the Phase IIIA liner toward the toe of the south-facing 2H:1V temporary waste slope, resulting in a wedge-shaped slide mass. This mechanism is critical because the liner interface shear strength is much lower than that of the underlying foundation or the overlying waste materials. The result in Table 5.2 for this interim case indicates a static factor of safety of 1.5, which is considered acceptable for this temporary condition.

The potential for a shallow circular failure to occur through the south-facing 2H:1V Phase IIIA intermediate fill slope without intersecting the liner system was not performed since analyses for the Phase I temporary waste slopes indicated that a temporary waste fill slope inclined at 1.5H:1V would be adequately stable (Section 5.3.4) with respect to this potential sliding mechanism. Since the Phase IIIA intermediate waste fill slope will be inclined at 2H:1V, it will be expected to be more stable than the Phase I temporary waste slopes were. In addition, the Phase I temporary waste slopes were observed to perform well after their construction, which further demonstrates that the 2H:1V Phase IIIA intermediate fill slope should be adequately stable with respect to a circular failure entirely through waste.

### 5.3.6 Final Closure Conditions

The three potential failure scenarios of importance for the final closure configuration, as shown conceptually on Figure 5.3, are:

- Displacement of the final cover system on the 3.5H:1V sideslopes between benches.
- A large wedge failure through the waste and along the base and perimeter sideslope liner systems.
- A circular failure entirely through the waste.

The stability analyses for the final closure conditions were performed by HAI, under subcontract to Golder, as part of the current design. Appendix H.5 contains HAI's slope stability report while the results of HAI's stability analyses are summarized in Table 5.2 and discussed in the following paragraphs.

The weakest interface in the B-18 final cover system is the nonwoven geotextile/40-mil textured HDPE geomembrane interface. Large seismic displacements at this interface could result in a tensile failure of the HDPE geomembrane. The current state-of-practice is to generally limit seismic displacements of the cover system to less than about 12 inches. Table 5.2 shows that the static factor of safety for veneer-type sliding of the cover system along the geotextile/HDPE geomembrane interface is 1.6, which is well above the allowable 1.5. The estimated seismic displacement along this interface was calculated to be about 2.7 inches for the updated MCE event (Section 2.5.3). Hence, the final cover system of B-18 is considered to be adequately stable under the design static and seismic loading. Minor repairs to the cover system may be required if the seismic displacement of the cover system exceeds about 2 to 3 inches.

In order to evaluate a deep, wedge-shaped failure mechanism (along the base liner) for the final closure condition, HAI evaluated 6 representative cross-sections (A-A' to F-F') through B-18. The locations of these 6 cross-sections are shown in Appendix H.5. For each cross-section, multiple sliding mechanisms were considered.

HAI reviewed the interface shear strength test data for B-18 to determine the weakest interface for each phase of construction. The original design report for B-18 (ESI, 1990) assumed the most critical interface would be located at the interface of the textured geomembrane and the geonet side of the geocomposite. The interface was found to have a residual friction angle of 9 degrees and 800 psf adhesion. However, during construction of Phase II, a bonded geotextile was included below the geocomposite to increase the shear strength of the liner system (i.e., a geocomposite with geotextiles heat bonded to both sides of the geonet was used during construction). Therefore, the lower shear strength properties used for the Phase I side slope liner were based on a different critical interface in the liner system. Based on the URS 2005 report, archived samples of the existing Phase II liner system components were recovered from storage and tested for interface shear strength. Two shear tests were performed on multiple components that represented all of the possible interfaces in the existing B-18 Phase II liner systems. Tests performed on these "sandwich-like" specimens of the Phase II liner system demonstrated that failure occurred along the clay/textured geomembrane interface in one test and the clay/geotextile interface in the other test. The results of these tests yielded a peak interface friction angle of 20 degrees with an adhesion of approximately 1,900 psf, and a residual interface friction angle of 19 degrees with approximately 1,800 psf adhesion. For the stability analysis the adhesion was conservatively considered to be 0 psf.

It should be noted that failure in a liner system occurs along the interface with the lowest peak shear strength. Therefore, the weakest interface in the liner system is the interface with the lowest peak strength. Based on the direct shear testing performed by SGI Testing Services, LLC (2003) on the archived Phase II liner system materials (see Appendix A of the URS 2005 report), the lowest peak shear strength is along either the textured geomembrane/compacted clay liner interface or the geotextile/compacted clay interface (peak friction angle of 20 degrees). Even though the clay liner has a lower residual friction angle of 13 degrees with lower adhesion (SGI, 2003), the higher internal peak shear strength of the clay (26 degrees) in comparison with the two above-mentioned interfaces (20 degrees) results in detrimental shear displacements occurring along either of the two geosynthetic liner/clay interfaces and not within the clay liner itself. The "sandwich-like" specimen tests presented in the URS 2005 report demonstrated this.

To confirm the friction angles for the B-18 Phase III liner system, similar "conformance" testing was completed on stock materials from geosynthetic manufacturer's that will supply materials for the Phase III expansion. Based on the testing conducted by Precision Geosynthetic Laboratories (results included in Appendix H.5), the weakest interface is the geocomposite to textured HDPE geomembrane. The measured peak friction angle was approximately 28 degrees with a residual friction angle of 12 degrees. For the stability analysis, the 12 degree residual friction angle was used for the Phase III expansion area. The initial stability report by HAI assumed that the friction angle for Phase III would be similar to Phase II. Based on the recent testing, HAI lowered the Phase III friction angle. An addendum to the original report is included in Appendix H.5 to address the stability analysis using the lower strength values.

Using the above interface shear strengths, Sections D-D' and F-F' were found to be the most critical of the 6 cross-sections considered since their potential failure mechanisms had the lowest static factor of safety and lowest yield accelerations. HAI therefore performed two-dimensional site response analyses (using QUAD4M) and seismic displacement analyses for sections D-D' and F-F'. In the two-dimensional response analyses, four different input ground motion time histories were used to provide a range of anticipated waste mass accelerations (both from the near-field and far-field events). The results of the seismic displacement analyses performed for section D-D' and F-F' indicate that, under the updated MCE ground motions (Section 2.5.3), the maximum seismic displacements will be less

than 1 inch. Therefore, the overall final landfill configuration is considered to be adequately stable with respect to deep, wedge-shaped failure mechanisms.

The last closure configuration condition analyzed was a circular failure entirely through the waste. Section D-D' contained the critical circular shear surface. As can be seen on Table 5.2, the calculated static factor of safety for this case was 2.2 and the seismic displacement during the updated MCE event (Section 2.5.3) is anticipated to be less than 12 inch. Hence, the final landfill configuration is considered to be acceptable with regards to static and seismic stability of circular shear surfaces through the waste.

Finally, the need for a three-dimensional stability analysis for the final landfill configuration was not deemed necessary since no conceivable three-dimensional movements could be hypothesized that would lead to significantly lower factors of safety than those for the two-dimensional cases discussed above.

#### 5.4 Cover Soil Erosion

Appendix I contains the analyses performed to assess the erosion rate of the B-18 vegetative cover soil layer based on the planned vegetation, slope steepness, slope length, and climatological conditions. The soil erosion analyses were performed using the computer program RUSLE2 (NRCS, 2004), which uses the Revised Universal Soil Loss Equation (RUSLE) along with the appropriate site-specific parameters listed above to calculate the potential soil erosion loss in tons per acre per year.

The results of the soil erosion analyses indicate a maximum cover soil erosion rate of about 1 ton per acre per year for the typical 3.5H:1V closure slopes between benches. This maximum rate is approximately half of the maximum allowable rate of 2 tons per acre per year suggested by the USEPA (1989). This cover soil erosion rate assumes that vegetation is established on the final cover. If no vegetation (i.e., bare ground) is assumed, the calculated cover soil erosion rate is about 9 tons per acre per year. Hence, it will be important to establish and maintain an acceptable amount of vegetation on the B-18 final cover to control soil erosion losses. As such, a specification for revegetation of the final landfill slopes is provided for in Appendix O.

#### 5.5 Surface Water Drainage

##### 5.5.1 General

The surface water analyses presented in Appendix J are divided into sections that address the following requirements:

- The general hydrology and design criteria.
- Phases I and II run-on control.
- Phases I and II run-off control.
- Phase III run-on control.
- Phase III run-off control.

- Closure drainage control.

The B-18 surface water drainage control systems are described in Section 4.9. As discussed in Section 4.9, run-on control refers to the collection and off-site diversion of surface water that has originated outside of the B-18 limits and, therefore, has not been affected by the active disposal area. Run-off control refers to the collection of surface water from roads used for waste truck or landfill equipment access and from portions of the waste area with intermediate cover. This run-off does not come into direct contact with the waste disposal area, but it will be retained on-site in accordance with the KHF permitting requirements.

The basic surface water drainage control design criteria for B-18 are:

- Hydraulic structures should be capable of conveying the 6-hour PMP storm event that is considered to have maximum intensities based on the rainfall-duration curve data shown Appendix J. Culverts may be designed for flows as low as those from the 25-year storm event as long as water overtopping the culvert is contained within a drainage control system that has been designed for the peak PMP discharge.
- All run-off containment basins, except the temporary one for the Phase I intermediate condition, are designed for the 24-hour PMP event, which is 10.3 inches of rainfall (NOAA, 1998). It is noted that during the original design of B-18 (ESI, 1990a), the 24-hour PMP event used in the analyses was only 7.4 inches based on the available data at that time (CDWR, 1976). The temporary Phase I intermediate basin was required only during the Phase II construction period and was designed for the 25-year, 24-hour storm.
- During the original design of B-18 (ESI, 1990a), peak storm run-offs were calculated using the rational method for small watersheds along with run-off coefficients of 0.40 for natural areas, 0.90 for roads, and 0.60 for interior cover areas. Volume requirements for the former and existing containment basins were also based on these run-off coefficients. These methods and parameters are applicable for the Phases I and II run-on and run-off calculations presented in Appendices J.2 and J.3.
- For the current design, peak storm run-offs were calculated using the computer program HEC-HMS version 3.1.0, developed by the United States Army Corps of Engineers. In the HEC-HMS analyses, an SCS curve number of 81 was used to model the final cover soil and areas surrounding B-18, except a SCS curve number of 74 was used for the natural terrain west of B-18. The volume requirement for the proposed South Containment Basin was based on the design flows calculated from the HEC-HMS analyses. These methods and parameters are applicable for the closure drainage control calculations presented in Appendix J.4.
- In the original B-18 design (ESI, 1990a), Manning's roughness coefficients used in the design of ditches and culverts were 0.013 for smooth asphalt, 0.018 for earth channels (which extend onto roadway slopes), and 0.019 for CMP. In the current design for the closure condition, the following Manning's roughness coefficients (i.e., "n" values) were used:

<b>Channel Lining</b>	<b>Manning's n for Stability</b>	<b>Manning's n for Capacity</b>
Grass	0.030	0.035
Turf Reinforcement Mat	0.030	0.035
Rip-rap	0.035	0.040
Asphalt or Shotcrete	0.016	0.016

### 5.5.2 Phases I and II Run-On Control

Figure 5.5 shows individual water shed areas that contribute run-on flow to the diversion ditches located along the outside edge of the B-18 Perimeter Road. These ditches intercept the run-on and direct it away from the B-18 active area. Table 5.3 summarizes the previously calculated maximum flows for Phase I and II during the PMP event at key locations along the diversion ditch system and shows the estimated peak flow in comparison with the ditch capacity. In each case, the asphalt-lined ditch is capable of containing the design flow.

A 24-inch diameter CMP runs beneath the B-18 stockpile access road to convey the computed 25-year peak flow. The roadway above the culvert is graded as a swale to convey higher flows for the PMP event, across the road and into a natural drainage channel at the toe of the B-18 Perimeter Road fill slope, which eventually discharges back into the asphalt V-ditch system.

### 5.5.3 Phases I and II Run-Off Control

Table 5.4 summarizes previously calculated run-off conditions for Phase I and II at each of the hydraulic structures required to convey the PMP run-off from roads used for waste truck or landfill equipment access. In each case, the ditch or culvert capacity exceeds the appropriate estimated peak flow.

Table 5.5 compares the capacity of the former temporary Phase I containment basin and the Northeast Containment Basin (see Sheets 5 and 10, respectively, in Appendix A.1) with the estimated run-off volumes from the respective design storms. The capacity shown for the temporary Phase I containment basin in the clay borrow pit is for a height to the top of the lined area. Freeboard is not required for this basin because the basin could not be overtopped above the clay pit walls which extend high above the lined area.

The Phase I Intermediate Closure basin was on the top of a liner that was installed to prevent infiltration into the waste. This containment basin was sized only for run-off from the interim closure slope. This basin was only required until the Phase II construction was completed.

The capacity for the Northeast Containment Basin is based on allowance for a 2-foot freeboard because embankment overtopping could occur at this location.

### 5.5.4 Phase III Run-on Control

Run-on control during Phase III will be performed in a similar manner as it has historically been performed during Phase I and II with the use of ditches on the outside of the perimeter road as well as brow ditches at the top of cut slopes. Figure 5.5 shows individual water shed areas that contribute run-on flow for Phase III and at Closure to the diversion ditches located along the outside edge of the B-18 Perimeter Road. These ditches intercept the run-on and direct it away from the B-18 active area. The run-on areas have decreased in size compared to Phases I and II; however, the run-on

control ditches have remained the same size. To avoid ponding around the southeast side of B-18 some additional fill is added to provide positive drainage from localized low points. Buried 18-inch diameter HDPE solid wall pipe is to be installed below the B-18 south berm to provide drainage of two localized low points. The drainage pipe is maintained outside the limits of the landfill.

The permanent stormwater run-on controls, such as the brow ditches, within the Phase IIIA watershed will be constructed as part of Phase IIIA. During the subsequent placement of waste in Phase IIIA (while Phase IIIB is being constructed), a temporary lined stormwater containment berm will be utilized to prevent stormwater run-on from contacting the Phase IIIA waste. The configuration of this temporary lined containment berm is shown on Sheet C-4A in Appendix A.2. The top of this berm will be approximately 8 feet higher than the nearby high point on the Phase IIIB “bench floor”; therefore, overtopping of this berm by stormwater run-on from the south will not occur. If necessary, portable pumps will be used by site personnel to convey the clean ponded stormwater run-on retained on the south side of the temporary berm to just south of the nearby high point on the Phase IIIB “bench floor,” where it can then gravity flow to the Northeast Containment Basin. A maximum of approximately 2 feet of stormwater could pool against the south side of the temporary berm. However, it should be noted that only small amounts of stormwater are anticipated since Phase IIIB is planned to be constructed during the dry season and, once Phase IIIB is completed, run-on control between Phase IIIA and Phase IIIB will no longer be required.

#### 5.5.5 Phase III Run-Off Control

Run-off control during Phase III operations will be very similar to the current operations. The existing B-18 waste fill is above the existing perimeter road and capable of diverting flows to the Northeast Containment Basin. Initially Phase III waste will be placed in the “valley” formed by the existing waste and the Phase III lined slope. Active areas will control run-off with soil berms to keep stormwater from reaching the basin. Areas covered with interim soil cover will drain within the “valley” to the Northeast Containment Basin. In the event of a PMP prior to the Phase III waste fill reaching the elevation of the perimeter road, where run-off can be diverted to the South Containment Basin, active pumping from the Northeast Containment Basin to the South Containment Basin would be required to maintain adequate capacity.

Appendix J.4, Table 4 summarizes run-off conditions at each of the hydraulic structures required to convey the PMP run-off. In each case, the ditch capacity exceeds the appropriate estimated peak flow.

Table 5.5 compares the capacity of the Northeast Containment Basin and South Containment Basin (see Sheets C-3 and C-4 in Appendix A.2) with the estimated run-off volumes from the 24-hour PMP design storm. Sufficient on-site storage capacity exists to contain all run-off within the basins, however, some active pumping during the 24-hour PMP storm will be required (approximately 1 acre foot) from the northeast basin to the south basin.

The permanent stormwater run-off controls, such as the perimeter channels, within the Phase IIIA watershed will be constructed as part of Phase IIIA. During subsequent placement of waste in Phase IIIA (while Phase IIIB is being constructed), a temporary lined stormwater containment berm will be utilized to contain stormwater flowing off of the south-facing Phase IIIA temporary waste fill slope. This temporary berm will be 10 feet tall (see Sheet C-4A in Appendix A.2). As shown in the Phase IIIA hydrology calculations in Appendix J.3, the basin that will be formed on the north side of this berm will have sufficient capacity to contain the entire run-off volume generated by the 24-hour PMP event while maintaining a freeboard of greater than 1 foot. Stormwater run-off that is impounded on the north side of the temporary berm will be considered leachate and will be managed in an

appropriate manner by site personnel (i.e., through the use of portable pumps to convey the stormwater into tanker trucks for transportation to an on-site treatment facility). Stormwater run-off from the north, east, and west facing waste slopes of Phase IIIA will flow to the Northeast Containment Basin. It should be noted that only small amounts of stormwater are anticipated for this temporary case as Phase IIIB is planned to be constructed during the dry season and, once Phase IIIB is completed, run-off control between Phase IIIA and Phase IIIB will no longer be required.

As described in the Phase IIIA hydrology calculations in Appendix J.3, during the construction of Phase III (i.e., before the South Containment Basin is constructed), the existing Northeast Containment Basin will not have sufficient capacity to contain the stormwater volume generated by the 24-hour PMP event. Specifically, there will be approximately 14 acre-feet of water that will have to be conveyed from the Northeast Containment Basin to the site's existing East Retention Basin (located approximately 2,000 feet north of the Northeast Containment Basin, as shown on Sheet C-1 in Appendix A.2). A 21-inch orifice outlet device will be set 3 feet below the top of the existing embankment of the Northeast Containment Basin. Water will flow through this orifice and into a pipeline (preliminarily sized at 21-inch inside diameter) that will convey this overflow by gravity to the East Retention Basin. During the Phase III construction, the orifice outlet device and gravity flow pipeline will prevent the overtopping of the existing Northeast Containment Basin during the 24-hour PMP event.

#### 5.5.6 Closure Drainage

At closure, the trapezoidal earthen ditches along benches and the Cover Access Road are designed to convey the flow from the 6-hour PMP event as shown in Appendix J, Table 4. As previously discussed, the 6-hour PMP event has a higher rainfall intensity than the 24-hour PMP and is therefore more conservative for sizing the conveyance structures. Conveyance of surface water from the cover and the adjacent areas will occur along the final B-18 Perimeter Road, which will be graded to slope into the closure cover as shown in Detail 4 on Sheet C-7 in Appendix A.2. The peak surface water run-off generated by the 24-hour PMP event will be contained in either the Northeast Containment Basin or the South Containment Basin.

### 5.6 Leachate Collection and Removal

In accordance with USEPA guidance for landfill geosynthetic designs (USEPA, 1987), Appendix K includes the following calculations to support the design of the B-18 LCRS:

- The capacity of the primary LCRS at each area to transmit the mean annual precipitation during the operating period.
- The capacity of the primary LCRS at each sump to convey significantly greater volumes of leachate than historically measured without the build-up of 12 inches of hydrostatic head on the base liner system.
- The suitability of the geotextile to act as a filter between the base operations layer and the primary LCRS drainage gravel layer.

The calculations are based on the conservative assumption that, during operations, all rainfall will percolate through the waste and into the primary LCRS.

The calculations show that the transmissivity of the existing Trevira 1125/Polynet 3000 geocomposite drainage layer used on the sideslopes will have a transmissivity greater than that required to convey the mean annual precipitation considering the maximum waste overburden pressure of nearly 25,000 psf.

The transmissivity of the existing base geocomposite is approximately equal to that required to convey the mean annual precipitation drainage case. However, considerable redundant capacity is provided by the 12 inches of drainage gravel above the base geocomposite in the primary LCRS. The base portion of the secondary LCRS also includes a redundant, 12-inch-thick drainage gravel layer. Furthermore, a geonet layer was provided for a width of 80 feet above the vadose trench to provide drainage in this area.

Filter calculations for the geotextile between the base operations layer and the primary LCRS drainage gravel indicate that the existing Trevira 1125 geotextile is adequate.

Historic records (January 2001 to December 2007) indicate that the primary LCRS generates an average of 360 gallons per day for all four sumps. This volume is significantly less than the 36,000 gallon per day system capacity.

The secondary LCRS, has averaged 10 gallons per day over the period of January 2001 to December 2007. Peak flows have approached 150 gallons per day. Recent monitoring has indicated that no liquids are being collected in the secondary LCRS. The Response Action Plan (RAP) (SEC Donohue 1992a) determined that the Action Leakage Rate (ALR) for each sump ranged from 1,250 to 3,500 gallons per day. These values have a minimum calculated safety factor of 3. Liquids collected in the secondary LCRS have not approached the ALR. The current ALRs remain valid for the proposed expansion since the limiting factor was the length of geocomposite at the toe of slope and this length remains unchanged, conservative transmissivity values are used in the calculations.

The vadose zone collection system has not collected any liquids during the period January 2001 to December 2007. The Vadose Zone Response Plan (SEC Donohue 1992b) allows from 3.5 to 6.6 gallons per day to be collected in the vadose sumps based on a de minimus leakage rate of 20 gallons per acre per day. The vadose system will not be modified by the proposed expansion; therefore, the allowable leakage rates remain valid.

In the event leakage in the secondary or vadose collection systems exceeds the ALR, then appropriate actions in accordance with the RAP will be implemented.

## 5.7 Riser Pipe Designs

Appendix L includes the engineering calculations performed to support the following riser pipe requirements:

- Design of the main 24-inch diameter steel vertical riser pipe and its foundation, located about 6.5 feet above the primary liner system in the sump area, as illustrated in Section B on Sheet 21 in Appendix A.1.
- Provision of adequate crushing strength for the lower 18-inch diameter stainless steel vertical riser pipe that is approximately 7 feet long and is located immediately below the 24-inch diameter steel vertical riser pipe.



- Assurance that the pressure exerted by the main vertical riser pipe foundation will not create a bearing capacity failure in the underlying clay liners.
- Evaluation of the stresses and deflections in the bottom portions of the sideslope riser pipes.

As shown in Section B on Sheet 21 in Appendix A.1, the main vertical riser pipe will be placed inside of a larger, 30-inch diameter corrugated HDPE pipe to avoid the development of high drag loads on the 24-inch diameter steel pipe. The corrugated pipe will not develop significant vertical stresses because it will readily deflect in an accordion-like manner in the longitudinal direction as the surrounding waste settles. The corrugated pipe will be held away from the steel pipe with flexible spacers at about 10-foot centers to avoid long sections where the two pipes would otherwise be in continuous contact. To be conservative, the calculations assume that a contact area of 10 percent of the total contact area between the two pipes develops and that it is capable of transferring drag loads to the inner steel pipe. In addition, significant factors of safety are provided for each of the key components of the system to minimize the potential for large deformation of the riser pipe to occur.

The 6-foot by 6-foot by 1.5-foot-thick reinforced concrete foundation for the main riser pipe was designed to spread any load on the pipe over a sufficient area so that there is a high factor of safety against potential bearing capacity deformations of the underlying clay liner. This is accomplished because the minimum bearing capacity factor of safety is estimated to be between 7 and 10 when using a conservative estimate of the strength of the clay liner. A slip connection has been included in the riser pipe at approximately elevation 900 ft-MSL to reduce the load on the foundation. The loads above the slip connection will be transferred within the waste.

Compression loading on the lower stainless steel pipe is calculated considering at-rest pressures resulting from the main riser pipe foundation loading. The factor of safety against crushing is greater than 5, which is considered appropriately conservative for this system.

Finally, calculations of deflection for the lower portions of the sideslope riser pipes show that:

- The carbon and stainless steel pipe deflections will be on the order of 0.1 inches, which is relatively small with regard to the allowable deflections for these pipes.
- The maximum deflection of the 8-inch diameter HDPE SDR 8.3 pipe is estimated to be on the order of 20 to 30 percent of its diameter.

Although the deflection of the HDPE pipe is higher than would normally be desirable, it is considered to be acceptable because this pipe is included as a second (i.e., redundant) system for pumping from the secondary LCRS. From an operations viewpoint, it was determined that it would be better to have these two redundant types of pipes to minimize the potential for pump access loss because of material deterioration.

## 5.8 Cover Infiltration

Appendix M includes calculations similar to those performed to support the design of the currently-permitted final closure cover system for B-18 (DTSC, 2003). These calculations were performed using the updated computer program HELP version 3.07 (Schroeder et al., 1994) to estimate the amount of infiltration through and head on the final cover system. The infiltration analyses were conducted by assuming the following parameters:

- The vegetative cover soil layer is 2.5-foot-thick with a permeability of  $2 \times 10^{-4}$  cm/s, based on past experience with this type of material at the KHF.
- The HELP program's default climate data for Fresno, California and Bakersfield, California were used to model the climatological conditions at the KHF. Use of Fresno climate is a conservative assumption since Fresno receives approximately 50 percent more rainfall annually than the KHF, based on historic precipitation data.
- The HDPE geomembrane will have 0.50 holes per acre resulting from manufacturer's flaws (where each hole has a 1 mm diameter), 1.0 hole per acre resulting from installation defects (where each hole has an area of  $1 \text{ cm}^2$ ), and "excellent" placement quality.
- The nonwoven geotextile component of the final cover system has an in-plane permeability of 0.25 to 0.40 cm/s.
- The foundation layer has a permeability of  $1 \times 10^{-5}$  cm/sec
- The slope of the final cover system is 25 percent (i.e., 4H:1V).

Based on the above assumptions, the results of the HELP analyses indicate that a maximum head of about 3 to 4 inches will develop on the geomembrane during extended rainy seasons (similar to Fresno) and that acceptably low infiltration rates will occur through the HDPE geomembrane. Since a head of only 3 to 4 inches on the geomembrane is not anticipated to compromise the stability of the final cover system, the permitted final cover system is considered adequate for B-18. Additionally, the permitted cover system has been used to close other facilities at KHF since 1994 without failure or apparent build up of liquids within the cover.

## 5.9 Frost and Biotic Protection

The effects of frost penetration on the B-18 final closure cover were evaluated. Appendix N.1 provides two maps that each show estimated depths of frost penetration for the United States. Both of these maps indicate that the maximum depth of frost penetration at the KHF is less than 6 inches. Past experience and observations at the KHF corroborate this finding. Hence, any frost penetration that occurs is anticipated to be confined to the uppermost portions of the 2.5-foot-thick vegetative cover soil layer and should not present a significant potential to deteriorate the cover system or to cause special maintenance requirements.

The effects of burrowing animals on the B-18 final cover system were also evaluated. Information presented in Appendix N.2 indicates that burrowing animals will be confined to the vegetative cover soil layer due to the presence of the underlying HDPE geomembrane. Past experience at the KHF indicates that HDPE geomembranes are effective barriers to burrowing animals. Hence, the performance of the B-18 final cover is not expected to be impacted by burrowing animals.

## 6.0 REFERENCES

California Department of Water Resources (CDWR), 1976, Rainfall Analysis for Drainage Design Volume I, Short-Duration Precipitation Frequency Data, October.

Department of Toxic Substances Control (DTSC), 2003, Hazardous Waste Facility Permit, Kettleman Hills Facility, June 16.

Donohue and Associates, Inc., 1988a, Engineering Report, Chemical Waste Management, Inc., Kettleman Hills Facility, Landfill B-19, Phases II and III, Kings County, California, October.

Donovan, N., 1983, A Practitioner's View of Site Effects on Strong Ground Motion, Proceedings of Conference XXII on Site-Specific Effects of Soil and Rock on Ground Motion and the Implications for Earthquake-Resistant Design, July 25-27, USGS.

Duncan, J.M., and Buchignani, A.L., 1976, An Engineering Manual for Settlement Studies, Department of Civil Engineering, University of California – Berkeley, June.

EMCON Associates, 1989, Progress Report, Soil/Waste Compatibility Testing, Kettleman Hills Facility, Kettleman City, California, December 26.

EMCON Associates, 1986, Hydrogeologic Characterization, Kettleman Hills Facility, Kings County, California, December.

Environmental Construction Services, Inc. (ECS), 1992a, Clay Source, Landfill B-18, Phases IA and IB, Kettleman Hills Facility, Kettleman City, California, January 9.

Environmental Construction Services, Inc. (ECS), 1992b, Secondary Clay Liner, Landfill B-18, Phases IA and IB, Kettleman Hills Facility, Kettleman City, California, March 30.

Environmental Construction Services, Inc. (ECS), 1992c, Secondary HDPE Liner and Leachate Collection System, Landfill B-18, Phases IA and IB, Kettleman Hills Facility, Kettleman City, California, March 30.

Environmental Construction Services, Inc. (ECS), 1992d, Primary Clay Liner, Landfill B-18, Phases IA and IB, Kettleman Hills Facility, Kettleman City, California, March 30.

Environmental Construction Services, Inc. (ECS), 1992e, Primary HDPE Liner and Leachate Collection System, Landfill B-18, Phases IA and IB, Kettleman Hills Facility, Kettleman City, California, March 30.

Environmental Construction Services, Inc. (ECS), 1992f, Summary Construction Observation, Landfill B-18, Phases IA and IB, Kettleman Hills Facility, Kettleman City, California, March 30.

Environmental Construction Services, Inc. (ECS), 1992g, Operational Features, Landfill B-18, Phases IA and IB, Kettleman Hills Facility, Kettleman City, California, June.

Environmental Construction Services, Inc. (ECS), 1992h, Design Changes and Design Clarifications, Landfill B-18, Phases IA and IB, Kettleman Hills Facility, Kettleman City, California, February 18.

Environmental Solutions, Inc. (ESI), 1992, Test Fill and Infiltration Test Results, Landfill Unit B-18, Phases I and II and Final Closure, January 23.

Environmental Solutions, Inc. (ESI), 1990a, Engineering and Design Report, Landfill Unit B-18, Phases I and II and Final Closure, Kettleman Hills Facility, Kings County, California, Volumes I and II, August.

Environmental Solutions, Inc. (ESI), 1990b, Construction Specifications and Quality Assurance Plan, Landfill Unit B-18, Phases I and II and Final Closure, Kettleman Hills Facility, Kings County, California, July 31.

Franklin, A.G., and Chang, F.K., 1977, Permanent Displacements of Earth Embankments by Newmark Sliding Block Analysis, Earthquake Resistance of Earth and Rock-Fill Dams, Report 5, U.S. Army Engineer Waterways Experiment Station, November.

Geosyntec Consultants, 2008a, Clay Stockpile and Test Pad Report, Kettleman Hills Facility, Kettleman City, California, December.

Geosyntec Consultants, 2008b, Clay Source Testing: Summary of Field and Laboratory Test Results, Kettleman Hills Facility, Kettleman City, California, February 11.

Geosyntec Consultants, 2001, Site-Specific Groundwater Monitoring Plan, Kettleman Hills Facility, Kings County, California, May.

Golder Associates Inc., 1992, Subgrade Geologic Mapping and Chemical Analysis for Landfill B-18, Phase I, Kettleman Hills Facility, Kettleman City, California, March 30.

Golder Associates Inc., 1989a, Supporting Calculations for the Landfill B-15 Closure Plan, Kettleman Hills Facility, December.

Golder Associates Inc., 1989c, Waste Settlement Report for Final Landfill Cover Design, Kettleman Hills Facility, July.

Golder Associates Inc., 1988, Updated Evaluation of Site Design Ground Motions for the CWM Kettleman Hills Facility, September.

Golder Construction Services, Inc. (GCS), 1993a, Clay Liner Source Report (Volume 1), Landfill B-18, Phases IIA and IIB, Kettleman Hills Facility, Kettleman City, California, May.

Golder Construction Services, Inc. (GCS), 1993b, Subgrade Geologic Mapping and Chemical Analysis Report (Volume 2), Landfill B-18, Phases IIA and IIB, Kettleman Hills Facility, Kettleman City, California, May.

Golder Construction Services, Inc. (GCS), 1993c, Excavation and Structural Fill Placement Construction Report (Volume 3), Landfill B-18, Phases IIA and IIB, Kettleman Hills Facility, Kettleman City, California, August.

Golder Construction Services, Inc. (GCS), 1993d, Secondary Clay Liner Construction Report (Volume 4), Landfill B-18, Phases IIA and IIB, Kettleman Hills Facility, Kettleman City, California, September.

Golder Construction Services, Inc. (GCS), 1993e, Secondary and Vadose HDPE Liner and Leachate Collection System Report (Volume 5), Landfill B-18, Phases IIA and IIB, Kettleman Hills Facility, Kettleman City, California, October.

Golder Construction Services, Inc. (GCS), 1993f, Primary Clay Liner Construction Report (Volume 6), Landfill B-18, Phases IIA and IIB, Kettleman Hills Facility, Kettleman City, California, October.

Golder Construction Services, Inc. (GCS), 1993g, Primary HDPE Liner and Leachate Collection System Construction Report (Volume 7), Landfill B-18, Phases IIA and IIB, Kettleman Hills Facility, Kettleman City, California, November.

Golder Construction Services, Inc. (GCS), 1993h, Summary Construction Report (Volume 8), Landfill B-18, Phases IIA and IIB, Kettleman Hills Facility, Kettleman City, California, November 8.

Golder Construction Services, Inc. (GCS), 1993i, Operational Features Report (Volume 9), Landfill B-18, Phases IIA and IIB, Kettleman Hills Facility, Kettleman City, California, December 6.

Hudson, M.B., Beikae, M., and Idriss, I.M., 1994, QUAD4M, a Computer Program to Evaluate the Seismic Response of Soil Structures Using Finite Element Procedures and Incorporating a Compliant Base, Center for Geotechnical Modeling, Department of Civil and Environmental Engineering, University of California, Davis, 1994-05.

J&L Testing Company, 1991a, Leachate Compatibility of Geosynthetic Materials – Kettleman Hills Facility, Final Report, November 4.

J&L Testing Company, 1991b, Geotechnical Laboratory Test Results Aggregate/Leachate Compatibility Testing, Kettleman Hills Facility, November 7.

J&L Testing Company, 1992, NSC 60 mil Textured HDPE Chemical Compatibility Testing EPA Method 9090 – Kettleman Hills Facility, September 8.

Kings County, 1990, Chemical Waste Management, Kettleman Hills Facility, B-18 Administrative Approval Permits 90-23 and 90-24, Kings County Planning Agency, August.

Makdisi, F.I., and Seed, H.B., 1978, Simplified Procedure for Estimating Dam and Embankment Earthquake-Induced Deformation, Journal of the Geotechnical Engineering Division, ASCE, Vol. 104, No. GT7, July, pp. 849-868.

National Oceanic and Atmospheric Administration (NOAA), 1998, Hydrometeorological Report No. 58, Probable Maximum Precipitation for California – Calculation Procedures.

Natural Resources Conservation Service (NRCS), 2004, RUSLE2 – Instructions & User Guide, United States Department of Agriculture, May.

Newmark, N.M., 1965, Effects of Earthquakes on Dams and Embankments, Fifth Rankine Lecture.

Purdue University (Ronald A. Siegel), 1986, STABL User Manual, West Lafayette, Indiana, June 4.

Regional Water Quality Control Board (RWQCB), Central Valley Region, 1998, Order No. 98-058, Waste Discharge Requirements for Chemical Waste Management, Inc., Kettleman Hills Facility, Kings County, February 27.

Roger Foott and Associates, Inc., 1990a, Final Report, Unit B-18 Landfill, Holocene Fault Investigation, Kettleman Hills Facility, August 14.

Roger Foott and Associates, Inc., 1990b, Phase I Holocene Surface Faulting Study, Nunez Fault and Kettleman Hills Facility, April 2.

Schroeder, P.R., Aziz, N.M., Lloyd, C.M., and Zappi, P.A., 1994, The Hydrologic Evaluation of Landfill Performance (HELP) Model: User's Guide for Version 3, EPA/600/R-94/168a, September.

SEC Donohue Environment & Infrastructure, 1992a, Response Action Plan, Landfill B-18, Kettleman Hills Facility, June.

SEC Donohue Environment & Infrastructure, 1992a, Vadose Response Plan, Landfill B-18, Kettleman Hills Facility, June.

Seed, R.B., and Bonaparte, R., 1992, Seismic Analysis and Design of Lined Waste Fills: Current Practice, ASCE Geotechnical Special Publication No. 31, Stability and Performance of Slopes and Embankments, June 29-July 1.

Seed, R.B., Mitchell, J.K., and Seed, H.B., 1988, Slope Stability Failure Investigation: Landfill Unit B-19, Phase I-A, Kettleman Hills, California, Report No. UCB/GT/88-01, Department of Civil Engineering, University of California, Berkeley, July.

TRI/Environmental, Inc., 1991, Chemical Compatibility Testing of National Seal 60 mil Geomembrane with Kettleman Hills Waste Leachate, Soltex Resin, NSC#CO2A, Final Report, October 14.

United States Environmental Protection Agency (USEPA), 1989, Technical Guidance Document: Final Covers on Hazardous Waste Landfills and Surface Impoundments, EPA/530-SW-89-047, July.

United States Environmental Protection Agency (USEPA), 1987, Minimum Technology Guidance on Double Liner Systems for Landfills and Surface Impoundments - Design, Construction and Operation, EPA/530/SW-85/014, April.

Woodring, W.P., Stewart, R., and Richards, R.W., 1940, Geology of the Kettleman Hills Oil Field, California; Stratigraphy, Paleontology, and Structure, United States Geological Survey Professional Paper No. 195, 170 p.

Woodward-Clyde Consultants, 1987, Seismic Stability Evaluation for the Toe Buttress Construction, Operating Industries, Inc. Site, Monterey Park, California, Document No. 120-R12-RT-EPNN-1, Prepared for U.S. EPA, May 27.

**The following references were used in the Phase I and Phase II engineering report but have not specifically been included in the Phase III and Closure. The references are included herein for completeness:**

Chemical Waste Management, Inc. (CWMI), 1989, Operation Plan for Landfill Unit B-19, Kettleman Hills Facility. June.

Donohue and Associates, Inc., 1988b, Construction Documents, Landfill Unit B-19, Phases II and III, Kettleman Hills Facility. September.

Geoservices, Inc., 1990, Consulting Engineers. Direct Shear Interface Strength Testing Selected Geotextile Interfaces. April 5.

Geosyntec, Inc., 1988, Final Report on the Direct Shear Testing for the Chemical Waste Management, Inc. New Milford, Connecticut Landfill. Prepared for Geoservices, Inc. Consulting Engineers. October 11.

Golder Associates Inc., 1990a, Combined Closure Plan for Landfills B-1/4/S/6/7, B-8/9/9 Expansion /9 Extension /10/11, Surface Impoundments P-5/12/12A/13/17 and Area S-3, Kettleman Hills Facility. Revision 2, Draft. June.

Golder Associates Inc., 1990b, Direct Shear Testing Program for Landfill Cover Design, Kettleman Hills Facility. June 29.

Golder Associates Inc., 1990c, Closure Plan for Landfill B16, Kettleman Hills Facility, Kettleman City, California. April 23.

Golder Associates Inc., 1989b, Feasibility Study for Final Landfill Cover Systems, Kettleman Hills Facility (Draft), August.

Golder Associates Inc., 1989d, Filling Plan, Landfill B-19, Phases II and III, Kettleman Hills Facility, May.

- Golder Associates Inc., 1988a, Filling Plan, Phase IB and III, Kettleman Hills Facility, August.
- Golder Associates Inc., 1988a, Dynamic Stability of Cut Slopes in Bedrock, Landfill B-19, Kettleman Hills Facility, June.
- Golder Associates Inc., 1988c, Filling Plan, Phase IB and III, Kettleman Hills Facility, August.
- Gundle Lining Systems, Inc., 1989, Direct Shear Friction Testing, Gundle Friction Sheet, Mirafi 140N Geotextile, March 26.
- Gundle Lining Systems, Inc., 1988a, Direct Shear Test Results, Textured HDPE and Soil, October.
- Gundle Lining Systems, Inc., 1988b, Direct Shear Test Results, Gundle HDT and Fabric, Covered XL-4, Dry and Saturated Conditions, September.
- Gundle Lining Systems, Inc., 1988c, Direct Shear Test Results, Textural HDPE and Sand, Dry and Saturated Conditions, June 15.
- Gundle Lining Systems, Inc., 1988d, Lab Report #2683.
- Gundle Lining Systems, Inc., 1987a, Direct Shear Testing of Friction Liner Material, March 11.
- Gundle Lining Systems, Inc., 1987b, Direct Shear Friction Testing, Gundnet XL-4 versus 80 mil Gundline, November.
- Gundle Lining Systems, Inc., (not dated), Polyethylene VS. PVC Liners.
- Gundle Lining Systems, Inc., (not dated), Direct Shear Testing of Friction Liner Materials (Several Separate Reports).
- Koerner, R., 1986, Designing with Geosynthetics.
- Lambe, T.W., and Whitman, R.V., 1969, Soil Mechanics, New York: John Wiley & Sons, Inc.
- Murphy, W.L. and Gilbert, P.A., 1985, Settlement and Cover Subsidence of Hazardous Waste Landfills, Prepared for U.S. EPA. Document No. 600/2-85-035, April.
- SLT North America, Inc., (not dated), Physical Properties of Textured HDPE Liners, Friction Flex Application Data.
- U.S. Department of Agriculture, 1987, Agriculture Handbook 537, Predicting Rainfall Erosion Losses, December.
- U.S. Department of the Navy, Naval Facilities Engineering Command, 1986, Soil Mechanics Design Manual 7.01, September.
- U.S. EPA, 1990, RCRA Hazardous Waste Facility Permit (Part B) for Kettleman Hills Facility, March.
- U.S. EPA, 1988, Lining of Waste Containment and Other Impoundment Facilities, EPA-600/2-88/052, September.
- U.S. EPA, 1979, Design and Construction of Covers for Solid Waste Landfills, EPA-600/2-79-165, August.
- U.S. EPA, 1983, The Hydrologic Evaluation of Landfill Performance (HELP) Model, Version 2, EPA/530-SW-84-OIO, August.
- Water Resources Engineers, Inc., 1977, County of Solano, Hydrology and Drainage Design Procedure, October.

Winterkorn, H.F., and Fang, H.-Y. (eds.), 1975, Foundation Engineering Handbook, Chapter 23, Buried Structures, Van Nostrand Reinhold Company.

Yen, B.C., and Scanlan, B., 1975, Sanitary Landfill Settlement Rates, ASCE Journal of the Geotechnical Engineering Division, May.



**TABLES**

**TABLE 3.1**  
**KEY BORING INFORMATION**

BORING	NORTHING EASTING	GROUND ELEVATION (Feet) TOTAL DEPTH	SAMPLE NUMBER (Mode) <sup>(1)</sup>	SAMPLE DEPTH (Feet)	STRATIGRAPHIC UNIT DESCRIPTION <sup>(2)</sup>	STRATIGRAPHIC UNIT NUMBER	RECOVERY (%)	PURPOSE
L18-A	8,943 840	856 38.7	S-1 (PB)	5 - 6.1	ss	18-10	91	<ul style="list-style-type: none"> <li>Obtain samples of Unit 18-10. This unit occurs at the toe of the western cut slope and bottom of excavation, Phase I/II (See Sections 8 and 14). Unit 18-10 also occurs at toe and middle section of eastern cut slope at Section 18.</li> </ul>
			S-2 (PB)	10 - 12.5	cs/ss	18-10	84	
			S-3 (PB)	17-19.5	cs/ss	18-10	96	
			S-4 (PB)	25-27.5	silty ss	18-10	100	
			S-5 (PB)	33-35.5	silty ss w/cs	18-10	88	
			S-6 (PB)	37-38.7	silty ss w/cs	18-10	88	
L18-B	8,755 860	861 39.5	S-1 (PB)	6-8.5	cs	18-12	92	<ul style="list-style-type: none"> <li>Determine depth to top of silty ss (Unit 18-11).</li> <li>Obtain samples of Unit 18-12. This unit occurs near the toe of western cut slope, Phase I/II (See Sections 14+00 and 18+00).</li> <li>Obtain samples of Unit 18-11. This unit occurs at toe of western cut slope - See Sections 14+00 and 18+00.</li> </ul>
			S-2 (PB)	11.5-14	silty ss	18-11	96	
			S-3 (PB)	20-22.5	ss	18-11	64	
			S-4 (PB)	28-30.5	ss w/cs/slt	18-11	88	
			S-5 (PB)	37-39.5	ss	18-11	80	
L18-C	8,623 2,120	754 89	B-1 (DR)	6-7.5	colluvium (cl)	Qc	87	<ul style="list-style-type: none"> <li>Determine colluvium thickness.</li> <li>Obtain samples of ss, silt (Unit 18-7). This unit occurs at bottom of excavation, Phase III/IV (See Sections 14+00 and 18+00) and at toe of western in-dipping cut slope, Phases III &amp; IV (See Section 14+00).</li> </ul>
			B-2 (DR)	12-13.5	colluvium (cl)	Qc	53	
			S-1 (PB)	15-17.3	silt	18-7	91	
			S-2 (PB)	20-22.5	silt	18-7	92	
			S-3 (PB)	25-27.5	silt	18-7	88	
			S-4 (PB)	33-35	cs/silt	18-7	95	
			S-5 (PB)	41-43.1	silty ss	18-7	95	
			S-6 (PB)	48-50.1	sh clayey silt	18-7	90	
			S-7 (PB)	56-58	silt	18-7	90	
			S-8 (PB)	64-66.3	clayey silt	18-7	78	
			S-9 (PB)	72-74.3	ss, silty ss	18-7	100	
S-10 (PB)	80-82	silt/cs	18-7	95				
S-11 (PB)	87-89	silt	18-7	85				
L18-D	8,785 2,480	740 86	B-1 (DR)	5-6.5	colluvium	--	87	<ul style="list-style-type: none"> <li>Determine colluvium thickness.</li> <li>Clarify contact of Units 18-4 and 18-3.</li> <li>Clarify contact of Units 18-4 and 18-5.</li> <li>Obtain samples of these units.</li> <li>Units 18-4 and 18-5 occur at eastern over-dipping cut slope, Phase III and IV (See Sections 14+00 and 18+00).</li> </ul>
			B-2 (DR)	10-11.5	colluvium	--	100	
			B-3 (Bag)	14	colluvium	--	--	
			S-1 (PB)	15-17.3	silty ss	18-5	78	
			S-2 (PB)	22-24.3	silt	18-5	96	
			S-3 (PB)	29-31.5	cs/silt	18-4	80	
			S-4 (PB)	36-38.5	cs/silt	18-4	92	
			S-5 (PB)	44-46.5	cs	18-4	60	
			S-6 (PB)	52-54.3	cs	18-4	65	
			S-7 (PB)	60-62.5	cs/silt	18-4	48	
			S-8 (PB)	68-70.5	cs	18-4	56	
S-9 (PB)	76-78.5	silty ss	18-3	32				
S-10 (PB)	81-83.5	silty ss	18-3	36				
S-11 (PB)	83.5-86	silty ss	18-3	68				
L18-E	8,895 2,670	727 62.5	B-1 (DR)	5-6.5	colluvium (cl)	--	87	<ul style="list-style-type: none"> <li>Determine colluvium thickness.</li> <li>Clarify contact of Units 18-2 and 18-3.</li> <li>Obtain samples of colluvium Units 18-3 and 18-2. These units may serve as foundation materials or run-off retention berms or larger berm for Phase III &amp; IV configuration.</li> </ul>
			S-1 (PB)	16-12.5	colluvium (cl)	--	68	
			S-2 (PB)	15-17.5	ss	18-3	84	
			S-3 (PB)	20-22.5	ss	18-3	56	
			S-4 (PB)	28-30.2	ss	18-3	86	
			S-5 (PB)	35-37.5	sandy silt	18-3	88	
			S-6 (PB)	43-45	sandy silt	18-3	80	
			S-7 (PB)	51-53	cs	18-2	95	
S-8 (PB)	60-62.5	sandy cs	18-2	96				

(1) PB = Pitcher Barrel; DR = Drive Sampler

(2) cs = Claystone; ss = Sandstone; silt = Siltstone

TABLE 3.1  
KEY BORING INFORMATION  
(Continued)

BORING	NORTHING EASTING	GROUND ELEVATION (Feet) TOTAL DEPTH	SAMPLE NUMBER (Mode) <sup>(1)</sup>	SAMPLE DEPTH (Feet)	STRATIGRAPHIC UNIT DESCRIPTION <sup>(2)</sup>	STRATIGRAPHIC UNIT NUMBER	RECOVERY (%)	PURPOSE
L18-F	8,930 1,538	821 58.5	S-1 (PB)	6-8.5	cs	18-8	100	• Obtain samples of Unit 18-8 (clay). This unit occurs in eastern out-dipping cut slope, Phase I/II (See Section 8+00).
			S-2 (PB)	16-18.5	cs	18-8	88	
			S-3 (PB)	26-28.5	cs	18-8	92	
			S-4 (PB)	36-38.5	cs	18-8	76	
			S-5 (PB)	46-48.1	cs	18-8	100	
			S-6 (PB)	56-58.5	cs	18-8	84	
L18-G	7,500 1,914	853 77.5	S-1 (PB)	6-8.5	ss	18-13	56	• Obtain samples of Units 18-13 and 18-12. Unit 18-13 (sandstone) comprises the western cut slope, Phase I/II. Unit 18-12 (claystone) occurs near the toe of the cut slope, Phase I/II, at Section 18+00.
			S-2 (PB)	14-16.5	ss	18-13	56	
			S-3 (PB)	22-23.7	ss	18-13	88	
			S-4 (PB)	30-32	ss	18-13	60	
			S-5 (PB)	40-41.3	ss	18-13	92	
			S-6 (PB)	45-47.5	cs	18-12	60	
			S-7 (PB)	50-51.8	cs	18-12	72	
			S-8 (PB)	60-62.5	cs	18-12	40	
			S-9 (PB)	65-67	cs	18-12	70	
			S-10 (PB)	75-77.5	ss	18-12	32	
L18-H	8,065 2,055	865 57.5	S-1 (PB)	6-8.5	cs	18-10	72	• Obtain samples of Unit 18-10 underlying the fossil bed. This unit occurs at out-dipping cut slope, eastern side, Phase I/II (see Sections 14+00 and 18+00). In Section 8+00 Unit 18-10 occurs at bottom of excavation.
			S-2 (PB)	15-17.5	silty ss or with sand	18-10	76	
			S-3 (PB)	25-27.5	or with sand	18-10	68	
			S-4 (PB)	35-37.5	cs	18-10	92	
			S-5 (PB)	45-47.5	silty ss	18-10	96	
			S-6 (PB)	55-57.5	or with sand	18-10	48	
L18-I	8,022 2,415	766 18.5	B-1 (DR)	6-7.5	colluvium (cl)	--	87	• Determine colluvium thickness.
			S-1 (PB)	12-13.8	colluvium (cl)	--	78	• Obtain sample of Unit 18-8 (claystone).
			S-2 (PB)	16-18.5	cs	18-8	92	
L18-J	228,390 1,701,985	820 172.5	S-1 (PB)	5 - 7.5	cs	18-8	68	• Obtain samples of Unit 18-8. This unit will be used as liner material. • The primary purpose is to evaluate the continuity of the claystone and to determine the existence and thickness of thin sandstone strata as noted on the log of Monitoring Well K-8.
			S-2 (PB)	10 - 12.5	cs	18-8	88	
			S-3 (PB)	15 - 17.5	cs	18-8	88	
			S-4 (PB)	20 - 22	cs/ss	18-8	75	
			S-5 (PB)	25 - 27.5	cs	18-8	76	
			S-6 (PB)	30 - 32.5	cs	18-8	96	
			S-7 (PB)	35 - 37.5	cs	18-8	100	
			S-8 (PB)	40 - 42.5	cs	18-8	72	
			S-9 (PB)	45 - 47.5	cs	18-8	92	
			S-10 (PB)	50 - 52.5	cs	18-8	92	
			S-11 (PB)	55 - 57.5	cs	18-8	92	
			S-12 (PB)	60 - 62.5	cs	18-8	96	
			S-13 (PB)	65 - 67.5	cs	18-8	84	
			S-14 (PB)	70 - 72.5	cs	18-8	88	
			S-15 (PB)	75 - 77.5	cs	18-8	100	
			S-16 (PB)	80 - 82.5	cs	18-8	96	
			S-17 (PB)	85 - 87.5	cs	18-8	88	
			S-18 (PB)	90 - 92.5	cs	18-8	84	
			S-19 (PB)	95 - 97.5	cs/ss	18-8	32	
			S-20 (PB)	100 - 101.5	cs	18-8	60	
			S-21 (PB)	105 - 107.5	cs	18-8	100	
			S-22 (PB)	110 - 112.5	cs	18-8	100	
			S-23 (PB)	115 - 117.5	cs	18-8	96	
			S-24 (PB)	120 - 122.5	cs	18-8	100	
			S-25 (PB)	125 - 127.5	cs	18-8	96	

(1) PB = Pitcher Barrel; DR = Drive Sampler  
(2) cs = Claystone; ss = Sandstone; sh = Silstone

TABLE 3.1  
KEY BORING INFORMATION  
(Continued)

BORING	NORTHING EASTING	GROUND ELEVATION (Feet) TOTAL DEPTH	SAMPLE NUMBER (Mole) <sup>(1)</sup>	SAMPLE DEPTH (Feet)	STRATIGRAPHIC UNIT DESCRIPTION <sup>(2)</sup>	STRATIGRAPHIC UNIT NUMBER	RECOVERY (%)	PURPOSE
L18-J (Cont.)			S-26 (PB)	130 - 132.8	cs	18-8	100	
			S-27 (PB)	135 - 137.5	cs	18-8	100	
			S-28 (PB)	140 - 142.5	cs	18-8	100	
			S-29 (PB)	145 - 147.5	cs	18-8	100	
			S-30 (PB)	150 - 152.5	cs	18-8	100	
			S-31 (PB)	155 - 157.5	cs	18-8	100	
			S-32 (PB)	160 - 162.5	cs	18-8	100	
			S-33 (PB)	165 - 167.5	slt	18-7	92	
			S-34 (PB)	170 - 172.5	ss	18-7	88	
L18-K	228,390 1,701,722	804 97.5	S-1 (PB)	5 - 7.5	ss	18-9	88	<ul style="list-style-type: none"> <li>Obtain samples of Unit 18-9. This strata will be excavated concurrently with the claystone in order to develop the clay borrow pit.</li> <li>Samples from this boring will be utilized for various combinations of claystone to determine the potential for mixing of the two rock types as they are excavated from the borrow pit.</li> </ul>
			S-2 (PB)	10 - 12.5	silty ss	18-9	92	
			S-3 (PB)	15 - 17.5	silty ss	18-9	100	
			S-4 (PB)	20 - 22.5	silty ss	18-9	60	
			S-5 (PB)	25 - 27.5	ss	18-9	96	
			S-6 (PB)	30 - 32.5	sandy silt	18-9	100	
			S-7 (PB)	35 - 37.2	silty ss	18-9	86	
			S-8 (PB)	40 - 42.5	silty ss	18-9	92	
			S-9 (PB)	45 - 47	slt	18-9	95	
			S-10 (PB)	50 - 52.5	sandy silt	18-9	88	
			S-11 (PB)	55 - 57.5	sandy silt	18-9	68	
			S-12 (PB)	60 - 62.5	sandy silt	18-9	56	
			S-13 (PB)	65 - 67.2	ss	18-9	86	
			S-14 (PB)	70 - 72.5	silty ss	18-9	100	
			S-15 (PB)	75 - 76.8	silty ss	18-9	94	
			S-16 (PB)	80 - 82.3	ss	18-9	52	
			S-17 (PB)	85 - 87.5	cs	18-8	88	
			S-18 (PB)	90 - 92.5	cs	18-8	100	
			S-19 (PB)	95 - 97.5	cs	18-8	100	

(1) PB = Pitcher Barrel; DR = Drive Sampler  
(2) cs = Claystone; ss = Sandstone; silt = Siltstone

TABLE 3.2

MATRIX OF INVESTIGATION ACTIVITY VS. ROCK STRUCTURE

INVESTIGATION ACTIVITY					
STRATIGRAPHIC UNIT	TEST TRENCHES	TEST PITS	BORINGS	EXISTING AND PREVIOUS MONITORING WELLS	
Colluvium	All Test Trenches	All Test Pits	L18-C, L18-D, L18-E, L18-I	-	
18-1	-	-	-	K-19, K-29	
18-2	-	-	L18-E	K-19, K-29	
18-3	-	-	L18-D, L18-E	K-2, K-19	
18-4	DT-E	-	L18-D	K-1, K-2, K-26	
18-5	DT-E	-	L18-D	K-1, K-2, K-26, K-38	
18-6	DT-E	-	-	K-1, K-2, K-26, K-38	
18-7	DT-B, DT-E, T-1, T-2	TP-5, TP-6, TP-20, TP-21, TP-28	L18-C, L18-F	K-1, K-2, K-8, K-26, K-32, K-38	
18-8	DT-A, DT-B, DT-C, T-3	TP-1, TP-6, TP-7, TP-8, TP-9, TP-27, TP-36, TP-37, TP-38, TP-39, TP-40, TP-41	L18-F, L18-I, L18-J	K-8, K-32, K-33, K-38	
18-9	DT-A, DT-D	TP-1, TP-2, TP-3, TP-4, TP-26, TP-42, TP-43	L18-K	K-8, K-33	
18-10	DT-A, DT-D	TP-4, TP-12, TP-13, TP-18, TP-29, TP-35, TP-35A	L18-A, L18-H	K-8, K-33	
18-11	DT-A, DT-D	TP-11, TP-19, TP-25, TP-30	L18-B	K-8, K-18, K-33	
18-12	DT-A, DT-D	TP-10, TP-16, TP-17, TP-31, TP-34	L18-B, L18-G	K-21, K-33	
18-13	DT-A, DT-D, DT-F	TP-14, TP-15, TP-22, TP-23, TP-24, TP-32, TP-33	L18-G	K-18, K-21, K-33	
18-14	-	-	-	K-18, K-21	

89-977 (8/14/90)

TABLE 3.3

GEOTECHNICAL PARAMETERS FROM PRIOR INVESTIGATIONS

PARAMETER	PHASES II & III B-19 LANDFILL DESIGN	SEED, RAYMOND B. ET AL. INVESTIGATION OF PHASE I B-19 LANDFILL FAILURE	GENERIC EVALUATIONS OF KHF LANDFILL CLOSURES	EMPIRICAL OR MEASURED DATA FROM PUBLISHED LITERATURE
<b>I. STRENGTH PROPERTIES</b>				
<u>SANDSTONE</u> Cross-bed Strength (In-dipping)	C (psf)	800 <sup>(1)</sup>		
	Ø (Degrees)	40		
Anisotropic Strength (Out-dipping)	C (psf)	--		
	Ø (Degrees)	--		
<u>SILTSTONE</u> Cross-bed Strength (In-dipping)	C (psf)	800 <sup>(1)</sup>		
	Ø (Degrees)	40		
Anisotropic Strength (Out-dipping)	C (psf)	0 <sup>(1)</sup>		
	Ø (Degrees)	36		
<u>CLAYSTONE</u> Cross-bed Strength (In-dipping)	C (psf)	800 <sup>(1)</sup>		
	Ø (Degrees)	40		
Anisotropic Strength (Out-dipping)	C (psf)	0 <sup>(1)</sup>		
	Ø (Degrees)	36		
<u>COMPACTED FILL</u>	C (psf)	600 <sup>(1)</sup>	400	500 <sup>(2)</sup>
	Ø (Degrees)	26	38	31
<u>CLAY LINER</u>	C (psf)		2,200 <sup>(5)</sup>	1300 (peak) <sup>(6)</sup> , 600 (residual)
	Ø (Degrees)			
<u>WASTE</u>	Unit Weight (pcf)	85 <sup>(3)</sup>	85 <sup>(3)</sup>	110 <sup>(3)</sup>
	C (psf)	700	0	0
	Ø (Degrees)	0	27	28
<b>LINER SYSTEM INTERFACES</b>				
Waste/Protective Soil	Ø (Degrees)	--	>>8°	31 <sup>(6)</sup>
Protective Soil/Geotextile	Ø (Degrees)	--	>>8°	
Geotextile/Granular Layer	Ø (Degrees)	--	>>8°	>30
Geotextile/Geonet	Ø (Degrees)	--	>12 (Residual)	
HDPE/Geonet	Ø (Degrees)	--	8.5 (Residual)	
				23 <sup>(8)</sup>
HDPE/Compacted Clay	Ø (Degrees)	--	0	11 <sup>(6)</sup>
	τ (psf)	--	900	0
- Textured HDPE	Ø (Degrees)	--	--	26 <sup>(9)</sup>
	τ (psf)	--	--	0
- Textured HDPE	Ø (Degrees)	--	--	27 <sup>(4)</sup>
	τ (psf)	--	--	0
Compacted Clay/Geotextile	Ø (Degrees)	--	24 (Residual)	

(1) See Footnotes next page.

TABLE 3.3

GEOTECHNICAL PARAMETERS FROM PRIOR INVESTIGATIONS  
(Continued)

PARAMETER	PHASES II & III B-19 LANDFILL DESIGN	SEED, RAYMOND B. ET AL. INVESTIGATION OF PHASE I B-19 LANDFILL FAILURE	GENERIC EVALUATIONS OF KHF LANDFILL CLOSURES	EMPIRICAL OR MEASURED DATA FROM PUBLISHED LITERATURE
HDPE/Geotextile - Smooth HDPE $\phi$ (Degrees)	--	8° (Residual)	9 <sup>(6)</sup>	9 <sup>(9)</sup>
- Textured HDPE $\phi$ (Degrees)	--	--		32 <sup>(9)</sup>
HDPE/Soil - Smooth HDPE $\phi$ (Degrees)	--	--		18,18,26,23,15,21,15
- Textured HDPE $\phi$ (Degrees)	--	--		29.8,34,33,35,29,27, 26,25,35
HDPE/Geocomposite - Smooth HDPE $\phi$ (Degrees)	--			11°, 16.6
- Textured HDPE $\phi$ (Degrees)	--			42°, 38.5 <sup>(10)</sup>
<b>II. CONSOLIDATION PROPERTIES</b>				
<b>SANDSTONE</b>				
E (KSF)	--			
Recompression Ratio (Percent) <sup>(1)</sup>	0			
<b>SILTSTONE</b>				
$e_o$	.74			
E (KSF)	--			(250-500)( $\sigma_1 - \sigma_3$ ) <sup>(11)</sup>
Recompression Ratio (Percent) <sup>(1)</sup>	1.4			
<b>CLAYSTONE</b>				
$e_o$	.93			
E (KSF)	--			(250-500)( $\sigma_1 - \sigma_3$ ) <sup>(11)</sup>
Recompression Ratio (Percent) <sup>(1)</sup>	1.4			
<b>COMPACTED FILL</b>				
Typical Value of Compression (percent of original height)				4 <sup>(7)</sup>
<b>CLAY LINER</b>				
$e_o$		.82, .83, .87		
Second Compression Index			.005 to .03	
Cv (Ft/Yr)		2		
<b>WASTE</b>				
Typical Value of Compression (percent or original height)			10,14.5 <sup>(6)</sup>	
Second Compression Index				.1 to .4 <sup>(7)</sup> , .09 <sup>(12)</sup>

(1) Donohue 1988, Appendix F.  
 (2) EMCON (Pond P-9 levees). Reference 3.  
 (3) Donohue 1988, Appendix F, Figure V-9.  
 (4) Koerner, 1986.  
 (5) Seed, et al., 1988)  
 (6) Golder, 1988c.  
 (7) Navy, 1982.  
 (8) SLT, Friction Flex.

(9) Gundle, 1988a.  
 (10) Gundle, 1988c.  
 (11) Winterkorn et al., 1975.  
 (12) Yen, et al., 1975.  
 (13) Gundle, 1987.







TABLE 3.5

LABORATORY TESTS OF TEST PIT SAMPLES

NUMBER	TEST PIT NO.	SAMPLE TYPE	SAMPLE NO.	SAMPLE DEPTH (Feet)	STRATIGRAPHIC UNIT	INDEX PROPERTIES					COMPACTION PROPERTIES		STRENGTH		MISCELLANEOUS			
						MATERIAL TYPE	VISUAL CLASSIFICATION	PLASTICITY INDEX	PERCENT PASSING NO. 200	SIEVE ANALYSIS/ (7) HYDROMETER	SPECIFIC GRAVITY	MODIFIED PROCTOR	STANDARD PROCTOR	UNCONSOLIDATED UNDRAINED (UU) TRIAXIAL	CONSOLIDATED UNDRAINED (CU) TRIAXIAL	PERMEABILITY	CONSOLIDATION (8)	SHRINK/SWELL POTENTIAL
1	DT-A	Sack	1	5	Colluvium	cl												
2	DT-A	Sack	2	5	18-8	CS	X	X	X		X	X	X	X	(2)	(3)	(5)	(2)
3	DT-C	Sack	2		Colluvium	cl												
4	DT-C	Sack	1	8	18-8	CS	X	X	X		X		X	(2)	(3)	(5)	(2)	
5	TP-1	Sack	B-1	7	18-9	SS	X		X		X							
6	TP-2	Sack	B-1	10	Colluvium	cl	X		(6)									
7	TP-3	Sack	B-1	15	Colluvium	cl												
8	TP-7	Sack	B-1	10	Colluvium	cl												
9	TP-8	Sack	B-1	7	Colluvium	cl	X		(6)									
10	TP-11	Sack	B-1	7	Colluvium	S/C	X		X									
11	TP-13	Sack	B-1	4	Colluvium	cl	X		X									
12	TP-15	Sack	B-1	7	Colluvium	S/C												
13	TP-17	Sack	B-1	8	Colluvium	cl												
14	TP-18	Sack	B-1	2	Colluvium	cl	X		(6)									
15	TP-18	Sack	B-2	12	Colluvium	C/S												
16	TP-23	Sack	B-1	0-4	Colluvium	S/M	X		(6)									
17	TP-25	Sack	B-1	0-7	Colluvium	SC/S/M	X		(6)		(6)			(6)			(6)	
18	TP-26	Sack	B-1	0-10.5	Colluvium	S/C	X		(6)									
19	TP-27	Sack	B-1	0-12	Colluvium	S/C	X		(6)									
20	TP-28	Sack	B-1	0-12.5	Colluvium	S/C												
21	TP-28	Sack	B-2	12.5-13.5	18-7	CS/SLT												
TEST TOTALS FOR INITIAL TEST PITS							12	2	9	3	3	4		2 (Series)	3	2	3	
ANTICIPATED TESTS FOR TEST PITS TP-29 THROUGH TP-43							4	4	--	3	--	--		--	--	--	--	

TABLE 3.5

LABORATORY TESTS OF  
TEST PIT SAMPLES  
(Continued)

NUMBER	TEST PIT NO.	SAMPLE TYPE	SAMPLE NO.	SAMPLE DEPTH (Feet)	STRATIGRAPHIC UNIT	INDEX PROPERTIES					COMPACTION PROPERTIES		STRENGTH		MISCELLANEOUS			
						MATERIAL TYPE	VISUAL CLASSIFICATION	PLASTICITY INDEX	PERCENT PASSING NO. 200	SIEVE ANALYSIS/ (7) HYDROMETER	SPECIFIC GRAVITY	MODIFIED PROCTOR	STANDARD PROCTOR	UNCONSOLIDATED UNDRAINED (UU) TRIAXIAL	CONSOLIDATED UNDRAINED (CU) TRIAXIAL	PERMEABILITY	CONSOLIDATION (8)	SHRINK/SWELL POTENTIAL
22	TP-29	Sack	B-1	4-65	18-10	CS												
23	TP-30	Sack	B-1	7	18-11	SS/CS												
24	TP-31	Sack	B-1	3.5	18-12	CS	X	X										
25	TP-32	Sack	B-1	5	18-13	SS												
26	TP-33	Sack	B-1	8	18-13	SS												
27	TP-34	Sack	B-1	4	18-12	CS												
28	TP-35A	Sack	B-1	7	18-10	SS												
29	TP-36	Sack	B-1	4	18-8	CS	X	X		X								
30	TP-37	Sack	B-1	6	18-8	CS						X						
31	TP-38	Sack	B-1	9	18-8	CS	X	X		X								
32	TP-39	Sack	B-1	10	18-8	CS												
33	TP-40	Sack	B-1	3	18-8	CS	X	X		X								
34	TP-41	Sack	B-1	3.5	18-8	CS												
35	TP-42	Sack	B-1	6	18-9	SS	X			X	X	X		X				
36	TP-43	Sack	B-1	6	18-9	SS/SLT												
TEST TOTALS TP29 THROUGH TP-43							4	4	--	3	--	--		--	--			
TEST TOTALS ALL TEST PITS							16	6	9	6		3		4	2 (Series)	3	2	3

NOTES:

89-977 (8/14/90)

- (1)  $\sigma_3 = 4, 8, 12$  k.s.f.
- (2) Sample at 90% relative compaction and optimum moisture content.
- (3) If permeability criteria is satisfied, sample at 90% relative compaction and optimum moisture content.
- (4) Sample at 95% relative compaction at optimum moisture content.
- (5) Loading sequence: 0.5, 1, 2, 4, 8, 16, 32 k.s.f.
- (6) Based on the percentage passing no. 200 test results prepare a composite sample using the three samples with smaller percentage of fines. Run compaction, permeability and shrink/swell potential at 90% relative compaction and optimum moisture content. Mixing with claystone samples will be considered upon review of preliminary results.
- (7) Sieve analysis if percentage passing no. 200 sieve is less than 40%. Hydrometer analysis if greater than 40%.
- (8) Time readings requested.

TABLE 3.6

**GEOTECHNICAL/GEOCHEMICAL  
ANALYSIS METHODS**

TYPE OF TEST	STANDARD
<b>Geotechnical</b> Moisture Content Liquid and Plastic Limits Shrinkage Limit Grain Size Analysis Specific Gravity Moisture Density Relations: <ul style="list-style-type: none"> <li>• (Modified Proctor)</li> <li>• (Standard Proctor)</li> </ul> Direct Shear Unconsolidated Undrained Triaxial Hydraulic Conductivity	ASTM D2216-80 ASTM D4318-84 ASTM D427-83 ASTM D422-63 ASTM D854-83  ASTM D1557-78, Method A  ASTM D698-78, Method A  ASTM D3080-72  Corps of Engineers EM 1110-2-1906 Corps of Engineers EM 1110-2-1906
<b>Background Geochemistry</b> Priority Pollutants: <ul style="list-style-type: none"> <li>• Volatile Organics</li> <li>• Semi-Volatile Organics</li> <li>• Pesticides</li> </ul> California Regulated Metals Total Organic Carbon Specific Conductance pH Nitrate Sulfate Cyanide Chloride	  EPA 8240 EPA 8270 EPA 8080  CCR Title 22 Section 66699  EPA 9060 EPA 9050 EPA 9045 EPA 9200 EPA 9035 EPA 9010 EPA 9250

TABLE 3.7

SUMMARY OF PLASTICITY INDEX DATA  
BY STRATIGRAPHIC UNIT

STRATIGRAPHIC UNIT	BORING NO.	SAMPLE NO.	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USC SYMBOL
COLLUVIUM	L18-C	B-1	6.0 - 7.5	35	19	CL
COLLUVIUM	L18-D	B-2	10.0 - 11.5	29	13	CL
18-2	L18-E	S-8	60.0 - 62.5	53	32	CH
18-3	L18-E	S-6	43.0 - 45.0	32	6	ML
18-4	L18-D	S-6	52.0 - 54.3	67	42	CH
18-5	L18-D	S-2	22.0 - 24.3	49	29	CL/CH
18-7	L18-C	S-1	15.0 - 17.3	38	17	CL
18-7	L18-C	S-3	25.0 - 27.5	46	23	CL
18-7	L18-C	S-7	56.0 - 58.0	60	36	CH
18-7	L18-C	S-11	87.0 - 89.0	41	17	CL
18-9	L18-K	S-10	80.0 - 82.3	30	11	CL
18-10	L18-H	S-1	6.0 - 8.5	81	50	CH
18-10	L18-H	S-4	35.0 - 37.5	78	51	CH
18-10	L18-H	S-6	55.0 - 57.5	71	49	CH
18-12	L18-B	S-1	6.0 - 8.5	64	36	CH
18-12	L18-G	S-7	50.0 - 51.8	78	49	CH
18-12	L18-G	S-9	65.0 - 67.0	60	36	CH
18-12	TP-31	B-1	3.5	70	49	CH
18-8	L18-F	S-1	6.0 - 8.5	78	55	CH
18-8	L18-F	S-3	26.0 - 28.5	69	57	CH
18-8	L18-F	S-6	56.0 - 58.5	59	39	CH
18-8	L18-I	S-2	16.0 - 18.5	58	36	CH
18-8	L18-J	S-1	5.0 - 7.5	55	30	CH
18-8	L18-J	S-3	15.0 - 17.5	67	41	CH
18-8	L18-J	S-5	25.0 - 27.5	79	50	CH
18-8	L18-J	S-7	35.0 - 37.5	64	40	CH
18-8	L18-J	S-9	45.0 - 47.5	74	49	CH
18-8	L18-J	S-11	55.0 - 57.5	69	46	CH
18-8	L18-J	S-13	65.0 - 67.5	74	50	CH
18-8	L18-J	S-15	75.0 - 77.5	33	17	CL
18-8	L18-J	S-17	85.0 - 87.5	56	38	CH
18-8	L18-J	S-22	110.0 - 112.5	71	47	CH
18-8	L18-J	S-24	120.0 - 122.5	70	42	CH
18-8	L18-J	S-26	130.0 - 132.8	88	60	CH
18-8	L18-J	S-28	140.0 - 142.5	85	53	CH
18-8	L18-J	S-30	150.0 - 152.5	88	62	CH
18-8	L18-J	S-32	160.0 - 162.5	55	30	CH

89-977 (8/12/90)

**TABLE 3.8**  
**PERCENT PASSING NO. 200 SIEVE**

STRATIGRAPHIC UNIT	MATERIAL TYPE	BORING/ TEST PIT NO.	SAMPLE NO.	DEPTH (ft.)	PERCENT PASSING NO. 200 SIEVE
Colluvium	Soil	TP-2	B-1	10	57
Colluvium	Soil	TP-8	B-1	7	81
Colluvium	Soil	TP-11	B-1	7	39
Colluvium	Soil	TP-13	B-1	4	48
Colluvium	Soil	TP-18	B-1	2	58
Colluvium	Soil	TP-23	B-1	0-4	33
Colluvium	Soil	TP-25	B-1	0-7	57
Colluvium	Soil	TP-26	B-1	0-10.5	52
Colluvium	Soil	TP-27	B-1	0-12	69
18-3	ss/slt	L18-D	S-10	81-83.5	24
18-3	ss	L18-E	S-2	15-17.5	24
18-9	ss	L18-K	S-1	5-7.5	11
18-9	ss/slt	L18-K	S-4	20-22.5	26
18-9	ss/slt	L18-K	S-8	40-42.5	21
18-9	ss	L18-K	S-13	65-67.5	19
18-10	slt/cs	L18-A	S-3	17-19.5	55
18-10	ss/slt	L18-A	S-4	25-27.5	73
18-10	cs/ss	L18-A	S-6	37-38.7	47
18-10	ss	L-18H	S-2	15-17.5	37
18-13	ss	L18-G	S-1	6-8.5	11
18-13	ss	L18-G	S-5	40-41.3	11

89-977 (8/12/90)

TABLE 3.9

**COMPACTION TEST RESULTS  
(MODIFIED PROCTOR, ASTM D1557-78)**

BORING NO./ TEST PIT NO.	COMPOSITE SAMPLE NO.	MATERIAL TYPE	SAMPLE PREPARATION	OPTIMUM MOISTURE CONTENT (%)	MAXIMUM DRY DENSITY (PCF)
<b>1. Modified Proctor Test (ASTM D1557-78)</b>					
L18-J	No. 1	Claystone	S-1, S-2, S-3, S-5, and S-6	22.8	98.7
L18-J	No. 2	Claystone	S-9, S-10, S-11, S-12, S-14, and S-15	21.7	100.7
L18-J	No. 3	Claystone	S-22, S-24, S-26, S-28, and S-30	24.9	96.2
L18-J/L18-K	No. 4	30% Sandstone/ 70% Claystone	S-1 through S-5, Boring L18-14 plus claystone from Boring L18-J	20.8	104.9
L18-J/L18-K	No. 5	50% Sandstone/ 50% Claystone	S-1 through S-5, Boring L18-K plus claystone from Boring L18-J	19.6	106.6
L18-J/L18-K	No. 6	30% Sandstone/ 70% Claystone	S-6 through S-10, Boring L18-K plus claystone from Boring L18-J	21.9	102.9
L18-J/L18-K	No. 7	50% Sandstone/ 50% Claystone	S-6 through S-10, Boring L18-K plus claystone from Boring L18-J	20.4	103.7
L18-J/L18-K	No. 8	30% Sandstone/ 70% Claystone	S-11 through S-15, Boring L18-K plus claystone from Boring L18-J	19.8	104.0
L18-J/L18-K	No. 9	50% Sandstone/ 50% Claystone	S-11 through S-15, Boring L18-K plus claystone from Boring L18-J	19.4	104.8
TP-11, TP-25, TP-26	No. 10	Colluvium (Silty Clay)	Mixture from all test pits	12.3	123.3
TP-42, B-1	---	Sandstone	---	15.0	114.8
DT-A, B-2	---	Claystone	---	21.5	104.2
DT-C, B-1	---	Claystone	---	23.5	99.0
<b>2. Standard Proctor, ASTM D698</b>					
TP-36, TP-37, TP-38	No. 11	Claystone	Mixture from all test pits	29.7*	87.7*
L18-J/L18-K	No. 4	30% Sandstone/ 70% Claystone	S-1 through S-5, Boring L18-K plus claystone from Boring L18-J	27.0*	94.2*

89-977 (8/12/90)

TABLE 3.10

SUMMARY OF PERMEABILITY TESTS

TEST PIT/BORING NO.	COMPOSITE SAMPLE NO.	MATERIAL TYPE	STRATIGRAPHIC UNIT	OPTIMUM MOISTURE CONTENT (%)	MAXIMUM DRY DENSITY (PCF)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USCS	PERMEABILITY TEST										
									MOLD SIZE (INCHES)	MAXIMUM PARTICLE SIZE (INCHES)	INITIAL WATER CONTENT (%)	INITIAL DRY DENSITY (PCF)	INITIAL RELATIVE COMPACTION (%)	FINAL WATER CONTENT (%)	FINAL DRY DENSITY	FINAL RELATIVE COMPACTION	CONFINING PRESSURE (psi)	GRADIENT	K (cm/sec)
L18-J	2	Claystone	18-8	21.7	100.7	63	40	CH	2.5	3/8	22.4	91.6	91	33.6	90.1	89	40	41.2	$2.0 \times 10^{-8}$
DT-A, B-2	--	Claystone	18-8	21.5	104.2	82	54	CH	2.5	3/8	24.0	93.3	90	29.5	96.4	93	40	82.4	$1.9 \times 10^{-9}$
TP-36, TP-37, TP-38	11	Claystone	18-8	23.5	99.0	76	45	CH	4	1/4	28.7	89.4	90	33.2	90.4	91	40	82.4	$4.1 \times 10^{-9}$
TP-36, TP-37, TP-38	11	Claystone	18-8	23.5	99.0	76	45	CH	4	1/4	28.6	89.5	90	33.7	89.7	91	40	82.4	$5.0 \times 10^{-9}$
L18-J, S-21	--	Claystone	18-8	24.9	99.0	76	45	CH	4	(1)	31.2	89.3	90	34.4	88.5	89	40	82.4	$2.1 \times 10^{-8}$

(1) Weathered by repeated wetting and drying for two weeks. Maximum particle size resulted from the weathering process only.



TABLE 3.11

SUMMARY OF SWELL TEST RESULTS  
(UNDISTURBED SAMPLES)

BORING NO.	SAMPLE NO.	SAMPLE DEPTH (ft.)	STRATI-GRAPHIC UNIT	MATERIAL TYPE	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	NATURAL		APPLIED PRESSURE (PSF)	SWELL (1) (%)
							WATER CONTENT (%)	DRY DENSITY (PCF)		
18-J 18-J	S-1 S-1	5.0 - 7.5 5.0 - 7.5	18-8 18-8	Claystone Claystone	55 55	30 30	23.4 20.6	87.7 89.6	600 12,000	4.0 -1.0
18-J 18-J	S-7 S-7	35.0 - 37.5 35.0 - 37.5	18-8 18-8	Claystone Claystone	64 64	24 24	25.0 26.5	96.0 93.9	600 12,000	1.8 0.7
18-J 18-J	S-24 S-24	120.0 - 122.5 120.0 - 122.5	18-8 18-8	Claystone Claystone	70 70	42 42	29.4 29.7	93.2 94.0	600 12,000	1.6 0.7
18-J 18-J	S-32 S-32	160.0 - 162.5 160.0 - 162.5	18-8 18-8	Claystone Claystone	55 55	30 30	21.2 20.6	96.7 97.6	600 12,000	0.4 -0.4

89-977 (8/12/90)

(1) As a percent of the sample height after application of the pressure.

TABLE 3.12

SUMMARY OF SWELL TEST RESULTS  
(REMOLDED SAMPLES)

BORING/ TEST PIT NO.	COMPOSITE SAMPLE NO.	MATERIAL TYPE	STRATI- GRAPHIC UNIT	SAMPLE PREPARATION	OPTIMUM MOISTURE CONTENT (%)	MAXIMUM DRY DENSITY (PCF)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	U S S	INITIAL WATER CONTENT (%)	INITIAL DRY DENSITY (PCF)	INITIAL RELATIVE COMPACTION (%)	APPLIED PRESSURE (PSF)	SWELL <sup>(1)</sup> %
DT-A, B-2	--	Claystone	18-8	--	21.5	104.2	82	54	CI1	24.3	93.1	89	0	22.0
	--	Claystone	18-8	--	21.5	104.2	82	54	CI1	24.1	93.1	89	1,200	7.1
	--	Claystone	18-8	--	21.5	104.2	82	54	CI1	27.3	93.1	89	6,000	1.0
DT-C, B-1	--	Claystone	18-8	--	23.5	99.0	76	45	CH	26.0	88.7	90	0	12.9
	--	Claystone	18-8	--	23.5	99.0	76	45	CH	25.6	88.8	90	1,200	3.7
	--	Claystone	18-8	--	23.5	99.0	76	45	CH	28.1	89.4	90	5,000	1.0
L18-J/L18-K	4	30% Sandstone/ 70% Claystone	18-9/18-8	S-1 through S-5, Boring L18-K plus claystone from Boring L18-J.	20.8	104.9	--	--	CL	23.3	94.1	90	0	9.7
	4	30% Sandstone/ 70% Claystone	18-9/18-8	S-1 through S-5, Boring L18-K plus claystone from Boring L18-J.	20.8	104.9	--	--	CL	23.0	94.2	90	1,200	2.7
L18-J/L18-K	6	30% Sandstone/ 70% Claystone	18-9/18-8	S-6 through S-10 Boring L18-K plus claystone from Boring L18-J.	21.9	102.9	--	--	CL	24.3	92.3	90	0	11.8
	6	30% Sandstone/ 70% Claystone	18-9/18-8	S-6 through S-10 Boring L18-K plus claystone from Boring L18-J.	21.9	102.9	--	--	CL	24.2	92.3	90	1,200	3.2
L18-J/L18-K	8	30% Sandstone/ 70% Claystone	18-9/18-8	S-11 through S-15 Boring L18-K plus claystone from Boring L18-J.	19.8	104.0	--	--	CL	22.1	93.4	90	0	13.4
	8	30% Sandstone/ 70% Claystone	18-9/18-8	S-11 through S-15 Boring L18-K plus claystone from Boring L18-J.	19.8	104.0	--	--	CL	21.5	93.8	90	1,200	3.9
TP-11, TP-25, TP-26	10	Colluvium (silty clay)	--	Mixture from all test pits.	12.3	123.3	--	--	CL	14.9	110.3	89	0	4.5
	10	Colluvium (silty clay)	--	Mixture from all test pits.	12.3	123.3	--	--	CL	15.0	110.3	89	1,200	0.2

(1) As a percent of the sample height after application of pressure.

TABLE 3.13

GEOTECHNICAL LABORATORY TEST RESULTS ON PECTEN CLAYSTONE

Source: Geosyntec (2008)

Boring ID	Sample ID	Depth (ft)		USCS	As-Received Conditions		Sieve		Atterberg Limits		Laboratory Compaction			Hydraulic Conductivity (cm/s)	Test Conditions (MC, RC)
		From	To		Moisture Content (D2216) (%)	Dry Density (pcf)	Fines (%)	LL (%)	PL (%)	PI (%)	Maximum Dry Density (pcf)	Optimum Moisture (%)			
CS-1	1-2	10.5	12	CH - Fat Clay	16.0		92.2	100	35	65				7.0E-08	+2, 90%*
CS-1	1-3	15	16.5												
CS-1	1-4	20	21.5	CH - Fat Clay	18.5	100.6	96.0	88	32	56					
CA-1A	Bulk 1A-1	0	5	CH - Fat Clay with Sand	12.4		76.0	55	21	34	122	12.5		7.4E-09, 9.2E-09	+3, 92%, +3, 89%
CA-1A	1A-2	10.5	12		19.3	100.3									
CA-1A	1A-3	16	16.5	MH - Elastic Silt	20.3		98.1	97	44	53					
CA-1A	1A-5	25	26.5	CH - Fat Clay	20.9	98.6	93.3	105	41	64				6.2E-08	+2, 90%*
CA-1A	1A-6	30	31.5	MH - Elastic	23.1										
CA-1A	1A-7	35	36.5	Silt			89.6	89	39	50				9.6E-08	+2, 90%*
CA-1A	1A-8	40	41.5	CH - Fat Clay	21.2		89.5	78	31	47					
CA-1A	1A-9	45	46.5	CH - Fat Clay	24.4	98.2	87.7	82	35	47					
CA-1A	1A-11	55	56.5	CH - Fat Clay with Sand	18.6	95.8	84.2	58	29	29					
CA-1A	1A-13	65	66	SC - Clayey Sand	3.4		17.4								
CS-2	Bulk 2-1	0	5												
CS-2	Bulk 2-2	6.5	10.5	CH - Fat Clay	14.1		96.3	104	36	68	113.1	15.6		3.7E-09	+3, 92%
CS-2	2-2	10.5	12	CH - Fat Clay	16.5	106.4	95.2	100	34	66					
CS-2	2-4	20	21.5	CH - Fat Clay	21.0		95.3	92	39	53				8.6E-08	+2, 90%*
CS-2	2-7	35	36.5	CH - Fat Clay	21.0	100.6	89.8	93	33	60					
CS-2	2-9	45	46.5	CH - Fat Clay	24.7	99.7	98.6	104	37	67					
CS-2	2-11	55	56.5	CH - Fat Clay	24.0		96.7	82	33	49				8.2E-08	+2, 90%*
CS-2	2-13	65	66												
CS-2	2-14	70	71.5	CH - Fat Clay	25.1	97.7	98.4	112	40	72				1.7E-08	+2, 90%*
CS-2	2-16	80	81.5	CH - Fat Clay	25.4		91.1	129	41	88				5.3E-08	+2, 90%*
CS-2	2-17	85	86.5												
TP-1	TP1-1	9	10	CH - Fat Clay	20.8		93.0	100	37	63	109.9	17.8		1.1E-08	+3, 92%
TP-2	TP2-1	0	8	CH - Fat Clay	14.6		97.8	92	31	61	111.7	16.2		5.0E-09	+3, 92%
TP-3	TP3-1	11	12	CH - Fat Clay	21.9		91.1	102	35	67	108.2	17.4		6.5E-09	+3, 92%
TP-4	TP4-1	9	10	CH - Fat Clay	17.0		88.5	93	34	59	105.5	20.1		1.4E-08	+3, 92%

Note: \*Samples collected with a California type sampler tested for hydraulic conductivity were compacted at 90% relative compaction of the maximum dry density of similar materials from the test pad construction of Landfill B-18 Phases 1A/1B (Environmental Construction Services, 1991).

**TABLE 5.1**  
**MATERIAL AND INTERFACE PROPERTIES USED FOR STABILITY CALCULATIONS**

Material or Interface	Material/Interface Properties			Source/Remarks
	Total Unit Weight (pcf)	Cohesion Intercept, c (psf)	Friction Angle, $\phi$ (degrees)	
<b>Used by ESI (1990a) for the analysis of temporary rock cut slopes, compacted fill slopes, and temporary Phase I intermediate fill slopes:</b>				
Hazardous Waste and Operations Layer (Shallow Sliding)	115	300	27	conservative parameters due to lack of site-specific testing
Hazardous Waste and Operations Layer (Deep Sliding)	115	0	31	Golder (1989a), conservative
Bedrock (Cross Bedding Strength)	130	800	40	Donohue & Associates (1988) and direct shear test results in Appendix D.8
Bedrock (Along Bedding Strength)	130	0	36	Donohue & Associates (1988) and UU triaxial test results in Appendix D.5
Structural Fill	125	2,000	30	UU triaxial test results on compacted sandstone in Appendix D.5
Clay Liner and Clay Liner/Textured HDPE Geomembrane Interface (Long Term)	125	1,150	20	CU triaxial test results on compacted claystone in Appendix D.7
Clay Liner and Clay Liner/Textured HDPE Geomembrane Interface (Short Term or Low Confining Stress)	125	3,600	0	UU triaxial test results on compacted claystone in Appendix D.6
Textured HDPE Geomembrane/Geonet Interface	-	0	15	Gundie (1987a) and Geosyntec (1988)
Geonet/Geotextile (Heat Bonded) Interface	-	0	>30	Fluid Systems, Inc. (Appendix F)
Geotextile/Drainage Gravel Interface	-	0	>21	expected to be stronger than the geotextile/clay liner interface
Geotextile/Clay Liner Interface	-	0	21	Golder (1990b)
Textured HDPE Geomembrane/Geocomposite Interface	-	0	24	Golder (1990b)
Geocomposite/Drainage Gravel Interface	-	0	>21	expected to be stronger than the geotextile/clay liner interface
Geotextile/Operations Layer Interface (Shallow Sliding)	-	300	27	the strength of the operations layer controls
Geotextile/Operations Layer Interface (Deep Sliding)	-	0	31	the strength of the operations layer controls
<b>Used by HAI (Appendix H.4) for the analysis of the temporary Phase IIIA intermediate fill slope:</b>				
Hazardous Waste	115	0	31	ESI (1990a), Rust E&I (1998), URS (2005)
Bedrock	150	800	40	ESI (1990a), Rust E&I (1998), URS (2005)
Phase IIIA Liner Interface	-	0	22	HAI (Appendix H.4)

**TABLE 5.1 (continued)**  
**MATERIAL AND INTERFACE PROPERTIES USED FOR STABILITY CALCULATIONS**

Material or Interface	Material/Interface Properties			Source/Remarks
	Total Unit Weight (pcf)	Cohesion Intercept, c (psf)	Friction Angle, $\phi$ (degrees)	
<b>Used by HAI (Appendix H.5) for the analysis of the final closure configuration:</b>				
Hazardous Waste	115	0	31	ESI (1990a), Rust E&I (1998), URS (2005)
Clay Liner	115	1,150	20	ESI (1990a), Rust E&I (1998), URS (2005)
Bedrock	150	800	40	ESI (1990a), Rust E&I (1998), URS (2005)
Phase I Bottom Liner Interface	-	0	17	ESI (1990a), Rust E&I (1998), URS (2005)
Phase I Sideslope Liner Interface	-	800	9	ESI (1990a), Rust E&I (1998), URS (2005)
Phase II Bottom Liner Interface	-	0	19	ESI (1990a), Rust E&I (1998), URS (2005)
Phase II Sideslope Liner Interface	-	0	19	ESI (1990a), Rust E&I (1998), URS (2005)
Phase III Liner Interface	-	0	12	HAI (Appendix H.5)
Vegetative Cover Soil/Geotextile Interface	110	100	21	HAI (Appendix H.5)
Geotextile/40-mil Textured HDPE Geomembrane Interface	110	0	25	HAI (Appendix H.5), conservative based on site-specific direct shear laboratory testing
40-mil Textured HDPE Geomembrane/Foundation Layer Interface	110	0	28	HAI (Appendix H.5)
Foundation Layer/Hazardous Waste Interface	110	0	31	HAI (Appendix H.5)

**TABLE 5.2**  
**SUMMARY OF SLOPE STABILITY ANALYSES**

Case <sup>1</sup>	Static Factor of Safety <sup>2</sup>	Seismic Stability	
		Allowable Design Displacement for the MCE (inches)	Estimated Displacement for the MCE (inches)
<b>Temporary Rock Cut Slopes (see Figure 5.1 and Appendix H.2):</b>			
2H:1V Slopes Across Bedding Planes	2.4	1	0
3H:1V Slopes Subparallel to Bedding Planes	2.2	1	<0.1
<b>Compacted Fill Slopes (see Appendix H.3):</b>			
Northeast Containment Basin Embankment	2.2	3	0
<b>Temporary Phase I Intermediate Fill Slopes (see Figure 5.2 and Appendix H.4):</b>			
Wedge Sliding Along Landfill Base and Phase I/II Berm Slope	2.5	6	<0.1
Circular Sliding Entirely Through Waste	1.5	12	0.5
<b>Temporary Phase IIIA Intermediate Fill Slope (see Figure 5.3 and Appendix H.4):</b>			
Wedge Sliding Along Phase IIIA Liner System	1.5	N/A	N/A
<b>Final Closure Configuration (see Figure 5.3 and Appendix H.5):</b>			
3.5H:1V Cover Slopes Between Benches (i.e., Veneer Stability)	1.6	12	2.7
Wedge Sliding Along Base and Sideslope of Landfill	2.3	6	<1
Circular Sliding Entirely Through Waste	2.2	12	<12

Notes:

1. Several scenarios were analyzed for most of the cases but only the critical values (i.e., lowest factors of safety and highest seismic displacements) for each case are shown. See Appendix H for complete results.
2. The minimum acceptable static factor of safety is considered to be 1.5.
3. N/A = not analyzed.

**TABLE 5.3**  
**PERIMETER RUN-ON DIVERSION DITCH FLOW**  
**AND CAPACITY SUMMARY**

DITCH LOCATION	ASPHALT V-DITCH DIMENSIONS		MINIMUM DITCH SLOPE (%)	PMP FLOW ESTIMATE (cfs)	DITCH CAPACITY (cfs)
	WIDTH (feet)	DEPTH (minimum)			
<u>Phase I Area</u> (see Sheet 5 in Appendix A.1) Brow Ditches North Portion of West Perimeter Road South Portion of West Perimeter Road South Perimeter Road to South Borrow Pit Road West Portion of North Perimeter Road East Portion of North Perimeter Road	2	1	5.6	8.5	13.5
	5	1	0.6	10.4	13.3
	5	3	0.6	61.5	64.6
	5	2	8.3	121.5	139.6
	5	1.25	1.0	24.0	24.3
	5	1.0	8.0	26.4	48.5
<u>Phase II Area</u> (see Sheet 10 in Appendix A.1) North Portion of South Perimeter Road	5	2.5	3.6	121.5	124.8

89-977 (8/14/90)

**TABLE 5.4**

**ACTIVE ROAD RUN-OFF CONTROL SUMMARY**

STRUCTURE	STRUCTURE DESCRIPTION	MINIMUM SLOPE (%)	ESTIMATED FLOW (cfs)		FLOW CAPACITY (cfs)
			25-YEAR STORM	PMP	
<b>I. Phase I</b> (see Sheet 5 in Appendix A.1) Inside Perimeter Road V-ditch  Concrete-enclosed CMP pipe along West Perimeter Road at access ramp.  CMP culvert down south landfill slope to the Phase I/II Berm.  Concrete-encased CMP pipe at Phase I/II Berm Access Road.  Top of Phase I/II Berm V-Ditch.  CMP culvert beneath Phase I/II Berm crest toward the clay pit retention basin.  Corrugated pipe at top of Phase I/II Berm to convey run-off into the clay pit containment basin.  Corrugated pipe to convey run-off from North Bench Road into the clay pit.	5-feet wide x 1.25-feet deep	0.6	N/A	14.4	18.8
	12-inch diameter	0.6	2	N/A	4.7
	18-inch diameter	50	N/A	14.4	15.1
	18-inch diameter	0.5	3.9	N/A	4.8
	5-feet wide x 1.25-foot deep	0.5	N/A	14.4	17.2
	30-inch diameter	0.5	N/A	15.6	33.8
	30-inch diameter	50	N/A	15.6	33.8
	18-inch diameter	50	N/A	7.8	8.5
<b>II. Phase II</b> (see Sheet 10 in Appendix A.1) CMP culverts to convey run-off from Bench Road to northeast containment basin at the following locations:  - End of South Bench Road  - End of North Bench Road	30-inch diameter	0.5	N/A	21.0	33.9
	24-inch diameter	0.5	N/A	11.2	21.3

N/A = Not Applicable

89-977 (8/14/90)



**TABLE 5.5  
CONTAINMENT BASIN CAPACITY SUMMARY**

Basin	Estimated 24-hour PMP Run-off Volume (acre-feet)	Basin Capacity (acre-feet)
<b>Temporary Basins:</b>		
Phase I Containment Basin (see Sheet 6 in Appendix A.1)	8	33
Phase I Intermediate Closure Basin (see Sheet 6 in Appendix A.1)	5	5
<b>Permanent Basins:</b>		
Northeast Containment Basin (see Sheet C-3 in Appendix A.2)	34*	33
South Containment Basin (see Sheet C-3 in Appendix A.2)	32	48


\*will require pumping to South Containment Basin to maintain full containment of run-off

**TABLE 5.6**

**FINAL CLOSURE RUN-OFF CONTROL SUMMARY**

Structure	Dimensions		Minimum Slope (%)	Estimated Peak PMP Flow (cfs)	Maximum Flow Depth (feet)
	Bottom Width (feet)	Depth (feet)			
Final Drainage Benches (see Detail 2 on Sheet C-10 in Appendix A.2): trapezoidal, earthen	12	2	2	51	0.8
Cover Access Road (see Detail 5 on Sheet C-10 in Appendix A.2): Asphalt-Lined V-Ditch + Earthen Road	43.5	2 to 3.5	8	104	1.6
New B-18 Perimeter Road (see Detail 4 on Sheet C-7 in Appendix A.2): Asphalt-Lined Trapezoidal Ditch + Earthen Road + Earthen V-Ditch/2-Foot-Tall Earthen Berm)	37	2 to 3.5	1.4	270	2.9

**FIGURES**



Source: USGS La Cima (1978), Las Viejos (1981), Kettleman City (1981) and Kettleman Plain (1994) 1:24,000 Scale Topographic Maps.



Property Boundary  
Kettleman Hills Facility

Existing  
Landfill Unit  
B-18

**FIGURE 1.1**  
**SITE VICINITY MAP**  
WM/LANDFILL UNIT B-18 KETTLEMAN HILLS FACILITY/CA

89-977DR REV. 08/14/90






FIGURE 2.1  
LANDFILL B-18  
PRE-DEVELOPMENT  
TOPOGRAPHY  
LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY  
ENVIRONMENTAL SOLUTIONS, INC.



Source: Woodring Et. Al. (1940)  
 0 0.5  
 Scale in Miles





FIGURE 2.2  
 AREA GEOLOGIC MAP  
 WM/LANDFILL UNIT B-18 KETTLEMAN HILLS FACILITY/CA



FIGURE 2.3  
 SITE GEOLOGIC MAP  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.

REFERENCE: THIS GEOLOGIC MAP IS BASED ON FIELD WORK DONE BY TAYLOR, DUNN AND NEWMAN, GEOLGIC ASSOCIATES AND NUGENT, FOSTER ASSOCIATES.



**TABLE 1**

POINT	DEPTH (FEET)	DATE
TP-1	10.00	1/15/80
TP-2	10.00	1/15/80
TP-3	10.00	1/15/80
TP-4	10.00	1/15/80
TP-5	10.00	1/15/80
TP-6	10.00	1/15/80
TP-7	10.00	1/15/80
TP-8	10.00	1/15/80
TP-9	10.00	1/15/80
TP-10	10.00	1/15/80
TP-11	10.00	1/15/80
TP-12	10.00	1/15/80
TP-13	10.00	1/15/80
TP-14	10.00	1/15/80
TP-15	10.00	1/15/80
TP-16	10.00	1/15/80
TP-17	10.00	1/15/80
TP-18	10.00	1/15/80
TP-19	10.00	1/15/80
TP-20	10.00	1/15/80
TP-21	10.00	1/15/80
TP-22	10.00	1/15/80
TP-23	10.00	1/15/80
TP-24	10.00	1/15/80
TP-25	10.00	1/15/80
TP-26	10.00	1/15/80
TP-27	10.00	1/15/80
TP-28	10.00	1/15/80
TP-29	10.00	1/15/80
TP-30	10.00	1/15/80
TP-31	10.00	1/15/80
TP-32	10.00	1/15/80
K-1	10.00	1/15/80
K-2	10.00	1/15/80
K-3	10.00	1/15/80
K-4	10.00	1/15/80
K-5	10.00	1/15/80
K-6	10.00	1/15/80
K-7	10.00	1/15/80
K-8	10.00	1/15/80
K-9	10.00	1/15/80
K-10	10.00	1/15/80
K-11	10.00	1/15/80
K-12	10.00	1/15/80
K-13	10.00	1/15/80
K-14	10.00	1/15/80
K-15	10.00	1/15/80
K-16	10.00	1/15/80
K-17	10.00	1/15/80
K-18	10.00	1/15/80
K-19	10.00	1/15/80
K-20	10.00	1/15/80
K-21	10.00	1/15/80
K-22	10.00	1/15/80

**TABLE 2**

STRATIGRAPHIC UNIT	DESCRIPTION
10-1	CLAY BORROW STRATUM
10-2	CLAY BORROW STRATUM
10-3	CLAY BORROW STRATUM
10-4	CLAY BORROW STRATUM
10-5	CLAY BORROW STRATUM
10-6	CLAY BORROW STRATUM
10-7	CLAY BORROW STRATUM
10-8	CLAY BORROW STRATUM
10-9	CLAY BORROW STRATUM
10-10	CLAY BORROW STRATUM
10-11	CLAY BORROW STRATUM
10-12	CLAY BORROW STRATUM
10-13	CLAY BORROW STRATUM
10-14	CLAY BORROW STRATUM
10-15	CLAY BORROW STRATUM
10-16	CLAY BORROW STRATUM
10-17	CLAY BORROW STRATUM
10-18	CLAY BORROW STRATUM
10-19	CLAY BORROW STRATUM
10-20	CLAY BORROW STRATUM
10-21	CLAY BORROW STRATUM
10-22	CLAY BORROW STRATUM
10-23	CLAY BORROW STRATUM
10-24	CLAY BORROW STRATUM
10-25	CLAY BORROW STRATUM
10-26	CLAY BORROW STRATUM
10-27	CLAY BORROW STRATUM
10-28	CLAY BORROW STRATUM
10-29	CLAY BORROW STRATUM
10-30	CLAY BORROW STRATUM
10-31	CLAY BORROW STRATUM
10-32	CLAY BORROW STRATUM






NOTE: SEE THE SOIL LITHOLOGICAL UNIT SHEETS (ATTACHED)

- LEGEND**
- K-1 EXISTING EXPLORATION WELL
  - L1B-A BOREHOLES DRILLED FOR B-18 INVESTIGATION
  - DT-1 SOIL TEST
  - TP-1 TEST PIT
  - TP-2 HORIZONTAL TEST PIT
  - TP-3 COMPLETION TRENCH
  - APPROXIMATE STRATIGRAPHIC CONTACT
  - - - FACILITY BOUNDARY
  - - - LANDFILL BOUNDARY
  - - - PROPERTY BOUNDARY
  - 2'00" THICKNESS OF COLLATION (WHERE AVAILABLE) AND DATE, COLLATION THICKNESS IN TEST PIT: 1
  - 50' STRIKE AND DIP OF BEDDING
  - 75' STRIKE AND DIP OF JOINT
  - VERTICAL JOINT
  - CLAY BORROW STRATUM




**FIGURE 3.1**  
**SITE GEOLOGIC AND EXPLORATION MAP**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.






**FIGURE 3.2**  
**GEOLOGIC CROSS SECTIONS**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.



SYMBOL	STRATIGRAPHIC UNIT	BORING NO.	SAMPLE NO.	DEPTH (FT.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USC SYMBOL
○	18-8	L18-J	S-1	5.0 - 7.5	55	30	CH
◊	18-8	L18-J	S-3	15.0 - 17.5	67	41	CH
△	18-8	L18-J	S-5	25.0 - 27.5	79	50	CH
□	18-8	L18-J	S-7	35.0 - 37.5	64	40	CH
●	18-8	L18-J	S-9	45.0 - 47.5	74	49	CH
◆	18-8	L18-J	S-11	55.0 - 57.5	69	46	CH
▲	18-8	L18-J	S-13	65.0 - 67.5	74	50	CH
■	18-8	L18-J	S-15	75.0 - 77.5	33	17	CL
⊙	18-8	L18-J	S-17	85.0 - 87.5	56	38	CH
⊕	18-8	L18-J	S-22	110.0-112.5	71	47	CH
⊗	18-8	L18-J	S-24	120.0-122.5	70	42	CH
⊠	18-8	L18-J	S-26	130.0-132.8	88	60	CH
⊕	18-8	L18-J	S-28	140.0-142.5	85	53	CH
⊕	18-8	L18-J	S-30	150.0-152.5	88	62	CH
⊠	18-8	L18-J	S-32	160.0-162.5	55	30	CH

**FIGURE 3.3**  
**PLASTICITY CHART**  
**STRATIGRAPHIC UNIT 18-8**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**



COBBLES	GRAVEL		SAND			SILT AND CLAY FRACTION
	coarse	fine	coarse	medium	fine	

**LEGEND**




-  CLAYSTONE
-  SANDSTONE

FIGURE 3.4

**GRAIN SIZE CURVE ENVELOPES**

LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY


**ENVIRONMENTAL SOLUTIONS, INC.**



**FIGURE 3.5**  
**MATERIAL WATER CONTENT**  
**VS.**  
**PLASTICITY INDEX**  
**STRATUM 18-8**  
**LANDFILL UNIT B-18**  
**KETTLEMAN HILLS FACILITY**

**LEGEND**  
 [ ] SHALLOW TEST PIT SAMPLE

**ENVIRONMENTAL SOLUTIONS, INC.**



**CURRENT INVESTIGATION (B-18, PHASES I & II)**

- ▲ L18-B, S-3 @20-22.5' (SANDSTONE)
- L18-C, S-7 @56-58' (CLAYSTONE)
- L18-D, S-2 @22-24.5' (CLAYSTONE)
- L18-F, S-6 @56-58.5' (CLAYSTONE)

**PREVIOUS INVESTIGATION (B-19, PHASES II & III)**

- CLAYSTONE - DIRECT SHEAR
- ◻ SILTSTONE - DIRECT SHEAR
- ▲ SANDSTONE - DIRECT SHEAR

**FIGURE 3.6**  
**SUMMARY**  
**"DIRECT SHEAR TEST RESULTS"**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.







FIGURE 5.1  
STABILITY CONSIDERATIONS  
FOR  
ROCK CUT SLOPES  
LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY  
ENVIRONMENTAL SOLUTIONS, INC.



SECTION A-A'



KEY PLAN


FIGURE 5.2

STABILITY CONSIDERATIONS  
FOR PHASE I  
INTERMEDIATE FILL SLOPE


LANDFILL UNIT B-18

KETTLEMAN HILLS FACILITY

ENVIRONMENTAL SOLUTIONS, INC.




A. PHASE IIIA INTERMEDIATE FILL SLOPE



B. FINAL CLOSURE





PHASE I  
LANDFILL  
UNIT B-18

PHASE II  
LANDFILL  
UNIT B-18

LEGEND

— SURFACE WATER DRAINAGE AREA BOUNDARY

INCLUDING AREA  
FROM SOUTH STOCKPILE



FIGURE 5.4


**SURFACE WATER DRAINAGE  
AREA MAP FOR PHASES I AND II**

LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY

ENVIRONMENTAL SOLUTIONS INC.

PROJECT No.	063-91887
FILE No.	06391887ADD1
REV. A SCALE	1"=300'
DESIGN	PM 10/31/08
CADD	PM 10/31/08
CHECK	RH 11/4/08
REVIEW	SGS 11/4/08

**FIGURE 5.5**



**LEGEND**



SURFACE WATER DRAINAGE AREA  
BOUNDARY AND DESIGNATION

**APPENDIX A  
CONSTRUCTION DRAWINGS**

**APPENDIX A.1**

**PHASES I AND II DRAWINGS**

**APPENDIX A.2**

**PHASE III AND FINAL CLOSURE DRAWINGS**

**APPENDIX A.1**  
**PHASES I AND II DRAWINGS**

**CONSTRUCTION DRAWINGS  
LANDFILL UNIT B-18  
PHASES I AND II  
AND  
FINAL CLOSURE**

**KETTLEMAN HILLS FACILITY  
KINGS COUNTY, CALIFORNIA**

**PREPARED FOR:**

**CHEMICAL WASTE MANAGEMENT, INC. - (CWMI)**

**PREPARED BY:**


**ENVIRONMENTAL SOLUTIONS, INC.**

**JANUARY, 1991**




**REVISED ISSUE FOR  
PHASE II CONSTRUCTION**  
(JANUARY 29, 1993)

1090



REGIONAL LOCATION MAP  
 0 30 60 MILES  
 SCALE



SITE LOCATION MAP  
 0 600 1200 FEET  
 SCALE

LEGEND

GENERAL LINES

- KHF PROPERTY BOUNDARY
- MAIN TOPIC OF DRAWING
- - - SUBTOPIC OF DRAWING
- CENTER LINE
- HIDDEN LINE
- FLOW LINE
- EXISTING GRADE
- WORK DONE BY OTHERS
- 10 FOOT CONTOUR LINE
- 2 FOOT CONTOUR LINE
- STATION

MONITORING WELL TYPES

- K-1 EXISTING MONITORING WELLS TO BE MAINTAINED AND PROTECTED AS REQUIRED
- K-2 EXISTING MONITORING WELLS TO BE DECOMMISSIONED DURING PHASE I
- K-18 EXISTING MONITORING WELLS TO BE DECOMMISSIONED DURING PHASE II
- K-81 PROPOSED MONITORING WELLS

GEOSYNTHETIC LINER TYPES

- HOPE
- GDTEXTILE
- GEONET
- GEOCOMPOSITES

FILL PATTERNS

- GENERAL FILL
- STRUCTURAL FILL
- COMPACTED CLAY
- GRAVEL
- CONCRETE
- SAND
- WASTE
- NATURAL GRADE

ABBREVIATIONS

- A.C. ASPHALT CONCRETE
- ADMIN. ADMINISTRATION
- APPROX. APPROXIMATE
- C CUT
- CL CENTER LINE
- CMP CORRUGATED METAL PIPE
- CWMI CHEMICAL WASTE MANAGEMENT, INC.
- DIA. DIAMETER
- E. EASTING
- EL. ELEVATION
- F FILL
- FSU FINAL STABILIZATION UNIT
- HDPE HIGH DENSITY POLYETHYLENE
- HPFL HIGH POINT IN FLOW LINE
- KHF KETTLEMAN HILLS FACILITY
- L LENGTH
- LPFL LOW POINT IN FLOW LINE
- LT. LEFT
- MIN. MINIMUM
- N. NORTHING
- N.T.S. NOT TO SCALE
- P.C. POINT OF CURVATURE
- P.I. POINT OF INTERSECTION
- P.T. POINT OF TANGENCY
- R RADIUS
- RT. RIGHT
- T TANGENCY
- TYP. TYPICAL
- Δ INTERNAL ANGLE
- Ø DIAMETER

INDEX OF DRAWINGS

SHEET NO.	ESI FILE NO.	TITLE
1	D-89977-FD001	INDEX, LEGEND AND GENERAL NOTES
2A	D-89977-FD002	PHASE I EXCAVATION PROJECT PLAN
2	D-89977-FD002	PROJECT PLAN
3A	D-89977-FD003	PHASE I CONSTRUCTION SEQUENCE PLAN
3	D-89977-FD003	PHASE I EXCAVATION AND SITE PREPARATION PLAN
4	D-89977-FD004	PHASE I TOP OF SECONDARY LINER
5	D-89977-FD005	PHASE I TOP OF PRIMARY LINER
6	D-89977-FD006	PHASE I INTERMEDIATE WASTE FILL PLAN
7	D-89977-FD007	CLAY BORROW PIT EXPANSION PLAN
8	D-89977-FD008	PHASE II EXCAVATION AND SITE PREPARATION PLAN
9	D-89977-FD009	PHASE II TOP OF SECONDARY LINER
10	D-89977-FD010	PHASE II TOP OF PRIMARY LINER
11	D-89977-FD011	PHASE I AND II FINAL CLOSURE PLAN
12	D-89977-FD012	GRADING DETAILS
13	D-89977-FD013	GRADING DETAILS
14	D-89977-FD014	GRADING DETAILS
15	D-89977-FD015	CROSS SECTIONS
16	D-89977-FD016	LINER DETAILS AND SECTIONS
17	D-89977-FD017	LINER DETAILS AND SECTIONS
18	D-89977-FD018	TYPICAL SUMP PLAN
18A	D-89977-SU018	TYPICAL SUMP PLAN
18	D-89977-FD019	SUMP AND RISER DETAILS
20	D-89977-FD020	SUMP AND RISER DETAILS
21	D-89977-FD021	SUMP AND RISER DETAILS
22	D-89977-FD022	SUMP AND RISER DETAILS
23	D-89977-FD023	MISCELLANEOUS CROSS SECTIONS
24	D-89977-FD024	DRAINAGE DETAILS
25	D-89977-FD025	SURVEY CONTROL


GENERAL NOTES

- THESE DRAWINGS AND THE SPECIFICATIONS SHOULD BE USED TOGETHER. IF A DIFFERENCE OCCURS, THE CWMI PROJECT MANAGER SHALL DETERMINE WHICH TAKES PRECEDENCE.
- THE B-18 LANDFILL CONSTRUCTION WILL OCCUR WITHIN AREAS APPROVED BY VARIOUS GOVERNMENT AGENCIES. NO WORK SHALL OCCUR OUTSIDE OF THE CONSTRUCTION AREAS SHOWN ON THE DRAWINGS WITHOUT SPECIFIC APPROVAL OF THE CWMI PROJECT MANAGER.
- PRIOR TO COMMENCING ANY CUT OR FILL, OR IN ANY WAY DISTURBING THE EXISTING LAND CONTOURS, CONTRACTOR SHALL VERIFY THE ACCURACY OF THE CONTOUR ELEVATIONS SHOWN IN THE DRAWINGS.

MISCELLANEOUS

- CONTROL POINT
- FENCE
- SLOPE
- POINT OF INTERSECTION
- CURVE IDENTIFICATION
- CONTROL POINT

KEY





NO.	DATE	DESCRIPTION	BY	CHK'D BY
3	7/28/91	ISSUED FOR PHASE II CONSTRUCTION	K.R.	W.P.
2	1/02/91	ISSUED FOR CONSTRUCTION	K.R.	W.P.
1	8/24/90	ISSUED FOR BID	W.D.	W.P.
0	7/11/90	ISSUED FOR PERMITTING	K.A.B.	W.P.

PREPARED BY: K.J. Koval  
 CHECKED BY: R. P. ...  
 APPROVED BY: R.P.E.  
 REGISTERED PROFESSIONAL ENGINEER  
 No. 41021  
 Exp. 5-31-95  
 CIVIL  
 STATE OF CALIFORNIA

CONSTRUCTION DRAWINGS  
 LANDFILL UNIT B-18  
 CWMI-KETTLEMAN HILLS FACILITY  
 KINGS COUNTY CALIFORNIA

INDEX, LEGEND AND GENERAL NOTES  
 ENVIRONMENTAL SOLUTIONS, INC.

SHEET NO.	TOTAL SHEETS	SECTION
89-977-0-89977-FD001	25	3
AS NOTED	89-03-304.2.1	1



KEY PLAN

MONITORING WELL LOCATIONS

WELL	SYMBOL	NORTHING	EASTING
A-5	◆	229555.82	1700458.82
A-6A	◆	229531.78	1700882.00
K-1	◆	228396.11	1702295.51
K-2	◆	228821.88	1701783.44
K-5	◆	230247.04	1700301.74
K-6	◆	228987.57	1700832.82
K-10	◆	230637.82	1698600.88
K-10A	◆	230623.02	1698600.82
K-11	◆	230023.23	1698006.78
K-11A	◆	230005.95	1698025.24
K-13	◆	229655.76	1699941.96
K-14	◆	228678.71	1699405.88
K-15	◆	228262.68	1698455.82
K-16	◆	228948.07	1702852.02
K-18	◆	227189.58	1701580.87
K-19	◆	228792.09	1702724.07
K-21	◆	227406.85	1700927.31
K-22	◆	227512.80	1700797.53
K-23	◆	227248.07	1700828.99
K-24	◆	230114.22	1700144.78
K-25	◆	230507.23	1699923.07
K-25A	◆	230493.88	1699937.88
K-26	◆	228070.27	1702707.95
K-27	◆	228825.41	1702883.15
K-28	◆	228638.02	1702881.13
K-28	◆	229080.76	1702888.34
K-30	◆	230115.92	1700113.44
K-31	◆	229418.24	1700178.86
K-32	◆	228018.07	1702313.81
K-33	◆	227398.12	1702060.82
K-38	◆	229369.80	1701010.81
K-40	◆	229687.86	1700284.82
K-46	◆	230843.24	1699397.02
K-48	◆	230432.92	1700653.00
K-49	◆	229812.11	1701781.88
K-50	◆	230719.43	1699730.73
K-51	◆	227530.00	1702510.00
K-53	◆	227543.00	1702215.00
K-57	◆	227435.00	1701185.00
K-01R	◆	228150.00	1702785.00
K-32R	◆	227770.00	1702400.00

SEE NOTE 2

STOCKPILE AND ACCESS ROAD CONSTRUCTION SURVEY CONTROL POINTS OF INTERSECTION



POINT OF INTERSECTION	NORTHING	EASTING	ELEVATION
P.I.-R1	228796.87	1698205.55	860.0
P.I.-R2	228574.32	1698448.32	840.0
P.I.-R3	228821.84	1700187.41	840.0
P.I.-R4	228873.80	1700272.07	820.0
P.I.-R5	229100.83	1700676.77	861.0
P.I.-R9	227618.22	1702234.88	830.0
P.I.-R10	228908.68	1702588.41	890.0
P.I.-R11	228238.18	1702174.38	952.4
P.I.-R18	229105.63	1700842.12	847.0
P.I.-SP1	228338.65	1698088.21	952.2
P.I.-SP2	228984.80	1699353.28	880.4
P.I.-SP3	228702.85	1699207.26	880.4
P.I.-SP4	229400.92	1698513.68	850.5
P.I.-SP5	228573.26	1698840.43	850.0
P.I.-SP6	228984.50	1699848.74	850.0
P.I.-SP7	228917.80	1700108.88	850.0
P.I.-SP8	228980.14	1701545.22	952.4
P.I.-SP9	228448.63	1701808.85	952.1
P.I.-SP10	228918.64	1702285.90	958.5
P.I.-SP11	228931.48	1702338.27	958.2
P.I.-SP12	228541.09	1702519.15	958.9
P.I.-SP13	228935.88	1702788.84	854.3
P.I.-SP14	228868.12	1702348.87	950.0
P.I.-SP15	228518.41	1701359.42	950.0

NOTES

- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
- SEE LEGEND ON SHEET 1 FOR MONITORING WELL SYMBOLS.
- EXISTING PERIMETER FENCE WILL BE EXTENDED TO ENCLOSE THE B-18 LANDFILL AREA INTO THE KHF ACTIVE FACILITY AREA.
- LOCATION APPROXIMATE. FINAL LOCATION TO BE DETERMINED BY OWNER.

0 300 600 FEET  
SCALE

3	3/7/81	MODIFIED CONTRACTOR STAGING AREA	KJK
2	1/2/81	ISSUED FOR CONSTRUCTION	KJK
1	8/24/80	ISSUED FOR BID	MD
0	7/8/80	ISSUED FOR PERMITTING	KAB
<p>LANDFILL UNIT B-18 CONSTRUCTION PLANS CWM-KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA</p> <p>PHASE I EXCAVATION PROJECT PLAN</p> <p>ENVIRONMENTAL SOLUTIONS, INC.</p> <p>89-877 D-89977-EX002 3 1"=300' 89-03-304.2.1 2A</p>			



KEY PLAN

MONITORING WELL LOCATIONS

WELL	SYMBOL	NORTHING	EASTING
A-5	◆	22955.82	1700456.82
A-6A	◆	229531.79	1700682.00
K-1	◆	228398.11	1702295.51
K-2	◆	228921.29	1701783.44
K-5	◆	230247.04	1700301.74
K-6	◆	228997.57	1700632.92
K-10	◆	230637.32	1698800.98
K-10A	◆	230623.02	1698820.82
K-11	◆	230023.23	1698006.76
K-11A	◆	230005.33	1698025.24
K-12	◆	229655.78	1699941.96
K-14	◆	228678.71	1699405.58
K-15	◆	228262.06	1698455.62
K-16	◆	228948.07	1702852.02
K-18	◆	227189.58	1701580.97
K-19	◆	228792.08	1702724.07
K-21	◆	227406.85	1700927.31
K-22	◆	227512.80	1700797.53
K-23	◆	227248.07	1700628.99
K-24	◆	230114.22	1700144.79
K-25	◆	230507.23	1699923.07
K-25A	◆	230493.36	1699937.98
K-26	◆	229070.27	1702707.95
K-27	◆	228625.41	1702693.15
K-28	◆	228638.02	1702681.13
K-29	◆	228080.76	1702689.34
K-30	◆	230115.82	1700113.44
K-31	◆	229416.24	1700178.96
K-32	◆	228018.07	1702313.81
K-33	◆	227396.12	1702060.82
K-36	◆	228369.50	1701010.81
K-40	◆	229687.86	1700284.82
K-46	◆	230643.24	1699397.02
K-48	◆	230432.92	1700653.00
K-49	◆	229612.11	1701781.68
K-50	◆	230719.43	1699730.73
K-51	◆	227530.00	1702510.00
K-53	◆	227543.00	1702215.00
K-57	◆	227435.00	1701185.00
K-01R	◆	228150.00	1702785.00
K-82R	◆	227770.00	1702400.00

SEE NOTE 2

STOCKPILE AND ACCESS ROAD CONSTRUCTION SURVEY CONTROL POINTS OF INTERSECTION

POINT OF INTERSECTION	NORTHING	EASTING	ELEVATION
P.I.-R1	228786.97	1698205.55	960.0
P.I.-R2	228574.32	1698448.32	940.0
P.I.-R3	228621.64	1700157.41	940.0
P.I.-R4	228673.80	1700272.07	920.0
P.I.-R5	229100.83	1700676.77	961.0
P.I.-R9	227813.22	1702254.88	930.0
P.I.-R10	228908.66	1702588.41	980.0
P.I.-R11	228238.18	1702174.36	952.4
P.I.-R18	229105.83	1700842.12	847.0
P.I.-SP1	228638.85	1699068.21	952.2
P.I.-SP2	228984.80	1698553.29	980.4
P.I.-SP3	228702.85	1698207.28	980.4
P.I.-SP4	228400.92	1698513.88	980.5
P.I.-SP5	228573.26	1698640.43	980.0
P.I.-SP6	228984.50	1698946.74	950.0
P.I.-SP7	228917.80	1700106.98	950.0
P.I.-SP8	228880.14	1701545.22	952.4
P.I.-SP9	228448.83	1701808.85	952.1
P.I.-SP10	228818.64	1702295.80	956.5
P.I.-SP11	228831.48	1702336.27	956.2
P.I.-SP12	228541.08	1702519.15	956.9
P.I.-SP13	228935.66	1702788.64	954.3
P.I.-SP14	228888.12	1702346.97	950.0
P.I.-SP15	228518.41	1701359.42	950.0





- NOTES
- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
  - SEE LEGEND ON SHEET 1 FOR MONITORING WELL SYMBOLS.
  - EXISTING PERIMETER FENCE WILL BE EXTENDED TO ENCLOSE THE B-18 LANDFILL AREA INTO THE KMF ACTIVE FACILITY AREA.



2/1/94	ISSUED FOR CONSTRUCTION	KJK
0/7/90	ISSUED FOR PERMITTING	KAB
<p>LANDFILL UNIT B-18 CONSTRUCTION PLANS          CWM1-KETTLEMAN HILLS FACILITY          KINGS COUNTY CALIFORNIA</p> <p>PHASE I EXCAVATION PROJECT PLAN</p> <p>ENVIRONMENTAL SOLUTIONS, INC.</p>		
89-877	D-89977-FD002	2
1"=300'	89-03-304.2.1	2





KEY PLAN

POINTS OF INTERSECTION


POINT	NORTHING	EASTING	ELEV.
P00	228,888.87	1,701,118.85	742.0
P01	228,888.41	1,701,148.18	744.1
P02	228,888.14	1,701,178.18	740.1
P03	228,888.14	1,701,208.72	746.1
P04	227,844.45	1,701,238.72	742.1
P05	227,844.45	1,701,268.72	748.0
P06	227,844.45	1,701,298.72	744.0
P07	227,844.45	1,701,328.72	740.0
P08	227,844.45	1,701,358.72	746.0
P09	228,771.08	1,701,388.72	742.0
P10	228,771.08	1,701,418.72	748.0
P11	228,771.08	1,701,448.72	744.0
P12	228,771.08	1,701,478.72	740.0
P13	228,771.08	1,701,508.72	746.0
P14	228,771.08	1,701,538.72	742.0
P15	228,771.08	1,701,568.72	748.0
P16	228,771.08	1,701,598.72	744.0
P17	228,771.08	1,701,628.72	740.0
P18	228,771.08	1,701,658.72	746.0
P19	228,771.08	1,701,688.72	742.0
P20	228,771.08	1,701,718.72	748.0
P21	228,771.08	1,701,748.72	744.0
P22	228,771.08	1,701,778.72	740.0
P23	228,771.08	1,701,808.72	746.0
P24	228,771.08	1,701,838.72	742.0
P25	228,771.08	1,701,868.72	748.0
P26	228,771.08	1,701,898.72	744.0
P27	228,771.08	1,701,928.72	740.0
P28	228,771.08	1,701,958.72	746.0
P29	228,771.08	1,701,988.72	742.0
P30	228,771.08	1,702,018.72	748.0
P31	228,771.08	1,702,048.72	744.0
P32	228,771.08	1,702,078.72	740.0
P33	228,771.08	1,702,108.72	746.0
P34	228,771.08	1,702,138.72	742.0
P35	228,771.08	1,702,168.72	748.0
P36	228,771.08	1,702,198.72	744.0
P37	228,771.08	1,702,228.72	740.0
P38	228,771.08	1,702,258.72	746.0
P39	228,771.08	1,702,288.72	742.0
P40	228,771.08	1,702,318.72	748.0
P41	228,771.08	1,702,348.72	744.0
P42	228,771.08	1,702,378.72	740.0
P43	228,771.08	1,702,408.72	746.0
P44	228,771.08	1,702,438.72	742.0
P45	228,771.08	1,702,468.72	748.0
P46	228,771.08	1,702,498.72	744.0
P47	228,771.08	1,702,528.72	740.0
P48	228,771.08	1,702,558.72	746.0
P49	228,771.08	1,702,588.72	742.0
P50	228,771.08	1,702,618.72	748.0
P51	228,771.08	1,702,648.72	744.0
P52	228,771.08	1,702,678.72	740.0
P53	228,771.08	1,702,708.72	746.0
P54	228,771.08	1,702,738.72	742.0
P55	228,771.08	1,702,768.72	748.0
P56	228,771.08	1,702,798.72	744.0
P57	228,771.08	1,702,828.72	740.0
P58	228,771.08	1,702,858.72	746.0
P59	228,771.08	1,702,888.72	742.0
P60	228,771.08	1,702,918.72	748.0
P61	228,771.08	1,702,948.72	744.0
P62	228,771.08	1,702,978.72	740.0
P63	228,771.08	1,703,008.72	746.0
P64	228,771.08	1,703,038.72	742.0
P65	228,771.08	1,703,068.72	748.0
P66	228,771.08	1,703,098.72	744.0
P67	228,771.08	1,703,128.72	740.0
P68	228,771.08	1,703,158.72	746.0
P69	228,771.08	1,703,188.72	742.0
P70	228,771.08	1,703,218.72	748.0
P71	228,771.08	1,703,248.72	744.0
P72	228,771.08	1,703,278.72	740.0
P73	228,771.08	1,703,308.72	746.0
P74	228,771.08	1,703,338.72	742.0
P75	228,771.08	1,703,368.72	748.0
P76	228,771.08	1,703,398.72	744.0
P77	228,771.08	1,703,428.72	740.0
P78	228,771.08	1,703,458.72	746.0
P79	228,771.08	1,703,488.72	742.0
P80	228,771.08	1,703,518.72	748.0
P81	228,771.08	1,703,548.72	744.0
P82	228,771.08	1,703,578.72	740.0
P83	228,771.08	1,703,608.72	746.0
P84	228,771.08	1,703,638.72	742.0
P85	228,771.08	1,703,668.72	748.0
P86	228,771.08	1,703,698.72	744.0
P87	228,771.08	1,703,728.72	740.0
P88	228,771.08	1,703,758.72	746.0
P89	228,771.08	1,703,788.72	742.0
P90	228,771.08	1,703,818.72	748.0
P91	228,771.08	1,703,848.72	744.0
P92	228,771.08	1,703,878.72	740.0
P93	228,771.08	1,703,908.72	746.0
P94	228,771.08	1,703,938.72	742.0
P95	228,771.08	1,703,968.72	748.0
P96	228,771.08	1,703,998.72	744.0
P97	228,771.08	1,704,028.72	740.0
P98	228,771.08	1,704,058.72	746.0
P99	228,771.08	1,704,088.72	742.0
P100	228,771.08	1,704,118.72	748.0

CURVE DATA

CURVE NO.	LOCATION OF P.I.		A	B	L	T
	NORTHING	EASTING				
00	228,888.87	1,701,118.85	89°00'00"	85.00	81.67	84.88
01	228,888.14	1,701,178.18	88°00'00"	85.00	84.61	78.28
02	227,844.45	1,701,238.72	87°00'00"	85.00	78.71	48.85
03	227,844.45	1,701,298.72	86°00'00"	85.00	74.28	48.01
04	227,844.45	1,701,358.72	85°00'00"	85.00	88.08	36.41
05	228,771.08	1,701,418.72	84°00'00"	85.00	8.14	8.87
06	228,771.08	1,701,478.72	83°00'00"	85.00	78.28	78.28
07	228,771.08	1,701,538.72	82°00'00"	85.00	85.04	18.18
08	228,771.08	1,701,598.72	81°00'00"	85.00	88.08	88.48
09	228,771.08	1,701,658.72	80°00'00"	85.00	88.08	48.88
10	228,771.08	1,701,718.72	79°00'00"	85.00	8.28	4.23
11	228,771.08	1,701,778.72	78°00'00"	85.00	36.28	18.48
12	228,771.08	1,701,838.72	77°00'00"	85.00	118.11	81.47
13	228,771.08	1,701,898.72	76°00'00"	85.00	48.48	27.05

NOTES

- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
- SEE SHEET 3 FOR CROSS SECTION AND DETAIL PLAN CALLOUTS.
- SEE SHEET 5 FOR DRAINAGE PLAN AND DETAIL PLAN CALLOUTS. (BID ITEM 2.7)





NO.	DATE	DESCRIPTION	BY	CHKD.
2	04/04/00	ISSUED FOR CONSTRUCTION	KJK	RP
1	03/14/00	ISSUED FOR BID	KJK	RP
0	02/10/00	ISSUED FOR COMMENTS	KJK	RP

LANDFILL UNIT B-18  
CONSTRUCTION PLANS  
CMI-KETTLEMAN HILLS FACILITY  
KINGS COUNTY CALIFORNIA

PHASE I  
CONSTRUCTION SEQUENCE PLAN

ENVIRONMENTAL SOLUTIONS, INC.  
 DRAWING NO. 89-877 D-89977-EX003 SHEET 2  
 DATE 89-03-30 1"=100' 3A





KEY PLAN



- NOTES
1. SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
  2. TRANSITION FROM PERIMETER BENCH/ROAD (SECTION A, 3,15) TO ACCESS ROAD WITH BERM (SECTION B, 3,15).
  3. THE EAST SLOPE OF THE CLAY PIT EXCAVATION MAY BE VARIED TO CONFORM TO THE BASE OF THE CLAYSTONE STRATUM.
  4. SEE SHEET 25 FOR SURVEY CONTROL.



2	2/12/91	ISSUED FOR CONSTRUCTION	RVH	KKP
1	5/24/90	ISSUED FOR BIDDING	KJK	KKP
0	7/31/90	ISSUED FOR PERMITTING	KJK	KKP
REV	DATE	DESCRIPTION	BY	CHK'D
PREPARED BY: <i>Gregory K. Robinson</i> CHECKED BY: <i>ROE</i> <b>LANDFILL UNIT B-18</b> <b>CONSTRUCTION PLANS</b> CWM-KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA <b>PHASE I EXCAVATION</b> <b>AND</b> <b>SITE PREPARATION PLAN</b> ENVIRONMENTAL SOLUTIONS, INC.				
NO. 89-977	FILE NO. D-89977-FD003	DATE 2		
SCALE 1"=100'	REV. 89-03-304.2.1	PAGE 3		



KEY PLAN

POINTS OF INTERSECTION			
POINT	NORTHING	EASTING	ELEV.
P52	228,071.00	1,700,885.00	846.0
P53	228,290.00	1,700,998.00	840.0
P54	227,828.00	1,701,785.00	832.0
P55	227,587.88	1,708,071.88	830.7
P56	228,101.11	1,701,321.08	841.8
P57	228,898.34	1,701,130.87	784.7
P58	228,328.21	1,701,182.78	727.5
P59	228,528.08	1,701,288.88	734.5
P60	228,434.14	1,701,338.88	722.4
P61	228,488.34	1,701,417.48	724.4
P62	228,877.80	1,701,242.44	784.0
P63	228,174.47	1,701,338.38	727.4
P64	228,080.27	1,701,422.87	780.7
P65	227,800.33	1,701,584.10	785.2
P66	227,813.24	1,701,818.80	748.3
P67	227,843.58	1,701,860.47	742.3
P68	228,138.82	1,701,368.82	780.8
P69	228,133.80	1,701,388.48	781.2
P70	228,400.58	1,701,452.80	724.7
P71	228,334.27	1,701,348.88	722.2
P72	228,248.88	1,701,418.83	720.8
R11	228,847.47	1,701,334.87	788.2
R12	228,371.18	1,701,802.28	794.8
R13	227,830.83	1,702,004.78	722.5
R14	228,308.12	1,701,201.78	728.5
R15	228,441.08	1,701,481.82	728.5
R16	227,731.37	1,701,428.30	885.5
R17	227,422.13	1,701,788.18	787.1
R18	227,830.83	1,702,004.78	728.5
R19	227,808.27	1,701,888.30	788.0
R20	228,133.80	1,701,388.48	781.2

CURVE DATA						
CURVE NO.	NORTHING	EASTING	Δ	R	L	T
66	228,071.00	1,700,885.00	85°05'58"	30.00	81.24	82.78
68	228,290.00	1,700,998.00	54°22'42"	30.00	28.81	18.28
70	227,528.00	1,701,785.00	84°48'48"	30.00	78.88	48.84
71	227,881.87	1,701,856.81	72°43'17"	30.00	68.48	38.81
72	228,898.34	1,701,130.87	84°18'45"	30.00	82.30	88.81
73	228,320.17	1,701,184.54	115°28'58"	30.00	100.70	78.08
74	228,468.34	1,701,417.48	82°27'58"	30.00	80.89	82.30
75	228,877.80	1,701,242.44	71°11'58"	30.00	82.13	35.79
76	228,308.12	1,701,201.78	108°10'55"	30.00	88.28	70.33
77	227,843.58	1,701,860.47	88°02'22"	35.00	38.41	24.18
78	228,138.82	1,701,388.48	84°38'58"	35.00	38.88	22.79
79	228,400.58	1,701,452.80	92°06'11"	30.00	90.37	81.87

- NOTES
- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
  - THE EAST SIDE SECONDARY LINER CONTROL LINE IS THE EDGE OF THE LINER AT THE BEGINNING OF THE ANCHOR TRENCH.
  - THE NORTH, SOUTH AND WEST SECONDARY LINER CONTROL LINE IS THE TOP OF THE SLOPE.
  - TAPER WIDTH OF GEONET AS REQUIRED TO REMAIN WITHIN THE BOTTOM AREA.

REGISTERED PROFESSIONAL ENGINEER  
 CIVIL  
 STATE OF CALIFORNIA  
 No. 41021  
 EXP. MAR 31, 1991

SCALE: 1" = 100'

REV.	DATE	DESCRIPTION	BY	CHKD.
2	01/02/91	ISSUED FOR CONSTRUCTION	KJK	KKP
1	8/24/90	ISSUED FOR BID	MD	KKP
0	7/31/90	ISSUED FOR PERMITTING	KJK	KKP



DESIGNED BY: [Signature] CHECKED BY: [Signature] APPROVED BY: [Signature]

LANDFILL UNIT B-18  
 CONSTRUCTION PLANS  
 CMMI-KETTLEMAN HILLS FACILITY  
 KINGS COUNTY CALIFORNIA

PHASE I  
 TOP OF SECONDARY LINER

ENVIRONMENTAL SOLUTIONS, INC.

PROJECT NO.	89-977	FILE NUMBER	D-89977-FD004	REVISION	2
SCALE	1"=100'	DATE	89-03-304.2.1	SHEET	4



**CULVERT SCHEDULE**

NO.	DIA. (IN.)	LENGTH (FT.)	TYPE	WIDTH (W)	DEPTH (H)
C1	12	30	V-1	2	1
C2	12	30	V-2	3	1
C3	12	170	V-3	3	1.5
C4	24	155W	V-4	3	2.5
C5	18	60	V-5	3	2.5
C6	30	170W	V-6	3	3
C7	12	30W	V-7	3	1.25

**V-DITCH SCHEDULE**

NO.	DIA. (IN.)	LENGTH (FT.)	TYPE	WIDTH (W)	DEPTH (H)
V-1	2	1			
V-2	3	1			
V-3	3	1.5			
V-4	3	2.5			
V-5	3	2.5			
V-6	3	3			
V-7	3	1.25			

**DROP INLET SCHEDULE**

NO.	DEPTH (FT.)	DIA. (IN.)	OUTLET PIPE DIA. (IN.)	OUTLET PIPE LENGTH (FT.)
D1	4	36	12	36
D2	4	36	24	42
D3	4	36	18	72
D4	4	36	12	80
D5	4	72	24	85 EA.
D6	4	36	18	80
D7	4	72	18	145
D8	5	72	30	170
D9	4	36	18	140

NOTE: LENGTH IS APPROXIMATE. ACTUAL LENGTH WILL BE DETERMINED AT COMPLETION OF GRADING. LENGTH INCLUDES DOWNSLOPE PIPE.

**POINTS OF INTERSECTION**

POINT	NORTHING	EASTING	ELEV.
P10	226,874.32	1,700,885.00	787.5
P11	226,894.86	1,701,180.38	728.6
P12	226,820.10	1,701,261.58	727.0
P13	226,487.86	1,701,823.08	724.8
P14	226,478.08	1,701,422.88	727.2
P15	226,884.82	1,701,248.42	728.6
P16	226,115.77	1,701,375.87	726.8
P17	226,091.20	1,701,415.48	726.2
P18	227,880.75	1,701,884.88	728.0
P19	227,805.88	1,701,818.02	748.3
P20	227,843.98	1,701,888.41	748.1
P21	226,106.71	1,701,884.88	726.8
P22	226,118.57	1,701,828.88	724.8
P23	226,402.78	1,701,480.84	726.4
P24	226,280.20	1,701,248.21	724.4
P25	226,347.84	1,701,844.21	727.4
P10	226,874.32	1,700,885.00	787.5
P11	226,894.86	1,701,180.38	728.6
P12	226,820.10	1,701,261.58	727.0
P13	226,487.86	1,701,823.08	724.8
P14	226,478.08	1,701,422.88	727.2
P15	226,884.82	1,701,248.42	728.6
P16	226,115.77	1,701,375.87	726.8
P17	226,091.20	1,701,415.48	726.2
P18	227,880.75	1,701,884.88	728.0
P19	227,805.88	1,701,818.02	748.3
P20	227,843.98	1,701,888.41	748.1
P21	226,106.71	1,701,884.88	726.8
P22	226,118.57	1,701,828.88	724.8
P23	226,402.78	1,701,480.84	726.4
P24	226,280.20	1,701,248.21	724.4
P25	226,347.84	1,701,844.21	727.4

**CURVE DATA**

CURVE NO.	LOCATION OF P.I.	NORTHING	EASTING	A	R	L	T
10	226,874.32	1,700,885.00	84°01'25"	30.00	82.05	58.84	
11	226,822.32	1,701,185.30	110°38'55"	30.00	98.97	72.30	
12	226,478.08	1,701,422.88	82°37'54"	30.00	85.86	82.30	
13	226,884.82	1,701,248.42	71°36'48"	30.00	92.36	58.88	
14	226,308.18	1,701,207.38	108°45'44"	30.00	80.35	68.72	
15	227,805.88	1,701,818.02	86°13'12"	25.00	38.48	24.28	
16	227,843.98	1,701,888.41	64°38'34"	26.00	34.90	22.70	
17	226,402.78	1,701,480.84	92°08'05"	30.00	90.37	51.97	

- NOTES**
- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
  - THE EAST SIDE PRIMARY LINER CONTROL LINE IS THE EDGE OF THE LINER AT THE BEGINNING OF THE ANCHOR TRENCH.
  - THE NORTH, SOUTH AND WEST PRIMARY LINER CONTROL LINE IS THE TOP OF THE SLOPE.
  - FOR CLAY PROCESSING AREA DRAINAGE SEE SHEET 3A.
  - EXTEND 18" DIA. PIPE 20 FEET BEYOND TOE OF SLOPE TOE OF SLOPE.
  - DUE TO SHALLOW BURIAL DEPTH CULVERT BACKFILL SHALL BE CONCRETE. PROVIDE 8 INCHES OF COVER MINIMUM.
  - ALL DROP INLETS SHALL BE OF 12 GAGE THICKNESS.
  - ALL CULVERTS AND OUTLETS SHALL BE OF 18 GAGE THICKNESS.
  - BLEND 5:1 TO 3:1 SLOPE BREAK INTO LANDFILL BOTTOM TO CREATE SMOOTH TRANSITION.
- SCALE: 1" = 100'

3/17/91	REMOVED SECTION B:5:24	KJK	AKP
2/10/91	ISSUED FOR CONSTRUCTION	KJK	AKP
1/24/90	ISSUED FOR BID	MD	AKP
0/7/90	ISSUED FOR PERMITTING	KJK	AKP



REGISTERED PROFESSIONAL ENGINEER  
 ENVIRONMENTAL SOLUTIONS, INC.  
 NO. 41021  
 CIVIL  
 STATE OF CALIFORNIA

LANDFILL UNIT B-18  
 CONSTRUCTION PLANS  
 CWA1-KETTLEMAN HILLS FACILITY  
 KINGS COUNTY CALIFORNIA

PHASE I  
 TOP OF PRIMARY LINER

ENVIRONMENTAL SOLUTIONS, INC.

89-977 D-89977-F0005 3  
 1"=100' 89-03-304.2.1 5



KEY PLAN





NOTES

1. SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
2. SEE SHEET 3 FOR DRAINAGE CONTROL.
3. RUN-OFF FROM LANDFILL SLOPES SHALL BE DETAINED IN A TEMPORARY POND FORMED AT THE LANDFILL TOE OR PUMPED TO THE PHASE I RETENTION BASIN AT THE OPTION OF THE OWNER.



2/1/02/01	ISSUED FOR CONSTRUCTION	RVH	XXP
0/1/01/00	ISSUED FOR PERMITTING	KJK	XXP
DATE	DESCRIPTION	BY	CHK'D
01/01/01	ISSUED FOR PERMITTING	RVH	XXP
<p>LANDFILL UNIT B-18 CONSTRUCTION PLANS CMI-KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA</p> <p>PHASE I INTERMEDIATE WASTE FILL PLAN</p> <p>ENVIRONMENTAL SOLUTIONS, INC.</p>			
89-977	D-89977-FD006	2	
1"=100'	89-03-304.2.1	6	



KEY PLAN



POINT	NORTHING	EASTING	ELEV.
X1	228,458.08	1,702,218.70	788.1
X2	228,188.35	1,701,488.25	782.0
X3	227,898.98	1,702,074.48	807.8
X4	228,104.18	1,702,027.00	802.1
X5	228,118.42	1,702,040.01	800.0
X6	228,042.44	1,702,087.48	800.0
X7	228,181.81	1,702,388.38	800.0
X8	228,287.00	1,702,182.41	800.0
X9	228,180.92	1,702,028.92	800.0



- NOTES
- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
  - SEE SHEET 5 FOR DRAINAGE CONTROL.
  - RUN-OFF FROM LANDFILL SLOPES SHALL BE DETAINED IN A TEMPORARY POND FORMED AT THE LANDFILL TOE OR PUMPED TO THE PHASE I RETENTION BASIN AT THE OPTION OF THE OWNER.
  - THE BERM SEPARATING THE PHASE I RETENTION BASIN AND THE FUTURE CLAY AREA EXCAVATION MAY BE EXCAVATED AT THE OPTION OF THE OWNER.
  - THE BOTTOM OF THE FUTURE CLAY EXCAVATION AREA IS LOWER THAN THE EXCAVATION DESIGN GRADE FOR PHASE II (SEE SHEET 8). AT THE OPTION OF THE OWNER THE CLAY EXCAVATION GRADE MAY BE RAISED TO PREVENT THE USE OF BACKFILL AT THE BOTTOM.



DATE	DESCRIPTION	BY	CHK
2/7/79	ISSUED FOR PHASE II CONSTRUCTION	KJK	AT
0/1/79	ISSUED FOR PERMITTING	KJK	AT
LANDFILL UNIT B-18 CONSTRUCTION PLANS CWM-KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA CLAY BORROW PIT EXPANSION PLAN ENVIRONMENTAL SOLUTIONS, INC. SHEET NO. 89-977 REV. FILE NUMBER 0-89977-F007 SHEET 2 SCALE 1"=100' 89-03-304.2.1 SHEET 7			





KEY PLAN

POINT	NORTHING	EASTING	ELEV.
P101	228,731.97	1,702,883.03	786.7
P102	228,841.80	1,702,815.80	786.0
P103	228,872.47	1,702,082.38	786.8
P104	228,184.14	1,701,828.28	816.0
P105	228,113.91	1,701,808.47	836.0
P106	228,868.48	1,701,468.81	737.7
P107	228,810.79	1,701,886.31	723.4
P108	228,865.34	1,701,868.27	718.9
P109	228,738.08	1,702,238.47	708.8
P110	228,860.45	1,702,283.84	701.7
P111	228,572.08	1,702,328.88	708.6
P112	228,878.81	1,702,477.38	686.0
P113	228,778.80	1,702,888.87	700.0
P114	228,820.82	1,702,537.08	700.0
P115	228,585.88	1,702,368.18	700.0
P116	228,865.18	1,702,828.10	897.7
P117	228,481.28	1,702,512.83	701.0
P118	228,402.78	1,702,553.42	896.3
P119	228,284.30	1,702,804.85	702.7
P120	228,443.38	1,702,708.72	700.0
P121	228,188.08	1,702,570.85	708.4
P122	228,181.82	1,702,338.88	708.5
P123	228,224.48	1,702,804.13	708.8
P124	227,852.18	1,702,088.20	721.1
P125	228,088.89	1,701,828.11	718.4
P126	228,188.07	1,701,850.87	720.0
P127	228,240.08	1,701,886.33	720.0
P128	228,379.32	1,701,770.85	715.8
P129	228,434.87	1,701,728.28	717.6
P130	228,378.80	1,701,812.88	781.0
P131	228,388.37	1,701,858.00	782.0
P132	227,788.88	1,702,028.37	718.8
P133	228,380.38	1,701,382.00	785.1
P134	228,212.85	1,701,838.30	725.7
P135	228,808.01	1,702,372.75	708.0
P136	227,888.31	1,702,000.18	788.3
P137	227,788.18	1,702,180.88	780.8
P138	228,877.37	1,702,548.48	788.38
P139	228,028.28	1,702,288.85	784.8
P140	228,844.08	1,702,027.17	785.7
P141	227,858.08	1,701,865.82	785.3
P142	227,783.14	1,702,118.84	748.6
P143	228,118.05	1,702,480.85	710.2
P144	228,108.81	1,702,581.82	752.0
P145	228,081.44	1,702,808.02	752.0
P146	228,617.28	1,702,800.48	788.6
P147	228,088.83	1,702,388.70	730.0
P148	228,084.33	1,702,380.48	730.0
P149	228,888.77	1,702,717.37	713.0
P150	228,388.02	1,702,817.02	710.0
P151	228,888.08	1,702,808.43	710.0


B-COORDINATES AND ELEVATIONS SHALL BE DETERMINED FROM PHASE I AS-BUILT SURVEY.

CURVE NO.	LOCATION OF P. I.				
	NORTHING	EASTING	A	R	L
71	228,841.80	1,702,815.80	33°21'24"	48.80	48.48
72	228,872.47	1,702,082.38	36°20'58"	110.00	108.34
73	228,184.14	1,701,802.29	51°37'24"	48.80	48.74
74	228,887.37	1,702,548.48	45°21'01"	110.00	98.08
75	228,028.28	1,702,288.85	22°18'22"	110.00	88.01
76	228,844.08	1,702,157.17	10°22'36"	30.00	9.08

- NOTES
- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
  - REMOVE EXISTING DRAINAGE STRUCTURES AND TRANSPORT TO STORAGE AREA AS DIRECTED BY THE OWNER. BACKFILL EXCAVATIONS WITH CLAY AS SPECIFIED FOR CLAY LINER.
  - FIELD LOCATE SUMP AS APPROVED BY OWNER.



2/28/91	ISSUED FOR PHASE II CONSTRUCTION	K.K.P.	K.P.
0/7/90	ISSUED FOR PERMITTING	K.K.P.	K.P.
REV	DATE	DESCRIPTION	BY
1	02/28/91	ISSUED FOR PERMITTING	RVE
LANDFILL UNIT B-18 CONSTRUCTION PLANS CRYM-KITTLEMAN HILLS FACILITY KINGS COUNTY, CALIFORNIA <b>PHASE II EXCAVATION AND SITE PREPARATION PLAN</b> ENVIRONMENTAL SOLUTIONS, INC.			
NO. 89-977	D-89977-FDOOB	REVISION	2
SCALE 1"=100'	89-03-304.2.1	SHEET	8




**KEY PLAN**

POINT	NORTHING	EASTING	ELEV.
P55	227,537.86	1,702,071.85	830.7
P56	228,100.83	1,701,318.37	841.8
P130	227,630.63	1,702,004.78	778.5
P131	227,845.00	1,702,218.00	830.0
P132	228,074.39	1,702,685.18	790.0
P133	228,524.03	1,702,801.11	770.0
P134	228,732.11	1,702,707.35	770.7
P135	228,842.11	1,702,515.88	770.0
P136	228,872.88	1,702,082.47	800.0
P137	228,134.85	1,701,802.87	820.0
P138	228,118.81	1,701,908.47	840.0
P139	228,885.81	1,701,486.73	730.8
P140	228,807.71	1,701,886.88	728.8
P141	228,884.88	1,701,885.38	717.4
P142	228,737.38	1,702,240.48	707.3
P143	228,860.58	1,702,283.72	705.2
P144	228,572.87	1,702,328.87	707.3
P145	228,879.70	1,702,478.66	702.5
P146	228,827.32	1,702,328.78	705.4
P147	228,838.88	1,702,328.18	705.5
P148	228,801.85	1,702,584.85	708.2
P149	228,559.75	1,702,587.73	704.4
P150	228,804.75	1,702,829.02	701.2
P151	228,481.10	1,702,515.43	704.4
P152	228,402.98	1,702,553.77	702.8
P153	228,289.72	1,701,808.67	708.2
P154	228,188.85	1,702,370.31	708.8
P155	228,148.51	1,702,328.43	711.1
P156	227,185.43	1,702,487.88	708.7
P157	227,885.80	1,702,050.47	733.0
P158	228,071.18	1,701,857.10	718.6
P159	228,307.51	1,702,389.87	708.5
P160	228,244.34	1,701,837.29	722.6
P161	228,379.74	1,701,771.61	718.4
P162	228,438.08	1,701,738.40	720.8
B318			
B328			
B338			
B34	228,218.85	1,701,849.86	723.2
B35	228,808.43	1,702,571.22	708.0


\* COORDINATES AND ELEVATIONS SHALL BE DETERMINED FROM PHASE I AS-BUILT SURVEY.

**NOTES**


- SEE SHEET I FOR LEGEND AND GENERAL NOTES.
- THE WEST SIDE SECONDARY LINER CONTROL LINE IS THE EDGE OF LINER AT THE BEGINNING OF THE ANCHOR TRENCH.
- THE NORTH, SOUTH AND EAST SECONDARY LINER CONTROL LINE IS THE TOP OF THE SLOPE.





REV	DATE	DESCRIPTION	DESIGNED BY	CHECKED BY
4	10/02/01	REVISED CALL OUTS FOR SUMPS AND RISERS	GGI	ANB
3	7/29/98	ACCESS ROAD WIDTH REDUCED TO 44' ELIMINATED PHASE II A-B DIVIDING BERM ADDED TYPICAL SECTIONS A-9/18A, B-9/18A MODIFIED GRADING IN SUMP AREA MODIFIED SURVEY CONTROL TO REFLECT MOVE OWNERS	GGI	
2	7/26/91	ISSUED FOR PHASE II CONSTRUCTION	KJK	
0	7/31/90	ISSUED FOR PERMITTING	KJK	



LANDFILL UNIT B-18  
 CONSTRUCTION PLANS  
 CWM-KETTLEMAN HILLS FACILITY  
 KINGS COUNTY CALIFORNIA  
**PHASE II**  
**TOP OF SECONDARY LINER**  
 ENVIRONMENTAL SOLUTIONS, INC.  
 JOB NO: 88-877    REV. FILE NUMBER: D-89977-FD009    SHEET: 4  
 SCALE: 1"=100'    DRAWING NUMBER: 89-03-304.2.1    SHEET: 9







**KEY PLAN**

**POINTS OF INTERSECTION**

POINT	NORTHING	EASTING	ELEV.
P171	228,894.08	1,701,481.72	728.7
P172	228,800.98	1,701,554.56	722.4
P173	228,815.75	1,701,640.80	728.2
P174	228,870.79	1,701,698.35	718.8
P175	228,742.72	1,702,240.77	706.8
P176	228,742.04	1,702,248.75	706.4
P177	228,862.08	1,702,288.70	707.6
P178	228,577.87	1,702,380.48	706.6
P179	228,680.45	1,702,472.58	706.0
P180	228,787.83	1,702,418.72	706.0
P181	228,840.88	1,702,528.22	706.0
P182	228,805.49	1,702,588.15	706.6
P183	228,554.31	1,702,589.81	706.6
P184	228,508.28	1,702,669.15	711.0
P185	228,586.85	1,702,564.78	706.1
P186	228,921.24	1,702,828.48	708.7
P187	228,458.84	1,702,518.28	706.6
P188	228,404.48	1,702,558.57	706.4
P189	228,285.05	1,702,818.30	706.4
P190	228,283.24	1,702,818.08	706.7
P191	228,458.48	1,702,721.38	706.4
P192	228,183.11	1,702,574.20	711.5
P193	228,146.51	1,702,520.43	713.2
P194	228,185.45	1,702,497.88	712.3
P195	227,852.74	1,702,048.88	726.4
P196	228,088.70	1,701,802.48	722.3
P197	228,208.42	1,701,852.33	725.6
P198	228,211.28	1,701,897.58	720.5
P199	228,224.07	1,701,852.30	725.5
P200	228,215.70	1,701,845.35	725.6
P201	228,377.13	1,701,787.05	722.0
P202	228,458.70	1,701,781.70	725.5
P203	227,706.82	1,702,028.24	725.5

**CULVERT SCHEDULE**

NO.	DIA. (IN.)	LENGTH (FT.)
C8	30	70
C9	24	40
C10	18	90

**DROP INLET SCHEDULE**


NO.	DEPTH D (FT.)	DIA. (IN.)
D10	4	30
D11	4	24
D12	4	18

**V-DITCH SCHEDULE**


TYPE	WIDTH (W)	DEPTH (H)
V-1	2	1
V-2	3	1
V-3	5	1.5
V-4	5	2
V-5	5	2.5
V-6	5	3
V-7	5	1.25

**NOTES**



- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
- THE WEST SIDE SECONDARY LINER CONTROL LINE IS THE EDGE OF LINER AT THE BEGINNING OF THE ANCHOR TRENCH.
- THE NORTH, SOUTH AND EAST SECONDARY LINER CONTROL LINE IS THE TOP OF THE SLOPE.
- ALL DROP INLETS SHALL BE OF 12 GAGE THICKNESS.
- ALL CULVERTS AND OUTLETS SHALL BE OF 18 GAGE THICKNESS.
- THE DRAINAGE FROM CONTROL POINT P55 TO CONTROL POINT P133 IS NOT A PART OF PHASE II CONSTRUCTION.



DATE	DESCRIPTION	BY	CHK'D BY
4/10/03	REVISED CALL OUTS FOR SLUMPS AND RISERS	GGI	GGI
3/17/03	ACCESS ROAD WIDTH REDUCED TO 44' ELIMINATED PHASE IIA-B DIVIDING BERM ADDED TYPICAL SECTIONS 1-10/18A, 8-10/18A MODIFIED GRADING IN SLUMP AREA MODIFIED SURVEY CONTROL TO REFLECT ABOVE CHANGES	GGI	GGI
2/7/03	ISSUED FOR PHASE II CONSTRUCTION	KLR	KLR
0/13/00	ISSUED FOR PERMITTING	KLR	KLR



DRAWN BY: \_\_\_\_\_ CHECKED BY: \_\_\_\_\_  
 DESIGNED BY: \_\_\_\_\_ APPROVED BY: \_\_\_\_\_  
**LANDFILL UNIT B-18**  
**CONSTRUCTION PLANS**  
 CWM-KETTLEMAN HILLS FACILITY  
 KINGS COUNTY CALIFORNIA  
**PHASE II**  
**TOP OF PRIMARY LINER**  
 ENVIRONMENTAL SOLUTIONS, INC.  
 SHEET NO. **89-877** PROJECT NO. **D-89977-FD010** PERMIT NO. **4**  
 SCALE: **1"=100'** FILE NO. **89-03-304.2.1** SHEET NO. **10**



N. 229.000


N. 228.500

N. 228.000


N. 227.500




- NOTES
- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
  - BENCHES WILL BE PROVIDED AT APPROXIMATELY 50-FOOT INTERVALS AS SHOWN ON SECTION B, SHEET 17. SLOPES BETWEEN BENCHES WILL HAVE A SLOPE OF APPROXIMATELY 3:1. THE BENCHES WILL SLOPE AT 3% TO CONTROL DRAINAGE.




DATE	DESCRIPTION	BY	CHKD
2/24/91	ISSUED FOR PHASE II CONSTRUCTION	KLK	APP
0/7/90	ISSUED FOR PERMITTING	MO	APP
DESIGNED BY: M.D.    DRAWN BY: K. Parkhurst    CHECKED BY: R.O.E.			
<b>LANDFILL UNIT B-18 CONSTRUCTION PLANS</b> CWM/KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA			
<b>PHASE I AND II FINAL CLOSURE PLAN</b>			
ENVIRONMENTAL SOLUTIONS, INC.			
PROJECT NO.	DRAWING NO.	SHEET NO.	
89-977	D-89977-FD011	2	
SCALE	DATE PLOTTED		SHEET
1"=100'	89-03-304.2.1		11




DETAIL PLAN 1  
PHASE I SUMPS





STATION	COORDINATE		ELEVATION
	N	E	
P7	228,528.63	1,701,181.87	724.0
P8	228,523.45	1,701,294.07	721.0
U1	228,471.09	1,701,252.04	711.3
U2	228,472.29	1,701,265.72	709.8
U3	228,433.91	1,701,252.12	712.0
U4	228,443.49	1,701,279.94	711.8
U5	228,465.95	1,701,262.13	709.3
P9	228,433.98	1,701,327.34	718.8
B4	228,309.28	1,701,200.98	730.0
P20	228,334.73	1,701,350.02	718.6
U6	228,280.84	1,701,316.10	712.1
U7	228,291.11	1,701,337.20	712.0
U8	228,263.86	1,701,341.50	709.3
U9	228,256.60	1,701,342.26	711.3
U10	228,261.96	1,701,350.04	709.8
P21	228,246.92	1,701,417.46	721.4
P12	228,173.47	1,701,333.28	724.0
P10	228,468.26	1,701,418.16	725.3
P19	228,401.18	1,701,452.95	726.0
B5	228,441.75	1,701,462.05	730.0
D1	228,177.31	1,701,331.96	723.2




SECTION A  
TRANSVERSE SECTION  
SUMP IB



SECTION B  
TRANSVERSE SECTION  
SUMP IA



SECTION C  
LONGITUDINAL SECTION  
SUMPS IA AND IB



NOTES:  
1) ELEVATIONS SHOWN ARE PHASE I EXCAVATION.

REV	DATE	DESCRIPTION	BY	CHK'D BY
2	01/08/00	ISSUED FOR CONSTRUCTION	RVH	KKP
1	01/24/00	ISSUED FOR BID	RVH	KKP
0	07/11/00	ISSUED FOR PERMITTING	MD	KKP


DESIGNED BY: K. HAYNIG    CHECKED BY: A. Robinson    APPROVED BY: RDE

LANDFILL UNIT B-18  
CONSTRUCTION PLANS  
CMAA-KETTLEMAN HILLS FACILITY  
KINGS COUNTY CALIFORNIA


GRADING DETAILS

ENVIRONMENTAL SOLUTIONS, INC.


DWG NO.	88-977	REV FILE NUMBER	D-89977-FD012	DATE	2
SCALE	AS NOTED	UNIT FILE NUMBER	89-03-304.2.1	SHEET	12




**DETAIL PLAN 1**  
PHASE I RETENTION BASIN  
SCALE: 0 40 80 FEET




**SECTION A**  
PHASE I BERM FILL RETENTION BASIN EXCAVATION GRADE  
SCALE: 0 40 80 FEET




**DETAIL PLAN 1**  
N.W. ROAD INTERSECTION  
SCALE: 0 50 100 FEET




**SECTION C**  
RETENTION BASIN ACCESS ROAD  
SCALE: 0 10 20 FEET



**SECTION B**  
RETENTION BASIN BENCH  
SCALE: 0 10 20 FEET




**DETAIL 1**  
TYPICAL STRUCTURAL FILL FOUNDATION BENCHING  
SCALE: 0 10 20 FEET



NOTE  
1. SEE SHEET 1 FOR LEGEND AND GENERAL NOTES

2	1/2/91	ISSUED FOR CONSTRUCTION	RYM	KRP
0	7/31/90	ISSUED FOR PERMITTING	MD	KRP
LANDFILL UNIT B-18 CONSTRUCTION PLANS CHMI-KITTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA				
GRADING DETAILS				
ENVIRONMENTAL SOLUTIONS, INC.				
89-877	0-89977-FD013	2		
AS NOTED	89-03-304.2.1	13		




SURVEY CONTROL			
STATION	COORDINATE		ELEVATION
	N	E	
US1	228,694.65	1,702,353.30	688.0
US2	228,676.57	1,702,360.08	688.4
US3	228,694.30	1,702,393.04	688.4
US4	228,708.34	1,702,380.42	688.4
US5	228,403.94	1,702,614.92	688.5
US6	228,434.94	1,702,600.51	688.0
US7	228,445.83	1,702,619.52	688.1
US8	228,434.21	1,702,629.71	688.0
V11	228,895.14	1,702,357.83	686.0
V12	228,435.78	1,702,614.73	688.0
P109	228,738.06	1,702,239.47	703.8
P110	228,660.45	1,702,293.34	700.0
P111	228,572.06	1,702,328.89	703.9
P112	228,679.61	1,702,477.39	699.0
P113	228,773.60	1,702,399.87	700.0
P114	228,820.82	1,702,537.03	700.0
P115	228,585.83	1,702,589.13	700.0
P116	228,505.19	1,702,829.10	697.7
P117	228,461.28	1,702,512.83	701.0
P118	228,402.79	1,702,553.42	698.5
P119	228,264.20	1,702,608.85	702.8
P120	228,443.26	1,702,703.72	700.0
P124	228,289.03	1,702,543.82	702.8
B26	228,608.01	1,702,572.75	706.0


- NOTES:
- ELEVATIONS CALLED OUT IN SECTION MAY ONLY APPLY ALONG THAT SECTION LINE; CHECK AGAINST PLAN.
  - THE LIMIT OF SUMPS IIA AND IIB ARE DEFINED BY THE 3:1 SLOPE BREAK; EVERYTHING DOWNSLOPE OF THE SLOPE BREAK IS TO BE CONSIDERED SLUMP IIA OR IIB AS APPROPRIATE

DETAIL PLAN 1  
PHASE IIA SUMP  
EXCAVATION GRADE  
SCALE 0 40 80 FEET


DETAIL PLAN 2  
PHASE IIB SUMP  
EXCAVATION GRADE  
SCALE 0 40 80 FEET




SECTION A  
SUMP IIA  
SCALE 0 20 40 FEET



SECTION C  
SUMP IIB  
SCALE 0 20 40 FEET



SECTION B  
SUMP IIA  
SCALE 0 20 40 FEET



SECTION D  
SUMP IIB  
SCALE 0 20 40 FEET




DATE	DESCRIPTION	BY	CHK'D BY
2/17/94	ISSUED FOR PHASE II CONSTRUCTION	RWR	ATP
0/13/90	ISSUED FOR PERMITTING	KKR	ATP

DESIGNED BY: G. J. KAVELI  
CHECKED BY: R. D. E.  
PROJECT: LANDFILL UNIT B-18  
CONSTRUCTION PLANS  
CWM-KETTLEMAN HILLS FACILITY  
KINGS COUNTY CALIFORNIA


GRADING DETAILS

ENVIRONMENTAL SOLUTIONS, INC.


DWG NO.	88-977	DATE PLOTTED	D-89977-014	REVISION	2
PROJECT	89-03-304.2.1	SHEET			14




SECTION A  
PERIMETER BENCH/ROAD  
3 | 8 | 5  
0 10 20 FEET  
SCALE




SECTION B  
ACCESS ROAD WITH BERM  
3 | 3 | 5  
0 10 20 FEET  
SCALE




SECTION C  
PHASE II ACCESS RAMP  
3 | 3 | 5  
0 10 20 FEET  
SCALE




SECTION B  
TEMPORARY LINER TRENCH AT PHASE I & II DIVIDING BERM  
3 | 5 | 7  
0 10 20 FEET  
SCALE




SECTION E  
ACCESS ROAD (TYP.)  
3 | 3 | 5  
0 10 20 FEET  
SCALE



SECTION F  
VADOSE TRENCH  
3 | 8 | 5  
0 10 20 FEET  
SCALE



SECTION B  
LINER EXTENSION AT PHASE I & II DIVIDING BERM  
8 | 1 | 5  
0 10 20 FEET  
SCALE




SECTION C  
AREA IIA AND IIB DIVIDING BERM  
8 | 1 | 5  
0 10 20 FEET  
SCALE




- NOTES
- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
  - SEE DETAIL 3.16.16 FOR COMPLETED ANCHOR TRENCH DETAILS. WIDTH OF TOP LINER TRENCH EXCAVATION MAY BE VARIED TO SUIT EXCAVATION AND BACKFILLING EQUIPMENT.
  - REMOVE THE MATERIAL TO 3.5 FEET BELOW ORIGINAL DESIGN GRADE TO ALLOW FOR PLACEMENT OF PHASE II LINER.

0 10 20 FEET  
SCALE















SECTION D  
PERIMETER BENCH/ROAD AT FILL (TYPICAL)  
8 | 1 | 5  
0 40 80 FEET  
SCALE



SECTION A  
PERIMETER BENCH/ROAD AT FILL (TYPICAL)  
3 | 8 | 5  
0 40 80 FEET  
SCALE


3/7/89	ISSUED FOR PHASE II CONSTRUCTION	K.K.	AKP
2/24/90	ISSUED FOR CONSTRUCTION	K.K.	AKP
1/24/90	ISSUED FOR BID	K.K.	AKP
0/7/90	ISSUED FOR PERMITTING	KAD	AKP
REV	DATE	ISSUED BY	APP'D BY
		K.J. Kavali	G. De
<p>LANDFILL UNIT B-18 CONSTRUCTION PLANS CWM1-KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA</p>			
CROSS SECTIONS			
ENVIRONMENTAL SOLUTIONS, INC.			
DES. NO.	PROJECT NUMBER	REVISION	
89-877	D-89977-FD015	3	
SCALE	SHEET NUMBER		
1"=10'	89-03-304.2.1		15




- NOTES**
- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
  - GEOTEXTILE SHALL BE TREVIRA 1125 OR EQUAL.
  - GEOTEXTILE SHALL BE TREVIRA 1155 OR EQUAL.
  - GEOCOMPOSITE SHALL BE TREVIRA 1125 HEAT BONDED TO POLYNET 3000.
  - GEOCOMPOSITE SHALL BE TREVIRA 1155 HEAT BONDED TO POLYNET 3000.
  - GEOCOMPOSITE SHALL BE TREVIRA 1125 OR 1155 HEAT BONDED TO POLYNET 3000 AT THE OPTION OF THE OWNER.
  - GEOTEXTILE SHALL ALWAYS BE FACING UP.
  - GEONET SHALL BE POLYNET 3000 OR EQUAL.
  - PROTECTIVE LINER SHALL BE REMOVED BY OPERATIONS STAFF PRIOR TO PLACEMENT OF OPERATIONS LAYER.
  - BASE OPERATIONS LAYER SHALL CONSIST OF SOILS EXCAVATED FROM ONSITE SOURCES. SOIL PARTICLE SIZE SHALL HAVE MAXIMUM DIAMETER OF 6 INCHES.
  - SIDE SLOPE OPERATIONS LAYER SHALL CONSIST OF SOILS EXCAVATED FROM ONSITE SOURCES. SOIL PARTICLE SIZE SHALL HAVE MAXIMUM DIAMETER OF 1 INCH.
  - DRAINAGE LAYER MATERIAL SHALL CONSIST OF A SUB-ANGULAR TO ROUNDED WASHED GRAVEL MEETING THE GRADATION REQUIREMENTS SPECIFIED IN SECTION 02924 OF THE SPECIFICATIONS.
  - LINER SYSTEM SCALES ARE EXAGGERATED FOR CLARITY.
  - ANCHOR TRENCH BACKFILL SHALL BE PLACED WITH RUBBER TIRE COMPACTION AND MOISTURE CONDITIONING.
  - WIDTH MAY VARY TO FIT CONSTRUCTION EQUIPMENT REQUIREMENTS.
  - THE PROTECTIVE LINER SHALL BE SUITABLE TO PREVENT THE OPERATIONS LAYER FROM CLOGGING THE SECONDARY LEACHATE CONTROL SYSTEM.
  - THE BOTTOM 12" OF PRIMARY CLAY LINER SHALL BE CONSTRUCTED IN ONE LIFT TO PROTECT UNDERLYING GEOSYNTHETIC LINER SYSTEM. THE UPPER 12" WILL HAVE A PERMEABILITY OF  $K_{10} = 1 \times 10^{-10}$  cm/sec.



3/7/91	ISSUED FOR PHASE II CONSTRUCTION AND GEOTEXTILE MODIFICATION	DVD	ASP
2/10/91	ISSUED FOR CONSTRUCTION	DVD	ASP
0/7/90	ISSUED FOR PERMITTING	DVD	ASP
PROJECT: LANDFILL UNIT B-18 CONSTRUCTION PLANS CMMI-KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA LINER DETAILS AND SECTIONS ENVIRONMENTAL SOLUTIONS, INC. FILE NUMBER: 89-977 PROJECT NUMBER: D-89977-FD016 SHEET: 3 AS NOTED: 89-03-304.2.1 SHEET: 16			



**SECTION A**  
 PHASE II ACCESS RAMP 9,10,16A  
 SCALE 0 5 10 FEET



**SECTION B**  
 PHASE II DIVISION 9,10,16A  
 SCALE 0 5 10 FEET

**NOTES**

- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
- SEE SHEET 16 FOR GEOSYNTHETIC MATERIAL NOTES.
- REMOVE PROTECTIVE LINERS AS WASTE IS ADVANCED UP THE SLOPE.
- LINER ELEMENT THICKNESSES AND SPACING EXAGGERATED FOR CLARITY.
- SELECT SUBBASE SHALL BE ONSITE MATERIAL WITH A MAXIMUM PARTICLE SIZE LESS THAN 1", CLASSIFIED AS SW OR SM (BY THE UNIFIED SOIL CLASSIFICATION SYSTEM), AND SHALL CONFORM TO THE FOLLOWING GRADATION:

SIEVE SIZE	PERCENT PASSING SIEVE
1"	100
NO. 4	70-100
NO. 10	40-90
NO. 40	20-60
NO. 200	9-20

THE MATERIAL SHALL BE SUBANGULAR AND SHALL ALSO CONFORM TO THE FOLLOWING REQUIREMENTS:

TEST	TEST METHOD NO.	REQUIREMENT
R-VALUE <sup>(1)</sup>	CALIF 301	60 (MIN.)
SAND EQUIVALENT	CALIF 217	20 (MIN.)









UPPER TWO FEET OF SELECT SUBBASE SHALL BE COMPACTED TO 90% OF MAXIMUM DRY DENSITY PER ASTM D1557.

<sup>(1)</sup> R-VALUE REQUIREMENT MAY BE WAIVED IF MATERIAL HAS AN SE > 30.



DATE	1/29/93	ADDED NEW SECTIONS 4-9, 10/16A, 8-9, 10/16A	GG/
NO.		DESCRIPTION	DATE
DESIGNED BY	LANDFILL UNIT B-18 CONSTRUCTION PLANS		
CHECKED BY	CWM-KETTLEMAN HILLS FACILITY		
APPROVED BY	KINGS COUNTY CALIFORNIA		
<b>PHASE II LINER DETAILS AND SECTIONS</b>			
ENVIRONMENTAL SOLUTIONS, INC.			
NO. 89-977	FILE NO. D-89977-016A	SHEET 1	
AS SHOWN	DATE 89-03-304.2.1	SHEET 16A	





**NOTES**

- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES
- SEE SHEET 16 FOR GEO SYNTHETIC MATERIAL NOTES
- EXTEND PAVEMENT UP SLOPE TO THE SAME ELEVATION AS THE OUTSIDE EDGE OF THE BERM.
- PROTECTIVE LINER IS REMOVED AS WASTE IS ADVANCED UP THE SLOPE



5	1/25/18	VOID ON SECTION E-9, 10/17	007
4	10/22/18	REDUCED ACCESS ROAD WIDTH TO 44' ELIMINATED PHASE II 4-8 DIVIDING BEAM REVISED DETENTION BASIN	KJK [Signature]
3	7/26/18	ISSUED FOR PHASE II CONSTRUCTION AND GEOTEXTILE MODIFICATION	DVD [Signature]
2	1/20/18	ISSUED FOR CONSTRUCTION	DVD [Signature]
0	7/31/10	ISSUED FOR PERMITTING	DVD [Signature]
DATE		DESCRIPTION	BY
DATE		APPROVED BY	APPROVED BY



DESIGNED BY: [Signature] CHECKED BY: [Signature] PREPARED BY: [Signature]

LANDFILL UNIT B-18  
CONSTRUCTION PLANS  
CWM-KETTLEMAN HILLS FACILITY  
KINGS COUNTY CALIFORNIA

**LINER DETAILS AND SECTIONS**

ENVIRONMENTAL SOLUTIONS, INC.

JOB NO. 89-977 PROJECT FILE NUMBER D-89977-FD017 SHEET NO. 4  
AS NOTED PROJECT FILE NUMBER 89-03-304.2.1 SHEET NO. 17



SURVEY CONTROL			
STATION	COORDINATE		ELEVATION
	N	E	
U1*	228,471.09	1,701,252.04	711.3
U2*	228,472.29	1,701,265.72	709.8
U3*	228,433.91	1,701,252.12	712.0
U4*	228,449.49	1,701,279.94	711.8
U6*	228,280.84	1,701,316.10	712.1
U7*	228,291.11	1,701,337.20	712.0
U9*	228,256.80	1,701,342.26	711.3
U10*	228,261.98	1,701,350.04	709.8
U3	228,524.96	1,701,166.33	729.8
P82	228,520.10	1,701,281.59	727.0
P83	228,437.99	1,701,322.05	724.9
U21	228,496.10	1,701,221.53	723.4
U22	228,501.43	1,701,281.90	723.4
U23	228,441.14	1,701,312.42	723.4
U24	228,397.52	1,701,237.60	723.4
P94	228,330.20	1,701,348.21	724.6
P95	228,247.54	1,701,411.89	727.4
U4	228,177.86	1,701,331.58	729.8
U25	228,266.89	1,701,285.64	723.4
U26	228,316.61	1,701,344.21	723.4
U27	228,255.24	1,701,380.13	723.4
U28	228,226.14	1,701,337.84	723.4

\* CONTROL POINTS FROM EXCAVATION GRADE



SURVEY CONTROL			
STATION	COORDINATE		ELEVATION
	N	E	
U11	228,480.16	1,701,240.95	716.9
U12	228,482.87	1,701,271.59	716.9
U13	228,427.50	1,701,246.79	716.9
U14	228,448.86	1,701,288.71	716.9
U15	228,282.45	1,701,307.99	716.9
U16	228,298.35	1,701,339.35	716.9
U17	228,259.23	1,701,362.22	716.9
U18	228,244.41	1,701,340.68	716.9

SECONDARY LINER (SEE NOTE 2)



DETAIL PLAN 1  
SUMP 1A




DETAIL PLAN 2  
SUMP 1B



DETAIL 1  
SUMP 1A



SECTION A  
SUMP 1B



- NOTES:
- ELEVATIONS SHOWN ARE TOP OF PRIMARY LINER.
  - SURVEY CONTROL GIVEN IN THE LOWER SURVEY CONTROL TABLE ARE CONTROL ELEVATIONS FOR THE TOP OF SECONDARY LINER. THE POINTS GIVEN ARE FOR THE BOTTOM OF SUMPS 1A AND 1B RESPECTIVELY.

REV	DATE	DESCRIPTION	BY	CHK'D BY
3	1/28/93	MODIFIED CALLOUT FOR DETAIL 1-18/18 CLARIFIED DIMENSIONS OF HDPE SUMP B CHAMBER	GGI	
2	1/2/91	ISSUED FOR CONSTRUCTION	RVH	
0	7/31/90	ISSUED FOR PERMITTING	RVH	


DESIGNED BY	CHECKED BY	APPROVED BY



LANDFILL UNIT B-18  
CONSTRUCTION PLANS  
CMMI-KETTLEMAN HILLS FACILITY  
KINGS COUNTY CALIFORNIA

TYPICAL SUMP PLANS

ENVIRONMENTAL SOLUTIONS, INC.

DWG NO.	REV. NO.	DATE	SHEET NO.
89-877	D-89977-FD018		3
SCALE	DWG FILE NUMBER		
NONE	89-030304.2.1		18






**SURVEY CONTROL**

STATION	COORDINATE		ELEVATION
	N	E	
P203	228,742.72	1,702,240.77	709.8
P204	228,742.04	1,702,248.75	708.4
P205	228,787.63	1,702,416.72	---
P206	228,662.09	1,702,296.70	707.8
P207	228,577.67	1,702,330.48	709.8
P208	228,680.45	1,702,472.58	705.0
P209	228,640.86	1,702,528.22	703.7
P214	228,501.24	1,702,828.46	706.8
P215	228,459.64	1,702,518.29	706.8
P216	228,404.49	1,702,556.57	705.3
P217	228,265.05	1,702,613.50	708.4
P218	228,263.24	1,702,613.06	708.7
P219	228,456.48	1,702,721.58	---
U71	228,717.66	1,702,305.45	700.8
U72	228,740.62	1,702,389.91	700.8
U73	228,686.35	1,702,438.70	700.8
U74	228,637.78	1,702,348.43	699.5
U75	228,705.42	1,702,373.01	699.5
U76	228,707.51	1,702,380.73	699.5
U77	228,701.55	1,702,374.05	699.5
U78	228,703.65	1,702,381.78	699.5
U79	228,706.99	1,702,378.80	698.0
U80	228,447.43	1,702,558.94	700.8
U81	228,483.28	1,702,625.56	700.8
U82	228,438.84	1,702,667.57	700.8
U83	228,344.51	1,702,814.31	700.8
U84	228,409.42	1,702,812.82	699.5
U85	228,416.39	1,702,816.56	699.5
U86	228,414.42	1,702,820.04	699.5
U87	228,407.45	1,702,816.11	699.5
U88	228,409.09	1,702,817.28	698.0

**DETAIL PLAN 1 SURVEY CONTROL**

STATION	COORDINATE		ELEVATION
	N	E	
U61	228,705.89	1,702,332.84	694.0
U62	228,719.71	1,702,383.76	694.0
U63	228,691.50	1,702,409.18	694.0
U64	228,662.89	1,702,355.97	694.0
U65	228,439.89	1,702,584.05	694.0
U66	228,460.22	1,702,621.84	694.0
U67	228,436.04	1,702,644.70	694.0
U68	228,382.91	1,702,614.70	694.0

\* STATIONS U61-U68 ARE SECONDARY LINER CONTROL POINTS AND RELATE TO CONTROL POINTS U71-U74 AND U81-U84.



**NOTES:**  
 1. SECTIONS SHOWN ON SHEET 19A B 20A ARE TYPICAL OF BOTH SUMPS. PLAN VIEW DIMENSIONS TAKE PRECEDENCE OVER DIMENSIONS FOUND ON TYPICAL SECTION VIEWS.





3	1/25/93	MODIFIED GRADING PER CWM1 MODIFIED SURVEY CONTROL. ADDED CALLOUTS FOR DETAIL PLAN 1-18A/20A AND SECTIONS A-18A/19A, B-18A/19A, A-18A/20A	GGI
2	7/28/91	ISSUED FOR PHASE II CONSTRUCTION	RWH


DRAWN BY: \_\_\_\_\_ CHECKED BY: \_\_\_\_\_ APPROVED BY: \_\_\_\_\_  
**LANDFILL UNIT B-18 CONSTRUCTION PLANS**  
**CWM1-KETTLEMAN HILLS FACILITY**  
 KINGS COUNTY CALIFORNIA  
**PHASE II**  
**PRIMARY SUMP GRADING DETAILS**  
 ENVIRONMENTAL SOLUTIONS, INC.

PROJECT NO.	89-877	DATE	D-89977-SUO18	SHEET NO.	3
AS NOTED	89-03-304.2.1				18A


CONTROL POINTS U75-U78 ARE EDGE OF CLAY, BUT DO NOT ACCOUNT FOR BEVELED EDGES




SECTION A  
VADOSE SUMP DETAIL  
19/19  
N.T.S.



DETAIL 1  
VADOSE SUMP DETAIL  
19.20A/19  
V.T.S.



DETAIL 2  
SECONDARY SUMP  
19/19  
V.T.S.



DETAIL 3  
PIPE PERFORATION  
19/19  
N.T.S.

SECTION A  
SUMP B  
COMBINED SECTION  
19/19  
0 5 10 FEET  
SCALE

- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
- THE DIMENSIONS FOR THE SUMP CENTERLINES AND TRENCH WIDTHS ARE CONTROLLED BY THE SUMP EXCAVATION GRADE CONTROL LINES. THESE DIMENSIONS ARE TO BE LAID OUT AT THE CORNER WHERE THE VADOSE TRENCH AND SUMP EXCAVATION COINCIDE (SEE SHEET 18).
- SIDE SLOPE RISER PIPE PERFORATIONS SHALL BE 1/2" DIAMETER HOLES EVENLY SPACED ALONG THE BOTTOM 3' OF THE RISER PIPE EVERY 6" IN THE LONGITUDINAL DIRECTION. THE PERFORATIONS SHALL BE SEPARATED BY 90 DEGREES IN THE TRANSVERSE DIRECTION. WRAP THE PERFORATED SECTION WITH TWO LAYERS OF GEOTEXT.
- LAP DRAINAGE LAYER GEOCOMPOSITE OVER HDPE FLATSTOCK SIDEWALLS A MINIMUM OF 6 INCHES.

3/29/93	ADDED NOTE 4	SGI
	CLARIFIED SUMP HOPE BOX	
2/10/93	ISSUED FOR CONSTRUCTION	RVH
0/31/90	ISSUED FOR PERMITTING	RVH
REV	DATE	REVISION




DESIGNED BY: RICHARD D. ELSON  
 CHECKED BY: [ ]  
 APPROVED BY: [ ]  
**LANDFILL UNIT B-18  
 CONSTRUCTION PLANS  
 CWMI-KETTEMAN HILLS FACILITY  
 KINGS COUNTY CALIFORNIA**


**SUMP AND RISER DETAILS**

ENVIRONMENTAL SOLUTIONS, INC.

PROJECT NO.	89-977	NET FILE NUMBER	D-89977-FD019	REVISION	3
SCALE	AS NOTED	DATE/TIME REVISION	89-03-304.1.2	SHEET	19




SECTION A  
TYPICAL PHASE II PRIMARY SUMP AND SIDESLOPE RISER




SECTION B  
TYPICAL PHASE II VADOSE SUMP AND SIDESLOPE RISER


- NOTES:
- SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.
  - WRAP CARBON STEEL PIPE WITH TWO LAYERS OF TAPECOAT OR APPROVED EQUAL.
  - DUE TO BEND IN SECTION THE VADOSE TRENCH & PRIMARY SUMP RISER TRENCH ARE SHOWN OUT OF PLANE WITH RESPECT TO EACH OTHER.
  - VADOSE SUMP GRAVEL TERMINATES BY FEATHERING INTO 5:1 SLOPE INSIDE THE VADOSE SUMP RISER PIPE RUNS.



DATE	REVISION	BY	CHKD
2/10/94	REVISED NOTES FOR PHASE II RISERS AND SUMPS	GGJ	GGJ
1/28/93	ADDED SECTIONS A-18A/19A, B-18A/19A	GGJ	GGJ
DATE	DESCRIPTION	BY	CHKD
DATE	DESCRIPTION	BY	CHKD
DRAWN BY: _____ CHECKED BY: _____ APPROVED BY: _____ <b>LANDFILL UNIT B-18</b> <b>CONSTRUCTION PLANS</b> <b>CWMI-KETTLEMAN HILLS FACILITY</b> KINGS COUNTY CALIFORNIA			
<b>PHASE II</b>			
<b>SUMP AND RISER DETAILS</b>			
ENVIRONMENTAL SOLUTIONS, INC.			
PROJECT NO.	DIST. FILE NO.	REVISED	
88-877	D-89977-SU019	2	
SCALE	DATE	SHEET	
1"=5'	89-03-304.2.1	19A	



SECTION B  
PRIMARY SUMP  
AND RISER





SECTION C  
SECONDARY SUMP  
AND RISER  
AT PIPE TRENCH

NOTES:  
1. SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.  
2. WRAP CARBON STEEL PIPE WITH TWO LAYERS OF TAPECOAT OR APPROVED EQUAL.



0 5 10 FEET  
SCALE

DATE	DESCRIPTION	BY	CHECKED
2/1/08	ISSUED FOR CONSTRUCTION	RWH	SKD
0/1/08	ISSUED FOR PERMITTING	RWH	SKD
LANDFILL UNIT B-18 CONSTRUCTION PLANS CWM1-KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA <b>SUMP AND RISER DETAILS</b>			
ENVIRONMENTAL SOLUTIONS, INC. 89-877 D-89977-FD020 2 1"=5' 89-03-304.2.1 20			




SECTION A  
SUMP 118 18A/20A

0 5 10 FEET  
SCALE

DETAIL PLAN  
PHASE IIA SUMP  
TOP OF PRIMARY LINER 18A/20A

0 5 10 FEET  
SCALE




SECTION A  
SUMP 11A 20A/20A




0 5 10 FEET  
SCALE




REV	DATE	DESCRIPTION	BY	CHECKED BY
1	1/25/93	ADDED DETAIL PLAN 1-18A/20A AND SECTIONS A-18A/20A, A-20A/20A	GGI	
DESIGNED BY: _____ CHECKED BY: _____ APPROVED BY: _____ <b>LANDFILL UNIT B-18 CONSTRUCTION PLANS</b> CWM-KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA				
<b>PHASE II SUMP AND RISER DETAILS</b>				
ENVIRONMENTAL SOLUTIONS, INC.				
JOB NO.	REV. FILE NUMBER	REV. FILE NUMBER	SHEET	
89-877	D-89977-SUO20		1	
SCALE	DATE	FILE NUMBER	SHEET	
AS SHOWN	89-03-304.2.1		20A	




DETAIL 1  
VERTICAL RISER FOUNDATION  
SCALE 0 1/2 1 FOOT



DETAIL 2  
VERTICAL RISER BASE  
SCALE 0 1/2 1 FOOT




DETAIL 1  
VERTICAL RISER FOUNDATION




DETAIL 4  
VERTICAL RISER PIPE JOINT (TYPICAL)  
SCALE 0 1 2 FEET


NOTE:  
VERTICAL SECTION OF STAINLESS STEEL RISER SHALL BE PERFORATED WITH 8 ROWS OF 1/2" DIA. HOLES SPACED 6" APART VERTICALLY AND 60" APART RADIALLY. PERFORATED SECTION OF RISER SHALL BE WRAPPED WITH TWO LAYERS OF GEONET.



DETAIL PLAN 3  
STAINLESS STEEL PLATE 2|2|2|  
SCALE 0 1 2 FEET



DETAIL PLAN 2  
STEEL PLATE 2|2|2|  
SCALE 0 1 2 FEET



SECTION B  
VERTICAL RISER 19, 20A|2|  
SCALE 0 1 2 FEET

NOTES  
1. SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.

REV	DATE	DESCRIPTION	BY	CHK'D BY
3	1/29/93	MODIFIED CALLOUT FOR SECTION B-19/21 MODIFIED VERTICAL RISER BASE OF DETAIL 2-2 2 2	GGI	
2	1/2/91	ISSUED FOR CONSTRUCTION	KAB	
0	7/31/90	ISSUED FOR PERMITTING	KJK	


SCALE	DATE	DESCRIPTION	BY	CHK'D BY
AS NOTED	89-977	0-89977-FD021		3
				21




LANDFILL UNIT B-18  
CONSTRUCTION PLANS  
CUMI-KETTLEMAN HILLS FACILITY  
KINGS COUNTY CALIFORNIA

ENVIRONMENTAL SOLUTIONS, INC.







**SECTION A**  
LEACHATE HOLDING TANK  
22/22  
SCALE  
0 4 8 FEET




**DETAIL 1**  
THIRD CONTAINMENT OVERFLOW  
22/22  
SCALE  
0 4 8 FEET




**SECTION C**  
PRIMARY RISER PIPE  
22/22  
SCALE  
0 4 8 FEET




**SECTION A**  
SUMP IA, IB, AND IIA  
SIDE SLOPE RISER PIPES  
5, 10/22  
SCALE  
0 2 4 FEET  
NOTE: SECTION CUT PERPENDICULAR TO SLOPE



**DETAIL 3**  
SIDE SLOPE RISER TRENCH CLAY PLUG (TYP.)  
22/22  
SCALE  
0 2 4 FEET



**DETAIL 3**  
(TYPICAL)  
22/22  
SCALE  
0 4 8 FEET




**PLAN**  
LANDFILL UNIT B-18  
CONSTRUCTION PLANS  
22/22  
SCALE  
0 4 8 FEET

**NOTES:**  
1. SUMP IA RISER PAD IS REFLECTED IMAGE OF SUMP IB RISER PAD.  
2. FOR SUMP IB RISER PAD DETAIL SEE SHEET 22A.


**NOTES:**  
1. FRONT EDGE OF SLAB SHALL BE CONSTRUCTED PARALLEL TO THE TOP OF SLOPE.  
2. ACTUAL PIPE SPACING AND ANGLE RELATIVE TO THE EDGE OF THE SLAB MAY VARY SLIGHTLY DUE TO PAD ALIGNMENT AND AS BUILT CONDITIONS.



3	10/02/93	ADDED SECOND SUMP DETAILS, REV. RISER AND PAD DETAIL FOR PHASE I	R.MAY	R.D.
2	11/27/90	ISSUED FOR CONSTRUCTION	SEA	CCP
0	10/31/90	ISSUED FOR PERMITTING	R.MAY	1007
REV.	DATE	DESCRIPTION	DESIGNED BY	CHECKED BY
DRAWN BY R.MAY		CHECKED BY	APPROVED BY ROE	
<b>LANDFILL UNIT B-18 CONSTRUCTION PLANS CIVIL-KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA</b>				
<b>SUMP AND RISER DETAILS</b>				
<b>ENVIRONMENTAL SOLUTIONS, INC.</b>				
JOB NO. 89-977	ESTIMATE NUMBER D-89977 FD022	REVISION 3		
SCALE AS NOTED	DRAWING NUMBER 89-03-304.2.1	SHEET 22		




DETAIL PLAN 1  
SECONDARY SUMP 11A  
SCALE 0 20 40 FEET




DETAIL PLAN 2  
SECONDARY SUMP 11B  
SCALE 0 20 40 FEET

STATION	COORDINATE		ELEVATION
	N	E	
U61	228,705.89	1,702,332.84	694.0
U62	228,719.71	1,702,383.76	694.0
U63	228,691.50	1,702,409.16	694.0
U64	228,662.89	1,702,355.97	694.0
U65	228,439.89	1,702,584.05	694.0
U66	228,460.22	1,702,621.84	694.0
U67	228,436.04	1,702,644.70	694.0
U68	228,382.91	1,702,614.70	694.0
U91	228,699.06	1,702,355.21	693.0
U92	228,700.10	1,702,359.07	693.0
U93	228,696.24	1,702,360.12	693.0
U94	228,695.20	1,702,356.26	693.0
U95	228,429.86	1,702,622.17	693.0
U96	228,433.34	1,702,624.13	693.0
U97	228,431.37	1,702,627.62	693.0
U98	228,427.89	1,702,625.65	693.0



SECTION A  
SUMP 11B SIDE SLOPE RISER PIPES  
SCALE 0 2 4 FEET

NOTE: SECTION CUT PERPENDICULAR TO SLOPE




DETAIL 2  
COLLECTION SUMP 22A/22  
SCALE 0 4 8 FEET


- NOTES:
- FRONT EDGE OF SLAB SHALL BE CONSTRUCTED PARALLEL TO THE TOP OF SLOPE.
  - ACTUAL PIPE SPACING AND ANGLE RELATIVE TO THE EDGE OF THE SLAB MAY VARY SLIGHTLY DUE TO PAD ALIGNMENT AND AS BUILT CONDITIONS.




1	10/22/93	ISSUED FOR CONSTRUCTION	GG	DLA
0	7/16/93	ISSUED FOR CLIENT REVIEW	R.MAY	DLA
REV	DATE	DESCRIPTION	BY	CHK'D
BY	R.MAY	DESIGNED	L. BROWN	CHECKED
<b>CONSTRUCTION DRAWINGS</b> <b>LANDFILL UNIT B-18</b> <b>CYMI-KETTLEMAN HILLS FACILITY</b> KINGS COUNTY CALIFORNIA				
<b>PHASE II SUMPS AND CELL 11B</b> <b>SIDE SLOPE RISER DETAILS</b>				
<b>ENVIRONMENTAL SOLUTIONS, INC.</b>				
NO. 89-877	NET FILE NUMBER	D-89977-FD022A	1	
AS NOTED	DATE FILE NUMBER	89-03-304.2.1	22A	




**SECTION A**  
PHASE II EMBANKMENT AND RETENTION BASIN  
SCALE: 0 50 100 FEET



**SECTION A**  
PHASE I INTERIM SLOPE CONFIGURATION  
SCALE: 0 10 20 FEET



**SECTION A**  
PERIMETER BENCHROAD 5.1023  
SCALE: 0 10 20 FEET




**SECTION B**  
PHASE I & II DIVIDING BERM  
SCALE: 0 10 20 FEET




NOTES  
1. SEE SHEET 1 FOR LEGEND AND GENERAL NOTES.

3	7/26/91	ISSUED FOR PHASE II CONSTRUCTION	50%	AKP
2	1/2/91	ISSUED FOR CONSTRUCTION	50%	AKP
0	7/31/89	ISSUED FOR PERMITTING	DVD	AKP
REV	DATE	DESCRIPTION	BY	CHK
PREPARED BY: R. J. Kowalski CHECKED BY: G. K. Parkin CONSTRUCTION DRAWINGS LANDFILL UNIT B-18 CWM1-KESTLERMAN HILLS FACILITY ELINGS COUNTY CALIFORNIA MISCELLANEOUS CROSS SECTIONS ENVIRONMENTAL SOLUTIONS, INC. DRAWING NO. 89-877 FILE NO. D-89977-FD023 SHEET NO. 3 AS NOTED 89-03-304.2.1 23				



SECTION A  
DRAINAGE SECTION THROUGH DITCH AND ROAD  
SCALE 0 10 20 FEET



DETAIL 1  
DRAINAGE DETAIL AT CUT SLOPE (TYP.)  
SCALE 0 3 6 FEET



NO.	DATE	DESCRIPTION	BY	CHECKED BY
2	1/27/98	ISSUED FOR CONSTRUCTION	KAB	KAP
1	5/24/90	ISSUED FOR BID	KAB	KAP
DESIGNED BY	DRAWN BY	CHECKED BY	APPROVED BY	
K. Benac	K. Benac	RDE	RDE	
<b>LANDFILL UNIT B-18</b> <b>CONSTRUCTION PLANS</b> CWM1-KETTLEMAN HILLS FACILITY KINGS COUNTY CALIFORNIA				
<b>DRAINAGE DETAILS</b>				
ENVIRONMENTAL SOLUTIONS, INC.				
PROJECT NO.	DATE	SCALE	SHEET	TOTAL SHEETS
88-977	D-89977-FD024	AS NOTED	2	24

# SURVEY CONTROL FOR PHASE I EXCAVATION AND BACKFILL PLAN (SHEET 3)

POINTS OF INTERSECTION									CONTROL POINTS									CURVE DATA										
POINT	DESCRIPTION	NORTHING	EASTING	ELEV.	POINT	DESCRIPTION	NORTHING	EASTING	ELEV.	POINT	DESCRIPTION	NORTHING	EASTING	ELEV.	CURVE NO.	DESCRIPTION	LOCATION OF P.I.				D	R	L	T				
																		NORTHING	EASTING	D	R	L	T					
P1	N.W. CORNER TOP PHASE I EXCAVATION	228,070.82	1,700,865.22	846.0	A2	NORTH ACCESS ROAD	229,248.42	1,701,606.92	836.2	A1	NORTH ACCESS ROAD	229,141.05	1,701,443.93	841.0	1	N.W. CORNER TOP PHASE I EXCAVATION	229,070.82	1,700,865.22	93°05'54"	48.80'	80.92'	52.57'						
P2	WEST SIDE TOP PHASE I EXCAVATION	228,230.09	1,700,969.19	840.0	A3	NORTH ACCESS ROAD AND CLAY PROCESS ACCESS ROAD	228,812.74	1,701,350.82	780.0	A4	END CLAY PROCESS AREA ROAD	228,874.23	1,702,269.34	755.1	2	WEST SIDE TOP PHASE I EXCAVATION	228,230.09	1,700,969.19	34°22'42"	48.80'	29.88'	15.41'						
P3	S.W. CORNER TOP PHASE I EXCAVATION	227,328.27	1,701,785.03	832.0	A4	NORTH ACCESS ROAD AND CLAY PROCESS ACCESS ROAD	228,580.82	1,702,136.83	710.0	A7	END CLAY PROCESS AREA ROAD	228,535.81	1,702,174.20	758.7	3	S.W. CORNER TOP PHASE I EXCAVATION	227,328.27	1,701,785.03	88°44'08"	48.80'	73.68'	45.44'						
P4	S.E. CORNER TOP PHASE I EXCAVATION	227,446.16	1,702,217.87	830.0	A6	END NORTH ACCESS ROAD	228,158.44	1,701,781.74	767.4	A8	END SOUTH ACCESS ROAD	228,805.82	1,702,806.25	750.0	4	OUTSIDE EDGE BENCHROAD	228,545.75	1,700,889.58	14°52'24"	50.00'	12.96'	6.53'						
P5	N.E. CORNER TOP PHASE I EXCAVATION	228,111.91	1,701,480.38	840.0	A8	SOUTH ACCESS ROAD	228,082.19	1,702,645.08	790.0	A11	END WELL ACCESS ROAD	227,600.43	1,702,241.26	--	5	OUTSIDE EDGE BENCHROAD	228,409.54	1,700,870.78	25°48'23"	110.00'	48.54'	25.28'						
P6	N.W. TOE AREA 1A	228,868.31	1,701,130.21	731.2	A10	SOUTH ACCESS ROAD	227,610.79	1,702,236.08	830.0	A13	END WELL ACCESS ROAD	227,311.50	1,701,864.04	--	6	OUTSIDE EDGE BENCHROAD	228,202.72	1,700,837.61	12°38'04"	110.00'	24.19'	12.15'						
P7	N.W. TOP AREA 1A SUMP	228,528.63	1,701,181.87	724.0	A12	SOUTH ACCESS ROAD	227,399.04	1,702,065.83	860.0	B1	NORTH END PHASE II BENCH	228,952.51	1,701,317.87	764.0	7	OUTSIDE EDGE BENCHROAD	228,025.07	1,701,044.08	23°50'51"	110.00'	48.62'	25.24'						
P8	N.E. TOP AREA 1A SUMP	228,523.46	1,701,294.07	721.0	B2	L.P.F.L. PHASE II BENCH	228,370.78	1,701,801.48	790.8	B3	SOUTH END PHASE II BENCH	227,428.41	1,701,991.39	84.1	8	OUTSIDE EDGE BENCHROAD	227,946.58	1,701,158.74	15°00'10"	50.00'	13.09'	6.58'						
P9	S.E. TOP AREA 1A SUMP	228,433.96	1,701,327.34	718.8	C1	N.W. TOE CLAY PIT	228,733.64	1,701,619.98	840.0	B4	WEST END SUMP DIVIDING BERM	228,308.29	1,701,189.02	730.0	9	N.W. TOE AREA 1A	228,868.31	1,701,130.21	98°30'07"	50.00'	84.21'	56.02'						
P10	S.E. TOE AREA	228,448.26	1,701,418.18	720.9	C2	S.W. TOE CLAY PIT	228,545.82	1,701,821.36	860.0	B5	EAST END SUMP DIVIDING BERM	228,441.75	1,701,462.05	730.0	10	N.E. TOE AREA 1A	228,876.30	1,701,243.74	81°33'34"	50.00'	53.72'	28.78'						
P11	N.E. TOE AREA 1A	228,879.30	1,701,243.74	730.5	C3	S.E. TOE CLAY PIT	228,583.21	1,701,854.25	840.0	C5	CLAY PIT ROAD	228,554.38	1,702,081.13	760.0	11	S.W. TOP DIVIDING BERM AREA 1A	228,308.29	1,701,199.02	115°48'48"	50.00'	101.00'	78.75'						
P12	S.W. TOP AREA 1B SUMP	228,171.94	1,701,331.26	724.0	C4	N.E. TOE CLAY PIT	228,771.02	1,701,654.84	860.0	C8	CLAY PIT ROAD AT BENCH	228,567.02	1,701,710.34	720.0	12	S.E. TOE AREA 1A	228,446.26	1,701,418.18	92°27'50"	50.00'	80.89'	52.28'						
P13	WEST TOE AREA 1B	228,073.11	1,701,408.68	726.8	C6	CLAY PIT ROAD	228,419.26	1,701,950.01	758.9	C13	INSIDE EDGE END 780 BENCH	228,798.28	1,701,902.98	778.8	13	N.W. TOP DIVIDING BERM AREA 1B	228,308.29	1,701,199.02	109°10'55"	50.00'	95.28'	78.38'						
P14	WEST TOE AREA 1B	227,893.85	1,701,588.08	731.8	C7	CLAY PIT ROAD	228,325.50	1,701,829.08	748.9	C15	INSIDE EDGE END 780 BENCH	228,980.86	1,701,545.89	778.6	14	N.E. TOE AREA 1B	228,401.18	1,701,452.95	92°06'05"	50.00'	80.37'	51.87'						
P15	S.W. TOE AREA 1B	227,812.04	1,701,818.73	740.0	C9	N.W. CORNER BENCH	228,726.96	1,701,486.56	720.0	CP1	CONTROL POINT CLAY PROCESS GRADING	228,817.15	1,702,461.52	750.0	15	S.W. TOE AREA 1B	227,625.57	1,701,808.15	63°49'04"	50.00'	58.89'	31.13'						
P16	S.E. TOE AREA 1B	227,843.18	1,701,861.42	738.9	C10	N.E. CORNER BENCH	228,896.86	1,701,642.93	710.0	CP2	CLAY PROCESS ACCESS ROAD	228,748.35	1,702,839.32	750.0	16	S.E. TOE AREA 1B	227,857.27	1,701,853.03	60°24'37"	50.00'	52.72'	28.11'						
P17	EAST TOE AREA 1B AT RAMP	228,136.88	1,701,567.88	726.8	C11	S.E. CORNER BENCH	228,580.09	1,701,982.41	720.0	CP3	EAST SIDE CLAY PROCESS AREA	228,810.32	1,702,784.77	750.0	17	INSIDE EDGE ACCESS RAMP	227,631.87	1,701,856.81	72°45'17"	50.00'	63.48'	36.81'						
P18	EAST TOE AREA 1B AT RAMP	228,151.99	1,701,601.75	727.7	C12	S.W. CORNER BENCH	228,412.40	1,701,826.04	720.0	CP11	NORTH SIDE CLAY PROCESS AREA	229,104.44	1,702,487.92	750.0	18	OUTSIDE EDGE ACCESS RAMP	227,422.13	1,701,796.18	85°06'54"	50.00'	74.28'	46.91'						
P19	N.E. TOE AREA 1B	228,401.18	1,701,452.95	721.2	C14	INSIDE EDGE N.E. CORNER 780 BENCH	229,064.74	1,701,615.07	778.5	S1	OUTSIDE EDGE BENCHROAD	228,545.75	1,700,889.58	843.5	19	N.W. TOE CLAY PIT	228,733.64	1,701,619.98	90°00'00"	25.00'	38.27'	25.00'						
P20	N.E. TOP AREA 1B SUMP	228,334.73	1,701,360.02	718.8	CP4	S.E. CORNER CLAY PROCESS AREA	228,109.13	1,702,593.00	758.0	S2	OUTSIDE EDGE BENCHROAD	227,846.98	1,701,158.74	839.0	20	N.E. TOE CLAY PIT	228,771.02	1,701,654.84	90°00'00"	25.00'	39.27'	25.00'						
P21	S.E. TOP AREA 1B SUMP	228,248.82	1,701,417.46	721.4	CP5	WEST SIDE CLAY PROCESS AREA	228,580.82	1,702,152.99	758.2	T1	END RAMP LINER TRENCH	228,103.67	1,701,614.80	729.3	21	S.W. TOE CLAY PIT	228,545.82	1,701,821.36	90°00'00"	25.00'	38.27'	25.00'						
S3	OUTSIDE EDGE BENCHROAD	228,409.54	1,700,870.78	843.3	CP6	WEST SIDE CLAY PROCESS AREA	228,557.56	1,702,191.17	758.3	T2	END RAMP LINER TRENCH	227,832.45	1,701,848.38	758.0	22	S.E. TOE CLAY PIT	228,583.21	1,701,854.25	90°00'00"	25.00'	38.27'	25.00'						
S4	OUTSIDE EDGE BENCHROAD	228,202.72	1,700,937.81	841.2	CP7	WEST SIDE CLAY PROCESS AREA	228,584.17	1,702,182.29	758.5	T3	END RAMP LINER TRENCH	227,846.13	1,701,992.58	787.3	23	CLAY PIT ROAD	228,419.26	1,701,950.01	8°03'34"	50.00'	7.00'	3.52'						
S5	OUTSIDE EDGE BENCHROAD	228,023.07	1,701,044.08	840.8	CP8	WEST SIDE CLAY PROCESS AREA	228,776.89	1,702,070.19	758.4	T4	END RAMP LINER TRENCH	227,767.94	1,701,418.47	831.8	24	CLAY PIT ROAD	228,325.50	1,701,829.08	84°38'12"	40.00'	88.05'	43.30'						
R1	WEST END ACCESS RAMP	227,731.37	1,701,429.30	831.8	CP9	WEST SIDE CLAY PROCESS AREA	228,854.14	1,702,299.41	754.3	T5	SLOPE BREAK IN LINER TRENCH	227,747.43	1,701,442.83	831.8	25	N.E. CORNER 780 BENCH	229,064.74	1,701,615.07	90°00'00"	50.00'	78.54'	50.00'						
R2	S.W. CORNER ACCESS RAMP	227,422.13	1,701,796.18	793.2	CP10	NORTH SIDE CLAY PROCESS AREA	229,100.49	1,702,363.51	752.3	T6	END TOP LINER TRENCH	229,100.93	1,701,318.44	837.9	26	NORTH ACCESS ROAD	229,111.01	1,701,480.38	37°44'41"	112.00'	73.78'	38.29'						
R3	S.E. CORNER ACCESS RAMP	227,821.09	1,701,985.23	770.7						T7	END TOP LINER TRENCH	227,538.02	1,702,071.53	821.8	27	NORTH ACCESS ROAD	229,268.42	1,701,608.92	73°17'51"	77.50'	128.05'	84.09'						
R4	EAST SIDE ACCESS RAMP	227,804.27	1,701,996.83	764.0						T8	EDGE ACCESS ROAD	228,184.53	1,701,788.06	837.9	28	EDGE ACCESS ROAD	228,836.32	1,701,947.28	63°53'38"	50.00'	55.78'	31.18'						
R5	EAST SIDE ACCESS RAMP	228,151.00	1,701,801.75	727.7						T9	EDGE ACCESS ROAD	228,800.68	1,701,963.72	115°33'08"	50.00'	100.84'	78.32'											
										T10	EDGE ACCESS ROAD	228,510.34	1,702,126.89	51°54'40"	50.00'	45.30'	24.34'											
										T11	EDGE ACCESS ROAD	228,184.53	1,701,788.06	837.9	29	EDGE ACCESS ROAD	228,184.53	1,701,788.06	110°51'48"	50.00'	94.79'	72.80'						
										T12	EDGE ACCESS ROAD	228,132.12	1,701,785.48	86°08'14"	50.00'	60.33'	34.40'											
										T13	EDGE ACCESS ROAD	227,866.17	1,702,040.33	72°43'18"	50.00'	63.48'	36.81'											
										V1	START AREA 1A VADOSE TRENCH	228,871.27	1,701,190.75	728.2	30	NORTH ACCESS ROAD	227,818.30	1,702,232.32	99°37'31"	100.00'	173.80'	118.38'						
										V2	START AREA 1A VADOSE TRENCH	227,836.82	1,701,837.36	737.7	31	ACCESS ROAD	227,836.82	1,702,257.26	9°57'38"	400.00'	69.54'	34.88'						
															32	ACCESS ROAD	228,082.19	1,702,465.08	30°48'04"	400.00'	215.03'	118.18'						
															33	EAST SIDE CLAY PROCESS AREA	228,761.39	1,702,862.78	130°00'03"	30.00'	68.07'	64.34'						
															34	NORTH SIDE CLAY PROCESS AREA	229,100.49	1,702,363.51	70°57'28"	50.00'	41.82'	35.84'						
															35	WEST SIDE CLAY PROCESS AREA	228,580.82	1,702,152.99	65°38'58"	50.00'	39.88'	21.88'						
															36	SOUTH SIDE CLAY PROCESS AREA	228,108.13	1,702,583.00	111°08'10"	50.00'	94.98'	72.84'						

1) L.P.F.L. - LOW POINT OF FLOW LINE  
 \* LOCATION GIVEN IN TABLE SUPERSEDES THE LOCATION ON THE DRAWING.  
 -- MATCH GRADE AT PERIMETER BENCHROAD



2 11/2/91	ISSUED FOR CONSTRUCTION	J.A.	KFP
1 9/28/90	ISSUED FOR BID	RVH	KFP
0 6/1/89	ISSUED FOR PERMITTING	MD	KFP
REV	DATE	DESCRIPTION	BY
1	02/21/91	REVISION	RVH
<b>LANDFILL UNIT B-18</b> <b>CONSTRUCTION PLANS</b> <b>UNIT 1-KITTLEMAN HILLS FACILITY</b> <b>KINGS COUNTY CALIFORNIA</b>			
<b>SURVEY CONTROL</b>			
ENVIRONMENTAL SOLUTIONS, INC.			
NO. 88-877	PROJECT NO. D-89977-FD025	REVISED 2	
AS NOTED	89-03-304.1.2	SHEET	25

**APPENDIX A.2**  
**PHASE III AND FINAL CLOSURE DRAWINGS**

# CONSTRUCTION DRAWINGS FOR THE B-18 CLASS I LANDFILL PHASE III EXPANSION AND FINAL CLOSURE

KETTLEMAN HILLS FACILITY  
KINGS COUNTY, CALIFORNIA  
NOVEMBER 2008

PREPARED FOR:  
CHEMICAL WASTE MANAGEMENT

REV	DATE	DESCRIPTION	DESIGN	DRAWN	REVIEW
A	9/16/2008	ISSUED FOR PERMITTING MEETING	KJK	KJK	SGS
B	1/10/2009	ISSUED FOR PERMITTING	KJK	KJK	SGS
C	5/2/2011	RE-ISSUED FOR PERMITTING	KJK	KJK	RH

**Golder Associates**  
230 Commerce, Suite 200  
Irvine, California 92602  
(714) 508-4400


**CHEMICAL WASTE MANAGEMENT  
KETTLEMAN HILLS FACILITY**  
35251 OLD SKYLINE ROAD  
KETTLEMAN CITY, CALIFORNIA 93239  
(559) 386-9711

**B-18 CLASS I LANDFILL  
PHASE III EXPANSION AND  
FINAL CLOSURE**  
TITLE SHEET

SHEET NUMBER  
**T-1**  
1 OF 11 SHEETS

## SHEET INDEX

DRAWING NO.	TITLE	SHEET NO.
083-91887EXP-T1	TITLE SHEET	T-1
083-91887EXP-C1	SITE PLAN	C-1
083-91887EXP-C2	EXISTING CONDITIONS (AS OF MARCH 28, 2008)	C-2
083-91887EXP-C3	BASE LINER PLAN	C-3
083-91887EXP-C4A	PHASE IIIA FILL PLAN	C-4A
083-91887EXP-C4	FINAL CLOSURE PLAN	C-4
083-91887EXP-C5	CROSS SECTIONS A TO D	C-5
083-91887EXP-C6	CROSS SECTIONS E TO I	C-6
083-91887EXP-C7	PHASE III BASE LINER CONSTRUCTION DETAILS	C-7
083-91887EXP-C8	PHASE III LCRS SYSTEM DETAILS	C-8
083-91887EXP-C9	DRAINAGE DETAILS	C-9
083-91887EXP-C10	CLOSURE DETAILS	C-10



### GENERAL NOTES

- THESE DRAWINGS AND SPECIFICATIONS SHALL BE USED TOGETHER. IF A DIFFERENCE OCCURS, THE CWM PROJECT MANAGER SHALL DETERMINE WHICH TAKES PRECEDENCE.
- THE LANDFILL B-18 CONSTRUCTION WILL OCCUR WITHIN AREAS APPROVED BY VARIOUS GOVERNMENT AGENCIES. NO WORK SHALL OCCUR OUTSIDE OF THE CONSTRUCTION AREAS SHOWN ON THE DRAWINGS WITHOUT SPECIFIC APPROVAL OF THE CWM PROJECT MANAGER.
- PRIOR TO COMMENCING ANY CUT OR FILL, OR IN ANY WAY DISTURBING THE EXISTING LAND CONTOURS, CONTRACTOR SHALL VERIFY THE ACCURACY OF THE CONTOUR ELEVATIONS SHOWN IN THE DRAWINGS.


### LEGEND

	STRUCTURAL FILL		HDPE GEOMEMBRANE
	GENERAL FILL		GEOTEXTILE
	COMPACTED CLAY LINER		GEOCOMPOSITE
	RIP-RAP		PROPERTY LINE
	CONCRETE		10' CONTOUR
	OPERATIONS LAYER		2' CONTOUR
	SUBGRADE		FLOWLINE
			LIMIT OF GRADING


### ABBREVIATIONS

A.C.	ASPHALT CONCRETE
C	CENTER LINE
CMP	CORRUGATED METAL PIPE
CWM	CHEMICAL WASTE MANAGEMENT
EL	ELEVATION
HDPE	HIGH DENSITY POLYETHYLENE
H.P.	HIGH POINT
MIN.	MINIMUM
TYP.	TYPICAL
Ø	DIAMETER

### KEY






PLANS PREPARED UNDER  
THE SUPERVISION OF:



RE-ISSUED FOR PERMITTING

2-24-11



**NOTE**  
 1. SOIL EXCAVATED FROM WITHIN LANDFILL B-17 MAY BE UTILIZED FOR STRUCTURAL FILL, CLAY LINER, OPERATIONS LAYER, DAILY COVER AND/OR FINAL COVER.

BASE TOPOGRAPHY FLOWN BY AERIAL MAPPING SERVICES, INC., MARCH 29, 2008 (NAD 27).

REV	DATE	DESCRIPTION	DESIGN	DRAWN	REVIEW
A	9/10/2008	ISSUED FOR PERMITTING MEETING	KJK	KJK	SGS
B	11/04/2008	ISSUED FOR PERMITTING	KJK	KJK	SGS

**Golder Associates**  
 230 Commerce, Suite 200  
 Irvine, California 92602  
 (714) 508-4400

**CHEMICAL WASTE MANAGEMENT  
 KETTLEMAN HILLS FACILITY**  
 35251 OLD SKYLINE ROAD  
 KETTLEMAN CITY, CALIFORNIA 93239  
 (559) 386-9711


**B-18 CLASS I LANDFILL  
 PHASE III EXPANSION AND  
 FINAL CLOSURE**

**SITE PLAN**

SHEET NUMBER


**C-1**

2 OF 11 SHEETS



ISSUED FOR PERMITTING





BASE TOPOGRAPHY FLOWN BY AERIAL MAPPING SERVICES, INC., MARCH 28, 2008 (NAD 27).

REV	DATE	DESCRIPTION	DESIGN	DRAWN	REVIEW
A	6/4/2008	ISSUED FOR MEETING	KJK	KJK	SGS
B	9/16/2008	ISSUED FOR PERMITTING MEETING	KJK	KJK	SGS
C	11/04/2008	ISSUED FOR PERMITTING	KJK	KJK	SGS




**CHEMICAL WASTE MANAGEMENT  
KETTLEMAN HILLS FACILITY**  
35251 OLD SKYLINE ROAD  
KETTLEMAN CITY, CALIFORNIA 93239  
(559) 386-6151

**B-18 CLASS I LANDFILL  
PHASE III EXPANSION AND  
FINAL COVER  
EXISTING CONDITIONS  
(AS OF MARCH 28, 2008)**


SHEET NUMBER

**C-2**



PLANS PREPARED UNDER THE SUPERVISION OF:

ISSUED FOR PERMITTING



REV	DATE	DESCRIPTION	DRAWN	REVIEW
A	8/10/2008	ISSUED FOR PERMITTING MEETING	KJK	SSS
B	1/10/2009	ISSUED FOR PERMITTING	KJK	SSS
C	8/10/2011	RE-ISSUED FOR PERMITTING	KJK	RR

**Golden Associates**  
 230 Commerce, Suite 200  
 Irvine, California 92602  
 (714) 508-4400

**CHEMICAL WASTE MANAGEMENT  
 KETTLEMAN HILLS FACILITY**  
 35251 OLD SKYLINE ROAD  
 KETTLEMAN CITY, CALIFORNIA 93239  
 (559) 386-9711



**B-B18 CLASS I LANDFILL  
 PHASE III EXPANSION AND FINAL  
 CLOSURE**  
**BASE LINER PLAN**

SHEET NUMBER	<b>C-3</b>
4 OF 11 SHEETS	


- NOTES**
- GRADES SHOWN ARE TOP OF CLAY LINER.
  - REMOVE ORGANIC MATERIAL AND LOOSE FILL PRIOR TO SUBGRADE PREPARATION.
  - 48" Ø DRAINAGE PIPES ARE INSTALLED TO DRAIN RUN-ON AROUND THE LANDFILL. PIPES SHALL BE INSTALLED AT THE LOCATION SHOWN SUCH THAT THE PIPE IS LOCATED ON THE OUT SIDE OF THE DRAINAGE CHANNEL. INSTALLATION WILL REQUIRE CUTS INTO THE NATURAL GRADE.
  - END 18" Ø PIPE WITH GATE VALVES ON EACH BRANCH. EXTEND PIPE TO EDGE OF BASIN INV. EL. 862.

PLANS PREPARED UNDER THE SUPERVISION OF:  
  
**RE-ISSUED FOR PERMITTING**

BASE TOPOGRAPHY FLOWN BY AERIAL MAPPING SERVICES, INC., MARCH 28, 2008.



- NOTES:
- GRADES SHOWN FOR PHASE IIIA (EXCEPT TEMPORARY WASTE SLOPE) ARE TO TOP OF FINAL COVER.
  - PHASE IIIIB GRADING SHOWN AS TOP OF PROPOSED LINER.
  - SOIL BERMS ON DRAINAGE BENCH, COVER ACCESS ROAD AND SOUTH PERIMETER ROAD NOT SHOWN FOR CLARITY.



RE-ISSUED FOR PERMITTING


REV	DATE	DESCRIPTION	DESIGN	DRAWN	REVIEW
C	8/10/2011	RE-ISSUED FOR PERMITTING	KJK	KJK	RH

**Golder Associates**  
 230 Commerce, Suite 200  
 Irvine, California 92602  
 (714) 508-4400

**CHEMICAL WASTE MANAGEMENT  
 KETTLEMAN HILLS FACILITY**  
 35251 OLD SKYLINE ROAD  
 KETTLEMAN CITY, CALIFORNIA 93239  
 (559) 386-9711

**B-18 CLASS I LANDFILL  
 PHASE III EXPANSION AND FINAL  
 CLOSURE**  
**PHASE IIIA FILL PLAN**


SHEET NUMBER  
**C-4A**  
 5 OF 12 SHEETS




BASE TOPOGRAPHY FLOWN BY AERIAL MAPPING SERVICES, INC., MARCH 26, 2008 (NAD 27).

ISSUED FOR PERMITTING

- NOTES:
- GRADES SHOWN ARE TO TOP OF FINAL COVER.
  - SOIL BERMS ON DRAINAGE BENCH, COVER ACCESS ROAD AND SOUTH PERIMETER ROAD NOT SHOWN FOR CLARITY.



120 0 120  
1" = 120' Feet







REV	DATE	DESCRIPTION	DESIGN	DRAWN	REVIEW
A	9/19/2008	ISSUED FOR PERMITTING MEETING	KJK	KJK	SGS
B	11/07/2008	ISSUED FOR PERMITTING	KJK	KJK	SGS

**Golden Associates**  
 230 Commerce, Suite 200  
 Irvine, California 92602  
 (714) 508-4400

**CHEMICAL WASTE MANAGEMENT  
 KETTLEMAN HILLS FACILITY**  
 35251 OLD SKYLINE ROAD  
 KETTLEMAN CITY, CALIFORNIA 93239  
 (559) 386-9711

**B-18 CLASS I LANDFILL  
 PHASE III EXPANSION AND FINAL  
 CLOSURE**  
**FINAL CLOSURE PLAN**

SHEET NUMBER  
**C-4**  
 5 OF 11 SHEETS




REV	DATE	DESCRIPTION	DESIGN	DRAWN	REVIEW
A	9/16/2008	ISSUED FOR PERMITTING MEETING	K/K	K/K	SGS
B	11/04/2008	ISSUED FOR PERMITTING	K/K	K/K	SGS




**CHEMICAL WASTE MANAGEMENT  
KETTLEMAN HILLS FACILITY**  
35251 OLD SKYLINE ROAD  
KETTLEMAN CITY, CALIFORNIA 93239  
(559) 386-9711

**B-18 CLASS I LANDFILL  
PHASE III EXPANSION AND FINAL  
CLOSURE**  
**CROSS SECTIONS A TO D**


SHEET NUMBER	<b>C-5</b>
6 OF 11 SHEETS	




ISSUED FOR PERMITTING




**E**  
C-3, C-4 | C-4  
LOOKING NORTH  
LCRS RISER PIPES  
1" = 30'




**F**  
C-3, C-4 | C-6  
LOOKING EAST  
PHASE III NORTH SIDE  
1" = 30'



**G**  
C-3 | C-4  
LOOKING NORTH  
SOUTH STORMWATER CONTAINMENT BASIN  
1" = 30'




**H**  
C-4 | C-6  
LOOKING NORTH  
NORTHEAST ACCESS ROAD  
1" = 30'



**I**  
C-4 | C-6  
LOOKING NORTH  
EXISTING NORTHEAST PERIMETER ROAD  
AND STORMWATER CONTAINMENT BASIN  
1" = 30'

ISSUED FOR PERMITTING









REV	DATE	DESCRIPTION	DESIGN	DRAWN	REVIEW
A	11/06/2009	ISSUED FOR PERMITTING MEETING	K.K.	K.K.	K.K.
B	11/06/2009	ISSUED FOR PERMITTING	K.K.	K.K.	K.K.
C	FEB 2010	REVISED FOR ANNOUATRIC COMMENTS	K.K.	K.K.	K.K.

**Golden Associates**  
230 Commercial, Suite 200  
Irvine, California 92602  
(714) 508-4400

**CHEMICAL WASTE MANAGEMENT  
KETTLEMAN HILLS FACILITY**  
35251 OLD SKYLINE ROAD  
KETTLEMAN CITY, CALIFORNIA 95239  
(559) 386-9711

**B-18 CLASS I LANDFILL  
PHASE III EXPANSION AND FINAL  
CLOSURE**  
CROSS SECTIONS E TO I

SHEET NUMBER  
**C-6**  
7 OF 11 SHEETS



REV	DATE	DESCRIPTION	DESIGN	DRAWN	REVIEW
A	9/10/2008	ISSUED FOR PERMITTING MEETING	K.K.	K.K.	S.S.
B	1/10/2009	ISSUED FOR PERMITTING	K.K.	K.K.	S.S.
C	FEB 2010	REVISED PER RWQCBOTIC COMMENTS	K.K.	K.K.	S.S.

**Golden Associates**  
230 Commerce, Suite 200  
Irvine, California 92602  
(714) 508-4400







**CHEMICAL WASTE MANAGEMENT  
KETTLEMAN HILLS FACILITY**  
35251 OLD SKYLINE ROAD  
KETTLEMAN CITY, CALIFORNIA 95239  
(559) 386-9711

**B-18 CLASS I LANDFILL  
PHASE III EXPANSION AND FINAL  
PHASE III BASE LINER  
CONSTRUCTION DETAILS**



PLANS PREPARED UNDER THE SUPERVISION OF:  
**REGULATORY SERVICES**  
PROFESSIONAL ENGINEER  
CIVIL  
STATE OF CALIFORNIA

SHEET NUMBER  
**C-7**  
8 OF 11 SHEETS

ISSUED FOR PERMITTING




NOTE: 10" Ø SDR 13.5 (I.D. = 9.062) MAY BE USED FOR 3' TRANSITION IF TOLERANCE IS TO TIGHT FOR SDR 11 PIPE



NOTES:  
1. AS SHOWN FOR PHASE 1B AND 1IB  
2. OPPOSITE HAND FOR PHASE 1A  
3. EXISTING TANK, SAMPLING PLATFORM, PUMPS AND CONTROLS TO BE RELOCATED TO NEW TANK PAD.

ISSUED FOR PERMITTING



REVIEW	DESIGN	DATE	REV
SGS	KJK	9/10/2008	A
SGS	KJK	11/04/2008	A
DESCRIPTION	ISSUED FOR PERMITTING		
DESCRIPTION	ISSUED FOR PERMITTING		






**Golden Associates**  
230 Commerce, Suite 200  
Irvine, California 92602  
(714) 508-4400

**CHEMICAL WASTE MANAGEMENT  
KETTLEMAN HILLS FACILITY**  
35251 OLD SKYLINE ROAD  
KETTLEMAN CITY, CALIFORNIA 95239  
(559) 386-9711

**B-18 CLASS I LANDFILL PHASE III  
EXPANSION AND FINAL CLOSURE**  
**PHASE III LCRS SYSTEM DETAILS**

SHEET NUMBER  
**C-8**  
9 OF 11 SHEETS





ISSUED FOR PERMITTING

REV	DATE	DESCRIPTION	DESIGN	DRAWN	REVIEW
A	9/16/2018	ISSUED FOR PERMITTING	K/K	K/K	SSS
B	11/04/2018	ISSUED FOR PERMITTING	K/K	K/K	SSS






**Gold Associates**  
 230 Commerce, Suite 200  
 Irvine, California 92602  
 (714) 508-1400

**CHEMICAL WASTE MANAGEMENT  
 KETTLEMAN HILLS FACILITY**  
 35251 OLD SKYLINE ROAD  
 KETTLEMAN CITY, CALIFORNIA 93239  
 (559) 386-9711

**B-18 CLASS I LANDFILL  
 PHASE III EXPANSION AND  
 FINAL COVER  
 DRAINAGE DETAILS**

PLANS PREPARED UNDER  
 THE SUPERVISION OF  
 [Signature]  
 REGISTERED PROFESSIONAL ENGINEER  
 CIVIL  
 STATE OF CALIFORNIA  
 9-30-2010

SHEET NUMBER  
**C-9**  
 10 OF 11 SHEETS




REV	DATE	DESCRIPTION	DESIGN	DRAWN	REVIEW
A	9/16/2008	ISSUED FOR PERMITTING MEETING	K/K	K/K	SSS
B	11/04/2008	ISSUED FOR PERMITTING	K/K	K/K	SSS

**Golder Associates**  
230 Commerce, Suite 200  
Irvine, California 92602  
(714) 508-4400

**CHEMICAL WASTE MANAGEMENT  
KETTLEMAN HILLS FACILITY**  
35251 OLD SKYLINE ROAD  
KETTLEMAN CITY, CALIFORNIA 93239  
(559) 386-9711

**B-18 CLASS I LANDFILL  
PHASE III EXPANSION AND FINAL  
CLOSURE**  
CLOSURE DETAILS

SHEET NUMBER  
**C-10**  
11 OF 11 SHEETS









ISSUED FOR PERMITTING

**APPENDIX B  
BORING LOGS**

## LOG OF BORING L18-A

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-A		ELEVATION: 856'	DATE
COORDINATES: N. 228,940 E. 1,700,840		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/12/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 1 OF 3

### LEGEND

	SANDS		SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
	SILTS		SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
	CLAYS		CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
				PI - Atterberg Limits Test	%200 - Percentage Passing
				COMP - Compaction Test	HYD - Hydrometer Test
				DIR - Direct Shear Test	SG - Specific Gravity Test
				TX - Triaxial Test	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
1						CS	<b>SAN JOAQUIN FORMATION</b>			
2						CS	CLAYSTONE/SANDSTONE, gray, light brown, gray brown, orange claystone; interbedded claystone/sandstone, laminated, soft, weak			
3						CS				
4						CS				
5	PB	S-1	300 - 400	1.0 1.1		SS	- predominantly claystone from 0' - 0.5' - sandstone at 4.5'	18	98	
6						CS	- gray claystone, orange-tan silty sandstone (interbedded)			
7						CS				
8						CS				
9						CS				
10						CS/SS	- orange claystone laminae, sandstone			
11	PB	S-2	250	2.1 2.5		SS				
12						SS	- tan, light brown sandstone, very fine, clean			
13						SS				
14						SS				
15						SS	- light brown, gray brown, orange claystone, lesser gray claystone, sandstone from 12.5' to 17'			

## LOG OF BORING L18-A

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-A		ELEVATION: 856'	DATE
COORDINATES: N. 228,940 E. 1,700,840		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/12/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 2 OF 3

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
16					CS/SS					
17	PB	S-3	250	2.4	SS		- clean, very fine sandstone	16	102	%200
18					slt/cs		- interbedded siltstone/claystone, laminated			
19			300				- interbedded sandstone/claystone, laminated to very thin bedded			
20							- fine, clean, sandstone, tan with gray claystone lamination			
21					SS/CS		- red, hard cemented sandstone			
22										
23										
24										
25	PB	S-4	350	2.5			- very fine, silty sandstone, light brown	20	%200	
26					SS/slt		- silty sandstone, sandy siltstone			
27							- very fine, silty sandstone, light brown with minor claystone pocket/lamination			
28										
29										
30										
31										
32					SS/CS					
33										
34	PB	S-5	350	2.2						
35							- claystone with sandstone			CHEM

### LOG OF BORING L18-A

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-A		ELEVATION: 856'	DATE
COORDINATES: N. 228,940 E. 1,700,840		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/12/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 3 OF 3







DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
36	X				SS/CS	▨	- very fine silty sandstone with claystone laminations			
37					CS	▨	- claystone with interbedded sandstone laminae			
38	PB	S-6	1.5 1.7		SS	▨	- silty sandstone with claystone laminae	15	102	%200

- TOTAL DEPTH = 38.7'
- NO GROUND WATER ENCOUNTERED
- BACKFILLED WITH CEMENT GROUT VIA TREMIE

## LOG OF BORING L18-B

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-B		ELEVATION: 861'	DATE
COORDINATES: N. 228,750 E. 1,700,860		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/13/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 1 OF 3

### LEGEND

 SANDS	 SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
 SILTS	 SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
 CLAYS	 CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
		PI - Atterberg Limits Test	%200 - Percentage Passing
		COMP - Compaction Test	HYD - Hydrometer Test
		DIR - Direct Shear Test	SG - Specific Gravity Test
		TX - Triaxial Test	




DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
1							<u>SAN JOAQUIN FORMATION</u>			
2							CLAYSTONE, gray, highly plastic, minor very fine sand, occasional sandstone pockets (bioturbation), laminae			
3										
4										
5										
6					CS					
7	PB	S-1	2.3 2.5				- silty claystone, high plasticity, some sandstone modules and bedding	22	96	PI HYD
8							- gray claystone, minor very fine sand at 8.3'			
9										
10										
11										
12	PB	S-2	2.4 2.5		SS		SILTY SANDSTONE, tan, light brown, mottled orange, very fine grained			
13										
14										
15										





### LOG OF BORING L18-B

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-B		ELEVATION: 861'	DATE
COORDINATES: N. 228,750 E. 1,700,860		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/13/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 3 OF 3

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
36										
37										
38	PB	S-5		$\frac{2.0}{2.5}$	SS		SANDSTONE, tan, fine to medium grained, clean	14	106	%200
39										

- TOTAL DEPTH = 39.5'
- NO GROUND WATER ENCOUNTERED
- BACKFILLED WITH CEMENT GROUT VIA TREMIE

## LOG OF BORING L18-C

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-C		ELEVATION: 754'	DATE
COORDINATES: N. 228,620 E. 1,702,120		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/13/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 1 OF 5

### LEGEND

SANDS	SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
SILTS	SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
CLAYS	CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
		PI - Atterberg Limits Test	%200 - Percentage Passing
		COMP - Compaction Test	HYD - Hydrometer Test
		DIR - Direct Shear Test	SG - Specific Gravity Test
		TX - Triaxial Test	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
1							<u>COLLUVIUM</u>			
2							SANDY CLAY, light brown, damp (to 7.5'), low to moderate plasticity, 20 to 40% very fine grained sand.			
3										
4										
5					cl					
6										
7	DR	B-1	15	1.3 1.5			- very stiff from 6' to 7.5'			PI
8										
9										
10										
11										
12										
13	DR	B-2	17	.8 15	sp		- 1/2" thick, clean, very fine grained sand lens.			
14					cl		- very stiff from 12' to 13.5'			
15										

## LOG OF BORING L18-C

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf		
BORING NUMBER: L18-C		ELEVATION: 754'	DATE	
COORDINATES: N. 228,620 E. 1,702,120		BORING DIA.: 5"	STARTED	COMPLETED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/13/90	3/14/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 2 OF 5	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
16	PB	S-1		$\frac{2.1}{2.3}$	cl			23	100	PI HYD
17					slt		<u>SAN JOAQUIN FORMATION</u>			
18										
19							SILTSTONE, gray - brown, mottled orange, non - plastic, occasional gray claystone laminae, (Iron oxide stained.)			
20							- bedding @ ~ 20° @ 16'			CHM
21	PB	S-2		$\frac{2.3}{2.5}$			- siltstone, non-plastic, trace of very fine grained sand.			
22										
23										
24										
25										
26	PB	S-3		$\frac{2.2}{2.5}$	slt cs		- silty claystone - clayey siltstone, moderate plasticity at 26'	14	102	PI
27										
28					slt		- siltstone at 27.2'			
29										
30					cs/slt		CLAYSTONE/SILTSTONE, gray claystone, light gray-brown, clayey siltstone, inter bedded, laminated.			
31										
32										
33										
34	PB	S-4		$\frac{1.9}{2.0}$						
35										

### LOG OF BORING L18-C

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf		
BORING NUMBER: L18-C		ELEVATION: 754'	DATE	
COORDINATES: N. 228,620 E. 1,702,120		BORING DIA.: 5"	STARTED	COMPLETED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/13/90	3/14/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 3 OF 5	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
36						▨				
37					SS	▨	SANDSTONE, SILTY SANDSTONE, light brown, very fine to fine grained			
38						▨				
39						▨				
40						▨				
41						▨				
42	PB	S-5	2.0 2.1			▨	- silty sandstone, light brown, very fine grained.	12	102	
43						▨				
44						▨				
45						▨				
46						▨				
47						▨				
48						▨				
49	PB	S-6	1.9 2.1		slt, cs	▨	SANDSTONE, CLAYSTONE, gray brown, gray, interbedded (laminated-thin bedded), occasional sandstone interbeds.			
50						▨				
51						▨				
52						▨	- gray siltstone, non-plastic at 49.9'			
53						▨				
54						▨				
55						▨				

### LOG OF BORING L18-C

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-C		ELEVATION: 754'	DATE
COORDINATES: N. 228,620 E. 1,702,120		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/13/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 4 OF 5

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
56	X PB	S-7	1.8 2.0		CS					PI HYD TX DIR
57					SS					
58					CS					
59					slt					
60					slt, CS					
61										
62										
63										
64										
65	X PB	S-8	1.8 2.3				- gray brown, clayey siltstone with very thin gray claystone laminae, orange (iron oxide stained)			TX
66										
67										
68										
69										
70										
71										
72										
73	X PB	S-9	2.3 2.3				SANDSTONE, SILTY SANDSTONE, light brown, very fine grained, 10 to 20% fines.	8	10.5	
74										
75										

## LOG OF BORING L18-C

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-C		ELEVATION: 754'	DATE
COORDINATES: N. 228,620 E. 1,702,120		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/13/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 5 OF 5







DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
76						●●●●●●●●				
77						●●●●●●●●				
78					st	▨▨▨▨▨▨	SILTSTONE, light brown, minor sand, occasional claystone interbeds, claystone with moderate plasticity	14	106	%200
79					st	▨▨▨▨▨▨				
80						▨▨▨▨▨▨				
81	PB	S-10		1.9 2.0		▨▨▨▨▨▨				
82					st/ cs	▨▨▨▨▨▨	- siltstone/claystone (interbedded.)			
83						▨▨▨▨▨▨				
84						▨▨▨▨▨▨				
85						▨▨▨▨▨▨				
86						▨▨▨▨▨▨				
87						▨▨▨▨▨▨				
88	PB	S-11		1.7 2.0	cs st	▨▨▨▨▨▨	- sandy, silty claystone with moderate plasticity. - sandy siltstone.	12	106	PI




TOTAL DEPTH 89'  
NO GROUNDWATER ENCOUNTERED  
BACKFILLED WITH CEMENT GROUT VIA TREMIE

## LOG OF BORING L18-D

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-D		ELEVATION: 740'	DATE
COORDINATES: N. 228,780 E. 1,702,480		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/14/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 1 OF 5

### LEGEND

 SANDS	 SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
 SILTS	 SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
 CLAYS	 CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
		PI - Atterberg Limits Test	%200 - Percentage Passing
		COMP - Compaction Test	HYD - Hydrometer Test
		DIR - Direct Shear Test	SG - Specific Gravity Test
		TX - Triaxial Test	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
					gc		FILL - sandy, clayey gravel			
1					cl		<u>COLLUVIUM</u>	19		PI HYD
2				Sandy clay, light brown; dry (to 5' deep), low plasticity, stiff 30 to 40% very fine sand.						
3										
4										
5										
6	DR	B-1	11	$\frac{1.3}{1.5}$						
7										
8										
9										
10										
11	DR	B-2	11	$\frac{1.5}{1.5}$						
12										
13										
14	B	B-3	(BAG)		slt/ ss		<u>SAN JOAQUIN FORMATION</u>			
15							CEMENTED SILTSTONE-SANDSTONE WITH FOSSILS (MYA BED), orange, brown, hard, strong			







### LOG OF BORING L18-D

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-D		ELEVATION: 740'	DATE
COORDINATES: N. 228,780 E. 1,702,480		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/14/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	3/15/90
		PAGE: 4	OF 5

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
56						▨				
57						▨				
58						▨				
59						▨				
60						▨				
61	PB	S-7		1.2 2.5		▨	- interbedded claystone/siltstone and very fine grained sandstone			
62						▨				
63						▨				
64						▨				
65						▨				
66						▨				
67						▨				
68						▨				
69	PB	S-8		1.4 2.5		▨	- gray claystone			
70						▨				
71						▨				
72						▨				
73						▨				
74					slt/ ss	▨	SILTSTONE, SILTY SANDSTONE, tan, light brown, orange mottling/layering			
75						▨				

### LOG OF BORING L18-D

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-D		ELEVATION: 740'	DATE
COORDINATES: N. 228,780 E. 1,702,480		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/14/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 5 OF 5







DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
76	X PB	S-9	$\frac{0.8}{2.5}$		slt	[diagonal lines]	- nonplastic siltstone, silty sandstone, interbedded/laminated, occasional claystone laminae			
77						[dotted]	- tan, silty sandstone, fine/orange, cemented siltstone at 77'			
78						[diagonal lines]				
79										
80										
81	X PB	S-10	$\frac{0.9}{2.5}$		slt	[dotted]	- tan, silty sandstone, orange siltstone with fossils (clam shell) at 81.9'	16	109	%200
82						[diagonal lines]				
83										
84	X PB	S-11	$\frac{1.7}{2.5}$		slt	[dotted]	- very fine silty sandstone, tan, brown, mottled orange (bioturbation)			
85						[diagonal lines]				




- TOTAL DEPTH = 86'
- NO GROUND WATER ENCOUNTERED
- BACKFILLED WITH CEMENT GROUT VIA TREMIE

## LOG OF BORING L18-E

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-E		ELEVATION: 727'	DATE
COORDINATES: N. 228,890 E. 1,702,670		BORING DIA.: 5"	STARTED    COMPLETED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/19/90    3/20/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 1    OF 4

### LEGEND

	SANDS		SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
	SILTS		SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
	CLAYS		CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
				PI - Atterberg Limits Test	%200 - Percentage Passing
				COMP - Compaction Test	HYD - Hydrometer Test
				DIR - Direct Shear Test	SG - Specific Gravity Test
				TX - Triaxial Test	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
1							<u>COLLUVIUM</u> SANDY CLAY, light brown, dry, low to moderate plasticity, 10 to 40% very fine grained sand. Numerous thin interbeds/laminae of sand (sp), probably intermittent alluvial deposits			
2										
3										
4										
5										
6	DR	B-1	19	1.3 1.5	cl		- very stiff			
7										
8							- numerous cemented sandstone fragments (hard, orange brown, to 1/2" Ø), occasional gray claystone fragments from 8' to 13'			
9										
10							- cemented sandstone fragments			
11	PB	S-1		1.7 2.5			- very stiff to hard, light brown sandy clay with claystone fragments, moderate plasticity	16	106	
12										
13										
14							<u>SAN JOAQUIN FORMATION</u> SANDSTONE, tan, very fine to fine, occasional siltstone, claystone laminae, occasional orange			
15										

## LOG OF BORING L18-E

PROJECT NUMBER: 89-977				PROJECT NAME: B-18 LANDFILL, KHF						
BORING NUMBER: L18-E				ELEVATION: 727'		DATE				
COORDINATES: N. 228,890 E. 1,702,670				BORING DIA.: 5"		STARTED	COMPLETED			
DRILLING METHODS: MUD ROTARY				WATER DEPTH: NONE		3/19/90	3/20/90			
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)				CHECKED BY: J. BADEL		PAGE: 2 OF 4				
DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
16	PB	S-2		$\frac{2.1}{2.5}$		SS	- cemented laminae	12		%200
17							- tan, fine sandstone, clean, with minor claystone laminae at 19'			
18										
19										
20	PB	S-3		$\frac{1.4}{2.5}$		SS	- very fine silty sandstone at 21'			
21										
22										
23										
24										
25										
26										
27										
28										
29	PB	S-4		$\frac{1.9}{2.2}$		SS	- very fine to fine sandstone (sp-sm) at 30'			
30										
31						cs/ slt	CLAYSTONE/SILTSTONE, gray brown, with orange laminae			
32										
33										
34						slt/ cs	SILTSTONE, SANDY SILTSTONE, CLAYSTONE			
35							predominantly siltstone, sandy siltstone			



## LOG OF BORING L18-E

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-E		ELEVATION: 727'	DATE
COORDINATES: N. 228,890 E. 1,702,670		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	COMPLETED
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 4 OF 4







DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
56										
57										
58										
59										
60										
61	PB	S-8		2.4 2.5			- gray sandy claystone, mottled orange (sand in pockets - bioturbation) at 62'	28	95	PI
62										


- TOTAL DEPTH = 62.5'
- NO GROUND WATER ENCOUNTERED
- BACKFILLED WITH CEMENT GROUT VIA TREMIE

## LOG OF BORING L18-F

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-F		ELEVATION: 821'	DATE
COORDINATES: N. 228,930 E. 1,701,540		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/20/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 1 OF 4

### LEGEND

	SANDS		SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
	SILTS		SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
	CLAYS		CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
				PI - Atterberg Limits Test	%200 - Percentage Passing
				COMP - Compaction Test	HYD - Hydrometer Test
				DIR - Direct Shear Test	SG - Specific Gravity Test
				TX - Triaxial Test	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS	
1							<u>SAN JOAQUIN FORMATION</u>				
2							CLAYSTONE, gray, brown with orange laminae, slightly weathered, soft, weak, laminated to thin bedded, occasional very fine sand laminae, occasional siltstone interbeds/laminae; highly plastic				
3											
4											
5											
6											
7	PB	S-1	2.5 2.5		cs			- olive brown, silty claystone, moderate to high plasticity	20	103	PI HYD
8											
9											
10											
11											
12											
13											
14											
15											







## LOG OF BORING L18-F

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-F		ELEVATION: 821'	DATE
COORDINATES: N. 228,930 E. 1,701,540		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/20/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	3/21/90
		PAGE: 4	OF 4







DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
56	PB	S-6		2.1 2.5		▨	- gray claystone, highly plastic with 1/2" thick orange (iron oxide cemented) sandstone lamination and several sandy bioturbation pockets	26	95	PI HYD TX DIR
57										
58										









- TOTAL DEPTH = 58.5'
- NO GROUND WATER ENCOUNTERED
- BACKFILLED WITH CEMENT GROUT VIA TREMIE

## LOG OF BORING L18-G

PROJECT NUMBER: 89-977	PROJECT NAME: B-18 LANDFILL, KHf		
BORING NUMBER: L18-G	ELEVATION: 853'	DATE	
COORDINATES: N. 227,500 E. 1,701,910	BORING DIA.: 5"	STARTED	COMPLETED
DRILLING METHODS: MUD ROTARY	WATER DEPTH: NONE	3/21/90	3/22/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)	CHECKED BY: J. BADEL	PAGE: 1 OF 5	

### LEGEND

	SANDS		SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
	SILTS		SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
	CLAYS		CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
				PI - Atterberg Limits Test	%200 - Percentage Passing
				COMP - Compaction Test	HYD - Hydrometer Test
				DIR - Direct Shear Test	SG - Specific Gravity Test
				TX - Triaxial Test	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
<u>SAN JOAQUIN FORMATION</u>										
1					ss (silty)		SILTY SANDSTONE, tan-gray, mottled orange, very fine, weakly cemented, occasional claystone laminae, bioturbation, occasional fossils (description based on access road cut exposure adjacent to the boring)	9	107	%200
2										
3					SS		SANDSTONE, tan very fine to fine, clean, occasional iron oxide cemented sandstone laminae, interbeds (orange reddish brown), occasional silty sandstone interbeds, occasional iron oxide cemented siltstone laminae	9	107	%200
4										
5					SS		- very fine, light brown, clean sandstone	9	107	%200
6										
7	PB	S-1	1.4 2.5		SS		- very fine, light brown, clean sandstone	9	107	%200
8										
9					SS		- very fine, light brown, clean sandstone	9	107	%200
10										
11					SS		- very fine, light brown, clean sandstone	9	107	%200
12										
13					SS		- very fine, light brown, clean sandstone	9	107	%200
14										
15	PB	S-2	1.4 2.5		SS		- very fine, light brown, clean sandstone	9	107	%200

### LOG OF BORING L18-G

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-G		ELEVATION: 853'	DATE
COORDINATES: N. 227,500 E. 1,701,910		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/21/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 2 OF 5

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
16	PB	S-2		$\frac{1.4}{2.5}$						
17										
18										
19										
20										
21										
22	PB	S-3		$\frac{1.5}{1.7}$			- very fine, clean sandstone			
23										
24										
25										
26										
27										
28										
29										
30	PB	S-4		$\frac{1.2}{2.0}$			- very fine, clean sandstone, 1/4" thick iron oxide cemented clay lamination (orange)			
31										
32										
33										
34										
35										

## LOG OF BORING L18-G

PROJECT NUMBER: 89-977				PROJECT NAME: B-18 LANDFILL, KHF						
BORING NUMBER: L18-G				ELEVATION: 853'		DATE				
COORDINATES: N. 227,500 E. 1,701,910				BORING DIA.: 5"		STARTED	COMPLETED			
DRILLING METHODS: MUD ROTARY				WATER DEPTH: NONE		3/21/90	3/22/90			
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)				CHECKED BY: J. BADEL		PAGE: 3 OF 5				
DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
36						.....				
37						.....				
38						.....				
39						.....				
40						.....				%200 TX
41	PB	S-5		1.2 1.3		.....	- very fine to fine clean sandstone			
42						.....				
43						.....				
44						.....	CLAYSTONE, dark gray, highly plastic			
45						.....				
46	PB	S-6		1.5 2.5		.....	- gray claystone, highly plastic	30	91	
47						.....				
48						.....				
49					CS	.....				
50						.....				PI TX HYD
51	PB	S-7		1.3 1.8		.....	- dark gray claystone, highly plastic, gypsum clots, striated slick surfaces	29	92	
52						.....				
53						.....				
54						.....				
55						.....				

## LOG OF BORING L18-G


PROJECT NUMBER: 89-977				PROJECT NAME: B-18 LANDFILL, KHF			
BORING NUMBER: L18-G				ELEVATION: 853'		DATE	
COORDINATES: N. 227,500 E. 1,701,910				BORING DIA.: 5"		STARTED	COMPLETED
DRILLING METHODS: MUD ROTARY				WATER DEPTH: NONE		3/21/90	3/22/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)				CHECKED BY: J. BADEL		PAGE: 4 OF 5	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
56										
57										
58										
59										
60	X									
61	PB	S-8		1.0 2.5			- gray claystone with sandy pockets (bioturbation)			
62	X									
63										
64										
65	X									
66	PB	S-9		1.4 2.0			- gray claystone, high plasticity with silt-sand filled pockets (bioturbation)	27	95	PI HYD
67										
68										
69										
70										
71							SANDSTONE, SILTY SANDSTONE, tan very fine, occasional silty sandstone pockets, occasional claystone laminae			
72										
73						SS 				
74										
75										

## LOG OF BORING L18-G

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-G		ELEVATION: 853'	DATE
COORDINATES: N. 227,500 E. 1,701,910		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/21/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 5 OF 5

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
76 77	PB	S-10		$\frac{0.8}{2.5}$			- clean sandstone with silty sandstone pockets and brown claystone lamination			







- TOTAL DEPTH = 77.5'
- NO GROUND WATER ENCOUNTERED
- BACKFILLED WITH CEMENT GROUT VIA TREMIE







## LOG OF BORING L18-H

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-H		ELEVATION: 865'	DATE
COORDINATES: N. 228,060 E. 1,702,050		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/22/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 1 OF 4

### LEGEND


	SANDS		SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
	SILTS		SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
	CLAYS		CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
				PI - Atterberg Limits Test	%200 - Percentage Passing
				COMP - Compaction Test	HYD - Hydrometer Test
				DIR - Direct Shear Test	SG - Specific Gravity Test
				TX - Triaxial Test	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
1					cl		FILL, sandy clay (drilling pad)			
2							<u>COLLUVIUM</u>			
3					cl		SANDY CLAY, light brown, dry, low plasticity			
4										
5							<u>SAN JOAQUIN FORMATION</u>			
6							CLAYSTONE, gray, highly plastic, occasional thin sandstone interbeds laminae			
7	PB	S-1	1.8 2.5		cs		- gray highly plastic silty claystone	29	89	PI
8										
9							SANDSTONE - SILTY SANDSTONE			
10										
11										
12					ss					
13										
14										
15										





## LOG OF BORING L18-H

PROJECT NUMBER: 89-977				PROJECT NAME: B-18 LANDFILL, KHF						
BORING NUMBER: L18-H				ELEVATION: 865'		DATE				
COORDINATES: N. 228,060 E. 1,702,050				BORING DIA.: 5"		STARTED	COMPLETED			
DRILLING METHODS: MUD ROTARY				WATER DEPTH: NONE		3/22/90	3/22/90			
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)				CHECKED BY: J. BADEL		PAGE: 4 OF 4				
DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
56 57	PB	S-6	1.2 2.5				- gray claystone with sand filled pockets (bioturbation)	25	96	PI
<ul style="list-style-type: none"> <li>TOTAL DEPTH = 57.5'</li> <li>NO GROUND WATER ENCOUNTERED</li> <li>BACKFILLED WITH CEMENT GROUT VIA TREMIE</li> </ul>										

## LOG OF BORING L18-I

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-I		ELEVATION: 766'	DATE
COORDINATES: N. 228,020 E. 1,702,410		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/23/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 1 OF 2


### LEGEND

SANDS	SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
SILTS	SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
CLAYS	CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
		PI - Atterberg Limits Test	%200 - Percentage Passing
		COMP - Compaction Test	HYD - Hydrometer Test
		DIR - Direct Shear Test	SG - Specific Gravity Test
		TX - Triaxial Test	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
1							COLLUVIUM			
2							SILTY CLAY, light brown, dry (to 13') low to moderate plasticity, minor very fine sand, occasional root voids (pin-holes), minor caliche			
3										
4										
5										
6										
7	DR	B-1	35	$\frac{1.3}{1.5}$		cl	- hard			
8							- occasional hard, gray claystone fragments (detrital) to 1/2" Ø, from 7' to 10'			
9										
10										
11										
12										
13	PB	S-1		$\frac{1.4}{1.8}$			- sandy clay, light brown, dry, low to moderate plasticity, 20 to 40% very fine sand, occasional claystone fragments			
14										
15										

### LOG OF BORING L18-I

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-I		ELEVATION: 766'	DATE
COORDINATES: N. 228,020 E. 1,702,410		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/23/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 2 OF 2







DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
16	PB	S-2		2.3 2.5	CS		<u>SAN JOAQUIN FORMATION</u> CLAYSTONE, gray, highly plastic, includes brown laminae, occasional siltstone, very fine sand laminae - laminated claystone/siltstone with very fine sand laminae	19	92	PI HYD
17										
18										



- TOTAL DEPTH = 18.5'
- NO GROUND WATER ENCOUNTERED
- BACKFILLED WITH CEMENT GROUT VIA TREMIE

## LOG OF BORING L18-J

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-J		ELEVATION: 820'	DATE
COORDINATES: N. 228,390 E. 1,701,985		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	5/8/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 1 OF 9

### LEGEND

 SANDS	 SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
 SILTS	 SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
 CLAYS	 CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
		PI - Atterberg Limits Test	%200 - Percentage Passing
		COMP - Compaction Test	HYD - Hydrometer Test
		DIR - Direct Shear Test	SG - Specific Gravity Test
		TX - Triaxial Test	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS		
					cl		FILL, sandy clay to clayey sand					
1					cs		<u>SAN JOAQUIN FORMATION</u>					
2				CLAYSTONE, gray, brown, highly plastic, occasional thin sandstone/siltstone interbeds and laminae								
3												
4												
5												
6	PB	S-1	1.7 2.5						- gray, dark brown silty claystone interbedded sandstone, minor silt pockets, faint orange mottling	24	92	PI HYD SW
7												
8												
9												
10												
11	PB	S-2	2.2 2.5						- dark brown claystone, 1/8" thick gypsum layer (along bedding?)			
12												
13												
14												
15												

## LOG OF BORING L18-J

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-J		ELEVATION: 820	DATE
COORDINATES: N. 228,390 E. 1,701,985		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	5/8/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 2 OF 9

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
16	PB	S-3		$\frac{2.2}{2.5}$			- 70° joint filled with 1/4" thick gypsum vein	24	92	PI
17							- gray, brown silty claystone interbedded sandstone, minor orange mottling			
18										
19										
20	PB	S-4		$\frac{1.5}{2.0}$	ss		- orange, cemented sandstone, fine grained			
21										
22										
23										
24										
25	PB	S-5		$\frac{1.9}{2.5}$			- bedding at 25°	24	99	PI
26							- gray dark brown claystone interbedded sandstone			
27										
28					cs					
29										
30	PB	S-6		$\frac{2.4}{2.5}$			- gray, brown claystone, laminated very thin- orange (iron oxide) stain along bedding (at 30°), 1/4" thick gypsum vein along joint (across bedding)			
31										
32										
33										
34										
35										





### LOG OF BORING L18-J

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-J		ELEVATION: 820'	DATE
COORDINATES: N. 228,390 E. 1,701,985		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	5/8/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 4 OF 9

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
56	X PB	S-11		2.3 2.5			- gray, orange claystone, laminated, thin interbedded sandstone lens	26	99	PI
57										
58										
59										
60	X PB	S-12		2.4 2.5			- gray claystone, laminated			
61										
62										
63										
64										
65	X PB	S-13		2.1 2.5			- bedding attitude rotates ~ 90° (NE to NW) at 66'	25	100	PI
66							- dark gray claystone, thin interbedded sandstone			
67										
68										
69										
70	X PB	S-14		2.2 2.5			- dark brown-gray claystone			
71										
72										
73										
74										
75										

## LOG OF BORING L18-J

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-J		ELEVATION: 820'	DATE
COORDINATES: N. 228,390 E. 1,701,985		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	5/8/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 5 OF 9

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
76	X PB	S-15		2.5 2.5			- gray, brown, minor orange claystone, thin interbedded sandstone	25	94	PI HYD COMP PER
77										
78										
79										
80										
81	X PB	S-16		2.4 2.5			- blue gray claystone with occasional sand pockets (bioturbation?)			
82										
83										
84										
85										
86	X PB	S-17		2.2 2.5			- gray brown claystone with sand pockets or thin sand interbed	25	99	PI
87										
88										
89										
90										
91	X PB	S-18		2.1 2.5			- gray, orange claystone with large sand pockets or sandstone interbeds			
92										
93										
94										
95							- claystone with sandstone			CHEM

## LOG OF BORING L18-J

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-J		ELEVATION: 820'	DATE
COORDINATES: N. 228,390 E. 1,701,985		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	COMPLETED
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 6 OF 9

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
96	X PB	S-19		0.8 2.5	ss	▨	- intermittent sandstone from a 95.5' to 105' - cemented sandstone			
97						▨				
98						▨				
99						▨				
100	X PB	S-20		0.9 1.5	ss/ cs	▨	- very fine silty sandstone, noncemented, mottled, tan/orange	13	121	
101						▨				
102						▨				
103						▨				
104						▨				
105	X PB	S-21		2.5 2.5		▨	- dark gray claystone			
106						▨				
107						▨				
108						▨				
109						▨				
110	X PB	S-22		2.5 2.5	cs	▨	- dark gray claystone, thin interbedded sandstone, 1/4" sandstone lens	23	103	PI
111						▨				
112						▨				
113						▨				
114						▨				
115						▨				



## LOG OF BORING L18-J

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-J		ELEVATION: 820'	DATE
COORDINATES: N. 228,390 E. 1,701,985		BORING DIA.: 5"	STARTED COMPLETED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	5/8/90 5/9/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 8 OF 9

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
136	X PB	S-27		$\frac{2.5}{2.5}$			- dark gray claystone			
137										
138										
139										
140										
141	X PB	S-28		$\frac{2.5}{2.5}$			- dark gray claystone, thin interbedded sandstone	28	93	PI
142										
143										
144										
145										
146	X PB	S-29		$\frac{2.5}{2.5}$			- dark gray claystone			
147										
148										
149										
150										
151	X PB	S-30		$\frac{2.5}{2.5}$			- dark gray claystone, thin interbedded sandstone	28	96	PI
152										
153										
154										
155										

### LOG OF BORING L18-J

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-J		ELEVATION: 820'	DATE
COORDINATES: N. 228,390 E. 1,701,985		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	5/8/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 9 OF 9







DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
156	X PB	S-31	$\frac{2.5}{2.5}$	$\frac{2.5}{2.5}$		[Hatched Profile]	- dark gray claystone - harder (slower drilling)	20	104	PI HYD SW
157										
158										
159										
160	X PB	S-32	$\frac{2.5}{2.5}$	$\frac{2.5}{2.5}$		[Dotted Profile]	- silty	20	104	PI HYD SW
161										
162							SILTY SANDSTONE, tan, very fine, noncemented			
163					ss					
164										
165	X PB	S-33	$\frac{2.3}{2.5}$	$\frac{2.3}{2.5}$		[Diagonal Profile]	SILTSTONE, light brown, gray, mottled orange, nonplastic	20	104	PI HYD SW
166										
167					slt					
168										
169										
170	X PB	S-34	$\frac{2.2}{2.5}$	$\frac{2.2}{2.5}$		[Dotted Profile]	SANDSTONE, SILTY SANDSTONE, orange brown, very fine grained, noncemented	20	104	PI HYD SW
171										
172					cs		CLAYSTONE, dark brown, black, highly plastic			

















- TOTAL DEPTH = 172.5'
- NO GROUND WATER ENCOUNTERED
- BACKFILLED WITH CEMENT GROUT VIA TREMIE

# LOG OF BORING L18-K

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-K		ELEVATION: 804'	DATE
COORDINATES: N. 228,390 E. 1,701,722		BORING DIA.: 5"	STARTED COMPLETED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	5/9/90 5/10/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 1 OF 6

## LEGEND

	SANDS		SANDSTONE (ss)	PB - Pitcher Barrel	PER - Permeability Test
	SILTS		SILTSTONE (slt)	DR - Drive Ring Sample	SW - Swelling Test
	CLAYS		CLAYSTONE (cs)	CHEM - Chemical Test	SI - Sieve Analysis Test
				PI - Atterberg Limits Test	%200 - Percentage Passing
				COMP - Compaction Test	HYD - Hydrometer Test
				DIR - Direct Shear Test	SG - Specific Gravity Test
				TX - Triaxial Test	

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
					cl		FILL, sandy, clay			
1							<u>SAN JOAQUIN FORMATION</u>			
2							SANDSTONE, SILTY SANDSTONE, occasional sandy siltstone, tan, light brown, orange brown, typically very fine, non to weakly cemented			
3										
4										
5										
6	PB	S-1	2.2 2.5							
7							- very fine sandstone, tan, mottled orange			%200
8					ss					
9										
10										
11	PB	S-2	2.3 2.5							
12							- tan, silty sandstone, very fine, minor claystone fragments, weakly cemented			
13										
14										
15										



## LOG OF BORING L18-K

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHF	
BORING NUMBER: L18-K		ELEVATION: 840'	DATE
COORDINATES: N. 228,390 E. 1,701,722		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	5/9/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 2 OF 6

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PERFOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
16	X PB	S-3		$\frac{2.5}{2.5}$			- tan, silty sandstone, very fine			
17										
18										
19										
20										
21	X PB	S-4		$\frac{1.5}{2.5}$			- tan, silty sandstone with orange brown siltstone interbed/pockets			%200
22										
23										
24										
25										
26	X PB	S-5		$\frac{2.4}{2.5}$			- clean sandstone with silty sandstone, sandy siltstone interbeds (or pockets)			SG COMP PER SW
27										
28										
29										
30										
31	X PB	S-6		$\frac{2.5}{2.5}$			- tan, sandy siltstone, mottled orange with minor gray claystone pocket (bioturbation)			
32										
33										
34										
35										






## LOG OF BORING L18-K

PROJECT NUMBER: 89-977				PROJECT NAME: B-18 LANDFILL, KHF						
BORING NUMBER: L18-K				ELEVATION: 804'		DATE				
COORDINATES: N. 228,390 E. 1,701,722				BORING DIA.: 5"		STARTED	COMPLETED			
DRILLING METHODS: MUD ROTARY				WATER DEPTH: NONE		5/9/90	5/10/90			
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)				CHECKED BY: J. BADEL		PAGE: 5 OF 6				
DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
76	X PB	S-15		1.7 1.8			- orange brown silty sandstone, very fine			COMP PER SW
77										
78										
79										
80							- cemented from 80' to 82'			
81	X PB	S-16		1.2 2.3						%200 PI
82										
83							CLAYSTONE, gray, brown, highly plastic, faint orange mottling			
84										
85										
86	X PB	S-17		2.2 2.5			- dark gray claystone			
87										
88										
89					CS					
90										
91	X PB	S-18		2.5 2.5			- dark gray claystone			
92										
93										
94										
95										

## LOG OF BORING L18-K

PROJECT NUMBER: 89-977		PROJECT NAME: B-18 LANDFILL, KHf	
BORING NUMBER: L18-K		ELEVATION: 740'	DATE
COORDINATES: N. 228,780 E. 1,702,480		BORING DIA.: 5"	STARTED
DRILLING METHODS: MUD ROTARY		WATER DEPTH: NONE	3/14/90
ENG/GEO: R. HARLAN (WAHLER ASSOCIATES)		CHECKED BY: J. BADEL	PAGE: 6 OF 6

DEPTH IN FEET	SAMPLE TYPE	SAMPLE NO.	RESISTANCE (BLOWS PER FOOT)	RECOVERY	USCS/ROCK TYPE	PROFILE	DESCRIPTION	MOISTURE CONTENT %	DRY DENSITY (pcf)	OTHER TESTS
96 97	PB	S-19		$\frac{25}{25}$			- dark gray claystone			

- TOTAL DEPTH = 97.5'
- NO GROUND WATER ENCOUNTERED
- BACKFILLED WITH CEMENT GROUT VIA TREMIE

**APPENDIX C**  
**TRENCH AND TEST PIT LOGS**

# TRENCH NO. T-1

SHEET 1 OF 2


DATE 7/21/90

EQUIPMENT: DOZER LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP

BEARING: N50°E NOTES: LOG OF PORTION OF NORTH WALL OF DOZER CUT DT-B

FIELD ENGINEER: R. H. (WAHLER)

DEPTH NO.	UNITS	DESCRIPTION	SAMPLE NO.	LAB TESTS	STRUCTURE			
					NO.	STRIKE	DIP	TYPE
1	<b>COLLUVIUM</b> SANDY CLAY (cl, occasional sc): Light brown, dry-damp; low plasticity; 10-40% very fine sand; typically contains root voids. Unit 1 type-material which occurs beneath disturbed unit 3, and units 2 & 4 are very soft, easily gouged with fingers. Occasional clayey sand, very fine, loose (sc); occasional charcoal.				△	N42°W	33°SW	bedding on unit 5b
2	<b>SAN JOAQUIN FORMATION</b> SANDSTONE (SS): Tan-light brown; well-cemented (hard); moderately strong; underlain by.							
3	SANDSTONE (SS): White-tan, minor orange mottling: Very thick bedded (little discernable bedding). Very fine, non-weakly cemented; soft; friable (easily crumbled to loose soil with fingers).							




REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

### TRENCH NO. T-1 (cont.)

EQUIPMENT: DOZER		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		SHEET <u>2</u> OF <u>2</u>	
BEARING: N50°E		NOTES: LOG OF PORTION OF NORTH WALL OF DOZER CUT DT-B		DATE <u>2/21/90</u>	
FIELD ENGINEER: R. H. (WAHLER)		STRUCTURE		DIP	
DEPTH NO.	UNITS	DESCRIPTION	NO.	STRIKE	TYPE
⑥	SAN JOAQUIN FORMATION (cont.)	SILTY SANDSTONE: Tan-gray; very fine; soft; friable to weak; laminated-thin bedded; 30-40% fines (sm); some siltstone-sandy siltstone interbeds.	△	N43°W	31°SW bedding
①a	COLLUVIUM (?)	SANDY CLAY: Gray-light brown; abundant white mottling (precipitate/gypsum?); appears very stiff; moderate plasticity; possibly severely weathered San Joaquin Formation?			




REV. B/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA



TRENCH NO. T-2		SHEET 1 OF 1	
EQUIPMENT: DOZER		DATE: 2/27/90	
BEARING: N4°E		FIELD ENGINEER: R. H. (WAHLER)	
NOTES:		STRUCTURE	
DEPTH NO.	UNITS DESCRIPTION	SAMPLE NO.	LAB TESTS
①	SANDY CLAY (CL); Light brown; dry-slightly damp; low-moderate plasticity; 10-40% very fine sand; excavates easily.		
②	<b>SAN JOAQUIN FORMATION</b> SANDSTONE (SS): White-tan; very fine; non-weakly cemented; excavates with moderate difficulty; very dense.		
③	CEMENTED SANDSTONE/SILTSTONE (SS/SLT): Orange-brown; moderately hard; moderately strong; excavates with difficulty; appears planar.		




CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

# TRENCH NO. T-3


EQUIPMENT: DOZER		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		SHEET 1 OF 1			
BEARING: S72°W		NOTES:		DATE: 3/23/90			
FIELD ENGINEER: R. H. (WAHLER)		UNITS		STRUCTURE			
DEPTH NO.	DESCRIPTION	SAMPLE NO.	LAB TESTS	NO.	STRIKE	DIP	TYPE
①	SANDY CLAY (SC): Light brown; dry, low-moderate plasticity; 20-40% very fine sand; numerous root voids (pin-hole); caliche along root voids & soil fractures (desiccation cracks); very stiff to hard.			△	N46°W	26°SW	bedding
②	CLAYSTONE (CST): Gray/brown; severely weathered to about 1' below contact with slightly weathered at depth. soft; weak; laminated to thin bedded; occasional siltstone; very fine sandstone laminae.			△	N55°W	73°SW	bedding
				△	N68°W	40°SW	bedding
				△	N43°W	24°SW	bedding

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA



### TEST PIT NO. TP-1

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING: S53°W	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE 2/20/90	LOGGED BY: R. H. (WAHLER)	
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-1	0--6'		NONE	<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; dry -damp; low-moderate plasticity; 20-40% very fine sand; numerous root voids; occasional white precipitate (gypsum?); stiff; excavates easily.</p> <p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② CLAYEY SILTSTONE/CLAYSTONE (SLT/CS): Light brown mottled orange (siltstone); moderate-dark gray (claystone), interbedded; laminated to thin bedded; slightly weathered; soft; weak; excavates with moderate difficulty; 1/4" to 1" thick slabs of hard clay (up to 6" dia.).</p> <p>③ CEMENTED SANDSTONE (SS): White/tan, some orange, brown mottling; fine to coarse sand; moderately hard; moderately strong; slightly weathered.</p> <p>④ SANDSTONE (SS): Tan/white, mottled orange; slightly weathered; very fine; 5-30% fines (sp-sm); very thick bedded; soft; friable; excavates with slight difficulty.</p>	① B-1	~7'



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-2**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: S50°W		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/20/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-2	0'--15'		NONE	<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; dry-damp; low-moderate plasticity; 20-40% very fine sand; numerouw root voids; occasional white precipitate (gypsum?); stiff; excavates easily.</p> <p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② SANDSTONE (SS): Tan/white; faint orange mottling; slightly weathered; soft friable; excavates with slight difficulty; very fine grained.</p>		



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-3**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING: S55°W	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/20/90		LOGGED BY: R.H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-3	0'~18'		NONE	<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; damp; low-moderate plasticity; 10-20% very fine sand, occasional lenses of fine, clayey sand; 10-40% fines; stiff; excavates easily.</p> <p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② SANDSTONE (SS): Tan, stained white (precipitation/gypsum?); some orange mottling; soft; friable; very fine.</p>	① B-1	~15'



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-4**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: S53°W		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/20/90		
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-4	0'--6.5'@ NE end 0--3.5'@ SW end (Thickens to NE towards channel)		NONE	<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; dry-damp; low-moderate plasticity; 10-40% very fine sand; appears firm-stiff; excavates easily.</p> <p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② SANDSTONE (SS): Tan/white, minor orange mottling; very fine; 5-30% fines; soft; friable; slightly weatered; very thick bedded. Excavates with slight difficulty.</p> <p>③ CLAYSTONE (CS): Gray, mottled white (gypsum?); slightly weathered; laminated to very thin bedded; soft; weak; occasional fossils; sand content varies along laminae and in-filled pockets (bioturbation). Excavates with slight difficulty as hard, angular chunks of clay up to ~2" dia.</p>		



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-5

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: N50°E		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/21/90		
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-5	0'-10'		NONE	<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; dry-slightly damp; 30-40% very fine sand; low plasticity appears firm; excavates easily.</p> <p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② SANDSTONE (SS): Light gray; very fine; 20-40% non-plastic fines; soft; friable; excavates with slight difficulty as loose soil to ~3" dia. chunks (easily broken by hand).</p>		
	10'-11.5'					



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-6

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: N38°E		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/21/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-6	varies (see sketch)		NONE	<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; damp; 10-40% very fine sand; low-moderate plasticity; excavates easily; numerous root voids; occasional concentrations of precipitate along root voids (white stringers).</p> <p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② CLAYSTONE (CS): Dark gray; some orange laminae; damp (moderate-severely weathered); soft, friable.</p> <p>③ SILTSTONE/SANDY SILTSTONE (SLT): Tan with orange laminae; slightly weathered; laminated-very thin bedded; soft; excavates with slight difficulty as chunks up to ~2" dia. (can be broken by hand with some difficulty).</p>		



REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.


PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA



### TEST PIT NO. TP-7

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: N36°E		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/22/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-7	0'-12.5'		NONE	<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; dry-slightly damp; low-moderate plasticity; 10-40% very fine sand; numerous root voids; occasional precipitation (gypsum?) stringers; excavates easily; stiff.</p> <p>8-12.5' - medium brown; excavates with moderate difficulty, very stiff, damp; moderate plasticity; generally less sand content (10-20%); occasional gray claystone fragments to 1/2" dia.</p>	<div style="border: 1px solid black; padding: 2px; display: inline-block;">1</div> B-1	~110'
	12.5'-15'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② CLAYSTONE (CS): Dark gray with occasional orange banding (Fe-stain along bedding); slightly weathered; laminated to thin bedded; soft; weak; occasional very fine sand laminae; highly plastic; excavates with slight difficulty as ~1/2" to 3" dia. slabs (up to ~1" thick) of hard clay.</p>		



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-8**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: N41°E		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/22/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-8	0'-14.5'		none	<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; dry-slightly damp; low-moderate plasticity; 10-40% very fine sand; excavates slightly difficultly; stiff; root voids.</p> <p>brown; damp; moderately plastic; excavates with moderate difficulty; occasional white precipitate (gypsum?); rare slickensides (striated slick surfaces noted @ ~9',11'); minor black organic material from ~4' to 14.5'.</p> <p>Occasional gray claystone fragments from ~10' to 14.5' (increased fragments from ~14' to 14.5').</p>	① B-1	7'
	14.5'-15'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② CLAYSTONE (CS): Dark gray; some orange banding; soft; weak; highly plastic; laminated - very thin bedded.</p>		




REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-9**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: N41°E		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/22/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-9	0'-18'		NONE	<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; slightly damp; low-moderate plasticity; root voids.</p> <p>moderate brown; damp; moderately plastic; numerous fine, clayey sand and clean sand laminae (intermittent alluvial deposits); excavates with moderate difficulty (very stiff).</p> <p>NOTE: Unable to reach bedrock (colluvium &gt; 18' deep). Test pit located at floor of DT-B</p>		



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-10

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: S56°W		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/22/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-10	0 - 7'		NONE	<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① CLAYEY SAND, SANDY CLAY (cl,sc): Light brown; dry to damp (moisture content increases with depth); varies from (sc) to (cl), 30-70% fines; medium dense/stiff (very stiff, damp @ depth). Excavates with slight difficulty. Mottled white (gypsum?).</p> <p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② CLAYSTONE (CS): Gray; severely weathered; soft; plastic.</p> <p>②a CLAYSTONE (CS): Dark gray; severely weathered; soft; weak; excavates with moderate difficulty; thick-very thick bedded (bedding not apparent); excavates as ~1/2" to 3" chunks of hard CH.</p>		
	7' - 9'					
	9' - 12.5'					



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-11**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: S51°W		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/21/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-11	0 - 14'		NONE	<p align="center"><u>COLLUVIUM</u></p> <p>① CLAYEY SAND (sc): Light brown; dry-damp; very fine; 20-40% fines; excavates easily; appears loose near surface to medium dense, dense with depth; grades into cleaner sand (10-20% fines) and sandy clay (30-40% very fine sand); moderate white precipitate.</p> <p>9' - 14': Excavates with moderate difficulty (dense); abundant white precipitate (gypsum).</p> <p>13' - 14': Includes white, tubular chunks of hard, cemented sandstone, at random orientations.</p>	① B-1	~7'
	14' - 17.5'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② INTERBEDDED CLAYSTONE/SANDSTONE (CS/SS): Dark gray claystone, highly plastic, soft, weak; tan-gray, very fine sandstone with minor orange mottling; soft, friable; both materials SS non-weakly cemented, laminated - thin bedded (planer chunks up to ~3" thick); Severly weathered claystone, plastic, @ contact (14'--14.5')</p>		




REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

## TEST PIT NO. TP-12

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: N67°W		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/22/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-12	0 - 10.5'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl occasional SC): Dry-slightly damp to ~5'; damp below ~5'; low plasticity; 30-40% very fine sand; occasional grades to clayey sand; appears loose to ~5' (excavates with moderate difficulty below 5'); variable white precipitate.</p>		
	10.5' - 15.5'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② INTERBEDDED CLAYEY SILTSTONE, CLAYSTONE, SANDSTONE: (SLT/CS/SS): Clayey siltstone-brown; claystone-gray; sandstone-tan; entire unit laminated-thin bedded; non-weakly cemented very fine SS; predominately clayey siltstone/claystone (SS ~25% of unit).</p>		



SCALE: 1" = 5'

REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.


PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

TEST PIT NO. TP-13

BEDDING  $\Delta$ : N47°, 32°SW

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: S83°W		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/22/90		
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE NUMBER	DEPTH
TP-13	0 - 6.5'			<p><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; dry to ~5'; damp below ~5'; low-moderate plasticity; variable white precipitate; root voids; stiff to ~5'; very stiff below 5'; 30-40% very fine sand.</p>		
	6.5' - 11.5'			<p><u>SAN JOAQUIN FORMATION</u></p> <p>② CLAYSTONE (CS): Dark, gray; laminated; lesser brown, clayey siltstone laminae; some orange stain along bedding; abundant gypsum @ contact with ①; soft; weak.</p> <p>③ SILTY SANDSTONE (SLT/SS): Tan-light brown; very fine; thick-very thick bedded (bedding not discernible); non-weakly cemented; soft; friable.</p>	① B-1	~4'




REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

TEST PIT NO. TP-14

BEDDING  $\Delta$ : N48°, 33°SW

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: S51°W		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 2/22/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-14	0 - ~7'			<p><u>COLLUVIUM</u></p> <p>① CLAYEY SAND (sc): Light brown; dry; very loose-loose; very fine; 20-40% fines; excavates easily.</p>		
	7' - ~12'			<p><u>SAN JOAQUIN FORMATION</u></p> <p>② SANDSTONE (SS): Tan-white; thin-medium bedding; (dense) friable: non-cemented (easily crumbled with fingers); excavates with slight difficulty.</p>		



REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.


PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA



**TEST PIT NO. TP-15**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: S54°W		
RIG: CAT 426 BACKHOE		PIT WIDTH: 36"		DATE: 2/27/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-15	0 - 11'			<p align="center"><u>COLLUVIUM</u></p> <p>① CLAYEY SAND (sc occasional cl): Light brown; slightly damp; very fine; 20-40% fines; occasional grades to sandy clay; 30-40% very fine sand; excavates easily; appears medium dense; occasional white mottling (precipitate/gypsum?); numerous root voids.</p>	1 B-1	~7'
	11' - 12'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② SANDSTONE (SS): Tan-white; soft; friable; very fine; very thick bedded; excavates with slight difficulty; occasionally thin (up to ~1" thick) cemented layers. Excavates as loose, fine sand (sp).</p>		



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-16

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: N54°E		
RIG: CAT 426 BACKHOE		PIT WIDTH: 36"		DATE: 2/27/90		
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-16	0 - 5.5'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (ci): Light brown; damp; low plasticity; 30-40% very fine sand; appears very stiff; excavates easily; root voids; variable white mottling (gypsum(?) stringers along root voids and soil fractures).</p>		
	5.5' - 8.5'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② CLAYSTONE (CS): Moderate-dark gray; severely weathered to ~1.5' below contact (slightly weathered at greater depth); soft; weak (plastic where severely weathered); excavates with slight difficulty; laminated to very thin bedded.</p>		



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-17

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: S44°E		
RIG: CAT 426 BACKHOE		PIT WIDTH: 36"		DATE: 2/27/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-17	0 - 8'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light moderate brown; slightly damp-damp; low plasticity; 30-40% very fine sand; numerous root voids; white precipitate; excavates with ease - slight difficulty; appears very stiff.</p>	<div style="border: 1px solid black; padding: 2px; display: inline-block;">1</div> B-1	-8'
	8' - 10'		<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② SAND-CLAYEY SAND (SP-SC): Tan-light brown; very fine; 5-15% fines; resembles (probably derived from) San Joaquin Formation sandstone immediately upslope (SW); includes gray claystone fragments to 1/2" dia.</p>			
	10' - 11.5'		<p>③ CLAYSTONE (CS): Dark gray; laminated to thin bedded, soft; weak; highly plastic.</p>			




REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-18

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING: S44°E	
RIG: CAT 426 BACKHOE		PIT WIDTH: 36"		DATE: 2/27/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-18	0 - 10'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light moderate brown; slightly damp; low-moderate plasticity; 10-40% very fine, sand; stiff-very stiff; excavates with slight difficulty; variable white precipitate.</p>	① B-1	~2' (sample from n-opposite wall of dozer cut)
	10' - 13.5'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② CLAYSTONE (CS): Dark gray; soft; weak; laminated-thin bedded; highly plastic; slickensides; numerous very fine sandstone, siltstone laminae (up to ~1/2" thick).</p>	② B-2	~12'



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-19**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: S55°W		
RIG: CAT 426 BACKHOE		PIT WIDTH: 36"		DATE: 2/27/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-19	0 - ~13' (see sketch)			<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY, CLAYEY SAND (cl,SC): Light brown; slightly damp; variable cl,SC; cl: low plasticity, 10-40% very fine sand; SC: very fine, 10-40% fines; excavates easily to ~8'; slightly difficult excavation below ~8'. Occasional laminated sand/silt, SP/ML-cl (old alluvium deposits).</p>		
	13' - 15'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② INTERBEDDED SANDSTONE/CLAYSTONE (CS/SS): Sandstone: Tan, mottled orange; very fine; bioturbation; soft, friable; claystone: Dark gray; highly plastic; excavates with slight difficulty.</p>		




REV. 6/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-20**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING: S53°W		
RIG: CAT 426 BACKHOE		PIT WIDTH: 36"		DATE: 2/27/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-20	0 - 15.5'			<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY(cl): Light brown; dry-damp low-moderate plasticity; 10-40% very fine sand; excavates easily.</p>		
	15.5' - 16'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② CLAYEY SILTSTONE (SLT): Light gray-brown; slighty plastic; soft; friable.</p>		




REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-21

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING: N72°W	
RIG: CAT 426 BACKHOE		PIT WIDTH: 36"		DATE: 2/27/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-21	0 - 11'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Light brown; slightly damp-damp; low-moderate plasticity; 10-30% very fine sand; stiff (excavates with slight difficulty).</p>		
	11' - 12.5'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② CLAYEY SILTSTONE (SLT): Light gray; soft; friable to weak; low-moderate plasticity; laminated; fragments can be crumbled by fingers with moderate effort.</p>		




REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

TEST PIT NO. TP-22

BEDDING  $\Delta$ : N50°W, 28°SW

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING:		
RIG: CAT 426 BACKHOE		PIT WIDTH: 30"		DATE: 3/19/90		
LOGGED BY: A. S. B. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION - EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-22	0 - 4.5'			<p><u>COLLUVIUM</u></p> <p>① SANDY CLAY to CLAYEY SAND (cl-sc): Moderate brown; fine sand; about 25% slightly plastic to low plastic fines; loose; dry.</p>		
	4.5' - 8'			<p><u>SAN JOAQUIN FORMATION</u></p> <p>② SANDSTONE (SS): Brownish gray; fine to medium sand; ~5-10% silt; streaks of gypsum; loose to medium dense; dry; 4" thick cemented, hard reddish sandstone at 6.5'.</p>		



REV. B/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977


LOCATION KETTLEMAN, CALIFORNIA



TEST PIT NO. TP-23

STRIKE  $\Delta$ : N40°W, 31°SW DIP

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:		
RIG: CAT 426 BACKHOE		PIT WIDTH: 30"		DATE: 3/19/90		LOGGED BY: A. S. B. (WAHLER)	
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE		
					NUMBER	DEPTH	
TP-23	0 - 4'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SILTY SAND (sm): Moderate brown; fine sand; 15-20% slightly plastic to low plastic fines; dry.</p>	B-1		
	4' - 5.5'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② INTERBEDDED CLAYSTONE and SILTSTONE (CS/SLT): Laminated to thinly bedded; olive-gray with yellow-orange to yellow-brown staining; thin (1/8") sand laminae.</p>			



REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.


PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

TEST PIT NO. TP-24

STRIKE  $\Delta$ : N40°W, 31°SW DIP

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGY MAP		BEARING:		
RIG: CAT 426 BACKHOE		PIT WIDTH: 30"		DATE: 3/19/90		
LOGGED BY: A. S. B. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-24	0 - 4.5'			<p><u>COLLUVIUM</u></p> <p>① CLAYEY SAND (sm): Moderate brown; 15-20% non-plastic fines; fine sand; loose; dry.</p>		
	4.5' - 6.0'			<p><u>SAN JOAQUIN FORMATION</u></p> <p>② SANDSTONE (SS): Light gray with yellow-brown streaks; fine sand; weakly cemented; old borrow holes in sandstone at contact (filled in with silty sand Oc) included "wavy" lenses of olive-gray claystone in sandstone).</p>		



SCALE: 1"=5'

REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-25**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 30"		DATE: 3/19/90		LOGGED BY: A. S. B. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-25	0 - 7'			<p align="center"><u>COLLUVIUM</u></p> <p>① CLAYEY to SILTY SAND (sc-sm): Moderate brown; fine to very fine sand; pockets of sandy clay; ~20-25% slightly plastic fines.</p>	B-1	0-7'
	7' - 12.5'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② INTERBEDDED CLAYSTONE/SANDSTONE (CS/SS): Thinly bedded; bioturbation; olive-gray.</p>		



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-26**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 30"		DATE: 3/19/90		LOGGED BY: A. S. B. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-26	0 - 10.5'			<p align="center"><u>COLLUVIUM</u></p> <p>① CLAYEY SAND (sc): Moderate yellow-brown; fine to very fine sand; slightly to low plastic fines; dry; loose to moderately dense.</p>	B-1	0-10.5'
	10.5' - 12'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② SANDSTONE (SS): Moderate yellow-brown mottled with yellow-orange stains.</p>		



SCALE: 1"=5'

REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-27

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 30"		DATE: 3/19/90		LOGGED BY: A. S. B. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-27	0 - 12'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Moderate yellow-brown; fine to very fine sand; low to moderate plastic fines; compact; dry; stiff.</p>	B-1	0-12'




REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-28**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 30"		DATE: 3/19/90		LOGGED BY: A. S. B. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-28	0 - 12.5'			<p align="center"><u>COLLUVIUM</u></p> <p>① CLAYEY SAND (sc): Moderate yellow-brown; fine to very fine sand; ~25-30% slightly to low plastic fines; medium dense; dry.</p>	B-1	0-12.5'
	12.5'-13.5'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② INTERBEDDED CLAYSTONE/SILTSTONE (CS/SLT): Light brownish gray; with yellow-orange laminates; thinly bedded.</p>	B-2	12.5'-13.5'




REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-29

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/10/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-29	0 - 4'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SILTY CLAY (cl)</p>		
	4' - 6.5'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-10 CLAYSTONE (CS): Gray; highly plastic; excavates as angular; gravel to cobble-sized chunks of highly plastic, hard clay; chunk size increases with depth. NOTE: Claystone is only one lithologic member of Unit 18-10 (interbedded SS, CS, SLT, SILTY SS).</p>	B-1	4-6.5' (composite)



SCALE: 1"=5'

REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-30**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/10/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-30	0 - 3'			<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl)</p>	B-1	-7'
	3' - 7'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-11 INTERBEDDED SANDSTONE/CLAYSTONE (SS/CS): Tan, very fine, clean sandstone (excavates as loose SP) with lesser, interbedded gray claystone (thin beds up to 1.5" thick, highly plastic; excavating as angular chunks up to ~3" dia. hard clay). NOTE: Unit 18-11 is predominately clean SS.</p>		



SCALE: 1"=5'

REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.


PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA



**TEST PIT NO. TP-31**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING:		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/10/90		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		LOGGED BY: R. H. (WAHLER)		
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-31	0 - 3'			<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl): Moderate-dark brown; moderate plasticity; very stiff to hard.</p>	B-1	3'-6' composite
	3' - 6'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-12 CLAYSTONE (CS): Gray; highly plastic; moderate to severely weathered to ~3.5'; fresh-slightly weathered below 3.5' (size of excavated blocks increases with depth and with decreased weathering); excavates as hard, angular, gravel to cobble-sized blocks.</p>		




REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-32**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING:		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/10/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-32	0 - 3'			<p align="center"><u>COLLUVIUM</u></p> <p>① CLAYEY SAND (SC)</p>		
	3' - 5'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-13 SANDSTONE (SS): Tan-white; occasional gypsum/caliche (thin, white cemented layers, up to ~.5" thick); excavates as clean, very fine sand (loose SP).</p>	B-1	-5'



SCALE: 1"=5'

REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-33**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/10/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-33	0 - 5'			<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl)</p>		
	5' - 8'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-13 SANDSTONE (SS): Tan, some orange mottling; excavates as clean, very fine to fine sand (loose SP); non-cemented with occasional thin cemented beds (up to ~2' thick)</p>	B-1	~8'



SCALE: 1"=5'

REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-34**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP		BEARING:		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/10/90		
LOGGED BY: R. H. (WAHLER)						
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-34	0 - 2'			<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl)</p>		
	2' - 5'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-12 CLAYSTONE (CS): Gray; moderate to severely weathered to 3'; slightly weathered below 3'; excavates as angular gravel to boulder sized blocks of hard claystone. Blocks become larger (up to 1') below the weathered zone.</p>	B-1	~4'



SCALE: 1"=5'

REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-35**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/11/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-35	0 - >16'			<p align="center"><u>COLLUVIUM</u></p> <p>① SILTY CLAY, SANDY CLAY, CLAYEY SAND (cl, sc)</p>		



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-36**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/10-5/11/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-36	0 - .5'			<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl)</p>		
	.5' - 4'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unk 18-8 CLAYSTONE (CS): Gray, orange-brown; moderate to severely weathered to 1.5'; fresh, slightly weathered below 1.5'; excavates as angular, gravel to boulder-sized blocks &amp; slabs of hard CH.</p>	B-1	~4'



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-37

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/10-5/11/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-37	0 - 1.5'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl)</p>		
	1.5' - 6'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-8 CLAYSTONE (CS): Gray, orange-brown; laminated to thin bedded cl; moderate-severely weathered to 2.5'; fresh-slightly weathered below 2.5'; excavates as angular, gravel to boulder-sized blocks and slabs of hard CH (below 2.5').</p>	B-1	~6'



SCALE: 1" = 5'

REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**TEST PIT NO. TP-38**

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/11/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-38	0 - 5'			<p align="center"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl)</p>		
	5' - 9'			<p align="center"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-8 CLAYSTONE (CS): Gray, orange-brown, light brown; laminated to thin bedded; occasional sand laminae (very minor); excavates as gravel-cobble-sized blocks.</p>		



REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.


PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA



### TEST PIT NO. TP-39

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:		
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/11/90		LOGGED BY: R. H. (WAHLER)	
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE		
					NUMBER	DEPTH	
TP-39	0 - 8'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl)</p>			
	8' - 11'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-8 CLAYSTONE (CS): Gray, highly plastic; hard, excavates as angular; gravel to cobble-sized blocks with 6" dia.; minor sand laminae.</p>			



REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-40

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/11/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-40	0 - 4'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>① Unit 18-8 CLAYSTONE (CS): Gray, brown, occasional orange; highly plastic; includes .5' thick cemented sandstone bed at 3'; laminated to thin bedded; excavates as gravel to cobble-sized slabs and blocks. NOTE: Excavated in cut slope.</p>	B-1	~3'



SCALE: 1" = 5'

REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

## TEST PIT NO. TP-41

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/11/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-41	0 - 3.5'			<u>SAN JOAQUIN FORMATION</u>  ① Unit 18-8 CLAYSTONE (CS): Moderate brown - gray-brown, occasional orange laminae; highly plastic; excavates as gravel-cobble-sized chunks (to ~5"); minor very fine sand laminae. NOTE: Excavated in cut slope.	B-1	~3.5'




SCALE: 1" = 5'

REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.  
 PROJECT NO. 89-977  
 LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-42

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/10-5/11/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-42	0 - 2.5'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl)</p>		
	2.5' - 6'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-9 SANDSTONE-SILTY SANDSTONE (SS): Tan, light brown, mottled orange; very fine; 5-20% fines; excavates as loose sand (SP-SM) or as friable chunks (easily crushed by hand).</p>	B-1	~6'



SCALE: 1" = 5'

REV. 8/14/90


CLIENT CHEMICAL WASTE MANAGEMENT, INC.

PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

### TEST PIT NO. TP-43

SHEET 1 OF 1		LOCATION: SEE FIGURE 2.3 - SITE GEOLOGIC MAP			BEARING:	
RIG: CAT 426 BACKHOE		PIT WIDTH: 24"		DATE: 5/10-5/11/90		LOGGED BY: R. H. (WAHLER)
TEST PIT NO.	DEPTH INTERVAL	SOIL TYPE	WATER DEPTH	MATERIAL DESCRIPTION EXCAVATION CHARACTERISTICS	SAMPLE	
					NUMBER	DEPTH
TP-43	0 - 1.5'			<p style="text-align: center;"><u>COLLUVIUM</u></p> <p>① SANDY CLAY (cl)</p>		
	1.5' - 7'			<p style="text-align: center;"><u>SAN JOAQUIN FORMATION</u></p> <p>② Unit 18-9 SILTY SANDSTONE-SANDY SILTSTONE (SS/SLT): Light brown, mottled orange; very fine sand; excavates as friable (easily powdered by hand) chunks and loose soil (SM-ML) contains numerous pockets of gray, brown claystone (CH) - bioturbation.</p>	B-1	-6'



SCALE: 1" = 5'

REV. 8/14/90

CLIENT CHEMICAL WASTE MANAGEMENT, INC.


PROJECT NO. 89-977

LOCATION KETTLEMAN, CALIFORNIA

**APPENDIX D  
LABORATORY DATA**

<b>APPENDIX D.1</b>	<b>PLASTICITY CHARTS</b>
<b>APPENDIX D.2</b>	<b>GRAIN SIZE DISTRIBUTIONS</b>
<b>APPENDIX D.3</b>	<b>MODIFIED PROCTOR COMPACTION TESTS</b>
<b>APPENDIX D.4</b>	<b>STANDARD PROCTOR COMPACTION TESTS</b>
<b>APPENDIX D.5</b>	<b>UU TRIAXIAL COMPRESSION TESTS (UNDISTURBED SAMPLES)</b>
<b>APPENDIX D.6</b>	<b>UU TRIAXIAL COMPRESSION TESTS (REMOLDED SAMPLES)</b>
<b>APPENDIX D.7</b>	<b>CU TRIAXIAL COMPRESSION TESTS</b>
<b>APPENDIX D.8</b>	<b>SUMMARY OF DIRECT SHEAR TESTS</b>
<b>APPENDIX D.9</b>	<b>CONSOLIDATION TESTS</b>
<b>APPENDIX D.10</b>	<b>GEOCHEMICAL TESTS</b>


**APPENDIX D.1**  
**PLASTICITY CHARTS**



SYMBOL	STRATIGRAPHIC UNIT	BORING NO.	SAMPLE NO.	DEPTH (FT.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USC SYMBOL
○	18-2	L18-E	S-8	60.0 - 62.5	53	32	CH
⬡	18-3	L18-E	S-6	43.0 - 45.0	32	6	ML
△	18-4	L18-D	S-6	52.0 - 54.3	67	42	CH
□	18-5	L18-D	S-2	22.0 - 24.3	49	29	CL/CH


**FIGURE D.1.1**  
**PLASTICITY CHART**  
**STRATIGRAPHIC UNITS**  
**18-2 THROUGH 18-5**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**






SYMBOL	STRATIGRAPHIC UNIT	BORING NO.	SAMPLE NO.	DEPTH (FT.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USC SYMBOL
○	18-7	L18-C	S-1	15.0 - 17.3	38	17	CL
⬡	18-7	L18-C	S-3	25.0 - 27.5	46	23	CL
△	18-7	L18-C	S-7	56.0 - 58.0	60	36	CH
□	18-7	L18-C	S-11	87.0 - 89.0	41	17	CL

FIGURE D.1.2  
**PLASTICITY CHART**  
**STRATIGRAPHIC UNIT 18-7**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.




SYMBOL	STRATIGRAPHIC UNIT	BORING NO.	SAMPLE NO.	DEPTH (FT.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USC SYMBOL
○	18-8	L18-F	S-1	6.0 - 8.5	78	55	CH
⊙	18-8	L18-F	S-3	26.0 - 28.5	69	57	CH
△	18-8	L18-F	S-6	56.0 - 58.5	59	39	CH
□	18-8	L18-I	S-2	16.0 - 18.5	58	36	CH

FIGURE D.1.3  
**PLASTICITY CHART**  
**STRATIGRAPHIC UNIT 18-8**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**




SYMBOL	STRATIGRAPHIC UNIT	BORING NO.	SAMPLE NO.	DEPTH (FT.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USC SYMBOL
○	18-8	L18-J	S-1	5.0 - 7.5	55	30	CH
⬡	18-8	L18-J	S-3	15.0 - 17.5	67	41	CH
△	18-8	L18-J	S-5	25.0 - 27.5	79	50	CH
□	18-8	L18-J	S-7	35.0 - 37.5	64	40	CH
●	18-8	L18-J	S-9	45.0 - 47.5	74	49	CH
⬢	18-8	L18-J	S-11	55.0 - 57.5	69	46	CH
▲	18-8	L18-J	S-13	65.0 - 67.5	74	50	CH
■	18-8	L18-J	S-15	75.0 - 77.5	33	17	CL
⊙	18-8	L18-J	S-17	85.0 - 87.5	56	38	CH
⬢	18-8	L18-J	S-22	110.0-112.5	71	47	CH
⊠	18-8	L18-J	S-24	120.0-122.5	70	42	CH
⊞	18-8	L18-J	S-26	130.0-132.8	88	60	CH
⊕	18-8	L18-J	S-28	140.0-142.5	85	53	CH
⊗	18-8	L18-J	S-30	150.0-152.5	88	62	CH
⊞	18-8	L18-J	S-32	160.0-162.5	55	30	CH

FIGURE D.1.4  
**PLASTICITY CHART**  
**STRATIGRAPHIC UNIT 18-8**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**




SYMBOL	STRATIGRAPHIC UNIT	BORING NO.	SAMPLE NO.	DEPTH (FT.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USC SYMBOL
○	18-9	18-K	S-10	80.0 - 82.3	30	11	CL

FIGURE D.1.5  
**PLASTICITY CHART**  
**STRATIGRAPHIC UNIT 18-9**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**




SYMBOL	STRATIGRAPHIC UNIT	BORING NO.	SAMPLE NO.	DEPTH (FT.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USC SYMBOL
○	18-10	L18-H	S-1	6.0 - 8.5	81	50	CH
⬡	18-10	L18-H	S-4	35.0 - 37.5	78	51	CH
△	18-10	L18-H	S-6	55.0 - 57.5	71	49	CH

FIGURE D.1.6  
**PLASTICITY CHART  
 STRATIGRAPHIC UNIT 18-10**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.



SYMBOL	STRATIGRAPHIC UNIT	BORING NO.	SAMPLE NO.	DEPTH (FT.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USC SYMBOL
○	18-12	L18-B	S-1	6.0 - 8.5	64	36	CH
⬡	18-12	L18-G	S-7	50.0 - 51.8	78	49	CH
△	18-12	L18-G	S-9	65.0 - 67.0	60	36	CH
□	18-12	TP-31	B-1	3.5	70	49	CH

FIGURE D.1.7  
**PLASTICITY CHART**  
**STRATIGRAPHIC UNIT 18-12**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.




SYMBOL	STRATIGRAPHIC UNIT	BORING NO.	SAMPLE NO.	DEPTH (FT.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	USC SYMBOL
○	COLLUVIUM	L18-C	B-1	6.0 - 7.5	35	19	CL
⬡	COLLUVIUM	L18-D	B-2	10.0 - 11.5	29	13	CL

FIGURE D.1.8  
**PLASTICITY CHART  
 COLLUVIUM**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.

**APPENDIX D.2**  
**GRAIN SIZE DISTRIBUTIONS**




SYMBOL	BORING	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE	USCS
○—○	L18-D	10.0 - 11.5	29	13	Colluvium	Clayey Sand	SC






SYMBOL	BORING	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE	USCS
○—○	L18-C	15.0-17.3	38	17	18-7	Claystone	CH
△-----△	L18-C	56.0-58.0	60	36	18-7	Claystone	CH




SYMBOL	BORING	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE	USCS
○—○	L18-I	16.0-18.5	58	36	18-8	Claystone	CH
△----△	L18-F	6.0-8.5	78	55	18-8	Claystone	CH
□—□	L18-F	26.0-28.5	59	47	18-8	Claystone	CH
+-----+	L18-F	56.0-58.5	59	39	18-8	Claystone	CH



COBBLES	GRAVEL		SAND			SILT AND CLAY FRACTION
	coarse	fine	coarse	medium	fine	

**FIGURE D.2.4**  
**GRAIN SIZE DISTRIBUTION**  
**STRATIGRAPHIC UNIT 18-8**  
  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**


SYMBOL	BORING	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE	USCS
○—○	L18-J	5-7.5	55	30	18-8	Claystone	CH
△---△	L18-J	35-37.5	64	40	18-8	Claystone	CH
□—□	L18-J	75-77.5	33	17	18-8	Claystone	CH
○- - -○	L18-J	120-122.5	70	42	18-8	Claystone	CH
◇- -◇	L18-J	160-162.5	55	30	18-8	Claystone	CH



COBBLES	GRAVEL		SAND			SILT AND CLAY FRACTION
	coarse	fine	coarse	medium	fine	

**FIGURE D.2.5**  
**GRAIN SIZE DISTRIBUTION**  
**STRATIGRAPHIC UNIT 18-8**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**


SYMBOL	TEST PIT	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE	USCS
○—○	DT-A,B-2	5.0	82	54	18-8	Claystone	CH
+-----+	DT-C,B-1	8.0	78	56	18-8	Claystone	CH
△—△	TP-36,B-1	4.0	78	56	18-8	Claystone	CH
□—□	TP-38,B-1	9.0	52	34	18-8	Claystone	CH
◇—◇	TP-40,B-1	3.0	28	7	18-8	Claystone	CH



COBBLES	GRAVEL		SAND			SILT AND CLAY FRACTION
	coarse	fine	coarse	medium	fine	

**FIGURE D.2.6**  
**GRAIN SIZE DISTRIBUTION**  
**STRATIGRAPHIC UNIT 18-8**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**


SYMBOL	TEST PIT TYPE	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE	USCS
+——+	TP-1, B-1	7.0	--	--	18-9	Sandstone	SM
Δ-----Δ	TP-42, B-1	6.0	--	--	18-9	Sandstone	SM



COBBLES	GRAVEL		SAND			SILT AND CLAY FRACTION
	coarse	fine	coarse	medium	fine	

**FIGURE D.2.7**  
**GRAIN SIZE DISTRIBUTION**  
**STRATIGRAPHIC UNIT 18-9**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**

SYMBOL	BORING	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE	USCS
○—○	L18-B	37.0-39.5	--	--	18-11	Sandstone	SM




COBBLES	GRAVEL		SAND			SILT AND CLAY FRACTION
	coarse	fine	coarse	medium	fine	

**FIGURE D.2.8**  
**GRAIN SIZE DISTRIBUTION**  
**STRATIGRAPHIC UNIT 18-11**  
  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.




SYMBOL	BORING	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE	USCS
○—○	L18-B	6.0-8.5	64	36	18-12	Claystone	CH
△-----△	L18-G	50.0-51.8	78	44	18-12	Claystone	CH
+-----+	L18-G	65.0-67.0	60	36	18-12	Claystone	CH



COBBLES	GRAVEL		SAND			SILT AND CLAY FRACTION
	coarse	fine	coarse	medium	fine	


**FIGURE D.2.9**  
**GRAIN SIZE DISTRIBUTION**  
**STRATIGRAPHIC UNIT 18-12**  
  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.

**APPENDIX D.3**  
**MODIFIED PROCTOR COMPACTION TESTS**




SUMMARY OF COMPACTION TEST RESULTS			
SYMBOL	○	△	□
SAMPLE NO.	COMP. NO. 1	COMP. NO. 2	COMP. NO. 3
MATERIAL TYPE	CLAYSTONE	CLAYSTONE	CLAYSTONE
TEST METHOD	ASTM D1557, METHOD 78A		
MAXIMUM DRY DENSITY (PCF)	98.7	100.7	96.2
OPTIMUM MOISTURE CONTENT (%)	22.8	21.7	24.9
LIQUID LIMIT	67	63	76
PLASTICITY INDEX	40	40	50
SPECIFIC GRAVITY	2.79	2.79	2.79
UNIFIED SOILS CLASSIFICATION	CH	CH	CH

FIGURE D.3.1  
**MODIFIED PROCTOR TESTS**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.



SUMMARY OF COMPACTION TEST RESULTS				
SYMBOL	○	△	□	●
SAMPLE NO.	TP-42, B-1	DT-C, B-1	COMP. NO. 10	DT-A, B-2
MATERIAL TYPE	SANDSTONE	CLAYSTONE	COLLUVIUM	CLAYSTONE
TEST METHOD	ASTM D1557, METHOD 7BA			
MAXIMUM DRY DENSITY (PCF)	114.8	99.0	123.3	104.2
OPTIMUM MOISTURE CONTENT (%)	15.0	23.5	12.3	21.5
LIQUID LIMIT	--	76	--	82
PLASTICITY INDEX	--	45	--	54
SPECIFIC GRAVITY	2.8	2.8	2.7	2.7
UNIFIED SOILS CLASSIFICATION	SM	CL	SC	CH

FIGURE D.3.2  
**MODIFIED PROCTOR TESTS**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.




SUMMARY OF COMPACTION TEST RESULTS			
SYMBOL	○	△	□
SAMPLE NO.	COMP. NO. 5	COMP. NO. 7	COMP. NO. 9
MATERIAL TYPE	50% cs/50% ss	50% cs/50% ss	50% cs/50% ss
TEST METHOD	ASTM D1557, METHOD 78A		
MAXIMUM DRY DENSITY (PCF)	106.6	103.7	105.3
OPTIMUM MOISTURE CONTENT (%)	19.8	20.3	19.0
LIQUID LIMIT	--	--	--
PLASTICITY INDEX	--	--	--
SPECIFIC GRAVITY	2.75	2.75	2.75
UNIFIED SOILS CLASSIFICATION	CL	CL	CL

FIGURE D.3.3

**MODIFIED PROCTOR TESTS**

LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY

**ENVIRONMENTAL SOLUTIONS, INC.**



SUMMARY OF COMPACTION TEST RESULTS			
SYMBOL	○	△	□
SAMPLE NO.	COMP. NO. 4	COMP. NO. 6	COMP. NO. 8
MATERIAL TYPE	70% cs/30% ss	70% cs/30% ss	70% cs/30% ss
TEST METHOD	ASTM D1557, METHOD 78A		
MAXIMUM DRY DENSITY (PCF)	104.9	102.9	104.0
OPTIMUM MOISTURE CONTENT (%)	20.8	21.9	19.8
LIQUID LIMIT	--	--	--
PLASTICITY INDEX	--	--	--
SPECIFIC GRAVITY	2.7	2.7	2.7
UNIFIED SOILS CLASSIFICATION	CL	CL	CL


FIGURE D.3.4

**MODIFIED PROCTOR TESTS**

LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY

**ENVIRONMENTAL SOLUTIONS, INC.**

**APPENDIX D.4**  
**STANDARD PROCTOR COMPACTION TESTS**



SUMMARY OF COMPACTION TEST RESULTS		
SYMBOL	○	△
SAMPLE NO.	COMP. NO. 1	COMP. NO. 11
MATERIAL TYPE	70% cs/30% ss	CLAYSTONE
TEST METHOD	ASTM D698 (STANDARD PROCTOR)	
MAXIMUM DRY DENSITY (PCF)	94.2	87.7
OPTIMUM MOISTURE CONTENT (%)	27.0	29.7
LIQUID LIMIT	--	76
PLASTICITY INDEX	--	45
SPECIFIC GRAVITY	2.8	2.8
UNIFIED SOILS CLASSIFICATION	CL	CH

FIGURE D.4.1  
**STANDARD PROCTOR TESTS**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.



**APPENDIX D.5**  
**UU TRIAXIAL COMPRESSION TESTS**  
**(UNDISTURBED SAMPLES)**

TABLE D.5.1

SUMMARY OF UNCONSOLIDATED UNDRAINED (UU) TRIAXIAL TEST  
(UNDISTURBED SAMPLES)

BORING NO.	SAMPLE NO.	SAMPLE DEPTH (FT)	STRATIGRAPHIC UNIT	MATERIAL TYPE	NATURAL		CONFINING PRESSURE (PSI)	DEVIATOR STRESS			
					WATER CONTENT (%)	DRY DENSITY (PCF)		PEAK (PSI)	STRAIN (%)	RESIDUAL (PSI)	STRAIN (%)
L18-B	S-3	20.0 - 22.5	18-11	Sandstone	20	101.0	27.8	106.4	6	71.1	11
L18-B	S-5	37.0 - 39.5	18-11	Sandstone	18	101.1	55.6	255.6	8	130.3	10
L18-B	S-5	37.0 - 39.5	18-11	Sandstone	13	102.9	83.3	291.7	4	231.4	11
L18-C	S-8	64.0 - 66.3	18-7	Claystone	22	98.5	27.8	142.7	4	81.4	10
L18-C	S-6	48.0 - 50.1	18-7	Claystone	19	102.8	55.6	221.2	4	142.9	10
L18-C	S-8	64.0 - 66.3	18-7	Claystone	19	105.0	83.3	179.7	4	124.6	10
L18-D	S-2	22.0 - 24.3	18-5	Claystone	19	95.1	27.8	143.8	3	101.9	8
L18-D	S-3	29.0 - 31.5	18-5	Claystone	19	100.4	55.6	214.0	5	144.8	10
L18-D	S-2	22.0 - 24.3	18-5	Claystone	17	93.0	83.3	254.1	5	232.0	10
L18-F	S-6	56.0 - 58.5	18-8	Claystone	26	95.0	27.8	182.2	2	73.6	8
L18-F	S-5	46.0 - 48.1	18-8	Claystone	26	94.9	55.6	163.3	2	65.1	7
L18-F	S-6	56.0 - 58.5	18-8	Claystone	29	88.3	83.3	123.9	3	72.7	7
L18-G	S-4	30.0 - 32.0	18-13	Sandstone	16	101.5	27.8	135.5	3	82.1	10
L18-G	S-5	40.0 - 41.3	18-13	Sandstone	12	101.5	55.6	235.6	4	176.1	10
L18-G	S-4	30.0 - 32.0	18-13	Sandstone	14	101.0	83.3	270.8	4	215.4	12.5
L18-G	S-6	45.0 - 47.5	18-12	Claystone	30	91.3	27.8	130.6	2	53.1	7
L18-G	S-7	50.0 - 51.8	18-12	Claystone	28	91.8	55.6	95.4	2	78.3	5
L18-G	S-6	45.0 - 47.5	18-12	Claystone	29	92.7	83.3	144.3	2	72.7	7




FIGURE D.5.1  
**UNCONSOLIDATED UNDRAINED  
 TRIAXIAL TEST RESULTS**  
**BORING NO. L18-B**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**

SPECIMEN NO.	SAMPLE NO.	DEPTH (FEET)	INITIAL STATE		CONFINING PRESSURE (PSI)	DEVIATOR STRESS AT FAILURE (PSI)	STRAIN AT FAILURE (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE
			w (%)	$\gamma_d$ (PCF)					
①	S-3	20.0-22.5	19.6	101.0	27.8	106.4	6.0	18-11	UNDISTURBED SANDSTONE
②	S-5	37.0-39.5	17.9	101.1	55.6	255.6	2.5		
③	S-5	37.0-39.5	13.2	102.9	83.3	291.7	3.5		





FIGURE D.5.2  
**UNCONSOLIDATED UNDRAINED  
 TRIAXIAL TEST RESULTS**  
 BORING NO. L18-C  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**



SPECIMEN NO.	SAMPLE NO.	DEPTH (FEET)	INITIAL STATE		CONFINING PRESSURE (PSI)	DEVIATOR STRESS AT FAILURE (PSI)	STRAIN AT FAILURE (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE
			w (%)	$\gamma_g$ (PCF)					
①	S-8	64.0 - 66.3	21.7	98.5	27.8	142.7	3.5	18-7	UNDISTURBED SILTY CLAYSTONE
②	S-6	48.0 - 50.1	18.7	102.8	55.6	221.2	3.5		
③	S-8	64.0 - 66.3	19.3	105.0	83.3	179.7	4.0		



SPECIMEN NO.	SAMPLE NO.	DEPTH (FEET)	INITIAL STATE		CONFINING PRESSURE (PSI)	DEVIATOR STRESS AT FAILURE (PSI)	STRAIN AT FAILURE (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE
			$\sigma_3$ (%)	$\gamma_c$ (PCF)					
①	S-2	22.0 - 24.3	18.6	95.1	27.8	143.0	3.0	18-5	UNDISTURBED CLAYSTONE
②	S-3	29.0 - 31.5	19.1	100.4	55.6	214.0	4.5		
③	S-2	22.0 - 24.3	17.4	93.0	83.3	254.1	4.5		

FIGURE D.5.3  
**UNCONSOLIDATED UNDRAINED TRIAXIAL TEST RESULTS**  
**BORING NO. L18-D**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY

ENVIRONMENTAL SOLUTIONS, INC.



AXIAL STRAIN (%)

TOTAL NORMAL STRESS (PSI)

SPECIMEN NO.	SAMPLE NO.	DEPTH (FEET)	INITIAL STATE		CONFINING PRESSURE (PSI)	DEVIATOR STRESS AT FAILURE (PSI)	STRAIN AT FAILURE (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE
			w (%)	γ <sub>v</sub> (PCF)					
①	S-6	56.0 - 59.5	25.9	95.0	27.8	182.2	1.6	18-8	UNDISTURBED CLAYSTONE
②	S-5	46.0 - 48.1	25.6	94.9	55.6	163.3	1.6		
③	S-6	58.0 - 58.5	28.8	88.3	83.3	123.9	3.0		

FIGURE D.5.4  
**UNCONSOLIDATED UNDRAINED TRIAXIAL TEST RESULTS**  
**BORING NO. L18-F**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS, INC.




FIGURE D.5.5  
**UNCONSOLIDATED UNDRAINED  
 TRIAXIAL TEST RESULTS**  
**BORING NO. L18-G**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**

SPECIMEN NO.	SAMPLE NO.	DEPTH (FEET)	INITIAL STATE		CONFINING PRESSURE (PSI)	DEVIATOR STRESS AT FAILURE (PSI)	STRAIN AT FAILURE (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE
			$\alpha$ (%)	$\gamma_d$ (pcf)					
①	S-4	30.0 - 32.0	16.2	101.5	27.8	135.5	2.5	18-13	UNDISTURBED SANDSTONE
②	S-5	40.0 - 41.3	12.1	101.5	55.6	235.6	4.0		
③	S-4	30.0 - 32.0	14.3	101.0	83.3	270.8	4.0		




FIGURE D.5.6  
**UNCONSOLIDATED UNDRAINED  
 TRIAXIAL TEST RESULTS**  
**BORING NO. L18-G**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**

SPECIMEN NO.	SAMPLE NO.	DEPTH (FEET)	INITIAL STATE		CONFINING PRESSURE (PSI)	DEVIATOR STRESS AT FAILURE (PSI)	STRAIN AT FAILURE (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE
			w (%)	$\gamma_d$ (pcf)					
①	S-8	45.0 - 47.5	29.8	91.3	27.8	130.6	1.2	18-12	UNDISTURBED CLAYSTONE
②	S-7	50.0 - 51.8	28.4	91.8	55.6	95.4	1.2		
③	S-6	45.0 - 47.5	29.4	92.7	83.3	144.3	1.4		





**APPENDIX D.6**  
**UU TRIAXIAL COMPRESSION TESTS**  
**(REMOLDED SAMPLES)**

TABLE D.6.1

SUMMARY OF UNCONSOLIDATED UNDRAINED (UU) TRIAXIAL TEST  
(REMOLDED SAMPLES)


TEST PIT NO.	SAMPLE NO.	SAMPLE DEPTH (FT)	STRATIGRAPHIC UNIT	MATERIAL TYPE	INITIAL STATE		CONFINING PRESSURE (PSI)	DEVIATOR STRESS			
					WATER CONTENT (%)	DRY DENSITY (PCF)		PEAK (PSI)	STRAIN (%)	RESIDUAL (PSI)	STRAIN (%)
DT-A	B-2	5	18-8	Claystone compacted to 90% relative compaction (Modified Proctor) and 5% above optimum.	26.7	93.4	27.8	65.3	14	65.1	15
DT-A	B-2	5	18-8		26.5	93.7	55.6	74.1	14	74.0	15
DT-A	B-2	5	18-8		26.6	93.7	88.3	81.3	13	80.8	15
TP-42	B-1	6	18-9	Sandstone compacted to 95% relative compaction (Modified Proctor) at optimum.	14.9	108.7	27.8	127.2	4	108.0	10
TP-42	B-1	6	18-9		14.8	109.0	55.6	186.8	6	179.0	12
TP-42	B-1	6	18-9		14.8	109.0	83.3	244.6	8	201.9	15



SPECIMEN NO.	SAMPLE NO.	DEPTH (FEET)	INITIAL STATE		CONFINING PRESSURE (PSI)	DEVIATOR STRESS AT FAILURE (PSI)	STRAIN AT FAILURE (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE
			$\alpha$ (%)	$\gamma_g$ (PCF)					
①	B-2	5	26.7	93.4	27.8	65.3	14.0	18-B	CLAYSTONE COMPACTED TO 90% RELATIVE COMPACTION, 5% ABOVE OPTIMUM (MODIFIED PROC TOR)
②	B-2	5	26.5	93.7	55.6	74.1	14.0		
③	B-2	5	26.6	93.7	63.3	91.3	13.0		

FIGURE D.6.1  
**UNCONSOLIDATED UNDRAINED TRIAXIAL TEST RESULTS**  
**TEST PIT NO. DT-A**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY

ENVIRONMENTAL SOLUTIONS, INC.



SPECIMEN NO.	SAMPLE NO.	DEPTH (FEET)	INITIAL STATE		CONFINING PRESSURE (PSI)	DEVIATOR STRESS AT FAILURE (PSI)	STRAIN AT FAILURE (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE
			$\omega$ (%)	$\gamma_d$ (PCF)					
①	B-1	6	14.9	108.7	27.8	127.2	4.0	18-9	SANDSTONE COMPACTED TO 95% RELATIVE COMPACTOR (MODIFIED PROCTOR AT OPTIMUM MOISTURE CONTENT)
②	B-1	6	14.8	109.0	55.6	186.8	6.0		
③	B-1	6	14.8	109.0	83.3	244.6	8.0		





FIGURE D.6.2  
**UNCONSOLIDATED UNDRAINED TRIAXIAL TEST RESULTS**  
**BOREHOLE NO. TP-42**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**

**APPENDIX D.7**  
**CU TRIAXIAL COMPRESSION TESTS**

**TABLE D.7.1**  
**SUMMARY OF CONSOLIDATED UNDRAINED (CU) TRIAXIAL TEST**  
**(REMOLED SAMPLES)**





TEST PIT NO.	SAMPLE NO.	SAMPLE DEPTH (ft)	STRATI-GRAPHIC UNIT	MATERIAL TYPE	INITIAL STATE		CONFINING PRESSURE (PSI)	DEVIATOR STRESS		STRAIN RATE (%/Hour)
					WATER CONTENT (%)	DRY DENSITY (PCF)		PEAK (PSI)	STRAIN (%)	
DT-A	B-2	5	18-8	Claystone compacted to 90% relative compaction (Modified Proctor) and 5% above optimum.	26.4	93.8	34.7	42.38	5.01	3.87
DT-A	B-2	5	18-8		26.3	94.0	69.4	64.76	3.02	3.89
DT-A	B-2	5	18-8		26.7	93.6	138.9	97.44	8.99	3.97
DT-C	B-1	8	18-8	Claystone compacted to 90% relative compaction (Modified Proctor) at 5% above optimum.	28.2	89.1	34.7	40.18	6.0	3.90
DT-C	B-1	8	18-8		28.2	89.3	69.4	62.73	7.99	3.91
DT-C	B-1	8	18-8		28.2	89.3	138.9	108.75	6.97	3.95

89-977 (8/14/90)



SYMBOL	BORING/ SAMPLE NO.	SPECIMEN NO.	DEPTH (FEET)	SAMPLE TYPE	SOIL TYPE	INITIAL STATE			FINAL STATE			EFFECTIVE CONFINING PRESSURE (PSI)	BACK PRESSURE (PSI)	FAILURE		STRAIN RATE (%/hr)
						$\gamma_d$ (PCF)	$w$ (%)	SATURATION (%)	$\gamma_d$ (PCF)	$w$ (%)	SATURATION (%)			DEV. STRESS (PSI)	STRAIN (%)	
○	DT-C, B-1	1	8	CLAYSTONE COMPACTED TO 90% RELATIVE COMPACTION (MODIFIED PROCTOR) AND 5% ABOVE OPTIMUM	CLAYSTONE	89.1	28.2	82.6	89.5	33.9	100.00	34.7	50.0	40.18	6.0	3.90
△	DT-C, B-1	2	8		CLAYSTONE	89.3	28.2	82.9	92.0	32.0	100.00	69.4	50.0	62.73	7.99	3.91
□	DT-C, B-1	3	8		CLAYSTONE	89.3	28.2	82.9	95.7	29.4	100.00	138.9	50.0	108.85	6.97	3.95

FIGURE D.7-2  
**CONSOLIDATED-UNDRAINED TRIAXIAL  
 COMPRESSION TEST RESULTS**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS INC



SYMBOL	BORING/ SAMPLE NO.	SPECIMEN NO.	DEPTH (FEET)	SAMPLE TYPE	SOIL TYPE	INITIAL STATE			FINAL STATE			EFFECTIVE CONFINING PRESSURE (PSI)	BACK PRESSURE (PSI)	FAILURE		STRAIN RATE (%/hr)
						$\gamma_d$ (PCF)	$w$ (%)	SATURATION (%)	$\gamma_d$ (PCF)	$w$ (%)	SATURATION (%)			DEV. STRESS (PSI)	STRAIN (%)	
○	DT-A, B-2	1	5	CLAYSTONE COMPACTED TO 90% RELATIVE COMPACTION (MODIFIED PROCTOR) AND 5% ABOVE OPTIMUM	CLAYSTONE	93.8	26.4	84.5	94.0	31.1	100.00	34.7	50.0	42.38	5.01	3.67
△	DT-A, B-2	2	5		CLAYSTONE	94.0	26.3	84.2	95.8	29.9	100.00	69.4	50.0	64.76	8.02	3.89
□	DT-A, B-2	3	5		CLAYSTONE	93.6	26.7	85.0	98.7	28.0	100.00	138.9	50.0	97.44	8.99	3.97

FIGURE D.7-3  
**CONSOLIDATED-UNDRAINED TRIAXIAL  
 COMPRESSION TEST RESULTS**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
 ENVIRONMENTAL SOLUTIONS INC



**APPENDIX D.8**  
**SUMMARY OF DIRECT SHEAR TESTS**

TABLE D.8.1


SUMMARY OF DIRECT SHEAR TEST RESULTS

BORING NO.	SAMPLE NO.	SAMPLE DEPTH (FT)	STRATIGRAPHIC UNIT	MATERIAL TYPE	NATURAL		NORMAL LOAD (PSF)	SHEAR STRESS (PSF)			
					WATER CONTENT (%)	DRY DENSITY (PCF)		PEAK	STRAIN (%)	RESIDUAL	STRAIN (%)
L18-B	S-3	20.0 - 22.5	18-11	Sandstone	18	96.8	4,000	5,377	7	3,253	16
L18-B	S-3	20.0 - 22.5	18-11	Sandstone	20	98.5	6,000	6,676	7	4,546	17
L18-B	S-3	20.0 - 22.5	18-11	Sandstone	20	98.3	8,000	9,297	7	5,653	14
L18-B	S-5	37.0 - 39.5	18-11	Sandstone	12	98.8	6,000*	7,908	5	6,228	17
L18-C	S-7	56.0 - 58.0	18-7	Claystone	21	103.4	4,000	6,161	6	5,377	17
L18-C	S-7	56.0 - 58.0	18-7	Claystone	26	98.5	8,000	7,146	4	5,287	17
L18-C	S-7	56.0 - 58.0	18-7	Claystone	27	96.0	11,500	7,371	3	4,234	17
L18-C	S-8	64.0 - 66.3	18-7	Claystone	21	100.3	8,000*	10,104	5	6,273	14
L18-D	S-2	22.0 - 24.5	18-5	Claystone	14	96.2	4,000	5,579	5	3,405	17
L18-D	S-2	22.0 - 24.5	18-5	Claystone	19	97.6	8,000	7,729	6	5,422	17
L18-D	S-2	22.0 - 24.5	18-5	Claystone	21	97.2	12,000	11,045	7	6,037	17
L18-D	S-2	22.0 - 24.5	18-5	Claystone	17	99.5	8,000*	10,908	6	9,947	14
L18-F	S-6	56.0 - 58.5	18-8	Claystone	26	94.8	4,000	8,715	5	3,562	17
L18-F	S-6	56.0 - 58.5	18-8	Claystone	32	87.7	8,000	6,900	7	4,951	17
L18-F	S-6	56.0 - 58.5	18-8	Claystone	29	92.0	12,000	13,532	6	4,862	17
L18-F	S-6	56.0 - 58.5	18-8	Claystone	30	91.7	8,000	7,729	4	4,010	14

89-977 (8/7/90)

\* Unsaturated

**APPENDIX D.9**  
**CONSOLIDATION TESTS**




BORING : DT-C, B-1                      DESCRIPTION : silty CLAYSTONE, yellow brn (CH)  
 DEPTH (ft) : 8                              LIQUID LIMIT : 76  
 SPEC. GRAVITY : 2.79                      PLASTIC LIMIT : 45

	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	28.1	89.4	83	.849
FINAL	30.5	94.1	100	.852

Remark : July 1990

Project ESK-101A	Kettleman	
Wahler Associates	CONSOLIDATION TEST	Figure No.



BORING : DT-A, B-2      DESCRIPTION : silty CLAYSTONE, yellow brn (CH)  
 DEPTH (ft) : 5      LIQUID LIMIT : 82  
 SPEC. GRAVITY : 2.84      PLASTIC LIMIT : 54

	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	27.3	93.1	86	.906
FINAL	29.9	95.9	100	.851

Remark : July 1990

Project ESK-101A

Kettleman

Wahler  
Associates

CONSOLIDATION TEST

Figure No.

**APPENDIX D.10**  
**GEOCHEMICAL TESTS**

# Analytical Report

LOG NO: A90-06-087

Received: 15 JUN 90  
Reported: 29 JUN 90

Mr. Julio Badel  
Environmental Solutions, Inc.  
21 Technology Drive  
Irvine, California 92718

Project: 89-977

## REPORT OF ANALYTICAL RESULTS

Page 1

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED		
06-087-1	L18-A S-5	28 MAY 90		
06-087-2	L18-C S-2	28 MAY 90		
06-087-3	L18-F S-1	28 MAY 90		
PARAMETER		06-087-1	06-087-2	06-087-3
Antimony, mg/kg		<0.2	<0.2	<0.2
Arsenic, mg/kg		6.8	9.9	11
Barium, mg/kg		15	27	17
Beryllium, mg/kg		<0.02	<0.02	<0.02
Cadmium, mg/kg		<0.06	<0.06	<0.06
Chromium, mg/kg		42	55	42
Cobalt, mg/kg		10	13	9.0
Copper, mg/kg		15	30	25
Lead, mg/kg		1.0	<0.8	<0.8
Mercury, mg/kg		<0.3	<0.3	<0.3
Molybdenum, mg/kg		<0.08	<0.08	<0.08
Nickel, mg/kg		55	88	56
Selenium, mg/kg		<0.4	<0.4	<0.4
Silver, mg/kg		<0.02	<0.02	<0.02
Thallium, mg/kg		31	42	36
Vanadium, mg/kg		23	34	20
Zinc, mg/kg		51	58	58
Cyanide, mg/kg		<0.5	<0.5	<0.5
Nitrate + Nitrite (as NO3), mg/kg		6	120	24
Total Organic Carbon, mg/kg		800	1900	870
Specific Conductance, umhos/cm		1500	3300	40000
pH, Units		8.4	7.4	7.2
Chloride, mg/kg		11	68	170
Sulfate, mg/kg		360	1800	28000
Nitric Acid Digestion, Date		06/22/90	06/22/90	06/22/90

# Analytical Report

LOG NO: A90-06-087

Received: 15 JUN 90

Reported: 29 JUN 90

Mr. Julio Badel  
Environmental Solutions, Inc.  
21 Technology Drive  
Irvine, California 92718

Project: 89-977

## REPORT OF ANALYTICAL RESULTS

Page 2

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED		
06-087-1	L18-A S-5	28 MAY 90		
06-087-2	L18-C S-2	28 MAY 90		
06-087-3	L18-F S-1	28 MAY 90		
PARAMETER		06-087-1	06-087-2	06-087-3
B/N,A Ext.Pri.Poll. (EPA-8270)				
Date Analyzed		06/21/90	06/21/90	06.21.90
Date Extracted		06/20/90	06/20/90	06.20.90
Dilution Factor, Times		1	1	1
1,2,4-Trichlorobenzene, mg/kg		<0.3	<0.3	<0.3
1,2-Dichlorobenzene, mg/kg		<0.3	<0.3	<0.3
1,2-Diphenylhydrazine, mg/kg		<0.3	<0.3	<0.3
1,3-Dichlorobenzene, mg/kg		<0.3	<0.3	<0.3
1,4-Dichlorobenzene, mg/kg		<0.3	<0.3	<0.3
2,4,5-Trichlorophenol, mg/kg		<0.3	<0.3	<0.3
2,4,6-Trichlorophenol, mg/kg		<0.3	<0.3	<0.3
2,4-Dichlorophenol, mg/kg		<0.3	<0.3	<0.3
2,4-Dimethylphenol, mg/kg		<0.3	<0.3	<0.3
2,4-Dinitrophenol, mg/kg		<0.8	<0.8	<0.8
2,4-Dinitrotoluene, mg/kg		<0.3	<0.3	<0.3
2,6-Dinitrotoluene, mg/kg		<0.3	<0.3	<0.3
2-Chloronaphthalene, mg/kg		<0.3	<0.3	<0.3
2-Chlorophenol, mg/kg		<0.3	<0.3	<0.3
2-Methyl-4,6-dinitrophenol, mg/kg		<2	<2	<2
2-Methylnaphthalene, mg/kg		<0.3	<0.3	<0.3
2-Methylphenol, mg/kg		<0.3	<0.3	<0.3
2-Nitroaniline, mg/kg		<2	<2	<2
2-Nitrophenol, mg/kg		<0.3	<0.3	<0.3
3,3'-Dichlorobenzidine, mg/kg		<0.3	<0.3	<0.3
3-Nitroaniline, mg/kg		<2	<2	<2





# Analytical Report

LOG NO: A90-06-087

Received: 15 JUN 90

Reported: 29 JUN 90

Mr. Julio Badel  
Environmental Solutions, Inc.  
21 Technology Drive  
Irvine, California 92718

Project: 89-977

## REPORT OF ANALYTICAL RESULTS

Page 3

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED		
06-087-1	L18-A S-5	28 MAY 90		
06-087-2	L18-C S-2	28 MAY 90		
06-087-3	L18-F S-1	28 MAY 90		
PARAMETER		06-087-1	06-087-2	06-087-3
4-Bromophenylphenylether, mg/kg		<0.3	<0.3	<0.3
4-Chloro-3-methylphenol, mg/kg		<0.3	<0.3	<0.3
4-Chloroaniline, mg/kg		<0.6	<0.6	<0.6
4-Chlorophenylphenylether, mg/kg		<0.3	<0.3	<0.3
4-Methylphenol, mg/kg		<0.3	<0.3	<0.3
4-Nitroaniline, mg/kg		<2	<2	<2
4-Nitrophenol, mg/kg		<0.8	<0.8	<0.8
Acenaphthene, mg/kg		<0.3	<0.3	<0.3
Acenaphthylene, mg/kg		<0.3	<0.3	<0.3
Aniline, mg/kg		<0.6	<0.6	<0.6
Anthracene, mg/kg		<0.3	<0.3	<0.3
Benzidine, mg/kg		<1	<1	<1
Benzo(a)anthracene, mg/kg		<0.3	<0.3	<0.3
Benzo(a)pyrene, mg/kg		<0.3	<0.3	<0.3
Benzo(b)fluoranthene, mg/kg		<0.3	<0.3	<0.3
Benzo(g,h,i)perylene, mg/kg		<0.3	<0.3	<0.3
Benzo(k)fluoranthene, mg/kg		<0.3	<0.3	<0.3
Benzyl Alcohol, mg/kg		<0.6	<0.6	<0.6
Benzoic acid, mg/kg		<2	<2	<2
Butylbenzylphthalate, mg/kg		<0.3	<0.3	<0.3
Chrysene, mg/kg		<0.3	<0.3	<0.3
Di-n-octylphthalate, mg/kg		<0.3	<0.3	<0.3
Dibenzo(a,h)anthracene, mg/kg		<0.3	<0.3	<0.3
Dibenzofuran, mg/kg		<0.3	<0.3	<0.3
Dibutylphthalate, mg/kg		<2	<2	<2

# Analytical Report

LOG NO: A90-06-087

Received: 15 JUN 90  
Reported: 29 JUN 90

Mr. Julio Badel  
Environmental Solutions, Inc.  
21 Technology Drive  
Irvine, California 92718

Project: 89-977

## REPORT OF ANALYTICAL RESULTS

Page 4

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED		
06-087-1	L18-A S-5	28 MAY 90		
06-087-2	L18-C S-2	28 MAY 90		
06-087-3	L18-F S-1	28 MAY 90		
PARAMETER		06-087-1	06-087-2	06-087-3
Diethylphthalate, mg/kg		<0.3	<0.3	<0.3
Dimethylphthalate, mg/kg		<0.8	<0.8	<0.8
Fluoranthene, mg/kg		<0.3	<0.3	<0.3
Fluorene, mg/kg		<0.3	<0.3	<0.3
Hexachlorobenzene, mg/kg		<0.3	<0.3	<0.3
Hexachlorobutadiene, mg/kg		<0.3	<0.3	<0.3
Hexachlorocyclopentadiene, mg/kg		<0.3	<0.3	<0.3
Hexachloroethane, mg/kg		<0.3	<0.3	<0.3
Indeno(1,2,3-c,d)pyrene, mg/kg		<0.3	<0.3	<0.3
Isophorone, mg/kg		<0.3	<0.3	<0.3
N-Nitrosodimethylamine, mg/kg		<2	<2	<2
N-Nitrosodiphenylamine, mg/kg		<0.3	<0.3	<0.3
N-Nitrosodi-n-propylamine, mg/kg		<1	<1	<1
Nitrobenzene, mg/kg		<0.3	<0.3	<0.3
Naphthalene, mg/kg		<0.3	<0.3	<0.3
Phenanthrene, mg/kg		<0.3	<0.3	<0.3
Phenol, mg/kg		<0.3	<0.3	<0.3
Pentachlorophenol, mg/kg		<0.3	<0.3	<0.3
Pyrene, mg/kg		<0.3	<0.3	<0.3
Bis(2-chloroethoxy)methane, mg/kg		<0.3	<0.3	<0.3
Bis(2-chloroethyl)ether, mg/kg		<0.3	<0.3	<0.3
Bis(2-chloroisopropyl)ether, mg/kg		<0.3	<0.3	<0.3
Bis(2-ethylhexyl)phthalate, mg/kg		<0.3	0.4	<0.3

Semi-Quantified Results \*\*

# Analytical Report

LOG NO: A90-06-087

Received: 15 JUN 90  
Reported: 29 JUN 90

Mr. Julio Badel  
Environmental Solutions, Inc.  
21 Technology Drive  
Irvine, California 92718

Project: 89-977

## REPORT OF ANALYTICAL RESULTS

Page 5

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED
06-087-1	L18-A S-5	28 MAY 90
06-087-2	L18-C S-2	28 MAY 90
06-087-3	L18-F S-1	28 MAY 90

PARAMETER	06-087-1	06-087-2	06-087-3
A C21 Hydrocarbon, mg/kg	2	---	---
A C22 Hydrocarbon, mg/kg	4	---	---
A C27 Hydrocarbon, mg/kg	10	---	---
Heptacosane, mg/kg	2	---	---

\*\* Quantification based upon comparison of total ion count of the compound with that of the nearest internal standard.



# Analytical Report

LOG NO: A90-06-087

Received: 15 JUN 90  
Reported: 29 JUN 90

Mr. Julio Badel  
Environmental Solutions, Inc.  
21 Technology Drive  
Irvine, California 92718

Project: 89-977

## REPORT OF ANALYTICAL RESULTS

Page 6

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED		
06-087-1	L18-A S-5	28 MAY 90		
06-087-2	L18-C S-2	28 MAY 90		
06-087-3	L18-F S-1	28 MAY 90		
PARAMETER		06-087-1	06-087-2	06-087-3
Pesticides/PCBs (EPA 8080)				
Date Analyzed		06/22/90	06/22/90	06/22/90
Date Extracted		06/21/90	06/21/90	06/21/90
Dilution Factor, Times		1	1	1
Aldrin, mg/kg		<0.001	<0.001	<0.001
Chlordane, mg/kg		<0.01	<0.01	<0.01
p,p'-DDD, mg/kg		<0.001	<0.001	<0.001
p,p'-DDE, mg/kg		<0.001	<0.001	<0.001
p,p'-DDT, mg/kg		<0.002	<0.002	<0.001
Dieldrin, mg/kg		<0.001	<0.001	<0.001
Endosulfan I, mg/kg		<0.001	<0.001	<0.001
Endosulfan II, mg/kg		<0.002	<0.002	<0.002
Endosulfan Sulfate, mg/kg		<0.002	<0.002	<0.002
Endrin, mg/kg		<0.002	<0.002	<0.002
Endrin Aldehyde, mg/kg		<0.001	<0.001	<0.001
Heptachlor epoxide, mg/kg		<0.001	<0.001	<0.001
Heptachlor, mg/kg		<0.001	<0.001	<0.001
Methoxychlor, mg/kg		<0.007	<0.007	<0.007
Aroclor 1016, mg/kg		<0.02	<0.02	<0.02
Aroclor 1221, mg/kg		<0.02	<0.02	<0.02
Aroclor 1232, mg/kg		<0.02	<0.02	<0.02
Aroclor 1242, mg/kg		<0.02	<0.02	<0.02
Aroclor 1248, mg/kg		<0.02	<0.02	<0.02
Aroclor 1254, mg/kg		<0.02	<0.02	<0.02
Aroclor 1260, mg/kg		<0.02	<0.02	<0.02

# Analytical Report

LOG NO: A90-06-087

Received: 15 JUN 90

Reported: 29 JUN 90

Mr. Julio Badel  
Environmental Solutions, Inc.  
21 Technology Drive  
Irvine, California 92718

Project: 89-977

## REPORT OF ANALYTICAL RESULTS

Page 7

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED		
06-087-1	L18-A S-5	28 MAY 90		
06-087-2	L18-C S-2	28 MAY 90		
06-087-3	L18-F S-1	28 MAY 90		
PARAMETER		06-087-1	06-087-2	06-087-3
Aroclor 1262, mg/kg		<0.02	<0.02	<0.02
Toxaphene, mg/kg		<0.02	<0.02	<0.02
BHC, alpha isomer, mg/kg		<0.001	<0.001	<0.001
BHC, beta isomer, mg/kg		<0.001	<0.001	<0.001
BHC, delta isomer, mg/kg		<0.001	<0.001	<0.001
BHC, gamma isomer (Lindane), mg/kg		<0.001	<0.001	<0.001

# Analytical Report

LOG NO: A90-06-087

Received: 15 JUN 90  
Reported: 29 JUN 90

Mr. Julio Badel  
Environmental Solutions, Inc.  
21 Technology Drive  
Irvine, California 92718

Project: 89-977

## REPORT OF ANALYTICAL RESULTS

Page 8

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED		
06-087-1	L18-A S-5	28 MAY 90		
06-087-2	L18-C S-2	28 MAY 90		
06-087-3	L18-F S-1	28 MAY 90		
PARAMETER		06-087-1	06-087-2	06-087-3
Vol. Pri. Poll. (EPA-8240)				
Date Analyzed		06/22/90	06/21/90	06/21/90
Date Extracted		06/22/90	06/21/90	06/21/90
Dilution Factor, Times		1	1	1
Tetrachloroethylene, ug/kg		<5	<5	<5
1,1,1-Trichloroethane, ug/kg		<5	<5	<5
1,1,2,2-Tetrachloroethane, ug/kg		<5	<5	<5
1,1,2-Trichloroethane, ug/kg		<5	<5	<5
1,1-Dichloroethane, ug/kg		<5	<5	<5
1,1-Dichloroethene, ug/kg		<5	<5	<5
1,2-Dichloroethane, ug/kg		<5	<5	<5
1,2-Dichlorobenzene, ug/kg		<5	<5	<5
1,2-Dichloropropane, ug/kg		<5	<5	<5
1,3-Dichlorobenzene, ug/kg		<5	<5	<5
1,4-Dichlorobenzene, ug/kg		<5	<5	<5
2-Chloroethylvinylether, ug/kg		<5	<5	<5
2-Hexanone, ug/kg		<50	<50	<50
Acetone, ug/kg		<50	<50	<50
Acrolein, ug/kg		<100	<100	<100
Acrylonitrile, ug/kg		<100	<100	<100
Bromodichloromethane, ug/kg		<5	<5	<5
Benzene, ug/kg		<5	<5	<5
Bromomethane, ug/kg		<5	<5	<5
Bromoform, ug/kg		<5	<5	<5
Chlorobenzene, ug/kg		<5	<5	<5



B C Analytical

# Analytical Report

LOG NO: A90-06-087

Received: 15 JUN 90

Reported: 29 JUN 90

Mr. Julio Badel  
 Environmental Solutions, Inc.  
 21 Technology Drive  
 Irvine, California 92718

Project: 89-977

## REPORT OF ANALYTICAL RESULTS

Page 9

LOG NO	SAMPLE DESCRIPTION, SOIL SAMPLES	DATE SAMPLED		
06-087-1	L18-A S-5	28 MAY 90		
06-087-2	L18-C S-2	28 MAY 90		
06-087-3	L18-F S-1	28 MAY 90		
PARAMETER		06-087-1	06-087-2	06-087-3
Carbon Tetrachloride, ug/kg		<5	<5	<5
Chloroethane, ug/kg		<5	<5	<5
Chloroform, ug/kg		<5	<5	<5
Chloromethane, ug/kg		<10	<10	<10
Carbon Disulfide, ug/kg		<10	<10	<10
Dibromochloromethane, ug/kg		<5	<5	<5
Ethylbenzene, ug/kg		<5	<5	<5
Freon 113, ug/kg		<5	<5	<5
Methyl ethyl ketone, ug/kg		<50	<50	<50
Methyl isobutyl ketone, ug/kg		<25	<25	<25
Methylene chloride, ug/kg		<5	<5	<5
Styrene, ug/kg		<5	<5	<5
Trichloroethene, ug/kg		<5	<5	<5
Trichlorofluoromethane, ug/kg		<5	<5	<5
Toluene, ug/kg		<5	<5	<5
Vinyl acetate, ug/kg		<25	<25	<25
Vinyl chloride, ug/kg		<5	<5	<5
Total Xylene Isomers, ug/kg		<25	<25	<25
cis-1,3-Dichloropropene, ug/kg		<5	<5	<5
trans-1,2-Dichloroethene, ug/kg		<5	<5	<5
trans-1,3-Dichloropropene, ug/kg		<5	<5	<5
Other Vol.Pri.Poll. (EPA-8240)		---	---	---



# Analytical Report

LOG NO: A90-06-087

Received: 15 JUN 90

Reported: 29 JUN 90

Mr. Julio Badel  
Environmental Solutions, Inc.  
21 Technology Drive  
Irvine, California 92718

Project: 89-977

## REPORT OF ANALYTICAL RESULTS


Page 10

-----  
The detection limit for p,p'-DDT on samples A90-06-087  
-1 and -2 "L18-A S-5 and L18-C S-2" analyzed by  
EPA-8080 was elevated to 0.002 mg/kg. This was due to  
trace level contamination which carried over from the  
extraction of a sample containing high levels of  
p,p'-DDT.

-- G. Havalias 06/22/90

Based on historical data, the bis(2-ethylhexyl)phthalate  
found in the samples on the EPA-8270 analysis could  
have been introduced as a random laboratory  
contamination.

-- G. Havalias 06/29/90

  
Edward Wilson, Laboratory Manager





**APPENDIX E**  
**CLAY LINER TEST PAD DATA**

<b>APPENDIX E.1</b>	<b>PHASES I AND II TEST PAD REPORT</b>
<b>APPENDIX E.2</b>	<b>PHASE III CLAY SOURCE TESTING REPORT</b>
<b>APPENDIX E.3</b>	<b>CLAY STOCKPILE AND TEST PAD REPORT</b>
<b>APPENDIX E.4</b>	<b>PHASES I AND II CLAY LINER COMPACTION SPECIFICATIONS</b>

**APPENDIX E.1**  
**PHASES I AND II TEST PAD REPORT**

**TEST FILL AND  
INFILTRMETER TEST RESULTS**

**LANDFILL UNIT B-18  
PHASES I AND II AND FINAL CLOSURE**

Prepared For:

**CHEMICAL WASTE MANAGEMENT, INC. (CWMI)**

January 23, 1992

# ENVIRONMENTAL SOLUTIONS, INC.

January 23, 1992

Project No. 89-977

Mr. Robert Henry  
Project Manager  
Chemical Waste Management, Inc.  
35251 Old Skyline Road  
Kettleman City, California 93239

Transmittal  
Test Fill and Infiltrometer Test Results Report  
Landfill Unit B-18  
Phases I and II and Final Closure  
Kettleman Hills Facility  
Kings County, California

Dear Mr. Henry:

Enclosed are 15 copies of the report entitled *Test Fill and Infiltrometer Test Results, Landfill Unit B-18, Phases I and II and Final Closure*.

Field measured permeabilities coupled with laboratory permeability tests indicate that the claystone used for the test fill and proposed for use as the liner/cap provides an adequate low permeability soil layer for the B-18 Landfill, Phases I and II and Final Closure.


We will be pleased to provide any clarifications necessary in response to reviews by the agencies or your staff.

Very truly yours,

Kerry K. Parkinson, P.E.  
Civil Engineer (License No. 41021)

KKP:hs  
Enclosures

cc: Dick Ellison  
Ken Floom  
Julio Badel



# TABLE OF CONTENTS

	<u>PAGE NO.</u>
LIST OF TABLES/LIST OF FIGURES	ii
1.0 INTRODUCTION	1
2.0 CONSTRUCTION OF THE TEST FILL	1
2.1 Subgrade Preparation	2
2.2 Equipment	2
2.3 Construction Sequence	2
2.4 Field and Laboratory Testing	3
2.4.1 Field Tests	3
2.4.2 Laboratory Tests	4
3.0 INFILTROMETER (SDRI) TEST	5
3.1 SDRI Description	5
3.2 Site Preparation and Installation	5
3.3 Data Collection	6
4.0 THEORY	6
5.0 SDRI TEST RESULTS AND CONCLUSIONS	10
6.0 REFERENCES	11
TABLES	
FIGURES	
APPENDIX A: ONE-DIMENSIONAL SWELL TEST RESULTS	
APPENDIX B: SDRI FIELD DATA SHEETS	

## TABLE OF CONTENTS (Continued)

### LIST OF TABLES

<u>TABLE NO.</u>	<u>TITLE</u>
1	Equipment Utilized in the Test Fill Construction
2	Estimate of Swell Flow Volume
3	Infiltrometer Test Results

### LIST OF FIGURES

<u>FIGURE NO.</u>	<u>TITLE</u>
1	Site Vicinity Map
2	B-18 Landfill Test Fill Location
3	Test Fill Plan, Cross Section and Detail
4	Compaction Data - Test Fill
5	Atterberg Limits - Test Fill Soil
6	Grain Size Distribution - Test Fill Soil
7	Laboratory Permeability Versus Water Content
8	Schematic of Infiltrometer Test Model
9	12-Inch Soil Tension/Suction Versus Time
10	18-Inch Soil Tension/Suction Versus Time
11	Infiltration Versus Time

## 1.0 INTRODUCTION

1. This report presents the Sealed Double Ring Infiltrometer (SDRI) test results and the geotechnical data associated with the construction of the test fill at the Kettleman Hills Facility (see Figure 1). The purposes of the test fill were to model placement and compaction procedures for the construction of the B-18 Landfill clay liner/cap and to verify that these procedures will achieve the specified compaction and permeability criteria.
2. The objective of the SDRI test is to evaluate the saturated, vertical permeability of the clay liner material to verify that it meets the specification for permeability of less than or equal to  $1 \times 10^{-7}$  cm/sec and to assess if laboratory permeability values are comparable to field permeabilities. In this report, the terms permeability and hydraulic conductivity are used interchangeably.
3. The methods used to construct the test fill including field and laboratory testing, are presented in Chapter 2.0. The design and installation of the infiltrometer are described in Chapter 3.0. The theory and data analyses are presented in Chapter 4.0. The results of the test, analyses and conclusions are presented in Chapter 5.0. References are included in Chapter 6.0.

## 2.0 CONSTRUCTION OF THE TEST FILL

1. The test fill was constructed between January 22 and February 1, 1991, at the location shown in Figure 2. The test fill plan, cross section, and detail are presented in Figure 3.
2. Material used as fill consisted of onsite clay hauled from the B-18 Clay Processing Area. Moisture conditioning in conjunction with weathering and particle size reduction were performed in the Clay Processing Area prior to hauling and placement. The procedures used for processing and construction of the test fill are considered similar to those that would be used for the B-18 Landfill.
3. The clay was originally derived from the Stratum 18-8 (claystone) previously characterized during the design phase (see Section 3.5 of the *Engineering and Design Report, Landfill Unit B-18*, August, 1990 [Environmental Solutions, Inc., 1990a]) as a suitable clay source for clay liner construction.

## 2.1 SUBGRADE PREPARATION

1. The area within the test fill was initially cleared of vegetation and loose soil. The surface soils were then graded to form a smooth, firm subgrade surface. Finally, a drainage system consisting of geonet (Polynet 3000) and a layer of geotextile (Trevira 1155) was placed over the subgrade as shown in Figure 3.

## 2.2 EQUIPMENT

1. In order to simulate clay liner/cap construction conditions for Phases I and II and Final Closure, the test fill was constructed using equipment similar to that which would be used during the B-18 Landfill bottom and final closure liner/cap construction. The equipment used and their respective functions are listed in Table 1.

## 2.3 CONSTRUCTION SEQUENCE

1. Initially, a 1-foot thick base lift of clay was placed and compacted to provide protection for the geonet/geotextile drainage system. Then, each of the five lifts comprising the test fill was constructed according to the following steps:
  - Moisture conditioning, weathering, and particle size reduction were performed in the B-18 Clay Processing Area to meet the revised specification from the *Construction Specifications and Quality Assurance Plan, Landfill Unit B-18, Phases I and II, and Final Closure*, which specifies the following:
    - Moisture Content: Within the range defined by the area formed by connecting the following points for the Modified Proctor Compaction curve:
      - 2 to 5 percent above the optimum moisture content for a density equal to 90 percent of the maximum Modified Proctor density.
      - 3 percent above the optimum moisture content at 97 percent of the maximum Modified Proctor density.
      - 1 percent above the optimum moisture content at 98 percent of the maximum Modified Proctor density.
  - This criterion, which allows a lower water content for higher compactive efforts, was established to: (1) assure that both the required strength and permeability characteristics are realized; and (2) provide flexibility for the contractor and CQA engineer to work with a range of water contents without having a clay which is either too wet or dry. This flexibility is desirable in hot, dry areas where exact water content is difficult to control. This specification is represented by the area designated as "Specified Window" in Figure 4.



- The moisture conditioned clay was hauled to the test fill area by a scraper and unloaded in loose lifts approximately 8 inches thick. A motor grader was utilized to smooth the uneven lifts and to maintain a 2 percent slope in the longitudinal direction.
- After the entire test fill area was covered with a loose lift of clay, a Caterpillar 825C compactor made four passes for each lift. Compacted lift thicknesses were approximately 6 inches. Four passes were determined during the initial testing to achieve approximately the minimum specified density of 90 percent of Modified Proctor maximum dry density. The infiltrometer test was performed on a fill compacted near the lower, acceptable dry density to assure that the permeability criteria ( $\approx 10^{-7}$  cm/sec) could be achieved for the more conservative, lower density.
- Each lift was tested to verify the as-built moisture content and density.

## 2.4 FIELD AND LABORATORY TESTING

1. Field and laboratory tests were conducted on the test fill to evaluate if the construction equipment and procedures would meet the specifications for compaction and permeability of the clay liner.
2. These tests were performed in accordance with the procedures and frequencies outlined in the following documents:
  - Appendix E (Test Fill and Infiltration Test Plan) of the *Engineering and Design Report, Landfill Unit B-18, Phases I and II, and Final Closure* (Environmental Solutions, Inc., 1990a).
  - *Construction Specifications and Quality Assurance Plan, Landfill Unit B-18, Phases I and II, and Final Closure* (Environmental Solutions, Inc., 1990b).

### 2.4.1 FIELD TESTS

1. Initially, the first lift had to be constructed several times until the procedure to achieve the required water content and density was developed. After the appropriate procedure was developed, the moisture density specifications were achieved for the majority of tests.
2. Field density (compaction) tests, consisting of a minimum of two nuclear density tests and one sand cone density test for each lift, were conducted at the locations shown in Figure 3. The compaction test results within the tested zone are shown in Figure 4.

3. The majority of the density tests fall within the lower portion of the specified moisture-density window. Also, except for point 18(5) the tests are within or very close to the specified range. Because point 18(5) has a lower density, its effects on the results, if any, would be in the conservative direction.

#### 2.4.2 LABORATORY TESTS

1. Laboratory tests were conducted on soil samples recovered in six thin-walled Shelby tube samplers collected after the construction of the test fill. These tests include:
  - Atterberg Limits
  - Grain Size Analyses
  - One-Dimensional Swell Test
  - Permeability

The Shelby Tube sample locations are shown in Figure 3.

2. Atterberg Limits test results are presented in Figure 5. The material consistently had a plasticity in the CH (highly plastic clay) range with liquid limits varying between 65 and 79 percent, and a plasticity index between 44 and 55 percent.
3. Figure 6 shows the grain size distribution determined from the hydrometer tests for the six samples. These data show the relative uniformity of the clay with 80 percent or greater of the soil by weight passing the No. 200 sieve.
4. Appendix A provides a summary table of the One-Dimensional Swell tests. These results indicate that the compacted clay has a high potential to swell with an average swell of 16.5 percent under low confining pressure (70 psf, average value).
5. Laboratory permeability test results are shown in Figure 7 as a function of the initial moisture content. These tests indicate that under laboratory conditions (with applied consolidation pressures from 2.2 ksf to 6.2 ksf to prevent swelling) measured permeability values varied from  $1.5 \times 10^{-8}$  cm/sec to  $2.8 \times 10^{-10}$  cm/sec. These values, in conjunction with the infiltrometer test results discussed below, provide the basis to conclude that the clay used for the construction of the test fill adequately meets the permeability criterion of  $10^{-7}$  cm/sec or less.

### 3.0 INFILTROMETER (SDRI) TEST

1. An SDRI, developed by Trautwein Soil Testing Equipment of Houston, Texas, was used to assess the in situ permeability of the test fill constructed with onsite clay which is to be used for the B-18 Landfill clay liner. Eight tensiometer probes were installed around the inner ring to measure the soil suction. The SDRI test layout is shown in Figure 3. The schematic of the infiltrometer test model is presented in Figure 8. The theory and analysis of the test are described in Section 4.0. A summary of the SDRI system installation and data collection is presented in the following sections.

#### 3.1 SDRI DESCRIPTION

1. The SDRI consists of two rings: a fiberglass, 5-feet by 5-feet ring (inner ring) which is positioned in the center of a second aluminum 12-feet by 12-feet ring (outer ring) as shown in Figure 8. The inner ring is sealed over the top to avoid evaporation losses. Both rings are filled with water, and the loss of water from the inner ring is measured periodically. This water loss is the sum of the flow due to infiltration ( $Q_i$ ), filling of pore space due to swelling of the clay ( $Q_s$ ), and volumetric changes of water within the inner ring due to temperature variations. The water head in the inner and outer ring is maintained at a constant level slightly above the top of the inner ring.

#### 3.2 SITE PREPARATION AND INSTALLATION

1. The surface of the test fill was prepared for the installation of the SDRI by using a motor grader and a smooth drum roller to level and smooth the upper lift. The entire test fill area was lightly sprayed with water and covered with a black plastic tarp to prevent cracking.
2. The outer ring was positioned on the tarp and its outline was marked on the tarp to locate the trenches for the ring. The outer ring trench was cut with a Ditch Witch Series 1420 to a depth of 18 inches. The inner ring was positioned in the center of the outer ring and its outline was marked. The 5-inch-deep trench for the inner ring was cut by hand using small tools.
3. The outer ring trench was sealed with bentonite pellets surrounding the ring at the bottom and vertical sides. The trench for the inner ring was grouted with viscous Volclay grout.

4. After the installation of both rings was completed, a topographic survey was made to establish the original horizontal and vertical positions of the test fill surface including selected points on and around the inner ring. The primary purpose of the survey was to monitor the amount of swelling during the test.
5. The outer ring was flooded until the inner ring was slightly submerged, then the inner ring was partially filled through one plastic tube while air was removed through a second tube connected to the highest point of the cover. Then, the outer ring was filled to its final depth and the inner ring was topped off. Finally, plastic bags for measuring water flow within the inner ring were installed, and the test commenced.

### 3.3 DATA COLLECTION

1. The volume change of water within the flexible bag (shown in Figure 3) was indicative of the volume of water infiltrating through (the volume of water lost) the inner ring. The volume change was determined by calculating the change in the weight of the bag over a known time period (usually once per day). During the early days of the test, several bags of water were needed to account for higher flow rates due to minor surface desiccation cracking. The infiltration flow rates stabilized after several days. SDRI field data sheets are presented in Appendix B.

## 4.0 THEORY

1. The objective of the infiltrometer test is to measure the saturated permeability of the clay material for the B-18 Landfill under very low confining stresses. The test is performed by measuring the seepage of water through saturated soil.
2. In addition to being driven by the hydraulic gradient caused by the ponded water, seepage of water into the test fill also occurs due to high capillary suction of the partially saturated clay, as opposed to fully saturated conditions associated with laboratory tests. Performance of the field tests must also account for swelling of the clay at low confining stresses, which decreases the compacted density and increases permeability, as opposed to laboratory testing when higher confining stresses preclude swelling of the clay.

3. The saturated permeability is computed using a form of Darcy's Law which includes terms for the total hydraulic gradient. The governing equation that describes the infiltration of water through the compacted clay is developed below, based on the terms and sign convention shown in Figure 8<sup>(1)</sup>:

$$q = -K \frac{\Delta h}{\Delta L} \quad (1)$$

where:

$q$  = Infiltration rate per unit area and time (L/T)

$K$  = Saturated permeability (L/T)

$\frac{\Delta h}{\Delta L}$  = Total hydraulic gradient (L/L)

$\Delta h$  =  $h_1 - h_2$

$\Delta L$  =  $z_1 - z_2$

$h$  = Total head

$h$  =  $z + \bar{\phi}$

$z$  = Elevation head

$\bar{\phi}$  = Pressure head (due to hydraulic head or soil suction/tension)

In Figure 8, substituting for  $\Delta h$  and  $\Delta L$ , yields the equation:

$$q = -K \left[ \frac{(z_1 + \bar{\phi}_1) - (z_2 + \bar{\phi}_2)}{(z_1 - z_2)} \right] \quad (2)$$

For any given wetting front,  $L_f = z_1 - z_2$ . Substituting this into Equation (2), the infiltration rate at any wetting front is calculated as:

$$q = -K \left[ \frac{\bar{\phi}_1}{L_f} - \frac{\bar{\phi}_2}{L_f} + 1 \right] \quad (3)$$

4. As shown in Figure 8, at Point 1 the pressure head is equal to the depth of water in the outer ring,  $D_f$ , with soil suction/tension equal to zero, i.e., the soil is saturated. At this point, the pressure head,  $D_f = \bar{\phi}_1$ . Also, since the clay fill is unsaturated below the wetting front, the in situ pressure head at Point 2 will be equal to the soil suction and negative in sign convention, and can be designated simply as  $\bar{\phi}$ , i.e.,  $\bar{\phi} = -\bar{\phi}_2$ . Substituting into Equation 3:

$$q = -K \left[ \frac{D_f}{L_f} + \frac{\bar{\phi}}{L_f} + 1 \right] \quad (4)$$

5. Equation 4 is time dependent. That is, the infiltration flow rate per unit area ( $q$ ) and the depth of the wetting front ( $L_f$ ) are interrelated and vary with time. As the wetting front advances,

<sup>(1)</sup> The minus sign indicates that the flow is in the negative Z-direction (downward).

Equation 4 can be rearranged to calculate permeability at various wetting front depths, determined by tensiometer measurements, as follows:

$$K = - \frac{q}{1 + \frac{D_f}{L_f} + \frac{\bar{\phi}}{L_f}} \quad (5)$$

The length of the wetting front ( $L_f$ ) is known by noting the depth to which tensiometers indicate moisture content increases. The depth of flooding ( $D_f$ ) is taken as an average value of readings measured during the test. The soil suction ( $\bar{\phi}$ ) is set equal to the stabilized or weighted soil tension value, measured prior to the passage of the wetting front, and is dependent on the shape of the suction versus time plot. The infiltration rate ( $q$ ) is determined by weighing the flexible bag periodically to determine the volume of water lost.

6. The measured volume of water lost is corrected to account for swelling of the soil and temperature changes. The total water lost is the sum of the following:

- $Q = Q_i + Q_s + Q_t$  (6)
- $Q$  = measured water loss
- $Q_i$  = flow due to infiltration
- $Q_s$  = flow due to swell
- $Q_t$  = flow due to temperature changes (considered to be insignificant)

7. The infiltration rate per unit area ( $q$ ) is:

$$q = \frac{Q_i}{A} = \frac{Q - Q_s - Q_t}{A} = \frac{Q - Q_s}{A} \quad (7)$$

A close estimate of  $Q_s$  can be obtained by assuming that any volume change that occurs is due to vertical swelling and that the additional volume generated by the swelling is water filling the soil pores. Based on these two assumptions:

$$Q_s = \Delta s \times A \quad (8)$$

where:

$\Delta s$  = amount of swelling (as surveyed) at the time the water front passes a given tensiometer

$A$  = area of inner ring

A plot of total water lost versus time is used to determine the total flow ( $Q$ ) at the time the wetting front passes the tensiometer.

8. The test procedure and analysis methodology described above is based on the following assumptions:
- Darcy's Law applies.
  - A sharp wetting front exists between the saturated soil and the unsaturated soil.
  - The measured water loss from the flexible bag represents the water lost due primarily to infiltration through the inner ring, and soil swelling. Changes due to temperature variations are not significant.
  - The test fill is homogeneous and isotropic.
  - Flow through the inner ring is vertically downward.
  - Any volume change that occurs is vertical.
  - The wetting front under the outer ring reaches a given depth  $L_f$  at the same time as the wetting front under the inner ring.
9. The first assumption that Darcy's Law applies is valid due to the fact that the ground water flow is laminar when the wetting front reaches the tensiometer tip. The second assumption of a sharp wetting front is valid early during the test. At later times a transition zone between the saturated and partially-saturated soil is likely to exist.
10. The assumption concerning the measured water loss is based on the fact that the inner ring is completely purged of air; additional volume generated by swelling is water filling the soil pores, and water temperature variations are relatively small due to measuring flow volumes at similar times each day of the test. Considering that the fill was placed under controlled conditions, the assumptions that the test fill is homogeneous and isotropic is appropriate.
11. The assumption that any volume change that occurs is vertical is based on the very low magnitude of the confining stresses in the upper 18 inches of the test fill. There are practically no constraints for vertical swelling.
12. The assumption of vertical flow through the inner ring is based on the fact that an equal head is maintained between the inner and outer ring, and as a result the only driving force is vertically downward. This basis, in effect, also assumes that the wetting fronts for the inner and outer rings advance at the same rate, which would eliminate the possibility of soil suction causing lateral movement.
13. The last assumption is necessary due to the fact that the sealed inner ring apparatus precludes the installation of soil tensiometers under the inner ring to monitor the advance of the wetting front within the inner ring.

## 5.0 SDRI TEST RESULTS AND CONCLUSIONS

1. The infiltrometer test was conducted over a period of approximately two months to evaluate the permeability of the upper 18 inches of test fill. Based on the tensiometer readings (Figures 9 and 10), the wetting front (zone of saturation) reached depths of 12 and 18 inches in about 18 and 53 days, respectively. The tensiometers installed at a depth of 6 inches were damaged by wind and consequently no readings were taken at this depth as originally intended.
2. Figure 11 presents the accumulated total water flow,  $Q$ , as a function of time. The initial flow rate over the time interval of 0 to 5,000 minutes was about two times the average flow rate that occurred during saturation of the top 12 inches. This higher flow rate was likely due to water filling small surface cracks/voids. This condition was accounted for in determining the rate of flow.
3. Table 2 summarizes the survey data indicating the swell of the test fill soil, when the wetting front had reached 12 and 18 inches, respectively. Table 2 also shows the calculated flow due to swell ( $Q_s$ ) for these periods.
4. The suction pressure for both sets of tensiometers (Figures 9 and 10) was approximately 70 centibars, or 280 inches of water pressure.
5. The results of the infiltrometer test using Equation 5 are summarized in Table 3. The field measured permeabilities for both the 0- to 12-inches and 0- to 18-inches increments are less than  $1 \times 10^{-7}$  cm/sec. Based on these results, coupled with the laboratory permeability tests, it is concluded that the claystone, used for the test fill and proposed for use as the liner/cap, provides an adequate low permeability soil layer for the B-18 Landfill.
6. The test fill results are one to two orders of magnitude higher than laboratory permeabilities. These differences are expected and are primarily due to the unrestrained swelling of the clay which occurs during field testing (Chen and Yamamoto, 1987). The low hydraulic conductivity measured in the laboratory is a function of the consolidation pressure used in the test to prevent swelling. This consolidation pressure simulates the effect of the waste fill overburden on the clay liner. The SDRI test is more indicative of the stress condition for the cover system (very low confining stresses).



## 6.0 REFERENCES

Chen, Hsien W. and Leonard O. Yamamoto. *Permeability Tests for Hazardous Waste Management Unit Clay Liners, Proceedings of Geotechnical and Geohydrologic Aspects of Waste Management*; 1987.

Environmental Solutions, Inc., 1990a. *Engineering and Design Report, Landfill Unit B-18, Phases I and II and Final Closure, Kettleman Hills Facility, Kings County, California*, August 1990.

Environmental Solutions, Inc., 1990b. *Construction Specifications and Quality Assurance Plan, Landfill Unit B-18, Phases I and II and Final Closure, Kettleman Hills Facility, Kings County, California*, September 24, 1990.

Golder Associates. *Test Fill and Infiltrometer Test Results, Landfill B-19, Phase IA, Kettleman Hills Facility, Kettleman City, California*, January 1987.

Trautwein Soil Testing Equipment. *Installation and Operating Instruction for the Sealed-Double Ring Infiltrometer*, March 1989.

**TABLE 1**

**EQUIPMENT UTILIZED IN THE TEST FILL CONSTRUCTION**

EQUIPMENT	FUNCTION
Caterpillar D8N Dozer	Grading test fill
Caterpillar 14G Motor Grader	Grading test fill; scarifying previous lifts
Caterpillar 631E Scraper	Hauling clay from B-18 Clay Processing Area
Caterpillar 825C Compactor	Compacting lifts;
Ingersoll-Rand SP-56 Smooth Drum Roller	Dressing test fill
Water Truck	Moisture conditioning

89-977 (1/23/92/hs)

**TABLE 2**

**ESTIMATE OF SWELL FLOW VOLUME**




TEST INTERVAL	AVERAGE SURVEYED VERTICAL SWELLING (ft)	AREA OF TEST (ft <sup>2</sup> )	SWELL FLOW VOLUME (cc)
0 to 12 inches	0.17	25	120,300
0 to 18 inches	0.20	25	141,600

89-977 (1/9/92/mg)

**TABLE 3**  
**INFILTROMETER TEST RESULTS**


TEST INTERVAL	CUMULATIVE WATER LOSS $Q$ (cc)	FLOW DUE TO SWELL $Q_s$ (cc)	FLOW DUE TO INFILTRATION $Q_i$ (cc)	INFILTRATION RATE PER UNIT AREA $q$ (cm/sec)	DEPTH OF WATER IN OUTSIDE RING $D_r$ (in)	DEPTH OF WETTED FRONT $L_f$ (in)	SUCTION PRESSURE $\phi$ (in of H <sub>2</sub> O)	$K = \frac{q}{1 + \frac{D_r}{L_f} + \frac{\phi}{L_f}}$ (cm/sec)
<b>DEPTH: 0 to 12 INCHES</b> Tensiometers: TN-2, TN-3, TN-6, TN-7 Total Swelling: 1.98 inches % of Swelling - Field: 17.0 % of Swelling - Lab: 16.5	180,000	120,300	59,700	$1.3 \times 10^{-6}$	15	12	280	$5.1 \times 10^{-8}$
<b>DEPTH: 0 to 18 INCHES</b> Tensiometers: TN-4, TN-5 Total Swelling: 2.40 inches % of Swelling - Field: 13.3 % of Swelling - Lab: 16.5	280,000	141,600	140,400	$1.20 \times 10^{-6}$	15	18	280	$6.9 \times 10^{-8}$

89-977 (1/9/82/mg)




REFERENCE: USGS 7.5 MINUTE TOPOGRAPHIC MAP OF LA CIMA, DATED 1963, PHOTOREVISED 1971, LOS VIEJOS, DATED 1954, PHOTOREVISED 1981, KETTLEMAN CITY, DATED 1963, PHOTOREVISED 1981, AND KETTLEMAN PLAIN, CALIFORNIA, DATED 1953, PHOTOINSPECTED 1978.

FIGURE 1  
**SITE VICINITY MAP**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**




**LEGEND**

- FACILITY BOUNDARY
- B-18 LANDFILL BOUNDARY



CONTOUR INTERVAL: 2 FEET

**FIGURE 2**  
**B-18 LANDFILL**  
**TEST FILL LOCATION**  
LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**





**TEST FILL PLAN**




**LEGEND**

- 4(5) • NUCLEAR DENSITY TEST LOCATION
- ▲ LIFT NUMBER
- TEST NUMBER
- 7(3) △ SAND CONE DENSITY TEST LOCATION
- ▲ LIFT NUMBER
- TEST NUMBER
- ST-6 ⊕ SHELBY TUBE SAMPLE LOCATION AND NUMBER



**DETAIL 1**  
TENSIO METER PROBES LAYOUT

**FIGURE 3**  
**TEST FILL PLAN,**  
**CROSS SECTION AND DETAIL**  
  
LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**




**LEGEND**

- 18(5) NUCLEAR DENSITY TEST  
LIFT NUMBER  
TEST NUMBER
- ▲ 16(4) SAND CONE TEST  
LIFT NUMBER  
TEST NUMBER
- MODIFIED PROCTOR (ASTM D1557-78)  
COMPACTION POINTS
- SPECIFIED MOISTURE-DENSITY WINDOW  
USED FOR CONSTRUCTION CONTROL

**FIGURE 4**  
**COMPACTION DATA**  
**TEST FILL**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**






SYMBOL	SHELBY TUBE NO.	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	SOIL TYPE (USCS SOIL CLASSIFICATION)
△	ST-1	78	54	OLIVE CLAY (CH)
⊙	ST-2	76	51	OLIVE CLAY (CH)
X	ST-3	79	54	OLIVE CLAY (CH)
⊠	ST-4	79	55	OLIVE CLAY (CH)
+	ST-5	76	52	OLIVE CLAY (CH)
⬡	ST-6	65	44	OLIVE CLAY (CH)


**FIGURE 5**  
**ATTERBERG LIMIT**  
**TEST FILL SOIL**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**

SYMBOL	SAMPLE NO.	LIQUID LIMIT(%)	PLASTICITY INDEX (%)	SOIL TYPE
△	ST-1	78	54	OLIVE CLAY (CH)
⊙	ST-2	76	51	OLIVE CLAY (CH)
X	ST-3	79	54	OLIVE CLAY (CH)
⊠	ST-4	79	55	OLIVE CLAY (CH)
+	ST-5	76	52	OLIVE CLAY (CH)
⊕	ST-6	65	44	OLIVE CLAY (CH)



COBBLES	GRAVEL		SAND			SILT AND CLAY FRACTION
	coarse	fine	coarse	medium	fine	

**FIGURE 6**  
**GRAIN SIZE DISTRIBUTION**  
**TEST FILL SOIL**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**



**LEGEND**


ST-2  
○ LABORATORY PERMEABILITY AND SAMPLE NUMBER

FIGURE 7

**LABORATORY PERMEABILITY VERSUS WATER CONTENT**

LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY

**ENVIRONMENTAL SOLUTIONS, INC.**




NOT TO SCALE

FIGURE 8

**SCHEMATIC OF  
INFILTRMETER TEST MODEL**


LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY

**ENVIRONMENTAL SOLUTIONS, INC.**



**LEGEND**  
..... TN-2  
———— TN-3  
———— TN-6  
- - - - TN-7


FIGURE 9  
12-INCH SOIL TENSION/SUCTION  
VERSUS TIME  
LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY  
ENVIRONMENTAL SOLUTIONS, INC.



**LEGEND**

- TN-4
- - - TN-5

FIGURE 10  
**18-INCH SOIL TENSION/SUCTION  
VERSUS TIME**  
LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY  
ENVIRONMENTAL SOLUTIONS, INC.



**LEGEND**

TN-2  THE TIME WHEN THE TENSIO METER INDICATED A SATURATED SOIL CONDITION EXISTED.

FIGURE 11

**INFILTRATION VERSUS TIME**

LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY

**ENVIRONMENTAL SOLUTIONS, INC.**

APPENDIX A  
ONE-DIMENSIONAL SWELL TEST RESULTS



# ONE DIMENSIONAL SWELL TEST

ASTM 4546-85

Project Name:	<u>B-18 Landfill</u>		
Project No.:	<u>89-977H</u>		
Tested By:	<u>GH</u>	Date:	<u>03/08/91</u>
Input Checked By:	<u>GH</u>	Date:	<u>03/13/91</u>
Reviewed By:	<u>we</u>	Date:	<u>4/5/91</u>

Vertical Stress (psi):	0.470	0.467	0.467	0.468	0.465	0.464
Frame No.:	1	2	3	4	5	6
Sample No.:	ST-1	ST-2	ST-3	ST-4	ST-5	ST-6
Depth (ft):	---	---	---	---	---	---
Liquid Limit (LL):	78	76	79	79	76	65
Plasticity Index (PI):	54	51	54	55	52	44

WATER CONTENT	Trim	Final	Trim	Final	Trim	Final	Trim	Final	Trim	Final	Trim	Final
Wet Wt.+Tare (gm):	219.35	309.43	284.96	316.34	175.14	264.93	150.53	294.07	143.39	271.65	208.92	315.20
Dry Wt.+Tare (gm):	194.56	253.75	248.23	261.60	158.94	211.22	140.33	238.76	133.51	219.52	187.15	262.55
Wt. of Tare (gm):	92.08	114.49	91.99	126.32	89.76	76.62	90.16	105.23	92.18	81.31	89.82	115.62
Moisture Content (%):	24.19	39.98	23.51	40.46	23.42	39.90	20.33	41.42	23.91	37.72	22.37	35.83

DENSITY AND SATURATION	Initial		Final		Initial		Final		Initial		Final	
	Initial	Final	Initial	Final	Initial	Final	Initial	Final	Initial	Final	Initial	Final
Wet Soil+Tare (gm):	1141.40	309.43	1130.70	316.34	1132.40	264.93	1131.00	294.07	1140.20	271.65	1148.70	315.20
Ring/Tare (gm):	967.30	114.49	962.60	126.32	966.20	76.62	969.00	105.23	969.30	81.31	970.80	115.62
Wet Soil (gm):	174.10	194.94	168.10	190.02	166.20	188.31	162.00	188.84	170.90	190.34	177.90	199.58
Moisture Content (%):	25.02	39.98	24.26	40.46	23.48	39.90	21.32	41.42	23.65	37.72	21.08	35.83
Dry Soil (gm):	139.26	139.26	135.28	135.28	134.60	134.60	133.53	133.53	138.21	138.21	146.93	146.93
Length of Sample (in):	0.8750	1.0323	0.8750	1.0270	0.8750	1.0035	0.8750	1.0291	0.8750	0.9995	0.8750	1.0243
Diameter of Sample (in):	2.870	2.870	2.870	2.870	2.870	2.870	2.870	2.870	2.870	2.870	2.870	2.870
Volume of Sample (c.c.):	92.760	109.436	92.760	108.874	92.760	106.383	92.760	109.097	92.760	105.959	92.760	108.588
Wet Density (PCF):	117.1	111.2	113.1	108.9	111.8	110.5	109.0	108.0	115.0	112.1	119.7	114.7
Dry Density (PCF):	93.7	79.4	91.0	77.5	90.5	79.0	89.8	76.4	93.0	81.4	98.8	84.4
Specific Gravity:	2.70	2.70	2.70	2.70	2.70	2.70	2.70	2.70	2.70	2.70	2.70	2.70
Volume of Solids (%):	55.60	47.13	54.01	46.02	53.74	46.86	53.32	45.33	55.18	48.31	58.67	50.11
Volume of Liquid (%):	37.56	50.88	35.38	50.28	34.07	50.49	30.69	50.70	35.24	49.20	33.39	48.49
Volume of Air (%):	6.84	1.99	10.60	3.70	12.19	2.65	15.99	3.97	9.57	2.49	7.95	1.40
Deg. of Saturation (%):	84.60	96.24	76.94	93.14	73.65	95.01	65.74	92.74	78.64	95.18	80.77	97.20

SUMMARY	Initial	Final	Initial	Final	Initial	Final	Initial	Final	Initial	Final	Initial	Final
Moisture Content (%):	25.02	39.98	24.26	40.46	23.48	39.90	21.32	41.42	23.65	37.72	21.08	35.83
Dry Density (PCF):	93.7	79.4	91.0	77.5	90.5	79.0	89.8	76.4	93.0	81.4	98.8	84.4
Deg. of Saturation (%):	84.60	96.24	76.94	93.14	73.65	95.01	65.74	92.74	78.64	95.18	80.77	97.20
Final Swell (%):		17.98		17.37		14.69		17.61		14.23		17.06

Note: 1. Specific gravity is assumed.      2. Demineralized water used.

**APPENDIX B**  
**SDRI FIELD DATA SHEETS**



**Chemical Waste Management, Inc.**

Post Office Box 471  
Kettleman City, California 93239  
209 386-9711

B-1

**TRANSMITTAL LETTER**

To Environmental Solutions, Inc  
21 Technology Drive  
Irvine, CA 92718  
ATTN: Julio Badel

Date 3/28/91  
Project No. 89-03

Sent by

- Mail
- Air Freight
- Hand Carried
- Under Separate Cover
- Enclosed

Quantity	Item	Description
4	B-18 TestCell Field Data Sheets	(2) Originals (2) Copies
Remarks		

Per Vien Perez

Initial 3'

STATION I-1		INFILTRMETER READINGS										SWELL DATA			
DATE	FIELD ENGR	WATER TEMP.	WATER DEPTH	INITIAL TIME	FINAL TIME	TIME INTERVAL	INITIAL WT OF BAG (GRAMS)	FINAL WT OF BAG (GRAMS)	CHANGE IN WT (GRAMS)	NW CORNER Δh	NE CORNER Δh	SE CORNER Δh	SW CORNER Δh		
74	1/31/91	NOP/JB	13°C	15'	16:37	(2/1) 07:45	15.1	3711 <sup>*5</sup>	133		3.0	3.0	3.0	3.0	
								3758 <sup>*2</sup>	137	7199					
								3749 <sup>*6</sup>	103						
FR	2/1/91	NOP/JB	11°C	15"	07:45	(2/1) 16:15	8.5	3923 <sup>*4</sup>	132	7437	3.6	3.0	3.5	3.6	
								4234 <sup>*12</sup>	151						
								4234 <sup>*12</sup>	151						
								4269 <sup>*11</sup>	155						
								3842 <sup>*1</sup>	120						
								3927 <sup>*3</sup>	125	15733					
								1300 <sup>*9</sup>	129						
SAT	2/2/91	VOP	11°C	15"	08:50	15:40	6.9	1315 <sup>*10</sup>	120		2.9	2.94	2.98	2.9	
								3950 <sup>*2</sup>	212						
								3943 <sup>*5</sup>	170	9877					
								4198 <sup>*6</sup>	345						
SAT	2/2/91	VOP	11°C	15"	15:45	(2/3) 07:45	18.1	4201 <sup>*4</sup>	265		2.9	2.94	2.98	2.9	
								4246 <sup>*3</sup>	321						
								4086 <sup>*1</sup>	314	15486					
								421 <sup>*8</sup>	1243						
SUN	2/3/91	VOP		15"	09:50	(2/3) 15:35	5.9	1362 <sup>*10</sup>	1116		2.89	2.92	2.97	2.9	
								4164 <sup>*11</sup>	2480						
								4339 <sup>*12</sup>	2512	3935					

JOB NO. 89-03 PROJECT B-18 Infiltrimeter \_\_\_\_\_

INFILTRMETER FIELD DATA

COMPARISON  
932.9A

911

②

STATION I-1		INFILTRMETER READINGS										SWELL DATA			
DATE	FIELD ENGR	WATER TEMP.	WATER DEPTH	INITIAL TIME	FINAL TIME	TIME INTERVAL	INITIAL WT OF BAG (GRAMS)	FINAL WT OF BAG (GRAMS)	CHANGE IN WT (GRAMS)	NW CORNER Δh	NE CORNER Δh	SE CORNER Δh	SW CORNER Δh		
SUN	2/3/91	13°C	15"	1540	1705	15.5	4500 <sup>#3</sup>	2200		936.03	936.11	936.38	936.24		
							4161 <sup>#5</sup>	1935							
							4158 <sup>#2</sup>	2090							
							4802 <sup>#6</sup>	1754	8248						
MON	2/4/91	11°C	15"	0710	0740	9.5	1421 <sup>#8</sup>	1217		2.88	2.92	2.96	2.9		
							1400 <sup>#9</sup>	1119							
							4377 <sup>#1</sup>	2248							
							4113 <sup>#7</sup>	2384	4343						
MON	2/4/91	14°C	15"	1643	1550	23.2	4160 <sup>#5</sup>	1912		2.88	2.92	2.96	2.9		
							4421 <sup>#6</sup>	2292							
							4308 <sup>#11</sup>	1295							
							4084 <sup>#12</sup>	1949	57448						
TUE	2/5/91	15°C	15"	1555	1430	22.7	1377 <sup>#9</sup>	677							
							1367 <sup>#10</sup>	947							
							3993 <sup>#8</sup>	924							
							4697 <sup>#3</sup>	1155	57730						
WED	2/6/91	14°C	15"	1435	1600	25.4	4416 <sup>#8</sup>	167		2.74	2.81	2.75	2.75		
							4392 <sup>#1</sup>	2530							
							4265 <sup>#4</sup>	1623							
							4195 <sup>#6</sup>	1463	57483						

JOB NO. 87-03 PROJECT B-18 Infiltrimeter

INFILTRMETER FIELD DATA

STATION I-1		INFILTROMETER READINGS										SWELL DATA			
DATE	FIELD ENGR	WATER TEMP.	WATER DEPTH	INITIAL TIME	FINAL TIME	TIME INTERVAL	INITIAL WT OF BAG (GRAMS)	FINAL WT OF BAG (GRAMS)	CHANGE IN WT (GRAMS)	NW CORNER Δh	NE CORNER Δh	SE CORNER Δh	SW CORNER Δh		
TH 2/7/91	VOP	19.6°C	15"	1600	1625 (2-B)	25	1402 <sup>*9</sup>	1049							
				1600			4288 <sup>*12</sup>	1337							
				1600			4599 <sup>*13</sup>	2059							
				1600			4826 <sup>*11</sup>	1490	9175						
FR 2/8/91	VOP	16.0°C	14.9"	1630	1627 (2-B)	64.1	4289 <sup>*2</sup>	456		2.74	2.73	2.78	2.76		
							4571 <sup>*4</sup>	387							
							4437 <sup>*1</sup>	459							
							4725 <sup>*3</sup>	457							
							4224 <sup>*6</sup>	401							
							1492 <sup>*8</sup>	252	21308						
MO 2/11/91	VOP	12°C	14.9"	0834	1145 (2-12)	27.2	1311 <sup>*10</sup>	1068		2.74	2.73	2.79	2.76		
							4421 <sup>*12</sup>	762							
							4627 <sup>*11</sup>	1083							
							4370 <sup>*5</sup>	903	10913	2.84	2.73	2.88	2.75		
TUE 2/12/91	VOP	19.4°C	14.8"	1150	1407 (5-B)	26.3	4863 <sup>*1</sup>	1030							
							4327 <sup>*6</sup>	1048							
							4100 <sup>*2</sup>	1587							
							1418 <sup>*8</sup>	1077	9466						

JOB NO. 89-03 PROJECT B-18 Infiltrometer

INFILTROMETER FIELD DATA

STATION I-1		INFILTRMETER READINGS										SWELL DATA			
DATE	FIELD ENGR	WATER TEMP.	WATER DEPTH	INITIAL TIME	FINAL TIME	TIME INTERVAL	INITIAL WT OF BAG (GRAMS)	FINAL WT OF BAG (GRAMS)	CHANGE IN WT (GRAMS)	NW CORNER Δh	NE CORNER Δh	SE CORNER Δh	SW CORNER Δh		
2/3/91	VOP	16°C	14.8"	1407	1442	24.6	1366 <sup>#9</sup>	951		2.72	2.73	2.8	2.73		
							1304 <sup>#11</sup>	904							
							4722 <sup>#4</sup>	1981							
							4973 <sup>#3</sup>	2900	8626						
2/14/91	VOP	16.0°C	14.75"	1442	1530	23.8	4367 <sup>#1</sup>	1338		2.71	2.73	2.82	2.69		
							4725 <sup>#5</sup>	1536							
							1398 <sup>#8</sup>	1124							
							1347 <sup>#10</sup>	1123	6716						
2/15/91	VOP	16°C	14.75"	1430	1550	72.3	1808 <sup>#4</sup>	1189		2.64	2.6	2.79	2.57		
							4617 <sup>#3</sup>	1874							
							5060 <sup>#11</sup>	1046							
							5481 <sup>#12</sup>	1246							
							4531 <sup>#6</sup>	2100							
							4504 <sup>#2</sup>	2115	9426						
2/18/91	VOP	14°C	13.8"	1450	1510	24.4	1414 <sup>#8</sup>	122							
							1386 <sup>#10</sup>	1109							
							4771 <sup>#5</sup>	2476							
							4747 <sup>#1</sup>	1122	5899						

WED

TH

FR

MON \*

Wind pull down wires, unable to measure swell data

JOB NO. 89-03 PROJECT B-18 Landfill Infiltrometer

INFILTRMETER FIELD DATA

STATION I-1		INFILTROMETER READINGS										SWELL DATA			
DATE	FIELD ENGR	WATER TEMP.	WATER DEPTH	INITIAL TIME	FINAL TIME	TIME INTERVAL	INITIAL WT OF BAG (GRAMS)	FINAL WT OF BAG (GRAMS)	CHANGE IN WT (GRAMS)	NW CORNER Δh	NE CORNER Δh	SE CORNER Δh	SW CORNER Δh		
TUE 2/19/91	VOP	16°C	13.8"	1510	1351 <sup>(2-20)</sup>	22.6	4537 <sup>*6</sup>	2997		-	-	-	-		
WED 2/20/91	VOP	16°C	14.8"	1351	1450 <sup>(2-21)</sup>	25.0	5056 <sup>*11</sup>	1264	5332	-	-	-	-		
TH 2/21/91	VOP	16°C	14.75"	1450	1425 <sup>(2-22)</sup>	23.6	4586 <sup>*1</sup>	1911	4874						
FR 2/22/91	VOP	16°C	14.5"	1425	1700 <sup>(2-23)</sup>	74.6	4561 <sup>*6</sup>	2881	4884	1.44	1.48	1.45	1.42		
							4920 <sup>*5</sup>	2104		1.44	1.48	1.45	1.42		
							4679 <sup>*4</sup>	1984							
							4942 <sup>*3</sup>	2251							
							1459 <sup>*8</sup>	1075							
							1442 <sup>*9</sup>	1151	12029						
MON 2/25/91	VOP	15°C	14.0"	1700	1555 <sup>(2-26)</sup>	22.9	4713 <sup>*12</sup>	1802		1.43	1.46	1.45	1.40		
							4351 <sup>*2</sup>	3384	3878						
TUE 2/26/91	VOP	15°C	16.0"	1555	1515 <sup>(2-27)</sup>	23.3	432 <sup>*10</sup>	1174		1.42	1.46	1.45	1.40		
							4520 <sup>*6</sup>	1996	3346						
WED 2/27/91	VOP	13°C	16.0"	1515	1180 <sup>(3-1)</sup>	43.8	484 <sup>*4</sup>	1500		1.42	1.46	1.45	1.40		
							4567 <sup>*1</sup>	1536	6345						

JOB NO. 89-03 PROJECT B-18 INFILTRATED

INFILTROMETER FIELD DATA



STATION I-1		INFILTRMETER READINGS										SWELL DATA			
DATE	FIELD ENGR	WATER TEMP.	WATER DEPTH	INITIAL TIME	FINAL TIME	TIME INTERVAL	INITIAL WT OF BAG (GRAMS)	FINAL WT OF BAG (GRAMS)	CHANGE IN WT (GRAMS)	NW CORNER Δh	NE CORNER Δh	SE CORNER Δh	SW CORNER Δh		
3/11/91	VOP	13°C	16.0"	1100	1010	95.2	4368 <sup>#6</sup>	1010		1.42	1.46	1.45	1.40		
							4982 <sup>#3</sup>	993							
							5012 <sup>#2</sup>	797							
							1376 <sup>#10</sup>	930	12008						
3/5/91	VOP	12°C	16.0"	1010	821	24.5	4511 <sup>#2</sup>	3299		1.41	1.46	1.45	1.40		
							5166 <sup>#11</sup>	2525	3853						
							4565 <sup>#5</sup>	869		1.41	1.44	1.43	1.39		
3/6/91	VOP	12°C	15.0"	1041	900	46.3	1425 <sup>#9</sup>	987	4134						
							1457 <sup>#8</sup>	671							
3/8/91	VOP	11°C	14.9"	900	1530	78.5	4511 <sup>#4</sup>	705		1.40	1.42	1.41	1.39		
							4136 <sup>#1</sup>	772	7956						
3/11/91	RA	11°C	14.2"	1530	1105	43.6	4474 <sup>#2</sup>	1840		16.2	15.8	15.4	16.0		
							4569 <sup>#</sup>	2330	4873						
3/13/91	RA	11°C	14.2"	1105	1330	122.4	4000 <sup>#4</sup>	570							
							3848 <sup>#</sup>	581	6687						
3/18/91	RA	10°C	14.3"	1330	1405	48.6	4457 <sup>#</sup>	1196							
							3937 <sup>#2</sup>	2091	5109						
3/20/91	RA/VOP	11°C	15"	1405	1540	49.6	4167 <sup>#6</sup>	1811							
							4987 <sup>#12</sup>	1322	6023						

JOB NO. 82-023 PROJECT B-18 Testfill

INFILTRMETER FIELD DATA

wires broke  
wires broke  
swell data measured by topographic survey



4-3-91

STATION <u>I-1</u>				TENSIO METER READINGS (CENTIBARS)							
DATE	TIME	FIELD ENGR	ATM. PRESSURE (IN. Hg)	6"	12"	12"	18"	18"	12"	12"	6"
				1	2	3	4	5	6	7	8
1/31/91	1641	VOP/JB		34	30	18	18	18	24	11	16
2/1/91	0750	VOP/JB		45	54	32	32	30	44	34	20
2/1/91	1617	VOP/RAG		45	51	40	38	36	46	38	15
2/2/91	0855	VOP	29.41	50	58	50	50	46	52	46	-*
2/2/91	1350	VOP		51	59	52	53	49	54	48	-
2/3/91	1000	VOP		4	62	58	60	54	59	52	-
2/3/91	1550	VOP		4	60	57	58	54	60	51	-
2/4/91	0717	VOP		2	62	62	62	58	62	56	-
2/4/91	1645	VOP		3	61	62	62	58	62	56	-
2/5/91	1605	VOP		4	61	64	64	60	64	58	
2/6/91	1442	VOP		4	62	66	66	62	64	60	
2/7/91	1611	RG/RA		4	62	66	66	63	66	60	
2/8/91	1640	VOP		4	62	68	68	66	68	58	
2/11/91	0836	VOP		2	62	72	70	68	70	60	
2-12-91	1150	RG		4	52	68	72	68	72	58	
2/13/91	1429	VOP		3	2	64	70	68	72	40	
2/14/91	1453	VOP		4	2	52	72	68	71	13	
2/15/91	1448	VOP		4	0	30	70	68	70	6	
2/18/91	1455	VOP		-*	0	6	74	70	14	0	
2/19/91	1528	VOP		-	0	6	76	70	14	0	
2/20/91	1351	VOP		-	0	6	77	70	12	0	
2/21/91	1500	VOP		-	0	6	78	70	12	0	
2/22/91	1458	VOP		-	0	6	76	69	12	0	
2/23/91	1705	VOP		-	0	6	76	71	10	0	
2/26/91	1602	VOP		-	0	6	76	70	10	0	
2/27/91	1520	VOP		-	0	6	76	70	10	0	
3/1/91	1105	VOP		-	0	6	76	70	10	0	
3/5/91	1012	VOP		-	0	6	76	70	9	0	
3/6/91	1051	VOP		-	0	4	77	71	8	0	
3/8/91	914	VOP		-	0	2	78	71	8	0	

⊗ Refilled

JOB NO. 89-03

PROJECT B-18 Infiltrometer

TENSIO METER FIELD DATA



**APPENDIX E.2**  
**PHASE III CLAY SOURCE TESTING REPORT**



3990 Old Town Avenue  
Suite B-101  
San Diego, CA 92110

PH 619.297.1530  
FAX 619.297.1532

[www.geosyntec.com](http://www.geosyntec.com)

11 February 2008

Rodney Walter  
Waste Management, Inc.  
5903 Spring Blossom Street  
Bakersfield, California 93313

Subject: Clay Source Testing: Summary of Field and Laboratory Test Results  
Kettleman Hills Facility  
Kettleman City, California

Dear Rodney:

Geosyntec Consultants (Geosyntec) is pleased to provide Waste Management, Inc. (WMI) with the results of our recent investigation of a proposed clay source at the Kettleman Hills Facility (KHF), located in Kings County, California. The Pecten Claystone, a clay layer located in the San Joaquin Formation on the eastern boundary of Landfill B-17 has been identified as a potential clay source for use in the liner system of the proposed Class I/II (hazardous waste) Landfill B-18 expansion (see Figure 1). Clay from this clay layer has been used for clay liners on site successfully in the past. Based on discussions with you and a review of preliminary designs for the expansion of Landfill B-18, we understand approximately 35,000 cubic yards (cy) of clay material will be needed for the first phase of the Landfill B-18 expansion.

#### **PROJECT DESCRIPTION**

The Code of Federal Regulations Part 264 (Subtitle C) and the California Code of Regulations (CCR) Titles 23 and 22 have the following requirements for the clay liner component of a hazardous waste landfill:

- The compacted soil material shall have a hydraulic conductivity of no more than  $1 \times 10^{-7}$  centimeters per second (cm/s),

# Geosyntec<sup>®</sup>

consultants

- The clay liner shall consist of materials with at least 30 percent of the material, by weight, passing a No. 200 U.S. Standard sieve, and
- The materials shall be fine-grained soils with a significant clay content and without organic matter, in the "SC" (clayey sand), "CL" (clay, sandy or silty clay), or "CH" (clay, sandy clay) classes of the Unified Soil Classification System.

The purpose of our investigation was to evaluate whether the earthen material in the proposed clay source meets the requirements stated above and to determine the geographic extent of these materials. Our scope for this phase of work included performing a field investigation to evaluate the limit of the claystone material and collect samples, laboratory testing, and preparation of this letter report. We have also prepared plans, specifications and construction quality assurance recommendations for construction of a test pad; these documents have been provided under separate cover.

## REVIEW OF EXISTING DOCUMENTATION

We have reviewed existing borings performed by others in the general vicinity of the proposed clay source. Copies of relevant and available borings in the vicinity are included in Attachment 1. We have also reviewed the following documents summarizing laboratory and field testing of clay materials used at the site in the past:

- Environmental Construction Services, Inc., 1991, "Clay Source Report, Landfill B-18, Phase IA and IB, Kettleman Hills Facility, Kettleman City, California," dated 25 November 1991.
- Environmental Solutions, Inc., 1990 "Engineering and Design Report, Landfill Unit B-18, Phases I and II and Final Closure, Kettleman Hills Facility, Kings County, California," dated August 1990.
- Environmental Solutions, Inc., 1992, "Test Fill and Infiltration Test Results, Landfill Unit B-18, Phases I and II and Final Closure," dated 23 January 1992.
- Golder Construction Services, 1993, "Construction Reports for Landfill B-18, Phase IIA and IIB, Volume I – Clay Source Report, Kettleman Hills Facility, Kettleman City, California," dated May 1993.

## **FIELD INVESTIGATION**

Our field investigation was performed at the site by Layne Christensen Company on 27 November and 28 November 2008. Three borings (CS-1, CS-1A, and CS-2) were advanced to depths ranging from 21 feet to 91 feet using the hollow stem auger (HSA) drilling method. The borings were sampled at approximately 5 foot intervals with a California sampler; bulk samples of soil cuttings were also collected. Locations of the borings are shown on Figure 1. Four test pits were also excavated to depths ranging from 10 to 12 feet by KHF staff. The borings and test pits were sampled and logged in accordance with the Unified Soil Classification System by an engineer from our firm. Boring and test pit logs are provided in Attachment 2.

## **LABORATORY TESTING**

Samples from the borings and test pits were collected and returned to our office for review. Based on a review of the boring logs and samples, laboratory tests were assigned and select soil samples were delivered to Excel Geotechnical Testing, Inc. for laboratory testing. Potential clay source material was tested for the plasticity characteristics, grain size analyses, compaction, and permeability. Results of these tests are summarized in Table 1 and are presented in Attachment 3. Laboratory testing was performed in general accordance with American Society for Testing and Materials (ASTM) standards. Hydraulic conductivity tests performed on samples collected with a California sampler were based on maximum dry density results of similar clay materials from the test pad construction for Landfill B-18 Phase I/II (Environmental Construction Services, Inc., 1991); the actual degree of relative compaction may vary for these samples. During hydraulic conductivity testing of these samples, under a confinement of 5 pounds per square inch (psi), significant swelling was noted. This suggests that the Pecten claystone materials may be considered highly expansive.

## **CONCLUSIONS**

Based on our field investigation and a review of previous work at the site, the Pecten Claystone ranges in depth from a few feet (at the northeastern boundary) to more than 90 feet deep at the western boundary of the clay layer. The clay layer is estimated to dip to the southwest at approximately 32 degrees. The surface of this clay layer may be expected to be weathered and may contain some disturbance due to previous grading at the site in some areas.

Based on a review of the available data and the results of our field and laboratory tests, the proposed clay source is generally classified as fat clay (CH) with approximately 90 percent of




# Geosyntec<sup>®</sup>

consultants

material passing the No. 200 sieve. Based on preliminary laboratory testing, the laboratory hydraulic conductivity of the compacted clay is on the order of  $5 \times 10^{-9}$  cm/s to  $1 \times 10^{-8}$  cm/s when compacted to a minimum relative compaction of approximately 92 percent and at least two percent wet of the optimum moisture content. The proposed material is anticipated to generally meet the state and federal requirements for a compacted clay liner and to be suitable for use in the construction of the expansion of Landfill B-18. However, field hydraulic conductivity and laboratory hydraulic conductivity can often vary by more than an order of magnitude. Results of the test pad Sealed Double Ring Infiltrometer test, which will be performed during construction of landfill B-17 Phase A1 on material excavated from the Pecten Claystone, will provide more conclusive results on the in-situ hydraulic conductivity of the proposed material. Specifications, drawings, and construction quality assurance testing recommendations for the test pad construction have been provided under separate cover.

We appreciate the opportunity to work on this project. If you have any questions, please call Jane Soule at 619.297.1530 x 208.

Sincerely,



Jane W. Soule, R.C.E. 59815  
Project Engineer



**Attachments:**


- Table 1: Summary of Geotechnical Laboratory Test Results
- Figure 1: Site Plan
- Attachment 1: Previous Investigations
- Attachment 2: Current Field Investigation
- Attachment 3: Laboratory Test Results

TABLE 1  
 SUMMARY OF GEOTECHNICAL LABORATORY TEST RESULTS  
 CLAY SOURCE EVALUATION - PECTEN CLAYSTONE  
 KETTLEMAN HILLS FACILITY, KETTLEMAN CITY, CALIFORNIA








Boring ID	Sample ID	Depth (ft)		USCS	As-Received Conditions		Sieve Fines (%)	Atterberg Limits			Laboratory Compaction			Test Conditions (MC, RC)
		From	To		Moisture Content (D2216) (%)	Dry Density (pcf)		LL (%)	PL (%)	PI (%)	Maximum Dry Density (pcf)	Optimum Moisture (%)	(cm/s)	
CS-1	1-2	10.5	12	CH - Fat Clay	16.0		92.2	100	35	65			7.0E-08	+2, 90%*
CS-1	1-3	15	16.5											
CS-1	1-4	20	21.5	CH - Fat Clay	18.5	100.6	96.0	88	32	56				
CA-1A	Bulk 1A-1	0	5	CH - Fat Clay with Sand	12.4		76.0	55	21	34	122	12.5		7.4E-08, 9.2E-09
CA-1A	1A-2	10.5	12		19.3	100.3								+3, 92%, +3, 89%
CA-1A	1A-3	16	16.5	MH - Elastic Silt	20.3		98.1	97	44	53				
CA-1A	1A-5	25	26.5	CH - Fat Clay	20.9	98.6	93.3	105	41	64				6.2E-08
CA-1A	1A-6	30	31.5	MH - Elastic Silt	23.1		89.6	89	39	50				9.6E-08
CA-1A	1A-7	35	36.5											
CA-1A	1A-8	40	41.5	CH - Fat Clay	21.2		89.5	78	31	47				
CA-1A	1A-9	45	46.5	CH - Fat Clay	24.4	98.2	87.7	82	35	47				
CA-1A	1A-11	55	56.5	CH - Fat Clay with Sand	18.6	95.8	84.2	58	29	29				
CA-1A	1A-13	65	66	SC - Clayey Sand	3.4		17.4							
CS-2	Bulk 2-1	0	5	CH - Fat Clay	14.1		96.3	104	36	68	113.1	15.6		3.7E-09
CS-2	Bulk 2-2	6.5	10.5											
CS-2	2-2	10.5	12	CH - Fat Clay	16.5	106.4	95.2	100	34	66				
CS-2	2-4	20	21.5	CH - Fat Clay	21.0		95.3	92	39	53				8.6E-08
CS-2	2-7	35	36.5	CH - Fat Clay	21.0	100.6	89.8	93	33	60				
CS-2	2-9	45	46.5	CH - Fat Clay	24.7	99.7	98.6	104	37	67				
CS-2	2-11	55	56.5	CH - Fat Clay	24.0		96.7	82	33	49				8.2E-08
CS-2	2-13	65	66											
CS-2	2-14	70	71.5	CH - Fat Clay	25.1	97.7	98.4	112	40	72				1.7E-08
CS-2	2-16	80	81.5	CH - Fat Clay	25.4		91.1	129	41	88				5.3E-08
CS-2	2-17	85	86.5											
TP-1	TP1-1	9	10	CH - Fat Clay	20.8		93.0	100	37	63	109.9	17.8		1.1E-08
TP-2	TP2-1	0	8	CH - Fat Clay	14.6		97.8	92	31	61	111.7	16.2		5.0E-09
TP-3	TP3-1	11	12	CH - Fat Clay	21.9		91.1	102	35	67	108.2	17.4		6.5E-09
TP-4	TP4-1	9	10	CH - Fat Clay	17.0		88.5	93	34	59	105.5	20.1		1.4E-08


Note: \*Samples collected with a California type sampler tested for hydraulic conductivity were compacted at 90% relative compaction of the maximum dry density of similar materials from the test pad construction of Landfill B-18 Phases 1A/1B (Environmental Construction Services, 1991).

F:\CAD\SC0386 KMAN B-17 CON\figures\location of pecten claystone.dwg




**LEGEND:**

-  BORING, CURRENT INVESTIGATION
-  TEST PIT, CURRENT INVESTIGATION
-  BORING, URS (2003)
-  BORING EMCON (1985)
-  APPROXIMATE LIMITS OF PECTEN CLAYSTONE
-  B-17 LIMIT OF GRADING
-  B-17 LIMIT OF LINER



NOTE:  
PECTEN CLAYSTONE LIMITS BASED ON MAPPING BY URS (2003).

SITE PLAN LANDFILL B-17 KETTLEMAN HILLS FACILITY		
	DATE:	JAN 08
	PROJECT NO.	SC0478
		FIGURE <b>1</b>

## Attachment 1: Previous Investigations

# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA		Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft)				
5					5			Interlayered light olive-brown (2.5Y 5/4) clayey SILTSTONE and silty CLAYSTONE; lithified  (gypsum layers in top 20 feet)
					10			
					15			
					20			

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.35  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900'MSL

CLASSIFICATION DATA			FIELD DATA			Depth In Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)					
c						25			Interlayered light olive-brown (2.5Y 5/4) clayey SILTSTONE and silty CLAYSTONE; lithified
						30			
						35			
						40			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36

BORING NO. K-5

BY JK/SW DATE 6/1/84 - 6/14/84

SURFACE ELEV. 900'MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Core Recovery	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
2			4'			45	1	Light olive-brown (2.5Y 5/4) CLAYSTONE with reddish-yellow (7.5YR 6/8) 1/4-inch claystone layers; occasional light gray (10YR 7/1) fine sandstone lenses cemented with gypsum	
			2'			50	2	Light olive-brown (2.5Y 5/4) very fine, silty SANDSTONE Light olive-brown (2.5Y 5/4) silty CLAYSTONE Light olive-brown (2.5Y 5/4) very fine, silty SANDSTONE; loose	
						55		(olive-yellow (2.5Y 6/6))	
						60		Light olive-brown, (2.5Y 5/4) silty CLAYSTONE	

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900'MSL

CLASSIFICATION DATA			FIELD DATA		Depth In Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
e					65			Olive-brown (2.5Y 5/4) clayey - sandy SILTSTONE  Light olive-brown (2.5Y 5/4) CLAYSTONE  Light olive-brown (2.5Y 5/4) silty SANDSTONE  Light olive-brown (2.5Y 5/4) CLAYSTONE  Olive-brown (2.5Y 5/4) clayey-silty, very fine SANDSTONE
					70			
					75			
					80			

REMARKS:





# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Core Recovery	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
6						85			(gypsum at 83 feet) Grayish-brown (2.5Y 5/2) CLAYSTONE
			5'			90			Thinly interlayered grayish-brown (2.5Y 5/2) CLAYSTONE and light olive-brown (2.5Y 5/4) SILTSTONE
			2' 0"			95		3	Grayish-brown (2.5Y 5/2) to light olive-brown (2.5Y 5/4) CLAYSTONE with silty partings Thinly interlayered grayish-brown (2.5Y 5/2) CLAYSTONE and light olive-brown (2.5Y 5/4) SILTSTONE Light olive-brown (2.5Y 5/4) clayey SILTSTONE; woody fossils
						100		4	Light olive-brown (2.5Y 5/4) CLAYSTONE with occasional silty partings Light olive-brown (2.5Y 5/4) silty, fine SANDSTONE; loose


REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)					
						105			Gray (N5) CLAYSTONE  Light olive-brown (2.5Y 5/4) very fine silty SANDSTONE  Interlayered light olive-brown (2.5Y 5/4) SILTSTONE and gray (N5) CLAYSTONE  Light olive-brown (2.5Y 5/4) very fine silty SANDSTONE
						110			
						115			
						120			

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Finer (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)					
<						125			Gray (N5) CLAYSTONE  Light olive-brown (2.5Y 5/4) very fine silty SANDSTONE  Interlayered light olive-brown (2.5Y 5/4) SILTSTONE and gray (N5) CLAYSTONE Light olive-brown (2.5Y 5/4) fine SANDSTONE; poorly graded  Gray (N6) CLAYSTONE  Light olive-gray (2.5Y 5/4) sandy SILTSTONE  Gray (N6) CLAYSTONE
						130			
						135			
						140			

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.35  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	CORR Re-Coverry	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
									Gray (N6) CLAYSTONE Interlayered light olive-brown (2.5Y 5/4) CLAYSTONE and very fine SANDSTONE Light olive-brown (2.5Y 5/6) silty, fine SANDSTONE Light olive-brown (2.5Y 5/4) CLAYSTONE Light olive-brown (2.5Y 5/4) slightly silty, fine SANDSTONE; poorly graded (woody fossils at 145 feet) (loose from 145 feet to 148 1/2 feet)
			4'			145			
			1'6"						Interlayered light olive-brown (2.5Y 5/4) very fine sandy SILTSTONE and CLAYSTONE
						150			
						155			
						160			Light olive-brown (2.5Y 5/4) slightly silty, fine to medium SANDSTONE; well graded

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)					
c						165			Light olive-brown (2.5Y 5/4) slightly silty, fine to medium SANDSTONE
						170			Light olive-brown (2.5Y 5/4) sandy SILTSTONE
						175			Light olive-brown (2.5Y 5/4) silty, fine to medium SANDSTONE
						180			Light olive-brown (2.5Y 5/4) CLAYSTONE
									Light olive-brown (2.5Y 5/4) very silty, very fine SANDSTONE
									Interlayered light olive-brown (2.5Y 5/4) very fine, silty SANDSTONE and sandy SILTSTONE

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Core Recovery	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
						185			Interlayered light olive-brown (2.5Y 5/4) very fine, silty SANDSTONE and sandy SILTSTONE  (light olive brown (2.5Y 5/6))
			5'			190			Light olive-brown (2.5Y 5/4) very fine, silty SANDSTONE; very well graded (1-inch clay stringer at 190.5 feet)
						195		7	Interlayered light olive-brown (2.5Y 5/4) SILTSTONE and grayish-brown (2.5Y 5/2) CLAYSTONE  Grayish-brown (2.5Y 5/2) CLAYSTONE with silty partings; iron staining present (olive-gray (5Y 4/2); woody fragments at 196 feet) (dark olive-gray (N4); no silty partings)
			5'			200		8	(olive-gray (5Y 4/2) with silty partings)

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA		Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Finer (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
2					205			Light olive-gray (5Y 6/2) silty SANDSTONE with occasional dark gray (N4) claystone stringers
					210			Dark gray (N4) CLAYSTONE
					215			
					220			Interlayered light olive-gray (5Y 6/2) silty, fine to medium SANDSTONE and SILTSTONE

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36

BORING NO. K-5

BY JK/SW DATE 6/1/84 - 6/14/84

SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/ Ft.)					
6						225			Interlayered light olive-gray (5Y 6/2) silty, fine to medium SANDSTONE and SILTSTONE
						230			Blue gray (N6) CLAYSTONE with silty partings
						235			
						240			Tan to light gray silty, very fine SANDSTONE

REMARKS:





# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.35  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Core Re-Cover	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
~									Tan to light gray silty, fine SANDSTONE
			5'			245	9		Olive-brown (2.5Y 5/4) CLAYSTONE with orange and dark gray (N5) bands; silty to very fine sandy partings; black organics present (dark gray (N5))
			5'				10		Tan to buff SILTSTONE
						250			Medium gray (N6) CLAYSTONE with occasional limonite staining  (slickensides at 249.5 feet)
						255			Olive-gray (5Y 5/2) silty, very fine SANDSTONE with silty layers
						250			

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84- 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900'MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Finer (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)					
c						265			Blue gray (N6) silty CLAYSTONE with silty partings
						270			
						275			
						280			

REMARKS



**EMCON**  
ENGINEERING

# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Finer (No. 200)	Liquid Limit	Plasticity Index	Core Re-Cover	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
K						285			Olive-gray (5Y 6/2) silty, very fine SANDSTONE with blue gray (N5) claystone stringers
						290			Olive-gray (5Y 6/2) SILTSTONE
			5'			295			Light gray to tan silty, fine to medium SANDSTONE
						295	11		Brown gray (2.5Y 5/2) CLAYSTONE with occasional orange and drk gray (N4) thin beds; very fine sandy silt partings present
						295			(medium gray (N5), very silty)
			5'			295	12		(very silty with abundant silt partings)
						300			(fine sandy partings)

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900'MSL

CLASSIFICATION DATA			FIELD DATA		Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
<					305			Blue gray (N6) silty CLAYSTONE  (decrease of silt)
					310			
					315			Light olive (5Y 6/2) slightly silty, fine SANDSTONE with thin blue gray (N6) claystone layers
					320			

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900'MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)					
e						325			Light olive (5Y 6/2) slightly silty, fine SANDSTONE with thin blue gray (N5) claystone layers
						330			
						335			(very silty)
						340			(fine to medium grained and light gray (5Y 6/1))

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Finer (No. 200)	Liquid Limit	Plasticity Index	Core Re-Cover	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
←			5'			345	13		Orange-brown (7.5YR 7/8) sandy CLAYSTONE Tan to light gray (10YR 5/6) silty, fine to medium SANDSTONE  (1/2-inch clayey layer)
			4'			350	14		(1/2-inch clayey layer) (orange brown (7.5YR 7/8), clayey stringers from 346 feet to 349 feet)
						355	15		(olive-gray (5y 5/2) with occasional siltstone lenses)
						360			(orange brown (7.5YR 7/8))

REMARKS.



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft. Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasti- city Index	Compre- sive Strength (TSF)	Penetra- tion (Blows/ Ft.)				
6						365		Orange brown (7.5YR 7/8) slightly silty, fine to medium SANDSTONE
						370		
						375		
						380		

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36

BORING NO. K-5

BY JK/SW DATE 6/1/84 - 6/14/84

SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Core Recovery	Compressive Strength (TSF)	Penetration (Blows/ Ft.)				
c						385			Gray to tan slightly silty, fine to medium SANDSTONE
						390			Olive-gray (2.5Y 5/2) fine sandy SILTSTONE
			4'6"			396	16		Gray to tan slightly silty, fine to medium SANDSTONE
						398			Banded light olive-gray, black and orange clayey SILTSTONE with very fine sandy partings
						395			Dark gray (N5) CLAYSTONE with abundant very fine sandy silt partings
			3'0"			400	17		

REMARKS:








# LOG OF EXPLORATORY BORING

PROJECT NUMBER 244-01.36

BORING NO. K-5

BY JK/SW DATE 6/1/84 - 6/14/84

SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)					
←						405			Blue gray (N6) fine sandy SILTSTONE  (very sandy)
						410			Blue gray (N6) silty fine to medium SANDSTONE
						415			Blue gray (N6) CLAYSTONE  (very sandy)
						420			

REMARKS.



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 244-01.36

BORING NO. K-5

BY JK/SW DATE 6/1/84 - 6/14/84

SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Finer (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)					
<						425			Blue gray (N6) sandy CLAYSTONE  (decrease of sand (increase of sand)
						430			
						435			(very silty)
						440			

REMARKS.



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft. Ground Water Levels	Samples	DESCRIPTION
% Finer (No. 200)	Liquid Limit	Plasti- city Index	Core Re- Cover	Compres- sive Strength (TSF)	Penetra- tion (Blows/ Ft.)			
c			5'			18	Dark to medium gray (N5) CLAYSTONE with tight gray very fine sandy - silty partings; black organics present  (very silty partings)  (1-inch sandy layer) (very silty)	
			5'			445	(blue gray (N6))  Blue gray (N6) silty, fine SANDSTONE with shell fragments Blue gray (N6) sandy-clayey SILTSTONE; very moist	
						450	Blue gray (N6) silty CLAYSTONE with very fine sandy-silty partings	
						455	Blue gray (N6) very fine sandy SILTSTONE	
						460	Dark gray (N6) silty CLAYSTONE with light gray (N7) very fine sandy - silty partings	

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA		Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
←								Dark gray (N6) silty CLAYSTONE with light gray (N7) very fine sandy - silty partings
					465			Interlayered dark gray (N6) CLAYSTONE and SILTSTONE
					470			Dark gray (N6) silty CLAYSTONE with light gray (N7) very fine sandy-silty partings
					475			
					480			

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.35  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900' MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines No.200	Liquid Limit	Plasticity Index	Core Re-Coverry	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
									Dark gray (N6) silty CLAYSTONE with light gray (N7) very fine sandy - silty partings
			2' 8"			485		20	Dark gray (N4) very silty - clayey very fine SANDSTONE; black organics at 485 1/4 feet  (black organics at 488 1/4 feet)
			0'			490		21	
			2'			495		22	
			1' 3"			600		23	Dark gray (N1) very fine, silty SANDSTONE with very thin organic stringers

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36  
 BY JK/SW DATE 6/1/84 - 6/14/84

BORING NO. K-5  
 SURFACE ELEV. 900'MSL

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Core Recovery	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
			1'3"				23		
			3'			505	24		Dark gray (5Y 4/1) CLAYSTONE with very fine, very silty sandy stringers
			1'			510			Dark gray (N4) slightly silty, fine SANDSTONE with occasional claystone stringers
						515			
						520			
									Log below a depth of 508 feet obtained from adjacent borehole. Claystone at 495 feet on column below corresponds to claystone at 503 feet on above column.

REMARKS:



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36

BORING NO. K-5

BY JK DATE 6/12/84

SURFACE ELEV. -

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Levels	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Core Re-Cover	Compressive Strength (TSF)	Penetration (Blows/Ft.)				
c			2'				25	Dark gray (5Y 4/1) CLAYSTONE with occasional sandy stringers	
			0'			500	26	Dark gray (5Y 4/1) CLAYSTONE with very fine silty sandstone stringers	
			1'				27	Dark gray (5Y 4/1) fine silty SANDSTONE with occasional clay stringers; very loose	
			2'			505	28	Dark gray (5Y 4/1) CLAYSTONE with 1/4-inch stringers	
			4'			510	29	Dark gray (5Y 4/1) silty, very fine SANDSTONE with clay stringers  (3-inches with very hard caliche cement)  (fine grained)	
			3'			515	30	Interlayered dark gray clayey - silty, fine SANDSTONE and CLAYSTONE with abundant organics and shell fragments	

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-01.36

BORING NO. K-5

BY JK DATE 6/12/84

SURFACE ELEV. -

CLASSIFICATION DATA			FIELD DATA			Depth in Ft.	Ground Water Level	Samples	DESCRIPTION
% Fines (No. 200)	Liquid Limit	Plasticity Index	Core Recovery	Compressive Strength (TSP)	Penetration (Blows/Ft.)				
			5'				30	Dark gray (5Y 4/1) very fine, very silty SANDSTONE with frequent claystone stringers	
			5'			520	31	Dark gray (5Y 4/1) CLAYSTONE with occasional sandy partings	
								BOTTOM OF BORING	
						525			

REMARKS:





# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 1 OF 24  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				0		ML	SANDY SILTSTONE, fill.
				5			
				10	ⓑ	SS	SILTY SANDSTONE; yellowish gray (5Y, 7/2); 40% silt; very fine grained; moderately graded; minor siltstone laminae; calcareously cemented; moderately indurated; dry.
				15			
				20			

REMARKS Well K-30 was drilled with air-rotary drilling equipment to a total depth of 480 feet. The borehole was converted to a ground-water monitoring well (see Completion Diagram).

ⓑ denotes a bag sample.



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 2 OF 4  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				20	(B) SS	[Dotted pattern]	SILTY SANDSTONE (continued). 20% disseminated silt;
				25			
				30	(B) SS/ SLST	[Dotted pattern]	change of color to dusky yellow (5Y, 6/4); <15% silt; very fine- to fine-grained; arkosic(?); poorly graded.
				35		[Alternating dotted and horizontal line patterns]	SANDSTONE and SILTSTONE interbedded, 2:1. sandstone: dusky yellow (5Y, 6/4). siltstone: light olive-gray (5Y, 5/2); poorly developed bedding.
				40			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 3 OF 24  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				40	(B)	SS/ SLST	SANDSTONE and SILTSTONE interbedded (continued).
				45		SS	
				50	(B)		SANDSTONE.
				55		CLST	
				60			SILTY CLAYSTONE; light olive-gray (5Y, 5/2) 20-30% silt; limonitic partings; poorly indurated; slightly damp.

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 4 OF  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				60	(B)	CLST	SILTY CLAYSTONE (continued).
				65			change of color to dark gray (N3).
				70	(B)		15% disseminated silt; massive.
				75			gypsum viens.
				80			

REMARKS Began water injection at 80 feet.





# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 6 OF  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				100	(B) CLST	CLST	SILTY CLAYSTONE (continued).
				105			
				110	(B)		minor yellowish gray (5Y, 7/2) siltstone stringers.
				115			
				120			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 7 OF 24  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				120	(B)	CLST	SILTY CLAYSTONE (continued).
				125			
				130	(B)		<u>Pecten</u> (?) shell fragments.
				135			
				140			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 8 OF  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				140	(B) CLST	CLST	SILTY CLAYSTONE (continued). minor organic material; 1 shell frag- ment.
				145			
				150	(B)		fine sandstone partings; organic rich.
				155			
				160			change of color to light olive-gray (5Y, 5/2); 20% fine disseminated sand; moderately fissile; gypsum stringers; minor fossils; minor limonitic sand- stone pebbles; poorly indurated.

REMARKS







# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 10 OF  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				180	(B)	CLST/ SLST	CLAYSTONE and SANDY SILTSTONE interbedded (continued).  very poor cuttings return.
				185			
				190	(B)		
				195			
				200			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 11 OF 24  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				200	(B)	CLST /SLST	CLAYSTONE and SANDY SILTSTONE interbedded (continued). CLST:SLST = 1:1.  increase of disseminated sand within the siltstone portion.
				205		SS	
				210	(B)		SILTY SANDSTONE; dusky yellow (5Y, 6/4); very fine- to fine-grained; quartzose; moderately graded; claystone laminae; limonitic staining.
				215			change of color to dark yellowish orange (10YR, 6/6); 40% silt; fine grained; quartzose; iron-oxide cement; abundant organics; poorly indurated.
				220			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 12 OF  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				220	(R)	SS	SILTY SANDSTONE (continued).
				225		SLST /SS	
				230	(R)		SILTSTONE and SANDSTONE interbedded, 2:1. siltstone: light olive-gray (5Y, 5/2); <math>\frac{1}{2}</math>"-thick beds; fissile; limonitic partings. sandstone: dark yellowish orange (10YR, 6/6).
				235			
				240			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 13 OF 24  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				240	(B)	SLST /SS	SILTSTONE and SANDSTONE interbedded (continued).
				245			
				250	(B)		
				255			
				260			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 14 OF  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				260	(B)	SLST /SS	SILTSTONE AND SANDSTONE interbedded (continued). @ 260': organic interbeds(?).
				265		SS	
				270	(B)		SANDSTONE; dusky yellow (5Y, 6/4); 20% silt; fine grained; quartzose; moderate- ly graded; gypsum stringers; organics; moderately indurated; harder drilling.
				275			
				280			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 15 OF 24  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETROMETER (TSF)	PENETRATION (Blows/FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO-GRAPHIC COLUMN	DESCRIPTION
				280	(B)	SS	SANDSTONE (continued).
				285			30% siltstone interbeds.
				290	(B)		
				295		SS/ SLST	
				300			SILTY SANDSTONE and SILTSTONE interbedded (continued on next page).

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 16 OF  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				300	(B)	SS/ SLST	<p>SILTY SANDSTONE and SILTSTONE interbedded.                      silty sandstone: light olive-brown (5Y, 5/6); very fine grained; quartzose.                      siltstone: light olive-brown (5Y, 5/6); thinly bedded; sandstone partings; fissile.</p>
				305			
				310	(B)	CLST /SLST	<p>CLAYSTONE and SILTSTONE interbedded, 1:1.                      claystone: medium dark gray (N4); fissile; poorly indurated.                      siltstone: light olive-brown (5Y, 5/6); fine to very fine sandstone partings; fissile; poorly indurated.</p>
				315			
				320			

REMARKS





# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 17 OF 24  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				320	(B)	CLST /SLST	CLAYSTONE and SILTSTONE interbedded (continued).
				325			
				330	(B)		siltstone portion becomes sandy; limoni- tic staining.
				335			gypsum stringers.
				340			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 18 OF  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				340	(B)	CLST SLST	CLAYSTONE and SILTSTONE interbedded (continued). CLST:SLST = 7:3.
				345			
				350	(B)	CLST	
				355			SILTY CLAYSTONE; medium dark gray (N4); 15-20% light olive-brown (5Y, 5/6) siltstone interbeds; moderately fissile; poorly indurated.
				360			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 19 OF 24  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				366	(B)	CLST	SILTY CLAYSTONE (continued).
				365		SS	
				370	(B)		SILTY SANDSTONE; moderate yellowish brown (10YR, 5/4); 30-40% silt; very fine-to fine-grained; arkosic; limonitic cementation; moderately indurated.
				375			
				380		CLST	CLAYSTONE (continued on next page).

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 20 OF 27  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETROMETER (TSF)	PENETRATION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO-GRAPHIC COLUMN	DESCRIPTION
				380	(B) CLST	CLAYSTONE	CLAYSTONE; medium dark gray (N4); no siltstone beds; organic material.
				385			
				390	(B)		occasional moderate yellowish brown (10YR, 5/4); limonitic, very fine, silty sandstone interbeds.
				395			
				400			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 21 OF 24  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				400	(B) CLST		CLAYSTONE (continued). 10% moderate yellowish brown (10YR, 5/4) siltstone interbeds.
				405			
				410	(B) CLST /SS		SILTY CLAYSTONE and SANDSTONE interbedded. silty claystone: medium dark gray (N4). sandstone: moderate yellowish brown (10YR, 5/4); very fine grained; limonitic staining.
				415			
				420			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 22 OF  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				420	(R) CLST	CLAYSTONE	CLAYSTONE (continued).
				425			
				430	(R)		minor very silty claystone interbeds; abundant organic material.
				435			
			▽	440			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 23 OF 24  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT. SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				440	SS	<p>SANDSTONE; dark gray (N3); no clay or silt; fine- to medium-grained; quartzose; mafics; poorly graded; subrounded to well rounded; friable; wet(?).</p> <p style="text-align: center;">Rec. 0.0'</p> <p style="text-align: center;">445</p> <p style="text-align: center;">Rec. 0.0'</p> <p style="text-align: center;">450</p> <p style="text-align: center;">Rec. 0.0'</p> <p style="text-align: center;">455</p> <p style="text-align: center;">CORE BOX 1</p> <p style="text-align: center;">Rec. 5.0'</p> <p style="text-align: center;">460</p>

@ 455': color change to medium dark gray to dark gray (N4 to N3); <5% silt; quartzose; 10% lithics; rounded; massive; moderately to poorly indurated.

REMARKS The borehole was continuously cored from 440- to 480-feet.



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224-56.17  
 PROJECT NAME Kettleman Hills  
 BY CW DATE 7/21 - 7/24/85

BORING NO. K-30  
 PAGE 24 OF  
 SURFACE ELEV. 878.0'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				460		SS	SANDSTONE (continued). @ 461': <10% disseminated silt.
				CORE BOX 2			
				Rec. 4.5'			@ 464'-465': friable.
				465			
				CORE BOX 3			@ 466': 42° dip. @ 466.5': change of grain size to fine.
				Rec. 5.0'			@ 469'-469.5': 0.5"-thick siltstone interbeds deposited every 0.5".
				470			@ 472': <5% disseminated silt and clay fine- to medium-grained; quartzose; 20% lithics; siltstone laminae deposited every 0.5'; poorly indurated.
				CORE BOX 4			@ 474.5'-475': friable. @ 475': change of grain size to medium to very fine; moderately to poorly graded; massive.
				Rec. 5.0'			@ 476'-477.5': unit becomes a silty sandstone to a sandy siltstone with 50% disseminated silt; very fine grained SILTSTONE; medium dark gray (N4); 10-20% sandstone interbeds; 0.25"- to 0.5"-thick beds; organic laminae; poorly indurated.
				475			@ 477.5'-478.5': no sand; massive. @ 478.5': <25% very fine sandstone laminae; <30° dip.
				CORE BOX 5		SLST	
				Rec. 5.0'			
				480			TERMINATED BORING AT 480 FEET.

REMARKS





KETTLEMAN HILLS MONITORING WELL SUMMARY

MONITORING WELL K-30

LOKI 2

NORTHING: 230115.9  
EASTING: 1700113.4

Well Construction Data <sup>2</sup>	Date Measured
TOC (TOSP) Elevation <sup>3</sup> :	878.83 ft. MSL 96-Apr-01
Ground Surface Elevation	877.7 ft. MSL 87-Nov-22
TOTAL WELL DEPTH:	465 ft. BGS. 87-Nov-22
TOTAL BOREHOLE DEPTH:	480 ft. BGS. 87-Nov-22
Measured Depth to Top of Sand Pack:	421 ft. BGS. 87-Nov-22 #5 7.8' S
Measured Depth to Top of Screen:	435 ft. BGS. 87-Nov-22 #10 5.2' S
Measured Depth to Pump Intake <sup>4</sup> :	457.8 ft. BGS. 87-Nov-22
Measured Depth to Water:	433.40 ft. BTOC 96-Dec-01

Well Deviation Calculations <sup>1</sup>			
Measurement	True Vertical Depth	Ref. Elevation	True Vertical Elevation
WELL TD:	463.45 ft. BGS.	414.20 ft. MSL	414.20
Top of Sand:	419.92 ft. BGS.	457.73 ft. MSL	457.73
Top of Screen:	433.61 ft. BGS.	444.04 ft. MSL	444.04
Pump Intake:	455.66 ft. BGS.	421.99 ft. MSL	421.99
GW Measurement:	432.03 ft. BTOC	446.80 ft. MSL	446.80

Measured Depth (ft.)	Course Length (ft.)	Drift/Deviation Angle (°)	Well Deviation Survey Results			True Elevation (MSL)
			Vertical Course (ft.)	True Vertical Depth (ft.)	True Vertical Elevation (MSL)	
0	0	0.0	0	0	877.65	
25	25	0.2	25.0	25.0	852.65	
50	25	0.6	25.0	50.0	827.65	
75	25	1.1	25.0	75.0	802.66	
100	25	1.8	25.0	100.0	777.67	
125	25	2.6	25.0	125.0	752.69	
150	25	3.6	25.0	149.9	727.74	
175	25	3.2	25.0	174.9	702.78	
200	25	2.9	25.0	199.8	677.81	
225	25	3.4	25.0	224.8	652.86	
250	25	3.9	24.9	249.7	627.92	
275	25	4.9	24.9	274.6	603.01	
300	25	4.2	24.9	299.6	578.07	
325	25	5.7	24.9	324.5	553.20	
350	25	6.0	24.9	349.3	528.34	
375	25	6.4	24.8	374.2	503.49	
400	25	5.9	24.9	399.0	478.62	
425	25	8.8	24.7	423.7	453.92	
450	25	6.7	24.8	448.6	429.09	
462	12	5.1	12.0	460.5	417.14	

Date Installed: 85-Jul-24  
Well Deviation Survey Date: 85-Jul-29

- Notes:
1. True Vertical Depth and True Vertical Elevation calculations based on closest previous deviation measurement (i.e. for 460', use deviation measured at 450')
  2. Well Construction Data from Emcon, (1985) and site records.
  3. TOC elevations & GW Measurements provided by R. Reed, CWMI
  4. Pump Intake Depth = Pump depth - (TOC - GSE).



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 1 OF  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				0		CLST	SILTY CLAYSTONE; grayish olive (10Y,4/2); 30% silt; 10% very fine sandstone laminae with limonitic staining. 10' with gypsum vining; very poorly indurated.
				5			
				10	(B)		
				15			
				20			

REMARKS Borings K-46 and K-46(RD-1) were plugged and abandoned as a result of swollen claystone beds blocking the passage of PVC casing. Well K-46(RD-2) was located 65 feet east of K-46(RD-1). K-46(RD-2) was drilled with air-rotary drilling equipment to a total depth of 461 feet. During the completion procedures mud-rotary drilling methods were employed. The borehole was converted to a ground-water monitoring well (see Completion Diagram).



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 3 OF 4  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				40	(B)	CLST	SILTY CLAYSTONE (Continued).
				45		SS	
				50	(B)		SANDSTONE; moderate olive-brown (5Y,4/4); 5% silt; very fine-to fine-grained; quartzose; lithic; minor cementation friable to poorly indurated.
				55			
				60			increase of black mica content.

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD.2)  
 PAGE 4 OF 24  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				60	(B)	SS	SANDSTONE (Continued).
				65		SS/ SLST	SANDSTONE and SILTSTONE interbedded, 3:2. sandstone: light olive-brown (5Y, 5/6). siltstone: light olive-brown (5Y, 5/6).
				70	(B)		
				75		CLST SS	CLAYSTONE and SANDSTONE interbedded, 13:7. claystone: light olive-brown (5Y, 5/6). sandstone: light olive-brown (5Y, 5/6) very fine grained.
				80			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD.1)  
 PAGE 5 OF 2  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				80	(B)	CLST SS	CLAYSTONE and SANDSTONE interbedded (Continued).
				85			
				90	(B)	CLST	CLAYSTONE, light olive-gray (5Y, 5/2).
				95		SS	SANDSTONE (Continued on next page).
				100			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD.2)  
 PAGE 6 OF 24  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				100	(B)	SS	SANDSTONE; light olive-brown (5Y, 5/6); 10% silt; fine grained; 15% medium and coarse; 15-20% claystone laminae; minor medium to coarse, dark lithics.
				105			
				110	(B)		20% disseminated silt; 5-10% claystone.
				115		SS/ SLST	
				120			SANDSTONE and SILTSTONE interbedded, 7:3. sandstone: light olive-brown (5Y, 5/6) fine-to medium-grained; quartzose; abundant pelecypod(?) shell fragments; bone(?) fragments. siltstone: olive (10Y, 5/2).

REMARKS





# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 7 OF 4  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				120	(B)	SS/ SLST	SANDSTONE and SILTSTONE interbedded (Continued).  siltstone comprises the major portion of the unit.
				125		CLST	
				130	(B)		CLAYSTONE; moderate olive-brown (5Y, 4/10)
				135			
				140			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-1)  
 PAGE 8 OF 24  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETROMETER (TSF)	PENETRATION (Blows/Ft)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO-GRAPHIC COLUMN	DESCRIPTION
				140	(B)	CLST	CLAYSTONE (Continued).
				145			
				150	(B)		SILTSTONE; olive (10Y, 5/2).
				155		SLST	
				160			

REMARKS





# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33

BORING NO. K-46(RD-2)

PROJECT NAME Kettleman Hills

PAGE 10 OF 24

BY MAC, BB DATE 10/9 - 10/10/85

SURFACE ELEV. 871.30'  
M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				180	(B)	SLST /SS	SILTSTONE and SANDSTONE interbedded (Continued).
				185		SLST	SANDY SILTSTONE; olive (10Y, 5/2).
				190	(B)		
				195			
				200			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RP :  
 PAGE 11 OF L.  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				200	(B)	SLST ✓	SANDY SILTSTONE (Continued).
				205			
				210	(B)		
				215			
				220			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 12 OF 24  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				220	(B)	SLST	SANDY SILTSTONE (Continued).
				225		SS	SILTY SANDSTONE; light olive-brown (5Y, 5/6); 20% silt; fine-to medium-grained; quartzose; lithic; poorly graded.
				230	(B)		
				235			
				240		SLST	SILTSTONE; grayish olive (10Y, 4/2); < 5% very fine sand; occasional limonitic staining.

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 13 OF  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				240	(B)	SLST	SILTSTONE (Continued).
				245		CLST/ SLST	
				250	(B)		
				255			
				260			

CLAYSTONE and SILTSTONE interbedded.  
 10% limonitic, very fine sandstone  
 laminae.

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 14 OF 24  
 SURFACE ELEV. 871.30'  
 M.S.E.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				260	(B)	CLST /SLS	CLAYSTONE and SILTSTONE interbedded (Continued).
				265		CLST /SS	CLAYSTONE and SANDSTONE interbedded.
				270	(B)	SS/ SLST	SANDSTONE and SILTSTONE interbedded, 3:2. sandstone: light olive-brown (5Y, 5/6); fine-to medium- grained; quartzose; lithic. siltstone: grayish olive (10Y, 4/2).
				275			
				280			

REMARKS





# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 15 OF .  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				280	(B)	SS/ SLST	SANDSTONE and SILTSTONE interbedded (Continued).
				285		SLST/ CLST	
				290	(B)		SILTSTONE and CLAYSTONE interbedded, 3:2. siltstone: light olive-gray (5Y, 5/2). claystone: greenish black (5GY, 2/1).
				295			harder drilling.
				300			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 16 OF 24  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				300	(B)	SLST/ CLST	SILTSTONE and CLAYSTONE interbedded (Continued).
				305		SS	
				310	(B)		CLAYEY SANDSTONE; light olive-brown (5Y, 5/6); 20-25% clay; very fine grained; quartzose; poorly graded.
				315		SS/ CLST	
				320			SANDSTONE and CLAYSTONE interbedded. sandstone: light olive-brown (5Y, 5/6)

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224. 56.33

BORING NO. K-46(RD-)

PROJECT NAME Kettleman Hills

PAGE 17 OF

BY MAC, BB DATE 10/9 - 10/10/85

SURFACE ELEV. 871.30'  
M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				320	(B)	SS/ CLST	SANDSTONE and CLAYSTONE interbedded (Continued).
						CLST	CLAYSTONE; greenish black (5G, 2/1); 10-15% siltstone laminae; 5% very fine sandstone laminae.
				325			
				330	(B)		
				335			
				340			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224- 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 18 OF 24  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				340	(B)	CLST	CLAYSTONE (Continued).
						SS	CLAYEY SANDSTONE; light olive-brown (5Y, 4/4); 15% clay; very fine grained; poorly graded; 10% claystone laminae.
				345		CLST	
				350	(B)		CLAYSTONE; dark greenish gray (5G, 4/1); 15-20% grayish olive (10Y, 4/2) and yellowish brown (5Y, 5/4) siltstone interbeds.
				355			
				360			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC,BB DATE 10/9 - 10/85

BORING NO. K-46(RD-2)  
 PAGE 19 OF 22  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				360	(B)	CLST	CLAYSTONE (Continued).
				365			
				370	(B)		SANDSTONE and CLAYSTONE interbedded, 1:1. sandstone: light olive-brown (5Y, 5/4); very fine-to fine-grained; micaceous; poorly graded. claystone: dark greenish gray (5G, 4/1)
				375		SS/ CLST	
				380			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 20 OF 24  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				380 (B)		SS/ CLST	SANDSTONE and CLAYSTONE interbedded (Continued).
				385		CLST	
				390 (B)			CLAYSTONE; dark greenish gray (5G, 4/1); 5% sand; 10% sandstone laminae; 15-20% siltstone laminae; black organic laminae; pyrite nodules; occasional gypsum veins.
				395			harder drilling.
				400			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 21 OF  
 SURFACE ELEV. 871.30'  
 M. S. L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				400	(B)	CLST	CLAYSTONE (Continued).
				405			harder drilling.
				410	(B)		harder drilling.
				415			harder drilling.
				420			

REMARKS



# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC,BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 22 OF 24  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				420		CLST	<p>CLAYSTONE (Continued).                      @ 420': color change to greenish black (5GY, 2/1); 40% fine to medium, quartzose, 50% lithics, moderate to well graded, angular to subangular sand, moderately bioturbated; minor slickensides; abundant <i>Mya</i>; poorly indurated; damp.</p> <p>SANDY SILTSTONE; dark greenish gray (5G, 4/1); 20% very fine sand.</p> <p>SILTSTONE and SANDSTONE interbedded, 1:1.                      siltstone: dark greenish gray (5G, 4/1) very thinly laminated; well indurated.                      sandstone: medium light gray (N6); very fine grained; very thinly laminated.</p> <p>@ 431.5': SLST:SS = 7:3.                      siltstone: medium dark gray (N4); poorly indurated.                      sandstone: medium gray (N5); occasional organic fragments; rare pyrite nodules.</p> <p>@ 433'. brownish black (5YR, 2/1) to black (N1) organic laminae.</p> <p>@ 440'-442': low degree of slumping.</p>
				CORE BOX 1 REC. 5.0'		SLST	
				425		SLST /SS	
				CORE BOX 2 REC. 5.0'			
				430			
				CORE BOX 3 REC. 5.0'			
				435			
				CORE BOX 4 REC. 4.5'			
				440			

REMARKS The borehole was continuously cored from 420 - to 461 - feet.





# LOG OF EXPLORATORY BORING

PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 23 OF .  
 SURFACE ELEV. 871.30'  
 M.S.I.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ FL)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				440		SLST /SS	SILTSTONE and SANDSTONE interbedded (Continued). @ 441': decrease of sandstone portion.
				CORE BOX 5			
			▽	445		SS	CLAYEY SANDSTONE; dark greenish gray (5GY, 4/1); ≤20% clay; medium-to coarse-grained; quartzose; moderate to well graded; subangular to subrounded; massive; occasional cement, calcareous; poorly indurated; moist. @ 445': harder drilling.
			REC. 5.0'	CORE BOX 6	(P)		
				450			@ 449'-450': minor sandy claystone interbeds.
				CORE BOX 7			
				455			@ 451'-452' occasional organic laminae and fragments.  @ 452.5': change of grain size to fine to medium.
				CORE BOX 8			
				460		SLST	@ 455': very poorly indurated; minor friable sandstone. @ 456': 1.0"-thick siltstone interbeds.
				CORE BOX 8			
				460			SILTSTONE; dark greenish gray (5GY, 4/1). very fine silty sandstone to sandy siltstone interbeds with 60% silt and clay; organic laminae. @ 459.5': 10% silty sandstone to sandy siltstone interbeds.
				REC. 5.0'	(P)		
				460			
				REC. 5.0'	(P)		



REMARKS (P) denotes a 5-to 6-inch preserved sample.



# LOG OF EXPLORATORY BORING


PROJECT NUMBER 224 - 56.33  
 PROJECT NAME Kettleman Hills  
 BY MAC, BB DATE 10/9 - 10/10/85

BORING NO. K-46(RD-2)  
 PAGE 24 OF 24  
 SURFACE ELEV. 871.30'  
 M.S.L.

TORVANE (TSF)	POCKET PENETRO- METER (TSF)	PENETRA- TION (Blows/ Ft.)	GROUND WATER LEVELS	DEPTH IN FT.	SAMPLES	LITHO- GRAPHIC COLUMN	DESCRIPTION
				460	SLST		SILTSTONE (Continued).
				465			 TERMINATED BORING AT 461'.
				470			
				475			
				480			

REMARKS





**EMCON**  
Associates

San Jose, California

CHEMICAL WASTE MANAGEMENT, INC.  
KETTLEMAN HILLS FACILITY  
KINGS COUNTY, CALIFORNIA

K-46 (RD-2) WELL COMPLETION DIAGRAM

FIGURE

PROJECT NO.  
224-56.33

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

Log of Boring 17-2  
 Sheet 1 of 10

Date(s) Drilled	10/30/02 - 11/4/02	Logged By	M. McKenzie	Checked By (Date)	M. Hatch
Drilling Method	Air Rotary	Drill Bit Size/Type	5" cutting bit	Total Depth Drilled (feet)	150.0
Drill Rig Type	TH-60	Drilling Contractor	PC Exploration	Approximate Surface Elevation	868
Groundwater Level	Not encountered	Location		Inclination from Horizontal/Bearing	90°
Borehole Completion	Bentonite grout			Hammer Data	NA

Elevation, feet	Depth, feet	ROCK CORE						Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTE AND LAB TESTS	
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %	Fracture Drawing Number			Type	Number	Blows /12 in	Recovery, inches		Drill Time [Rate, ft/hr]
868	0								HIGHLY SAN JOAQUIN FORMATION Dense, moist, light brown becoming brown, sandy SILT (ML), highly weathered						
	1														
866	2														
	3														
864	4														
	5														
	6										1			1640	MC=14, SA(90)
862	7											34			
	8														
860	9							SAN JOAQUIN FORMATION Silty CLAYSTONE (CH), olive brown, soft, highly to moderately weathered grading to clayey SILTSTONE (ML) locally							
	10														
858	11														
	12										2			1648	MC=18
856	13											65			

Report: GEO CO. \_OIL\_ 17B; File: 2764461.GPJ; 1/22/2003 17-2

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

## Log of Boring 17-2

Sheet 2 of 10

Elevation, feet	Depth, feet	ROCK CORE							Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTE AND LAB TEST	
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %	Fracture Drawing Number	Type			Number	Blows /12 in	Recovery, inches	Drill Time [Rate, ft/hr]		
13																
854	14															
	15															
852	16															
	17															
850	18															
	19															
848	20															
	21															
846	22	1	1	40												
	23															
844	24															
	25															
842	26															
	27															
840	28	2	1	100	0											
	29				0											

Report: GEO\_CORE+SOIL\_17B; File: 27644618.GPJ; 1/22/2003 17-2

Silty to clayey SANDSTONE (SM/SC) and sandy SILTSTONE (ML), light olive gray, interbedded, soft, highly to moderately weathered

CLAYSTONE (CL), grayish brown with reddish brown mottled zones, laminated

Silty sandstone, gray



Figure A-3

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

## Log of Boring 17-2

Sheet 3 of 10

Elevation, feet	Depth, feet	ROCK CORE					Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES			FIELD NOTES AND LAB TESTS	
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %			Fracture Drawing Number	Type	Number		Blows /12 in Recovery, inches
838	29				0								
	30											0740	
	31						Silty sandstone					0744	
836	32	3	1	80			Silty SANDSTONE (SM), light grayish brown, soft, highly to moderately weathered					[60]	
	33												
834	34												
	35						Sandy SILTSTONE (ML), brownish gray to olive gray with reddish brown zones, highly weathered locally					0749	
832	36		1		2		1: 25-30°, B, Vn, Sd, Su, Pl, S						
	37												
830	38	4		76	1				5A			[60]	
	39				1								
828	40				1		1: 30°, B, Vn, Cl, Su, Pl, S					0758	
	41				1		Silty sandstone					0805	
826	42	5	2	100	2							[43]	
	43				1		Lighter color						
824	44				0								
	45											0812	

Report: GEO COR...SOIL 17B: File: 2764461.GPJ: 1/22/2003 17-2

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

Log of Boring 17-2  
 Sheet 4 of 10

Elevation, feet	Depth, feet	ROCK CORE						Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTES AND LAB TESTS	
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %	Fracture Drawing Number			Type	Number	Blows /12 in	Recovery, inches		Drill Time [Rate, f/hr]
45					0									0816	
822	46				1			1: 30°, B, Vn, Cl, Su, Pl, Sr							
	47	6	2	86	0			Silty SANDSTONE (SM), light brownish gray, soft, moderately weathered						[60]	
820	48				0										
	49														
818	50				0									0821	
	51													0826	
	52	2			1			√ Slightly darker color							
816	53	7		86	2			1: 30°, B, Vn, Sd, Su, Pl, S	X	6			[100]	MC=7	
	54		3					2: 30° B, Vn, Cl, Su, Pl, S SILTSTONE (ML), brownish gray, soft, highly to moderately weathered, laminated and thinly bedded with sandstone layers							
	55				2									0829	
	56				0			1: 30°, B, Vn, CL, Su, Pl, S	X	7				0835	MC=17
812	57														
	58	8	3	80	2			2: 30°, B, Mw, Sd, Fi, Pl, S, 1/2" sandstone layer					[50]		
	59				2										
808	60				0									0841	
	61													0851	

Report: GEO\_CORE+SOIL\_17B; File: 27644618.GPJ; 1/22/2003 17-2

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

### Log of Boring 17-2

Sheet 5 of 10

Elevation, feet	Depth, feet	ROCK CORE						Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTES AND LAB TESTS	
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %	Fracture Drawing Number			Type	Number	Blows /12 in	Recovery, inches		Drill Time [Rate, ft/hr]
61					0										
806	62	9	3	76	0									[100]	
	63				0			Silty SANDSTONE (SM), olive gray, soft, highly weathered							
804	64														
	65				0			Silty SANDSTONE (SM), light brownish gray, soft, moderately weathered						0854	
802	66													0859	
	67													[100]	
800	68	10	3	16			NR								
	69														
798	70				0									0902	
	71		3		0									0907	
796	72														
	73	11		50	0									[100]	
	74						NR								
794	75				0									0910	
	76				1			CLAYSTONE (CL), brownish gray, soft, laminated with lesser sandstone 1: 30°, B, Vn, Sd, Su, Pl, Sr						0913	
792	77														

Report: GEO\_CORE+SOIL\_17B; File: 2764461.GPJ; 1/22/2003 17:2



Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

Log of Boring 17-2

Sheet 6 of 10

Elevation, feet	Depth, feet	ROCK CORE					Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOT AND LAB TE	
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %			Fracture Drawing Number	Type	Number	Blows /12 in		Recovery, inches
77														
	77	12		90	2								[43]	
-790	78		3		2									
	79		4		1									
-788	80				0			Silty SANDSTONE (SM), gray, soft, moderately weathered					0920	
	81				0								0929	
-786	82		4		0									
	83	13		100	0								[50]	
	84				1			1: 30°, B, Vn, Sd, Su, Pl, S						
	85				0								0935	
	86				0								0941	
-782	87		4		0									
	88	14		80	0								[43]	
-780	89				0									
	90				0								0948	
	91				0								0952	
-776	92		4		0			Sandy SILTSTONE (ML), gray, moderately soft to soft, moderately weathered						
	93	15		60	0								[43]	

Report: GEO CORE+SOIL 17B; File: 27644618.GPJ; 1/22/2003, 17-2

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

Log of Boring 17-2

Sheet 7 of 10

Elevation, feet	Depth, feet	ROCK CORE					Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTES AND LAB TESTS	
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %			Fracture Drawing Number	Type	Number	Blows / 12 in Recovery, inches		Drill Time [Rate, ft/hr]
93														
774	94		4				NR							
	95												0959	
	96		4	0				Sandy SILTSTONE (ML), olive gray with iron staining, moderately soft, moderately weathered						
772	96		5		2									
	97													
	98	16		42	1		NR							
770	98													
	99													
768	100				0			Olive brown SILTSTONE (ML), moderately soft, moderately weathered						
	101				0									
766	102		5					Silty CLAYSTONE (CL), dark gray, moderately soft						
	103	17		100	0									
	104				0									
764	104													
	105							Gray SILTSTONE (ML)					1019	
	106							Silty SANDSTONE (SM), reddish brown, soft, friable, thinly bedded and laminated					1024	
762	106													
	107		NR											
	108	NR		NR									[100]	
760	108													
	109													

Report: GEO CL...+SOIL 178; File: 27644618.GPJ; 1/22/2003 17:2

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

Log of Boring 17-2

Sheet 8 of 10

Elevation, feet	Depth, feet	ROCK CORE					Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTES AND LAB TESTS		
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %			Fracture Drawing Number	Type	Number	Blows /12 in		Recovery, inches	Drill Time [Rate, ft/hr]
109															
758	110				0			Silty SANDSTONE (SM), light olive brown, moderately soft						1027	
	111				0									1031	
756	112	19	5	80	4			1: 30°, B, Vn, Sd, Su, Pl, S						[60]	
	113				3			Sandy SILTSTONE (ML), gray, moderately soft to soft							
754	114								10						
	115				2									1036	
752	116				1			1: 25-30°, B, Vn, Sd, Su, Pl, Sr						1042	
	117	20	5	30				Silty SANDSTONE (SM), brownish gray, moderately soft, moderately weathered							
750	118					NR								[75]	
	119														
748	120				2			CLAYSTONE (CH), brownish gray, laminated and thinly bedded						1046	
	121				2									1030	
746	122	21	6	80	3			1: 30°, B, Vn, Cl, Su, Pl, S							
	123													[75]	WA(99)
744	124					NR		Silty SANDSTONE (SM), light gray, soft, friable							
	125													1034	

Report: GEO CORE+SOIL 17B, File: 2764461.GPJ, 1/22/2003 17-2



Figure A-3



Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

### Log of Boring 17-2

Sheet 10 of 10


Elevation, feet	Depth, feet	ROCK CORE						Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES					FIELD NO. AND LAB TEST
		Run No.	Box No.	Recovery, %	Fractures per Foot	RQD, %	Fracture Drawing Number			Type	Number	Blows /12 in	Recovery, inches	Drill Time [Rate, ft/hr]	
141															
-726	142	25	6	70				CLAYSTONE (CL), olive brown, moderately soft, moderately to slightly weathered							
	143													[50]	
-724	144						NR	Silty SANDSTONE (SM), light grayish brown, moderately soft, slightly weathered							
	145													1122	
	146													1131	
-722	147														
	148	26		0											[75]
-720	149														
	150														1135
-718	151							Bottom of Boring at 150 feet							
	152														
-716	153														
	154														
-714	155														
	156														
-712	157														

Report: GEO\_CORE+SOIL\_17B; File: 2764461.GPJ; 1/22/2003 17:2



Figure A-3

Date(s) Drilled	10/29/02	Logged By	M. McKenzie	Checked By (Date)	M. Hatch
Drilling Method	Air Rotary	Drill Bit Size/Type	5" cutting bit	Total Depth Drilled (feet)	140.0
Drill Rig Type	TH-60	Drilling Contractor	PC Exploration	Approximate Surface Elevation	852
Groundwater Level	Not encountered	Location		Inclination from Horizontal/Bearing	90°
Borehole Completion	Bentonite grout			Hammer Data	NA



Report: GEO\_COI...SOIL\_17B; File: 2764461.GPJ; 1/22/2003 17-3



Figure A-4

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

### Log of Boring 17-3

Sheet 2 of 9

Elevation, feet	Depth, feet	ROCK CORE						Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES					FIELD NOTE AND LAB TESTS	
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %	Fracture Drawing Number			Type	Number	Blows /12 in	Recovery, inches	Drill Time (Rate, ft/hr)		
13																
838	14															
	15															
836	16										3	56				
	17															
834	18															
	19										4					
832	20							Sandstone								0740
	21				0			CLAYSTONE (CH), olive gray, laminated								
	22	1	1	50	1			1: 30°, B, Vn, Fe, Su, Pl, S								
830	23							Silty SANDSTONE (SM), gray, weakly cemented, moderately soft								[100]
	24						NR									
828	25							CLAYSTONE (CH), dark olive gray, thinly bedded and laminated with silt and sand laminations								0743
	26				4			1: 30°, B, Vn, Sd, Su, Pl, S								0750
826	27				5			2: 30°, B, N, Gy, Fi, Pl, Sr								
	28	2	1	90	3			3: 42°, J, N30E 4: J horizontal, manganese								
824	29				5			Increasing silt, with sand laminations, light color			5					[75]

Report: GEO\_CORE-SOIL\_17B; File: 27644618.GPJ; 1/22/2003 17-3

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

### Log of Boring 17-3

Sheet 3 of 9

Elevation, feet	Depth, feet	ROCK CORE					Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTE AND LAB TESTS		
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %			Fracture Drawing Number	Type	Number	Blows /12 in		Recovery, inches	Drill Time [Rate, ft/hr]
822	29				5			Silty CLAYSTONE (CH) grading to SILTSTONE (ML), light olive gray							
	30				6			3: 30°, B, Vn, Cl, Su, Pl, S							0754
	31				6			1: 60°, Jn, Vn, Cl, Su, Pl, S							0758
820	32				6			2: 30°, B, Vn, Cl, Su, Pl, S	6						WA(98), LL=83, PI=49
	33	3	1	98	3										[43]
	34				1			3: 30°, B, Vn, Sd, Su, Pl, R Silty sandstone, brown, moderately soft							
818	35				1			4: 30°, B, N, Gy, Fi, Pl, R Claystone, dark gray							0805
	36				5			1: 30°, B, N, Gy, Fe, Pl, R CLAYSTONE (CH), dark olive gray, thinly bedded and laminated, sandstone laminations, decreased silt							0815
816	37				6			2: 30°, B, Vn, Fc, Su, Pl, S							
	38	4	2	95	5			3: 60°, Sh, Vn, Fe, Su, Pl, S							
814	39				6			Increased sand laminations	7						[43]
	40				7			4: 30°, B, Vn, Sd, Su, Pl, Sr							
812	41				>15			Darker color, waxy claystone							0822
	42				6			1: 20-25°, B, Vn, Cl, Su, Pl, Sr							0831
810	43	5	2	100	5			2: 25-30°, B, N, Gy, Fi, Pl, R							
	44				3				8						[43] WA(99), LL=78, PI=48
808	45				7										0838

Report: SED\_CO...\_DIL\_17B; File: 2764461.GPJ; 1/22/2003 17-3



Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

Log of Boring 17-3

Sheet 4 of 9

Elevation, feet	Depth, feet	ROCK CORE					Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTE AND LAB TESTS	
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %			Fracture Drawing Number	Type	Number	Blows /12 in		Recovery, inches
806	45				6			1: 30°, B, Vn, Sd, Su, Pl, Sr					0644	
	46				5			2: 30°, B, Mw, Gy, Fi, Pl, Sr						
804	47	6	2	100	4								[43]	
	48				6			3: 90°, J, Mw, Mn&Gy&Fe, Fi&Pa, Pl, S, N45E						
	49				3									
802	50				6			1: 30°, B, VN, Ct, Su, Pl, S					0851	
	51				5			2: 30°, B, N, Gy, Fi, Pl, Sr					0856	
	52				5			Very dark gray						
800	53	7	3	98	3								[75]	
	54				5									
798	55				2			3: 30°, B, N, Sd, Fi, Pl, R					0900	
	56				4			Becomes dark brown					0906	
796	57				3			2: 40°, B, N, Gy, Fi, Pl, S						
	58	8	3	100	3			3: 30°, B, Vn, Sd, Su, Pl, S					[60]	
794	59				3									
	60				2								0911	
792	61				3			1: 30°, B, Mw, SE, Fi, Pl, R					0920	
								2: 75°, J, Mw, Gy, Fi, Pl, Sr						
								1/2" thick N40W 75 NE						

Report: GEO\_CORE+SOIL\_17B; File: 27644618.GPJ; 1/22/2003 17:3



Figure A-4

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

### Log of Boring 17-3

Sheet 5 of 9

Elevation, feet	Depth, feet	ROCK CORE						Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTES AND LAB TEST
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %	Fracture Drawing Number			Type	Number	Blows /12 in	Recovery, inches	
61					3			← Becomes dark gray						
790	62	9	3	100	2			3: 30°, B, Mw, Gy, Fi, Pl, S	X	10				WA(94)
	63				2									[75]
788	64		4		0									
	65				0									0924
	66				3			1: 30°, B, N, Gy, Fi, Pl, S 2: 30°, B, Vn, Cl, Su, Pl, S						0931
	67				1			← Increased waxy claystone						
784	68	10	4	100	2			3: 60°, J/Sh, waxy surface, clay gypsum, iron 1/32" thick ← Increased sandstone laminations and thin layers, and waxy clay layers	X	11				[60]
	69				7									
782	70				1			Silty CLAYSTONE (CL), gray 1: 30°, B, Vn, Cl, Su, Pl, S						0936
	71				3			2: 30°, B, N, Gy, Fi, Pl, S						0944
780	72				3			← With sandstone layers to 1/2" thick						
	73	11	4	100	1									[100]
	74				1									
778	75				2			Siltstone						0947
	76				0			1: 30°, B, Vn, Sd, Su, Pl, Sr	X	12				0952
	77													

Report: GEO\_CORE-soil\_17B; File: 27644618.GPJ; 1/22/2003 17:3

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

### Log of Boring 17-3

Sheet 7 of 9

Elevation, feet	Depth, feet	ROCK CORE					Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTES AND LAB TEST	
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %			Fracture Drawing Number	Type	Number	Blows /12 in		Recovery, inches
93					1			Grades to silty SANDSTONE (SM)						
758	94													
	95												1050	
													1058	
756	96									15				
	97													
		16	5	80									[60]	
754	98													
	99						NR							
752	100							Sandy SILTSTONE (ML), light olive gray, moderately soft						1100
														1110
	101		5		7			1: 30°, B, Vn, Cl, Su, Pl, S 2: 60°, B, N, Gy, Fl, Wa, Sr 3: 40°, N, N, Gy, Fl, Pl, Sr						
750	102													
		17	6		1									
	103				4									[75] UC(151), DD=103
748	104				1									
	105				0			Sandy CLAYSTONE (CL) gray, moist, moderately soft						1114
														1122
746	106				0									WA(75)
					0									
	107													
		18	6	76	0									[75]
744	108							Silty SANDSTONE (SM), light gray to light brown, moderately soft, moderately weathered						
					0									
	109													

Report: GED\_CORE+SOIL\_17B; File: 2764461.GPJ; 1/22/2003 17-3

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

# Log of Boring 17-3

Sheet 8 of 9

Elevation, feet	Depth, feet	ROCK CORE					Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTES AND LAB TESTS		
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %			Fracture Drawing Number	Type	Number	Blows /12 in		Recovery, inches	Drill Time (Rate, ft/hr)
109					0										
742	110														1126
	111														1132
740	112	19	6	24											[43]
	113					NR									
738	114														
	115						CLAYSTONE (CH), gray, moderately soft, moderately to slightly weathered								1139
	116				1										1143
736	116				4		1: 30°, B, Vn, Cl, Su, Pl, Sr Dark gray color	X	18						
	117														
734	118	20	6	80	0		Olive gray, silty CLAYSTONE (CH)								[60]
	119				2										
	120					NR									1148
732	120		6		0										1152
	121														
	122				2		1: 30°, B, W, Fe, Fi, Pl, Sr 2: 30°, B, Vn, Cl, Su, Pl, S								
730	122	21	7	80	4										[50]
	123						Silty SANDSTONE (SM), olive gray, moderately soft	X	19						
	124				0										
728	124					NR									
	125														1158

Report: GEO COR. - 17B, File: 2764461.GPJ, 1/22/2003 17-3

Project: Kettleman Hills Facility Expansion  
 Project Location: Kettleman City, California  
 Project Number: 27644618.10006

### Log of Boring 17-3

Sheet 9 of 9

Elevation, feet	Depth, feet	ROCK CORE						Lithology	MATERIAL DESCRIPTION	SOIL SAMPLES				FIELD NOTES AND LAB TEST
		Run No.	Box No.	Recovery, %	Fractures per Foot	R Q D, %	Fracture Drawing Number			Type	Number	Blows /12 in	Recovery, inches	
125					0									1203
726	126				2			Silty fine SANDSTONE (SM) with fine sandy siltstone layers 1: 30°, B, Vn, Sd, Su, Pl, Sr						
	127													
724	128	22	7	60	1			Silty SANDSTONE (SM), olive gray, friable	X	20				[75]
	129						NR							
722	130				0			Silty CLAYSTONE (CH), dark gray, moderately soft, slightly weathered						1207
	131				0									1210
720	132							1: 30°, B, Vn, Cl, Su, Pl, Sr	X	21				
	133	23	7	50	1			Silty SANDSTONE (SM), light olive gray, slightly weathered						[37]
718	134						NR							
	135				0									1218
716	136				2			1: 20°, B, Vn, Sd, Su, Pl, Sr						1223
	137													
714	138	24	7	48				Fine SANDSTONE (SP), light olive gray						[60]
	139						NR							
712	140													1228
	141							Bottom of Boring at 140 feet						

Report: GEO\_CORE+SOIL\_17B; File: 2764461.GPJ; 1/22/2003 17:3



Figure A-4



## Attachment 2: Current Field Investigation

**KEY SHEET - CLASSIFICATIONS AND SYMBOLS**

GS FORM:  
KEY 09/99

**EMPIRICAL CORRELATIONS WITH STANDARD PENETRATION RESISTANCE N VALUES \***

	N VALUE * (BLOWS/FT)	CONSISTENCY	UNCONFINED COMPRESSIVE STRENGTH (TONS/SQ FT)		N VALUE * (BLOWS/FT)	RELATIVE DENSITY
<b>FINE GRAINED SOILS</b>	0 - 2	VERY SOFT	<0.25	<b>COARSE GRAINED SOILS</b>	0 - 4	VERY LOOSE
	3 - 4	SOFT	0.25 - 0.50		5 - 10	LOOSE
	5 - 8	FIRM	0.50 - 1.00		11 - 30	MEDIUM DENSE
	9 - 15	STIFF	1.00 - 2.00		31 - 50	DENSE
	16 - 30	VERY STIFF	2.00 - 4.00		>50	VERY DENSE
	31 - 50	HARD	>4.00			
	>50	VERY HARD				

\* ASTM D 1586; NUMBER OF BLOWS OF 140 POUND HAMMER FALLING 30 INCHES TO DRIVE A 2 IN. O.D., 1.4 IN. I.D. SAMPLER ONE FOOT.

**UNIFIED SOIL CLASSIFICATION AND SYMBOL CHART**

MAJOR DIVISIONS		SYMBOLS	DESCRIPTIONS	
<b>COARSE GRAINED SOILS</b>	GRAVEL AND GRAVELLY SOILS	CLEAN GRAVELS	GW WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES	
		LITTLE OR NO FINES	GP POORLY GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES	
		GRAVELS WITH FINES	GM SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURES	
	MORE THAN 50% OF COARSE FRACTION RETAINED ON NO.4 SIEVE	CLEAN SANDS	LITTLE OR NO FINES	SW WELL GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
			POORLY GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES	SP
		SANDS WITH FINES	SM SILTY SANDS, SAND-SILT MIXTURES	
MORE THAN 50% OF MATERIAL COARSER THAN NO. 200 SIEVE SIZE	SANDS WITH FINES	APPRECIABLE AMOUNT OF FINES	SC CLAYEY SANDS, SAND-CLAY MIXTURES	
<b>FINE GRAINED SOILS</b>	SILTS AND CLAYS	LQUID LIMIT LESS THAN 50	ML INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY	
			CL INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, BANDY CLAYS, SILTY CLAYS, LEAN CLAYS	
			OL ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY	
	SILTS AND CLAYS	LQUID LIMIT GREATER THAN 50	MH INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILT	
			CH INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS	
			OH ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS	
<b>HIGHLY ORGANIC SOILS</b>		PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENT	

NOTE: DUAL SYMBOLS USED FOR BORDERLINE CLASSIFICATIONS


**PARTICLE SIZE IDENTIFICATION**

BOULDERS	>300 mm
COBBLES	75 - 300 mm
GRAVEL: COARSE	19.0 - 75 mm
GRAVEL: FINE	4.75 - 19 mm
SAND: COARSE	2.00 - 4.75 mm
SAND: MEDIUM	0.425 - 2.00 mm
SAND: FINE	0.075 - 0.425 mm
SILT	0.075 - 0.002 mm
CLAY	<0.002 mm

WELL GRADED - HAVING WIDE RANGE OF GRAIN SIZES AND APPRECIABLE AMOUNTS OF ALL INTERMEDIATE PARTICLE SIZES

POORLY GRADED - PREDOMINANTLY ONE GRAIN SIZE, OR HAVING A RANGE OF SIZES WITH SOME INTERMEDIATE SIZES MISSING

**PLASTICITY CHART**



**OTHER MATERIAL SYMBOLS**

Siltstone	Sand
Sandstone	Silt
Siltstone/Claystone	Silty Sand
Claystone	Evaporite
Shale	Artificial Fill
Siltstone/Sandstone	Debris Fill
Conglomerate	Asphalt
Granitic	Concrete

**WELL SYMBOLS**

HYDRATED BENTONITE CHIPS
BENTONITE CEMENT GROUT
FILTER PACK
CONCRETE
NATIVE/SLOUGH
CENTRALIZER

**SAMPLER AND OTHER SYMBOLS**

BULK SAMPLE	Water Level at Time Drilling, or as Shown
CORE SAMPLE	Static Water Level
GRAB SAMPLE	MSL: Mean Sea Level
HAND AUGER	AGS: Above Ground Surface
DRIVE SAMPLE	BGS: Below Ground Surface
GROUNDWATER SAMPLE	BTOC: Below Top of Casing
	HSA: Hollow Stem Auger

GS FORM:  
BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					COMMENTS		
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING		TIME	
1	<b>SAN JOAQUIN FORMATION</b> Dense, moist, light yellowish brown (2.5Y 6/4), FAT CLAY [CH] with fine to very fine sand		854	BULK 1A-1						Bulk Sample from 0-5'	
2											
3											
4											
5					850	1A-1		8/11/20			
6					849						
7					848	BULK 1A-2					
8	Hard, moist, light gray (2.5Y 7/1) to very dark grayish brown (2.5Y 3/2), mottled coloring, FAT CLAY [CH], with thin interbedded laminations of very fine sand, contains iron oxide stain and is cemented locally.		847						Bulk Sample from 5-10'		
9											
10					845						
11					844	1A-2		10/31/43			
12					843						
13					842						
14					841						
15			Becomes SILTY CLAY		840	1A-3		25/50/50			
16					839						
17					838						
18			837								
19			836								
20			835	1A-4		22/50/5"					
21			834								
22			833								
23			832								
24			831								
25	Calcite infilling, increase in silt and fine sand [ML], becomes pale yellow (2.5Y 7/4)		830	1A-5		16/34/39					
26											
27					829						
28					828						
29					827						
30					826						
31	Hard, moist, dark gray (2.5Y 4/1), FAT CLAY [CH], with thin laminations of iron oxide stained silty fine sand.		825	1A-6		61/50/5"					
32											

BORING LOG NO. WELL (STEVE) NO SIG SC0458.GPJ GEOSYNTEC.GDT 1/30/08

CONTRACTOR Layne Christensen      NORTHING  
EQUIPMENT CME-95      EASTING  
DRILL MTHD Hollow Stem Auger      ANGLE Vertical  
DIAMETER 8"      BEARING -----  
LOGGER K. Botelho      REVIEWER A. Greene      PRINTED Jan 30, 08

REMARKS: Located about 50' south and 10' west of K-25

COORDINATE SYSTEM:  
SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS





10875 Rancho Bernardo Rd, Suite 200  
 San Diego, CA 92127  
 Tel: (858) 674-6559  
 Fax: (858) 674-6586

**BORING CS-1A**  
**START DATE Nov 26, 07**  
**FINISH DATE Nov 27, 07**

**SHEET 2 OF 3**  
**ELEVATION 855 FT MSL**

**PROJECT Kettleman Hills Facility**  
**LOCATION Kettleman City**  
**PROJECT NUMBER SC0458-01**

GS FORM:  
 BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					TIME	COMMENTS
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING		
33		[Diagonal Hatching]	822							
34			821							
35	Contains manganese staining locally		820	1A-7	[Symbol]	12/26/50/5"				
36			819							
37			818							
38			817							
39			816							
40			815	1A-8	[Symbol]	17/46/50/4"				
41			814							
42			813							
43			812							
44			811							
45	Decrease in sandy interbeds	810	1A-9	[Symbol]	12/38/50/4"					
46		809								
47		808								
48		807								
49		806								
50		805	1A-10	[Symbol]	22/56/50/3"					
51		804								
52		803								
53		802								
54		801								
55	Becomes yellowish brown (2.5Y 6/2), FAT CLAY [CH] with sand	800	1A-11	[Symbol]	32/50/5"					
56		799								
57		798								
58	Very dense, moist, light yellowish brown (2.5Y 6/2), clayey fine SAND [SC]	797								
59		796							Drilling indicates change at 58'	
60		795	1A-12	[Symbol]	50/50/1"					
61		794								
62	Decrease in silt	793								
63		792								
64		791								

End for the day  
 @16:30 resume  
 drilling following  
 day 11/27/2007 @  
 6:30

Drilling indicates  
 change at 58'

BORING LOG NO WELL (STIEVE) NO SIG SC0458.GPJ GEOSYNTEC.GDT 1/30/08

CONTRACTOR Layne Christensen      NORTHING  
 EQUIPMENT CME-95                      EASTING  
 DRILL MTHD Hollow Stem Auger      ANGLE Vertical  
 DIAMETER 8"                              BEARING -----  
 LOGGER K. Botelho      REVIEWER A. Greene      PRINTED Jan 30, 08

REMARKS: Located about 50' south and 10' west of K-25

COORDINATE SYSTEM:  
 SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS



10875 Rancho Bernardo Rd, Suite 200  
 San Diego, CA 92127  
 Tel: (858) 674-6559  
 Fax: (858) 674-6586

**BORING CS-1A**

**SHEET 3 OF 3**

**START DATE Nov 26, 07**

**ELEVATION 855 FT MSL**

**FINISH DATE Nov 27, 07**

**PROJECT Kettleman Hills Facility**

**LOCATION Kettleman City**

**PROJECT NUMBER SC0458-01**

GS FORM:  
BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					TIME	COMMENTS
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING		
65	Very dense, moist, light yellowish brown (2.5Y 6/2), fine poorly graded SAND [SP] with trace silt		790	1A-13		44/120/4"				Poor recovery added sand catcher to sampler
66			789			110/5"				
Total Depth = 66.5 ft bgs.										

BORING LOG NO WELL (STEVE) NO SIG SC0458.GPJ GEOSNTEC.GDT 1/30/08

CONTRACTOR Layne Christensen      NORTHING  
 EQUIPMENT CME-95                      EASTING  
 DRILL MTHD Hollow Stem Auger      ANGLE Vertical  
 DIAMETER 8"                              BEARING  
 LOGGER K. Botelho      REVIEWER A. Greene      PRINTED Jan 30, 08

REMARKS: Located about 50' south and 10' west of K-25

COORDINATE SYSTEM:  
SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS



10875 Rancho Bernardo Rd, Suite 200  
 San Diego, CA 92127  
 Tel: (858) 674-6559  
 Fax: (858) 674-6586

**BORING CS-1** **SHEET 1 OF 1**  
**START DATE** Nov 26, 07 **ELEVATION** 845 FT MSL  
**FINISH DATE** Nov 26, 07  
**PROJECT** Kettleman Hills Facility  
**LOCATION** Kettleman City  
**PROJECT NUMBER** SC0458-01

GS FORM:  
BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					TIME	COMMENTS	
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING			
1	<b>SAN JOAQUIN FORMATION</b> Soft, moist, light yellowish brown (2.5Y 6/4), FAT CLAY [CH] with trace very fine sand, medium plastic.  Becomes hard  Becomes pale yellow to grayish brown (2.5Y 7/3-5/2), with iron oxide stain and calcite locally, contains fine poorly graded sand laminations.  increase in moisture and slight color change to light olive brown (2.5Y 5/4) Becomes cemented  Total Depth = 21.5 ft bgs.		844	BULK 1-1						Bulk Sample from 0-5'	
2			843								
3			842								
4			841								
5			840								
6			839			1-1		20/14/24			
7			838			BULK 1-2					
8			837								
9			836								
10			835								Bulk Sample from 5-10'
11			834			1-2		17/44/50/5"			
12			833								
13			832								
14			831								
15			830								
16			829			1-3		6/38/50/5"			
17			828								
18			827								
19			826								
20			825								
21			824			1-4		8/40/50/5"			

BORING LOG NO WELL (STEVE) NO SIG SC0458.GPJ GEOSYNTEC.GDT 1/30/08

**CONTRACTOR** Layne Christensen **NORTHING**  
**EQUIPMENT** CME-95 **EASTING**  
**DRILL MTHD** Hollow Stem Auger **ANGLE** Vertical  
**DIAMETER** 8" **BEARING** -----  
**LOGGER** K. Botelho **REVIEWER** A. Greene **PRINTED** Jan 30, 08

**REMARKS:** Located about 85' south and 15' west of K-25  
  
**COORDINATE SYSTEM:**  
 SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS

GS FORM:  
BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					TIME	COMMENTS
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING		
1	<b>SAN JOAQUIN FORMATION</b> Hard, moist, grayish brown (2.5Y 5/2), and bluish black (GLEYS 2.5/10B), FAT CLAY [CH], medium to high plasticity, mottled, iron oxide staining.		874	BULK 2-1						Highly cemented for the first foot of drilling Bulk Sample from 0-5'
2			873							
3			872							
4			871							
5			870							
6	Contains very thin layers of pale yellow (2.5Y 7/3), fine sandy silt layers, cemented, laminations appear to be at angles of about 30°		869	2-1		22/42/20				Bulk Sample from 5-10'
7			868	BULK 2-2						
8			867							
9			866							
10			865							
11			864							
12			863							
13			862							
14			861							
15			860							
16	Becomes very dark gray (2.5Y 3/1), decrease in laminations		859	2-3		17/28/50				
17			858							
18			857							
19			856							
20			855							
21			854	2-4		16/27/50/4"				
22			853							
23			852							
24			851							
25			850							
26	Contains calcite infilling locally		849	2-5		17/35/50/2"				
27			848							
28			847							
29			846							
30			845							
31			844	2-6		24/50/5"				
32			843							

BORING LOG NO WELL (STEVE) NO SIG SC0458.GPJ GEOSINTEC.GDT 1/30/08

**CONTRACTOR** Layne Christensen      **NORTHING**  
**EQUIPMENT** CME-95      **EASTING**  
**DRILL MTHD** Hollow Stem Auger      **ANGLE** Vertical  
**DIAMETER** 8"      **BEARING** -----  
**LOGGER** K. Botelho      **REVIEWER** A. Greene      **PRINTED** Jan 30, 08

**REMARKS:** Located about 10' east and 160' south of K-25

**COORDINATE SYSTEM:**  
SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS

GS FORM:  
BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					TIME	COMMENTS	
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING			
33			842								
34			841								
35			840	2-7		27/50/50/4"					
36			839								
37			838								
38			837								
39			836								
40			835	2-8		38/50/5"					
41	Increase in laminations, contains interbedded silt lenses [CH/MH]			834							
42			833								
43			832								
44			831								
45	Hard, moist, very dark grayish brown (2.5Y 3/2), FAT CLAY [CH], medium to high plasticity, with pale yellow silty laminations, contains calcite infilling and both manganese and iron oxide staining locally.			830	2-9		13/37/50/4"				
46			829								
47		828									
48		827									
49		826									
50	Increasing laminations of pale yellow sandy silt and occasionally fine silty sand.		825	2-10		19/50/5"					
51		824									
52		823									
53		822									
54		821									
55		820	2-11		11/33/50/4"						
56		819									
57		818									
58		817									
59	Becomes dark gray (GLEYS 4/N)	816									
60		815	2-12		26/50/4"						
61		814									
62		813									
63		812									
64		811									

BORING LOG NO WELL (STEVE) NO SIG SC0458.GPJ GEOSYNTEC.GDT 1/30/08

CONTRACTOR Layne Christensen      NORTHING  
EQUIPMENT CME-95                      EASTING  
DRILL MTHD Hollow Stem Auger      ANGLE Vertical  
DIAMETER 8"                              BEARING -----  
LOGGER K. Botelho      REVIEWER A. Greene      PRINTED Jan 30, 08

REMARKS: Located about 10' east and 160' south of K-25

COORDINATE SYSTEM:  
SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS



10875 Rancho Bernardo Rd, Suite 200  
 San Diego, CA 92127  
 Tel: (858) 674-6559  
 Fax: (858) 674-6586

**BORING CS-2**

**SHEET 3 OF 3**

**START DATE Nov 27, 07**

**ELEVATION 875 FT MSL**

**FINISH DATE Nov 27, 07**

**PROJECT Kettleman Hills Facility**

**LOCATION Kettleman City**

**PROJECT NUMBER SC0458-01**

GS FORM:  
BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					COMMENTS
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING	
65	Decrease in laminations		810	2-13		23/37/50/4"			
66			809						
67			808						
68			807						
69			806						
70	Becomes moist, dark gray (GLEY1 4/N), CLAY [CH], medium to high plasticity, laminated with light gray (GLEY1 2/N) fine sandy silt.		805	2-14		8/20/50/5"			
71			804						
72			803						
73			802						
74			801						
75	Contains trace pale yellow silty sand laminations		800	2-15		27/40/50/2"			
76			799						
77			798						
78			797						
79			796						
80			795	2-16		15/50/50/4"			
81	Becomes dark grayish brown (2.5Y 4/2) to olive yellow (2.5Y 6/6), FAT CLAY [CH], fissured.		794						
82			793						
83		792							
84		791							
85	Returns to dark gray (2.5Y 4/1), FAT CLAY [CH]	790	2-17		28/50/5"				
86		789							
87		788							
88		787							
89		786							
90	Very dense, moist, light gray (2.5Y 7/1), fine clayey SAND [SC].	785	2-18		34/50/1"				
91		784							

BORING LOG NO WELL (STEVE) NO SIG SC0458.GPJ GEOSYNTEC.GDT 1/30/08

CONTRACTOR Layne Christensen      NORTHING  
 EQUIPMENT CME-95                      EASTING  
 DRILL MTHD Hollow Stem Auger      ANGLE Vertical  
 DIAMETER 8"                              BEARING -----  
 LOGGER K. Botelho      REVIEWER A. Greene      PRINTED Jan 30, 08

REMARKS: Located about 10' east and 160' south of K-25

COORDINATE SYSTEM:  
 SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS

GS FORM:  
BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					TIME	COMMENTS
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING		
1	<b>SAN JOAQUIN FORMATION</b> Hard, moist, light yellowish brown (2.5Y 6/4), with occasional orange coloring, FAT CLAY(CH), medium plasticity  Becomes pale yellow to orange, cemented  Becomes dark gray		899	BULK TP1-1						
2			898							
3			897							
4			896							
5			895							
6			894							
7			893							
8	Dense, moist, light to dark gray, fine clayey sand with silt (SC)		892						Excavation indicates soil becomes harder	
9			891	BULK TP1-2						
10			890							
Total Depth = 10 ft bgs.										

BORING LOG NO WELL (STEVE)/NO SIG SC0458.GPJ GEOSINTEC.GDT 1/30/08

CONTRACTOR Waste Management      NORTHING  
EQUIPMENT CME-95                      EASTING  
DRILL MTHD Back Hoe Test Pit      ANGLE Vertical  
DIAMETER 3' x 8'                        BEARING -----  
LOGGER K. Botelho      REVIEWER A. Greene      PRINTED Jan 30, 08

REMARKS: Located about 50' east of K-46 and 120' north of K-46

COORDINATE SYSTEM:  
SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS



10875 Rancho Bernardo Rd, Suite 200  
 San Diego, CA 92127  
 Tel: (858) 674-6559  
 Fax: (858) 674-6586

**BORING TP-2**  
 START DATE Nov 27, 07  
 FINISH DATE Nov 27, 07

**SHEET 1 OF 1**  
 ELEVATION 900 FT MSL

PROJECT Kettleman Hills Facility  
 LOCATION Kettleman City  
 PROJECT NUMBER SC0458-01

GS FORM:  
 BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					TIME	COMMENTS
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING		
1	<b>SAN JOAQUIN FORMATION</b> Hard, moist, light yellowish brown (2.5Y 6/4), FAT CLAY(CH), medium plasticity		899							Fissured from 1 to 5 feet
2	with pale yellow to orange colorations		898							
3	Becomes cemented		897							
4			896							
5	Appearance of white mineral occasionally along side walls of test pit		895							
6			894							
7			893							
8			892							
9	Becomes light gray, highly cemented		891	BULK TP2-1						
10	Total Depth = 10 ft bgs.		890							

BORING LOG NO WELL (STEVE) NO SIG SC0458.GPJ GEOSYNTEC.GDT 1/30/08

CONTRACTOR Waste Management      NORTHING  
 EQUIPMENT CME-95                      EASTING  
 DRILL MTHD Back Hoe Test Pit      ANGLE Vertical  
 DIAMETER 3' x 10'                      BEARING -----  
 LOGGER K. Botelho      REVIEWER A. Greene      PRINTED Jan 30, 08

REMARKS: Located about 150' east of K-50 and 20' north

COORDINATE SYSTEM:  
 SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS





10875 Rancho Bernardo Rd, Suite 200  
 San Diego, CA 92127  
 Tel: (858) 674-6559  
 Fax: (858) 674-6586

**BORING TP-3**

**SHEET 1 OF 1**

START DATE Nov 27, 07

ELEVATION 870 FT MSL

FINISH DATE Nov 27, 07

PROJECT Kettleman Hills Facility

LOCATION Kettleman City

PROJECT NUMBER SC0458-01

GS FORM:  
BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					TIME	COMMENTS	
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING			
1	<b>SAN JOAQUIN FORMATION</b> Hard, moist, light yellowish brown (2.5Y 6/4), FAT CLAY (CH), medium to high plasticity  Orange coloration  Becomes more cemented  Total Depth = 12 ft bgs.		869								
2			868								
3			867								
4			866								
5			865								
6			864								
7			863								
8			862								
9			861								
10			860								
11			859		BULK TP3-1						
12			858								

BORING LOG NO WELL (STEVE) NO SIG SC0458.GPJ GEOSYNTEC.GDT 1/30/08

CONTRACTOR Waste Management      NORTHING  
 EQUIPMENT CME-95                      EASTING  
 DRILL MTHD Back Hoe Test Pit      ANGLE Vertical  
 DIAMETER 3' x 8'                        BEARING ----  
 LOGGER K. Botelho      REVIEWER A. Greene      PRINTED Jan 30, 08

REMARKS: Located about 30' west of K-46 and 20' north  
  
 COORDINATE SYSTEM:  
 SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS



10875 Rancho Bernardo Rd, Suite 200  
 San Diego, CA 92127  
 Tel: (858) 674-6559  
 Fax: (858) 674-6586

**BORING TP-4**  
**START DATE Nov 27, 07**  
**FINISH DATE Nov 27, 07**

**SHEET 1 OF 1**  
**ELEVATION 895 FT MSL**

**PROJECT Kettleman Hills Facility**  
**LOCATION Kettleman City**  
**PROJECT NUMBER SC0458-01**

GS FORM:  
 BORE 1/99

**BOREHOLE RECORD**

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOLIC LOG	ELEVATION (ft)	SAMPLES					TIME	COMMENTS
				NUMBER	TYPE	BLOW COUNTS	% RECOVERY	PID READING		
1	<b>SAN JOAQUIN FORMATION</b> Hard, moist, light yellowish brown (2.5Y 6/4), FAT CLAY (CH) with yellowish to brown discolorations, highly cemented  Becomes light grayish brown  Total Depth = 10 ft bgs.		894						side walls appear fissured	
2			893							
3			892							
4			891							
5			890							
6			889							
7			888							
8			887							
9			886		BULK TP4-1					
10			885							

BORING LOG NO WELL (STEVE) NO SIG. SC0458.GPJ GEOSYNTEC.GDT 1/30/08

**CONTRACTOR** Waste Management      **NORTHING**  
**EQUIPMENT** CME-95                      **EASTING**  
**DRILL MTHD** Back Hoe Test Pit        **ANGLE** Vertical  
**DIAMETER** 3' x 10'                      **BEARING** ----  
**LOGGER** K. Botelho    **REVIEWER** A. Greene    **PRINTED** Jan 30, 08

**REMARKS:**  
  
**COORDINATE SYSTEM:**  
 SEE KEY SHEET FOR SYMBOLS AND ABBREVIATIONS



## Attachment 3: Laboratory Test Results





**Excel Geotechnical Testing, Inc.**

"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation

Project No: 289


Client Sample ID: CS-1A

Lab Sample No: L103

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CS-1A	L103	122.0	12.5	

Notes:



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation

Project No: 289


Client Sample ID: CS-2

Lab Sample No: L104

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CS-2	L104	113.1	15.6	

Note(s):



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**Project Name:** KHF Clay Source Evaluation  
**Project No:** 289  
**Client Sample ID:** TP-1  
**Lab Sample No:** L105

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID	Lab Sample No	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
TP-1	L105	109.9	17.8	

Notes:



**Excel Geotechnical Testing, inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: TP-2  
 Lab Sample No: L106

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
TP-2	L106	111.7	16.2	

Note(s):





**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: TP-3  
 Lab Sample No: L107

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
TP-3	L107	108.2	17.4	

Note(s):



**Excel Geotechnical Testing, Inc.**  
 "Excellence In Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: TP-4  
 Lab Sample No: L108

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
TP-4	L108	105.5	20.1	

Note(s):



**Excel Geotechnical Testing, Inc.**  
"Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
Project No: 289  
Client Sample ID: TP-1  
Lab Sample No: L105

ASTM C 136, D 422, D 854,  
D 1140, D 2216, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cont.  
Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.8
#20	0.850	99.6
#40	0.425	99.1
#60	0.250	97.8
#100	0.150	95.1
#200	0.075	93.0

Hydrometer Particle Diameter (mm)	% Finer
0.0262	80.8
0.0111	61.4
0.0060	40.2
0.0032	18.0
0.0014	3.5

Gravel (%):	
Sand (%):	7.0
Fines (%):	93.0
Silt (%):	58.5
Clay (%):	34.5

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):	2.65
-----------------------	------



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
TP-1	L105	20.8	93.0	100	37	63	CH - Fat clay

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.

Hydrometer soil specimen conglomerated and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable).



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: TP-2  
 Lab Sample No: L106

ASTM C 136, D 422, D 654,  
 D 1140, D 2216, D 2487, D 4518

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cont.,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	100.0
#20	0.850	99.9
#40	0.425	99.8
#60	0.250	99.8
#100	0.150	99.4
#200	0.075	97.8

Hydrometer Particle Diameter (mm)	% Finer
0.0268	79.7
0.0102	70.3
0.0059	63.7
0.0027	54.3
0.0012	34.4

Gravel (%):	
Sand (%):	2.2
Fines (%):	97.8
Silt (%):	35.0
Clay (%):	62.8

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):	2.65
-----------------------	------



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
TP-2	L106	14.6	97.8	92	31	61	CH - Fat clay

Notes:

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.

Hydrometer soil specimen conglomerated and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable).



**Excel Geotechnical Testing, Inc.**  
"Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
Project No: 289  
Client Sample ID: TP-3  
Lab Sample No: L107

A57M C 136, D 422, D 824,  
D 1540, D 2216, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size Spec. Gravim. Moist. Cont.  
Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	97.9
#4	4.75	97.3
#10	2.00	96.0
#20	0.850	95.4
#40	0.425	94.8
#60	0.250	93.9
#100	0.150	92.5
#200	0.075	91.1

Hydrometer Particle Diameter (mm)	% Finer
0.0270	88.2
0.0101	83.5
0.0052	79.5
0.0026	77.1
0.0011	72.4

Gravel (%)	2.7
Sand (%)	6.2
Fines (%)	91.1
Silt (%)	11.7
Clay (%)	79.4

Coeff. Unif. (Cu)	
Coeff. Curv. (Cc)	

Specific Gravity (-)	2.63
----------------------	------



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
TP-3	L107	21.9	91.1	102	35	67	CH - Fat clay

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.

Hydrometer soil specimen conglomerated and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable).



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 6786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: TP-4  
 Lab Sample No: L108

ASTM C 136, D 422, D 854,  
 D 1140, D 2226, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cont.,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	99.4
#4	4.75	99.0
#10	2.00	97.6
#20	0.850	95.4
#40	0.425	93.6
#60	0.250	91.7
#100	0.150	90.1
#200	0.075	88.5

Hydrometer Particle Diameter (mm)	% Finer
0.0256	86.6
0.0095	85.1
0.0048	83.2
0.0024	81.2
0.0011	64.1

Gravel (%):	1.0
Sand (%):	10.5
Fines (%):	88.5
Silt (%):	5.3
Clay (%):	83.2

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (G <sub>s</sub> ):	2.65
-------------------------------------	------



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
TP-4	L108	17.0	88.5	93	34	59	CH - Fat clay

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.

Hydrometer soil specimen conglomered and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable).



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**Project Name:** KHF Clay Source Evaluation  
**Project No:** 289  
**Client Sample ID:** CS-1-2 & CS-1-3  
**Lab Sample No:** L070 & L071

ASTM C 136, D 422, D 854,  
 D 3180, D 2216, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cons.,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.7
#20	0.850	99.3
#40	0.425	98.4
#60	0.250	96.8
#100	0.150	94.5
#200	0.075	92.2

Hydrometer Particle Diameter (mm)	% Finer
0.0275	86.2
0.0108	73.1
0.0056	64.4
0.0029	56.9
0.0012	54.7

Gravel (%):	
Sand (%):	7.8
Fines (%):	92.2
Silt (%):	29.9
Clay (%):	62.3

Specific Gravity (-):	2.65
-----------------------	------

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	



Client Sample ID	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-1-2 & CS-1-3	L070 & L071	16.0	92.2	100	35	65	CH - Fat clay

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.




**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"  
 941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-1-4  
 Lab Sample No: L072

ASTM C 136, D 422, D 854,  
 D 1148, D2114, D 2487, D 6318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.9
#20	0.850	99.8
#40	0.425	99.2
#60	0.250	98.5
#100	0.150	97.5
#200	0.075	96.0

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	
Sand (%):	4.0
Fines (%):	96.0
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Cuv. (Cc):	

Specific Gravity (-):



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-1-4	L072	18.5	96.0	88	32	56	CH - Fat clay

Note(s):






**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"  
 841 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 950 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-1A  
 Lab Sample No: L103

ASTM C 136, D 422, D 854,  
 D 1140, D 3216, D 2487, D 3318

**SOIL INDEX PROPERTIES**

Grain Size, Sp. Gravity, Moist. Cont.,  
 Unp. Compaction, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	100.0
#20	0.850	99.7
#40	0.425	98.2
#60	0.250	93.2
#100	0.150	84.2
#200	0.075	76.0

Hydrometer Particle Diameter (mm)	% Finer
0.0292	65.9
0.0110	56.8
0.0057	52.1
0.0028	47.6
0.0012	45.4

Gravel (%):	
Sand (%):	24.0
Fines (%):	76.0
Silt (%):	25.0
Clay (%):	51.0

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (G <sub>s</sub> ):	2.65
-------------------------------------	------



Client Sample ID	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-1A	L103	12.4	76.0	55	21	34	CH - Fat clay with sand

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-1A-3  
 Lab Sample No: L075

ASTM C 436, D 422, D 854,  
 D 1149, D2216, D 2487, D4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
 Exp. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	100.0
#20	0.850	99.8
#40	0.425	99.6
#60	0.250	99.5
#100	0.150	99.2
#200	0.075	98.1

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	
Sand (%):	1.9
Fines (%):	98.1
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-1A-3	L075	20.3	98.1	97	44	53	MH - Elastic silt

Note(s):



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-1A-5  
 Lab Sample No: L077

ASTM C136, D 422, D 425,  
 D 1140, D 2216, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cont.,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	100.0
#20	0.850	99.5
#40	0.425	98.9
#60	0.250	98.1
#100	0.150	95.9
#200	0.075	93.3

Hydrometer Particle Diameter (mm)	% Finer
0.0275	86.6
0.0109	70.9
0.0058	56.8
0.0031	37.3
0.0014	16.6

Gravel (%)	
Sand (%)	6.7
Fines (%)	93.3
Silt (%)	41.3
Clay (%)	52.0

Coeff. Unif. (Cu)	
Coeff. Curv. (Cc)	

Specific Gravity (-):	2.65
-----------------------	------



Client Sample ID	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-1A-5	L077	20.9	93.3	105	41	64	CH - Fat clay

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation

Project No: 289


Client Sample ID: CS-1A-6 & CS-1A-7

Lab Sample No: L078 & L079

ASTM C 136, D 422, D 854,  
 D 1540, D 2216, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Char.,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.8
#20	0.850	99.2
#40	0.425	98.4
#60	0.250	95.6
#100	0.150	92.3
#200	0.075	89.6

Hydrometer Particle Diameter (mm)	% Finer
0.0293	82.2
0.0112	70.4
0.0062	43.7
0.0034	4.5
0.0014	2.1

Gravel (%):	
Sand (%):	10.4
Fines (%):	89.6
Silt (%):	76.3
Clay (%):	13.3

Specific Gravity (-):	2.65
-----------------------	------

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	



Client Sample ID	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-1A-6 & CS-1A-7	L078 & L079	23.1	89.6	89	39	50	MH - Elastic silt

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.

Hydrometer soil specimen conglomerated and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable).




**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"  
 941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KRP Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-1A-8  
 Lab Sample No: L080

ASTM C 136, D 422, D 854,  
 D 7540, D2316, D 2487, D4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	100.0
#20	0.850	100.0
#40	0.425	99.8
#60	0.250	98.3
#100	0.150	93.5
#200	0.075	89.5

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%)	
Sand (%)	10.5
Fines (%)	89.5
Silt (%)	
Clay (%)	

Coeff. Unif. (Cu)	
Coeff. Curv. (Cc)	

Specific Gravity (-):



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-1A-8	L080	21.2	89.5	78	31	47	CH - Fat clay

Note(s):



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 660 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation

Project No: 289


Client Sample ID: CS-1A-9

Lab Sample No: L081

ASTM C 136, D 422, D 654,  
 D 1140, D 2226, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cont.  
 Rep. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	98.5
#4	4.75	94.6
#10	2.00	91.3
#20	0.850	90.4
#40	0.425	89.9
#60	0.250	89.4
#100	0.150	88.6
#200	0.075	87.7

Hydrometer Particle Diameter (mm)	% Finer
0.0302	84.0
0.0116	68.5
0.0060	58.0
0.0033	9.7
0.0014	4.9

Gravel (%):	5.4
Sand (%):	6.9
Fines (%):	87.7
Silt (%):	40.5
Clay (%):	47.2

Coeff. Univ. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-): 2.65



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-1A-9	L081	24.4	87.7	82	35	47	CH - Fat clay

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.

Hydrometer soil specimen conglomerrated and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable).




**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"  
 941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-1A-11  
 Lab Sample No: L083

ASTM C 136, D 422, D 854,  
 D 1148, D 3316, D 2487, D-4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cont.,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	98.9
#4	4.75	96.9
#10	2.00	93.5
#20	0.850	91.5
#40	0.425	90.5
#60	0.250	89.2
#100	0.150	86.3
#200	0.075	84.2

Hydrometer Particle Diameter (mm)	% Finer
0.0314	69.5
0.0124	44.2
0.0064	32.9
0.0033	11.2
0.0014	2.8

Gravel (%):	3.1
Sand (%):	12.7
Fines (%):	84.2
Silt (%):	57.5
Clay (%):	26.7

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (G <sub>s</sub> ):	2.65
-------------------------------------	------



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-1A-11	L083	18.6	84.2	58	29	29	CH - Fat clay with sand

Note(s)

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-1A-13  
 Lab Sample No: L085

ASTM C 136, D 423, D 1551,  
 D 1140, D2216, D 2487, D4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	100.0
#20	0.850	99.9
#40	0.425	97.1
#60	0.250	86.7
#100	0.150	39.4
#200	0.075	17.4

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	
Sand (%):	82.6
Fines (%):	17.4
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):	
-----------------------	--



Client Sample ID	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-1A-13	L085	3.4	17.4				

Note(s):





**Excel Geotechnical Testing, Inc.**  
"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation

Project No: 289


Client Sample ID: CS-2

Lab Sample No: L104

ASTM C 136, D 423, D 854,  
D 1148, D 2216, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size Spec., Gravity, Moist. Cont.,  
Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	99.1
#4	4.75	98.6
#10	2.00	98.6
#20	0.850	98.4
#40	0.425	98.1
#60	0.250	97.8
#100	0.150	97.3
#200	0.075	96.3

Hydrometer Particle Diameter (mm)	% Finer
0.0247	91.8
0.0093	87.4
0.0048	84.1
0.0024	80.0
0.0010	73.8

Gravel (%):	1.4
Sand (%):	2.3
Fines (%):	96.3
Silt (%):	11.9
Clay (%):	84.4

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):	2.65
-----------------------	------



Client Sample ID	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-2	L104	14.1	96.3	104	36	68	CH - Fat clay

Notes(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.

Hydrometer soil specimens conglomerated and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable).



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-2-2  
 Lab Sample No: L087

ASTM C 136, D 422, D 854,  
 D 1140, D 2216, D 7487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.1
#20	0.850	98.8
#40	0.425	98.4
#60	0.250	98.0
#100	0.150	97.1
#200	0.075	95.2

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	
Sand (%):	4.8
Fines (%):	95.2
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-2-2	L087	16.5	95.2	100	34	66	CH - Fat clay

Note(s):



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-2-4  
 Lab Sample No: L089

ASTM C 136, D 422, D 854,  
 D 1140, D 2316, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size Spec. Gravity, Minis. Coat,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.9
#20	0.850	99.9
#40	0.425	99.8
#60	0.250	99.7
#100	0.150	99.3
#200	0.075	95.3

Hydrometer Particle Diameter (mm)	% Finer
0.0316	89.2
0.0120	73.0
0.0062	56.8
0.0032	38.6
0.0014	8.9

Gravel (%):	
Sand (%):	4.7
Fines (%):	95.3
Silt (%):	44.7
Clay (%):	50.6

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (G <sub>s</sub> ):	2.65
-------------------------------------	------



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-2-4	L089	21.0	95.3	92	39	53	CH - Fat clay

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.

Hydrometer soil specimen conglomerated and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable).




**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"  
 941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**Project Name:** KHF Clay Source Evaluation  
**Project No:** 289  
**Client Sample ID:** CS-2-7  
**Lab Sample No:** L092

ASTM C 136, D 422, D 854,  
 D 1140, D 2216, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cont.,  
 Seg. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.9
#20	0.850	99.4
#40	0.425	95.9
#60	0.250	92.9
#100	0.150	91.5
#200	0.075	89.8

Hydrometer Particle Diameter (mm)	% Finer
0.0311	84.7
0.0119	68.5
0.0062	53.2
0.0032	37.5
0.0014	8.3

Gravel (%):	
Sand (%):	10.2
Fines (%):	89.8
Silt (%):	39.8
Clay (%):	50.0

Specific Gravity (-):	2.65
-----------------------	------

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	



Client Sample ID	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-2-7	L092	21.0	89.8	93	33	60	CH - Fat clay

Notes:

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.  
 Hydrometer soil specimen conglomerated and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable).



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-2-9  
 Lab Sample No: L094

ASTM C 136, D 432, D 454,  
 D 3140, D 2717, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Grav., Moist. Cont.,  
 Exp. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	99.9
#10	2.00	99.8
#20	0.850	99.7
#40	0.425	99.7
#60	0.250	99.5
#100	0.150	99.3
#200	0.075	98.6

Hydrometer Particle Diameter (mm)	% Finer
0.0309	96.4
0.0118	78.5
0.0061	62.2
0.0032	37.2
0.0014	9.7

Gravel (%):	0.1
Sand (%):	1.3
Fines (%):	98.6
Silt (%):	44.6
Clay (%):	54.0

Specific Gravity (-):	2.65
-----------------------	------

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	



Client Sample ID	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-2-9	L094	24.7	98.6	104	37	67	CH - Fat clay

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.

Hydrometer soil specimen conglomerated and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable).



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation

Project No: 289


Client Sample ID: CS-2-11

Lab Sample No: L095

ASTM C 135, D 422, D 654,  
 D 1140, D 2216, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cont.,  
 Req. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.9
#20	0.850	99.9
#40	0.425	99.6
#60	0.250	99.2
#100	0.150	98.5
#200	0.075	96.7

Hydrometer Particle Diameter (mm)	% Finer
0.0315	90.1
0.0121	68.4
0.0062	53.9
0.0032	35.2
0.0014	9.8

Gravel (%)	
Sand (%)	3.3
Fines (%)	96.7
Silt (%)	47.2
Clay (%)	49.5

Coeff. Unif. (Cu)	
Coeff. Curv. (Cc)	

Specific Gravity (-)	2.65
----------------------	------



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-2-11	L095	24.0	96.7	82	33	49	CH - Fat clay

Note(s):  
 An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.




**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"  
 941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-2-13 & CS-2-14  
 Lab Sample No: L097 & L098

ASTM C 136, D 422, D 854,  
 D 1140, D 2216, D 2487, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cont.,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	100.0
#20	0.850	99.9
#40	0.425	99.9
#60	0.250	99.9
#100	0.150	99.3
#200	0.075	98.4

Hydrometer Particle Diameter (mm)	% Finer
0.0315	91.8
0.0121	69.3
0.0062	57.2
0.0031	43.6
0.0015	28.9

Gravel (%):	
Sand (%):	1.6
Fines (%):	98.4
Silt (%):	47.1
Clay (%):	51.3

Specific Gravity (-):	2.65
-----------------------	------

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-2-13 & CS-2-14	L097 & L098	25.1	98.4	112	40	72	CH - Fat clay

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.

Hydrometer soil specimen conglomerated and formed a cloudy substance which settled to the lower portion of the test tube (i.e., the test results may be questionable)



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: KHF Clay Source Evaluation  
 Project No: 289  
 Client Sample ID: CS-2-16 & CS-2-17  
 Lab Sample No: L100 & L101

ASTM C 136, D 422, D 854,  
 D 1140, D 2316, D 2487, D 418

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Cont.,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.6
#20	0.850	99.1
#40	0.425	98.4
#60	0.250	96.4
#100	0.150	93.1
#200	0.075	91.1

Hydrometer Particle Diameter (mm)	% Finer
0.0307	86.5
0.0116	71.5
0.0060	58.4
0.0030	48.2
0.0015	30.7

Gravel (%):	
Sand (%):	8.9
Fines (%):	91.1
Silt (%):	34.7
Clay (%):	56.4

Specific Gravity (-):	2.65
-----------------------	------

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CS-2-16 & CS-2-17	L100 & L101	25.4	91.1	129	41	88	CH - Fat Clay

Note(s):

An assumed specific gravity of 2.65 was used when analyzing the hydrometer test results.





**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D5084 \***

Project Name:	KHF Clay Source Evaluation
Project Number:	289
Client Name:	Geosyntec Consultants
Site Sample ID:	CS-1A
Lab Sample Number:	L103
Material Type:	Soil
Specified Value (cm/sec):	NA
Date Test Started:	12/21/2007

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity (cm/s)
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
(-)	(pcf)	(% )	(pcf)	(% )	(psi)	(psi)	(psi)	(-)	(-)	(cm/s)
Notes 2, 3 & 4	122.0	12.5	108.0	15.4	75.0	70.0	5.0	DTW	6	9.2E-9

*885010*

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 89% of the maximum dry unit weight and the optimum moisture content plus 3%.
7. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>  
**ASTM D5084 \***

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CS-1A
<b>Lab Sample Number:</b>	L103
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	12/21/2007

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
(-)	(pcf)	(%)	(pcf)	(%)	(psi)	(psi)	(psi)	(-)	(-)	(cm/s)
Notes 2, 3 & 4	122.0	12.5	112.4	15.4	75.0	70.0	5.0	DTW	6	7.4E-9

92.1%

**Notes:**

- Method C, "Falling-Head, Increasing-Tail water" test procedures were followed during the testing.
- All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
- Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
- Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
- Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
- Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 3%.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations.

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D5084 \***

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CS-2
<b>Lab Sample Number:</b>	L104
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	12/21/2007

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity (cm/s)
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
(-)	(pcf)	(%)	(pcf)	(%)	(psi)	(psi)	(psi)	(-)	(-)	(cm/s)
Notes 2, 3 & 4	113.1	15.6	104.0	18.5	75.0	70.0	5.0	DTW	12	3.7E-9

92%

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 3%.
7. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>  
**ASTM D5084 \***

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	TP-1
<b>Lab Sample Number:</b>	L105
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	12/21/2007

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity (cm/s)
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
(-)	(pcf)	(% )	(pcf)	(% )	(psi)	(psi)	(psi)	(-)	(-)	(cm/s)
Notes 2, 3 & 4	109.9	17.8	101.0	20.7	75.0	70.0	5.0	DTW	4	1.1E-8

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
- Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
- Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
- Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
- Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 3%.
- Type of permeant liquid: DTW = Desired Tap Water, DDI = Desired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>  
**ASTM D5084** \*

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	TP-2
<b>Lab Sample Number:</b>	L106
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	12/21/2007

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity
	Max. DUW	Opt. MC	Dry Unit Weight	Moisture Content	Cell Press.	Back Press.	Consolid. Press.	Permeant Liquid <sup>(7)</sup>	Average Gradient	
(-)	(pcf)	(%)	(pcf)	(%)	(psi)	(psi)	(psi)	(-)	(-)	(cm/s)
Notes 2, 3 & 4	111.7	16.2	102.8	19.1	75.0	70.0	5.0	DTW	9	5.0E-9

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 3%.
7. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D5084 \***

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	TP-3
<b>Lab Sample Number:</b>	L107
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	12/21/2007

Remolded Specimen	Proctor <sup>(5)</sup>		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity (cm/s)
	Compaction		Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
	Max. DUW (pcf)	Opt. MC (%)								
(-)										
Notes 2, 3 & 4	108.2	17.4	99.0	20.2	75.0	70.0	5.0	DTW	8	6.5E-9

**Notes:**

1. Method C. "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 3%.
7. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>  
**ASTM D5084** \*

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	TP-4
<b>Lab Sample Number:</b>	L108
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	12/21/2007

Remolded Specimen	Proctor <sup>(5)</sup>		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity (cm/s)
	Compaction		Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
	Max. DUW (pcf)	Opt. MC (%)								
(-)										
Notes 2, 3 & 4	105.5	20.1	97.1	22.9	75.0	70.0	5.0	DTW	4	1.4E-8

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 3%.
7. Type of permeant liquid: DTW = Desired Tap Water, DDI = Desired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>  
**ASTM D5084** \*

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CS1-2 & CS1-3
<b>Lab Sample Number:</b>	L070 & L071
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	1/23/2008

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity  (cm/s)
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
	(-)	(-)	(-)	(-)	(-)	(-)	(-)	(-)	(-)	
Notes 2, 3 & 4	104.0	20.0	93.6	21.9	75.0	70.0	5.0	DTW	14	7.0E-8

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Assumed Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 90% of the maximum dry unit weight and the optimum moisture content plus 2%.
7. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

- Laboratory temperature at 22±3 °C.
- Test specimen final conditions are not presented.





**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>  
**ASTM D5084** \*

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CS1A-5
<b>Lab Sample Number:</b>	L077
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	1/23/2008

Remolded Specimen	Proctor <sup>(5)</sup>		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity  (cm/s)
	Max.	Opt.	Dry Unit	Moisture	Cell	Back	Consolid.	Permeant	Average	
	DUW (pcf)	MC (%)	Weight (pcf)	Content (%)	Press. (psi)	Press. (psi)	Press. (psi)	Liquid <sup>(7)</sup> (-)	Gradient (-)	
(-)										
Notes 2, 3 & 4	104.0	20.0	93.4	21.9	75.0	70.0	5.0	DTW	18	6.2E-8

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Assumed Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 90% of the maximum dry unit weight and the optimum moisture content plus 2%.
7. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>  
**ASTM D5084** \*

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CS1A-6 & CS1A-7
<b>Lab Sample Number:</b>	L07B & L079
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	1/22/2008

Remolded Specimen	Proctor <sup>(5)</sup>		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity
	Max.	Opt.	Dry Unit	Moisture	Cell	Back	Consolid.	Permeant	Average	
	DUW	MC	Weight	Content	Press.	Press.	Press.	Liquid <sup>(7)</sup>	Gradient	
(-)	(pcf)	(%)	(pcf)	(%)	(psi)	(psi)	(psi)	(-)	(-)	(cm/s)
Notes 2, 3 & 4	104.0	20.0	93.5	21.9	75.0	70.0	5.0	DTW	15	9.6E-8

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
- Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
- Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
- Assumed Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
- Based on the target values of 90% of the maximum dry unit weight and the optimum moisture content plus 2%.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D5084 "**

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CS2-4
<b>Lab Sample Number:</b>	L089
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	1/22/2008

Remolded Specimen	Proctor <sup>(5)</sup>		Specimen Initial		Test Conditions					Hydraulic Conductivity
	Compaction		Conditions <sup>(6)</sup>		Cell Press.	Back Press.	Consolid. Press.	Permeant Liquid <sup>(7)</sup>	Average Gradient	
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)						
(-)	104.0	20.0	93.6	21.9	75.0	70.0	5.0	DTW	16	8.6E-8

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Assumed Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 90% of the maximum dry unit weight and the optimum moisture content plus 2%.
7. Type of permeant liquid: DTW = Desired Tap Water, DDI = Desired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.


**Excel Geotechnical Testing, Inc.**
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075

Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>
**ASTM D5084** \*

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CS2-11
<b>Lab Sample Number:</b>	L095
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	1/22/2008

Remolded Specimen	Proctor <sup>(5)</sup>		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity
	Max.	Opt.	Dry Unit	Moisture	Cell	Back	Consolid.	Permeant	Average	
	DUW	MC	Weight	Content	Press.	Press.	Press.	Liquid <sup>(7)</sup>	Gradient	
(-)	(pcf)	(%)	(pcf)	(%)	(psi)	(psi)	(psi)	(-)	(-)	(cm/s)
Notes 2, 3 & 4	104.0	20.0	93.5	21.8	75.0	70.0	5.0	DTW	18	8.2E-8

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
- Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
- Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
- Assumed Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
- Based on the target values of 90% of the maximum dry unit weight and the optimum moisture content plus 2%.
- Type of permeant liquid: DTW = Desired Tap Water, DDI = Desired Deionized Water

**\* Deviations:**

Laboratory temperature at 22±3 °C.

Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>  
**ASTM D5084** \*

<b>Project Name:</b>	KHF Clay Source Evaluation
<b>Project Number:</b>	289
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CS2-13 & CS2-14
<b>Lab Sample Number:</b>	L097 & L098
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	1/22/2008

Remolded Specimen	Proctor <sup>(5)</sup>		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity (cm/s)
	Compaction		Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
	Max. DUW (pcf)	Opt. MC (%)								
(-)										
Notes 2, 3 & 4	104.0	20.0	93.4	22.0	75.0	70.0	5.0	DTW	16	1.7E-8

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Assumed Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 90% of the maximum dry unit weight and the optimum moisture content plus 2%.
7. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Desired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>  
**ASTM D5084** \*

Project Name:	KHF Clay Source Evaluation
Project Number:	289
Client Name:	Geosyntec Consultants
Site Sample ID:	CS2-16 & CS2-17
Lab Sample Number:	L100 & L101
Material Type:	Soil
Specified Value (cm/sec):	NA
Date Test Started:	1/22/2008

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
(-)										
Notes 2, 3 & 4	104.0	20.0	93.5	21.9	75.0	70.0	5.0	DTW	15	5.3E-8

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
- Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
- Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height. *Modified*
- Maximum Dry Unit Weight (DCW) and Optimum Moisture Content (MC) based on Standard Proctor Compaction Test (ASTM D:698). *1557*
- Based on the target values of 95% of the maximum dry unit weight and the optimum moisture content plus 2%.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water *90*

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.

**APPENDIX E.3**  
**CLAY STOCKPILE AND TEST PAD REPORT**



*Prepared for*

**Chemical Waste Management, Inc.**  
35251 Old Skyline Road  
Kettleman City, CA 92139

# **CLAY STOCKPILE AND TEST PAD REPORT**

## **KETTLEMAN HILLS FACILITY KINGS COUNTY, CALIFORNIA**

*Prepared by*

**Geosyntec**   
consultants

engineers | [scientists](#) | [innovators](#)

3990 Old Town Avenue, Suite B101  
San Diego, California 92110

Project Number SC0472

December 2008





**TABLE OF CONTENTS (continued)**

	<b><u>Page</u></b>
5.5.3 Soil Suction.....	14
5.5.4 Hydraulic Conductivity .....	15
5.5.5 Laboratory Data and Comparison to Field Data.....	15
<b>6. SUMMARY AND CONCLUSIONS.....</b>	<b>17</b>
<b>REFERENCES .....</b>	<b>18</b>

**TABLE OF CONTENTS (continued)**

**TABLES**

- Table 1 Clay Stockpile Testing Frequencies
- Table 2 Clay Test Pad Testing Frequencies
- Table 3 SDRI Measurements
- Table 4 Comparison of Current and Previous Laboratory Test Results of Pecten Claystone

**FIGURES**

- Figure 1 Site Plan
- Figure 2 SDRI Test Setup
- Figure 3 SDRI Infiltration Rate and Recorded Swell
- Figure 4 Moisture Content versus Depth below SDRI Inner Ring

**APPENDICES**

- A. Project Documents
  - A-1 Project Specifications – Section 02220
  - A-2 CQA Plan - Addendum 1
- B. Construction Documentation
  - B-1 Photo Log
  - B-2 Compaction Equipment Specification Sheet
- C. Clay Stockpile and Test Pad Results
  - C-1 Laboratory Test Summary Table and Results
  - C-2 Test Pad Compaction Test Results
- D. SDRI Test Results

**CLAY STOCKPILE AND TEST PAD REPORT  
KETTLEMAN HILLS FACILITY  
KINGS COUNTY, CALIFORNIA**

I certify that this document and attachments presented in this report are accurate and complete. This report was prepared by the staff of Geosyntec Consultants under my supervision to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who are directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete.

*Jane Soule*

Jane Soule

California Professional Civil Engineer No. 59815

10/20/09  
Date



## 1. INTRODUCTION

### 1.1 Terms of Reference

This report presents the results of the clay stockpile and test pad evaluation for Chemical Waste Management, Inc. (CWMI) at the Kettleman Hills Facility in Kings County, California. This report was prepared by Ms. Jane Soule, G.E., and has been reviewed by Mr. Michael J. Minch, G.E., of Geosyntec Consultants, Inc. (Geosyntec), in accordance with the peer review policies of the firm.

### 1.2 Project Description

The Kettleman Hills Facility is approximately 1,600 acres with approximately 474 acres within the active operation area. The site is located in Kings County, California and is owned and operated by CWMI. Three waste management units are currently permitted and operated at the site, Landfill B-17 (Class II/III), Landfill B-19 (II/III) and Landfill B-18 (Class I/II). The planned expansion of Landfill B-18 will require construction of compacted clay liner (CCL) meeting the requirements of Subtitle C of Title 40 of the Code of Federal Requirements (CFR) §264.301 and California Code of Regulations (CCR), Title 23 §2541. These regulations specify that the CCL meet the following requirements:

- an in-situ (field) hydraulic conductivity no greater than  $1 \times 10^{-7}$  centimeters per second (cm/s);
- at least 30 percent of the material, by weight, shall pass a No. 200 U.S. Standard Sieve (0.075 mm); and
- be fine grained soil with a significant clay content without organic matter, in the "SC" (clayey sand), "CL" (clay, sandy or silty clay) or "CH" (clay, sandy clay) classes of the Unified Soil Classification System (USCS).

An onsite clay source was identified on the eastern boundaries of the Landfill B-17 project area (see Figure 1). The potential clay source is part of the Pecten claystone which has been used as a CCL for previous hazardous landfill liner construction projects at the site and has been demonstrated to meet the regulatory requirements. Previous clay investigations and testing programs on the Pecten claystone are summarized in the following reports:

- Environmental Construction Services (ECS), 1991, "Clay Source Report, Landfill B-18, Phases IA and IB, Kettleman Hills Facility, Kettleman City, California, Prepared for Chemical Waste Management, Inc., 25 November 1991.

- Environmental Solutions, Inc. (ESI), 1992, "Test Fill and Infiltrometer Test Results, Landfill B-18 Phases I and II and Final Closure," Prepared for Chemical Waste Management, Inc., 23 January 1992.
- Golder Construction Services (GSC), 1993, "Landfill B-18, Phases IIA and IIB Construction Reports Volume 1 – Clay Liner Source Report," Prepared for Chemical Waste Management, Inc., May 1993.

.These previous investigations are summarized in Section 2 of this report.

During the recent construction of Landfill B-17 Phase A1, approximately 24,000 cubic yards (cy) of soil from the Pecten claystone located northeast of Landfill B-17 Phase A1 was excavated and stockpiled for future use in construction of a CCL for the proposed Landfill B-18 expansion. Material from the stockpile was used to construct a test pad for field hydraulic conductivity testing. The requirements of the test pad construction are summarized in the project specifications Section 02220 (Geosyntec, 2007, see Appendix A-1). Construction quality assurance (CQA) testing requirements for the clay stockpile and test pad are summarized in the CQA Plan, Addendum 1 (Geosyntec, 2008, see Appendix A-2). Appendix B contains photographic documentation detailing activities during test pad construction and testing.

### **1.3 Purpose and Scope of Work**

The purpose of this report is to document the method and equipment used during construction of the test pad as a minimum basis for future construction, that the test pad was constructed in accordance with the project specifications, and to evaluate whether the soil from the identified clay source meets the regulatory requirements for a CCL. Geosyntec's scope of work included the following tasks:

- Visual observation and laboratory testing of the clay excavation and stockpiling;
- Observing and documenting construction of the test pad;
- Performing in-place density and moisture content testing of the clay test pad;
- Laboratory testing of the clay test pad; and
- Providing, installing, and monitoring a sealed double-ring infiltrometer (SDRI) test on the clay test pad.

Geosyntec's services also included preparation of this CQA report summarizing the results of field observations and laboratory data.

## 2. PREVIOUS ONSITE CLAY EVALUATIONS

Previous clay source evaluations have been performed at the Kettleman Hills Facility for CCLs in Landfill B-18. Geosyntec has reviewed available reports on these activities. A summary of these reports is provided below.

Material was excavated onsite from the Pecten claystone for use in the Phase I and II clay liner for Landfill B-18. Field and laboratory testing from a SDRI test, site source evaluation and liner construction was reviewed (ESI, 1992; ECS, 1991; and GSC, 1993). These reports indicate that the clay material used in construction of the Phase I and II compacted clay liners had the following properties:

- Unified Soil Classification System description as a fat clay (CH) with an average of more than 80 percent or greater passing the No. 200 sieve (ranging from 48-94 percent);
- High swell potential (ESI reported an average swell of 16.5 percent under a low confining pressure);
- Average Liquid Limit (LL) of approximately 76 (ranging from 35 to 90) and an average Plasticity Index (PI) of approximately 55 (ranging from 18 to 68);
- Laboratory hydraulic conductivity ranging from approximately  $2 \times 10^{-10}$  centimeters/second (cm/s) to  $2 \times 10^{-7}$  cm/s with an average on the order of  $8 \times 10^{-9}$  cm/s.

These reports indicate that the Pecten claystone material, when compacted to greater than 90 percent of the maximum dry density per ASTM D1557 at a moisture content between +2% and +5% of the optimum moisture content, has a laboratory and field hydraulic conductivity less than  $1 \times 10^{-7}$  cm/s.

### 3. CLAY STOCKPILE

#### 3.1 General

Clay material was excavated and stockpiled during July and August 2008 by Wood Brothers, Inc., (WBI). The clay material was excavated from the Pecten claystone located northeast of the Landfill B-17 area (see Figure 1). An engineering geologist from Geosyntec identified the limits of the claystone in the field with WBI prior to excavation. WBI stockpiled the low-permeability soil north of Landfill B-17 Phase A1 as approved by CWMI. Geosyntec monitored the excavation and performed conformance tests on the low-permeability soil as described in the following sections.

#### 3.2 Stockpile Activities – CQA Monitoring

Geosyntec monitored that the borrow and stockpile areas were cleared and grubbed prior to excavation. Geosyntec personnel documented the activities during the clay soil excavation and stockpiling, and observed that material placed in the clay stockpile did not contain significant quantities of sandy soils or other unsuitable material.

#### 3.3 Clay Stockpile Pre-Construction Activities – CQA Testing

The project specifications (Appendix A-1) require that the material to be placed in the clay stockpile meet the following specifications:

- Free of debris, rocks, gravel greater than 1 inch in any direction and other deleterious material;
- At least 30 percent of the material, by weight, shall pass the No. 200 sieve;
- Be classified as CL, SC, or CH in accordance with ASTM D2487; and
- Have a compacted field hydraulic conductivity of less than or equal to  $1 \times 10^{-7}$  cm/sec<sup>1</sup>.

As the soil was excavated, Geosyntec collected representative samples and shipped them to Excel Geotechnical Testing (Excel) for laboratory testing in accordance with the CQA Plan. The following CQA tests were performed, at a minimum frequency of 1

---

<sup>1</sup> Field hydraulic conductivity of soils was evaluated using the SDRI (see Section 5).



per 5,000 cubic yards (cy), to evaluate compliance of the clay stockpile with the requirements specified for the clay source material:

- Moisture-Density Relationship (ASTM D 1557);
- Sieve Analysis (ASTM D 422);
- Atterberg Limits (ASTM D 4318);
- Classification (ASTM D 2487); and
- Hydraulic Conductivity (ASTM D 5084), remolded sample.

The required testing frequencies are presented in Table 2.

The moisture-density relationship (modified Proctor) testing results (ASTM D 1557), documented in Appendix C-1, indicate that the low-permeability soil had a maximum dry unit weight ranging from approximately 106 to 120 pcf with an optimum moisture content varying from approximately 13 to 18 percent.

Atterberg limits (ASTM D 4318) testing performed on the clay stockpile is documented in Appendix C-1. Results of this testing indicate a Liquid Limit (LL) varying from 61 to 110 percent and a Plasticity Index (PI) ranging from 38 to 69 percent. The sieve analysis (ASTM D 422) test results indicate that the low-permeability soil had a fines content ranging from 74 to 94 percent. These tests cited above indicate that the soil is classified as fat clay (CH) according to ASTM D 2487 soil classifications.

As required by the technical specification, Geosyntec obtained bulk samples of the clay stockpile at the specified frequency for hydraulic conductivity testing (ASTM D 5084). The samples were compacted to a minimum of 92 percent relative compaction with moisture contents ranging from 2 to 5 percent wet of the optimum moisture content. Hydraulic conductivity test results ranged from  $2 \times 10^{-8}$  to  $9 \times 10^{-8}$  cm/s. The hydraulic conductivity test results are presented in Appendix C-1.

## **4. CLAY TEST PAD CONSTRUCTION**

### **4.1 Overview**

CQA testing was performed during the construction of the clay test pad by using methods and frequencies specified in the Project Documents, as presented in Table 2. Laboratory and field test results performed on the clay stockpile and test pad are included in Appendix C. Appendix B contains photographic documentation detailing activities during test pad construction and testing.

### **4.2 Clay Liner Test Pad Construction**

#### **4.2.1 General**

The construction of the clay test pad began on 28 July 2008 and was completed on 7 August 2008. The test pad was constructed approximately 50 feet wide by 50 feet long and consisted of six 6-in lifts. Observations and testing conducted on the clay liner test pad by Geosyntec are described in the following sections. SDRI testing is described in Section 5.

#### **4.2.2 Test Pad Construction**

Geosyntec CQA personnel continuously monitored activities performed prior to and during construction of the clay test pad. CQA monitoring activities performed during clay test pad construction included monitoring of processed material placement, measurement of lift thickness, documentation of the number of passes performed by compaction equipment, and a visual assessment of incoming soil. The following sections describe construction test pad.

##### **4.2.2.1 Site Preparation**

Prior to construction of the test pad, the area was cleared and grubbed. The subgrade was then proof-rolled to eliminate soft zones, irregularities, and abrupt changes in grade. The subgrade was graded to slope a grade of approximately 2 to 3 percent to provide positive drainage.

##### **4.2.2.2 Stockpile Material Processing**

WBI moisture conditioned the clay in the stockpile prior to placement in lifts for the test pad. Moisture conditioning typically included applying water to the surface with a water truck. Due to cementation in the formational soil, significant quantities of oversize particles were present in the stockpile. Further, due to the high plasticity of the clay material, significant clods were present upon wetting. The material was processed in the stockpile to reduce particle/clod size by mixing using a tractor with a rotary disc

and a bushog<sup>2</sup>. In addition, one to three laborers were present to manually remove oversize particles.

#### 4.2.2.3 In-situ Material Processing, Placement and Compaction

Soil was transported to the test pad area from the adjacent stockpile area with paddlewheel scrapers. The test pad was constructed in six lifts, each with a compacted lift height of no greater than 6 inches. Loose lift thickness was on the order of 8 inches. Moisture was added periodically with a water truck to maintain the clay's moisture content.

Each lift was compacted with approximately 16 passes using a Rex 3-35 pad foot compactor (specification sheet for compactor is provided in Appendix B-2). After placement and compaction of each lift, a series of field density test were conducted to measure the soil density and compaction (See Section 4.2.3). In order to improve the bonding between layers, the surface of each lift was scarified and wetted with the disc and bushog prior to placement of a new lift.

The surface of the test fill was graded level with a motor grader, and rolled with two passes of a single drum smooth roller. The test pad was covered in an additional lift of clay and visqueen to minimize desiccation until installation of the SDRI was initiated. The visqueen and additional lift were removed prior to construction of the SDRI.

#### 4.2.3 Test Pad Construction – CQA Testing

Compaction and moisture content specifications for the clay test pad are as follows:

“The clay shall be compacted to at least 92 percent relative compaction. The moisture content shall be uniform and shall be 2% to 5% wet of optimum moisture content.”

CQA testing was conducted on the clay test pad to control the amount of moisture in the fill, monitor the effectiveness of the compaction procedures, and to evaluate the properties of the low-permeability soil. Geosyntec performed the following tests during and after the construction of the clay test pad:

- Nuclear Density and Water Content (ASTM D 6938);
- Moisture-Density Relationship (ASTM D 1557);

---

<sup>2</sup> A bushog is typically used in agricultural applications to clear weeds between rows.

- Sieve Analysis (ASTM D 422);
- Thin-wall, Drive Tube Density (ASTM D 2937);
- Atterberg Limits (AST D4318);
- Hydraulic Conductivity (ASTM D 5084); and
- SDRI (ASTM D 5093) (described in Section 4.4.3.4).

The required frequencies and the number of tests taken during construction of the clay test pad are listed in Table 2.

In-place field density/moisture was monitored by the nuclear gauge (ASTM D 6938) and the drive cylinder test (ASTM D 2937). Areas with failing moisture content or compaction tests were reworked or replaced. Holes from nuclear gauge or drive cylinder testing were filled with powdered bentonite.

Results obtained from the nuclear density gauge indicated that the low-permeability soil was compacted with an average moisture content of 21 percent and an average relative compaction of 94 percent. Drive cylinder test and in-place density/moisture test results are included in Appendices C-1 and C-2, respectively.

Saturated hydraulic conductivity was measured by laboratory flexible wall permeability testing (ASTM D 5084). Samples were obtained by using thin wall tubing and sent to Excel for testing. Saturated hydraulic conductivity measured in the laboratory ranged from  $3 \times 10^{-9}$  to  $1 \times 10^{-8}$  cm/s. The hydraulic conductivity test results performed on the clay test pad are summarized in Table C-3 of Appendix C-1.

## 5. SDRI TESTING

### 5.1 Overview

A SDRI test (ASTM D-5093) was performed to evaluate the field hydraulic conductivity of the clay test pad and to provide a correlation between field and laboratory hydraulic conductivity.

The SDRI test provides a direct measurement of the vertical, one-dimensional, infiltration rate of water through soil at very low confining stresses. The SDRI apparatus includes a 2-ft square inner ring and a 6-ft square outer ring. This large size allows for the testing of both micro (i.e., inter-granular) and macro (i.e., through discontinuities) effects on the infiltration rate of liquid flow through a soil layer. The infiltration rate ( $q$ ) is defined as the quantity of liquid entering a porous material per unit area per unit time. The hydraulic conductivity ( $k$ ), which is not a direct measurement from this test, is defined as the flux of liquid per unit hydraulic gradient. Derivation of equations relating infiltration rate to hydraulic conductivity is provided in Section 5.4.

### 5.2 Site Preparation and Equipment Installation

The SDRI was installed by Geosyntec personnel on 12 August 2008. The SDRI test apparatus consists of an open-air, square shaped, metal outer ring and a covered, square shaped, fiberglass inner ring. The outer ring measures 6 ft on a side, and 3 ft high. The inner ring measures 2 ft on each side and 10-inches high at its peak. The outer ring was embedded in a bentonite chip filled trench to an average depth of 18 in. The inner ring was embedded in a bentonite grout filled trench to an average depth of about 3 in. Both the inner and the outer rings were then filled with water. The outer ring was filled with water to a depth of approximately 12 to 13 in., completely submerging the inner ring. A flexible bag was attached to the inner ring with flexible Tygon tubing and barbed nylon hose fittings. The infiltration rate was measured for the 4 ft<sup>2</sup> section of the test pad soil directly underlying the inner ring. During the test, the outer ring served only as a water reservoir for inducing a uniform hydraulic head and a flow boundary to produce one-dimensional vertical flow beneath the inner ring. Floating panels of insulation were placed in the water reservoir to reduce evaporation. This insulation also minimized changes in water temperature. The SDRI set up is shown schematically in Figure 2.

Water-filled flexible bags were attached to the inlet port of the inner ring. The flexible bags were submerged underwater in the outer ring reservoir. This allowed the hydraulic head on the inner ring to equalize with that of the outer ring without flow between the two rings. Flow into the inner ring was measured over discrete time intervals by measuring the change in mass of the bags. The SDRI was installed 12 August 2008 and

data was collected between 13 August and 13 October 2008, when the test was terminated and the equipment was removed.

### 5.3 Data Collection

Geosyntec personnel collected the SDRI data during the majority of the testing period however, CWMI personnel collected data while Geosyntec was not on-site and supplied the data to Geosyntec. The data recorded included the following:

- Outer Ring Water Depth ( $D_f$ ) - measured using a stationary scale as the depth of standing water in the outer ring,
- Water Temperature ( $T$ ) - measured with a thermometer as the water temperature in the outer ring,
- Depth to the Inner Ring ( $H_s$ ) – measured depth from a point on the top of the inner ring to a stationary string hung across the outer ring. This measurement evaluates swelling of the clay in test area.
- Inner Ring Infiltration ( $M_i-M_f$ ) - measured as the difference between initial and final weight of the water in the flexible bags for a given period of time, and
- Soil Moisture Content ( $MC$ ) - measured after completion of the test for the soil column beneath the inner ring; the profile of  $MC$  vs. depth was used to estimate the depth of the wetting front.

#### 5.3.1 Outer Ring Water Depth ( $D_f$ )

The water depth in the outer ring ( $D_f$ ) was recorded using a ruler fixed to the outer ring. The ring was filled up to 12.1 to 13.8 in. above the test fill pad surface. The depth of water was used to estimate the total hydraulic head to induce flow. Table 3 presents the measured outer ring water depths.

#### 5.3.2 Water Temperature ( $T$ )

The temperature of the water ( $T$ ) was measured with a thermometer placed in the outer ring reservoir. Temperature was measured to estimate the effects of thermal expansion and contraction of the water on the infiltration rate. Water within the inner ring could expand and contract slightly with changes in temperature. As the water cools, it contracts and more water is pulled out of the flexible bags and into the space within the

inner ring; as the water warms, it expands and is pushed out of the ring into the bag. The density of water is non-linearly related to its temperature. Table 3 also presents the measured water temperatures.

Based on the field measurements, the temperature changes are considered negligible between initial and final readings. Therefore, the space within the inner ring above the test section remained relatively constant between these readings.

### 5.3.3 Depth to Inner Ring ( $H_s$ )

The depth to the inner ring ( $H_s$ ) was recorded using a ruler measuring the distance between a point on the top of the inner ring to a stationary string fastened across the outer ring. This value corresponds to the height of swell of the clay in the test area. Total swell was estimated to be greater than 3.5 inches. Table 3 presents the measured outer ring water depths.

### 5.3.4 Inner Ring Infiltration ( $M_i$ - $M_f$ )

Flexible bags were used to measure the volume of water infiltrating through the test section underlying the inner ring. The inner ring infiltration data were collected by the following procedure for each time interval:

- flexible bags were filled with water and their valves were closed. The exterior of the bags were then dried and weighed to the nearest tenth of a gram ( $M_i$ );
- each bag was submerged in the outer ring with the valves still closed;
- each time interval for infiltration monitoring was started by attaching the flexible bags to the inner ring inlet tube connected to the lower flow port and the valves opened; the date and time was recorded;
- each time interval for infiltration was ended by closing the valve on the flexible bag, disconnecting the bag from the inner ring inlet tubing, and recording the date and time;
- the use of multiple bags allowed for the beginning of one interval to be concurrent with the end of the previous interval as a full bag was swapped out for partially emptied bag;
- the flexible tubing was secured so that it remained submerged; and

- the flexible bags were removed from the outer ring reservoir, dried, and weighed to the nearest tenth of a gram ( $M_f$ );

The volume of water infiltrating the test section during a particular time interval was computed by subtracting the final bag mass from the initial bag mass (i.e.,  $M_i - M_f$ ). Table 3 presents the measured masses of the bags.

### 5.3.5 Soil Moisture Content (MC)

At the end of the test, the soil moisture profile was evaluated by taking soil samples from below the inner ring. The water from within the inner and outer rings was first evacuated and the inner ring removed to allow sampling of the test section soil.

Soil samples were obtained by cutting 6-in by 6-in block samples with 0.1 foot and 0.2 foot thicknesses down to a maximum depth of 2 feet (24 inches) below the surface. Each 0.1 ft or 0.2 ft. interval was placed in a sealed plastic bag to preserve the in-situ moisture content. The soil moisture content was tested in the laboratory in accordance with ASTM D 2216. Results of the moisture content tests are discussed in Section 5.5.2 and are presented in Appendix D.

## 5.4 Theory

The seepage of water into the test area is driven by the hydraulic gradient caused by the ponded water and high capillary suction of the partially saturated clay (as opposed to fully saturated conditions associated with laboratory tests).

The saturated hydraulic conductivity can be computed using a form of Darcy's Law which includes terms for the total hydraulic gradient. The governing equation that describes the infiltration of water through the compacted clay is developed below, based on the terms and sign convention in Figure 2.

$$q = -ki = -k \frac{\Delta h}{\Delta L} \quad (1)$$

Where,

$q$  = infiltration rate per unit area and time (L/T)

$k$  = saturated hydraulic conductivity (L/T)

$\frac{\Delta h}{\Delta L}$  = total hydraulic gradient (L/L), or  $i$

$\Delta h = h_1 - h_2$

$\Delta L = z_1 - z_2$

$h$  = Total Head

$h = z + \varphi$

$z$  = elevation head



$\varphi$  = pressure head due to hydraulic head or soil suction/tension

$$q = -k \left[ \frac{(z_1 + \varphi_1) - (z_2 + \varphi_2)}{(z_1 - z_2)} \right] \quad (2)$$

For any given wetting front,  $L_f = z_1 - z_2$ . Substituting this into Equation (2), the infiltration rate at any wetting front is calculated as:

$$q = -k \left[ \frac{\varphi_1}{L_f} - \frac{\varphi_2}{L_f} + 1 \right] \quad (3)$$

As shown in Figure 2, at Point 1, the pressure head is equal to the depth of water in the outer ring,  $D_f$ , with soil suction/tension equal to zero (i.e., the soil is saturated). At Point 1, the pressure head is  $D_f = \varphi_1$ . Also, since the clay fill is unsaturated below the wetting front, the in situ pressure head at Point 2 will be equal to the soil suction and negative in sign convention, and can be designated simply at  $\varphi$ , i.e.,  $\varphi = -\varphi_2$ . Substituting into Equation (3):

$$q = -k \left[ \frac{D_f}{L_f} + \frac{\varphi}{L_f} + 1 \right] \quad (4)$$

Equation (4) is time dependent. That is, the infiltration flow rate per unit area ( $q$ ) and the depth of the wetting front ( $L_f$ ) are interrelated and vary with time. As the wetting front advances, Equation 4 can be rearranged to calculate hydraulic conductivity as the infiltration rate appears to stabilize from daily readings:

$$k = -\frac{q}{\frac{D_f}{L_f} + \frac{\varphi}{L_f} + 1} \quad (5)$$

Equation 5 was used to calculate the hydraulic conductivity of the compacted clay liner. Results of the test are presented below in Section 5.5.

## 5.5 Results

### 5.5.1 Infiltration Rate

The infiltration rate per unit area ( $q$ ) is calculated as the total water lost during a measured time increment. The calculated infiltration rate ( $q$ ) is presented in Table 3. The infiltration rate at the end of the test was measured at  $8 \times 10^{-7}$  cm/s and was observed to generally decrease over time (see Figure 3).

### 5.5.2 Wetting Front

The conventional method to estimate the depth to the wetting front ( $D_f$ ) at the end of the test requires obtaining moisture content samples along a vertical column of soil below the inner ring. The moisture profile with depth is then compared against the saturation line and the original moisture content to estimate the depth of the wetting front.

Geosyntec collected moisture samples at 0.1 to 0.2 feet increments along two moisture columns. Figure 4 presents a plot of this moisture content versus depth. As shown in Figure 4, the moisture content decreases with depth as would be expected when significant swelling of the clay occurs<sup>3</sup>. Based on the results of the moisture content testing and visual observation of the soil upon excavation<sup>4</sup>, the wetting front ( $L_f$ ) is estimated to be approximately 1.4 feet (17 inches). At a depth of approximately 1.9 feet (23 inches), the moisture content of the soil beneath the inner ring is equivalent to the as-compacted conditions. The soil between depths of 1.4 feet and 1.9 feet represent an area where increased moisture content, but not saturated, due to soil suction.

### 5.5.3 Soil Suction

Soil suction was not directly measured as part of this field work. However, lysimeters installed as part of the SDRI constructed for development of Phase I/II of Landfill B-18 (ESI, 1992) measured a soil suction of 280 inches of pressure with tensiometers in unsaturated soil below the SDRI inner ring.

Geosyntec developed a soil-moisture characteristic curve for the soil at the wetting front, relating the volumetric water content of the soil to the suction head, using the van Genuchten function (van Genuchten, 1980). The van Genuchten curve-fitting parameters used in the function were back-calculated from the water retention parameters recommended in the Hydraulic Evaluation of Landfill Performance (HELP) model documentation (Schroeder et al. 1994) for moderately compacted clays of high plasticity. Based on the moisture content measured in the laboratory for the soil just below the wetting front, the soil-moisture characteristic curve results in an unsaturated soil suction of approximately 33 feet (396 inches). This value is on the same order of magnitude with the suction pressures measured in the field during previous

---

<sup>3</sup> Moisture content at saturation is a function of the dry density of the soil (i.e., the volume of void space). As soil swells and becomes less dense, the volume of void increases, thereby increasing the moisture content at saturation.

<sup>4</sup> Free water was observed in the voids of the soil matrix to a depth of approximately 1.4 feet. From approximately 1.4 feet to 1.9 feet, the material was softened and visually wetter. At a depth of approximately 1.9 feet and below, the soil was hard visually similar to areas outside the SDRI area.

investigations. For use in these calculations, Geosyntec has assumed a soil suction of 280 inches (23 feet) consistent with that previously monitored at the site.

#### 5.5.4 Hydraulic Conductivity

Using Equation 5, the hydraulic conductivity is calculated using the data from the last testing interval, as follows:

$$k = -\frac{q}{\frac{D_f}{L_f} + \frac{\phi}{L_f} + 1} = \frac{7.6 \times 10^{-7} \text{ cm/s}}{\frac{12.5}{17} + \frac{280}{17} + 1} = 4.2 \times 10^{-8} \text{ cm/s}$$

The results of this test indicate that the field hydraulic conductivity of the Pecten claystone, when compacted to the specifications presented in Appendix A, meet the hydraulic conductivity requirements of a compacted clay liner as outlined in Section 1.2.

#### 5.5.5 Laboratory Data and Comparison to Field Data

As discussed in Section 4.2.3, Geosyntec tested the hydraulic conductivity of 10 samples collected using 3-inch diameter thin-wall Shelby tubes from the test pad area. These samples were tested at a minimum confining pressure of 2 psi. The average hydraulic conductivity of the laboratory testing on the test pad samples is approximately  $5.1 \times 10^{-9}$  cm/s (see Appendix C).

The field test results are approximately one order of magnitude higher than laboratory results. These differences are expected and may be attributed to the unrestrained swelling of the clay which occurs during field testing when compared to laboratory results which have small consolidation pressures preventing some of the swelling. The low hydraulic conductivity measured in the laboratory is a function of the consolidation pressure used in the test to prevent swelling.

By comparing laboratory and field hydraulic conductivity testing, the following correlation factor ( $CF_k$ ) is calculated:

$$CF_k = \frac{k_{field}}{k_{lab}} = \frac{4.2 \times 10^{-8} \text{ cm/s}}{5.1 \times 10^{-9} \text{ cm/s}} = 8.2$$

Therefore, during future construction a correlation factor of 8.2 should be applied against laboratory test results to estimate field hydraulic conductivity of the CCL.

## 6. SUMMARY AND CONCLUSIONS

Excavation and stockpiling of clay from the Pecten Claystone, as well as test pad construction, was performed in general accordance with the requirements presented in Appendix A. The excavated clay was classified as a fat clay (CH) with more than 30 percent of the material, by weight, passing the No. 200 sieve. This material, when tested in the both the laboratory and field, has a hydraulic conductivity no greater than  $1 \times 10^{-7}$  cm/s. Therefore, this material meets the requirements of a CCL as defined by 40 CFR §264.301 and CCR Title 23 §2541. Further, this material is similar to the material previously used as CCL for Landfill B-18 at the Kettleman Hills Facility (see Table 4).

During future construction a correlation factor of 8.2 should be applied against laboratory test results to estimate field hydraulic conductivity of the CCL.

## **REFERENCES**

- Environmental Construction Services (ECS), 1991, "Clay Source Report, Landfill B-18, Phases IA and IB, Kettleman Hills Facility, Kettleman City, California, Prepared for Chemical Waste Management, Inc., 25 November 1991.
- Environmental Solutions, Inc. (ESI), 1992, "Test Fill and Infiltrometer Test Results, Landfill B-18 Phases I and II and Final Closure," Prepared for Chemical Waste Management, Inc., 23 January 1992.
- Geosyntec Consultants (2007), "Construction Quality Assurance (CQA) Plan for Landfill B-17, Phase A1, Kettleman Hills Facility, Kings County, California," Prepared for Chemical Waste Management, Inc., July 2007.
- Geosyntec Consultants (2008), "Technical Specifications for Landfill B-17, Phase A1, Kettleman Hills Facility, Kings County, California," Prepared for Chemical Waste Management, Inc., January 2008.
- Golder Construction Services (GSC), 1993, "Landfill B-18, Phases IIA and IIB Construction Reports Volume 1 – Clay Liner Source Report," Prepared for Chemical Waste Management, Inc., May 1993.
- Schroeder, P.R., Lloyd, C.M., and Zappi, P.A., 1994, "The hydrologic evaluation of landfill performance (HELP) model, user's guide for version 3," U.S. Environmental Protection Agency, Office of Research and Development, Washington, D.C., Report No. EPA/600/R-94/168a.
- Van Genuchten, M. T., 1980, "A closed form equation for predicting the hydraulic conductivity of unsaturated soils," Soil Science Society of America Journal, 44, 892–898.

**TABLE 1  
CLAY STOCKPILE TESTING FREQUENCIES**

Test	ASTM Standard	Required Frequency	Number of Tests	Actual Frequency <sup>1</sup>
Moisture-Density Relationship	ASTM D 1557	1 per 5,000 CY	7	1 per 3,371 CY
Sieve Analysis	ASTM D 422	1 per 5,000 CY	7	1 per 3,371 CY
Atterberg Limits	ASTM D 4318	1 per 5,000 CY	7	1 per 3,371 CY
Hydraulic Conductivity	ASTM D 5094	1 per 5,000 CY	7	1 per 3,371 CY

Notes

1. Based on approximately 23,600 cy of clay material stockpiled.

**TABLE 2  
CLAY TEST PAD TESTING FREQUENCIES**

Test	ASTM Standard	Required Number of Tests	Number of Tests
<i>Bulk Samples:</i>			
Moisture-Density Relationship	ASTM D 1557	3	3
<i>In-Situ Density/Moisture:</i>			
Nuclear Density	ASTM 6938	5 per lift	40 (min 5 per lift)
<i>Shelby Tube Samples:</i>			
Sieve Analysis	ASTM D 422	6	6
Density	ASTM D 2937	6	10
Atterberg Limits	ASTM D 4318	6	10
Hydraulic Conductivity	ASTM D 5094	6	10

**TABLE 3  
SDRI MEASUREMENTS**

Date	Time	Water Level, Df (in)	Water Temp. (°F)	Rain?	Inner Ring Height, Hs (in)	Initial (full) Bag Mass (grams)	Final (empty) Bag Mass (grams)	Elapsed Time (hours)	Flow Q (cm <sup>3</sup> /s)	Infiltration Rate q (cm/s)
8/13/2008	8:00	12.75	76	N		1485.1	0			
8/14/2008	8:04	12.75	80	N		1618.7	0	24.07		
8/14/2008	12:54	12.75	82	N		2023.3	179	28.90		
8/15/2008	8:34	12.75	84	N	9.8	0	1885.1	48.57		
8/16/2008	7:40	12.63	84	N	9.6	2167.8	2049.5	71.67		
8/17/2008	8:50	12.50	86	N	9.4	1914.6	1834.5	96.83	0.0343	9.2E-06
8/18/2008	8:27	12.44	84	N	9.2	2272.4	1944.1	120.45	0.0322	8.7E-06
8/19/2008	7:55	12.38	83	N	9.0	2110.8	1740.5	143.92	0.0310	8.3E-06
8/20/2008	8:07	12.25	81	N	8.8	1848.3	1852.2	168.12	0.0222	6.0E-06
8/21/2008	8:10	12.25	82	N	8.6	2099.7	2137.4	192.17	0.0173	4.7E-06
8/22/2008	8:03	12.38	82	N	8.5	2031	2056.7	216.05	0.0149	4.0E-06
8/23/2008	8:18	12.25	82	N	8.4	2014.8	2074	240.30	0.0143	3.9E-06
8/25/2008	8:32	12.13	84	N	8.3	1984.6	1998.5	288.53	0.01233	3.3E-06
8/26/2008	7:02	13.25	84	N	8.2	1956.3	1978	311.03	0.01324	3.6E-06
8/27/2008	8:09	13.13	84	N	8.1	2035	2032.4	336.15	0.01174	3.2E-06
8/29/2008	8:12	13	86	N	7.9	2027.3	2079.2	384.20	0.00453	*See Note
8/30/2008	8:49	12.9375	88	N	7.8	2018.6	968.3	408.82	0.01195	3.2E-06
8/31/2008	8:37	12.9375	86	N	7.7	2057.4	1804.4	432.62	0.01100	3.0E-06
9/2/2008	8:57	12.75	80	N	7.6	2088.4	907.9	480.95	0.013	3.4E-06
9/3/2008	9:11	12.628	80	N	7.5	2078.2	1027.9	505.18	0.012	3.3E-06
9/4/2008	8:15	12.5	81	N	7.5	2119.4	1191.4	528.25	0.011	2.9E-06
9/5/2008	9:05	13.8	82	N	7.4	2220.5	2297.6	553.08	0.011	3.0E-06
9/8/2008	8:30	13.7	85	N	7.2	2098.5	2013.2	624.50	0.00621	1.7E-06
9/9/2008	8:30	13.5	84	N	7.2	2227.8		648.50		
9/10/2008	8:35	13.5	82	N	7.1	2226.6	1625.7	672.58	0.00694	1.9E-06
9/11/2008	8:25	13.1	80	N	7.1	4262.8	1761.4	696.42	0.005	1.5E-06
9/15/2008	10:10	13.313	82	N	7	2246.4	3730.2	794.17	0.004	1.1E-06



**TABLE 3  
SDRI MEASUREMENTS**

Date	Time	Water Level, Df (in)	Water Temp. (°F)	Rain?	Inner Ring Height, Hs (in)	Initial (full) Bag Mass (grams)	Final (empty) Bag Mass (grams)	Elapsed Time (hours)	Flow Q (cm <sup>3</sup> /s)	Infiltration Rate q (cm/s)
9/16/2008	8:20	13.25	82	N	6.9	2142.4	1788.2	816.33	0.006	1.5E-06
9/17/2008	8:35	13.125	82	N	6.9	2175.8	1718.9	840.58	0.005	1.3E-06
9/18/2008	8:06	13	79	N	6.9	2045.3	1760.4	864.10	0.005	1.3E-06
9/19/2008	8:37	13	78	N	6.9	1946.9	1663.9	888.62	0.004	1.2E-06
9/22/2008	8:31	12.75	76	N	6.8	1970	1087.7	960.52	0.003	8.9E-07
9/23/2008	8:28	12.6875	75	N	6.8	1984.6	1666.9	984.47	0.004	9.5E-07
9/24/2008	8:33	12.625	76	N	6.8	1722.2	1596.5	1008.55	0.004	1.2E-06
9/25/2008	8:10	12.375	78	N	6.7	1590.1	1498.8	1032.17	0.003	7.1E-07
9/26/2008	8:20	12.25	78	N	6.6	1498.1	1281.2	1056.33	0.004	9.6E-07
9/29/2008	9:00	13.375	82	N	6.6	2293.3	1157.2	1129.00	0.003	7.1E-07
9/30/2008	9:30	12.25	80	N	6.6	2284.8	1951.2	1153.50	0.004	1.0E-06
10/1/2008	9:10	12.25	82	N	6.6	2305.4	2269.8	1177.17	0.000	4.7E-08
10/2/2008	8:45	13.25	80	N	6.6	2212.1	1988.3	1200.75	0.004	1.1E-06
10/3/2008	9:30	13.25	77	N	6.5	2166.4	1759	1225.50	0.005	1.4E-06
10/6/2008	9:50	13	72	N	6.5	2303.2	2161.3	1297.83	0.003	6.8E-07
10/7/2008	8:25	13	72	N	6.4	2219.1	2161	1320.42	0.002	4.7E-07
10/8/2008	11:00	12.875	74	N	6.4	2164.5	1958.5	1347.00	0.003	7.3E-07
10/9/2008	10:30	12.75	72	N	6.4	2159.3	1731	1370.50	0.005	1.4E-06
10/10/2008	9:30	12.50	68	N	6.4	2297.5	1810.1	1393.50	0.004	1.1E-06
10/13/2008	9:01	12.5	61	N	6.3	2184.9	1915.6	1465.02	0.003	7.6E-07

\* Field data from 8/28/08 unclear. No bag weights recorded. Data not used.


= Empty bag, data not used

**TABLE 4**  
**COMPARISON OF CURRENT AND PREVIOUS LABORATORY TEST**  
**RESULTS OF PECTEN CLAYSTONE**

	Soil Classification	Percent Passing No. 200 Sieve <sup>1</sup> (%)	LL/PI (%) <sup>2</sup>	Laboratory Hydraulic Conductivity <sup>1</sup> (cm/s)
Current Investigation	CH	89 (74 – 94)	93/64	$3 \times 10^{-8}$ ( $9 \times 10^{-8}$ to $3 \times 10^{-9}$ )
Previous Landfill B-18 CCL Testing <sup>3</sup>	CH	>80 (48 - 94)	76/55	$8 \times 10^{-9}$ ( $2 \times 10^{-7}$ to $2 \times 10^{-10}$ )


Notes:

1. First value reported is approximate average test results. Values in parentheses are ranges of data results.
2. Values reported are approximate averages.
3. Based on ECS (1991), ESI (1992), and GSC (1993).



P:\CAD\SC0472.kmcon\figures\17 A1 site plan.dwg



<b>SITE PLAN</b> <b>KETTLEMAN HILLS FACILITY</b> <b>KINGS COUNTY, CALIFORNIA</b>		
<b>Geosyntec</b> consultants	DATE:	NOV 08
	PROJECT NO.	SC0472
		FIGURE <b>1</b>



**Geosyntec**  
consultants

**SDRI Test Setup**  
Kettleman Hills Facility  
Kings County, California


**FIGURE NO. 2**  
PROJECT NO. SC0472  
DATE: 17-Dec-08



**Geosyntec** consultants

Infiltration Rate and Recorded Swell  
 Kettleman Hills Facility  
 Kings County, California

**FIGURE NO. 3**  
 PROJECT NO. SC0472  
 DATE 25-Nov-08



**APPENDIX A  
PROJECT DOCUMENTS**

**APPENDIX A-1**  
**Project Specifications – Section 02220**



## SECTION 02220

### COMPACTED CLAY LINER

#### PART 1 – GENERAL

##### 1.1 SCOPE OF WORK

- A. Furnishing all labor, materials, tools, supervision, transportation, and installation equipment necessary for the construction of the Compacted Clay Liner (CCL) test pad, as specified herein, as shown on the Construction Drawings and in accordance with the Construction Quality Assurance (CQA) Plan.
- B. Earthwork Contractor shall construct the CCL test pad to the elevations, lines, grades, and dimensions as shown on the Plans and described in the Specifications, unless otherwise directed by the Engineer.
- C. Earthwork Contractor shall use clay from the source(s) selected by the owner.
- D. The clay borrow source may contain some debris and oversize particles. The Earthwork Contractor shall remove large and easily recognizable debris. This debris must be removed prior to clay placement. Debris removal is considered part of the cost of clay placement.

##### 1.2 RELATED SECTIONS

- A. Section 02200 - Earthwork

##### 1.3 REFERENCES

- A. ASTM D422 - Standard Test Method for Particle Size Analysis of Soils
- B. ASTM D854 - Standard Test Methods for Specific Gravity of Soils
- C. ASTM D1140 - Standard Test Methods for Amount of Material in Soils Finer than the No. 200 Sieve.
- D. ASTM D1556 - Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method.
- E. ASTM D1557 - Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort
- F. ASTM D1587 - Standard Practice for Thin-Walled Tube Geotechnical Sampling of Soils

- G. ASTM D2216 - Standard Test Method for Laboratory Determination of Water (Moisture) Content of Soil, Rock, and Soil-Aggregate Mixtures.
- H. ASTM D2434 - Standard Test Method for Permeability of Granular Soils (Constant Head).
- I. ASTM D2487 - Standard Test Method for Classification of Soils for Engineering Purposes.
- J. ASTM D2922 - Standard Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).
- K. ASTM D3017 - Standard Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth).
- L. ASTM D4318 - Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.
- M. ASTM D5084 - Standard Test Methods for Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter.
- N. ASTM D5093 - Standard Test Method for Field Measurement of Infiltration Rate Using a Double-Ring Infiltrometer with a Sealed Inner Ring
- O. Landfill B-17 Phase A1, Kettleman Hills Facility, Construction Quality Assurance Plan (CQA Plan).

#### **1.4 QUALITY ASSURANCE**

- A. Construction Quality Assurance (CQA) monitoring shall be the responsibility of the Owner or Owner's Representative in accordance with the approved CQA Plan.
- B. Quality control testing associated with filling and compaction operations shall be performed by the Owner or Owner's Representative in compliance with the CQA Plan and this Specification. The Contractor shall assist the Owner or Owner's Representative in obtaining clay samples at the frequencies provided in the CQA Plan.
- C. Contractor shall provide labor, materials (granular bentonite), and equipment (chain trencher) necessary for the installation of the QA Monitor supplied Sealed Double Ring Infiltrometer equipment in accordance with ASTM D5093.
- D. Earthwork Contractor shall give advance notice of at least 24 hours to the Owner or Owner's Representative when ready for compaction testing and inspection.

**PART 2 – PRODUCTS****2.1 CLAY**

- A. Clay at the borrow source may not meet the contract specification for moisture content. Drying and/or wetting of this material may be required prior to placement.
- B. Clay shall be free of debris, rocks, gravel greater than 1 inch in any direction, and other deleterious material.
- C. At least 30 percent of the material, by weight, shall pass the No. 200 sieve.
- D. Acceptable soils are those meeting the requirements of ASTM D 2487 for CL, SC, or CH with a compacted field permeability of less than or equal to  $1 \times 10^{-7}$  cm/sec.

**2.3 EQUIPMENT**

- A. Provide equipment to excavate and transport clay from borrow source to test pad area.
- B. Compaction equipment shall be of suitable mechanical type and adequate to obtain the densities specified, and shall provide satisfactory breakdown of materials to form a dense fill. Flooding or jetting methods of compaction shall not be used.
- C. Locations inaccessible to heavy equipment shall be compacted by means of manually controlled pneumatic or vibrating tampers or by approved equivalent methods to achieve specified densities.
- D. Compaction equipment shall be operated in strict accordance with the manufacturer's instructions and recommendations. Equipment shall be maintained in such condition that it shall deliver the manufacturer's rated compactive effort. If inadequate relative compaction is obtained, the Earthwork Contractor shall provide larger and/or different types of additional equipment at no additional cost. Hand-operated equipment shall be capable of achieving the specified densities.
- E. Operate compaction equipment in strict accordance with the manufacturer's instructions and recommendations. If inadequate densities are obtained, provide larger and/or different types of additional equipment at no cost to the Owner.
- F. Provide water application equipment free of leaks and equipped with a distributor bar or other accepted device to ensure uniform application.
- G. Provide processing equipment suitable for providing a material that has a uniform moisture content.

- H. On-site water source shall be made available for the EARTHWORK CONTRACTOR for the work included in this Section. The water source is located approximately 1.25 miles north of the project area and shall be identified in the pre-bid meeting at the site.

### **PART 3 – EXECUTION**

#### **3.1 GENERAL**

The Earthwork Contractor shall:

- A. Verify that the survey control system is installed and properly protected from construction operations prior to all earthwork, including clay placement.
- B. Fill and compact all holes and other depressions prior to placement of clay.
- C. Maintain surface of clay at minimum 2 percent grades for drainage.
- D. Material incorporated into clay, determined by the Owner or Owner's Representative to be in violation of Specification requirements, shall be removed by the Earthwork Contractor at the Earthwork Contractor's expense.

#### **3.2 TEST PAD CONSTRUCTION**

- A. Fill and compact all holes and other depressions prior to placement of clay.
- B. Test pad area shall be cleared and grubbed.
- C. Construct a test pad on the prepared subgrade. Surface of the test pad subgrade shall be proof-rolled to eliminate soft zones, irregularities, and abrupt changes in grade. Slope the finished subgrade surface at a grade of approximately 2 to 3 percent. No standing water or excessive moisture is allowed to accumulate on the surface of the subgrade.
- D. The test pad shall be 50 feet long, 50 feet wide, and 3.5 feet deep. Some of the techniques to be monitored include: moisture conditioning, clod removal, scarification between lifts, number of equipment passes, lift thicknesses, and compactive effort.
- E. The Earthwork Contractor will be responsible for verification that material that does not meet the Specifications is removed from the clay prior to placement.

- F. Material incorporated into clay, determined by the Owner or Owner's Representative to be in violation of Specification requirements, shall be removed by the Earthwork Contractor at the Earthwork Contractor's expense.
- G. Contractor shall breakdown claystone materials as necessary to meet maximum particle size requirements.
- H. The clay material shall be compacted to at least 92 percent relative compaction. The moisture content shall be uniform and shall be 2% to 5% wet of the optimum moisture content.
- I. Clay material shall be compacted in lifts with a compacted thickness of no greater than 6 inches.
- J. Maintain surface of clay at minimum 2 percent grades for drainage.
- K. Earthwork Contractor shall take adequate measurements to prevent moisture loss from the CCL.
- L. Placement of successive clay layers shall not begin until the Owner or Owner's Representative has accepted the previous layer. Any damage to the previous layer or deterioration subsequent to acceptance shall be repaired by the Earthwork Contractor to the satisfaction of the Owner or Owner's Representative at the expense of the Earthwork Contractor.
- M. Earthwork Contractor shall scarify the top of each lift and correct moisture content prior to placement of overlying lift.
- N. Clay shall not be placed and compacted if the ambient air temperature drops below 32°F.
- O. Earthwork Contractor shall seal the last and uppermost layer of CCL, after achieving the compaction requirements, with two passes of a single drum smooth roller.
- P. Where test results indicate that the lift thickness, maximum particle size, in-place density/moisture content and or permeability of any portion of the clay does not meet the specified requirements, that particular portion shall be re-tested by the Owner or Owner's Representative and/or re-worked or replaced by the Earthwork Contractor at his expense until the required condition has been attained and the resulting product meets or exceeds the Specification requirements. No additional fill shall be placed over an area until the existing fill has been tested horizontally and vertically and determined by the Owner or Owner's Representative to meet the Compacted Clay Liner Specifications of this document.

- Q. Assist the QA Monitor in obtaining cylinder push samples of the test fill per ASTM D1587 for laboratory permeability testing. These samples will be used to correlate field to laboratory permeability results.
- R. Provide equipment and personnel to assist the QA Monitor in installing the Double Ring Infiltrometer per ASTM D 5093. The Infiltrometer has a 6-foot square outer ring and a 2-foot square inner ring. It is assumed that the assistance will require two laborers for one working day. Equipment needed includes:
- a. grout mixer
  - b. 20 50-lb bags of bentonite grout (Volclay or similar)
  - c. wheelbarrow and shovels for placing grout in trenches
  - d. 1200 gallons of potable water for test
- S. Keep personnel and equipment away from test area while test in running (estimated to be six weeks).

### 3.3 FIELD QUALITY CONTROL

- A. The minimum frequency and details of quality assurance testing are provided in the CQA Plan. The Earthwork Contractor shall be aware of all field quality assurance requirements and activities, and shall incorporate these into his schedule.
- B. All test holes, pits or other perforations resulting from testing of soils shall be filled with soil compacted to the satisfaction of the Owner or Owner's Representative.
- C. If a defective area is discovered in the earthwork, the Owner or Owner's Representative will determine the extent and nature of the defect by performing additional tests, observations, a review of records, or other means that the Owner or Owner's Representative deems appropriate.
- D. After the Owner or Owner's Representative determines the extent and nature of a defect, the Earthwork Contractor shall correct the deficiency at his expense to the satisfaction of the Owner or Owner's Representative.
- E. Additional testing will be performed to verify that the defect has been corrected before the Earthwork Contractor performs any additional work in the area of the deficiency.
- F. The Owner or Owner's Representative will determine in-place density and moisture content by any one or combination of the following methods: ASTM D1556, D2922, D2216, D3017, or other methods selected by the Owner or Owner's Representative. The Earthwork Contractor shall cooperate with this testing work by leveling small test areas designated by the Owner or Owner's

Representative. Backfilling of test areas shall be at Earthwork Contractor's sole expense. The frequency and location of testing shall be determined solely by the Owner or Owner's Representative. The Owner or Owner's Representative may test any lift of fill at any time, location, or elevation.

**\*\*END OF SECTION 02220\*\***

**APPENDIX A-1**  
**CQA Plan – Addendum 1**



**LANDFILL B-17 PHASE A1  
KETTLEMAN HILLS FACILITY  
CONSTRUCTION QUALITY ASSURANCE PLAN**

**ADDENDUM NO. 1**

**1.1 Clay Liner Excavation**

- Monitor that limits of borrow area are staked before work.
- Monitor that borrow area is cleared and grubbed prior to excavation.
- Visually observe excavated material for consistency with specifications.
- Monitor that upper 2 vertical feet of excavated material and material not meeting clay material specifications is stockpiled in general fill stockpile.
- Sample excavated material at a frequency of one sample per 5,000 cy of material excavated and perform the following laboratory tests:
  - Moisture-Density Relationship (ASTM D1557)
  - Sieve Analysis (ASTM D422)
  - Atterberg Limits (ASTM D4318)
  - Hydraulic Conductivity (ASTM D5094), remolded sample, compacted at a minimum of 90% relative compaction and at +2% optimum moisture content per ASTM D1557, at confining stress of 2 psi.

**1.2 Clay Liner Test Pad**

A compacted clay test pad will be constructed to evaluate the excavated material's performance as a compacted clay liner with a maximum hydraulic conductivity of  $1 \times 10^{-7}$  cm/sec.

- Monitor that limits of borrow area are staked before work.
- Determine correlation between number of passes with compaction equipment and relative density.
- Document equipment used to construct test pad.
- Monitor that clay material meets the particle size requirements in the project specifications (1-inch maximum).
- Monitor that material is placed in lifts with a compacted thickness no greater than 6 inches.
- Monitor that moisture content is uniform and meets the project specifications.

- Document number of passes for each lift.
- Perform nuclear density tests (ASTM D2922 and D3017) at a frequency of five tests per lift being placed.
- Collect a minimum of three bulk samples to be tested for Moisture-Density Relationship (ASTM D1557)
- Collect a minimum of six in-situ samples using thin-wall samplers (Shelby Tubes) from the completed compacted clay to be tested for the following:
  - Sieve Analysis (ASTM D422)
  - Density (ASTM D2937)
  - Atterberg Limits (ASTM D4318)
  - Hydraulic Conductivity (ASTM D5094)

**APPENDIX B  
CONSTRUCTION DOCUMENTATION**

**APPENDIX B-1**  
**Photo Log**



<b>Photo No.:</b>	1	<b>Date:</b>	07-31-08
<b>Photographer:</b>	David Williams		
<b>Subject:</b>	Preparing to perform FDT on clay test pad		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	2	<b>Date:</b>	07-31-08
<b>Photographer:</b>	David Williams		
<b>Subject:</b>	Documenting FDT on clay test pad		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	3	<b>Date:</b>	08-07-08
<b>Photographer:</b>	Jane Soule		
<b>Subject:</b>	Compaction of clay test pad with REX 3-35		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	4	<b>Date:</b>	08-07-08
<b>Photographer:</b>	Jane Soule		
<b>Subject:</b>	Preparing to take Shelby tube samples on final clay test pad lift		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	5	<b>Date:</b>	08-12-08
<b>Photographer:</b>	David Williams		
<b>Subject:</b>	Removal of visqueen layer used to maintain moisture of clay test pad prior to SDRI installation		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	6	<b>Date:</b>	08-12-08
<b>Photographer:</b>	David Williams		
<b>Subject:</b>	SDRI Installation, cutting trench for inner ring		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	7	<b>Date:</b>	08-12-08
<b>Photographer:</b>	David Williams		
<b>Subject:</b>	SDRI Installation, inner ring in place		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	8	<b>Date:</b>	08-12-08
<b>Photographer:</b>	David Williams		
<b>Subject:</b>	SDRI Installation, filling outer ring with water		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California





<b>Photo No.:</b>	9	<b>Date:</b>	08-12-08
<b>Photographer:</b>	David Williams		
<b>Subject:</b>	SDRI installation complete		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	10	<b>Date:</b>	08-27-08
<b>Photographer:</b>	Jane Soule		
<b>Subject:</b>	SDRI during monitoring with insulating cover.		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	11	<b>Date:</b>	10-13-08
<b>Photographer:</b>	Jane Soule		
<b>Subject:</b>	SDRI Setup, showing measurement of depth of water & thermometer, string used to evaluate swell (depth to top of inner ring).		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	12	<b>Date:</b>	10-13-08
<b>Photographer:</b>	Jane Soule		
<b>Subject:</b>	Edge of outer ring, showing extensive swell of clay (beyond that of bentonite installed along seam), after draining of water.		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	13	<b>Date:</b>	10-13-08
<b>Photographer:</b>	Jane Soule		
<b>Subject:</b>	SDRI removal, stakes placed on ground surfaces to show extent of swell (approximately 5 – 6 inches)		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	14	<b>Date:</b>	10-13-08
<b>Photographer:</b>	Jane Soule		
<b>Subject:</b>	Excavation of trench around SDRI for removal		
<b>Project:</b>	Kettleman Hills Facility Landfill B-17, Phase A1	<b>City/State:</b>	Kings County, California





<b>Photo No.:</b>	15	<b>Date:</b>	10-13-08
<b>Photographer:</b>	Mike Minch		
<b>Subject:</b>	Sampling of soil for moisture content testing from inner ring area		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California



<b>Photo No.:</b>	16	<b>Date:</b>	10-13-08
<b>Photographer:</b>	Jane Soule		
<b>Subject:</b>	Excavated trench within inner ring area, significant moisture evident to depth of 1.3 - 1.4 feet, increase in moisture from as-compacted condition evident to depth of 1.8 to 1.9 feet.		
<b>Project:</b>	Kettleman Hills Facility	<b>City/State:</b>	Kings County, California

**APPENDIX B-2**  
**Compaction Equipment Specification Sheet**

# REX MODEL 3-35 PACTOR SPECIFICATIONS



## ENGINE

Model 6V53 Detroit Diesel, 185 H.P. @ 2500 RPM, variable speed governor, 22" (559 mm) blower type fan, two stage dry type replaceable element air cleaner with service indicator, fuel and oil filters.

## TRANSMISSION AND TORQUE CONVERTER

Clark C-28000 series 3-speed forward and reverse power shift matched to a Clark C-270 series converter. Speeds: 1st-3.75; 2nd-7.25; 3rd-10.5.

## DRIVE

3-Wheel configuration for effective full width compaction and stability, all wheels drive. No Spin front differential; Mechanical driveline with heavy duty universals.

## AXLES AND WHEELS

Clark 33810 series heavy duty axles front and rear. Wheels: Open ring segmented pad type, 3" x 5" (76.2 mm x 127 mm) pads with raker bars.

## STEERING

Articulated front steer actuated by two hydraulic rams. Inside turning radius: 11'3" (3429 mm); Outside turning radius: 22'6" (6858 mm).

## BRAKES

Hydraulically operated, multiple disc service brakes running in oil.

**NOTE:** We reserve the right to amend these specifications at any time without notice.

The only warranty applicable is our standard written warranty. We make no other warranty, expressed or implied.

Mechanically operated multiple disc parking brake.

## SHOCK PROTECTION AND SHIELDING

Rear axle is shock absorber mounted. All wheels equipped with rubber cushions mounted between outer ring and inner ring to reduce shock and eliminate metal-to-metal contact. Fenders, guards, and railings designed for maximum operator protection. Engine compartment protected by heavy gauge hood which opens fully with spring assist.

## BLADE

9' Wide. Large full width blade. Hydraulically operated with up, down, and float positions. Blade raise above grade: 34" (864 mm); Blade down below grade: 4" (102 mm).

## ELECTRICAL

12 Volt system, 62 amp alternator, voltage regulator, starter, emergency and service shutoff.

## HYDRAULICS

A fully filtered system with service indicator, gear type pump, and spool valves.

## LIGHTS

Two front, two rear.

## GAUGES

Ammeter, engine oil pressure, transmission temperature and

pressure, water temperature, hour meter, fuel, air cleaner service indicator, and tachometer.

## OPERATOR CONTROLS & POSITIONING

Side facing, four way adjustable seating for full visibility front and rear. Travel direction and range and blade positioning hand controls. Braking and travel speed pedal controls. All located for operator comfort.

Operating weight less ROPS ... 36,000# (16330 KG)  
Operating weight with ROPS ... 37,500# (17010 KG)

## COMPACTIVE EFFORT

343 PSI (24.11 KG/cm<sup>2</sup>)

## CAPACITIES

Fuel 125 gal. (473 liters), hydraulic system 55 gal. (208 liters), cooling system 13 gal. (49 liters), transmission and torque converter 8.5 gal. (32 liters), engine crankcase 4 gal. (15 liters), wheel ends 16 pts. (7.5 liters) ea., differential 34 pts. (16 liters) ea.

## OPTIONS

1. Enclosed cab with built in ROPS, windshield wipers, front and rear tinted glass, dome light, lockable doors
2. Open ROPS
3. Heater and defroster fan
4. Air conditioning
5. Cold weather starting kit

# REXWORKS

P.O. Box 2037  
Milwaukee, Wisconsin 53201  
TELEX 26-9576  
International Offices: Milwaukee, Bogota, Miami,  
Athens, Singapore, Paris

Distributors in all principal cities of the world

**NIXON EQUIPMENT CO.**  
12050 CLARK STREET  
SANTA FE SPRINGS, CA. 90721  
(916) 944-8061

**APPENDIX C  
CLAY STOCKPILE AND TEST PAD RESULTS**



**APPENDIX C-1**  
**Laboratory Test Summary Table and Results**

**TABLE C-1**  
**SUMMARY OF GEOTECHNICAL LABORATORY TEST RESULTS**  
**CLAY SOURCE TESTING - PECTEN CLAYSTONE**  
**KETTLEMAN HILLS FACILITY, KINGS COUNTY, CALIFORNIA**

Site Sample No.	Date Sampled	Source	Atterberg Limits			Soil Classification (ASTM D 2487)	Fines Content		Laboratory		Permeability (ASTM D5084)		
			LL	PL	PI		% < # 200 Sieve	Natural Moisture Content %	Maximum Dry Density lb/ft <sup>3</sup>	Optimum Moisture %	Dry Unit Weight lb/ft <sup>3</sup>	Moisture Content %	Hydraulic Conductivity cm/s
CL-1	07/16/08	Clay stockpile	95	33	62	CH	87.4	15.3	111.0	17.3	99.1	19.1	9.3E-08
CL-2	07/24/08	Clay stockpile	61	23	38	CH	73.8	8.1	119.7	12.5	107.6	14.7	6.3E-08
CL-3	07/24/08	Clay stockpile	110	41	69	CH	93.5	22.6	106.0	18.0	96.9	20.1	4.0E-08
CL-4	07/27/08	Clay stockpile	88	27	61	CH	90.7	12.4	111.9	15.4	103.0	17.2	4.9E-08
CL-5	07/27/08	Clay test pad							113.6	16.0			
CL-6	07/31/08	Clay test pad	92	21	71						105.6	18.4	5.3E-09
CL-7	07/31/08	Clay test pad	90	23	67						100.0	20.6	3.6E-09
CL-8	07/31/08	Clay test pad	88	27	61						103.1	20.9	1.0E-08
CL-9	07/31/08	Clay test pad	88	29	59						104.6	21.2	3.1E-09
CL-10	08/03/08	Clay test pad							113.1	17.9			
CL-11	08/03/08	Clay stockpile	94	30	64	CH	89.8	16.2	112.8	16.6	103.5	18.3	2.3E-08
CL-12	08/04/08	Test Pad / FDT 5						20.4					
CL-13	08/04/08	Test Pad / FDT 8						18.9					
CL-14	08/04/08	Test Pad / FDT 14						20.6					
CL-15	08/07/08	Clay test pad							110.0	17.4			
CL-16	08/07/08	Clay test pad	98	31	67	CH	89.5	19.2			103.3	19.2	9.0E-09
CL-17	08/07/08	Clay test pad	99	30	69	CH	87.8	18.4			109.4	17.7	2.6E-09
CL-18	08/07/08	Clay test pad	95	27	68	CH	90.3	18.7			105.1	19.5	5.8E-09
CL-19	08/07/08	Clay test pad	98	32	66	CH	91.2	17.7			109.0	18.3	4.4E-09
CL-20	08/07/08	Clay test pad	95	28	67	CH	93.6	20			109.3	18.0	4.7E-09
CL-21	08/07/08	Clay test pad	103	29	74	CH	91.4	18.5			108.4	18.7	2.7E-09
CL-22	08/08/08	Clay stockpile	98	32	66	CH	87.2	15.7	107.4	18.1	98.7	20.3	5.8E-08
CL-23	08/11/08	Clay stockpile	89	27	62	CH	85.8	9.9	112.1	15.2	103.0	17.4	6.4E-08

Average:	93	29	64				89	17	112	16	104	19	2.6E-08
Max:	110	41	74				94	23	120	18	109	21	9.3E-08
Min:	61	21	38				74	8	106	13	97	15	2.6E-09

FDT = Field Density Test  
L = Lift Number

**TABLE C-2**  
**SUMMARY OF GEOTECHNICAL LABORATORY TEST RESULTS - STOCKPILE SAMPLES**  
**CLAY SOURCE TESTING - PECTEN CLAYSTONE**  
**KETTLEMAN HILLS FACILITY, KINGS COUNTY, CALIFORNIA**

Site Sample No.	Date Sampled	Source	Atterberg Limits			Soil Classification (ASTM D 2487)	Fines Content		Laboratory		Permeability (ASTM D5084)		
			LL	PL	PI		% < # 200 Sieve	Natural Moisture Content %	Maximum Dry Density lb/ft <sup>3</sup>	Optimum Moisture %	Dry Unit Weight lb/ft <sup>3</sup>	Moisture Content %	Hydraulic Conductivity cm/s
CL-1	07/16/08	Clay stockpile	95	33	62	CH	87.4	15.3	111.0	17.3	99.1	19.1	9.3E-08
CL-2	07/24/08	Clay stockpile	61	23	38	CH	73.8	8.1	119.7	12.5	107.6	14.7	6.3E-08
CL-3	07/24/08	Clay stockpile	110	41	69	CH	93.5	22.6	106.0	18.0	96.9	20.1	4.0E-08
CL-4	07/27/08	Clay stockpile	88	27	61	CH	90.7	12.4	111.9	15.4	103.0	17.2	4.9E-08
CL-11	08/03/08	Clay stockpile	94	30	64	CH	89.8	16.2	112.8	16.6	103.5	18.3	2.3E-08
CL-22	08/08/08	Clay stockpile	98	32	66	CH	87.2	15.7	107.4	18.1	98.7	20.3	5.8E-08
CL-23	08/11/08	Clay stockpile	89	27	62	CH	85.8	9.9	112.1	15.2	103.0	17.4	6.4E-08
Average:			91	30	60		87	14	112	16	102	18	5.6E-08
Max:			110	41	69		94	23	120	18	108	20	9.3E-08
Min:			61	23	38		74	8	106	13	97	15	2.3E-08

**TABLE C-3**  
**SUMMARY OF GEOTECHNICAL LABORATORY TEST RESULTS - TEST PAD SAMPLES**  
**CLAY SOURCE TESTING - PECTEN CLAYSTONE**  
**KETTLEMAN HILLS FACILITY, KINGS COUNTY, CALIFORNIA**

Site Sample No.	Date Sampled	Source	Atterberg Limits			Soil Classification (ASTM D 2487)	Fines Content		Laboratory		Permeability (ASTM D5084)		Hydraulic Conductivity cm/s
			LL %	PL %	PI		% < # 200 Sieve	Natural Moisture Content %	Maximum Dry Density lb/ft <sup>3</sup>	Optimum Moisture %	Dry Unit Weight lb/ft <sup>3</sup>	Moisture Content %	
CL-5	07/27/08	Clay test pad							113.6	16.0			
CL-6	07/31/08	Clay test pad	92	21	71						105.6	18.4	5.3E-09
CL-7	07/31/08	Clay test pad	90	23	67						100.0	20.6	3.6E-09
CL-8	07/31/08	Clay test pad	88	27	61						103.1	20.9	1.0E-08
CL-9	07/31/08	Clay test pad	88	29	59						104.6	21.2	3.1E-09
CL-10	08/03/08	Clay test pad							113.1	17.9			
CL-12	08/04/08	Test Pad / FDT 5						20.4					
CL-13	08/04/08	Test Pad / FDT 8						18.9					
CL-14	08/04/08	Test Pad / FDT 14						20.6					
CL-15	08/07/08	Clay test pad							110.0	17.4			
CL-16	08/07/08	Clay test pad	98	31	67	CH	89.5	19.2			103.3	19.2	9.0E-09
CL-17	08/07/08	Clay test pad	99	30	69	CH	87.8	18.4			109.4	17.7	2.6E-09
CL-18	08/07/08	Clay test pad	95	27	68	CH	90.3	18.7			105.1	19.5	5.8E-09
CL-19	08/07/08	Clay test pad	98	32	66	CH	91.2	17.7			109.0	18.3	4.4E-09
CL-20	08/07/08	Clay test pad	95	28	67	CH	93.6	20			109.3	18.0	4.7E-09
CL-21	08/07/08	Clay test pad	103	29	74	CH	91.4	18.5			108.4	18.7	2.7E-09
Average:			95	28	67		91	19	112	17	106	19	5.1E-09
Max:			103	32	74		94	21	114	18	109	21	1.0E-08
Min:			88	21	59		88	18	110	16	100	18	2.6E-09

**GEOMETRIC MEAN**  
 $5.35 \times 10^{-9}$

FDT = Field Density Test  
L = Lift Number

**SOIL SAMPLE LOG**

PROJECT: Kettleman Hills Landfill

LOCATION: Kettleman City, CA.

DESCRIPTION: Cell B17, Phase A1 Clay test pad

PROJECT NO.: SC0472

TASK NO.: 03/1

YEAR: 2008

SITE SAMPLE NO.	LAB SAMPLE NO.	VISUAL DESCRIPTION	SOURCE (LOCATION/DEPTH)	MATERIAL TYPE	DATE SAMPLED (day/mo)	TEST METHODS ASTM	QA ID
7	CL-1	Brownish grey clay	Clay stockpile	Clay liner soil	16/17	D422, 4318, 1557, 5084	JD
8	CL-2				24/17		JD
9	CL-3				24/17		JD
11	CL-4				27/17		JD
12	CL-5				27/17		JD
22	CL-6		Clay test pad/L-2		27/17	D1557	DW
23	CL-7		Clay test pad/lift 3		31/17	D 5084	DW
24	CL-8						JD
25	CL-9						JD
26	CL-10						JD
27	CL-11		Clay Test pad / L-4		3/8	D1557	JW
28	CL-12	Brownish grey clay	Clay stock pile		3/8	D422, 1557, 4318, 5084	DW
29	CL-13		Test pad / L-4 / FDT 5		4/8	D 2216	DW
30	CL-14		Test pad / L-4 / FDT 8				DW
31	CL-15		Test pad / L-5 / FDT 14				DW
32	CL-16		Clay test pad / L-6		7/8	D 1557	DW
33	CL-17		Clay Test pad / L-7		7/8	D5084	JD
34	CL-18						
35	CL-19						
36	CL-20						
37	CL-21						

NOTES:





**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 6786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-01  
 Lab Sample No: G115

ASTM C 136, D 422, D 854,  
 D 1146, D2216, D 2487, D4318

**SOIL INDEX PROPERTIES**


Graze Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits



Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	97.0
#10	2.00	95.9
#20	0.850	95.2
#40	0.425	94.4
#60	0.250	92.6
#100	0.150	89.6
#200	0.075	87.4

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	3.0
Sand (%):	9.6
Fines (%):	87.4
Silt (%):	
Clay (%):	



Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):

Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-01	G115	15.3	87.4	95	33	62	CH - Fat clay

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 850 1666 Fax: (770) 850 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-02  
 Lab Sample No: G124

ASTM C 136, D 422, D 854,  
 D 1140, D2216, D 2487, D4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	99.6
#10	2.00	99.4
#20	0.850	99.2
#40	0.425	98.0
#60	0.250	94.3
#100	0.150	84.6
#200	0.075	73.8

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	0.4
Sand (%):	25.8
Fines (%):	73.8
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-02	G124	8.1	73.8	61	23	38	CH - Fat clay with sand

Note(s):





# Excel Geotechnical Testing, Inc.

"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill

Project No: 309


Client Sample ID: CL-03

Lab Sample No: G147

ASTM C 136, D 422, D 854,  
 D 1140, D2216, D 2407, D4318

## SOIL INDEX PROPERTIES

Grain Size, Spec. Gravity, Moist. Content,  
 Exp. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.8
#20	0.850	99.1
#40	0.425	98.3
#60	0.250	97.2
#100	0.150	95.9
#200	0.075	93.5

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	
Sand (%):	6.5
Fines (%):	93.5
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):	
-----------------------	--



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-03	G147	22.6	93.5	110	41	69	CH - Fat clay

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30076  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill

Project No: 309


Client Sample ID: CL-04

Lab Sample No: G166

ASTM C 136, D 422, D 854,  
 D 1140, D2216, D 2487, D4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.9
#20	0.850	99.7
#40	0.425	98.8
#60	0.250	97.1
#100	0.150	94.0
#200	0.075	90.7

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	
Sand (%):	9.3
Fines (%):	90.7
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-04	G166	12.4	90.7	88	27	61	CH - Fat clay

Note(s):



# Excel Geotechnical Testing, Inc.

"Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
Project No: 309  
Client Sample ID: CL-11  
Lab Sample No: H043

ASTM C 136, D 422, D 854,  
D 1146, D2216, D 2487, D4318

## SOIL INDEX PROPERTIES

Grain Size, Spec. Gravity, Moist. Content,  
Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	99.6
#10	2.00	99.4
#20	0.850	99.2
#40	0.425	98.6
#60	0.250	96.6
#100	0.150	93.4
#200	0.075	89.8

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	0.4
Sand (%):	9.8
Fines (%):	89.8
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):	
-----------------------	--



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-11	H043	16.2	89.8	94	30	64	CH - Fat clay

Notes:



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30076  
 Tel: (770) 660 1666 Fax: (770) 660 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-16  
 Lab Sample No: H051

ASTM C 136, D 75, D 854,  
 D 1148, D2116, D 2487, D-9318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
 Exp. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.6
#20	0.850	98.9
#40	0.425	98.1
#60	0.250	96.4
#100	0.150	93.3
#200	0.075	89.5

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	
Sand (%):	10.5
Fines (%):	89.5
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	Pt (-)	
CL-16	H051	19.2	89.5	98	31	67	CH - Fat clay

Note(s):



**Excel Geotechnical Testing, Inc.**  
"Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kentleman B-17 Landfill  
Project No: 309  
Client Sample ID: CL-17  
Lab Sample No: H053

ASTM C 136, D 423, D 854,  
D 1140, D2029, D 2491, D4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
Seg. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	98.6
#4	4.75	97.4
#10	2.00	96.5
#20	0.850	95.6
#40	0.425	94.9
#60	0.250	93.4
#100	0.150	90.9
#200	0.075	87.8

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	2.6
Sand (%):	9.6
Fines (%):	87.8
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-17	H053	18.4	87.8	99	30	69	CH - Fat clay

Notes:



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-18  
 Lab Sample No: H055

ASTM C 136, D 422, D 844,  
 D 1149, D2216, D 3487, D4188

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	100.0
#10	2.00	99.4
#20	0.850	98.7
#40	0.425	97.9
#60	0.250	96.4
#100	0.150	93.6
#200	0.075	90.3

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%)	
Sand (%)	9.7
Fines (%)	90.3
Silt (%)	
Clay (%)	

Coeff. Unif. (Cu)	
Coeff. Curv. (Cc)	

Specific Gravity ( - ):  



Client Sample ID	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-18	H055	18.7	90.3	95	27	68	CH - Fat clay

Note(s)



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**Project Name:** Kettleman B-17 Landfill  
**Project No:** 309  
**Client Sample ID:** CL-19  
**Lab Sample No:** H057

ASTM C 136, D 152, D 854,  
 D 1140, D 3314, D 3497, D 4318

**SOIL INDEX PROPERTIES**

Grain Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	99.8
#10	2.00	98.9
#20	0.850	98.2
#40	0.425	97.3
#60	0.250	96.0
#100	0.150	93.7
#200	0.075	91.2

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	0.2
Sand (%):	8.6
Fines (%):	91.2
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-19	H057	17.7	91.2	98	32	66	CH - Fat clay

Note(s):



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-20  
 Lab Sample No: H058

ASTM C 136, D 475, D 484,  
 D 5140, D1226, D 2487, D4310

**SOIL INDEX PROPERTIES**

Grain Size, Spcn, Grad-by, Moist, Consist,  
 Eng. Classification, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	98.7
#10	2.00	97.9
#20	0.850	98.3
#40	0.425	97.6
#60	0.250	97.0
#100	0.150	95.8
#200	0.075	93.6

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	1.3
Sand (%):	5.1
Fines (%):	93.6
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):



Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-20	H058	20.0	93.6	95	28	67	CH - Fat clay

Note(s):





**Excel Geotechnical Testing, Inc.**  
"Excellence in Testing"


941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
Project No: 309  
Client Sample ID: CL-21  
Lab Sample No: H061

ASTM C 136, D 422, D 854,  
D 8140, D 2216, D 2487, D 2414

**SOIL INDEX PROPERTIES**

Grain Size, Spet. Gravity, Moist. Content,  
Plas. Characteristics, Atterberg Limits




Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	100.0
#4	4.75	99.8
#10	2.00	99.4
#20	0.850	98.8
#40	0.425	98.1
#60	0.250	96.7
#100	0.150	94.2
#200	0.075	91.4

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	0.2
Sand (%):	8.4
Fines (%):	91.4
Silt (%):	
Clay (%):	

Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (G<sub>s</sub>):



Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-21	H061	18.5	91.4	103	29	74	CH - Fat clay

Notes:



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 6786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-22  
 Lab Sample No: H078

ASTM C 136, D 422, D 854,  
 D 1140, D2216, D 2487, D4318

**SOIL INDEX PROPERTIES**


Grain Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits



Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	98.3
#4	4.75	97.8
#10	2.00	97.4
#20	0.850	97.3
#40	0.425	96.5
#60	0.250	93.5
#100	0.150	90.1
#200	0.075	87.2

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	2.2
Sand (%):	10.6
Fines (%):	87.2
Silt (%):	
Clay (%):	



Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Specific Gravity (-):

Client Sample ID.	Lab Sample No.	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-22	H078	15.7	87.2	98	32	66	CH - Fat clay

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-23  
 Lab Sample No: H080

ASTM C 136, D 422, D 854,  
 D 1140, D3116, D 2487, D4318

**SOIL INDEX PROPERTIES**


Grain Size, Spec. Gravity, Moist. Content,  
 Eng. Classification, Atterberg Limits



Sieve No.	Size (mm)	% Finer
3"	75	100.0
2"	50	100.0
1.5"	37.5	100.0
1"	25	100.0
3/4"	19	100.0
3/8"	9.5	98.7
#4	4.75	97.9
#10	2.00	96.6
#20	0.850	95.3
#40	0.425	93.4
#60	0.250	91.6
#100	0.150	89.4
#200	0.075	85.8

Hydrometer Particle Diameter (mm)	% Finer

Gravel (%):	2.1
Sand (%):	12.1
Fines (%):	85.8
Silt (%):	
Clay (%):	



Specific Gravity (-):	
Coeff. Unif. (Cu):	
Coeff. Curv. (Cc):	

Client Sample ID	Lab Sample No	Moisture Content (%)	Fines Content < No. 200 (%)	Atterberg Limits			Engineering Classification
				LL (-)	PL (-)	PI (-)	
CL-23	H080	9.9	85.8	89	27	62	CH - Fat clay

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 860 1666 Fax: (770) 850 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-01  
 Lab Sample No: G115

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CL-01	G115	111.0	17.3	

Note(s)



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-02  
 Lab Sample No: G124

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CL-02	G124	119.7	12.5	

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-03  
 Lab Sample No: G147

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CL-03	G147	106.0	18.0	

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-04  
 Lab Sample No: G166

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CL-04	G166	111.9	15.4	

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 850 1866 Fax: (770) 850 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-05  
 Lab Sample No: G167

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CL-05	G167	113.6	16.0	

Note(s):





**Excel Geotechnical Testing, Inc.**  
*"Excellence In Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-10  
 Lab Sample No: H042

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CL-10	H042	113.1	17.9	

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-11  
 Lab Sample No: H043

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CL-11	H043	112.8	16.6	

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30076  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-15  
 Lab Sample No: H065

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CL-15	H065	110.0	17.4	

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 850 1686 Fax: (770) 850 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-22  
 Lab Sample No: H078

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CL-22	H078	107.4	18.1	

Note(s):



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*


941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

Project Name: Kettleman B-17 Landfill  
 Project No: 309  
 Client Sample ID: CL-23  
 Lab Sample No: H080

ASTM D 1557

**COMPACTION MOISTURE-DENSITY RELATIONSHIP**

Modified - Method B



Client/Site Sample ID.	Lab Sample No:	Maximum Dry Unit Weight (pcf)	Optimum Moisture Content (%)	Remarks
CL-23	H080	112.1	15.2	

Note(s):



# Excel Geotechnical Testing, Inc.

"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

## FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>

ASTM D5084 \*

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-01
<b>Lab Sample Number:</b>	G115
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	7/27/2008

Remolded Specimen	Proctor <sup>(5)</sup>		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity
	Compaction		Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
	Max. DUW (pcf)	Opt. MC (%)								
(-)										
Notes 2, 3 & 4	110.0	17.3	99.1	19.1	72.0	70.0	2.0	DTW	12	9.3E-8

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 90% of the maximum dry unit weight and the optimum moisture content plus 2%.
7. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations.

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



# Excel Geotechnical Testing, Inc.

"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075

Tel: (770) 650 1666 Fax: (770) 650 5786

## FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>

ASTM D5084 \*

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-02
<b>Lab Sample Number:</b>	G124
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	7/27/2008

Remolded Specimen	Proctor <sup>(5)</sup>		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity (cm/s)
	Compaction		Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
	Max. DUW (pcf)	Opt. MC (%)								
(-)										
Notes 2, 3 & 4	119.7	12.5	107.6	14.7	72.0	70.0	2.0	DTW	14	6.3E-8

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 90% of the maximum dry unit weight and the optimum moisture content plus 2%.
7. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

**\* Deviations:**

Laboratory temperature at 22±3 °C.  
Test specimen final conditions are not presented.



# Excel Geotechnical Testing, Inc.

"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

## FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup> ASTM D5084 \*

Project Name:	Kettleman B-17 Landfill
Project Number:	309
Client Name:	Geosyntec Consultants
Site Sample ID:	CL-03
Lab Sample Number:	G147
Material Type:	Soil
Specified Value (cm/sec):	NA
Date Test Started:	8/01/2008

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity
	Max. DUW	Opt. MC	Dry Unit Weight	Moisture Content	Cell Press.	Back Press.	Consolid. Press.	Permeant Liquid <sup>(7)</sup>	Average Gradient	
(-)	(pcf)	(%)	(pcf)	(%)	(psi)	(psi)	(psi)	(-)	(-)	(cm/s)
Notes 2, 3 & 4	106.0	18.0	96.9	20.1	72.0	70.0	2.0	DTW	14	4.0E-8

### Notes:

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
- Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
- Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
- Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
- Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 2%.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

### \* Deviations:

Laboratory temperature at 22±3 °C.  
Test specimen final conditions are not presented.





**Excel Geotechnical Testing, Inc.**

"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST** <sup>(1)</sup>

**ASTM D5084 \***

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-04
<b>Lab Sample Number:</b>	G166
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/02/2008

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
(-)	(pcf)	(%)	(pcf)	(%)	(psi)	(psi)	(psi)	(-)	(-)	(cm/s)
Notes 2, 3 & 4	111.9	15.4	103.0	17.2	72.0	70.0	2.0	DTW	16	4.9E-8

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
- Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
- Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
- Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
- Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 2%.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



# Excel Geotechnical Testing, Inc.

"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

## FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>

ASTM D 5084 \*

Project Name:	Kettleman B-17 Landfill
Project Number:	309
Client Name:	Geosyntec Consultants
Site Sample ID:	CL-06
Lab Sample Number:	H021
Material Type:	Soil
Specified Value (cm/sec):	NA
Date Test Started:	8/04/2008

Specimen No.	Test Specimen Initial Condition					Test Conditions					Hydraulic Conductivity (cm/s)
	Spec. Prep. <sup>(2)</sup> (-)	Spec. Length (cm)	Spec. Diameter (cm)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(3)</sup> (-)	Average Gradient (-)	
I	ST	5.67	7.21	105.6	18.4	72.0	70.0	2.0	DTW	13	5.3E-9

Atterberg Test Results (LL, PL, PI) - ASTM D 4318: 

92	21	71
----	----	----

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- Specimen preparation: ST = Shelby Tube, R = Remolded, B = Block Sample.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
Test specimen final conditions are not presented.



# Excel Geotechnical Testing, Inc.

"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

## FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>

ASTM D 5084 \*

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-07
<b>Lab Sample Number:</b>	H023
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/04/2008

Specimen No.	Test Specimen Initial Condition					Test Conditions					Hydraulic Conductivity (cm/s)
	Spec. Prep. <sup>(2)</sup> (-)	Spec. Length (cm)	Spec. Diameter (cm)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(3)</sup> (-)	Average Gradient (-)	
1	ST	5.68	7.26	100.0	20.6	72.0	70.0	2.0	DTW	15	3.6E-9

Atterberg Test Results (LL, PL, PI) - ASTM D 4318: 

90	23	67
----	----	----

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- Specimen preparation: ST = Shelby Tube, R = Remolded, B = Block Sample.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



# Excel Geotechnical Testing, Inc.

"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

## FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>

ASTM D 5084 \*

**Project Name:**

Kettleman B-17 Landfill

**Project Number:**

309

**Client Name:**

Geosyntec Consultants

**Site Sample ID:**

CL-08

**Lab Sample Number:**

H025

**Material Type:**

Soil

**Specified Value (cm/sec):**

1.0E-7

**Date Test Started:**

8/04/2008

Specimen No.	Test Specimen Initial Condition					Test Conditions					Hydraulic Conductivity (cm/s)
	Spec. Prep. <sup>(2)</sup> (-)	Spec. Length (cm)	Spec. Diameter (cm)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(3)</sup> (-)	Average Gradient (-)	
1	ST	5.63	7.20	103.1	20.9	72.0	70.0	2.0	DTW	9	1.0E-8

**Atterberg Test Results (LL, PL, PI) - ASTM D 4318:**

88    27    61

### Notes:

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- Specimen preparation: ST = Shelby Tube, R = Remolded, B = Block Sample.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

### \* Deviations:

Laboratory temperature at 22±3 °C.  
Test specimen final conditions are not presented.



# Excel Geotechnical Testing, Inc.

"Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

## FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>

ASTM D 5084 \*

Project Name:

Kettleman B-17 Landfill

Project Number:

309

Client Name:

Geosyntec Consultants

Site Sample ID:

CL-09

Lab Sample Number:

H027

Material Type:

Soil

Specified Value (cm/sec):

NA

Date Test Started:

8/04/2008

Specimen No.	Test Specimen Initial Condition					Test Conditions					Hydraulic Conductivity (cm/s)
	Spec. Prep. <sup>(2)</sup> (-)	Spec. Length (cm)	Spec. Diameter (cm)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(3)</sup> (-)	Average Gradient (-)	
1	ST	5.64	7.18	104.6	21.2	72.0	70.0	2.0	DTW	16	3.1E-9

Atterberg Test Results (LL, PL, PI) - ASTM D 4318:

88	29	59
----	----	----

### Notes:

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- Specimen preparation: ST = Shelby Tube, R = Remolded, B = Block Sample.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

### \* Deviations:

Laboratory temperature at 22±3 °C.  
Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D5084 \***

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-11
<b>Lab Sample Number:</b>	H043
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/16/2008

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity (cm/s)
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
(-)										
Notes 2, 3 & 4	112.8	16.6	103.5	18.3	72.0	70.0	2.0	DTW	8	2.3E-8

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
- Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
- Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
- Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
- Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 2%.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**

"Excellence in Testing"

841 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D 5084 \***

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-16
<b>Lab Sample Number:</b>	H050
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/09/2008

Specimen No.	Test Specimen Initial Condition					Test Conditions					Hydraulic Conductivity (cm/s)
	Spec. Prep. <sup>(2)</sup> (-)	Spec. Length (cm)	Spec. Diameter (cm)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(3)</sup> (-)	Average Gradient (-)	
1	ST	5.70	7.10	103.3	19.2	72.0	70.0	2.0	DTW	13	9.0E-9

**Atterberg Test Results (LL, PL, PI) - ASTM D 4318:**

98	31	67
----	----	----

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. Specimen preparation: ST = Shelby Tube, R = Remolded, B = Block Sample.
3. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**

*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D 5084 <sup>\*</sup>**

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-17
<b>Lab Sample Number:</b>	H052
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/09/2008

Specimen No.	Test Specimen Initial Condition					Test Conditions					Hydraulic Conductivity (cm/s)
	Spec. Prep. <sup>(2)</sup> (-)	Spec. Length (cm)	Spec. Diameter (cm)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(3)</sup> (-)	Average Gradient (-)	
1	ST	5.66	7.16	109.4	17.7	72.0	70.0	2.0	DTW	16	2.6E-9

**Atterberg Test Results (LL, PL, PI) - ASTM D 4318:**

99	30	69
----	----	----

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- Specimen preparation: ST = Shelby Tube, R = Remolded, B = Block Sample.
- Type of permeant liquid: DTW = Desired Tap Water, DDI = Desired Deionized Water

**\* Deviations:**

Laboratory temperature at 22±3 °C.  
Test specimen final conditions are not presented.





**Excel Geotechnical Testing, Inc.**

*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**

**ASTM D 5084 \***

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-18
<b>Lab Sample Number:</b>	H054
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/09/2008

Specimen No.	Test Specimen Initial Condition					Test Conditions					Hydraulic Conductivity (cm/s)
	Spec. Prep. <sup>(2)</sup> (-)	Spec. Length (cm)	Spec. Diameter (cm)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(3)</sup> (-)	Average Gradient (-)	
1	ST	5.69	7.07	105.1	19.5	72.0	70.0	2.0	DTW	14	5.8E-9

**Atterberg Test Results (LL, PL, PI) - ASTM D 4318:**

95	27	68
----	----	----

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. Specimen preparation: ST = Shelby Tube, R = Remolded, B = Block Sample.
3. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

**\* Deviations:**

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"

941 Farrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 850 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D 5084 \***

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-19
<b>Lab Sample Number:</b>	H056
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/09/2008

Specimen No.	Test Specimen Initial Condition					Test Conditions					Hydraulic Conductivity (cm/s)
	Spec. Prep. <sup>(2)</sup> (-)	Spec. Length (cm)	Spec. Diameter (cm)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(3)</sup> (-)	Average Gradient (-)	
1	ST	5.71	7.15	109.0	18.3	72.0	70.0	2.0	DTW	14	4.4E-9

**Atterberg Test Results (LL, PL, PI) - ASTM D 4318:**

98	32	66
----	----	----

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- Specimen preparation: ST = Shelby Tube, R = Remolded, B = Block Sample.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5788

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D 5084 \***

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-20
<b>Lab Sample Number:</b>	H059
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/09/2008

Specimen No.	Test Specimen Initial Condition					Test Conditions					Hydraulic Conductivity (cm/s)
	Spec. Prep. <sup>(2)</sup> (-)	Spec. Length (cm)	Spec. Diameter (cm)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(3)</sup> (-)	Average Gradient (-)	
1	ST	5.63	7.19	109.3	18.0	72.0	70.0	2.0	DTW	14	4.7E-9

**Atterberg Test Results (LL, PL, PI) - ASTM D 4318:**

95	28	67
----	----	----

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- Specimen preparation: ST = Shelby Tube, R = Remolded, B = Block Sample.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**  
 "Excellence in Testing"

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1866 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D 5084 \***

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-21
<b>Lab Sample Number:</b>	H060
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/09/2008

Specimen No.	Test Specimen Initial Condition					Test Conditions					Hydraulic Conductivity (cm/s)
	Spec. Prep. <sup>(2)</sup> (-)	Spec. Length (cm)	Spec. Diameter (cm)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(3)</sup> (-)	Average Gradient (-)	
1	ST	5.62	7.24	108.4	18.7	72.0	70.0	2.0	DTW	15	2.7E-9

**Atterberg Test Results (LL, PL, PI) - ASTM D 4318:**

103	29	74
-----	----	----

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- Specimen preparation: ST = Shelby Tube, R = Remolded, B = Block Sample.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**

*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075

Tel: (770) 650 1666 Fax: (770) 650 6786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**

**ASTM D5084 \***

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-22
<b>Lab Sample Number:</b>	H078
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/22/2008

Remolded Specimen	Proctor <sup>(5)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity (cm/s)
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
(-)										
Notes 2, 3 & 4	107.4	18.1	98.7	20.3	72.0	70.0	2.0	DTW	14	5.8E-8

**Notes:**

1. Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
2. All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
3. Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
4. Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
5. Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
6. Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 2%.
7. Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.



**Excel Geotechnical Testing, Inc.**

*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**FLEXIBLE WALL PERMEABILITY TEST <sup>(1)</sup>**  
**ASTM D5084 \***

<b>Project Name:</b>	Kettleman B-17 Landfill
<b>Project Number:</b>	309
<b>Client Name:</b>	Geosyntec Consultants
<b>Site Sample ID:</b>	CL-23
<b>Lab Sample Number:</b>	H080
<b>Material Type:</b>	Soil
<b>Specified Value (cm/sec):</b>	NA
<b>Date Test Started:</b>	8/22/2008

Remolded Specimen	Proctor <sup>(3)</sup> Compaction		Specimen Initial Conditions <sup>(6)</sup>		Test Conditions					Hydraulic Conductivity (cm/s)
	Max. DUW (pcf)	Opt. MC (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Cell Press. (psi)	Back Press. (psi)	Consolid. Press. (psi)	Permeant Liquid <sup>(7)</sup> (-)	Average Gradient (-)	
(-)										
Notes 2, 3 & 4	112.1	15.2	103.0	17.4	72.0	70.0	2.0	DTW	13	6.4E-8

**Notes:**

- Method C, "Falling-Head, Increasing-Tailwater" test procedures were followed during the testing.
- All particles larger than 3/8 inch, if any, were discarded when forming the remolded specimen.
- Remolded specimen was formed by tamping the soil in one-centimeter-thick layers.
- Remolded specimen approximately 2.87 inches in diameter and 2.36 inches in height.
- Maximum Dry Unit Weight (DUW) and Optimum Moisture Content (MC) based on Modified Proctor Compaction Test (ASTM D 1557).
- Based on the target values of 92% of the maximum dry unit weight and the optimum moisture content plus 2%.
- Type of permeant liquid: DTW = Deaired Tap Water, DDI = Deaired Deionized Water

\* Deviations:

Laboratory temperature at 22±3 °C.  
 Test specimen final conditions are not presented.

**APPENDIX C-2**  
**Test Pad Compaction Test Results**

**SUMMARY OF FIELD DENSITY TEST**

PROJECT: Kettleman Hills Facility - Clay Source Evaluation  
 LOCATION: Kings County, CA  
 CONTRACTOR: Wood Brothers, Inc.

PROJECT NO.: SC0472  
 TASK NO.: 1  
 DATE: \_\_\_\_\_

**SPECIFICATION REQUIREMENTS**

SOURCE: On-site clay  
 % COMPACTION: 92% MOISTURE RANGE: 19.3% to 22.3% at/d  
18.0% to 21.0% (Samples 61-76)  
 NUCLEAR GAUGE TYPE: Troxler 3440 A NUCLEAR GAUGE SERIAL NO.: 20202

DATE OF TEST (day/mo)	TEST NO.	TEST LOCATION		LAB RESULTS			TYPE OF TEST		FIELD TEST RESULTS				PERCENT COMPACT (%)	PASS/ FAIL	RETEST NO	QA ID
				SAMPLE NO.	MAX UNIT WT (pcf)	O.M.C. (%)	ASTM D-2922	ASTM D-1556	DEPTH/ELEV (ft)	WET UNIT WT (pcf)	DRY UNIT WT (pcf)	F.M.C. (%)				
29/7	11	B-2	0-6"	CL-1	111.0	17.3			0.5	125.3	100.8	24.4	90.8	Fail	17	JD
29/7	12	B-4	0-6"	CL-1	111.0	17.3			0.5	125.2	102.1	22.7	92.0	Pass*	--	JD
29/7	13	C-3	0-6"	CL-1	111.0	17.3			0.5	125.0	103.8	21.4	93.5	Pass	--	JD
29/7	14	D-4	0-6"	CL-1	111.0	17.3			0.5	123.1	98.6	25.6	88.3	Fail	18	JD
29/7	15	E-2	0-6"	CL-1	111.0	17.3			0.5	125.5	102.7	22.2	92.5	Pass	--	JD
29/7	16	D-4	0-6"	CL-1	111.0	17.3			0.5	123.8	100.9	22.7	90.9	Fail	18	JD
29/7	17	B-2	0-6"	CL-1	111.0	17.3			0.5	123.1	100.1	22.9	90.2	Fail	19	JD
29/7	18	D-4	0-6"	CL-1	111.0	17.3			0.5	125.6	103.3	21.6	93.0	Pass	--	JD
29/7	19	B-2	0-6"	CL-1	111.0	17.3			0.5	123.3	99.9	23.4	90.0	Fail	20	JD
29/7	20	B-2	0-6"	CL-1	111.0	17.3			0.5	122.5	102.4	19.6	92.3	Pass	--	JD
30/7	21	D-5	6" - 12"	CL-1	111.0	17.3			0.5	121.7	101.5	19.9	91.4	Fail	27	JD
30/7	22	C-2	6" - 12"	CL-1	111.0	17.3			0.5	123.3	101.2	21.8	91.2	Fail	30	JD
30/7	23	B-2	6" - 12"	CL-1	111.0	17.3			0.5	123.2	101.6	21.2	91.5	Fail	28	JD
30/7	24	B-4	6" - 12"	CL-1	111.0	17.3			0.5	117.7	97.3	20.9	87.7	Fail	29	JD
30/7	25	D-4	6" - 12"	CL-1	111.0	17.3			0.5	114.4	97.8	23.2	88.1	Fail	26	JD
30/7	26	D-4	6" - 12"	CL-1	111.0	17.3			0.5	127.5	106.2	20.0	95.7	Pass	--	JD
30/7	27	E-5	6" - 12"	CL-1	111.0	17.3			0.5	124.0	102.8	20.6	92.6	Pass	--	JD
30/7	28	B-2	6" - 12"	CL-1	111.0	17.3			0.5	124.0	102.5	20.9	92.4	Pass	--	JD
30/7	29	B-4	6" - 12"	CL-1	111.0	17.3			0.5	129.7	103.1	20.9	92.9	Pass	--	JD
30/7	30	C-2	6" - 12"	CL-1	111.0	17.3			0.5	125.3	103.4	21.2	93.1	Pass	--	JD
30/7	31	D-5	12" - 18"	CL-1	111.0	17.3			0.5	124.6	102.9	20.5	92.7	Pass	--	JD
30/7	32	B-4	12" - 18"	CL-1	111.0	17.3			0.5	125.2	103.2	21.3	93.0	Pass	--	JD
30/7	33	D-2	12" - 18"	CL-1	111.0	17.3			0.5	125.2	103.8	20.6	93.5	Pass	--	JD
30/7	34	A-5	12" - 18"	CL-1	111.0	17.3			0.5	125.3	102.5	22.2	92.4	Pass	--	JD
30/7	35	B-2	12" - 18"	CL-1	111.0	17.3			0.5	127.0	107.5	18.1	96.9	Fail	NR	JD
30/7	36	C-3	18" - 24"	CL-1	111.0	17.3			0.5	123.8	101.0	22.6	91.0	Fail	37	JD
30/7	37	C-3	18" - 24"	CL-1	111.0	17.3			0.5	124.8	102.0	22.4	91.9	Fail	57	JD
30/7	38	D-3	18" - 24"	CL-1	111.0	17.3			0.5	125.6	102.6	21.8	92.4	Pass	--	JD
30/7	39	E-5	12" - 18"	CL-1	111.0	17.3			0.5	120.9	97.8	23.7	88.1	Fail	45	JD
30/7	40	E-3	12" - 18"	CL-1	111.0	17.3			0.5	123.8	101.0	22.6	91.0	Fail	42	JD
30/7	41	C-2	12" - 18"	CL-1	111.0	17.3			0.5	124.7	102.8	21.4	92.6	Pass	--	JD
30/7	42	E-3	12" - 18"	CL-1	111.0	17.3			0.5	125.3	102.2	22.9	92.1	Fail	46	JD
30/7	43	C-4	12" - 18"	CL-1	111.0	17.3			0.5	127.4	104.2	21.8	93.9	Pass	--	JD
30/7	44	B-4	12" - 18"	CL-1	111.0	17.3			0.5	126.4	103.6	22.0	93.4	Pass	--	JD
31/7	45	E-5	12" - 18"	CL-1	111.0	17.3			0.5	120.9	97.8	23.7	88.1	Fail	51	JD
31/7	46	E-3	12" - 18"	CL-1	111.0	17.3			0.5	123.8	101.0	22.6	91.0	Fail	48	JD
31/7	47	C-2	12" - 18"	CL-1	111.0	17.3			0.5	124.7	102.8	21.4	92.6	Pass	--	JD
31/7	48	E-3	12" - 18"	CL-1	111.0	17.3			0.5	125.3	102.2	22.9	92.1	Pass*	--	JD
31/7	49	C-4	12" - 18"	CL-1	111.0	17.3			0.5	127.4	104.2	21.8	93.9	Pass	--	JD
31/7	50	B-4	12" - 18"	CL-1	111.0	17.3			0.5	126.4	103.6	22.0	93.4	Pass	--	JD
01/8	51	E-5	12" - 18"	CL-1	111.0	17.3			0.5	120.9	97.8	23.7	88.1	Fail	--	JD
01/8	52	E-3	12" - 18"	CL-1	111.0	17.3			0.5	123.8	101.0	22.6	91.0	Fail	54	JD
01/8	53	C-2	12" - 18"	CL-1	111.0	17.3			0.5	124.7	102.8	21.4	92.6	Pass	--	JD
01/8	54	E-3	12" - 18"	CL-1	111.0	17.3			0.5	125.3	102.2	22.9	92.1	Pass*	--	JD
01/8	55	C-4	12" - 18"	CL-1	111.0	17.3			0.5	127.4	104.2	21.8	93.9	Pass	--	JD
01/8	56	B-4	12" - 18"	CL-1	111.0	17.3			0.5	126.4	103.6	22.0	93.4	Pass	--	JD
04/08	57	C-3	18" - 24"	CL-1	111.0	17.3			0.5	125.3	101.0	24.9	91.0	Fail	58	JD
04/08	58	C-3	18" - 24"	CL-1	111.0	17.3			0.5	126.2	102.0	23.7	91.9	Fail	63	JD
05/08	61	D-4	18" - 24"	CL-5	113.6	16.0			0.5	128.2	105.9	23.7	93.3	Fail	NR	JD
05/08	62	D-2	18" - 24"	CL-5	111.0	17.3			0.5	125.5	104.3	22.6	94.0	Pass**	--	JD
05/08	63	C-3	18" - 24"	CL-5	113.6	16.0			0.5	128.2	106.0	21.4	93.3	Pass	--	JD
05/08	64	B-4	18" - 24"	CL-5	113.6	16.0			0.5	127.5	105.9	22.9	93.2	Pass*	--	JD
05/08	65	B-2	18" - 24"	CL-5	113.6	16.0			0.5	127.0	105.3	21.8	92.7	Pass	--	JD
07/08	66	C-3	24" - 30"	CL-5	113.6	16.0			0.5	126.7	104.8	20.9	92.3	Pass	--	JD
07/08	67	B-4	24" - 30"	CL-5	113.6	16.0			0.5	124.5	104.9	19.6	92.4	Pass	--	JD
07/08	68	C-2	24" - 30"	CL-5	113.6	16.0			0.5	127.2	106.2	19.8	93.5	Pass	--	JD
07/08	69	A-1	24" - 30"	CL-5	113.6	16.0			0.5	125.0	105.4	18.6	92.8	Pass	--	JD
07/08	70	E-5	24" - 30"	CL-5	113.6	16.0			0.5	126.4	105.1	20.3	92.4	Pass	--	JD



DATE OF TEST (day/mo)	TEST NO.	TEST LOCATION		LAB RESULTS			TYPE OF TEST		FIELD TEST RESULTS				PERCENT COMPACT (%)	PASS/FAIL	RETEST NO.	QA ID
				SAMPLE NO.	MAX UNIT WT (pcf)	O.M.C. (%)	ASTM D-2922	ASTM D-1556	DEPTH/ELEV (ft)	WET UNIT WT (pcf)	DRY UNIT WT (pcf)	F.M.C. (%)				
07/08	71	D-4	30" - 36"	CL-5	113.6	16.0			0.5	130.4	109.9	18.6	96.8	Pass	--	JD
07/08	72	B-4	30" - 36"	CL-5	113.6	16.0			0.5	126.4	105.5	20.0	92.8	Pass	--	JD
07/08	73	C-3	30" - 36"	CL-5	113.6	16.0			0.5	126.8	104.1	21.4	91.6	Fail	NR	JD
07/08	74	D-2	30" - 36"	CL-5	113.6	16.0			0.5	127.9	107.3	19.2	94.4	Pass	--	JD
07/08	75	A-2	30" - 36"	CL-5	113.6	16.0			0.5	127.6	106.0	20.5	93.3	Pass	--	JD
07/08	76	D-4	30" - 36"	CL-5	113.6	16.0			0.5	127.5	106.8	19.4	94.1	Pass	--	JD

Tests 1-9: First lift was removed after significant failing tests.

Tests 59 and 60 were not recorded due to nuclear gauge malfunction.

Re-test of FDT 51 not recorded

Pass\* Moisture content was outside of range, but FDT was passed by Engineer.

Pass \*\* Previous proctor used for this test.

NR No Retest

Figure C-1: Location of Passing Field Density Tests  
 Clay Testpad  
 Kettleman Hills Facility, Kings County, California

Lift 1 - 0 to 6"					
	1	2	3	4	5
A					
B		X		X	
C			X		
D				X	
E		X			

Lift 2 - 6 to 12"					
	1	2	3	4	5
A					
B		X		X	
C		X			
D				X	
E					X

Lift 3 - 12 to 18"					
	1	2	3	4	5
A					X
B			XXXX		
C		XXX		XXX	
D		X			X
E			XX		

Lift 4 - 18 to 24"					
	1	2	3	4	5
A					
B		X		X	
C			X		
D		X	X		
E					

Lift 5 - 24 to 30"					
	1	2	3	4	5
A	X				
B				X	
C		X	X		
D					
E					X

Lift 6 - 30 to 36"					
	1	2	3	4	5
A		X			
B				X	
C					
D		X		XX	
E					

Note: Each box represents approximately 10 ft x 10 ft in the field  
 X' represents a passing field density test

**APPENDIX D  
SDRI Test Results**



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**Test Results Summary**

Project Name: Kettleman B-17 Landfill  
 Client Name: Geosyntec

**Index Test Results**

Sample Information				Test Information						Remarks
Site		Lab. No.	Moisture Content	Fines Content	Atterberg Limits			Soil Class.		
ID	Depth (ft)				ASTM D 2216 (%)	ASTM D 1140 (%)	ASTM D 4318			
	(-)	Top	Bottom	(-)			(-)	(-)	ASTM D 2487 (%)	
A	0.0	0.2	J079	73.5						
A	0.2	0.4	J080	59.6						
A	0.4	0.5	J081	51.4						
A	0.5	0.6	J082	49.2						
A	0.6	0.7	J083	50.2						
A	0.7	0.8	J084	52.0						
A	0.8	0.9	J085	48.1						
A	0.9	1.0	J086	45.2						
A	1.0	1.1	J087	43.6						
A	1.2	1.3	J089	42.8						
A	1.3	1.4	J090	38.9						
A	1.4	1.5	J091	34.3						
A	1.5	1.6	J092	32.6						
A	1.6	1.7	J093	31.7						
A	1.7	1.8	J094	33.6						
A	1.8	1.9	J095	29.0						
A	1.9	2.0	J096	22.7						



**Excel Geotechnical Testing, Inc.**  
*"Excellence in Testing"*

941 Forrest Street, Roswell, Georgia 30075  
 Tel: (770) 650 1666 Fax: (770) 650 5786

**Test Results Summary**

Project Name: Kettleman B-17 Landfill  
 Client Name: Geosyntec

**Index Test Results**

Sample Information				Test Information						Remarks
Site		Lab. No.	Moisture Content	Flies Content	Attreberg Limits			Soil Class.		
ID	Depth (ft)				ASTM D 2216 (%)	ASTM D 1140 (%)	ASTM D 4318			
	(-)	Top	Bottom	(-)			(-)	(-)	ASTM D 2487	
B	0.0	0.2	J097	68.7						
B	0.2	0.4	J098	60.2						
B	0.4	0.5	J099	55.5						
B	0.5	0.6	J100	51.8						
B	0.6	0.7	J101	51.9						
B	0.7	0.8	J102	51.8						
B	0.8	0.9	J103	47.2						
B	0.9	1.0	J104	44.3						
B	1.0	1.1	J105	45.4						
B	1.1	1.2	J106	43.0						
B-1	1.2	1.3	J107	41.0						
B-2	1.2	1.3	J108	41.6						
B-1	1.3	1.4	J109	40.3						
B-2	1.3	1.4	J110	40.7						
B	1.4	1.5	J111	35.3						
B	1.5	1.6	J112	31.8						
B	1.6	1.7	J113	30.7						
B	1.7	1.8	J114	29.0						
B	1.8	1.9	J115	21.5						
B	1.9	2.0	J116	22.3						
B	2.0	2.1	J117	23.8						

**APPENDIX E.4**  
**PHASES I AND II CLAY LINER COMPACTION SPECIFICATIONS**

# Design Change Form

KETTLEMAN HILLS FACILITY  
LANDFILL B-18

Number: 3

Date: May 29, 1991 Engineer: Kerry K. Parkinson

Location/Reference of Change: Construction Specifications and Quality Assurance Plan, Landfill Unit B-18, Phases I/II and Final Closure. Page 02924-6, Section B, Item d, which specifies the following:

d. Minimum Moisture Content: Within the range defined by the area formed by connecting the following points for the Modified Proctor Compaction curve.

- 3 to 5 percent above the optimum moisture content for a density equal to 90 percent of the maximum Modified Proctor density.

- 0 to 3 percent above the optimum moisture content for a density equal to 95 percent of the maximum Modified Proctor density.

Change: Change Section B, Item d, to the following:

d. Moisture Content: Within the range defined by the area formed by connecting the following points for the Modified Proctor Compaction curve.

- 2 to 5 percent above the optimum moisture content for a density equal to 90 percent of the maximum Modified Proctor density.

- 3 percent above the optimum moisture content at 97 percent of the maximum Modified Proctor density.

- 1 percent above the optimum moisture content at 98 percent of the maximum Modified Proctor density.

## APPROVAL FROM DESIGNER

Date: 5/29/91

Engineer: Kerry K. Parkinson

Time: P.M.

Type of Correspondence: Letter dated May 31, 1991 by EST

## ACKNOWLEDGEMENT FROM OWNER

Date: 6-5-91

Engineer: Scott M. [Signature]

Environmental Construction Services

# ENVIRONMENTAL SOLUTIONS, INC.

May 31, 1991

Project No. 89-977I

Mr. Scott Brown  
Engineering and Construction Manager  
Chemical Waste Management, Inc.  
35251 Old Skyline Road  
Kettleman City, California 93239

Revised Compaction Relationships  
Clay Liner Material from  
B-18 Clay Processing Area  
Landfill Unit B-18  
Kettleman Hills Facility

Dear Mr. Brown:

Pursuant to your request we have reevaluated the compaction specification for the Phase I clay liner construction at Landfill Unit B-18. This evaluation is based on compaction data from the testfill construction and interface testing program collected over the last six months. Additionally, we have reviewed the field density test results from the initial 10,000 cubic yards of clay liner placement.

The original specification from the Construction Specifications and Quality Assurance Plan, Landfill Unit B-18, Phases I and II, and Final Closure (Page 02924-6, Section B, Item d) specifies the following:

- Minimum Moisture Content: Within the range defined by the area formed by connecting the following points for the Modified Proctor Compaction curve.
  - 3 to 5 percent above the optimum moisture content for a density equal to 90 percent of the maximum Modified Proctor density.
  - 0 to 3 percent above the optimum moisture content for a density equal to 95 percent of the maximum Modified Proctor density.

This criterion, which allows a lower water content for higher compactive efforts, is established to: (1) assure that both the required strength and permeability characteristics are realized; and (2) provide flexibility for the contractor and CQA engineer to work with a range of water contents without having a clay which is too wet or dry, or too close to saturation. This flexibility is desirable in hot dry areas where exact water content is difficult to control. This specification is represented by the area designated as "Original Specification" in Figure 1, attached.

To further facilitate construction control of water content and quality assurance/quality control activities during clay liner placement, the moisture-density relationship graph is being changed to that shown by the "Revised Specification" in Figure 1. The revised moisture-density window is defined by the area encompassed by connecting the following water content density points:


- 2 percent above the optimum moisture content for a density equal to 90 percent of the maximum Modified Proctor density.
- 5 percent above the optimum moisture content for a density equal to 90 percent of the maximum Modified Proctor density.
- 3 percent above the optimum moisture content at 97 percent of the maximum Modified Proctor density.
- 1 percent above the optimum moisture content at 98 percent of the maximum Modified Proctor density.



The majority of material placed in the initial 10,000 cubic yards of clay liner is within the revised specification range. Test results indicate that a portion of the initial clay liner placement was at higher densities and moisture contents than the specification range. Due to the relatively low volume, minor deviation from the specification, and discontinuous placement of the material outside of this range, no planes of weakness or other detrimental features have been developed. Consequently, the clay liner placed to date is acceptable.

Please call us if you need further information regarding this material.

Very truly yours,




Kerry K. Parkinson, P.E.  
Civil Engineer

KKP:RDE:dk  
Attachments

cc: Bob Henry  
Richard Ellison  
Miro Knezevic

FIGURE I  
**LANDFILL UNIT B-18 PHASE I**  
 WATER CONTENT - DENSITY RELATIONSHIPS



# Design Change Form

KETTLEMAN HILLS FACILITY  
LANDFILL B-18

Number: 3 Modified

Date: June 28, 1991

Originating Engineer: Kerry K. Parkinson

Location/Reference of Change: Construction Specifications and Quality Assurance Plan, Landfill Unit B-18,

Phases I/II and Final Closure. Page 02924-6, Section B, Item d, which specifies the following:

- d. Minimum Moisture Content: Within the range defined by the area formed by connecting the following points for the Modified Proctor Compaction curve.
- 3 to 5 percent above the optimum moisture content for a density equal to 90 percent of the maximum Modified Proctor density.
  - 0 to 3 percent above the optimum moisture content for a density equal to 95 percent of the maximum Modified Proctor density.

Change: Change Section B, Item d, to the following:

- d. Moisture Content: Within the range defined by the area formed by connecting the following points for the Modified Proctor Compaction curve.
- 2 percent above the optimum moisture content for a density equal to 90 percent of the maximum Modified Proctor density.
  - 5 percent above the optimum moisture content for a density equal to 90 percent of the maximum Modified Proctor density.
  - 3 percent above the optimum moisture content at 97 percent of the maximum Modified Proctor density.
  - 1 percent above the optimum moisture content at 98 percent of the maximum Modified Proctor density.

The following tolerance criteria has been established for clay compaction at the B-18 Landfill:

- Twenty percent of the tests per equipment spread per day may be outside the specified moisture-density window by the following amount:
  - Moisture Content  $\pm 0.5\%$
  - Percent Compaction  $-0.5\%$
- So long as the average of all acceptable tests for that equipment spread per day falls within the moisture-density window.

## APPROVAL FROM DESIGNER

Date: 6/28/91

Engineer: Kerry K. Parkinson

Time: P.M.

Type of Correspondence: \_\_\_\_\_

## ACKNOWLEDGEMENT FROM OWNER

Date: 7/7/91

Engineer: James M. G.

# ENVIRONMENTAL SOLUTIONS, INC.

June 28, 1991

Project No. 89-9771

Mr. Scott Brown  
Engineering and Construction Manager  
Chemical Waste Management, Inc.  
35251 Old Skyline Road  
Kettleman City, California 93239

Moisture-Density Tolerance Criteria  
Clay Liner Material  
Landfill Unit B-18  
Kettleman Hills Facility

Dear Mr. Brown:

The purpose of this letter is to document the compaction test tolerance criteria established during our site visit on June 18, 1991. The tolerance criteria was developed based on our discussions with the CQA engineer and your staff, and review of the clay compaction results being realized. Those discussions and data indicated that a small percentage of tests were being considered as failures, even though they were just outside of the moisture-density window provided in our May 31, 1991, letter.

Your staff and the CQA Engineer requested that consideration be given to enlarging the window, if possible, without affecting necessary engineering properties of the material. We concluded that the window should not be changed without additional laboratory testing and analyses. However, it was also concluded that it would be acceptable for a small percentage of tests to lie just outside of the window, so long as average conditions were well within the basic criteria. This arrangement assures that the contractor continues to prepare and place the clay in a manner which provides the desired results, but also eliminates schedule delays and operational disruptions when the criteria is only occasionally missed by a small amount.

Accordingly, the following tolerance criteria, illustrated in the enclosed revision to Figure 1, has been established for clay compaction at the B-18 Landfill:

- Twenty percent of the tests per equipment spread per day may be outside the specified moisture-density window by the following amount:
  - Moisture Content       $\pm 0.5\%$
  - Percent Compaction    - 0.5%
- So long as the average of all acceptable tests for that equipment spread per day falls within the moisture-density window.

Please call us if you require additional information regarding this matter.

Very truly yours,



Kerry K. Parkinson, P.E.  
Civil Engineer


KKP:hd  
Enclosure

cc: Bob Henry  
Richard Ellison  
Miro Knezevic

FIGURE 1

# LANDFILL UNIT B-18 PHASE I

WATER CONTENT - DENSITY RELATIONSHIPS  
(REVISED JUNE 28, 1991)



— Specified Moisture-Density Window

- - - Tolerance Limit ( $\pm 0.5$  percent above optimum moisture,  $-0.5$  percent compaction)

**APPENDIX F**  
**LINER SYSTEM MATERIAL DATA**



**Kettleman Hills Facility – Landfill Unit B-18  
LINER SYSTEM MATERIAL DATA**

Project No.: 083-91887

Made By: RH

Date: 4-28-2008

Checked By: SS

Sheet: 1 of 1

Reviewed By: SS

**Objective:**

To provide data on the existing and proposed geosynthetic liner system materials for Landfill B-18.

**Given:**

*Existing B-18 Liner Systems:*

The existing (Phases I and II) B-18 base and sideslope liner systems contain the following geosynthetic components:

- 60-mil textured high-density polyethylene (HDPE) geomembrane;
- 80-mil smooth HDPE geomembrane;
- 8-ounce/square yard (oz/sy) nonwoven geotextile;
- 16-oz/sy nonwoven geotextile; and
- 200-mil geonet.

Product data sheets for the above-listed existing geosynthetic components of the B-18 liner systems were provided by ESI (1990). Copies of these product data sheets are provided in Attachment #1.

*Proposed B-18 Liner Systems:*

The proposed B-18 expansion area sideslope liner system contains the following geosynthetic components:

- 60-mil textured HDPE geomembrane;
- 16-oz/sy nonwoven geotextile; and
- geocomposite.

The proposed B-18 final closure cover system contains the following geosynthetic components:

- 40-mil textured HDPE geomembrane; and
- 12-oz/sy nonwoven geotextile.

Product data sheets that contain typical specified properties for the above-listed proposed geosynthetic components of the B-18 sideslope liner and cover systems are provided in Attachment #2. The data sheets provided in Attachment #2 were obtained from the Agru America, GSE Lining Technology, Inc. (GSE), Polyflex and Scaps. Inclusion of these data sheets does not imply that these materials will be used exclusively for the proposed B-18 expansion and/or final closure.

However, the actual geosynthetics used for the B-18 expansion and final closure are anticipated to have properties that are very similar to or the same as those given in Attachment #2. Attachment #3 provides EPA 9090 test results for products similar to the proposed liner materials. Results of the testing, similar to previous site specific testing, indicate the products are compatible with leachate. No additional EPA 9090 testing is proposed.

**Reference:**

Environmental Solutions, Inc. (ESI), "Engineering and Design Report, Landfill Unit B-18, Phases I and II and Final Closure, Kettleman Hills Facility, Kings County, California," August 1990.

**ATTACHMENT #1**  
**LINER SYSTEM MATERIAL DATA**



## NATIONAL SEAL COMPANY

## SUGGESTED THICKNESS SPECIFICATIONS

Thickness shall be measured in accordance with ASTM D 1593, paragraph 9.1.3 and ASTM D 751. The minimum average roll thickness shall be as specified with no individual thickness measurement on the sheet falling more than 5% below the specified value.

<u>SPECIFIED THICKNESS</u>	<u>MINIMUM AVERAGE ROLL VALUE</u>	<u>MINIMUM THICKNESS ALLOWED</u>
40 mil	40 mil	38 mil
60 mil	60 mil	57 mil
80 mil	80 mil	76 mil
100 mil	100 mil	95 mil

NATIONAL SEAL COMPANY  
ROLLSTOCK SPECIFICATIONS

**I. RESIN SPECIFICATION:**

NSC will use Union Carbide or Soltex resin or the equivalent.

Each lot of resin will be analyzed by National Seal Company's Laboratory as follows:

<u>SPECIFICATION</u>	<u>TEST METHOD</u>
Density	ASTM D 1505
Carbon Black Content	ASTM D 1603
Melt Flow Index	ASTM D 1238
Moisture Content	

**II. SHEET SPECIFICATION:**

Gauge	±5%
Width	15' Nominal
Carbon Black	2% to 3%
Appearance	smooth surface, minimal haze.

**III. QUALITY ASSURANCE and TESTING:**

1. Sheet appearance will be monitored continuously by production personnel and at least once per hour by a member of our Laboratory.
2. Sheet thickness will be continuously monitored by automatic gauging equipment located on the extruder.
3. Production will hold sheet thickness to within ±3% whenever possible. ±5% is our advertised tolerance.
4. National Seal Company's Laboratory will perform the following tests every 10,000 pounds of material produced:

<u>SPECIFICATION</u>	<u>TEST METHOD</u>
Tensile Properties	ASTM D 638
Carbon Black Dispersion	ASTM D 3015
Thickness	ASTM D 1593
Dimensional Stability	ASTM D 1204

See National Seal Company's Quality Control Manual for full listing of the tests which our Laboratory can perform. Please contact your sales representative for a pricing.

## PHYSICAL PROPERTIES

ALL PROPERTIES MEET OR EXCEED NSF STANDARD 54 SPECIFICATIONS FOR HDPE

PROPERTY	UNITS	TEST METHOD	VALUE
GAUGE OF MATERIAL	MILS	ASTM D 1593	40 (± 5%)
SPECIFIC GRAVITY, MINIMUM		ASTM D 792 A	0.94
MINIMUM TENSILE PROPERTIES		ASTM D 638	
TENSILE STRENGTH AT YIELD	PSI		2200
TENSILE STRENGTH AT BREAK	PSI		3800
ELONGATION AT YIELD	%		13
ELONGATION AT BREAK	%		600
MODULUS OF ELASTICITY	PSI		80,000
TEAR RESISTANCE, MINIMUM	PPI	ASTM D 1004	700
LOW TEMP. BRITTLINESS	DEG C.	ASTM D 746 B	-75° C.
SOIL BURIAL RESISTANCE MAX. CHANGE	%	ASTM D 3083 <sup>1</sup>	
TENSILE STRENGTH AT YIELD			10
TENSILE STRENGTH AT BREAK			10
ELONGATION AT YIELD			10
ELONGATION AT BREAK			10
MODULUS OF ELASTICITY			10
ENVIRONMENTAL STRESS CRACK RES.	HRS.	ASTM D 1693 <sup>1</sup>	1500
CARBON BLACK CONTENT	%	ASTM D 1603	2-3
CARBON BLACK DISPERSION	RATING	ASTM D 3015	A-2
MELT INDEX, CONDITION E, MAXIMUM	g/10m	ASTM D 1238	1.0
PUNCTURE RESISTANCE	LBS	FTMS 101, 2065	60
WATER VAPOR TRANSMISSION	g/M <sup>2</sup> hr.	ASTM E 96	0.008
HYDROSTATIC RESISTANCE	PSI	ASTM D 751 A	300

## NATIONAL SEAL SEAMING PROPERTIES

BONDED SEAM STRENGTH, MINIMUM	PPI	ASTM D 3083 <sup>1</sup>	80 & FTB <sup>2</sup>
SEAM PEEL ADHESION, MINIMUM	PPI	ASTM D 413 <sup>1</sup>	60 & FTB <sup>2</sup>
SOIL BURIAL RESISTANCE		ASTM D 3083 <sup>1</sup>	
BONDED SEAM STRENGTH, MAX. CHANGE	%		- 10
SEAM PEEL ADHESION			FTB <sup>2</sup>

1. AS MODIFIED IN NSF STANDARD NUMBER 54.
2. FILM TEARING BOND.

**PHYSICAL PROPERTIES**

ALL PROPERTIES MEET OR EXCEED NSF STANDARD 54 SPECIFICATIONS FOR HDPE

PROPERTY	UNITS	TEST METHOD	VALUE
GAUGE OF MATERIAL	MILS	ASTM D 1593	60 (± 5%)
SPECIFIC GRAVITY, MINIMUM		ASTM D 792 A	0.94
MINIMUM TENSILE PROPERTIES		ASTM D 638	
TENSILE STRENGTH AT YIELD	PSI		2200
TENSILE STRENGTH AT BREAK	PSI		3800
ELONGATION AT YIELD	%		13
ELONGATION AT BREAK	%		600
MODULUS OF ELASTICITY	PSI		80,000
TEAR RESISTANCE, MINIMUM	PPI	ASTM D 1004	700
LOW TEMP. BRITTLINESS	DEG C.	ASTM D 746 B	-75° C.
SOIL BURIAL RESISTANCE MAX. CHANGE	%	ASTM D 3083 <sup>1</sup>	
TENSILE STRENGTH AT YIELD			10
TENSILE STRENGTH AT BREAK			10
ELONGATION AT YIELD			10
ELONGATION AT BREAK			10
MODULUS OF ELASTICITY			10
ENVIRONMENTAL STRESS CRACK RES.	HRS.	ASTM D 1693 <sup>1</sup>	1500
CARBON BLACK CONTENT	%	ASTM D 1603	2-3
CARBON BLACK DISPERSION	RATING	ASTM D 3015	A-2
MELT INDEX, CONDITION E, MAXIMUM	g/10m	ASTM D 1238	1.0
PUNCTURE RESISTANCE	LBS	FTMS 101, 2065	90
WATER VAPOR TRANSMISSION	g/M <sup>2</sup> hr.	ASTM E 96	0.005
HYDROSTATIC RESISTANCE	PSI	ASTM D 751 A	450

**NATIONAL SEAL SEAMING PROPERTIES**

BONDED SEAM STRENGTH, MINIMUM	PPI	ASTM D 3083 <sup>1</sup>	120 & FTB <sup>2</sup>
SEAM PEEL ADHESION, MINIMUM	PPI	ASTM D 413 <sup>1</sup>	90 & FTB <sup>2</sup>
SOIL BURIAL RESISTANCE		ASTM D 3083 <sup>1</sup>	
BONDED SEAM STRENGTH, MAX. CHANGE	%		- 10
SEAM PEEL ADHESION			FTB <sup>2</sup>

1. AS MODIFIED IN NSF STANDARD NUMBER 54.

2. FILM TEARING BOND.

## PHYSICAL PROPERTIES

ALL PROPERTIES MEET OR EXCEED NSF STANDARD 54 SPECIFICATIONS FOR HDPE

PROPERTY	UNITS	TEST METHOD	VALUE
GAUGE OF MATERIAL	MILS	ASTM D 1593	80 (± 5%)
SPECIFIC GRAVITY, MINIMUM		ASTM D 792 A	0.94
MINIMUM TENSILE PROPERTIES		ASTM D 638	
TENSILE STRENGTH AT YIELD	PSI		2200
TENSILE STRENGTH AT BREAK	PSI		3800
ELONGATION AT YIELD	%		13
ELONGATION AT BREAK	%		600
MODULUS OF ELASTICITY	PSI		80,000
TEAR RESISTANCE, MINIMUM	PPI	ASTM D 1004	700
LOW TEMP. BRITTLINESS	DEG C.	ASTM D 746 B	- 75° C.
SOIL BURIAL RESISTANCE MAX. CHANGE	%	ASTM D 3083 <sup>1</sup>	
TENSILE STRENGTH AT YIELD			10
TENSILE STRENGTH AT BREAK			10
ELONGATION AT YIELD			10
ELONGATION AT BREAK			10
MODULUS OF ELASTICITY			10
ENVIRONMENTAL STRESS CRACK RES.	HRS.	ASTM D 1693 <sup>1</sup>	1500
CARBON BLACK CONTENT	%	ASTM D 1603	2-3
CARBON BLACK DISPERSION	RATING	ASTM D 3015	A-2
MELT INDEX, CONDITION E, MAXIMUM	g/10m	ASTM D 1238	1.0
PUNCTURE RESISTANCE	LBS	FTMS 101, 2065	110
WATER VAPOR TRANSMISSION	g/M <sup>2</sup> hr.	ASTM E 96	0.004
HYDROSTATIC RESISTANCE	PSI	ASTM D 751 A	600

## NATIONAL SEAL SEAMING PROPERTIES

BONDED SEAM STRENGTH, MINIMUM	PPI	ASTM D 3083 <sup>1</sup>	150 & FTB <sup>2</sup>
SEAM PEEL ADHESION, MINIMUM	PPI	ASTM D 413 <sup>1</sup>	120 & FTB <sup>2</sup>
SOIL BURIAL RESISTANCE		ASTM D 3083 <sup>1</sup>	
BONDED SEAM STRENGTH, MAX. CHANGE	%		- 10
SEAM PEEL ADHESION			FTB <sup>2</sup>

1. AS MODIFIED IN NSF STANDARD NUMBER 54.

2. FILM TEARING BOND.

## PHYSICAL PROPERTIES

ALL PROPERTIES MEET OR EXCEED NSF STANDARD 54 SPECIFICATIONS FOR HDPE

PROPERTY	UNITS	TEST METHOD	VALUE
GAUGE OF MATERIAL	MILS	ASTM D 1593	100 ( $\pm$ 5%)
SPECIFIC GRAVITY, MINIMUM		ASTM D 792 A	0.94
MINIMUM TENSILE PROPERTIES		ASTM D 638	
TENSILE STRENGTH AT YIELD	PSI		2200
TENSILE STRENGTH AT BREAK	PSI		3800
ELONGATION AT YIELD	%		13
ELONGATION AT BREAK	%		600
MODULUS OF ELASTICITY	PSI		80,000
TEAR RESISTANCE, MINIMUM	PPI	ASTM D 1004	700
LOW TEMP. BRITTLENESS	DEG C.	ASTM D 746 B	-75° C.
SOIL BURIAL RESISTANCE MAX. CHANGE	%	ASTM D 3083 <sup>1</sup>	
TENSILE STRENGTH AT YIELD			10
TENSILE STRENGTH AT BREAK			10
ELONGATION AT YIELD			10
ELONGATION AT BREAK			10
MODULUS OF ELASTICITY			10
ENVIRONMENTAL STRESS CRACK RES.	HRS.	ASTM D 1693 <sup>1</sup>	1500
CARBON BLACK CONTENT	%	ASTM D 1603	2-3
CARBON BLACK DISPERSION	RATING	ASTM D 3015	A-2
MELT INDEX, CONDITION E, MAXIMUM	g/10m	ASTM D 1238	1.0
PUNCTURE RESISTANCE	LBS	FTMS 101, 2065	130
WATER VAPOR TRANSMISSION	g/M <sup>2</sup> hr.	ASTM E 96	0.003
HYDROSTATIC RESISTANCE	PSI	ASTM D 751 A	750

## NATIONAL SEAL SEAMING PROPERTIES

BONDED SEAM STRENGTH, MINIMUM	PPI	ASTM D 3083 <sup>1</sup>	200 & FTB <sup>2</sup>
SEAM PEEL ADHESION, MINIMUM	PPI	ASTM D 413 <sup>1</sup>	150 & FTB <sup>2</sup>
SOIL BURIAL RESISTANCE		ASTM D 3083 <sup>1</sup>	
BONDED SEAM STRENGTH, MAX. CHANGE	%		- 10
SEAM PEEL ADHESION			FTB <sup>2</sup>

1. AS MODIFIED IN NSF STANDARD NUMBER 54.

2. FILM TEARING BOND.

# Trevira® Spunbonds are highly needed nonwoven engineering fabrics with excellent tensile properties, high filtration potential and outstanding permeability.

Trevira® Spunbond Type 11 products are 100% continuous filament polyester nonwoven needlepunched engineering fabrics. They deliver a combination of advantages unmatched by any other spunbonded geotextiles. They're resistant to freeze-thaw, soil chemicals and ultraviolet light exposure.

Trevira® Spunbonds are excellent where the requirement is (1) tensile reinforcement, (2) planar flow, (3) filtration, and (4) separation. For example, in roadways, railbeds, drainage systems, pondliners, retaining walls. And much more. Trevira® Spunbonds are extraordinary engineering fabrics.

## TYPICAL PHYSICAL PROPERTIES OF TREVIRA® TYPE 11 PRODUCTS

Fabric Property	Unit	Test Method	1112	1114	1120	1125	1135	1145	1155
Fabric Weight	oz/yd <sup>2</sup>	ASTM D-3776	3.6	4.2	6.0	7.4	10.5	13.5	16.2
Thickness, t	mils	ASTM D-1777	60	65	90	110	150	175	210
Grab Strength (MD/CD) <sup>1)</sup>	lbs	ASTM D-4632	110/90	135/110	205/175	270/225	390/330	500/425	625/560
Grab Elongation (MD/CD)	%	ASTM D-4632	70/85	70/85	75/85	75/85	75/85	90/95	90/95
Trapezoid Tear Strength (MD/CD)	lbs	ASTM D-4533	50/40	60/50	80/75	105/95	135/120	175/170	205/200
Puncture Resistance (5/16" hemispherical tip)	lbs	ASTM D-3787	50	60	90	115	155	175	240
Mullen Burst Strength	psi	ASTM D-3786	180	210	315	390	550	625	840
Water Flow Rate (5 cm. hd.)	gpm/ft <sup>2</sup>	ASTM D-4491	200	200	170	150	110	90	70
Permittivity, $\Psi$	sec <sup>-1</sup>	ASTM D-4491	2.72	2.72	2.31	1.77	1.50	1.22	0.95
Permeability, k	cm/sec	K = $\Psi$ t	0.41	0.45	0.53	0.49	0.57	0.54	0.51
AOS	Sieve Size mm	ASTM D-4751	70-100 .210-.149	70-100 .210-.149	70-100 .210-.149	70-120 .210-.125	70-120 .210-.125	100-140 .149-.105	100-170 .149-.088
Standard Roll Widths <sup>2)</sup>	ft		12.5 and 15.0						
Standard Roll Length <sup>2)</sup>	ft		400	400	300	300	300	300	300

<sup>1)</sup> MD = Machine Direction, CD = Cross Machine Direction.

<sup>2)</sup> Other width and length rolls are available upon request.

## MINIMUM AVERAGE ROLL VALUES (WEAKEST PRINCIPAL DIRECTION) OF TREVIRA® TYPE 11 PRODUCTS

Fabric Property	Unit	Test Method	1112	1114	1120	1125	1135	1145	1155
Fabric Weight	oz/yd <sup>2</sup>	ASTM D-3776	3.4	4.0	5.7	7.1	10.0	13.0	16.0
Thickness, t	mils	ASTM D-1777	50	55	80	100	135	160	200
Grab Strength	lbs	ASTM D-4632	80	100	155	200	290	375	500
Grab Elongation	%	ASTM D-4632	60	60	65	60	65	65	65
Trapezoid Tear Strength	lbs	ASTM D-4533	30	40	60	75	100	140	170
Puncture Resistance (5/16" hemispherical tip)	lbs	ASTM D-3787	35	45	75	95	130	155	200
Mullen Burst Strength	psi	ASTM D-3786	160	190	285	360	500	575	765
Water Flow Rate <sup>3)</sup> (5 cm. hd.)	gpm/ft <sup>2</sup>	ASTM D-4491	170	170	140	100	80	60	40
Permittivity $\Psi$ <sup>3)</sup>	sec <sup>-1</sup>	ASTM D-4491	2.31	2.31	1.90	1.36	1.09	0.82	0.54
Permeability, k <sup>3)</sup>	cm/sec	K = $\Psi$ t	0.29	0.32	0.39	0.35	0.37	0.33	0.27
AOS <sup>3)</sup>	Sieve Size mm	ASTM D-4751	70 .210	70 .210	70 .210	70 .210	70 .210	100 .149	100 .149

<sup>3)</sup> AOS "minimum average roll value" is a measure of the largest opening size in the fabric.



The information contained herein is offered free of charge, and is, to our best knowledge, true and accurate; however, all recommendations or suggestions are made without guarantee, since the conditions of use are beyond our control. There is no expressed warranty and no implied warranty of merchantability or of fitness for purpose of the product or products described herein. In submitting this information, no liability is assumed or license or other rights implied given with respect to any existing or pending patent, patent applications or trademarks. The observance of all legal regulations and patents is the responsibility of the user.

The names and logos HOECHST and TREVIRA are Reg. TM of Hoechst AG

Hoechst Celanese Corporation  
Spunbond Business Group  
P.O. Box 5887  
Spartanburg, SC 29304-5887 U.S.A.  
1 (800) 845-7597  
1 (803) 579-5479  
Telex: 9102404053

Hoechst

# TREVIRA® Spunbond Engineering Fabric Geotextile Selection Guide

## INTRODUCTION

Designers, owners, and contractors are now forced to choose from a multitude of geosynthetic products. The December 1987 issue of "Geotechnical Fabrics Report" listed 26 manufacturers or suppliers of geotextiles, and each supplier had several different products listed. When geonets, geogrids, and geocomposites are included, the list becomes very lengthy.

This brochure will only discuss geotextiles and will provide data to assist the specifier or user in selecting the proper fabric(s) for their application. Most data will be presented in a generic format; however, TREVIRA® Spunbond will be used to illustrate some of the presentation.

## Polyester or Polypropylene?

Almost all geotextiles available in the United States are manufactured from either polyester or polypropylene. Both polymers are synthetic "man-made" materials, but they display significantly different physical properties. Table 1 lists important characteristics for both polymers expressed as actual test results or as "excellent, good, fair, and poor".

As Table 1 illustrates, polyester and polypropylene display important differences in physical properties. These differences should always be considered when selecting geotextiles for any application.

## Woven or Nonwoven?

Woven geotextiles can be placed in two general categories by manufacturing method — Silt Film and Filament. All woven fabrics display high strength/low

	CHARACTERISTICS	
	Polyester	Polypropylene
Melting Point	478-490°F	320-350°F
UV Resistance	Excellent	Poor (Unstabilized) Fair-Excellent (Stabilized)
Creep Resistance	Excellent	Fair
Low Temperature (below 32°F) Workability	Excellent	Fair-Poor
Biological Resistance	Excellent	Excellent
Chemical Resistance*	Good	Good
Specific Gravity	1.36	0.9

\*Chemical resistance is difficult to generalize. Both polyester and polypropylene are unaffected by most chemicals, particularly in the concentrations commonly found in soil. However, if the fabric is being used in a waste containment facility or tank farm, and will therefore be exposed to higher concentrations, specific compatibility data should be requested from the geotextile manufacturers. If this data is unavailable, which is often the case with leachates, compatibility testing is suggested.

Figure 1

## LOAD-ELONGATION CURVE (MD)






Table 2

INDEX TESTS

PHYSICAL PROPERTY	TEST PROCEDURE
1) Weight	per ASTM D-3776
2) Thickness	per ASTM D-1777
3) Grab Strength	per ASTM D-4632
4) Grab Elongation	per ASTM D-4632
5) Trapezoid Tear Strength	per ASTM D-4533
6) Puncture Strength (modified) (this test is currently being balloted at ASTM for approval of a 5/16" flat tip with 1/32" x 45° chamfer)	per ASTM D-3787
7) Mullen Burst Strength	per ASTM D-3786
8) Permittivity	per ASTM D-4491
9) Apparent Opening Size (AOS)	per ASTM D-4751

"Typical" and "minimum average roll" results are listed on the TREVIRA® Spunbond sample cards.

Hoechst Celanese Corporation also routinely performs or has independent testing labs perform the following index and design tests:

PHYSICAL PROPERTY	TEST PROCEDURE
1) Ultraviolet Degradation	per ASTM D-4355
2) Transmissivity — fabric and fabric-net or fabric-core (Depending on boundary conditions, this test can be used as an index or design test.)	per ASTM D-4716
3) Abrasion Resistance	ASTM is currently balloting on an Abrasion Testing procedure utilizing the SBS (Sliding Block/Sandpaper Abrasion Test.)
4) Wide Width Tensile Test — This test is actually a design test but can be used for comparing fabrics.	per ASTM-4595
5) Friction Testing per the direct shear method — This test may be used as an index or design test.	This test is currently being balloted at ASTM.
6) Gradient Ratio Test — This test may be used as an index or design test.	This test is currently being balloted at ASTM.
7) Chemical Compatibility — This test may be used as an index or design test.	ASTM is currently working on this testing procedure.
8) Creep — This test may be used as an index or design test.	This test is currently being balloted at ASTM.

Table 3


### PHYSICAL PROPERTIES FOR PERFORMANCE

APPLICATION	FABRIC FUNCTION	IMPORTANT GEOTEXTILE PHYSICAL PROPERTY for PERFORMANCE
<b>1. Drainage</b> <ul style="list-style-type: none"> <li>• Underdrains</li> <li>• Recharge drains</li> <li>• Structure drains</li> </ul>	Filtration Separation	<ul style="list-style-type: none"> <li>• Permittivity</li> <li>• Coefficient of Permeability</li> <li>• AOS</li> <li>• Resistance to Clogging or Blinding (Gradient Ratio Test or Long-Term Soil-Fabric Filtration Test)</li> <li>• Trapezoid Tear Strength</li> <li>• Puncture Strength</li> </ul>
<b>2. Erosion Protection</b> <ul style="list-style-type: none"> <li>• Rip rap slope protection</li> <li>• Gabion bank protection</li> </ul>	Filtration Separation	<ul style="list-style-type: none"> <li>• Permittivity</li> <li>• Coefficient of Permeability</li> <li>• AOS</li> <li>• Resistance to Clogging or Blinding</li> <li>• Friction Angle (Direct Shear Test)</li> <li>• Puncture Strength</li> <li>• Trapezoid Tear Strength</li> <li>• Mullen Burst Strength</li> </ul>
<b>3. Stabilization</b> <ul style="list-style-type: none"> <li>• Aggregate roads and yards</li> <li>• Paved roads and parking lots</li> <li>• Railroad tracks</li> </ul>	Separation Reinforcement Filtration Planar Transport	<ul style="list-style-type: none"> <li>• Grab Tensile Strength</li> <li>• Mullen Burst Strength</li> <li>• Trapezoid Tear Strength</li> <li>• Puncture Strength</li> <li>• Permittivity</li> <li>• Transmissivity</li> <li>• Abrasion Resistance</li> <li>• Friction Angle (Direct Shear Test)</li> </ul>
<b>4. Soil Reinforcement</b> <ul style="list-style-type: none"> <li>• "Wrap around" walls</li> <li>• Reinforced slopes</li> <li>• Embankments over weak foundations</li> </ul>	Reinforcement	<ul style="list-style-type: none"> <li>• Wide Width Tensile Strength</li> <li>• Secant Modulus (confined)</li> <li>• Direct Shear or Pull Out Friction Angle</li> </ul>
<b>5. Lining Systems</b> <ul style="list-style-type: none"> <li>• Gas Relief Layer</li> <li>• Cushion Layer</li> <li>• Leachate Collection Systems</li> </ul>	Planar transport Separation Reinforcement Filtration Separation Planar Transport	<ul style="list-style-type: none"> <li>• Transmissivity</li> <li>• Mullen Burst Strength</li> <li>• Puncture Strength</li> <li>• Trapezoid Tear Strength</li> <li>• Permittivity</li> <li>• Coefficient of Permeability</li> <li>• AOS</li> <li>• Resistance to Clogging and Blinding</li> <li>• Friction Angle (Direct Shear Test)</li> <li>• Transmissivity (if fabric is used as the drain)</li> </ul>
<b>6. Asphalt Pavement</b> <ul style="list-style-type: none"> <li>• Asphalt Overlay</li> <li>• Chip Seal</li> <li>• Full depth asphalt</li> </ul>	Waterproofing (after absorbing tack coat) Reinforcement	<ul style="list-style-type: none"> <li>• Asphalt Retention/Absorption</li> <li>• Shrinkage Temperature</li> </ul>



**TEX-NET™**

# The Composite Drainage System



## Solid and Hazardous Waste Containment Drainage

### Primary Leachate Collection

TEX-NET, a composite of a drainage net and one or two layers of geotextile fabric, can provide a desired planar flow of liquids down the steep slopes of the walls and across the floor of waste containments to collection standpipes. The fabric acts as a filter to keep soil or fines from inhibiting any planar flow of leachate through the drainage net. It also acts as a cushion protecting the liner from damage. By having the fabric heat-laminated to the net, superior frictional resistance is achieved. Shear tests of TEX-NET with clayey soils indicate realistic friction angles in excess of 30°.

### Landfill Cap


There are two applications of TEX-NET in a typical landfill cap. One,

as the medium to drain surface water off the geomembrane cap...and two, under the landfill cap as a gas collector. TEX-NET with a geotextile on one side only is ideal for installation over the cap. TEX-NET with fabric on both sides is suggested for under the cap to reduce generated gas buildup. Gases will flow along the grid as freely as fluids.


### Gas Collection Within The Landfill

TEX-NET works very well in the collection and release of methane and other gases commonly generated in solid waste landfills. Strips of double-faced TEX-NET, if appropriately positioned throughout the refuse, will collect generated gas and direct its flow toward manifold pipes and onto the surface for collection and use, or flaring.

### TEX-NET IN A LANDFILL CAP



### TEX-NET WITHIN LANDFILL FOR GAS COLLECTION





***FLUID SYSTEMS, INC.***

**POLY-NET<sup>®</sup>**

**TRANSMISSIVITY - CHARTS**

513/771-5656  
800/346-9107  
FAX - 513/771-4844

32 Triangle Park Drive  
Suite 3201  
Cincinnati, Ohio 45246



# FLUID SYSTEMS, INC.

## POLY-NET™

PN-4000 FOR CLAY LINED FACILITIES  
PN-3000 CN — "CAP-NET"

<u>SPECIFICATION</u>	<u>PN-4000</u>	<u>PN-3000 CN</u>
ROLL LENGTH (MAXIMUM) (FT.)	300	300
ROLL WIDTH (+ 1 in.—0 in.) (FT.)	6.9	6.9
THICKNESS (IN.)	.300	.200
S.F. IN ROLL	2025	2025
WEIGHT PER ROLL (LBS.)	500	233
WEIGHT PER S.F.	.245	.115
*Available to Lengths of 400 Feet		
<u>PROPERTY</u>	<u>PN-4000</u>	<u>PN-3000 CN</u>
RAW MATERIAL (ALL DOMESTIC)	POLYETHYLENE (VIRGIN MATERIAL)	POLYETHYLENE (VIRGIN MATERIAL)
MANUFACTURING	FOAMED + EXTRUDED	FOAMED + EXTRUDED
COLOR	BLACK	BLACK
CARBON BLACK	2%	2%
DENSITY & POLYMER (g/cm <sup>3</sup> )	.936	.936
MELT INDEX (g/10 MIN)	1.10	1.10
TENSILE STRENGTH (LBS./IN.) (MACH. DIRECTION)	58	24
TENSILE STRENGTH (LBS./IN.) (TRANS. DIRECTION)	33	11
ELONGATION TO BREAK (MACH. DIRECTION)	175%	180%
ELONGATION TO BREAK (TRANS. DIRECTION)	165%	150%
POROSITY	.81-.84	.81-.84
U.V. RESISTANCE	STABLE	STABLE
TRANSMISSIVITY	— SEE TABLES —	— SEE TABLES —

513/771-5656  
800/346-9107  
FAX: 513/771-4844

POLY-NET IS PROUDLY MANUFACTURED IN THE U.S.

32 Triangle Park Drive  
Suite 3201  
Cincinnati, Ohio 45246

**POLYNET PN-3000**  
**PRODUCT DESCRIPTION**

PN-3000 is a profiled geonet manufactured by extruding two sets of polyethylene strands to form a diamond shape. The resulting net provides superior planar water flow, is inert to biological and naturally encountered chemicals, alkalis, and acids and is resistant to UV light exposure. Polynet PN-3000 conforms to the property values listed below.

<u>PROPERTY</u>	<u>METHOD</u>	<u>UNITS</u>	<u>QUALIFIER</u>	<u>VALUE</u>
Roll Length	-	ft	Normal	300
Roll Width	-	ft	Normal	7.54
Thickness	ASTM D1777	inches	Range	0.220±0.022
Area per Roll	-	ft <sup>2</sup>	Normal	2262
Weight per Roll		lbs	Normal	407
Weight per Square Foot	ASTM D3776 (option C)	lbs/ft <sup>2</sup>	Range	0.180±0.018
Carbon Black Content	ASTM D1603	percent	Range	2.5±0.5
Polymer Density	ASTM D1505	g/cm <sup>3</sup>	Range	0.937±0.002
Melt Flow Index	ASTM D1238 (condition E)	g/10 min.	Maximum	1.0
Tensile Strength (Machine Direction)	ASTM D1682 (modified)	ppi	Range	50±10
Transmissivity <sup>1</sup> (gradient=1.0 at 15,000 psf)	ASTM D4716	M <sup>2</sup> /sec	Minimum	1 X 10 <sup>-3</sup>

<sup>1</sup> Measured between two steel plates one hour after application of the confining pressure. Values may vary based on transmissivity specimen dimensions and specific laboratory.

**POLYNET PN-3000-CN  
PRODUCT DESCRIPTION**

PN-3000 CN is a foamed profiled geonet manufactured by extruding two sets of polyethylene strands to form a diamond shape. The resulting net provides superior planar water flow, is inert to biological and naturally encountered chemicals, alkalis, and acids and is resistant to UV light exposure. Polynet PN-3000-CN conforms to the property values listed below.

<u>PROPERTY</u>	<u>METHOD</u>	<u>UNITS</u>	<u>QUALIFIER</u>	<u>VALUE</u>
Roll Length	-	ft	Normal	300
Roll Width	-	ft	Normal	7.54
Thickness	ASTM D1777	inches	Range	0.220±0.022
Area per Roll	-	ft <sup>2</sup>	Normal	2262
Weight per Roll	-	lbs	Normal	260
Weight per Square Foot	ASTM D3776 (option C)	lbs/ft <sup>2</sup>	Range	0.115±0.011
Carbon Black Content	ASTM D1603	percent	Range	2.5±0.5
Polymer Density	ASTM D1505	g/cm <sup>3</sup>	Range	0.937±0.002
Melt Flow Index	ASTM D1238 (condition E)	g/10 min.	Maximum	1.0
Tensile Strength (Machine Direction)	ASTM D1682 (modified)	ppi	Range	28±10
Transmissivity <sup>1</sup> (gradient = 1.0 at 4,000 psf)	ASTM D4716	M <sup>2</sup> /sec	Minimum	1 X 10 <sup>-3</sup>

<sup>1</sup> Measured between two steel plates one hour after application of the confining pressure. Values may vary based on transmissivity specimen dimensions and specific laboratory.



**POLY-NET™**  
TRANSMISSIVITY


INSTALLATION METHOD

LEAK DETECTION  
HDPE LINER/POLY-NET/HDPE LINER

HYDRAULIC PRESSURE

**PN-3000 CN  
CAP-NET**

- ▼ 1000 PSF
- 2000 PSF
- 4000 PSF
- × 7000 PSF
- ▲ 10000 PSF
- 14000 PSF
- 20000 PSF



**FLUID SYSTEMS, INC.**

32 Triangle Park Drive  
Suite 3201  
Cincinnati, Ohio 45246  
513/771-5856  
800/346-9107  
FAX: 513/771-4844


**POLY-NET™**  
**TRANSMISSIVITY**

**INSTALLATION METHOD**  
 LEACHATE COLLECTION  
 CLAY SUBGRADE GEOTEXTILE  
 POLY-NET/HOPE LINER

**HYDRAULIC PRESSURE**

**PN-3000 CN  
 CAP-NET**

- ▼ 1000 PSF
- 2000 PSF
- 4000 PSF
- × 7000 PSF
- ▲ 10000 PSF
- 14000 PSF
- 20000 PSF



**FLUID SYSTEMS, INC.**

32 Triangle Park Drive 513/771-5656  
 Suite 3201 800/346-9107  
 Cincinnati, Ohio 45246 FAX: 513/771-4844

**POLY-NET™**  
TRANSMISSIVITY

INSTALLATION METHOD  
CLAY SUBGRADE/GEOTEXTILE/  
POLY-NET/GEOTEXTILE/CLAY SUBGRADE


HYDRAULIC PRESSURE

# LEACHATE COLLECTION FOR CLAY LINED FACILITY

## PN-4000

### SANDWICHED BETWEEN GEOTEXTILES

- ▼ 1000 PSF
- 2000 PSF
- 4000 PSF
- × 7000 PSF
- ▲ 10000 PSF
- 14000 PSF
- 20000 PSF



**FLUID SYSTEMS, INC.**

32 Triangle Park Drive Suite 3201  
Gincinnati, Ohio 45246  
513/771-5656 800/346-9107  
FAX: 513/771-4844

TABLE 5. HYDRAULIC TRANSMISSIVITY ( $M^2/SEC \times 10^{-3}$ )  
PN4000 GEONET

GRADIENT = 0.25

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	3.67	2.16	1.07	0.43	0.17
2.	4.54	3.02	1.27	0.58	0.19
3.	4.54	3.07	1.34	0.63	0.18
Avg:	4.25	2.75	1.23	0.55	0.18
SD:	0.50	0.51	0.14	0.10	0.01

GRADIENT = 0.50

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	2.56	1.65	0.78	0.30	0.13
2.	3.05	2.09	1.04	0.46	0.17
3.	2.94	2.05	1.08	0.46	0.18
Avg:	2.85	1.93	0.97	0.41	0.16
SD:	0.26	0.24	0.16	0.09	0.03

GRADIENT = 0.75

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	2.01	1.36	0.67	0.25	0.11
2.	2.69	1.74	0.85	0.37	0.13
3.	2.66	1.78	0.86	0.38	0.14
Avg:	2.45	1.63	0.79	0.33	0.13
SD:	0.38	0.23	0.11	0.07	0.02

$2 \times 10^{-2}$

GRADIENT = 1.0

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	1.83	1.22	0.57	0.22	0.10
2.	2.23	1.56	0.75	0.34	0.13
3.	2.26	1.49	0.76	0.34	0.13
Avg:	2.11	1.42	0.69	0.30	0.12
SD:	0.24	0.18	0.11	0.07	0.02

TABLE 3. HYDRAULIC TRANSMISSIVITY ( $M^2/SEC \times 10^{-3}$ )  
PN3000 GEONET

GRADIENT = 0.25

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	2.85	2.19	1.84	1.37	0.91
2.	2.13	2.81	2.29	1.45	0.80
3.	3.04	2.46	2.08	1.03	0.52
Avg:	2.67	2.49	2.07	1.28	0.54
SD:	0.48	0.31	0.23	0.22	0.25

GRADIENT = 0.50

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	2.21	1.84	1.44	0.92	0.26
2.	1.78	2.09	1.72	1.20	0.59
3.	2.23	1.97	1.45	0.78	0.38
Avg:	2.07	1.97	1.54	0.97	0.41
SD:	0.25	0.13	0.16	0.21	0.17

GRADIENT = 0.75

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	2.02	1.47	1.11	0.88	0.23
2.	1.61	1.72	1.44	1.04	0.54
3.	1.81	1.68	1.24	0.64	0.39
Avg:	1.81	1.62	1.26	0.85	0.37
SD:	0.21	0.13	0.17	0.20	0.15

GRADIENT = 1.0

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	1.75	1.46	1.20	0.81	0.22
2.	1.35	1.51	1.26	0.94	0.49
3.	1.56	1.47	1.10	0.58	0.30
Avg:	1.55	1.48	1.19	0.78	0.34
SD:	0.20	0.03	0.08	0.18	0.14

TABLE 3. HYDRAULIC TRANSMISSIVITY ( $M^2/Sec \times 10^{-3}$ )  
SOIL/TREVIRA 1120/PN3000 GEONET/TREVIRA 1120/SOIL

GRADIENT = 0.25

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	0.41	0.16	0.07	0.04	0.02
2.	0.42	0.17	0.08	0.05	0.04
3.	0.48	0.23	0.14	0.11	0.09
Avg:	0.44	0.19	0.10	0.07	0.05
SD:	0.04	0.04	0.04	0.04	0.04

GRADIENT = 0.50

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	0.36	0.14	0.08	0.03	0.02
2.	0.37	0.14	0.08	0.04	0.03
3.	0.40	0.18	0.11	0.07	0.06
Avg:	0.38	0.15	0.09	0.05	0.04
SD:	0.02	0.02	0.02	0.02	0.02

GRADIENT = 0.75

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	0.32	0.14	0.06	0.04	0.03
2.	0.32	0.14	0.06	0.05	0.03
3.	0.35	0.16	0.08	0.06	0.05
Avg:	0.33	0.15	0.07	0.05	0.04
SD:	0.02	0.01	0.01	0.01	0.01

GRADIENT = 1.0

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	0.26	0.12	0.05	0.03	0.03
2.	0.26	0.12	0.06	0.04	0.03
3.	0.29	0.14	0.07	0.05	0.04
Avg:	0.27	0.13	0.06	0.04	0.03
SD:	0.02	0.01	0.01	0.01	0.01

TABLE 5. HYDRAULIC TRANSMISSIVITY ( $M^2/Sec \times 10^{-3}$ )  
 SOIL/TREVIRA 1120/PN4000 GEONET/TREVIRA 1120/SOIL.

GRADIENT = 0.25

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	0.63	0.17	0.03	0.00	0.00
2.	0.66	0.19	0.05	0.02	0.02
3.	0.76	0.29	0.15	0.11	0.11
Avg:	0.68	0.22	0.08	0.04	0.04
SD:	0.07	0.06	0.06	0.06	0.06

GRADIENT = 0.50

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	0.62	0.18	0.02	0.00	0.00
2.	0.64	0.19	0.03	0.01	0.01
3.	0.71	0.24	0.08	0.06	0.05
Avg:	0.66	0.20	0.04	0.02	0.02
SD:	0.05	0.03	0.03	0.03	0.03

GRADIENT = 0.75

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	0.51	0.15	0.02	0.00	0.00
2.	0.53	0.16	0.03	0.01	0.01
3.	0.59	0.20	0.06	0.04	0.04
Avg:	0.54	0.17	0.04	0.02	0.02
SD:	0.04	0.03	0.02	0.02	0.02

GRADIENT = 1.0

<u>Specimen</u>	<u>5,000 psf</u>	<u>10,000 psf</u>	<u>15,000 psf</u>	<u>20,000 psf</u>	<u>25,000 psf</u>
1.	0.46	0.13	0.02	0.01	0.00
2.	0.47	0.13	0.03	0.02	0.01
3.	0.53	0.16	0.05	0.04	0.03
Avg:	0.49	0.14	0.03	0.02	0.01
SD:	0.04	0.02	0.02	0.02	0.02

**ATTACHMENT #2**  
**LINER SYSTEM MATERIAL DATA**



# High Density Polyethylene Micro Spike® Liner



## Product Data

Property	Test Method	Values				
Thickness, nominal (mm)		30 (.75)	40 (1.0)	60 (1.5)	80 (2.0)	100 (2.5)
Thickness (min. ave.), mil (mm)	ASTM D5994*	29 (.71)	38 (.95)	57 (1.43)	76 (1.90)	95 (2.38)
Thickness (lowest indiv. for 8 of 10 spec.), mil (mm)	ASTM D5994*	27 (.68)	36 (.90)	54 (1.35)	72 (1.80)	90 (2.25)
Thickness (lowest indiv. for 1 of 10 spec.), mil (mm)	ASTM D5994*	26 (.64)	34 (.85)	51 (1.28)	68 (1.70)	85 (2.13)
*The thickness values may be changed due to project specifications (i.e., absolute minimum thickness)						
Asperity Height (min. ave.), mil (mm)	GRI GM12	16 (.41)	16 (.41)	16 (.41)	16 (.41)	16 (.41)
Density, g/cc, minimum	ASTM D792, Method B	0.94	0.94	0.94	0.94	0.94
Tensile Properties (ave. both directions)	ASTM D6693, Type IV					
Strength @ Yield (min. ave.), lb/in width (N/mm)	2 in/minute	66 (11.6)	88 (15.4)	132 (23.1)	176 (30.8)	220 (38.5)
Elongation @ Yield (min. ave.), % (GL=1.3in)	5 specimens in each direction	13	13	13	13	13
Strength @ Break (min. ave.), lb/in width (N/mm)		66 (11.6)	88 (15.4)	132 (23.1)	176 (30.8)	220 (38.5)
Elongation @ Break (min. ave.), % (GL=2.0in)		350	350	350	350	350
Tear Resistance (min. ave.), lbs. (N)	ASTM D1004	23 (102)	30 (133)	45 (200)	60 (267)	72 (320)
Puncture Resistance (min. ave.), lbs. (N)	ASTM D4833	60 (267)	90 (400)	120 (534)	150 (667)	180 (801)
Carbon Black Content (range in %)	ASTM D4218	2 - 3	2 - 3	2 - 3	2 - 3	2 - 3
Carbon Black Dispersion (Category)	ASTM D5596	Only near spherical agglomerates for 10 views: 9 views in Cat. 1 or 2, and 1 view in Cat. 3				
Stress Crack Resistance (Single Point NCTL), hours	ASTM D5397, Appendix	300	300	300	300	300
Oxidative Induction Time, minutes	ASTM D3895, 200°C, 1 atm O <sub>2</sub>	≥100	≥100	≥100	≥100	≥100
Melt Flow Index, g/10 minutes	ASTM D1238, 190°C, 2.16kg	≤1.0	≤1.0	≤1.0	≤1.0	≤1.0
Oven Aging	ASTM D5721	80	80	80	80	80
with HP OIT, (% retained after 90 days)	ASTM D5685, 150°C, 500psi O <sub>2</sub>					
UV Resistance	GRI GM11	20hr. Cycle @ 75°C/4 hr. dark condensation @ 60°C				
with HP OIT, (% retained after 1600 hours)	ASTM D5885, 150°C, 500psi O <sub>2</sub>	50	50	50	50	50

These product specifications meet or exceed GRI's GM13

## Supply Information (Standard Roll Dimensions)

Thickness		Width		Length		Area (approx.)		Weight (average)	
mil	mm	ft	m	ft	m	ft <sup>2</sup>	m <sup>2</sup>	lbs	kg
30	.75	23	7	600.1	182.9	13,782	1,280	3,325	1,510
40	1.0	23	7	600.1	182.9	13,782	1,280	3,325	1,510
60	1.5	23	7	410.1	125	9,419	875	3,356	1,522
80	2.0	23	7	328.1	100	7,535	700	3,306	1,500
100	2.5	23	7	246.1	75	5,651	525	3,167	1,436

### Notes:

*All rolls are supplied with two slings. All rolls are wound on a 6 inch core. Special roll lengths are available on request.*

All information, recommendations and suggestions appearing in this literature concerning the use of our products are based upon tests and data believed to be reliable; however, it is the users responsibility to determine the suitability for their own use of the products described herein. Since the actual use by others is beyond our control, no guarantee or warranty of any kind, expressed or implied, is made by Agru/America as to the effects of such use or the results to be obtained, nor does Agru/America assume any liability in connection herewith. Any statement made herein may not be absolutely complete since additional information may be necessary or desirable when particular or exceptional conditions or circumstances exist or because of applicable laws or government regulations. Nothing herein is to be construed as permission or as a recommendation to infringe any patent.

500 Garrison Road, Georgetown, South Carolina 29440

843-546-0600

800-373-2478

Fax: 843-527-2738

email: salesmkg@agruamerica.com

www.agruamerica.com



# Micro Spike® Textured Geomembrane



Applications for HDPE and LLDPE Micro Spike®, textured geomembranes include projects where slope stability is critical. Micro Spike® is the only HDPE or LLDPE geomembrane that exhibits reproducible texture and friction angle values with the highest interface surface friction values in the industry.

Agru America's structured Geomembranes are produced on state-of-the-art equipment using a flat die-cast extrusion manufacturing process as opposed to blown film extrusion. Agru America is the only manufacturer of structured and embossed Geomembranes in North America.

*Micro Spike® surface texture*



## *Comparative properties for Design Consideration*

*Blown film co-extruded textured surfaces vs. Micro Spike® structured surfaces*

Design Consideration	Blown film co-extruded	Micro Spike® structured
Consistent core thickness	no	yes
Consistent surface texture	no	yes
Consistent asperity height	no	yes
Consistent interface friction	no	yes
Affect on mechanical properties	yes	no
Affect on stress crack potential	yes	no
Affect on multiaxial stress-strain	yes	no
Reduction in CQA program costs (less testing required)	no	yes

The calendared structured liner manufacturing process allows production of the only textured liner with a consistent core thickness, resulting in unchanged mechanical properties from that of smooth sheet. The consistent surface structuring or texture gives Micro Spike® Geomembranes reproducible friction angle values with efficiencies of over 95%.

**Representative Large Scale Interface Shear Values**  
 cap loading conditions (ASTM D3211)\*

Soil/Micro Spike® Surface	$\mu$	LD
Coarse Sand	34°	34°
General Fill	37°	37°
Slip Sand	31°	31°
New Mexican GCL	32°	32°

\*S&B Testing Services, Atlanta

Micro Spike® geomembranes are manufactured to meet or exceed current industry standards including GRI GM 13 (HDPE) and GRI GM 17 (LLDPE) test values, frequency of testing and functional requirements. Micro Spike® textured Geomembranes have smooth edges to allow for high quality thermal fusion welding between adjacent sheets. All Agru Geomembrane material is rolled on plastic pipe cores to ensure ease of installation without damage to the roll material.


Micro Spike® textured HDPE and LLDPE geomembrane has a decided advantage over blown film textured geomembrane:

**Reliability:** Micro Spike's® reproducible friction angles gives the design engineer the confidence that he has designed a system that will be built to meet or exceed the project design requirements.

**Cost Savings:** Micro Spike® is competitively priced with value added advantages including consistent core thickness and texture which reduces the on-site Quality Control and third party Quality Assurance costs.

**Consistent Material:** The structured "Micro Spikes" are totally integrated with the Geomembrane.

**High Interface shear:** Exceptional shear resistance between soil and geotextile components allows flexibility and stability during protective cover material placement. The textured asperity height is not only consistent but higher than competitive textured products.



*Why specify or use anything else!*

Agru has over 20 years experience with Geomembranes and 50 years experience with Thermoplastic Extrusion. Agru offers a wide range of concrete protective liners (Sure Grip), pipe fittings and semi-finished materials.

500 Garrison Road, Georgetown, South Carolina 29440


843-546-0600

800-321-1379

Fax: 843-546-0516

email: salesmkg@agruamerica.com

www.agruamerica.com



GSE HD Textured is the textured version of GSE HD. It is a high quality, high density polyethylene (HDPE) geomembrane with one or two coextruded, textured surfaces, and consisting of approximately 97.5% polyethylene, 2.5% carbon black and trace amounts of antioxidants and heat stabilizers; no other additives, fillers or extenders are used. The resin used is specially formulated, virgin polyethylene and is designed specifically for flexible geomembrane applications. GSE HD Textured has excellent resistance to UV radiation and is suitable for exposed conditions. This product allows projects with greater slopes to be designed since frictional characteristics are enhanced. *These product specifications meet or exceed GRI GM13.*

**Product Specifications**

TESTED PROPERTY	TEST METHOD	FREQUENCY	MINIMUM VALUE				
<b>Product Code</b>			HDT 030G000	HDT 040G000	HDT 060G000	HDT 080G000	HDT 100G000
Thickness, (minimum average) mil (mm)	ASTM D 5994	every roll	29 (0.73)	38 (0.96)	57 (1.45)	76 (1.93)	95 (2.41)
Lowest individual for 8 out of 10 values			27 (0.69)	36 (0.91)	54 (1.40)	72 (1.80)	90 (2.30)
Lowest individual for any of the 10 values			26 (0.66)	34 (0.86)	51 (1.30)	68 (1.73)	85 (2.16)
Density, g/cm <sup>3</sup>	ASTM D 1505	200,000 lb	0.94	0.94	0.94	0.94	0.94
Tensile Properties (each direction) <sup>(1)</sup>	ASTM D 6693, Type IV	20,000 lb					
Strength at Break, lb/in-width (N/mm)	Dumbell, 2 ipm		45 (8)	60 (11)	90 (16)	120(21)	150 (27)
Strength at Yield, lb/in-width (N/mm)			63 (11)	84 (15)	126 (22)	168 (29)	210 (37)
Elongation at Break, %	G.L. = 2.0 in (51 mm)		100	100	100	100	100
Elongation at Yield, %	G.L. = 1.3 in (33 mm)		12	12	12	12	12
Tear Resistance, lb (N)	ASTM D 1004	45,000 lb	21 (93)	28 (125)	42 (187)	56 (249)	70 (311)
Puncture Resistance, lb (N)	ASTM D 4833	45,000 lb	45 (200)	60 (267)	90 (400)	120 (534)	150 (667)
Carbon Black Content, %	ASTM D 1603*/4218	20,000 lb	2.0	2.0	2.0	2.0	2.0
Carbon Black Dispersion	ASTM D 5596	45,000 lb	+Note 1	+Note 1	+Note 1	+Note 1	+Note 1
Asperity Height	GRI GM 12	second roll	+Note 2	+Note 2	+Note 2	+Note 2	+Note 2
Notched Constant Tensile Load <sup>(2)</sup> , hr	ASTM D 5397, Appendix	200,000 lb	300	300	300	300	300
REFERENCE PROPERTY	TEST METHOD	FREQUENCY	NOMINAL VALUE				
Oxidative Induction Time, min	ASTM D 3895, 200° C; O <sub>2</sub> , 1 atm	200,000 lb	>100	>100	>100	>100	>100
Roll Length <sup>(3)</sup> (approximate), ft (m)	Standard Textured		830 (253)	700 (213)	520 (158)	400 (122)	330 (101)
Roll Width <sup>(3)</sup> , ft (m)			22.5 (6.9)	22.5 (6.9)	22.5 (6.9)	22.5 (6.9)	22.5 (6.9)
Roll Area, ft <sup>2</sup> (m <sup>2</sup> )			18,674 (1,735)	15,750 (1,463)	11,700 (1,087)	9,000 (836)	7,425 (690)

**NOTES:**

- +Note 1: Dispersion only applies to near spherical agglomerates. 9 of 10 views shall be Category 1 or 2. No more than 1 view from Category 3.
- +Note 2: 10 mil coverage. 8 of 10 readings ≥7 mils. Lowest individual ≥ 5 mils.
- GSE HD Standard Textured is available in rolls weighing about 4,000 lb (1,800 kg).
- <sup>(1)</sup>The combination of stress concentrations due to coextrusion texture geometry and the small specimen size results in large variation of test results. Therefore, these tensile properties are minimum average values.
- <sup>(2)</sup>NCTL for HD Textured is conducted on representative smooth membrane samples.
- All GSE geomembranes have dimensional stability of ±2% when tested with ASTM D 1204 and ITB of <-77° C when tested with ASTM D 746.
- <sup>(3)</sup>Roll lengths and widths have a tolerance of ± 1%.
- \*Modified.

DS006 HDtext R01/08/08

This information is provided for reference purposes only and is not intended as a warranty or guarantee. GSE assumes no liability in connection with the use of this information. Please check with GSE for current, standard minimum quality assurance procedures and specifications.

GSE and other trademarks in this document are registered trademarks of GSE Lining Technology, Inc. in the United States and certain foreign countries.

<b>North America</b>	GSE Lining Technology, Inc.	Houston, Texas	800.435.2008	281.443.8564	Fax: 281.230.6739
<b>South America</b>	GSE Lining Technology Chile S.A.	Santiago, Chile		56.2.595.4200	Fax: 56.2.595.4290
<b>Asia Pacific</b>	GSE Lining Technology Company Limited	Bangkok, Thailand		66.2.937.0091	Fax: 66.2.937.0097
<b>Europe &amp; Africa</b>	GSE Lining Technology GmbH	Hamburg, Germany		49.40.767420	Fax: 49.40.7674234
<b>Middle East</b>	GSE Lining Technology-Egypt	The 6th of October City, Egypt		20.2.828.8888	Fax: 20.2.828.8889



# Product Data Sheet

GSE STANDARD PRODUCTS

## GSE HD Geomembranes

GSE HD is a smooth, high quality, high density polyethylene (HDPE) geomembrane produced from specially formulated, virgin polyethylene resin. This polyethylene resin is designed specifically for flexible geomembrane applications. It contains approximately 97.5% polyethylene, 2.5% carbon black and trace amounts of antioxidants and heat stabilizers; no other additives, fillers or extenders are used. GSE HD has outstanding chemical resistance, mechanical properties, environmental stress crack resistance, dimensional stability and thermal aging characteristics. GSE HD has excellent resistance to UV radiation and is suitable for exposed conditions. *These product specifications meet or exceed GRI GM13.*

### Product Specifications

TESTED PROPERTY	TEST METHOD	FREQUENCY	MINIMUM VALUE				
			HDE 030A000	HDE 040A000	HDE 060A000	HDE 080A000	HDE 100A000
Product Code			HDE 030A000	HDE 040A000	HDE 060A000	HDE 080A000	HDE 100A000
Thickness, (minimum average) mil (mm) Lowest individual reading (-10%)	ASTM D 5199	every roll	30 (0.75) 27 (0.69)	40 (1.00) 36 (0.91)	60 (1.50) 54 (1.40)	80 (2.00) 72 (1.80)	100 (2.50) 90 (2.30)
Density, g/cm <sup>3</sup>	ASTM D 1505	200,000 lb	0.94	0.94	0.94	0.94	0.94
Tensile Properties (each direction)	ASTM D 6693, Type IV	20,000 lb					
Strength at Break, lb/in-width (N/mm)	Dumbell, 2 ipm		114 (20)	152 (27)	228 (40)	304 (53)	380 (67)
Strength at Yield, lb/in-width (N/mm)			63 (11)	84 (15)	126 (22)	168 (29)	210 (37)
Elongation at Break, %	G.L. 2.0 in (51 mm)		700	700	700	700	700
Elongation at Yield, %	G.L. 1.3 in (33 mm)		12	12	12	12	12
Tear Resistance, lb (N)	ASTM D 1004	45,000 lb	21 (93)	28 (125)	42 (187)	56 (249)	70 (311)
Puncture Resistance, lb (N)	ASTM D 4833	45,000 lb	54 (240)	72 (320)	108 (480)	144 (640)	180 (800)
Carbon Black Content, %	ASTM D 1603*/4218	20,000 lb	2.0	2.0	2.0	2.0	2.0
Carbon Black Dispersion	ASTM D 5596	45,000 lb	+Note 1	+Note 1	+Note 1	+Note 1	+Note 1
Notched Constant Tensile Load, hr	ASTM D 5397, Appendix	200,000 lb	300	300	300	300	300
REFERENCE PROPERTY	TEST METHOD	FREQUENCY	NOMINAL VALUE				
Oxidative Induction Time, min	ASTM D 3895, 200° C; O <sub>2</sub> , 1 atm	200,000 lb	>100	>100	>100	>100	>100
Roll Length <sup>(1)</sup> (approximate), ft (m)			1,120 (341)	870 (265)	560 (171)	430 (131)	340 (104)
Roll Width <sup>(1)</sup> , ft (m)			22.5 (6.9)	22.5 (6.9)	22.5 (6.9)	22.5 (6.9)	22.5 (6.9)
Roll Area, ft <sup>2</sup> (m <sup>2</sup> )			25,200 (2,341)	19,575 (1,819)	12,600 (1,171)	9,675 (899)	7,650 (711)

#### NOTES:

- +Note 1: Dispersion only applies to near spherical agglomerates. 9 of 10 views shall be Category 1 or 2. No more than 1 view from Category 3.
- GSE HD is available in rolls weighing about 3,900 lb (1,769 kg)
- All GSE geomembranes have dimensional stability of ±2% when tested with ASTM D 1204 and ITB of <-77° C when tested with ASTM D 746.
- <sup>(1)</sup>Roll lengths and widths have a tolerance of ± 1%.
- \*Modified.

DS005 HD R01/07/08

This information is provided for reference purposes only and is not intended as a warranty or guarantee. GSE assumes no liability in connection with the use of this information. Please check with GSE for current, standard minimum quality assurance procedures and specifications.

GSE and other trademarks in this document are registered trademarks of GSE Lining Technology, Inc. in the United States and certain foreign countries.

North America	GSE Lining Technology, Inc.	Houston, Texas	800.435.2008	281.443.8564	Fax: 281.230.6739
South America	GSE Lining Technology Chile S.A.	Santiago, Chile		56.2.595.4200	Fax: 56.2.595.4290
Asia Pacific	GSE Lining Technology Company Limited	Bangkok, Thailand		66.2.937.0091	Fax: 66.2.937.0097
Europe & Africa	GSE Lining Technology GmbH	Hamburg, Germany		49.40.767420	Fax: 49.40.7674234
Middle East	GSE Lining Technology-Egypt	The 6th of October City, Egypt		20.2.828.8888	Fax: 20.2.828.8889

[www.gseworld.com](http://www.gseworld.com)



GSE Nonwoven Geotextiles is a family of polypropylene, staple fiber, nonwoven, needlepunched geotextiles. Manufactured using an advanced manufacturing and quality system, these products are the most uniform and consistent nonwoven, needlepunched geotextile currently available in the industry. GSE combines a fiber selection and approval system with in-line quality control and a state-of-the-art laboratory to ensure that every roll shipped meets customer specifications. The company has performed extensive performance testing to evaluate suitability of its nonwovens for various applications. GSE Nonwoven Geotextiles are available in a range of weights to meet your specific project needs. *These product specifications meet or exceed GRI GT12, GRI GT13 and AASHTO M288.*

### Product Specifications

TESTED PROPERTY	TEST METHOD	FREQUENCY	NW4	NW6	NW8	NW10	NW12	NW16
Product Code			GEO 0408002	GEO 0608002	GEO 0808002	GEO 1008002	GEO 1208002	GEO 1608002
AASHTO M288 Class			3	2	1	>1	>>1	>>>1
Mass per Unit Area, oz/yd <sup>2</sup> (g/m <sup>2</sup> )	ASTM D 5261	90,000 ft <sup>2</sup>	4 (135)	6 (200)	8 (270)	10 (335)	12 (405)	16 (540)
Grab Tensile Strength, lb (N)	ASTM D 4632	90,000 ft <sup>2</sup>	120 (530)	170 (755)	220 (975)	260 (1,155)	320 (1,420)	390 (1,735)
Grab Elongation, %	ASTM D 4632	90,000 ft <sup>2</sup>	50	50	50	50	50	50
Puncture Strength, lb (N)	ASTM D 4833	90,000 ft <sup>2</sup>	60 (265)	90 (395)	120 (525)	165 (725)	190 (835)	240 (1,055)
Trapezoidal Tear Strength, lb (N)	ASTM D 4533	90,000 ft <sup>2</sup>	50 (220)	70 (310)	95 (420)	100 (445)	125 (555)	150 (665)
Apparent Opening Size, Sieve No. (mm)	ASTM D 4751	540,000 ft <sup>2</sup>	70 (0.212)	70 (0.212)	80 (0.180)	100 (0.150)	100 (0.150)	100 (0.150)
Permittivity, sec <sup>-1</sup>	ASTM D 4491	540,000 ft <sup>2</sup>	1.50	1.50	1.50	1.20	0.80	0.70
Permeability, cm/sec	ASTM D 4491	540,000 ft <sup>2</sup>	0.22	0.30	0.30	0.30	0.29	0.27
Water Flow Rate, gpm/ft <sup>2</sup> (l/min/m <sup>2</sup> )	ASTM D 4491	540,000 ft <sup>2</sup>	120 (4,885)	110 (4,480)	110 (4,480)	85 (3,460)	60 (2,440)	50 (2,035)
UV Resistance (% retained after 500 hours)	ASTM D 4355	per formulation	70	70	70	70	70	70
Roll Length <sup>(1)</sup> , ft (m)			600 (182)	600 (182)	600 (182)	300 (91)	300 (91)	300 (91)
Roll Width <sup>(1)</sup> , ft (m)			15 (4.6)	15 (4.6)	15 (4.6)	15 (4.6)	15 (4.6)	15 (4.6)
Roll Area, ft <sup>2</sup> (m <sup>2</sup> )			9,000 (836)	9,000 (836)	9,000 (836)	4,500 (418)	4,500 (418)	4,500 (418)

**NOTES:**


- The property values listed are in weaker principal direction. All values listed are Minimum Average Roll Values (MARV) except apparent opening size in mm and UV resistance. Apparent opening size (mm) is a Maximum Average Roll Value. UV is a typical value.
- <sup>(1)</sup>Roll lengths and widths have a tolerance of ±1%.

DS037 NW R08/30/07

This information is provided for reference purposes only and is not intended as a warranty or guarantee. GSE assumes no liability in connection with the use of this information. Please check with GSE for current, standard minimum quality assurance procedures and specifications.

GSE and other trademarks in this document are registered trademarks of GSE Lining Technology, Inc. in the United States and certain foreign countries.

<b>North America</b>	GSE Lining Technology, Inc.	Houston, Texas	800.435.2008	281.443.8564	Fax: 281.230.6739
<b>South America</b>	GSE Lining Technology Chile S.A.	Santiago, Chile		56.2.595.4200	Fax: 56.2.595.4290
<b>Asia Pacific</b>	GSE Lining Technology Company Limited	Bangkok, Thailand		66.2.937.0091	Fax: 66.2.937.0097
<b>Europe &amp; Africa</b>	GSE Lining Technology GmbH	Hamburg, Germany		49.40.767420	Fax: 49.40.7674234
<b>Middle East</b>	GSE Lining Technology-Egypt	The 6th of October City, Egypt		20.2.828.8888	Fax: 20.2.828.8889



# Product Data Sheet

GSE STANDARD PRODUCTS

## GSE FabriNet Geocomposites (Double-Sided)

GSE FabriNet geocomposite consists of GSE HyperNet geonet heat-laminated on both sides with a GSE nonwoven needlepunched geotextile. GSE HyperNet is a 200 mil thick geonet manufactured from a premium grade high density polyethylene resin. For the purpose of lamination to geonets, GSE nonwoven needlepunched geotextiles are available in mass per unit area range of 6 oz/yd<sup>2</sup> (200 g/m<sup>2</sup>) to 16 oz/yd<sup>2</sup> (540 g/m<sup>2</sup>). GSE FabriNet geocomposites are designed and formulated to perform drainage function under a range of anticipated site loads, gradients and boundary conditions. Index properties for the product are provided in the table below. Please contact GSE for further information regarding performance under site-specific conditions.

### Product Specifications

TESTED PROPERTY	TEST METHOD	FREQUENCY	MINIMUM AVERAGE ROLL VALUE <sup>(a)</sup>		
			6 oz/yd <sup>2</sup>	8 oz/yd <sup>2</sup>	10 oz/yd <sup>2</sup>
<b>Geocomposite</b>					
Product Code			F420600605	F420800805	F421001005
Transmissivity <sup>(b)</sup> , gal/min/ft (m <sup>2</sup> /sec)	ASTM D 4716	1/540,000 ft <sup>2</sup>	0.48 (1 x 10 <sup>-4</sup> )	0.48 (1 x 10 <sup>-4</sup> )	0.43 (9 x 10 <sup>-5</sup> )
Ply Adhesion, lb/in (g/cm)	ASTM D 7005	1/50,000 ft <sup>2</sup>	1.0 (178)	1.0 (178)	1.0 (178)
Roll Width <sup>(c)</sup> , ft (m)			14.5 (4.4)	14.5 (4.4)	14.5 (4.4)
Roll Length <sup>(c)</sup> , ft (m)			230 (70.1)	200 (60.9)	190 (58.0)
Roll Area, ft <sup>2</sup> (m <sup>2</sup> )			3,335 (310)	2,900 (269)	2,755 (256)
<b>Geonet core<sup>(d)</sup></b>					
Transmissivity <sup>(b)</sup> , gal/min/ft (m <sup>2</sup> /sec)	ASTM D 4716		9.66 (2 x 10 <sup>-3</sup> )	9.66 (2 x 10 <sup>-3</sup> )	9.66 (2 x 10 <sup>-3</sup> )
Thickness, mil (mm)	ASTM D 5199	1/50,000 ft <sup>2</sup>	200 (5)	200 (5)	200 (5)
Density, g/cm <sup>3</sup>	ASTM D 1505	1/50,000 ft <sup>2</sup>	0.94	0.94	0.94
Tensile Strength (MD), lb/in (N/mm)	ASTM D 5035	1/50,000 ft <sup>2</sup>	45 (7.9)	45 (7.9)	45 (7.9)
Carbon Black Content, %	ASTM D 1603*/4218	1/50,000 ft <sup>2</sup>	2.0	2.0	2.0
<b>Geotextile (prior to lamination)<sup>(d,e)</sup></b>					
Mass per Unit Area, oz/yd <sup>2</sup> (g/m <sup>2</sup> )	ASTM D 5261	1/90,000 ft <sup>2</sup>	6 (200)	8 (270)	10 (335)
Grab Tensile, lb (N)	ASTM D 4632	1/90,000 ft <sup>2</sup>	170 (755)	220 (975)	260 (1,155)
Puncture Strength, lb (N)	ASTM D 4833	1/90,000 ft <sup>2</sup>	90 (395)	120 (525)	165 (725)
AOS, US sieve (mm)	ASTM D 4751	1/540,000 ft <sup>2</sup>	70 (0.212)	80 (0.180)	100 (0.150)
Permittivity, (sec <sup>-1</sup> )	ASTM D 4491	1/540,000 ft <sup>2</sup>	1.5	1.5	1.2
Flow Rate, gpm/ft <sup>2</sup> (lpm/m <sup>2</sup> )	ASTM D 4491	1/540,000 ft <sup>2</sup>	110 (4,480)	110 (4,480)	85 (3,460)
UV Resistance, % retained	ASTM D 4355 (after 500 hours)	once per formulation	70	70	70

#### NOTES:

- <sup>(a)</sup>These are MARV values that are based on the cumulative results of specimens tested and determined by GSE. AOS in mm is a maximum average roll value.
- <sup>(b)</sup>Gradient of 0.1, normal load of 10,000 psf, water at 70° F between steel plates for 15 minutes.
- <sup>(c)</sup>Roll widths and lengths have a tolerance of ±1%.
- <sup>(d)</sup>Component properties prior to lamination.
- <sup>(e)</sup>Refer to geotextile product data sheet for additional specifications.
- \*Modified.

DS018 FabriNet R01/07/08

This information is provided for reference purposes only and is not intended as a warranty or guarantee. GSE assumes no liability in connection with the use of this information. Please check with GSE for current, standard minimum quality assurance procedures and specifications.

GSE and other trademarks in this document are registered trademarks of GSE Lining Technology, Inc. in the United States and certain foreign countries.

<b>North America</b>	GSE Lining Technology, Inc.	Houston, Texas	800.435.2008	281.443.8564	Fax: 281.230.6739
<b>South America</b>	GSE Lining Technology Chile S.A.	Santiago, Chile		56.2.595.4200	Fax: 56.2.595.4290
<b>Asia Pacific</b>	GSE Lining Technology Company Limited	Bangkok, Thailand		66.2.937.0091	Fax: 66.2.937.0097
<b>Europe &amp; Africa</b>	GSE Lining Technology GmbH	Hamburg, Germany		49.40.767420	Fax: 49.40.7674234
<b>Middle East</b>	GSE Lining Technology-Egypt	The 6th of October City, Egypt		20.2.828.8888	Fax: 20.2.828.8889

[www.gseworld.com](http://www.gseworld.com)

**POLY-FLEX, INC.**

*An Engineering  
Approach to  
Groundwater  
Protection*

## **REFERENCE MANUAL**

The information provided in this manual has been compiled by Poly-Flex, Inc. and to the best of our knowledge accurately represents Poly-Flex polyethylene geosynthetics. This information is offered without warranty. Final determination of the suitability of any information or products for the use contemplated and its manner of use is the sole responsibility of the end user. This information is subject to change without notice. 08/06





## TABLE OF CONTENTS

### I POLY-FLEX HDPE & LLDPE LINER SPECIFICATIONS

1. GENERAL REQUIREMENTS	1
1.1 Scope	1
1.2 Qualifications of Contractor Work Activities	1
1.3 Submittals	1
1.4 Meeting	2
1.5 Warranty	2
2. MATERIAL SPECIFICATIONS	3
2.1 Materials	3
2.2 Geomembrane Raw Materials	3
2.3 Rolls	3
Smooth HDPE Geomembrane Data Sheets	4
Textured HDPE Geomembrane Data Sheets	6
Smooth LLDPE Geomembrane Data Sheets	8
Textured LLDPE Geomembrane Data Sheets	10
2.4 Quality Control Specifications	12
3. GEOMEMBRANE INSTALLATION	14
3.1 Materials Logistics	14
3.2 Earthwork	14
3.3 Method of Placement	15
3.4 Field Seaming	15
3.5 Cover Material and Backfilling of Anchor Trench	19
3.6 Geomembrane Acceptance	19
Inherent Properties of Polyethylene Liners	20

### II POLY-FLEX DRAINAGE NET & GEOCOMPOSITE SPECIFICATIONS

1. GENERAL REQUIREMENTS	23
1.1 Scope	23
1.2 Qualifications	23
1.3 Submittals	23
2. MATERIAL SPECIFICATIONS	23
2.1 Materials	23
HDPE Drainage Net Data Sheet	24
Single-Sided Geocomposite Data Sheets	26
Double-Sided Geocomposite Data Sheets	28
2.2 Manufacturer's Quality Control Testing	30
3. INSTALLATION	30
3.1 Transportation and On-Site Storage	30
3.2 Method of Placement	30
3.3 Field Seaming	30
3.4 Cover Material	30
3.5 Repairs	30

## TABLE OF CONTENTS

### III POLY-FLEX POLYETHYLENE EMBED CHANNEL SPECIFICATION

1. GENERAL	33
1.1 Scope	33
1.2 References	33
1.3 Submittals	33
1.4 Manufacturer's Quality Control Testing	33
2. PRODUCT	33
2.1 Product	33
2.2 Shipment and Storage	33
3. INSTALLATION	34
3.1 Installation in concrete forms	34
3.2 Fabrication	34
3.3 Seaming	34
PEC Design Detail	35

### IV CHEMICAL RESISTANCE INFORMATION

1. CHEMICAL COMPATIBILITY OF POLY-FLEX LINERS	39
Chemical Compatibility Chart	40

### V GEOMEMBRANE MANUFACTURING QUALITY CONTROL & QUALITY ASSURANCE

1. DEFINITIONS	43
2. MANUFACTURING QUALITY CONTROL AND QUALITY ASSURANCE PROGRAM	43
2.1 Raw Material	43
3. MANUFACTURING	45
3.1 Blown Sheet Process	45
3.2 Process Quality Control	45
3.3 Roll Labeling	46
3.4 Storage, Staging and Shipping of Geomembrane Rolls	46
3.5 Laboratory Quality Control & Quality Assurance	47
4. MANUFACTURING QUALITY CONTROL PROGRAM FLOW CHART	48
5. PAPER FLOW FORMS	49
5.1 Product Quality Report	49
5.2 Railcar Resin Report	50
5.3 Quality Control Report	51
5.4 Hold Tag	52





## TABLE OF CONTENTS

### VI DRAINAGE NET AND GEOCOMPOSITE MANUFACTURING QUALITY CONTROL & QUALITY ASSURANCE

1.	MANUFACTURING QUALITY CONTROL AND QUALITY ASSURANCE	55
1.1	Applicable Test Methods	55
2.	RAW MATERIAL	55
3.	MANUFACTURING	56
3.1	Drainage Net	56
3.2	Drainage Net/Geotextile Geocomposite	56
3.3	Roll Labeling	56
3.4	Storage, Staging and Shipping of Drainage Net and Geocomposite Rolls	56
3.5	Laboratory Testing Program	57
3.6	Quality Control Report	58

Poly-Flex Liner  
Specifications

Drainage Net &  
Geocomposite

Polyethylene  
Embed Channel

Chemical  
Resistance

Geomembrane  
Manufacturing QC/QA

Net/Geocomposite  
Manufacturing QC/QA



Poly-Flex Liner  
Specifications

---

**POLY-FLEX  
HDPE & LLDPE  
LINER  
SPECIFICATIONS**



## POLY-FLEX LINER SPECIFICATIONS

## POLY-FLEX LINER SPECIFICATIONS



### 1. GENERAL REQUIREMENTS

#### 1.1 Scope

The following describes parameters for the manufacture, supply, and installation of Poly-flex polyethylene geomembranes. All procedures, operations, and methods shall be in strict accordance with the engineer's specifications, plans, and drawings.

#### 1.2 Qualifications of Contractor Work Activities

##### 1.2.1 Manufacturing

The manufacturer shall have at least five (5) years continuous experience in manufacturing polyethylene geomembrane and/or experience totaling 10,000,000 square feet of manufactured polyethylene geomembrane.

##### 1.2.2 Installation

The installation contractor shall be the manufacturer or a dealer trained to install the manufacturer's geomembrane.

Installation shall be performed under the constant direction of a field installation supervisor who shall remain on site and be responsible, throughout the liner installation, for liner layout, seaming, testing, repairs, and all other activities by the installer. The field installation supervisor shall have installed or supervised the installation of a minimum of 2,000,000 square feet of polyethylene geomembrane. Seaming shall be performed under the direction of a master seamer (who may also be the field installation supervisor) who has seamed a minimum of 2,000,000 square feet of polyethylene geomembrane, using the same type of seaming apparatus specified for this project. The field installation supervisor and/or master seamer shall be present whenever seaming is performed.

### 1.3 Submittals

#### 1.3.1 Manufacturer

The manufacturer shall provide the following information:

- A. Submittals with Bid Documents**
  - 1. List of material properties.
  - 2. Manufacturing quality control program.
- B. Submittals After Contract Award, Prior to Liner Installation**
  - 1. Copy of quality control certificates issued by the resin supplier.
  - 2. Copy of quality control certificates for the geomembranes in conformance with Section 2.4.3.

#### 1.3.2 Installation Contractor

The installer shall provide the following written information:

##### A. Submittals With Bid Documents

A list of completed facilities, totaling a minimum of 2,000,000 square feet, for which the installer has installed polyethylene geomembrane. For each installation, the following information shall be provided:

- a. Name and purpose of facility, location, and date of installation.
- b. Name of owner, design engineer, manufacturer, and name and telephone number of contact at the facility who can discuss the project.
- c. Thickness and quantity of the installed geomembrane.

##### B. Submittals by Successful Bidder Prior to Commencement of Installation

- 1. Proposed installation panel layout.
- 2. Resume(s) of the field installation supervisor and master seamer.

#### 1.4 Meeting

A daily meeting shall be held at the work area just prior to commencement of the work to discuss work activities. The earthwork contractor, the liner installer and the inspector shall be present.

#### 1.5 Warranty

A written Warranty shall be obtained from the manufacturer (for material) and the installation contractor (for workmanship). These documents shall warrant both the quality of the material and workmanship for a specified duration of time.



## POLY-FLEX LINER SPECIFICATIONS

## SMOOTH HDPE GEOMEMBRANE ENGLISH UNITS



### 2. MATERIAL SPECIFICATIONS

#### 2.1 Materials

- The geomembrane shall be High-Density Polyethylene (HDPE) or Linear Low Density Polyethylene (LLDPE).
- Gasket material shall be neoprene, closed cell medium, 1/4-inch thick, 2 inches wide with adhesive on one side, or other compatible gasket materials as required.
- Metal battens or banding and hardware shall be stainless steel.
- Water cut-off mastic shall be Neoprene Flashing Cement as supplied by Poly-Flex, Inc., or as required.
- Sealant shall be General Electric Silicone, RTV 103, or equivalent.

#### 2.2 Geomembrane Raw Materials

The geomembrane shall be manufactured of polyethylene resins produced in the United States and shall be compounded and manufactured specifically for the intended purpose. The resin manufacturer shall certify each lot for the following properties.

The natural polyethylene resin without the carbon black shall meet the following requirements:

Property	Test Method	HDPE Requirements	LLDPE Requirements
Density, g/cc	ASTM D 1505 or ASTM D 792	0.935 - 0.940	0.915 - 0.926
Melt Index, g/10 min.	ASTM D 1238	<0.4	<0.6

#### 2.3 Rolls

The geomembrane shall be a minimum 23.0 ft seamless width, as manufactured by Poly-Flex, Inc. (2000 W. Marshall Dr., Grand Prairie, TX 75051, 888-765-9359). Carbon black shall be added to the resin if the resin is not compounded for ultra-violet resistance.

The surface of the smooth geomembrane shall not have striations, roughness, pinholes, or bubbles.

The geomembrane shall be supplied in rolls. Labels on each roll shall identify the thickness of the material, the length and width of the roll, lot and roll numbers, and name of manufacturer.

The geomembrane rolls shall meet the following specifications:

Property	Test Method	Minimum Average Values				
		30 mil	40 mil	60 mil	80 mil	100 mil
Thickness, mils minimum average lowest individual reading	ASTM D 5199	30	40	60	80	100
Sheet Density, g/cc	ASTM D 1505/D 792	0.940	0.940	0.940	0.940	0.940
<b>Tensile Properties<sup>1</sup></b>						
ASTM D 6693						
1. Yield Strength, lb/in		63	84	126	168	210
2. Break Strength, lb/in		114	152	228	304	380
3. Yield Elongation, %		12	12	12	12	12
4. Break Elongation, %		700	700	700	700	700
Tear Resistance, lb	ASTM D 1004	21	28	42	56	70
Puncture Resistance, lb	ASTM D 4833	54	72	108	144	180
Stress Crack Resistance <sup>2</sup> , hrs	ASTM D 5397 (App.)	300	300	300	300	300
Carbon Black Content <sup>3</sup> , %	ASTM D 1603	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0
Carbon Black Dispersion	ASTM D 5596	-Note 4-				
Oxidative Induction Time (OIT) Standard OIT, minutes	ASTM D 3895	100	100	100	100	100
Oven Aging at 85°C High Pressure OIT - % retained after 90 days	ASTM D 5721 ASTM D 5885	80	80	80	80	80
UV Resistance <sup>5</sup> High Pressure OIT <sup>6</sup> - % retained after 1600 hrs	GRI CM11 ASTM D 5885	50	50	50	50	50
<b>Seam Properties</b>						
ASTM D 6392 (@ 2 in/min)						
1. Shear Strength, lb/in		57	80	120	160	200
2. Peel Strength, lb/in - Hot Wedge - Extension Fillet		45	60	91	121	151
		39	52	78	104	130
<b>Roll Dimensions</b>						
1. Width (feet):		23	23	23	23	23
2. Length (feet):		1000	750	500	375	300
3. Area (square feet):		23,000	17,250	11,500	8,625	6,900
4. Gross weight (pounds, approx.)		3,470	3,470	3,470	3,470	3,470

- Machine direction (MD) and cross machine direction (CMD) average values should be on the basis of 5 test specimens each direction. Yield elongation is calculated using a gauge length of 11.3 inches; break elongation is calculated using a gauge length of 2.0 inches.
  - The yield stress used to calculate applied load for the 3-NCL test shall be the mean value of MQC testing.
  - Other methods such as ASTM D 2118 are acceptable for determining the mean value of MQC testing.
  - Carbon black for 10 phr Ultra-Violet Inhibitor is added to the resin in accordance with the appropriate specification that can be established.
  - The condition of the test should be 20 hr UV cycle at 75°C followed by 4 hr condensation at 60°C.
  - UV resistance is based on percent retained value regardless of the original HP-OIT value.
- The data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06



## SMOOTH HDPE GEOMEMBRANE METRIC UNITS

### Minimum Average Values

Property	Test Method	0.75 mm	1.00 mm	1.50 mm	2.00 mm	2.50 mm
----------	-------------	---------	---------	---------	---------	---------

Thickness, microns	ASTM D 5199					
minimum average		750	1,000	1,500	2,000	2,500
lowest individual reading		675	900	1,350	1,800	2,250

Sheet Density, g/cc	ASTM D 1505/D 792	0.940	0.940	0.940	0.940	0.940
---------------------	-------------------	-------	-------	-------	-------	-------

#### Tensile Properties<sup>1</sup>

Property	ASTM D 1004	ASTM D 4833	ASTM D 5397 (App.)	ASTM D 1603	ASTM D 5596
----------	-------------	-------------	--------------------	-------------	-------------

1. Yield Strength, kN/m	93	125	187	249	311
2. Break Strength, kN/m					
3. Yield Elongation, %					
4. Break Elongation, %					

Tear Resistance, N	ASTM D 1004	240	320	480	640	800
--------------------	-------------	-----	-----	-----	-----	-----

Puncture Resistance, N	ASTM D 4833	300	300	300	300	300
------------------------	-------------	-----	-----	-----	-----	-----

Stress Crack Resistance <sup>2</sup> , hrs	ASTM D 5397 (App.)	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0
--	--------------------	-----------	-----------	-----------	-----------	-----------

Carbon Black Content <sup>3</sup> , %	ASTM D 1603	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0
---------------------------------------	-------------	-----------	-----------	-----------	-----------	-----------

Carbon Black Dispersion	ASTM D 5596	-Note 4-				
-------------------------	-------------	----------	--	--	--	--

Oxidative Induction Time (OIT)						
Standard OIT, minutes	ASTM D 3895	100	100	100	100	100

Oven Aging at 85°C	ASTM D 5721					
High Pressure OIT - % retained after 90 days	ASTM D 5885	80	80	80	80	80

UV Resistance <sup>5</sup>	GRI GM11					
High Pressure OIT <sup>6</sup> - % retained after 1600 hrs	ASTM D 5885	50	50	50	50	50

Seam Properties	ASTM D 6392					
	(@ 5 cm/min)					

1. Shear Strength, kN/m		10	14	21	28	35
2. Peel Strength, kN/m - Hot Wedge		7.9	10.5	15.9	21.2	26.4
- Extrusion Fillet		6.8	9.1	13.6	18.2	22.8

#### Roll Dimensions

1. Width (meters)		7	7	7	7	7
2. Length (meters)		304.9	228.7	152.4	114.3	91.5
3. Area (square meters)		2,137	1,603	1,068	801	641
4. Gross weight (kilograms, approx.)		1,574	1,574	1,574	1,574	1,574

- Machine direction (MD) and cross machine direction (CMD) average values should be on the basis of 5 test specimens; each direction. Yield elongation is calculated using a gauge length of 30 mm; Break elongation is calculated using a gauge length of 50 mm.
- The yield stress used to calculate the applied load for the SP-NCTL test should be the mean value via MOC testing.
- Other methods such as ASTM D 4218 or microwave methods are acceptable if an appropriate correlation can be established.
- Carbon black dispersion for 10 different views: Nine in Categories 1 and 2 with one allowed in Category 3.
- The condition of the test should be 20 hr. UV cycle at 75°C followed by 4 hr. condensation at 60°C.
- UV resistance is based on percent retained value regardless of the original HP-OIT value.

This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06

## TEXTURED HDPE GEOMEMBRANE ENGLISH UNITS



### Minimum Average Values

Property	Test Method	40 mil	60 mil	80 mil	100 mil
----------	-------------	--------	--------	--------	---------

Thickness, mils	ASTM D 5994				
minimum average		38	57	76	95
lowest individual of 8 of 10 readings		36	54	72	90
lowest individual of 10 readings		34	51	68	85

Sheet Density, g/cc	ASTM D 1505/D 792	0.940	0.940	0.940	0.940
---------------------	-------------------	-------	-------	-------	-------

#### Tensile Properties<sup>2</sup>

Property	ASTM D 1004	ASTM D 4833	ASTM D 5397 (App.)	ASTM D 1603	ASTM D 5596
----------	-------------	-------------	--------------------	-------------	-------------

1. Yield Strength, lb/in					
2. Break Strength, lb/in					
3. Yield Elongation, %					
4. Break Elongation, %					

Tear Resistance, lb	ASTM D 1004	28	42	56	70
---------------------	-------------	----	----	----	----

Puncture Resistance, lb	ASTM D 4833	60	90	120	150
-------------------------	-------------	----	----	-----	-----

Stress Crack Resistance <sup>3</sup> , hrs	ASTM D 5397 (App.)	300	300	300	300
--	--------------------	-----	-----	-----	-----

Carbon Black Content <sup>4</sup> , %	ASTM D 1603	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0
---------------------------------------	-------------	-----------	-----------	-----------	-----------

Carbon Black Dispersion	ASTM D 5596	-Note 5-				
-------------------------	-------------	----------	--	--	--	--

Oxidative Induction Time (OIT)					
Standard OIT, minutes	ASTM D 3895	100	100	100	100

Oven Aging at 85°C	ASTM D 5721				
High Pressure OIT - % retained after 90 days	ASTM D 5885	80	80	80	80

UV Resistance <sup>6</sup>	GRI GM11				
High Pressure OIT <sup>7</sup> - % retained after 1600 hrs	ASTM D 5885	50	50	50	50

Seam Properties	ASTM D 6392				
	(@ 2 ft/min)				

1. Shear Strength, lb/in		80	120	160	200
2. Peel Strength, lb/in - Hot Wedge		60	91	121	151
- Extrusion Fillet		52	78	104	130

#### Roll Dimensions

1. Width (feet)		23	23	23	23
2. Length (feet)		750	500	375	300
3. Area (square feet)		17,250	11,500	8,625	6,900
4. Gross weight (pounds, approx.)		3,500	3,500	3,470	3,470

- OIT readings: 8 trials at 7 mils and lowest individual reading must be  $\geq 5$  min.
- Yield strength is calculated using a gauge length of 30 mm; Break elongation is calculated using a gauge length of 50 mm.
- The yield stress used to calculate the applied load for the SP-NCTL test should be the mean value via MOC testing.
- Other methods such as ASTM D 4218 or microwave methods are acceptable if an appropriate correlation can be established.
- Carbon black dispersion for 10 different views: Nine in Categories 1 and 2 with one allowed in Category 3.
- The condition of the test should be 20 hr. UV cycle at 75°C followed by 4 hr. condensation at 60°C.
- UV resistance is based on percent retained value regardless of the original HP-OIT value.

This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06



## TEXTURED HDPE GEOMEMBRANE METRIC UNITS

### Minimum Average Values

1.00 mm 1.50 mm 2.00 mm 2.50 mm

Property	Test Method	1.00 mm	1.50 mm	2.00 mm	2.50 mm
Thickness, microns	ASTM D 5994	950	1,425	1,900	2,375
minimum average		900	1,350	1,800	2,250
lowest individual of 8 of 10 readings		850	1,275	1,700	2,125
lowest individual of 10 readings					
Asperity Height <sup>1</sup> , microns	GRI GM12	250	250	250	250
Sheet Density, g/cc	ASTM D 1505/D 792	0.940	0.940	0.940	0.940

#### Tensile Properties<sup>2</sup>

Property	Test Method	1.00 mm	1.50 mm	2.00 mm	2.50 mm
1. Yield Strength, kN/m	ASTM D 6693	15	22	29	37
2. Break Strength, kN/m		11	16	21	26
3. Yield Elongation, %		12	12	12	12
4. Break Elongation, %		100	100	100	100

Tear Resistance, N ASTM D 1004 125 187 249 311

Puncture Resistance, N ASTM D 4833 267 400 534 667

Stress Crack Resistance<sup>3</sup>, hrs ASTM D 5397 (App.) 300 300 300 300

Carbon Black Content<sup>4</sup>, % ASTM D 1603 2.0 - 3.0 2.0 - 3.0 2.0 - 3.0 2.0 - 3.0

Carbon Black Dispersion ASTM D 5596 -Note 5-

Oxidative Induction Time (OIT) Standard OIT, minutes ASTM D 3895 100 100 100 100

Oven Aging at 85°C ASTM D 5721 80 80 80 80

High Pressure OIT - % retained after 90 days ASTM D 5885 50 50 50 50

UV Resistance<sup>6</sup> GRI GM11

High Pressure OIT<sup>7</sup> - % retained after 1600 hrs ASTM D 5885 50 50 50 50

Seam Properties ASTM D 6392 (@ 5 cm/min)

1. Shear Strength, kN/m 14 24 28 35

2. Peel Strength, kN/m - Hot Wedge 10.5 15.9 21.2 26.4

- Extrusion Fillet 9.1 13.6 18.2 22.8

Roll Dimensions

1. Width (meters): 7 7 7 7

2. Length (meters): 228.7 152.4 114.3 91.5

3. Area (square meters): 1,603 1,068 801 641

4. Gross weight (kilograms, approx): 1,588 1,588 1,574 1,574

OIT 10 readings: 8 must be  $\geq$  180 minutes and lowest individual reading must be  $\geq$  130 minutes.

Machine direction (MD) and cross machine direction (CMD) average values should be on the basis of 5 test specimens each direction.

Yield elongation is calculated using a gauge length of 33 mm; Break elongation is calculated using a gauge length of 50 mm.

The Yield Stress used to calculate the applied load for the SP-AGTEL test should be the mean value via MQC testing.

Chemical resistance as per ASTM D 4218 or microvane methods are acceptable if an appropriate correlation can be established.

Carbon Black dispersion: 10, 40, 60, 80, 100, 120, 140, 160, 180, 200, 220, 240, 260, 280, 300, 320, 340, 360, 380, 400, 420, 440, 460, 480, 500, 520, 540, 560, 580, 600, 620, 640, 660, 680, 700, 720, 740, 760, 780, 800, 820, 840, 860, 880, 900, 920, 940, 960, 980, 1000, 1020, 1040, 1060, 1080, 1100, 1120, 1140, 1160, 1180, 1200, 1220, 1240, 1260, 1280, 1300, 1320, 1340, 1360, 1380, 1400, 1420, 1440, 1460, 1480, 1500, 1520, 1540, 1560, 1580, 1600, 1620, 1640, 1660, 1680, 1700, 1720, 1740, 1760, 1780, 1800, 1820, 1840, 1860, 1880, 1900, 1920, 1940, 1960, 1980, 2000, 2020, 2040, 2060, 2080, 2100, 2120, 2140, 2160, 2180, 2200, 2220, 2240, 2260, 2280, 2300, 2320, 2340, 2360, 2380, 2400, 2420, 2440, 2460, 2480, 2500, 2520, 2540, 2560, 2580, 2600, 2620, 2640, 2660, 2680, 2700, 2720, 2740, 2760, 2780, 2800, 2820, 2840, 2860, 2880, 2900, 2920, 2940, 2960, 2980, 3000, 3020, 3040, 3060, 3080, 3100, 3120, 3140, 3160, 3180, 3200, 3220, 3240, 3260, 3280, 3300, 3320, 3340, 3360, 3380, 3400, 3420, 3440, 3460, 3480, 3500, 3520, 3540, 3560, 3580, 3600, 3620, 3640, 3660, 3680, 3700, 3720, 3740, 3760, 3780, 3800, 3820, 3840, 3860, 3880, 3900, 3920, 3940, 3960, 3980, 4000, 4020, 4040, 4060, 4080, 4100, 4120, 4140, 4160, 4180, 4200, 4220, 4240, 4260, 4280, 4300, 4320, 4340, 4360, 4380, 4400, 4420, 4440, 4460, 4480, 4500, 4520, 4540, 4560, 4580, 4600, 4620, 4640, 4660, 4680, 4700, 4720, 4740, 4760, 4780, 4800, 4820, 4840, 4860, 4880, 4900, 4920, 4940, 4960, 4980, 5000, 5020, 5040, 5060, 5080, 5100, 5120, 5140, 5160, 5180, 5200, 5220, 5240, 5260, 5280, 5300, 5320, 5340, 5360, 5380, 5400, 5420, 5440, 5460, 5480, 5500, 5520, 5540, 5560, 5580, 5600, 5620, 5640, 5660, 5680, 5700, 5720, 5740, 5760, 5780, 5800, 5820, 5840, 5860, 5880, 5900, 5920, 5940, 5960, 5980, 6000, 6020, 6040, 6060, 6080, 6100, 6120, 6140, 6160, 6180, 6200, 6220, 6240, 6260, 6280, 6300, 6320, 6340, 6360, 6380, 6400, 6420, 6440, 6460, 6480, 6500, 6520, 6540, 6560, 6580, 6600, 6620, 6640, 6660, 6680, 6700, 6720, 6740, 6760, 6780, 6800, 6820, 6840, 6860, 6880, 6900, 6920, 6940, 6960, 6980, 7000, 7020, 7040, 7060, 7080, 7100, 7120, 7140, 7160, 7180, 7200, 7220, 7240, 7260, 7280, 7300, 7320, 7340, 7360, 7380, 7400, 7420, 7440, 7460, 7480, 7500, 7520, 7540, 7560, 7580, 7600, 7620, 7640, 7660, 7680, 7700, 7720, 7740, 7760, 7780, 7800, 7820, 7840, 7860, 7880, 7900, 7920, 7940, 7960, 7980, 8000, 8020, 8040, 8060, 8080, 8100, 8120, 8140, 8160, 8180, 8200, 8220, 8240, 8260, 8280, 8300, 8320, 8340, 8360, 8380, 8400, 8420, 8440, 8460, 8480, 8500, 8520, 8540, 8560, 8580, 8600, 8620, 8640, 8660, 8680, 8700, 8720, 8740, 8760, 8780, 8800, 8820, 8840, 8860, 8880, 8900, 8920, 8940, 8960, 8980, 9000, 9020, 9040, 9060, 9080, 9100, 9120, 9140, 9160, 9180, 9200, 9220, 9240, 9260, 9280, 9300, 9320, 9340, 9360, 9380, 9400, 9420, 9440, 9460, 9480, 9500, 9520, 9540, 9560, 9580, 9600, 9620, 9640, 9660, 9680, 9700, 9720, 9740, 9760, 9780, 9800, 9820, 9840, 9860, 9880, 9900, 9920, 9940, 9960, 9980, 10000.

UV resistance is based on percent retained value regardless of the original HP-OIT value.

This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06

## SMOOTH LLDPE GEOMEMBRANE ENGLISH UNITS



### Minimum Average Values

30 Mil 40 Mil 60 Mil 80 Mil

Property	Test Method	30 Mil	40 Mil	60 Mil	80 Mil
Thickness, mils	ASTM D 5199	30	40	60	80
minimum average		27	36	54	72
lowest individual reading					
Sheet Density, g/cc (max.)	ASTM D 1505/D 792	0.939	0.939	0.939	0.939

#### Tensile Properties<sup>1</sup>

Property	Test Method	30 Mil	40 Mil	60 Mil	80 Mil
1. Break Strength, lb/in	ASTM D 6693	114	152	228	304
2. Break Elongation, %		800	800	800	800
2% Modulus, lb/in <sup>2</sup> (max.)	ASTM D 5323	60,000	60,000	60,000	60,000
Tear Resistance, lb	ASTM D 1004	16	22	33	44

Puncture Resistance, lb ASTM D 4833 42 56 84 112

Axis-Symmetric Break Strain, % ASTM D 5617 30 30 30 30

Carbon Black Content<sup>2</sup>, % ASTM D 1603 2.0 - 3.0 2.0 - 3.0 2.0 - 3.0 2.0 - 3.0

Carbon Black Dispersion ASTM D 5596 -Note 3-

Oxidative Induction Time (OIT) Standard OIT, minutes ASTM D 3895 100 100 100 100

Oven Aging at 85°C ASTM D 5721 60 60 60 60

High Pressure OIT - % retained after 90 days ASTM D 5885 35 35 35 35

UV Resistance<sup>4</sup> GRI GM11

High Pressure OIT<sup>5</sup> - % retained after 1600 hrs ASTM D 5885 35 35 35 35

Seam Properties ASTM D 6392 (@ 2 in/min)

1. Shear Strength, lb/in 45 60 90 120

2. Peel Strength, lb/in - Hot Wedge 38 50 75 100

- Extrusion Fillet 34 44 66 88

Roll Dimensions

1. Width (feet): 23 23 23 23

2. Length (feet): 1,000 750 500 375

3. Area (square feet): 23,000 17,250 11,500 8,625

4. Gross weight (pounds, approx): 3,435 3,435 3,435 3,435

Machine direction (MD) and cross machine direction (CMD) average values should be on the basis of 5 test specimens each direction.

Break elongation is calculated using a gauge length of 2.0 inches.

Other methods such as ASTM D 4218 or microvane methods are acceptable if an appropriate correlation can be established.

Carbon Black dispersion for 10 different viscos: Nine in Categories 1 and 2 with one allowed in Category 3.

The condition of the test should be 20 hr. UV cycle at 75°C followed by 4 hr. condensation at 60°C.

UV resistance is based on percent retained value regardless of the original HP-OIT value.

This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06



## SMOOTH LLDPE GEOMEMBRANE METRIC UNITS

### Minimum Average Values

0.75 mm 1.00 mm 1.50 mm 2.00 mm

Property	Test Method	0.75 mm	1.00 mm	1.50 mm	2.00 mm
Thickness, microns	ASTM D 5199	750	1,000	1,500	2,000
minimum average		675	900	1,350	1,800
lowest individual reading					

Sheet Density, g/cc (max.)	ASTM D 1505/D 792	0.939	0.939	0.939	0.939
----------------------------	-------------------	-------	-------	-------	-------

#### Tensile Properties<sup>1</sup>

	ASTM D 6693				
--	-------------	--	--	--	--

1. Break Strength, kN/m		20	27	40	53
2. Break Elongation, %		800	800	800	800

2% Modulus, MPa (max.)	ASTM D 5323	414	414	414	414
------------------------	-------------	-----	-----	-----	-----

Tear Resistance, N	ASTM D 1004	70	100	150	200
--------------------	-------------	----	-----	-----	-----

Puncture Resistance, N	ASTM D 4833	190	250	370	500
------------------------	-------------	-----	-----	-----	-----

Axi-Symmetric Break Strain, %	ASTM D 5617	30	30	30	30
-------------------------------	-------------	----	----	----	----

Carbon Black Content <sup>2</sup> , %	ASTM D 1603	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0
---------------------------------------	-------------	-----------	-----------	-----------	-----------

Carbon Black Dispersion	ASTM D 5596	-Note 3-			
-------------------------	-------------	----------	--	--	--

Oxidative Induction Time (OIT)					
--------------------------------	--	--	--	--	--

Standard OIT, minutes	ASTM D 3895	100	100	100	100
-----------------------	-------------	-----	-----	-----	-----

Oven Aging at 85°C	ASTM D 5721				
--------------------	-------------	--	--	--	--

High Pressure OIT - % retained after 90 days	ASTM D 5885	60	60	60	60
--	-------------	----	----	----	----

UV Resistance <sup>4</sup>	GRI GM11				
----------------------------	----------	--	--	--	--

High Pressure OIT <sup>5</sup> - % retained after 1600 hrs	ASTM D 5885	35	35	35	35
--	-------------	----	----	----	----

#### Seam Properties

	ASTM D 6392				
--	-------------	--	--	--	--

	(@ 5 cm/min)				
--	--------------	--	--	--	--

1. Shear Strength, kN/m		7.9	10.5	15.8	21.0
-------------------------	--	-----	------	------	------

2. Peel Strength, kN/m - Hot Wedge		6.6	8.7	13.1	17.5
------------------------------------	--	-----	-----	------	------

- Extrusion Fillet		5.9	7.7	11.5	15.4
--------------------	--	-----	-----	------	------

#### Roll Dimensions

1. Width (meters)		7	7	7	7
-------------------	--	---	---	---	---

2. Length (meters)		304.9	228.7	152.4	114.3
--------------------	--	-------	-------	-------	-------

3. Area (square meters)		2,137	1,603	1,068	801
-------------------------	--	-------	-------	-------	-----

4. Gross weight (kilograms, approx.)		1,558	1,558	1,558	1,558
--------------------------------------	--	-------	-------	-------	-------

1 Machine direction (MD) and cross machine direction (CMD) average values should be on the basis of 5 test specimens each direction. Break elongation is calculated using a gauge length of 50 mm.

2 Other methods such as ASTM D 4218 or microwave methods are acceptable if an appropriate correlation can be established.

3 Carbon black dispersion for 10 different views: Nine in Categories 1 and 2 with one allowed in Category 3.

4 The condition of the test should be 20 hr. UV cycle at 75°C followed by 4 hr. condensation at 60°C.

5 UV resistance is based on percent retained value regardless of the original HIP-OIT value.

This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 17/06

## TEXTURED LLDPE GEOMEMBRANE ENGLISH UNITS



### Minimum Average Values

40 Mil 60 Mil 80 Mil

Property	Test Method	40 Mil	60 Mil	80 Mil
Thickness, mils	ASTM D 5994	38	57	76
minimum average		36	54	72
lowest individual of 8 of 10 readings				
lowest individual of 10 readings		34	51	68

Sheet Density, g/cc (max.)	ASTM D 1505/D 792	0.939	0.939	0.939
----------------------------	-------------------	-------	-------	-------

#### Tensile Properties<sup>2</sup>

	ASTM D 6693			
--	-------------	--	--	--

1. Break Strength, lb/in		60	90	120
2. Break Elongation, %		250	250	250

2% Modulus, lb/in <sup>2</sup> (max.)	ASTM D 5323	60,000	60,000	60,000
---------------------------------------	-------------	--------	--------	--------

Tear Resistance, lb	ASTM D 1004	22	33	44
---------------------	-------------	----	----	----

Puncture Resistance, lb	ASTM D 4833	44	66	88
-------------------------	-------------	----	----	----

Axi-Symmetric Break Strain, %	ASTM D 5617	30	30	30
-------------------------------	-------------	----	----	----

Carbon Black Content <sup>3</sup> , %	ASTM D 1603	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0
---------------------------------------	-------------	-----------	-----------	-----------

Carbon Black Dispersion	ASTM D 5596	-Note 4-			
-------------------------	-------------	----------	--	--	--

Oxidative Induction Time (OIT)				
--------------------------------	--	--	--	--

Standard OIT, minutes	ASTM D 3895	100	100	100
-----------------------	-------------	-----	-----	-----

Oven Aging at 85°C	ASTM D 5721			
--------------------	-------------	--	--	--

High Pressure OIT - % retained after 90 days	ASTM D 5885	60	60	60
--	-------------	----	----	----

UV Resistance <sup>5</sup>	GRI GM11			
----------------------------	----------	--	--	--

High Pressure OIT <sup>6</sup> - % retained after 1600 hrs	ASTM D 5885	35	35	35
--	-------------	----	----	----

#### Seam Properties

	ASTM D 6392			
--	-------------	--	--	--

	(@ 2 in/min)			
--	--------------	--	--	--

1. Shear Strength, lb/in		60	90	120
--------------------------	--	----	----	-----

2. Peel Strength, lb/in - Hot Wedge		50	75	100
-------------------------------------	--	----	----	-----

- Extrusion Fillet		44	66	88
--------------------	--	----	----	----

#### Roll Dimensions

1. Width (feet)		23	23	23
-----------------	--	----	----	----

2. Length (feet)		750	500	375
------------------	--	-----	-----	-----

3. Area (square feet)		17,250	11,500	8,625
-----------------------	--	--------	--------	-------

4. Gross weight (pounds, approx.)		3,465	3,465	3,435
-----------------------------------	--	-------	-------	-------

1 Of 10 readings: 8 must be  $\geq$  7 mils and lowest individual reading must be  $\geq$  5 mils.

2 Machine direction (MD) and cross machine direction (CMD) average values should be on the basis of 5 test specimens each direction.

3 Other methods such as ASTM D 4218 or microwave methods are acceptable if an appropriate correlation can be established.

4 Carbon black dispersion for 10 different views: Nine in Categories 1 and 2 with one allowed in Category 3.

5 The condition of the test should be 20 hr. UV cycle at 75°C followed by 4 hr. condensation at 60°C.

6 UV resistance is based on percent retained value regardless of the original HIP-OIT value.

This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06



**Minimum Average Values**

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
Thickness, microns	ASTM D 5994	950	1,425	1,900
minimum average		900	1,350	1,800
lowest individual of 8 of 10 readings		850	1,275	1,700
lowest individual of 10 readings				
Asperity Height <sup>1</sup> , microns	GRI GM12	250	250	250
Sheet Density, g/cc (max.)	ASTM D 1505/D 792	0.939	0.939	0.939

**Tensile Properties<sup>2</sup>**

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
1. Break Strength, kN/m	ASTM D 6693	11	16	21
2. Break Elongation, %		250	250	250
2% Modulus, MPa (max.)	ASTM D 5523	414	414	414

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
Tear Resistance, N	ASTM D 1004	100	150	200

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
Puncture Resistance, N	ASTM D 4833	200	300	400

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
Axis-Symmetric Break Strain, %	ASTM D 5617	30	30	30

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
Carbon Black Content <sup>3</sup> , %	ASTM D 1603	2.0 - 3.0	2.0 - 3.0	2.0 - 3.0

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
Carbon Black Dispersion	ASTM D 5596	→Note 4→		

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
Oxidative Induction Time (OIT)				

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
Standard OIT, minutes	ASTM D 3895	100	100	100

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
Oven Aging at 85°C	ASTM D 5721			

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
High Pressure OIT <sup>6</sup> - % retained after 90 days	ASTM D 5885	60	60	60

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
UV Resistance <sup>5</sup>	GRI GM11			

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
High Pressure OIT <sup>6</sup> - % retained after 1600 hrs	ASTM D 5885	35	35	35

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
Seam Properties	ASTM D 6392			

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
1. Shear Strength, kN/m	(@ 5 cm/min)	10.5	15.8	21.0

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
2. Peel Strength, kN/m - Hot Wedge		8.7	13.1	17.5

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
- Extrusion Fillet		5.9	7.7	11.5

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
3. Area (square meters)		7	7	7

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
4. Cross weight (kilograms, approx.):		228.7	152.4	114.3

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
5. Length (meters)		1,603	1,068	801

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
6. UV resistance is based on percent retained value regardless of the original HP-OIT value.		1,572	1,572	1,558

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
7. This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06				

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
8. OIT 10 readings: 8 met be $\leq$ 180 microns and lowest individual reading must be $\geq$ 130 microns.				

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
9. Machine direction (MD) and cross machine direction (CMD) average values should be on the basis of 5 test specimens each direction.				

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
10. Break elongation is calculated as gauge length of 20 mm.				

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
11. OIT values are acceptable if an appropriate correlation can be established.				

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
12. Carbon black dispersion has 10 different vees: Nine in Categories 1 and 2 with one allowed in Category 3.				

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
13. The condition of the test should be 20 hr. UV cycle at 75°C followed by 4 hr. condensation at 60°C.				

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
14. UV resistance is based on percent retained value regardless of the original HP-OIT value.				

Property	Test Method	1.00 mm	1.50 mm	2.00 mm
15. This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06				

**2.4 Quality Control Specifications**

**2.4.1 Raw Materials**

**A. Resin**

All resins for use in geomembrane must pass a candidate pre-approval process before being eligible for use. Each incoming railcar shall be sampled with the following testing performed and compared to the manufacturer's specifications:

1. Density: ASTM D 1505.
2. Melt Index: ASTM D 1238.
3. Oxidative Induction Time (OIT): ASTM D 3895.

**B. Additives**

All incoming materials are to be tested and approved prior to use with the following testing performed and compared to the manufacturer's specifications:

1. Carbon Black Content: ASTM D 1603.
2. Oxidative Induction Time (OIT): ASTM D 3895.

**2.4.2 Finished Product: During Production**

**A. Inspection**

Performed on each roll during manufacturing.

**1. Appearance**

Sheet surface appearance shall be monitored for flaws.

**2. Thickness**

A full width sample shall be cut from the end of each roll for thickness measurement.

**B. Roll Identification**

Four tags per roll shall be used.

1. Outside the core.
2. On the core plug.
3. On the roll surface.
4. On the production roll sample.

**C. Out-of-Spec. Material**

Any roll not meeting the specification for any of the above inspections shall be separated from other rolls and placed on hold.



## POLY-FLEX LINER SPECIFICATIONS

## POLY-FLEX LINER SPECIFICATIONS



### 2.4.3 Manufacturer's Quality Control & Quality Assurance Testing

#### A. Sampling

Full width samples shall be taken as retains from the end of each roll to the manufacturer's laboratory.

#### B. Testing

The geomembrane quality control testing shall meet the following frequency requirements:

Property	Test Method	Testing Frequency (min.)
Thickness (smooth sheet) (textured sheet)	ASTM D 5199 ASTM D 5994	per roll
Asperity Height (textured sheet only) Alternate the measurement side for double-sided textured sheet.	CRI GM17	every second roll
Sheet Density	ASTM D 1505/D 792	200,000 lb (90,000 kg)
Tensile Properties	ASTM D 6693	20,000 lb (9,000 kg)
1. Yield Strength (HDPE only)		
2. Break Strength		
3. Yield Elongation (HDPE only)		
4. Break Elongation		
7% Modulus (LLDPE only)	ASTM D 5323	per each formulation
Tear Resistance	ASTM D 1004	45,000 lb (20,000 kg)
Puncture Resistance	ASTM D 4833	45,000 lb (20,000 kg)
Asi-Symmetric Break Strain (LLDPE only)	ASTM D 5617	per each formulation
Stress Crack Resistance (HDPE only)	ASTM D 5397 (App.)	per CRI GM10
Carbon Black Content	ASTM D 1603	20,000 lb (9,000 kg)
Carbon Black Dispersion	ASTM D 5596	45,000 lb (20,000 kg)
Oxidative Induction Time (OIT) Standard OIT	ASTM D 3895	200,000 lb (90,000 kg)
Oven Aging at 85°C High Pressure OIT	ASTM D 5721 ASTM D 5885	per each formulation
UV Resistance High Pressure OIT	CRI GM11 ASTM D 5885	per each formulation

#### C. Welding Rod

A sample of welding rod shall be tested at a frequency of once per 25 rolls of welding rod. The following tests shall be performed on the sample:

1. Diameter ASTM D 5199
2. Density ASTM D 1505
3. Melt Index ASTM D 1238
4. Carbon Black Content ASTM D 1603

#### D. Reporting

Results from the testing shall be reviewed by the quality control manager. The test data shall then be transferred to the product data file for roll certification. Material that does not meet specifications shall be identified and placed on hold.

### 3. GEOMEMBRANE INSTALLATION

#### 3.1 Materials Logistics

##### 3.1.1 Transportation and On-site Storage

The geomembrane rolls shall be shipped by flatbed trailer to the job site. The geomembrane shall be stored so as to be protected from puncture, dirt, grease, moisture and excessive heat. Damaged material shall be stored separately for repair or replacement. The rolls shall be stored on a prepared smooth surface (not wooden pallets) and should not be stacked more than two rolls high.

#### 3.2 Earthwork

##### 3.2.1 General

The owner or his representative (soil quality assurance inspector) shall inspect the subgrade preparation. Prior to liner installation the subgrade shall be compacted in accordance with the project specifications. Weak or compressible areas which cannot be satisfactorily compacted should be removed and replaced with properly compacted fill. All surfaces to be lined shall be smooth and free of all foreign and organic material, sharp objects, or debris of any kind. The subgrade shall provide a firm, unyielding foundation with no sharp changes or abrupt breaks in grade. Standing water or excessive moisture shall not be allowed.

The installer, on a daily basis, shall approve the surface on which the geomembrane will be installed. After the supporting soil surface has been approved, it shall be the installer's responsibility to indicate to the inspector any changes to its condition that may require repair work.

##### 3.2.2 Anchor Trench

The anchor trench shall be excavated to the line, grade, and width shown on the project construction drawings, prior to liner system placement. Slightly rounded corners shall be provided in the trench to avoid sharp bends in the geomembrane.



## POLY-FLEX LINER SPECIFICATIONS

## POLY-FLEX LINER SPECIFICATIONS



### 3.3 Method of Placement

The rolls shall be deployed using a spreader bar assembly attached to a loader bucket or by other methods approved by the project engineer.

The installer shall be responsible for the following:

1. Equipment or tools shall not damage the geomembrane during handling, transportation and deployment.
2. Personnel working on the geomembrane shall not smoke or wear damaging shoes.
3. The method used to unroll the panels shall not cause scratches or crimps in the geomembrane and shall not damage the supporting soil.
4. Adequate loading (e.g., sand bags or similar items that will not damage the geomembrane) shall be placed to prevent uplift by wind (in case of high winds, continuous loading is recommended along edges of panels to minimize risk of wind flow under the panels).

#### 3.3.1 Weather Conditions

Geomembrane deployment shall proceed between ambient temperatures of 32° F and 104° F. Placement can proceed below 32° F only after it has been verified by the inspector that the material can be seamed according to the specification. Geomembrane placement shall not be done during any precipitation, in the presence of excessive moisture (e.g., fog, rain, dew) or in the presence of excessive winds, as determined by the installation supervisor.

### 3.4 Field Seaming

Approved seaming processes are fusion and extrusion welding. On side slopes, seams shall be oriented in the general direction of maximum slope, i.e., oriented down, not across the slope. In corners and odd-shaped geometric locations, the number of field seams shall be minimized.

No base T-seam shall be closer than 5 feet from the toe of the slope. Seams shall be aligned with the least possible number of wrinkles and "fishmouths." If a fishmouth or wrinkle is found, it shall be relieved and cap-stripped.

#### 3.4.1 Seam Overlap

Geomembrane panels must have a finished minimum overlap of 4 inches for fusion welding and 6 inches for extrusion welding.

Cleaning solvents may not be used unless the product is approved by the liner manufacturer.

#### 3.4.2 Test Seams

Field test seams shall be conducted on the liner to verify that seaming conditions are satisfactory. Test seams shall be conducted at the beginning of each seaming period and at least once every 4 hours, for each seaming apparatus and personnel used that day.

All test seams shall be made in contact with the substrate. Welding rod used for extrusion welding shall have the same properties as the resin used to manufacture the geomembrane. The test seam samples shall be 10 feet long for fusion welding and 3 feet long for extrusion welding with the seam centered length-wise. Three specimens shall be cut from each end of the test seams by the inspector. The inspector shall use a tensiometer to test 3 specimens for shear and 3 specimens for peel. Each specimen shall be one inch wide with a grip separation of 4 inches plus the width of the seam. The seam shall be centered between the clamps. The rate of grip separation shall be 2 inches per minute.

#### 3.4.3 Assessment of Seam Test Results

For both smooth and textured seams the strength of two out of three 1.0 inch (25 mm) wide strip specimens should meet or exceed values given in this specification. The third must meet or exceed 80% of the given values. The shear percent elongation should exceed 50%. The assumed gauge length is considered to be the unseamed sheet material on either side of the welded area. Elongation measurements should be omitted for field testing. In addition, the peel separation should not exceed 25% based on the proportion of area of separated bond to the area of the original bonding. Regarding the locus-of-break patterns of the different seaming methods in shear and peel, the following are unacceptable break codes per their description in the ASTM D 6392. In this regard, SIP is an acceptable break code.

#### Unacceptable Break Codes

Hot Wedge: AD and AD-BRK > 25%

Extrusion Fillet: AD1, AD2 and AD-Weld (unless strength is achieved)

#### 3.4.4 Non-Destructive Seam Testing

The Installer shall non-destructively test all field seams over their full length.

##### A. Vacuum Box Testing

Equipment for testing extrusion seams shall be comprised of the following:

1. A vacuum box assembly consisting of a rigid housing, a transparent viewing window, a soft rubber gasket attached to the bottom, port hole or valve assembly, and a vacuum gauge.
2. Soapy solution in a plastic bucket with a mop.

The following procedures shall be followed by the installer:

1. Excess sheet overlap shall be trimmed away.
2. Wet a strip of geomembrane approximately 12 inches wide by the length of box with the soapy solution.
3. Place the box over the wetted area and compress.
4. Create a vacuum of 3 - 5 psig.
5. Ensure that a leak-tight seal is created.
6. For a period of approximately 10 seconds, examine the geomembrane through the viewing window for the presence of animated soap bubbles.



## POLY-FLEX LINER SPECIFICATIONS



## POLY-FLEX LINER SPECIFICATIONS



7. If no animated bubbles appear after 10 seconds, close the vacuum valve and open the bleed valve, move the box over the next adjoining area with a minimum 3 inches overlap and repeat the process.

8. All areas where animated soap bubbles appear shall be marked, repaired and then retested. The following procedures shall apply to locations where seams cannot be non-destructively tested.

1. If the seam is accessible to testing equipment prior to final installation, the seam shall be non-destructively tested prior to final installation.
2. If the seam cannot be tested prior to final installation, the seams shall be spark tested according to the spark tester manufacturer's procedures.

### B. Air Pressure Testing (For Double Fusion Seams Only)

Equipment for testing double fusion seams shall be comprised of the following:

1. An air pump equipped with pressure gauge capable of generating and sustaining a pressure between 25 and 30 psi.
2. A pressure gauge equipped with a sharp hollow needle.

The following procedures shall be followed by the installer:

1. Seal one end of the seam to be tested.
2. Insert needle or other approved pressure feed device through the sealed end of the channel created by the double wedge fusion weld.
3. Energize the air pump to verify the unobstructed passage of air through the channel.
4. Seal the other end of the channel.
5. Energize the air pump to a pressure between 25 and 30 psi, close valve, allow 2 minutes for the injected air to come to equilibrium in the channel, and sustain pressure for approximately 5 minutes.
6. If loss of pressure exceeds 4 psi, or pressure does not stabilize, locate faulty area, repair and retest.
7. If pressure does not drop below the acceptable value after five minutes, cut the air channel open at the opposite end from the pressure gauge. The air channel should deflate immediately indicating that the entire length of the seam has been tested.

### 3.4.5 Destructive Seam Testing

Destructive seam testing should be minimized to preserve the integrity of the liner. The installer shall provide the inspector with one destructive test sample per project specifications (usually once per 500 feet of seam length) from a location specified by the inspector.

#### A. Sampling Procedure

In order to obtain test results prior to completion of liner installation, samples shall be cut by the installer as the seaming progresses. The installer shall also record the date, location, and pass or fail description. All holes in the geomembrane resulting from obtaining the seam samples shall be immediately patched and vacuum tested.

### B. Size and Disposition of Samples

The samples shall be 12 inches wide by 36 inches long with the seam centered lengthwise. The sample shall be cut into three equal-length pieces, one to be given to the inspector, one to be given to the owner and one to the installer.

### C. Field Laboratory Testing

The inspector shall test ten 1-inch wide specimens from his sample, five specimens for shear strength and five for peel strength.

### D. Independent Laboratory Testing

The owner, at his discretion and expense, may send seam samples to a laboratory for testing. The test method and procedures to be used by the independent laboratory shall be the same as used in field testing.

### E. Procedures for Destructive Test Failure

The following procedures shall apply whenever a sample fails the field destructive test:

1. The installer shall cap strip the seam between the failed location and any passed test locations.
2. The installer can retrace the welding path to an intermediate location (usually 10 feet from the location of the failed test), and take a sample for an additional field test. If this test passes, then the seam shall be cap stripped between that location and the original failed location; if the test fails, then the process is repeated.
3. Over the length of seam failure, the installer shall either cut out the old seam, reposition the panel and reseat, or add a cap strip.

### 3.4.6 Defects and Repairs

All seams and non-seam areas of the geomembrane shall be inspected by the inspector for defects, holes, blisters, undispersed raw materials, and any sign of contamination by foreign matter. The surface of the geomembrane shall be clean at the time of inspection.

#### A. Evaluation

Each suspect location in seam and non-seam areas shall be non-destructively tested as appropriate in the presence of the inspector. Each location that fails the non-destructive testing shall be marked by the inspector, and repaired accordingly.

#### B. Repair Procedures

1. Defective seams shall be cap stripped or replaced.
2. Small holes shall be repaired by extrusion welding a bead of extrudate over the hole. If the hole is larger than 1/4 inch, it shall be patched.
3. Tears shall be repaired by patching. If the tear is on a slope or an area susceptible to stress and has a sharp end it must be rounded prior to patching.
4. Blisters, large cuts and undispersed raw materials shall be repaired by patches.



## POLY-FLEX LINER SPECIFICATIONS

- Patches shall be completed by extrusion welding. The weld area shall be ground no more than 10 minutes prior to welding. No more than 10% of the thickness shall be removed by grinding. Welding shall commence where the grinding started and must overlap the previous seam by at least 2 inches. Reseaming over an existing seam without regrinding shall not be permitted. The welding shall restart by grinding the existing seam and rewedding a new seam.

Patches shall be round or oval in shape, made of the same geomembrane, and extend a minimum of 6 inches beyond the edge of defects.

### C. Verification of Repairs

Each repair shall be non-destructively tested. Repairs that pass the non-destructive test shall be taken as an indication of an adequate repair. Failed tests indicate that the repair shall be repeated and retested until passing test results are achieved.

The inspector shall keep daily documentation of all non-destructive and destructive testing. This documentation shall identify all seams that initially failed the test and include evidence that these seams were repaired and successfully retested.

### 3.5 Cover Material and Backfilling of Anchor Trench

The geomembrane shall be covered as soon as possible. The covering operation shall not damage the geomembrane. The cover soil material shall be free of foreign and organic material, sharp objects, or debris of any kind, which could potentially damage the geomembrane. No construction equipment or machinery shall operate directly on the geomembrane. The use of lightweight machinery (i.e., generator, etc.) with low ground pressure is allowed.

The anchor trench shall be backfilled by the earthwork contractor. Trench backfill material shall be placed and compacted in accordance with the project specifications.

Care shall be taken when backfilling the trenches to prevent any damage to the geomembrane. If damage occurs, it shall be repaired prior to backfilling.

### 3.6 Geomembrane Acceptance

The installer shall retain all ownership and responsibility for the geomembrane until accepted by the owner. Final acceptance is when all of the following conditions are met:

- Installation is finished.
- Verification of the adequacy of all field seams and repairs, including associated testing, is complete.

## POLY-FLEX LINER SPECIFICATIONS



### INHERENT PROPERTIES OF POLYETHYLENE LINERS

The properties listed in the table below are primarily inherent on the resin type used to produce the liner or are directly proportional to the thickness of the liner and less dependent on the manufacturing method. Therefore, these properties will not change from roll to roll or even lot to lot. Hence, they should not be included as part of routine quality control testing. The exception to this is Oxidative Induction Time. This test is a measurement of the amount of anti-oxidant added to the resin to produce the finished sheet. This test can function both as a performance test and a quality control test. As a quality control test it is desirable to run the test at high temperatures to keep the test duration short. This test is routinely run at the time of manufacture. As a performance test it is desirable to run the test at lower temperatures. Testing at lower temperatures cannot be done for quality control purposes.

The information given below is based on nominal values. Individual test results may vary from these values depending upon the reproducibility of the test.

### NOMINAL PROPERTIES

TEST DESCRIPTION	TEST METHOD	UNITS	HDPE	LLDPE
Modulus of Elasticity	ASTM D 6693	lb/in <sup>2</sup>	110,000	45,000
Secant Modulus	ASTM D 5323	lb/in <sup>2</sup>	60,000	45,000
Volatile Loss	ASTM D 1203	%	0.1	0.1
Dimensional Stability	ASTM D 1204	%	+/- 0.5	+/- 1.0
Water Absorption (24 hr @ 23 °C)	ASTM D 570	% change	0.1	0.1
Coefficient of Linear Thermal Expansion	ASTM D 696	(cm/cm • °C)	1.2 x 10 <sup>-4</sup>	1.4 x 10 <sup>-4</sup>
Moisture Vapor Transmission Rate (100 °F and 100% relative humidity)	ASTM E 96	g/m <sup>2</sup> -day 100 mil	0.17	—
		80 mil	0.20	0.25
		60 mil	0.26	0.33
		40 mil	0.39	0.45
		30 mil	0.50	0.57
Low Temperature Brittleness	ASTM D 746	°F	<-112	<-112
Oxidative Induction Time	ASTM D 3895	minutes @ 200 °C	100	100
		minutes @ 150 °C	2000	2000
Multi-Axial Tension	ASTM D 5617	stress, lb/in <sup>2</sup>	2200	1500
		strain, %	18	40+
Melt Index	ASTM D 1238	g/10 minutes	0.20	0.20



Drainage Net &  
Geocomposite

**POLY•FLEX  
DRAINAGE NET  
&  
GEOCOMPOSITE  
SPECIFICATIONS**



## POLY-FLEX DRAINAGE NET & GEOCOMPOSITE SPECIFICATIONS

## HDPE DRAINAGE NET ENGLISH UNITS



### Minimum Average Values

Property	Test Method	GN-200	GN-250
Thickness	ASTM D 5199	200 mils	250 mils
Density, min.	ASTM D 1505	0.940 g/cc	0.940 g/cc
Carbon Black Content	ASTM D 1603	1.5 - 3.0%	1.5 - 3.0%
Tensile Strength, (Peak, MD)	ASTM D 7179	45 lb/in	60 lb/in
Transmissivity, (MD) metal plate/net/metal plate hydraulic gradient, $i = 1$ normal pressure = 10,000 lb/ft <sup>2</sup> seat time = 15 minutes	ASTM D 4716	5.0 gal/min-ft	7.2 gal/min-ft

Roll Dimensions			
1. Roll Width	14 ft	14 ft	14 ft
2. Roll Length	325 ft	325 ft	275 ft
3. Roll Area	4550 ft <sup>2</sup>	4550 ft <sup>2</sup>	3850 ft <sup>2</sup>

The above property values, unless otherwise specified, are the minimum acceptable average test results for any roll based on the specified test methods and do not refer to an individual test specimen. This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06A

## 1. GENERAL REQUIREMENTS

### 1.1 Scope

The following describes parameters for the manufacture, supply, and installation of Poly-Flex Drainage Net and Geocomposites.

### 1.2 Qualifications

The drainage net manufacturer shall have successfully manufactured 5,000,000 square feet of polyethylene drainage net.

### 1.3 Submittals

The manufacturer shall provide the following information:

- List of material properties.
- Quality control certificate for the drainage net, geotextile, and geocomposite rolls, upon request.

## 2. MATERIAL SPECIFICATIONS

### 2.1 Materials

#### 2.1.1 Drainage Net

The drainage net shall be manufactured by extruding two sets of polyethylene strands to form a three dimensional structure to provide for planar flow. The drainage net shall be manufactured of polyethylene resin produced in the United States and compounded and manufactured specifically for the intended application. The natural polyethylene resin without the carbon black shall meet the following requirements:

Property	Test Method	Requirements
Density, g/cc	ASTM D 1505 or ASTM D 792	0.945 - 0.955
Melt Index, g/10 min.	ASTM D 1238	< 1.0

The drainage net shall be supplied in rolls 14 feet wide, as manufactured by Poly-Flex, Inc. (2000 W. Marshall Dr., Grand Prairie, Texas 75051). Labels on each roll shall identify the thickness of the material, the width and length of the roll, roll number, and name of the manufacturer. The drainage net rolls shall meet the requirements in this specification.

#### 2.1.2 Geotextile

The geotextile shall be a non-woven, needle punched polyester or polypropylene fabric manufactured in the United States for the specific application. The geotextile rolls shall be 15 feet wide and shall meet the requirements in this specification.

#### 2.1.3 Geocomposite

The geocomposite shall consist of the Poly-Flex HDPE drainage net heat bonded to one layer or sandwiched between two layers of geotextile to create a single-sided or double-sided geocomposite. The geocomposite shall be 13.5 feet wide. The geotextiles shall extend a minimum of 6 inches beyond the edges of drainage net on both sides of the geocomposite roll. The geotextile shall not be bonded to the drainage net within 6 inches from the edges of the rolls.

The drainage net and geocomposite rolls shall meet the following specifications:



## HDPE DRAINAGE NET METRIC UNITS

### Minimum Average Values

Property	Test Method	GN-200	GN-250
Thickness	ASTM D 5199	5.1 mm	6.3 mm
Density, min.	ASTM D 1505	0.940 g/cc	0.940 g/cc
Carbon Black Content	ASTM D 1603	1.5 - 3.0%	1.5 - 3.0%
Tensile Strength (Peak, MD)	ASTM D 7179	7.9 kN/m	10.5 kN/m

Transmissivity, (MD)  
metal plate/net/metal plate  
hydraulic gradient,  $i = 1$   
normal pressure = 480 kPa  
seat time = 15 minutes

#### Roll Dimensions

1. Roll Width	4.27 m	4.27 m
2. Roll Length	99.0 m	83.8 m
3. Roll Area	422.7 m <sup>2</sup>	357.7 m <sup>2</sup>

The above property values, unless otherwise specified, are the minimum acceptable average test results for any roll based on the specified test methods and do not refer to an individual test specimen. This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06

## SINGLE-SIDED GEOCOMPOSITES ENGLISH UNITS



### GEOCOMPOSITE PROPERTIES

Property	Test Method	GC-06S-2.0	GC-08S-2.0	GC-06S-2.5	GC-08S-2.5
Transmissivity, (MD), gal/(min-ft) metal plate/geocomposite/metal plate hydraulic gradient, $i = 1$ normal pressure = 10,000 lb/ft <sup>2</sup> seat time = 15 minutes	ASTM D 4716	1.2 ( $2.5 \times 10^{-4}$ m <sup>2</sup> /sec)	1.0 ( $2 \times 10^{-4}$ m <sup>2</sup> /sec)	2.4 ( $5 \times 10^{-4}$ m <sup>2</sup> /sec)	1.4 ( $2.9 \times 10^{-4}$ m <sup>2</sup> /sec)
Ply Adhesion, lb/in	ASTM D 7005	1	1	1	1
<b>Roll Dimensions</b>					
1. Width, ft		13.5	13.5	13.5	13.5
2. Length, ft		300	250	225	175

### COMPONENT PROPERTIES

#### Geonet

Thickness, mil	ASTM D 5199	200	200	250	250
Density, min., g/cc	ASTM D 1505	0.940	0.940	0.940	0.940
Carbon Black Content, %	ASTM D 1603	1.5 - 3.0	1.5 - 3.0	1.5 - 3.0	1.5 - 3.0
Tensile Strength, (Peak, MD), lb/in	ASTM D 7179	45	45	60	60
Transmissivity, (MD), gal/(min-ft) metal plate/net/metal plate hydraulic gradient, $i = 1$ normal pressure = 10,000 lb/ft <sup>2</sup> seat time = 15 minutes	ASTM D 4716	5.0 ( $1.0 \times 10^{-3}$ m <sup>2</sup> /sec)	5.0 ( $1.0 \times 10^{-3}$ m <sup>2</sup> /sec)	7.2 ( $1.5 \times 10^{-3}$ m <sup>2</sup> /sec)	7.2 ( $1.5 \times 10^{-3}$ m <sup>2</sup> /sec)

#### Geotextile

Unit Weight, oz/yd <sup>2</sup>	ASTM D 5261	6	8	6	8
Grab Strength, lb	ASTM D 4632	160	220	160	220
Grab Elongation, %	ASTM D 4632	50	50	50	50
Tear Strength, lb	ASTM D 4533	65	80	65	80
Puncture Strength, lb	ASTM D 4833	90	120	90	120
Permittivity, sec <sup>-1</sup>	ASTM D 4491	1.3	1.3	1.3	1.3
AO5, MaxARV	ASTM D 4751	70 sieve	80 sieve	70 sieve	80 sieve
UV Stability, % ret. (500 hr.)	ASTM D 4355	70	70	70	70

The above property values, unless otherwise specified, are the minimum acceptable average test results for any roll based on the specified test methods and do not refer to an individual test specimen. Geotextile property values are Minimum Average Roll values, except for AO5, which is Maximum Average Roll Value. Geonet and Geotextile properties are tested prior to lamination. This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06





## SINGLE-SIDED GEOCOMPOSITES METRIC UNITS

Property	Minimum Average Values			
	GC-065-2.0	GC-085-2.0	GC-065-2.5	GC-085-2.5
Transmissivity, (MD), m <sup>2</sup> /sec metal plate/geocomposite/metal plate hydraulic gradient, i = 1 normal pressure = 480 kPa seat time = 15 minutes	2.5 x 10 <sup>-4</sup> (15 l/min-m)	2.0 x 10 <sup>-4</sup> (12 l/min-m)	5.0 x 10 <sup>-4</sup> (30 l/min-m)	2.9 x 10 <sup>-4</sup> (17 l/min-m)
Ply Adhesion, kN/m	0.17	0.17	0.17	0.17
<b>Roll Dimensions</b>				
1. Roll Width, m	4.1	4.1	4.1	4.1
2. Roll Length, m	91.4	76.2	68.6	53.4

### COMPONENT PROPERTIES

Geonet	ASTM D 5199	ASTM D 1505	ASTM D 1603	ASTM D 7179	ASTM D 4716
Thickness, mm	5.1	0.940	1.5 - 3.0	7.9	1.0 x 10 <sup>-3</sup> (62 l/min-m)
Density, min., g/cc	0.940	0.940	1.5 - 3.0	7.9	1.0 x 10 <sup>-3</sup> (62 l/min-m)
Carbon Black Content, %	1.5 - 3.0	1.5 - 3.0	1.5 - 3.0	10.5	1.5 x 10 <sup>-3</sup> (89 l/min-m)
Tensile Strength, (Peak, MD), kN/m	7.9	7.9	10.5	10.5	1.5 x 10 <sup>-3</sup> (89 l/min-m)
Transmissivity, (MD), m <sup>2</sup> /sec metal plate/metal plate hydraulic gradient, i = 1 normal pressure = 480 kPa seat time = 15 minutes	5.1	0.940	1.5 - 3.0	7.9	1.0 x 10 <sup>-3</sup> (62 l/min-m)
<b>Geotextile</b>					
Unit Weight, g/m <sup>2</sup>	203	712	50	289	400
Grab Strength, N	271	979	50	356	534
Grab Elongation, %	203	712	50	289	400
Tear Strength, N	271	979	50	356	534
Puncture Strength, N	203	712	50	289	400
Permittivity, sec <sup>-1</sup>	271	979	50	289	400
AOS, MaxARV, mm	0.212	0.180	0.212	0.180	0.180
UV Stability, % ret. (500 hr.)	70	70	70	70	70

The above property values, unless otherwise specified, are the minimum acceptable average test results for any roll based on the specified test methods and do not refer to an individual test specimen. Geotextile property values are Minimum Average Roll values, except for AOS, which is Maximum Average Roll Value. Geonet and Geotextile properties are tested prior to lamination. This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06

## DOUBLE-SIDED GEOCOMPOSITES ENGLISH UNITS



Property	Minimum Average Values			
	GC-06D-2.0	GC-08D-2.0	GC-06D-2.5	GC-08D-2.5
Transmissivity, (MD), gal/min-ft metal plate/geocomposite/metal plate hydraulic gradient, i = 1 normal pressure = 10,000 lb/ft <sup>2</sup> seat time = 15 minutes	0.8 x 10 <sup>-4</sup> (0.8 x 10 <sup>-4</sup> m <sup>2</sup> /sec)	0.4	0.2	1.0
Ply Adhesion, lb/in	1	1	1	1
<b>Roll Dimensions</b>				
1. Roll Width, ft	13.5	13.5	13.5	13.5
2. Roll Length, ft	250	200	175	150

### COMPONENT PROPERTIES

Geonet	ASTM D 5199	ASTM D 1505	ASTM D 1603	ASTM D 7179	ASTM D 4716
Thickness, mil	200	0.940	1.5 - 3.0	45	5.0
Density, min., g/cc	0.940	0.940	1.5 - 3.0	45	5.0
Carbon Black Content, %	1.5 - 3.0	1.5 - 3.0	1.5 - 3.0	60	7.2
Tensile Strength, (Peak, MD), lb/in	45	45	60	60	7.2
Transmissivity, (MD), gal/min-ft metal plate/metal plate hydraulic gradient, i = 1 normal pressure = 10,000 lb/ft <sup>2</sup> seat time = 15 minutes	0.8 x 10 <sup>-4</sup> (0.8 x 10 <sup>-4</sup> m <sup>2</sup> /sec)	0.4	0.2	1.0	1.0 x 10 <sup>-3</sup> (1.0 x 10 <sup>-3</sup> m <sup>2</sup> /sec)
<b>Geotextile</b>					
Unit Weight, oz/yd <sup>2</sup>	6	8	6	6	8
Grab Strength, lb	160	220	160	220	220
Grab Elongation, %	50	50	50	50	50
Tear Strength, lb	65	80	65	80	80
Puncture Strength, lb	90	120	90	120	120
Permittivity, sec <sup>-1</sup>	1.3	1.3	1.3	1.3	1.3
AOS, MaxARV	70 sieve	80 sieve	70 sieve	80 sieve	80 sieve
UV Stability, % ret. (500 hr.)	70	70	70	70	70

The above property values, unless otherwise specified, are the minimum acceptable average test results for any roll based on the specified test methods and do not refer to an individual test specimen. Geotextile property values are Minimum Average Roll values, except for AOS, which is Maximum Average Roll Value. Geonet and Geotextile properties are tested prior to lamination. This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06



## DOUBLE-SIDED GEOCOMPOSITES METRIC UNITS



## POLY-FLEX DRAINAGE NET & GEOCOMPOSITE SPECIFICATION

### GEOCOMPOSITE PROPERTIES

Property	Test Method	Minimum Average Values			
		GC-06D-2.0	GC-08D-2.0	GC-06D-2.5	GC-08D-2.5
Transmissivity, (MD), m <sup>2</sup> /sec	ASTM D 4716	0.8 x 10 <sup>-4</sup> (5.0 l/min-m)	4.0 x 10 <sup>-5</sup> (2.5 l/min-m)	2.0 x 10 <sup>-4</sup> (12 l/min-m)	1.0 x 10 <sup>-4</sup> (6.2 l/min-m)
metal plate/geocomposite/metal plate hydraulic gradient, I = 1					
normal pressure = 480 kPa					
seat time = 15 minutes					
Ply Adhesion, kN/m	ASTM D 7005	0.17	0.17	0.17	0.17

### Roll Dimensions

1. Roll Width, m	4.1	4.1	4.1	4.1
2. Roll Length, m	76.2	61	53.4	45.7

### COMPONENT PROPERTIES

Geonet		Geotextile			
Thickness, mm	ASTM D 5199	5.1	5.1	6.3	6.3
Density, min., g/cc	ASTM D 1505	0.940	0.940	0.940	0.940
Carbon Black Content, %	ASTM D 1603	1.5 - 3.0	1.5 - 3.0	1.5 - 3.0	1.5 - 3.0
Tensile Strength, (Peak, MD), kN/m	ASTM D 7179	7.9	7.9	10.5	10.5
Transmissivity, (MD), m <sup>2</sup> /sec	ASTM D 4716	1.0 x 10 <sup>-3</sup> (62 l/min-m)	1.0 x 10 <sup>-3</sup> (62 l/min-m)	1.5 x 10 <sup>-3</sup> (89 l/min-m)	1.5 x 10 <sup>-3</sup> (89 l/min-m)
metal plate/net/metal plate hydraulic gradient, I = 1					
normal pressure = 480 kPa					
seat time = 15 minutes					
Unit Weight, g/m <sup>2</sup>	ASTM D 5261	203	271	203	271
Grab Strength, N	ASTM D 4632	712	979	712	979
Grab Elongation, %	ASTM D 4632	50	50	50	50
Tear Strength, N	ASTM D 4533	289	356	289	356
Puncture Strength, N	ASTM D 4833	400	534	400	534
Permittivity, sec <sup>-1</sup>	ASTM D 4491	1.3	1.3	1.3	1.3
AOS, MaxARV, mm	ASTM D 4751	0.212	0.180	0.212	0.180
UV Stability, % ret. (500 hr.)	ASTM D 4355	70	70	70	70

The above property values, unless otherwise specified, are the minimum acceptable average test results for any roll based on the specified test methods and do not refer to an individual test specimen. Geotextile property values are Minimum Average Roll values, except for AOS, which is Maximum Average Roll Value. Geonet and Geotextile properties are tested prior to lamination. This data is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. These values are subject to change without notice. REV. 11/06

### 2.2 Manufacturer's Quality Control Testing

The Drainage Net shall be tested by its manufacturer once every 50,000 square feet for listed properties, except the transmissivity, which shall be tested once every 100,000 square feet.

The geotextile shall be tested by its manufacturer once every 100,000 square feet, except for AOS and Permittivity, which shall be tested once every 500,000 square feet and UV stability, which shall be per manufacturer historical data.

The geocomposite shall be tested by its manufacturer once every 100,000 square feet for the listed properties. Any rolls not meeting the requirements of the specification shall be rejected. The manufacturer shall prepare a quality control report to be submitted to the project engineer upon request.

## 3. INSTALLATION

### 3.1 Transportation and On-site Storage

The drainage net and geocomposite rolls shall be wrapped in a plastic cover. The drainage net and geocomposite rolls shall be shipped to the job site in a manner not to damage the rolls.

### 3.2 Method of Placement

The subgrade shall be free of foreign and organic material, sharp objects, or debris of any kind, which could potentially damage the geocomposite. The rolls shall be deployed using a spreader bar assembly attached to a loader bucket or by other methods approved by the project engineer. On side slopes, the rolls shall be deployed in the general direction of the maximum slope. The deployment equipment shall not damage the underlying subgrade or geosynthetics. A smooth rub sheet may be needed for installation of the geocomposite over a textured geomembrane. The rub sheet is placed between the geocomposite and the textured geomembrane to prevent damage to geocomposite during positioning. The rub sheet is removed after deployment. Drainage net and geocomposite shall be placed and secured in an anchor trench as shown on the project drawings. Sandbags shall be placed on leading edges of the panels to prevent wind uplift. An extra layer of drainage net or geocomposite may be required at the intersection of any two sideslopes to cover the area where the panels are staggered.

### 3.3 Field Seaming

Drainage net panels shall be overlapped by a minimum of 2 inches. Non-black plastic ties shall be used at 5-foot intervals in the direction of the roll length and at 2-foot intervals across the end of the panel to tie the drainage net panels. Metallic ties shall not be allowed. On slopes, the spacing of ties across the roll end shall be 6 inches. The geotextile flaps of the adjacent panels shall be heat-bonded or sewn on all sides in accordance with the project specification.

### 3.4 Cover Material

The drainage net and geocomposite shall be covered as soon as possible. The covering operation shall not damage the drainage net or the geocomposite. The cover soil material shall be free of foreign and organic material, sharp objects, or debris of any kind, which could potentially damage the geocomposite. No construction equipment or machinery shall operate directly on the geocomposite. The use of lightweight machinery (i.e., generator, etc.) with low ground pressure is allowed.

### 3.5 Repairs

All panels shall be inspected for damage. Any damaged area shall be repaired by a patch of the same material extending one foot beyond the edges of the damaged area.



---

**POLY-FLEX  
POLYETHYLENE  
EMBED CHANNEL  
SPECIFICATION**

Polyethylene  
Embed Channel



## POLYETHYLENE EMBED CHANNEL SPECIFICATION

## POLYETHYLENE EMBED CHANNEL SPECIFICATION



### GENERAL

#### 1.1 Scope

The following describes parameters for the manufacture, supply, and installation of Poly-Flex High Density Polyethylene Embed Channel (PEC). All procedures, operations, and methods shall be in strict accordance with the engineer's specifications and drawings.

#### 1.2 References

American Society for Testing and Materials

#### 1.3 Submittals

1. The manufacturer shall maintain test records of the resins used to manufacture the PEC. This record shall be made available to the Engineer upon request.
2. The contractor shall submit shop drawings showing the exact location and installation procedures.
3. At the engineer's request, sample(s) of PEC shall be submitted.

#### 1.4 Manufacturer's Quality Control Testing

All resins for use in PEC must pass the Poly-Flex raw material specifications before being eligible for use. Each lot shall be sampled and tested in the Poly-Flex, Inc. laboratory. The tests shall include density, melt index, and carbon black content. All additives and concentrates must pass Poly-Flex specifications.

### PRODUCT

#### 2.1 Product

The PEC shall be manufactured by Poly-Flex, Inc. The raw material shall be made of polyethylene resins manufactured in the United States. Carbon black shall be added to the resin if the resin is not precompounded for ultra-violet resistance. The final product shall meet the following values:

Density:	ASTM D1505	± 0.940 g/cc
Melt Index:	ASTM D1238	± 0.4 g/10 minutes
Carbon Black Content:	ASTM D1603	2% - 3%
Tensile Strength at Yield:	ASTM D6693	2,100 lb/in <sup>2</sup>
Dimensions:	As shown on the drawing on page 35.	
Weight:	0.45 lb/ft	
Length:	5 ft and 10 ft	

#### 2.2 Shipment and Storage

PEC shall be shipped in a manner not to be damaged by packaging or handling and shall be stored in a clean environment.

### INSTALLATION

PEC can be nailed to wooden forms or pushed or vibrated into poured concrete. A 3-inch clearance is recommended from concrete edges or corners.

#### 3.1 Installation in concrete forms

PEC shall be installed inside the concrete forms in accordance with the shop drawings prior to pouring concrete. Place PEC in the designated locations with the surface of PEC in contact with the form. PEC shall be secured to the wooden forms by means of nails driven from the inside of PEC into the forms (see Step 1 drawing). All exposed nails shall be clipped at the surface of PEC after removal of the forms (see Step 2 drawing).

#### 3.2 Fabrication

PEC can be prefabricated into frames and vibrated into freshly poured concrete. Small air vent holes shall be drilled in approximately 3-foot intervals in the surface of PEC prior to its placement into fresh concrete. Butt welded connections are made by extrusion welding the back side of the 3.5-inch surface and the outside of the legs. Backup HDPE plates are sometimes used behind the surface to be butt welded to reinforce the connection. A very flat extrusion weld bead is then placed on the 3.5-inch surface. PEC can also be butt welded similar to HDPE pipe welding techniques (See Figure 1). The two pieces (A & B) to be welded are laid on a flat surface. Each piece is held in contact with the "welding mirror" (C) for approximately 45 seconds until a melt bead (D) forms at the mirror; the mirror is removed (E) and the pieces are pushed together (F) fusing the molten plastic. This process gives a full perimeter weld of the PEC. Care must be exercised to assure alignment of the channels after the weld. This method can also be used for miter joints.

It is necessary to prevent gaps or repair gaps caused by thermal contraction or improper placement of the PEC. The liner-to-PEC connection will not be water tight unless the PECs are properly joined at their ends. Other PEC installation details are available from Poly-Flex, Inc.

#### 3.3 Seaming

All seaming shall be done in accordance with the Poly-Flex extrusion seaming procedures, as outlined in this manual, and by experienced technicians who are qualified by Poly-Flex, Inc. to seam Poly-Flex liners.

The following steps shall be followed prior to welding Poly-Flex liners to the PEC:


1. Remove cement paste, form oils, curing compound or other contaminants from the surface of PEC. The 3.5-inch wide surface shall be clean and dry. The welding surfaces of the PEC can be taped prior to its installation. The tape is removed after the concrete is hardened to expose the clean surfaces of PEC for welding.
2. Use a hot air gun to tack liner to PEC in a straight line in the center of the PEC surface.
3. A grinder with 80-grit disc shall be used to remove the surface contamination and oxidation from the welding surface area prior to the extrusion welding. Place the extrudate on the center line (see Step 3 drawing). All air vent or nail holes shall also be ground and covered with the extrudate.

All seams shall be non-destructively tested, whenever possible, by using a vacuum box apparatus if the PEC connection is designed to be waterproof.

Since destructive seam testing is not possible, it is very important that seaming be done by qualified technicians.



# POLYETHYLENE EMBED CHANNEL SPECIFICATION





---

# CHEMICAL RESISTANCE INFORMATION

Chemical  
Resistance

## CHEMICAL RESISTANCE INFORMATION

### CHEMICAL COMPATIBILITY OF POLY-FLEX LINERS

Chemical compatibility or resistance, as applied to geomembranes, is a relative term. Actual compatibility would mean that one material dissolves in the other such as alcohol in water or grease in gasoline. An example of incompatibility would be oil and water. In liners it is undesirable to have the chemicals dissolve in the liner, hence the term compatibility is the reverse of what is normally meant in the chemical industry. In the strictest sense and from a laboratory perspective, chemical compatibility, as the term applies to this industry, would imply that the chemical has no effect on the liner. On the other hand, from an engineering perspective, chemical compatibility means that a liner survives the exposure to a given chemical even though the chemical could have some effect on the performance of the liner, but not enough to cause failure. Therefore, one must understand and define chemical compatibility for a specific project.

Generally polyethylene is effected by chemicals in one of three ways.

1. No effect—This means that the chemical in question and the polyethylene do not interact. The polyethylene does not gain (lose) weight or swell, and the physical properties are not significantly altered.
2. Oxidizes (cross linking)—Chemicals classed as oxidizing agents cause the polyethylene molecules to cross link and cause irreversible changes to the physical properties of the liner. Basically they make the liner brittle.

3. Plasticizer—Chemicals in this classification are soluble in the polyethylene structure. They do not change the structure of the polyethylene itself but act as a plasticizer. In doing so, the liner experiences weight gain of 3-15%, may swell by up to 10%, and has measurable changes in physical properties (e.g. the tensile strength at yield may decrease by up to 20%). Even under these conditions the liner maintains its integrity and is not breached by liquids, provided the liner has not been subjected to any stress. These effects are reversible once the chemicals are removed and the liner has time to dry out.

Aside from the effect that chemicals have on a liner is the issue of vapor permeation through the liner. Vapor permeation is molecular diffusion of chemicals through the liner. Vapor transmission for a given chemical is dependent primarily on liner type, contact time, chemical solubility, temperature, thickness, and concentration gradient, but not on hydraulic head or pressure. Transmission through the liner can occur in as little as 1-2 days. Normally, a small amount of chemical is transmitted. Generally HDPE has the lowest permeation rate of the liners that are commercially available.

As stated above chemical compatibility is a relative term. For example, the use of HDPE as a primary containment of chlorinated hydrocarbons at a concentration of 100% may not be recommended, but it may be acceptable at 0.1% concentration for a limited time period or may be acceptable for secondary containment. Factors that go into assessment of chemical compatibility are type of chemical(s), concentration, temperature and the type of application. No hard and fast rules are available to make decisions on chemical compatibility. Even the EPA 9090 test is just a method to generate data so that an opinion on chemical compatibility can be more reliably reached.

A simplified table on chemical resistance is provided to act as a screening process for chemical containment applications.

## CHEMICAL RESISTANCE INFORMATION

CHEMICAL CLASS	CHEMICAL EFFECT	PRIMARY CONTAINMENT (LONG TERM CONTACT) HDPE	SECONDARY CONTAINMENT (SHORT TERM CONTACT) HDPE	LDPE
CARBOXYLIC ACID - Unsubstituted (e.g. Acetic acid) - Substituted (e.g. Lactic acid) - Aromatic (e.g. Benzoic Acid)	1	B C A	C B A	C A A
	3	B C	C C	B C
	3	B C	C C	B C
ALDEHYDES (e.g. Acetaldehyde) - Aliphatic (e.g. Formaldehyde) - Aromatic (e.g. Furfural)	1	A A	A A	A A
	3	B C	C C	B C
	3	B C	C C	B C
AMINE - Primary (e.g. Ethylamine) - Secondary (e.g. Diethylamine) - Aromatic (e.g. Aniline)	1	A A	A A	A A
	3	B C	C C	B C
	3	B C	C C	B C
ESTER (e.g. Ethyl acetate) ETHER (e.g. Ethyl ether)	1	A A	A A	A A
	3	B C	C C	B C
	3	B C	C C	B C
HYDROCARBONS - Aliphatic (e.g. Hexane) - Aromatic (e.g. Benzene) - Mixed (e.g. Crude Oil)	1	A A	A A	A A
	3	B C	C C	B C
	3	B C	C C	B C
HALOGENATED HYDROCARBONS - Aliphatic (e.g. Dichloroethane) +M - Aromatic (e.g. Chlorobenzene)	1	A A	A A	A A
	3	B C	C C	B C
	3	B C	C C	B C
ALCOHOLS - Aliphatic (e.g. Ethyl alcohol) - Aromatic (e.g. Phenol)	1	A A	A A	A A
	2	A C	A C	A B
	2	A C	A C	A B
INORGANIC ACID - Non-oxidizers (e.g. Hydrochloric acid) - Oxidizers (e.g. Nitric Acid)	1	A A	A A	A A
	1	A A	A A	A A
	1	A A	A A	A A
SALTS (e.g. Calcium chloride) METALS (e.g. Cadmium) KETONES (e.g. Methyl ethyl ketone)	1	A A	A A	A A
	3	C C	C C	B C
	2	C C	C C	C C

Chemical Effect (see discussion on Chemical Resistance)

1. No Effect—Most chemicals of this class have no or minor effect.
2. Oxidize—Chemicals of this class will cause irreversible degradation.
3. Plasticizer—Chemicals of this class will cause a reversible change in physical properties.

Chart Rating

- A. Most chemicals of this class have little or no effect on the liner. Recommended regardless of concentration or temperature (below 150° F).
- B. Chemicals of this class will affect the liner to various degrees. Recommendations are based on the specific chemical, concentration and temperature. Consult with Poly-Flex, Inc.
- C. Chemicals of this class at high concentrations will have significant effect on the physical properties of the liner. Generally not recommended but may be acceptable at low concentrations and with special design considerations. Consult with Poly-Flex, Inc.

The data in this table is provided for informational purposes only and is not intended as a warranty or guarantee. Poly-Flex, Inc. assumes no responsibility in connection with the use of this data. Consult with Poly-Flex, Inc. for specific chemical resistance information and liner selection.



---

**GEOMEMBRANE  
MANUFACTURING  
QUALITY CONTROL  
& QUALITY  
ASSURANCE**

Geomembrane  
Manufacturing QC/QA





**GEOMEMBRANE MANUFACTURING  
QUALITY CONTROL & QUALITY ASSURANCE**

**GEOMEMBRANE MANUFACTURING  
QUALITY CONTROL & QUALITY ASSURANCE**



**1. DEFINITIONS**

Manufacturing Quality Control (MQC) is a planned system of routine inspections that is used to directly monitor and control the quality of a material.

Manufacturing Quality Assurance (MQA) is independent of the MQC and includes inspections, verifications, audits, and evaluations of materials and workmanship necessary to determine and document the quality of a material.

**2. MANUFACTURING QUALITY CONTROL  
AND QUALITY ASSURANCE PROGRAM**

**2.1 Raw Material**

Poly-Flex, Inc.'s quality control and quality assurance for HDPE and LLDPE geomembrane manufacturing starts with the testing of the raw materials. The resin manufacturers provide documentation confirming that the raw materials comply with Poly-Flex, Inc. specifications.

Resin manufacturers report the following properties with each resin shipment:

- Density This property is a measure of unit weight and is an indicator of the degree of crystallinity. It can be related to the material's chemical resistance, rigidity, permeability, tensile strength, and deformation characteristics.
- Melt Index This property is an indication of the molecular weight and rheological properties of the polymer and can be related to the processability.
- Carbon Black Content (pre-compounded only) The carbon black content is an important property to ensure protection against ultraviolet radiation. The raw materials may be pre-compounded with the carbon black. However, if resins are not pre-compounded, Poly-Flex, Inc. will supplement them with the appropriate quantity of carbon black before manufacturing liner.

**2.1.1 Geomembrane Material Railcar Acceptance**

All resins, additives and concentrates used in Poly-Flex geomembranes must have their physical integrity validated before they can be released into the production material stream. All incoming railcars are sampled; incoming materials not delivered by railcar are statistically sampled. Upon verification of the resin compliance with the specifications, the resin is pumped from the railcar into the silos dedicated to the production of the geomembrane.

1. Resin samples are taken from each of the four payload compartments in an incoming railcar.
2. Resin samples are sent to the laboratory. Using state of the art equipment, highly trained Quality Assurance personnel test the resin to ensure that it meets the specifications for producing Poly-Flex geomembranes. The following tests are performed and compared against Poly-Flex specifications:

Property	Resins	Additives & Concentrates
Density (ASTM D 1505)	•	•
Melt Index (ASTM D 1238)	•	•
Carbon Black Content (ASTM D 1603)	•	•
Oxidative Induction Time (ASTM D 3895)	•	•

3. After meeting production specifications, the resin is pumped from its railcar into a silo dedicated to that material.
4. Off-spec material is returned to the vendor.

**Applicable Test Methods**

American Society for Testing and Materials (ASTM)

- ASTM D 792 Specific gravity (relative density) and density of plastics by displacement
- ASTM D 1004 Initial tear resistance of plastic sheeting
- ASTM D 1238 Flow rates of thermoplastics by extrusion platometers
- ASTM D 1505 Density of plastics by the Density-Gradient technique
- ASTM D 1603 Carbon black in olefin plastics
- ASTM D 1898 Sampling of plastics
- ASTM D 3895 Test method for oxidative induction time of polyolefins by thermal analysis
- ASTM D 4833 Index Puncture Resistance of geotextiles, geomembranes and related products
- ASTM D 5199 Test method for measuring nominal thickness of geotextiles and geomembrane
- ASTM D 5323 Determination of 2% secant modulus for polyethylene geomembranes
- ASTM D 5397 Procedure to perform a single point notched constant tensile load - Appendix (SP-NCTL) test
- ASTM D 5596 Test method for microscopic evaluation of the dispersion of carbon black in polyolefin geosynthetics
- ASTM D 5617 Multi-axial tension test for geosynthetics
- ASTM D 5721 Practice for air-oven aging of polyolefin geomembranes
- ASTM D 5885 Test method for oxidative induction time of polyolefin geosynthetics by high pressure differential scanning calorimetry
- ASTM D 5994 Test method for measuring the core thickness of textured geomembranes
- ASTM D 6392 Determining the integrity of nonreinforced geomembrane seams produced using thermo-fusing methods
- ASTM D 6693 Determining tensile properties of nonreinforced polyethylene and nonreinforced flexible polypropylene geomembranes

**Geosynthetic Research Institute (GRI) Standards**

- GM 10 Specification for the stress crack resistance of geomembrane sheet
- GM 11 Accelerated weathering of geomembranes using a fluorescent UVA-condensation exposure device
- GM 12 Measurement of the asperity height of textured geomembranes using a depth gauge

**Addendum to Test Procedures**

The following are modifications or clarifications to test procedures.

1. Specifications are based on the average of Machine Direction (MD) and Cross Direction (XMD) values.
2. Specimens shall be taken uniformly across the width of the sheet as stated in ASTM D 1898.

**3. MANUFACTURING**

**3.1 Blown Sheet Process**

Polyethylene resin is pumped directly from storage silos or from totes on the floor to hoppers above the extruder. Hoppers feed resin into the extruder. The resin is heated to the melting point in the extruder barrel. It is conveyed through the barrel by the rotation of a specially designed screw which, in conjunction with heating elements along the barrel, provides consistency to produce a molten polymer stream.

The molten material is forced through a screen pack, which act as a final filter for impurities or contaminants, and up through a die. It extrudes from the circular die as a film tube ("bubble"), pulled vertically by a set of nip rollers located at the top of a cooling tower. An IBC (Internal Bubble Cooling) unit, part of the extruder, maintains consistent bubble diameter. Material gauge is monitored and maintained by a computer system which controls the operation of the extruder.

At the top of the tower the bubble passes through a collapsing frame and is pulled through the nip rollers. The material is directed back toward the ground, and continues cooling as it approaches a winding machine. Before being taken up by the winder, the tube is split and spread to its deployable width. The winder rolls the finished geomembrane onto a specially made heavy-duty core.

**3.2 Process Quality Control**

Poly-Flex geomembranes are manufactured via the blown sheet process. This is a continuous process. The key elements to successfully producing a high-quality liner is to maintain consistency in both the raw material and the process. As described above, raw material consistency is established in the laboratory when the resin is initially received. Consistency during the processing is assured by an on-line quality control monitor. This representative of the quality department has been specially trained to monitor the process and the liners during the manufacturing process.

The extrusion process starts with the verification of the formulation. This is done at the beginning of each order or blend change by the extrusion manager and then is continuously monitored by the on-line quality control representative.

The process conditions during manufacturing have been optimized for each resin formulation. These conditions are kept in a log book which is available to the line operator. These process conditions must be maintained throughout the production run. Any variation of process parameters from the set point range recorded on the process log book are immediately reported to the production supervisor by the on-line quality control representative. If the variation exceeds the control range, the quality control representative places the material being produced on hold. Materials are placed on hold until the process is brought under control.

The on-line quality monitor can also place material on hold if the material has any visual defect (holes, water spots, or scratches) or dimensional abnormalities (width, length, and thickness).

All materials placed on hold will be further inspected and tested. If the material passes specification and is approved by the quality control manager and/or production manager, the material will then be released into stock. If the material fails to pass specification or does not get approval of either the quality control manager or production manager then the material will be reclassified or scrapped. In either case it cannot be sold as a prime Poly-Flex geomembrane.

Poly-Flex geomembranes are continuously monitored for pinholes during the manufacturing process by spark testing equipment. The spark tester unit is a perpetual monitor of any holes that could surface in the sheet. The spark tester monitors the entire layflat width of the sheet as it is being manufactured. The detector operates from a 120 V AC power supply. The 120 volts are transformed to a higher voltage that ranges from 0-24 kilovolts. The electrode is made up of a long semiconductor blanket that is positioned to lay over the sheet as it passes over a steel roller prior to final winding. A grounding conductor is connected to the roller with a return line to the controller. If a hole passes under the electrically charged blanket, the voltage will arc to the steel roller and the detection system will sense the voltage drop, thus triggering an audible alarm and shutting down the winder. Twice per shift, the quality control technician tests the spark tester by introducing a 1/32" pinhole in the sheet. This hole is at the end of a roll after the scheduled footage has been achieved. The winder continues to run until the hole is detected. Once the hole is detected, the alarm sounds and the winder shuts down. The quality control technician restarts the winder and cuts out the entire layflat area of the pinhole.

After a roll of material has been produced it is labeled and a retain is cut for laboratory evaluation.

**3.3 Roll Labeling**

Three labels are affixed to each roll, as described below:

1. One label on the outside of the core.
2. One label on the core plug.
3. One label on the roll surface.

An additional label is attached to the laboratory sample.

**3.4 Storage, Staging and Shipping of Geomembrane Rolls**

Finished rolls (verified and labeled) are moved to the storage area using a specially designed cart and remain in storage until a Purchase Order is received. Rolls selected for shipment are moved to a staging area, where they are held for a truck. Before loading the order for shipment, all documentation is checked against the information on the roll labels. Rolls are lifted and moved using a loading arm equipped with rigging and hooks. Fork-lifting machinery are never to be used to lift or move geomembrane rolls.





# GEOMEMBRANE MANUFACTURING QUALITY CONTROL & QUALITY ASSURANCE

# GEOMEMBRANE MANUFACTURING QUALITY CONTROL & QUALITY ASSURANCE



## 5. PAPER FLOW FORMS

### 5.1 Product Quality Report

This report documents the raw material manufacturer's test results for the physical properties of the incoming resin. Each incoming shipment to Poly-Flex is accompanied by such a report. A copy of this report is sent to the engineer/client with the finished product.

See Item 10-20-202

**Certificate of Analysis**

<p>Shipped To: <b>ROZ MEXTECA</b>          2004 W. WARDWELL          7500 FRANKLIN TX 75061          USA</p> <p>Customer: <b>CH2M HILL</b>          PO # 10007          SPO Date 12/25/03          Package: <b>BULK</b>          Make: <b>Polysar</b>          Lot #: <b>031321467</b></p>	<p>CPC Delivery #: <b>0654376</b>          PO #: <b>10007</b>          SPO Date: <b>12/25/03</b>          Package: <b>BULK</b>          Make: <b>Polysar</b>          Lot #: <b>031321467</b></p>
--	---

Product: **POLYETHYLENE TEREPHTHALATE**

Property	Test Method	Value	Unit
Inher Invis	ASTM D1238	0.10	g/10m
Inher Flow	ASTM D1238	0.25	g/10m
Density	ASTM D1505	0.9250	g/cm <sup>3</sup>
Production Date		12/20/03	

The data set forth herein has been carefully compiled by Chemron Polysar Chemical Company LP. It is intended to provide a true and accurate representation of the material as received or supplied, applicable to its use, and the user assumes all risk and liability in connection therewith.

J. E. Edwards  
 Certification Systems Manager  
 For Cost questions, contact Peter Spillman at 713-288-4789

Page 1 of 1

### 5.2 Railcar Resin Report

This report is used by Poly-Flex's laboratory to document results of tests performed on incoming raw material. These results are checked against Poly-Flex's raw material specifications and the Product Quality Report issued by the material manufacturer.

### RAILCAR RESIN REPORT

PO # <b>031306</b> Date Rec'd <b>02/03/03</b>	LOCATION <b>HOPE</b> BUY INFORMATION <b>HOPE</b>	Weight <b>185,300</b> Batch Code
--	---	-------------------------------------

Material <b>POLYETHYLENE TEREPHTHALATE</b> Grade <b>330001</b> Lot # <b>031301</b> Type <b>HOPE</b> Description <b>Prime Polysar HOPE</b> Present <b>100%</b>	Melt Index <b>0.12</b> Density <b>0.925</b> Film Thickness Compressive	Ship Arrived Manufacture Expire
--	---	--

<b>CARC CAPACITY</b> (Cubic in) <b>100</b> (Cubic ft) <b>7</b>	Cyl. Vol. <b>100</b> Tare <b>100</b> Net <b>100</b>	Weight <b>185,300</b> Discrepancy <b>100</b> Agreement %
--	---	--

<b>LABORATORY TESTING REPORT</b> Method A <b>0.10</b> CA <b>0.11</b> CB <b>0.10</b> E <b>0.13</b> Avg. <b>0.11</b> R <b>100</b> Method B <b>0.25</b> CA <b>0.25</b> CB <b>0.25</b> E <b>0.25</b> Avg. <b>0.25</b> R <b>100</b> Method C <b>0.925</b> CA <b>0.925</b> CB <b>0.925</b> E <b>0.925</b> Avg. <b>0.925</b> R <b>100</b> Method D <b>12/20/03</b>	Test Type <b>Range</b> Test Results <b>Average</b> Test Method <b>ASTM D1238</b> Test Temp <b>300</b> Test Rate <b>10</b> Test Pressure <b>10</b> Test Viscosity <b>10</b> Test Density <b>10</b> Test Production Date <b>10/20/03</b>
---	--

BR Analysis <b>0.10</b> BR Sample <b>0.10</b> BR Description <b>0.10</b> BR Date <b>02/03/03</b>	Pumping Information Pumping Rate <b>100</b> Pumping Time <b>100</b> Pumping Pressure <b>100</b> Pumping Temperature <b>100</b>	This Report Prepared for <b>HOPE</b> By <b>HOPE</b> Checked by <b>HOPE</b> Approved by <b>HOPE</b> Date <b>02/03/03</b>
---	--	--



---

**DRAINAGE NET  
AND  
GEOCOMPOSITE  
MANUFACTURING  
QUALITY CONTROL  
& QUALITY  
ASSURANCE**



## NET & GEOCOMPOSITE MANUFACTURING QUALITY CONTROL & QUALITY ASSURANCE

## NET & GEOCOMPOSITE MANUFACTURING QUALITY CONTROL & QUALITY ASSURANCE



### 1. MANUFACTURING QUALITY CONTROL AND QUALITY ASSURANCE

This section describes the manufacturing quality control and quality assurance for Poly-Flex drainage net and geocomposite products.

#### 1.1 Applicable Test Methods

American Society for Testing and Materials (ASTM)	
ASTM D 1505	Density of plastics by the density-gradient technique
ASTM D 1603	Carbon black in olefin plastics
ASTM D 4355	Deterioration of geotextiles by exposure to light, moisture and heat in Xenon Arc type apparatus
ASTM D 4491	Water permeability of geotextiles by the permittivity method
ASTM D 4533	Trapezoid tearing strength of geotextiles
ASTM D 4632	Breaking load and elongation of geotextiles (grab method)
ASTM D 4716	Determining the (in-plane) flow rate per unit width and hydraulic transmissivity of geosynthetics using constant head
ASTM D 4751	Determining apparent opening size of geotextiles
ASTM D 4833	Index puncture resistance of geotextiles, geomembranes, and related products
ASTM D 5199	Measuring nominal thickness of geotextiles and geomembranes
ASTM D 5261	Measuring mass per unit area of geotextiles
ASTM D 7005	Determining the bond strength ply adhesion of geocomposites
ASTM D 7179	Determining geonet breaking force

### 2. RAW MATERIAL

All resins, additives and concentrates used in Poly-Flex drainage net must meet Poly-Flex specifications before being released into the production material stream. Resin samples are taken from each incoming railcar. The resin density, melt index and carbon black content (for precompounded resins) are determined in the Poly-Flex laboratory. Upon verification of the resin compliance with the specifications, the resin is pumped from its railcar into a silo dedicated to production of the drainage net.

### 3. MANUFACTURING

#### 3.1 Drainage Net

Poly-Flex drainage net consists of approximately 97% polyethylene, 1.5 to 3.0% carbon black, and other additives. The drainage net is continuously monitored during the manufacturing process. The key element to successfully manufacturing high quality drainage nets is to maintain consistency in both the raw material and the process. Raw material consistency is established in the laboratory when the resin is initially received and tested. An on-line quality control monitor establishes consistency during the processing. This representative of the quality department has been specially trained to monitor the process and the products during the manufacturing process. The on-line quality monitor can place material on hold if the material has any visual defects or dimensional abnormalities. All materials placed on hold will be further inspected and tested. If the material passes specification and is approved by the quality control manager and/or production manager, the material will then be released into stock. If the material fails to pass the specification or does not get approval of the quality control manager or production manager then the material will be reclassified or scrapped. In either case it cannot be sold as a prime Poly-Flex drainage net.

#### 3.2 Drainage Net/Geotextile Geocomposite

Poly-Flex geocomposites consist of a geotextile bonded to one or both sides of the Poly-Flex drainage net. All geotextiles must meet the specifications before being eligible for production of geocomposites. Poly-Flex utilizes a heat bonding process to laminate the geotextile to the drainage net. An on-line quality control monitor establishes consistency during the processing. This representative of the quality department has been specially trained to monitor the process and the products during the lamination process. The on-line quality monitor can place material on hold if the material has any visual defects or dimensional abnormalities. All materials placed on hold will be further inspected and tested. If the material passes specification and is approved by the quality control manager and/or production manager, the material will then be released into stock. If the material fails to pass the specification or does not get approval of the quality control manager or production manager then the material will be reclassified or scrapped. In either case it cannot be sold as a prime Poly-Flex geocomposite.

#### 3.3 Roll Labeling

Three labels are affixed to each roll as described below:

1. One label on the inside of the core.
2. One label on the face on the roll.
3. One label on the end of the roll.

An additional label is attached to the laboratory sample.

#### 3.4 Storage, Staging and Shipping of Drainage Net and Geocomposite Rolls


All drainage net and geocomposite rolls are stretch wrapped prior to moving them to the storage area. Before shipment, all documentation is checked against the information on the roll labels. A full truckload consists of 24 rolls of drainage net and/or geocomposite material.











SKAPS Industries • 335 Athena Dr • Athens • GA 30601 • USA

- Home
- Products
- Technical
- India Plant
- Sales Office
- Clients
- Job Openings
- Office Locations
- Photo Gallery
- Directions
- Contact Us

GeoNet
GeoComposite
NonWoven
Woven

**DRAINAGE NET**

[:: Go Back ::](#)


**SKAPS TRANSNET™ HDPE GEOCOMPOSITE WITH 220 MIL GEONET**

**SKAPS TRANSNET™ GeoComposite** consists of SKAPS GeoNet made from HDPE resin with non-woven polypropylene GeoTextile fabric heat bonded on both sides of GeoNet.

Property	Test Method	Unit	Required Value			Qualifier
			with 6 oz.	with 8 oz.	with 10 oz.	
<b>GeoNet</b>						
Mass per unit area	ASTM D 5261	lb/ft <sup>2</sup>	0.17	0.17	0.17	Minimum
Thickness	ASTM D 5199	mil	220±20	220±20	220±20	Range
Carbon Black	ASTM D 4218	%	2 to 3	2 to 3	2 to 3	Range
Tensile Strength	ASTM D 5035	lb/in	45	45	45	Minimum
Melt Flow	ASTM D 1238 <sup>3</sup>	g/10 min	1	1	1	Maximum
Density	ASTM D 1505	g/cm <sup>3</sup>	0.94	0.94	0.94	Minimum
Transmissivity <sup>1</sup>	ASTM D 4716	m <sup>2</sup> /sec	1x10 <sup>-3</sup>	1x10 <sup>-3</sup>	1x10 <sup>-3</sup>	MARV <sup>2</sup>
<b>Composite</b>						
Ply Adhesion (Minimum)	GRI GC7	m <sup>2</sup> /sec	0.5	0.5	0.5	MARV
Ply Adhesion (Average)	GRI GC7	lb/in	1	1	1	MARV
Transmissivity <sup>1a</sup>	ASTM D 4716	m <sup>2</sup> /sec	2.75x10 <sup>-4</sup>	2.25x10 <sup>-4</sup>	2.0x10 <sup>-4</sup>	MARV
<b>GeoTextile</b>						
Fabric Weight	ASTM D 5261	oz/yd <sup>2</sup>	6	8	10.0	MARV
Grab Strength	ASTM D 4632	lb	150	225	270	MARV
Grab Elongation	ASTM D 4632	%	50	50	50	MARV
Tear Strength	ASTM D 4533	lb	60	90	100	MARV
Puncture Resistance	ASTM D 4833	gpm/ft <sup>2</sup>	95	130	165	MARV
Mullen Burst	ASTM D 3786 <sup>4</sup>	psi	325	450	550	MARV
Water Flow Rate	ASTM D 4491	gpm/ft <sup>2</sup>	125	100	75	MARV
Permittivity	ASTM D 4491	sec <sup>-1</sup>	1.63	1.26	0.94	MARV
Permeability	ASTM D 4491	cm/sec	0.48	0.3	0.30	MARV
AOS	ASTM D 4751	US Sieve	70	80	100	MARV

**Notes:**

1. Transmissivity measured using water at 21 ± 2°C (70 ± 4°F) with a gradient of 1.0 and a confining pressure of 15000 psf between steel plates after 15 minutes. Values may vary between individual labs.
- 1a Transmissivity measured using water at 21 ± 2°C (70 ± 4°F) with a gradient of 0.1 and a confining pressure of 10000 psf between steel plates after 15 minutes. Values may vary between individual labs.
2. MARV is statistically defined as mean minus two standard deviations and it is the value which is exceeded by 97.5% of all the test data.
3. Condition 190/2.16
4. Modified



SKAPS Industries • 335 Athena Dr • Athens • GA 30601 • USA

- [Home](#)
- [Products](#)
- [Technical](#)
- [India Plant](#)
- [Sales Office](#)
- [Clients](#)
- [Job Openings](#)
- [Office Locations](#)
- [Photo Gallery](#)
- [Directions](#)
- [Contact Us](#)

- [GeoNet](#)
- [GeoComposite](#)
- [NonWoven](#)
- [Woven](#)

## SKAPS GT-112

### Nonwoven Geotextiles

SKAPS GT-112 is a needle-punched nonwoven geotextile made of 100% polypropylene staple fibers, which are formed into a random network for dimensional stability. SKAPS GT-112 resists ultraviolet deterioration, rotting, biological degradation, naturally encountered basics and acids. Polypropylene is stable within a pH range of 2 to 13. SKAPS GT-112 conforms to the physical values listed below:

[:: Go Back ::](#)

PROPERTY	TEST METHOD	UNIT	M.A.R.V. (Minimum Average Roll Value)
<b>Weight (Typical)</b>	ASTM D5261	oz/yd <sup>2</sup> (g/m <sup>2</sup> )	12.0 (407)
<b>Grab Tensile</b>	ASTM D4632	lbs (kN)	300 (1.33)
<b>Grab Elongation</b>	ASTM D4632	%	50
<b>Trapezoid Tear Strength</b>	ASTM D4533	lbs (kN)	115 (0.511)
<b>Puncture Resistance</b>	ASTM D4833	lbs (kN)	180 (0.80)
<b>Mullen Burst</b>	ASTM D3786	psi (kPa)	600 (4134)
<b>Permittivity*</b>	ASTM D4491	sec <sup>-1</sup>	1.0
<b>Water Flow*</b>	ASTM D4491	gpm/ft <sup>2</sup> (l/min/m <sup>2</sup> )	75 (3055)
<b>A.O.S.*</b>	ASTM D4751	U.S. Sieve (mm)	100 (0.150)
<b>U.V. Resistance</b>	ASTM D4355	%/hrs	70/500

\* At the time of manufacturing. Handling, storage, and shipping may change these properties.

<b>PACKAGING</b>	
<b>Roll Dimension (W x L) - Ft</b>	12.5 x 360 / 15 x 300
<b>Square Yards per Roll</b>	500
<b>Estimated Roll Weight - lbs</b>	375

\* At the time of manufacturing. Handling may change these properties.

This information is provided for reference purposes only and is not intended as a warranty or guarantee. SKAPS assumes no liability in connection with the use of this information.

[Home](#) :: [Products](#) :: [Location](#) :: [Directions](#) :: [Jobs](#)

**ATTACHMENT #3**  
**EPA 9090 LABORATORY TESTING ON**  
**LINER SYSTEM MATERIALS**



**TRI/ENVIRONMENTAL, INC.**  
*A Texas Research International Company*

May 30, 1997

Mr. Paul Barker  
AGRU/America, Inc.  
300 West Davis, Suite 520  
Conroe, Texas 77305

Dear Mr. Barker:

TRI/Environmental, Inc. (TRI) is pleased to present this 120 Day Final Report for geosynthetic chemical compatibility studies via EPA Method performed on AGRU smooth 60 mil HDPE geomembrane.

TRI thanks AGRU/America for the opportunity to work on this project. Please call me if you have any questions or require any additional information.

Respectfully submitted,

A handwritten signature in cursive script that reads "Martin D. Nelson". The signature is written in black ink and is positioned below the typed name.

Martin D. Nelson  
Project Manager: Geosynthetic Technologies

cc: Mr. Sam R. Allen  
Program Manager

## FOREWORD

The testing reported herein is based upon accepted industry practice as well as the test method listed. TRI/Environmental Inc. (TRI) neither accepts responsibility for nor makes claim as to the final use and purpose of the materials tested.

Tests were performed under laboratory conditions and not under actual usage conditions. TRI can give no conclusions as to the serviceability, life expectancy or general durability of the products tested when used in a lining and/or leachate collection system.

**A 120 Day Final Report:**  
**Laboratory Testing of Geosynthetics**  
**for Waste Containment**  
**EPA Method 9090**

May 1997

Submitted to:  
**AGRU/America, Inc.**  
300 West Davis, Suite 520  
Conroe, Texas 77305

Attn: Mr. Paul Barker

Submitted by:  
**TRI/Environmental, Inc.**  
9063 Bee Caves Rd.  
Austin, Texas 78733



## 1.0 INTRODUCTION

This report describes the work performed by TRI/Environmental, Inc. (TRI) to determine the chemical compatibility of one geomembrane product with one waste leachate. The objective was to determine the resistance of the geomembrane to changes caused by exposure to leachate. Changes in physical and mechanical properties were measured after exposure to the leachate at 23°C and 50°C for 30, 60, 90 and 120 days. Exposures were performed in accordance with the exposure regimen specified in United States Environmental Protection Agency (EPA) Method 9090A.

Methods, results and discussion are provided in the sections which follow. Test results are provided in the Tables of Results which accompany this report.

## 2.0 METHODS

### 2.1 Materials

The material selected for evaluation in this chemical compatibility study was 60 mil smooth High Density Polyethylene (HDPE) geomembrane manufactured by Agru/America, Inc. Roll #638571 was provided by Agru/America.

### 2.2 Leachate

The exposure leachate used during the testing was a synthetic municipal solid waste (MSW) leachate. TRI generated the synthetic municipal waste leachate by spiking a quantity of actual MSW leachate (secured from the NENT Landfill in Hong Kong) with various chemical constituents as required by the Pennsylvania Department of Environmental Regulation (PADER). Spiking was accomplished using standard solutions used for instrument calibration for organics and salts used for the inorganics. Spiking was performed to assure a minimum concentration as defined by the PADER requirements. The exposure media met all requirements as defined by PADER.

After spiking, the leachate, contained in a fifty-five gallon drum, was stirred for twenty four hours and allowed to settle. Leachate was then transferred to exposure cells for chemical resistance testing.

### 2.3 Exposure Conditions

Geomembrane specimens were exposed to the waste leachate following the specifications of EPA Method 9090A as they relate to exposure to waste fluids. The tanks used for these exposures were maintained at  $23 \pm 2^\circ\text{C}$  and  $50 \pm 2^\circ\text{C}$  throughout the 120-day exposure period. Tanks were constructed from chemically resistant glass, fitted with stirrers and heated with a circulating hot

water heat exchanger system. The 50°C tanks were sealed with a lid, and a reflux condenser was installed to minimize loss of volatile leachate components.

#### 2.4 Testing Procedures

Table 2 lists tests performed on the geomembrane. The number of test replicates was doubled for baseline determinations on unexposed material.

Table 2. Tests performed on geomembranes		
Test or Physical Property	Method	Number of replicate specimens
Dimensions and weight	EPA 9090	3 readings
Hardness	ASTM D 2240 D scale	5
Volatiles and Extractables	EPA SW 870 Appendix III	2
Specific Gravity	ASTM D 792	3
Tensile Properties	ASTM D 638	3
Modulus of Elasticity	ASTM D 882 Tangential Modulus	3
Hydrostatic Resistance	ASTM D 751 Method A	3
Tear Strength	ASTM D 1004	3
Puncture Resistance	FTMS 101C Method 2065	3
Environmental Stress Crack Resistance	ASTM D 1693	2

Where appropriate testing was performed in both the machine and transverse directions.

### 3.0 Results and Discussion

Test results are presented in the Test Results section which is included with this report. Test results are presented in tabular form as well as graphical form.

In considering these results, it must be determined through engineering judgment whether observed differences in the value of test results measured before and after immersion are due to product variability, unidentified factors relating to the test procedure, or leachate interaction with the products. Any significant chemical interaction with leachate would be expected to result in degradation trends which are consistent across the various properties being evaluated, and not isolated to one set of test results only. However, with each type of material there may be specific properties which are highly sensitive to leachate-induced effects. These factors must be considered in evaluating the various test results for a given product.

Also of critical importance is the issue of product variability. With geomembranes, a range of physical and mechanical index test values covering 15% or more of the average is not uncommon. This can be traced to variability inherent in the product, and the randomness associated with the onset of failure under the specified testing conditions. However, in chemical compatibility testing the statistical sampling of a broad range of manufactured product is not possible. Therefore, the small size of the sample population tested at each time point must be taken into consideration. The criteria to be applied in evaluating data measured before and after leachate immersion should be that property changes, if observed, are consistent and so great that product variability and experimental factors can be ruled out.

In this report, standard deviations (STD) are reported for most measurements involving three or more replicate specimens. In statistics, the standard deviation is defined as root of the mean squared deviations of individual test results about the mean value. The standard deviation is a quantitative measure of variability within a group of measurements.

One related measure of variability observed within a sample set, relative to the magnitude of the mean value itself, is the *coefficient of variation or variance (COV)*. The coefficient of variance is defined as the standard deviation divided by the mean associated with a group of specimens, and may be expressed as a percentage. The COV provides an indication of what proportion of the mean value may be attributable to random experimental factors or product variability. It is useful to consider apparent changes in property values against the criterion of COV since observed changes which fall below the COV may not be significant. This approach was used in preparing the tables in the next sections.

The term *range* refers to the difference between the extreme highest and lowest points within a group of measured values. Considering range as a percentage of the mean values provides another measure of variability within a dataset.

In the tables, the high and low extremes for percentage change in mean values are listed for comparison against COV and range as a percentage of mean from the baseline sample group. The high and low percentage changes are the extremes from data measured at 30, 60, 90 and 120 days.

#### Agru/America 60 mil smooth HDPE Geomembrane

Table 3 illustrates the range of variability in baseline data compared with some of the observed changes in average test values measured after immersion for the HDPE geomembrane.

Test	Baseline COV (%) <sup>*</sup>	Baseline Range as % of Mean <sup>*</sup>	High Observed % Change	Low Observed % Change
Stress @ yield (MD)	3	8	+5	-6
Elongation @ yield (MD)	5	12	+20	+1
Stress @ break (MD)	5	14	+14	-13
Elongation @ break (MD)	4	11	+8	-15
Tangential Modulus (MD)	4	12	+9	-6
Tear Strength (MD)	2	6	+4	-2
Puncture Resistance	2	6	+8	0
Hydrostatic Resistance	2	5	+4	0

\* Note that the greatest baseline change for the four exposure periods was reported.


AGRU/America  
9090A Final Report  
Page 5

#### 4.0 CONCLUSION

Changes in certain measured physical and mechanical properties were noted for the geomembrane. However, the observed changes were random and are believed to be the effects of product variability and experimental factors. In the opinion of the authors, the data, considered together, support the conclusion that observed changes were not caused by exposure to the test leachate.

TRI/Environmental, Inc. is pleased to have been selected to participate in this project. We trust that the information provided in this report meets your requirements for technical documentation of this chemical compatibility study. Please do not hesitate to call if you have any questions or require any additional information.

Respectfully submitted,



Sam R. Allen  
Program Manager  
Geosynthetic Technologies

TRI/Environmental, Inc.

TRI GEOSYNTHETICS SERVICES DIVISION  
 PaDEP Leachate Analysis  
 Testing performed by TRI/Environmental, Inc.

Analysis: March 02-27, 1999

Analytes	LOQ (ug/L)	Blank (ug/L)	PaDEP Synthetic Leachate (ug/L)
Organics: SW 846 Methods 624, 625, 608			
Acenaphthene	10	ND	113
Acenaphthylene	25	ND	67
Anthracene	10	ND	52
Benzene	10	ND	811
Benzo(a)anthracene	10	ND	28
Benzo(a)pyrene	10	ND	52
Benzo(ghi)perylene	10	ND	45
Benzo(k)fluoranthene	50	ND	33
3,4-benzofluoranthene	25	ND	49
Chrysene	10	ND	52
Dibenzo(a,h)anthracene	10	ND	48
Ethyl benzene	10	ND	2600
Fluoranthene	10	ND	54
Fluorene	10	ND	52
Indeno(1,2,3,c,d)pyrene	50	ND	63
Naphthalene	10	ND	288
Phenanthrene	10	ND	65
Pyrene	10	ND	45
Styrene	10	ND	170
Toluene	10	ND	15000
Xylenes	10	ND	280
PCBs	10	ND	ND
Aldrin	10	ND	ND
1,2-Dichlorobenzene	10	ND	1200
1,4-Dichlorobenzene	10	ND	700
Hexachlorobenzene	10	ND	300
Pentachlorobenzene	10	ND	170
Trichlorobenzene**	50	ND	160
Tetrachlorobenzene**	10	ND	150
2-chloronaphthalene	10	ND	100
Chlorobenzene	10	ND	19000
4,4-DDT	10	ND	ND
4,4-DDE	50	ND	ND
4,4-DDD	10	ND	ND

TRI GEOSYNTHETICS SERVICES DIVISION

PaDEP Leachate Analysis

Testing performed by TRI/Environmental, Inc.

Analysis: March 02-27, 1999

Analytes	LOQ (ug/L)	Blank (ug/L)	PaDEP Synthetic Leachate (ug/L)
----------	---------------	-----------------	---------------------------------------

Organics: SW 846 Methods 624, 625, 608 (Continued)

Heptane	10	ND	70
Hexane	10	ND	70
Octane	10	ND	60
Bromoform	10	ND	1200
Carbon tetrachloride	25	ND	500
Chlorodibromomethane	10	ND	30
Chloroethane	10	ND	1000
Chloroform	10	ND	6800
Dichlorobromomethane	10	ND	140
Dichlorodifluoromethane	30	ND	600
1,1-Dichloroethane	50	ND	10300
1,2-Dichloroethane	25	ND	16050
Dichloropropane	10	ND	1300
cis-Dichloroethene	10	ND	350
trans-Dichloroethene	40	ND	700
Ethylene dichloride *12DCA	10	ND	ND
Hexachloroethane	10	ND	600
Methyl bromide	50	ND	120
Methyl chloride	10	ND	120
Methylene chloride	50	ND	12000
Tetrachloroethene	50	ND	700
Tetrachloroethane**	50	ND	800
1,1,1-Trichloroethane	10	ND	900
1,1,2-Trichloroethane	10	ND	500
Trichloroethene	10	ND	800
Trichlorofluoromethane	10	ND	75
Vinyl chloride	10	ND	185

TRI GEOSYNTHETICS SERVICES DIVISION  
 PaDEP Leachate Analysis  
 Testing performed by TRI/Environmental, Inc.

Analysis: March 02-27, 1999

Analytes	LOQ (ug/L)	Blank (ug/L)	PaDEP Synthetic Leachate (ug/L)
Organics: SW 846 Methods 624, 625, 608 (Continued)			
Acrolein	10	ND	345
Acrylonitrile	25	ND	45
Acetone	10	ND	15000
Amyl acetate	10	ND	70
Benzidine	10	ND	70
Butyl alcohol**	10	ND	220
Bis(2-chloroethoxy)methane	10	ND	32
Bis(2-chloroethoxy)ether	50	ND	70
Bis(2-chloroisopropyl)ether	25	ND	70
Bis(2-ethylhexyl)phthalate	10	ND	900
4-bromophenyl phenyl ether	10	ND	60
Butyl benzyl phthalate	10	ND	200
cresol**	10	ND	425
Chlordane	10	ND	ND
alpha-BHC	50	ND	ND
beta-BHC	10	ND	ND
gamma-BHC	10	ND	ND
delta-BHC	10	ND	ND
Dieldrin	10	ND	ND
Dichlorobenzidine	10	ND	100
Diethyl phthalate	10	ND	30
Dibutyl phthalate	10	ND	70
Dimethyl phthalate	10	ND	70
Isobutyl alcohol	10	ND	12000
Isopropyl alcohol	10	ND	200
Methyl alcohol	10	ND	160
2-chloroethyl vinyl ether	10	ND	700
2-chlorophenol	50	ND	1400
Dichlorophenol**	10	ND	1300
Dimethyl phenol**	10	ND	50
Dinitro-o-cresol	10	ND	60
Dinitrophenol**	10	ND	60
Dinitrotoluene**	10	ND	100
Diphenylhydrazine	10	ND	50
Ethyl acetate	10	ND	110
Ethyl ether	10	ND	100
Ethyl alcohol	10	ND	25000
Endosulfan	10	ND	50
Endrin	10	ND	19



**TRI GEOSYNTHETICS SERVICES DIVISION**  
**PaDEP Leachate Analysis**  
 Testing performed by TRI/Environmental, Inc.

Analysis: March 02-27, 1999

Analytes	LOQ (ug/L)	Blank (ug/L)	PaDEP Synthetic Leachate (ug/L)
Organics: SW 846 Methods 624, 625, 608 (Continued)			
Formaldehyde	10	ND	ND
Heptachlor	50	ND	ND
Hexachlorocyclopentadiene	10	ND	80
Hexachlorobutadiene	10	ND	500
Isophorone	10	ND	6000
Methyl ethyl ketone	10	ND	13500
Methyl isobutyl ketone	10	ND	750
Nitrophenol**	10	ND	20
N-nitrosodimethylamine	10	ND	120
N-nitrosodi-n-propylamine	10	ND	120
Nitrobenzene	10	ND	600
Pentachlorophenol	10	ND	450
Phenol	10	ND	15000
Pyridine	10	ND	700
Toluene	50	ND	1260
Toxophene	50	ND	300
Trichlorophenol**	10	ND	400
2,4,5-TP	10	ND	50
METALS (EPA Method 200 Series)			
			(mg/L)
Aluminum (202.1)	1	ND	15
Antimony (204.1)	1	ND	20
Arsenic (206.2)	1	ND	5
Barium (208.1)	1	ND	120
Beryllium (210.1)	1	ND	2
Boron (212.3)	1	ND	15
Cadmium (213.1)	1	ND	15
Chromium (218.1)	1	ND	10
Copper (220.1)	1	ND	10
Iron (236.1)	1	ND	800
Lead (239.1)	1	ND	10
Manganese (243.1)	1	ND	1000
Mercury (245.1)	1	ND	ND
Molybdenum (246.1)	1	ND	5
Nickel (249.1)	1	ND	ND
Silver (272.1)	1	ND	8
Selenium (270.2)	1	ND	ND
Tin (282.1)	1	ND	ND
Titanium (283.1)	1	ND	ND
Thallium (279.1)	1	ND	ND
Zinc (289.1)	1	ND	25
CONVENTIONALS (EPA Methods)			
			(mg/L)
Oil and Grease (413.1)	20	ND	500
Total petroleum hydrocarbons (418.1)	10	ND	9000
Ammonia-nitrogen (350.2)	50	ND	600
Cyanide (335.2)	15	ND	ND
Fluoride (340.1-340.2)	15	ND	500
Chloride (325.3)	10	ND	8000
Nitrate (353.3)	1	ND	3
Nitrite (353.3)	1	ND	ND
Sulfate (375.4)	1	ND	250
TDS	1	ND	13400
pH	NA	ND	7.2

TRI GEOSYNTHETICS SERVICES DIVISION  
 PaDEP Leachate Analysis  
 Testing performed by TRI/Environmental, Inc.

QUALITY ASSURANCE REPORT

Analysis: March 02-27, 1999

Analytes	Blank (ug/L)	PaDEP Synthetic Leachate (ug/L)
<b>Surrogate Recoveries</b>		
1,2-Dichloroethane-d4	156%	124%
Toluene-d8	100%	95%
Bromofluorobenzene	117%	73%
Trifluorotoluene	120%	113%
2-Fluorophenol (Acid Surr)	110%	110%
Phenol-d6 (Acid Surr)	98%	123%
Nitrobenzene-d5 (BN Surr)	68%	74%
2-Fluorobiphenyl (BN Surr)	124%	102%
2,4,6-Tribromophenol (Acid Surr)	92%	76%
p-Terphenyl-d14 (BN Surr)	90%	96%
<b>Compounds</b>		
	Matrix Spike	Matrix Spike Dup
Phenol	17%	32%
2-Chlorophenol	30%	89%
1,4-Dichlorobenzene	26%	97%
N-Nitroso-Di-N-Propylamine	69%	105%
1,2,4-Trichlorobenzene	39%	86%
4-Chloro-3-Methylphenol	83%	100%
Acenaphthene	88%	120%
4-Nitrophenol	17%	13%
2,4-Dinitrotoluene	72%	96%
Pentachlorophenol	71%	73%
Pyrene	88%	118%
<b>METALS</b>		
Arsenic	90%	87%
Barium	98%	101%
Cadmium	92%	93%
Chromium	84%	86%
Lead	79%	80%
Mercury	94%	98%
Selenium	82%	89%
Silver		

A Final Report:

**Laboratory Testing of Geomembrane  
for Waste Containment  
EPA Method 9090A**

October 1999

Submitted to:

**Poly-Flex Inc.  
2000 W. Marshall Drive  
Grand Prairie, Texas 75051**

**Attn: Mr. Lou Jacobsen**

Submitted by:

**TRI/Environmental, Inc.  
9063 Bee Caves Rd.  
Austin, Texas 78733**



October 24, 1999

Mr. Lou Jacobsen  
Poly-Flex, Inc.  
2000 W. Marshall Drive  
Grand Prairie, Texas 75051

Dear Mr. Jacobsen:

TRI/Environmental, Inc. (TRI) is pleased to present this Final Report for geomembrane chemical compatibility studies via EPA Method 9090A.

TRI thanks Poly-Flex, Inc. for the opportunity to participate in this project and trusts this report fully documents all testing performed. Please call me if you have any questions or require any additional information.

Respectfully submitted,

A handwritten signature in cursive script that reads "Sam R. Allen".

Sam R. Allen  
Vice President and Division Manager  
Geosynthetic Services

## 1.0

## INTRODUCTION

This report describes the work performed by TRI/Environmental, Inc. (TRI) to determine the chemical compatibility of one geomembrane product with one waste leachate. The objective was to determine the resistance of the geomembrane to changes caused by exposure to leachate. Changes in physical and mechanical properties were measured after exposure to the leachate at 23°C and 50°C for 30, 60, 90 and 120 days. Exposures were performed in accordance with the exposure regimen specified in United States Environmental Protection Agency (EPA) Method 9090A.

Methods, results and discussion are provided in the sections which follow. Test results are provided in the Tables of Results which accompany this report.

## 2.0

## METHODS

### 2.1

#### Materials

The material selected for evaluation in this chemical compatibility study was 60 mil smooth high density polyethylene (HDPE) geomembrane manufactured by PolyFlex, Inc..

### 2.2

#### Leachate

The exposure leachate used during the testing was a synthetic municipal solid waste (MSW) leachate. TRI generated the synthetic municipal waste leachate by spiking a quantity of actual MSW leachate (secured from the NENT Landfill in Hong Kong) with various chemical constituents as required by the Pennsylvania Department of Environmental Regulation (PADER). Spiking was accomplished using standard solutions used for instrument calibration for organics and salts used for the inorganics. Spiking was performed to assure a minimum concentration as defined by the PADER requirements. The exposure media met all requirements as defined by PADER.

After spiking, the leachate, contained in a fifty-five gallon drum, was stirred for twenty four hours and allowed to settle. Leachate was then transferred to exposure cells for chemical resistance testing.

### 2.3

#### Exposure Conditions

Geomembrane specimens were exposed to the waste leachate following the specifications of EPA Method 9090A as they relate to exposure to waste fluids. The tanks used for these exposures were maintained at  $23 \pm 2^\circ\text{C}$  and  $50 \pm 2^\circ\text{C}$  throughout the 120-day exposure period. Tanks were constructed from chemically resistant glass, fitted with stirrers and heated with a circulating hot

water heat exchanger system. The 50°C tanks were sealed with a lid, and a reflux condenser was installed to minimize loss of volatile leachate components.

#### 2.4 Testing Procedures

Table 1 lists tests performed on the geomembrane. The number of test replicates was doubled for baseline determinations on unexposed material.

Table 1. Tests performed on geomembranes		
Test or Physical Property	Method	Number of replicate specimens
Dimensions and weight	EPA 9090	3 readings
Hardness	ASTM D 2240 D scale	5
Volatiles and Extractables	EPA SW 870 Appendix III	2
Specific Gravity	ASTM D 792	3
Tensile Properties	ASTM D 638	3
Modulus of Elasticity	ASTM D 882 Tangential Modulus	3
Hydrostatic Resistance	ASTM D 751 Method A	3
Tear Strength	ASTM D 1004	3
Puncture Resistance	FTMS 101C Method 2065	3
Environmental Stress Crack Resistance	ASTM D 1693	2

Where appropriate testing was performed in both the machine and transverse directions.

### 3.0 Results and Discussion

Test results are presented in the Test Results section which is included with this report. Test results are presented in tabular form as well as graphical form.

In considering these results, it must be determined through engineering judgment whether observed differences in the value of test results measured before and after immersion are due to product variability, unidentified factors relating to the test procedure, or leachate interaction with the products. Any significant chemical interaction with leachate would be expected to result in degradation trends which are consistent across the various properties being evaluated, and not isolated to one set of test results only. However, with each type of material there may be specific properties which are highly sensitive to leachate-induced effects. These factors must be considered in evaluating the various test results for a given product.

Also of critical importance is the issue of product variability. With geomembranes, a range of physical and mechanical index test values covering 15% or more of the average is not uncommon. This can be traced to variability inherent in the product, and the randomness associated with the onset of failure under the specified testing conditions. However, in chemical compatibility testing the statistical sampling of a broad range of manufactured product is not possible. Therefore, the small size of the sample population tested at each time point must be taken into consideration. The criteria to be applied in evaluating data measured before and after leachate immersion should be that property changes, if observed, are consistent and so great that product variability and experimental factors can be ruled out.

In this report, standard deviations (STD) are reported for most measurements involving three or more replicate specimens. In statistics, the standard deviation is defined as root of the mean squared deviations of individual test results about the mean value. The standard deviation is a quantitative measure of variability within a group of measurements.

One related measure of variability observed within a sample set, relative to the magnitude of the mean value itself, is the *coefficient of variation or variance* (COV). The coefficient of variance is defined as the standard deviation divided by the mean associated with a group of specimens, and may be expressed as a percentage. The COV provides an indication of what proportion of the mean value may be attributable to random experimental factors or product variability. It is useful to consider apparent changes in property values against the criterion of COV since observed changes which fall below the COV may not be significant. This approach was used in preparing the tables in the next sections.

The term *range* refers to the difference between the extreme highest and lowest points within a group of measured values. Considering range as a percentage of the mean values provides another measure of variability within a dataset.

In the tables, the high and low extremes for percentage change in mean values are listed for comparison against COV and range as a percentage of mean from the baseline sample group. The high and low percentage changes are the extremes from data measured at 30, 60, 90 and 120 days.

**Poly-Flex 60 mil smooth HDPE Geomembrane**

Table 2 illustrates the range of variability in baseline data compared with some of the observed changes in average test values measured after immersion for the HDPE geomembrane.

Table 2. Baseline coefficients of variation and range of percentage change results for PolyFlex 60 mil HDPE Geomembrane (mechanical properties testing only)				
Test	Baseline COV (%)*	Baseline Range as % of Mean*	High Observed % Change	Low Observed % Change
Stress @ yield (MD)	2	5	+5	1
Elongation @ yield (MD)	2	6	+6	-1
Stress @ break (MD)	6	16	+7	-1
Elongation @ break (MD)	6	22	+4	-4
Tangential Modulus (MD)	13	33	+7	-9
Tear Strength (MD)	2	6	+1	-2
Puncture Resistance	2	4	+4	-3
Hydrostatic Resistance	1	3	+1	-3

\* Note that the greatest baseline change for the four exposure periods was reported.



#### 4.0 CONCLUSION

Changes in certain measured physical and mechanical properties were noted for the geomembrane. However, the observed changes were random and are believed to be the effects of product variability and experimental factors. In the opinion of the authors, the data, considered together, support the conclusion that observed changes were not caused by exposure to the test leachate.

TRI/Environmental, Inc. is pleased to have been selected to participate in this project. We trust that the information provided in this report meets your requirements for technical documentation of this chemical compatibility study. Please do not hesitate to call if you have any questions or require any additional information.

Respectfully submitted,



Sam R. Allen  
Vice President and Division Manager  
Geosynthetics Technologies

TRI/Environmental, Inc.

## FOREWORD

The testing reported herein is based upon accepted industry practice as well as the test method listed. TRI/Environmental Inc. (TRI) neither accepts responsibility for nor makes claim as to the final use and purpose of the materials tested.

Tests were performed under laboratory conditions and not under actual usage conditions. TRI can give no conclusions as to the serviceability, life expectancy or general durability of the products tested when used in a lining and/or leachate collection system.

**EPA METHOD 9090A TEST RESULTS**

**GEOSYNTHETIC DIMENSIONS**

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Exposure to PADER Waste Leachate**  
**Dimensional Stability Data**

Date: October, 1998

Exposure Time and Temperature

SQL  
Quality Review

Test Parameters	Temp.	30 Day			60 Day			90 Day			120 Day		
		Baseline	Exposed	% Change	Baseline	Exposed	% Change	Baseline	Exposed	% Change	Baseline	Exposed	% Change
<b>POLYFLEX GEOMEMBRANE: 60 mil HDPE</b>													
Thickness (mils)	23C	58	59	1.7	61	61	0.0	58	58	0.0	85	64	-1.5
	50C	61	61	0.0	61	61	0.0	61	61	0.0	61	61	0.0
Length (inches)	23C	10.03	10.02	-0.1	10.04	10.04	0.0	10.04	10.04	0.0	10.02	10.01	-0.1
	50C	10.02	10.02	0.0	10.00	10.00	0.0	10.01	10.01	0.0	10.01	10.00	-0.1
Width (inches)	23C	8.02	8.01	-0.1	8.00	8.00	0.0	8.02	8.02	0.0	8.01	8.01	0.0
	50C	8.01	8.01	0.0	8.00	8.00	0.0	8.01	8.01	0.0	8.00	8.00	0.0
Mass (g)	23C	71.98	72.06	0.1	76.34	76.81	0.6	72.65	72.89	0.3	79.39	79.62	0.3
	50C	76.29	76.39	0.1	75.03	75.26	0.3	75.89	75.91	0.3	78.43	78.62	0.5

**EPA METHOD 9090A TEST**

**POLY-FLEX 60 mil SMOOTH HDPE GEOMEMBRANE**

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Exposure to PADER Waste Leachate**

Report Date: October 1999

Exposure Time and Temperature

Test Parameters	30 Day			60 Day			90 Day			120 Day		
	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C
<b>POLYFLEX GEOMEMBRANE: 60 mil HDPE</b>												
Tensile Properties:	2597	2819	2675	2658	2682	2752	2454	2582	2524	2629	2717	2514
Tensile Stress @ Yield (psi)	2825	2754	2893	2810	2777	2898	2476	2422	2478	2852	2624	2788
ASTM D638	2561	2573	2666	2505	2583	2685	2365	2447	2511	2711	2839	2771
Machine Direction	2673			2590			2402			2674		
	2593			2570			2380			2617		
	2537			2522			2419			2540		
Average	2598	2649	2678	2576	2667	2705	2416	2484	2504	2637	2660	2684
STD	44	77	11	81	87	36	39	70	20	53	41	120
Coefficient of Variation	2	3	0	2	3	1	2	3	1	2	2	4
% Change		2	3		4	5		3	4		1	2
Tensile Properties:	4839	4822	4508	3811	4737	4288	4819	4674	4808	4915	4773	4190
Tensile Strength @ Break (psi)	4454	4411	4814	3921	4458	4705	4529	4765	4789	4850	4438	4822
ASTM D638	3942	4215	4355	4781	4022	4183	4470	4497	4780	4034	4803	4720
Machine Direction	4638			3787			4377			5055		
	4672			4984			4510			4295		
	4520			4912			4374			4864		
Average	4478	4418	4492	4328	4405	4389	4480	4645	4786	4536	4605	4577
STD	251	166	106	589	294	226	86	111	20	360	137	277
Coefficient of Variation	6	4	2	13	7	5	2	2	0	8	3	6
% Change		-1	0		2	1		4	7		-1	-1
Tensile Properties:	13.8	13.8	13.8	13.1	13.4	13.0	13.4	14.0	14.2	13.1	13.6	13.6
Elongation @ Yield (%)	13.8	13.8	13.8	14.0	14.0	13.0	12.8	13.6	14.0	13.3	13.6	13.6
ASTM D638	12.9	13.1	12.9	12.7	13.4	14.2	12.3	13.8	14.0	13.1	12.7	13.6
Machine Direction	13.8			14.0			13.5			13.8		
	13.8			12.5			13.8			13.8		
	13.4			14.2			14.1			12.9		
Average	13.6	13.6	13.5	13.4	13.6	13.4	13.3	13.8	14.1	13.3	13.3	13.6
STD	0.3	0.3	0.4	0.7	0.3	0.8	0.6	0.2	0.1	0.3	0.4	0.0
Coefficient of Variation	2	2	3	5	2	4	5	1	1	2	3	0
% Change		-0	-1		1	-0		4	6		0	2

SZA w/24/99  
 Quality Review/Date

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Exposure to PADER Waste Leachate**

Report Date: October 1999

Exposure Time and Temperature

Test Parameters	30 Day			60 Day			90 Day			120 Day		
	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C
<b>POLYFLEX GEOMEMBRANE: 60 mil HDPE</b>												
<b>Tensile Properties:</b>	605	594	609	479	630	664	638	609	625	632	599	581
Elongation @ Break (%)	602	585	612	528	598	594	697	616	637	623	556	611
ASTM D638	532	559	650	620	523	565	616	655	627	519	598	598
Machine Direction	603			516			598			644		
	599			639			614			588		
	664			642			689			619		
Average	601	579	624	571	584	574	642	627	630	601	584	597
STD	38	15	19	65	45	14	38	20	5	44	20	12
Coefficient of Variation	6	3	3	11	8	2	6	3	1	7	3	2
% Change		-4	4		2	1		-2	-2		-3	-1
<b>Tensile Properties:</b>	875	600	800	575	700	625	730	690	670	690	630	665
Set after Break (%)	684	580	620	670	670	680	720	710	740	700	575	695
ASTM D638	642	580	685	680	560	660	720	760	660	595	700	660
Machine Direction	681			610			720			720		
	605			700			750			720		
	485			750			740			680		
Average	625	587	635	664	650	655	730	720	697	684	635	673
STD	77	9	36	57	51	23	12	29	31	42	51	15
Coefficient of Variation	12	2	6	9	8	3	2	4	4	6	8	2
% Change		-6	2		-2	-1		-1	-5		-7	-2
<b>Tensile Properties:</b>	2113	2122	2162	2161	2091	2115	1959	2155	2140	2176	2187	2030
Tensile Stress @ 100% Elongation (psi)	2112	2130	2144	2130	2030	2150	1980	2188	2031	2153	2129	2240
ASTM D638	2112	2111	2187	2122	2051	2123	1978	1896	2152	2204	2175	2307
Machine Direction	2236			2092			1985			2210		
	2132			2138			1883			2147		
	2055			2150			2013			2135		
Average	2128	2121	2184	2132	2057	2129	1983	2083	2108	2171	2164	2192
STD	52	8	18	22	25	15	18	133	54	28	25	118
Coefficient of Variation	2	0	1	1	1	1	1	6	3	1	1	5
% Change		-0	2		-4	-0		5	6		-0	1
<b>Tensile Properties:</b>	2151	2158	2184	2251	2107	2217	2049	2219	2177	2271	2233	2067
Tensile Stress @ 200% Elongation (psi)	2144	2171	2188	2246	1833	2148	2132	2193	2089	2214	2164	2318
ASTM D638	2130	2135	2190	2208	2084	2193	2110	1989	2140	2309	2176	2275
Machine Direction	2252			2183			2119			2220		
	2165			2244			2111			2188		
	2107			2144			1929			2170		
Average	2160	2155	2181	2213	2041	2186	2075	2137	2135	2229	2191	2230
STD	49	15	12	39	77	29	70	98	38	48	30	96
Coefficient of Variation	2	1	1	2	4	1	3	5	2	2	1	4
% Change		-0	1		-8	-1		3	3		-2	0

SDA 10-24-99  
 Quality Review/Date

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Exposure to PADER Waste Leachate**

Report Date: October 1999

Exposure Time and Temperature

Test Parameters	30 Day			60 Day			90 Day			120 Day		
	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C
<b>POLYFLEX GEOMEMBRANE: 60 mil HDPE</b>												
<b>Tensile Properties:</b>	2758	2838	2801	2590	2801	2731	2804	2819	2876	2763	2788	2819
Tensile Stress @ Yield (psi)	2711	2743	2788	2874	2752	2767	2736	2787	2901	2785	2785	2861
ASTM D638	2763	2730	2822	2706	2760	2775	2865	2814	2853	2745	2832	2870
Transverse Direction	2775			2712			2702			2786		
	2835			2685			2579			2778		
	2713			2873			2831			2679		
Average	2759	2704	2804	2707	2774	2758	2686	2800	2877	2758	2805	2850
STD	42	47	14	85	19	19	73	23	20	39	19	22
Coefficient of Variation	2	2	0	3	1	1	3	1	1	1	1	1
% Change		-2	2		3	2		4	7		2	3
<b>Tensile Properties:</b>	4428	4745	4179	4882	5168	4106	4824	4381	4079	4547	4850	4328
Tensile Strength @ Break (psi)	4020	4238	3744	5015	4844	4529	4676	5186	4810	4385	4534	4702
ASTM D638	4512	4827	5018	4927	4597	5084	5002	4341	5175	4358	4458	4924
Transverse Direction	4108			3750			4307			4485		
	4797			4554			5012			4022		
	4142			4997			4441			4849		
Average	4335	4537	4314	4688	4870	4573	4710	4640	4688	4443	4613	4651
STD	271	217	529	446	234	400	266	395	456	247	170	246
Coefficient of Variation	6	5	12	10	5	9	6	9	10	6	4	5
% Change		5	-0		4	-2		-1	-0		4	5
<b>Tensile Properties:</b>	12.1	12.7	12.9	12.5	11.9	12.7	12.4	11.9	12.5	12.9	12.3	12.7
Elongation @ Yield (%)	12.9	11.5	12.9	12.5	11.9	12.5	12.5	12.7	12.5	12.1	12.1	12.1
ASTM D638	12.9	12.1	12.3	12.5	12.5	12.5	12.6	12.5	12.3	12.3	12.7	13.6
Transverse Direction	12.9			12.5			12.5			12.9		
	12.9			12.5			12.6			13.2		
	12.7			12.5			12.5			12.7		
Average	12.7	12.1	12.7	12.5	12.1	12.6	12.5	12.4	12.4	12.7	12.4	12.8
STD	0.3	0.5	0.3	0.0	0.3	0.1	0.1	0.3	0.1	0.4	0.2	0.6
Coefficient of Variation	2	4	2	0	2	1	1	3	1	3	2	5
% Change		-5	-0		-3	1		-1	-1		-2	1
<b>Tensile Properties:</b>	668	689	677	695	692	592	656	619	557	628	660	612
Elongation @ Break (%)	675	697	641	680	653	618	654	722	668	603	624	640
ASTM D638	663	636	696	703	732	694	635	618	704	603	611	598
Transverse Direction	672			680			694			620		
	634			655			625			563		
	693			730			633			680		
Average	668	674	671	691	692	635	650	653	643	616	632	617
STD	18	27	23	23	32	43	23	49	63	35	21	17
Coefficient of Variation	3	4	3	3	5	7	4	7	10	6	3	3
% Change		1	1		0	-8		1	-1		3	0

SDA 10-24-99  
 Quality Review/Date



**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Exposure to PADER Waste Leachate**

Report Date: October 1999

Exposure Time and Temperature

Test Parameters	30 Day			60 Day			90 Day			120 Day		
	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C
<b>POLYFLEX GEOMEMBRANE: 60 mil HDPE</b>												
Tensile Properties:	632	625	630	780	800	740	750	870	640	710	720	645
Set after Break (%)	664	650	640	750	700	700	740	770	740	830	670	890
ASTM D638	641	660	675	780	770	730	740	720	780	660	680	740
Transverse Direction	635			710			770			695		
	815			740			750			660		
	646			800			710			740		
Average	639	645	646	760	757	723	743	720	720	688	690	692
STD	15	15	19	30	42	17	18	41	59	35	22	39
Coefficient of Variation	2	2	3	4	6	2	2	6	8	5	3	6
% Change		1	1		-0	-5		-3	-3		1	1
Tensile Properties:	1864	1970	1919	1906	1963	1917	1923	1858	2013	1963	1999	1997
Tensile Stress @ 100% Elongation (psi)	1829	1878	1963	1848	2002	2026	1902	1828	2006	1995	2011	2079
ASTM D638	2003	1949	2021	1907	1952	1995	1824	1957	1871	1978	1994	1992
Transverse Direction	1864			1915			1932			1983		
	2074			1888			1845			2000		
	1972			1863			1829			1854		
Average	1884	1966	1988	1908	1962	1979	1893	1947	1997	1976	2001	2023
STD	46	13	42	21	22	46	43	13	18	17	7	40
Coefficient of Variation	2	1	2	1	1	2	2	1	1	1	0	2
% Change		-1	-1		4	4		3	6		1	2
Tensile Properties:	2076	2022	1977	1972	2088	2033	1968	1988	2075	2024	2026	2144
Tensile Stress @ 200% Elongation (psi)	1966	2085	2174	2068	2089	2180	1906	1973	2018	2129	2149	2122
ASTM D638	2033	1979	2046	1952	1970	2014	1861	1958	1965	2146	2123	2148
Transverse Direction	2072			2056			1966			2049		
	2232			1941			1894			2114		
	2021			1907			1829			1975		
Average	2072	2032	2056	1983	2042	2069	1921	1972	2028	2073	2099	2137
STD	77	48	82	59	52	65	38	13	37	62	53	11
Coefficient of Variation	4	2	4	3	3	3	2	1	2	3	3	1
% Change		-2	-0		3	4		3	5		1	3
Modulus of Elasticity:	124744	91394	103184	81704	71107	78795	79633	67663	73895	124744	108123	103176
Tangential (psi)	104279	103855	87868	78006	77275	71089	65292	63822	76812	104279	99124	110352
ASTM D882	117219	93445	130990	86535	74487	81924	69526	82386	77912	117219	103275	99878
Machine Direction	90144			77189			73605			90144		
	96237			75676			78201			96237		
	98766			72165			69619			98766		
Average	105232	96231	107347	78713	74283	77269	72646	77958	76206	105232	102841	104502
STD	13234	6981	21860	4558	2521	4553	5059	7303	1695	12081	2874	4338
Coefficient of Variation	13	7	20	6	3	6	7	9	2	11	3	4
% Change		-9	2		-6	-2		7	5		-2	-1

SEP 10 24 99  
 Quality Review/Date

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Exposure to PADER Waste Leachate**

Report Date: October 1999

Exposure Time and Temperature

Test Parameters	30 Day			60 Day			90 Day			120 Day		
	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C
<b>POLYFLEX GEOMEMBRANE: 60 mil HDPE</b>												
Modulus of Elasticity:	132588	133256	116768	86098	72302	75135	70208	82564	94042	132588	135318	150382
Tangential (psi)	139879	129438	128450	84982	88581	94898	87874	73789	68801	136879	144267	129457
ASTM D882	127699	121289	112878	77760	81035	85404	75071	90021	85348	161236	145930	146805
Transverse Direction	122310			77047			78012			156135		
	123564			85823			79633			163050		
	129848			96784			81637			129848		
Average	129311	120994	118365	84718	80987	85145	75239	82125	82084	147119	141838	142215
STD	8438	6003	8104	5527	6584	8069	4849	6634	11361	13520	4860	8138
Coefficient of Variation	5	5	7	6	8	9	6	8	14	9	3	8
% Change		-2	-8		-5	1		9	9		-4	-3
Indentation Hardness:												
Reading	61	61	62	63	62	63	65	64	62	62	63	64
ASTM D2240	60	61	62	62	62	62	65	63	64	63	64	63
(with TYPE D DUROMETER)	61	62	63	62	62	62	65	63	63	63	63	63
	62			64			63			63		
	62			63			63			62		
	62			62			64			63		
Average	61	61	62	63	62	62	64	63	63	63	63	63
STD	1	1	1	1	0	0	1	0	1	0	0	0
Coefficient of Variation	1	1	1	1	0	1	1	1	1	1	1	1
% Change		0	2		-1	-1		-1	-2		1	1
Specific Gravity:												
ASTM D792, Method A	0.949	0.950	0.950	0.950	0.948	0.949	0.950	0.948	0.950	0.949	0.949	0.949
	0.949	0.949	0.950	0.950	0.949	0.950	0.949	0.948	0.948	0.949	0.948	0.949
	0.950	0.950	0.950	0.948	0.949	0.947	0.948	0.948	0.948	0.949	0.949	0.949
	0.951			0.948			0.949			0.949		
	0.949			0.948			0.949			0.948		
	0.950			0.947			0.948			0.950		
Average	0.950	0.950	0.950	0.948	0.949	0.949	0.949	0.948	0.949	0.949	0.949	0.948
STD	0.001	0.001	0.000	0.001	0.000	0.001	0.001	0.000	0.001	0.001	0.000	0.000
Coefficient of Variation	0.086	0.081	0.000	0.118	0.050	0.131	0.072	0.050	0.099	0.081	0.050	0.000
% Change		0.00	0.04		0.02	0.02		-0.05	-0.02		-0.04	0.00
Environmental Stress Crack Resistance:												
ASTM D1693, Condition B												
Machine Direction (% Failed)	N/A	0	0	N/A	0	0	N/A	0	0	N/A	0	0
Transverse Direction (% Failed)	N/A	0	0	N/A	0	0	N/A	0	0	N/A	0	0

SR 10-24-99  
 Quality Review/Date

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Exposure to PADER Waste Leachate**

Report Date: October 1999

Exposure Time and Temperature

Test Parameters	30 Day			60 Day			90 Day			120 Day		
	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C
<b>POLYFLEX GEOMEMBRANE: 60 mil HDPE</b>												
Puncture Resistance:	91	90	95	86	93	95	87	89	91	88	91	92
Load @ Rupture (lbs)	91	91	94	88	92	94	89	86	90	92	92	98
FTMS 101C Method 2085	92	92	83	91	89	84	87	88	90	97	89	87
	93			82			94			96		
	93			93			90			96		
	89			94			91					
Average	92	91	94	91	91	94	90	88	90	94	91	95
STD	1	1	1	3	2	0	2	1	0	3	1	2
Coefficient of Variation	2	1	1	3	2	0	3	1	1	4	1	2
% Change		-1	3		1	4		-2	1		-3	1
Volatiles and Extractables:	-0.05	-0.05	-0.03	-0.03	0.00	-0.10	-0.05	-0.15	-0.05	0.03	-0.05	0.00
Diameter Change (%)	-0.05	-0.08	0.03	0.00	-0.05	-0.08	0.03	0.00	-0.05	-0.05	-0.03	-0.05
SW 870 - Appendix III-D	0.00			-0.10			-0.05			-0.05		
Machine Direction	0.00			-0.08			-0.20			0.00		
Average	-0.03	-0.07	0.00	-0.05	-0.03	-0.08	-0.07	-0.08	-0.05	-0.02	-0.04	-0.03
STD	0.03	0.02	0.03	0.04	0.03	0.01	0.08	0.08	0.00	0.03	0.01	-0.00
Volatiles and Extractables:	0.28	0.18	0.15	0.10	0.13	0.20	0.15	0.25	0.10	0.18	0.20	0.08
Diameter Change (%)	0.08	0.23	0.18	0.15	0.05	0.13	0.00	0.03	0.18	0.18	0.18	0.10
SW 870 - Appendix III-D	0.23			0.03			0.13			0.03		
Transverse Direction	0.05			0.25			0.38			0.73		
Average	0.18	0.21	0.17	0.13	0.09	0.17	0.17	0.14	0.14	0.28	0.19	0.09
STD	0.10	0.02	0.02	0.08	0.04	0.04	0.14	0.11	0.04	0.27	0.01	0.01
Volatiles and Extractables:	0.07	0.06	0.10	0.08	0.07	0.08	0.05	0.07	0.08	0.05	0.05	0.08
% Volatiles	0.07	0.08	0.08	0.08	0.08	0.08	0.06	0.08	0.07	0.05	0.05	0.05
SW 870 - Appendix III-D	0.08			0.07			0.04			0.05		
	0.08			0.07			0.04			0.05		
Average	0.08	0.07	0.09	0.07	0.08	0.08	0.05	0.08	0.08	0.05	0.05	0.08
STD	0.00	0.01	0.01	0.01	0.00	0.00	0.01	0.00	0.00	0.00	0.00	0.01
Volatiles and Extractables:	0.21	0.21	0.22	0.20	0.21	0.25	0.28	0.22	0.22	0.21	0.22	0.22
% Extractables	0.20	0.22	0.21	0.22	0.19	0.18	0.25	0.21	0.22	0.19	0.21	0.22
SW 870 - Appendix III-D	0.20			0.20			0.31			0.22		
	0.21			0.18			0.32			0.20		
Average	0.21	0.22	0.22	0.20	0.20	0.22	0.29	0.22	0.22	0.21	0.22	0.22
STD	0.00	0.01	0.01	0.01	0.01	0.04	0.03	0.01	0.00	0.01	0.01	0.00

SPR 10-24-99  
Quality Review/Date

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Exposure to PADER Waste Leachate**


Report Date: October 1999

Exposure Time and Temperature


Test Parameters	30 Day			60 Day			90 Day			120 Day		
	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C	Baseline	23C	50C
<b>POLYFLEX GEOMEMBRANE: 60 mil HDPE</b>												
Tear Resistance:	55	54	54	55	53	53	57	55	55	55	54	58
Tear Resistance (lbs)	54	54	54	53	54	52	55	55	54	55	53	54
ASTM D1004	54	52	55	54	54	55	55	57	55	53	53	53
Machine Direction	54			52			57			54		
	52			52			54			54		
	55			53			57			57		
Average	54	53	54	53	54	53	56	56	55	55	53	54
STD	1	1	1	1	0	1	1	1	0	1	0	1
Coefficient of Variation	2	2	1	2	1	2	2	2	1	2	1	2
% Change		-1	1		1	0		-0	-2		-2	-1
Tear Resistance:	51	54	53	52	55	51	51	51	51	51	53	53
Tear Resistance (lbs)	50	54	51	52	51	51	53	51	51	50	53	52
ASTM D1004	51	51	52	50	54	55	53	58	52	50	52	52
Transverse Direction	50			48			56			50		
	49			48			55			50		
	54			48			54			52		
Average	51	53	52	49	53	52	54	54	51	51	53	52
STD	2	2	1	2	2	2	2	4	0	1	0	0
Coefficient of Variation	3	3	2	4	3	4	3	7	1	2	1	1
% Change		4	2		8	6		0	-4		4	4
Hydrostatic Resistance:	490	495	500	500	495	500	500	485	495	500	495	505
Load @ Rupture (psi)	500	510	510	490	485	490	515	505	485	485	510	505
ASTM D751	505	500	500	505	490	490	520	490	485	510	500	500
	500			510			515			480		
	495			495			505			500		
	500						510			500		
Average	498	502	503	500	493	493	511	497	495	499	502	503
STD	5	8	6	7	2	5	7	6	0	6	6	2
Coefficient of Variation	1	2	1	1	0	1	1	1	0	1	1	0
% Change		1	1		-1	-1		-3	-3		1	1

SR 10-24-99  
 Quality Review/Date


**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GM/PADER Leachate




**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GMPADDER Leachate



**POLYFLEX EPA METHOD 9090A**  
60 mil smooth HDPE GM/PADER Leachate




**POLYFLEX EPA METHOD 9090A**  
60 mil smooth HDPE GM/PADER Leachate







**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GM/PADER Leachate



**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GM/PADER Leachate




**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GM/PADER Leachate




# POLYFLEX EPA METHOD 9090A


60 mil smooth HDPE GM/PADER Leachate




**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GM/PADER Leachate




**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GM/PADER Leachate



**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GM/PADER Leachate




**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GM/PADER Leachate






# POLYFLEX EPA METHOD 9090A


60 mil smooth HDPE GM/PADER Leachate




**POLYFLEX EPA METHOD 9090A**  
60 mil smooth HDPE GM/PADER Leachate



**POLYFLEX EPA METHOD 9090A**  
60 mil HDPE GM/PADER Leachate




**POLYFLEX EPA METHOD 9090A**  
60 mil HDPE GM/PADER Leachate




# POLYFLEX EPA METHOD 9090A


60 mil smooth HDPE GM/PADER Leachate




**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GM/PADER Leachate



**POLYFLEX EPA METHOD 9090A**  
 60 mil smooth HDPE GM/PADER Leachate



**POLYFLEX EPA METHOD 9090A**  
60 mil smooth HDPE GM/PADER Leachate





A Final Report:

**Laboratory Testing of  
SKAPS Industries HDPE Geonet  
EPA Method 9090A**

January 2003

Submitted to:

**SKAPS Industries**  
571 Industrial Parkway  
Commerce, GA 30529

Attn: **Mr. Perry Vyas**

Submitted by:

**TRI/Environmental, Inc.**  
9063 Bee Caves Rd.  
Austin, Texas 78733



TRI/ENVIRONMENTAL, INC.  
*A Texas Research International Company*

---

January 10, 2003

**Mr. Perry Vyas**  
**SKAPS Industries**

571 Industrial Parkway  
Commerce, GA 30529

Dear Mr. Vyas:

TRI/Environmental, Inc. (TRI) is pleased to present this Final Report for a geonet chemical compatibility study performed in general accordance with EPA Method 9090A.

TRI is very pleased to be of service to SKAPS Industries. Please call me if you have any questions or require any additional information.

Respectfully submitted,

A handwritten signature in black ink that reads "Sam R. Allen". The signature is written in a cursive style with a large, sweeping initial 'S'.

Sam R. Allen  
Vice President and Division Manager  
Geosynthetic Services Division

## **FOREWORD**

The testing reported herein is based upon accepted industry practice as well as the test method listed. TRI/Environmental Inc. (TRI) neither accepts responsibility for nor makes claim as to the final use and purpose of the materials tested.

Tests were performed under laboratory conditions and not under actual usage conditions. TRI can give no conclusions as to the serviceability, life expectancy or general durability of the products tested when used in a lining and/or leachate collection system.

## **1.0 INTRODUCTION**

This report describes the work performed by TRI/Environmental, Inc. (TRI) to determine the chemical compatibility of one HDPE geonet product with one waste leachate. The objective was to determine the resistance of the geonet to changes caused by exposure to leachate. Changes in physical, mechanical and hydraulic properties were measured after exposure to the leachate at 23°C and 50°C for 30, 60, 90 and 120 days. Exposures were performed in accordance with the exposure regimen specified in United States Environmental Protection Agency (EPA) Method 9090A.

All samples were logged in and all testing performed under TRI log number E2173-46-05. Methods, results and discussion are provided in the sections which follow. Test results are provided in the Tables of Results which accompany this report.

## **2.0 METHODS**

### **2.1 Materials**

The material selected for evaluation in this chemical compatibility study was Skaps Industries HDPE biplaner geonet.

### **2.2 Leachate**

The waste leachate used was supplied by TRI and was a synthetic MSW leachate approximating the PaDER leachate recipe.

### **2.3 Exposure Conditions**

Geonet specimens were exposed to the waste leachate following the specifications of EPA Method 9090A as they relate to exposure to waste fluids. The tanks used for these exposures were maintained at  $23 \pm 2^\circ\text{C}$  and  $50 \pm 2^\circ\text{C}$  throughout the 120-day exposure period. Tanks were constructed from chemically resistant glass fitted with stirrers. The 50°C tanks were heated with a circulating hot water heat exchanger system. They were also sealed with a lid, and a reflux condenser was installed to minimize loss of volatile leachate components.

### **2.4 Testing Procedures**

Table 1 lists tests performed on the geonet. The number of test replicates was doubled for baseline determinations on unexposed material.

Table 1. Tests performed on Skaps Industries HDPE Geonet		
Test or Physical Property	Method	Number of replicate specimens
Dimensions and weight	EPA 9090	2 readings
Strip Tensile Strength	ASTM D 5035	3 MD & TD readings
Strip Tensile Elongation	ASTM D 5035	3 MD & TD readings
Compressive Strength	ASTM D 1621	3 readings
Transmissivity	ASTM D 4716	3 readings
CBR Puncture	ASTM D 6241	3 readings
Volatiles and Extractables	SW870 - Appendix III-D	2 readings

### 3.0 RESULTS AND DISCUSSION

Test results are presented in the Test Results section which is included with this report. Test results are presented in tabular form as well as graphical form.

In considering these results, it must be determined through engineering judgment whether observed differences in the value of test results measured before and after immersion are due to product variability, unidentified factors relating to the test procedure, or leachate interaction with the product. Any significant chemical interaction with leachate would be expected to result in degradation trends which are consistent across the various properties being evaluated, and not isolated to one set of test results only. However, with each type of material there may be specific properties which are highly sensitive to leachate-induced effects. These factors must be considered in evaluating the various test results for a given product.

Also of critical importance is the issue of product variability. With HDPE geonets, a range of physical and mechanical index test values covering 20% or more of the average is not uncommon. This can be traced to variability inherent in the product, and the randomness associated with the onset of failure under the specified testing conditions. However, in chemical compatibility testing the statistical sampling of a broad range of manufactured product is not possible. Therefore, the small size of the sample population tested at each time point must be taken into consideration. The criteria to be applied in evaluating data measured before and after leachate immersion should be that property changes, if observed, are consistent and so great that product variability and experimental factors can be ruled out.

In this report, standard deviations (STD) are reported for measurements involving three or more replicate specimens. In statistics, the standard deviation is defined as root of the mean squared deviations of individual test results about the mean value. The standard deviation is a quantitative measure of variability within a group of measurements.

One related measure of variability observed within a sample set, relative to the magnitude of the mean value itself, is the *coefficient of variation or variance* (COV). The coefficient of variance is defined as the standard deviation divided by the mean associated with a group of specimens, and may be expressed as a percentage. The COV provides an indication of what proportion of the mean value may be attributable to random experimental factors or product variability. It is useful to consider apparent changes in property values against the criterion of COV since observed changes which fall below the COV may not be significant. This approach was used in preparing the tables in the next section.

The term *range* refers to the difference between the extreme highest and lowest points within a group of measured values. Considering range as a percentage of the mean values provides another measure of variability within a dataset.

In the tables, the high and low extremes for percentage change in mean values are listed for comparison against COV and range as a percentage of mean from the baseline sample group. The high and low percentage changes are the extremes from data measured at 30, 60, 90 and 120 days.

### Skaps Industries HDPE Biplaner Geonet

Table 2 illustrates the range of variability in baseline data compared with some of the observed changes in average test values measured after immersion for the geonet.


Table 2. Baseline coefficients of variation and range of percentage change results				
Test	Baseline COV (%)*	Baseline Range as % of Mean*	High Observed % Change	Low Observed % Change
Strip Tensile Strength (MD)	7	17	9	-9
Strip Tensile Elongation @ Maximum Load (MD)	6	18	9	-8
Compressive Strength	6	17	4	-6
Transmissivity	2.18	6.63	-0.17	-9.54
CBR Puncture	7	20	9	-9

#### 4.0 CONCLUSION

Changes in certain measured physical and mechanical properties were noted for the geonet. However, the observed variances were random and are believed to be the effects of product variability and experimental factors. In the opinion of the authors, the data, considered together, support the conclusion that observed variances were not caused by exposure to the test leachate.

TRI/Environmental, Inc. is pleased to have been selected to participate in this project. We trust that the information provided in this report meets your requirements for technical documentation of this chemical compatibility study. Please do not hesitate to call if you have any questions or require any additional information.

Respectfully submitted,



Sam R. Allen  
Vice President and Division Manager  
Geosynthetic Services Division

TRI/Environmental, Inc.

**APPENDIX:**

**EPA METHOD 9090A TEST RESULTS**

**SKAPS INDUSTRIES HDPE GEONET TEST RESULTS**

**Dimensions**

**TRI LOG NUMBER: E2173-46-05**



**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Client: Skaps Industries**

Report Date: January 2003  
 TRI Log Number: E2173-46-05

Exposure Time and Temperature

Test Parameters	Temp.	30 Day			60 Day			90 Day			120 Day		
		Baseline	Exposed	% Change	Baseline	Exposed	% Change	Baseline	Exposed	% Change	Baseline	Exposed	% Change

**GEONET: HDPE GEONET EXPOSED TO PADER MSW SYNTHETIC LEACHATE**

Thickness (mils)	23C	224	228	1.8	234	234	0.0	230	230	0.0	228	228	0.0
	50C	232	232	0.0	228	229	0.4	230	231	0.4	229	229	0.0
Length (inches)	23C	6.00	6.00	0.0	6.00	5.85	-2.5	6.00	5.96	-0.7	6.02	6.01	-0.2
	50C	6.00	5.83	-2.8	6.00	5.89	-1.8	6.00	6.00	0.0	5.99	6.00	0.2
Width (inches)	23C	4.04	4.06	0.5	4.01	4.02	0.2	4.01	4.04	0.7	4.02	4.04	0.5
	50C	4.02	4.02	0.0	4.01	4.01	0.0	4.03	4.03	0.0	4.03	4.01	-0.5
Mass (g)	23C	14.91	14.92	0.1	15.46	15.47	0.1	15.30	15.31	0.1	15.23	15.25	0.1
	50C	17.06	17.06	0.0	16.86	16.86	0.0	17.05	17.05	0.0	14.93	14.93	0.0

# **EPA METHOD 9090A TEST RESULTS**

## **SKAPS INDUSTRIES HDPE GEONET TEST RESULTS**

**TRI LOG NUMBER: E2173-46-05**

### **NOTE ON TEST RESULTS**

**This section includes generated test data provided in both tabular and graphical form. Each graph is represented by a series of "I" beam plots. Each "I" beam represents a single test population and illustrates the high and low value as the end points, and the mean as a central box on the beam.**

**At each testing period, two "I" beams are shown. The left beam represents the 23°C exposed specimens while the right beam represents the 50°C specimens. The initial "I" beam represents the baseline or unexposed test specimens.**

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Client: Skaps Industries**

Report Date: January 2003  
 TRI Log Number: E2173-46-05

Exposure Time and Temperature

Test Parameters	Baseline	30 Day		60 Day		90 Day		120 Day	
		23C	50C	23C	50C	23C	50C	23C	50C

**GEONET: HDPE GEONET EXPOSED TO PaDER MSW SYNTHETIC LEACHATE**

<b>Strip Tensile Properties:</b>	143	158	173	130	167	131	166	168	133
Maximum Strength (lbs)	167	144	162	153	152	167	148	165	150
ASTM D5035	153	151	147	149	173	126	157	172	144
Machine Direction	150								
	170								
	144								
Average	155	151	161	144	164	141	157	168	142
STD	11	6	11	10	9	18	7	3	7
Coefficient of Variation	7	4	7	7	5	13	5	2	5
% Change		-2	4	-7	6	-9	2	9	-8
<b>Strip Tensile Properties:</b>	33	34	35	30	35	35	31	35	33
Elongation @ Max. Strength (%)	36	28	32	35	42	34	33	36	28
ASTM D5035	35	33	24	32	31	31	35	33	31
Machine Direction	30								
	31								
	33								
Average	33	32	30	32	36	33	33	35	31
STD	2	3	5	2	5	2	2	1	2
Coefficient of Variation	6	8	15	6	13	5	5	4	7
% Change		-4	-8	-2	9	1	0	5	-7

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Client: Skaps Industries**

Report Date: January 2003  
 TRI Log Number: E2173-46-05

Exposure Time and Temperature

Test Parameters	Baseline	30 Day		60 Day		90 Day		120 Day	
		23C	50C	23C	50C	23C	50C	23C	50C

**GEONET: HDPE GEONET EXPOSED TO PaDER MSW SYNTHETIC LEACHATE**

<b>Strip Tensile Properties:</b>	56	55	60	57	49	59	53	60	47
Maximum Strength (lbs)	57	53	59	57	56	54	53	61	59
ASTM D5035	64	51	60	56	62	51	52	58	56
Transverse Direction	57								
	51								
	53								
Average	56	53	60	57	56	55	53	60	54
STD	4	2	0	0	5	3	0	1	5
Coefficient of Variation	7	3	1	1	10	6	1	2	9
% Change		-6	6	1	-1	-3	-7	6	-4
<b>Strip Tensile Properties:</b>	129	171	163	151	169	148	155	135	165
Elongation @ Max. Strength (%)	172	160	139	159	157	141	168	147	177
ASTM D5035	153	115	133	160	189	149	167	149	148
Transverse Direction	133								
	151								
	149								
Average	146	149	145	157	172	146	163	144	163
STD	14	24	13	4	13	4	6	6	12
Coefficient of Variation	10	16	9	3	8	2	4	4	7
% Change		1	-2	6	16	-1	10	-3	10

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Client: Skaps Industries**

Report Date: January 2003  
 TRI Log Number: E2173-46-05

Exposure Time and Temperature

Test Parameters	Baseline	30 Day		60 Day		90 Day		120 Day	
		23C	50C	23C	50C	23C	50C	23C	50C

**GEONET: HDPE GEONET EXPOSED TO PaDER MSW SYNTHETIC LEACHATE**

<b>Compressive Strength:</b>	35951	36083	33732	25141	34508	39672	33045	35164	31349
Strength at Rib Layover (psf)	35677	31833	39106	40149	23798	32742	32879	34119	33234
ASTM D1621	38252	34801	31922	37048	42045	37877	39494	40486	36492
	36837								
	32100								
	33888								
Average	35451	34239	34920	34113	33450	36764	35139	36590	33692
STD	1989	1780	3051	6469	7487	2937	3080	2788	2124
Coefficient of Variation	6	5	9	19	22	8	9	8	6
% Change		-3	-1	-4	-6	4	-1	3	-5
<b>Transmissivity:</b>	1.96E-03	1.88E-03	1.91E-03	1.77E-03	1.94E-03	1.87E-03	1.90E-03	1.96E-03	1.90E-03
(m2/sec)	1.95E-03	1.88E-03	1.89E-03	1.76E-03	1.91E-03	1.84E-03	1.93E-03	1.96E-03	1.96E-03
ASTM D4716	2.01E-03	1.89E-03	1.94E-03	1.78E-03	1.84E-03	1.82E-03	1.95E-03	1.94E-03	1.89E-03
	1.94E-03								
	2.00E-03								
	1.88E-03								
Average	1.96E-03	1.88E-03	1.91E-03	1.77E-03	1.90E-03	1.84E-03	1.93E-03	1.95E-03	1.92E-03
STD	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Coefficient of Variation	2.18	0.25	1.07	0.46	2.21	1.11	1.07	0.48	1.61
% Change		-3.75	-2.21	-9.54	-3.07	-5.79	-1.53	-0.17	-2.04
<b>CBR Puncture:</b>	292	238	292	279	345	296	308	279	256
Puncture Resistance (lbs)	235	247	298	289	276	278	311	265	275
ASTM D6241	280	270	265	240	273	255	289	246	288
	285								
	286								
	284								
Average	277	252	285	269	298	276	303	263	273
STD	19	13	14	21	33	17	10	14	13
Coefficient of Variation	7	5	5	8	11	6	3	5	5
% Change		-9	3	-3	8	-0	9	-5	-1

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Client: Skaps Industries**

Report Date: January 2003  
 TRI Log Number: E2173-46-05

Exposure Time and Temperature


Test Parameters	Baseline	30 Day		60 Day		90 Day		120 Day	
		23C	50C	23C	50C	23C	50C	23C	50C

**GEONET: HDPE GEONET EXPOSED TO PaDER MSW SYNTHETIC LEACHATE**

<b>Volatiles and Extractables:</b>	-1.51	-1.51	-1.01	-2.00	-0.51	0.00	-1.00	-0.50	-1.01
Machine Diameter Change (%)	-3.02	-2.51	-1.51	-1.01	-1.50	-1.01	-2.01	-2.53	-0.51
SW 870 - Appendix III-D	-2.51								
	-1.01								
<b>Average</b>	-2.01	-2.01	-1.26	-1.51	-1.01	-0.51	-1.51	-1.52	-0.76
<b>STD</b>	0.79	0.50	0.25	0.50	0.50	0.51	0.50	1.02	0.25
<b>Volatiles and Extractables:</b>	-3.02	-3.48	-1.51	-1.04	-1.01	-1.49	-0.51	-1.03	-1.54
Transverse Diameter Change (%)	-3.98	-3.48	-1.00	-3.05	-1.00	-1.52	-1.02	-1.54	-1.53
SW 870 - Appendix III-D	-1.99								
	-0.50								
<b>Average</b>	-2.37	-3.48	-1.26	-2.05	-1.01	-1.51	-0.77	-1.29	-1.54
<b>STD</b>	1.29	0.00	0.26	1.01	0.01	0.02	0.26	0.25	0.00
<b>Volatiles and Extractables:</b>	0.07	0.11	0.09	0.11	0.16	0.12	0.11	0.12	0.11
% Volatiles	0.07	0.11	0.12	0.10	0.16	0.08	0.10	0.13	0.08
SW 870 - Appendix III-D	0.07								
	0.07								
<b>Average</b>	0.07	0.11	0.11	0.11	0.16	0.10	0.11	0.13	0.10
<b>STD</b>	0.00	0.00	0.02	0.00	0.00	0.02	0.00	0.01	0.01
<b>Volatiles and Extractables:</b>	0.16	0.25	0.21	0.16	0.13	0.22	0.08	0.18	0.10
% Extractables	0.14	0.18	0.25	0.32	0.30	0.27	0.19	0.35	0.30
SW 870 - Appendix III-D	0.16								
	0.25								
<b>Average</b>	0.18	0.22	0.23	0.24	0.22	0.25	0.14	0.27	0.20
<b>STD</b>	0.04	0.04	0.02	0.08	0.09	0.03	0.05	0.08	0.10


# SKAPS IND. - EPA METHOD 9090A TEST

HDPE Geonet vs PaDER MSW Leachate



# SKAPS IND. - EPA METHOD 9090A TEST


HDPE Geonet vs PaDER MSW Leachate






# SKAPS IND. - EPA METHOD 9090A TEST

HDPE Geonet vs PaDER MSW Leachate




# SKAPS IND. - EPA METHOD 9090A TEST

HDPE Geonet vs PaDER MSW Leachate



# SKAPS IND. - EPA METHOD 9090A TEST

HDPE Geonet vs PaDER MSW Leachate





TRI/ENVIRONMENTAL, INC.  
A Texas Research International Company

---

February 11, 2004

**Mr. Anarag**  
**Skaps Industries**  
571 Industrial Parkway  
Commerce, GA 30529

Dear Mr. Anarag:

TRI/Environmental, Inc. (TRI) is pleased to present this Final Report for a geotextile chemical resistance study performed in general accordance with EPA Method 9090A as applied by ASTM D 6389-99, *Standard Practice for Tests to Evaluate the Chemical Resistance of Geotextiles to Liquids*.

TRI is very pleased to be of service to Skaps Industries. Please call me if you have any questions or require any additional information (800 880 8378).

Respectfully submitted,

A handwritten signature in black ink that reads "Sam R. Allen". The signature is written in a cursive, slightly slanted style.

Sam R. Allen  
Vice President and Division Manager  
Geosynthetic Services Division  
[www.GeosyntheticTesting.com](http://www.GeosyntheticTesting.com)

A Final Report:

**Laboratory Testing of Geotextile  
for Waste Containment  
EPA Method 9090A**

February 2004

Submitted to:

**Skaps Industries**

571 Industrial Parkway  
Commerce, GA 30529

Attn: **Mr. Anarag**

Submitted by:

**TRI/Environmental, Inc.**

9063 Bee Caves Rd.  
Austin, Texas 78733

## **FOREWORD**

The testing reported herein is based upon accepted industry practice as well as the test method listed. TRI/Environmental Inc. (TRI) neither accepts responsibility for nor makes claim as to the final use and purpose of the materials tested.

Tests were performed under laboratory conditions and not under actual usage conditions. TRI can give no conclusions as to the serviceability, life expectancy or general durability of the products tested when used in a lining and/or leachate collection system.

## **1.0 INTRODUCTION**

This report describes the work performed by TRI/Environmental, Inc. (TRI) to determine the chemical compatibility of one geotextile product with one synthetic waste leachate. The objective was to determine the resistance of the geotextile to changes caused by exposure to leachate. Changes in physical, mechanical and hydraulic properties were measured after exposure to the leachate at 23°C and 50°C for 30, 60, 90 and 120 days. Exposures were performed in accordance with the exposure regimen specified in United States Environmental Protection Agency (EPA) Method 9090A.

All samples were logged in and all testing performed under TRI log number E2183-79-10. Methods, results and discussion are provided in the sections which follow. Test results are provided in the Tables of Results which accompany this report.

## **2.0 METHODS**

### **2.1 Materials**

The material selected for evaluation in this chemical compatibility study was Skaps.GTE 160 polypropylene staple fiber nonwoven needlepunched geotextile.

### **2.2 Leachate**

The waste leachate used was supplied by TRI and was a synthetic MSW leachate approximating the PaDER leachate recipe.

### **2.3 Exposure Conditions**

Geotextile specimens were exposed to the waste leachate following the specifications of EPA Method 9090A as they relate to exposure to waste fluids. The tanks used for these exposures were maintained at  $23 \pm 2^\circ\text{C}$  and  $50 \pm 2^\circ\text{C}$  throughout the 120-day exposure period. Tanks were constructed from chemically resistant glass fitted with stirrers. The 50°C tanks were heated with a circulating hot water heat exchanger system. They were also sealed with a lid, and a reflux condenser was installed to minimize loss of volatile leachate components.

### **2.4 Testing Procedures**

Table 1 lists tests performed on the geotextile. The number of test replicates was doubled for baseline determinations on unexposed material.

Table 1. Tests performed on TNS - Nevown, Inc. nonwoven geotextile		
Test or Physical Property	Method	Number of replicate specimens
Dimensions and weight	EPA 9090A	2 readings
Grab Tensile Strength	ASTM D 4632	3 MD & TD readings
Grab Tensile Elongation	ASTM D 4632	3 MD & TD readings
Trapezoidal Tear Strength	ASTM D 4533	3 MD & TD readings
Puncture Resistance	ASTM D 4833	3 readings
Mullen Burst	ASTM D 3786	3 readings
Permittivity	ASTM D 4491	3 readings

### 3.0 RESULTS AND DISCUSSION

Test results are presented in the Test Results section which is included with this report. Test results are presented in tabular form as well as graphical form.

In considering these results, it must be determined through engineering judgment whether observed differences in the value of test results measured before and after immersion are due to product variability, unidentified factors relating to the test procedure, or leachate interaction with the product. Any significant chemical interaction with leachate would be expected to result in degradation trends which are consistent across the various properties being evaluated, and not isolated to one set of test results only. However, with each type of material there may be specific properties which are highly sensitive to leachate-induced effects. These factors must be considered in evaluating the various test results for a given product.

Also of critical importance is the issue of product variability. With nonwoven geotextiles, a range of physical and mechanical index test values covering 20% or more of the average is not uncommon. This can be traced to variability inherent in the product, and the randomness associated with the onset of failure under the specified testing conditions. However, in chemical compatibility testing the statistical sampling of a broad range of manufactured product is not possible. Therefore, the small size of the sample population tested at each time point must be taken into consideration. The criteria to be applied in evaluating data measured before and after leachate immersion should be that property changes, if observed, are consistent and so great that product variability and experimental factors can be ruled out.

In this report, standard deviations (STD) are reported for measurements involving three or more replicate specimens. In statistics, the standard deviation is defined as root of the mean squared deviations of



individual test results about the mean value. The standard deviation is a quantitative measure of variability within a group of measurements.

One related measure of variability observed within a sample set, relative to the magnitude of the mean value itself, is the *coefficient of variation or variance* (COV). The coefficient of variance is defined as the standard deviation divided by the mean associated with a group of specimens, and may be expressed as a percentage. The COV provides an indication of what proportion of the mean value may be attributable to random experimental factors or product variability. It is useful to consider apparent changes in property values against the criterion of COV since observed changes which fall below the COV may not be significant. This approach was used in preparing the tables in the next section.

The term *range* refers to the difference between the extreme highest and lowest points within a group of measured values. Considering range as a percentage of the mean values provides another measure of variability within a dataset.

In the tables, the high and low extremes for percentage change in mean values are listed for comparison against COV and range as a percentage of mean from the baseline sample group. The high and low percentage changes are the extremes from data measured at 30, 60, 90 and 120 days.

### SKAPS GTE 160 nonwoven polypropylene geotextile

Table 2 illustrates the range of variability in baseline data compared with some of the observed changes in average test values measured after immersion for the geotextile.


<b>Table 2. Baseline coefficients of variation and range of percentage change results for geotextile</b>				
<b>Test</b>	<b>Baseline COV (%)*</b>	<b>Baseline Range as % of Mean*</b>	<b>High Observed % Change</b>	<b>Low Observed % Change</b>
<b>Grab Tensile Strength (MD)</b>	8	22	12	-1
<b>Grab Tensile Elongation @ Maximum Load (MD)</b>	8	24	2	-4
<b>Trapezoidal Tear Strength (MD)</b>	8	22	7	-8
<b>Puncture Strength</b>	17	50	3	-9
<b>Mullen Burst Strength</b>	8	26	5	-9

#### 4.0 CONCLUSION

While some changes in certain measured physical and mechanical properties were noted for the geotextile, the observed variances were random and are believed to be the effects of product variability and experimental factors.

TRI/Environmental, Inc. is pleased to have been selected to participate in this project. We trust that the information provided in this report meets your requirements for technical documentation of this chemical compatibility study. Please do not hesitate to call if you have any questions or require any additional information.

Respectfully submitted,



Sam R. Allen  
Vice President and Division Manager  
Geosynthetic Services Division

TRI/Environmental, Inc.

**APPENDIX:**

**EPA METHOD 9090A TEST RESULTS**

**SKAPS GTE 160 Nonwoven Geotextile TEST RESULTS**

**Dimensions**

**TRI LOG NUMBER: E2183-79-10**

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**

Client: Skaps Industries

Report Date: February 2004  
 TRI Log Number: E2189-79-10

Exposure Time and Temperature

Test Parameters	Temp.	30 Day			60 Day			90 Day			120 Day		
		Baseline	Exposed	% Change	Baseline	Exposed	% Change	Baseline	Exposed	% Change	Baseline	Exposed	% Change

**GEOTEXTILE: POLYPROPYLENE NONWOVEN EXPOSED TO PaDER SYNTHETIC MSW LEACHATE**

GEOTEXTILE ROLL ID: GTE-160

Thickness (mils)	23C	115	112	-2.6	112	112	0.0	118	118	0.0	108	107	-0.9
	50C	107	104	-2.8	118	117	-0.8	117	113	-3.4	114	117	2.6
Length (inches)	23C	8.06	8.04	-0.2	8.07	8.03	-0.5	8.10	8.00	-1.2	8.05	8.00	-0.6
	50C	8.08	7.97	-1.4	8.06	7.96	-1.2	8.08	7.95	-1.6	8.01	7.94	-0.9
Width (inches)	23C	4.05	4.01	-1.0	4.02	4.00	-0.5	4.00	3.96	-1.0	3.98	3.95	-0.8
	50C	4.00	3.92	-2.0	4.01	3.99	-0.5	4.06	4.02	-1.0	4.06	4.04	-0.5
Mass (g)	23C	4.88	4.87	-0.2	4.88	4.95	1.4	5.01	5.01	0.0	6.55	6.51	-0.6
	50C	4.38	4.38	0.0	5.15	5.08	-1.4	5.08	5.05	-0.6	5.60	5.53	-1.2

# **EPA METHOD 9090A TEST RESULTS**

## **SKAPS GTE 160 Nonwoven Geotextile TEST RESULTS**

**TRI LOG NUMBER: E2183-79-10**

### **NOTE ON TEST RESULTS**

This section includes generated test data provided in both tabular and graphical form. Each graph is represented by a series of "I" beam plots. Each "I" beam represents a single test population and illustrates the high and low value as the end points, and the mean as a central box on the beam.

At each testing period, two "I" beams are shown. The left beam represents the 23°C exposed specimens while the right beam represents the 50°C specimens. The initial "I" beam represents the baseline or unexposed test specimens.

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Client: Skaps Industries**

Report Date: February 2004  
 TRI Log Number: E2183-79-10

Exposure Time and Temperature

Test Parameters	Baseline	30 Day		60 Day		90 Day		120 Day	
		23C	50C	23C	50C	23C	50C	23C	50C

**GEOTEXTILE: POLYPROPYLENE NONWOVEN EXPOSED TO PADER SYNTHETIC MSW LEACHATE**  
**GEOTEXTILE ROLL ID: GTE-160**

<b>Grab Tensile Properties:</b>	164	206	183	182	215	208	204	214	230
Maximum Strength (lbs)	167	185	208	184	223	196	199	246	205
ASTM D4632	202	211	222	232	240	215	192	161	218
Machine Direction	204								
	187								
	155								

Average	180	201	204	199	226	206	198	207	218
STD	19	11	16	23	10	8	5	35	10
Coefficient of Variation	11	6	8	12	5	4	2	17	5
% Change		12	14	11	26	15	10	15	21

<b>Grab Tensile Properties:</b>	96	109	93	119	94	91	91	95	108
Elongation @ Max. Strength (%)	89	105	100	106	95	98	99	107	98
ASTM D4632	95	107	101	113	91	101	87	103	103
Machine Direction	104								
	109								
	155								

Average	108	107	98	113	93	97	92	102	103
STD	22	2	4	5	2	4	5	5	4
Coefficient of Variation	20	2	4	5	2	4	5	5	4
% Change		-1	-9	4	-14	-10	-15	-6	-5

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Client: Skaps Industries**

Report Date: February 2004  
 TRI Log Number: E2183-79-10

Exposure Time and Temperature

Test Parameters	Baseline	30 Day		60 Day		90 Day		120 Day	
		23C	50C	23C	50C	23C	50C	23C	50C

**GEOTEXTILE: POLYPROPYLENE NONWOVEN EXPOSED TO PADER SYNTHETIC MSW LEACHATE**  
**GEOTEXTILE ROLL ID: GTE-160**

<b>Grab Tensile Properties:</b>	321	345	289	308	338	323	290	285	274
Maximum Strength (lbs)	325	343	310	338	277	317	309	303	309
ASTM D4632	282	252	282	287	252	329	292	310	298
Transverse Direction	288								
	220								
	258								

Average	282	313	294	311	289	323	297	299	294
STD	36	43	12	21	36	5	9	11	15
Coefficient of Variation	13	14	4	7	12	2	3	4	5
% Change		11	4	10	2	14	5	6	4

<b>Grab Tensile Properties:</b>	98	97	93	97	98	93	99	91	93
Elongation @ Max. Strength (%)	115	112	104	109	99	100	99	103	104
ASTM D4632	94	94	103	97	85	93	92	94	95
Transverse Direction	83								
	95								
	99								

Average	97	101	100	101	94	95	97	96	97
STD	9	8	5	6	6	3	3	5	5
Coefficient of Variation	10	8	5	6	7	3	3	5	5
% Change		4	3	4	-3	-2	-1	-1	0

**TABLE OF CHEMICAL COMPATIBILITY TEST RESULTS**  
**Client: Skaps Industries**

Report Date: February 2004  
 TRI Log Number: E2183-79-10

Exposure Time and Temperature

Test Parameters	Baseline	30 Day		60 Day		90 Day		120 Day	
		23C	50C	23C	50C	23C	50C	23C	50C

**GEOTEXTILE: POLYPROPYLENE NONWOVEN EXPOSED TO PADER SYNTHETIC MSW LEACHATE**  
**GEOTEXTILE ROLL ID: GTE-160**

<b>Mullen Burst Strength:</b>	455	380	415	390	450	450	435	415	380
Burst Strength (psi)	420	400	380	400	430	415	410	405	385
ASTM D3786	425	345	415	400	410	410	380	365	350
	400								
	350								
	405								

Average	409	375	403	397	430	425	408	395	372
STD	32	23	16	5	16	18	22	22	15
Coefficient of Variation	8	6	4	1	4	4	6	5	4
% Change		-8	-1	-3	5	4	-0	-3	-9

<b>Permittivity:</b>	1.63	1.61	1.79	1.53	1.66	1.97	1.83	2.06	1.72
(sec -1)	1.81	1.64	1.64	1.97	1.97	2.18	1.97	1.67	1.61
ASTM D4491	1.63	1.53	1.88	1.97	1.83	1.88	1.91	1.91	2.00
	1.79								
	1.76								
	1.68								

Average	1.72	1.59	1.77	1.82	1.82	2.01	1.90	1.88	1.78
STD	0.07	0.05	0.10	0.21	0.13	0.13	0.06	0.16	0.16
Coefficient of Variation	4.28	2.91	5.59	11.38	6.96	6.25	3.01	8.54	9.24
% Change		-7.18	3.11	6.21	6.02	17.09	10.87	9.51	3.50

<b>Trapezoidal Tear</b>	87	97	78	85	106	61	85	102	101
Tear Strength - (lbs)	86	87	94	82	91	78	101	70	104



**APPENDIX G  
SETTLEMENT ANALYSES**

<b>APPENDIX G.1</b>	<b>FOUNDATION SETTLEMENT</b>
<b>APPENDIX G.2</b>	<b>CLAY LINER RATE OF CONSOLIDATION</b>
<b>APPENDIX G.3</b>	<b>CLAY LINER CONSOLIDATION SETTLEMENT</b>
<b>APPENDIX G.4</b>	<b>POST-CLOSURE WASTE SETTLEMENT</b>

**APPENDIX G.1**  
**FOUNDATION SETTLEMENT**



**Kettleman Hills Facility – Landfill Unit B-18  
FOUNDATION SETTLEMENT**

Project No.: 083-91887

Made By: LAQ

Date: 05-20-2008

Checked By: EH

Sheet: 1 of 6

Reviewed By: 

**Objectives:**

1. To estimate the magnitude and distribution of settlement of the Landfill B-18 foundation due to the overlying waste.
2. To evaluate whether the final gradient of the Landfill B-18 foundation after settlement is the required minimum of 2% to maintain adequate drainage.

**Given:**

The Landfill B-18 expansion geometry and as-built landfill configuration used to generate the evaluated sections were obtained from AutoCAD drawings (see Drawings). All other data used for these calculations are based on the original Environmental Solutions, Inc. (ESI, 1990) calculations, including site geology and foundation stratigraphy (see Attachment 1). The original calculation was performed utilizing the computer program SETTLE developed by Geosoft Inc.; however, this program is no longer available. Golder programmed the settlement equations into Microsoft Excel to perform the foundation settlement calculations.

**Assumptions (Assumptions are consistent with those used by ESI):**

1. Claystone and siltstone are considered the same. Previous investigations indicate that the compression characteristics of the claystone and siltstone are practically the same.
2. Foundation materials are highly overconsolidated, therefore the stress-strain relationship under loading is considered to be within the elastic range of materials.
3. Rebound and settlement of foundation will occur during excavation and waste placement. Therefore the gross weight, rather than the net weight of the waste fill will be used.
4. Sandstone under the landfill foundation is considered to be incompressible.
5. The foundation materials are considered to be homogeneous and isotropic. The stress-strain behavior of the materials under load is characterized by the Young's Modulus and the Poisson's Ratio.

**Method:**

1. Determination of Young's Modulus (E)

The elastic modulus may be expressed in terms of the shear strength of the soil:

$$E = kS_u$$

Where k is a function of the Plasticity Index (PI). Values for the on-site claystone materials at various depths are shown in Figure 1. By using the linear progression method, the scattered data may be represented by a straight line. The best fit straight line takes the form of:



Kettleman Hills Facility – Landfill Unit B-18  
FOUNDATION SETTLEMENT

Project No.: 083-91887

Made By: LAQ

Date: 05-20-2008

Checked By: EH


Sheet: 2 of 6

Reviewed By: *[Signature]*

$$PI (\%) = 37.2 + 0.05y (\text{ft})$$

where y is equal to the depth below ground surface. The results of the above statistical analysis indicate that the variation of PI with depth is not significant.

Figure 1: PI vs. Depth for claystone material.





**Kettleman Hills Facility – Landfill Unit B-18  
FOUNDATION SETTLEMENT**

Project No.: 083-91887

Made By: LAQ

Date: 05-20-2008


Checked By: EH

Sheet: 3 of 6

Reviewed By: *[Signature]*

Therefore, it was assumed that the PI is constant with depth. Taking the average depth for all data, the PI value for the foundation material was estimated to be approximately 41. By assuming the overconsolidation ratio (OCR) of the claystone is 2, the value of K was estimated to be 420 as shown in the Figure 2.

**Figure 2:** Chart for estimating Undrained Modulus of Clay.



$$E_u = K S_u$$

$E_u$  = UNDRAINED MODULUS OF CLAY

$K$  = FACTOR FROM CHART ABOVE

$S_u$  = UNDRAINED SHEAR STRENGTH OF CLAY



**Kettleman Hills Facility – Landfill Unit B-18  
FOUNDATION SETTLEMENT**

Project No.: 083-91887

Made By: LAQ

Date: 05-20-2008

Checked By: EH

Sheet: 4 of 6

Reviewed By: *EBB*

The shear strength of the foundation material is summarized in the following table:

<b>Geologic Unit</b>	<b>Shear Strength (psi)<sup>1</sup></b>
18-5	127.0
18-7	110.6
18-8	91.1
18-12	72.2
<b>Average</b>	<b>100.2</b>

<sup>1</sup>Obtained from UU triaxial test results

Taking the average shear strength ( $S_u$ ), the elastic modulus ( $E_u$ ) is estimated to be:  
 $E_u = K \times S_u = 420 \times (100 \text{ lb/in}^2 \times 144 \text{ in}^2/\text{ft}^2 / 1000 \text{ lb/kip}) = 6,048 \text{ kip/ft}^2$ , round to 6,000 ksf.

2. Determination of Poisson's Ratio ( $\nu$ )

The value of Poisson's Ratio was found to be insensitive to the compressibility coefficient used to calculate the settlement. Poisson's Ratio was back-calculated using the average compressibility coefficient determined by using a value of the Poisson's Ratio from 0 to 0.5. The resulting Poisson's Ratio was estimated to be 0.38.

3. Determination of Compressibility Index ( $C_u$ )

The Compressibility coefficient is related to E and  $\nu$  by:

$$C_u = \frac{1-\nu^2}{E}$$

4. Determination of changes in stress with depth ( $\Delta\sigma$ )

Since it was assumed that the deformation of the foundation is elastic under the waste loading, the Boussinesq Equation was used to determine  $\Delta\sigma$ . To calculate  $\Delta\sigma$  under the center of a rectangular loaded area:

$$\Delta\sigma = \sigma_0 m I$$

Where:

$\sigma_0$  = initial stress at a specific depth

m = number of influences, for the center of a foundation m = 4

$\sigma_0 = \gamma z$

$\gamma$  = soil unit weight

z = depth to the middle of layer to be evaluated

$$I = \frac{1}{4\pi} \left[ \frac{2MN\sqrt{V}}{V+V_1} \frac{V+1}{V} + \tan^{-1} \left( \frac{2MN\sqrt{V}}{V-V_1} \right) \right]$$



Kettleman Hills Facility – Landfill Unit B-18  
FOUNDATION SETTLEMENT

Project No.: 083-91887

Made By: LAQ

Date: 05-20-2008

Checked By: EH

Sheet: 5 of 6

Reviewed By:

$$M = \frac{B}{z}; N = \frac{L}{z}$$

$$V = M^2 + N + 1; V_1 = (MN)^2$$

B = Base of foundation

L = Length of foundation

To calculate  $\Delta\sigma$  under a point that is not at the center of the rectangular loaded area, the following is used:

$$\Delta\sigma = \sigma_0 I_1 + \sigma_0 I_2 + \sigma_0 I_3 + \sigma_0 I_4$$

5. Calculation of Settlement ( $\Delta H$ )

The foundation settlement can then be calculated by:

$$\Delta H = \varepsilon H$$

Where:

$\varepsilon$  = vertical strain determined by  $\varepsilon = \Delta\sigma C_u$

H = thickness of the layer where settlement is calculated

The total settlement is determined by  $\sum \Delta H$  under the point being evaluated.

**Calculations and Results:**

1. Settlement Calculation

Foundation settlement calculations were performed for Sections 1-1', 2-2', and 3-3' for each of the points shown on Drawing 1, Cross sections are shown on Drawings 3, 4 and 5, respectively. All settlement results are summarized in the Table 1 through Table 3 in the Tables Section of this calculation brief. Settlement along the landfill foundation ranges from 0.74 inches (Section 2-2' Point 2A) to 13.55 inches (Section 2-2 Point 2K<sub>1</sub>)).

2. Final Gradient Computation

The formula utilized for the final gradient calculation is defined as follows:

$$G_f = \frac{(EL_2 - \Delta H_2) - (EL_1 - \Delta H_1)}{(\Delta X_2 - \Delta X_1)}$$

Where:

$EL_2$  = elevation at point 2

$EL_1$  = elevation at point 1

$\Delta H_2$  = settlement at point 2

$\Delta H_1$  = settlement at point 1

$(\Delta X_2 - \Delta X_1)$  = Distance between two points



**Kettleman Hills Facility – Landfill Unit B-18  
FOUNDATION SETTLEMENT**

Project No.: 083-91887

Made By: LAQ

Date: 05-20-2008

Checked By: EH

Sheet: 6 of 6

Reviewed By: 

Final gradient calculations were performed in Sections 2-2' and 3-3'(as shown on Drawing 4 and 5) since the two sections are the ones along the drainage direction. All final gradient results are summarized in Table 4 and Table 5 in the Tables Section of this report.

In all cases the gradient remains in excess of 2% when measured in the direction of flow. Some locations in the sections are not perpendicular to the contours and therefore the slope is not reported; however, the computed settlement at these locations are observed to be of similar magnitude and the original grade would be maintained.

3. Strain Difference Computation

The formula utilized for the final gradient calculation is defined as follows:

$$\Delta\varepsilon = \frac{G_f - G_i}{d}$$

In where:

$G_f$  = final gradient

$G_i$  = initial gradient

$d$  = distance between two points

Final strain calculations were performed in Sections 2-2' and 3-3'since these two sections are the ones along the drainage direction. All strain difference results are summarized in Table 6 through Table 7 in the Tables Section of this report.

The result all points have less than the design maximum strain of 0.1%.

**Conclusions:**

Based on the foundation settlement calculations for the selected sections, we can assume that the bottom gradient of the landfill along the critical sections will be maintained at a minimum of 2% meeting the minimum requirement for drainage.

Based on the foundation settlement calculations for the selected sections, we can assume that there will be no abrupt changes along the surface of the foundation due to settlement. The maximum allowable strain due to settlement is less than 0.1% which is less than the yield strain of the synthetic liner. Therefore the liner stays intact.

**Reference:**

Environmental Solutions, Inc. (ESI), "Engineering and Design Report, Landfill Unit B-18, Phases I and II and Final Closure, Kettleman Hills Facility," August 1990, Appendix G.1.

Bowles, J.E., "Foundation Analysis and Design," Fifth Edition, 1996, pp. 291-296.



**Table 1**  
**Settlement Calculation Summary**  
**Section 1-1'**

Point No.	A Geologic Unit	B % Clay in A	C Calculated Settlement (assumed a 100% Clay Content) (in)	BxC Estimated Settlement (in)	Total Settlement (in)
1 A	18-7	30%	11.90	3.57	3.57
1 B	18-7	30%	13.85	4.16	4.16
1 C	18-8	100%	3.14	3.14	7.74
	18-7	30%	15.35	4.60	
1 D	18-8	100%	5.71	5.71	8.52
	18-7	30%	9.38	2.82	
1 E	18-9	0%	0.00	0.00	8.99
	18-8	100%	6.24	6.24	
	18-7	30%	9.17	2.75	
1 F	18-9	0%	0.00	0.00	11.18
	18-8	100%	8.26	8.26	
	18-7	30%	9.75	2.93	
1 G	18-9	0%	0.00	0.00	12.63
	18-8	100%	9.50	9.50	
	18-7	30%	10.43	3.13	
1 H	18-10	50%	4.72	2.36	9.63
	18-9	0%	0.00	0.00	
	18-8	100%	6.24	6.24	
	18-7	30%	3.41	1.02	
1 I	18-10	50%	6.55	3.28	5.47
	18-9	0%	0.00	0.00	
	18-8	100%	2.10	2.10	
	18-7	30%	0.33	0.10	
1 J	18-12	100%	0.69	0.69	1.80
	18-11	10%	1.48	0.15	
	18-10	50%	1.27	0.63	
	18-9	0%	0.00	0.00	
	18-8	100%	0.32	0.32	
1 K	18-13	10%	1.46	0.15	1.20
	18-12	100%	0.01	0.01	
	18-11	10%	0.99	0.10	
	18-10	50%	1.25	0.63	
	18-9	0%	0.00	0.00	
	18-8	100%	0.32	0.32	

**Table 2**  
**Settlement Calculation Summary**  
**Section 2-2'**

Point No.	A Geologic Unit	B % Clay in A	C Calculated Settlement (assumed a 100% Clay Content) (in)	BxC Estimated Settlement (in)	Total Settlement (in)
2 A	18-4	100%	0.28	0.28	0.74
	18-3	20%	2.32	0.46	
2 B	18-5	20%	0.61	0.12	2.43
	18-4	100%	0.62	0.62	
	18-3	20%	8.43	1.69	
2 C	18-5	20%	2.56	0.51	2.90
	18-4	100%	0.81	0.81	
	18-3	20%	7.91	1.58	
2 D	18-6	20%	1.33	0.27	3.62
	18-5	20%	2.78	0.56	
	18-4	100%	0.96	0.96	
	18-3	20%	9.18	1.84	
2 E	18-7	30%	3.15	0.95	4.62
	18-6	20%	1.63	0.33	
	18-5	20%	3.14	0.63	
	18-4	100%	1.21	1.21	
	18-3	20%	7.57	1.51	
2 F	18-7	30%	7.57	2.27	5.92
	18-6	20%	1.90	0.38	
	18-5	20%	3.38	0.68	
	18-4	100%	1.49	1.49	
	18-3	20%	5.54	1.11	
2 G	18-8	100%	8.96	8.96	11.94
	18-7	30%	8.55	2.57	
	18-6	20%	2.07	0.41	
	18-5	20%	3.10	0.62	
	18-4	100%	1.22	1.22	
2 H	18-8	100%	1.22	1.22	5.14
	18-7	30%	9.21	2.76	
	18-6	20%	2.32	0.46	
	18-5	20%	3.47	0.69	
2 I	18-10	50%	0.63	0.31	6.45
	18-9	0%	0.00	0.00	
	18-8	100%	5.17	5.17	
	18-7	30%	2.74	0.82	
	18-6	20%	0.71	0.14	
2 J	18-10	50%	4.46	2.23	13.32
	18-9	0%	0.00	0.00	
	18-8	100%	9.10	9.10	
	18-7	30%	6.63	1.99	

**Table 2**  
**Settlement Calculation Summary**  
**Section 2-2'**

Point No.	A Geologic Unit	B % Clay in A	C Calculated Settlement (assumed a 100% Clay Content) (in)	BxC Estimated Settlement (in)	Total Settlement (in)
2 K	18-10	50%	6.71	3.36	11.58
	18-9	0%	0.00	0.00	
	18-8	100%	7.54	7.54	
	18-7	30%	2.28	0.68	
2 K <sub>1</sub>	18-10	50%	8.39	4.20	13.55
	18-9	0%	0.00	0.00	
	18-8	100%	7.81	7.81	
	18-7	30%	5.13	1.54	
2 L	18-10	50%	9.20	4.60	9.89
	18-9	0%	0.00	0.00	
	18-8	100%	5.09	5.09	
	18-7	30%	0.65	0.19	
2 M	18-11	10%	2.45	0.25	5.83
	18-10	50%	6.24	3.12	
	18-9	0%	0.00	0.00	
	18-8	100%	2.47	2.47	
2 N	18-12	100%	1.36	1.36	5.29
	18-11	10%	1.92	0.19	
	18-10	50%	3.23	1.62	
	18-9	0%	0.00	0.00	
	18-8	100%	2.12	2.12	
2 O	18-13	10%	2.91	0.29	1.25
	18-12	100%	0.42	0.42	
	18-11	10%	0.55	0.06	
	18-10	50%	0.97	0.48	
	18-9	0%	0.00	0.00	

**Table 3**  
**Settlement Calculation**  
**Section 3-3'**

Point No.	A Geologic Unit	B % Clay in A	C Calculated Settlement (assumed a 100% Clay Content) (in)	BxC Estimated Settlement (in)	Total Settlement (in)
3 A	18-13	10%	14.10	1.41	1.41
3 B	18-13	10%	22.54	2.25	2.25
3 C	18-12	100%	4.07	4.07	5.79
	18-13	10%	17.24	1.72	
3 D	18-11	10%	10.13	1.01	4.89
	18-12	100%	3.73	3.73	
	18-13	10%	1.53	0.15	
3 D <sub>1</sub>	18-10	50%	8.40	4.20	8.37
	18-11	10%	6.98	0.70	
	18-12	100%	3.18	3.18	
	18-13	10%	2.97	0.30	
3 D <sub>2</sub>	18-10	50%	10.00	5.00	8.46
	18-11	10%	7.72	0.77	
	18-12	100%	2.55	2.55	
	18-13	10%	1.39	0.14	
3 D <sub>3</sub>	18-10	50%	11.36	5.68	9.09
	18-11	10%	7.95	0.79	
	18-12	100%	2.61	2.61	
	18-13	10%	0.78	0.08	
3 E	18-10	50%	13.23	6.61	9.65
	18-11	10%	7.39	0.74	
	18-12	100%	2.29	2.29	
3 F	18-10	50%	11.58	5.79	5.79

**Table 4  
Grade Calculation  
Section 2-2'**

Point No.	Initial Elevation (ft)	Settlement (ft)	Final Elevation (ft)	Distance (ft)	Initial Grade (%)	Final Grade (%)	Allowable Grade 2.0%
2 A	739.09	0.06	739.03	108.83	29.41%	29.54%	OK
2 B	707.08	0.20	706.88				
2 C	709.53	0.24	709.29	112.14	2.18%	2.15%	OK
Not connected with same slope							
2 D	710.65	0.30	710.35	139.54	2.34%	2.28%	OK
2 E	713.91	0.39	713.52				
Not perpendicular to the slope							
2 F	716.55	0.49	716.06	297.93	2.42%	2.25%	OK
2 G	723.75	0.99	722.76				
2 H	724.75	0.43	724.32	41.39	2.42%	3.78%	OK
2 I	767.51	0.54	766.97	95.62	44.72%	44.61%	OK
Not connected with same slope							
2 J	742.76	1.11	741.65	85.61	8.29%	8.12%	OK
2 K	735.66	0.96	734.70				
2 K <sub>1</sub>	737.01	1.13	735.88	58.91	2.29%	2.01%	OK
2 L	752.87	0.82	752.05	35.67	44.46%	45.32%	OK
2 M	780.00	0.49	779.51	60.9	44.55%	45.10%	OK
2 N	796.86	0.44	796.42	33.99	49.60%	49.73%	OK
2 O	837.27	0.10	837.17	Not connected with same slope			

**Table 5  
Grade Calculation  
Section 3-3'**

Point No.	Initial Elevation (ft)	Settlement (ft)	Final Elevation (ft)	Distance (ft)	Initial Grade (%)	Final Grade (%)	Allowable Grade 2.0%
3 A	745.79	0.12	745.67	144.24	2.49%	2.54%	OK
3 B	742.2	0.19	742.01				
3 C	739.04	0.48	738.56	130.45	2.42%	2.65%	OK
3 D	731.57	0.41	731.16	320.67	2.33%	2.31%	OK
3 D <sub>1</sub>	725.37	0.70	724.67	266.92	2.32%	2.43%	OK
3 D <sub>2</sub>	734.00	0.70	733.30	Not connected with same slope			
3 D <sub>3</sub>	725.27	0.76	724.51	Not connected with same slope			
3 E	726.61	0.76	725.85	63.73	2.10%	2.10%	OK
3 F	736.35	0.80	735.55	396.01	2.46%	2.45%	OK
8	837.27	0.48	836.79	Not connected with same slope			


**Table 6**  
**Strain Calculation**  
**Section 2-2'**

Point No.	Initial Elevation (ft)	Distance (ft)	Initial Grade (%)	Final Grade (%)	$\Delta\epsilon$	Allowable Strain 0.1%
2 A	739.09	108.83	29.41%	29.54%	0.0012%	OK
2 B	707.08		2.18%	2.15%	0.0003%	OK
2 C	709.53	70.61	1.59%	1.50%	0.0012%	OK
2 D	710.65	139.54	2.34%	2.28%	0.0004%	OK
2 E	713.91		1.79%	1.72%	0.0005%	OK
2 F	716.55	297.93	2.42%	2.25%	0.0006%	OK
2 G	723.75		41.39	2.42%	3.78%	0.0331%
2 H	724.75	95.62	44.72%	44.61%	0.0012%	OK
2 I	767.51		Not connected with same slope			
2 J	742.76	85.61	8.29%	8.12%	0.0020%	OK
2 K	735.66		58.91	2.29%	2.01%	0.0047%
2 K <sub>1</sub>	737.01	35.67	44.46%	45.32%	0.0240%	OK
2 L	752.87		60.90	44.55%	45.10%	0.0091%
2 M	780.00	33.99	49.60%	49.73%	0.0039%	OK
2 N	796.86		Not connected with same slope			
2 O	837.27	162.7	44.70%	50.85%	0.0378%	OK
8	910.00					

**Table 7  
Strain Calculation  
Section 3-3'**

Point No.	Initial Elevation (ft)	Distance (ft)	Initial Grade (%)	Final Grade (%)	$\Delta\epsilon$	Allowable Strain 0.1%
3 A	745.79	144.24	2.49%	2.54%	0.0003%	OK
3 B	742.2		2.42%	2.65%	0.0018%	OK
3 C	739.04	320.67	2.33%	2.31%	0.0001%	OK
3 D	731.57		2.20%	2.43%	0.0009%	OK
3 D <sub>1</sub>	725.37	Not connected with same slope				
3 D <sub>2</sub>	734.00	Not connected with same slope				
3 D <sub>3</sub>	725.27	63.73	1.96%	2.10%	0.0022%	OK
3 E	726.61		2.46%	2.45%	0.0000%	OK
3 F	736.35	396.01	Not connected with same slope			
8	837.27		Not connected with same slope			





**TABLE 1**

BORING	DEPTH (FEET)	ELEVATION
L18-A	226.840	1,702.840
L18-B	226.780	1,702.880
L18-C	226.650	1,702.180
L18-D	226.780	1,702.880
L18-E	226.880	1,702.870
L18-F	226.880	1,701.840
L18-G	227.850	1,701.810
L18-H	226.080	1,702.080
L18-I	226.080	1,702.410
L18-J	226.840	1,701.888
L18-K	226.880	1,701.772
K-1	226.808	1,702.888
K-2	226.853	1,701.788
K-3	226.887	1,702.882
K-18	226.888	1,702.882
K-18	227.188	1,701.880
K-18	226.782	1,702.724
K-21	227.457	1,702.822
K-22	227.818	1,702.787
K-28	227.248	1,702.628
K-28	226.070	1,702.207
K-27	226.828	1,702.882
K-28	226.828	1,702.881
K-28	226.081	1,702.888
K-22	226.018	1,702.812
K-28	227.388	1,702.080
K-28	226.888	1,701.010
K-28	226.812	1,701.781

**TABLE 2**

STRATIGRAPHIC UNIT	DESCRIPTION
18-1	SS, SILTY SS, OCCASIONAL SLT
18-2	CS, OCCASIONAL SS
18-3	SS, SLT, MINKER CS
18-4	CS
18-5	SS, SLT, MINKER CS, INCLUDES
18-6	"W" POSSIBLE BED
18-7	SS, OCCASIONAL THIN SLT, CS
18-8	SS, SLT, SILTY SS, SANDY SLT, CS
18-9	CS
18-9	SS, SILTY SS, SLT, SANDY SLT
18-10	SS, CS, SLT, SILTY SS, INCLUDES
18-10	"TRACHYCARINUS" FOSSIL BED
18-11	SS, MINKER CS
18-12	CS
18-13	SS, SILTY SS, MINKER CS

NOTE: MORE THAN ONE LITHOLOGIC UNIT DENOTES INTERFINGERING

- LEGEND**
- EXISTING MONITORING WELLS
  - BOREHOLES DRILLED FOR B-18 INVESTIGATION
  - SEWER TRENCH
  - TEST PIT
  - PROPOSED TEST PIT
  - EXPLORATORY TRENCH
  - APPROXIMATE STRATIGRAPHIC CONTACT
  - FACILITY BOUNDARY
  - LANDFILL BOUNDARY
  - PROPERTY BOUNDARY
  - THICKNESS OF COLLUVIUM (WHERE MEASURED IN ROAD CUTS, BORINGS, TRENCHES OR TEST PITS.)
  - STRIKE AND DIP OF BEDDING
  - STRIKE AND DIP OF JOINT
  - VERTICAL JOINT
  - CLAY BORROW STRATUM

0 100 200 FEET  
SCALE



**ATTACHMENT 1**

**FIGURE 3.1**


**SITE GEOLOGIC AND EXPLORATION MAP**


LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY


ENVIRONMENTAL SOLUTIONS, INC.




NOTE:  
 SETTLEMENT CALCULATION POINTS  
 BASED ON CHANGES IN GRADE AND/OR  
 GEOLOGIC CONTACTS (BASED ON E.S.I.,  
 1990) AS SHOWN ON FIGURE 3.1








PROJECT		WASTE MANAGEMENT, INC. LANDFILL UNIT B-18 KETTLEMAN HILLS FACILITY			
TITLE		SETTLEMENT CROSS-SECTION LOCATIONS (BASE GRADES)			
	PROJECT No.	FILE No.	SETTL SECTIONS		
	DESIGN KK 04/08	SCALE	REV. A		
	CADD FFG 10/08				
	CHECK EH 05/08				
	REVIEW SS 11/08				
			<b>DWG 1</b>		





PROJECT		WASTE MANAGEMENT, INC. LANDFILL UNIT B-18 KETTLEMAN HILLS FACILITY	
TITLE		SETTLEMENT CROSS-SECTION LOCATIONS (CLOSURE GRADES)	
	PROJECT No.	FILE No.	SETTL. SECTIONS
	DESIGN KK 04/14/08	SCALE AS SHOWN	REV. A
	CADD LAQ 04/18/08		
	CHECK REVIEW		
			<b>DWG 2</b>



### LEGEND

-  2008 DESIGN (FINAL CLOSURE)
-  1990 DESIGN (ESI)
-  EXISTING GROUND (MARCH 2008)
-  ASBUILT SUBGRADE
-  EXISTING SUBSURFACE GEOLOGY
-  SUBGRADE ANALYSIS POINT
-  COVER ANALYSIS STATION


PROJECT		WASTE MANAGEMENT, INC. LANDFILL UNIT B-18 KETTLEMAN HILLS FACILITY	
TITLE		SETTLEMENT CROSS-SECTION 1-1'	
	PROJECT No.	FILE No.	SETTL SECTIONS
	DESIGN KK 04/08	SCALE AS SHOWN	REV. A
	CADD FFG 04/08	<b>DWG 3</b>	
	CHECK EH 05/08		
REVIEW SS 11/08			



**LEGEND**

- 2008 DESIGN (FINAL CLOSURE)
- 1990 DESIGN (ESI)
- EXISTING GROUND (MARCH 2008)
- ASBUILT SUBGRADE
- EXISTING SUBSURFACE GEOLOGY
- SUBGRADE ANALYSIS POINT
- COVER ANALYSIS STATION


PROJECT		WASTE MANAGEMENT LANDFILL UNIT B-18 KETTLEMAN HILLS FACILITY	
TITLE		SETTLEMENT CROSS-SECTION 2-2'	
	DESIGN	KK	04/08
	CADD	FFG	04/08
	CHECK	EH	05/08
	REVIEW	SS	11/08
FILE No.		SETTL. SECTIONS	SCALE AS SHOWN REV. A
		<b>DWG 4</b>	










**LEGEND**


- 2008 DESIGN (FINAL CLOSURE)
- - - - - 1990 DESIGN (ESI)
- ..... EXISTING GROUND (MARCH 2008)
- ASBUILT SUBGRADE
- EXISTING SUBSURFACE GEOLOGY
- ⊕ B  
⊕ 2 SUBGRADE ANALYSIS POINT
- ⊕ 2 COVER ANALYSIS STATION

PROJECT		WASTE MANAGEMENT LANDFILL UNIT B-18 KETTLEMAN HILLS FACILITY	
TITLE		SETTLEMENT CROSS-SECTION 3-3'	
	PROJECT No.	FILE No.	SETTL SECTIONS
	DESIGN KK 04/08	SCALE AS SHOWN	REV. A
	CADD FFC 04/08	<b>DWG 5</b>	
	CHECK EH 05/08		
REVIEW SS 11/08			



### LEGEND

-  2008 DESIGN (FINAL CLOSURE)
-  1990 DESIGN (ESI)
-  EXISTING GROUND (MARCH 2008)
-  ASBUILT SUBGRADE
-  EXISTING SUBSURFACE GEOLOGY
-  SUBGRADE ANALYSIS POINT
-  COVER ANALYSIS STATION

PROJECT		WASTE MANAGEMENT LANDFILL UNIT B-18 KETTLEMAN HILLS FACILITY	
TITLE		SETTLEMENT CROSS-SECTION 4-4'	
	PROJECT No.	FILE No.	SETTL SECTIONS
	DESIGN KK 04/08	SCALE AS SHOWN	REV. A
	CADD FFG 04/08	<b>DWG 6</b>	
	CHECK EH 05/08		
REVIEW SS 11/08			

**APPENDIX G.2**  
**CLAY LINER RATE OF CONSOLIDATION**




# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/1/90 Subject CONSOLIDATION OF Sheet No. 1 of 6  
Chkd. By Jpi Date 8/15/90 BOTTOM CLAY LINER FOR Proj. No. 89-977  
KETTLEMAN HILL B-18 LANDFILL

OBJECTIVE : TO EVALUATE THE CONSOLIDATION CHARACTERISTIC OF BOTTOM CLAY LINER FOR STRENGTH EVALUATION

- REF : (1) LAMBE & WHITEMAN (1969) "SOIL MECHANICS" PUBLISHED BY JOHN WILEY & SONS, INC. P408-410
- (2) DEP. OF NAVY, NAVAL FACILITIES ENGINEERING COMMAND (1971) "DESIGN MANUAL, DM-7" MARCH

PHYSICAL PROPERTIES :



THICKNESS OF UPPER CLAY LINER : 1.5' + 0.2' (TOLERANCE)

LOWER CLAY LINER : 3.5' + 0.35' (TOLERANCE)

DRAINAGE PATH = ONE WAY DOWNWARD

CONSOLIDATION COEFFICIENT  $C_v$  = BASED ON CONSOLIDATION TESTS RESULTS ON TWO COMPACTED CLAY FROM KETTLEMAN HILL BORROW AREA (SEE FIGS 2 & 3)

BASED ON PRESENT INCOMING WASTE RATE OF 500,000 CY/YR  
FILL OPERATION PERIOD = 16 yrs to 19 yrs TO FULL HEIGHT  
FOR TOTAL VOLUME OF  $9.7 \times 10^6$  C.Y.


# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/1/90 Subject CONSOLIDATION OF BOTTOM Sheet No. 2 of       
 Chkd. By Tpi Date 8/15/90 CLAY LINER FOR KETTLEMAN Proj. No. 89-977  
HILL B-18 LANDFILL

FROM CONSOLIDATION TEST RESULTS  
 (SEE ATTACHED FIGS. 2 & 3)

$H = \text{LENGTH OF DRAIN PATH FOR SAMPLE} = \frac{1.0}{2} \text{ ft}$

SAMPLE No.	CONSOLIDATION PRESSURE (psf)	D <sub>o</sub> (IN)	D <sub>100</sub> (IN)	D <sub>50</sub> = $\frac{D_o + D_{100}}{2}$ (IN)	t <sub>50</sub> (MIN)	C <sub>v</sub> = $\frac{0.177 (H)^2}{t_{50}}$ IN <sup>2</sup> /MIN
DT-C, B-1 8'	8000	0.0036	0.0072	0.0054	5	0.00985
	16000	0.00	0.0240	0.0120	0.09	0.547
	32000	0.00	0.0442	0.0221	0.09	0.547
DT-A, B-2 5'	8000	0.0020	0.0076	0.0048	4	0.0123
	16000	0.0	0.0286	0.0143	0.7	0.0704
	32000	0.0	0.046	0.023	23	0.00214



# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/2/90 Subject CONSOLIDATION Sheet No. 3 of       
Chkd. By mpa Date 8/15/90 KETTLEMAN HILL B-18 LANDFILL Proj. No. 89-977

BASED ON THE TEST RESULTS, A CONSERVATIVE VALUE OF  $C_v = 0.0021$  IN<sup>2</sup>/MIN. IS USED FOR THE FOLLOWING CALCULATIONS.

## UPPER CLAY LINER

$$T_o = \frac{C_v t_o}{H^2} \quad \text{--- (REF 2)}$$

WHERE  $T_o$  = TIME FACTOR AT END OF CONSTRUCTION  
 $t_o$  = END OF LANDFILL OPERATION (USE 16 yrs)  
 $H$  = THICKNESS OF CLAY LAYER = 1.7'

$$T_o = \frac{0.0021 \times 16 \times (365 \times 24 \times 60)}{(1.7 \times 12)^2} = 42.3$$

DEGREE OF CONSOLIDATION  $U > 96\%$  — SEE REF(2), FIG. 6.6  
DURING AND AT END OF LANDFILL OPERATION (SEE ATTACHMENT)

## LOWER CLAY LINER

$$T_o = \frac{0.0021 \times 16 \times (365 \times 24 \times 60)}{(3.9 \times 12)^2} = 8.1$$

DEGREE OF CONSOLIDATION  $U = 96\%$  — SEE REF (2)  
DURING AND AT END OF LANDFILL OPERATION FIG. 6-6  
(SEE ATTACHMENT 1)

$T \approx 10$  when  $U = 100\%$

$$t = \frac{T H^2}{C_v} = \frac{10 \times (3.9 \times 12)^2}{0.0021} \times \frac{1}{365 \times 24 \times 60} = 19.8 \text{ yrs}$$

∴ THE LOWER LAYER OF CLAY LINER IS EXPECTED TO REACHED 100% CONSOLIDATION IN 3 YEARS AFTER THE FINAL FILL OPERATION.

# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/2/90 Subject CONSOLIDATION Sheet No. 4 of       
Chkd. By TPA Date 8/15/90 KETTLEMAN HILL Proj. No. 89-977  
E-18 LANDFILL

## CHECK CONSOLIDATION OF CLAY LINER BENEATH RISER

THE THICKEST CLAY LINER BENEATH THE RISER WILL BE  
5.0' + 0.35' (TOLERANCE) FOR THE LOWER CLAY LAYER.

$$T_0 = \frac{0.0021 \times 16 \times (365 \times 24 \times 60)}{(5.35 \times 12)^2}$$
$$= 4.28$$

SEE REF. (2) FIG. 6-6 (SEE ATTACHMENT 1)

THE LOWEST DEGREE OF CONSOLIDATION WOULD BE  
NEAR THE END OF LANDFILL OPERATION AND WOULD  
HAVE AT LEAST ABOUT 92% DEGREE OF  
CONSOLIDATION AND REACH 100% DEGREE CONSOLIDATION  
IN WITHIN A FEW YEARS

TIME TO REACH 100% CONSOLIDATION  $T = 6$  — Ref. (2)

$$t = \frac{TH^2}{C_v} = \frac{6 \times (5.35 \times 12)^2}{0.0021} \times \frac{1}{365 \times 24 \times 60}$$
$$= 22.3 \text{ yrs}$$

THAT IS (22.3 - 16) yrs = 6.3 yrs AFTER CONSTRUCTION

# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/2/90 Subject CONSOLIDATION Sheet No. 5 of       
Chkd. By tpa Date 8/15/90 KETTLEMAN HILL Proj. No. 89-977  
B-18 LANDFILL

## EVALUATE PHASE I LANDFILL OPERATION V.S. CONSOLIDATION

PHASE I OPERATION PERIOD ABOUT TWO YEARS

$$T_0 = \frac{0.0021 \times 2 \times (365 \times 24 \times 60)}{(5.35 \times 12)^2}$$
$$= 0.53$$

REF (2) FIG. 6-6

AT THE END OF LANDFILL OPERATION, THE DEGREE OF CONSOLIDATION WOULD BE APPROXIMATELY 55% FOR THE OVERALL THICKNESS OF CLAY

FOR  $U = 55\%$  REF (1) FIG. 27.3  
 $T \approx 0.25$

FOR  $T \approx 0.25$  REF (1) FIG 27.2  
 $Z = 1$

$U$  (AT HDPE/CLAY INTERFACE)  $\approx 30\%$  CONSOLIDATION AT INTERFACE

CONCLUSION:


- (1) CONSOLIDATION HAS REACHED ABOUT 96% FOR THE TWO CLAY LINERS AT THE BOTTOM OF THE LANDFILL WHEN THE FINAL LANDFILL OPERATION IS COMPLETED. THE DEGREE OF CONSOLIDATION IS FOUND TO BE AT LEAST 96% THROUGH OUT THE OPERATION PERIOD. BECAUSE THIS DEGREE OF CONSOLIDATION IS CLOSE TO THE 100% MARK, THE CLAYS ARE PRACTICALLY FULLY CONSOLIDATED AND THE CLAY STRENGTH COULD BE ESTIMATED FROM THE CONSOLIDATED UNDRAWN TRIAXIAL COMPRESSION RESULTS.

# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/2/90 Subject CONSOLIDATION Sheet No. 6 of       
Chkd. By JJA Date 8/15/90 Proj. No. 89-977

(2) BASED ON CONSOLIDATION EVALUATION FOR PHASE I FILL OPERATION, THE LOWEST DEGREE OF CONSOLIDATION AT THE INTERFACE OF THE CLAY LINER AND THE HDPE IS ABOUT 30% AT THE END OF PHASE I OPERATION. THEREFORE, THE STRENGTH OF THE CLAY LINER SHOULD BE ESTIMATED FROM THE UNCONSOLIDATED - UNDRAINED TRIAXIAL COMPRESSION TEST RESULTS FOR PHASE I STABILITY ANALYSIS. IT SHOULD ALSO BE REALIZED THAT THE STRENGTH FROM UU TEST OF AN UNSATURATED SAMPLE MAY BE HIGHER THAN THAT OF A SATURATED SAMPLE BECAUSE OF CAPILLARY ACTION. BASED ON THE UU TEST RESULTS, THE STRENGTH OF RECOMPACTED CLAY WAS REPORTED TO BE  $\phi = 8^\circ$  &  $C = 3600 \text{ psf}$ . IN CONSIDERATION OF THE SATURATED CONDITION, THE  $\phi$  WAS NOT INCLUDED IN THE STRENGTH PARAMETER IN ANALYZING THE STABILITY OF THE PHASE I LANDFILL.


272  
8-15-90



BASELINER

FIG. 1

7pi  
8-15-90




DT-C, B-1, 8'

FIG. 2


<p>WAHLER ASSOCIATES</p>	<p>Kettelman</p>	<p>CONSOLIDATION TEST TIME - COMPRESSION CURVES</p>		
		<p>PROJECT NO.</p> <p>ESK 101A</p>	<p>DATE</p> <p>7/90</p>	<p>FIGURE NO.</p>
<p>PALO ALTO • CALIF.</p>				



276  
8-15-90



DT-A, B-2, 5' FIG. 3



**FIGURE 6-6**  
Time Factors for Consolidation Analysis

ATTACHMENT 1




Fig. 27.3 Average consolidation ratio: linear initial excess pore pressure. (a) Graphical interpretation of average consolidation ratio. (b)  $U$  versus  $T$ .

value for  $c_v$ . This is generally done by observing the rate of compression of an undisturbed sample during an oedometer (or consolidation) test (see Sections 9.1 and 20.2).

Figure 27.4 shows a typical set of dial readings, showing change in thickness with time, obtained during one increment of load. The form of such actual time versus compression curves is similar to, but not exactly the same as, the theoretical curves predicted from consolidation theory. The following *fitting methods* are commonly used to determine  $c_v$  from such test results (Lambe, 1951).

**Square root method.** Extend a tangent to the straight-line portion of the observed curve back to intersect zero time and obtain the corrected zero point  $d_s$ . Through  $d_s$  draw a straight line having an inverse slope 1.15 times the tangent. Theoretically, this straight line should cut the observed compression-time curve at 90% compression. Thus the time to 90% compression is 12.3 minutes. From Fig. 27.3, the dimensionless time  $T$  for 90% compression is 0.848. Substituting these results, with  $H$  equal to the thickness of the sample per drainage surface (1.31 cm in this case) into Eq. 27.8b,  $c_v$  is determined to be  $26.2 \times 10^{-4}$  cm<sup>2</sup>/sec.

**Log method.** As shown in Fig. 27.4b, tangents are drawn to the two straight-line portions of the observed curve. The intersection of these curves defines the  $d_{100}$  point. The corrected zero point  $d_s$  is located by laying off above a point in the neighborhood of 0.1 minute a distance equal to the vertical distance between this point and one at a time which is four times greater. The 50% compression point is halfway between  $d_s$  and  $d_{100}$ , or at a time of 3.3 minutes. From the theoretical curve,  $T = 0.197$  for 50% compression. Using Eq. 27.8b,  $c_v$  is then computed at  $22.7 \times 10^{-4}$  cm<sup>2</sup>/sec.

**Discussion of results.** Obviously, these fitting methods contain arbitrary steps that compensate for differences

between actual and theoretical behavior. A correction for the initial point is usually required because of apparatus errors or the presence of a small amount of air in the specimen. An arbitrary determination of  $d_{90}$  or  $d_{100}$  is required because compression continues to occur even after excess pore pressures are dissipated. This *secondary compression* occurs because the mineral skeleton has time-dependent stress-strain properties (Chapter 20); the importance of secondary compression will be discussed in Section 27.7. The fitting methods have been developed to provide the best possible estimates for  $c_v$ . It is hardly surprising that the two methods yield somewhat different results. The square root method usually gives a larger value of  $c_v$  than does the log method, and this method is usually preferred.

In addition to the problems involved in evaluating  $c_v$  from a given increment,  $c_v$  varies from increment to increment and is different for loading and unloading. Figure 27.5 shows typical results. Moreover,  $c_v$  usually varies considerably among samples of the same soil.

Thus it is quite difficult to select a value of  $c_v$  for use in a particular engineering problem and hence it is difficult to predict accurately the rate of settlement or heave. Often the actual observed rate of settlement or heave of a structure is two to four times faster than the rate predicted on the basis of  $c_v$  as measured using undisturbed samples (e.g., see Bromwell and Lambe, 1968). Such differences arise partially because of the difficulties in measuring  $c_v$ , partially because of shortcomings in the linear theory of consolidation, and partially because of the two- and three-dimensional effects discussed in Section 27.6. Predictions of rate of consolidation are useful only to indicate in advance of construction the approximate time required for consolidation. If the actual rate of consolidation is critical to the design, as in certain stability problems where the excess

equation applicable to numerous physical problems. In particular, the equations for transient heat flow are basically identical to these equations for consolidation, with temperature replacing excess pore pressure. Solutions have been obtained for many problems in heat flow involving a variety of initial and boundary conditions, and these solutions often may be used to considerable advantage in the study of consolidation.

**27.2 SOLUTION FOR UNIFORM INITIAL EXCESS PORE PRESSURE**

The simplest case of consolidation is the one-dimensional problem in which: (a) the total stress is constant with time, so that  $\partial \sigma_v / \partial t = 0$ ; (b) the initial excess pore pressure is uniform with depth; and (c) there is drainage at both the top and bottom of the consolidating stratum. These conditions are met by the loading in Fig. 26.2 provided that the loading is applied in a time that is very small compared to the consolidation time so that literally no consolidation occurs before the loading is complete. The total vertical stress at any point will then be constant during the consolidation process.

For this problem, it is convenient to convert Eq. 27.4

by introducing nondimensional variables:

$$Z = \frac{z}{H} \tag{27.8a}$$

$$T = \frac{c_v t}{H^2} \tag{27.8b}$$

where  $z$  and  $Z$  are measured from the top of the consolidating stratum and  $H$  is one-half of the thickness of the consolidating stratum. (The reason for this choice of  $H$  will be apparent later.) The nondimensional time  $T$  is called the *time factor*. With these variables, Eq. 27.4 becomes

$$\frac{\partial^2 u_e}{\partial Z^2} = \frac{\partial u_e}{\partial T} \tag{27.9}$$

We now need a solution to Eq. 27.9 satisfying the following conditions:

Initial condition at  $t = 0$ :

$$u_e = u_0 \text{ for } 0 \leq Z \leq 2$$

Boundary condition at all  $t$ :

$$u_e = 0 \text{ for } Z = 0 \text{ and } Z = 2$$




Fig. 27.2 Consolidation ratio as function of depth and time factor: uniform initial excess pore pressure.

ATTACHMENT 3

**APPENDIX G.3**  
**CLAY LINER CONSOLIDATION SETTLEMENT**



Kettleman Hills Facility – Landfill Unit B-18 Expansion  
Settlement of Clay Liner

Project No.: 083-91887

Made By: EH

Date: 10/28/08

Checked By: RH

Sheet: 1 of 2

Reviewed By:

**Objective:**

Estimate the additional settlement due to the increased waste loads from the Phase III expansion.

**Reference:**

Environmental Solutions Inc. (ESI) Engineering Report Settlement Calculations (Attached).

**Discussion:**

ESI previously calculated the settlement of the clay liner due to placement of 230 feet of waste. The expansion project will increase the waste height to approximately 300 feet. This additional load will result in further compression of the clay.

**Calculation:**

1) Primary consolidation settlement

- The maximum load due to waste:  $\text{Max. } \sigma_v = 300' \times 115\text{pcf} = 34.5 \text{ ksf}$
- The consolidation settlement at 34.5 ksf is approximately 9.5% of the total thickness (see Figures 1 and 2).

Clay Liner	Primary	Secondary
Initial clay liner thickness	1.5'	3.5'
Consolidation settlement (9.5%)	0.14'	0.33'
Post Consolidation Thickness	1.36'	3.17'

2) Secondary consolidation settlement (or creep settlement)

Secondary consolidation settlement will occur after the closure of the landfill. The secondary settlement can be computed using the following equation:

$$\Delta_s = C_\alpha(H_t)\text{Log}(t_s/t_p)$$

$\Delta_s$  = secondary settlement (ft)

$C_\alpha$  = coefficient of secondary compression, 0.005 per ESI

$H_t$  = initial thickness

$t_s$  = duration of secondary compression assuming to be 30 years post closure period.

$t_p$  = time to complete primary consolidation conservatively assumed to be 20 years (1994-2014) to fill landfill.

Primary Clay Liner:  $\Delta_s = 0.005 (1.36) \text{Log}(30/20) = 0.0012 \text{ ft}$

Secondary Clay Liner:  $\Delta_s = 0.005 (3.17) \text{Log}(30/20) = 0.0028 \text{ ft}$

3) Final Clay Liner Thickness

Primary clay liner:  $1.5' - 0.14' - 0.0012' = 1.36' > 1.0' \text{ OK}$

Secondary liner:  $3.5' - 0.33' - 0.0028' > 3.0' \text{ OK}$

4) Settlement for clay liner beneath vertical riser



**Kettleman Hills Facility – Landfill Unit B-18 Expansion  
Settlement of Clay Liner**

Project No.: 083-91887

Made By: EH

Date: 10/28/08

Checked By: RH

Sheet: 2 of 2

Reviewed By: 

Settlement of the clay liner beneath the vertical riser is estimated to increase by an additional 5% due to riser imposed loads.

Thus, settlement of the clay below the riser will be  $9.5\% + 5.0\% = 14.5\%$  of the original thickness. Secondary compression is considered to be negligible based on previous calculation.

Settlement in the secondary clay liner =  $14.5\% \times 5' = 0.725'$

The final secondary clay liner thickness is estimated to be  $5' - 0.725' \cong 4.3' > 3'$  OK

Settlement in the primary clay liner =  $14.5\% \times 3' = 0.44'$

The final primary clay liner thickness is estimated to be  $3' - 0.44' \cong 2.5' > 1'$  OK

# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/8/90 Subject SETTLEMENT OF Sheet No. 1 of       
Chkd. By      Date 11/5/90 CLAY LINER Proj. No. 89-977

OBJECTIVE : TO ESTIMATE SETTLEMENT OF CLAY LINER FOR KETTLEMAN HILL B-18 LANDFILL BASE IN DETERMINING COMPLIANCE WITH MINIMUM THICKNESS (3') REQUIREMENT FOR BOTTOM CLAY L

REFERENCE : (1) LAMBE & WHITEMAN (1969) "SOIL MECHANICS" PUBLISHED BY JOHN WILEY & SONS, INC.

(2) DEPT. OF NAVY, NAVAL FACILITIES ENGINEERING COMMAND (1971) "DESIGN MANUAL, DM-7" MARCH.

DISCUSSION : TOTAL SETTLEMENT OF BASE CLAY LINER WILL INCLUDE PRIMARY AND SECONDARY SETTLEMENT. THE PRIMARY SETTLEMENT IS ASSOCIATED WITH THE CONSOLIDATION SETTLEMENT AND THE SECONDARY SETTLEMENT IS ASSOCIATED WITH THE CREEP MOVEMENT AFTER THE COMPLETION OF PRIMARY SETTLEMENT OR CONSOLIDATION.

$$\Delta_T = \Delta_p + \Delta_s$$

WHERE  $\Delta_T$  = TOTAL SETTLEMENT  
 $\Delta_p$  = PRIMARY SETTLEMENT DUE TO CONSOLIDATION  
 $\Delta_s$  = SECONDARY SETTLEMENT DUE TO CREEP AFTER  $\Delta_p$

MAX. FILL (OVERBURDEN PRESSURE) AT COMPLETION OF LANDFILL OPERATION IS ESTIMATED TO BE APPROXIMATELY 210 - FEET OF WASTE ABOVE THE LINER SYSTEM.

$$\text{Max. } \sigma_v = 230' \times 115 \text{ pcf} = 26450 \text{ psf or } 26.4 \text{ KSF}$$



# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/3/90 Subject SETTLEMENT OF Sheet No. 2 of       
 Chkd. By zpc Date 8/16/90 CLAY LINER Proj. No. 89-077

BASED ON CONSOLIDATION TEST RESULTS ON COMPACTED CLAY SAMPLES FROM CLAY BORROW MATERIAL AT THE SITE. FOR MAX.  $\sigma_v = 24.2$  KSF. THE CONSOLIDATION SETTLEMENT IS ESTIMATED TO BE APPROXIMATELY 7% OF THE TOTAL THICKNESS OF CLAY CONCERNED. (SEE ATTACHED FIGS. 1 & 2)

	PRIMARY	SECONDARY
INITIAL CLAY LINER THICKNESS	1.5'	3.5'
CONSOLIDATION SETTLEMENT $\Delta_p$	1.5' x 0.07 = 0.105' = 1.26"	3.5' x 0.07 = 0.245' = 2.94"

HOWEVER, BASED ON THE CALCULATION ON CONSOLIDATION CHARACTERISTIC OF CLAY LINER FOR B-18 LANDFILL, IT WAS FOUND THAT AT LEAST 96% OF THE CONSOLIDATION WILL BE COMPLETED AT THE END OF THE FINAL LANDFILL OPERATION THEREFORE, SETTLEMENT AFTER THE FINAL LANDFILL CLOSURE WILL BE MAINLY FROM THE SECONDARY SETTLEMENT OR CREEP SETTLEMENT. THE SECONDARY SETTLEMENT CAN BE COMPUTED USING THE FOLLOWING EQUATION:

$$\Delta_s = C_\alpha (H_c) \log \frac{t_{sec}}{t_p} \quad (\text{REF 2})$$

WHERE  $\Delta_s$  = SETTLEMENT FROM SECONDARY COMPRES  
 $C_\alpha$  = COEFFICIENT OF SECONDARY COMPRESSION  
 $H_c$  = INITIAL THICKNESS OF COMPRESSIBLE STRATUM  
 $t_{sec}$  = USEFUL LIFE OF STRUCTURE.  
 $t_p$  = TIME TO COMPLETION OF PRIMARY CONSOLIDATION

# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/3/90 Subject SETTLEMENT OF Sheet No. 3 of       
 Chkd. By [Signature] Date 8/3/90 CLAY LINER Proj. No.     

REF. 2 FIGURE 3.5 (SEE ATTACHMENT 1)  
 FOR COMPLETELY REMOLDED SAMPLES USING  $w\% \approx 28\%$  (Fig. 1.82)  
 $C_{\alpha} = 0.003$  TO  $0.005$

BASED ON LAB RESULTS FROM LOG. TIME CURVE OF THE CONSOLIDATION TEST,  
 (SEE FIGS. 3 & 4)

$C_{\alpha} = 0.0015$  TO  $0.006$  FOR APPROPRIATE PRESSURES

USE  $C_{\alpha} = 0.005$  FOR ESTIMATE

BASED ON CALCULATION OF CONSOLIDATION BEHAVIOR OF  
 CLAY LINER, THE CONSOLIDATION SETTLEMENT OF CLAY LINER  
 GENERALLY COMPLETE AT ABOUT 2 TO 3 YEARS AFTER  
 THE FINAL LANDFILL CLOSURE. THEREFORE SECONDARY  
 SETTLEMENT COMMENCE AFTER THAT. THE SETTLEMENT  
 DURING THE POST-CLOSURE PERIOD =

### SECONDARY SETTLEMENT FOR CLAY LINER AT LANDFILL BOTTOM

PRIMARY CLAY LINER (REDUNDANT) $= 0.005 (1.5 - 0.105) \log \frac{30}{18}$ $= 0.0015'$	SECONDARY CLAY LINER $= 0.005 (3.5 - 0.245) \log \frac{30}{18}$ $= 0.0036'$
FINAL THICKNESS FOR: PRIMARY CLAY LINER (REDUNDANT) $= 1.5 - 0.105 - 0.0015$ $= 1.39'$	SECONDARY CLAY LINER $= 3.5 - 0.245 - 0.0036$ $= 3.25'$

\* CHECK SETTLEMENT FOR CLAY LINER BENEATH VERTICAL RISER  
 REF. RISER BEARING CAPACITY COMPUTATION, PAGE 3 OF 4

PRIMARY SETTLEMENT DUE TO RISER IMPOSED LOAD = 5% OF THICKNESS

	PRIMARY CLAY LINER	SECONDARY CLAY LINER
TOTAL PRIMARY SETTLEMENT	$(0.07 + 0.005) \times 3 = 0.225'$	$(0.07 + 0.005) \times 5 = 0.375'$
SECONDARY SETTLEMENT	$0.005 (3 - 0.225) \log \frac{30}{18} = 0.0031'$	$0.005 (5 - 0.375) \log \frac{30}{18} = 0.0051'$
TOTAL	$= 0.2281'$	$= 0.3801'$
FINAL THICKN	$(3 - 0.2281) = 2.77'$	$(5 - 0.3801) = 4.42'$

# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/8/90 Subject SETTLEMENT OF Sheet No. 4 of       
Chkd. By [Signature] Date 8/16/90 CLAY LINER Proj. No. 89-977

## CONCLUSION :

1. BASED ON THE ABOVE CALCULATIONS, AT THE LANDFILL BASE, THE TOTAL SETTLEMENT OF THE SECONDARY CLAY LINER AT THE BOTTOM OF THE LANDFILL :

$$\begin{aligned}\Delta_T &= \Delta_P + \Delta_s \\ &= 0.245 + 0.0036 \\ &= 0.25'\end{aligned}$$


THEREFORE, THE 3.5-FOOT CLAY LAYER BENEATH THE LEACHATE COLLECTION SYSTEM WILL MAINTAIN A MINIMUM THICKNESS REQUIREMENT OF 3-FOOT DURING THE POST-CLOSURE PERIOD.

2. TOTAL SETTLEMENT AT THE VERTICAL RISER BASE FOR THE SECONDARY CLAY LINER IS COMPUTED IN THE FOLLOWING :

$$\begin{aligned}\Delta_T &= \Delta_P + \Delta_s \\ &= 0.375 + 0.0051' \\ &= 0.38'\end{aligned}$$

THEREFOR, THE 5-FOOT SECONDARY LCRS CLAY LINER WILL MAINTAIN ITS THICKNESS OF NO. LESS THAN 3-FOOT FOR THE PERMIUM.

Upi 8-16-90



BORING : DT-C, B-1                      DESCRIPTION : silty CLAYSTONE, yellow brn (CH)  
 DEPTH (ft) : 8                              LIQUID LIMIT : 76  
 SPEC. GRAVITY : 2.79                      PLASTIC LIMIT : 45

	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	28.1	89.4	83	.949
FINAL	30.5	94.1	100	.852

Remark : July 1990

FIG. 1

Project ESK-101A


Kettleman

Wahler Associates

CONSOLIDATION TEST

Figure No.

071 8-16-90



BORING : DT-A, B-2                      DESCRIPTION : silty CLAYSTONE, yellow brn (CH)  
 DEPTH (ft) : 5                              LIQUID LIMIT : 82  
 SPEC. GRAVITY : 2.84                      PLASTIC LIMIT : 54


	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	27.3	93.1	86	.906
FINAL	29.9	95.9	100	.851

Remark : July 1990

FIG. 2

Project ESK-101A	Kettleman
Wahler Associates	CONSOLIDATION TEST                      Figure No.

mi 8-1690



DT-C, B-1, 8'

FIG. 3

WAHLER ASSOCIATES

Kettlerman

PALO ALTO • CALIF.

CONSOLIDATION TEST  
TIME - COMPRESSION CURVES

PROJECT NO.


ESK 101A

DATE

7/90

FIGURE NO.

VPC - 8-16-90



DT. A, B-2, 5'

FIG. 4




Kettleman

PALO ALTO • [REDACTED] • CALIF.

CONSOLIDATION TEST  
TIME - COMPRESSION CURVES

PROJECT NO.	DATE	FIGURE NO.
ESK 101A	7/90	



**FIGURE 3.5**  
 Approximate Correlations for Consolidation Characteristics of Silts and Clays

7-3-14

Ref : NAVFAC, DM-7

(Handwritten notes)



**APPENDIX G.4**  
**POST-CLOSURE WASTE SETTLEMENT**



**Kettleman Hills Facility – Landfill Unit B-18  
POST-CLOSURE WASTE SETTLEMENT**

Project No.: 083-91887

Made By: LAQ

Date: 05-28-2008

Checked By: EH

Sheet: 1 of 1

Reviewed By:

**Objective:**

1. To estimate the effects of secondary settlement of the waste fill on the landfill cover post-closure grade for drainage.
2. Utilize Environmental Solutions Inc. (ESI) original calculation methods and assumptions and apply them to the new expansion configuration.

**Given:**

For the new landfill expansion geometry and as-built landfill configuration used to generate the evaluated sections where obtained from AutoCAD drawings (see Drawings 1 through 6 in Appendix G-1). All other data used for these calculations are based on the original Environmental Solutions Inc. (ESI) calculation, including site geology and foundation stratigraphy (see Attachment 1).

**Assumptions and Methods:**

All assumptions and methods utilized on this calculation are based on the ESI original calculation dated August 14, 1990. ESI calculations are included in Attachment 1.

**Calculations and Results:**

Calculation methods are described on ESI original calculation dated August 14, 1990. Calculations are shown in Attachment 1. Results for the new calculations are attached in Table 1 to 4. The calculations indicate the post-closure settlement will be approximately 9.3% of the waste thickness.

**Conclusions:**

As stated by ESI in their original calculation; "Based on the final cover post-closure settlement calculations for the selected sections, the results indicate that the changes of the grade after settlement will have no adverse effect on the surface drainage. After settlement, the gradients are still more than 3% which is the minimum requirement for drainage." Based on a review of ESI's calculations, Golder agrees with their original conclusions. In some cases shown in Table 3 the apparent gradient is less than 3%. The locations resulting in a value less than the required 3% are due to the location of the selected section not being nearly perpendicular to the new cover drainage slope. By observation and comparison with Section 2-2', these locations maintain a minimum 3% true slope.

As stated by ESI in their original calculation, "Due to the geometry of the final cover it is expected that the length of the slopes in the soil cover and liner systems will be reduced due to settlement. A minimal reduction strain is expected and should be readily absorbed by the soil cover and the liner systems without causing any damage".

**Reference:**

Environmental Solutions Inc. "Engineering and Design report Landfill Unit B-18 Phase 1, 2 and Final Closure, Kettleman Hills Facility". August 1990. Appendix G.4

**Table 1**  
**Post-Closure Waste Settlement**  
**Section 1-1'**

**Assumptions:**

Containers in waste:	0.15 %
Containers Voids:	0.10 %
$H_{waste}$ :	280 ft
$\gamma_{waste}$ :	115 pcf
$E_{waste}$ :	40,000 psf
$C_{cc}$ :	0.02
$W_{waste}$ :	14,500,000 $cy^3$
Incoming Waste:	550,000 $cy^3/yr$
Stages:	5
Post-Closure period:	30 yr

$$S_T = S_C + S_V + S_P + S_S$$

$S_C$	0.0%
$S_V$	1.5%
$S_P$	6.0%
$S_S$	1.7%
$S_T$	9.3%
$T$	27 yr
$t$	5.40 yr

$S_{b1}$  40%

Stage	$t_1$ (yr)	$t_2$ (yr)	$\log t_1/t_2$	$C_{cc}$	$\delta H$
1	5.4	51.6	0.98	0.02	0.0039 H
2	5.4	46.2	0.93	0.02	0.0037 H
3	5.4	40.8	0.88	0.02	0.0035 H
4	5.4	35.4	0.82	0.02	0.0033 H
5	5.4	30.0	0.74	0.02	0.0030 H

$\Delta\sigma$  0.0174 H

**Final Grade Calculation**

Station	Finish Elevation (ft)	Waste Thickness (ft)	$\Delta H$ 0.093H (ft)	Final Elevation (ft)	Distance (ft)	Initial Grade (%)	Final Grade (%)
1	806.18	0	0.00	806.18	375.43	24.6%	20.4%
2	898.62	171.15	15.88	882.74	419.64	23.5%	21.4%
3	997.29	268.59	24.92	972.37	49.85	19.2%	19.3%
4	1006.88	268.29	24.89	981.99	49.85	20.9%	20.6%
5	996.47	266.67	24.74	971.73	212.15	21.5%	15.9%
6	950.83	137.61	12.77	938.06	240.09	21.9%	16.6%
7	898.32	0	0.00	898.32			

Note: See Drawing 1 and 2 in Appendix G-1 for Section location and Drawing 3 for Cross Section profile.



**Table 3**  
**Post-Closure Waste Settlement**  
**Section 3-3'**

Assumptions:

Containers in waste:	0.15 %
Containers Voids:	0.10 %
$H_{waste}$ :	280 ft
$\gamma_{waste}$ :	115 pcf
$E_{waste}$ :	40,000 psf
$C_{cr}$ :	0.02
$W_{waste}$ :	14,500,000 cy <sup>3</sup>
Incoming Waste:	550,000 cy <sup>3</sup> /yr
Stages:	5
Post-Closure period:	30 yr

$$S_T = S_C + S_V + S_D + S_S$$

$S_C$	0.0%
$S_V$	1.5%
$S_D$	6.0%
$S_S$	1.7%
$S_T$	9.3%
$T$	27 yr
$t$	5.40 yr

$$S_{b1} = 40.3\%$$

Stage	$t_1$ (yr)	$t_2$ (yr)	$\log t_1/t_2$	$C_u$	$\delta H$
1	5.4	51.6	0.98	0.02	0.0039 H
2	5.4	46.2	0.93	0.02	0.0037 H
3	5.4	40.8	0.88	0.02	0.0035 H
4	5.4	35.4	0.82	0.02	0.0033 H
5	5.4	30.0	0.74	0.02	0.0030 H
				$\Delta\sigma$	0.0174 H

Final Grade Calculation

Station	Finish Elevation (ft)	Waste Thickness (ft)	$\Delta H$ 0.093H (ft)	Final Elevation (ft)	Distance (ft)	Initial Grade (%)	Final Grade (%)
1	890.51	0	0.00	890.51	252.19	23.7%	17.4%
2	950.18	169.36	15.71	934.47	252.17	19.8%	16.1%
3	1000.00	268.31	24.89	975.11	227.75	6.3%	5.9%
4	1014.46	278.29	25.82	988.64	181.73	crossing ridge of top deck	
5	1012.84	285.82	26.52	986.32	341.58	crossing ridge of top deck	
6	1007.53	273.53	25.38	982.15	146.71	crossing ridge of top deck	
7	1006.62	279.34	25.92	980.70	364.03	22.8%	20.4%
8	923.48	185.27	17.19	906.29	301.74	24.4%	18.7%
9	850	0	0.00	850.00			

Notes: See Drawing 1 and 2 in Appendix G-1 for Section location and Drawing 5 for Cross Section profile.

Points 4, 5 and 6 currently cross the ridge line of the top deck and therefore do not reflect true slope. Section 2-2' provides points across the top deck that are along true slope.

**Table 4**  
**Post-Closure Waste Settlement**  
**Section 4-4'**

Assumptions:

Containers in waste:	0.15 %
Containers Voids:	0.10 %
H <sub>waste</sub> :	280 ft
γ <sub>waste</sub> :	115 pcf
E <sub>waste</sub> :	40,000 psf
C <sub>cc</sub> :	0.02
W <sub>waste</sub> :	14,500,000 cy <sup>3</sup>
Incoming Waste:	550,000 cy <sup>3</sup> /yr
Stages:	5
Post-Closure period:	30 yr

$$S_T = S_C + S_V + S_D + S_S$$

S <sub>C</sub>	0.0%
S <sub>V</sub>	1.5%
S <sub>D</sub>	6.0%
S <sub>S</sub>	1.7%
S <sub>T</sub>	9.3%
T	27 yr
t	5.40 yr

S<sub>D1</sub> 40.3%

Stage	t <sub>1</sub> (yr)	t <sub>2</sub> (yr)	log t <sub>1</sub> /t <sub>2</sub>	C <sub>cc</sub>	δH
1	5.4	51.6	0.98	0.02	0.0039 H
2	5.4	46.2	0.93	0.02	0.0037 H
3	5.4	40.8	0.88	0.02	0.0035 H
4	5.4	35.4	0.82	0.02	0.0033 H
5	5.4	30.0	0.74	0.02	0.0030 H

Δσ 0.0174 H

Final Grade Calculation

Station	Finish Elevation (ft)	Waste Thickness (ft)	ΔH 0.093H (ft)	Final Elevation (ft)	Distance (ft)	Initial Grade (%)	Final Grade (%)
1	848.28	0.00	0.00	848.28	193.06	24.2%	17.9%
2	895.07	131.82	12.23	882.84	271.02	24.2%	20.4%
3	960.64	243.47	22.59	938.05	148.6	7.6%	6.9%
4	971.89	254.54	23.62	948.27	114.97	11.7%	10.3%
5	958.46	237.72	22.06	936.40	310.89	24.3%	22.2%
6	882.96	168.21	15.61	867.35	346.76	24.0%	19.5%
7	799.63	0.00	0.00	799.63			

See Drawing 1 and 2 in Appendix G-1 for Section location and Drawing 6 for Cross Section profile.

Attachment 1

ESI Settlement Calculations

# ENVIRONMENTAL SOLUTIONS, INC.

By N.A. Date 8-10-90 Subject LANDFILL B-18 FINAL Sheet No. \_\_\_\_\_ of \_\_\_\_\_

Chkd. By GSC Date 8/14/90 COVER POST-CLOSURE SETTLEMENT Proj. No. 89-977

## TABLE OF CONTENTS

Purpose and References	1
Total settlement of Landfill	2
Post closure Grade Evaluation for Sections 1, 2, 3 & 4	9
Conclusion	14
Attachment	
A. Drawings showing plan and sections for post-closure settlement analysis	



# ENVIRONMENTAL SOLUTIONS, INC.

By VJ/NA/KSC Date 7-12-90 Subject LANDFILL B-18 FINAL COVER Sheet No. 1 of 14

Chkd. By GSC Date 8/14/90 POST-CLOSURE GRADE EVALUATION Proj. No. 89-977

PURPOSE : TO EVALUATE THE EFFECT OF SECONDARY SETTLEMENT OF THE WASTE FILL ON THE LANDFILL COVER POST-CLOSURE GRADE FOR DRAINAGE.

## REFERENCE :

1. SOIL MECHANICS, LAMBE & WHITTON (Figure 1)
2. NAVFAC DM 7-1, (Figure 2)
3. WASTE SETTLEMENT REPORT FOR FINAL LANDFILL COVER DESIGN, GOLDER ASSOCIATES INC., JULY 1989.
4. W.L. Murphy and P.A. Gilbert (1985)  
"Settlement and cover subsidence of Hazardous Waste Landfills"

# ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 8/10/90 Subject WASTE SETTLEMENT Sheet No. 2 of 14  
Chkd. By \_\_\_\_\_ Date \_\_\_\_\_ KETTLEMAN HILL, B-18 Proj. No. 89-977  
LANDFILL

Objective : To evaluate the waste settlement behavior and parameters for waste settlement analysis. The results of the waste settlement analysis will be used to determine the influence of final grade of the final cover after closure of the landfill.

REF : (1) W.L. Murphy and P.A. Gilbert (1985) "Settlement and Cover Subsidence of Hazardous Waste Landfills"

DISCUSSION : TOTAL SETTLEMENT OF LANDFILL

$$S_T = S_c + S_v + S_d + S_s$$

WHERE  $S_c$  = CONSOLIDATION SETTLEMENT OF BULK WASTE

$S_v$  = SETTLEMENT DUE TO COLLAPSE OF VOIDS INSIDE WASTE CONTAINERS

$S_d$  = SETTLEMENT DUE TO CONTAINER WASTES AFTER CONTAINERS CORRODED AND COLLAPSE

$S_s$  = SECONDARY SETTLEMENT OF WASTE DUE TO CREEP.

IT IS EXPECTED THAT THE CONSOLIDATION SETTLEMENT WILL BE ESSENTIALLY COMPLETE BEFORE THE FINAL CLOSURE. THEREFORE THE CONSOLIDATION SETTLEMENT IS NOT NECESSARY TO BE INCLUDED IN THIS EVALUATION WHICH WILL BE USED TO DETERMINE THE FINAL COVER INFLUENCE. THE FOLLOWING EVALUATION WILL ONLY INCLUDE THE DETERMINATION OF  $S_v$  &  $S_d$ .  $S_c$  WAS DETERMINED PREVIOUSLY (SEE ATTACHMENT) USING THE CORRELATION OF  $C_u$  V.S. WATER CONTENT OF

# ENVIRONMENTAL SOLUTIONS, INC.

By G. Chou Date 8/10/90 Subject Waste Settlement Sheet No. 3 of 14  
Chkd. By \_\_\_\_\_ Date \_\_\_\_\_ Kettleman Hill, B-18 Landfill Proj. No. 89-977

NORMALLY CONSOLIDATED CLAY.

ASSUMPTION: (1) BASED ON CHEM. WASTE OFFICIALS, THE AMOUNT OF CONTAINERIZED WASTE CONTAINED IN THE B-18 LANDFILL IS EXPECTED TO BE APPROXIMATELY 15%.

(2) THE % OF VOIDS IN THE CONTAINER IS EXPECTED TO HAVE AT MOST 10% OF THE CONTAINER VOLUME.

(3) ASSUME THE DRUM CONTAINER WILL BE EVENLY DISTRIBUTED IN THE LANDFILL DURING THE LIFE OF THE LANDFILL OPERATION.

(4) ASSUME ALL CONTAINER WILL BE INTACTED DURING THE PERIOD OF LANDFILL OPERATION. THEREFORE ALL SETTLEMENT CAUSED BY DRUM WASTE WILL OCCUR AFTER CLOSURE AND WILL DIRECTLY AFFECT THE FINAL COVER.

CALCULATION:

$$\begin{aligned} * S_v & \text{ (collapse of containers voids)} \\ & = 0.10 \times 0.15 \\ & = 0.015 \quad \text{or } 1.5\% \text{ OF THE TOTAL WASTE HEIGHT} \end{aligned}$$

$$\begin{aligned} * S_d & \text{ (settlement of waste inside drums)} \\ & \text{BECAUSE THE WASTE DRUM ARE EVENLY DISTRIBUTED,} \\ & \text{THE AVERAGE STRESS TO THE WASTE INSIDE THE} \\ & \text{DRUMS AFTER THE DRUMS CORRODED IS} \\ & 115 \text{ pcf} \times 210 \left(\frac{1}{2}\right) \text{ WHERE } 210' \text{ IS THE TOTAL} \\ & \text{EXPECTED HEIGHT OF WASTE} \end{aligned}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By G. CHOW Date 8/10/90 Subject Waste settlement Sheet No. 4 of 14  
Chkd. By \_\_\_\_\_ Date \_\_\_\_\_ Kettleman Hill, B-18 Landfill Proj. No. 89-977

$$S_D = 115 \times \frac{210}{2} \times \frac{1}{E}$$

WHERE  $E = 49,000 \text{ psf}$  (REF. 1)

$$S_D = \frac{115 \times 105}{49,000} = 0.30 \text{ or } 30\% \text{ OF THE DRUM WASTE}$$

SINCE THE DRUM WASTE IS ONLY 15% OF THE WASTE

$$S_D = 0.30 \times 0.15 = 0.045 \text{ or } 4.5\% \text{ OF THE TOTAL WASTE HEIGHT}$$

\*  $S_s = 0.02$  or 2% OF THE TOTAL WASTE HEIGHT  
(See page 5 & 6)

TOTAL SETTLEMENT AFTER CLOSURE

$$S_T = 0.015 + 0.045 + 0.02$$

$$= 0.075 \text{ or } 7.5\% \text{ OF THE TOTAL HEIGHT}$$

CONCLUSION:

USE 7.5% OF THE TOTAL HEIGHT TO CALCULATE SETTLEMENT AFTER CLOSURE.

# ENVIRONMENTAL SOLUTIONS, INC.

By vpi Date 7-17-90 Subject LANDFILL B7B FINAL Sheet No. 5 of 14  
Chkd. By GSC Date 8/14/90 COVER POST-CLOSURE GRADE EVALUATION Proj. No. 89-977

SETTLEMENT CHARACTERISTICS OF THE WASTE FILL IS SIMILAR TO  
THE BEHAVIOR OF NORMALLY CONSOLIDATED CLAY.

THE SECONDARY SETTLEMENT MAY BE ESTIMATED BY  
THE FOLLOWING EQUATION

$$\Delta_s = C_\alpha H \log \frac{t_2}{t_1}$$

WHERE

$C_\alpha$  = RATE OF SECONDARY COMPRESSION

$H$  = THICKNESS OF THE SOIL LAYER

$t_2$  = FINAL TIME

$t_1$  = INITIAL TIME (time when primary consolidation completes)

TYPICAL VALUES OF  $C_\alpha$  FOR NORMALLY CONSOLIDATED CLAY  
VARY FROM 0.005 TO 0.02. Ref. 1 (see fig. 1) BY ASSUMING THE NATURAL  
MOISTURE CONTENT OF THE WASTE FILL RANGES FROM 30 TO  
40 %, THE VALUE OF  $C_\alpha$  IS ESTIMATED TO BE ABOUT  
0.003 TO 0.004. Ref. 2 (see fig. 2) TO BE CONSERVATIVE, A CONSTANT  
VALUE OF 0.02 WILL BE USED.

# ENVIRONMENTAL SOLUTIONS, INC.

By opi Date 7-17-90 Subject LANDFILL B-18 FINAL COVER Sheet No. 6 of 14  
 Chkd. By GSC Date 8/14/90 POST-CLOSURE GRADE EVALUATION Proj. No. 89-977

## ESTIMATE OF SECONDARY CONSOLIDATION OF WASTE FILL

TOTAL VOLUME OF B-18  $\approx 9.5 \times 10^6$  cy

ASSUME INCOMING WASTE IS ABOUT 500,000 cy/YEAR.

$\therefore$  OPERATIONAL LIFE OF B-18

$$T = \frac{9.5 \times 10^6}{500,000} = 19 \text{ YEARS}$$

DIVIDE THE FULL OPERATIONAL LIFE OF THE LANDFILL INTO

5 STAGES, THE OPERATIONAL LIFE FOR EACH STAGE

$t = \frac{19}{5} = 3.8$  YEARS Assuming primary consolidation completed at the end of each stage

FOR A TYPICAL 30-YEAR POST-CLOSURE PERIOD, THE

THE SECONDARY SETTLEMENT OF EACH STAGE

STAGE	FINAL TIME	$\log t/t_c$	$C_\alpha$	$S = \frac{H}{L} c_\alpha \log t/t_c$
1	45.2	$\log 45.2/3.8$	0.02	0.0043
2	41.4	$\log 41.4/3.8$	0.02	0.0041
3	37.6	$\log 37.6/3.8$	0.02	0.0040
4	33.8	$\log 33.8/3.8$	0.02	0.0038
5	30	$\log 30/3.8$	0.02	0.0036

$$\Delta_s = 0.0198H \approx 2\%$$

Figure 1

7/14

$\frac{C_c}{C_c} \text{ large when } \frac{\Delta P}{P_0}$




Fig. 27.14 Primary and secondary compression.

skeleton. The relative importance of primary and secondary compression depend on the time required to dissipate pore pressures and hence on the thickness of the soil.

The relative importance of secondary and primary compression varies with the type of soil and also with the ratio of stress increment to initial stress.

The magnitude of secondary compression is often expressed by the slope  $C_\alpha$  of the final portion of the time compression curve on semi-log paper (Fig. 27.17). Table 27.2 gives typical values for this slope  $C_\alpha$ . The




Fig. 27.15  $e$  versus  $\log \bar{\sigma}_v$  as function of duration of secondary compression (After Bjerrum, 1967).

time rate of secondary compression is largest for highly plastic soils and especially for organic soils.

The ratio of secondary to primary compression is largest when the ratio of stress increment to initial stress is small. This is illustrated in Fig. 27.18, which shows that the usual form of time-compression curve occurs only when the stress increment is large. Fortunately, most problems involving important settlements involve relatively large increments of stress.

Taylor (1942) was the first person to propose a rational theory of secondary compression. This theory modeled the soil skeleton as a viscoelastic material. Recent work in this area is directed at the developing models of behavior and numerical techniques for solving secondary compression problems with complicated rheologic models.

The phenomenon of secondary compression greatly complicates prediction of the time history and final magnitude of settlement. Bjerrum (1967) has discussed this subject. Secondary compression also makes it difficult to determine  $c_\alpha$  accurately from laboratory tests.

27.8 SUMMARY OF MAIN POINTS

1. The differential equation of continuity, which is the basis for the study of consolidation, equates the net flow to the change in volume of the soil.

Table 27.2 Typical Values for Rate of Secondary Compression  $C_\alpha$

	$C_\alpha$
Normally consolidated clays	0.005 to 0.02
Very plastic soils; organic soils	0.03 or higher
Precompressed clays with OCR > 2	less than 0.001

From Ladd, 1967.




Fig. 27.16 Relation of instantaneous and delayed compression to primary and secondary compression. (a) For different thicknesses. (b) For a given thickness.

Ref: Soil Mechanics Lamb & Whitman




FIGURE 16  
Coefficient of Secondary Compression as Related to  
Natural Water Content

Ref: NAVFAC DM 7-1



# ENVIRONMENTAL SOLUTIONS, INC.

By JPI Date 7-16-90 Subject LANDFILL B-13 FINAL COVER Sheet No. 9 of 14  
 Chkd. By GSC Date 8/14/90 POST-CLOSURE GRADE EVALUATION Proj. No. 89-977

THE FINAL GRADE ON THE LANDFILL COVER BETWEEN ANY TWO POINTS MAY BE CALCULATED AS FOLLOWS:

$$G_f = \frac{(EL_2 - \Delta H_2) - (EL_1 - \Delta H_1)}{(\Delta X_2 - \Delta X_1)}$$

WHERE

EL<sub>2</sub> = ELEVATION AT POINT 2


EL<sub>1</sub> = ELEVATION AT POINT 1

ΔH<sub>2</sub> = SETTLEMENT AT POINT 2

ΔH<sub>1</sub> = SETTLEMENT AT POINT 1

(ΔX<sub>2</sub> - ΔX<sub>1</sub>) = DISTANCE BETWEEN 2 POINTS

Total settlement after closure = 0.075 of the Total Ht.







# ENVIRONMENTAL SOLUTIONS, INC.

By N.A. Date 8-10-90 Subject LANDFILL B-18 FINAL COVER Sheet No. 12 of 14  
 Chkd. By GSC Date 8/14/90 POST-CLOSURE GRADE EVALUATION Proj. No. 89-977  
SECTION 3

STATION	ELEVATION (FT)	WASTE THICKNESS (FT)	ΔH 0.075 H (FT)	FINAL ELEVATION (FT)	DISTANCE (FT)	FINAL GRADE %
1	830	0	0	830	85	18.7
2	850	55	4.13	845.87	165	20.15
3	890	145	10.88	879.12	470	3.8
4	910	175	13.13	896.87	450	6.1
5	940	210	15.75	924.25	220	8.5
6	920	192	14.4	905.6	205	0*
7	920	190	14.25	905.75	285	19.8
8	850	10	0.75	849.25	15	28.3
9	845	0	0	845		

\* Refer to Attachment A section on plan view, section not nearly perpendicular to the drain slope.

# ENVIRONMENTAL SOLUTIONS, INC.

By N.A. Date 8-10-90 Subject LANDFILL B-18 FINAL COVER Sheet No. 13 of 14

Chkd. By GSC Date 8/14/90 POST-CLOSURE GRADE EVALUATION Proj. No. 89-977  
SECTION 4

1						
2						
3						
4						
5	FINAL GRADE %	19.3	22.5	23.2	14.1	
6						
7						
8						
9	DISTANCE (FT)	175	440	440	275	
10						
11						
12						
13	FINAL ELEVATION (FT)	808	841.75	940.87	838.7	800
14						
15						
16						
17						
18						
19	ΔH 0.075 H (FT)	0	8.25	19.13	11.3	0
20						
21						
22						
23	WASTE THICKNESS (FT)	0	110	255	150	0
24						
25						
26						
27						
28						
29	ELEVATION (FT)	808	850	960	850	800
30						
31						
32						
33						
34	STATION	1	2	3	4	5
35						
36						

# ENVIRONMENTAL SOLUTIONS, INC.

By N.A. Date 8-10-90 Subject Conclusion Sheet No. 14 of 14  
Chkd. By ESC Date 8/14/90 Proj. No. 89-977

1  
2 Based on the final cover post-closure settlement  
3  
4 calculations for the four sections. The results indicate  
5  
6 change of grade after settlement will have no  
7  
8 adverse effect on surface drainage.  
9

10 After settlement the gradients are still more than  
11  
12 3%. which is the min. requirement for drainage.  
13

14 A summary for final cover Post-closure grade  
15  
16 evaluation is shown on pages 10-13 for sections 1-4  
17

18 Due to the geometry of the final cover, the length  
19  
20 of the slope will be reduced due to the settlement  
21  
22 and thus the liner. The reduce in strain is  
23  
24 expected to be small and will be readily  
25  
26 absorbed by the soil cover and the liner  
27  
28 without causing damage to the system.  
29  
30  
31  
32  
33  
34  
35  
36

**APPENDIX H  
STABILITY ANALYSES**

<b>APPENDIX H.1</b>	<b>GENERAL METHODOLOGY FOR ROCK CUTSLOPE, COMPACTED FILL SLOPE, AND INTERMEDIATE PHASE I CLOSURE STABILITY ANALYSES</b>
<b>APPENDIX H.2</b>	<b>ROCK CUTSLOPE STABILITY</b>
<b>APPENDIX H.3</b>	<b>COMPACTED FILL SLOPE STABILITY</b>
<b>APPENDIX H.4</b>	<b>INTERMEDIATE PHASE I CLOSURE AND INTERMEDIATE PHASE IIIA WASTE SLOPE STABILITY</b>
<b>APPENDIX H.5</b>	<b>FINAL CLOSURE STABILITY</b>

**APPENDIX H.1**  
**GENERAL METHODOLOGY FOR ROCK CUTSLOPE, COMPACTED**  
**FILL SLOPE, AND INTERMEDIATE PHASE I CLOSURE STABILITY**  
**ANALYSES**



# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject \_\_\_\_\_

Sheet No. 0 of 28

Chkd. By GSC Date 8/13/90 \_\_\_\_\_

Proj. No. 89-977

GENERAL

B-18 LANDFILL  
SLOPE STABILITY ANALYSIS

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B. Date 8/9/90 Subject B-18 LANDFILL Sheet No. 1 of 28  
Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## SLOPE STABILITY ANALYSIS

OBJECTIVE EVALUATE THE STATIC AND SEISMIC STABILITY OF THE SLOPES FOR THE FOLLOWING CASES:

- ROCK CUTS
- COMPACTED FILL EMBANKMENTS
- TEMPORARY PHASE I INTERMEDIATE WASTE FILL
- CLOSURE CONDITIONS

## REFERENCES

- 1- PERMANENT DISPLACEMENTS OF EARTH EMBANKMENTS BY NEWMARK SLIDING BLOCK ANALYSIS. FRAUHLIN AND CHANG, U.S. ARMY ENGINEERS WATERWAYS EXPERIMENT STATION, NOVEMBER 1977.
2. FIFTH RANKINE LECTURE, EFFECTS OF EARTHQUAKES ON DAMS AND EMBANKMENTS, N.M. NEWMARK, 1965
3. A PRACTITIONER'S VIEW OF SITE EFFECTS ON STRONG GROUND MOTION. NEVILLE DONOVAN. PROCEEDINGS OF CONFERENCE XXII. U.S. DEPARTMENT OF THE INTERIOR GEOLOGICAL SURVEY, SANTA FE NEW MEXICO, JULY 1983.
4. SEISMIC STABILITY EVALUATION FOR THE TOE BUTTRESS CONSTRUCTION, OPERATING INDUSTRIES, INC. SITE, MONTEDEY PARK, CALIFORNIA. DOCUMENT No 120-R12-RT-EPNN-1, PREPARED FOR U.S. EPA BY Woodward-Clyde Consultants

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 2 of 28  
Chkd. By GSC Date 8/15/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

5 EDENGINEERING REPORT, CHEMICAL WASTE MANAGEMENT,  
INC KETTLEMAN HILLS FACILITY, LANDFILL B-19, PHASES  
II AND III, DONOHUE & ASSOCIATES, OCTOBER 1983.

6 SLOPE STABILITY FAILURE INVESTIGATION, LANDFILL  
UNIT B-19, PHASE I-A, KETTLEMAN HILLS, CALIFORNIA,  
SEED R.B ET AL U.C.B, July 1988

7 OPERATIONS PLAN FOR LANDFILL UNIT B-19, CWM,  
KETTLEMAN HILLS FACILITY, REVISION 0, JUNE 26,  
1989.

8 FEASIBILITY STUDY FOR FINAL LANDFILL COVER SYSTEMS,  
KETTLEMAN HILLS FACILITY - DRAFT- GOLDER ASSOCIATES  
INC., AUGUST 1989

9 DIRECT SHEAR TESTING PROGRAM FOR LANDFILL  
COVER DESIGN KETTLEMAN HILLS FACILITY, GOLDER  
ASSOCIATES, JUNE 29, 1990

10 UPDATED EVALUATION OF SITE DESIGN GROUND  
MOTIONS FOR THE CWM KETTLEMAN HILLS FACILITY,  
GOLDER ASSOCIATES, SEPTEMBER 1988.

11 FILLING PLAN LANDFILL B-19, PHASES II AND III,  
KETTLEMAN HILLS FACILITY, GOLDER ASSOCIATES, MAY 1989.

12 SUPPORTING CALCULATIONS FOR THE LANDFILL B-15  
CLOSURE PLAN, KETTLEMAN HILLS FACILITY, GOLDER  
ASSOCIATES, DECEMBER 1989.

13 CLOSURE PLAN FOR LANDFILL B-16, KETTLEMAN  
HILLS FACILITY, KETTLEMAN CITY, CALIFORNIA,  
GOLDER ASSOCIATES, APRIL 23, 1990

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 3 of 28  
Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

- 1  
2 14 COMBINED CLOSURE PLAN FOR LANDFILLS B-1/4/5/6/7,  
3 B-8/9/9 EXPANSION / 9 EXTENSION / 10/11, SURFACE  
4 IMPOUNDMENTS P-5/12/12A/13/17 AND AREA S-3, REVISION  
5 2 - DRAFT - KETTLEHOLE HILLS FACILITY, GOLDBER  
6 ASSOCIATES JUNE 1988  
7
- 8 15 DIRECT SHEAR INTERFACE STRENGTH TESTING  
9 SELECTED GEOTEXTILE INTERFACES, Geoservices  
10 INC. CONSULTING ENGINEERS, APRIL 5 1990.  
11
- 12 16 GEOSYNTEC PROJECT G88-383, FINAL REPORT  
13 ON THE DIRECT SHEAR TESTING FOR THE WASTE  
14 MANAGEMENT, INC. NEW MILFORD, CONNECTICUT,  
15 LANDFILL, GEOSERVICES INC. CONSULTING  
16 ENGINEERS, OCTOBER 11, 1988  
17
- 18 17 FRICTION FLEY™ APPLICATION DATA, SLT  
19 NORTH AMERICA, INC  
20
- 21 18 DIRECT SHEAR TESTING OF FRICTION LIVER  
22 MATERIALS, GUNDEL LIVING SYSTEMS, INC,  
23 (SEVERAL SEPARATE REPORTS)  
24
- 25 19 TECHNICAL GUIDANCE DOCUMENT: FINAL COVERS  
26 ON HAZARDOUS WASTE LANDFILLS AND SURFACE  
27 IMPOUNDMENTS, EPA /530-SW-89-047 JULY  
28 1989.  
29
- 30 20 STABLES USER MANUAL - SCHOOL OF CIVIL  
31 ENGINEERING, INDIANA DEPARTMENT OF  
32 HIGHWAYS, RONALD A. SIEGEL, JUNE 4, 1975  
33  
34  
35  
36

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B. Date 8/9/90 Subject B-18 LAUDFILL Sheet No. 4 of 28  
Chkd. By GK Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

21 DYNAMIC STABILITY OF CUT SLOPES IN BEDROCK,  
LAUDFILL B-19, GOLDBER ASSOCIATES, JUNE 1989

22 Lambe, Whitman, Soil Mechanics, John Wiley &  
Sons, Inc, 1969

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B. Date \_\_\_\_\_ Subject B-18 LANDFILL Sheet No. 5 of 28  
Chkd. By GK Date 8/15/80 SLOPE STABILITY Proj. No. 89-977

## EARTHQUAKE GROUND MOTION PARAMETERS

THE SEISMIC DESIGN OF THE B-18 LANDFILL SHOULD BE BASED ON THE MAXIMUM CREDIBLE EARTHQUAKE (MCE) ACCORDING TO 22 CAC 67108(b). THE MCE IS THE LARGEST EARTHQUAKE CONSIDERED POSSIBLE TO OCCUR ON A FAULT UNDER PRESENT GEOLOGIC CONDITIONS WITHOUT REGARD TO RECURRENCE INTERVAL.

THE IDENTIFICATION AND CHARACTERIZATION OF POTENTIAL SOURCES OF EARTHQUAKES IS PRESENTED IN REFERENCE 10

FROM REFERENCE 10, THE DOMINANT SEISMIC SOURCE IS:

- COOLING-TYPE EARTHQUAKE
- NORTH DOUG SEGMENT OF THE RAMP-THrust
- $M_s = 7.0$
- FOCAL DEPTH 10 KM
- HIGHEST POTENTIAL MEAN PEAK ACCELERATION IS 0.43g. THE 0.43g VALUE IS THE RESULT OF ADDING A FACTOR OF 20% TO THE BASE ACCELERATION OF 0.36g BECAUSE THE SOURCE STRUCTURE IS A THRUST FAULT.  
(REFERENCE 10)

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LAUDFILL Sheet No. 6 of 28  
Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

COMPUTER PROGRAM "STABLES" DEVELOPED BY  
PURDUE UNIVERSITY (REFERENCE  
20). THE PROGRAM CALCULATES THE FACTOR OF  
SAFETY AGAINST SLOPE FAILURE BY A TWO-DIMENSIONAL  
LIMITING EQUILIBRIUM METHOD.

THE CALCULATION OF THE FACTOR OF SAFETY AGAINST  
SLOPE INSTABILITY IS PERFORMED USING:

- Modified Bishop METHOD OF SLICES  
(CIRCULAR FAILURE SURFACES)
- Modified Jambu METHOD OF SLICES  
(BLOCK, WEDGE FAILURE MODE)

## SEISMICALLY-INDUCED PERMANENT DISPLACEMENTS

THE AMPLITUDE OF SEISMICALLY-INDUCED PERMANENT  
DISPLACEMENT IS CALCULATED USING THE METHOD  
SUGGESTED BY NEWMARK (REFERENCE 2) AND  
EXPANDED BY FRANKLIN & CHOW (REFERENCE 1).

THIS METHOD OF ANALYSIS INVOLVES CALCULATING THE  
EARTHQUAKE-INDUCED INERTIA FORCE (THE DRIVING  
FORCE) ON A POTENTIAL SLIDING MASS AND  
COMPARING THIS DRIVING FORCE WITH THE RESISTING  
FORCE DUE TO THE SHEAR STRENGTH OF THE  
MATERIALS. THE SEISMICALLY-INDUCED PERMANENT  
DISPLACEMENT OF THE POTENTIAL SLIDE MASS OCCURS  
WHenever THE DRIVING FORCE EXCEEDS THE  
RESISTING FORCE. THEREFORE, IF THE AVERAGE  
INDUCED ACCELERATION ON A POTENTIAL SLIDE MASS  
IS LARGER THAN ITS YIELD ACCELERATION (THE  
ACCELERATION AT WHICH THE POTENTIAL MASS WILL JUST  
BEGIN TO MOVE), THE MOVEMENT WILL START AND  
STOP WHEN THE DIRECTION OF THE GROUND

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 7 of 28  
Chkd. By \_\_\_\_\_ Date \_\_\_\_\_ SLOPE STABILITY ANALYSIS Proj. No. 89-979

ACCELERATION IS DECREASED AND THE AVERAGE ACCELERATION BECOMES LESS THAN THE YIELD ACCELERATION. BY DOUBLE INTEGRATION OF THE PART OF THE AVERAGE ACCELERATION TIME HISTORY THAT EXCEEDS THE YIELD ACCELERATION, PERMANENT DISPLACEMENTS CAN BE CALCULATED. THIS PROCEDURE IS SHOWN IN FIGURE 1.


THE YIELD ACCELERATION FOR A GIVEN SLOPE CONFIGURATION IS DETERMINED BY ESTIMATING THE HORIZONTAL EARTHQUAKE LOADING COEFFICIENT "K" WHICH RESULTS IN A PSEUDOSTATIC FACTOR OF SAFETY EQUAL TO 1.

K IS GIVEN IN TERMS OF  $g$ , THEREFORE REPRESENTS THE HORIZONTAL ACCELERATION APPLIED TO THE SLIDING MASS.

PERMANENT DISPLACEMENTS ARE CALCULATED AS A FUNCTION OF THE YIELD ACCELERATION USING FRANKLIN & CHAN UPPER BOUND ENVELOPE CURVES SHOWN IN FIGURE 2. (REFERENCE 1)

FRANKLIN AND CHAN EXPANDED NEWHOLD'S DATA BASE. ALL EARTHQUAKE RECORDS WERE SCALED TO 0.5  $g$  PEAK ACCELERATION AND 30-IN./SEC PEAK VELOCITY AND THE RESULTING SCALED PERMANENT DISPLACEMENTS ARE PLOTTED AGAINST THE RATIO  $N/A$  ON A LOGARITHMIC PLOT. IN THIS PLOT UPPER BOUND CURVES ARE PRESENTED FOR VARIOUS RANGES IN THE VALUE OF  $N/A$  WHERE  $N$  IS THE YIELD ACCELERATION AND  $A$  IS THE MAXIMUM EARTHQUAKE ACCELERATION ACTING UPON THE POTENTIAL SLIDING MASS. THE PROPOSED UPPER BOUND CURVES ARE DESCRIBED IN THE LEGEND OF FIGURE 2 (UPPER RIGHT HAND CURVES)





(EXAMPLE ONLY)




FIGURE 1




Figure 16. Upper bound envelope curves of permanent displacements for all natural and synthetic records analyzed

(REFERENCE 1)

18.5  
17 10

FIGURE 2

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 10 of 28  
Chkd. By GSC Date 8/15/90 SLOPE STABILITY ANALYSIS. Proj. No. 89-977

SOIL PROFILE AVAILABLE SUBSURFACE INFORMATION AND SITE GEOLOGY INDICATE THAT THE B-18 SITE IS CONSIDERED AS A "ROCK" SITE. CONSEQUENTLY THE UPPER BOUND CURVE IN FIGURE 2 DESIGNATED AS ROCK SITE RECORDS IS USED IN THIS ANALYSIS.

## ANALYSIS PROCEDURE

THE PROCEDURE TO OBTAIN UNSCALED PERMANENT DISPLACEMENTS FOR A GIVEN SLOPE CONFIGURATION IS AS FOLLOWS:

OBTAIN  $K_y$  (YIELD ACCELERATION) BY USING STABL 5 COMPUTER PROGRAM.  $K$  VARIES TO OBTAIN  $\lambda$  S.F. = 1


ASSUME THREE DIFFERENT VALUES OF  $A$  ( $A_1, A_2, A_3$ ).  $A$  IS THE MAXIMUM GROUND ACCELERATION

OBTAIN  $\frac{K_y}{A_1}$ ,  $\frac{K_y}{A_2}$ ,  $\frac{K_y}{A_3}$

$K_y = N \Rightarrow$  WITH  $\frac{N}{A_1}$ ,  $\frac{N}{A_2}$  AND  $\frac{N}{A_3}$   
ENTER FIGURE 2.


# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 11 of 28  
 Chkd. By GSC Date 8/15/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977



OBTAIN PERMANENT DISPLACEMENT VALUES BASED ON:

- $\frac{V}{A} = 30$  (SITE SPECIFIC PARAMETER)
- $U_m = U_s \frac{V^2}{1,800 A}$  (FROM REFERENCE 1)



# ENVIRONMENTAL SOLUTIONS, INC.

By J. B. Date 8/9/90 Subject B-18 LANDFILL Sheet No. 12 of 28  
Chkd. By SSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## VELOCITY/ACCELERATION (V/A) RATIO

From REFERENCE 3. Donovan proposes relationships for site dependent  $\frac{V}{A}$  ratios. Range of  $\frac{V}{A}$  values for rock and soil sites are shown in Figure 3

A conservative estimate of  $\frac{V}{A}$  ratio for the KHF is obtained by

$$\left(\frac{V}{A}\right)_{KHF} = \frac{\left(\frac{V}{A}\right)_{\text{AVERAGE ROCK SITES}} + \left(\frac{V}{A}\right)_{\text{AVERAGE SOIL SITES}}}{2}$$

$$\left(\frac{V}{A}\right)_{KHF} = \frac{37 + 23}{2} = 30$$

⇒ ESTIMATE PERMANENT DISPLACEMENTS FOR A RANGE OF PEAK GROUND ACCELERATIONS (.3g TO .5g) FOR THE SITE SPECIFIC  $\frac{V}{A}$  RATIO OF 30.




Figure 3. Measured velocity/acceleration (V/A) ratios and derived V/A equations. Shaded areas show range of values obtained using equation for rock and soil sites.

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL

Sheet No. 14 of 28

Chkd. By GSC Date 8/14/90 SLOPE STABILITY ANALYSIS

Proj. No. 89-977

## UNSCALED PERMANENT DISPLACEMENTS

FROM REFERENCE 1 (PAGE 20)

$$U_m = U_s \cdot \frac{V^2}{11800 A}$$

$U_m$  = UNSCALED PERMANENT DISPLACEMENT

$A$  = MAXIMUM GROUND ACCELERATION

$V$  = MAXIMUM GROUND VELOCITY

$U_s$  = STANDARDIZED MAXIMUM DISPLACEMENT (FROM FIG 2)

FOR  $\frac{V}{A} = 30$

$V = 30 \cdot A$
------------------


$A$	$V$ (INCH/SEC)	$U_m = U_s \cdot \frac{V^2}{11800 A}$
.3	9.0	$U_m = .15 U_s$
.4	12.0	$U_m = .20 U_s$
.5	15.0	$U_m = .25 U_s$
.6	18.0	$U_m = .30 U_s$
.7	21.0	$U_m = .35 U_s$

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 15 of 28  
Chkd. By GSC Date 8/14/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## ALLOWABLE DESIGN DISPLACEMENT FOR THE MCE

FOR EACH CONDITION THE PEAK EARTHQUAKE ACCELERATION WHICH WILL CAUSE THE ALLOWABLE DESIGN DISPLACEMENT IS ESTIMATED AS FOLLOWS



BECAUSE OF THE WAY SEISMIC WAVES PROPAGATE, ATTENUATION FACTORS ARE CONSIDERED TO TAKE INTO ACCOUNT THE EFFECT OF THE WASTE PILE ON THE SEISMIC DEFORMATIONS

FOR DEEP FAILURE MODE, THE ACCELERATION IN THE SLIDING MASS IS ASSUMED TO BE .8 TIMES THE PEAK BASE ACCELERATION ( $A_0$ )


$$A = .8 A_0$$



# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 16 of 28  
 Chkd. By GS Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977


OR  $A_0 = 1.25 A$



THIS RELATIONSHIP IS CONSERVATIVE BASED ON THE RESULTS OF DYNAMIC RESPONSE ANALYSIS FOR THE OPERATING INDUSTRIES LANDFILL (REFERENCE 4) FOR 0.50 g AND 0.25 g AS SHOWN IN FIGURES 5 AND 6 RESPECTIVELY.

- NOTE THAT FOUNDATION CONDITIONS FOR BOTH LANDFILLS ARE SIMILAR. DEUSED WASTE MATERIALS WILL BE PLACED AT THE B-18 LANDFILL, THEREFORE A HIGHER ATTENUATION FACTOR IS CONSIDERED (.8 AS OPPOSED TO .7 FOR .25 g)

- THE ACCELERATION IN THE SLIDING MASS (A) IS ASSUMED TO BE THE SAME AS THE PEAK BASE ACCELERATION FOR SHALLOW FAILURE MODE SUCH AS THE COVER LINER SLIDING. (SEE FIGURE 6)



VARIATION OF MAXIMUM ACCELERATION ALONG THE SURFACE OF THE LANDFILL





FIGURE 5

Project: OPERATING INDUSTRIES LANDFILL  
Project No. 120R12

RESULTS OF DYNAMIC RESPONSE ANALYSIS - CASE 1


Fig. E-5



# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 19 of 28  
Chkd. By GSC Date 8/14/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## ESTIMATED DISPLACEMENT FOR THE MCE



## DISK ASSESSMENT FOR DYNAMIC CONDITIONS

A PROBABILISTIC ASSESSMENT OF DESIGN GROUND MOTIONS FOR THE KETTLEMAN HILLS FACILITY IS PRESENTED IN REFERENCE 10 (GOLDER ASSOCIATES)

FIGURE 4 (FROM REFERENCE 10) PRESENTS THE RELATIONSHIP BETWEEN THE PROBABILITY OF EXCEEDANCE AND PEAK ACCELERATION ( $g$ ) FOR TIME PERIODS OF 1, 20, AND 50 YEARS.

BASED ON THIS FIGURE THE PROBABILITY OF EXCEEDANCE


# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL  
Chkd. By SSC Date 8/14/90 SLOPE STABILITY ANALYSIS

Sheet No. 20 of 28  
Proj. No. 89-977

(POE) FOR THE ALLOWABLE DESIGN DISPLACEMENT IS ESTIMATED.

AS SHOWN IN FIGURE 4:



( $A_0$ ) PEAK ACCELERATION




Figure 3. Probability of exceedance as a function of time period

FIGURE 4

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL  
Chkd. By GSC Date 8/14/90 SLOPE STABILITY ANALYSIS

Sheet No. 22 of 28  
Proj. No. 89-977

## CASES TO BE ANALYZED

### I - ROCK CUTS

a- 2:1 SLOPES WITH POTENTIAL SLIDING  
ACROSS BEDDING PLANES

b - 3:1 SLOPES WITH POTENTIAL SLIDING  
ALONG BEDDING PLANES.

### II COMPACTED FILL EMBANKMENTS

a- RUNOFF RETENTION BASIN

b. SMALL EMBANKMENT TO COMPLETE PHASE I/4 BEAM

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B. Date 8/9/90 Subject B-18, LANDFILL Sheet No. 22A of 28  
Chkd. By gsc Date 8/15/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## III TEMPORARY PHASE I INTERMEDIATE WASTE FILL

a - WEDGE MOVEMENT ALONG THE LINER SURFACE

- ENTIRELY ALONG INTERFACE
- THROUGH WASTE AT BASE / BEDD INTERSECTION

b - CIRCULAR FAILURE WITHIN THE WASTE

- WITH WASTE STRENGTH:  $\phi = 31^\circ$ ,  $c = 0$
- WITH WASTE STRENGTH  $\phi = 27^\circ$ ,  $c = 300 \text{ psf}$

## IV FINAL CLOSURE CONDITIONS

a - 3.6 : 1 SLOPE BETWEEN BEDDCHES  
(INFINITE SLOPE MODEL)

1 - AT CLAY / OPERATION LAYER INTERFACE

2 - AT ROUGHENED HDPE / CLAY INTERFACE

3 - AT GEOCOMPOSITE / ROUGHENED HDPE INTERFACE  
(NO COHESION ALLOWANCE)

4 - AT GEOCOMPOSITE / ROUGHENED HDPE INTERFACE  
( $c = 50 \text{ psf}$ )

b - WEDGE MOVEMENT ALONG THE LINER SURFACE.

1 - ENTIRELY ALONG INTERFACE

2 - THROUGH WASTE AT BASE / SLOPE  
INTERSECTION.

c - CIRCULAR FAILURE WITHIN THE WASTE





# ENVIRONMENTAL SOLUTIONS, INC.

By J. B. Date 8/9/90 Subject B-18 LANDFILL  
 Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS

Sheet No. 23 of 28  
 Proj. No. 89-977

## TYPICAL LINED SYSTEM DETAILS.




# ENVIRONMENTAL SOLUTIONS, INC.

By JB Date 8/9/90 Subject B-18 LANDFILL

Sheet No. 24 of 28

Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS

Proj. No. 89-979



BOTTOM LINER SYSTEM

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LAUDFILL Sheet No. 25 of 28  
 Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## MATERIAL AND INTERFACE STRENGTH PARAMETERS USED FOR STABILITY CALCULATIONS -

MATERIAL OR INTERFACE	DESIGN STRENGTH PARAMETERS			SOURCE / REMARKS
	TOTAL UNIT WEIGHT (PCF)	C (PSF)	φ (DEGREES)	
WASTE/OPERATIONS LAYER (SHALLOW FAILURE PLANES)	115	30	27	USED AS A CONSERVATIVE PARAMETER
WASTE/OPERATIONS LAYER (DEEP FAILURE PLANES)	115	0	31	Golden Associates, December 1989. Conservative
<u>CROSS BEDDING</u>				
CLAYSTONE	130	800	40	• Donohue & Associates, Inc, October 1988. Confirmed by Direct Shear Tests
SILTSTONE	130	800	40	
SANDSTONE	130	800	40	
<u>ALONG BEDDING</u>				
CLAYSTONE	130	0	36	• Donohue & Associates, Inc, October 1988. Confirmed by UU Triaxial Tests
SILTSTONE	130	0	36	
SANDSTONE	130	0	36	
STRUCTURAL FILL	125	2,000	30	CONSERVATIVE VALUE BASED ON UU TRIAXIAL TEST ON SANDSTONE COMPACTED TO 95% RELATIVE COMPACTM

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 26 of 28  
 Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

MATERIAL OR INTERFACE	DESIGN STRENGTH PARAMETERS			SOURCE / REMARKS
	TOTAL UNIT WEIGHT (PCF)	C (PSF)	$\phi$ (DEGREES)	
<u>LINDER SYSTEM: BASE AND SIDE SLOPES</u>				
- COMPACTED CLAY (LONG TERM)	125	1,150 <sup>(1)</sup>	20°	CU TRIAXIAL TESTS ON CLAYSTONE COMPACTED TO 90% RELATIVE COMPACTION
- COMPACTED CLAY / ROUGHENED HDPE LINER (LONG TERM)	125	1,150 <sup>(1)</sup>	20°	
- COMPACTED CLAY (SHORT TERM OR LOW CONFINING STRESS)	125	3,600	0	UU TRIAXIAL TEST ON CLAYSTONE COMPACTED TO 90% RELATIVE COMPACTION
- COMPACTED CLAY / ROUGHENED HDPE LINER (SHORT TERM OR LOW CONFINING STRESS)	125	3,600	0	UU TRIAXIAL TEST ON CLAYSTONE COMPACTED TO 90% RELATIVE COMPACTION
ROUGHENED HDPE / GEONET	-	0	15°	<u>EcunTools</u> - Guide, March 11 1987 - Geo Syntec, Inc, October 11, 1988
GEONET / GEOTEXTILE (HEAT BONDED)	-	0	>30°	Fluid Systems, Inc
GEOTEXTILE / DRAINAGE LAYER	-	0	>25°	
GEOTEXTILE / COMPACTED CLAY	-	0	21°	Goldier Associates, June 29, 1990
ROUGHENED HDPE / GEOCOMPOSITE	-	0	24°	Goldier Associates, June 29, 1990
		50	24°	" " "
GEO COMPOSITE / DRAINAGE LAYER	-	0	>21°	ANTICIPATED TO BE HIGHER THAN GEOTEXTILE / COMPACTED CLAY
GEOTEXTILE / BASE OPERATIONS LAYER	-	300	27° (SHALLOW FAILURE)	
	-	0	31° (DEEP FAILURE)	

THE SHEAR STRENGTH OF

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 27 of 28  
 Chkd. By GAC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

MATERIAL OR INTERFACE	DESIGN STRENGTH PARAMETERS			SOURCE / REMARKS
	TOTAL UNIT WEIGHT (PCF)	C (PSF)	φ (DEGREES)	
				THE BASE OPERATIONS LAYER CONTROLS. PROPERTIES OF THE BASE OPERATIONS LAYER ARE CONSIDERED TO BE THE SAME AS THOSE OF THE WASTE.
<u>LINED SYSTEM - FINAL COVER (CLOSURE)</u>				
COMPACTED CLAY - (SHORT TERM OR LOW CONFINING STRESS)	125	3600	0	UU TRIAXIAL TEST ON CLAYSTONE COMPACTED TO 90% RELATIVE COMPACTION
COMPACTED CLAY / ROUGHENED HDPE LINER - LOW CONFINING STRESS.	-	0	32	Goldor Associates, June 29, 1990
ROUGHENED HDPE / GEOCOMPOSITE -	-	0	24	Goldor Associates, June 29, 1990
GEOCOMPOSITE / VEGETATIVE SOIL COVER	-	100	22	Goldor Associates, June 29, 1990
VEGETATIVE SOIL COVER	-	40	26°	ASSUMED FOR MEDIUM DENSE CLAYEY SAND

(1) BASED ON DT-A, B-2 TEST RESULTS. DT-C, B-1 IS LESS PLASTIC AND STROUGER

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B. Date 8/9/90 Subject B-18 LANDFILL Sheet No. 28 of 28  
Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## PERFORMANCE CRITERIA (GENERAL)

STATIC FACTOR OF SAFETY : 1.5 (MINIMUM)

ALLOWABLE SEISMIC DEFORMATION : 1-INCH FOR  
FAILURE SURFACE THROUGH THE LINED SYSTEM.  
LARGED DEFORMATIONS ARE ACCEPTABLE FOR  
FAILURE MODES THROUGH THE WASTE PILE OR VEGETATIVE  
COVER

COMPUTER OUTPUT. REFER TO COMPUTER OUTPUT  
FOR EACH CASE. (CONTAINED  
IN A SEPARATE VOLUME). FILE NAME, FAILURE  
MODE, CALCULATED FACTORS OF SAFETY AND  
YIELD ACCELERATION ARE LISTED FOR EACH SPECIFIC  
CASE.

**APPENDIX H.2**  
**ROCK CUTSLOPE STABILITY**

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B. Date 8/9/90 Subject B-18 LAUDFILL Sheet No. 0. of 13  
Chkd. By \_\_\_\_\_ Date \_\_\_\_\_ SLOPE STABILITY ANALYSIS Proj. No. 89-977

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

CASE I

STABILITY OF CUT SLOPES.

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29



# ENVIRONMENTAL SOLUTIONS, INC.

By J. B. Date 8/9/90 Subject B-18 LANDFILL

Sheet No. 1 of 13

Chkd. By CSC Date 8/13/90 SLOPE STABILITY ANALYSIS

Proj. No. 89-977

CASE IA

2:1 SLOPE.

(CROSS BEDDING STRENGTH)

(DESIGN PERIOD : 5 YRS)

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 2 of 13  
 Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## CASE I-A

### PERFORMANCE CRITERIA

- MINIMUM STATIC FACTOR OF SAFETY: 1.5
- ALLOWABLE MAXIMUM DISPLACEMENT FOR THE DESIGN EARTHQUAKE PEAK ACCELERATION: 1 INCH

PLAN VIEW OF PHASE I EXCAVATION IS SHOWN IN FIGURE 7  
 SLOPE STABILITY MODEL IS SHOWN IN FIGURE 8

FILE NAME	E= EARTHQUAKE S= STATIC	FAILURE MODE	K (1)	FACTOR OF SAFETY	REMARKS
RUN 4 CUT	E	CIRCULAR	.5	1.06(2)	
RUN 5 CUT	E	CIRCULAR	.54	1.0(2)	
RUN 6 CUT	S	CIRCULAR	0	2.42(3)	

- (1) HORIZONTAL EARTHQUAKE LOADING COEFFICIENT  
 (2) PSEUDOSTATIC  
 (3) STATIC

$$N = K_y = .54 \quad ; \quad \text{FOR } A = .7, \quad \frac{N}{A} = \frac{.54}{.7} = .77$$

CLAY BORROW  
AREA EXCAVATION

PHASE I  
LANDFILL UNIT B-18  
EXCAVATION


PHASE I BENCH  
(60' WIDE)

ACCESS ROAD  
(30' WIDE)

PERIMETER ROAD  
(60' TOTAL WIDTH,  
35' TRAVELED WAY,  
15' ALLOWANCE FOR CAP)

LIMIT OF PHASE I  
LANDFILL UNIT B-18

FIGURE 7




2:1 SLOPE

1.5:1 SLOPE

2:1 SLOPE

K-22

K-21



# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 5 of 13  
Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

1  
2 ⇒ FROM FIGURE 2,  $N/A = .77$  THE STANDARDIZED  
3 MAXIMUM DISPLACEMENT IS LESS THAN 1 INCH. NO  
4 PERMANENT SEISMIC DISPLACEMENT

5  $A = A_0$ ,

6  
7 ⇒ FROM FIGURE 9 POE IS  $< 40 \times 10^{-4}$   
8 FOR 5 YEARS;

9 CONCLUSION

- 10  
11 • S.F.  $> 1.5$  OK.  
12  
13 • NEGLIGIBLE SEISMIC DISPLACEMENT  
14  
15 •  $K_y = .54$   
16  
17 • POE  $< 40 \times 10^{-4}$  FOR 5 YEARS WHICH IS  
18 THE DESIGN RECURRENCE PERIOD  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

TEMPORARY ROCK CUT ; 2:1 SLOPE , CROSS BEDDING  
STRENGTH  
CASE IA




Figure 3. Probability of exceedance as a function of time period

FIGURE 9

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 7 of 13  
Chkd. By CSK Date 8/12/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

CASE I B  
ROCK CUT  
3:1 SLOPE  
(ALONG BEDDING STRENGTH)  
(DESIGN PERIOD 5 YEARS)

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 8 of 13  
 Chkd. By JSC Date 8/15/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## CASE I B

### PERFORMANCE CRITERIA SAME AS CASE IA


- PLAN VIEW OF PHASE II EXCAVATION IS SHOWN IN FIGURE 10
- SLOPE STABILITY MODEL IS SHOWN IN FIGURE 11

FILE NAME	E = EARTHQUAKE S = STATIC	FAILURE MODE	K (1)	SAFETY FACTOR	REMARKS
RUN 7 CUT	E	CIRCL2	.5	.73 (2)	
RUN 8 CUT	E	CIRCL2	.32	1.0 (2)	
RUN 9 CUT	S	CIRCL2	0	2.19	

(1) HORIZONTAL EARTHQUAKE LOADING COEFFICIENT  
 (2) PSEUDOSTATIC FACTOR OF SAFETY. USED TO ESTIMATE YIELD ACCELERATION, IN THIS CASE  $K_y = .32$  (FILE NAME RUN8CUT)

ESTIMATE SEISMIC DEFORMATIONS FOR  $A = .5, .6$  AND  $.7$





PHASE 1  
LANDFILL UNIT B-18  
EXCAVATION

FIGURE 10

CHEM WASTE MANAG. INC.  
SLOPE STABILITY ANALYSIS




FIGURE 11

BY NEA


# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 11 of 13  
 Chkd. By ESC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## CASE I-b

K <sub>y</sub> = N	A	K <sub>y</sub> /A	U <sub>s</sub> * (INCHES)	V/A	U <sub>m</sub> = $\frac{U_s V^2}{1,800 A}$	U <sub>m</sub> * * (INCHES)
.32	.5	.64	1	30	U <sub>m</sub> = .25 U <sub>s</sub>	.25
.32	.6	.53	4	30	U <sub>m</sub> = .30 U <sub>s</sub>	1.20
.32	.7	.46	8	30	U <sub>m</sub> = .35 U <sub>s</sub>	2.80

\* FROM FIGURE 2  
 \* \* PERMANENT DISPLACEMENT



# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/9/90 Subject B-18 LANDFILL Sheet No. 12 of 13  
Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

$$A_0 = A$$

FROM FIG 12 P O E =  $8.0 \times 10^{-4}$  FOR 5 YEARS  
FOR 1-INCH DEFORMATION :  $.58g > .43g$  OK.

## CONCLUSION:

STATIC SAFETY FACTOR =  $2.2 > 1.5$  OK.

- SEISMIC DISPLACEMENT: MINIMAL
- P O E FOR 1-INCH DISPLACEMENT =  $8.0 \times 10^{-4}$  (5 YEARS)
- $K_y = .32$  (YIELD)

CASE I-b.




Figure 3. Probability of exceedance as a function of time period

FIGURE 12

**APPENDIX H.3**  
**COMPACTED FILL SLOPE STABILITY**

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/10/90 Subject B-18 LAUDFILL Sheet No. 0 of 12  
Chkd. By gsc Date 8/11/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

## CASE II

STABILITY OF COMPACTED  
FILL EMBANKMENT

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 1 of 12  
Chkd. By GSC Date 8/11/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

CASE II-A

RUNOFF RETENTION BASIN

(DESIGN PERIOD: 20 YEARS)



# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 2 of 12  
 Chkd. By GK Date 8/11/90 SLOPE STABILITY. Proj. No. 89-977

## CASE II-A

### PERFORMANCE CRITERIA

- MINIMUM STATIC FACTOR OF SAFETY : 1.5
- ALLOWABLE MAXIMUM DISPLACEMENT FOR THE DESIGN EARTHQUAKE PEAK ACCELERATION : 3-INCH

PLAN VIEW OF THE RETENTION BASIN IS SHOWN IN FIGURE 13

SLOPE STABILITY MODEL (SECTION A) IS PRESENTED IN FIGURE 14

AS SHOWN IN FIGURE 14, THE CRITICAL SLOPE IS ON THE SOUTH WEST SIDE FOR DEEP FAILURE MODE

COMPUTED FACTOR OF SAFETY ARE PRESENTED IN SHEET 5

- THE YIELD ACCELERATION FOR THE SOUTH WEST SLOPE IS ABOUT .5 (FILE NAME RN13M2S.SW)

### SEISMIC DEFORMATIONS

\* FROM FIGURE 2.

$K_y = N$	A	$K_y/A$	$U_s^*$ (INCHES)	$\frac{V}{A}$	$U_m$ (INCHES)
.5	.7	.71	.70	30	NEGLECTIBLE
.5	.6	.83	< 1.0	30	"
.5	.5	1.0	< 1.0	30	"





# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/10/90 Subject B-18 LAUDFILL Sheet No. 5 of 12  
 Chkd. By GSC Date 8/11/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977


## RUNOFF RETENTION BASIN

RUN NO	FILE NAME	S = STATIC E = EARTHQUAKE	FAILURE MODE	K(1)	SAFETY FACTOR	REMARKS
1	RN1BM1S.SW	E	CIRC12	0.4	1.21 (3)	(1) HORIZONTAL EARTHQUAKE LOADING COEFFICIENT (2) STATIC (3) PSEUDOSTATIC. USED TO ESTIMATE SEISMIC DISPLACEMENTS (4) A PSEUDOSTATIC F.S < 1.0 DOES NOT IMPLY FAILURE CONDITIONS
2	RN1BM2S.SW	E	CIRC12	0.5	1.03 (3)	DEEPA FAILURE - SOUTH WEST SLOPE THROUGH STRUCTURAL FILL AND NATURAL MATERIAL (SAME)
3	RUN1BU.SW	S	CIRC12	0	3.06 (2)	(same)
4	RN2BM1S.SW	E	CIRC12	0.4	0.87 (3)	SHALLOW FAILURE - SOUTH WEST SLOPE
5	RN2BM2S.SW	E	CIRC12	0.2	1.29 (3)	SHALLOW FAILURE - SOUTH WEST SLOPE
6	RN2BM3S.SW	E	CIRC12	0.3	1.05 (3)	SHALLOW FAILURE - SOUTH WEST SLOPE
7	DUN2BM.SW	S	CIRC12	0	2.20 (2)	SHALLOW FAILURE WITHIN NATURAL MATERIAL (LOCAL)
8	RUN3BM.SW	S	CIRC12	0	5.15 (2)	FAILURE WITHIN STRUCTURAL FILL
9	DUN1BM.NE	S	CIRC12	0	3.46 (2)	SLOPE ON NE SLOPE
10	RUN1BM1S.NE	E	CIRC12	0.5	1.48 (3)	SLOPE ON NE SLOPE

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 6 of 12  
Chkd. By JSC Date 8/14/90 SLOPE STABILITY Proj. No. 89-977

FROM SHEET 2,  $U_m$  (PERMANENT DISPLACEMENTS) ARE  
NEGLECTIBLE



FROM FIGURE 15,  $POE < 30 \times 10^{-3}$  (20 YRS)

## CONCLUSIONS

- STATIC FACTOR OF SAFETY  $> 1.5$
- PERMANENT SEISMIC DISPLACEMENTS: NONE
- $K_y = .5g$
- $POE < 30 \times 10^{-3}$  FOR 20 YEARS

CASE II-A

CASE II-B




Figure 3. Probability of exceedance as a function of time period

FIGURE 15

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 8 of 12  
Chkd. By GC Date 8/11/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

CASE II-B.

(SMALL EMBANKMENT TO COMPLETE PHASE I/II BEDM)

(DESIGN PERIOD 5 YEARS)

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 9 of 12  
Chkd. By GSC Date 8/11/90 SLOPE STABILITY ANALYSIS Proj. No. 84-977

## CASE II-B

### PERFORMANCE CRITERIA

- 1 - MINIMUM STATIC FACTOR OF SAFETY = 1.5
- 2 - ALLOWABLE MAXIMUM DISPLACEMENT FOR THE DESIGN EARTHQUAKE PEAK ACCELERATION = 1. INCH

PLAN VIEW OF THE CLAY BORROW AREA IS SHOWN IN FIGURE 16

SLOPE STABILITY MODEL IS SHOWN IN FIGURE 17.

- FINAL BENCH ELEVATION IS 720' AS OPPOSED TO 710' AS SHOWN IN THE MODEL. THIS MINOR DISCREPANCY SHOULD NOT AFFECT THE ANALYSIS RESULTS
- BENCHES BETWEEN THE FILL AND NATIVE MATERIAL WERE NOT INCLUDED IN THE MODEL FOR SIMPLICITY. THIS SHOULD NOT AFFECT THE ANALYSIS RESULTS.

CALCULATED FACTORS OF SAFETY ARE SHOWN IN SHEET 12

THE YIELD ACCELERATION IS GREATER THAN 0.6  $\Rightarrow$  THE PEAK ACCELERATION TO INDUCE A PERMANENT DISPLACEMENT IS GREATER THAN 0.7 BASED ON PREVIOUS RESULTS  $\Rightarrow$  SEISMIC DISPLACEMENTS ARE NEGLIGIBLE

POE  $\ll 3.0 \times 10^{-4}$  (5 yrs) AS SHOWN IN FIGURE 15 FOR THE DIVERT DETENTION BASIN EMBANKMENT. ACTUAL LIFE OF CLAY BORROW AREA EMBANKMENT IS ABOUT 5 YEARS

### CONCLUSIONS

- STATIC FACTOR OF SAFETY  $> 1.5$
- SEISMIC DISPLACEMENTS: NEGLIGIBLE

-  $K_y > 0.6$

POE  $\ll 3.0 \times 10^{-3}$  FOR 5 YEARS







FIGURE 16

CASE II-B  
 (CLAY BORROW AREA)



# ENVIRONMENTAL SOLUTIONS, INC.

By J. B. Date 8/10/90 Subject B-18 LANDFILL  
 Chkd. By gsc Date 8/11/90 SLOPE STABILITY ANALYSIS

Sheet No. 12 of 12  
 Proj. No. 89-977

SHALL EMBANKMENT TO COMPLETE PHASE I/II BERM)

FILE NAME	S = STATIC E = EARTHQ.	FAILURE MODE	(3) K	FACTOR OF SAFETY	REMARKS
DUN 1 BERM	S	CIRC2	0	3.17 (2)	THREE RUN WITH DIFFERENT INITIATION POINTS
DUN 2 BERM	E	CIRC2	0.3	1.69 (4)	✓
DUN 3 BERM	E	CIRC2	0.5	1.25 (1)	✓
DUN 4 BERM	E	CIRC2	0.6	1.09 (1)	

(1) PSEUDOSTATIC, (2) STATIC  
 (3) K = HORIZONTAL EARTHQUAKE LOADING COEFFICIENT  
 $K_y > .6$  (FILE NAME RUN 4 BERM)  
 ⇒ MINIMAL DEFORMATIONS  
 ALLOWABLE DESIGN DISPLACEMENT FOR THE UCE: 1 INCH  
 ESTIMATED DISPLACEMENT FOR THE MCE = 0

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

**APPENDIX H.4**  
**INTERMEDIATE PHASE I CLOSURE AND INTERMEDIATE**  
**PHASE IIIA WASTE SLOPE STABILITY**

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject B-18 LAUDFILL Sheet No. 0 of 24  
Chkd. By gsc Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

CASE III

STABILITY OF TEMPORARY PHASE I  
INTERMEDIATE WASTE FILL

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 1 of 24  
Chkd. By GSC Date 9/12/90 SLOPE STABILITY ANALYSIS Proj. No. 89-997

CASE III - A

WEDGE MOVEMENT ALONG THE  
LINED SURFACE

(DESIGN PERIOD 10 YRS)

H.A

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 2 of 24  
 Chkd. By GSC Date 9/13/90 SLOPE STABILITY Proj. No. 89-977

## CASE III-A1

### PERFORMANCE CRITERIA

- MINIMUM STATIC FACTOR OF SAFETY : 1.5
- MAXIMUM ALLOWABLE DISPLACEMENT FOR THE DESIGN EARTHQUAKE PEAK ACCELERATION : 1- INCH

PLAN VIEW OF THE TOP OF THE LINER AND TEMPORARY COVER ARE SHOWN IN FIGURES 18 AND 19 RESPECTIVELY.

- SLOPE STABILITY MODEL IS SHOWN IN FIGURE 20

COMPUTED FACTORS OF SAFETY ARE:

FILE NAME	S = STATIC E = EARTHQUAKE	FAILURE MODE	K (1)	SAFETY FACTOR	REMARKS
KH7BL. 1S	S	BLOCK 2	0	2.54 (2)	FOR ALL CASES: GEocomposite on 3:1 slope, $\phi = 24^\circ$ , $c=0$ CLAY LINER $c = 3600$ psf $\phi = 0$ $\phi = 15^\circ$ GEONET/ ROUGHENED HDPE AT BOTTOM
KH7BL. 1E	E	BLOCK 2	0.3	1.11 (3)	
KH7BL. 2E	E	BLOCK 2	0.4	0.87 (3)	
KH7BL. 3E	E	BLOCK 2	0.35	0.98 (3)	

(1) HORIZONTAL EARTHQUAKE LOADING COEFFICIENT

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B

Date 8/10/90

Subject B-18 LANDFILL

Sheet No. 3 of 24

Chkd. By \_\_\_\_\_


Date \_\_\_\_\_

SLOPE STABILITY

Proj. No. 89-979

(2) STATIC

(3) PSEUDOSTATIC. A VALUE LESS THAN 1 DOES NOT NECESSARILY IMPLY FAILURE. THEY ARE USED TO ESTIMATE THE YIELD ACCELERATION WHICH RELATED TO THE PERMANENT DISPLACEMENT BY THE N/A RATIO SHOWN IN FIGURE 2.



$$K_y = .33 \text{ (CONSERVATIVE)}$$



ANCHOR TRENCH  
DRAINAGE SWALE

EDGE OF LINER AT  
BEGINNING OF  
ANCHOR TRENCH

2:1 SLOPE

SEE NOTE 3

CONTROL LINE  
END OF LINER  
(FUTURE)

BENCH

FIGURE 18

CROSS SECTION FOR  
SLOPE STABILITY ANALYSIS

8" DIA SCH. 80  
PARALLEL PIPE

BREAK IN GRADE

PERIMETER BENCH/ROAD  
EDGE OF LINER AT  
BEGINNING OF  
ANCHOR TRENCH


5:1 SLOPE

ANCHOR TRENCH

2:1 SLOPE

CULVERT INLET

SECOND  
ANCHOR






FIGURE 19



# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 7 of 24  
 Chkd. By GSC Date 8/13/90 SLOPE STABILITY Proj. No. 89-977

CRITICAL INTERFACE ON 3:1 SLOPE IS ROUGHENED HDPE/  
 GEOCOMPOSITE,  $\phi = 24^\circ$  (SEE SHEET 21)

CRITICAL INTERFACE AT THE BOTTOM PART OF THE  
 LANDFILL: GEOTEXT / ROUGHENED HDPE,  $\phi = 15^\circ$ . (SEE  
 SHEET 21)

$$K_y \approx .33$$

CASE III - A(1)


K <sub>y</sub>	A	K <sub>y</sub> / A	U <sub>s</sub> * (INCHES)	U <sub>m</sub> = U <sub>s</sub> V <sup>2</sup> / 11800 A	V/ A	U <sub>m</sub> ** (INCHES)
.33	.5	.66	1	U <sub>m</sub> = .25 U <sub>s</sub>	30	.25
.33	.6	.55	2.6	U <sub>m</sub> = .30 U <sub>s</sub>	30	.80
.33	.7	.47	7	U <sub>m</sub> = .35 U <sub>s</sub>	30	2.45

\* FROM FIGURE 2.

\*\* PERVAZENT DISPLACEMENTS

# ENVIRONMENTAL SOLUTIONS, INC.

By J B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 8 of 24  
 Chkd. By GSC Date 8/13/90 SLOPE STABILITY Proj. No. 89-977



$$A = .62, \quad A_0 = \frac{A}{.8} \text{ (DEEP FAILURE MODE)}$$

$$A_0 = \frac{.61}{.8} = .76$$

OPERATION PERIOD: ABOUT 10 YEARS  
 FROM FIGURE 21  $POE < 6 \times 10^{-4}$  FOR 10 YEARS

## CONCLUSION

- STATIC FACTOR OF SAFETY  $2.54 > 1.5$  OK
- SEISMIC DISPLACEMENT 1-INCH FOR  $A_0 > .7$
- $POE < 6 \times 10^{-4}$  FOR 10 YEARS

CASE III - A.1




Figure 3. Probability of exceedance as a function of time period


FIGURE 20-A

# ENVIRONMENTAL SOLUTIONS, INC.

By JB Date 8/13/90 Subject B-18 LANDFILL Sheet No. 10 of 24  
 Chkd. By GSC Date 8/15/90 SLOPE STABILITY Proj. No. 89977

## CASE III - A.2

FAILURE THROUGH THE LINED SYSTEM AT THE BASE AND THROUGH THE WASTE AT BASE/SLOPE INTERSECTION



## PERFORMANCE CRITERIA


SAME AS CASE III - A.1

SLOPE STABILITY MODEL IS SHOWN IN FIGURE 20-A

COMPUTED FACTORS OF SAFETY ARE

FILE NOUE	S = STATIC E = EARTHQUAKE	FAILURE MODE	K (i)	SAFETY FACTOR	REMARKS
NH 7BL. 1S	S	BLOCK 2	0	3.10(2)	(1) HORIZONTAL EARTHQUAKE LOADING COEFFICIENT (2) STATIC (3) PSEUDOSTATIC
NH 7BL. 1E	E	BLOCK 2	0.30	1.37(3)	
NH 7BL. 2E	E	BLOCK 2	0.40	1.15(3)	
NH 7BL. 3E	E	BLOCK 2	0.49	1.0(3)	

CASE III - A.2



7483 7377

FIGURE 20-B



# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/14/90 Subject B-18 LANDFILL Sheet No. 12 of 24  
 Chkd. By SEC Date 8/15/90 SLOPE STABILITY Proj. No. 84-977


$K_y = .49$  (FROM SHEET 59-A, FILE NAME: NH7BL.3E)

CASE III - A.2

SEISMIC DISPLACEMENT

K <sub>y</sub>	A	$\frac{K_y}{A}$	U <sub>s</sub> * (INCHES)	$U_m = U_s \frac{V^2}{1,800 A}$	$\frac{V}{A}$	U <sub>m</sub> (INCHES)
.49	.5	.98	0	$U_m = .25 U_s$	30	0
.49	.6	.82	0	$U_m = .30 U_s$	30	0
.49	.7	.70	.8	$U_m = .35 U_s$	30	.28

\* FROM FIGURE 2



HIGHEST POTENTIAL

HEAD PEAK ACCELERATION

PEAK ACCELERATION (A)

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/14/90 Subject B-18 LANDFILL Sheet No. 13 of 24  
Chkd. By GC Date 8/15/90 SLOPE STABILITY Proj. No. 89-977

FOR 1 INCH DISPLACEMENT  $A > .7$

$A_0 > .7$

OPERATION PERIOD: ABOUT 10 YEARS

FROM FIGURE 20-C:  $POE < 6.0 \times 10^{-4}$

## CONCLUSION

STATIC SAFETY FACTOR  $> 1.5$

SEISMIC DISPLACEMENT:  $0$

$POE < 6.0 \times 10^{-4}$

CASE III-A-2




Figure 3. Probability of exceedance as a function of time period

FIGURE 20-C.

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 15 of 24  
Chkd. By GSC Date 8/13/90 SLOPE STABILITY ANALYSIS Proj. No. 89-977

CASE III - B

(CIRCULAR FAILURE THROUGH THE WASTE.)

III B - 1. NO COHESION ALLOWED FOR WASTE

III B - 2. COHESION ALLOWED FOR WASTE

(DESIGN PERIOD 10 YEARS)

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 16 of 24  
 Chkd. By GC Date 8/13/90 SLOPE STABILITY Proj. No. 89-977

## CASE III - B (1)

### PERFORMANCE CRITERIA

- MINIMUM STATIC FACTOR OF SAFETY: 1.5.
- MAXIMUM ALLOWABLE DISPLACEMENT FOR THE DESIGN EARTHQUAKE PEAK ACCELERATION > 6 INCHES
- SLOPE STABILITY MODEL IS SHOWN IN FIGURE 21

FACTORS OF SAFETY WERE COMPUTED USING TWO DIFFERENT STRENGTH PARAMETERS FOR THE WASTE

SHORT TERM       $C = 300 \text{ psf}$   
                           $\phi = 27^\circ$   
                           $\gamma = 115 \text{ pcf}$

LONG TERM       $C = 0$   
                           $\phi = 31^\circ$   
                           $\gamma = 115 \text{ pcf}$

HORIZONTAL EARTHQUAKE  
LOADING COEFFICIENT

MAY WASTE ELEV.	FILE NAME	FAILURE MODE	E-EARTHQUAKE S-STATIC	K	SAFETY FACTOR	(1) STATIC (2) PSEUDOSTATIC, USED TO ESTIMATE $K_y$ . REMARKS
810	KHICR.1S	CIRC12	S	0	1.33 (1)	WASTE $C=0, \phi=31^\circ$
810	KHICR.1E	CIRC12	E	.3	.80 (2)	" "
810	KHICR.2E	CIRC12	E	.20	.93 (2)	" "
810	KHICR.3E	CIRC12	E	.14	1.03 (2)	" "
810	KHICR.2S	CIRC12	S	0	1.5 (1)	WASTE $C=300 \text{ psf}, \phi=27^\circ$

CASE III - B




FIGURE 21

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject B-18 LAUDFILL Sheet No. 18 of 24  
 Chkd. By GSC Date 8/13/90 SLOPE STABILITY Proj. No. 89-977


$K_y = .145$  (FILE NAME: KHICR.3E)

CASE III - B(i)

K <sub>y</sub>	A	K <sub>y</sub> / A	U <sub>s</sub> * (INCHES)	V/ A	U <sub>m</sub> = $\frac{U_s V^2}{1800 A}$	U <sub>m</sub> (INCHES)
.145	.3	.48	6	30	U <sub>m</sub> = .15 U <sub>s</sub>	.90
.145	.4	.36	13	30	U <sub>m</sub> = .20 U <sub>s</sub>	2.60
.145	.5	.29	22	30	U <sub>m</sub> = .25 U <sub>s</sub>	5.50

\* FROM FIGURE 2

ALLOWABLE DESIGN DISPLACEMENT



# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/10/90 Subject B-18 LANDFILL Sheet No. 19 of 24  
Chkd. By GSC Date 8/13/90 SLOPE STABILITY Proj. No. 89-977

FOR SHALLOW FAILURE  $A = A_0$

DESIGN PERIOD = 10 YEARS

$A = .5$  FOR AN ALLOWABLE DESIGN PERMANENT  
DISPLACEMENT OF 6 INCHES

FROM FIGURE 22  $POE = 3.0 \times 10^{-3}$

## CONCLUSION

- 1 - STATIC FACTOR OF SAFETY = 1.3 < 1.5. SHALLOW FAILURE. CONSERVATIVE SINCE COHESION IS NOT ALLOWED FOR THE WASTE. IN REALITY, SOME COHESION (~300 PSF) SHOULD BE CONSIDERED FOR WASTE MATERIALS
- $K_v = .145$
- $POE = 3.0 \times 10^{-3}$  FOR 6-INCH DISPLACEMENT
- AN ALLOWABLE MAXIMUM DEFORMATION OF 6 INCHES IN THE WASTE PILE IS ACCEPTABLE BASED ON THE SLOPE CONFIGURATION AT THE TOE AND THE FACT THAT HIGHER FACTORS OF SAFETY WERE CALCULATED FOR THE CASE III-A.
- STATIC FACTOR OF SAFETY FOR  $C = 300$  PSF AND  $\phi = 27^\circ$  (WASTE) = 1.5 OK.



CASE III-b

$c=0$   
 $\phi=31^\circ$




Figure 3. Probability of exceedance as a function of time period

# ENVIRONMENTAL SOLUTIONS, INC.

By J.B Date 8/13/90 Subject B-18 LANDFILL Sheet No. 21 of 24  
 Chkd. By GSC Date 8/15/90 SCOPE STABILITY Proj. No. 89-977

CASE III - B(2) - COHESION ALLOWED FOR WASTE

$c = 300 \text{ psf}$   
 $\phi = 27^\circ$   
 $\gamma = 115 \text{ pcf}$

PERFORMANCE CRITERIA

SAUE AS III - B(1)

SCOPE STABILITY MODEL IS SHOWN IN FIGURE 2/

FACTORS OF SAFETY ARE AS FOLLOWS

MAX. WASTE ELEV.	FILE NAME	FAILURE MODE	E= EARTHQ. S= STATIC	(1) K	SAFETY FACTOR	REMARKS
810	KHICD.2S	CIRC2	S	0	1.5(2)	WASTE c = 300 psf $\phi = 27^\circ$
810	NHICR.2S	CIRC2	F	.3	.92(3)	
810	NHICR.3S	CIRC2	F	.24	1.0(3)	

(1) HORIZONTAL EARTHQUAKE LOADING COEFFICIENT


(2) STATIC

(3) PSEUDOSTATIC. A VALUE LESS THAN 1 DOES NOT NECESSARILY IMPLY FAILURE.

# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/13/90 Subject B-18 LANDFILL Sheet No. 22 of 24  
 Chkd. By GC Date 8/15/90 SLOPE STABILITY Proj. No. 89-977

## YIELD ACCELERATION



$K_y = .24$

CASE III - B(2)

$K_y$	A	$\frac{K_y}{A}$	$U_s^*$ (INCHES)	$\frac{V}{A}$	$U_m = \frac{U_s Y^2}{1,800 A}$	$U_m$ (INCHES)
.24	.3	.80	0	30	$U_m = .15 U_s$	0
.24	.4	.60	1	30	$U_m = .20 U_s$	.2
.24	.5	.48	6	30	$U_m = .25 U_s$	1.50

\* FROM FIGURE 2


# ENVIRONMENTAL SOLUTIONS, INC.

By J. B Date 8/13/90 Subject B-18 LANDFILL

Sheet No. 23 of 24

Chkd. By GSC Date 8/15/90 SLOPE STABILITY

Proj. No. 89-977



FOR SHALLOW FAILURE  $A = A_0$

FROM FIGURE 22X.

$A \approx .6$  FOR 6-INCH DISPLACEMENT CONSERVATIVE  
 $A = A_0$

POE =  $10^{-3}$  (DESIGN PERIOD 10 YRS)

## CONCLUSION

- STATIC FACTOR OF SAFETY 1.5
- ESTIMATED DISPLACEMENT FOR THE MCE = 0.5" < 6" OK
- DOE =  $10^{-3}$  (10 YRS)

CASE III - B(2)




Figure 3. Probability of exceedance as a function of time period

FIGURE 22-A



**HUSHMAND ASSOCIATES, INCORPORATED**  
Geotechnical, Earthquake and Environmental Engineers

**May 2, 2011**

Golder Associates Inc.  
230 Commerce, Suite 200  
Irvine, California, USA 92602  
Mr. Ryan Hillman, P.E.

**SUBJECT: SLOPE STABILITY ANALYSIS**  
KETTLEMAN HILLS FACILITY  
LANDFILL UNIT B-18, PHASE IIIA EXPANSION  
KETTLEMAN CITY, KINGS COUNTY, CALIFORNIA  
**HAI PROJECT NO. GLD-11-001**

This letter report summarizes the results of Hushmand Associates, Inc. (HAI) slope stability analyses for the proposed Phase IIIA temporary waste slopes of the Class I/II (hazardous and designated wastes) Landfill Unit B-18 at Chemical Waste Management (CWM) Kettleman Hills Facility (KHF). The KHF is located in Kettleman City, Kings County, California approximately one mile north of State Route 41 and 2.5 miles west of Interstate Freeway 5.

CWM is planning to construct the proposed Landfill B-18 Phase III expansion in 2 phases – Phase IIIA and Phase IIIB. The proposed final cover grades analyzed previously (HAI 2008 and 2009) are not changing; however, CWM has requested a static stability analysis be conducted for the temporary waste slope that would be formed at the Phase IIIA-IIIB interface.

This report presents the results of static slope stability evaluations for the most critical slope cross section of the temporary Phase IIIA expansion area of the landfill, identified and provided by Golder Associates Inc. (Golder). More details on the project background, project description, and regulatory requirements are provided in Golder's report (2011).

### **Material Properties**

Key material properties of various components of the landfill needed to perform static slope stability analyses are: (1) unit weight, and (2) shear strength parameters.

Detailed site-specific information on waste, existing liner systems, and foundation bedrock material properties are provided in the design and conformance testing reports prepared during early 1990's (Golder, 1990, 1991; ESI, 1990, 1992, 1993), and more recent reports prepared for Kettleman Hills Facility (Rust, 1998; URS, 2005; HAI, 2008, 2009). HAI (2008) recommended that assumed properties used for design be further verified by performing site-specific tests on the actual materials that would be used during construction. Golder performed site-specific laboratory testing on the proposed liner system materials for the landfill expansion area to verify the interface properties. The proposed Phase III liner system configuration is shown in Appendix

A. Interface shear strength testing was performed on the sandwich-like multilayer structure of the Phase III liner system. The test results indicated that the weakest interface was the double sided (DS) geocomposite and 60-mil textured HDPE geomembrane for all applied normal loads. The peak interface shear strength properties were measured as approximately  $\phi = 26^\circ$  and  $C = 0$ . Additional testing also confirmed these results. Appendix A provides results of the interface shear tests performed on the Phase III proposed liner system materials. To be conservative reduced shear strength properties of  $\phi = 22^\circ$  and  $C = 0$  were chosen for this static slope stability analyses. The material properties of the waste and liner interfaces used in the static stability analyses of Phase IIIA temporary slopes are shown in Table 1.

**Table 1. Selected Material Properties for Static Stability Analysis**

Material/Interface	Unit Weight	$\phi$ (degree)	C (psf)
HW <sup>1</sup>	115 pcf	31	0
Bedrock <sup>1</sup>	150 pcf	40	800
Expansion Area Liner Interface <sup>2</sup>	----	22	0

- (1) Environmental Solutions, Inc. (1990, 1992, 1993); Rust Environmental & Infrastructure, Inc. (1998); URS (2005).
- (2) Golder Associates, Inc. (2011).

### Stability Analysis

Conventional two-dimensional (2-D) limit-equilibrium stability analyses were performed for the existing bottom/side slope liner and waste fill slopes using landfill cross section B-B' (see Figure 1). The computer program GSTABL7 v. 2.005 developed by Gregory Geotechnical Software was used to calculate the factors of safety against potential failure. The program uses 2-D limit equilibrium theory to provide general solutions for slope stability problems with provisions of using the Modified Bishop, Modified Janbu, or Spencer Methods. Both circular and non-circular potential sliding surfaces can be prespecified or randomly generated. The Spencer, and Modified Janbu methods were used for this study. The minimum factor of safety was obtained by varying the initiation and exit points of the trial failure planes.

The Modified Janbu Method of analysis, which normally provides conservative results, was initially used to evaluate a large number of potential failure mechanisms for each cross section analyzed. At least hundred (100) potential failure surfaces are randomly generated by the program and the most critical surface resulting in the lowest factor of safety is identified. The most critical failure plane determined by the Modified Janbu Method is then reanalyzed using the Spencer Method. This method satisfies both force and moment equilibrium and thus provides more realistic (usually higher) estimates of the factors of safety. The Janbu method is generally more conservative compared with the more rigorous Spencer Method and typically results in lower factors of safety than the Spencer Method.

The GSTABL7 output plots, presented in Appendix B, illustrate the 2-D cross section, various potential failure surface conditions considered, and the most critical failure surfaces analyzed in the stability analysis of the proposed landfill temporary fill slopes. The failure surface with the lowest factor of safety is identified with two arrows at its initiation and termination points. The factor of safety for the most critical potential failure plane (a deep failure plane along the Phase IIIA liner) computed using Spencer method was equal to 1.52.

### **Conclusion**

This report addresses static stability of the landfill slopes for the proposed temporary Phase IIIA fill configuration of the Landfill B-18. The presented analyses demonstrated that computed static factors of safety is higher than 1.5 for the analyzed section. The analyses indicated that the proposed Phase IIIA temporary landfill configuration would result in a stable configuration under static loading conditions in compliance with applicable regulations.

### **Closure**

We trust this report meets your present requirements. If you have any questions regarding this report, please contact this office at your convenience. We appreciate this opportunity to provide our professional services to Golder.

Sincerely yours,

Very truly yours,

**HUSHMAND ASSOCIATES, INC.**



Naz Mokarram, Ph.D.  
Senior Staff Engineer


Ben Hushmand, Ph.D., P.E. 44777  
President, Principal Engineer



## **References**

- Environmental Solutions, Inc., 1990. "Engineering and Design Report, Landfill Unit B-18, Phase I and II and Final Closure, Kettleman Hills Facility, Kings County, California, Volumes I and II," report prepared for Chemical Waste Management, Inc., August.
- Environmental Solutions, Inc., 1992. "Backup Calculations Supporting the Interface testing Program for Landfill Unit B-18, Kettleman Hills Facility, Kings County, California," report prepared for Chemical Waste Management, Inc., February.
- Environmental Solutions, Inc., 1993. "Revised Intermediate Waste Fill Plan, Landfill Unit B-18, Phase I, Kettleman Hills Facility, Kings County, California, Volumes I and II," report prepared for Chemical Waste Management, Inc., August.
- Golder Associates, Inc. (1990) "Direct Shear Testing Program for Landfill Cover Design, Kettleman Hills Facility", June 29, 1990.
- Golder Associates, Inc. (1991) "Landfill B-19, Phase IA Redesign and Closure Plan, Kettleman Hills Facility, Kettleman City, California," Volumes I-IV, April 15, 1991.
- Golder Associates, Inc. (2011) "Engineering and Design Report, Landfill Unit B-18, Kettleman Hills Facility, Kettleman City, California" Report to Kettleman Hills Facility.
- Hushmand Associates, Inc. (2008) "Slope Stability Analysis Report, Kettleman Hills Facility, Hazardous Waste Landfill Unit B-18 Expansion, Kettleman City, Kings County, California," Report to Kettleman Hills Facility, September.
- Hushmand Associates, Inc. (2009) "Addendum Report- Slope Stability Analysis, Kettleman Hills Facility, Hazardous Waste Landfill Unit B-18 Expansion, Kettleman City, Kings County, California," Report to Kettleman Hills Facility, December.
- Rust Environment & Infrastructure, Inc., 1997 (Rev 1: 1998) "Preliminary Stability Evaluation, Municipal Solid Waste Landfill Unit B-19, Kettleman Hills Facility, Kettleman City, Kings County, California," Technical Report prepared for Chemical West Management, Inc., July.
- URS (2005) "Preliminary Stability Analyses, Kettleman Hills Facility Expansion, Kettleman City, California," prepared for Chemical West Management, Inc.

# FIGURES




PHASE IIIA  
WASTE FILL PLAN  
(SHADED)

**LANDFILL B-18**

LIMIT OF  
PROPOSED  
PHASE IIIA  
LLINER

TEMPORARY LANDFILL  
ACCESS ROAD

EXISTING LIMIT  
B-18 LANDFILL  
860.4




PROJECT		<b>CHEMICAL WASTE MANAGEMENT B-18 CLASS I LANDFILL KETTLEMAN HILL FACILITY</b>	
TITLE		<b>PHASE IIIA FILL PLAN</b>	
PROJECT No.	FILE No.		
DESIGN KJK 5/4/2011	SCALE	REV.	
CADD KJK 5/4/2011			
CHECK RH 5/4/2011			
REVIEW -- 5/4/2011			
		<b>FIGURE 1</b>	

BASE TOPOGRAPHY FLOWN BY AERIAL MAPPING SERVICES, INC., MARCH 14, 2011 (NAD 27).

**APPENDIX A**

**INTERFACE SHEAR TEST**  
**RESULTS**

TEST CONFIGURATION 1



TEST CONDITIONS:

SAMPLE PREPARATION:

- Specimens were cut along machine direction to 14" x 17" for the upper box, and 14" x 19" for the lower box, with an effective test area of 12" x 12".
- The Maximum Dry Density (MDD) of the soil is **111.8 pcf** at **16.4%** Optimum Moisture Content (OMC).
- Soil specimen was remolded to **102.86 pcf**; i.e., **92.0%** of MDD at **20.5%** moisture content. (forming 2 inch layer in the TOP and BOTTOM boxes).
- The three intermediate geosynthetic specimens were floating during shear run.

CONSOLIDATION:

- Each set of specimen was consolidated under **Dry** condition for **24 hrs** @ normal load before shearing.
- Normal loads were applied using **Hydraulics** for the highest load, **Bladder** for the intermediate and lowest loads.

SHEAR TEST:

- Shear test was conducted @ **0.040** in/min.
- Sheared @ minimi **3.0** inch horizontal displacement.
- Test specimens were sheared i **Dry** condition.
- Test were performed in general accordance with ASTM D6243 / ASTM D5321 using Brainard-Kilman LG-112 Direct Shear machine with effective test area of 12 in X 12 in.



TEST RESULTS:

Normal Stresses Applied		Asperity Heights (C#44500)				Asperity Heights (C# 44501)				Moisture Content (Soil)		PEAK STRENGTH		POST- PEAK STRENGTH AT 3.0 INCHES	
		UP		DOWN		UP		DOWN				Shear Stress (psf)	Secant Angle (degrees)	Shear Stress (psf)	Secant Angle (degrees)
		Before	After	Before	After	Before	After	Before	After						
(psi)	(psf)	(mils)	(mils)	(mils)	(mils)	(mils)	(mils)	(mils)	(mils)	(%)	(%)	(psf)	(degrees)	(psf)	(degrees)
34.7	5,000	23.7	23.1	24.4	23.2	23.5	19.4	24.4	23.7	20.5	18.6	2,709	28	1,148	13
69.4	10,000	23.7	22.9	23.7	22.3	22.9	17.7	24.3	22.1	20.5	19.8	4,737	25	2,032	11
104.2	15,000	24.6	22.8	25.3	24.6	24.8	16.3	24.0	23.0	20.5	20.1	7,953	28	3,283	12
<b>Note:</b> N/A - Not Applicable		<b>COHESION (psf) :</b>										<b>0</b>		<b>19</b>	
		<b>COEFFICIENT OF FRICTION :</b>										<b>0.52</b>		<b>0.21</b>	
		<b>FRICTION ANGLE (degrees) :</b>										<b>27.7</b>		<b>12.1</b>	

NOTE: The friction angles and cohesion results given here are based on mathematically determined best fit line.


OBSERVATIONS:

- No tilting of the system or any abnormalities observed during and after the test.
- Superficial abrasion on the geosynthetics interfacing sides (typical to all loads).
- Sliding occurred between the DS Geocomposite (C# 62070) and 60 mil HDPE (C# 44501) on all loads. See attached photos (907-1-15,000 psf / 907-1-10,000 psf / 907-1-5,000 psf).




**TABLE 1-A**  
**CLIENT: GOLDER & ASSOCIATES**  
**PROJECT: KETTLEMAN HILLS**

INTERFACE SHEAR TEST RESULT (ASTM D5321/6243)  
 PGL Job No. G091078

Reviewed By:   
 Date: 19-Oct-09

**TEST CONFIGURATION**     **1-A**



**TEST CONDITIONS:**

**SAMPLE PREPARATION:**

- Specimens were cut along machine direction to 14" x 17" for the upper box, and 14" x 19" for the lower box, with an effective test area of 12" x 12".
- Geosynthetic specimens were secured via flat bar clamping mechanisms complete with bolts and nuts (7-pairs).

**CONSOLIDATION:**

- The specimen was consolidated under **Dry** condition for **2 hrs** @ normal load before shearing.
- Normal load was applied using **Bladder**

**SHEAR TEST:**

- Shear test was conducted @ **0.04** in/ min.
- Sheared @ minimum **3.0** inch horizontal displacement.
- The test specimens were sheared at **Dry** condition .
- Test were performed in general accordance with ASTM D6243 / ASTM D5321 using Brainard-Kilman LG-112 Direct Shear machine with effective test area of 12 in X 12 in.


**TEST RESULTS:**

Normal Stresses Applied		Asperity Heights mils		PEAK STRENGTH		POST- PEAK STRENGTH AT <u>3.0</u> INCHES	
				Shear Stress	Secant Angle	Shear Stress	Secant Angle
(psi)	(psf)	Before	After	(psf)	(degrees)	(psf)	(degrees)
69.44	10,000	25.5	18.4	4940	26	2135	12

**OBSERVATIONS:**


- No tilting of the system or any abnormalities observed during and after the test.
- Superficial abrasion on the geosynthetics interfacing sides (typical to all loads).
- Sliding occurred between the two interfacing surfaces.

**Figure #2**  
**Shear Stress/ Displacement Curve**




**TABLE 1-B**  
**CLIENT: GOLDER & ASSOCIATES**  
**PROJECT: KETTLEMAN HILLS**

INTERFACE SHEAR TEST RESULT (ASTM D5321/6243)  
PGL Job No. G091078

Reviewed By:   
Date: 19-Oct-09

**TEST CONFIGURATION 1-B**



**TEST CONDITIONS:**

**SAMPLE PREPARATION:**

- Specimens were cut along machine direction to 14" x 17" for the upper box, and 14" x 19" for the lower box, with an effective test area of 12" x 12".
- Geosynthetic specimens were secured via flat bar clamping mechanisms complete with bolts and nuts (7-pairs).

**CONSOLIDATION:**

- The specimen was consolidated under **Dry** condition for **2 hrs** @ normal load before shearing.
- Normal load was applied using **Bladder**

**SHEAR TEST:**

- Shear test was conducted @ **0.04** in/ min.
- Sheared @ minimum **3.0** inch horizontal displacement.
- The test specimens were sheared at **Dry** condition .
- Test were performed in general accordance with ASTM D6243 / ASTM D5321 using Brainard-Kilman LG-112 Direct Shear machine with effective test area of 12 in X 12 in.


**TEST RESULTS:**

Normal Stresses Applied		Asperity Heights		PEAK STRENGTH		POST- PEAK STRENGTH AT <u>3.0</u> INCHES	
		mils		Shear Stress	Secant Angle	Shear Stress	Secant Angle
(psi)	(psf)	Before	After	(psf)	(degrees)	(psf)	(degrees)
69.44	10,000	<b>24.8</b>	<b>19.3</b>	4903	26	2282	13

**OBSERVATIONS:**

- No tilting of the system or any abnormalities observed during and after the test.
- Superficial abrasion on the geosynthetics interfacing sides (typical to all loads).
- Sliding occurred between the two interfacing surfaces.


**Figure #2**  
**Shear Stress/ Displacement Curve**





@ 15,000 psf





@ 10,000 psf




@ 5,000 psf

## **APPENDIX B**

# **SLOPE STABILITY ANALYSIS PLOTS**

# Kettleman Hills Landfill B-18 Phase IIIA Interim Slope

z:\projects-proposals-laboratory\hai2011\2011 projects\waste management\khfb-b\p3jan1-22.pl2 Run By: NM, HAI 4/29/2011 03:18PM




GSTABL7 v.2 FSmin=1.250

Safety Factors Are Calculated By The Simplified Janbu Method



# Kettleman Hills Landfill B-18 Phase IIIA Interim Slope

z:\projects-proposals-laboratory\hai2011\2011 projects\waste management\khfb-b\p3spen1-22.plt Run By: NM, HAI 4/29/2011 03:28PM



GSTABL7 v.2 FSmin=1.521

Factor Of Safety Is Calculated By GLE (Spencer`s) Method (0-2)



**APPENDIX H.5**  
**FINAL CLOSURE STABILITY**



**HUSHMAND ASSOCIATES, INCORPORATED**  
Geotechnical, Earthquake and Environmental Engineers

## **SLOPE STABILITY ANALYSIS REPORT**

# **KETTLEMAN HILLS FACILITY HAZARDOUS WASTE LANDFILL UNIT B-18 EXPANSION KETTLEMAN CITY, KINGS COUNTY, CALIFORNIA**

Prepared for:

Chemical Waste Management, Inc.  
Kettleman Hills Facility, 35251 Old Skyline Road  
Kettleman City, California 93239

Prepared by:

Hushmand Associates, Inc.  
250 Goddard  
Irvine, California 92618

September 2008



**HUSHMAND ASSOCIATES, INCORPORATED**  
Geotechnical, Earthquake and Environmental Engineers

September 15, 2008

Golder Associates Inc.  
230 Commerce, Suite 200  
Irvine, California, USA 92602

Attn: Mr. Scott Sumner, P.E.  
Principal

**SUBJECT: SLOPE STABILITY ANALYSIS REPORT  
KETTLEMAN HILLS FACILITY  
HAZARDOUS WASTE LANDFILL UNIT B-18 EXPANSION  
KETTLEMAN CITY, KINGS COUNTY, CALIFORNIA  
HAI PROJECT No. 08-0228**

Dear Mr. Sumner:


Hushmand Associates, Inc. (HAI) is pleased to submit to Golder Associates, Inc. (Golder) four (4) copies of the slope stability evaluation report for the Class I/II hazardous waste landfill unit B-18 (Landfill B-18) expansion at Waste Management, Inc. (WMI) Kettleman Hills Facility.

We trust this report meets your present requirements. If you have any questions regarding this report, please contact this office at your convenience. We appreciate this opportunity to provide our professional services to Golder.

Sincerely yours,

HUSHMAND ASSOCIATES, INC.

Ben Hushmand, PhD, PE 44777  
President, Principal Engineer



S. Ali Bastani, PhD, PE,  
Vice President, Principal Engineer





## TABLE OF CONTENTS

	<u>Page</u>
INTRODUCTION.....	1
1.1 GENERAL.....	1
1.2 BACKGROUND AND PROJECT DESCRIPTION.....	2
1.2.1 Background.....	2
1.2.2 Project Description and Scope.....	2
1.3 REGULATORY REQUIREMENTS FOR STATIC AND SEISMIC STABILITY.....	3
2.0 SITE DESIGN GROUND MOTIONS.....	4
2.1 PREVIOUS SITE DESIGN GROUND MOTIONS.....	4
2.2 SITE DESIGN GROUND MOTIONS UPDATE.....	5
2.2.1 Site Design Response Spectra.....	5
2.2.2 Design Ground Motions.....	6
2.3 LIQUEFACTION.....	8
2.4 SEISMIC SETTLEMENT.....	8
3.0 SLOPE STABILITY AND LANDFILL DISPLACEMENT ANALYSIS.....	9
3.1 GENERAL.....	9
3.2 LANDFILL GEOMETRY AND ANALYSIS SECTIONS.....	9
3.3 LANDFILL LINER DESIGN.....	10
3.4 MATERIAL PROPERTIES.....	10
3.5 ANALYSIS APPROACH.....	12

3.6 STATIC AND PSEUDO-STATIC STABILITY ANALYSES.....13

3.6.1 Liner and Waste Mass Static Stability.....14

3.6.2 Pseudo-Static Stability Analyses.....14

3.7 SEISMIC DEFORMATION ANALYSES.....15

3.7.1 Simplified Analysis of Landfill Slopes Seismic Deformations .....15

3.7.2 Site Response and Newmark Slope Deformation Analyses .....17

3.8 STATIC AND SEISMIC STABILITY OF FINAL COVER.....19

4.0 CONCLUSIONS.....21

5.0 REFERENCES.....22

**TABLES**

Table 1 Selected Material Properties for Static and Seismic Stability Analyses

Table 2 Summary of Slope Stability Analysis Results

Table 3 Results of Simplified Seismic Deformation Analyses for Landfill Liner

Table 4 Seismically-Induced Permanent Displacements from Newmark Deformation Analyses (Cross Section D-D', Failure Surface 1 along Landfill Liner)

Table 5 Seismically-Induced Permanent Displacements from Newmark Deformation Analyses (Cross Section F-F', Failure Surface 3 along Landfill Liner)

Table 6 Seismically-Induced Permanent Displacements from Newmark Deformation Analyses (Cross Section D-D', Cover Analysis)

**FIGURES**

Figure 1 Proposed B-18 Landfill Liner Grades

Figure 2 Proposed B-18 Landfill Final Grading

Figure 3 Analysis Cross Sections A-A', B-B', C-C' and Potential Failure Planes

Figure 4 Analysis Cross Sections D-D', E-E', F-F' and Potential Failure Planes

Figure 5 5-Percent Damped Site Design Response Spectra for Near-Field and Far-Field Earthquakes

Figure 6 Original Horizontal Acceleration Record & Response Spectrum Matched to Design Response Spectrum – 1994 Northridge Eq. Castaic 090

Figure 7 Original Corrected Time Histories – 1994 Northridge Earthquake Station: Castaic Old Ridge\_090

## **FIGURES (continued)**

- Figure 8 Spectrum Compatible Time Histories – 1994 Northridge Earthquake Station: Castaic Old Ridge\_090
- Figure 9 Original Horizontal Acceleration Record & Response Spectrum Matched to Design Response Spectrum – 1989 Loma Prieta Eq. Gilroy Array 090 Record
- Figure 10 Original Corrected Time Histories – 1989 Loma Prieta Eq. Record Station: Gilroy Array 090
- Figure 11 Spectrum Compatible Time Histories – 1989 Loma Prieta Eq. Station: Gilroy Array 090
- Figure 12 Original Horizontal Acceleration Record & Response Spectrum Matched to Design Response Spectrum – 1994 Northridge Eq. Pacoima Kagel Canyon 360 Record
- Figure 13 Original Corrected Time Histories – 1994 Northridge Eq. Record Station: Pacoima Kagel Canyon 360 Record
- Figure 14 Spectrum Compatible Time Histories – 1994 Northridge Eq. Station: Pacoima Kagel Canyon 360 Record
- Figure 15 Original Horizontal Acceleration Record & Response Spectrum Matched to Design Response Spectrum – 1999 Chi Chi Eq. CHY042 N Record
- Figure 16 Original Corrected Time Histories – 1999 Chi Chi Eq. Record Station: CHY042 N
- Figure 17 Spectrum Compatible Time Histories – 1999 Chi Chi Eq. Station: CHY042 N
- Figure 18 Proposed Landfill Liner System
- Figure 19 Shear Modulus Reduction and Damping (Hazardous Waste) and Clay (Liner) Used in This Study
- Figure 20a Section D-D', Finite Element (Quad4M) Mesh
- Figure 20b Section F-F', Finite Element (Quad4M) Mesh
- Figure 20c Section D-D', Finite Element (Quad4M) Mesh
- Figure 21 Earthquake Induced Displacements, Section D-D' – Failure Plane 1  
2-D Quad4m Dynamic Response Analysis (Previous Ground Moutions)
- Figure 22 Earthquake Induced Displacements, Section D-D' – Failure Plane 1  
2-D Quad4m Dynamic Response Analysis (Recent Ground Moutions)
- Figure 23 Earthquake Induced Displacements, Section F-F' – Failure Plane 3  
2-D Quad4m Dynamic Response Analysis (Previous Ground Moutions)
- Figure 24 Earthquake Induced Displacements, Section F-F' – Failure Plane 3  
2-D Quad4m Dynamic Response Analysis (Recent Ground Moutions)
- Figure 25 Proposed Landfill Final Cover

## **APPENDICES**

- Appendix A Figures from ESI 1993 and RUST 1998 Reports (Design Earthquake Ground Motions and Landfill Liner Systems)
- Appendix B Slope Stability Analysis Results
- Appendix C Static and Seismic Stability of Final Cover

# **SLOPE STABILITY ANALYSIS REPORT**

## **KETTLEMAN HILLS FACILITY HAZARDOUS WASTE LANDFILL UNIT B-18 EXPANSION KETTLEMAN CITY, KINGS COUNTY, CALIFORNIA**

### **1.0 INTRODUCTION**

#### **1.1 GENERAL**

This report summarizes the results of Hushmand Associates, Inc. (HAI) slope stability analyses for the proposed expansion of the existing Class I/II (hazardous and designated wastes) Landfill Unit B-18 at Chemical Waste Management (CWM) Kettleman Hills Facility (KHF). The KHF is located in Kettleman City, Kings County, California approximately one mile north of State Route 41 and 2.5 miles west of Interstate Freeway 5.

In 2005, URS Corporation (URS) prepared a stability analysis report as part of an Environmental Impact Report (EIR) for the proposed Landfill Unit B-18 expansion (URS, 2005). To improve the proposed landfill expansion design, Golder Associates, Inc. (Golder) recently proposed some modifications to the URS final fill plan (Golder, 2008a, 2008b). These modifications required additional slope stability evaluations to demonstrate conformance of the proposed revised fill plan with regulatory requirements. A preliminary slope stability analysis report was then prepared by HAI (2008) in support of the EIR preparation for the proposed landfill expansion (CH2M Hill, 2008).

This report provides detailed stability evaluations for design of the revised landfill expansion fill plan, and is an appendix to a comprehensive design report prepared by Golder for the proposed landfill expansion (Golder, 2008b). The scope of this report is to evaluate static and seismic slope stability for the proposed Landfill Unit B-18 expansion fill plan configuration geometry as provided by Golder. Stability of landfill liner and waste slopes were analyzed to meet the design criteria discussed in Section 1.3. More details on the project background, project description, and regulatory requirements are provided in the landfill expansion EIR and design report (CH2M Hill, 2008; Golder, 2008b).

The following sections discuss the site design criteria, design earthquake motions, material properties used in static and pseudo-static slope stability and seismic deformation analyses, static slope stability and seismic deformation analysis methods, and results of the analyses.

## **1.2 BACKGROUND AND PROJECT DESCRIPTION**

### **1.2.1 Background**

The presently permitted design of the Class I/II Landfill Unit B-18 was developed in 1990 based on the results of detailed seismicity and static and dynamic slope stability analyses (Environmental Solutions, Inc. [ESI], 1990 and 1992). The landfill was constructed in two phases in early 1990's, designated as Phases I and II (see Figure A-1 of Appendix A) with corresponding leachate collection and removal systems (LCRSs). The existing liner systems in the Phase I and II areas meet applicable California Code of Regulations (CCR) Title 22 requirements. The configuration of the final fill plan for the 1990 design and existing liner systems for the landfill Phases I and II are provided in Appendix A (Figures A-2 to A-4).

### **1.2.2 Project Description and Scope**

The CWM has proposed to expand the existing Class I/II Landfill Unit B-18 to provide an additional 5.0 million cubic yards of air space for a total capacity of approximately 15.7 million cubic yards. The proposed expansion design modifications to the 1990 ESI landfill liner grades and final grading plans includes expansion of the landfill footprint (mainly to the west and northwest of the site) requiring placement of approximately 12 acres of new composite liner, and increasing the landfill height and slope steepness (Figures 1 and 2, respectively). The expansion will also require rerouting of surface water and development of a new lined retention basin southeast of the landfill. Expansion of the site requires performing new analyses to demonstrate its conformance with applicable federal and state regulations for design of Class I/II landfills. These analyses include:

- Updating site seismicity and design ground motions using the recent attenuation relationships,
- Static and seismic stability of landfill slopes and liner system for final fill configuration,
- Landfill final cover stability, and
- Waste settlement and its effects on landfill final cover performance.

This report addresses the first three analysis items listed above (seismicity and ground motions, static and seismic stability of landfill slopes and liner system, and landfill final cover stability) and includes effects of increased landfill height and slope steepness on stability evaluations. The stability report presented here will be included as part of the Design Report being prepared by Golder for the proposed landfill expansion evaluation. The design issues associated with the landfill settlement and its effects on landfill cover performance are addressed in the Design Report.

The proposed final fill plan and landfill cover grades modified from the 1990 ESI final fill plan design are shown in Figure 2. A preliminary fill plan for the proposed Landfill B-18 expansion was initially developed, which was then refined based on the results of slope stability analysis iterations to arrive at the final fill plan design shown in Figure 2. Locations and configurations of the cross sections, which were evaluated for stability, are shown in Figures 1 through 4.

### **1.3 REGULATORY REQUIREMENTS FOR STATIC AND SEISMIC STABILITY**

The existing Class I/II Landfill B-18 was designed in accordance with applicable regulations in CCR Titles 22 and 23 and the specific conditions in the site hazardous waste facility permit. CCR Titles 22 and 23 require consideration of the Maximum Credible Earthquake (MCE) for Class I landfills.

MCE is defined by California Geological Survey (CGS) as “the maximum earthquake that appears capable of occurring under the presently known tectonic framework.” Thus, for stability evaluations of the expanded Landfill Unit B-18, the MCE is used as the design earthquake and is evaluated for faults determined to produce potentially damaging ground motions at the site. Near- and far-field seismic events are evaluated to assure that both higher intensity and lower intensity earthquakes are considered. Near-field events at this site generate shorter duration, higher intensity, and higher frequency ground shaking compared to far-field earthquakes that result in longer duration but lower intensity and lower frequency ground shaking.

For seismic stability, the present state-of-the-practice is to estimate landfill slope displacements for design earthquakes, using a Newmark (Newmark, 1965) equivalent method, and demonstrate that they are below an allowable value that maintains the integrity of the landfill. Current engineering practice for slope stability evaluation along the landfill liner is to allow a maximum seismically-induced permanent slope displacement of six to twelve inches to correspond to acceptable performance for well-designed liner systems (Seed and Bonaparte, 1992). Class I landfills at KHF are designed to meet the lower bound displacement (more conservative) by limiting the maximum allowable slope displacement along the landfill liner to only six inches, which is also used in the design of the Class I/II Landfill Unit B-18 in this report. The criteria commonly used for landfill cover design, which allows a maximum seismically-induced permanent displacement of up to twenty four inches (2 feet) of the final covers, is based on the understanding that these would be relatively easily accessible and thus quickly repairable in the event of damage by a major seismic occurrence.

## **2.0 SITE DESIGN GROUND MOTIONS**

### **2.1 PREVIOUS SITE DESIGN GROUND MOTIONS**

A detailed discussion of the site geology, faulting, and seismicity was presented in the design report prepared for Landfill Unit B-18 (ESI, 1990) and more recent reports prepared for Landfill Unit B-19 at Kettleman Hills Facility (Rust Environment & Infrastructure [Rust], 1998; URS, 2005; HAI, 2006). Deterministic and probabilistic seismic hazard evaluations of the site were performed by Rust (1998), and also independently by William Lettis & Associates (WLA), reported as Appendix A of the 1998 Rust report. The ground motions and seismic design parameters presented in the 1998 Rust report were used in the 2005 URS and 2006 HAI reports, which were also used in the preliminary seismic deformation analyses performed for the Landfill B-18 expansion EIR preparation (HAI, 2008a). The following summarizes results of the 1998 seismic ground shaking evaluations and the selected ground motions used in two-dimensional seismic response analyses at the KHF site:

- The closest seismic sources to the site are segments of the blind Ramp Thrust Fault that is present beneath the site at approximate distances of 8 to 27 km, while the most active sources in the site area are associated with the San Andreas Fault zone at a distance of about 35 km from the site.
- No evidence of fault rupture hazard is known to exist at the project site (i.e., within 200 feet of Landfill Unit B-18).
- The Ramp Thrust Kettleman Hills North Dome segment (Magnitude [ $M_w$ ] 6.6) of the blind Ramp Thrust faults and the San Andreas Slack Canyon-Cajon Pass segment ( $M_w$  7.8) will produce the highest near-field and far-field ground motions at the site, respectively. The MCE's associated with these faults were selected as the site design events.
- The deterministic values of peak horizontal ground accelerations (PHGA) for the near-field and far-field design events were estimated as 0.57g and 0.21g, respectively. The calculated PHGA of 0.57g approximately corresponds to an average probabilistic return period of 1,000 years (RUST, 1998).
- Duration of ground shaking is a major factor influencing the level of seismic-induced slope displacements. Empirical relations are available that provide an estimate of earthquake shaking duration as a function of earthquake magnitude, distance, and site condition (Abrahamson and Silva, 1996). Using the Abrahamson and Silva empirical relationship the ground shaking duration for Landfill Unit B-18, which is characterized as rock site, is estimated to be about 10 seconds and 32 seconds for the near-field design event ( $M = 6.6$ ,  $r = 10$  km) and far-field design event ( $M = 7.8$ ,  $r = 35$  km), respectively. Duration of the ground shaking was used in the simplified Newmark-type seismic deformation analyses for the proposed site expansion EIR (HAI, 2008a).

- One “distant” (far-field) and three “local” (near-field) earthquake records were selected and scaled to correspond to the design peak horizontal accelerations in rock as design input motions. These records have a peak acceleration, frequency content, and duration representative of the expected earthquake motions at the site. The selected records were:
  - 1) Caltech A-1 synthetic acceleration time history simulating a M 8+ earthquake on the San Andreas Fault, scaled to peak amplitude 0.21g,
  - 2) Seed-Hayward synthetic acceleration time history simulating a M ~ 7 earthquake matched to the site design response spectrum to approximate the near-field MCE,
  - 3) Castaic Old Ridge Route, sedimentary rock outcrop, Ch 1 (90 deg Component) acceleration record from the 1994 ( $M_w \approx 6.7$ ) Northridge, California earthquake scaled to a peak amplitude of 0.57g, and
  - 4) Pacoima-Kagel Canyon, sedimentary rock outcrop, Ch 3 (360 deg Component) acceleration record from the 1994 ( $M_w \approx 6.7$ ) Northridge, California earthquake scaled to a peak amplitude of 0.57g.

Details of the above site design earthquake parameters derivation, including figures illustrating time histories of the selected acceleration records and a comparison of their response spectra with the site design response spectrum are provided in the 1998 Rust report. The 1998 ground motion time history and response spectrum plots are also provided in Appendix A of this report. These acceleration time histories were adjusted by scaling the peak ground acceleration (PGA).

## **2.2 SITE DESIGN GROUND MOTIONS UPDATE**

### **2.2.1 Site Design Response Spectra**

Deterministic seismic hazard analyses (DSHA) were performed for the Ramp Thrust Kettleman Hills North Dome segment of the blind Ramp Thrust faults (Great Valley Fault, Segment 14) and an earthquake scenario similar to the San Andreas 1857 earthquake using the latest attenuation relationships and the site faulting and seismicity data. As discussed above, these faults produce the highest near-field and far-field ground motions at the site, respectively. The MCE’s associated with these faults were selected as the site design events. The MCE magnitude and closest source to site distance for these faults were updated based on the latest information on the site faulting and seismicity. For the near-field source two different fault geometry models were used in the analyses. The first one was based on the fault database developed for the 2008 update of the national seismic hazard maps (Petersen et al., 2008) representing the site with averaged seismicity parameters from adjacent faults around the site, while the second one was based on an older but site-specific local seismicity investigation (Stein and Ekstrom, 1992; Ekstrom et al., 1992). The magnitude and distance values used in the deterministic seismic hazard analyses were:

- Ramp Thrust Kettleman Hills North Dome:
  - (Case 1)  $M_w \cong 7$ ,  $R_x \cong 6.5$  km,  $R_{rup} \cong 10$  km, Rupture Width  $\cong 38.4$  km, Top of Rupture  $\cong 8.1$  km, and Dip Angle  $\cong 22$  degrees (Petersen et al., 2008)



- (Case 2)  $M_w \cong 7$ ,  $R_x \cong 8$  km,  $R_{rup} \cong 8$  km, Rupture Width  $\cong 17$  km, Top of Rupture  $\cong 6$  km and Dip Angle  $\cong 45$  degrees (Stein and Ekstrom, 1992; Ekstrom et al., 1992)
- San Andreas 1857 Earthquake:  $M_w \cong 8$  and Distance  $\cong 35$  km (Petersen et al., 2008)

For the near-field source, using the above fault geometries, initially two different deterministic design response spectra were developed, and then the site final design response spectrum was generated by averaging these two response spectra. Based on the subsurface geology and results of exploratory borings drilled at the site (ESI, 1990; Rust, 1998), ground motion evaluations for the project site were performed using four recently developed attenuation relationships for an average shear wave velocity of approximately 760 m/s (~ 2500 ft/sec) estimated for the upper 30 meters (~ 100 feet) of the site.

Attenuation relationships describe the relation of ground motion levels with earthquake magnitude and distance (closest distance between site and earthquake rupture plane). These empirical relationships are used to describe the variation of response spectral accelerations at specific structural periods of vibration and damping ratios with earthquake magnitude and distance, and to incorporate the local geologic conditions and the near-source effects. The selected attenuation relationships are based on the Next Generation Attenuation (NGA) relationships as listed below:

- Abrahamson and Silva, 2008
- Campbell and Bozorgnia, 2008
- Boore and Atkinson, 2007
- Chiou and Young, 2006

Figure 5 presents the estimated site design response spectra for the near-field and far-field seismic sources (Ramp Thrust Kettleman Hills North Dome and San Andreas faults, respectively). Based on this figure, the deterministic values of PHGA for the near-field and far-field design events were estimated as 0.62g and 0.16g, respectively.

### **2.2.2 Design Ground Motions**

One “distant” (far-field) and three “local” (near-field) earthquake records were selected and matched to the respective site design response spectrum to be used as input motions in site response analysis for the landfill. These records have a peak acceleration, frequency content, and duration approximately representative of the expected earthquake motions at the site. The selected records were from the Strong Motion Database of **Pacific Earthquake Engineering Research (PEER) Center** (<http://peer.berkeley.edu/smcat/search.html>) as listed below:

- The CHY042, USGS Class B site ( $V_s^* = 360-750$  m/s), north component acceleration record from the 1999 ( $M_w \approx 7.6$ ) Chi-Chi, Taiwan earthquake
- The Castaic Old Ridge Route, sedimentary rock outcrop (USGS Class B site,  $V_s^* = 360-750$  m/s), Ch 1 (90 deg Component) acceleration record from the 1994 ( $M_w \approx 6.7$ ) Northridge, California earthquake

- The Gilroy Array #1, sedimentary rock outcrop (USGS Class A site,  $V_s^* > 750$  m/s), 90 deg component acceleration record from the 1989 ( $M_W \approx 6.9$ ) Loma Prieta, California earthquake
- The Pacoima-Kagel Canyon, sedimentary rock outcrop (USGS Class B site,  $V_s^* = 360-750$  m/s), Ch 3 (360 deg Component) acceleration record from the 1994 ( $M_W \approx 6.7$ ) Northridge, California earthquake

Where  $V_s^*$  is the average shear wave velocity to a depth of 30 m (~ 100 ft).

The above candidate earthquake records were selected based on the following seismological properties:

- Spectral content (initial recordings with energy in the matching frequency band),
- Magnitude of the design earthquake  $\pm 0.5$ ,
- Source to site distance (source to recording station distances of 8 to 35 km), and
- Rupture directivity.

Once the reference time histories were selected, they were adjusted to provide the response spectrum compatible time histories according to the following approach and criteria:

1. Adjustment of the response spectrum of the reference time histories was performed using a time-domain procedure described by Abrahamson (1991, 1998).
2. The response spectrum of the spectrum compatible time histories should follow reasonably the recommended design response spectra.

The program EZ-FRISK version 7.26 spectral matching routine (Risk Engineering, 2008) was used to develop spectrum-compatible horizontal motions using the above-mentioned startup motions. The spectral matching was performed within the frequency range of PGA to 10.0 seconds. In order to remove the drift induced in displacement time histories as a result of spectral matching, the baseline correction module of EZ-FRISK was applied to the spectrally-matched ground motions. The final design ground motions are baseline-corrected.

Figures 6 through 17 illustrate plots of the original natural records and the final (the response spectrum compatible) time histories and response spectra for the selected earthquake records. Acceleration, velocity, and displacement time histories and 5-percent damped acceleration response spectra are provided in these plots.

These four spectrum compatible records were selected as the updated input ground motions for the landfill dynamic response analysis based on the site design spectra and seismological properties. These motions provide an estimate of the landfill median dynamic response. The selected records were used as input motion in two-dimensional seismic response analysis of the proposed Landfill Unit B-18 expansion. Digitized time history data for the spectrum compatible earthquake records are provided in electronic format for use in the analysis.

## **2.3 LIQUEFACTION**

The potential for liquefaction occurrence in the area of the proposed landfill expansion is considered to be very low or non-existent. The KHF site is underlain by Tertiary sedimentary rocks of the Etchegoin-Jacalitos (Te), San Joaquin (Ts), and Tulare (Tt) Formations. The Landfill Unit B-18 is located within the San Joaquin Formation sedimentary bedrock. The San Joaquin Formation consists primarily of fine-grained sedimentary rocks, principally shale, claystone, and sandstone, which are not susceptible to liquefaction. Groundwater at the site is also deeper than 50 feet. Therefore, based on the site subsurface geology, the potential for liquefaction at the site is very low.

## **2.4 SEISMIC SETTLEMENT**

Similarly, the potential for seismically-induced settlements of the landfill foundation materials was estimated to be negligible based on the subsurface geology and cemented nature of the bedrock. The site foundation materials are classified primarily as the Tertiary sedimentary rocks, which are not susceptible to seismically-induced settlement.

### **3.0 SLOPE STABILITY AND LANDFILL DISPLACEMENT ANALYSIS**

#### **3.1 GENERAL**

The slopes of the proposed Class I/II Landfill B-18 expansion were evaluated for stability under both static and dynamic loading conditions. As part of this evaluation, the effects of dynamic landfill deformations were considered relative to performance of the base liner system during the estimated design ground motions due to the MCE as required by the California Code of Regulations for seismic design of Class I and Class II landfills (see Section 1.3 of the report). The approach used in evaluating the stability and deformation of the slopes involved conventional analytical methods of slope stability evaluation and a refined Newmark-type (Newmark, 1965) seismic deformation analysis including dynamic site response analysis using two-dimensional (2-D) equivalent-linear wave propagation and finite element models.

The information required for the slope stability and landfill deformation analyses consisted of the site geology and seismicity, geometry of the fill plan and landfill bottom excavation and side slopes, and material parameters for waste, the liner systems, and the foundation bedrock. This information was based on the site-specific data gathered for the analysis including laboratory test data (ESI, 1990, 1992; Rust, 1998; URS, 2005; HAI, 2006), design of preliminary proposed fill plans for expanded landfill configuration (URS, 2005; CH2M Hill, 2008; HAI, 2008; Golder, 2008a), in-house compiled database of material properties, and a literature survey of published data on slope stability and seismic deformation analysis of landfills.

The site geology and seismicity is described in detail in the ESI (1990) and Rust (1998) reports. The landfill bottom excavation and side slopes, and proposed new fill plan and cover grades are shown in Figures 1 and 2. A fill plan for the proposed new design of Landfill Unit B-18 expansion was developed by Golder. This fill plan shown in Figure 2, is evaluated for stability using the results of static and seismic slope stability analyses presented in this report.

#### **3.2 LANDFILL GEOMETRY AND ANALYSIS SECTIONS**

Figures 1 and 2 present plan views of the Landfill Unit B-18 base and the proposed final fill plan contours, respectively. Six cross sections of the landfill were analyzed for slope stability including waste slopes and landfill liner system. These cross sections (A-A', B-B', C-C', D-D', E-E', and F-F') are shown in Figures 3 and 4, and their locations are shown on Figures 1 and 2.

Stability of the bottom/side slope and waste fill slopes were analyzed using representative cross sections selected through critical areas of the landfill. Locations of the stability analysis sections were selected based on variations in the landfill geometry such as height and steepness of waste slopes, orientation, height, and steepness of landfill bottom and side slopes around the landfill perimeter.

### **3.3 LANDFILL LINER DESIGN**

Configurations of the existing landfill bottom/side slope liners that comply with state and federal regulations are provided in the ESI 1990 and 2005 URS reports. Figures from the 1990 and 2005 reports are presented in Appendix A of this report illustrating the liner designs for the bottom/side slopes. Figure 18 presents configuration of the proposed liner system for the expansion areas of the landfill. In the slope stability analyses, for each liner configuration, the weakest interface in the composite liner system is expected to provide the preferred failure path for potential failure planes.

### **3.4 MATERIAL PROPERTIES**

Key material properties of various components of the landfill needed to perform static and seismic slope stability analyses are: (1) unit weight, (2) shear strength parameters (static and dynamic), (3) dynamic small-strain shear modulus (or shear wave velocity) and damping ratio properties, and (4) variation of the shear modulus and damping ratio with shear strain during shaking.

Detailed site-specific information on waste, existing liner systems, and foundation bedrock material properties are provided in the Golder and ESI design and conformance testing reports prepared during early 1990's (Golder, 1990, 1991; ESI, 1990, 1992, 1993), and more recent reports prepared for Kettleman Hills Facility (Rust, 1998; URS, 2005; HAI, 2006). The preliminary stability evaluations performed in support of the EIR preparation for the proposed Landfill Unit B-18 expansion (URS, 2005; HAI, 2008) used the same material properties as in the earlier investigations listed above except for the liner interface shear strength properties in the Phase II area of the landfill. In 2003, URS obtained samples of the landfill Phase II liner system that were archived at the KHF site. Interface shear strength testing was performed on the sandwich-like multilayer structure of the liner system and the results were used to refine the interface properties reported in the previous investigations (URS, 2005). In this report, the material properties from the previous investigations (Phase I liner system) and the URS (2005) report for the Phase II liner system were used for the static and seismic slope stability analyses. The Class I waste and foundation bedrock shear strength and unit weight properties, liner interface shear strength values, and dynamic waste, clay liner, and bedrock properties used in the analyses presented in this report are provided in Table 1. The assumed properties used for design should be further verified by performing site-specific tests on the actual materials that will be used during construction. More detailed discussion of the material properties used is provided below.

#### Hazardous Waste Material Properties

The unit weight, shear strength, and dynamic properties of the existing hazardous (Class I) waste materials in the landfill were based on the prior KHF landfill investigations by Golder (1990, 1991), ESI (1990, 1993), and HAI (2006). The landfill Class I waste material was characterized as having static and dynamic properties similar to those for relatively dense cohesionless sand material with a Poisson's ratio of 0.35. The total unit weight of the waste was assumed as 115 pcf in stability and dynamic response analyses, and its shear strength parameters (friction angle and cohesion) were assumed to be 31 degrees and 0 psf, respectively.

The low-strain shear modulus of the Class I waste was assumed to be a function of the mean effective confining pressure as shown below (Seed and Idriss, 1970):

$$G_{\max} = 1000 K_2 (\sigma'_m)^{1/2}$$

Where  $G_{\max}$  and  $\sigma'_m$  represent the soil maximum (low-strain) shear modulus and mean effective stress, respectively, and are in psf. The dimensionless parameter  $K_2$  is determined from the void ratio or relative density. The  $K_2$  was assumed as 60, which is a typical value for relatively dense sands (Seed and Idriss, 1970).

### Liner Interface Shear Strength and Dynamic Properties

In the slope stability analyses for Landfill Unit B-18, potential failure surfaces pass through the waste and the weakest interface in the liner above the landfill foundation bedrock due to relatively low interface shear strength properties of the liner and high strength of the bedrock. Based on the site-specific data from the earlier studies at Kettleman Hills Facility (Golder, 1990, 1991; ESI, 1990, 1992) and our in-house database and literature survey for existing liner system configurations, an interface friction angle of 17 and 9 degrees for the Phase I base liner and slope liner were used, respectively. An interface friction angle of 19 degrees was measured in the recent interface shear tests performed on the “sandwich-like” specimens of the Phase II liner system (URS, 2005). The same type of liner as in the Phase II liner system was assumed to be used for the proposed landfill expansion area. Adhesion coefficient for the liner interfaces is assumed to be zero except for the Phase I slope liner where an adhesion value of 800 psf was used (ESI, 1992). The assumed interface strength properties for the proposed new liner in the expanded landfill areas should be further evaluated by conformance testing on the materials used during construction.

The total unit weight of the clay used in the liner system was assumed as 115 pcf in stability and dynamic response analyses. The clay material used in the liner system was characterized as having a Poisson’s ratio of 0.35 and a nonlinear shear modulus given by the relation shown below for the low-strain conditions (Hardin and Drenevich, 1972):

$$G_{\max} = 14760 [(2.973-e)^2/(1+e)] (\text{OCR})^a (\sigma'_m)^{1/2}$$

Where  $G_{\max}$  and  $\sigma'_m$  represent the soil maximum shear modulus and mean effective stress, respectively, and are in psf, “e” is void ratio and OCR is overconsolidation ratio, and the value of power “a” depends on the plasticity index of soil.

### Bedrock Properties

Shear strength parameters for the foundation bedrock materials were estimated based on the previous KHF landfill investigations. A cohesion value of 800 psf and friction angle of 40 degrees were used in the stability analyses. The shear wave velocity and unit weight of the foundation rock were estimated to be about 2,500 fps and 150 pcf, respectively.

## Modulus and Damping Ratio Variation

The nonlinear modulus reduction and damping ratio increase curves used in the dynamic response analyses for the landfill waste, clay liner, and foundation bedrock materials are the same as those used in the previous KHF investigations and are presented in Figure 19. The figure illustrates how the shear modulus and damping ratio change with the level of induced cyclic shear strains for different landfill materials.

### **3.5 ANALYSIS APPROACH**

Landfill liners in seismically active areas such as California undergo dynamic loads during earthquakes in addition to static loads generated by the dead weight of the waste. Liners, particularly along landfill side slopes, are subjected to tensile stresses due to settlement and creep-induced downward movement of the waste mass. During earthquakes, the landfill mass moves dynamically under the effects of ground accelerations and generates additional stresses in the landfill liner.

CCR Title 22 requires that slopes of a landfill and the foundation beneath the slopes maintain a minimum factor of safety of 1.5 under seismic loading conditions. The factor of safety is usually calculated using pseudo-static limit equilibrium analytical methods. Since achieving a pseudo-static factor of safety of 1.5 for relatively high accelerations generated during MCE events is difficult and costly, the regulations allow for an alternate, more rigorous and detailed design approach involving quantified evaluation of the seismic deformations and displacements of the landfill mass in lieu of the pseudo-static analysis. At present the evaluation of seismic deformations is the most common approach for seismic design of waste fills in California.

The present state-of-practice in seismic design of landfills is based on Newmark (Newmark, 1965) or a simplified Newmark-type method (e.g. Franklin and Chang, 1977; Makdisi-Seed, 1978; Bray et al., 1998) to estimate the order of magnitude of seismically-induced permanent displacements of landfill slopes. Additionally, the current practice relies on engineering judgment by establishing an allowable deformation (about 6 inches) to compare with displacements computed from Newmark method along the liner system.

Our analyses were conducted in the following evaluation/computational sequence:

- Static slope stability and selection of critical failure surfaces;
- Evaluation of yield acceleration coefficients for the critical failure surfaces determined from static slope stability analyses;
- Dynamic site response analysis and calculation of potential slide mass average acceleration; and
- Estimation of seismically-induced permanent deformations for the design “local” and “distant” MCE events.

The above approach originally developed by Seed and Martin (1966) and later used by Makdisi and Seed (1978) for seismic analysis of earth dams, generally results in conservative (larger) permanent displacements, compared to more rigorous fully coupled nonlinear dynamic deformation analysis (Lin and Whitman, 1983).

The four stages of the approach used in this study are further described in the following sections.

### **3.6 STATIC AND PSEUDO-STATIC STABILITY ANALYSES**

#### Analysis Method

Conventional two-dimensional (2-D) limit-equilibrium stability analyses were performed for the existing and proposed bottom/side slope liner and waste fill slopes using landfill cross sections A-A', B-B', C-C', D-D', E-E', and F-F'.

The computer program GSTABL7 v. 2.003 developed by Gregory Geotechnical Software was used to calculate the factors of safety against potential failure. This program was originally developed based on the computer program PC STABL 5M (Achilleos, 1988). The program uses 2-D limit equilibrium theory to provide general solutions for slope stability problems with provisions of using the Modified Bishop, Modified Janbu, or Spencer Methods. Both circular and non-circular potential sliding surfaces can be prespecified or randomly generated. The Spencer, Modified Janbu and Modified Bishop methods were used for this study. The minimum factor of safety was obtained by varying the initiation and exit points of the trial failure planes.

The Modified Janbu Method of analysis, which normally provides conservative results, was initially used to evaluate a large number of potential failure mechanisms for each cross section analyzed. In each analysis case, at least one thousand (1000) potential failure surfaces were randomly generated by the program and the most critical surface resulting in the lowest factor of safety was identified. The most critical failure plane determined by the Modified Janbu Method was then reanalyzed using the Spencer Method. This method satisfies both force and moment equilibrium and thus provides more realistic (usually higher) estimates of the factors of safety and yield acceleration coefficients. The Janbu method is generally more conservative compared with the more rigorous Spencer Method and typically results in lower factors of safety than the Spencer Method (Duncan, 1992). The modified Bishop method was used to analyze circular failure surfaces.

The GSTABL7 output plots, presented in Appendix B, illustrate the 2-D cross sections, various potential failure surface conditions considered, and the most critical failure surfaces analyzed in the stability analysis of the final fill slopes of the proposed landfill expansion.

The appendix presents computer plots for all the cases analyzed illustrating geometry of landfill cross-sections and the ten most critical potential failure planes searched by the program, as well as computed factors of safety. The failure surface with the lowest factor of safety is identified with two arrows at its initiation and termination points.



The material properties of the waste and liner interfaces used in the static and pseudo-static stability analyses are shown in Table 1 and the results of the analyses are summarized in Table 2 and on Figures 3 and 4.

### **3.6.1 Liner and Waste Mass Static Stability**

Slope stability analyses were performed for the final fill plan geometry. Six cross sections at different locations across the landfill were selected for analysis. Figures 1 and 2 show plan views of the Landfill B-18 excavation and the final fill/landfill cover geometry, respectively, and the locations of the cross sections selected for the analysis. In each part of the landfill where its cross section configuration changes, one or more sections were selected for two-dimensional stability evaluations. The configuration of the proposed landfill expansion final fill slopes are illustrated by the selected cross sections shown in Figures 3 and 4.

The most important potential failure mechanism considered was for a wedge (block failure) sliding through the waste mass and along the existing and expanded landfill base liner system. Potential failure surfaces were assumed to pass along the weakest interface in the lining system and then through the landfill mass to the surface. Stability of the slopes against circular failure through the waste mass was also investigated.

The slope stability analyses for Landfill Unit B-18 showed that sliding along the liner systems and/or waste mass was consistently more critical than a sliding surface through the foundation material. Therefore, in the stability analyses, the foundation bedrock was modeled as being impenetrable.

### **3.6.2 Pseudo-Static Stability Analyses**

Pseudo-static analyses, necessary to compute yield acceleration coefficient ( $K_y$ ), were performed for the critical potential failure surfaces through waste and base liner system, identified from results of the static slope stability analyses discussed in Section 3.6.1 for the selected cross sections (Table 2 and Figures 3 and 4). The yield acceleration is defined as the acceleration which results in a pseudo-static factor of safety of 1.0. The computed yield acceleration,  $K_y$ , represents limiting value of the horizontal seismic coefficient beyond which movement of a potential slide mass will occur.

For each cross section, pseudo-static analysis using the Spencer Method was performed to compute an estimate of yield acceleration coefficient ( $K_y$ ) for the most critical potential failure plane identified from the static slope stability analysis for that section. Density and shear strength properties summarized in Table 1 were also used for the pseudo-static stability analyses.

#### Stability Results

Table 2 presents a summary of the computed static factors of safety and yield acceleration coefficients for the critical cases analyzed in this study.

Appendix B presents plots of all the cases analyzed illustrating geometry of landfill cross-sections, the most critical potential failure surfaces, and values of computed static factors of safety and yield accelerations for these surfaces searched by the program. Sample printouts of input and output files providing details of the analysis results are also presented in Appendix B.

For all final (long-term) static conditions, the minimum acceptable factor of safety is 1.5. This criterion was satisfied by the potential failure surfaces analyzed for the proposed fill plan, base liner designs, and the estimated material properties.

The results of the pseudo-static stability analyses show that the lowest yield acceleration coefficient was approximately equal to 0.23 for failure along the liner and waste mass in cross sections A-A' (east), D-D' (east), E-E' (east), and F-F' (east).

The combination of yield acceleration coefficient and slide mass geometry that could potentially result in the largest estimates of the seismically-induced displacements were used in the site response and Newmark displacement analyses described in the following sections. Based on the computed yield accelerations presented in Table 2 and landfill cross sections geometry (Figure 4), the potential failure planes #1 and #3 associated with cross sections D-D' and F-F', respectively were judged to produce the largest seismic displacements and thus, were selected for dynamic site response and seismic deformation analyses.

### **3.7 SEISMIC DEFORMATION ANALYSES**

The acceptability of a slope for earthquake conditions is generally determined by the magnitude of the seismically-induced permanent displacement resulting from the design earthquake.

A small allowable displacement is intended to preclude the possibility of large displacements that might disrupt the flexible membrane liner (FML)/clay composite layers or other components of the leachate collection and removal (LCR) system. A conservative value of the allowable displacement along the landfill liner on the order of 6 inches was considered acceptable for Landfill B-18. This is equal to the lower bound of the allowable displacement range commonly used in the industry (6 to 12 inches) as suggested by Seed and Bonaparte (1992).

Preliminary estimates of the landfill slopes seismic deformations were obtained previously (HAI, 2008) using the simplified analysis method by Bray et al. (1998) and are presented in the following section. A more detailed evaluation of the seismic deformations using two-dimensional site response analyses and Newmark (1965) slope displacement calculation method was performed for this study and is presented in Section 3.7.2 below.

#### **3.7.1 Simplified Analysis of Landfill Slopes Seismic Deformations**

Preliminary estimates of the landfill slopes seismic deformations were obtained using the simplified analysis method by Bray et al. (1998).

This method requires estimating the yield acceleration ( $k_y$ ) for the potential slide mass, the ground motion parameters ( $MHA_r$ ,  $T_m$ , and  $D_{5-95}$ ), fundamental period of equivalent 1-D slide mass at small strains ( $T_s$ ), and maximum horizontal equivalent acceleration (MHEA) for the potential slide mass. The ground motion parameters are defined as:

$MHA_r$  = Maximum Horizontal Acceleration expected at the site at rock level (g),

$T_m$  = Mean period of input rock motion (sec), and

$D_{5-95}$  = Significant duration of shaking, i.e., 5-95% normalized Arias intensity (sec).

The  $MHA_r$  and  $D_{5-95}$  values for the site design ground motions are provided in Section 2.0 and  $T_m$  can be estimated from the following relationships:

$$\ln(T_m) = \ln(C_1 + C_2 \cdot (M-6) + C_3 \cdot r) \quad M \leq 7.25$$

$$\ln(T_m) = \ln(C_1 + 1.25 \cdot C_2 + C_3 \cdot r) \quad 7.25 \leq M \leq 8.0$$

where  $M$  and  $r$  are the earthquake magnitude and distance and parameters  $C_1$ ,  $C_2$ , and  $C_3$  and the standard error ( $\epsilon_r$ ) for a rock site condition are as listed below:

$$C_1 = 0.411, C_2 = 0.0837, C_3 = 0.00208, \text{ and } \epsilon_r = 0.437$$

The fundamental period of slide mass ( $T_s$ ) is calculated using the equation  $T_s = 4H/V_s$ , where  $H$  is the maximum vertical distance between the ground surface and slip surface used to determine  $k_y$  and  $V_s$  is representative small-strain shear wave velocity of materials above sliding mass. The landfill shear wave velocity profile provided in the 2005 URS report was used to calculate the values of parameter  $T_s$  for this study.

Charts provided by Bray et al. (1998) were then used to estimate the normalized MHEA and sliding mass displacement for deep-seated slide surfaces. The normalized MHEA is defined as a function of the normalized fundamental period of slide mass ( $T_s/T_m$ ). The normalized displacement of the potential slide mass is correlated to the ratio of  $k_y/k_{max}$ , where  $k_{max} = MHEA/g$ .

Table 3 provides results of the simplified seismic deformation analyses. The table provides yield accelerations, maximum horizontal equivalent accelerations (MHEA),  $k_y/k_{max}$  ratios, and estimated slope displacements for the cross sections analyzed.

As seen from Table 3, for potential deep failure planes along the landfill bottom liner the estimated permanent displacements are consistently less than 1 inch except for the western part of cross section B-B' where a slope displacement of about 1 inch was estimated. These preliminary estimated values of the seismic displacements are considerably smaller than the maximum allowable displacement of 6 inches commonly used in the industry (Seed and Bonaparte, 1992). These displacements are also in agreement with the seismic displacements estimated by URS (2005).

### **3.7.2 Site Response and Newmark Slope Deformation Analyses**

#### Two-Dimensional Dynamic Site Response Analyses

After yield acceleration coefficients were determined, dynamic response of the landfill and average acceleration time histories of the potential sliding masses were evaluated for three representative “local” (near-field) and one “distant” (far-field) input ground motions. The analyses provide a measure of earthquake energy attenuation/amplification characteristics of the landfill.

To account for the uncertainties introduced by variation of the landfill geometry, two-dimensional finite element computer program QUAD4M (Hudson et al., 1994) was used to evaluate dynamic response of the landfill and average acceleration time histories of the potential sliding waste masses identified from the stability analyses. The two-dimensional analyses provide a more realistic estimate of the seismically-induced displacements of waste slopes compared to one-dimensional site response analysis computer codes such as SHAKE91 (Schnabel et al., 1972; Idriss and Sun, 1991). However, it should be noted that because the landfill geometry is three-dimensional, the use of two-dimensional site response analyses generally provides a conservative estimate of the landfill dynamic response.

QUAD4M was recently developed by modifying and improving QUAD4 program which was initially developed in 1973 (Idriss et al., 1973). The main changes in QUAD4M are: 1) addition of energy absorbing boundaries that can be used to model the material underlying the finite element model as a linear elastic half space, 2) computing average acceleration time history (seismic coefficients) of a defined potential failure mass, and 3) a new method for formulation of damping. QUAD4M approximately incorporates the nonlinear material properties of soil and waste in the analyses by using the equivalent linear method (Seed and Idriss, 1970). In this method, the strain-dependent shear modulus and damping ratio of the material are selected to be compatible with the computed level of strain in each element. The dynamic response is computed repeatedly until the dynamic properties determined from the two sequential cycles differ by less than a specified value. This analysis is done in the time domain, and for any set of properties it is a linear analysis.

QUAD4M analyses were performed for Cross Sections D-D’ and F-F’ and their most critical failure planes (failure planes 1 and 3 in Figure 4, respectively). These cross sections represent the most critical cases based on their geometry, factor of safeties and the minimum  $K_y$  values computed from the pseudo-static stability analyses. The finite element meshes used to model these cross sections are shown in Figures 20a and 20b. The “seismic coefficient” option in QUAD4M was used to calculate the average acceleration time history of potential deep failure mass sliding along the landfill bottom. This is done using the computed time histories of the shear forces for the elements along the bottom and dividing the resultant shear force by the mass of the waste bounded by the potential failure plane along the liner (Seed and Martin, 1966).

The input design ground motions were applied as outcrop motions at the top of the bedrock underlying the landfill, i.e., the “elastic halfspace” below the finite element mesh. The analyses were performed for two sets of ground motions:

- 1 - The near-field and far-field MCE ground motions used previously (see Section 2.1) for seismic deformation analyses of the KHF landfill units B-19 and B-18 (RUST, 1998; URS, 2005, and HAI, 2006), and
- 2 - The updated site design near-field and far-field MCE ground motions developed in this study (see Section 2.2.2).

This provides a comparison of the new landfill design seismic deformations for the old and updated ground motions, and also a comparison of the landfill response for scaled versus spectrally matched ground motions.

The finite element meshes for the cross sections analyzed (Figures 20a and 20b) show the critical potential failure surfaces that were specified for calculation of the average acceleration time histories (seismic coefficients) in the QUAD4M analyses. These seismic coefficient time histories were later used in a Newmark-type analysis method (Newmark, 1965) as described in the following section to estimate the order of magnitude of the permanent seismically-induced displacements along the liner.

### Seismically-Induced Permanent Displacements

The consequences of earthquake shaking on the landfill slopes were evaluated using Makdisi and Seed's procedure (1978) which is a type of Newmark pseudo-dynamic double-integration displacement analysis. This approach is most appropriate for slopes consisting of materials that are not likely to suffer any significant loss of their shear strength due to seismic shaking. The waste and liner materials in the Landfill B-18 are such materials.

During an earthquake, over numerous cycles of loading, a slide mass can move incrementally along a potential failure plane through displacement accumulation. Based on this concept, the Newmark method computes, from a series of pseudo-static analyses, the yield acceleration,  $K_y$  beyond which movement of a slide mass will occur. The permanent displacement resulting from an earthquake is then computed by double integration of the slide mass average acceleration time history whenever the acceleration exceeds  $K_y$ .

The average acceleration time histories computed in the QUAD4M response analyses for the most critical potential failure mass identified in the pseudo-static analyses were used as input for Newmark deformation analyses to evaluate the permanent seismically-induced displacements along the liner system. The displacement calculated by this method is a function of the yield accelerations which were computed in the pseudo-static stability analyses. Figures 21 and 22 illustrate variation of potential slide mass displacement ( $\delta$ ) versus the yield acceleration  $K_y$  for Cross Section D-D' and for the two sets of design ground motions used in the analyses (the RUST 1998 design ground motions and the updated ground motions developed for this study). Figures 23 and 24 illustrate variation of potential slide mass displacement ( $\delta$ ) versus the yield acceleration  $K_y$  for Cross Section F-F' and for the two sets of design ground motions discussed above. Tables 4 and 5 and Figures 21 through 24 summarize the results of calculated seismically-induced permanent displacement ( $\delta$ ) using the average acceleration time history of the waste mass computed from the QUAD4M analyses as input in the Newmark double-integration method for cross sections D-D' and F-F'.

As seen from Figures 21 through 24, for the potential deep failure plane # 1 located in the northeastern part of cross section D-D', and the potential deep failure plane # 3 located in the northeastern part of cross section F-F' (Figure 4) the largest permanent displacements are induced for the 1994 Northridge earthquake Pacoima-Kagel Canyon and Castaic Old Ridge Route accelerograms scaled to a PHGA of 0.57g. However, calculated displacements for  $K_y$  values larger than 0.12 are less than 1 inch. Additionally, the Newmark deformation analyses show that the calculated seismically-induced permanent displacements of the critical potential slide mass are nearly zero for  $K_y$  values larger than 0.12 for the "distant" Caltech A-1 synthetic record and CHY042N Chi-Chi earthquake record scaled to 0.21g and 0.16g, respectively. These estimated values of the seismic displacements are considerably smaller than the maximum allowable displacement of 6 inches commonly used in the industry (Seed and Bonaparte, 1992).

### **3.8 STATIC AND SEISMIC STABILITY OF FINAL COVER**

A preliminary estimate of the final cover seismic deformations was obtained by using the simplified analysis method by Franklin and Chang (1977). A more detailed evaluation of the landfill cover seismic deformations using two-dimensional site response analysis and Newmark (1965) displacement calculation method was also performed. The above analyses are presented below.

#### Simplified Analysis of Landfill Cover

Static and seismic stability of the landfill final cover were evaluated using the infinite slope stability analysis model. Effect of the slope benches were also considered in the analyses. The landfill final cover slope will have an overall inclination of 4.0H:1V with localized inclinations of approximately 3.5H:1V to allow for benching. The cover soils will not become fully saturated given the low annual rate of precipitation in the area, drainage through geotextile in the cover, and the steepness of the final cover slopes.

The proposed final cover for Landfill B-18, shown in Figure 25, includes a 40-mil textured HDPE geomembrane overlain by a geotextile and an approximately 2.5-foot-thick vegetative soil cover over the geosynthetics. The geotextile is a 12-oz/sy non-woven layer that cushions the HDPE geomembrane and provides some drainage. The slope stability analyses were performed for the weakest interface strength in the final cover. The weakest interface is assumed to be along the geomembrane/geotextile interface (see Appendix C).

Peak strength values were used for analysis of seismic loading and the partially saturated final cover condition. Access is available for the final cover to make any necessary repairs after a seismic event; therefore, residual strengths to evaluate short-term impacts are not appropriate.

Appendix C provides the cover soil and interface properties used in the stability analyses, and the detailed static and seismic stability calculations for the cover system described above. The appendix shows that the cover system is stable for both static and seismic loading conditions; however, the estimated permanent displacement is about 12 inches. Hence, a more rigorous two-dimensional dynamic site response and Newmark displacement analysis was performed to more accurately calculate the final cover displacement.

## Two-Dimensional Dynamic Cover Response Analyses

After yield acceleration coefficient for the cover was determined (see Appendix C), dynamic response of the landfill and average acceleration time histories of the potential sliding cover section were evaluated for three representative “local” (near-field) and one “distant” (far-field) input ground motions. To account for the uncertainties introduced by variation of the landfill geometry, two-dimensional finite element computer program QUAD4M was used to evaluate dynamic response of the landfill and average acceleration time histories of the potential sliding cover section identified from the stability analyses. The two-dimensional analyses provide a more realistic estimate of the seismically-induced displacements of the cover compared to the simplified methods.

QUAD4M analysis was performed for the cover section of Cross Section D-D'. The finite element mesh used to model the cross section is shown in Figure 20c. The input design ground motions were applied as outcrop motions at the top of the bedrock underlying the landfill, i.e., the “elastic halfspace” below the finite element mesh. The analyses were performed for the same ground motions used for the liner stability analysis discussed in Section 3.7.2.

The finite element mesh for the cross section analyzed (Figure 20c) shows the critical potential failure surface through the landfill cover that was specified for calculation of the average acceleration time histories in the QUAD4M analyses. The computed average acceleration time history of the specified cover section was then used in a Newmark-type analysis method (Newmark, 1965) as described in the following section to estimate the order of magnitude of the seismically-induced permanent displacements of the cover.

## Seismically-Induced Permanent Displacements

The permanent displacement resulting from the earthquakes are then computed by double integration of the slide mass average acceleration time history whenever the acceleration exceeds  $K_y$ .

The average acceleration time history computed from the QUAD4M dynamic response analyses for the most critical potential failure mass identified in the pseudo-static analyses was used as input for Newmark deformation analyses to evaluate the permanent seismically-induced displacements of the failure mass. The displacement calculated by this method is a function of the yield acceleration computed in the Appendix C ( $K_y \sim 0.2g$ ). Table 6 summarizes the results of calculated landfill cover seismically-induced permanent displacement ( $\delta$ ) using the average acceleration time history of the potential failure section computed from the QUAD4M analyses as input in the Newmark double-integration method for cross section D-D'.

The Newmark deformation analyses show that the calculated seismically-induced permanent displacements of the landfill cover are considerably less than the maximum allowable displacement of 12 inches commonly used in the industry (Seed and Bonaparte, 1992).

## **4.0 CONCLUSIONS**

This report addresses static and seismic stability of the landfill slopes for a proposed expansion of the Landfill B-18. The stability report presented here will be included as part of the design report, being prepared by Golder Associates, Inc. for the proposed Landfill B-18 expansion.

The following changes from the original design were implemented and evaluated in this report:

- Final fill plan geometry was modified to enhance landfill capacity while maintaining static and seismic stability of the landfill slopes.
- The landfill footprint was expanded in the west-northwestern area, using the existing cut slopes in the hills west and northwest of the site to buttress the landfill slopes and enhance stability.

A deterministic seismic hazard analysis was performed to update the site seismic design response spectrum and ground motions. Static and seismic stability evaluations of the proposed final fill slopes and landfill base liner and cover systems were conducted for the new Landfill B-18 fill design. The presented analyses demonstrated that computed static factors of safety were higher than 1.5 for all analyzed sections.

The seismic stability analyses were conducted for the MCE design ground motions. The postulated near-field and far-field MCEs for Landfill B-18 were characterized by a peak horizontal acceleration in lithified earth material of approximately 0.62g and 0.16g, respectively.

The analyses indicated that the proposed new landfill expansion design (Golder, 2008) would result in a stable configuration under both static and seismic loading conditions in compliance with applicable regulations. The acceptability of the landfill slopes for earthquake loading conditions was determined by the relatively small magnitude of the seismically-induced permanent displacements resulting from the local and distant MCE design earthquake events. The results of the conservative Newmark-type permanent displacement analyses presented in this study indicated that computed maximum displacements along the liner system during the design earthquake events are less than 1 inch. Maximum seismically-induced permanent displacement within the waste prism in the cover/gas collection system is about 6 inches which is less than the maximum allowable value of 12 inches.

The analyses were performed for the landfill final fill configurations. Slope stability analyses are required for design of the proposed landfill expansion interim fill conditions. Site-specific laboratory testing of the proposed materials to be used in the liner systems should be performed for design of the landfill expansion. Additionally, conformance testing of the liner materials should be performed during construction to verify properties used in the design of the landfill expansion.



## **5.0 REFERENCES**

- Abrahamson, N.A. (1991) "Non-stationary spectral matching," *Seismological Research Letters*, Vol. 62, No. 1.
- Abrahamson, N.A. and Silva, W.J. (1996) "Empirical Ground Motion Models," Report Prepared for Brookhaven National Laboratory, New York, NY, May, 144 pp.
- Abrahamson, N.A. (1998) "Non-stationary spectral matching program RSPMATCH," PG&E Internal Report, February.
- Abrahamson, N.A., 2000, Effects of rupture directivity on probabilistic seismic hazard analysis: proceedings of the Sixth International Conference on Seismic Zonation, Earthquake Engineering Research Institute, CD-ROM, Paper No. 50.
- Abrahamson, N. A. and W. J. Silva (2008) "Summary of the Abrahamson and Silva NGA ground-motion relations", *Earthquake Spectra*, in Press
- Achilleos, E. (1988) "User's Guide for PC STABL 5M," Purdue University, West Lafayette, Indiana, 132 p.
- Boore, D. M., and Atkinson, G., M., 2007, Boore-Atkinson NGA Ground Motion Relations for the Geometric Mean Horizontal Component of Peak and Spectral Ground Motion Parameters, Pacific Earthquake Engineering Research Center (PEER) report, 2007/01.
- Bozorgnia, Y., and Campbell, K., 2008, NGA ground motion model for the geometric mean horizontal component of PGA, PGV, PGD and 5% damped linear elastic response spectra for periods ranging from 0.01 to 10 s, *Earthquake Spectra*, in Press
- Bray, J. D., Rathjje, E. M., Augello, A. J., Merry, S. M. (1998) "Simplified Seismic Design Procedure of Geosynthetic-Lined Solid Waste Landfills," *Geosynthetics International*, Vol. 5.
- California Geological Survey, 2003, The Revised 2002 California Probabilistic Seismic Hazard Maps, by T. Cao, W. A. Bryant, B. Rowshandel, D. Branum, and C. J. Wills, June 2003.
- Chiou, B. S.-J., and Young, R., R., 2006, Chiou and Youngs PEER-NGA Empirical Ground Motion Model for the Average Horizontal Component of Peak Acceleration and Pseudo-Spectral Acceleration for Spectral Periods of 0.01 to 10 Seconds, Pacific Earthquake Engineering Research Center (PEER) report.
- CH2MHILL (2008) "B-18/B-20 Hazardous Waste Disposal Project, Kettleman Hills Facility, Chemical Waste Management, Inc.," prepared for Kings County Planning Agency, State Clearinghouse No. 2005041064, March.

- Duncan, M. (1992) "State-of-the-Art: Static Stability and Deformation Analysis," ASCE Geotechnical Special Publication No. 31, Stability and Performance of Slopes and Embankments-II, pp. 222-266.
- Ekstrom, G., R. S. Stein, J. P. Eaton, and D. Eberhart-Phillips (1992) "Seismicity and Geometry of a 110-km-Long Blind Thrust Fault. The 1985 Kettleman Hills, California, Earthquake," Journal of Geophysical Research, Vol. 97, No. B4, pages 4843-4864, April 10, 1992.
- Environmental Solutions, Inc., 1990. "Engineering and Design Report, Landfill Unit B-18, Phase I and II and Final Closure, Kettleman Hills Facility, Kings County, California, Volumes I and II," report prepared for Chemical Waste Management, Inc., August.
- Environmental Solutions, Inc., 1992. "Backup Calculations Supporting the Interface testing Program for Landfill Unit B-18, Kettleman Hills Facility, Kings County, California," report prepared for Chemical Waste Management, Inc., February.
- Environmental Solutions, Inc., 1993. "Revised Intermediate Waste Fill Plan, Landfill Unit B-18, Phase I, Kettleman Hills Facility, Kings County, California, Volumes I and II," report prepared for Chemical Waste Management, Inc., August.
- Franklin, A. G. and F. K. Chang (1977) "Permanent Displacements of Earth Embankments by Newmark Sliding Block Analysis," Earthquake Resistance of Earth and Rock-Fill Dams, Report 5, U. S. Dept. of the Army, Corps of Engineers, Waterways Experiment Station, November.
- Golder Associates, Inc. (1990) "Direct Shear Testing Program for Landfill Cover Design, Kettleman Hills Facility", June 29, 1990.
- Golder Associates, Inc. (1991) "Landfill B-19, Phase IA Redesign and Closure Plan, Kettleman Hills Facility, Kettleman City, California," Volumes I-IV, April 15, 1991.
- Golder Associates, Inc. (2003) "Shear Strength Testing on Compacted Fill Material, Landfill B-19, Phase 1B, Kettleman Hills Facility," performed for Waste Management, Inc.
- Golder Associates, Inc. (2008a) "Proposed Modifications to Landfill B-18 Expansion Project," Report to Kettleman Hills Facility, April.
- Golder Associates, Inc. (2008b) ".....," Report to Kettleman Hills Facility, September.
- Hardin, B.O., and Drenevich, V.P. (1972) "Shear Modulus and Damping in Soils: Design Equations and Curves," Journal of the Soil Mechanics and Foundations Division, ASCE, Vol.98, No.SM7, pp.667-692.

- Hudson, M., I.M. Idriss, and M. Beikae (1994) "A Computer Program To Evaluate the Seismic Response of Soil Structures Using Finite Element Procedures and Incorporating A Compliant Base," Report from the Center of Geotechnical Modeling, Department of civil and Environmental Engineering, University of California, Davis
- Hushmand Associates, Inc., 2003, revised 2006. "Slope Stability Analysis for Cell Redesign and Bioreactor Evaluation, Kettleman Hills Facility Municipal Solid Waste Landfill Unit B-19, Kettleman City, Kings County, California," November 2003, revised November 2006.
- Hushmand Associates, Inc., 2008. "Preliminary Slope Stability, Kettleman Hills Facility, Hazardous Waste Landfill Unit B-18 Expansion, Kettleman City, Kings County, California," April.
- Idriss, I.M., et al. (1973) "QUAD-4, A Computer Program for Evaluating the Seismic Response of Soil Structures by Variable Damping Finite Elements," Report No. EERC 73-16, Earthquake Engineering Research Center, University of California, Berkeley, California, June.
- Idriss, I.M. and Sun, (1991) "A Computer Program for Conducting Equivalent Linear Seismic Response Analyses of Horizontally Layered Soil Deposits- Program modified based on the Original SHAKE program published in December 1972 by Schnabel, Lysmer and Seed".
- Lin, J.S. and Whitman, R.V. (1983) "Decoupling Approximation to the Evaluation of Earthquake Induced Plastic Slip in Earth Dams," J. Earthquake Engineering Structural Dynamics, Vol. 11, pp. 667-678
- Makdisi, F. I. and H. B. Seed (1978) "Simplified Procedure for Estimating Dam and Embankment Earthquake-Induced Deformation," Journal of the Geotechnical Engineering Division, ASCE, Vol. 104, No. GT7, July, pp. 849-868.
- Newmark, N. M. (1965) "Effects of Earthquakes on Dams and Embankments," 5th Rankine Lecture, Geotechnique, Vol. 15, No. 2, pp. 139-160.
- Petersen, Mark D., Frankel, Arthur D., Harmsen, Stephen C., Mueller, Charles S., Haller, Kathleen M., Wheeler, Russell L., Wesson, Robert L., Zeng, Yuehua, Boyd, Oliver S., Perkins, David M., Luco, Nicolas, Field, Edward H., Wills, Chris J., and Rukstales, Kenneth S., 2008, "Documentation for the 2008 Update of the United States National Seismic Hazard Maps: U.S. Geological Survey Open-File" Report 2008-1128, 61 p.
- Rust Environment & Infrastructure, Inc., 1997 (Rev 1: 1998) "Preliminary Stability Evaluation, Municipal Solid Waste Landfill Unit B-19, Kettleman Hills Facility, Kettleman City, Kings County, California," Technical Report prepared for Chemical West Management, Inc., July.
- Seed, H.B., and R. Bonaparte, 1992. "Seismic Analysis and Design of Lined Waste Fills: Current Practice," ASCE Geotechnical Special Publication No. 31, Stability and Performance of Slopes and Embankments, June 29-July 1, 1992.

- Seed H.B., and I.M. Idriss, 1970. "Soil Moduli and Damping Factors for Dynamic Response Analysis," Report No. EERC 70-10, University of California, Berkeley, December.
- Seed and Martin, G.R. (1966) "The Seismic Coefficient in Earth Dam Design," ASCE, Vol.92, No. SM3, Proc. Paper 4824, May 1966, pp. 25-58.
- Seed H.B., R.T. Wong, I.M. Idriss, and K. Tokimatsu, 1984. "Moduli and Damping Factors for Dynamic Analyses of Cohesionless Soils," Earthquake Engineering Research Center, Report No. UCB/EERC-84/14.
- Schnabel P. B., J. Lysmer, and H. B. Seed (1972) "SHAKE: A Computer Program for Earthquake Response Analysis of Horizontally Layered Sites," Report No. EERC 72-12, College of Engineering, Earthquake Engineering Research Center, University of California, Berkeley, California, December.
- Somerville, P.G., Smith, N.F., Graves R.W. and Abrahamson, N.A., 1997, Modification of Empirical Strong Ground Motion Attenuation Relations to Include the Amplitude and Duration Effects of Rupture Directivity, *Seismological Research Letters*, Volume 68, Number 1, January/February.
- Stein, R. S., and Ekstrom, G. (1992), Seismicity and Geometry of a 110-km-Long Blind Thrust Fault 2. Synthesis of the 1982–1985 California Earthquake Sequence, *J. Geophys. Res.*, 97(B4), 4865–4883.
- URS (2005) "Preliminary Stability Analyses, Kettleman Hills Facility Expansion, Kettleman City, California," prepared for Chemical West Management, Inc.

**Table 1. Selected Material Properties for Static and Seismic Stability Analyses**

Material/Interface	Unit Weight	Shear Strength Properties		Shear Wave Velocity ( $V_s$ - ft/sec) or Shear Modulus (G, psf) Relation	Modulus Reduction & Damping Curves
		Friction Angle (degree)	Cohesion (psf)		
HW <sup>1</sup>	115 pcf	31	0	$G = 1000 K_2 (\sigma'_m)^{1/2}$ $K_2 = 60$ for relatively dense sands (Seed and Idriss, 1970)	See Figure 19 Relatively dense sand (Seed et al., 1984)
Clay Liner <sup>1,2</sup>	115 pcf	20	1,150	$G = \frac{14,760(2.97 - e)^2}{1 + e} (OCR)^k \sigma'_m^{0.5}$ (Hardin and Drenvich, 1972)	See Figure 19 (Seed and Idriss, 1970)
Bedrock <sup>1</sup>	150 pcf	40	800	$V_s = 2500$ fps	See Figure 19 (Schnabel et al. 1972)
Phase I Bottom Liner Interface <sup>1</sup>	----	17	0	----	----
Phase I Side Slope Liner Interface <sup>1</sup>	----	9	800	----	----
Phase II Bottom Liner Interface <sup>1</sup>	----	19	0	----	----
Phase II Side Slope Liner Interface <sup>1</sup>	----	19	0	----	----
Expansion Area Liner Interface <sup>3</sup>	----	19	0	----	----

- (1) Environmental Solutions, Inc. (1990, 1992, 1993); Rust Environmental & Infrastructure, Inc. (1998); URS (2005).
- (2) Modeled as a layer in site dynamic response analysis to include effects of softer clay layer on ground motion.
- (3) Golder Associates, Inc. (2008b).

**Table 2a. Summary of Slope Stability Analysis Results  
(Landfill East and North Sides)**

Cross Section	Failure Plane Number	Description	Static Factor of Safety	Yield Acceleration, $k_y$ (g)
A-A'	1	Deep Block Failure through Bottom Liner	2.589	0.254
	2	Deep Block Failure through Bottom Liner	2.689	0.225
	3	Deep Block Failure through Bottom Liner	2.722	0.237
B-B'	1	Deep Block Failure through Bottom Liner	6.8	0.453
	2	Deep Block Failure through Bottom Liner	8.59	0.385
	3	Deep Block Failure through Bottom Liner	6.54	0.356
C-C'	1	Deep Block Failure through Bottom Liner	3.06	0.395
	2	Deep Block Failure through Bottom Liner	4.35	0.47
D-D'	1	Deep Block Failure through Bottom Liner	2.34	0.232
	2	Deep Block Failure through Bottom Liner	2.82	0.273
E-E'	1	Deep Block Failure through Bottom Liner	2.743	0.265
	2	Deep Block Failure through Bottom Liner	2.747	0.23
	3	Deep Block Failure through Bottom Liner	2.73	0.237
F-F'	1	Deep Block Failure through Bottom Liner	2.805	0.252
	2	Deep Block Failure through Bottom Liner	2.467	0.225
	3	Deep Block Failure through Bottom Liner	2.46	0.225

**Table 2b. Summary of Slope Stability Analysis Results  
(Landfill West and South Sides)**

Cross Section	Failure Plane Number	Description	Static Factor of Safety	Yield Acceleration, $k_y$ (g)
A-A'	I	Deep Block Failure through Bottom Liner	4.194	0.42
	II	Deep Block Failure through Bottom Liner	7.249	0.315
B-B'	I	Deep Block Failure through Bottom Liner	3.5	0.395
	II	Deep Block Failure through Bottom Liner	8.93	0.487
C-C'	I	Deep Block Failure through Bottom Liner	4.92	0.345
	II	Deep Block Failure through Bottom Liner	5.64	0.34
D-D'	I	Deep Block Failure through Bottom Liner	3.88	0.375
	II	Circular Failure	2.5	0.32
	III	Circular Failure	2.18	0.26
E-E'	I	Deep Block Failure through Bottom Liner	5.431	0.425
	II	Deep Block Failure through Bottom Liner	8.879	0.344
F-F'	I	Circular Failure	2.578	0.325
	II	Deep Block Failure through Bottom Liner	5.894	0.435
	III	Deep Block Failure through Bottom Liner	7.205	0.375

**Table 3 - Results of Simplified Seismic Deformation Analyses for Landfill Liner**

Analyzed Cross Section	Yield Acceleration $K_y$ (g)	Maximum Horizontal Acceleration $K_{max}$ (g)	$K_y/K_{max}$	Estimated Slope Deformation <sup>(1)</sup> (in)
A-A' - East	0.225	0.218	1.03	<1
A-A' - West	0.315	0.275	1.15	<1
B-B' - East	0.356	0.193	1.84	<1
B-B' - West	0.395	0.504	0.78	~ 1.0
C-C' - North	0.395	0.197	2.01	<1
C-C' - South	0.340	0.249	1.37	<1
D-D' - East	0.232	0.223	1.04	<1
D-D' - West	0.375	0.281	1.33	<1
E-E' - East	0.230	0.203	1.13	<1
E-E' - West	0.344	0.374	0.92	<1
F-F' - East	0.225	0.203	1.11	<1
F-F' - West	0.375	0.374	1.00	<1

Notes:

- (1) Estimated seismic deformations in above table are for the local design earthquake on the blind Ramp Thrust at a distance of 10 km. Seismic deformations computed for the distant seismic event on the San Andreas Fault zone at 35 km from the site were negligible.



**Table 4. Seismically-Induced Permanent Displacements from Newmark Deformation Analyses  
(Cross Section D-D', Failure Surface 1 along Landfill Liner)**

	Ground Motion	Yield Acceleration Ky (g)	Maximum Acceleration Kmax (g)	Permanent Displacement (in)
Old Records <sup>1</sup>	Pacoima	0.232	0.187	<1
	Castaic	0.232	0.192	<1
	Seed Hayward	0.232	0.133	<1
	Caltech Synthetic Record A1	0.232	0.109	<1
New Records <sup>2</sup>	Pacoima	0.232	0.189	<1
	Castaic	0.232	0.145	<1
	Gilroy	0.232	0.183	<1
	Chi Chi	0.232	0.074	<1

Notes:

- (1) Records scaled to design PGA used in the previous analyses of KHF Landfills (Rust, 1998; URS, 2005; HAI, 2006).
- (2) Spectrally matched records developed based on an updated seismic hazard analysis in 2008 used for this project.

**Table 5. Seismically-Induced Permanent Displacements from Newmark Deformation Analyses  
(Cross Section F-F', Failure Surface 3 along Landfill Liner)**

	Ground Motion	Yield Acceleration Ky (g)	Maximum Acceleration Kmax (g)	Permanent Displacement (in)
Old Records <sup>1</sup>	Pacoima	0.225	0.184	<1
	Castaic	0.225	0.189	<1
	Seed Hayward	0.225	0.128	<1
	Caltech Synthetic Record A1	0.225	0.104	<1
New Records <sup>2</sup>	Pacoima	0.225	0.179	<1
	Castaic	0.225	0.137	<1
	Gilroy	0.225	0.175	<1
	Chi Chi	0.225	0.068	<1

Notes:

- (1) Records scaled to design PGA used in the previous analyses of KHF Landfills (Rust, 1998; URS, 2005; HAI, 2006).
- (2) Spectrally matched records developed based on an updated seismic hazard analysis in 2008 used for this project.



**Table 6. Seismically-Induced Permanent Displacements from Newmark Deformation Analyses  
(Cross Section D-D', Cover Analysis)**

Record Sets	Ground Motion	Yield Acceleration Ky (g)	Maximum Acceleration Kmax (g)	Permanent Displacement (in)
Old Records <sup>1</sup>	Pacoima	0.2	0.58	6.29
	Castaic	0.2	0.42	3.73
	Seed Hayward	0.2	0.29	<1
	Caltech Synthetic Record A1	0.2	0.23	<1
New Records <sup>2</sup>	Pacoima	0.2	0.51	2.71
	Castaic	0.2	0.31	~1
	Gilroy	0.2	0.40	1.36
	Chi Chi	0.2	0.15	<1

Notes:

- (1) Records scaled to design PGA used in the previous analyses of KHF Landfills (Rust, 1998; URS, 2005; HAI, 2006).
- (2) Spectrally matched records developed based on an updated seismic hazard analysis in 2008 used for this project.

# FIGURES





Project No.: 08-0228

Date: JULY, 2008

Drawn by: K.J.Kavli

Checked by: SGS

**FIGURE 1**  
**PROPOSED B-18 LANDFILL LINER GRADES**  
 KETTLEMAN HILLS LANDFILL FACILITY




Project No.: 08-0228

Date: JULY, 2008

Drawn by: K.J.Kavli

Checked by: SGS

**FIGURE 2**  
**PROPOSED B-18 LANDFILL**  
**FINAL GRADING**  
 KETTLEMAN HILLS LANDFILL FACILITY



**LEGEND:**

- NORTH OR EAST FAILURE PLANE
- WEST OR SOUTH FAILURE PLANE


- ⊙ NORTH OR EAST PLANE NUMBER
- Ⓜ WEST OR SOUTH PLANE NUMBER

SCALE 1 inch = 200 ft  
 0' 50' 100' 200'

Project No. 08-0228  
 Kettleman Hills Facility - Unit B-18  
 Kettleman City, Kings County, California

**HAI** HUSHMAND ASSOCIATES INC.  
 Geotechnical, Earthquake and Environmental Engineers

ANALYSIS CROSS SECTIONS A-A', B-B', C-C' AND POTENTIAL FAILURE PLANES



SUMMARY OF SLOPE STABILITY ANALYSIS RESULTS

SECTION	CASE NO.	FS	Ky
D-D'	1	2.34	0.232
	2	2.82	0.273
	I	3.88	0.375
D-D'	II	2.50 *	0.320*
	III	2.18 *	0.260*
	E-E'	1	2.74
2		2.75	0.230
3		2.73	0.237
I		>4.00	0.425
II		>4.00	0.344
F-F'		1	2.61
	2	2.47	0.225
	3	2.46	0.225
	I	2.58 *	0.325*
	II	>4.00	0.435
	III	>4.00	0.375

\*Using Modified Bishop Method.

LEGEND:

- NORTH OR EAST FAILURE PLANE      ② NORTH OR EAST PLANE NUMBER
- WEST OR SOUTH FAILURE PLANE      □ WEST OR SOUTH PLANE NUMBER


SCALE 1 inch = 200 ft  



 0' 50' 100' 200'




Project No. 08-0228	Kettleman Hills Facility - Unit B-18 Kettleman City, Kings County, California
	<b>HUSHMAND ASSOCIATES INC.</b> <small>Geotechnical, Earthquake and Environmental Engineers</small>

ANALYSIS CROSS SECTIONS D-D', E-E',  
F-F' AND POTENTIAL FAILURE PLANES









Project No.  
08-0228




Landfill B-18 Expansion Project  
Kettleman City, Kings County, CA



**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

**ORIGINAL CORRECTED TIME HISTORIES**  
**1994 NORTHRIDGE EARTHQUAKE**  
**STATION: CASTAIC OLD RIDGE\_090**

Figure  
7



Project No.  
08-0228



Landfill B-18 Expansion Project  
Kettleman City, Kings County, CA






**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

**SPECTRUM COMPATIBLE TIME HISTORIES**  
**1994 NORTHRIDGE EARTHQUAKE**  
**STATION: CASTAIC OLD RIDGE\_090**

Figure  
8





Project No.  
08-0228




Landfill B-18 Expansion Project  
Kettleman City, Kings County, CA



**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

**ORIGINAL CORRECTED TIME HISTORIES**  
**1989 LOMA PRIETA EARTHQUAKE**  
**STATION: GILROY ARRAY 090**

Figure  
10



Project No.  
08-0228



Landfill B-18 Expansion Project  
Kettleman City, Kings County, CA






**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

**SPECTRUM COMPATIBLE TIME HISTORIES**  
**1989 LOMA PRIETA EARTHQUAKE**  
**STATION: GILROY ARRAY 090**

Figure  
11







Project No.  
08-0228




Landfill B-18 Expansion Project  
Kettleman City, Kings County, CA



**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

**ORIGINAL CORRECTED TIME HISTORIES**  
**1994 NORTHRIDGE EARTHQUAKE**  
**STATION: PACOIMA KAGEL CANYON 360**

Figure  
13



Project No.  
08-0228



Landfill B-18 Expansion Project  
Kettleman City, Kings County, CA






**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

**SPECTRUM COMPATIBLE TIME HISTORIES**  
**1994 NORTHRIDGE EARTHQUAKE**  
**STATION: PACOIMA KAGEL CANYON 360**

Figure  
14





Project No.  
08-0228




Landfill B-18 Expansion Project  
Kettleman City, Kings County, CA



**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

**ORIGINAL CORRECTED TIME HISTORIES**  
**1999 CHI CHI EARTHQUAKE**  
**STATION:CHY042 N**

Figure  
16



Project No.  
08-0228


Landfill B-18 Expansion Project  
Kettleman City, Kings County, CA



**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

**SPECTRUM COMPATIBLE TIME HISTORIES**  
**1999 CHI CHI EARTHQUAKE**  
**STATION:CHY042 N**

Figure  
17





Project No.  
08-0228

Landfill B-18 Expansion Project  
Kettleman, Kings County, California




**HUSHMAND ASSOCIATES, INC.**  
Geotechnical and Earthquake Engineers


**PROPOSED LANDFILL  
LINER SYSTEM**



HW: Hazardous Waste



SCALE 1 inch = 120 ft



Project No.  
08-0228

Landfill B-18 Expansion Project  
Kettleman City, Kings County, California





**HUSHMAND ASSOCIATES INC.**  
Geotechnical, Earthquake and Environmental Engineers


SECTION D - D'  
FINITE ELEMENT (QUAD4M) MESH

Figure  
20a







SCALE 1 inch = 150 ft  
  
 0' 37.5' 75' 150'


Project No. 08-0228	Landfill B-18 Expansion Project Kettleman City, Kings County, California
	HUSHMAND ASSOCIATES INC. Geotechnical, Earthquake and Environmental Engineers

SECTION F - F'  
 FINITE ELEMENT (QUAD4M) MESH

Figure  
 20b




SCALE 1 inch = 120 ft  
  
 0' 30' 60' 120'


Project No. 08-0228	Landfill B-18 Expansion Project Kettleman City, Kings County, California
	HUSHMAND ASSOCIATES INC. Geotechnical, Earthquake and Environmental Engineers

SECTION D - D'  
 FINITE ELEMENT (QUAD4M) MESH


Figure  
 20c




Project No. 08-0228	<b>Landfill B-18 Expansion Project</b> Kettleman City, Kings County, California	 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers	<b>EARTHQUAKE INDUCED DISPLACEMENTS</b> <b>SECTION D-D' - FAILURE PLANE 1</b> <b>2-D QUAD4M DYNAMIC RESPONSE ANALYSIS</b> <b>(PREVIOUS GROUND MOTIONS)</b>	Figure 21




Project No. 08-0228	Landfill B-18 Expansion Project Kettleman City, Kings County, California	 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers
	Earthquake Induced Displacements SECTION D-D' - FAILURE PLANE 1 2-D QUAD4M DYNAMIC RESPONSE ANALYSIS (RECENT GROUND MOTIONS)	





Project No. 08-0228	Landfill B-18 Expansion Project Kettleman City, Kings County, California	 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers	<b>EARTHQUAKE INDUCED DISPLACEMENTS</b> <b>SECTION F-F' - FAILURE PLANE 3</b> <b>2-D QUAD4M DYNAMIC RESPONSE ANALYSIS</b> <b>(RECENT GROUND MOTIONS)</b>	Figure
				24



Project No.  
08-0228

Landfill B-18 Expansion Project  
Kettleman, Kings County, California




**HUSHMAND ASSOCIATES, INC.**  
Geotechnical and Earthquake Engineers

**PROPOSED LANDFILL  
FINAL COVER**

# **APPENDIX A**







**NOTES**

1. SEE SHEET 1 FOR LEGEND AND GENERAL NOTES
2. BENCHES WILL BE PROVIDED AT APPROXIMATELY 50-FOOT INTERVALS AS SHOWN ON SECTION B. SHEET 17. INTERMEDIATE BETWEEN BENCHES WILL HAVE A SLOPE OF APPROXIMATELY 3.6:1. THE BENCHES WILL SLOPE AT 3% TO CONTROL DRAINAGE.

SOURCE: ENVIRONMENTAL SOLUTIONS, INC., 1990

Project No.  
08-0228

Landfill B-18 Expansion Project  
Kettleman City, Kings County, California



**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers


**PHASE I AND II**

**FINAL CLOSURE PLAN**


(Landfill Unit B-18 Construction Plans)

Figure

A-2



**TYPICAL SLOPE LINER**





**TYPICAL BASE LINER**

**NOTES**


- 1a. GEOTEXTILE SHALL BE TREVIRA 1125 OR EQUAL.
- 1b. GEOTEXTILE SHALL BE TREVIRA 1155 OR EQUAL.
- 1c. GEOCOMPOSITE SHALL BE TREVIRA 1125 HEAT BONDED TO POLYNET 3000.
- 1d. GEOCOMPOSITE SHALL BE TREVIRA 1125 OR 1155 HEAT BONDED TO POLYNET 3000.
- 1e. GEOCOMPOSITE SHALL BE TREVIRA 1125 OR 1155 HEAT BONDED TO POLYNET 3000 AT THE OPTION OF THE OWNER.
- 1f. GEOTEXTILE SHALL ALWAYS BE FACING UP.
2. GEONET SHALL BE POLYNET 3000 OR EQUAL.
3. PROTECTIVE LINER SHALL BE REMOVED BY OPERATIONS STAFF PRIOR TO PLACEMENT OF OPERATIONS LAYER.
4. BASE OPERATIONS LAYER SHALL CONSIST OF SOILS EXCAVATED FROM ONSITE SOURCES. SOIL PARTICLE SIZE SHALL HAVE MAXIMUM DIAMETER OF 8 INCHES.
5. SIDE SLOPE OPERATIONS LAYER SHALL CONSIST OF SOILS EXCAVATED FROM ONSITE SOURCES. SOIL PARTICLE SIZE SHALL HAVE MAXIMUM DIAMETER OF 1 INCH.
6. DRAINAGE LAYER MATERIAL SHALL CONSIST OF A SUB-ANGULAR TO ROUNDED WASHED GRAVEL MEETING THE GRADATION REQUIREMENTS SPECIFIED IN SECTION 02924 OF THE SPECIFICATIONS.
7. LINER SYSTEM SCALES ARE EXAGGERATED FOR CLARITY.
8. THE BOTTOM 12" OF PRIMARY CLAY LINER SHALL BE CONSTRUCTED IN ONE LIFT TO PROTECT UNDERLYING GEOSYNTHETIC LINER SYSTEM. THE UPPER 12" WILL HAVE A PERMEABILITY OF  $K_{max} = 10^{-7} \text{ cm/sec}$ .

SOURCE: ENVIRONMENTAL SOLUTIONS, INC., 1990

Project No. 08-0228	Landfill B-18 Expansion Project Kettleman City, Kings County, California	Figure A-3
 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers		<b>DETAILS OF THE LANDFILL BASE GEOCOMPOSITE LINER SYSTEM</b>  <b>EXISTING PHASE 1 LINER</b>




**SLOPE LINER**  
SCALE: NTS




**BOTTOM LINER**  
SCALE: NTS

SOURCE: URS, 2005

Project No. 08-0228	Landfill B-18 Expansion Project Kettleman City, Kings County, California
	 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers

**PROPOSED LINER SYSTEM**

AVERAGE RETURN PERIOD vs. ACCELERATION



Seismic Hazard Evaluation, Landfill Unit B-19, Kettleman Hills Facility  
Attenuation relations for blind thrust faults and rock sites.

SOURCE: RUST, 1998

Project No.  
08-0228


Landfill B-18 Expansion Project  
Kettleman City, Kings County, California




**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

**PEAK HORIZONTAL ACCELERATION  
IN ROCK VERSUS AVERAGE  
RETURN PERIOD**

Figure  
A-5





(a) Caltech A-1 Synthetic Record Scaled to 0.21g Peak Acceleration




(b) Comparison of Pseudo-Acceleration Response Spectrum of Caltech A-1 Synthetic Earthquake Record and Target Design Spectrum (Peak Acceleration Scaled to 0.21g)

SOURCE: RUST, 1998

Project No. 08-0228	<b>Landfill B-18 Expansion Project</b> Kettleman City, Kings County, California	<b>CALTECH A-1 SYNTHETIC ACCELERATION RECORD AND DYNAMIC RESPONSE SPECTRUM</b>	Figure A-6
 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers			





(a) Modified Seed-Hayward Synthetic Record Scaled to 0.57g Peak Acceleration




(b) Comparison of Pseudo-Acceleration Response Spectrum of the Modified Seed-Hayward Synthetic Earthquake Accelerogram and Target Design Spectrum (Peak Acceleration of Synthetic Record Scaled to 0.57g)

SOURCE: RUST, 1998

Project No. 08-0228	<b>Landfill B-18 Expansion Project</b> Kettleman City, Kings County, California	<b>MODIFIED SEED-HAYWARD SYNTHETIC ACCELERATION RECORD AND DYNAMIC RESPONSE SPECTRUM SCALED TO TARGET MCE RESPONSE SPECTRUM</b>	Figure A-7
 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers			




(a) Northridge Castaic Old Ridge Route CH 1 Record Scaled to 0.57g Peak Acceleration




(b) Comparison of Pseudo-Acceleration Response Spectrum of M6.7 January 17, 1994 Northridge Earthquake Castaic - Old Ridge Route, CHN 1:90 DEG Record and Target Design Spectrum (Peak Acceleration Scaled to 0.57g)


SOURCE: RUST, 1998

Project No. 08-0228	<b>Landfill B-18 Expansion Project</b> Kettleman City, Kings County, California	<b>CASTAIC ACCELERATION RECORD AND DYNAMIC RESPONSE SPECTRUM</b>  <b>LOCAL DESIGN EARTHQUAKE</b>	Figure A-8
 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers			






(a) Northridge Pacoima - Kagel Canyon CH 3 Record Scaled to 0.57g Peak Acceleration



(b) Comparison of Pseudo-Acceleration Response Spectrum of M6.7 January 17, 1994 Northridge Earthquake Pacoima - Kagel Canyon, CHN 3:360 DEG Record and Target Design Spectrum (Peak Acceleration Scaled to 0.57g)


SOURCE: RUST, 1998

Project No. 08-0228	<b>Landfill B-18 Expansion Project</b> Kettleman City, Kings County, California	<b>PACOIMA-KAGEL CANYON ACCELERATION RECORD AND DYNAMIC RESPONSE SPECTRUM</b>	Figure
 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers			

# **APPENDIX B**

# KHF, SECTION A-A', EAST, STATIC, FAILURE PLANE 1

c:\slope\seca-esj1 new.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/24/2008 05:46PM



GSTABL7 v.2 FSmin=2.209


Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SECTION A-A', EAST, STATIC, FAILURE PLANE 1

c:\slope\seca-ess1 new.plt Run By: Jason Lee, Hushmand Associates, Inc 7/24/2008 05:50PM

Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0




GSTABL7 v.2 FSmin=2.589

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION A-A', EAST, STATIC, FAILURE PLANE 1

c:\slope\seca-ees1 new.plt Run By: Jason Lee, Hushmand Associates, Inc 7/24/2008 06:11PM



GSTABL7 v.2 FSmin=1.021

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)






# KHF, SECTION A-A', EAST, STATIC, FAILURE PLANE 2

c:\slope\seca-ess2.plt Run By: Jason Lee, Hushmand Associates, Inc 7/24/2008 12:13PM

Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0




GSTABL7 v.2 FSmin=2.689

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION A-A', EAST, PSEUD-STATIC, FAILURE PLANE 2

c:\slope\seca-ees2.plt Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 04:28PM



GSTABL7 v.2 FSmin=1.008


Factor Of Safety Is Calculated By The Simplified anlb Method





# KHF, SECTION A-A', EAST, STATIC, FAILURE PLANE 3

c:\slope\seca-esj3.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 10:42AM



GSTABL7 v.2 FSmin=2.472

Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method





# KHF, SECTION A-A', EAST, PSEUD-STATIC, FAILURE PLANE 3

c:\slope\seca-ees3.plt Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 04:42PM

1500

Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0

Load Peak(A) Kh Coef.	Value
0.570(g)	0.237(g)<

1200


900

600

300

0

128.6 428.6 728.6 1028.6 1328.6 1628.6 1928.6 2228.6 2528.6



GSTABL7 v.2 FSmin=1.005


Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION A-A', WEST, STATIC, FAILURE PLANE I

c:\slope\seca-wsj i.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:14AM

#	FS	Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
a	2.831	Refuse	1	115.0	115.0	0.0	31.0	0
b	2.831	Liner	2	115.0	115.0	0.0	19.0	0
c	2.866	Bedrock	3	130.0	130.0	800.0	40.0	0
d	2.885	P1 Base	4	115.0	115.0	0.0	17.0	0
e	2.885	P1 Slope	5	115.0	115.0	800.0	9.0	0
f	2.897							
g	2.897							
h	2.897							
i	2.897							
j	2.897							



GSTABL7 v.2 FSmin=2.831


Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method



# KHF, SECTION A-A', WEST, STATIC, FAILURE PLANE I

c:\slope\seca-wss i.plt Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:16AM

Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0




GSTABL7 v.2 FSmin=4.194

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION A-A', WEST, PSEUDO-STATIC, FAILURE PLANE I

c:\slope\seca-wes i.plt Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:18AM




GSTABL7 v.2 FSmin=1.002

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION A-A', WEST, STATIC, FAILURE PLANE II

c:\slope\seca-ws.ii.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:19AM



GSTABL7 v.2 FSmin=5.435


Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method



# KHF, SECTION A-A', WEST, STATIC, FAILURE PLANE II

c:\slope\seca-wss ii.plt Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:20AM

Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0



GSTABL7 v.2 FSmin=7.249


Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)





# KHF, SECTION A-A', WEST, PSEUD-STATIC, FAILURE PLANE II

c:\slope\seca-wes ii.plt Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:21AM




GSTABL7 v.2 FSmin=1.004

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 1

c:\khf\slope\secb-esj1.p12 Run By: BH 7/10/2008 02:23PM




GSTABL7 v.2 FSmin=4.248

Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method



# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 1

c:\khf\slope\secb-ess1.plt Run By: BH 7/10/2008 02:25PM




GSTABL7 v.2 FSmin=6.798

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, PSEUD-STATIC, FAILURE PLANE 1

c:\khf\slopese\b-ees1.plt Run By: BH 7/10/2008 02:21PM




GSTABL7 v.2 FSmin=1.001

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 2

c:\khnfslope\secb-esj2.pl2 Run By: BH 7/11/2008 03:34PM




GSTABL7 v.2 FSmin=7.317

Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method



# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 2

c:\khnfslope\secb-ess2.plt Run By: BH 7/11/2008 03:35PM




GSTABL7 v.2 FSmin=8.590

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, PSEUD-STATIC, FAILURE PLANE 2

c:\khf\slope\secb-ees2.plt Run By: BH 7/11/2008 03:37PM




GSTABL7 v.2 FSmin=1.009

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 3

c:\khnfslope\secb-esj3.p12 Run By: BH 7/11/2008 03:39PM



GSTABL7 v.2 FSmin=5.698


Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method





# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 3

c:\khf\slope\secb-ess3.plt Run By: BH 7/11/2008 03:40PM




GSTABL7 v.2 FSmin=6.542

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, PSEUD-STATIC, FAILURE PLANE 3

c:\khnfslop\psecb-ees3.plt Run By: BH 7/11/2008 03:41PM



Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0

Load Peak(A) kh Coef.	Value
0.570(g)	0.570(g)
0.356(g)	0.356(g)


GSTABL7 v.2 FSmin=1.008

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', WEST, STATIC, FAILURE PLANE I

c:\kfh\slope\secb-wsjj.pl2 Run By: BH 7/10/2008 04:29PM




GSTABL7 v.2 FSmin=2.438

Safety Factors Are Calculated By The Simplified  $\alpha$ n $\beta$  Method



# KHF, SEC. B-B', WEST, STATIC, FAILURE PLANE I

c:\kfh\slope\secb-wssi.plt Run By: BH 7/10/2008 04:30PM




GSTABL7 v.2 FSmin=3.500

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', WEST, PSEUDO-STATIC, FAILURE PLANE I

c:\kfh\slp\secb-west.wesi.plt Run By: BH 7/10/2008 04:32PM




GSTABL7 v.2 FSmin=1.001

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', ~~EST~~, STATIC, FAILURE PLAN II

c:\khnfslop\secb-wsjj.pl2 Run By: BH 7/10/2008 05:28PM




GSTABL7 v.2 FSmin=4.34

Safety Factors Are Calculated By The Simplified  $\alpha$ n $\beta$  Method



# KHF, SEC. B-B', ~~EST~~, STATIC, FAILURE PLAN II

c:\khnfslop\pelsecb-wssj.plt Run By: BH 7/10/2008 05:29PM




GSTABL7 v.2 FSmin=8.928  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', WEST, PSEUDO-STATIC, FAILURE PLANE II

c:\kfh\slope\secb-wesj.plt Run By: BH 7/10/2008 05:40PM




GSTABL7 v.2 FSmin=1.099  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)





# KHF, SEC. C-C; NORTH, STATIC, FAILURE SURFACE 1

c:\khslope\secc-nsj1.pl2 Run By: BH 7/10/2008 06:51PM




GSTABL7 v.2 FSmin=1.968

Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method



# KHF, SEC. C-C; NORTH, STATIC, FAILURE SURFACE 1

c:\khslope\secc-nss1.plt Run By: BH 7/10/2008 06:52PM




GSTABL7 v.2 FSmin=3.08

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. C-C', NORTH, PSEUDO-STATIC, FAILURE SURFACE 1

c:\kfh\slope\secc-nes1.plt Run By: BH 7/10/2008 06:53PM




GSTABL7 v.2 FSmin=1.002

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. C-C; NORTH, STATIC, FAILURE SURFACE 2

c:\khslope\secc-nsj2.pl2 Run By: BH 7/11/2008 02:51PM



GSTABL7 v.2 FSmin=2.446


Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method



# KHF, SEC. C-C; NORTH, STATIC, FAILURE SURFACE 2

c:\khslope\secc-nss2.plt Run By: BH 7/11/2008 02:53PM

Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0




GSTABL7 v.2 FSmin=4.346

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. C-C', NORTH, PSEUDO-STATIC, FAILURE SURFACE 2

c:\kfh\slope\secc-nes2.plt Run By: BH 7/11/2008 02:54PM




GSTABL7 v.2 FSmin=1.018

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. C-C', SOUTH, STATIC, FAILURE SURFACE I

c:\kfh\slope\secc-ssji.pl2 Run By: BH 7/11/2008 02:25PM




GSTABL7 v.2 FSmin=4.032

Safety Factors Are Calculated By The Simplified  $\alpha$ n $\beta$  Method



# KHF, SEC. C-C', SOUTH, STATIC, FAILURE SURFACE I

c:\kfh\slope\secc-sssi.plt Run By: BH 7/11/2008 02:26PM



GSTABL7 v.2 FSmin=4.920


Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)





# KHF, SEC. C-C', SOUTH, PSEUDO-STATIC, FAILURE SURFACE I

c:\khslope\secc-sesi.plt Run By: BH 7/11/2008 02:27PM



GSTABL7 v.2 FSmin=1.002


Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)





# KHF, SEC. C-C', SOUTH, STATIC, FAILURE SURFACE II

c:\khslope\secc-sssii.plt Run By: BH 7/11/2008 02:30PM




GSTABL7 v.2 FSmin=5.39

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. C-C', SOUTH, PSEUDO-STATIC, FAILURE SURFACE II

c:\khslope\secc-sesii.plt Run By: BH 7/11/2008 02:32PM




GSTABL7 v.2 FSmin=1.05

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. D-D', EAST, STATIC, FAILURE SURFACE 1

c:\khslope\secd-esj1.p12 Run By: BH 7/11/2008 10:14AM




GSTABL7 v.2 FSmin=2.025

Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method



# KHF, SEC. D-D', EAST, STATIC, FAILURE SURFACE 1

c:\kfh\slope\secd-ess1.plt Run By: BH 7/11/2008 10:15AM




GSTABL7 v.2 FSmin=2.337

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. D-D', EAST, PSEUDO-STATIC, FAILURE SURFACE 1

c:\kfh\slopelsecd-ees1.plt Run By: BH 7/11/2008 10:16AM




GSTABL7 v.2 FSmin=1.004  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. DEAST, STATIC, FAILURE SURFACE 2

c:\khslope\secd-esj2.pl2 Run By: BH 7/11/2008 10:21AM



GSTABL7 v.2 FSmin=2.28


Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method





# KHF, SEC. DEAST, STATIC, FAILURE SURFACE 2

c:\kfh\slope\secd-ess2.plt Run By: BH 7/11/2008 10:24AM




GSTABL7 v.2 FSmin=2.87  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. DEAST, PSEUD-STATIC, FAILURE SURFACE 2

c:\khnfslop\secd-ees2.plt | Run By: BH 7/11/2008 10:40AM




GSTABL7 v.2 FSmin=1.025  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)





# KHF, SEC. DWEST, STATIC, FAILURE SURFACE I

c:\kfh\slope\secd-wssi.plt Run By: BH 7/11/2008 11:35AM




GSTABL7 v.2 FSmin=3.8  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. D WEST, PSEUD-STATIC, FAILURE SURFACE I

c:\kfhfslpsecc-wesi.plt Run By: BH 7/11/2008 11:36AM




GSTABL7 v.2 FSmin=1.009  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. DWEST, STATIC, FAILURE PLANE II

c:\khslope\secd-wsbjii.pl2 Run By: BH 7/11/2008 01:17PM




GSTABL7 v.2 FSmin=2.501

Safety Factors Are Calculated By The Modified Bishop Method



# KHF, SEC. DWEST, PSEUD-STATIC, FAILURE PLANE II

c:\khf\slope\secd-webii.plt Run By: BH 7/11/2008 01:16PM




GSTABL7 v.2 FSmin=1.019  
Factor Of Safety Is Calculated By The Modified Bishop Method



# KHF, SEC. DWEST, STATIC, FAILURE PLANE III

c:\khslope\secd-wsbjii.pl2 Run By: BH 7/11/2008 01:31PM




GSTABL7 v.2 FSmin=2.18  
Safety Factors Are Calculated By The Modified Bishop Method





# KHF, SEC. DWEST, PSEUD-STATIC, FAILURE PLANE III

c:\khf\slope\secd-web\iii.pl2 Run By: BH 7/11/2008 01:33PM




GSTABL7 v.2 FSmin=1.048  
Safety Factors Are Calculated By The Modified Bishop Method



# KHF, SECTION E-E', EAST, STATIC, FAILURE PLANE 1

c:\slope\sece-esj1.p12 Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 01:56PM




GSTABL7 v.2 FSmin=2.342

Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method



# KHF, SECTION E-E', EAST, STATIC, FAILURE PLANE 1

c:\slope\sece-ess1.plt Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 02:06PM




GSTABL7 v.2 FSmin=2.743  
 Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION E-E', EAST, PSEUD-STATIC, FAILURE PLANE 1

c:\slope\sece-ees1.plt Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 02:08PM




GSTABL7 v.2 FSmin=1.004  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION E-E', EAST, STATIC, FAILURE PLANE 2

c:\slope\sece-esj2.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 01:46PM




GSTABL7 v.2 FSmin=2.502  
 Safety Factors Are Calculated By The Simplified  $\alpha$ n $\beta$  Method



# KHF, SECTION E-E', EAST, STATIC, FAILURE PLANE 2

c:\slope\sece-ess2.plt Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 02:10PM




Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0

GSTABL7 v.2 FSmin=2.747  
 Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION E-E', EAST, PSEUD-STATIC, FAILURE PLANE 2

c:\slopes\sece-ees2.plt Run By: Jason Lee, Hushmand Associates, Inc 7/24/2008 01:23PM




GSTABL7 v.2 FSmin=1.030  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION E-E', EAST, STATIC, FAILURE PLANE 3

c:\slope\sece-esj3.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 01:32PM




GSTABL7 v.2 FSmin=2.506  
Safety Factors Are Calculated By The Simplified  $\alpha$ n $\beta$  Method





# KHF, SECTION E-E', EAST, STATIC, FAILURE PLANE 3

c:\slope\sece-ess3.plt Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 02:40PM




GSTABL7 v.2 FSmin=2.730  
 Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION E-E', EAST, PSEUD-STATIC, FAILURE PLANE 3

c:\slope\sece-ees3.plt Run By: Jason Lee, Hushmand Associates, Inc 7/11/2008 02:43PM




GSTABL7 v.2 FSmin=1.006  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION E-E' WEST, STATIC, FAILURE PLANE I

c:\slope\sece-wsj i.p12 Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:27AM




GSTABL7 v.2 FSmin=4.10

Safety Factors Are Calculated By The Simplified  $\alpha$ nb Method



# KHF, SECTION E-E', WEST, STATIC, FAILURE PLANE I

c:\slope\sece-wss i.plt Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:29AM



GSTABL7 v.2 FSmin=5.431

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)




# KHF, SECTION E-E', WEST, PSEUD-STATIC, FAILURE PLANE I

c:\slopel\sece-wes i.plt Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:31AM

Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0

Load	Value
Peak(A)	0.570(g)
kh Coef.	0.425(g)<




GSTABL7 v.2 FSmin=1.000  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION E-E', WEST, STATIC, FAILURE PLANE II

c:\slope\sece-wsj ii.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:33AM




GSTABL7 v.2 FSmin=7.373  
 Safety Factors Are Calculated By The Simplified  $\alpha$ n $\beta$  Method



# KHF, SECTION E-E', WEST, STATIC, FAILURE PLANE II

c:\slope\sece-wss ii new2.plt Run By: Jason Lee, Hushmand Associates, Inc 7/24/2008 03:53PM

Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0




GSTABL7 v.2 FSmin=0.89  
 Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION E-E', WEST, STATIC, FAILURE PLANE II

c:\slope\sece-wes ii new2.plt Run By: Jason Lee, Hushmand Associates, Inc 7/24/2008 04:03PM



GSTABL7 v.2 FSmin=1.004


Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)





# KHF, SECTION F-F', EAST, STATIC, FAILURE PLANE 1

c:\slope\secf-esj1new.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/24/2008 02:20PM



#	FS	Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion (psf)	Friction Angle (deg)	Piez. Surface No.
a	2.482	Refuse	1	115.0	115.0	0.0	31.0	0
b	2.482	Liner	2	115.0	115.0	0.0	19.0	0
c	2.482	Bedrock	3	130.0	130.0	800.0	40.0	0
d	2.482	P1 Base	4	115.0	115.0	0.0	17.0	0
e	2.523	P1 Slope	5	115.0	115.0	800.0	9.0	0

g	2.523
h	2.523
i	2.523
j	2.523


GSTABL7 v.2 FSmin=2.482

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SECTION F-F', EAST, STATIC, FAILURE PLANE 1

c:\slope\secf-ess1new.plt Run By: Jason Lee, Hushmand Associates, Inc 7/24/2008 02:21PM




Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0

GSTABL7 v.2 FSmin=2.805  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION F-F', EAST, STATIC, FAILURE PLANE 1

c:\slope\secf-ees1new.plt Run By: Jason Lee, Hushmand Associates, Inc 7/24/2008 02:23PM




GSTABL7 v.2 FSmin=1.005  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)





# KHF, SECTION F-F', EAST, STATIC, FAILURE PLANE 2

c:\slope\secf-ess2.plt Run By: Jason Lee, Hushmand Associates, Inc 7/10/2008 02:29PM




GSTABL7 v.2 FSmin=2.467

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION F-F', EAST, PSEUDO-STATIC, FAILURE PLANE 2

c:\slope\secf-ees2.plt Run By: Jason Lee, Hushmand Associates, Inc 7/10/2008 02:42PM




GSTABL7 v.2 FSmin=1.004  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION F-F', EAST, STATIC, FAILURE PLANE 3

c:\slope\secf-esj3.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/10/2008 02:07PM




GSTABL7 v.2 FSmin=2.258

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SECTION F-F', EAST, STATIC, FAILURE PLANE 3

c:\slope\secf-ess3.plt Run By: Jason Lee, Hushmand Associates, Inc 7/10/2008 02:10PM



Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0

GSTABL7 v.2 FSmin=2.460


Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)





# KHF, SECTION F-F', EAST, PSEUDO-STATIC, FAILURE PLANE 3

c:\slope\secf-ees3.plt Run By: Jason Lee, Hushmand Associates, Inc 7/10/2008 02:12PM




GSTABL7 v.2 FSmin=1.002  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION F-F', WEST, STATIC, FAILURE PLANE I

c:\slope\secf-wsj i.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/10/2008 04:39PM




GSTABL7 v.2 FSmin=2.578

Safety Factors Are Calculated By The Modified Bishop Method



# KHF, SECTION F-F', WEST, STATIC, FAILURE PLANE I

c:\slope\secf-wss i.plt Run By: Jason Lee, Hushmand Associates, Inc 7/10/2008 04:30PM




GSTABL7 v.2 FSmin=2.547

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION F-F', WEST, STATIC, FAILURE PLANE I

c:\slope\sectf-web i.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/25/2008 11:40AM




GSTABL7 v.2 FSmin=1.003

Safety Factors Are Calculated By The Modified Bishop Method



# KHF, SECTION F-F', WEST, STATIC, FAILURE PLANE II

c:\slope\secf-wsj ii new.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:51AM




GSTABL7 v.2 FSmin=4.028

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SECTION F-F', WEST, STATIC, FAILURE PLANE II

c:\slope\secf-wss ii new.plt Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:53AM




GSTABL7 v.2 FSmin=5.894  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION F-F', WEST, PSEUDO-STATIC, FAILURE PLANE II

c:\slope\secf-wes ii new.plt Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:55AM




GSTABL7 v.2 FSmin=1.006  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION F-F', WEST, STATIC, FAILURE PLANE III

c:\slope\secf-wsj iii new.pl2 Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:57AM



GSTABL7 v.2 FSmin=3.835


Safety Factors Are Calculated By The Simplified Janbu Method





# KHF, SECTION F-F', WEST, STATIC, FAILURE PLANE III

c:\slope\secf-wss iii new.plt Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 09:59AM




GSTABL7 v.2 FSmin=7.205

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION F-F', WEST, PSEUDO-STATIC, FAILURE PLANE III

c:\slope\secf-wes iii new.plt Run By: Jason Lee, Hushmand Associates, Inc 7/14/2008 10:00AM



GSTABL7 v.2 FSmin=1.006  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



Kettleman Hills Landfill B-18 Site Response, F East, Pacoima 360  
 UNITS (E for English, S for SI):  
 \*\*\* (A1)  
 E DRE PRM ROCKVP ROCKVS ROCKRHO \*\*\* (5F10.0)  
 \*\*\* 1 0.65 3000.00 2500.00 150.00 \*\*\* (3I5)  
 NEML NDP1 NSLP  
 \*\*\* 1504 1586 1  
 KGMAX KGEQ N1EQ N2EQ N3EQ NUMB KV KSAV \*\*\* (8I5)  
 \*\*\* 2000 2000 1 2000 4 1  
 DTEQ EQMUL1 UGMAX1 UGMAX2 HDRX HDRY NPLX NPLY PRINPUL \*\*\*  
 (5F10.0,4I5,F10.0) \*\*\*  
 EARTHQUAKE INPUT FILE NAME(S) & FORMAT(S) (\* For FREE FORMAT) \*\*\* (A)  
 \*\*\* 0.02 I.0 0.0 0.0 5 0 0 0 0.20  
 pac360A.DAT  
 \* SOUT AOUT KOUT \*\*\* (3I5)  
 \*\*\* 0 0 1  
 SEISMIC COEFF OUTPUT FORMAT (M or C), FILE PREFIX, AND SUFFIX: \*\*\* (A)  
 \*\*\*

C fEpac2  
 Q4K NSEG ESEG \*\*\* (2I5)  
 \*\*\* 91 771  
 NOSEG \*\*\* (15I5)  
 \*\*\* 2 3 6 11 16 22 28 35 42 50 58 67 76 85 94  
 104 114 125 136 148 160 172 184 197 210 223 236 249 263 277  
 291 305 320 335 350 365 380 395 411 427 443 459 476 493 510  
 528 546 564 582 600 619 638 657 676 695 714 733 751 769 788  
 786 785 803 802 821 820 819 838 837 856 855 875 874 894 893  
 914 913 935 934 957 956 978 1000 999 1023 1022 1046 1045  
 1044  
 ELSEG \*\*\* (15I5)  
 \*\*\* 3 5 6 7 9 10 11 13 14 15 16 18 19 20 21  
 23 24 25 26 27 29 30 31 32 33 35 36 37 38 39  
 40 42 43 44 45 46 47 49 50 51 52 53 54 55 57  
 58 59 60 61 62 63 65 66 67 68 69 70 71 73 74  
 75 76 77 78 79 81 82 83 84 85 86 87 88 90 91  
 92 93 94 95 96 97 99 100 101 102 103 104 105 106 107  
 109 110 111 112 113 114 115 116 117 119 120 121 122 123 124  
 125 126 127 128 130 131 132 133 134 135 136 137 138 139 141  
 142 143 144 145 146 147 148 149 150 152 153 154 155 156 157  
 158 159 160 161 163 164 166 167 168 169 170 171 172 173  
 175 176 177 178 179 180 181 182 183 184 185 187 188  
 191 192 193 194 195 196 197 199 200 201 202 203 204 205 206  
 207 208 209 211 212 213 214 215 216 217 218 219 220 221 223  
 224 225 226 227 228 229 230 231 232 233 234 236 238 239  
 240 241 242 243 244 245 246 247 248 250 251 252 253 254 255  
 256 257 258 259 260 262 263 264 265 266 267 268 269 270 271  
 272 273 275 276 277 278 279 280 281 282 283 284 285 286 287  
 289 290 291 292 293 294 295 296 297 298 299 300 301 303 304  
 305 306 307 308 309 310 311 312 313 314 315 317 318 319 320  
 321 322 323 324 325 326 327 328 329 331 332 333 334 335 336  
 337 338 339 340 341 342 343 346 347 348 349 350 351 352

LSTR	N	NP1	**N2	NP3	NP4	TYPE	DENS	PO	GMX	G	XL				
353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368
369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384
385	386	389	390	391	392	393	394	395	396	397	398	399	400	401	402
401	402	404	405	406	407	408	409	410	411	412	413	414	415	416	417
417	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433
433	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449
449	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465
465	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481
481	482	484	485	486	487	488	489	490	491	492	493	494	495	496	497
497	498	499	501	502	503	504	505	506	507	508	509	510	511	512	513
513	514	515	516	518	519	520	521	522	523	524	525	526	527	528	529
529	530	531	532	533	535	536	537	538	539	540	541	542	543	544	545
545	546	547	548	549	550	552	553	554	555	556	557	558	559	560	561
561	562	563	564	565	566	567	568	570	571	572	573	574	575	576	577
577	578	579	580	581	582	583	584	585	586	588	589	590	591	592	593
593	594	595	596	597	598	599	600	601	602	603	604	606	607	608	609
609	610	611	612	613	614	615	616	617	618	619	620	621	622	624	625
625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640
640	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656
656	657	658	660	661	662	663	664	665	666	667	668	669	670	671	672
672	673	674	675	676	678	679	680	681	682	683	684	685	686	687	688
688	689	690	691	692	693	694	696	697	698	699	700	701	702	703	704
704	705	706	707	708	709	710	711	713	714	715	716	717	718	719	720
720	721	722	723	724	725	726	727	730	731	732	733	734	735	736	737
737	738	739	740	741	742	743	747	748	749	750	751	752	753	754	755
755	756	757	758	759	760	765	766	767	768	769	770	771	772	773	774
774	775	776	783	784	785	786	787	788	789	790	791	792	793	802	803
803	804	805	806	807	808	809	810	811	821	822	823	824	825	826	827
827	828	829	841	842	843	844	845	846	847	848	862	863	864	865	866
866	867	868	884	885	886	887	888	889	906	907	908	909	928	929	930
930	950	951	952	973	974	975	976	977	978	979	980	981	982	983	984



157	168	180	179	167	2	115.00	fEpac2	0.35	4178.61	3342.89	0.05	220	235	248	247	234	115.00	fEpac2	0.35	5697.98	4558.38	0.05	
158	169	181	180	168	2	115.00	0.05	4598.09	3678.47	0.05	221	236	249	248	235	115.00	0.35	6012.39	4809.91	0.05	6012.39	4809.91	0.05
159	170	182	181	169	2	115.00	0.05	4979.66	3983.73	0.05	222	237	250	249	236	115.00	0.35	6322.61	5058.09	0.05	6322.61	5058.09	0.05
160	171	183	182	170	2	115.00	0.05	5340.05	4272.04	0.05	223	239	252	251	238	115.00	0.35	418.01	334.41	0.05	418.01	334.41	0.05
161	172	184	183	171	2	115.00	0.05	5674.17	4539.33	0.05	224	239	252	251	239	115.00	0.35	1386.46	1109.17	0.05	1386.46	1109.17	0.05
162	173	185	184	172	3	115.00	0.05	5984.27	4787.41	0.05	225	240	253	252	239	115.00	0.35	2063.90	1651.12	0.05	2063.90	1651.12	0.05
163	174	187	186	174	3	115.00	0.05	418.01	334.41	0.05	226	241	255	254	240	115.00	0.35	2809.31	2247.45	0.05	2809.31	2247.45	0.05
164	175	188	187	175	2	115.00	0.05	1381.68	1105.34	0.05	227	242	256	255	241	115.00	0.35	3417.75	2734.20	0.05	3417.75	2734.20	0.05
165	176	189	188	176	2	115.00	0.05	2051.26	1641.01	0.05	228	243	257	256	242	115.00	0.35	3906.74	3125.39	0.05	3906.74	3125.39	0.05
166	177	190	189	177	2	115.00	0.05	2794.67	2235.73	0.05	229	244	258	257	243	115.00	0.35	4344.51	3475.61	0.05	4344.51	3475.61	0.05
167	178	191	190	178	2	115.00	0.05	3401.30	2721.04	0.05	230	245	260	259	244	115.00	0.35	4749.88	3799.90	0.05	4749.88	3799.90	0.05
168	179	192	191	178	2	115.00	0.05	3885.09	3108.07	0.05	231	246	262	261	245	115.00	0.35	5113.07	4080.46	0.05	5113.07	4080.46	0.05
169	180	193	192	179	2	115.00	0.05	4321.87	3457.40	0.05	232	247	263	262	246	115.00	0.35	5454.90	4363.92	0.05	5454.90	4363.92	0.05
170	181	194	193	180	2	115.00	0.05	4726.06	3780.85	0.05	233	248	264	263	247	115.00	0.35	5780.98	4624.78	0.05	5780.98	4624.78	0.05
171	182	195	194	181	2	115.00	0.05	5085.38	4088.50	0.05	234	249	265	264	248	115.00	0.35	6082.93	4866.34	0.05	6082.93	4866.34	0.05
172	183	196	195	182	2	115.00	0.05	5426.37	4341.10	0.05	235	250	266	265	249	115.00	0.35	6385.64	5108.51	0.05	6385.64	5108.51	0.05
173	184	197	196	183	2	115.00	0.05	5751.22	4600.98	0.05	236	252	267	266	251	115.00	0.35	418.01	334.41	0.05	418.01	334.41	0.05
174	185	198	197	184	3	115.00	0.05	6051.98	4841.58	0.05	237	253	267	266	252	115.00	0.35	1556.20	1244.96	0.05	1556.20	1244.96	0.05
175	186	199	198	185	2	115.00	0.05	418.01	334.41	0.05	238	254	268	267	253	115.00	0.35	2476.61	1981.28	0.05	2476.61	1981.28	0.05
176	187	200	199	186	3	115.00	0.05	1549.54	1239.63	0.05	239	255	269	268	254	115.00	0.35	3096.61	2477.29	0.05	3096.61	2477.29	0.05
177	188	201	200	187	2	115.00	0.05	2464.18	1971.35	0.05	240	256	270	269	255	115.00	0.35	3624.95	2899.96	0.05	3624.95	2899.96	0.05
178	189	202	201	188	2	115.00	0.05	3075.91	2460.73	0.05	241	257	271	270	256	115.00	0.35	4095.79	3276.63	0.05	4095.79	3276.63	0.05
179	190	203	202	189	2	115.00	0.05	3602.71	2882.17	0.05	242	258	272	271	257	115.00	0.35	4496.87	3597.49	0.05	4496.87	3597.49	0.05
180	191	204	203	190	2	115.00	0.05	4071.68	3257.35	0.05	243	259	273	272	258	115.00	0.35	4874.26	3899.41	0.05	4874.26	3899.41	0.05
181	192	205	204	191	2	115.00	0.05	4467.40	3573.92	0.05	244	260	274	273	259	115.00	0.35	5227.62	4182.09	0.05	5227.62	4182.09	0.05
182	193	206	205	192	2	115.00	0.05	4843.58	3874.87	0.05	245	261	275	274	260	115.00	0.35	5549.56	4439.65	0.05	5549.56	4439.65	0.05
183	194	207	206	193	2	115.00	0.05	5192.22	4153.77	0.05	246	262	276	275	261	115.00	0.35	5859.85	4687.88	0.05	5859.85	4687.88	0.05
184	195	208	207	194	2	115.00	0.05	5513.29	4410.63	0.05	247	263	277	276	262	115.00	0.35	6153.62	4922.90	0.05	6153.62	4922.90	0.05
185	196	209	208	195	2	115.00	0.05	5822.57	4658.06	0.05	248	264	278	277	263	115.00	0.35	6448.66	5158.93	0.05	6448.66	5158.93	0.05
186	197	210	209	196	2	115.00	0.05	6119.69	4895.75	0.05	249	266	280	279	265	115.00	0.35	418.01	334.41	0.05	418.01	334.41	0.05
187	198	211	210	197	3	115.00	0.05	418.01	334.41	0.05	250	267	281	280	266	115.00	0.35	1566.49	1253.19	0.05	1566.49	1253.19	0.05
188	199	212	211	198	2	115.00	0.05	1560.85	1248.68	0.05	251	268	282	281	267	115.00	0.35	2495.77	1996.62	0.05	2495.77	1996.62	0.05
189	200	213	212	199	2	115.00	0.05	2485.27	1688.21	0.05	252	269	283	282	268	115.00	0.35	3128.56	2502.85	0.05	3128.56	2502.85	0.05
190	201	214	213	200	2	115.00	0.05	3111.05	2488.84	0.05	253	270	284	283	269	115.00	0.35	3659.27	2927.42	0.05	3659.27	2927.42	0.05
191	202	215	214	201	2	115.00	0.05	3440.46	2923.37	0.05	254	271	285	284	270	115.00	0.35	4132.39	3206.32	0.05	4132.39	3206.32	0.05
192	203	216	215	202	2	115.00	0.05	3640.46	3290.08	0.05	255	272	286	285	271	115.00	0.35	4542.33	3693.86	0.05	4542.33	3693.86	0.05
193	204	217	216	203	2	115.00	0.05	4112.60	3290.08	0.05	256	273	287	286	272	115.00	0.35	4921.60	3937.28	0.05	4921.60	3937.28	0.05
194	205	218	217	204	2	115.00	0.05	4517.41	3613.95	0.05	257	274	288	287	273	115.00	0.35	5279.49	4223.59	0.05	5279.49	4223.59	0.05
195	206	219	218	205	2	115.00	0.05	4895.65	3916.52	0.05	258	275	289	288	274	115.00	0.35	5605.53	4484.42	0.05	5605.53	4484.42	0.05
196	207	220	219	206	2	115.00	0.05	5252.30	4201.84	0.05	259	276	290	289	275	115.00	0.35	5917.37	4733.90	0.05	5917.37	4733.90	0.05
197	208	221	220	207	2	115.00	0.05	5574.85	4459.88	0.05	260	277	291	290	276	115.00	0.35	6217.12	4973.70	0.05	6217.12	4973.70	0.05
198	209	222	221	208	2	115.00	0.05	5885.84	4708.68	0.05	261	278	292	291	277	115.00	0.35	6511.69	5209.35	0.05	6511.69	5209.35	0.05
199	210	223	222	209	3	115.00	0.05	6187.41	4949.92	0.05	262	280	294	293	279	115.00	0.35	418.01	334.41	0.05	418.01	334.41	0.05
200	211	224	223	210	3	115.00	0.05	418.01	334.41	0.05	263	281	295	294	280	115.00	0.35	1576.77	1261.42	0.05	1576.77	1261.42	0.05
201	212	225	224	211	2	115.00	0.05	1572.16	1257.73	0.05	264	282	296	295	281	115.00	0.35	2514.94	2011.95	0.05	2514.94	2011.95	0.05
202	213	226	225	212	2	115.00	0.05	2005.08	1605.08	0.05	265	283	297	296	282	115.00	0.35	3160.51	2528.41	0.05	3160.51	2528.41	0.05
203	214	227	226	213	2	115.00	0.05	3146.19	2516.95	0.05	266	284	298	297	283	115.00	0.35	3693.59	2954.87	0.05	3693.59	2954.87	0.05
204	215	228	227	214	2	115.00	0.05	3678.21	2942.57	0.05	267	285	299	298	284	115.00	0.35	4170.19	3336.15	0.05	4170.19	3336.15	0.05
205	216	229	228	215	2	115.00	0.05	4153.52	3322.81	0.05	268	286	300	299	285	115.00	0.35	4587.79	3670.24	0.05	4587.79	3670.24	0.05
206	217	230	229	216	2	115.00	0.05	4567.42	3653.94	0.05	269	287	301	300	286	115.00	0.35	4968.94	3975.15	0.05	4968.94	3975.15	0.05
207	218	231	230	217	2	115.00	0.05	4947.73	3958.18	0.05	270	288	302	301	287	115.00	0.35	5328.87	4263.09	0.05	5328.87	4263.09	0.05
208	219	232	231	218	2	115.00	0.05	5306.74	4245.39	0.05	271	289	303	302	288	115.00	0.35	5661.49	4529.19	0.05	5661.49	4529.19	0.05
209	220	233	232	219	2	115.00	0.05	5636.41	4509.13	0.05	272	290	304	303	289	115.00	0.35	5974.89	4779.91	0.05	5974.89	4779.91	0.05
210	221	234	233	220	2	115.00	0.05	5949.12	4759.29	0.05	273	291	305	304	290	115.00	0.35	6276.30	5021.04	0.05	627		

283	301	316	315	300	115.00	fEpac2	0.35	5087.31	4069.85	0.05	346	369	384	383	368	2	115.00	fEpac2	0.35	1574.57	1259.66	0.05
284	302	317	316	301	0.05		0.05	5428.20	4342.56	0.05	347	370	385	384	369	2	115.00		0.35	2510.84	2008.67	0.05
285	303	318	317	302	0.05		0.05	5753.14	4602.51	0.05	348	371	386	385	370	2	115.00		0.35	3153.67	2522.94	0.05
286	304	319	318	303	0.05		0.05	6052.10	4841.68	0.05	349	372	387	386	371	2	115.00		0.35	3686.25	2949.00	0.05
287	305	320	319	304	0.05		0.05	6341.58	5073.26	0.05	350	373	388	387	372	2	115.00		0.35	4162.23	3329.78	0.05
288	306	321	320	305	0.05		0.05	6637.74	5310.19	0.05	351	374	389	388	373	2	115.00		0.35	4578.07	3662.45	0.05
289	307	322	321	306	0.05		0.05	6934.01	5551.87	0.05	352	375	390	389	374	2	115.00		0.35	4958.81	3967.65	0.05
290	308	323	322	307	0.05		0.05	7232.35	5799.64	0.05	353	376	391	390	375	2	115.00		0.35	5318.30	4254.64	0.05
291	309	324	323	308	0.05		0.05	7532.76	6052.82	0.05	354	377	392	391	376	2	115.00		0.35	5649.52	4570.62	0.05
292	310	325	324	309	0.05		0.05	7835.24	6310.68	0.05	355	378	393	392	377	2	115.00		0.35	5962.59	4770.07	0.05
293	311	326	325	310	0.05		0.05	8140.80	6573.53	0.05	356	379	394	393	378	2	115.00		0.35	6266.64	5010.91	0.05
294	312	327	326	311	0.05		0.05	8448.43	6841.68	0.05	357	380	395	394	379	2	115.00		0.35	6547.14	5230.77	0.05
295	313	328	327	312	0.05		0.05	8758.14	7115.32	0.05	358	381	396	395	380	2	115.00		0.35	6843.78	5475.02	0.05
296	314	329	328	313	0.05		0.05	9069.94	7394.81	0.05	359	382	397	396	381	2	115.00		0.35	7148.01	5734.41	0.05
297	315	330	329	314	0.05		0.05	9383.83	7679.61	0.05	360	383	398	397	382	2	115.00		0.35	7486.65	6019.32	0.05
298	316	331	330	315	0.05		0.05	9709.82	7969.24	0.05	361	384	400	399	383	2	115.00		0.35	7860.02	6348.02	0.05
299	317	332	331	316	0.05		0.05	10047.92	8263.13	0.05	362	385	401	400	384	2	115.00		0.35	8269.98	6726.39	0.05
300	318	333	332	317	0.05		0.05	10398.14	8561.68	0.05	363	386	402	401	385	2	115.00		0.35	8703.02	7144.42	0.05
301	319	334	333	318	0.05		0.05	10760.47	8865.30	0.05	364	387	403	402	386	2	115.00		0.35	9179.61	7603.69	0.05
302	320	335	334	319	0.05		0.05	11134.91	9174.41	0.05	365	388	404	403	387	2	115.00		0.35	9693.81	8117.94	0.05
303	321	336	335	320	0.05		0.05	11521.46	9488.41	0.05	366	389	405	404	388	2	115.00		0.35	10246.62	8688.04	0.05
304	322	337	336	321	0.05		0.05	11921.11	9807.82	0.05	367	390	406	405	389	2	115.00		0.35	10839.25	9325.25	0.05
305	323	338	337	322	0.05		0.05	12333.86	10142.04	0.05	368	391	407	406	390	2	115.00		0.35	11472.08	10048.23	0.05
306	324	339	338	323	0.05		0.05	12759.71	10491.53	0.05	369	392	408	407	391	2	115.00		0.35	12147.28	10867.83	0.05
307	325	340	339	324	0.05		0.05	13198.66	10856.82	0.05	370	393	409	408	392	2	115.00		0.35	12865.79	11807.51	0.05
308	326	341	340	325	0.05		0.05	13650.71	11238.41	0.05	371	394	410	409	393	2	115.00		0.35	13628.16	12879.51	0.05
309	327	342	341	326	0.05		0.05	14115.96	11636.82	0.05	372	395	411	410	394	2	115.00		0.35	14434.41	14097.51	0.05
310	328	343	342	327	0.05		0.05	14594.41	12052.66	0.05	373	396	412	411	395	2	115.00		0.35	15285.89	15468.89	0.05
311	329	344	343	328	0.05		0.05	15086.06	12486.41	0.05	374	397	413	412	396	2	115.00		0.35	16188.89	16991.89	0.05
312	330	345	344	329	0.05		0.05	15591.81	12938.66	0.05	375	398	414	413	397	2	115.00		0.35	17148.01	18779.41	0.05
313	331	346	345	330	0.05		0.05	16111.66	13410.41	0.05	376	399	415	414	398	2	115.00		0.35	18188.89	20848.89	0.05
314	332	347	346	331	0.05		0.05	16645.51	13902.66	0.05	377	400	416	415	399	2	115.00		0.35	19325.25	23125.25	0.05
315	333	348	347	332	0.05		0.05	17193.36	14416.06	0.05	378	401	417	416	400	2	115.00		0.35	20572.71	25629.71	0.05
316	334	349	348	333	0.05		0.05	17755.21	14951.81	0.05	379	402	418	417	401	2	115.00		0.35	21948.89	28378.89	0.05
317	335	350	349	334	0.05		0.05	18331.06	15509.66	0.05	380	403	419	418	402	2	115.00		0.35	23460.02	31360.02	0.05
318	336	351	350	335	0.05		0.05	18921.91	16089.81	0.05	381	404	420	419	403	2	115.00		0.35	25099.81	34599.81	0.05
319	337	352	351	336	0.05		0.05	19527.76	16692.66	0.05	382	405	421	420	404	2	115.00		0.35	26872.71	38148.88	0.05
320	338	353	352	337	0.05		0.05	20148.61	17318.41	0.05	383	406	422	421	405	2	115.00		0.35	28798.89	42048.89	0.05
321	339	354	353	338	0.05		0.05	20784.46	17967.26	0.05	384	407	423	422	406	2	115.00		0.35	30872.71	46222.71	0.05
322	340	355	354	339	0.05		0.05	21435.31	18639.11	0.05	385	408	424	423	407	2	115.00		0.35	33018.89	50768.89	0.05
323	341	356	355	340	0.05		0.05	22101.16	19334.96	0.05	386	409	425	424	408	2	115.00		0.35	35338.02	55688.02	0.05
324	342	357	356	341	0.05		0.05	22782.01	20054.81	0.05	387	410	426	425	409	2	115.00		0.35	37848.89	61048.89	0.05
325	343	358	357	342	0.05		0.05	23478.86	20808.66	0.05	388	411	427	426	410	2	115.00		0.35	40572.71	67032.71	0.05
326	344	359	358	343	0.05		0.05	24191.71	21596.51	0.05	389	412	428	427	411	2	115.00		0.35	43528.89	73488.89	0.05
327	345	360	359	344	0.05		0.05	24920.56	22419.36	0.05	390	413	429	428	412	2	115.00		0.35	46728.89	80368.89	0.05
328	346	361	360	345	0.05		0.05	25675.41	23277.21	0.05	391	414	430	429	413	2	115.00		0.35	50272.71	87728.71	0.05
329	347	362	361	346	0.05		0.05	26446.26	24171.06	0.05	392	415	431	430	414	2	115.00		0.35	54108.89	95638.89	0.05
330	348	363	362	347	0.05		0.05	27233.11	25091.91	0.05	393	416	432	431	415	2	115.00		0.35	58272.71	104148.71	0.05
331	349	364	363	348	0.05		0.05	28037.96	26039.76	0.05	394	417	433	432	416	2	115.00		0.35	62708.89	113448.89	0.05
332	350	365	364	349	0.05		0.05	28859.81	27014.61	0.05	395	418	434	433	417	2	115.00		0.35	67468.89	123648.89	0.05
333	351	366	365	350	0.05		0.05	29697.66	28017.46	0.05	396	419	435	434	418	2	115.00		0.35	72572.71	134888.71	0.05
334	352	367	366	351	0.05		0.05	30551.51	29048.31	0.05	397	420	436	435	419	2	115.00		0.35	78068.89	147328.89	0.05
335	353	368	367	352	0.05		0.05	31421.36	30108.16	0.05	398	421	437	436	420	2	115.00		0.35	83972.71	161048.71	0.05
336	354	369	368	353	0.05		0.05	32307.21	31198.01	0.05	399	422	438	437	421	2	115.00		0.35	90308.89	176248.89	0.05
337	355	370	369	354	0.05		0.05	33209.06	32317.86	0.05	400	423	439	438	422	2	115.00		0.35	97108.89	193048.89	0.05
338	356	371	370	355	0.05		0.05	34126.91	33467.71	0.05	401	424	440	439	423	2	115.00		0.35	104408.89	212488.89	0.05
339	357	372	371	356	0.05		0.05	35050.76	34647.56	0.05	402	425	441	440	424	2	115.00		0.35	112248.89	234688.89	0.05
340	358	373	372	357	0.05		0.05	35980.61	35857.41	0.05	403	426	442	441	425	2	115.00		0.35	120648.89	259728.89	0.05
341	359	374	373	358	0.05		0.05	36926.46	37097.26	0.05	404	427	443	442	426	2	115.00		0.35	129668.89	288768.89	0.05
342	360	375	374	359	0.05		0.05	37888.31	38367.11	0.05	405	428	444	443	427	2	115.00		0.35	139328.89	3218	

409	435	451	450	434	4178.04	3342.43	0.35	4178.04	3342.43	0.05
410	436	452	451	435	4597.39	3677.91	0.35	4597.39	3677.91	0.05
411	437	453	452	436	3983.14	3983.14	0.05	3983.14	3983.14	0.05
412	438	454	453	437	5339.29	4271.43	0.35	5339.29	4271.43	0.05
413	439	455	454	438	5673.30	4538.64	0.35	5673.30	4538.64	0.05
414	440	456	455	439	5987.03	4789.62	0.35	5987.03	4789.62	0.05
415	441	457	456	440	6288.78	5031.03	0.35	6288.78	5031.03	0.05
416	442	458	457	441	6574.68	5259.74	0.35	6574.68	5259.74	0.05
417	443	459	458	442	6847.49	5477.99	0.35	6847.49	5477.99	0.05
418	444	460	459	443	7144.22	5715.37	0.35	7144.22	5715.37	0.05
419	446	462	461	445	418.01	334.41	0.35	418.01	334.41	0.05
420	446	463	462	446	1300.46	1112.37	0.35	1300.46	1112.37	0.05
421	447	464	463	447	2070.59	1656.45	0.35	2070.59	1656.45	0.05
422	448	465	464	448	2614.27	2251.42	0.35	2614.27	2251.42	0.05
423	449	466	465	448	3422.18	2737.45	0.35	3422.18	2737.45	0.05
424	450	467	466	449	3911.81	3129.45	0.35	3911.81	3129.45	0.05
425	451	468	467	450	4549.32	3479.46	0.35	4549.32	3479.46	0.05
426	452	469	468	451	4754.58	3803.66	0.35	4754.58	3803.66	0.05
427	453	470	469	452	5118.24	4094.59	0.35	5118.24	4094.59	0.05
428	454	471	470	453	5460.00	4368.00	0.35	5460.00	4368.00	0.05
429	455	472	471	454	5786.06	4628.85	0.35	5786.06	4628.85	0.05
430	456	473	472	455	6088.40	4870.72	0.35	6088.40	4870.72	0.05
431	457	474	473	456	6378.65	5102.92	0.35	6378.65	5102.92	0.05
432	458	475	474	457	6659.17	5327.33	0.35	6659.17	5327.33	0.05
433	459	476	475	458	6923.47	5538.78	0.35	6923.47	5538.78	0.05
434	460	477	476	459	7216.43	5773.15	0.35	7216.43	5773.15	0.05
435	462	479	478	461	418.01	334.41	0.35	418.01	334.41	0.05
436	463	480	479	462	1562.18	1249.20	0.35	1562.18	1249.20	0.05
437	464	481	480	463	2487.75	1990.20	0.35	2487.75	1990.20	0.05
438	465	482	481	464	3115.19	2492.15	0.35	3115.19	2492.15	0.05
439	466	483	482	465	3644.91	2919.93	0.35	3644.91	2919.93	0.05
440	467	484	483	466	4177.42	3293.93	0.35	4177.42	3293.93	0.05
441	468	485	484	467	4573.30	3618.64	0.35	4573.30	3618.64	0.05
442	469	486	485	468	5001.78	3921.43	0.35	5001.78	3921.43	0.05
443	470	487	486	469	5458.82	4267.05	0.35	5458.82	4267.05	0.05
444	471	488	487	470	5882.10	4465.68	0.35	5882.10	4465.68	0.05
445	472	489	488	471	6190.58	4714.63	0.35	6190.58	4714.63	0.05
446	473	490	489	472	6469.06	4952.47	0.35	6469.06	4952.47	0.05
447	474	491	490	473	6739.67	5175.25	0.35	6739.67	5175.25	0.05
448	475	492	491	474	6999.56	5391.73	0.35	6999.56	5391.73	0.05
449	476	493	492	475	7287.47	5529.98	0.35	7287.47	5529.98	0.05
450	477	494	493	476	418.01	334.41	0.35	418.01	334.41	0.05
451	479	496	495	478	1572.44	1257.95	0.35	1572.44	1257.95	0.05
452	480	497	496	479	2506.86	2005.49	0.35	2506.86	2005.49	0.05
453	481	498	497	480	3147.04	2517.63	0.35	3147.04	2517.63	0.05
454	482	499	498	481	3679.12	2943.30	0.35	3679.12	2943.30	0.05
455	483	500	499	482	4154.50	3323.60	0.35	4154.50	3323.60	0.05
456	484	501	500	483	4568.62	3654.90	0.35	4568.62	3654.90	0.05
457	485	502	501	484	4948.98	3959.18	0.35	4948.98	3959.18	0.05
458	486	503	502	485	5308.05	4246.44	0.35	5308.05	4246.44	0.05
459	487	504	503	486	5637.90	4510.32	0.35	5637.90	4510.32	0.05
460	488	505	504	487	5950.64	4760.51	0.35	5950.64	4760.51	0.05
461	489	506	505	488	6251.35	5001.08	0.35	6251.35	5001.08	0.05
462	490	507	506	489	6533.68	5226.94	0.35	6533.68	5226.94	0.05
463	491	508	507	490	6805.63	5444.50	0.35	6805.63	5444.50	0.05
464	492	509	508	491	7069.59	5655.67	0.35	7069.59	5655.67	0.05
465	493	510	509	492	7358.51	5866.81	0.35	7358.51	5866.81	0.05
466	494	511	510	493	418.01	334.41	0.35	418.01	334.41	0.05
467	496	513	512	495	1385.59	1108.47	0.35	1385.59	1108.47	0.05
468	496	514	513	496	2056.15	1644.92	0.35	2056.15	1644.92	0.05
469	497	515	514	496	2796.50	2237.20	0.35	2796.50	2237.20	0.05
470	498	516	515	497	3401.77	2721.42	0.35	3401.77	2721.42	0.05
471	499	517	516	498						

472	500	518	517	499	3884.63	3107.70	0.35	3884.63	3107.70	0.05
473	501	519	518	500	4320.70	3456.56	0.35	4320.70	3456.56	0.05
474	502	520	519	501	4724.33	3779.47	0.35	4724.33	3779.47	0.05
475	503	521	520	502	5082.97	4066.37	0.35	5082.97	4066.37	0.05
476	504	522	521	503	5423.56	4338.85	0.35	5423.56	4338.85	0.05
477	505	523	522	504	5747.79	4598.23	0.35	5747.79	4598.23	0.05
478	506	524	523	505	6046.53	4837.22	0.35	6046.53	4837.22	0.05
479	507	525	524	506	6335.79	5068.63	0.35	6335.79	5068.63	0.05
480	508	526	525	507	6613.31	5290.65	0.35	6613.31	5290.65	0.05
481	509	527	526	508	6875.91	5500.65	0.35	6875.91	5500.65	0.05
482	510	528	527	509	7136.60	5709.35	0.35	7136.60	5709.35	0.05
483	511	529	528	510	7429.55	5934.64	0.35	7429.55	5934.64	0.05
484	513	531	530	512	418.01	334.41	0.35	418.01	334.41	0.05
485	514	532	531	513	1551.85	1241.48	0.35	1551.85	1241.48	0.05
486	515	533	532	514	2468.49	1974.79	0.35	2468.49	1974.79	0.05
487	516	534	533	515	3083.09	2466.47	0.35	3083.09	2466.47	0.05
488	517	535	534	516	3610.43	2888.34	0.35	3610.43	2888.34	0.05
489	518	536	535	517	4080.04	3264.03	0.35	4080.04	3264.03	0.05
490	519	537	536	518	4477.62	3582.09	0.35	4477.62	3582.09	0.05
491	520	538	537	519	4854.22	3883.38	0.35	4854.22	3883.38	0.05
492	521	539	538	520	5204.49	4163.59	0.35	5204.49	4163.59	0.05
493	522	540	539	521	5525.87	4420.70	0.35	5525.87	4420.70	0.05
494	524	542	541	523	6126.71	4901.37	0.35	6126.71	4901.37	0.05
495	524	542	542	524	6403.94	5123.16	0.35	6403.94	5123.16	0.05
496	525	543	542	525	6673.19	5338.55	0.35	6673.19	5338.55	0.05
497	526	544	543	526	6927.76	5542.21	0.35	6927.76	5542.21	0.05
498	527	545	544	527	7179.99	5743.99	0.35	7179.99	5743.99	0.05
499	528	546	545	528	7470.65	5976.52	0.35	7470.65	5976.52	0.05
500	529	547	546	529	418.01	334.41	0.35	418.01	334.41	0.05
501	531	549	548	530	1556.27	1245.02	0.35	1556.27	1245.02	0.05
502	532	550	549	531	2476.73	1981.38	0.35	2476.73	1981.38	0.05
503	533	551	550	532	3096.81	2477.45	0.35	3096.81	2477.45	0.05
504	534	552	551	533	3629.17	2900.14	0.35	3629.17	2900.14	0.05
505	535	553	552	534	4066.02	3276.82	0.35	4066.02	3276.82	0.05
506	537	555	554	536	4497.15	3597.72	0.35	4497.15	3597.72	0.05
507	538	556	555	537	4874.56	3899.65	0.35	4874.56	3899.65	0.05
508	539	557	556	538	5227.96	4182.37	0.35	5227.96	4182.37	0.05
509	540	558	557	539	5549.91	4439.93	0.35	5549.91	4439.93	0.05
510	541	559	558	540	5860.21	4688.17	0.35	5860.21	4688.17	0.05
511	542	560	559	541	6154.02	4923.22	0.35	6154.02	4923.22	0.05
512	543	561	560	542	6431.79	5145.43	0.35	6431.79	5145.43	0.05
513	544	562	561	543	6701.61	5361.29	0.35	6701.61	5361.29	0.05
514	545	563	562	544	6958.46	5566.77	0.35	6958.46	5566.77	0.05
515	546	564	563	545	7200.53	5760.43	0.35	7200.53	5760.43	0.05
516	547	565	564	546	7481.81	5985.45	0.35	7481.81	5985.45	0.05
517	549	567	566	548	418.01	334.41	0.35	418.01	334.41	0.05
518	550	568	567	549	1562.48	1249.99	0.35	1562.48	1249.99	0.05
519	551	569	568	550	2488.31	1990.65	0.35	2488.31	1990.65	0.05
520	55									

535	567	585	584	566	3	115.00	fEpac2	418.01	334.41	0.05	598	632	651	650	631	631	115.00	fEpac2	5939.30	4751.44	0.05
536	568	586	585	567	2	115.00	0.35	1571.84	1257.47	0.05	599	633	652	651	632	632	115.00	0.35	6239.68	4991.74	0.05
537	569	587	586	568	2	115.00	0.35	2505.75	2004.60	0.05	600	634	653	652	633	633	115.00	0.35	6520.90	5216.72	0.05
538	570	588	587	569	2	115.00	0.35	3145.18	2516.16	0.05	601	635	654	653	634	634	115.00	0.35	6792.59	5434.07	0.05
539	571	589	588	570	2	115.00	0.35	3677.13	2941.71	0.05	602	636	655	654	635	635	115.00	0.35	7056.26	5645.01	0.05
540	572	590	589	571	2	115.00	0.35	4152.33	3321.88	0.05	603	637	656	655	636	636	115.00	0.35	7306.08	5844.86	0.05
541	573	591	590	572	2	115.00	0.35	4565.99	3652.79	0.05	604	638	657	656	637	637	115.00	0.35	7545.80	6036.64	0.05
542	574	592	591	573	2	115.00	0.35	4946.23	3956.99	0.05	605	639	658	657	638	638	115.00	0.35	7828.53	6262.82	0.05
543	575	593	592	574	2	115.00	0.35	5305.18	4244.15	0.05	606	641	660	659	640	640	115.00	0.35	8118.01	6534.41	0.05
544	576	594	593	575	2	115.00	0.35	5634.65	4507.72	0.05	607	642	661	660	641	641	115.00	0.35	8418.01	6834.41	0.05
545	577	595	594	576	2	115.00	0.35	5947.30	4757.84	0.05	608	643	662	661	642	642	115.00	0.35	8721.97	7132.97	0.05
546	578	596	595	577	2	115.00	0.35	6247.91	4988.33	0.05	609	644	663	662	643	643	115.00	0.35	9032.87	7430.10	0.05
547	579	597	596	578	2	115.00	0.35	6529.92	5223.93	0.05	610	645	664	663	644	644	115.00	0.35	9351.87	7736.71	0.05
548	580	598	597	579	2	113.00	0.35	6801.79	5441.43	0.05	611	646	665	664	645	645	113.00	0.35	9678.81	8042.81	0.05
549	581	599	598	580	2	113.00	0.35	7065.67	5652.53	0.05	612	647	666	665	646	646	113.00	0.35	9999.81	8348.41	0.05
550	582	600	599	581	2	113.00	0.35	7316.18	5852.95	0.05	613	648	667	666	647	647	113.00	0.35	10300.81	8644.01	0.05
551	583	601	600	582	3	113.00	0.35	7504.63	6083.70	0.05	614	649	668	667	648	648	113.00	0.35	10599.81	8929.61	0.05
552	585	603	602	584	3	113.00	0.35	7648.01	6334.41	0.05	615	650	669	668	649	649	113.00	0.35	10899.81	9205.21	0.05
553	585	604	603	585	2	115.00	0.35	7748.12	6511.29	0.05	616	651	670	669	650	650	115.00	0.35	11199.81	9480.81	0.05
554	586	605	604	585	2	115.00	0.35	7803.96	6651.16	0.05	617	652	671	670	651	651	115.00	0.35	11499.81	9756.41	0.05
555	587	606	605	586	2	115.00	0.35	7860.47	6752.57	0.05	618	653	672	671	652	652	115.00	0.35	11799.81	10032.01	0.05
556	588	607	606	587	2	115.00	0.35	7918.29	6828.23	0.05	619	654	673	672	653	653	115.00	0.35	12099.81	10307.61	0.05
557	589	608	607	588	2	115.00	0.35	7977.54	6883.70	0.05	620	655	674	673	654	654	115.00	0.35	12399.81	10583.21	0.05
558	590	609	608	589	2	115.00	0.35	8038.19	6930.00	0.05	621	656	675	674	655	655	115.00	0.35	12699.81	10858.81	0.05
559	591	610	609	590	2	115.00	0.35	8100.22	6967.54	0.05	622	657	676	675	656	656	115.00	0.35	12999.81	11134.41	0.05
560	592	611	610	591	2	115.00	0.35	8163.73	7006.00	0.05	623	658	677	676	657	657	115.00	0.35	13299.81	11410.01	0.05
561	593	612	611	592	2	115.00	0.35	8228.74	7045.86	0.05	624	659	678	677	658	658	115.00	0.35	13599.81	11685.61	0.05
562	594	613	612	593	2	115.00	0.35	8295.25	7087.13	0.05	625	660	679	678	659	659	115.00	0.35	13900.81	11961.21	0.05
563	595	614	613	594	2	115.00	0.35	8363.26	7129.01	0.05	626	661	680	679	660	660	115.00	0.35	14200.81	12236.81	0.05
564	596	615	614	595	2	115.00	0.35	8432.77	7171.50	0.05	627	662	681	680	661	661	115.00	0.35	14500.81	12512.41	0.05
565	597	616	615	596	2	115.00	0.35	8503.78	7214.66	0.05	628	663	682	681	662	662	115.00	0.35	14800.81	12788.01	0.05
566	598	617	616	597	2	115.00	0.35	8576.29	7258.37	0.05	629	664	683	682	663	663	115.00	0.35	15100.81	13063.61	0.05
567	599	618	617	598	2	115.00	0.35	8650.30	7302.66	0.05	630	665	684	683	664	664	115.00	0.35	15400.81	13339.21	0.05
568	600	619	618	599	2	115.00	0.35	8725.81	7347.54	0.05	631	666	685	684	665	665	115.00	0.35	15700.81	13614.81	0.05
569	601	620	619	600	3	115.00	0.35	8802.82	7393.01	0.05	632	667	686	685	666	666	115.00	0.35	16000.81	13890.41	0.05
570	603	622	621	602	3	113.00	0.35	8881.33	7439.11	0.05	633	668	687	686	667	667	113.00	0.35	16300.81	14166.01	0.05
571	604	623	622	603	2	113.00	0.35	8961.34	7485.86	0.05	634	669	688	687	668	668	113.00	0.35	16600.81	14441.61	0.05
572	605	624	623	604	2	113.00	0.35	9042.85	7533.25	0.05	635	670	689	688	669	669	113.00	0.35	16900.81	14717.21	0.05
573	606	625	624	605	2	113.00	0.35	9125.86	7581.26	0.05	636	671	690	689	670	670	113.00	0.35	17200.81	15000.01	0.05
574	607	626	625	606	2	113.00	0.35	9210.37	7629.87	0.05	637	672	691	690	671	671	113.00	0.35	17500.81	15280.01	0.05
575	608	627	626	607	2	115.00	0.35	9300.38	7679.08	0.05	638	673	692	691	672	672	115.00	0.35	17800.81	15560.01	0.05
576	609	628	627	608	2	115.00	0.35	9395.89	7728.89	0.05	639	674	693	692	673	673	115.00	0.35	18100.81	15840.01	0.05
577	610	629	628	609	2	115.00	0.35	9496.90	7779.30	0.05	640	675	694	693	674	674	115.00	0.35	18400.81	16120.01	0.05
578	611	630	629	610	2	115.00	0.35	9603.41	7830.31	0.05	641	676	695	694	675	675	115.00	0.35	18700.81	16400.01	0.05
579	612	631	630	611	2	115.00	0.35	9715.42	7881.82	0.05	642	677	696	695	676	676	115.00	0.35	19000.81	16680.01	0.05
580	613	632	631	612	2	115.00	0.35	9832.93	7933.83	0.05	643	678	697	696	677	677	115.00	0.35	19300.81	16960.01	0.05
581	614	633	632	613	2	115.00	0.35	9956.94	7986.34	0.05	644	679	698	697	678	678	115.00	0.35	19600.81	17240.01	0.05
582	615	634	633	614	2	115.00	0.35	10087.45	8039.35	0.05	645	680	699	698	679	679	115.00	0.35	19900.81	17520.01	0.05
583	616	635	634	615	2	115.00	0.35	10224.46	8092.86	0.05	646	681	700	699	680	680	115.00	0.35	20200.81	17800.01	0.05
584	617	636	635	616	2	115.00	0.35	10367.97	8146.87	0.05	647	682	701	700	681	681	115.00	0.35	20500.81	18080.01	0.05
585	618	637	636	617	2	115.00	0.35	10517.98	8201.38	0.05	648	683	702	701	682	682	115.00	0.35	20800.81	18360.01	0.05
586	619	638	637	618	2	115.00	0.35	10674.49	8256.39	0.05	649	684	703	702	683	683	115.00	0.35	21100.81	18640.01	0.05
587	620	639	638	619	3	115.00	0.35	10837.50	8311.90	0.05	650	685	704	703	684	684	115.00	0.35	21400.81	18920.01	0.05
588	622	641	640	621	3	115.00	0.35	11007.01	8367.91	0.05	651	686	705	704	685	685	115.00	0.35	21700.81	19200.01	0.05
589	623	642	641	622	2	115.00	0.35	11183.02	8424.42	0.05	652	687	706	705	686	686	115.00	0.35	22000.81	19480.01	0.05
590	624	643	642	623	2	115.00	0.35	11365.53	8481.43	0.05	653	688	707	706	687	687	115.00	0.35	22300.81	19760.01	0.05
591	625	644	643	624	2	113.00	0.35	11554.54	8538.94	0.05	654	689	708	707	688	688	113.00	0.35	22600.81	20040.01	0.05
592	626	645	644	625	2	113.00	0.35	11750.05	8596.95	0.05	655	690	709	708	689	689	113.00	0.35	22900.81	20320.01	0.05
593	627	646	645	626	2	113.00	0.35	11952.06	8655.46	0.05	656	691	710	709	690	690	113.00	0.35	23200.81	20600.01	0.05
594	628	647	646	627	2	113.00	0.35	12160.57	8714.47	0.05	657	692	711	710	691	691	113.00</				



661	698	699	718	717	2	115.00	fEpac2	1561.67	1249.34	0.05	724	765	783	782	764	764	115.00	fEpac2	6189.74	4951.79	0.05	
662	699	700	719	718	2	115.00	0.35	2486.80	1989.44	0.05	725	766	784	783	765	765	765	115.00	0.35	6468.20	5174.56	0.05
663	700	701	720	719	2	115.00	0.35	3113.60	2490.88	0.05	726	767	785	784	766	766	766	115.00	0.35	6738.79	5391.03	0.05
664	701	702	721	720	2	115.00	0.35	3643.20	2914.56	0.05	727	768	786	785	767	767	767	115.00	0.35	6998.61	5598.89	0.05
665	702	703	722	721	2	115.00	0.35	4115.57	3292.45	0.05	728	769	787	786	768	768	768	115.00	0.35	7227.42	5781.94	0.05
666	703	704	723	722	2	115.00	0.35	4521.04	3616.83	0.05	729	770	788	787	769	769	769	115.00	0.35	7496.45	5997.16	0.05
667	704	705	724	723	2	115.00	0.35	4899.43	3919.54	0.05	730	771	790	789	771	771	771	115.00	0.35	818.01	334.41	0.05
668	705	706	725	724	2	115.00	0.35	5256.36	4205.09	0.05	731	772	791	790	772	772	772	115.00	0.35	1568.19	1254.55	0.05
669	706	707	726	725	2	115.00	0.35	5579.32	4463.45	0.05	732	773	792	791	773	773	773	115.00	0.35	2498.94	1999.15	0.05
670	707	708	727	726	2	115.00	0.35	5890.43	4712.34	0.05	733	774	793	792	774	774	774	115.00	0.35	3133.84	2307.07	0.05
671	708	709	728	727	2	115.00	0.35	6187.42	4949.94	0.05	734	775	794	793	775	775	775	115.00	0.35	3664.95	2831.96	0.05
672	709	710	729	728	2	115.00	0.35	6465.87	5187.67	0.05	735	776	795	794	776	776	776	115.00	0.35	4139.14	3311.31	0.05
673	710	711	730	729	2	115.00	0.35	6736.37	5386.10	0.05	736	777	796	795	777	777	777	115.00	0.35	4549.85	3639.88	0.05
674	711	712	731	730	2	115.00	0.35	6996.00	5596.80	0.05	737	778	797	796	778	778	778	115.00	0.35	4929.43	3943.34	0.05
675	712	713	732	731	2	115.00	0.35	7244.41	5819.55	0.05	738	780	798	797	779	779	779	115.00	0.35	5287.65	4230.12	0.05
676	713	714	733	732	2	115.00	0.35	7491.43	5993.14	0.05	739	781	799	798	780	780	780	115.00	0.35	5614.78	4491.82	0.05
677	714	715	734	733	3	115.00	0.35	7777.63	6222.10	0.05	740	782	800	799	781	781	781	115.00	0.35	5926.88	4741.51	0.05
678	716	717	736	735	3	115.00	0.35	818.01	334.41	0.05	741	783	801	800	782	782	782	115.00	0.35	6226.90	4981.52	0.05
679	717	718	737	736	2	115.00	0.35	1563.55	1250.84	0.05	742	784	802	801	783	783	783	115.00	0.35	6506.91	5205.53	0.05
680	718	719	738	737	2	115.00	0.35	2490.30	1992.24	0.05	743	785	803	802	784	784	784	115.00	0.35	6778.30	5422.64	0.05
681	719	720	739	738	2	115.00	0.35	3119.44	2495.55	0.05	744	786	804	803	785	785	785	115.00	0.35	7041.29	5633.03	0.05
682	720	721	740	739	2	115.00	0.35	3649.48	2919.58	0.05	745	787	805	804	786	786	786	115.00	0.35	7290.41	5832.33	0.05
683	721	722	741	740	2	115.00	0.35	4122.37	3297.90	0.05	746	788	806	805	787	787	787	115.00	0.35	7579.69	6063.75	0.05
684	722	723	742	741	2	115.00	0.35	4508.09	3623.48	0.05	747	790	808	807	789	789	789	115.00	0.35	818.01	334.41	0.05
685	723	724	743	742	2	115.00	0.35	4908.09	3926.47	0.05	748	790	809	808	808	808	808	115.00	0.35	1387.39	1109.91	0.05
686	724	725	744	743	2	115.00	0.35	5265.39	4212.31	0.05	749	791	810	809	790	790	790	115.00	0.35	2058.39	1646.72	0.05
687	725	726	745	744	2	115.00	0.35	5589.55	4471.64	0.05	750	792	811	810	791	791	791	115.00	0.35	2797.32	2237.86	0.05
688	726	727	746	745	2	115.00	0.35	5900.95	4720.76	0.05	751	793	812	811	792	792	792	115.00	0.35	3401.97	2721.58	0.05
689	727	728	747	746	2	115.00	0.35	6199.05	4959.24	0.05	752	794	813	812	793	793	793	115.00	0.35	3884.39	3107.51	0.05
690	728	729	748	747	2	115.00	0.35	6477.69	5182.15	0.05	753	795	814	813	794	794	794	115.00	0.35	4320.13	3456.10	0.05
691	729	730	749	748	2	115.00	0.35	6748.48	5398.78	0.05	754	796	815	814	795	795	795	115.00	0.35	4723.51	3778.10	0.05
692	730	731	750	749	2	115.00	0.35	7009.07	5607.26	0.05	755	797	816	815	796	796	796	115.00	0.35	5081.82	4065.45	0.05
693	731	732	751	750	2	115.00	0.35	7257.68	5806.15	0.05	756	798	817	816	797	797	797	115.00	0.35	5421.23	4337.78	0.05
694	732	733	752	751	2	115.00	0.35	7449.42	5959.54	0.05	757	799	818	817	798	798	798	115.00	0.35	5746.10	4596.93	0.05
695	733	734	753	752	3	115.00	0.35	7674.21	6139.37	0.05	758	800	819	818	799	799	799	115.00	0.35	6044.76	4835.81	0.05
696	735	736	754	753	3	115.00	0.35	7918.01	6354.41	0.05	759	801	820	819	800	800	800	115.00	0.35	6333.89	5087.12	0.05
697	737	738	756	755	2	115.00	0.35	8129.09	6596.87	0.05	760	802	821	820	801	801	801	115.00	0.35	6611.16	5288.93	0.05
698	739	740	758	757	2	115.00	0.35	8329.09	6861.27	0.05	761	803	822	821	802	802	802	115.00	0.35	6873.66	5498.92	0.05
699	740	741	759	758	2	115.00	0.35	8539.85	7147.88	0.05	762	804	823	822	803	803	803	115.00	0.35	7129.43	5703.54	0.05
700	741	742	760	759	2	115.00	0.35	8750.61	7443.66	0.05	763	805	824	823	804	804	804	115.00	0.35	7375.74	5900.59	0.05
701	742	743	761	760	2	115.00	0.35	8961.37	7749.44	0.05	764	806	825	824	805	805	805	115.00	0.35	7658.37	6126.69	0.05
702	743	744	762	761	2	115.00	0.35	9172.13	8065.22	0.05	765	807	826	825	806	806	806	115.00	0.35	7941.01	6341.41	0.05
703	744	745	763	762	2	115.00	0.35	9382.89	8391.00	0.05	766	808	827	826	807	807	807	115.00	0.35	8223.51	6566.21	0.05
704	745	746	764	763	2	115.00	0.35	9593.65	8716.78	0.05	767	810	829	828	808	808	808	115.00	0.35	8506.03	6801.01	0.05
705	746	747	765	764	2	115.00	0.35	9804.41	9042.56	0.05	768	811	830	829	810	810	810	115.00	0.35	8788.74	7045.84	0.05
706	747	748	766	765	2	115.00	0.35	10015.17	9368.34	0.05	769	812	831	830	811	811	811	115.00	0.35	9071.48	7290.62	0.05
707	748	749	767	766	2	115.00	0.35	10225.93	9694.12	0.05	770	813	832	831	812	812	812	115.00	0.35	9354.19	7535.40	0.05
708	749	750	768	767	2	115.00	0.35	10436.69	10019.90	0.05	771	814	833	832	813	813	813	115.00	0.35	9636.90	7780.18	0.05
709	750	751	769	768	2	115.00	0.35	10647.45	10345.68	0.05	772	815	834	833	814	814	814	115.00	0.35	9919.61	8024.96	0.05
710	751	752	770	769	2	115.00	0.35	10858.21	10671.46	0.05	773	816	835	834	815	815	815	115.00	0.35	10202.32	8269.74	0.05
711	752	753	771	770	3	115.00	0.35	11068.97	11000.24	0.05	774	817	836	835	816	816	816	115.00	0.35	10405.03	8514.52	0.05
712	753	754	772	771	3	115.00	0.35	11279.73	11329.02	0.05	775	818	837	836	817	817	817	115.00	0.35	10607.74	8759.30	0.05
713	754	755	773	772	3	115.00	0.35	11490.49	11657.80	0.05	776	819	838	837	818	818	818	115.00	0.35	10810.45	9004.08	0.05
714	755	756	774	773	2	115.00	0.35	11701.25	11986.58	0.05	777	820	839	838	819	819	819	115.00	0.35	11013.16	9248.86	0.05
715	756	757	775	774	2	115.00	0.35	11912.01	12315.36	0.05	778	821	840	839	820	820	820	115.00	0.35	11215.87	9493.64	0.05
716	757	758	776	775	2	115.00	0.35	12122.77	12644.14	0.05	779	822	841	840	821	821	821	115.00	0.35	11418.58	9738.42	0.05
717	758	759	777	776	2	115.00	0.35	12333.53	12972.92	0.05	780	823	842	841	822	822	822	115.00	0.35	11621.29	9983.20	0.05
718	759	760	778	777	2	115.00	0.35	12544.29	13301.70	0.05	781	824	843	842	823	823	823	115.00	0.35	11824.00</		

Table with 10 columns: ID (787-849), fEpac2 (0.05-0.35), Value (2914.88-4226.61), and ID (831-914). Rows contain numerical data for each column.

Table with 10 columns: ID (850-914), fEpac2 (0.35-0.05), Value (5609.81-3645.01), and ID (915-957). Rows contain numerical data for each column.

913	959	982	981	958	2	115.00	fEpac2	4936.10	3948.88	0.35	0.05	976	1024	1048	1047	1023	115.00	3105.01	2484.01	0.35	0.05
914	960	983	982	959	2	115.00	0.35	5294.62	4235.69	0.05	0.05	977	1025	1049	1048	1024	115.00	3633.98	2907.18	0.35	0.05
915	961	984	983	960	2	115.00	0.35	5622.68	4498.14	0.05	0.05	978	1026	1050	1049	1025	115.00	4105.57	3284.45	0.35	0.05
916	962	985	984	961	2	115.00	0.35	5935.00	4748.00	0.05	0.05	979	1027	1051	1050	1026	115.00	4508.82	3607.05	0.35	0.05
917	963	986	985	962	2	115.00	0.35	6235.25	4988.20	0.05	0.05	980	1028	1052	1051	1027	115.00	4886.71	3909.36	0.35	0.05
918	964	987	986	963	2	115.00	0.35	6516.05	5212.84	0.05	0.05	981	1029	1053	1052	1028	115.00	5241.97	4193.58	0.35	0.05
919	965	988	987	964	2	115.00	0.35	6787.64	5430.11	0.05	0.05	982	1030	1054	1053	1029	115.00	5564.27	4451.42	0.35	0.05
920	966	989	988	965	2	115.00	0.35	7051.21	5640.97	0.05	0.05	983	1031	1055	1054	1030	115.00	5874.97	4699.98	0.35	0.05
921	967	990	989	966	2	115.00	0.35	7300.65	5840.52	0.05	0.05	984	1032	1056	1055	1031	115.00	6170.33	4936.27	0.35	0.05
922	968	991	990	967	2	115.00	0.35	7540.46	6032.37	0.05	0.05	985	1033	1057	1056	1032	115.00	6448.42	5158.74	0.35	0.05
923	969	992	991	968	2	115.00	0.35	7769.96	6215.97	0.05	0.05	986	1034	1058	1057	1033	115.00	6718.56	5374.87	0.35	0.05
924	970	993	992	969	2	115.00	0.35	7999.46	6395.57	0.05	0.05	987	1035	1059	1058	1034	115.00	6976.80	5581.44	0.35	0.05
925	971	994	993	970	2	115.00	0.35	8228.96	6583.17	0.05	0.05	988	1036	1060	1059	1035	115.00	7224.90	5793.92	0.35	0.05
926	972	995	994	971	2	115.00	0.35	8447.64	6768.11	0.05	0.05	989	1037	1061	1060	1036	115.00	7465.96	5972.77	0.35	0.05
927	973	996	995	972	3	113.00	0.35	8733.98	6967.19	0.05	0.05	990	1038	1062	1061	1037	113.00	7690.65	6325.52	0.35	0.05
928	975	998	997	974	3	113.00	0.35	418.01	334.41	0.05	0.05	991	1039	1063	1062	1038	113.00	7915.34	6332.28	0.35	0.05
929	976	999	998	975	2	113.00	0.35	1575.51	1260.40	0.05	0.05	992	1040	1064	1063	1039	113.00	8140.04	6512.03	0.35	0.05
930	977	1000	999	976	2	113.00	0.35	2512.58	2010.07	0.05	0.05	993	1041	1065	1064	1040	113.00	8359.15	6687.32	0.35	0.05
931	978	1001	1000	977	2	113.00	0.35	3156.57	2525.26	0.05	0.05	994	1042	1066	1065	1041	113.00	8567.22	6853.78	0.35	0.05
932	979	1002	1001	978	2	113.00	0.35	3689.37	2951.49	0.05	0.05	995	1043	1067	1066	1042	113.00	8854.55	7083.64	0.35	0.05
933	980	1003	1002	979	2	113.00	0.35	4165.61	3332.49	0.05	0.05	996	1044	1068	1067	1043	113.00	9181.83	7313.46	0.35	0.05
934	981	1004	1003	980	2	113.00	0.35	4582.20	3665.76	0.05	0.05	997	1045	1069	1068	1044	113.00	9570.33	7557.22	0.35	0.05
935	982	1005	1004	981	2	113.00	0.35	4963.11	3970.49	0.05	0.05	998	1046	1070	1069	1045	113.00	9969.72	7813.41	0.35	0.05
936	983	1006	1005	982	2	113.00	0.35	5322.79	4258.23	0.05	0.05	999	1047	1071	1070	1046	113.00	10388.47	8083.97	0.35	0.05
937	984	1007	1006	983	2	113.00	0.35	5654.60	4523.68	0.05	0.05	1000	1048	1072	1071	1047	113.00	10709.59	8367.68	0.35	0.05
938	985	1008	1007	984	2	113.00	0.35	5967.81	4774.25	0.05	0.05	1001	1050	1074	1073	1049	113.00	11099.59	8671.98	0.35	0.05
939	986	1009	1008	985	2	113.00	0.35	6269.01	5015.21	0.05	0.05	1002	1051	1075	1074	1050	113.00	11513.74	9013.46	0.35	0.05
940	987	1010	1009	986	2	113.00	0.35	6553.02	5242.42	0.05	0.05	1003	1052	1076	1075	1051	113.00	11915.00	9313.46	0.35	0.05
941	988	1011	1010	987	2	113.00	0.35	6825.38	5460.31	0.05	0.05	1004	1053	1077	1076	1052	113.00	12281.89	9570.33	0.35	0.05
942	989	1012	1011	988	2	113.00	0.35	7089.76	5671.81	0.05	0.05	1005	1054	1078	1077	1053	113.00	12634.55	9845.26	0.35	0.05
943	990	1013	1012	989	2	113.00	0.35	7342.06	5873.65	0.05	0.05	1006	1055	1079	1078	1054	113.00	12978.20	10133.41	0.35	0.05
944	991	1014	1013	990	2	113.00	0.35	7581.19	6064.95	0.05	0.05	1007	1056	1080	1079	1055	113.00	13313.21	10441.77	0.35	0.05
945	992	1015	1014	991	2	113.00	0.35	7813.32	6250.66	0.05	0.05	1008	1057	1081	1080	1056	113.00	13645.43	10714.77	0.35	0.05
946	993	1016	1015	992	2	113.00	0.35	8045.45	6436.36	0.05	0.05	1009	1058	1082	1081	1057	113.00	13975.73	11000.60	0.35	0.05
947	994	1017	1016	993	2	113.00	0.35	8277.57	6626.06	0.05	0.05	1010	1059	1083	1082	1058	113.00	14304.55	11287.63	0.35	0.05
948	995	1018	1017	994	2	113.00	0.35	8485.53	6822.06	0.05	0.05	1011	1060	1084	1083	1059	113.00	14627.75	11578.20	0.35	0.05
949	996	1019	1018	995	3	113.00	0.35	8765.14	7012.11	0.05	0.05	1012	1061	1085	1084	1060	113.00	14943.69	11878.95	0.35	0.05
950	998	1021	1020	997	3	113.00	0.35	418.01	334.41	0.05	0.05	1013	1062	1086	1085	1061	113.00	15259.10	12149.41	0.35	0.05
951	998	1022	1021	997	2	113.00	0.35	1390.93	1112.75	0.05	0.05	1014	1063	1087	1086	1062	113.00	15568.88	12419.41	0.35	0.05
952	999	1023	1022	998	2	113.00	0.35	2068.39	1654.71	0.05	0.05	1015	1064	1088	1087	1063	113.00	15874.26	12694.41	0.35	0.05
953	1000	1024	1023	999	2	113.00	0.35	2809.33	2247.47	0.05	0.05	1016	1065	1089	1088	1064	113.00	16175.94	12978.95	0.35	0.05
954	1001	1025	1024	1000	2	113.00	0.35	3415.65	2732.52	0.05	0.05	1017	1066	1090	1089	1065	113.00	16471.53	13271.22	0.35	0.05
955	1002	1026	1025	1001	2	113.00	0.35	3932.52	3122.02	0.05	0.05	1018	1067	1091	1090	1066	113.00	16761.15	13573.32	0.35	0.05
956	1003	1027	1026	1002	2	113.00	0.35	4339.17	3471.34	0.05	0.05	1019	1068	1092	1091	1067	113.00	17044.01	13881.41	0.35	0.05
957	1004	1028	1027	1003	2	113.00	0.35	4743.59	3794.88	0.05	0.05	1020	1069	1093	1092	1068	113.00	17319.97	14194.98	0.35	0.05
958	1005	1029	1028	1004	2	113.00	0.35	5105.21	4084.17	0.05	0.05	1021	1070	1094	1093	1069	113.00	17598.63	14519.97	0.35	0.05
959	1006	1030	1029	1005	2	113.00	0.35	5446.37	4357.10	0.05	0.05	1022	1071	1095	1094	1070	113.00	17870.91	14846.66	0.35	0.05
960	1007	1031	1030	1006	2	113.00	0.35	5771.83	4617.46	0.05	0.05	1023	1072	1096	1095	1071	113.00	18138.32	15178.20	0.35	0.05
961	1008	1032	1031	1007	2	113.00	0.35	6072.47	4857.98	0.05	0.05	1024	1073	1097	1096	1072	113.00	18399.54	15510.03	0.35	0.05
962	1009	1033	1032	1008	2	113.00	0.35	6362.24	5089.79	0.05	0.05	1025	1074	1098	1097	1073	113.00	18654.43	15846.66	0.35	0.05
963	1010	1034	1033	1009	2	113.00	0.35	6642.07	5313.66	0.05	0.05	1026	1075	1099	1098	1074	113.00	18902.97	16184.41	0.35	0.05
964	1011	1035	1034	1010	2	113.00	0.35	6905.09	5524.07	0.05	0.05	1027	1076	1100	1099	1075	113.00	19144.26	16519.41	0.35	0.05
965	1012	1036	1035	1011	2	113.00	0.35	7161.44	5729.15	0.05	0.05	1028	1077	1101	1100	1076	113.00	19379.64	16857.22	0.35	0.05
966	1013	1037	1036	1012	2	113.00	0.35	7410.02	5928.02	0.05	0.05	1029	1078	1102	1101	1077	113.00	19608.94	17194.98	0.35	0.05
967	1014	1038	1037	1013	2	113.00	0.35	7640.30	6112.24	0.05	0.05	1030	1080	1104	1103	1078	113.00	19831.21	17533.32	0.35	0.05
968	1015	1039	1038	1014	2	113.00	0.35	7869.01	6295.21	0.05	0.05	1031	1081	1105	1104	1079	113.00	20047.43	17871.22	0.35	0.05
969	1016	1040	1039	1015	2	113.00	0.35	8097.72	6478.17	0.05	0.05	1032	1082	1106	1105	1080	113.00	20257.57	18213.41	0.35	0.05
970	1017	1041	1040	1016	2	113.00	0.35	8324.52	6659.62	0.05	0.05	1033	1083	1107	1106	1081	113.00	20			

1039	1089	1113	1112	1088	0.35	8367.58	6894.06	1102	1155	1179	1178	1154	115.00	0.35	6983.24	5586.59	0.05
1040	1090	1114	1113	1089	0.05	8571.14	6856.92	1103	1156	1180	1179	1155	115.00	0.35	7231.44	5785.15	0.05
1041	1091	1115	1114	1090	0.05	8853.75	7083.00	1104	1157	1181	1180	1156	115.00	0.35	7472.40	5977.92	0.05
1042	1092	1116	1115	1091	0.35	418.01	334.41	1105	1158	1182	1181	1157	115.00	0.35	7697.51	6158.01	0.05
1043	1093	1117	1116	1092	0.05	1559.93	1247.94	1106	1159	1183	1182	1158	115.00	0.35	7922.61	6338.09	0.05
1044	1094	1118	1117	1093	0.05	2483.55	1986.84	1107	1160	1184	1183	1159	115.00	0.35	8147.72	6518.18	0.05
1045	1095	1119	1118	1094	0.05	3108.18	2486.54	1108	1161	1185	1184	1160	115.00	0.35	8366.48	6693.18	0.05
1046	1096	1120	1119	1095	0.05	3637.38	2909.90	1109	1162	1186	1185	1161	115.00	0.35	8569.99	6855.99	0.05
1047	1097	1121	1120	1096	0.05	4109.26	3287.41	1110	1163	1187	1186	1162	115.00	0.35	8852.55	7082.04	0.05
1048	1098	1122	1121	1097	0.05	4513.33	3610.66	1111	1165	1189	1188	1164	115.00	0.35	9181.01	7334.41	0.05
1049	1100	1124	1123	1099	0.05	4891.40	3913.12	1112	1166	1190	1189	1165	115.00	0.35	1558.54	1246.83	0.05
1050	1101	1125	1124	1100	0.05	5247.39	4197.91	1113	1167	1191	1190	1166	115.00	0.35	2480.96	1684.77	0.05
1051	1102	1126	1125	1101	0.05	5667.83	4455.86	1114	1168	1192	1191	1167	115.00	0.35	3193.98	2483.10	0.05
1052	1103	1127	1126	1102	0.05	5880.68	4704.54	1115	1169	1193	1192	1168	115.00	0.35	3632.76	2906.21	0.05
1053	1104	1128	1127	1103	0.05	6176.64	4941.31	1116	1170	1194	1193	1169	115.00	0.35	4104.25	3283.40	0.05
1054	1105	1129	1128	1104	0.05	6454.85	5163.88	1117	1171	1195	1194	1170	115.00	0.35	4507.20	3608.46	0.05
1055	1106	1130	1129	1105	0.05	6725.16	5380.12	1118	1172	1196	1195	1171	115.00	0.35	4885.02	3908.02	0.05
1056	1107	1131	1130	1106	0.05	6983.89	5587.11	1119	1173	1197	1196	1172	115.00	0.35	5240.03	4192.03	0.05
1057	1108	1132	1131	1107	0.05	7232.10	5785.68	1120	1174	1198	1197	1173	115.00	0.35	5562.29	4449.83	0.05
1058	1109	1133	1132	1108	0.05	7473.04	5978.44	1121	1175	1199	1198	1174	115.00	0.35	5872.93	4698.34	0.05
1059	1110	1134	1133	1109	0.05	7698.19	6158.55	1122	1176	1200	1199	1175	115.00	0.35	6168.08	4934.46	0.05
1060	1111	1135	1134	1110	0.05	7923.34	6338.67	1123	1177	1201	1200	1176	115.00	0.35	6446.12	5156.89	0.05
1061	1112	1136	1135	1111	0.05	8148.49	6518.79	1124	1178	1202	1201	1177	115.00	0.35	6716.24	5372.99	0.05
1062	1113	1137	1136	1112	0.05	8367.21	6693.77	1125	1179	1203	1202	1178	115.00	0.35	6974.26	5579.41	0.05
1063	1114	1138	1137	1113	0.05	8570.76	6856.61	1126	1180	1204	1203	1179	115.00	0.35	7222.32	5777.86	0.05
1064	1115	1139	1138	1114	0.05	8853.35	7082.68	1127	1181	1205	1204	1180	115.00	0.35	7463.43	5970.74	0.05
1065	1116	1141	1140	1116	0.05	418.01	334.41	1128	1182	1206	1205	1181	115.00	0.35	7687.95	6150.36	0.05
1066	1118	1142	1141	1117	0.05	1559.88	1247.94	1129	1183	1207	1206	1182	115.00	0.35	7912.48	6329.99	0.05
1067	1119	1143	1142	1118	0.05	2483.55	1986.77	1130	1184	1208	1207	1183	115.00	0.35	8137.01	6509.61	0.05
1068	1120	1144	1143	1119	0.05	3108.04	2486.43	1131	1185	1209	1208	1184	115.00	0.35	8356.27	6685.02	0.05
1069	1121	1145	1144	1120	0.05	3637.23	2909.78	1132	1186	1210	1209	1185	115.00	0.35	8564.56	6851.65	0.05
1070	1122	1146	1145	1121	0.05	4109.09	3287.27	1133	1187	1211	1210	1186	115.00	0.35	8852.14	7081.72	0.05
1071	1123	1147	1146	1122	0.05	4513.12	3610.50	1134	1189	1212	1211	1188	115.00	0.35	9181.01	7334.41	0.05
1072	1124	1148	1147	1123	0.05	4891.16	3912.95	1135	1190	1213	1189	1189	115.00	0.35	1309.60	1112.48	0.05
1073	1125	1149	1148	1124	0.05	5247.15	4192.72	1136	1191	1214	1213	1190	115.00	0.35	2067.14	1653.72	0.05
1074	1126	1150	1149	1125	0.05	5647.15	4455.66	1137	1192	1215	1214	1191	115.00	0.35	2807.64	2246.11	0.05
1075	1127	1151	1150	1126	0.05	5869.57	4635.96	1138	1193	1216	1215	1192	115.00	0.35	3413.64	2740.91	0.05
1076	1128	1152	1151	1127	0.05	5880.42	4704.53	1139	1194	1217	1216	1193	115.00	0.35	3899.81	3119.85	0.05
1077	1129	1153	1152	1128	0.05	6176.35	4941.08	1140	1195	1218	1217	1194	115.00	0.35	4336.29	3499.03	0.05
1078	1130	1154	1153	1129	0.05	6454.56	5163.64	1141	1196	1219	1218	1195	115.00	0.35	4740.53	3792.42	0.05
1079	1131	1155	1154	1130	0.05	6724.86	5379.89	1142	1197	1220	1219	1196	115.00	0.35	5101.62	4081.30	0.05
1080	1132	1156	1155	1131	0.05	6983.57	5586.85	1143	1198	1221	1220	1197	115.00	0.35	5442.65	4354.12	0.05
1081	1133	1157	1156	1132	0.05	7231.77	5785.42	1144	1199	1222	1221	1198	115.00	0.35	5767.97	4614.38	0.05
1082	1134	1158	1157	1133	0.05	7472.72	5978.18	1145	1200	1223	1222	1199	115.00	0.35	6068.17	4854.54	0.05
1083	1135	1159	1158	1134	0.05	7697.85	6158.28	1146	1201	1224	1223	1200	115.00	0.35	6357.84	5086.27	0.05
1084	1136	1160	1159	1135	0.05	7922.98	6338.38	1147	1202	1225	1224	1201	115.00	0.35	6637.26	5309.81	0.05
1085	1137	1161	1160	1136	0.05	8148.10	6518.48	1148	1203	1226	1225	1202	115.00	0.35	6900.19	5520.15	0.05
1086	1138	1162	1161	1137	0.05	8366.84	6693.47	1149	1204	1227	1226	1203	115.00	0.35	7156.44	5725.15	0.05
1087	1139	1163	1162	1138	0.05	8572.95	6856.30	1150	1205	1228	1227	1204	115.00	0.35	7404.67	5923.73	0.05
1088	1141	1165	1164	1140	0.05	8852.95	7082.36	1151	1206	1229	1228	1205	115.00	0.35	7635.04	6108.03	0.05
1089	1142	1166	1165	1141	0.05	9181.01	7334.41	1152	1207	1230	1229	1206	115.00	0.35	7863.42	6290.73	0.05
1090	1143	1167	1166	1142	0.05	1559.84	1247.87	1153	1208	1231	1230	1207	115.00	0.35	8091.79	6473.43	0.05
1091	1144	1168	1167	1143	0.05	2486.31	1986.70	1154	1209	1232	1231	1208	115.00	0.35	8318.87	6655.09	0.05
1092	1145	1169	1168	1144	0.05	3107.89	2486.31	1155	1210	1233	1232	1209	115.00	0.35	8530.63	6824.54	0.05
1093	1146	1170	1169	1145	0.05	3637.07	2909.66	1156	1211	1234	1233	1210	115.00	0.35	8819.42	7055.54	0.05
1094	1147	1171	1170	1146	0.05	4108.92	3287.10	1157	1212	1235	1234	1211	115.00	0.35	9181.01	7334.41	0.05
1095	1148	1172	1171	1147	0.05	4512.92	3610.33	1158	1213	1236	1235	1212	115.00	0.35	1574.33	1259.40	0.05
1096	1149	1173	1172	1148	0.05	4890.97	3912.78	1159	1214	1237	1236	1213	115.00	0.35	2310.38	1808.31	0.05
1097	1150	1174	1173	1149	0.05	5246.90	4197.52	1160	1215	1238	1237	1214	115.00	0.35	3152.91	2322.33	0.05
1098	1151	1175	1174	1150	0.05	5569.32	4455.46	1161	1216	1239	1238	1215	115.00	0.35	3685.43	2948.34	0.05
1099	1152	1176	1175	1151	0.05	5880.16	4704.13	1162	1217	1240	1239	1216	115.00	0.35	4161.34	3229.07	0.05
1100	1153	1177	1176	1152	0.05	6176.07	4940.85	1163	1218	1241	1240	1217	115.00	0.35	4576.98	3661.14	0.05
1101	1154	1178	1177	1153	0.05	6454.26	5163.41	1164	1219	1242	1241	1218	115.00	0.35	4957.68	3966.14	0.05
					0.35	6724.56	5379.65	1165	1220	1243	1242	1219	115.00	0.35			

1165	1221	1244	1243	1220	0.35	5317.12	4253.70	0.05	1228	1286	1287	1310	1309	115.00	0.35	4123.69	3298.96	0.05
1166	1222	1245	1244	1221	0.05	5648.18	4518.55	0.05	1229	1287	1288	1311	1310	115.00	0.35	4530.97	3624.78	0.05
1167	1223	1246	1245	1222	0.05	5961.21	4768.97	0.05	1230	1288	1289	1312	1311	115.00	0.35	4909.77	3927.82	0.05
1168	1224	1247	1246	1223	0.35	6262.22	5009.78	0.05	1231	1289	1290	1313	1312	115.00	0.35	5267.15	4473.24	0.05
1169	1225	1248	1247	1224	0.05	6545.59	5236.47	0.05	1232	1290	1291	1314	1313	115.00	0.35	5591.54	4772.40	0.05
1170	1226	1249	1248	1225	0.05	6817.79	5454.23	0.05	1233	1291	1292	1315	1314	115.00	0.35	5903.00	5118.00	0.05
1171	1227	1250	1249	1226	0.05	7082.73	5665.61	0.05	1234	1292	1293	1316	1315	115.00	0.35	6201.31	5484.00	0.05
1172	1228	1251	1250	1227	0.05	7333.73	5866.99	0.05	1235	1293	1294	1317	1316	115.00	0.35	6480.00	5840.67	0.05
1173	1229	1252	1251	1228	0.05	7573.00	6043.68	0.05	1236	1294	1295	1318	1317	115.00	0.35	6750.83	6200.00	0.05
1174	1230	1253	1252	1229	0.05	7804.60	6243.68	0.05	1237	1295	1296	1319	1318	115.00	0.35	7011.62	6509.30	0.05
1175	1231	1254	1253	1230	0.05	8036.20	6428.96	0.05	1238	1296	1297	1320	1319	115.00	0.35	7260.27	6808.22	0.05
1176	1232	1255	1254	1231	0.05	8267.79	6614.23	0.05	1239	1297	1298	1321	1320	115.00	0.35	7500.75	7090.66	0.05
1177	1233	1256	1255	1232	0.05	8497.50	6780.56	0.05	1240	1298	1299	1322	1321	115.00	0.35	7727.69	7382.15	0.05
1178	1234	1257	1256	1233	0.05	8754.58	6934.41	0.05	1241	1299	1300	1323	1322	115.00	0.35	7954.62	7683.70	0.05
1179	1235	1258	1257	1234	0.05	9011.11	7080.56	0.05	1242	1300	1301	1324	1323	115.00	0.35	8181.56	7995.25	0.05
1180	1236	1259	1258	1235	0.05	9267.79	7220.27	0.05	1243	1301	1302	1325	1324	115.00	0.35	8408.50	8316.80	0.05
1181	1237	1260	1259	1236	0.05	9524.52	7354.27	0.05	1244	1302	1303	1326	1325	115.00	0.35	8635.44	8648.35	0.05
1182	1238	1261	1260	1237	0.05	9781.25	7482.27	0.05	1245	1303	1304	1327	1326	115.00	0.35	8862.18	8980.00	0.05
1183	1239	1262	1261	1238	0.05	10037.98	7610.27	0.05	1246	1304	1305	1328	1327	115.00	0.35	9088.92	9311.65	0.05
1184	1240	1263	1262	1239	0.05	10294.71	7738.27	0.05	1247	1305	1306	1329	1328	115.00	0.35	9315.66	9643.30	0.05
1185	1241	1264	1263	1240	0.05	10551.44	7866.27	0.05	1248	1306	1307	1330	1329	115.00	0.35	9542.40	9975.00	0.05
1186	1242	1265	1264	1241	0.05	10808.17	7994.27	0.05	1249	1307	1308	1331	1330	115.00	0.35	9769.14	10306.65	0.05
1187	1243	1266	1265	1242	0.05	11064.90	8122.27	0.05	1250	1308	1309	1332	1331	115.00	0.35	10000.00	10638.30	0.05
1188	1244	1267	1266	1243	0.05	11321.63	8250.27	0.05	1251	1309	1310	1333	1332	115.00	0.35	10230.86	10970.00	0.05
1189	1245	1268	1267	1244	0.05	11578.36	8378.27	0.05	1252	1310	1311	1334	1333	115.00	0.35	10461.72	11301.65	0.05
1190	1246	1269	1268	1245	0.05	11835.09	8506.27	0.05	1253	1311	1312	1335	1334	115.00	0.35	10692.58	11633.30	0.05
1191	1247	1270	1269	1246	0.05	12091.82	8634.27	0.05	1254	1312	1313	1336	1335	115.00	0.35	10923.44	11965.00	0.05
1192	1248	1271	1270	1247	0.05	12348.55	8762.27	0.05	1255	1313	1314	1337	1336	115.00	0.35	11154.30	12296.65	0.05
1193	1249	1272	1271	1248	0.05	12605.28	8890.27	0.05	1256	1314	1315	1338	1337	115.00	0.35	11385.16	12628.30	0.05
1194	1250	1273	1272	1249	0.05	12861.91	9018.27	0.05	1257	1315	1316	1339	1338	115.00	0.35	11616.02	12959.95	0.05
1195	1251	1274	1273	1250	0.05	13118.64	9146.27	0.05	1258	1316	1317	1340	1339	115.00	0.35	11846.88	13291.60	0.05
1196	1252	1275	1274	1251	0.05	13375.37	9274.27	0.05	1259	1317	1318	1341	1340	115.00	0.35	12077.74	13623.25	0.05
1197	1253	1276	1275	1252	0.05	13632.10	9402.27	0.05	1260	1318	1319	1342	1341	115.00	0.35	12308.56	13954.90	0.05
1198	1254	1277	1276	1253	0.05	13888.83	9530.27	0.05	1261	1319	1320	1343	1342	115.00	0.35	12539.42	14286.55	0.05
1199	1255	1278	1277	1254	0.05	14145.56	9658.27	0.05	1262	1320	1321	1344	1343	115.00	0.35	12770.28	14618.20	0.05
1200	1256	1279	1278	1255	0.05	14402.29	9786.27	0.05	1263	1321	1322	1345	1344	115.00	0.35	13001.14	14949.85	0.05
1201	1257	1280	1279	1256	0.05	14659.02	9914.27	0.05	1264	1322	1323	1346	1345	115.00	0.35	13231.96	15281.50	0.05
1202	1258	1281	1280	1257	0.05	14915.75	10042.27	0.05	1265	1323	1324	1347	1346	115.00	0.35	13462.82	15613.15	0.05
1203	1259	1282	1281	1258	0.05	15172.48	10170.27	0.05	1266	1324	1325	1348	1347	115.00	0.35	13693.68	15944.80	0.05
1204	1260	1283	1282	1259	0.05	15429.21	10298.27	0.05	1267	1325	1326	1349	1348	115.00	0.35	13924.54	16276.45	0.05
1205	1261	1284	1283	1260	0.05	15685.94	10426.27	0.05	1268	1326	1327	1350	1349	115.00	0.35	14155.40	16608.10	0.05
1206	1262	1285	1284	1261	0.05	15942.67	10554.27	0.05	1269	1327	1328	1351	1350	115.00	0.35	14386.26	16939.75	0.05
1207	1263	1286	1285	1262	0.05	16199.40	10682.27	0.05	1270	1328	1329	1352	1351	115.00	0.35	14617.12	17271.40	0.05
1208	1264	1287	1286	1263	0.05	16456.13	10810.27	0.05	1271	1329	1330	1353	1352	115.00	0.35	14847.98	17603.05	0.05
1209	1265	1288	1287	1264	0.05	16712.86	10938.27	0.05	1272	1330	1331	1354	1353	115.00	0.35	15078.84	17934.70	0.05
1210	1266	1289	1288	1265	0.05	16969.59	11066.27	0.05	1273	1331	1332	1355	1354	115.00	0.35	15309.70	18266.35	0.05
1211	1267	1290	1289	1266	0.05	17226.32	11194.27	0.05	1274	1332	1333	1356	1355	115.00	0.35	15540.56	18598.00	0.05
1212	1268	1291	1290	1267	0.05	17483.05	11322.27	0.05	1275	1333	1334	1357	1356	115.00	0.35	15771.42	18929.65	0.05
1213	1269	1292	1291	1268	0.05	17739.78	11450.27	0.05	1276	1334	1335	1358	1357	115.00	0.35	16002.28	19261.30	0.05
1214	1270	1293	1292	1269	0.05	18000.00	11578.27	0.05	1277	1335	1336	1359	1358	115.00	0.35	16233.14	19592.95	0.05
1215	1271	1294	1293	1270	0.05	18260.21	11706.27	0.05	1278	1336	1337	1360	1359	115.00	0.35	16464.00	19924.60	0.05
1216	1272	1295	1294	1271	0.05	18520.43	11834.27	0.05	1279	1337	1338	1361	1360	115.00	0.35	16694.86	20256.25	0.05
1217	1273	1296	1295	1272	0.05	18780.64	11962.27	0.05	1280	1338	1339	1362	1361	115.00	0.35	16925.72	20587.90	0.05
1218	1274	1297	1296	1273	0.05	19040.86	12090.27	0.05	1281	1339	1340	1363	1362	115.00	0.35	17156.58	20919.55	0.05
1219	1275	1298	1297	1274	0.05	19301.07	12218.27	0.05	1282	1340	1341	1364	1363	115.00	0.35	17387.44	21251.20	0.05
1220	1276	1299	1298	1275	0.05	19561.29	12346.27	0.05	1283	1341	1342	1365	1364	115.00	0.35	17618.30	21582.85	0.05
1221	1277	1300	1299	1276	0.05	19821.50	12474.27	0.05	1284	1342	1343	1366	1365	115.00	0.35	17849.16	21914.50	0.05
1222	1278	1301	1300	1277	0.05	20081.71	12602.27	0.05	1285	1343	1344	1367	1366	115.00	0.35	18080.02	22246.15	0.05
1223	1279	1302	1301	1278	0.05	20341.93	12730.27	0.05	1286	1344	1345	1368	1367	115.00	0.35	18310.88	22577.80	0.05
1224	1280	1303	1302	1279	0.05	20602.14	12858.27	0.05	1287	1345	1346	1369	1368	115.00	0.35	18541.74	22909.45	0.05
1225	1281	1304	1303	1280	0.05	20862.36	12986.27	0.05	1288	1346	1347	1370	1369	115.00	0.35	18772.60	23241.10	0.05
1226	1282	1305	1304	1281	0.05	21122.57	13114.27	0.05	1289	1347	1348	1371	1370	115.00	0.35	19003.46	23572.75	0.05
1227	1283	1306	1305	1282	0.05	21382.79	13242.27	0.05	1290	1348	1349	1372	1371	115.00	0.35	19234.32	23904.40	0.05

1291	1352	1353	1373	1372	115.00	0.35	4128.69	3302.95	1354	1418	1419	1435	1435	115.00	0.35	6950.17	5560.13
1292	1353	1354	1374	1373	115.00	0.35	4537.08	3629.66	1355	1419	1420	1436	1435	115.00	0.35	7154.13	5723.30
1293	1354	1355	1375	1374	115.00	0.35	4916.13	3932.91	1356	1421	1422	1438	1437	115.00	0.35	418.01	334.41
1294	1355	1356	1376	1375	115.00	0.35	5273.79	4219.03	1357	1422	1423	1439	1438	115.00	0.35	1559.09	1247.27
1295	1356	1357	1377	1376	115.00	0.35	5599.07	4479.25	1358	1423	1424	1440	1439	115.00	0.35	2481.99	1985.59
1296	1357	1358	1378	1377	115.00	0.35	5910.73	4728.58	1359	1424	1425	1441	1440	115.00	0.35	3105.59	2484.47
1297	1358	1359	1379	1378	115.00	0.35	6208.86	4967.88	1360	1425	1426	1442	1441	115.00	0.35	3634.59	2907.68
1298	1359	1360	1380	1379	115.00	0.35	6488.71	5190.97	1361	1426	1427	1443	1442	115.00	0.35	4106.24	3284.99
1299	1360	1361	1381	1380	115.00	0.35	6759.72	5407.98	1362	1427	1428	1444	1443	115.00	0.35	4589.63	3607.71
1300	1361	1362	1382	1381	115.00	0.35	7021.22	5616.78	1363	1428	1429	1445	1444	115.00	0.35	4897.56	3910.05
1301	1362	1363	1383	1382	115.00	0.35	7270.02	5816.02	1364	1429	1430	1446	1445	115.00	0.35	5242.96	4194.37
1302	1363	1364	1384	1383	115.00	0.35	7510.34	6008.28	1365	1430	1431	1447	1446	115.00	0.35	5565.28	4452.23
1303	1364	1365	1384	1384	115.00	0.35	7701.46	6191.17	1366	1431	1432	1448	1447	115.00	0.35	5876.01	4700.81
1304	1365	1366	1385	1384	115.00	0.35	7907.12	6325.69	1367	1432	1433	1449	1448	115.00	0.35	6171.48	4937.18
1305	1366	1367	1387	1386	115.00	0.35	818.01	654.41	1368	1433	1434	1450	1449	115.00	0.35	6449.59	5139.67
1306	1367	1368	1387	1387	115.00	0.35	1564.05	1251.24	1369	1434	1435	1451	1450	115.00	0.35	6679.01	5343.21
1307	1368	1369	1388	1387	115.00	0.35	2491.23	1992.98	1370	1435	1436	1451	1451	115.00	0.35	6878.15	5502.52
1308	1370	1371	1390	1389	115.00	0.35	3120.99	2496.79	1371	1437	1438	1453	1452	115.00	0.35	7156.86	5815.49
1309	1371	1372	1391	1390	115.00	0.35	3651.14	2920.91	1372	1438	1439	1454	1453	115.00	0.35	7477.83	6124.49
1310	1372	1373	1392	1391	115.00	0.35	4124.17	3299.34	1373	1439	1440	1455	1454	115.00	0.35	7811.11	6482.81
1311	1373	1374	1393	1392	115.00	0.35	4531.55	3625.24	1374	1440	1441	1456	1455	115.00	0.35	8166.66	6878.93
1312	1374	1375	1394	1393	115.00	0.35	4910.38	3928.30	1375	1441	1442	1457	1456	115.00	0.35	8532.15	7291.72
1313	1375	1376	1395	1394	115.00	0.35	5267.78	4214.22	1376	1442	1443	1458	1457	115.00	0.35	8908.17	7748.54
1314	1376	1377	1396	1395	115.00	0.35	5592.26	4473.81	1377	1443	1444	1459	1458	115.00	0.35	9294.78	8259.82
1315	1377	1378	1397	1396	115.00	0.35	5903.73	4722.99	1378	1444	1445	1460	1459	115.00	0.35	9697.29	8818.83
1316	1378	1379	1398	1397	115.00	0.35	6202.12	4961.70	1379	1445	1446	1461	1460	115.00	0.35	10118.11	9384.81
1317	1379	1380	1399	1398	115.00	0.35	6480.83	5184.66	1380	1446	1447	1462	1461	115.00	0.35	10653.14	10042.52
1318	1380	1381	1400	1399	115.00	0.35	6751.68	5401.34	1381	1447	1448	1463	1462	115.00	0.35	11263.53	10829.15
1319	1381	1382	1401	1400	115.00	0.35	7012.53	5610.34	1382	1448	1449	1464	1463	115.00	0.35	11951.69	11769.83
1320	1382	1383	1402	1401	115.00	0.35	7261.20	5808.96	1383	1449	1450	1465	1464	115.00	0.35	12709.55	12814.04
1321	1383	1384	1402	1401	115.00	0.35	7465.42	5972.32	1384	1450	1451	1465	1464	115.00	0.35	13542.21	13973.77
1322	1384	1385	1403	1402	115.00	0.35	7666.96	6133.57	1385	1451	1452	1467	1466	115.00	0.35	14481.01	15344.41
1323	1385	1387	1403	1404	115.00	0.35	7852.61	6314.14	1386	1452	1453	1468	1467	115.00	0.35	15528.63	16446.91
1324	1387	1388	1409	1405	115.00	0.35	8031.56	6501.10	1387	1453	1454	1469	1468	115.00	0.35	16748.13	17849.90
1325	1388	1389	1409	1405	115.00	0.35	8205.58	6690.96	1388	1454	1455	1469	1468	115.00	0.35	18119.16	19483.32
1326	1389	1390	1407	1409	115.00	0.35	8376.56	6893.25	1389	1455	1456	1470	1469	115.00	0.35	19653.06	21366.45
1327	1390	1391	1409	1408	115.00	0.35	8544.59	7117.11	1390	1456	1457	1471	1470	115.00	0.35	21404.57	23526.48
1328	1391	1392	1410	1409	115.00	0.35	8710.02	7352.22	1391	1457	1458	1472	1471	115.00	0.35	23397.60	26006.08
1329	1392	1393	1411	1410	115.00	0.35	8873.26	7598.22	1392	1458	1459	1473	1472	115.00	0.35	25645.44	28908.35
1330	1393	1394	1412	1411	115.00	0.35	9034.82	7855.06	1393	1459	1460	1474	1473	115.00	0.35	28174.51	32492.41
1331	1394	1395	1413	1412	115.00	0.35	9204.94	8122.75	1394	1460	1461	1475	1474	115.00	0.35	31032.77	36874.50
1332	1395	1396	1414	1413	115.00	0.35	9384.51	8408.61	1395	1461	1462	1476	1475	115.00	0.35	34202.22	42192.41
1333	1396	1397	1415	1414	115.00	0.35	9573.77	8716.62	1396	1462	1463	1477	1476	115.00	0.35	37737.43	48688.32
1334	1397	1398	1416	1415	115.00	0.35	9783.32	9054.66	1397	1463	1464	1478	1477	115.00	0.35	41718.01	56676.50
1335	1398	1399	1417	1416	115.00	0.35	10013.85	9437.48	1398	1464	1465	1478	1477	115.00	0.35	46218.17	65434.41
1336	1399	1400	1418	1417	115.00	0.35	10274.52	9874.01	1399	1465	1466	1480	1479	115.00	0.35	51370.11	76125.13
1337	1400	1401	1419	1418	115.00	0.35	10567.64	10376.11	1400	1466	1467	1482	1481	115.00	0.35	57252.63	88902.11
1338	1401	1402	1419	1419	115.00	0.35	10894.99	10959.59	1401	1467	1468	1483	1482	115.00	0.35	64031.99	104491.99
1339	1402	1403	1420	1420	115.00	0.35	11259.79	11622.64	1402	1470	1471	1484	1483	115.00	0.35	71931.55	124371.04
1340	1404	1405	1422	1421	115.00	0.35	7418.01	334.41	1403	1471	1472	1485	1484	115.00	0.35	80571.50	148481.04
1341	1405	1406	1423	1422	115.00	0.35	7645.53	398.42	1404	1472	1473	1486	1485	115.00	0.35	90145.60	17492.88
1342	1406	1407	1424	1423	115.00	0.35	7885.53	468.42	1405	1473	1474	1487	1486	115.00	0.35	101245.60	21492.88
1343	1407	1408	1425	1424	115.00	0.35	8111.48	548.91	1406	1474	1475	1488	1487	115.00	0.35	114291.16	26937.72
1344	1408	1409	1426	1425	115.00	0.35	8340.93	639.48	1407	1475	1476	1489	1488	115.00	0.35	129655.55	34000.44
1345	1410	1410	1427	1426	115.00	0.35	8573.10	742.48	1408	1476	1477	1490	1489	115.00	0.35	148053.45	43787.76
1346	1410	1411	1428	1427	115.00	0.35	8818.03	867.42	1409	1477	1478	1490	1489	115.00	0.35	16961.60	4848.48
1347	1411	1412	1429	1428	115.00	0.35	9076.30	1017.04	1410	1479	1480	1492	1491	115.00	0.35	19818.01	5344.41
1348	1412	1413	1430	1429	115.00	0.35	9358.04	1192.45	1411	1480	1481	1493	1492	115.00	0.35	23160.44	5848.35
1349	1413	1414	1431	1430	115.00	0.35	9665.61	1400.49	1412	1481	1482	1494	1493	115.00	0.35	27284.49	6487.60
1350	1414	1415	1432	1431	115.00	0.35	10011.21	1646.57	1413	1482	1483	1495	1494	115.00	0.35	32109.76	7319.76
1351	1415	1416	1433	1432	115.00	0.35	10408.55	1946.57	1414	1483	1484	1496	1495	115.00	0.35	37737.43	8393.08
1352	1416	1417	1434	1433	115.00	0.35	6461.55	5169.24	1415	1484	1485	1497	1496	115.00	0.35	44111.10	9711.26
1353	1417	1418	1435	1434	115.00	0.35	6732.00	5385.60	1416	1485	1486	1498	1497	115.00	0.35	51515.58	11268.88



fEpac2

37	206.35	690.31	0	0
38	206.35	686.81	0	0
39	206.35	675.86	0	0
40	206.35	664.91	0	0
41	206.35	653.97	0	0
42	206.35	643.02	0	0
43	206.35	638.52	4	4
44	223.10	693.50	0	0
45	223.10	690.00	0	0
46	223.10	678.95	0	0
47	223.10	668.89	0	0
48	223.10	658.84	0	0
49	223.10	648.79	0	0
50	223.10	639.74	0	0
51	223.10	635.24	4	4
52	239.86	696.69	0	0
53	239.86	693.19	0	0
54	239.86	681.84	0	0
55	239.86	670.50	0	0
56	239.86	659.15	0	0
57	239.86	647.80	0	0
58	239.86	636.46	0	0
59	239.86	631.96	4	4
60	256.62	699.88	0	0
61	256.62	696.38	0	0
62	256.62	685.85	0	0
63	256.62	675.31	0	0
64	256.62	664.78	0	0
65	256.62	654.25	0	0
66	256.62	643.71	0	0
67	256.62	633.18	0	0
68	273.37	628.68	4	4
69	273.37	703.07	0	0
70	273.37	696.57	0	0
71	273.37	687.96	0	0
72	273.37	676.35	0	0
73	273.37	664.73	0	0
74	273.37	653.12	0	0
75	273.37	641.51	0	0
76	273.37	629.90	0	0
77	273.37	625.40	4	4
78	290.13	706.26	0	0
79	290.13	702.76	0	0
80	290.13	690.07	0	0
81	290.13	677.38	0	0
82	290.13	664.69	0	0
83	290.13	652.00	0	0
84	290.13	639.31	0	0
85	290.13	626.61	0	0
86	290.13	622.11	4	4
87	306.89	709.46	0	0
88	306.89	705.96	0	0
89	306.89	692.19	0	0
90	306.89	678.42	0	0
91	306.89	664.64	0	0
92	306.89	650.87	0	0
93	306.89	637.10	0	0
94	306.89	623.33	0	0
95	306.89	618.83	4	4
96	323.64	712.65	0	0
97	323.64	709.15	0	0
98	323.64	696.42	0	0
99	323.64	683.69	0	0

Page 27

fEpac2

100	323.64	670.96	0	0
101	323.64	658.24	0	0
102	323.64	645.51	0	0
103	323.64	632.78	0	0
104	323.64	620.05	0	0
105	323.64	615.55	4	4
106	340.40	715.84	0	0
107	340.40	712.34	0	0
108	340.40	698.78	0	0
109	340.40	685.23	0	0
110	340.40	673.67	0	0
111	340.40	658.11	0	0
112	340.40	644.56	0	0
113	340.40	631.90	0	0
114	340.40	616.77	0	0
115	340.40	612.27	4	4
116	361.12	716.24	0	0
117	361.12	712.74	0	0
118	361.12	700.24	0	0
119	361.12	687.73	0	0
120	361.12	675.23	0	0
121	361.12	662.73	0	0
122	361.12	650.22	0	0
123	361.12	637.72	0	0
124	361.12	625.22	0	0
125	361.12	612.72	0	0
126	361.12	608.22	4	4
127	381.83	716.64	0	0
128	381.83	713.14	0	0
129	381.83	699.92	0	0
130	381.83	686.70	0	0
131	381.83	673.49	0	0
132	381.83	660.27	0	0
133	381.83	647.05	0	0
134	381.83	633.83	0	0
135	381.83	620.62	0	0
136	381.83	608.66	0	0
137	381.83	604.16	4	4
138	403.07	720.72	0	0
139	403.07	717.22	0	0
140	403.07	704.89	0	0
141	403.07	692.57	0	0
142	403.07	680.24	0	0
143	403.07	667.91	0	0
144	403.07	655.59	0	0
145	403.07	643.26	0	0
146	403.07	630.93	0	0
147	403.07	618.61	0	0
148	403.07	604.50	0	0
149	403.07	600.00	4	4
150	420.16	724.00	0	0
151	420.16	720.50	0	0
152	420.16	707.65	0	0
153	420.16	694.81	0	0
154	420.16	681.96	0	0
155	420.16	669.12	0	0
156	420.16	656.27	0	0
157	420.16	643.43	0	0
158	420.16	630.58	0	0
159	420.16	617.74	0	0
160	420.16	604.89	0	0
161	420.16	600.39	4	4
162	437.25	727.28	0	0

Page 28



fEpac2

163	437.25	723.78	0	0
164	437.25	710.61	0	0
165	437.25	697.45	0	0
166	437.25	684.28	0	0
167	437.25	671.11	0	0
168	437.25	657.95	0	0
169	437.25	644.78	0	0
170	437.25	631.62	0	0
171	437.25	618.45	0	0
172	437.25	605.28	0	0
173	437.25	600.78	4	4
174	434.34	730.56	0	0
175	434.34	727.56	0	0
176	434.34	713.57	0	0
177	434.34	700.09	0	0
178	434.34	686.60	0	0
179	434.34	673.11	0	0
180	434.34	659.62	0	0
181	434.34	646.14	0	0
182	434.34	632.65	0	0
183	434.34	619.16	0	0
184	434.34	605.68	0	0
185	434.34	601.18	4	4
186	471.44	733.84	0	0
187	471.44	730.34	0	0
188	471.44	717.91	0	0
189	471.44	705.49	0	0
190	471.44	693.06	0	0
191	471.44	680.63	0	0
192	471.44	668.20	0	0
193	471.44	655.78	0	0
194	471.44	643.35	0	0
195	471.44	630.92	0	0
196	471.44	618.50	0	0
197	471.44	606.07	0	0
198	471.44	601.57	4	4
199	488.53	737.12	0	0
200	488.53	733.62	0	0
201	488.53	720.91	0	0
202	488.53	708.19	0	0
203	488.53	695.47	0	0
204	488.53	682.76	0	0
205	488.53	670.04	0	0
206	488.53	657.33	0	0
207	488.53	644.61	0	0
208	488.53	631.89	0	0
209	488.53	619.18	0	0
210	488.53	606.46	4	4
211	488.53	601.96	0	0
212	505.62	740.40	0	0
213	505.62	736.90	0	0
214	505.62	723.90	0	0
215	505.62	710.89	0	0
216	505.62	697.89	0	0
217	505.62	684.88	0	0
218	505.62	671.88	0	0
219	505.62	658.87	0	0
220	505.62	645.87	0	0
221	505.62	632.86	0	0
222	505.62	619.86	0	0
223	505.62	606.85	0	0
224	505.62	602.35	4	4
225	522.71	743.68	0	0

fEpac2

226	522.71	740.18	0	0
227	522.71	726.89	0	0
228	522.71	713.60	0	0
229	522.71	700.30	0	0
230	522.71	687.01	0	0
231	522.71	673.71	0	0
232	522.71	660.42	0	0
233	522.71	647.13	0	0
234	522.71	633.83	0	0
235	522.71	620.54	0	0
236	522.71	607.24	0	0
237	522.71	602.74	4	4
238	539.80	746.96	0	0
239	539.80	743.46	0	0
240	539.80	729.88	0	0
241	539.80	716.30	0	0
242	539.80	702.72	0	0
243	539.80	689.13	0	0
244	539.80	675.55	0	0
245	539.80	661.97	0	0
246	539.80	648.39	0	0
247	539.80	634.80	0	0
248	539.80	621.22	0	0
249	539.80	607.64	0	0
250	539.80	603.14	4	4
251	556.89	750.25	0	0
252	556.89	746.75	0	0
253	556.89	734.13	0	0
254	556.89	721.52	0	0
255	556.89	708.91	0	0
256	556.89	696.30	0	0
257	556.89	683.69	0	0
258	556.89	671.08	0	0
259	556.89	658.47	0	0
260	556.89	645.86	0	0
261	556.89	633.25	0	0
262	556.89	620.64	0	0
263	556.89	608.03	0	0
264	556.89	603.53	4	4
265	573.98	753.53	0	0
266	573.98	750.03	0	0
267	573.98	737.15	0	0
268	573.98	724.28	0	0
269	573.98	711.41	0	0
270	573.98	698.53	0	0
271	573.98	685.66	0	0
272	573.98	672.79	0	0
273	573.98	659.91	0	0
274	573.98	647.04	0	0
275	573.98	634.17	0	0
276	573.98	621.29	0	0
277	573.98	608.42	0	0
278	573.98	603.92	4	4
279	591.08	756.81	0	0
280	591.08	753.31	0	0
281	591.08	740.17	0	0
282	591.08	727.04	0	0
283	591.08	713.90	0	0
284	591.08	700.76	0	0
285	591.08	687.63	0	0
286	591.08	674.49	0	0
287	591.08	661.36	0	0
288	591.08	648.22	0	0

fEpac2

289	591.08	635.09	0
290	591.08	621.95	0
291	591.08	608.81	0
292	591.08	604.31	4
293	608.17	760.09	0
294	608.17	756.59	0
295	608.17	743.19	0
296	608.17	729.79	0
297	608.17	716.39	0
298	608.17	702.99	0
299	608.17	689.60	0
300	608.17	676.20	0
301	608.17	662.80	0
302	608.17	649.40	0
303	608.17	636.00	0
304	608.17	622.60	0
305	608.17	609.21	0
306	608.17	604.71	4
307	625.26	763.37	0
308	625.26	759.87	0
309	625.26	747.35	0
310	625.26	734.82	0
311	625.26	722.30	0
312	625.26	709.78	0
313	625.26	697.26	0
314	625.26	684.73	0
315	625.26	672.21	0
316	625.26	659.69	0
317	625.26	647.17	0
318	625.26	634.64	0
319	625.26	622.12	0
320	625.26	609.60	0
321	625.26	605.10	4
322	642.35	766.65	0
323	642.35	763.15	0
324	642.35	750.47	0
325	642.35	737.79	0
326	642.35	725.11	0
327	642.35	712.42	0
328	642.35	699.74	0
329	642.35	687.06	0
330	642.35	674.38	0
331	642.35	661.70	0
332	642.35	649.02	0
333	642.35	636.34	0
334	642.35	623.66	0
335	642.35	609.99	0
336	642.35	605.49	4
337	658.64	766.96	0
338	658.64	763.46	0
339	658.64	750.70	0
340	658.64	737.94	0
341	658.64	725.19	0
342	658.64	712.43	0
343	658.64	699.67	0
344	658.64	686.91	0
345	658.64	674.15	0
346	658.64	661.40	0
347	658.64	648.64	0
348	658.64	635.88	0
349	658.64	623.12	0
350	658.64	610.36	0
351	658.64	605.86	4

fEpac2

352	674.92	767.27	0
353	674.92	763.77	0
354	674.92	750.91	0
355	674.92	738.06	0
356	674.92	725.20	0
357	674.92	712.34	0
358	674.92	699.49	0
359	674.92	686.63	0
360	674.92	673.78	0
361	674.92	660.92	0
362	674.92	648.06	0
363	674.92	635.21	0
364	674.92	622.35	0
365	674.92	610.74	0
366	674.92	606.24	4
367	692.68	771.34	0
368	692.68	767.84	0
369	692.68	754.78	0
370	692.68	741.73	0
371	692.68	728.67	0
372	692.68	715.61	0
373	692.68	702.55	0
374	692.68	689.49	0
375	692.68	676.44	0
376	692.68	663.38	0
377	692.68	650.32	0
378	692.68	637.26	0
379	692.68	624.20	0
380	692.68	611.14	0
381	692.68	606.64	4
382	710.45	775.42	0
383	710.45	771.92	0
384	710.45	758.55	0
385	710.45	745.19	0
386	710.45	731.83	0
387	710.45	718.46	0
388	710.45	705.10	0
389	710.45	691.73	0
390	710.45	678.37	0
391	710.45	665.01	0
392	710.45	651.64	0
393	710.45	638.28	0
394	710.45	624.92	0
395	710.45	611.55	0
396	710.45	607.05	4
397	728.21	779.49	0
398	728.21	775.99	0
399	728.21	763.37	0
400	728.21	750.75	0
401	728.21	738.14	0
402	728.21	725.52	0
403	728.21	712.90	0
404	728.21	700.28	0
405	728.21	687.67	0
406	728.21	675.05	0
407	728.21	662.43	0
408	728.21	649.81	0
409	728.21	637.19	0
410	728.21	624.58	0
411	728.21	611.96	0
412	728.21	607.46	4
413	745.97	783.56	0
414	745.97	780.06	0

fEpac2

415 745.97 767.16 0 0  
416 754.26 754.26 0 0  
417 745.97 741.36 0 0  
418 745.97 728.46 0 0  
419 745.97 715.56 0 0  
420 745.97 702.66 0 0  
421 745.97 689.76 0 0  
422 745.97 676.87 0 0  
423 745.97 663.97 0 0  
424 745.97 651.07 0 0  
425 745.97 638.17 0 0  
426 745.97 625.27 0 0  
427 745.97 612.37 0 0  
428 745.97 607.87 4  
429 763.74 787.64 0 0  
430 763.74 784.14 0 0  
431 763.74 770.95 0 0  
432 763.74 757.77 0 0  
433 763.74 744.59 0 0  
434 763.74 731.41 0 0  
435 763.74 718.23 0 0  
436 763.74 705.05 0 0  
437 763.74 691.86 0 0  
438 763.74 678.68 0 0  
439 763.74 665.50 0 0  
440 763.74 652.32 0 0  
441 763.74 639.14 0 0  
442 763.74 625.96 0 0  
443 763.74 612.77 0 0  
444 763.74 608.27 4  
445 781.50 791.71 0  
446 781.50 788.21 0  
447 781.50 774.71 0  
448 781.50 761.28 0  
449 781.50 747.82 0  
450 781.50 734.35 0  
451 781.50 720.89 0  
452 781.50 707.43 0  
453 781.50 693.96 0  
454 781.50 680.50 0  
455 781.50 667.04 0  
456 781.50 653.57 0  
457 781.50 640.11 0  
458 781.50 626.65 0  
459 781.50 613.18 0  
460 781.50 608.68 4  
461 799.26 795.78 0  
462 799.26 792.28 0  
463 799.26 779.52 0  
464 799.26 766.75 0  
465 799.26 753.99 0  
466 799.26 741.23 0  
467 799.26 728.46 0  
468 799.26 715.70 0  
469 799.26 702.94 0  
470 799.26 690.17 0  
471 799.26 677.41 0  
472 799.26 664.64 0  
473 799.26 651.88 0  
474 799.26 639.12 0  
475 799.26 626.35 0  
476 799.26 613.59 0  
477 799.26 609.09 4

fEpac2

478 817.02 799.85 0 0  
479 817.02 796.35 0 0  
480 817.02 783.33 0 0  
481 817.02 770.30 0 0  
482 817.02 757.28 0 0  
483 817.02 744.25 0 0  
484 817.02 731.23 0 0  
485 817.02 718.20 0 0  
486 817.02 705.18 0 0  
487 817.02 692.15 0 0  
488 817.02 679.12 0 0  
489 817.02 666.10 0 0  
490 817.02 653.07 0 0  
491 817.02 640.05 0 0  
492 817.02 627.02 0 0  
493 817.02 614.00 0 0  
494 817.02 609.50 4  
495 834.79 803.93 0 0  
496 834.79 800.43 0 0  
497 834.79 787.14 0 0  
498 834.79 773.85 0 0  
499 834.79 760.57 0 0  
500 834.79 747.28 0 0  
501 834.79 733.99 0 0  
502 834.79 720.70 0 0  
503 834.79 707.42 0 0  
504 834.79 694.13 0 0  
505 834.79 680.84 0 0  
506 834.79 667.55 0 0  
507 834.79 654.27 0 0  
508 834.79 640.98 0 0  
509 834.79 627.69 0 0  
510 834.79 614.40 0 0  
511 834.79 609.90 4  
512 834.79 608.00 0  
513 834.79 606.55 0  
514 834.79 604.50 0  
515 834.79 602.55 0  
516 834.79 600.55 0  
517 834.79 598.55 0  
518 834.79 596.55 0  
519 834.79 594.55 0  
520 834.79 592.55 0  
521 834.79 590.55 0  
522 834.79 588.55 0  
523 834.79 586.55 0  
524 834.79 584.55 0  
525 834.79 582.55 0  
526 834.79 580.55 0  
527 834.79 578.55 0  
528 834.79 576.55 0  
529 834.79 574.55 4  
530 834.79 572.55 0  
531 834.79 570.55 0  
532 834.79 568.55 0  
533 834.79 566.55 0  
534 834.79 564.55 0  
535 834.79 562.55 0  
536 834.79 560.55 0  
537 834.79 558.55 0  
538 834.79 556.55 0  
539 834.79 554.55 0  
540 834.79 552.55 0

fEpac2

541 871.04 678.66 0 0 0  
542 871.04 665.97 0 0 0  
543 871.04 653.29 0 0 0  
544 871.04 640.61 0 0 0  
545 871.04 627.92 0 0 0  
546 871.04 615.24 0 0 0  
547 871.04 602.56 4 0 0  
548 889.53 810.74 0 0 0  
549 889.53 806.50 0 0 0  
550 889.53 793.70 0 0 0  
551 889.53 780.89 0 0 0  
552 889.53 768.09 0 0 0  
553 889.53 755.29 0 0 0  
554 889.53 742.49 0 0 0  
555 889.53 729.68 0 0 0  
556 889.53 716.88 0 0 0  
557 889.53 704.08 0 0 0  
558 889.53 691.27 0 0 0  
559 889.53 678.47 0 0 0  
560 889.53 665.67 0 0 0  
561 889.53 652.87 0 0 0  
562 889.53 640.06 0 0 0  
563 889.53 627.26 0 0 0  
564 889.53 615.66 0 0 0  
565 889.53 611.16 4 0 0  
566 907.10 814.59 0 0 0  
567 907.10 811.09 0 0 0  
568 907.10 798.09 0 0 0  
569 907.10 785.09 0 0 0  
570 907.10 772.08 0 0 0  
571 907.10 759.08 0 0 0  
572 907.10 746.08 0 0 0  
573 907.10 733.08 0 0 0  
574 907.10 720.08 0 0 0  
575 907.10 707.09 0 0 0  
576 907.10 694.07 0 0 0  
577 907.10 681.07 0 0 0  
578 907.10 668.07 0 0 0  
579 907.10 655.07 0 0 0  
580 907.10 642.07 0 0 0  
581 907.10 629.07 0 0 0  
582 907.10 616.06 0 0 0  
583 907.10 611.56 4 0 0  
584 924.68 819.18 0 0 0  
585 924.68 815.68 0 0 0  
586 924.68 802.40 0 0 0  
587 924.68 789.12 0 0 0  
588 924.68 775.84 0 0 0  
589 924.68 762.55 0 0 0  
590 924.68 749.27 0 0 0  
591 924.68 735.99 0 0 0  
592 924.68 722.71 0 0 0  
593 924.68 709.43 0 0 0  
594 924.68 696.15 0 0 0  
595 924.68 682.87 0 0 0  
596 924.68 669.59 0 0 0  
597 924.68 656.31 0 0 0  
598 924.68 643.03 0 0 0  
599 924.68 629.75 0 0 0  
600 924.68 616.47 0 0 0  
601 924.68 611.97 4 0 0  
602 942.25 823.75 0 0 0  
603 942.25 820.27 0 0 0

fEpac2

604 942.25 807.55 0 0 0  
605 942.25 794.84 0 0 0  
606 942.25 782.13 0 0 0  
607 942.25 769.42 0 0 0  
608 942.25 756.70 0 0 0  
609 942.25 743.99 0 0 0  
610 942.25 731.28 0 0 0  
611 942.25 718.57 0 0 0  
612 942.25 705.86 0 0 0  
613 942.25 693.14 0 0 0  
614 942.25 680.43 0 0 0  
615 942.25 667.72 0 0 0  
616 942.25 655.01 0 0 0  
617 942.25 642.29 0 0 0  
618 942.25 629.58 0 0 0  
619 942.25 616.87 0 0 0  
620 942.25 612.37 4 0 0  
621 959.82 828.35 0 0 0  
622 959.82 824.85 0 0 0  
623 959.82 811.88 0 0 0  
624 959.82 798.91 0 0 0  
625 959.82 785.93 0 0 0  
626 959.82 772.96 0 0 0  
627 959.82 759.99 0 0 0  
628 959.82 747.01 0 0 0  
629 959.82 734.04 0 0 0  
630 959.82 721.06 0 0 0  
631 959.82 708.09 0 0 0  
632 959.82 695.12 0 0 0  
633 959.82 682.14 0 0 0  
634 959.82 669.17 0 0 0  
635 959.82 656.20 0 0 0  
636 959.82 643.22 0 0 0  
637 959.82 630.24 0 0 0  
638 959.82 617.27 0 0 0  
639 959.82 612.77 4 0 0  
640 977.40 832.94 0 0 0  
641 977.40 829.44 0 0 0  
642 977.40 816.21 0 0 0  
643 977.40 802.97 0 0 0  
644 977.40 789.74 0 0 0  
645 977.40 776.50 0 0 0  
646 977.40 763.27 0 0 0  
647 977.40 750.03 0 0 0  
648 977.40 736.80 0 0 0  
649 977.40 723.56 0 0 0  
650 977.40 710.32 0 0 0  
651 977.40 697.09 0 0 0  
652 977.40 683.85 0 0 0  
653 977.40 670.62 0 0 0  
654 977.40 657.38 0 0 0  
655 977.40 644.15 0 0 0  
656 977.40 630.91 0 0 0  
657 977.40 617.68 0 0 0  
658 977.40 613.18 4 0 0  
659 904.97 837.53 0 0 0  
660 904.97 834.05 0 0 0  
661 994.57 820.70 0 0 0  
662 994.57 807.36 0 0 0  
663 994.57 794.03 0 0 0  
664 994.57 780.70 0 0 0  
665 994.57 767.36 0 0 0  
666 994.57 754.03 0 0 0

fEpac2

667 994.97 740.70 0 0 0  
668 994.97 727.36 0 0 0  
669 994.97 714.03 0 0 0  
670 994.97 700.70 0 0 0  
671 994.97 687.36 0 0 0  
672 994.97 674.03 0 0 0  
673 994.97 660.69 0 0 0  
674 994.97 647.36 0 0 0  
675 994.97 634.03 0 0 0  
676 994.97 618.08 0 0 0  
677 994.97 613.58 4  
678 1012.30 843.08 0 0 0  
679 1012.30 838.56 0 0 0  
680 1012.30 825.29 0 0 0  
681 1012.30 812.02 0 0 0  
682 1012.30 798.75 0 0 0  
683 1012.30 785.48 0 0 0  
684 1012.30 772.21 0 0 0  
685 1012.30 758.95 0 0 0  
686 1012.30 745.68 0 0 0  
687 1012.30 732.41 0 0 0  
688 1012.30 719.14 0 0 0  
689 1012.30 705.87 0 0 0  
690 1012.30 692.60 0 0 0  
691 1012.30 679.33 0 0 0  
692 1012.30 666.07 0 0 0  
693 1012.30 652.80 0 0 0  
694 1012.30 639.53 0 0 0  
695 1012.30 626.26 0 0 0  
696 1012.30 621.76 4  
697 1029.64 846.58 0 0 0  
698 1029.64 843.08 0 0 0  
699 1029.64 830.04 0 0 0  
700 1029.64 817.00 0 0 0  
701 1029.64 803.96 0 0 0  
702 1029.64 790.92 0 0 0  
703 1029.64 777.88 0 0 0  
704 1029.64 764.84 0 0 0  
705 1029.64 751.80 0 0 0  
706 1029.64 738.76 0 0 0  
707 1029.64 725.72 0 0 0  
708 1029.64 712.68 0 0 0  
709 1029.64 699.64 0 0 0  
710 1029.64 686.60 0 0 0  
711 1029.64 673.56 0 0 0  
712 1029.64 660.52 0 0 0  
713 1029.64 647.48 0 0 0  
714 1029.64 634.44 4  
715 1029.64 629.94 0 0 0  
716 1046.97 851.11 0 0 0  
717 1046.97 847.61 0 0 0  
718 1046.97 834.89 0 0 0  
719 1046.97 822.16 0 0 0  
720 1046.97 809.44 0 0 0  
721 1046.97 796.72 0 0 0  
722 1046.97 784.00 0 0 0  
723 1046.97 771.27 0 0 0  
724 1046.97 758.55 0 0 0  
725 1046.97 745.83 0 0 0  
726 1046.97 733.11 0 0 0  
727 1046.97 720.38 0 0 0  
728 1046.97 707.66 0 0 0  
729 1046.97 694.94 0 0 0

fEpac2

730 1046.97 682.22 0 0 0  
731 1046.97 669.49 0 0 0  
732 1046.97 656.77 0 0 0  
733 1046.97 642.62 0 0 0  
734 1046.97 638.12 4  
735 1066.38 852.32 0 0 0  
736 1066.38 848.82 0 0 0  
737 1066.38 835.68 0 0 0  
738 1066.38 822.55 0 0 0  
739 1066.38 809.41 0 0 0  
740 1066.38 796.27 0 0 0  
741 1066.38 783.14 0 0 0  
742 1066.38 770.00 0 0 0  
743 1066.38 756.86 0 0 0  
744 1066.38 743.73 0 0 0  
745 1066.38 730.59 0 0 0  
746 1066.38 717.46 0 0 0  
747 1066.38 704.32 0 0 0  
748 1066.38 691.18 0 0 0  
749 1066.38 678.05 0 0 0  
750 1066.38 664.91 0 0 0  
751 1066.38 651.77 0 0 0  
752 1066.38 647.27 4  
753 1085.78 853.53 0 0 0  
754 1085.78 850.03 0 0 0  
755 1085.78 837.15 0 0 0  
756 1085.78 824.27 0 0 0  
757 1085.78 811.39 0 0 0  
758 1085.78 798.50 0 0 0  
759 1085.78 785.62 0 0 0  
760 1085.78 772.74 0 0 0  
761 1085.78 759.86 0 0 0  
762 1085.78 746.98 0 0 0  
763 1085.78 734.10 0 0 0  
764 1085.78 721.22 0 0 0  
765 1085.78 708.34 0 0 0  
766 1085.78 695.45 0 0 0  
767 1085.78 682.57 0 0 0  
768 1085.78 669.69 0 0 0  
769 1085.78 660.93 0 0 0  
770 1085.78 656.43 4  
771 1101.03 857.66 0 0 0  
772 1101.03 854.16 0 0 0  
773 1101.03 841.26 0 0 0  
774 1101.03 828.36 0 0 0  
775 1101.03 815.45 0 0 0  
776 1101.03 802.55 0 0 0  
777 1101.03 789.65 0 0 0  
778 1101.03 776.75 0 0 0  
779 1101.03 763.85 0 0 0  
780 1101.03 750.95 0 0 0  
781 1101.03 738.05 0 0 0  
782 1101.03 725.15 0 0 0  
783 1101.03 712.25 0 0 0  
784 1101.03 699.35 0 0 0  
785 1101.03 686.45 0 0 0  
786 1101.03 673.55 0 0 0  
787 1101.03 660.65 0 0 0  
788 1101.03 656.15 4  
789 1116.27 861.78 0 0 0  
790 1116.27 858.28 0 0 0  
791 1116.27 845.09 0 0 0  
792 1116.27 831.89 0 0 0

793 1116.27 818.70 0 0 0  
794 1116.27 805.50 0 0 0  
795 1116.27 792.31 0 0 0  
796 1116.27 779.11 0 0 0  
797 1116.27 765.92 0 0 0  
798 1116.27 752.72 0 0 0  
799 1116.27 739.53 0 0 0  
800 1116.27 726.33 0 0 0  
801 1116.27 713.14 0 0 0  
802 1116.27 699.94 0 0 0  
803 1116.27 686.75 0 0 0  
804 1116.27 673.55 0 0 0  
805 1116.27 660.36 0 0 0  
806 1116.27 647.16 4 0 0  
807 1131.52 865.91 0 0 0  
808 1131.52 862.41 0 0 0  
809 1131.52 849.77 0 0 0  
810 1131.52 837.12 0 0 0  
811 1131.52 824.47 0 0 0  
812 1131.52 811.83 0 0 0  
813 1131.52 799.18 0 0 0  
814 1131.52 786.54 0 0 0  
815 1131.52 773.89 0 0 0  
816 1131.52 761.24 0 0 0  
817 1131.52 748.60 0 0 0  
818 1131.52 735.95 0 0 0  
819 1131.52 723.31 0 0 0  
820 1131.52 710.66 0 0 0  
821 1131.52 698.01 0 0 0  
822 1131.52 685.37 0 0 0  
823 1131.52 672.72 0 0 0  
824 1131.52 660.08 0 0 0  
825 1131.52 647.44 4 0 0  
826 1146.76 870.04 0 0 0  
827 1146.76 866.54 0 0 0  
828 1146.76 853.51 0 0 0  
829 1146.76 840.47 0 0 0  
830 1146.76 827.44 0 0 0  
831 1146.76 814.41 0 0 0  
832 1146.76 801.37 0 0 0  
833 1146.76 788.34 0 0 0  
834 1146.76 775.31 0 0 0  
835 1146.76 762.27 0 0 0  
836 1146.76 749.24 0 0 0  
837 1146.76 736.21 0 0 0  
838 1146.76 723.17 0 0 0  
839 1146.76 710.14 0 0 0  
840 1146.76 697.11 0 0 0  
841 1146.76 684.07 0 0 0  
842 1146.76 671.04 0 0 0  
843 1146.76 659.79 0 0 0  
844 1146.76 655.29 4 0 0  
845 1163.08 874.46 0 0 0  
846 1163.08 870.96 0 0 0  
847 1163.08 858.22 0 0 0  
848 1163.08 845.46 0 0 0  
849 1163.08 832.75 0 0 0  
850 1163.08 820.01 0 0 0  
851 1163.08 807.28 0 0 0  
852 1163.08 794.54 0 0 0  
853 1163.08 781.81 0 0 0  
854 1163.08 769.07 0 0 0  
855 1163.08 756.33 0 0 0

856 1163.08 743.60 0 0 0  
857 1163.08 730.86 0 0 0  
858 1163.08 718.13 0 0 0  
859 1163.08 705.39 0 0 0  
860 1163.08 692.66 0 0 0  
861 1163.08 679.92 0 0 0  
862 1163.08 667.18 0 0 0  
863 1163.08 654.45 0 0 0  
864 1163.08 641.71 4 0 0  
865 1179.40 878.88 0 0 0  
866 1179.40 875.38 0 0 0  
867 1179.40 862.07 0 0 0  
868 1179.40 848.76 0 0 0  
869 1179.40 835.45 0 0 0  
870 1179.40 822.14 0 0 0  
871 1179.40 808.83 0 0 0  
872 1179.40 795.52 0 0 0  
873 1179.40 782.21 0 0 0  
874 1179.40 768.90 0 0 0  
875 1179.40 755.59 0 0 0  
876 1179.40 742.28 0 0 0  
877 1179.40 728.97 0 0 0  
878 1179.40 715.66 0 0 0  
879 1179.40 702.35 0 0 0  
880 1179.40 689.04 0 0 0  
881 1179.40 675.73 0 0 0  
882 1179.40 662.42 0 0 0  
883 1179.40 649.11 0 0 0  
884 1179.40 644.61 4 0 0  
885 1195.71 883.29 0 0 0  
886 1195.71 879.79 0 0 0  
887 1195.71 866.68 0 0 0  
888 1195.71 853.57 0 0 0  
889 1195.71 840.46 0 0 0  
890 1195.71 827.34 0 0 0  
891 1195.71 814.23 0 0 0  
892 1195.71 801.12 0 0 0  
893 1195.71 788.00 0 0 0  
894 1195.71 774.89 0 0 0  
895 1195.71 761.78 0 0 0  
896 1195.71 748.67 0 0 0  
897 1195.71 735.55 0 0 0  
898 1195.71 722.44 0 0 0  
899 1195.71 709.33 0 0 0  
900 1195.71 696.21 0 0 0  
901 1195.71 683.10 0 0 0  
902 1195.71 669.99 0 0 0  
903 1195.71 656.88 0 0 0  
904 1195.71 643.76 0 0 0  
905 1195.71 639.26 4 0 0  
906 1212.03 887.71 0 0 0  
907 1212.03 884.21 0 0 0  
908 1212.03 871.28 0 0 0  
909 1212.03 858.34 0 0 0  
910 1212.03 845.40 0 0 0  
911 1212.03 832.47 0 0 0  
912 1212.03 819.53 0 0 0  
913 1212.03 806.59 0 0 0  
914 1212.03 793.66 0 0 0  
915 1212.03 780.72 0 0 0  
916 1212.03 767.78 0 0 0  
917 1212.03 754.85 0 0 0  
918 1212.03 741.91 0 0 0

fEpac2

919	1212.03	728.98	0
920	1212.03	716.04	0
921	1212.03	703.10	0
922	1212.03	690.17	0
923	1212.03	677.23	0
924	1212.03	664.29	0
925	1212.03	651.36	0
926	1212.03	638.42	0
927	1212.03	625.48	4
928	1228.35	892.15	0
929	1228.35	888.63	0
930	1228.35	875.91	0
931	1228.35	863.18	0
932	1228.35	850.46	0
933	1228.35	837.73	0
934	1228.35	825.01	0
935	1228.35	812.29	0
936	1228.35	799.56	0
937	1228.35	786.84	0
938	1228.35	774.12	0
939	1228.35	761.39	0
940	1228.35	748.67	0
941	1228.35	735.94	0
942	1228.35	723.22	0
943	1228.35	710.50	0
944	1228.35	697.77	0
945	1228.35	685.05	0
946	1228.35	672.32	0
947	1228.35	659.60	0
948	1228.35	646.88	0
949	1228.35	633.08	0
950	1228.35	628.58	4
951	1247.50	892.40	0
952	1247.50	888.90	0
953	1247.50	875.90	0
954	1247.50	862.91	0
955	1247.50	849.91	0
956	1247.50	836.91	0
957	1247.50	823.91	0
958	1247.50	810.91	0
959	1247.50	797.91	0
960	1247.50	784.92	0
961	1247.50	771.92	0
962	1247.50	758.92	0
963	1247.50	745.92	0
964	1247.50	732.92	0
965	1247.50	719.92	0
966	1247.50	706.93	0
967	1247.50	693.93	0
968	1247.50	680.93	0
969	1247.50	667.93	0
970	1247.50	654.93	0
971	1247.50	641.94	0
972	1247.50	626.81	0
973	1247.50	622.31	4
974	1259.36	892.57	0
975	1259.36	889.07	0
976	1259.36	875.90	0
977	1259.36	862.73	0
978	1259.36	849.55	0
979	1259.36	836.38	0
980	1259.36	823.21	0
981	1259.36	810.04	0

Page 41

fEpac2

982	1259.36	796.87	0
983	1259.36	783.70	0
984	1259.36	770.52	0
985	1259.36	757.35	0
986	1259.36	744.18	0
987	1259.36	731.01	0
988	1259.36	717.84	0
989	1259.36	704.67	0
990	1259.36	691.49	0
991	1259.36	678.32	0
992	1259.36	665.15	0
993	1259.36	651.98	0
994	1259.36	638.81	0
995	1259.36	626.82	4
996	1259.36	622.32	4
997	1272.89	896.29	0
998	1272.89	892.79	0
999	1272.89	879.49	0
1000	1272.89	866.19	0
1001	1272.89	852.89	0
1002	1272.89	839.59	0
1003	1272.89	826.30	0
1004	1272.89	813.00	0
1005	1272.89	799.70	0
1006	1272.89	786.40	0
1007	1272.89	773.10	0
1008	1272.89	759.81	0
1009	1272.89	746.51	0
1010	1272.89	733.21	0
1011	1272.89	719.91	0
1012	1272.89	706.61	0
1013	1272.89	693.32	0
1014	1272.89	680.02	0
1015	1272.89	666.72	0
1016	1272.89	653.42	0
1017	1272.89	640.13	0
1018	1272.89	626.83	0
1019	1272.89	622.33	4
1020	1286.41	900.00	0
1021	1286.41	896.50	0
1022	1286.41	883.72	0
1023	1286.41	870.94	0
1024	1286.41	858.15	0
1025	1286.41	845.37	0
1026	1286.41	832.59	0
1027	1286.41	819.81	0
1028	1286.41	807.03	0
1029	1286.41	794.24	0
1030	1286.41	781.46	0
1031	1286.41	768.68	0
1032	1286.41	755.90	0
1033	1286.41	743.12	0
1034	1286.41	730.34	0
1035	1286.41	717.55	0
1036	1286.41	704.77	0
1037	1286.41	691.99	0
1038	1286.41	679.21	0
1039	1286.41	666.43	0
1040	1286.41	653.64	0
1041	1286.41	640.86	0
1042	1286.41	626.84	0
1043	1286.41	622.34	4
1044	1304.04	899.99	0

Page 42

1045	1304.04	896.49	0
1046	1304.04	883.65	0
1047	1304.04	870.81	0
1048	1304.04	857.97	0
1049	1304.04	845.13	0
1050	1304.04	832.29	0
1051	1304.04	819.45	0
1052	1304.04	806.61	0
1053	1304.04	793.77	0
1054	1304.04	780.93	0
1055	1304.04	768.09	0
1056	1304.04	755.25	0
1057	1304.04	742.41	0
1058	1304.04	729.57	0
1059	1304.04	716.73	0
1060	1304.04	703.89	0
1061	1304.04	691.05	0
1062	1304.04	678.21	0
1063	1304.04	665.37	0
1064	1304.04	652.53	0
1065	1304.04	639.69	0
1066	1304.04	626.85	0
1067	1304.04	622.35	4
1068	1321.66	899.97	0
1069	1321.66	896.47	0
1070	1321.66	883.64	0
1071	1321.66	870.80	0
1072	1321.66	857.96	0
1073	1321.66	845.12	0
1074	1321.66	832.28	0
1075	1321.66	819.44	0
1076	1321.66	806.60	0
1077	1321.66	793.76	0
1078	1321.66	780.93	0
1079	1321.66	768.09	0
1080	1321.66	755.25	0
1081	1321.66	742.41	0
1082	1321.66	729.57	0
1083	1321.66	716.73	0
1084	1321.66	703.89	0
1085	1321.66	691.05	0
1086	1321.66	678.22	0
1087	1321.66	665.38	0
1088	1321.66	652.54	0
1089	1321.66	639.70	0
1090	1321.66	626.86	0
1091	1321.66	622.36	4
1092	1339.29	899.96	0
1093	1339.29	896.46	0
1094	1339.29	883.62	0
1095	1339.29	870.79	0
1096	1339.29	857.95	0
1097	1339.29	845.11	0
1098	1339.29	832.27	0
1099	1339.29	819.44	0
1100	1339.29	806.60	0
1101	1339.29	793.76	0
1102	1339.29	780.92	0
1103	1339.29	768.09	0
1104	1339.29	755.25	0
1105	1339.29	742.41	0
1106	1339.29	729.57	0
1107	1339.29	716.74	0

1108	1339.29	703.90	0
1109	1339.29	691.06	0
1110	1339.29	678.22	0
1111	1339.29	665.39	0
1112	1339.29	652.55	0
1113	1339.29	639.71	0
1114	1339.29	626.87	0
1115	1339.29	622.37	4
1116	1356.92	899.95	0
1117	1356.92	896.45	0
1118	1356.92	883.61	0
1119	1356.92	870.78	0
1120	1356.92	857.94	0
1121	1356.92	845.10	0
1122	1356.92	832.27	0
1123	1356.92	819.43	0
1124	1356.92	806.59	0
1125	1356.92	793.76	0
1126	1356.92	780.92	0
1127	1356.92	768.08	0
1128	1356.92	755.25	0
1129	1356.92	742.41	0
1130	1356.92	729.58	0
1131	1356.92	716.74	0
1132	1356.92	703.90	0
1133	1356.92	691.07	0
1134	1356.92	678.23	0
1135	1356.92	665.39	0
1136	1356.92	652.56	0
1137	1356.92	639.72	0
1138	1356.92	626.88	0
1139	1356.92	622.38	4
1140	1374.55	896.94	0
1141	1374.55	893.44	0
1142	1374.55	880.60	0
1143	1374.55	867.77	0
1144	1374.55	854.93	0
1145	1374.55	842.10	0
1146	1374.55	829.26	0
1147	1374.55	816.42	0
1148	1374.55	803.59	0
1149	1374.55	790.75	0
1150	1374.55	777.92	0
1151	1374.55	765.08	0
1152	1374.55	752.25	0
1153	1374.55	739.41	0
1154	1374.55	726.58	0
1155	1374.55	713.74	0
1156	1374.55	700.91	0
1157	1374.55	688.07	0
1158	1374.55	675.24	0
1159	1374.55	662.40	0
1160	1374.55	649.57	0
1161	1374.55	636.73	0
1162	1374.55	623.90	0
1163	1374.55	611.06	0
1164	1374.55	598.23	4
1165	1374.55	585.39	0
1166	1374.55	572.56	0
1167	1374.55	559.72	0
1168	1374.55	546.89	0
1169	1374.55	534.05	0
1170	1374.55	521.22	0



fEpac2

1171	1392.17	819.42	0
1172	1392.17	806.58	0
1173	1392.17	793.75	0
1174	1392.17	780.92	0
1175	1392.17	768.08	0
1176	1392.17	755.25	0
1177	1392.17	742.41	0
1178	1392.17	729.58	0
1179	1392.17	716.75	0
1180	1392.17	703.91	0
1181	1392.17	691.08	0
1182	1392.17	678.24	0
1183	1392.17	665.41	0
1184	1392.17	652.58	0
1185	1392.17	639.74	0
1186	1392.17	626.91	0
1187	1392.17	622.41	4
1188	1409.80	899.91	0
1189	1409.80	896.41	0
1190	1409.80	883.64	0
1191	1409.80	870.87	0
1192	1409.80	858.10	0
1193	1409.80	845.33	0
1194	1409.80	832.56	0
1195	1409.80	819.79	0
1196	1409.80	807.03	0
1197	1409.80	794.26	0
1198	1409.80	781.49	0
1199	1409.80	768.72	0
1200	1409.80	755.95	0
1201	1409.80	743.18	0
1202	1409.80	730.41	0
1203	1409.80	717.64	0
1204	1409.80	704.87	0
1205	1409.80	692.10	0
1206	1409.80	679.33	0
1207	1409.80	666.56	0
1208	1409.80	653.80	0
1209	1409.80	641.03	0
1210	1409.80	626.92	0
1211	1409.80	622.42	4
1212	1423.92	895.89	0
1213	1423.92	892.39	0
1214	1423.92	879.11	0
1215	1423.92	865.84	0
1216	1423.92	852.57	0
1217	1423.92	839.29	0
1218	1423.92	826.02	0
1219	1423.92	812.75	0
1220	1423.92	799.48	0
1221	1423.92	786.20	0
1222	1423.92	772.93	0
1223	1423.92	759.66	0
1224	1423.92	746.39	0
1225	1423.92	733.11	0
1226	1423.92	719.84	0
1227	1423.92	706.57	0
1228	1423.92	693.29	0
1229	1423.92	680.02	0
1230	1423.92	666.75	0
1231	1423.92	653.48	0
1232	1423.92	640.20	0
1233	1423.92	626.93	0

Page 45

fEpac2

1234	1423.92	622.43	4
1235	1438.03	891.86	0
1236	1438.03	888.36	0
1237	1438.03	875.22	0
1238	1438.03	862.09	0
1239	1438.03	848.95	0
1240	1438.03	835.81	0
1241	1438.03	822.68	0
1242	1438.03	809.54	0
1243	1438.03	796.40	0
1244	1438.03	783.27	0
1245	1438.03	770.13	0
1246	1438.03	756.99	0
1247	1438.03	743.86	0
1248	1438.03	730.72	0
1249	1438.03	717.58	0
1250	1438.03	704.45	0
1251	1438.03	691.31	0
1252	1438.03	678.17	0
1253	1438.03	665.04	0
1254	1438.03	651.90	0
1255	1438.03	638.77	0
1256	1438.03	626.94	0
1257	1438.03	622.44	4
1258	1452.59	891.77	0
1259	1452.59	888.27	0
1260	1452.59	875.20	0
1261	1452.59	862.14	0
1262	1452.59	849.07	0
1263	1452.59	836.01	0
1264	1452.59	822.94	0
1265	1452.59	809.87	0
1266	1452.59	796.81	0
1267	1452.59	783.74	0
1268	1452.59	770.68	0
1269	1452.59	757.61	0
1270	1452.59	744.54	0
1271	1452.59	731.48	0
1272	1452.59	718.41	0
1273	1452.59	705.35	0
1274	1452.59	692.28	0
1275	1452.59	679.21	0
1276	1452.59	666.15	0
1277	1452.59	653.08	0
1278	1452.59	640.02	0
1279	1452.59	626.95	0
1280	1452.59	622.45	4
1281	1467.15	891.68	0
1282	1467.15	888.18	0
1283	1467.15	875.34	0
1284	1467.15	862.50	0
1285	1467.15	849.67	0
1286	1467.15	836.83	0
1287	1467.15	823.99	0
1288	1467.15	811.15	0
1289	1467.15	798.31	0
1290	1467.15	785.47	0
1291	1467.15	772.64	0
1292	1467.15	759.80	0
1293	1467.15	746.96	0
1294	1467.15	734.12	0
1295	1467.15	721.28	0
1296	1467.15	708.45	0

Page 46

fEpac2

1297	1467.15	695.61	0
1298	1467.15	682.77	0
1299	1467.15	669.93	0
1300	1467.15	657.09	0
1301	1467.15	644.25	0
1302	1467.15	626.96	0
1303	1467.15	622.46	4
1304	1484.16	886.68	0
1305	1484.16	883.18	0
1306	1484.16	870.14	0
1307	1484.16	857.10	0
1308	1484.16	844.06	0
1309	1484.16	831.02	0
1310	1484.16	817.98	0
1311	1484.16	804.94	0
1312	1484.16	791.90	0
1313	1484.16	778.86	0
1314	1484.16	765.82	0
1315	1484.16	752.78	0
1316	1484.16	739.74	0
1317	1484.16	726.70	0
1318	1484.16	713.66	0
1319	1484.16	700.62	0
1320	1484.16	687.58	0
1321	1484.16	674.54	0
1322	1484.16	661.50	0
1323	1484.16	648.46	0
1324	1484.16	635.43	0
1325	1484.16	630.93	4
1326	1501.18	881.67	0
1327	1501.18	878.17	0
1328	1501.18	865.16	0
1329	1501.18	852.14	0
1330	1501.18	839.13	0
1331	1501.18	826.11	0
1332	1501.18	813.10	0
1333	1501.18	800.08	0
1334	1501.18	787.06	0
1335	1501.18	774.05	0
1336	1501.18	761.03	0
1337	1501.18	748.02	0
1338	1501.18	735.00	0
1339	1501.18	721.98	0
1340	1501.18	708.97	0
1341	1501.18	695.95	0
1342	1501.18	682.94	0
1343	1501.18	669.92	0
1344	1501.18	656.91	0
1345	1501.18	643.89	0
1346	1501.18	639.39	4
1347	1518.19	876.67	0
1348	1518.19	873.17	0
1349	1518.19	860.18	0
1350	1518.19	847.19	0
1351	1518.19	834.20	0
1352	1518.19	821.21	0
1353	1518.19	808.23	0
1354	1518.19	795.24	0
1355	1518.19	782.25	0
1356	1518.19	769.26	0
1357	1518.19	756.27	0
1358	1518.19	743.28	0
1359	1518.19	730.29	0

Page 47

fEpac2

1360	1518.19	717.30	0
1361	1518.19	704.31	0
1362	1518.19	691.32	0
1363	1518.19	678.33	0
1364	1518.19	665.34	0
1365	1518.19	652.36	0
1366	1518.19	647.86	4
1367	1535.20	871.67	0
1368	1535.20	868.17	0
1369	1535.20	855.21	0
1370	1535.20	842.25	0
1371	1535.20	829.29	0
1372	1535.20	816.33	0
1373	1535.20	803.37	0
1374	1535.20	790.41	0
1375	1535.20	777.45	0
1376	1535.20	764.49	0
1377	1535.20	751.54	0
1378	1535.20	738.58	0
1379	1535.20	725.62	0
1380	1535.20	712.66	0
1381	1535.20	699.70	0
1382	1535.20	686.74	0
1383	1535.20	673.78	0
1384	1535.20	660.82	0
1385	1535.20	656.32	4
1386	1552.22	866.67	0
1387	1552.22	863.17	0
1388	1552.22	850.24	0
1389	1552.22	837.31	0
1390	1552.22	824.39	0
1391	1552.22	811.46	0
1392	1552.22	798.54	0
1393	1552.22	785.61	0
1394	1552.22	772.69	0
1395	1552.22	759.76	0
1396	1552.22	746.84	0
1397	1552.22	733.91	0
1398	1552.22	720.99	0
1399	1552.22	708.06	0
1400	1552.22	695.14	0
1401	1552.22	682.21	0
1402	1552.22	669.29	0
1403	1552.22	664.79	4
1404	1569.23	861.66	0
1405	1569.23	858.16	0
1406	1569.23	845.28	0
1407	1569.23	832.39	0
1408	1569.23	819.50	0
1409	1569.23	806.62	0
1410	1569.23	793.73	0
1411	1569.23	780.84	0
1412	1569.23	767.95	0
1413	1569.23	755.07	0
1414	1569.23	742.18	0
1415	1569.23	729.30	0
1416	1569.23	716.41	0
1417	1569.23	703.52	0
1418	1569.23	690.64	0
1419	1569.23	677.75	0
1420	1569.23	673.25	4
1421	1586.24	856.66	0
1422	1586.24	853.16	0

Page 48

fEpac2

1423 1586.24 840.32 0  
1424 1586.24 827.48 0  
1425 1586.24 814.63 0  
1426 1586.24 801.79 0  
1427 1586.24 788.95 0  
1428 1586.24 776.11 0  
1429 1586.24 763.27 0  
1430 1586.24 750.43 0  
1431 1586.24 737.58 0  
1432 1586.24 724.74 0  
1433 1586.24 711.90 0  
1434 1586.24 699.06 0  
1435 1586.24 686.22 0  
1436 1586.24 673.37 4  
1437 1603.25 851.66 0  
1438 1603.25 848.16 0  
1439 1603.25 835.37 0  
1440 1603.25 822.58 0  
1441 1603.25 809.79 0  
1442 1603.25 797.00 0  
1443 1603.25 784.21 0  
1444 1603.25 771.42 0  
1445 1603.25 758.63 0  
1446 1603.25 745.84 0  
1447 1603.25 733.05 0  
1448 1603.25 720.26 0  
1449 1603.25 707.47 0  
1450 1603.25 694.68 0  
1451 1603.25 681.89 4  
1452 1620.27 846.65 0  
1453 1620.27 843.15 0  
1454 1620.27 830.43 0  
1455 1620.27 817.70 0  
1456 1620.27 804.97 0  
1457 1620.27 792.24 0  
1458 1620.27 779.51 0  
1459 1620.27 766.79 0  
1460 1620.27 754.06 0  
1461 1620.27 741.33 0  
1462 1620.27 728.60 0  
1463 1620.27 715.87 0  
1464 1620.27 703.15 0  
1465 1620.27 698.65 4  
1466 1637.28 841.65 0  
1467 1637.28 838.15 0  
1468 1637.28 825.27 0  
1469 1637.28 812.39 0  
1470 1637.28 799.51 0  
1471 1637.28 786.63 0  
1472 1637.28 773.75 0  
1473 1637.28 760.87 0  
1474 1637.28 747.99 0  
1475 1637.28 735.11 0  
1476 1637.28 722.23 0  
1477 1637.28 709.35 0  
1478 1637.28 707.11 0  
1479 1620.65 841.62 4  
1480 1620.65 838.12 0  
1481 1620.65 824.80 0  
1482 1620.65 811.48 0  
1483 1620.65 798.16 0  
1484 1620.65 784.85 0  
1485 1620.65 771.53 0

Page 49

fEpac2

1486 1650.65 758.21 0  
1487 1650.65 744.90 0  
1488 1650.65 731.58 0  
1489 1650.65 718.26 0  
1490 1650.65 713.76 4  
1491 1664.01 841.58 0  
1492 1664.01 838.08 0  
1493 1664.01 825.70 0  
1494 1664.01 813.31 0  
1495 1664.01 800.93 0  
1496 1664.01 788.55 0  
1497 1664.01 776.17 0  
1498 1664.01 763.78 0  
1499 1664.01 751.40 0  
1500 1664.01 739.02 0  
1501 1664.01 724.91 0  
1502 1664.01 720.41 4  
1503 1679.26 837.32 0  
1504 1679.26 833.82 0  
1505 1679.26 820.98 0  
1506 1679.26 808.14 0  
1507 1679.26 795.29 0  
1508 1679.26 782.45 0  
1509 1679.26 769.61 0  
1510 1679.26 756.77 0  
1511 1679.26 743.93 0  
1512 1679.26 732.50 0  
1513 1679.26 728.00 4  
1514 1699.54 831.65 0  
1515 1699.54 828.15 0  
1516 1699.54 814.53 0  
1517 1699.54 800.92 0  
1518 1699.54 787.30 0  
1519 1699.54 773.69 0  
1520 1699.54 760.07 0  
1521 1699.54 746.45 0  
1522 1699.54 734.45 0  
1523 1699.54 729.95 4  
1524 1718.44 830.68 0  
1525 1718.44 827.18 0  
1526 1718.44 814.19 0  
1527 1718.44 801.20 0  
1528 1718.44 788.21 0  
1529 1718.44 775.23 0  
1530 1718.44 762.24 0  
1531 1718.44 749.25 0  
1532 1718.44 736.26 0  
1533 1718.44 731.76 4  
1534 1737.33 829.71 0  
1535 1737.33 826.21 0  
1536 1737.33 814.13 0  
1537 1737.33 802.04 0  
1538 1737.33 789.95 0  
1539 1737.33 777.86 0  
1540 1737.33 765.77 0  
1541 1737.33 753.69 0  
1542 1737.33 738.07 0  
1543 1737.33 733.57 4  
1544 1762.17 828.44 0  
1545 1762.17 824.94 0  
1546 1762.17 812.50 0  
1547 1762.17 800.06 0  
1548 1762.17 787.62 0

Page 50

fEpac2

1549	1762.17	775.18	0
1550	1762.17	762.74	0
1551	1762.17	750.16	0
1552	1762.17	745.66	4
1553	1780.40	823.52	0
1554	1780.40	820.02	0
1555	1780.40	809.85	0
1556	1780.40	799.69	0
1557	1780.40	789.52	0
1558	1780.40	779.36	0
1559	1780.40	769.19	0
1560	1780.40	759.03	0
1561	1780.40	754.53	4
1562	1798.63	818.59	0
1563	1798.63	815.09	0
1564	1798.63	805.65	0
1565	1798.63	796.21	0
1566	1798.63	786.78	0
1567	1798.63	777.34	0
1568	1798.63	767.90	0
1569	1798.63	763.40	4
1570	1816.86	813.67	0
1571	1816.86	810.17	0
1572	1816.86	801.82	0
1573	1816.86	793.47	0
1574	1816.86	785.12	0
1575	1816.86	776.77	0
1576	1816.86	772.27	4
1577	1835.09	808.74	0
1578	1835.09	805.24	0
1579	1835.09	798.71	0
1580	1835.09	792.18	0
1581	1835.09	785.65	0
1582	1835.09	781.15	4
1583	1853.32	803.82	0
1584	1853.32	796.92	0
1585	1853.32	790.02	4
1586	1871.55	798.89	4

Kettleman Hills Landfill B-18 Site Response, F East, Pacoima 360  
 Seismic Coefficient Surface Histories

Block	Time-sec	fEpac2
.020	-.000004	1.220
.040	-.000016	1.240
.060	-.000032	1.260
.080	-.000048	1.280
.100	-.000063	1.300
.120	-.000076	1.320
.140	-.000086	1.340
.160	-.000092	1.360
.180	-.000091	1.380
.200	-.000080	1.400
.220	-.000055	1.420
.240	-.000013	1.440
.260	.000051	1.460
.280	.000149	1.480
.300	.000278	1.500
.320	.000370	1.520
.340	.000371	1.540
.360	.000416	1.560
.380	.000683	1.580
.400	.001138	1.600
.420	.001665	1.620
.440	.002241	1.640
.460	.002553	1.660
.480	.002252	1.680
.500	.001975	1.700
.520	.002433	1.720
.540	.003064	1.740
.560	.002986	1.760
.580	.002300	1.780
.600	.001630	1.800
.620	.001173	1.820
.640	.001070	1.840
.660	.001377	1.860
.680	.001737	1.880
.700	.002254	1.900
.720	.002910	1.920
.740	.002971	1.940
.760	.002088	1.960
.780	.000655	1.980
.800	-.000272	2.000
.820	-.000423	2.020
.840	-.000626	2.040
.860	-.000947	2.060
.880	-.001039	2.080
.900	-.000873	2.100
.920	-.000282	2.120
.940	.001195	2.140
.960	.003352	2.160
.980	.004516	2.180
1.000	.003482	2.200
1.020	.001082	2.220
1.040	-.001026	2.240
1.060	-.001926	2.260
1.080	-.001845	2.280
1.100	-.001590	2.300
1.120	-.001899	2.320
1.140	-.002520	2.340
1.160	-.001866	2.360
1.180	-.000812	2.380
1.200	.003594	2.400
		2.420
		2.440
		2.460

fEpac2

.04171	.004171
.02720	.002720
.01171	.001171
.000360	.000360
.000186	.000186
.000795	.000795
.001651	.001651
.002511	.002511
.002955	.002955
.002384	.002384
.000002	.000002
.003131	.003131
.004667	.004667
.003835	.003835
.001576	.001576
.000514	.000514
.001025	.001025
.000086	.000086
.000825	.000825
.001411	.001411
.002394	.002394
.003789	.003789
.005241	.005241
.005717	.005717
.004479	.004479
.001708	.001708
.001707	.001707
.003507	.003507
.003309	.003309
.003223	.003223
.003830	.003830
.004393	.004393
.004221	.004221
.003156	.003156
.001785	.001785
.000759	.000759
.000697	.000697
.001728	.001728
.003070	.003070
.004231	.004231
.004531	.004531
.003906	.003906
.004178	.004178
.006837	.006837
.010547	.010547
.012922	.012922
.013447	.013447
.012517	.012517
.010145	.010145
.006827	.006827
.004264	.004264
.004163	.004163
.006305	.006305
.009108	.009108
.010945	.010945
.011208	.011208
.010912	.010912
.010893	.010893
.011102	.011102
.011780	.011780
.012773	.012773
.013201	.013201
.012887	.012887

fEpac2

2. 480 -. 012169  
2. 500 -. 011140  
2. 520 -. 009895  
2. 540 -. 008014  
2. 560 -. 005204  
2. 580 -. 003118  
2. 600 -. 003702  
2. 620 -. 006544  
2. 640 -. 009867  
2. 660 -. 012723  
2. 680 -. 015038  
2. 700 -. 016311  
2. 720 -. 016114  
2. 740 -. 014995  
2. 760 -. 013528  
2. 780 -. 011868  
2. 800 -. 010323  
2. 820 -. 009103  
2. 840 -. 007832  
2. 860 -. 007049  
2. 880 -. 007969  
2. 900 -. 010303  
2. 920 -. 012988  
2. 940 -. 014876  
2. 960 -. 015171  
2. 980 -. 014450  
3. 000 -. 013409  
3. 020 -. 011825  
3. 040 -. 009324  
3. 060 -. 005724  
3. 080 -. 001495  
3. 100 -. 002048  
3. 120 -. 004775  
3. 140 -. 007874  
3. 160 -. 011572  
3. 180 -. 014837  
3. 200 -. 017084  
3. 220 -. 018872  
3. 240 -. 021509  
3. 260 -. 026404  
3. 280 -. 032427  
3. 300 -. 037228  
3. 320 -. 041911  
3. 340 -. 048044  
3. 360 -. 055265  
3. 380 -. 062495  
3. 400 -. 068164  
3. 420 -. 070810  
3. 440 -. 071867  
3. 460 -. 075056  
3. 480 -. 079391  
3. 500 -. 087563  
3. 520 -. 107145  
3. 540 -. 137652  
3. 560 -. 167314  
3. 580 -. 178836  
3. 600 -. 165358  
3. 620 -. 137826  
3. 640 -. 109092  
3. 660 -. 077475  
3. 680 -. 044492  
3. 700 -. 018668  
3. 720 -. 005217

Page 3

fEpac2

3. 740 -. 031593  
3. 760 -. 058479  
3. 780 -. 078987  
3. 800 -. 084510  
3. 820 -. 083055  
3. 840 -. 079351  
3. 860 -. 068728  
3. 880 -. 056403  
3. 900 -. 050955  
3. 920 -. 052511  
3. 940 -. 056658  
3. 960 -. 049244  
3. 980 -. 070814  
4. 000 -. 077546  
4. 020 -. 082663  
4. 040 -. 086900  
4. 060 -. 090417  
4. 080 -. 093964  
4. 100 -. 096437  
4. 120 -. 094784  
4. 140 -. 087496  
4. 160 -. 075308  
4. 180 -. 060831  
4. 200 -. 048099  
4. 220 -. 040007  
4. 240 -. 036457  
4. 260 -. 036772  
4. 280 -. 040922  
4. 300 -. 047086  
4. 320 -. 050688  
4. 340 -. 047340  
4. 360 -. 035823  
4. 380 -. 017657  
4. 400 -. 003452  
4. 420 -. 022560  
4. 440 -. 036851  
4. 460 -. 047284  
4. 480 -. 056103  
4. 500 -. 063752  
4. 520 -. 067831  
4. 540 -. 065412  
4. 560 -. 056986  
4. 580 -. 046430  
4. 600 -. 037466  
4. 620 -. 031171  
4. 640 -. 026645  
4. 660 -. 022221  
4. 680 -. 016280  
4. 700 -. 008681  
4. 720 -. 000629  
4. 740 -. 007419  
4. 760 -. 016245  
4. 780 -. 025667  
4. 800 -. 033765  
4. 820 -. 037903  
4. 840 -. 036636  
4. 860 -. 031234  
4. 880 -. 024840  
4. 900 -. 020085  
4. 920 -. 016431  
4. 940 -. 011628  
4. 960 -. 004850  
4. 980 -. 003165

Page 4

fEpac2

5. 000 . 010454  
5. 020 . 014669  
5. 040 . 014828  
5. 060 . 011618  
5. 080 . 006785  
5. 100 . 002754  
5. 120 . 001034  
5. 140 . 001307  
5. 160 . 002192  
5. 180 . 002581  
5. 200 . 002671  
5. 220 . 003303  
5. 240 . 005328  
5. 260 . 009646  
5. 280 . 016740  
5. 300 . 025898  
5. 320 . 034543  
5. 340 . 039209  
5. 360 . 038329  
5. 380 . 033191  
5. 400 . 026244  
5. 420 . 018856  
5. 440 . 011090  
5. 460 . 003248  
5. 480 . 003677  
5. 500 . 008709  
5. 520 . 011661  
5. 540 . 012940  
5. 560 . 013264  
5. 580 . 014286  
5. 600 . 018047  
5. 620 . 025012  
5. 640 . 033340  
5. 660 . 039507  
5. 680 . 040075  
5. 700 . 034128  
5. 720 . 023848  
5. 740 . 012458  
5. 760 . 002658  
5. 780 . 003564  
5. 800 . 006547  
5. 820 . 008698  
5. 840 . 012029  
5. 860 . 017541  
5. 880 . 024933  
5. 900 . 031642  
5. 920 . 034793  
5. 940 . 034424  
5. 960 . 032211  
5. 980 . 029336  
6. 000 . 026840  
6. 020 . 025069  
6. 040 . 023551  
6. 060 . 022436  
6. 080 . 021830  
6. 100 . 020630  
6. 120 . 019118  
6. 140 . 014978  
6. 160 . 012078  
6. 180 . 010565  
6. 200 . 011439  
6. 220 . 013972  
6. 240 . 016205

Page 5

fEpac2

6. 260 . 017206  
6. 280 . 017035  
6. 300 . 015414  
6. 320 . 011415  
6. 340 . 004412  
6. 360 . 004577  
6. 380 . 012965  
6. 400 . 018333  
6. 420 . 020851  
6. 440 . 022609  
6. 460 . 024412  
6. 480 . 025444  
6. 500 . 025200  
6. 520 . 023919  
6. 540 . 022045  
6. 560 . 020156  
6. 580 . 018756  
6. 600 . 018082  
6. 620 . 017736  
6. 640 . 016693  
6. 660 . 013935  
6. 680 . 008567  
6. 700 . 000263  
6. 720 . 009979  
6. 740 . 020681  
6. 760 . 030592  
6. 780 . 037810  
6. 800 . 040730  
6. 820 . 039352  
6. 840 . 034312  
6. 860 . 027089  
6. 880 . 020209  
6. 900 . 015714  
6. 920 . 014375  
6. 940 . 015477  
6. 960 . 017224  
6. 980 . 018077  
7. 000 . 017358  
7. 020 . 014979  
7. 040 . 011556  
7. 060 . 008230  
7. 080 . 005861  
7. 100 . 004541  
7. 120 . 003451  
7. 140 . 001927  
7. 160 . 000319  
7. 180 . 001050  
7. 200 . 002053  
7. 220 . 002286  
7. 240 . 001843  
7. 260 . 001349  
7. 280 . 001837  
7. 300 . 004714  
7. 320 . 010380  
7. 340 . 017652  
7. 360 . 024210  
7. 380 . 028251  
7. 400 . 030281  
7. 420 . 031996  
7. 440 . 034872  
7. 460 . 039699  
7. 480 . 046434  
7. 500 . 054196

Page 6

fEpac2

7. 520 -. 060658  
7. 540 -. 063066  
7. 560 -. 060373  
7. 580 -. 053528  
7. 600 -. 044699  
7. 620 -. 036624  
7. 640 -. 031173  
7. 660 -. 028041  
7. 680 -. 025503  
7. 700 -. 022077  
7. 720 -. 017096  
7. 740 -. 010091  
7. 760 -. 000354  
7. 780 -. 012023  
7. 800 -. 025106  
7. 820 -. 036316  
7. 840 -. 044320  
7. 860 -. 049024  
7. 880 -. 050580  
7. 900 -. 048845  
7. 920 -. 043564  
7. 940 -. 035412  
7. 960 -. 026519  
7. 980 -. 019261  
8. 000 -. 014397  
8. 020 -. 010765  
8. 040 -. 007209  
8. 060 -. 004035  
8. 080 -. 002151  
8. 100 -. 001932  
8. 120 -. 003609  
8. 140 -. 008197  
8. 160 -. 016524  
8. 180 -. 027582  
8. 200 -. 038659  
8. 220 -. 046144  
8. 240 -. 047221  
8. 260 -. 041464  
8. 280 -. 030482  
8. 300 -. 016726  
8. 320 -. 002151  
8. 340 -. 012281  
8. 360 -. 026120  
8. 380 -. 038937  
8. 400 -. 050206  
8. 420 -. 059391  
8. 440 -. 065832  
8. 460 -. 069106  
8. 480 -. 069634  
8. 500 -. 068226  
8. 520 -. 065437  
8. 540 -. 061659  
8. 560 -. 057332  
8. 580 -. 052974  
8. 600 -. 048882  
8. 620 -. 044919  
8. 640 -. 040766  
8. 660 -. 036397  
8. 680 -. 032383  
8. 700 -. 029286  
8. 720 -. 027104  
8. 740 -. 025578  
8. 760 -. 024487

Page 7

fEpac2

8. 780 -. 023917  
8. 800 -. 024184  
8. 820 -. 025547  
8. 840 -. 027978  
8. 860 -. 030989  
8. 880 -. 033525  
8. 900 -. 033854  
8. 920 -. 030136  
8. 940 -. 021444  
8. 960 -. 068012  
8. 980 -. 009233  
9. 000 -. 038598  
9. 020 -. 047501  
9. 040 -. 062492  
9. 060 -. 070053  
9. 080 -. 069003  
9. 100 -. 061165  
9. 120 -. 049738  
9. 140 -. 038102  
9. 160 -. 028937  
9. 180 -. 022987  
9. 200 -. 019277  
9. 220 -. 016447  
9. 240 -. 012993  
9. 260 -. 007959  
9. 280 -. 001860  
9. 300 -. 003670  
9. 320 -. 006699  
9. 340 -. 006298  
9. 360 -. 002983  
9. 380 -. 002396  
9. 400 -. 009408  
9. 420 -. 017898  
9. 440 -. 027166  
9. 460 -. 035039  
9. 480 -. 038886  
9. 500 -. 038517  
9. 520 -. 036156  
9. 540 -. 034197  
9. 560 -. 033704  
9. 580 -. 034381  
9. 600 -. 035599  
9. 620 -. 036793  
9. 640 -. 037668  
9. 660 -. 038202  
9. 680 -. 037880  
9. 700 -. 035434  
9. 720 -. 029854  
9. 740 -. 021320  
9. 760 -. 010786  
9. 780 -. 000529  
9. 800 -. 011105  
9. 820 -. 019546  
9. 840 -. 025553  
9. 860 -. 039808  
9. 880 -. 032792  
9. 900 -. 033932  
9. 920 -. 032726  
9. 940 -. 029201  
9. 960 -. 025169  
9. 980 -. 023016  
10. 000 -. 024108  
10. 020 -. 028337

Page 8



fEpac2

10. 040 -. 034954  
10. 060 -. 043170  
10. 080 -. 051845  
10. 100 -. 059404  
10. 120 -. 064525  
10. 140 -. 066645  
10. 160 -. 065991  
10. 180 -. 063156  
10. 200 -. 058651  
10. 220 -. 053001  
10. 240 -. 046636  
10. 260 -. 039538  
10. 280 -. 031401  
10. 300 -. 022115  
10. 320 -. 012251  
10. 340 -. 002900  
10. 360 -. 005208  
10. 380 -. 012195  
10. 400 -. 018529  
10. 420 -. 024284  
10. 440 -. 028988  
10. 460 -. 032238  
10. 480 -. 034572  
10. 500 -. 037120  
10. 520 -. 040432  
10. 540 -. 044357  
10. 560 -. 048553  
10. 580 -. 052561  
10. 600 -. 056092  
10. 620 -. 059388  
10. 640 -. 062779  
10. 660 -. 066223  
10. 680 -. 069215  
10. 700 -. 071004  
10. 720 -. 070659  
10. 740 -. 067361  
10. 760 -. 061260  
10. 780 -. 053158  
10. 800 -. 043569  
10. 820 -. 032638  
10. 840 -. 020731  
10. 860 -. 009003  
10. 880 -. 000946  
10. 900 -. 008175  
10. 920 -. 013021  
10. 940 -. 016476  
10. 960 -. 019296  
10. 980 -. 021745  
11. 000 -. 023564  
11. 020 -. 024103  
11. 040 -. 022748  
11. 060 -. 019387  
11. 080 -. 014714  
11. 100 -. 009783  
11. 120 -. 005420  
11. 140 -. 001980  
11. 160 -. 000834  
11. 180 -. 003822  
11. 200 -. 007754  
11. 220 -. 012999  
11. 240 -. 019257  
11. 260 -. 025470  
11. 280 -. 029905

Page 9

fEpac2

11. 300 -. 030767  
11. 320 -. 027644  
11. 340 -. 021832  
11. 360 -. 014821  
11. 380 -. 007818  
11. 400 -. 001748  
11. 420 -. 003177  
11. 440 -. 006998  
11. 460 -. 009399  
11. 480 -. 009956  
11. 500 -. 008663  
11. 520 -. 005805  
11. 540 -. 001917  
11. 560 -. 002931  
11. 580 -. 007288  
11. 600 -. 010966  
11. 620 -. 013960  
11. 640 -. 016191  
11. 660 -. 017378  
11. 680 -. 017410  
11. 700 -. 016780  
11. 720 -. 016178  
11. 740 -. 015760  
11. 760 -. 015157  
11. 780 -. 014024  
11. 800 -. 012227  
11. 820 -. 009634  
11. 840 -. 006138  
11. 860 -. 001774  
11. 880 -. 003418  
11. 900 -. 009325  
11. 920 -. 015759  
11. 940 -. 022630  
11. 960 -. 036843  
11. 980 -. 037248  
12. 000 -. 044649  
12. 020 -. 051778  
12. 040 -. 068054  
12. 060 -. 062517  
12. 080 -. 064429  
12. 100 -. 063478  
12. 120 -. 059700  
12. 140 -. 053513  
12. 160 -. 045651  
12. 180 -. 037124  
12. 200 -. 028915  
12. 220 -. 021769  
12. 240 -. 016173  
12. 260 -. 012267  
12. 280 -. 009767  
12. 300 -. 007983  
12. 320 -. 006060  
12. 340 -. 003396  
12. 360 -. 000099  
12. 380 -. 004378  
12. 400 -. 009795  
12. 420 -. 016721  
12. 440 -. 024865  
12. 460 -. 033053  
12. 480 -. 039431  
12. 500 -. 042691  
12. 520 -. 043062  
12. 540 -. 041738

Page 10

fEpac2

12. 560 . 039781  
12. 580 . 037728  
12. 600 . 036002  
12. 620 . 035172  
12. 640 . 035580  
12. 660 . 036997  
12. 680 . 038804  
12. 700 . 040326  
12. 720 . 040822  
12. 740 . 039689  
12. 760 . 036879  
12. 780 . 039848  
12. 800 . 028258  
12. 820 . 023408  
12. 840 . 018408  
12. 860 . 013118  
12. 880 . 007291  
12. 900 . 000900  
12. 920 . 005786  
12. 940 . 012316  
12. 960 . 018155  
12. 980 . 022829  
13. 000 . 026002  
13. 020 . 027658  
13. 040 . 028024  
13. 060 . 027319  
13. 080 . 025844  
13. 100 . 024068  
13. 120 . 022708  
13. 140 . 022695  
13. 160 . 024658  
13. 180 . 028533  
13. 200 . 033628  
13. 220 . 038979  
13. 240 . 043713  
13. 260 . 046886  
13. 280 . 047481  
13. 300 . 045007  
13. 320 . 039770  
13. 340 . 032767  
13. 360 . 025336  
13. 380 . 018681  
13. 400 . 013604  
13. 420 . 010242  
13. 440 . 008171  
13. 460 . 006882  
13. 480 . 005986  
13. 500 . 005221  
13. 520 . 004453  
13. 540 . 003595  
13. 560 . 002693  
13. 580 . 002055  
13. 600 . 001968  
13. 620 . 002374  
13. 640 . 002748  
13. 660 . 002332  
13. 680 . 000579  
13. 700 . 002650  
13. 720 . 006997  
13. 740 . 011713  
13. 760 . 016119  
13. 780 . 019953  
13. 800 . 023290

Page 11

fEpac2

13. 820 . 026155  
13. 840 . 028456  
13. 860 . 030207  
13. 880 . 031486  
13. 900 . 032383  
13. 920 . 033014  
13. 940 . 033514  
13. 960 . 033971  
13. 980 . 034360  
14. 000 . 034656  
14. 020 . 034786  
14. 040 . 034636  
14. 060 . 034200  
14. 080 . 033549  
14. 100 . 032944  
14. 120 . 032818  
14. 140 . 033341  
14. 160 . 034052  
14. 180 . 034132  
14. 200 . 033043  
14. 220 . 030750  
14. 240 . 027445  
14. 260 . 023200  
14. 280 . 017976  
14. 300 . 011898  
14. 320 . 005422  
14. 340 . 000853  
14. 360 . 006443  
14. 380 . 011153  
14. 400 . 015162  
14. 420 . 018830  
14. 440 . 022326  
14. 460 . 035456  
14. 480 . 037798  
14. 500 . 028954  
14. 520 . 028959  
14. 540 . 028571  
14. 560 . 028469  
14. 580 . 029092  
14. 600 . 030359  
14. 620 . 031939  
14. 640 . 033445  
14. 660 . 034435  
14. 680 . 034658  
14. 700 . 034312  
14. 720 . 033855  
14. 740 . 033582  
14. 760 . 033458  
14. 780 . 033200  
14. 800 . 032482  
14. 820 . 031185  
14. 840 . 029392  
14. 860 . 027250  
14. 880 . 024958  
14. 900 . 022659  
14. 920 . 020403  
14. 940 . 018286  
14. 960 . 016457  
14. 980 . 014974  
15. 000 . 013569  
15. 020 . 011747  
15. 040 . 009139  
15. 060 . 005643

Page 12

fEpac2

15.080 -.001499  
15.100 .002833  
15.120 .006939  
15.140 .010519  
15.160 .013403  
15.180 .015520  
15.200 .016877  
15.220 .017478  
15.240 .017379  
15.260 .016923  
15.280 .016707  
15.300 .017177  
15.320 .018235  
15.340 .019307  
15.360 .019761  
15.380 .019342  
15.400 .018210  
15.420 .016657  
15.440 .014980  
15.460 .013463  
15.480 .012211  
15.500 .011043  
15.520 .009688  
15.540 .008113  
15.560 .006549  
15.580 .005197  
15.600 .004065  
15.620 .002905  
15.640 .001326  
15.660 -.000896  
15.680 .0033618  
15.700 .006393  
15.720 .008619  
15.740 .009808  
15.760 .009944  
15.780 .009436  
15.800 .008875  
15.820 .008884  
15.840 .009746  
15.860 .011232  
15.880 .012913  
15.900 .014419  
15.920 .015448  
15.940 .015859  
15.960 .015784  
15.980 .015510  
16.000 .015331  
16.020 .015360  
16.040 .015371  
16.060 .015086  
16.080 .014467  
16.100 .013543  
16.120 .012297  
16.140 .010799  
16.160 .009144  
16.180 .007238  
16.200 .004785  
16.220 .001674  
16.240 .001753  
16.260 .005027  
16.280 .007993  
16.300 .010840  
16.320 .013832

Page 13

fEpac2

16.340 .0177104  
16.360 .020541  
16.380 .023794  
16.400 .026565  
16.420 .028790  
16.440 .030561  
16.460 .032078  
16.480 .033499  
16.500 .034718  
16.520 .035384  
16.540 .035135  
16.560 .033884  
16.580 .031914  
16.600 .029746  
16.620 .027915  
16.640 .026791  
16.660 .026312  
16.680 .025948  
16.700 .025153  
16.720 .023622  
16.740 .021418  
16.760 .018851  
16.780 .016084  
16.800 .013101  
16.820 .009905  
16.840 .006681  
16.860 .003761  
16.880 .001451  
16.900 .000201  
16.920 .001595  
16.940 .003190  
16.960 .005066  
16.980 .006988  
17.000 .008678  
17.020 .010141  
17.040 .011737  
17.060 .013836  
17.080 .016562  
17.100 .019744  
17.120 .022967  
17.140 .025687  
17.160 .027505  
17.180 .028466  
17.200 .028975  
17.220 .029474  
17.240 .030241  
17.260 .031264  
17.280 .032237  
17.300 .032864  
17.320 .033039  
17.340 .032628  
17.360 .031421  
17.380 .029419  
17.400 .026965  
17.420 .024629  
17.440 .022867  
17.460 .021552  
17.480 .021582  
17.500 .021301  
17.520 .020576  
17.540 .019015  
17.560 .016533  
17.580 .013441

Page 14

fEpac2

17. 600 -. 010184  
17. 620 -. 007047  
17. 640 -. 004110  
17. 660 -. 001342  
17. 680 001253  
17. 700 003604  
17. 720 005638  
17. 740 007333  
17. 760 008713  
17. 780 009793  
17. 800 010595  
17. 820 011229  
17. 840 011925  
17. 860 012852  
17. 880 014097  
17. 900 015369  
17. 920 016333  
17. 940 016850  
17. 960 016961  
17. 980 016679  
18. 000 015994  
18. 020 014942  
18. 040 013568  
18. 060 011991  
18. 080 010434  
18. 100 009153  
18. 120 008399  
18. 140 008343  
18. 160 008955  
18. 180 009989  
18. 200 011125  
18. 220 011974  
18. 240 012164  
18. 260 011611  
18. 280 010520  
18. 300 009214  
18. 320 008005  
18. 340 007026  
18. 360 006163  
18. 380 005211  
18. 400 004029  
18. 420 002639  
18. 440 001248  
18. 460 000148  
18. 480 -. 000450  
18. 500 -. 000501  
18. 520 -. 000119  
18. 540 000526  
18. 560 001249  
18. 580 001784  
18. 600 001879  
18. 620 001333  
18. 640 000047  
18. 660 -. 001866  
18. 680 -. 004018  
18. 700 -. 005859  
18. 720 -. 007150  
18. 740 -. 008043  
18. 760 -. 008772  
18. 780 -. 009462  
18. 800 -. 009996  
18. 820 -. 010105  
18. 840 -. 009644

Page 15

fEpac2

18. 860 -. 008674  
18. 880 -. 007330  
18. 900 -. 005746  
18. 920 003997  
18. 940 002129  
18. 960 000254  
18. 980 001544  
19. 000 003234  
19. 020 004706  
19. 040 005852  
19. 060 006718  
19. 080 007461  
19. 100 008296  
19. 120 009395  
19. 140 010846  
19. 160 012614  
19. 180 014412  
19. 200 015914  
19. 220 016924  
19. 240 017358  
19. 260 017204  
19. 280 016367  
19. 300 014722  
19. 320 012226  
19. 340 008938  
19. 360 005092  
19. 380 001133  
19. 400 002417  
19. 420 005137  
19. 440 006934  
19. 460 008103  
19. 480 009100  
19. 500 010284  
19. 520 011739  
19. 540 013306  
19. 560 014837  
19. 580 016366  
19. 600 017905  
19. 620 019348  
19. 640 020516  
19. 660 021290  
19. 680 021794  
19. 700 022110  
19. 720 022145  
19. 740 021843  
19. 760 021154  
19. 780 019997  
19. 800 018293  
19. 820 016094  
19. 840 013676  
19. 860 011358  
19. 880 009246  
19. 900 007208  
19. 920 005029  
19. 940 002560  
19. 960 001140  
19. 980 002822  
20. 000 005142  
20. 020 006795  
20. 040 007736  
20. 060 008119  
20. 080 008087  
20. 100 007846

Page 16

fEpac2

20. 120 . 007587  
20. 140 . 007339  
20. 160 . 007030  
20. 180 . 006485  
20. 200 . 005551  
20. 220 . 004223  
20. 240 . 002672  
20. 260 . 001119  
20. 280 . 000351  
20. 300 . 001657  
20. 320 . 002678  
20. 340 . 003422  
20. 360 . 004005  
20. 380 . 004477  
20. 400 . 004817  
20. 420 . 004957  
20. 440 . 004873  
20. 460 . 004680  
20. 480 . 004556  
20. 500 . 004615  
20. 520 . 004814  
20. 540 . 004922  
20. 560 . 004767  
20. 580 . 004395  
20. 600 . 003825  
20. 620 . 003022  
20. 640 . 001960  
20. 660 . 000549  
20. 680 . 001217  
20. 700 . 003218  
20. 720 . 005276  
20. 740 . 007207  
20. 760 . 008988  
20. 780 . 010758  
20. 800 . 012651  
20. 820 . 014646  
20. 840 . 016574  
20. 860 . 018205  
20. 880 . 019378  
20. 900 . 020081  
20. 920 . 020430  
20. 940 . 020588  
20. 960 . 020672  
20. 980 . 020708  
21. 000 . 020622  
21. 020 . 020299  
21. 040 . 019661  
21. 060 . 018677  
21. 080 . 017408  
21. 100 . 016086  
21. 120 . 014931  
21. 140 . 013943  
21. 160 . 012971  
21. 180 . 011824  
21. 200 . 010365  
21. 220 . 008610  
21. 240 . 006720  
21. 260 . 004903  
21. 280 . 003290  
21. 300 . 001919  
21. 320 . 000851  
21. 340 . 000172  
21. 360 . 000060

Page 17

fEpac2

21. 380 . 000163  
21. 400 . 000753  
21. 420 . 001574  
21. 440 . 002449  
21. 460 . 003138  
21. 480 . 003443  
21. 500 . 003221  
21. 520 . 002339  
21. 540 . 000846  
21. 560 . 000994  
21. 580 . 002850  
21. 600 . 004377  
21. 620 . 005377  
21. 640 . 005797  
21. 660 . 005670  
21. 680 . 005187  
21. 700 . 004599  
21. 720 . 004125  
21. 740 . 003972  
21. 760 . 004217  
21. 780 . 004810  
21. 800 . 005706  
21. 820 . 006771  
21. 840 . 007846  
21. 860 . 008882  
21. 880 . 009838  
21. 900 . 010591  
21. 920 . 011051  
21. 940 . 011328  
21. 960 . 011658  
21. 980 . 012166  
22. 000 . 012785  
22. 020 . 013399  
22. 040 . 013943  
22. 060 . 014419  
22. 080 . 014859  
22. 100 . 015240  
22. 120 . 015443  
22. 140 . 015263  
22. 160 . 014608  
22. 180 . 013536  
22. 200 . 012208  
22. 220 . 010987  
22. 240 . 010252  
22. 260 . 010107  
22. 280 . 010444  
22. 300 . 011061  
22. 320 . 011679  
22. 340 . 012110  
22. 360 . 012322  
22. 380 . 012256  
22. 400 . 011895  
22. 420 . 011353  
22. 440 . 010700  
22. 460 . 009867  
22. 480 . 008684  
22. 500 . 007105  
22. 520 . 005340  
22. 540 . 003598  
22. 560 . 001989  
22. 580 . 000624  
22. 600 . 000452  
22. 620 . 001295

Page 18

fEpac2

22. 640 . 002046  
22. 660 . 002860  
22. 680 . 003767  
22. 700 . 004782  
22. 720 . 005889  
22. 740 . 006905  
22. 760 . 007630  
22. 780 . 007966  
22. 800 . 007998  
22. 820 . 007997  
22. 840 . 008195  
22. 860 . 008552  
22. 880 . 008817  
22. 900 . 008736  
22. 920 . 008256  
22. 940 . 007587  
22. 960 . 006960  
22. 980 . 006435  
23. 000 . 005967  
23. 020 . 005594  
23. 040 . 005432  
23. 060 . 005482  
23. 080 . 005524  
23. 100 . 005347  
23. 120 . 005020  
23. 140 . 004684  
23. 160 . 004338  
23. 180 . 003989  
23. 200 . 003683  
23. 220 . 003413  
23. 240 . 003076  
23. 260 . 002527  
23. 280 . 001759  
23. 300 . 000915  
23. 320 . 000139  
23. 340 . 000513  
23. 360 . 001036  
23. 380 . 001440  
23. 400 . 001804  
23. 420 . 002237  
23. 440 . 002851  
23. 460 . 003712  
23. 480 . 004751  
23. 500 . 005859  
23. 520 . 006923  
23. 540 . 007793  
23. 560 . 008392  
23. 580 . 008774  
23. 600 . 008901  
23. 620 . 008588  
23. 640 . 007762  
23. 660 . 006531  
23. 680 . 005139  
23. 700 . 003758  
23. 720 . 002380  
23. 740 . 000959  
23. 760 . 000574  
23. 780 . 002214  
23. 800 . 003877  
23. 820 . 005311  
23. 840 . 006223  
23. 860 . 006544  
23. 880 . 006516

fEpac2

23. 900 . 006380  
23. 920 . 006063  
23. 940 . 005507  
23. 960 . 005013  
23. 980 . 005076  
24. 000 . 005886  
24. 020 . 007184  
24. 040 . 008657  
24. 060 . 010065  
24. 080 . 011215  
24. 100 . 012111  
24. 120 . 012910  
24. 140 . 013720  
24. 160 . 014426  
24. 180 . 014663  
24. 200 . 014188  
24. 220 . 013095  
24. 240 . 011661  
24. 260 . 010176  
24. 280 . 008838  
24. 300 . 007728  
24. 320 . 006738  
24. 340 . 005682  
24. 360 . 004455  
24. 380 . 003012  
24. 400 . 001353  
24. 420 . 000411  
24. 440 . 001965  
24. 460 . 003019  
24. 480 . 003578  
24. 500 . 003984  
24. 520 . 004650  
24. 540 . 005610  
24. 560 . 006709  
24. 580 . 007956  
24. 600 . 009314  
24. 620 . 010495  
24. 640 . 011228  
24. 660 . 011494  
24. 680 . 011387  
24. 700 . 010977  
24. 720 . 010419  
24. 740 . 009860  
24. 760 . 009286  
24. 780 . 008650  
24. 800 . 007960  
24. 820 . 007222  
24. 840 . 006383  
24. 860 . 005416  
24. 880 . 004383  
24. 900 . 003283  
24. 920 . 002093  
24. 940 . 000888  
24. 960 . 000297  
24. 980 . 001440  
25. 000 . 002424  
25. 020 . 003146  
25. 040 . 003631  
25. 060 . 003981  
25. 080 . 004245  
25. 100 . 004507  
25. 120 . 004932  
25. 140 . 005608

fEpac2

25.160 .006471  
25.180 .007386  
25.200 .008262  
25.220 .009058  
25.240 .009781  
25.260 .010423  
25.280 .010931  
25.300 .011228  
25.320 .011233  
25.340 .010916  
25.360 .010345  
25.380 .009589  
25.400 .008679  
25.420 .007674  
25.440 .006596  
25.460 .005434  
25.480 .004152  
25.500 .002739  
25.520 .001320  
25.540 .000078  
25.560 -.000873  
25.580 -.001591  
25.600 -.002139  
25.620 -.002531  
25.640 -.002849  
25.660 -.003186  
25.680 -.003683  
25.700 -.004480  
25.720 -.005569  
25.740 -.006813  
25.760 -.008028  
25.780 -.009100  
25.800 -.010031  
25.820 -.010804  
25.840 -.011330  
25.860 -.011612  
25.880 -.011736  
25.900 -.011748  
25.920 -.011658  
25.940 -.011478  
25.960 -.011229  
25.980 -.010926  
26.000 -.010556  
26.020 -.010109  
26.040 -.009563  
26.060 -.008941  
26.080 -.008307  
26.100 -.007633  
26.120 -.006796  
26.140 -.005733  
26.160 -.004550  
26.180 -.003401  
26.200 -.002291  
26.220 -.001189  
26.240 -.000143  
26.260 .000813  
26.280 .001671  
26.300 .002437  
26.320 .003172  
26.340 .003918  
26.360 .004650  
26.380 .005351  
26.400 .005900

Page 21

fEpac2

26.420 .006049  
26.440 .005619  
26.460 .004637  
26.480 .003383  
26.500 .002241  
26.520 .001401  
26.540 .000801  
26.560 .000294  
26.580 .000222  
26.600 -.000729  
26.620 -.001117  
26.640 -.001247  
26.660 -.001011  
26.680 -.000488  
26.700 .000139  
26.720 .000687  
26.740 .000967  
26.760 .000936  
26.780 .000719  
26.800 .000506  
26.820 .000405  
26.840 .000445  
26.860 .000561  
26.880 .000661  
26.900 .000722  
26.920 .000666  
26.940 .000459  
26.960 .000234  
26.980 .000131  
27.000 .000155  
27.020 .000232  
27.040 .000305  
27.060 .000385  
27.080 .000495  
27.100 .000625  
27.120 .000793  
27.140 .001047  
27.160 .001420  
27.180 .001897  
27.200 .002520  
27.220 .003277  
27.240 .004020  
27.260 .004677  
27.280 .005271  
27.300 .005831  
27.320 .006392  
27.340 .006980  
27.360 .007577  
27.380 .008090  
27.400 .008384  
27.420 .008435  
27.440 .008355  
27.460 .008273  
27.480 .008235  
27.500 .008211  
27.520 .008141  
27.540 .008005  
27.560 .007814  
27.580 .007599  
27.600 .007408  
27.620 .007254  
27.640 .007161  
27.660 .007074

Page 22

fEpac2

27. 680 . 006872  
27. 700 . 006597  
27. 720 . 006329  
27. 740 . 006060  
27. 760 . 005759  
27. 780 . 005347  
27. 800 . 004768  
27. 820 . 004001  
27. 840 . 003042  
27. 860 . 001949  
27. 880 . 000779  
27. 900 . 000439  
27. 920 . 001662  
27. 940 . 002846  
27. 960 . 003952  
27. 980 . 004925  
28. 000 . 005693  
28. 020 . 006278  
28. 040 . 006801  
28. 060 . 007382  
28. 080 . 008149  
28. 100 . 009152  
28. 120 . 010273  
28. 140 . 011376  
28. 160 . 012370  
28. 180 . 013163  
28. 200 . 013696  
28. 220 . 014008  
28. 240 . 014178  
28. 260 . 014281  
28. 280 . 014370  
28. 300 . 014427  
28. 320 . 014453  
28. 340 . 014490  
28. 360 . 014539  
28. 380 . 014512  
28. 400 . 014270  
28. 420 . 013767  
28. 440 . 013036  
28. 460 . 012088  
28. 480 . 010908  
28. 500 . 009489  
28. 520 . 007886  
28. 540 . 006181  
28. 560 . 004443  
28. 580 . 002757  
28. 600 . 001160  
28. 620 . 000388  
28. 640 . 001947  
28. 660 . 003460  
28. 680 . 004737  
28. 700 . 005690  
28. 720 . 006379  
28. 740 . 006903  
28. 760 . 007359  
28. 780 . 007797  
28. 800 . 008185  
28. 820 . 008478  
28. 840 . 008734  
28. 860 . 009012  
28. 880 . 009274  
28. 900 . 009444  
28. 920 . 009415

Page 23

fEpac2

28. 940 . 009105  
28. 960 . 008549  
28. 980 . 007868  
29. 000 . 007203  
29. 020 . 006626  
29. 040 . 006098  
29. 060 . 005532  
29. 080 . 004790  
29. 100 . 003779  
29. 120 . 002535  
29. 140 . 001206  
29. 160 . 000006  
29. 180 . 000986  
29. 200 . 001704  
29. 220 . 002255  
29. 240 . 002821  
29. 260 . 003467  
29. 280 . 004117  
29. 300 . 004677  
29. 320 . 005117  
29. 340 . 005420  
29. 360 . 005566  
29. 380 . 005576  
29. 400 . 005453  
29. 420 . 005195  
29. 440 . 004799  
29. 460 . 004260  
29. 480 . 003596  
29. 500 . 002818  
29. 520 . 001912  
29. 540 . 000919  
29. 560 . 000088  
29. 580 . 001082  
29. 600 . 002086  
29. 620 . 003005  
29. 640 . 003795  
29. 660 . 004338  
29. 680 . 004605  
29. 700 . 004732  
29. 720 . 004899  
29. 740 . 005146  
29. 760 . 005394  
29. 780 . 005557  
29. 800 . 005644  
29. 820 . 005712  
29. 840 . 005804  
29. 860 . 005937  
29. 880 . 006117  
29. 900 . 006349  
29. 920 . 006634  
29. 940 . 006897  
29. 960 . 007059  
29. 980 . 007118  
30. 000 . 007045  
30. 020 . 006800  
30. 040 . 006493  
30. 060 . 006222  
30. 080 . 005982  
30. 100 . 005672  
30. 120 . 005230  
30. 140 . 004606  
30. 160 . 003818  
30. 180 . 002857

Page 24



30. 200 . 001742  
30. 220 . 000568  
30. 240 . 000609  
30. 260 . 001732  
30. 280 . 002732  
30. 300 . 003537  
30. 320 . 004056  
30. 340 . 004278  
30. 360 . 004288  
30. 380 . 004178  
30. 400 . 003983  
30. 420 . 003714  
30. 440 . 003404  
30. 460 . 003057  
30. 480 . 002661  
30. 500 . 002230  
30. 520 . 001813  
30. 540 . 001456  
30. 560 . 001217  
30. 580 . 001194  
30. 600 . 001375  
30. 620 . 001645  
30. 640 . 001892  
30. 660 . 002109  
30. 680 . 002372  
30. 700 . 002627  
30. 720 . 002756  
30. 740 . 002764  
30. 760 . 002729  
30. 780 . 002726  
30. 800 . 002852  
30. 820 . 003125  
30. 840 . 003448  
30. 860 . 003734  
30. 880 . 003897  
30. 900 . 003862  
30. 920 . 003675  
30. 940 . 003427  
30. 960 . 003185  
30. 980 . 002946  
31. 000 . 002666  
31. 020 . 002351  
31. 040 . 002056  
31. 060 . 001859  
31. 080 . 001856  
31. 100 . 002039  
31. 120 . 002333  
31. 140 . 002686  
31. 160 . 003028  
31. 180 . 003300  
31. 200 . 003429  
31. 220 . 003359  
31. 240 . 003134  
31. 260 . 002833  
31. 280 . 002527  
31. 300 . 002257  
31. 320 . 002024  
31. 340 . 001871  
31. 360 . 001852  
31. 380 . 001988  
31. 400 . 002282  
31. 420 . 002738  
31. 440 . 003344

31. 460 . 004075  
31. 480 . 004867  
31. 500 . 005582  
31. 520 . 006077  
31. 540 . 006275  
31. 560 . 006269  
31. 580 . 006301  
31. 600 . 006535  
31. 620 . 006976  
31. 640 . 007512  
31. 660 . 007944  
31. 680 . 008132  
31. 700 . 008013  
31. 720 . 007717  
31. 740 . 007384  
31. 760 . 007110  
31. 780 . 006854  
31. 800 . 006536  
31. 820 . 006120  
31. 840 . 005600  
31. 860 . 005045  
31. 880 . 004560  
31. 900 . 004161  
31. 920 . 003763  
31. 940 . 003290  
31. 960 . 002701  
31. 980 . 002010  
32. 000 . 001247  
32. 020 . 000388  
32. 040 . 000579  
32. 060 . 001631  
32. 080 . 002678  
32. 100 . 003660  
32. 120 . 004603  
32. 140 . 005530  
32. 160 . 006434  
32. 180 . 007282  
32. 200 . 008122  
32. 220 . 009022  
32. 240 . 009930  
32. 260 . 010764  
32. 280 . 011515  
32. 300 . 012213  
32. 320 . 012881  
32. 340 . 013554  
32. 360 . 014211  
32. 380 . 014760  
32. 400 . 015149  
32. 420 . 015376  
32. 440 . 015478  
32. 460 . 015509  
32. 480 . 015546  
32. 500 . 015656  
32. 520 . 015838  
32. 540 . 016037  
32. 560 . 016158  
32. 580 . 016067  
32. 600 . 015701  
32. 620 . 015123  
32. 640 . 014407  
32. 660 . 013555  
32. 680 . 012555  
32. 700 . 011455

32. 720 . 010351  
 32. 740 . 099291  
 32. 760 . 088258  
 32. 780 . 007233  
 32. 800 . 006296  
 32. 820 . 005614  
 32. 840 . 005257  
 32. 860 . 005143  
 32. 880 . 005144  
 32. 900 . 005109  
 32. 920 . 004905  
 32. 940 . 004520  
 32. 960 . 004039  
 33. 000 . 003496  
 33. 020 . 002888  
 33. 040 . 002226  
 33. 060 . 001509  
 33. 080 . 000717  
 33. 100 . 001151  
 33. 120 . 002181  
 33. 140 . 003232  
 33. 160 . 004332  
 33. 180 . 005499  
 33. 200 . 006633  
 33. 220 . 007570  
 33. 240 . 008235  
 33. 260 . 008636  
 33. 280 . 008852  
 33. 300 . 009028  
 33. 320 . 009280  
 33. 340 . 009676  
 33. 360 . 010214  
 33. 380 . 010805  
 33. 400 . 011355  
 33. 420 . 011815  
 33. 440 . 012174  
 33. 460 . 012456  
 33. 480 . 012679  
 33. 500 . 012803  
 33. 520 . 012712  
 33. 540 . 012314  
 33. 560 . 011648  
 33. 580 . 010890  
 33. 600 . 010147  
 33. 620 . 009357  
 33. 640 . 008483  
 33. 660 . 007564  
 33. 680 . 006590  
 33. 700 . 005483  
 33. 720 . 004195  
 33. 740 . 002793  
 33. 760 . 001364  
 33. 780 . 000055  
 33. 800 . 001419  
 33. 820 . 002687  
 33. 840 . 003838  
 33. 860 . 004847  
 33. 880 . 005727  
 33. 900 . 006493  
 33. 920 . 007110  
 33. 940 . 007580  
 33. 960 . 007928

33. 980 . 008138  
 34. 000 . 008196  
 34. 020 . 008126  
 34. 040 . 007965  
 34. 060 . 007729  
 34. 080 . 007393  
 34. 100 . 006929  
 34. 120 . 006284  
 34. 140 . 005430  
 34. 160 . 004377  
 34. 180 . 003089  
 34. 200 . 001641  
 34. 220 . 000182  
 34. 240 . 001221  
 34. 260 . 002493  
 34. 280 . 003605  
 34. 300 . 004642  
 34. 320 . 005670  
 34. 340 . 006705  
 34. 360 . 007704  
 34. 380 . 008585  
 34. 400 . 009272  
 34. 420 . 009740  
 34. 440 . 010043  
 34. 460 . 010258  
 34. 480 . 010429  
 34. 500 . 010584  
 34. 520 . 010722  
 34. 540 . 010788  
 34. 560 . 010704  
 34. 580 . 010493  
 34. 600 . 010234  
 34. 620 . 009960  
 34. 640 . 009669  
 34. 660 . 009347  
 34. 680 . 008958  
 34. 700 . 008379  
 34. 720 . 007560  
 34. 740 . 006555  
 34. 760 . 005433  
 34. 780 . 004309  
 34. 800 . 003245  
 34. 820 . 002229  
 34. 840 . 001280  
 34. 860 . 000396  
 34. 880 . 000483  
 34. 900 . 001390  
 34. 920 . 002317  
 34. 940 . 003249  
 34. 960 . 004163  
 34. 980 . 005038  
 35. 000 . 005909  
 35. 020 . 006852  
 35. 040 . 007908  
 35. 060 . 009066  
 35. 080 . 010295  
 35. 100 . 011292  
 35. 120 . 012214  
 35. 140 . 012979  
 35. 160 . 013574  
 35. 180 . 013934  
 35. 200 . 014141  
 35. 220 . 014251

fEpac2

35. 240 . 014196  
 35. 260 . 014002  
 35. 280 . 013696  
 35. 300 . 013252  
 35. 320 . 012659  
 35. 340 . 011913  
 35. 360 . 011077  
 35. 380 . 010278  
 35. 400 . 009600  
 35. 420 . 009043  
 35. 440 . 008529  
 35. 460 . 007927  
 35. 480 . 007076  
 35. 500 . 005862  
 35. 520 . 004345  
 35. 540 . 002743  
 35. 560 . 001265  
 35. 580 . 000025  
 35. 600 . 001175  
 35. 620 . 002280  
 35. 640 . 003419  
 35. 660 . 004629  
 35. 680 . 005885  
 35. 700 . 007057  
 35. 720 . 007997  
 35. 740 . 008677  
 35. 760 . 009162  
 35. 780 . 009559  
 35. 800 . 009934  
 35. 820 . 010237  
 35. 840 . 010396  
 35. 860 . 010399  
 35. 880 . 010287  
 35. 900 . 010140  
 35. 920 . 010085  
 35. 940 . 010215  
 35. 960 . 010520  
 35. 980 . 010868  
 36. 000 . 011091  
 36. 020 . 011126  
 36. 040 . 011001  
 36. 060 . 010814  
 36. 080 . 010687  
 36. 100 . 010620  
 36. 120 . 010572  
 36. 140 . 010531  
 36. 160 . 010418  
 36. 180 . 010180  
 36. 200 . 009840  
 36. 220 . 009488  
 36. 240 . 009208  
 36. 260 . 008969  
 36. 280 . 008692  
 36. 300 . 008328  
 36. 320 . 007889  
 36. 340 . 007359  
 36. 360 . 006657  
 36. 380 . 005816  
 36. 400 . 004956  
 36. 420 . 004184  
 36. 440 . 003505  
 36. 460 . 002860  
 36. 480 . 002173

fEpac2

36. 500 . 001413  
 36. 520 . 000638  
 36. 540 . 000100  
 36. 560 . 000796  
 36. 580 . 001449  
 36. 600 . 002103  
 36. 620 . 002808  
 36. 640 . 003598  
 36. 660 . 004470  
 36. 680 . 005357  
 36. 700 . 006239  
 36. 720 . 007088  
 36. 740 . 007854  
 36. 760 . 008552  
 36. 780 . 009235  
 36. 800 . 009917  
 36. 820 . 010538  
 36. 840 . 011032  
 36. 860 . 011390  
 36. 880 . 011651  
 36. 900 . 011844  
 36. 920 . 011943  
 36. 940 . 011896  
 36. 960 . 011697  
 36. 980 . 011406  
 37. 000 . 011093  
 37. 020 . 010761  
 37. 040 . 010359  
 37. 060 . 009850  
 37. 080 . 009213  
 37. 100 . 008504  
 37. 120 . 007824  
 37. 140 . 007232  
 37. 160 . 006690  
 37. 180 . 006118  
 37. 200 . 005509  
 37. 220 . 004900  
 37. 240 . 004277  
 37. 260 . 003649  
 37. 280 . 003038  
 37. 300 . 002441  
 37. 320 . 001829  
 37. 340 . 001169  
 37. 360 . 000443  
 37. 380 . 000326  
 37. 400 . 001100  
 37. 420 . 001868  
 37. 440 . 002587  
 37. 460 . 003175  
 37. 480 . 003578  
 37. 500 . 003793  
 37. 520 . 003872  
 37. 540 . 003879  
 37. 560 . 003869  
 37. 580 . 003880  
 37. 600 . 003874  
 37. 620 . 003805  
 37. 640 . 003682  
 37. 660 . 003531  
 37. 680 . 003388  
 37. 700 . 003239  
 37. 720 . 003073  
 37. 740 . 002913

fEpac2

37. 760 -. 002732  
37. 780 -. 002489  
37. 800 -. 002161  
37. 820 -. 001775  
37. 840 -. 001380  
37. 860 -. 000991  
37. 880 -. 000618  
37. 900 -. 000246  
37. 920 -. 000158  
37. 940 -. 000594  
37. 960 -. 001029  
37. 980 -. 001442  
38. 000 -. 001809  
38. 020 -. 002114  
38. 040 -. 002353  
38. 060 -. 002531  
38. 080 -. 002661  
38. 100 -. 002771  
38. 120 -. 002877  
38. 140 -. 002970  
38. 160 -. 003018  
38. 180 -. 002983  
38. 200 -. 002865  
38. 220 -. 002681  
38. 240 -. 002434  
38. 260 -. 002133  
38. 280 -. 001795  
38. 300 -. 001451  
38. 320 -. 001120  
38. 340 -. 000810  
38. 360 -. 000524  
38. 380 -. 000243  
38. 400 -. 000045  
38. 420 -. 000337  
38. 440 -. 000627  
38. 460 -. 000912  
38. 480 -. 001198  
38. 500 -. 001485  
38. 520 -. 001770  
38. 540 -. 002054  
38. 560 -. 002335  
38. 580 -. 002622  
38. 600 -. 002921  
38. 620 -. 003216  
38. 640 -. 003503  
38. 660 -. 003778  
38. 680 -. 004029  
38. 700 -. 004229  
38. 720 -. 004357  
38. 740 -. 004414  
38. 760 -. 004414  
38. 780 -. 004365  
38. 800 -. 004280  
38. 820 -. 004165  
38. 840 -. 004023  
38. 860 -. 003860  
38. 880 -. 003678  
38. 900 -. 003480  
38. 920 -. 003269  
38. 940 -. 003045  
38. 960 -. 002808  
38. 980 -. 002568  
39. 000 -. 002327

Page 31

fEpac2

39. 020 -. 002088  
39. 040 -. 001847  
39. 060 -. 001604  
39. 080 -. 001365  
39. 100 -. 001132  
39. 120 -. 000904  
39. 140 -. 000683  
39. 160 -. 000467  
39. 180 -. 000256  
39. 200 -. 000048  
39. 220 -. 000156  
39. 240 -. 000352  
39. 260 -. 000536  
39. 280 -. 000714  
39. 300 -. 000879  
39. 320 -. 001034  
39. 340 -. 001176  
39. 360 -. 001306  
39. 380 -. 001421  
39. 400 -. 001521  
39. 420 -. 001605  
39. 440 -. 001673  
39. 460 -. 001726  
39. 480 -. 001764  
39. 500 -. 001787  
39. 520 -. 001797  
39. 540 -. 001793  
39. 560 -. 001777  
39. 580 -. 001749  
39. 600 -. 001710  
39. 620 -. 001662  
39. 640 -. 001604  
39. 660 -. 001539  
39. 680 -. 001467  
39. 700 -. 001391  
39. 720 -. 001311  
39. 740 -. 001229  
39. 760 -. 001145  
39. 780 -. 001062  
39. 800 -. 000978  
39. 820 -. 000895  
39. 840 -. 000813  
39. 860 -. 000732  
39. 880 -. 000652  
39. 900 -. 000573  
39. 920 -. 000495  
39. 940 -. 000419  
39. 960 -. 000345  
39. 980 -. 000274  
40. 000 -. 000204

Page 32

# **APPENDIX C**



**Subject:** Cover Slope Stability

**By:** N.M.

**Checked By:** B.H.

**Date:** 7/21/08

**Date:** 7/21/08

**Project Name:** Kettleman B-18

**Project No:** 08-0228

**Sheet:** 1 of 8

### CLASS I WASTE FINAL COVER STABILITY

**Objective:**


Evaluate static and seismic stability (long term condition) and temporary stability during construction of the final landfill cover for Class I waste area at Kettleman Hills Facility (KHF) Landfill Unit B-18.

**Performance Criteria:**

- Static Loading: Minimum Factor of Safety of 1.5.
- Dynamic Loading: Allowable seismic displacements up to 12 inches.
- Temporary Loading Case during Construction: Minimum Factor of Safety 1.25.

**Geometry:**

The typical cover system for Class I waste is shown in Figure 1.



**Figure 1. Typical Cover System for Class I Waste**



**Subject:** Cover Slope Stability

**By:** N.M.

**Checked By:** B.H.

**Date:** 7/21/08

**Date:** 7/21/08

**Project Name:** Kettleman B-18

**Project No:** 08-0228

**Sheet:** 2 of 8

The shear strength parameters of the cover interfaces are shown in Table 1. The site-specific values of these parameters should be verified prior to the construction of the cover.


**Table 1. Shear Strength Properties for Interfaces in Figure 1**

INTERFACE	STRENGTH PARAMETERS		
	$\gamma$ (pcf)	c (psf)	$\phi$ (degrees)
Cover Soil / Geotextile	110	100	21
Geotextile / 40-Mil HDPE	110	0	25*
40-Mil HDPE / Intermediate Soil	110	0	28
Foundation Soil / Class I Waste	110	0	31

\* Results of site-specific laboratory interface direct shear tests performed on textured geomembrane and geotextile materials to be used for Class I waste cover construction under low confining pressures (pressure due to the weight of cover soil) indicate a residual friction angle of approximately 28 degrees for this interface (see attached). A conservative value of 25 degrees, however, was used in our analyses.

**Design Theory:**

The long-term stability of the cover (stability analysis for static case) is based on the infinite slope model shown in Figure 2.



**Figure 2. Equilibrium of Loads for a Unit Length of Cover**



**Subject:** Cover Slope Stability

**By:** N.M.

**Checked By:** B.H.

**Date:** 7/21/08

**Date:** 7/21/08

**Project Name:** Kettleman B-18

**Project No:** 08-0228

**Sheet:** 3 of 8

The safety factor against sliding can be evaluated using the following equation (Huang, 1983):

$$F.S. = \frac{c}{\gamma_T H \cos^2 \beta \tan \beta} + \frac{\tan \phi}{\tan \beta}$$

If  $c = 0$ , then:  $F.S. = \frac{\tan \phi}{\tan \beta}$

For seismic case ( $k_y > 0$ ):

$$F.S. = \frac{c(L / \cos \beta) + \gamma_T LH \cos \beta \tan \phi - k_y \gamma_T LH \sin \beta \tan \phi}{\gamma_T LH \sin \beta + k_y \gamma_T LH \cos \beta}$$

Note: This analysis is conservative since the effect of finite slope length and passive resistance wedge at the toe of the slope is not included.

### **Long-Term Static Stability:**

Based on the interface and material properties shown in Table 1, for Class I waste cover the weakest interface of the cover is the Geotextile / HDPE geomembrane interface. The following presents the infinite slope stability analysis performed for the Class I waste cover.

Static Stability for Geotextile / HDPE geomembrane interface:

$c = 0$  psf,  $\phi = 25^\circ$ ,  $\beta = 16^\circ$ ,  $H = 2.5 / (\cos 16) = 2.60$  ft,  $\gamma = 110$  pcf

$$F.S. = \frac{0}{110 \cdot 2.60 \cdot \cos^2 16 \cdot \tan 16} + \frac{\tan 25}{\tan 16} = 1.63 > 1.5 \text{ o.k.}$$

### **Construction Stage/Temporary Loading (Short-Term) Static Stability:**

The stability of cover needs to be evaluated for the temporary condition during cover placement. It is assumed that the cover is placed from bottom to top (backfilling up slope). When the equipment weight is considered, the stability is evaluated for a finite length of the slope, usually the distance between two benches. The equilibrium of forces for a finite length of the slope is shown on Figure 3 (Qian, Koerner, Gray, 2002). Figure 3 illustrates the forces applied on the cover for this case. The following symbols are used in this figure:

- $W_A$  = total weight of the active wedge including additional weight of soil wedge from the upper bench ( $W_{A1}$  and  $W_{A2}$ ) plus equipment weights on the slope and upper bench ( $W_{e1}$  and  $W_{e2}$ );
- $W_{A1}$  = weight of soil cover on the slope (included in  $W_A$ );
- $W_{A2}$  = weight of soil wedge from the upper bench (included in  $W_A$ );
- $W_{e1}$  = weight of equipment on slope (included in  $W_A$ );





**Subject:** Cover Slope Stability

**By:** N.M.

**Checked By:** B.H.

**Date:** 7/21/08

**Date:** 7/21/08


**Project Name:** Kettleman B-18

**Project No:** 08-0228

**Sheet:** 4 of 8

$W_{e2}$  = weight of equipment on upper bench (included in  $W_A$ );  
 $W_P$  = total weight of the passive wedge;  
 $N_A$  = effective force normal to the failure plane of the active wedge;  
 $N_P$  = effective force normal to the failure plane of the passive wedge;  
 $\gamma$  = unit weight of the cover soil;

$h$  = thickness of the cover;  
 $L$  = length of the slope measured along the slip plane;  
 $\beta$  = soil slope angle;  
 $\phi$  = friction angle of cover soil;  
 $\delta$  = interface friction angle;  
 $C_a$  = adhesion force between cover soil of the active wedge and geo-membrane or foundation;  
 $c_a$  = adhesion between cover soil of the active wedge and geo-membrane or foundation;  
 $C$  = cohesion force along the failure plane of the passive wedge;  
 $c$  = cohesion of the cover soil;  
 $E_A$  = inter-wedge force acting on the active wedge from the passive wedge;  
 $E_P$  = inter-wedge force acting on the passive wedge from the active wedge;  
 $FS$  = factor of safety against cover soil sliding.



**Figure 3. Equilibrium of Forces for a Finite Length Slope of a Uniformly Thick Cover Soil**



**Subject:** Cover Slope Stability

**By:** N.M.

**Checked By:** B.H.

**Date:** 7/21/08

**Date:** 7/21/08

**Project Name:** Kettleman B-18

**Project No:** 08-0228

**Sheet:** 5 of 8

---

For this condition the stability of the cover can be evaluated using the following equation:

$$FS = \frac{-b \pm \sqrt{b^2 - 4 \times a \times cc}}{2 \times a}$$

Where:

$$a = (W_A - N_A \times \cos \beta) \times \cos \beta$$

$$b = -[(W_A - N_A \times \cos \beta) \times \sin \beta \times \tan \phi + (N_A \times \tan \delta + C_a) \times \sin \beta \times \cos \beta + (C + W_P \times \tan \phi) \times \sin \beta]$$

$$cc = (N_A \times \tan \delta + C_a) \times \sin^2 \beta \times \tan \phi$$

$$W_A = W_{A1} + W_{A2} + W_{e1} + W_{e2}$$

$$W_{A1} = (\gamma \times h^2) \times [L/h - 1/\sin \beta - \tan(\beta/2)]$$

$$W_{A2} = (\gamma \times h^2) / (\sin 2\beta)$$

$$W_P = (\gamma \times h^2) / (\sin 2\beta)$$

$$N_A = W_A \times \cos \beta$$

$$C_a = c_a \times (L - h/\sin \beta)$$

$$C = (c \times h) / (\sin \beta)$$

For the up slope backfilling, the dynamic force resulting from acceleration and braking of the construction equipment is not considered. The weight of the equipment is added to the weight of the cover soil.

The pressure at the potential slip interface can be calculated from the following equation:

Equivalent equipment force per unit width at slip plane interface:  $W_e = q \times w \times I$

Where:

$$q = W_b / (2 \times w \times b);$$

$W_b$  = operating weight of equipment;

$w$  = length of equipment track;

$b$  = width of equipment track;

$I$  = influence factor at slip plane interface.

The contact pressure for a CAT D6N LGP tractor is 4.8 psi, with an operating weight of 40,000 lbs. The track dimensions are length ( $w$ ) = 122 in and width ( $b$ ) = 34 in. The track gauge (distance between centers of tracks) is 85 inches.

The influence factor for cover thickness ( $h$ ) of 2.5 ft can be calculated as:

$$b / h = 34 / (2.5 \times 12) = 1.13 \rightarrow I = 0.92$$



**HUSHMAND ASSOCIATES, INCORPORATED**  
**Geotechnical, Earthquake and Environmental Engineers**

**Subject:** Cover Slope Stability

**By:** N.M.

**Checked By:** B.H.

**Date:** 7/21/08

**Date:** 7/21/08

**Project Name:** Kettleman B-18

**Project No:** 08-0228

**Sheet:** 6 of 8

---

Using this influence factor, the equivalent pressure is evaluated below:

$$q = 40,000 / (2 \times 122 \times 34) = 4.8 \text{ psi} = 695 \text{ psf}$$

$$h = 2.5 \text{ ft} \rightarrow W_{e1} = 695 \times (122/12) \times 0.92 = 6,500 \text{ lbs}$$

We have also included additional surcharge of the construction equipment on the upper bench of the cover veneer. This load is estimated as a 500 psf uniform pressure acting on a length equal to  $h/\sin \beta$ .

$$\beta = 16^\circ \rightarrow W_{e2} = 500 \times 2.5 / \sin(16^\circ) = 4,550 \text{ lbs}$$

Using these equipment weights, the safety factor for temporary stability of geotextile / HDPE interface is calculated below:

$$\gamma = 110 \text{ pcf};$$

$$h = 2.5 \text{ ft};$$

$$L = 182 \text{ ft (Section D-D')};$$

$$\beta = 16^\circ;$$

$$\phi = 28^\circ;$$

$$\delta = 25^\circ;$$

$$c_a = 0 \text{ psf};$$

$$c = 100 \text{ psf};$$

$$W_e = 6,500 + 4,550 = 11,050 \text{ lbs.}$$

The following values are calculated using above parameters:

$$W_A = 59,801 \text{ lbs}$$

$$W_P = 1,301 \text{ lbs}$$

$$N_A = 57,500 \text{ lbs}$$

$$C_a = 0 \text{ lbs}$$

$$C = 910.0 \text{ lbs}$$

$$a = 4339.4 \text{ lb/ft}$$

$$b = -8181.7 \text{ lb/ft}$$

$$cc = 1075.9 \text{ lb/ft}$$

These values result in a factor of safety of 1.74 for finite length cover slope. This value is higher than the factor of safety of 1.63 for infinite slope analysis without the construction equipment weight.

**Seismic Stability:**

Seismic stability is evaluated for a finite length of the slope, usually the distance between two benches. This provides a more realistic analytical model of the cover stability since it includes the effect of passive



**Subject:** Cover Slope Stability

**By:** N.M.

**Checked By:** B.H.

**Date:** 7/21/08

**Date:** 7/21/08

**Project Name:** Kettleman B-18

**Project No:** 08-0228

**Sheet:** 7 of 8

resistance wedge at the toe of the slope. For this case equipment forces shown in Figure 3 will be set equal to zero and seismic acceleration will be applied on the cover mass. For this condition the stability of the cover can be evaluated using the following equation:

$$FS = \frac{-b \pm \sqrt{b^2 - 4 \times a \times cc}}{2 \times a}$$

Where:

$$a = (C_S \times W_A + N_A \times \sin \beta) \times \cos \beta + C_S \times W_P \times \cos \beta$$

$$b = -[(C_S \times W_A + N_A \times \sin \beta) \times \sin \beta \times \tan \phi + (N_A \times \tan \delta + C_a) \times \cos^2 \beta + (C + W_P \times \tan \phi) \times \cos \beta]$$

$$cc = (N_A \times \tan \delta + C_a) \times \sin \beta \times \cos \beta \times \tan \phi$$

$C_S$  = Seismic Coefficient

$W_A$  = total weight of the active wedge =  $\gamma \times h^2 \times [L/h - 1/\sin \beta - \tan(\beta/2)] + (\gamma \times h^2) / (\sin 2\beta)$

$W_P$  =  $(\gamma \times h^2) / (\sin 2\beta)$

$N_A$  =  $W_A \times \cos \beta$

$C_a$  =  $c_a \times (L - h/\sin \beta)$

$C$  =  $(c \times h) / (\sin \beta)$

Using the above equations, the Yield Acceleration ( $k_y$ ), corresponding to factor of safety of 1.0 was calculated for Geotextile / HDPE geomembrane interface (weakest interface in Class I waste cover):

$L = 182$  ft,  $h = 2.5$  ft,  $\gamma = 110$  pcf,  $c_a = 0$  psf,  $c = 100$  psf,  $\beta = 16^\circ$ ,  $\phi = 28^\circ$ ,  $\delta = 25^\circ$ ,

$H = 2.5 / (\cos 16) = 2.60$  ft,  $F.S. = 1.0 \implies k_y = 0.20$

The Newmark Displacement Correlations developed by Franklin and Chang (1977) were used to estimate the permanent seismic deformation of the cover system.

$$U_m = U_s \times \frac{V^2}{1800A}$$

Where:  $U_m$  = Unscaled Permanent Displacement (in.)

$U_s$  = Standardized Maximum Displacement (in.)

$A$  = Maximum Ground Acceleration (as fraction of g)

$V$  = Maximum Ground Velocity (in/s)

A conservative  $V/A$  ratio of 60 was used in the analyses, resulting in a maximum ground velocity of 34.8 in/s.  $U_s$  was obtained from standard displacement chart based on  $k_y/A$  ratio.

Based on these assumptions, the seismic displacement value in Table 2 was obtained for Class I waste landfill cover system. Based on our calculation it appears that the permanent seismic displacement is in the



**Subject:** Cover Slope Stability

**By:** N.M.

**Checked By:** B.H.

**Date:** 7/21/08

**Date:** 7/21/08

**Project Name:** Kettleman B-18

**Project No:** 08-0228

**Sheet:** 8 of 8

allowable range for the weakest interface of the cover, therefore the cover system meets the static and seismic stability criteria.

**Table 2. Permanent Seismic Displacement Evaluation for Class I Waste Cover**

<b>Interface</b>	<b><math>k_v^*</math> (g)</b>	<b>A (g)</b>	<b>V (in/s)</b>	<b><math>k_v/A</math></b>	<b><math>U_s</math> (in)</b>	<b><math>U_m</math> (in)</b>
Geotextile / HDPE*	0.20	0.58	34.8	0.35	~10.5	~12

**References:**

Huang, Y. H. (1983), "Stability Analysis of Earth Slopes".

Franklin, A. G. and Chang, F. K. (1977), "Permanent Displacements of Earth Embankments by Newmark Sliding Block Analysis", Report 5, Miscellaneous Papers S-71-17, U.S. Army Corps of Engineers Waterway Experiment Station, Vicksburg, Mississippi.

Qian, X., Koerner, R. M., Gray, D. H. (2002), "Geotechnical Aspects of Landfill Design and Construction".



**HUSHMAND ASSOCIATES, INCORPORATED**  
Geotechnical, Earthquake and Environmental Engineers

December 15, 2009

Golder Associates Inc.  
230 Commerce, Suite 200  
Irvine, California, USA 92602

Mr. Scott Sumner, P.E., Principal

**SUBJECT: ADDENDUM REPORT – PHASE III SLOPE STABILITY ANALYSIS  
KETTLEMAN HILLS FACILITY, HAZARDOUS WASTE  
LANDFILL UNIT B-18 EXPANSION, KETTLEMAN CITY,  
KINGS COUNTY, CALIFORNIA - HAI PROJECT No. 08-0228**

Dear Mr. Sumner:

Hushmand Associates, Inc. (HAI) is pleased to submit to Golder Associates, Inc. (Golder) this addendum letter report of the slope stability evaluations for the Class I/II hazardous waste landfill unit B-18 (Landfill B-18) expansion at Waste Management, Inc. (WMI) Kettleman Hills Facility.

This addendum updates portions of the HAI "Slope Stability Analysis Report, Kettleman Hills Facility, Hazardous Waste Landfill Unit B-18 Expansion, Kettleman City, Kings County, California," Report to Kettleman Hills Facility, September 2008. The addendum report has been prepared to incorporate revised interface shear strength testing results for the proposed liner system. The addendum report updates only those portions of the original report that are effected by the change in interface shear strength, references are included to sections of the original report as appropriate. This report should therefore be used in conjunction with the original HAI (2008) report.

#### Introduction

The existing Class I/II (hazardous and designated wastes) Landfill Unit B-18 at Chemical Waste Management (CWM) Kettleman Hills Facility (KHF) in Kettleman City, Kings County, California is proposed to be expanded. The existing landfill was constructed in phases (Phase I and II) in 1990's. For the proposed expansion (Phase III), URS Corporation and Hushmand Associates, Inc. performed slope stability and seismic deformation analyses in support of the EIR

preparation and design of the landfill expansion, respectively (URS, 2005; HAI, 2008). The results of these analyses were provided in a comprehensive design report by Golder Associates (Golder, 2008).

A number of investigations including site-specific testing on the landfill material properties were performed for design and construction of the earlier phases of the landfill (Golder, 1990, 1991; ESI, 1990, 1992, 1993). In 2003, URS obtained samples of the landfill Phase II liner system that were archived at the KHF site. Interface shear strength testing was performed on the sandwich-like multilayer structure of the liner system and the results (friction angle,  $\phi = 19^\circ$  and cohesion/adhesion,  $C = 0$ ) were used to refine the interface properties reported in the previous investigations (URS, 2005).

### Landfill Geometry and Analysis Sections

HAI (2008) developed six cross sections for the proposed landfill expansion (see Figures 1 and 2 of the HAI 2008 Report). These same six cross sections are evaluated in the addendum report using the updated interface shear strength properties.

This addendum report summarizes the results of the slope stability and seismic deformation analyses for the proposed landfill expansion area, extending from the landfill's southeast corner to northwest corner, along its southern and western boundaries.

The expansion area is located on the western and southern sides of cross sections A-A' through F-F' that were used in the previous stability analyses (HAI, 2008). Additionally, east side of Cross Section B-B' also passes through the expansion area and was also analyzed in the addendum. The interface shear strength of Phase I was not modified and therefore analysis of the northern and eastern boundaries for all cross sections except B-B' remains valid.

### Liner Interface Shear Strength Properties

HAI (2008), Section 3.4, used the material properties from the previous investigations for Phase I liner system and the URS (2005) report for Phase II liner system for static and seismic slope stability and deformation analyses. For the proposed expansion area liner system, the same interface properties ( $\phi = 19^\circ$ ,  $C = 0$ ) measured for the Phase II liner system were used (URS, 2005).

HAI (2008) recommended that assumed properties used for design be further verified by performing site-specific tests on the actual materials that would be used during construction. Golder recently performed site-specific laboratory testing on the proposed standard liner system materials for the landfill expansion area to determine the interface properties for the expansion liner system design.

Interface shear strength testing was performed by Precision Geosynthetic Laboratories of Anaheim, California on the sandwich-like multilayer structure of the liner system. The test results indicated that the weakest interface was the double sided (DS) geocomposite and 60-mil

HDPE for all applied normal loads. The ultimate interface shear strength properties at 3 inch displacement were measured as approximately  $\phi = 12^\circ$  and  $C = 0$ . Attachment A provides results of the interface shear tests performed on the Phase III proposed liner system materials. The results were used to refine the slope stability and seismic deformation analyses performed previously (HAI, 2008) for the landfill expansion design.

In the revised slope stability analyses presented here, residual interface shear strength properties measured by URS (2005) and Golder (2009) were used for the Phase II and Phase III slopes, respectively. The Phase I slopes have a slightly different liner system and a residual interface friction angle of 9 degrees was used for the analysis. The material properties for static and seismic stability analyses are summarized in Table 1 (updated version of HAI 2008 Table 1).

**Table 1. Selected Material Properties for Static and Seismic Stability Analysis**  
 (Replaces Table 1 of HAI 2008)

Material/Interface	Unit Weight	Shear Strength Properties		Shear Wave Velocity ( $V_s$ - ft/sec) or Shear Modulus ( $G$ , psf) Relation	Modulus Reduction & Damping Curves
		$\phi$ (degree)	$C$ (psf)		
HW <sup>1</sup>	115 pcf	31	0	$G = 1000 K_2 (\sigma'_m)^{0.5}$ $K_2 = 60$ for relatively dense sands (Seed and Idriss, 1970)	See Figure 19 Relatively dense sand (Seed et al., 1984)
Clay Liner <sup>1,2</sup>	115 pcf	20	1,150	$G = \frac{14,760(2.97 - e)^2}{1 + e} (OCR)^k \sigma_m^{0.5}$ (Hardin and Drenvich, 1972)	See Figure 19 (Seed and Idriss, 1970)
Bedrock <sup>1</sup>	150 pcf	40	800	$V_s = 2500$ fps	See Figure 19 (Schnabel et al. 1972)
Phase I Bottom Liner Interface <sup>1</sup>	----	17	0	----	----
Phase I Side Slope Liner Interface <sup>1</sup>	----	9	800	----	----
Phase II Bottom Liner Interface <sup>1</sup>	----	19	0	----	----
Phase II Side Slope Liner Interface <sup>3</sup>	----	19	0	----	----
Revised Expansion Area Liner Interface <sup>4</sup>	----	12	0	----	----

- (1) Environmental Solutions, Inc. (1990, 1992, 1993); Rust Environment & Infrastructure, Inc. (1998); URS (2005).
- (2) Modeled as a layer in site dynamic response analysis to include effects of softer clay layer on ground motion.
- (3) The residual interface shear strength properties measured by URS (2005) were used for the Phase II slopes.
- (4) Golder Associates, Inc. (2009).



### Static and Pseudo-Static Slope Stability Analyses

The analysis approach discussed in Section 3.5 of the original stability report (HAI 2008) remains unchanged in the addendum report.

As discussed in Section 3.6 of the HAI 2008 report, slope stability analyses were performed for the six cross sections analyzed in the 2008 report. Since the landfill is planned to be expanded mainly along its western and southern boundaries, and the new liner system properties only apply to these areas, potential failure planes on the west and south sides of Cross Sections A-A', B-B', C-C', D-D', E-E', and F-F' were analyzed. Additionally potential failure planes on the east side of Cross Section B-B' were analyzed. The most important potential failure mechanism considered was for a wedge (block failure) sliding through the waste mass and along the existing and expanded landfill base liner system. Potential failure surfaces were assumed to pass along the weakest interface in the lining system and then through the landfill mass to the surface.

Pseudo-static analyses, necessary to compute yield acceleration coefficient ( $K_y$ ), were also performed for the critical potential failure surfaces through waste and base liner system, identified from results of the static slope stability analyses for the selected cross sections. The yield acceleration is defined as the acceleration which results in a pseudo-static factor of safety of 1.0. The computed yield acceleration,  $K_y$ , represents limiting value of the horizontal seismic coefficient beyond which movement of a potential slide mass will occur.

For each cross section, pseudo-static analysis using the Spencer or Janbu Method was performed to compute an estimate of yield acceleration coefficient ( $K_y$ ) for the most critical potential failure plane identified from the static slope stability analysis for that section. The GSTABL7 output plots are presented in Attachment B for the various potential failure surface conditions considered, and the most critical failure surfaces analyzed in the stability analysis of the final fill slopes of the proposed landfill expansion.

Table 2b (replaces Table 2b of HAI 2008) below presents the results of the updated slope stability analyses (computed static factors of safety and yield acceleration coefficients) for the most critical potential failure surfaces using the new interface properties of  $\phi = 12^\circ$  and  $C = 0$ .

**Table 2b. Summary of Slope Stability Analysis Results (Landfill West and South Sides)**  
(Replaces Table 2b of HAI 2008)

Cross Section	Failure Plane Number	Description	Static Factor of Safety	Yield Acceleration, $K_y$ (g)
A-A' (west)	I	Deep Block Failure through Bottom Liner	2.55*	0.27*
	II	Deep Block Failure through Bottom Liner	5.41*	0.30*
B-B' (west)	I	Deep Block Failure through Bottom Liner	2.41	0.20
	II	Deep Block Failure through Bottom Liner	6.44	0.31
C-C' (south)	I	Deep Block Failure through Bottom Liner	3.74	0.23
	II	Deep Block Failure through Bottom Liner	3.62*	0.23*
D-D' (west)	I	Deep Block Failure through Bottom Liner	3.73	0.27
	II**	Circular Failure	2.50	0.32
	III**	Circular Failure	2.18	0.26
E-E' (west)	I	Deep Block Failure through Bottom Liner	3.42*	0.28*
	II	Deep Block Failure through Bottom Liner	3.90*	0.32*
F-F' (west)	I**	Circular Failure	2.58	0.33
	II	Deep Block Failure through Bottom Liner	4.40	0.29
	III	Deep Block Failure through Bottom Liner	3.31*	0.28*

Notes: \* Static Factor of Safety and  $K_y$  computed using Janbu's method.  
 \*\* Circular failure analysis from HAI 2008 included for completeness.  
 Static factor of safety and  $K_y$  for section B-B' (east) changed only slightly and thus are not reported. Static factors of safety and  $K_y$  values for Section B-B' are larger than 3.0 and 0.3, respectively.

For all final (long-term) static conditions, the minimum acceptable factor of safety is 1.5. This criterion was satisfied by the potential failure surfaces analyzed for the proposed fill plan, base liner designs, and the site-specific and estimated landfill material properties.

The results of the pseudo-static stability analyses show that the lowest yield acceleration coefficient was approximately equal to 0.20 for failure along the liner and waste mass in cross sections B-B' (west).

The combination of yield acceleration coefficient and slide mass geometry that could potentially result in the largest estimates of the seismically-induced displacements were used in the site response and Newmark displacement analyses as described in detail in the 2008 report (Golder,



2008). Based on the computed yield accelerations presented in Table 2b and landfill cross sections geometry, the potential failure plane #I for cross section B-B' and failure plane #I associated with cross section D-D' were judged to produce the largest seismic displacements and thus, were selected for dynamic site response and seismic deformation analyses. The estimated displacements were calculated based on updated 2008 site specific ground motions for the Kettleman Hills Landfill (HAI 2008).

#### Seismically-Induced Permanent Displacements

A detailed evaluation of the seismic deformations using two-dimensional finite element site response analyses and Newmark (1965) slope displacement calculation method was performed for this study. The analyses were performed for the most critical combinations of  $K_y$  values and failure plane geometries (Sections B-B', Failure Plane I, West and Section D-D', Failure Plane I, West) and the two sets of design earthquake motions used in the 2008 analyses (1994 Northridge Earthquake and 1979 Loma Prieta Earthquake records).

The average acceleration time histories computed in the QUAD4M response analyses for the most critical potential failure mass identified in the pseudo-static analyses were used as input for Newmark deformation analyses to evaluate the permanent seismically-induced displacements along the liner system. The displacement calculated by this method is a function of the yield accelerations which were computed in the pseudo-static stability analyses. Figures 1 through 4 (replace Figures 21 to 24 in HAI 2008) illustrate variation of potential slide mass displacement ( $\delta$ ) versus the yield acceleration  $K_y$  for cross sections B-B' and D-D' and for the two sets of design ground motions used in the analyses (Golder, 2008). Based on the  $K_y$  values in Table 2b and Figures 1 through 4, for the potential failure plane # I, located in the northwestern part of cross section B-B' the largest permanent displacement (~ 1.5 inch) is induced for the 1994 Northridge earthquake Castaic Old Ridge Route accelerograms scaled to a PHGA of 0.57g. For all other sections and potential failure planes for  $K_y$  values larger than 0.2 seismic induced liner displacements are less than 1 inch. These estimated values of the seismic displacements are considerably smaller than the maximum allowable displacement of 6 inches commonly used in the industry (Seed and Bonaparte, 1992). Therefore, the landfill will be stable both statically and seismically for the updated site-specific liner interface properties.

#### Conclusion

This addendum report summarizes the site specific liner interface shear strength testing performed by Golder and the updated slope stability and seismic deformation analyses for the proposed landfill expansion area slopes using the new strength properties. The site specific testing was performed to verify the strength properties originally used in the landfill expansion design in the HAI 2008 report. The measured liner interface friction angle ( $\phi = 12^\circ$ ) was found to be lower than the original value used in the design ( $\phi = 19^\circ$ ). Using this new interface friction angle, static and dynamic stability analyses were conducted for various cross sections of the proposed landfill expansion area.

The analyses indicated that the proposed new landfill expansion design (Golder, 2008) would result in a stable configuration under both static and seismic loading conditions in compliance with applicable regulations. The acceptability of the landfill slopes for earthquake loading conditions was determined by the relatively small magnitude of the seismically-induced permanent displacements resulting from the local and distant design earthquake events. The results of the analysis show that the computed static factors of safety are greater than 1.5 for all analyzed sections. The results of the conservative Newmark-type permanent displacement analyses presented in this study indicated that computed maximum displacements along the liner system during the design earthquake events are less than 1.5 inches.

### References

- Environmental Solutions, Inc., 1990. "Engineering and Design Report, Landfill Unit B-18, Phase I and II and Final Closure, Kettleman Hills Facility, Kings County, California, Volumes I and II," report prepared for Chemical Waste Management, Inc., August.
- Environmental Solutions, Inc., 1992. "Backup Calculations Supporting the Interface testing Program for Landfill Unit B-18, Kettleman Hills Facility, Kings County, California," report prepared for Chemical Waste Management, Inc., February.
- Environmental Solutions, Inc., 1993. "Revised Intermediate Waste Fill Plan, Landfill Unit B-18, Phase I, Kettleman Hills Facility, Kings County, California, Volumes I and II," report prepared for Chemical Waste Management, Inc., August.
- Golder Associates, Inc. (1990) "Direct Shear Testing Program for Landfill Cover Design, Kettleman Hills Facility", June 29, 1990.
- Golder Associates, Inc. (1991) "Landfill B-19, Phase IA Redesign and Closure Plan, Kettleman Hills Facility, Kettleman City, California," Volumes I-IV, April 15, 1991.
- Golder Associates, Inc. (2008) "Engineering and Design Report, Landfill Unit B-18, Kettleman Hills Facility, Kettleman City, California" Report to Kettleman Hills Facility.
- Hushmand Associates, Inc. (2008) "Slope Stability Analysis Report, Kettleman Hills Facility, Hazardous Waste Landfill Unit B-18 Expansion, Kettleman City, Kings County, California," Report to Kettleman Hills Facility, September.
- Newmark, N. M. (1965) "Effects of Earthquakes on Dams and Embankments," 5th Rankine Lecture, Geotechnique, Vol. 15, No. 2, pp. 139-160.
- URS (2005) "Preliminary Stability Analyses, Kettleman Hills Facility Expansion, Kettleman City, California," prepared for Chemical West Management, Inc.

Closure

We trust this addendum report meets your present requirements. If you have any questions regarding this report, please contact this office at your convenience. We appreciate this opportunity to provide our professional services to Golder.

Sincerely yours,

Very truly yours,

**HUSHMAND ASSOCIATES, INC.**




Ben Hushmand, Ph.D., P.E. 44777  
President, Principal Engineer



## FIGURES

**Section D-D', Failure Plane 'I', West**



**Legend**

- \*(O) Original record
- \*\*\*(F) Flipped record (multiplied by -1)

Project No.  
08-0228



Landfill B-18 Expansion Project  
Kettleman City, Kings County, California



**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

**EARTHQUAKE INDUCED DISPLACEMENTS**  
**SECTION D-D' - FAILURE PLANE I**  
**2-D QUAD4M DYNAMIC RESPONSE ANALYSIS**  
**(PREVIOUS GROUND MOTIONS)**

### Section D-D', Failure Plane "I", West




**Legend**  
 \*(O) Original record  
 \*\*\*(F) Flipped record (multiplied by -1)

 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers	Project No. 08-0228	Landfill B-18 Expansion Project Kettleman City, Kings County, California
	EARTHQUAKE INDUCED DISPLACEMENTS SECTION D-D' - FAILURE PLANE I 2-D QUAD4M DYNAMIC RESPONSE ANALYSIS (PREVIOUS GROUND MOTIONS)	




**Section B-B', Failure Plane 'I', West**



**Legend**  
 \*(O) Original record  
 \*\*(F) Flipped record (multiplied by -1)

Project No. 08-0228	Landfill B-18 Expansion Project Kettleman City, Kings County, California
	 <b>HUSHMAND ASSOCIATES INC.</b> Geotechnical and Earthquake Engineers

Section B-B', Failure Plane "1", West



Legend

- \* (O) Original record
- \*\* (F) Flipped record (multiplied by -1)

Project No.  
08-0228

Landfill B-18 Expansion Project  
Kettleman City, Kings County, California



**HUSHMAND ASSOCIATES INC.**  
Geotechnical and Earthquake Engineers

EARTHQUAKE INDUCED DISPLACEMENTS  
SECTION B-B' - FAILURE PLANE I  
2-D QUAD4M DYNAMIC RESPONSE ANALYSIS  
(UPDATED GROUND MOTIONS)

Figure

4

**APPENDIX A**

**INTERFACE SHEAR TEST**


**RESULTS**

**TABLE 1**  
**CLIENT: GOLDER & ASSOCIATES**  
**PROJECT: KETTLEMAN HILLS**

INTERFACE SHEAR TEST RESULT (ASTM D5321/6243)  
 PGL Job No. G090907

Reviewed By:   
 Date: 2-Oct-09

**TEST CONFIGURATION 1**



**TEST CONDITIONS:**

**SAMPLE PREPARATION:**

- Specimens were cut along machine direction to 14" x 17" for the upper box, and 14" x 19" for the lower box, with an effective test area of 12" x 12".
- The Maximum Dry Density (MDD) of the soil is **111.8** pcf at **16.4%** Optimum Moisture Content (OMC).
- Soil specimen was remolded to **102.88** pcf; i.e., **92.0%** of MDD at **20.5%** moisture content. (forming 2 inch layer in the TOP and BOTTOM boxes).
- The three intermediate geosynthetic specimens were floating during shear run.

**CONSOLIDATION:**

- Each set of specimen was consolidated under **Dry** condition for **24 hrs** @ normal load before shearing.
- Normal loads were applied using **Hydraulics** for the highest load, **Bladder** for the intermediate and lowest loads.

**SHEAR TEST:**

- Shear test was conducted @ **0.040** in/min
- Sheared @ minim **3.0** inch horizontal displacement.
- Test specimens were sheared in **Dry** condition.
- Test were performed in general accordance with ASTM D6243 / ASTM D5321 using Brainard-Kilman LG-112 Direct Shear machine with effective test area of 12 in X 12 in.



**TEST RESULTS:**

Normal Stresses Applied		Asperity Heights [C#44500]				Asperity Heights [C# 44501]				Moisture Content (Soil)		PEAK STRENGTH		POST-PEAK STRENGTH AT <b>3.0</b> INCHES	
		UP		DOWN		UP		DOWN				Shear Stress	Secant Angle	Shear Stress	Secant Angle
		(psf)	(psf)	(mils)	(mils)	(mils)	(mils)	(mils)	(mils)	(mils)	(mils)	(%)	(%)	(psf)	(degrees)
34.7	5,000	23.7	23.1	24.4	23.2	23.5	19.4	24.4	23.7	20.5	18.6	2,709	28	1,148	13
69.4	10,000	23.7	22.9	23.7	22.3	22.9	17.7	24.3	22.1	20.5	19.8	4,737	25	2,032	11
104.2	15,000	24.6	22.8	25.3	24.6	24.6	16.3	24.0	23.0	20.5	20.1	7,953	28	3,283	12
Note: N/A Not Applicable												COHESION (psf) :		19	
												COEFFICIENT OF FRICTION :		0.52	
												FRICTION ANGLE (degrees) :		27.7	

NOTE: The friction angles and cohesion results given here are based on mathematically determined best fit lines.

**OBSERVATIONS:**

- No tilting of the system or any abnormalities observed during and after the test.
- Superficial abrasion on the geosynthetics interfacing sides (typical to all loads).
- Sliding occurred between the DS Geocomposite (C# 62070) and 60 mil HDPE (C# 44501) on all loads. See attached photos (907-1-15,000 psf / 907-1-10,000 psf / 907-1-5,000 psf)




**TABLE 1-A**  
**CLIENT: GOLDER & ASSOCIATES**  
**PROJECT: KETTLEMAN HILLS**

INTERFACE SHEAR TEST RESULT (ASTM D5321/6243)  
PGL Job No. G091078

Reviewed By:   
Date: 19-Oct-09

**TEST CONFIGURATION 1-A**



**TEST CONDITIONS:**

**SAMPLE PREPARATION:**

- Specimens were cut along machine direction to 14" x 17" for the upper box, and 14" x 19" for the lower box, with an effective test area of 12" x 12".
- Geosynthetic specimens were secured via flat bar clamping mechanisms complete with bolts and nuts (7-pairs).

**CONSOLIDATION:**

- The specimen was consolidated under Dry condition for 2 hrs @ normal load before shearing.
- Normal load was applied using Bladder

**SHEAR TEST:**

- Shear test was conducted @ 0.04 in/ min.
- Sheared @ minimum 3.0 inch horizontal displacement.
- The test specimens were sheared at Dry condition .
- Test were performed in general accordance with ASTM D6243 / ASTM D5321 using Brainard-Kilman LG-112 Direct Shear machine with effective test area of 12 in X 12 in.


**TEST RESULTS:**

Normal Stresses Applied		Asperity Heights		PEAK STRENGTH		POST- PEAK STRENGTH AT <u>3.0</u> INCHES	
				Shear Stress	Secant Angle	Shear Stress	Secant Angle
(psi)	(psf)	Before	After	(psf)	(degrees)	(psf)	(degrees)
69.44	10,000	25.5	18.4	4940	26	2135	12

**OBSERVATIONS:**

- No tilting of the system or any abnormalities observed during and after the test.
- Superficial abrasion on the geosynthetics interfacing sides (typical to all loads).
- Sliding occurred between the two interfacing surfaces.

Figure #2  
Shear Stress/ Displacement Curve




**TABLE 1-B**  
**CLIENT: GOLDR & ASSOCIATES**  
**PROJECT: KETTLEMAN HILLS**

INTERFACE SHEAR TEST RESULT (ASTM D5321/6243)  
PGL Job No. G091078

Reviewed By:   
Date: 19-Oct-09

**TEST CONFIGURATION 1-B**



**TEST CONDITIONS:**

**SAMPLE PREPARATION:**

- Specimens were cut along machine direction to 14" x 17" for the upper box, and 14" x 19" for the lower box, with an effective test area of 12" x 12".
- Geosynthetic specimens were secured via flat bar clamping mechanisms complete with bolts and nuts (7-pairs).

**CONSOLIDATION:**

- The specimen was consolidated under Dry condition for 2 hrs @ normal load before shearing.
- Normal load was applied using Bladder

**SHEAR TEST:**

- Shear test was conducted @ 0.04 in/ min.
- Sheared @ minimum 3.0 inch horizontal displacement.
- The test specimens were sheared at Dry condition.
- Test were performed in general accordance with ASTM D6243 / ASTM D5321 using Brainard-Kilman LG-112 Direct Shear machine with effective test area of 12 in X 12 in.


**TEST RESULTS:**

Normal Stresses Applied		Asperity Heights		PEAK STRENGTH		POST- PEAK STRENGTH AT 3.0 INCHES	
				Shear Stress	Secant Angle	Shear Stress	Secant Angle
(psf)	(psf)	Before	After	(psf)	(degrees)	(psf)	(degrees)
69.44	10,000	24.8	19.3	4903	26	2262	13

**OBSERVATIONS:**


- No tilting of the system or any abnormalities observed during and after the test.
- Superficial abrasion on the geosynthetics interfacing sides (typical to all loads).
- Sliding occurred between the two interfacing surfaces.

Figure #2  
Shear Stress/ Displacement Curve






@ 15,000 psf



@ 10,000 psf






@ 5,000 psf

## **APPENDIX B**

# **SLOPE STABILITY ANALYSIS PLOTS**

# KHF, SECTION A-A', WEST, STATIC, FAILURE PLANE I (REVISED)

c:\slopet\cross sections\11-09la-a west (10-16)\sea-w-1.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 11:32AM




GSTABL7 v.2 FSmin=2.553

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SECTION A-A', WEST, PSEUDO-STATIC, FAILURE PLANE 1 (REVISED)

c:\slope\tcross sections\11-09\la-a west (10-16)\sea-w-jp1 surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 11:44AM




GSTABL7 v.2 FSmin=1.002

Factor Of Safety Is Calculated By The Simplified Janbu Method



# KHF, SECTION A-A', WEST, STATIC, FAILURE PLANE II (REVISED)

c:\slopet\cross sections\11-09\1a-a west (10-16)\sea-w-2.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 06:42PM




GSTABL7 v.2 FSmin=5.413

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SECTION A-A', WEST, PSEUDO-STATIC, FAILURE PLANE II (REVISED)

c:\slope\cross sections\11-09la-a west (10-16)\sea-wps-2 surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 06:34PM




GSTABL7 v.2 FSmin=1.021

Factor Of Safety is Calculated By The Simplified Janbu Method



# KHF, SEC. B-B', WEST, STATIC, FAILURE PLANE II (REVISED)

c:\slope\cross sections\11-09\lb-b west (oct 09)\secb-wsjj.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 11:59AM




GSTABL7 v.2 FSmin=1.960

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SEC. B-B', WEST, STATIC, FAILURE PLANE I (REVISED)

c:\slope\cross sections\11-09\b-b west (oct 09)\secb-ws1 surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 12:02PM



GSTABL7 v.2 FSmin=2.412


Factor Of Safety is Calculated By GLE (Spencer's) Method (0-2)





# KHF, SEC. B-B', WEST, PSEUDO-STATIC, FAILURE PLANE I (REVISED)

c:\slope\cross sections\11-09\lb-b west (oct.09)\secb-wps1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 12:07PM




GSTABL7 v.2 FSmin=1.025  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', WEST, STATIC, FAILURE PLANE II (REVISED)

c:\slope\cross sections\11-09lb-b west (oct 09)\secb-wsjii.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:37PM



#	FS	Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion (psf)	Friction Angle (deg)	Piez. Surface No.
a	4.535	Refuse	1	115.0	115.0	0.0	31.0	0
b	4.567	P2 Liner	2	115.0	115.0	0.0	19.0	0
c	4.648	Bedrock	3	130.0	800.0	800.0	40.0	0
d	4.700	P1 Base	4	115.0	115.0	0.0	17.0	0
e	4.741	P1 Slope	5	115.0	115.0	800.0	9.0	0
f	4.765	P3 Liner	6	115.0	115.0	0.0	12.0	0
g	4.791							
h	4.840							
i	4.853							
j	4.861							

GSTABL7 v.2 FSmin=4.535

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SEC. B-B', WEST, STATIC, FAILURE PLANE II (REVISED)

c:\slope\cross sections\11-09\b-b west (oct 09)\secb-ws2s surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:39PM

1800

Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
P2 Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0
P3 Liner	6	115.0	115.0	0.0	12.0	0

1500

1200


900

600

300

0

3.5 303.5 603.5 903.5 1203.5 1503.5 1803.5 2103.5 2403.5 2703.5




GSTABL7 v.2 FSmin=6.443

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', WEST, PSEUDO-STATIC, FAILURE PLANE II (REVISED)

c:\slope\cross sections\11-09\b-b west (oct 09)\secb-ws2ps.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:42PM




GSTABL7 v.2 FSmin=1.015

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 1 (REVISED)

c:\slope\cross sections\11-09lb-b east (oct 09)\secb-esj1.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:07PM




GSTABL7 v.2 FSmin=3.688

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 1 (REVISED)

c:\slope\cross sections\11-09\b-b east (oct 09)\secb-es1 surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:09PM




GSTABL7 v.2 FSmin=5.817

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, PSEUDO-STATIC, FAILURE PLANE 1 (REVISED)

c:\slopes\cross sections\11-09\lb-b east (oct 09)\secb-ep1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:13PM




Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Piez. Surface No.	Load Peak(A) kh Coef.	Value 0.570(g)
Refuse	1	115.0	115.0	0.0	31.0	0	0.340(g)<	
P2 Liner	2	115.0	115.0	0.0	19.0	0		
Bedrock	3	130.0	130.0	800.0	40.0	0		
P1 Base	4	115.0	115.0	0.0	17.0	0		
P1 Slope	5	115.0	115.0	800.0	9.0	0		
P3 Liner	6	115.0	115.0	0.0	12.0	0		

GSTABL7 v.2 FSmin=1.022  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 2 (REVISED)

c:\slope\cross sections\11-09\11-b east (oct 09)\secb-esj2.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:15PM



GSTABL7 v.2 FSmin=2.320


Safety Factors Are Calculated By The Simplified Janbu Method





# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 2 (REVISED)

c:\slope\cross sections\11-09\lb-b east (oct 09)\secb-es2 surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:16PM




GSTABL7 v.2 FSmin=3.327

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, PSEUDO-STATIC, FAILURE PLANE 2 (REVISED)

c:\slope\cross sections\11-09\lb-b east (oct 09)\secb-eps2.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 04:30PM



Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
P2 Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0
P3 Liner	6	115.0	115.0	0.0	12.0	0

Load Peak(A) Kh Coef.	Value 0.370(g) 0.310(g)<
-----------------------	--------------------------


GSTABL7 v.2 FSmin=1.011

Factor Of Safety is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 3 (REVISED)

c:\slope\cross sections\11-09\lb-b east (oct 09)\secb-es3.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:18PM




GSTABL7 v.2 FSmin=7.044

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SEC. B-B', EAST, STATIC, FAILURE PLANE 3 (REVISED)

c:\slope\cross sections\11-09\lb-b east (oct 09)\secb-eps3.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:27PM




GSTABL7 v.2 FSmin=7.665

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. B-B', EAST, PSEUDO-STATIC, FAILURE PLANE 3 (REVISED)

c:\slope\cross sections\11-09\b-b east (oct 09)\secb-esps3.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 05:28PM




GSTABL7 v.2 FSmin=1.001

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. C-C', SOUTH, STATIC, FAILURE SURFACE I (REVISED)

c:\slope\cross sections\11-09\c-c south (oct 09)\secc-ssj1.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 02:21PM




GSTABL7 v.2 FSmin=3.148

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SEC. C-C', SOUTH, STATIC, FAILURE SURFACE I (REVISED)

c:\slope\cross sections\11-09\c-c south (oct 09)\secc-ses1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 02:24PM



Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
P2 Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0
P3 Liner	6	115.0	115.0	0.0	12.0	0


GSTABL7 v.2 FSmin=3.743

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. C-C', SOUTH, PSEUDO-STATIC, FAILURE SURFACE I (REVISED)

c:\slope\cross sections\11-09\c-c south (oct 09)\secc-sss1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 02:39PM



GSTABL7 v.2 FSmin=0.993


Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)





# KHF, SEC. C-C', SOUTH, STATIC, FAILURE SURFACE II (REVISED)

c:\slope\cross sections\11-09\c-c south (oct 09)\secc-ssj2.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 02:27PM




GSTABL7 v.2 FSmin=3.616

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SEC. C-C', SOUTH, PSEUDO-STATIC, FAILURE SURFACE II (REVISED)

c:\slope\cross sections\11-09\c-c south (oct 09)\secc-ses2.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 03:02PM




GSTABL7 v.2 FSmin=1.008

Factor Of Safety Is Calculated By The Simplified Janbu Method



# KHF, SEC. D-D', WEST, STATIC, FAILURE PLANE I (REVISED)

c:\slop\cross sections\11-09\hd-d west (10-16)\sed-w-1ja.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 03:06PM




GSTABL7 v.2 FSmin=2.489

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SEC. D-D', WEST, STATIC, FAILURE PLANE I (REVISED)

c:\islopet\cross sections\11-09\ld-d west (10-16)\sed-w-1sa surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 03:09PM




GSTABL7 v.2 FSmin=3.733

Factor Of Safety is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SEC. D-D', WEST, PSEUDO-STATIC, FAILURE PLANE I (REVISED)

c:\slope\cross sections\11-09\d-d west (10-16)\sed-w-1spa surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 03:11PM




GSTABL7 v.2 FSmin=1.021  
Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION E-E' WEST, STATIC, FAILURE PLANE I (REVISED)

c:\slope\cross sections\11-09le-e west (oct 09)\sece-wsj i.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 06:02PM




GSTABL7 v.2 FSmin=3.418

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SECTION E-E' WEST, PSEUDO-STATIC, FAILURE PLANE I (REVISED)

c:\slope\cross sections\11-09\le-e west (oct 09)\sece-ws\1 surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 06:12PM




GSTABL7 v.2 FSmin=1.033

Factor Of Safety Is Calculated By The Simplified Janbu Method



# KHF, SECTION E-E', WEST, STATIC, FAILURE PLANE II (REVISED)

c:\slope\cross sections\11-09\le-e west (oct 09)\sece-wsp2.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 06:15PM



GSTABL7 v.2 FSmin=3.899


Safety Factors Are Calculated By The Simplified Janbu Method





# KHF, SECTION E-E', WEST, PSEUDO-STATIC, FAILURE PLANE II (REVISED)

c:\slope\cross sections\11-09\le-e west (oct 09)\sece-wp2 surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 06:22PM




GSTABL7 v.2 FSmin=1.021

Factor Of Safety Is Calculated By The Simplified Janbu Method



# KHF, SECTION F-F', WEST, STATIC, FAILURE PLANE II (REVISED)

c:\slope\cross sections\11-09\if-west (10-19)\if-w-1.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 03:31PM



#	FS	Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion (psf)	Friction Angle (deg)	Piez. Surface No.
a	3.199	Refuse	1	115.0	115.0	0.0	31.0	0
b	3.199	P2 Liner	2	115.0	115.0	0.0	19.0	0
c	3.199	Bedrock	3	130.0	130.0	800.0	40.0	0
d	3.199	P1 Base	4	115.0	115.0	0.0	17.0	0
e	3.440	P1 Slope	5	115.0	115.0	800.0	9.0	0
f	3.440	P3 Liner	6	115.0	115.0	0.0	12.0	0


GSTABL7 v.2 FSmin=3.199

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SECTION F-F', WEST, STATIC, FAILURE PLANE II (REVISED)

c:\slope\cross sections\11-09\1-west (10-19)\sef-w-1s.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 03:35PM



Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion (psf)	Friction Angle (deg)	Piez. Surface No.
Refuse	1	115.0	115.0	0.0	31.0	0
P2 Liner	2	115.0	115.0	0.0	19.0	0
Bedrock	3	130.0	130.0	800.0	40.0	0
P1 Base	4	115.0	115.0	0.0	17.0	0
P1 Slope	5	115.0	115.0	800.0	9.0	0
P3 Liner	6	115.0	115.0	0.0	12.0	0


GSTABL7 v.2 FSmin=4.398

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION F-F', WEST,PSEUDO-STATIC, FAILURE PLANE II (REVISED)

c:\slope\cross sections\11-09\1-f west (10-19)\sef-w-1sp.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 03:37PM




GSTABL7 v.2 FSmin=1.010

Factor Of Safety Is Calculated By GLE (Spencer's) Method (0-2)



# KHF, SECTION F-F', WEST, STATIC, FAILURE PLANE III (REVISED)

c:\slopetcross sections\11-09\ff-west (10-19)\secf-ws\iii.pl2 Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 03:40PM



#	FS	Soil Desc.	Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion (psf)	Friction Angle (deg)	Piez. Surface No.
a	3.313	Refuse	1	115.0	115.0	0.0	31.0	0
b	3.313	P2 Liner	2	115.0	115.0	0.0	19.0	0
c	3.313	Bedrock	3	130.0	130.0	800.0	40.0	0
d	3.313	P1 Base	4	115.0	115.0	0.0	17.0	0
e	3.460	P1 Slope	5	115.0	115.0	800.0	9.0	0
f	3.460	P3 Liner	6	115.0	115.0	0.0	12.0	0
g	3.460							
h	3.496							
i	3.496							


GSTABL7 v.2 FSmin=3.313

Safety Factors Are Calculated By The Simplified Janbu Method



# KHF, SECTION F-F', WEST, PSEUDO-STATIC, FAILURE PLANE III (REVISED)

c:\slope\cross sections\11-09M-f west (10-19)\sect-wss3 surface #1.plt Run By: Ashkaan, Hushmand Associates, Inc 11/10/2009 03:51PM



GSTABL7 v.2 FSmin=1.018

Factor Of Safety is Calculated By The Simplified Janbu Method





**APPENDIX I**  
**SOIL EROSION ANALYSES**





**Kettleman Hills Facility – Landfill Unit B-18  
SOIL EROSION**

Project No.: 083-91887

Made By: RH

Date: 4-18-2008

Checked By: SS

Sheet: 1 of 3

Reviewed By: SS

**Objective:**

To estimate and evaluate the soil loss due to surface water erosion from the proposed final closure cover slopes of Landfill B-18.

**Given:**

The proposed final closure cover slopes of Landfill B-18 will generally consist of benches every 50 vertical feet (maximum) with 3.5H:1V (horizontal:vertical) slopes between benches. Therefore, the worst case cover slope with regard to soil erosion is:

Slope Inclination = 3.5H:1V

Slope =  $\frac{1}{3.5} = 28.6\%$

Slope Vertical Height = 50 feet

Slope Horizontal Length =  $50 \times 3.5 = 175$  feet

Slope Length =  $\sqrt{50^2 + 175^2} = 182$  feet

This worst case cover slope was analyzed as described below.

Based on guidance from the United States Environmental Protection Agency (USEPA, 1989), the soil erosion loss should be less than 2 tons/acre/year (t/ac/yr), as shown in Attachment #1.

**Method:**

In order to estimate the amount of soil loss on the Landfill B-18 cover due to water erosion, the Revised Universal Soil Loss Equation (RUSLE) was used. The RUSLE was developed by the United States Department of Agriculture, Natural Resources Conservation Service (NRCS) to estimate sheet-rill (both rill and inter-rill) erosion and it considers soil and vegetation type as well as physical and climatic features of the landfill area. The RUSLE is expressed mathematically as:

$$a = r \times k \times l \times s \times c \times p$$

where:

a = daily soil loss due to erosion (units of tons/acre/day);

r = rainfall and runoff erosivity factor;

k = soil erodibility factor;

l = slope length factor;

s = slope steepness factor;

c = cover-management factor; and

p = supporting practices factor.

The daily values of soil erosion loss ("a" values) are summed over an entire year to calculate the estimated annual soil erosion loss (in t/ac/yr). These soil erosion calculations are best made using a computer program.



**Kettleman Hills Facility – Landfill Unit B-18  
SOIL EROSION**

Project No.: 083-91887

Made By: RH

Date: 4-18-2008

Checked By: SS

Sheet: 2 of 3

Reviewed By: SS

The RUSLE – Version 2 (RUSLE2) computer program, developed by the NRCS, was used to calculate the potential soil erosion loss from the Landfill B-18 worst-case cover slope described above. The RUSLE2 program was downloaded from the following URL:

[http://fargo.nserl.purdue.edu/rusle2\\_dataweb/RUSLE2\\_Index.htm](http://fargo.nserl.purdue.edu/rusle2_dataweb/RUSLE2_Index.htm)

**Assumptions:**

*Climate:* The default climate “CA\_Kings\_R6” was selected from the Kings County climate zones in RUSLE2 as most accurately representing the climate at the Kettleman Hills Facility. The CA\_Kings\_R6 climate has an annual precipitation of 6.9 inches. For the period of July 1948 through December 2001, the mean annual precipitation for the site was 6.82 inches according to data obtained from the Western Regional Climate Center data base for the Kettleman Climatological Station (see Attachment #2).

*Soils:* The NRCS has identified three types of soils at the Kettleman Hills Facility. These soils are: Kettleman Loam (5-15% slopes), Kettleman Loam (15-30% slopes), and Kettleman-Cantua Complex (30-50% slopes). The properties of these three soil types, as listed in the RUSLE2 program files, are as follows:

<b>Soil Property</b>	<b>Kettleman Loam (5-15% Slopes)</b>	<b>Kettleman Loam (15-30% Slopes)</b>	<b>Kettleman-Cantua (30-50% Slopes)</b>
Sand Content	40%	40%	40%
Silt Content	38%	38%	38%
Clay Content	23%	23%	23%
Erodibility Factor (k)	0.37	0.37	0.37
RUSLE2 Soil No.	#127	#128	#129

Based on the similarity of the above-listed soils at the Kettleman Hills Facility, Kettleman Loam (15-30% Slopes, RUSLE2 Soil No. 128) was selected to model the Landfill B-18 cover soil. Sensitivity analyses indicated that the three soil types listed above result in the same calculated soil loss if all other variables are held constant.

**Calculations:**

The soil erosion calculations were performed using the RUSLE2 computer program downloaded from the above-listed URL. The calculations were performed for two scenarios:

- 1) Bare Slope – the final cover slope was modeled as a construction site with bare ground.
- 2) Vegetated Slope – the final cover slope was modeled as having permanent ground cover consisting of warm season grass that is not harvested. The amount of grass canopy was reduced 50% from the default (base) value, which increased the amount of calculated erosion.



**Kettleman Hills Facility – Landfill Unit B-18  
SOIL EROSION**

Project No.: 083-91887	Made By: RH
Date: 4-18-2008	Checked By: SS
Sheet: 3 of 3	Reviewed By: SS

**Results:**

The results of the RUSLE2 calculations are shown in Attachment #3, which contains the RUSLE2 Worksheet Erosion Calculation Record sheets for each of the two scenarios analyzed. A summary of the results is given in the table below:

<b>Scenario</b>	<b>Final Cover Slope Inclination</b>	<b>Computed Soil Erosion Loss (t/ac/yr)</b>
Bare Ground	3.5H:1V	9.2
Vegetated Ground	3.5H:1V	0.97

**Conclusions:**

Once vegetation is established on the Landfill B-18 final cover slopes, the amount of soil erosion loss is estimated to be approximately half of the recommended maximum of 2 t/ac/yr (USEPA, 1989). As discussed in the RUSLE2 program documentation, the results obtained from RUSLE2 are to be used as guides in evaluating soil erosion potential and mitigation measures for soil erosion. As shown in the current case for Landfill B-18, maintaining vegetative cover on the final landfill sideslopes is essential for limiting soil erosion loss to an acceptable amount.

**Commentary:**

Golder has been providing engineering services at the Kettleman Hills Facility for over 20 years, including over 10 years of annual post-closure inspections. During this period, several landfill units have been closed. Unit B-13, Unit B-15, and the Combined Closure Area (totaling over 100 acres) were closed in the early- to mid- 1990's. Based on observations of the final cover slopes of these areas, soil erosion does not appear to be a problem at the Kettleman Hills Facility when vegetation is present.

**Reference:**

United States Environmental Protection Agency, "Technical Guidance Document: Final Covers on Hazardous Waste Landfills and Surface Impoundments," EPA/530-SW-89-047, July 1989.

**ATTACHMENT #1**  
**SOIL EROSION ANALYSES**

United States  
Environmental Protection  
Agency

Office of Solid Waste and  
Emergency Response  
Washington DC 20460

EPA/530-SW-89-047  
July 1989



# Technical Guidance Document:

## Final Covers on Hazardous Waste Landfills and Surface Impoundments

EPA/530-SW-89-047  
July 1989

TECHNICAL GUIDANCE DOCUMENT

FINAL COVERS ON HAZARDOUS WASTE LANDFILLS  
AND SURFACE IMPOUNDMENTS

Office of Solid Waste and Emergency Response  
U.S. Environmental Protection Agency  
Washington, DC 20460

In cooperation with

RISK REDUCTION ENGINEERING LABORATORY  
OFFICE OF RESEARCH AND DEVELOPMENT  
U.S. ENVIRONMENTAL PROTECTION AGENCY  
CINCINNATI, OHIO 45268

Table 2. Synopsis of Minimum Technology Guidance for Covers

Layer	Thickness	Slope	Requirements
<u>Top Layer</u>			
Vegetation	--	--	Persistent, drought-resistant, adapted to local conditions.
OR			
Surface Armor	5-10 in. (13-25 cm)		Cobbles, gravel.
ON			
Soil	≥ 24 in. (≥ 60 cm)	3-5%	Erosion rate < 2 ton/acre/yr (5.5 MT/ha/yr). } *
<u>Drainage Layer</u>			
Soil	≥ 12 in. (≥ 30 cm)	≥ 3%	SP (USCS) soil K > 1 x 10 <sup>-2</sup> cm/s; gravel toe drain.
OR			
Geosynthetic	variable	≥ 3%	Performance equivalent to soil, hydraulic transmissivity ≥ 3 x 10 <sup>-5</sup> m <sup>2</sup> /sec.
<u>Low-Permeability Layer</u>			
FML	≥ 20 mils (≥ 0.5 mm)	≥ 3%	In EPA Report No. EPA 600/2-88-052.
ON			
Low-Permeability Soil	≥ 24 in. (≥ 60 cm)	≥ 3%	In-place K < 1 x 10 <sup>-7</sup> cm/s and test fill.
<u>Optional Layers (site-specific design)</u>			
Gas Vent Layer	≥ 12 in. (≥ 30 cm)	≥ 2%	Similar to drainage layer.
Biotic Barrier	animal or root-dependent	--	Large materials, e.g., cobbles.

## 2. TOP LAYER

The Agency recommends a two-component top layer for a landfill cover system (Figure 1). The upper component should be vegetation or other surface treatment, designed to impede erosion but allowing surface runoff from major storm events. The Agency believes that, in most cases, vegetation underlain by soil, at least part of which is topsoil, will best accomplish these objectives. However, in some areas the prevailing climate may inhibit the establishment and maintenance of vegetation, or a planned alternative use of the site may preclude vegetation. In those cases, an armored surface without vegetation (Figure 2), and underlain by fill soil, might be used if it will minimize erosion and abrasion of the cover and allow, to the maximum practicable extent, surface drainage off the cover.

### 2.1 DESIGN

The Agency recommends that the vegetation component of the top layer meet the following specifications:

- o Locally adapted perennial plants.
- o Resistant to drought and temperature extremes.
- o Roots that will not disrupt the low-permeability layer.
- o Capable of thriving in low-nutrient soil with minimum nutrient addition.
- o Sufficient plant density to minimize cover soil erosion to no more than 2 tons/acre/year (5.5 MT/ha/yr), calculated using the USDA Universal Soil Loss Equation. }\*
- o Capable of surviving and functioning with little or no maintenance.

In landfill situations where the environment or other considerations make it inappropriate for maintaining sufficiently dense vegetation, armoring material may be substituted as the upper component of the top layer or in rare cases the whole layer. It is recommended that the material possess the following characteristics:



- o capable of remaining in place and minimizing erosion of itself and the underlying soil component during extreme weather events of rainfall and/or wind;
- o capable of accommodating settlement of the underlying material without compromising the purpose of the component;
- o surface slope approximately the same as the underlying soil (at least 3 percent slope); and
- o capable of controlling the rate of soil erosion from the cover to no more than 2 tons/acre/year (5.5 MT/ha/yr), calculated by using the USDA Universal Soil Loss Equation. }

\*  
}

Agency-recommended specifications for the lower soil component of the top layer include the following:

- o for vegetation support, a minimum thickness of 60 cm (24 in.) including at least 15 cm (6 in.) of topsoil (soil of lower quality may be used beneath an armored surface); greater total thickness where required, e.g., where maximum frost penetration exceeds this depth, or where greater plant-available water storage is necessary or desirable;
- o medium texture to facilitate seed germination and plant root development;
- o final top slope, after allowance for settling and subsidence, of at least 3 percent, but no greater than 5 percent, to facilitate runoff while minimizing erosion; and
- o minimum compaction to facilitate root development and sufficient infiltration to maintain growth through drier periods.

The owner or operator of the landfill should prepare a separate section specific to monitoring construction of the top layer to be included in the construction quality assurance (CQA) plan.

## 2.2 DISCUSSION

### 2.2.1 Upper Component of Top Layer

As noted in the design recommendations above, the upper component of the top layer may be vegetation (Agency-preferred, where possible) or other erosion-impeding materials. These are discussed separately below.

and, in general, increase the long-term maintenance of the cover system. Owners and operators using final slopes based on site-specific conditions should determine that the slopes will not result in the formation of erosion rills and gullies and will limit total erosion to less than 2.0 tons/acre/year (5.5 MT/ha/yr). The U.S. Department of Agriculture's Universal Soil Loss Equation (USLE) is recommended as the tool for use in evaluating erosion potential (EPA, 1982a). The Agency believes that a maximum erosion rate of 2.0 tons/acre/year (5.5 MT/ha/yr) is realistically achievable for a wide range of soils, climates, and vegetation. The Agency also believes that reliance on this criterion will minimize gully development and cover maintenance.



**ATTACHMENT #2**  
**SOIL EROSION ANALYSES**

# KETTLEMAN STN, CALIFORNIA (044536)

## Period of Record Monthly Climate Summary

Period of Record : 7/1/1948 to 12/31/2001

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Annual
Average Max. Temperature (F)	55.2	61.9	67.3	75.1	84.3	93.1	99.2	97.1	91.3	80.7	66.6	55.9	77.3
Average Min. Temperature (F)	38.5	43.3	45.8	50.0	56.2	63.3	69.2	67.9	63.7	56.2	46.8	39.5	53.4
Average Total Precipitation (in.)	1.42	1.37	1.13	0.61	0.29	0.05	0.01	0.03	0.19	0.28	0.64	0.80	6.82
Average Total Snow/Fall (in.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Average Snow Depth (in.)	0	0	0	0	0	0	0	0	0	0	0	0	0

Percent of possible observations for period of record.

Max. Temp.: 60.6% Min. Temp.: 60.1% Precipitation: 97.2% Snowfall: 97.4% Snow Depth: 97.4%

Check [Station Metadata](#) or [Metadata graphics](#) for more detail about data completeness.

Western Regional Climate Center, [wrgcc@dri.edu](mailto:wrgcc@dri.edu)

**ATTACHMENT #3**  
**SOIL EROSION ANALYSES**



## RUSLE2 Worksheet Erosion Calculation Record

Info: Kettleman Hills Facility - Landfill Unit B-18  
 3.5H:1V, 50-foot-tall final cover slopes (bare)

**Inputs:**

Owner name	Location
Waste Management, Inc.	California\Kings County\CA_Kings_R6

Location	Soil	Slope length (horiz)	Avg. slope steepness, %
California\Kings County\CA_Kings_R6	128 KETTLEMAN LOAM, 15 TO 30 PERCENT SLOPES\KETTLEMAN loam 85%	182	28.6

**Outputs:**

Management	Contouring	Strips / barriers	Diversion/terrace, sediment basin	Soil loss erod. portion, t/ac/yr	Soil detachment, t/ac/yr	Cons. plan. soil loss, t/ac/yr	Sed. delivery, t/ac/yr
Bare ground	a. rows up-and-down hill	(none)	(none)	9.2	9.2	9.2	9.2



## RUSLE2 Worksheet Erosion Calculation Record

Info: Kettleman Hills Facility - Landfill Unit B-18  
 3.5H:1V, 50-foot-tall final cover slopes (vegetated)

**Inputs:**

Owner name	Location
Waste Management, Inc.	California\Kings County\CA_Kings_R6

Location	Soil	Slope length (horiz)	Avg. slope steepness, %
California\Kings County\CA_Kings_R6	128 KETTLEMAN LOAM, 15 TO 30 PERCENT SLOPES\KETTLEMAN loam 85%	182	28.6

**Outputs:**

Management	Contouring	Strips / barriers	Diversion/terrace, sediment basin	Soil loss erod. portion, t/ac/yr	Soil detachment, t/ac/yr	Cons. plan. soil loss, t/ac/yr	Sed. delivery, t/ac/yr
Warm season grass; not harvested	a. rows up-and-down hill	(none)	(none)	0.97	0.97	0.97	0.97

**APPENDIX J**  
**SURFACE WATER DRAINAGE ANALYSES**

<b>APPENDIX J.1</b>	<b>PHASES I AND II HYDROLOGY AND DESIGN CRITERIA</b>
<b>APPENDIX J.2</b>	<b>PHASES I AND II RUN-ON CONTROL</b>
<b>APPENDIX J.3</b>	<b>PHASES I AND II RUN-OFF CONTROL AND RUN-OFF CONTROL FOR PHASE IIIA</b>
<b>APPENDIX J.4</b>	<b>FINAL CLOSURE DRAINAGE</b>



**APPENDIX J.1**  
**PHASES I AND II HYDROLOGY AND DESIGN CRITERIA**

# ENVIRONMENTAL SOLUTIONS, INC.

By JPM Date 8-15-90 Subject LANDFILL B-18 Sheet No. 1 of 59  
 Chkd. By \_\_\_\_\_ Date \_\_\_\_\_ DRAINAGE DESIGN Proj. No. 89.977

## TABLE OF CONTENT

I	HYDROLOGY AND DESIGN CRITERIA	} Appendix J.1	2/59
	CRITERIA AND METHODOLOGY		2/59
	TRIANGULAR DITCH CAPACITY		5/59
	DROP INLET CAPACITY		6/59
II	PHASE I RUN-ON CONTROL	} Appendix J.2	13/59
III	PHASE II RUN-ON CONTROL		22/59
IV	PHASE I RUN-OFF CONTROL	} Appendix J.3	25/59
V	PHASE II RUN-OFF CONTROL		28/59
VI	POST CLOSURE DRAINAGE	} Not Included (superseded by Appendix J.4)	38/59
VII	RETENTION BASIN SIZING		47/59
VIII	EXHIBITS	} Appendix J.3	51/59

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 7-24-90 Subject LANDFILL B-18 DRAINAGE Sheet No. 2 of 59  
Chkd. By N.A. Date 8-14-90 SYSTEM Proj. No. 89-977

PURPOSE: DESIGN LANDFILL B-18 DRAINAGE SYSTEM

DESIGN CRITERIA: 1. MAJOR DRAINAGE FEATURES ARE SIZED FOR PROBABLE MAXIMUM PRECIPITATION.

2. LESS CRITICAL DRAINAGE FEATURES ARE SIZED FOR 25-YEAR STORM.

METHODOLOGY: MAXIMUM DISCHARGE FOR DIVERSION DITCHES AND CONVERTS ARE DETERMINED BY THE RATIONAL METHOD, WHICH TAKES THE FORM OF

$$Q = CL A$$

WHERE

Q = MAXIMUM DISCHARGE (CFS)  
L = RAINFALL INTENSITY (IN/HR)  
A = DRAINAGE AREA  
C = RUNOFF COEFFICIENT

DIVERSION PIPES/DITCHES WILL BE SIZED USING THE MANNING'S FORMULA WHICH TAKES THE FORM OF

$$Q = \frac{1.486}{n} A R^{2/3} S^{1/2}$$

WHERE

R = HYDRAULIC RADIUS  
S = DITCH BED SLOPE  
Q = MAXIMUM DISCHARGE CAPACITY  
n = ROUGHNESS COEFFICIENT  
A = EFFECTIVE DRAINAGE AREA

# ENVIRONMENTAL SOLUTIONS, INC.

By UPI Date 7-24-90 Subject LANDFILL B-18, RUN ON & Sheet No. 3 of 59  
hkd. By N.A. Date 8-14-90 RUNOFF CONTROL Proj. No. 89-977

## DETERMINATION OF TIME OF CONCENTRATION

TIME OF CONCENTRATION MAY BE DETERMINED BY

$$1. T_c = \left( \frac{11.9 L^3}{H} \right)^{0.465}$$

(REFERENCE)

WHERE

$T_c$  = TIME OF CONCENTRATION

$L$  = LENGTH OF FLOW PATH (MILES)

$H$  = ELEVATION DIFFERENCE (FEET)

OR

$$2. T_c = L / \left( \frac{1.486 R^{2/3} S^{1/2}}{n} \right)$$

WHERE

$L$  = LENGTH OF FLOW PATH

$n$  = ROUGHNESS COEFFICIENT

$R$  = HYDRAULIC RADIUS

$S$  = DITCH BED SLOPE

## DETERMINATION OF RUNOFF COEFFICIENT

IF THE DRAINAGE BASIN UNDER CONSIDERATION CONSISTS OF MATERIALS WITH DIFFERENT SURFACE CHARACTERISTICS, A COMPOSITE RUNOFF COEFFICIENT WILL BE USED. THE COMPOSITE RUNOFF COEFFICIENT  $C_c$  MAY BE DETERMINED BY:

$$C_c = \frac{\sum C_i A_i}{\sum A_i}$$

WHERE  $C_i$  &  $A_i$  IS THE RUNOFF COEFFICIENT AND THE SURFACE AREA FOR EACH INDIVIDUAL MATERIAL, RESPECTIVELY. TYPICAL RUNOFF COEFFICIENT VALUES FOR DIFFERENT MATERIALS ARE SHOWN IN EXHIBIT 1.

WITH THE ON-SITE MATERIAL IS SIMILAR TO THE TYPE C

SOIL IN SOLANO COUNTY, A RUNOFF COEFFICIENT  $C$  OF 0.4 IS USED

# ENVIRONMENTAL SOLUTIONS, INC.

By dpi Date 8-12-90 Subject LANDFILL B-1B Sheet No. 4 of 59  
Chkd. By N.A. Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

1  
2 CULVERT DESIGN IS BASED ON INLET CONTROL MONOGRAPH  
3  
4 (EXHIBIT 2).

5  
6 SHORT-TERM RAINFALL INTENSITY / DURATION RELATIONSHIPS ARE  
7  
8 BASED ON PMP RECORD FOR COALINGA STATION (EXHIBIT 3)  
9  
10 THE RAINFALL INTENSITY DURATION CURVE IS SHOWN ON  
11  
12 EXHIBIT 4. EXHIBIT 5 ALSO SHOWS THE THE 25-YEAR STORM  
13  
14 RAINFALL INTENSITY / DURATION RELATIONSHIPS FOR COALINGA STATION  
15  
16 FOR CULVERT DESIGN. EXHIBIT 6 SHOWS THE RELATIVE  
17  
18 LOCATION BETWEEN THE SITE AND THE COALINGA STATION.  
19  
20 EXHIBIT 7 SHOWS THE PRECIPITATION DEPTH - DURATION - FREQUENCY  
21  
22 DATA USED TO DEVELOPE THE RAINFALL INTENSITY CURVE.  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

# ENVIRONMENTAL SOLUTIONS, INC.

By JPK Date 7-31-90 Subject LANDFILL B-B DRAINAGE Sheet No. 5 of 59  
 Chkd. By N.A. Date 8-14-90 DESIGN Proj. No. 89-97


## TRIANGULAR DITCH CAPACITY

(W=5 FT)

AF = FLOW AREA (ASSUME FLOW FULL)

P<sub>w</sub> = WETTED PERIMETER =  $2 \times \sqrt{2.5^2 + H^2}$

R = HYDRAULIC RADIUS = AF/P<sub>w</sub>



$Q = \frac{1.486}{n} A R^{2/3} S^{1/2}$

n = 0.013 FOR SMOOTH ASPHALT  
(EXHIBIT 9)

TYPE	H (FT)	AF (FT <sup>2</sup> )	P <sub>w</sub> (FT)	R (FT)	Q (CFS)	V (FPS)
2	1	2.5	5.38	0.46	171.2 S <sup>1/2</sup>	68.52 S <sup>1/2</sup>
3	1.25	3.13	5.59	0.56	243.2 S <sup>1/2</sup>	77.66 S <sup>1/2</sup>
4	1.5	3.75	5.83	0.64	319.4 S <sup>1/2</sup>	84.89 S <sup>1/2</sup>
5	2	5	6.40	0.78	484.5 S <sup>1/2</sup>	96.9 S <sup>1/2</sup>
6	2.5	6.25	7.07	0.88	658.0 S <sup>1/2</sup>	105.3 S <sup>1/2</sup>
7	3	7.5	7.81	0.96	834.2 S <sup>1/2</sup>	111.2 S <sup>1/2</sup>

## BROW DITCH (see page 17)


W = 2 FT TYPE 1

AF = 1 FT<sup>2</sup>

P<sub>w</sub> =  $2 \times 1 \times \sqrt{2} = 2.83$  FT

R = 0.35 FT

Q = 57.1 S<sup>1/2</sup> (CFS)



# ENVIRONMENTAL SOLUTIONS, INC.

By JRL Date 8-2-90 Subject LANDFILL B-18 DRAINAGE Sheet No. 6 of 59  
Chkd. By N.A. Date 9-14-90 DESIGN Proj. No. 89977

## DROP INLET CAPACITY

USING THE ORIFICE EQUATION, DROP INLET CAPACITY MAY BE ESTIMATED AS

$$Q = CA \sqrt{2gh}$$

WHERE

- C = INLET COEFFICIENT = 0.61
- g = 32.2 ft/sec<sup>2</sup>
- h = HEAD (ft)
- A = PIPE AREA (ft<sup>2</sup>)

PIPE DIAMETER	Q (cfs)
12"	3.78 $\sqrt{h}$
18"	8.50 $\sqrt{h}$
24"	15.1 $\sqrt{h}$
30"	24.0 $\sqrt{h}$


1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
34  
35  
36

# ENVIRONMENTAL SOLUTIONS, INC.

By JTP Date 6-12-90 Subject LANDFILL B-18 DRAINAGE Sheet No. 7 of 59  
Chkd. By KIA Date 8-14-90 DESIGN Proj. No. 82-977

1  
2 FIGURES 1 AND 2 SHOW THE RUN-OFF AREAS  
3  
4 FOR LANDFILL B-18 PHASE I AND PHASE II DEVELOPMENT.  
5  
6 PAGES 10 THROUGH 12 TABULATED THE AREA, AND MAXIMUM  
7  
8 DISCHARGE FOR THE RUN-OFF AREAS.  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36





LEGEND

— SURFACE WATER DRAINAGE AREA BOUNDARY

INCLUDING AREA FROM SOUTH STOCKPILE

FIGURE 2

SURFACE WATER DRAINAGE AREA MAP

LANDFILL UNIT B-18  
KETTLEMAN HILLS FACILITY  
ENVIRONMENTAL SOLUTIONS INC.

15/B 2601




FIGURE 2

SURFACE WATER DRAINAGE  
AREA MAP  
LANDFILL UNIT 3-12

ENVIRONMENTAL SOLUTIONS, INC.

Run-off **DRAINAGE DESIGN CALCULATION** for  
Phase I and Phase II

BY TRC DATE 8-6-90 SUBJECT LANDFILL B-18 DRAINAGE SHEET NO 10 OF 59  
CHKD N.A. DATE 8-14-90 DESIGN PROJECT NO 89.977

(see page 3) (see Exhibit 4)

DRAINAGE AREA	AREA (Ac)	LONGEST FLOW PATH (MI)	ELEVATION DIFFERENCE (FI)	TIME OF CONCENTRATION (Min)	RAINFALL (2) INTENSITY (in/Hr)	RUNOFF COEFFICIENT	MAXIMUM DISCHARGE (cfs)
A1	1.86	0.1	94	2	7.92 <sup>(1)</sup>	0.4	5.9
CUTSLOPE	0.19	0.05	38		7.92	0.4	0.6
TOTAL	2.05						
A2	0.96	0.08	74	2	7.92 <sup>(1)</sup>	0.4	3.0
CUTSLOPE	0.29						
TOTAL	1.25						
A4	4.35	0.1	153	2	7.92 <sup>(1)</sup>	0.4	13.8
CUTSLOPE	0.55						
TOTAL	4.90						
A5	2.65	0.07	135	1	7.92 <sup>(1)</sup>	0.4	8.4
CUTSLOPE	0.73						
TOTAL	3.38						
A6	1.41	0.08	90	2	7.92 <sup>(1)</sup>	0.4	4.5
CUTSLOPE	0.62						
TOTAL	2.03						
A7	3.41	0.07	96	1	7.92 <sup>(1)</sup>	0.4	10.8
CUTSLOPE	0.36						
TOTAL	3.77						
AB	8.77	0.15	115	3	7.92 <sup>(1)</sup>	0.4	27.8
CUTSLOPE	0.14						
TOTAL	8.91						

Notes:  
1. Assumed minimum time of concentration. (5 minutes)  
2. See Figure 1.

## DRAINAGE DESIGN CALCULATION

BY JPL DATE 8-6-90 SUBJECT LANDFILL B-18 SHEET NO 11 OF 59  
 CHKD N.A. DATE 8-14-90 DRAINAGE DESIGN PROJECT NO 89-977

DRAINAGE AREA	AREA (Ac)	LONGEST FLOW PATH (Mi)	ELEVATION DIFFERENCE (Ft)	TIME OF CONCENTRATION (Min)	RAINFALL (2) INTENSITY (in/Hr)	RUNOFF COEFFICIENT	MAXIMUM DISCHARGE (cfs)
A9	1.91	0.1	100	2	7.92 <sup>(1)</sup>	0.4	6.1
CUTSLOPE	0.15						
TOTAL	2.06						
A10	2.60	0.14	40	4	7.92 <sup>(1)</sup>	0.4	8.2
CUTSLOPE	0.22						
TOTAL	2.82						
A11	0.29						
A12	4.02	0.27	120	6	7.00	0.4	11.3
(STOCKPILE ACCESS ROAD AND SIDE SLOPES)							
TOTAL	35.48						
A2	1.08	0.05	38	1	7.92 <sup>(1)</sup>	0.4	3.4
CUTSLOPE	0.58	0.09	38		7.92	0.4	
ROAD	0.91						
TOTAL	2.37						
A13	1.96				7.92 <sup>(1)</sup>	0.9	13.9
CUTSLOPE	0.66				7.92 <sup>(1)</sup>	0.9	
TOTAL	2.62						
A14	7.7	0.20	180	5	7.92	0.4	24.9
A15	10.8	0.22	98	5	7.92	0.4	34.2
A16	1.81	0.09	70	2	7.92 <sup>(1)</sup>	0.4	5.73

- Notes:
1. Assumed minimum time of concentration. (5 minutes)
  2. See Figure 1.



**APPENDIX J.2**  
**PHASES I AND II RUN-ON CONTROL**

# ENVIRONMENTAL SOLUTIONS, INC.

By TPI Date 8-6-90 Subject LANDFILL B-1B Sheet No. 13 of 59  
Chkd. By N.A. Date 8-14-90 DRAINAGE DESIGN Proj. No. 02-977

## RUN-ON CONTROL PERIMETER DITCH (PHASE 1) FIGURE 3

DRAINAGE AREAS A1 & A3 DESIGN POINT A

TOTAL AREA: 3.30 ACRES (see page 10)

FLOW LENGTH: 890 ft

USE TYPE 2 V-DITCH AND 0.6% SLOPE  $D=1.0'$

$$V = 68.52 S^{1/2} = 68.52 \times \sqrt{0.006} = 5.3 \text{ fps}$$

$$\text{TIME OF CONCENTRATION } T_c = 2 + \frac{890}{5.3} = 4.8 \text{ min. SAY } 5$$

RAINFALL INTENSITY: 7.92 in/hr (see Exhibit 4)

$$Q = 0.4 \times 3.3 \times 7.92 = 10.4 \text{ cfs}$$

$$Q_{\text{DESIGN}} = 171.3 S^{1/2} = 171.3 \times \sqrt{0.006} = 13.3 > 10.4 \text{ cfs O.K.}$$

(see page 5)

DRAINAGE AREAS A1, A3 & A6 DESIGN POINT B

TOTAL AREA: 13.61 ACRES

FLOW LENGTH: 2270 ft

USE TYPE 5 V-DITCH AND 0.6% SLOPE  $D=2.0 \text{ ft}$

$$V = 96.9 S^{1/2} = 96.9 \times \sqrt{0.006} = 7.5 \text{ fps}$$

$$T_c = 4.8 + \frac{2270}{7.5} = 7.5 \text{ min}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-6-90 Subject LANDFILL B-18 Sheet No. 14 of 59  
Chkd. By N.A. Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-077

1  
2 RAINFALL INTENSITY = 6.2 in/hr

3  
4  $Q = 0.4 \times 13.61 \times 6.2 = 33.8 \text{ cfs.}$

5  
6  $Q_{DESIGN} = 484.5 S^{1/2} = 484.5 \times \sqrt{0.006} = 37.5 \text{ cfs} > 33.8 \text{ cfs O.K.}$

7  
8  
9 DRAINAGE AREAS A1, A3, A7 DESIGN POINT C

10  
11 TOTAL AREA = 17.62 acres

12  
13 FLOW LENGTH = 2750 ft

14  
15 USE TYPE 6 V-DITCH AND 0.6% slope D=2.5

16  
17  $V = 105.3 S^{1/2} = 105.3 \times \sqrt{0.006} = 8.15$

18  
19  $t_c = 7.8 + \frac{480}{8.15} = 8.8 \text{ min}$

20  
21 RAINFALL INTENSITY = 5.8 in/hr

22  
23  $Q = 0.4 \times 17.62 \times 5.8 = 40.9 \text{ cfs}$

24  
25  $Q_{DESIGN} = 658.0 \times \sqrt{0.006} = 50.9 \text{ cfs} > 40.9 \text{ O.K.}$



# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-6-90 Subject LANDFILL B-18 Sheet No. 15 of 59  
Chkd. By M.A. Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

DRAINAGE AREAS A1, A3 & A8 DESIGN POINT D

TOTAL AREA: 26.53 AC.

FLOW LENGTH: 2930 ft.

USE TYPE 7 V-DITCH AND 0.6% SLOPE D=3

$$V = 111.2 S^{1/2} = 111.2 \times \sqrt{0.0075} = 9.6 \text{ fps}$$

$$t_c = 8.8 + \frac{1.80}{9.6} = 9.7 \text{ min}$$

RAINFALL INTENSITY = 5.8 IN/HR

$$Q = 0.4 \times 26.53 \times 5.8 = 61.5 \text{ cfs}$$

$$Q_{\text{DESIGN}} = 834.2 \times \sqrt{0.006} = 64.6 \text{ cfs} \quad \text{OK}$$

DRAINAGE AREAS A1, A3 & A11 DESIGN POINT: E

TOTAL AREA = 31.64 AC

FLOW LENGTH: 2945 ft

$$t_c = 9.7 \text{ min}$$

RAINFALL INTENSITY = 5.8 IN/HR

$$Q = 31.64 \times 0.4 \times 5.8 = 73.4 \text{ cfs}$$

TYPE 7 V-DITCH AND 0.8% SLOPE

$$Q = 834.2 \times \sqrt{0.008} = 74.6 \text{ cfs} > 73.4 \text{ cfs} \quad \text{OK}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-7-90 Subject LANDFILL B-18 Sheet No. 16 of 59  
 Chkd. By N.A. Date 8-14-90 DRAINAGE DESIGN Proj. No. 89977

DRAINAGE AREAS A1, A3-A9, A11, A12, A14, A15, A16 DESIGN POINT F

AREAS A1, A3-A11, A11

$$T_c = 9.1 \text{ min}, L = 5.8 \text{ in/hr}, Q = 66.8 \text{ cfs}$$

AREAS A12 & A14

$$A_{12} = T_c = 6, L = 7, Q = 11.3 \text{ (see p. 11)}$$

$$A_{14} = T_c = 5, L = 7.92, Q = 24.3 \text{ (see p. 11)}$$

$$Q_{12-14} = 24.3 + \frac{7.92}{7} \times \frac{5}{6} \times 11.3 = 34.9 \text{ cfs}$$

Q FOR A1, A3-A11, A12, A14

$$Q = 73.4 + \frac{5.8}{7.92} \times 34.9 = 98.9 \text{ cfs}$$

Q FOR A1, A3-A11, A12, A14, AND A15

$$Q = 98.9 + \frac{5.8}{7.92} \times 34.2 = 123.9 \text{ cfs}$$

Q FOR A1, A3-A11, A12, A14, A15 AND A16

$$Q = 123.9 + \frac{5.8}{7.92} \times 5.73 = 128.1 \text{ cfs}$$

USE TYPE 5 V-DITCH WITH 8.3% SLOPE

$$Q = 484.5 \sqrt{0.083} = 139.6 \text{ cfs} > 128.1 \text{ cfs}$$



# ENVIRONMENTAL SOLUTIONS, INC.

By DRI Date 8-7-90 Subject LANDFILL B-1B DRAINAGE Sheet No. 18 of 59  
 Chkd. By N.A. Date 9-14-90 DESIGN Proj. No. 89-977

DRAINAGE AREA A2

DESIGN POINT G.


SWALE DESIGN

AREA : A2 = 1.08 (see p. 1)  
 SLOPE = 0.58  
 ROAD = 0.71  
 TOTAL = 2.37

RUN-OFF COEFFICIENT:  $\frac{1.08 \times 0.4 + 0.58 \times 0.4 + 0.71 \times 0.9}{2.37} = 0.55$

RAINFALL INTENSITY = 7.92 IN/HR (5 MIN. <sup>minimum</sup> TIME OF CONCENTRATION)

$Q = 0.55 \times 2.37 \times 7.92 = 10.3 \text{ cfs}$



TRY SWALE AS SHOWN:

$A_f = 0.5 \times 5 \times 0.5 = 1.25 \text{ ft}^2$

$P_w = 2 \times \sqrt{0.5^2 + 2.5^2} = 5.1 \text{ ft}$

$R = \frac{1.25}{5.1} = 0.25 \text{ ft}$

Slope = 0.09 (Existing shallowest slope in the drainage area)

$Q = \frac{1.486}{0.013} \times 1.25 \times 0.25^{2/3} \times \sqrt{0.09}$

n = 0.013 EXHIBT  
 TROWEL FINISH CONCRETE  
 OR EQUIVALENT

= 16.7 cfs > 10.3 cfs O.K.

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-7-90 Subject LANDFILL B-1B Sheet No. 19 of 59  
Chkd. By A.A. Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-917

DRAINAGE AREAS AZ & A13

DESIGN POINT H (see p. 11)

$$\text{TOTAL AREA} = 4.28$$

$$\text{TIME OF CONCENTRATION} = < 5 \text{ min}$$

$$\text{RAINFALL INTENSITY} = 7.92 \text{ IN/HR (USE MIN 5 MIN)}$$

$$C = \frac{0.4 \times 1.08 + 0.58 \times 0.4 + 0.9 \times (0.66 + 1.96)}{4.28} = 0.71$$

$$Q = 0.71 \times 7.92 \times 4.28 = 24.0 \text{ cfs}$$

USE TYPE 3 V-DITCH AND 1% SLOPE  $D=1.25$  (see p. 5)

$$Q_{\text{DESIGN}} = 24.3 \times \sqrt{0.01} = 24.3 \text{ cfs} > 24.0 \text{ O.K.}$$

DRAINAGE AREAS AZ, A13, AND SLOPE

DESIGN POINT I

$$\text{TOTAL AREA} = 4.33 + 0.66 = 4.99$$

$$\text{TIME OF CONCENTRATION} = < 5 \text{ min Use 5 minutes}$$

$$\text{RAINFALL INTENSITY} = 7.92 \text{ IN/HR. see Exhibit 4}$$

$$C = \frac{0.4 (1.08 + 0.58 + 0.66) + 0.9 (0.66 + 1.96)}{4.99} = 0.66$$

$$Q = 0.66 \times 4.99 \times 7.92 = 26.08$$

USE TYPE 2 V-DITCH AND 8% SLOPE

$$Q_{\text{DESIGN}} = 171.3 \times \sqrt{0.08} = 48.5 \text{ cfs} > 26.0 \text{ cfs O.K.}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By JAW Date 8-7-90 Subject LANDFILL B-1B Sheet No. 20 of 59  
 Chkd. By N.A. Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

## Design pt. J SWALE DESIGN

USE SWALE SIZE AS SHOWN IN CLAY PROCESSING AREA

$$A_T = 0.5 \times 40 \times 1 = 20 \text{ ft}^2$$

$$P_w = 2 \times \sqrt{1 + 20^2} = 40 \text{ ft}$$

$$R = \frac{20}{40} = 0.5 \text{ ft}$$

$$Q = \frac{1.486}{0.022} \times 0.5^{\frac{2}{3}} \times 20 \times \sqrt{0.015}$$

$$= 104 \text{ cfs} > 26.4 \text{ cfs} \quad \text{OK.}$$



slope = 0.015

n = 0.022

FOR EARTH CLEAN, AFTER WEATHERING

## CUTSLOPE AND ACCESS ROAD EAST OF B-1B STOCK PILE ACCESS ROAD

TOTAL AREA: 1.47 AC.

DESIGN POINT K

ASSUMED RAINFALL = 7.92 IN/HR

5 MIN TIME OF CONCENTRATION

$$C = \frac{0.99 \times 0.4 + 0.48 \times 0.9}{1.47} = 0.56$$

$$Q = 0.56 \times 1.47 \times 7.92 = 6.55$$

USE TYPE 2 V-DITCH & 6% SLOPE (SEE P. 5)

$$Q = 171.3 \times \sqrt{0.06}$$

$$= 429 \text{ cfs} > 6.55 \text{ cfs} \quad \text{O.K.}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-8-90 Subject LANDFILL B-18 Sheet No. 21 of 59  
hkd. By KLA Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

DRAINAGE AREA A18 DESIGN POINT L

$$Q = 10 \text{ cfs} \quad (\text{see p. 12})$$

USE TYPE 2 V-DITCH @ 0.5 % SLOPE (see p. 5)

$$Q_{\text{DESIGN}} = 171.3 \times \sqrt{0.005} = 12.1 \text{ cfs} > 10 \text{ cfs} \quad \text{O.K.}$$

DRAINAGE AREAS A18 & A19 DESIGN POINT M

$$Q = 10 + 4.1 = 14.1 \quad T_{18} = T_{19} = 5 \text{ min} \quad (\text{see p. 12})$$

USE TYPE 2 V-DITCH @ 1 % SLOPE (see p. 5)

$$Q_{\text{DESIGN}} = 171.3 \times \sqrt{0.01} = 17.1 \text{ cfs} > 14.1 \text{ cfs} \quad \text{OK}$$

DRAINAGE AREAS A17 ~ A20 DESIGN POINT N

$$Q = 12.9 + 10 + 4.1 + 1.3 = 28.3 \text{ cfs} \quad T_{17} = T_{18} = T_{19} = T_{20} = 5 \text{ min} \quad (\text{see p. 12})$$

USE TYPE 4 V-DITCH AND 0.8 % SLOPE (see p. 5)

$$Q_{\text{DESIGN}} = 319.4 \times \sqrt{0.008} = 28.6 \text{ cfs} > 28.3 \text{ cfs} \quad \text{OK}$$

DRAINAGE AREA A17 ~ A21 DESIGN POINT O

$$Q = 12.9 + 10 + 4.1 + 1.3 + 1.71 = 30.01 \text{ cfs} \quad (\text{see p. 12})$$

USE TYPE 4 V-DITCH AND 1 % SLOPE see p. 5

$$Q_{\text{DESIGN}} = 319.4 \times \sqrt{0.01} = 31.9 \text{ cfs} > 30.01 \text{ cfs} \quad \text{OK}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By J.P.L. Date 8-8-90 Subject LANDFILL B-18 Sheet No. 22 of 59  
Chkd. By M.A. Date 9-14-90 DRAINAGE DESIGN Proj. No. 60-977

RUN-ON CONTROL PERIMETER DITCH PHASE II FIGURE 4

DRAINAGE AREAS A1, A2 & A16 DESIGN POINT A

TOTAL Q = 121.5 cfs (see p. 16)

USE TYPE 6 V-DITCH AND 3.6% slope (see p. 5)

$$Q = 658 \times \sqrt{0.036} = 124.8 \text{ cfs} > 121.5 \text{ cfs} \text{ OK.}$$



2/23/51

DEEP	INLET	SCHEDULE	PIPE DIA. (IN)	PIPE LENGTH (FT)
D1	1	12	30	30
D2	1	24	30	30
D3	1	18	60	45
D4	1.5	12	30	20
D5	1.5	30	18	40
D6	1	18		




FIGURE 3  
**RUN-OFF DRAINAGE PLAN**  
**PHASE I**  
 ENVIRONMENTAL SOLUTIONS, INC.




FIGURE 4  
 RUN-ON DRAINAGE PLAN  
 PHASE II  
 CMMI KETTLEMAN HILL FACILITY  
 KINGS COUNTY, CALIFORNIA  
 ENVIRONMENTAL SOLUTIONS INC.

LEGEND  
 - - - - - SURFACE WATER DRAINAGE AREA BOUNDARY

**APPENDIX J.3**  
**PHASES I AND II RUN-OFF CONTROL AND RUN-OFF CONTROL FOR**  
**PHASE IIIA**

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-8-90 Subject LANDFILL E-18 Sheet No. 25 of 59  
Chkd. By N.A. Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

## RUN-OFF CONTROL PERIMETER DITCHES PHASE I FIGURE 5

WESTERN & SOUTHERN BENCH ROAD DESIGN POINT A

LENGTH = 2600 FT WIDTH = 40 FT

AREA = 2.38 ACRES RUNOFF COEFFICIENT = 0.9

USE TYPE 3 V-DITCH & 0.6 % SLOPE D = 1.25 (SEE P. 5)

$$V = 77.6 \times \sqrt{0.006} \\ = 6 \text{ fps}$$

$$T_c = \frac{2600}{6} = 432.4 \text{ sec} = 7.2 \text{ min}$$

$i = 6.7$  IN/HR SEE EXHIBIT 4

$$\therefore Q = 0.9 \times 6.7 \times 2.38 = 14.4 \text{ cfs}$$

$$Q_{\text{DESIGN}} = 243 \times \sqrt{0.006} = 18.8 \text{ cfs} > 14.4 \text{ cfs} \quad \text{O.K.}$$

DROP INLET AT END OF DITCH

USE 18" & CUP & 3 FT HEAD

$$Q = 15.1 \text{ cfs} > 14.4 \text{ cfs} \quad \text{O.K.}$$

USE SAME TYPE OF DITCH TO DIVERT RUN-OFF TO  
DROP INLET AT TOP OF CLAY PIT.  $Q = 243 \times \sqrt{0.005} = 17.2 > 14.4$

# ENVIRONMENTAL SOLUTIONS, INC.

By TTW Date 8-8-90 Subject LANDFILL B-18 Sheet No. 26 of 59  
Chkd. By K.A. Date 8-14-90 DRAINAGE DESIGN Proj. No. 89.977

NORTHERN BENCH POOD TO CLAY PIT DESIGN POINT B (see fig 5)

LENGTH = 1200 FT WIDTH = 40'

AREA = 1.1 ACRE RUNOFF COEFFICIENT = 0.9

$T_c = 5 \text{ min}$   $C = 7.92 \text{ in/hr}$

$$Q = 0.9 \times 7.92 \times 1.1 = 7.8 \text{ cfs}$$

USE TYPE 2 V-DITCH AND 1/0 SLOPE  $D=1'$

$$Q_{\text{DESIGN}} = 171.3 \sqrt{0.01} = 17.1 \text{ cfs} > 7.8 \text{ cfs}$$

DROP INLET

USE 18"  $\phi$  CMP & 12"  $\phi$  HEBD

$$Q = 8.5 \sqrt{1} = 8.5 \text{ cfs} > 7.8 \text{ cfs} \text{ OK.}$$

PHASE I/II DIVIDING BEAM

SOUTHERN SECTION

LENGTH = 850 FT WIDTH = 40'

AREA = .78 Acre RUNOFF COEFFICIENT = 0.9

$T_c = 5 \text{ min}$   $C = 7.92 \text{ in/hr}$

$$Q = 0.9 \times 7.92 \times .78 = 5.56 \text{ CFS}$$

$$Q_{\text{PIT}} = 14.4 \text{ CFS} + 5.56 \text{ CFS} = 19.96 \text{ CFS}$$

(SOUTHERN) SECTION  
Use Type 4:  $Q = 319.4 \text{ S}^{1/2} = 319.4 (.01)^{1/2} = 31.94 \text{ CFS}$

$$31.94 > 19.96 \text{ OK.}$$

TYPE 4 USED BECAUSE OF CULVERT

P. 27/59

SCHEDULE (see page 25)

DEEP	INLET	PIPE	PIPE	PIPE
TYPE	HEAD	INLET	INLET	INLET
	(ft)	(in)	(in)	(in)
37	3	18	140	140
08	25	74	140	110
19	1	18		




FIGURE 5  
 PHASE I RUN-OFF CONTROL PLAN  
 ENVIRONMENTAL SOLUTIONS, INC.

# ENVIRONMENTAL SOLUTIONS, INC.

By JDK Date 8-8-90 Subject LANDFILL B-18 Sheet No. 2B of 59

Chkd. By K.A. Date 9-14-90 DRAINAGE DESIGN Proj. No. 89-977

## ROW - OFF CONTROL PERIMETER DITCH PHASE II FIGURE 6

SOUTHERN BENCH ROAD DESIGN POINT A

LENGTH: 1600 FT

WIDTH = 40'

AREA = 1.47 ACRES

ROW-OFF COEFFICIENT = 0.9

USE TYPE 2 V-DITCH

D = 1.25

ALONG 6.1 % SLOPE PORTION

$$V = 68.5 \times \sqrt{0.061} = 17.1 \text{ fps}$$

$$t_c = \frac{830}{17} = 0.8 \text{ min}$$

ALONG 3.6 % SLOPE PORTION

$$V = 68.5 \times \sqrt{0.036} = 13 \text{ fps}$$

$$t_c = \frac{520}{13} = 0.7 \text{ min}$$

$$T_c = 7.2 + 0.8 + 0.7 = 8.7$$

$$L = 6.2 \text{ IN/HR}$$

$$Q = 0.9 \times 6.2 \times (238 + 1.47) = 21.7 \text{ cfs}$$

$$Q_{\text{DESIGN}} = 171.3 \times \sqrt{0.036} = 32.5 \text{ cfs} > 21.7 \text{ cfs} \quad \text{O.K.}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By JSP Date 8-8-90 Subject LANDFILL B-18 Sheet No. 29 of 59  
hkd. By N.A Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

NORTHERN BENCH ROAD DESIGN POINT B (see figure 6)

LENGTH = 1720 ft      WIDTH = 40'      AREA = 1.58 ACRES

$T_c = < 5$  min

$L = 7.92$  in/hr

$Q = 0.9 \times 1.58 \times 7.92 = 11.3$  cfs


USE TYPE 2 V-DITCH AND 10% SLOPE MIN

$Q_{DESIGN} = 17.3 \times \sqrt{0.01} = 17.1$  cfs  $> 11.3$  cfs O.K.



Run-off component Basin

PROP INLET TYPE	HEAD (ft)	PIPE INVERT (ft)	PIPE DIA (in)
D1	2.5	30	70
D4	2	24	40



PHASE I  
LANDFILL  
UNIT B-18

PHASE II  
LANDFILL  
UNIT B-18

LEGEND:  
- - - SURFACE WATER DRAINAGE AREA BOUNDARY



FIGURE 6  
Run-off CONTROL PLAN  
PHASE II  
CMI KETTLEMAN HILL FACILITY  
KINGS COUNTY, CALIFORNIA  
ENVIRONMENTAL SOLUTIONS II

# ENVIRONMENTAL SOLUTIONS, INC.

By JTM Date 8-9-90 Subject LANDFILL B-1B Sheet No. 31 of 59  
Inkd. By JM Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

## CULVERT DESIGN FIGURE 7 & FIGURE 8

ALL CULVERTS WILL BE DESIGNED FOR INLET CONTROL.

### CULVERT C1

LOCATION = PHASE 1 TRISM ACCESS ROAD & WEST PERIMETER BENCH ROAD

LENGTH = 150 FT

DIAMETER = 12"  $\phi$  CONCRETE ENCASED

DRAINAGE AREA = NORTHERN HALF OF WEST PERIMETER ROAD

LENGTH = 1170 FT

WIDTH = 40'

AREA =  $(1170 \times 40) / 43560 = 1.07$  ACRES

SLOPE = 0.6 %

APPROACH VELOCITY =  $V = 77.64 \times \sqrt{0.006} = 6$  fps. (TYPE 2 V-DITCH)

TIME OF CONCENTRATION TO CULVERT INLET =  $1170/6 = 3.25$  min

USE 5 min

$i = 2.1$  in/hr (25-YEAR)

$Q = CIA = 0.9 \times 2.1 \times 1.07 = 2$  cfs

FROM INLET CONTROL MONOGRAPH

$H_w/D = 0.9$   $\therefore H_w = 0.9 \times 12 = 10.8'' < 12''$  OK

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-9-90 Subject LANDFILL B-18 Sheet No. 32 of 51  
Chkd. By JH Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

## CULVERT 2

LOCATION: SOUTH STOCKPILE ROAD AND SOUTH PERIMETER ROAD

LENGTH = 120 ft

DIAMETER = 24"  $\phi$  CMP

DRAINAGE AREAS = A1, A2 + A9, AND A11

AREA = 28.82 ACRES

SLOPE = 0.5 %

APPROACH VELOCITY:  $V = 111.2 \sqrt{0.006} = 8.6$  fps

TIME OF CONCENTRATION TO CULVERT  $t_c = 9.1$  min

$L = 1.7$  in/hr (25-YEAR STORM)

$Q = 0.4 \times 1.7 \times 28.82 = 19.6$  cfs

FROM INLET CONTROL MONOGRAPH:

$H_w/D = 1.39$   $\therefore H_w = 1.39 \times 24 = 33.36$ "

USE 24"  $\phi$  CMP INLET  $\&$  3 ft HEAD

$Q = 15.1 \sqrt{3} = 26.2$  cfs  $> 19.6$  cfs O.K.

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-9-90 Subject LANDFILL B-18 Sheet No. 33 of 59  
Chkd. By AL Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

## CULVERT 3

LOCATION = ENTRANCE OF THE PHASE I/II BERM ROAD AND PHASE I  
PRISM ACCESS ROAD

LENGTH = 220 FT

DIAMETER = 18" C/P

DRAINAGE AREA = WESTERN BENCH ROAD

AREA = 2.35 ACRES

SLOPE = 0.5 %

TIME OF CONCENTRATION TO INLET = 7.2 MIN

$i = 1.8$  in/HR (25-YEAR STORM)

$Q = 0.9 \times 1.8 \times 2.35 = 3.9$  CFS

FROM INLET CONTROL MONOGRAPH

$H_w/D = 0.74$   $\therefore H_w = 0.74 \times 18 = 13.32" < 18" \text{ OK}$

# ENVIRONMENTAL SOLUTIONS, INC.

By Jpi Date 8-10-90 Subject LANDFILL B-18 Sheet No. 34 of 59  
Chkd. By M Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

## CULVERT 4

LOCATION = PHASE I/II BERM CREST AT TOP OF CLAY PIT.

LENGTH = 60 ft

DIAMETER = 30"  $\phi$  CUP

DRAINAGE AREA = WESTERN BENCH ROAD AND TOP OF PHASE I/II BERM

AREA = 3.75 ACRES

SLOPE = 0.5 %

TIME OF CONCENTRATION TO INLET = 9.5 min

$i = 5.8$  IN/HR PMP STORM

$$C = \frac{1.37 \times 0.4 + 2.38 \times 0.9}{3.75} = 0.72$$

$$Q = 0.72 \times 5.8 \times 3.75 = 15.6 \text{ cfs}$$

FROM INLET CONTROL MONOGRAPH

$$H_w/D = 0.79 \quad \therefore H_w = 0.79 \times 30 = 23.7$$

USE 30  $\phi$  CUP DROP INLET  $\&$  2 ft HEAD

$$Q = 24 \sqrt{2} = 33.8 \text{ cfs} > 15.6 \text{ cfs} \quad \text{O.K.}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-10-90 Subject LANDFILL B-18 Sheet No. 35 of 59  
Chkd. By AL Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

## CULVERT 5

LOCATION : EASTERN END OF SOUTH PERIMETER BENCH ROAD

LENGTH : 70 ft

DIAMETER = 30"  $\phi$  CMP

DRAINAGE AREA : WESTERN  $\&$  SOUTHERN BENCH ROAD

AREA : 3.85 ACRES

SLOPE = 0.5 %

TIME OF CONCENTRATION = 8.7 min

$L = 6.2$  IN/HR

$Q = 0.9 \times 6.2 \times 3.85 = 21$  cfs

FROM INLET CONTROL MONOGRAPH

$H_w/D = 0.95$   $\therefore H_w = 28.5$

USE 30"  $\phi$  CMP DROP INLET  $\&$  2.5' HEAD

$Q = 24 \times \sqrt{2.5} = 33.9$  cfs  $>$  21 cfs O.K.

# ENVIRONMENTAL SOLUTIONS, INC.

By JJA Date 8-10-90 Subject LANDFILL B-18 Sheet No. 36 of 59  
Chkd. By JJA Date 8-14-90 DRAINAGE DESIGN Proj. No. 89-977

## CULVERT 6

LOCATION = EASTERN END OF NORTH BENCH ROAD

LENGTH = 40'

DIAMETER = 24" CMP

DRAINAGE AREA = NORTHERN BENCH ROAD

AREA = 1.58 ACRES

TIME OF CONCENTRATION TO INLET = < 5 min

$L = 7.92$  in/hr

$Q = 0.9 \times 7.92 \times 1.58 = 11.2$  cfs


FROM INLET CONTROL MONOGRAPH

$H_w/D = 0.9$

$\therefore H_w = 0.9 \times 24 = 21.6$

USE 24" CMP DROP INLET & 24" HEAD

$Q = 15.1 \times \sqrt{2} = 21.3$  cfs > 11.2 cfs OK.



CONDUIT		SCHEMEL	
TYPE	DIMENSION (IN)	LENGTH (FEET)	DEPTH (FEET)
C1	12	150	
C2	24	120	
C3	10	220	
C4	30	60	
C5 <sup>(1)</sup>	24	70	
C6 <sup>(1)</sup>	24	40	

NOTE

(1) SAME AS DROP INLET DIO FROM D-1  
SEE FIGURE 6 FOR LOCATIONS.

FIGURE 7  
CONDUIT LOCATIONS FROM  
LANDFILL S-15  
ENVIRONMENTAL SOLUTIONS, INC.



TABLE 6

RUNOFF COEFFICIENT FOR 10-YEAR\* RETURN PERIOD

P. 51/59

I. LAND USE

<u>Nonagricultural</u>	<u>Coefficient C</u>
Business	0.70 to 0.95
Downtown	0.50 to 0.70
Neighborhood	
Residential	
Single-family	0.30 to 0.50
Multi-units, detached	0.40 to 0.60
Multi-units, attached	0.60 to 0.75
Residential (suburban lots > 1/2 acre)	0.25 to 0.40
Apartment dwelling	0.50 to 0.70
Industrial	
Light	0.50 to 0.80
Heavy	0.60 to 0.90
Parks, cemeteries	0.10 to 0.25
Playgrounds	0.20 to 0.35
Railroad yard	0.20 to 0.35
Unimproved	0.10 to 0.30


Agricultural/Open Space

<u>Hydrologic Soil Group</u> (See Table 2 and Fig. 2)	<u>Cultivated</u>	<u>Pasture</u>	<u>Oak Timber and Brush</u>
A	0.20	0.15	0.10
B	0.40	0.35	0.30
C	0.45	0.40	0.35
D	0.50	0.45	0.40

II. SURFACE TYPE

<u>Character of Surface</u>	<u>Coefficient C</u>
Pavement	
Asphaltic and Concrete	0.70 to 0.95
Brick	0.70 to 0.85
Roofs	0.75 to 0.95
Lawns, sandy soil	
Flat, 2 percent or less	0.05 to 0.10
Average, 2 to 7 percent	0.10 to 0.15
Steep, 7 percent or more	0.15 to 0.20
Lawns, heavy soil	
Flat, 2 percent	0.13 to 0.17
Average, 2 to 7 percent	0.18 to 0.22
Steep, 7 percent	0.25 to 0.35

\*For other return periods, determine runoff coefficient from Figure 10.



FHWA HEC 5

Figure 4-28 Inlet control nomograph for corrugated steel pipe culverts. The manufacturers recommended keeping HW/D to a maximum of 1.5 and preferably to no more than 1.0.

MAXIMUM ANNUAL PRECIPITATION (UNITS=INCHES)  
( TO CONVERT TO MILLIMETERS MULTIPLY BY 25.4 )

STATION NO. BSN REFER SUR COO 1967 0	STATION NAME COALINGA LSE	ELEV	SFC	TWP	RNG	LOT	RMM	LATITUDE	LONGITUDE	COUNTY
		663	04	215	15E	J	M	36.128	120.344	FRESNO

MINUTES-HOURS-DAYS OF YEAR-CALENDAR YEAR-M YEAR-WEATHER YEAR-YR FISCAL YEAR  
\*\*\*\*\* NO DATA AVAILABLE

YEAR	DURATION										
	5M	10M	15M	30M	1H	2H	3H	6H	12H	24H	C-YR
1940	0.09	0.14	0.21	0.28	0.43	0.64	0.84	1.24	1.75	1.77	10.76
1941	0.14	0.19	0.22	0.30	0.43	0.56	0.65	0.88	1.06	1.41	14.21
1942	0.10	0.14	0.19	0.22	0.25	0.42	0.65	0.93	0.95	0.99	5.10
1943	0.12	0.17	0.19	0.22	0.30	0.37	0.50	0.80	0.84	1.10	8.08
1944	0.07	0.10	0.13	0.16	0.21	0.37	0.49	0.69	0.76	1.39	5.49
1945	0.10	0.12	0.17	0.20	0.27	0.29	0.40	0.53	0.67	0.77	6.90
1946	0.06	0.10	0.12	0.17	0.37	0.48	0.61	0.80	0.82	0.90	5.73
1947	*****	*****	*****	*****	0.17	0.27	0.22	0.23	0.23	0.32	1.99
1948	0.05	0.09	0.12	0.17	0.23	0.46	0.50	0.54	0.64	0.86	5.48
1949	0.07	0.11	0.12	0.14	0.25	0.41	0.50	0.73	0.76	1.19	5.23
1950	0.13	0.15	0.17	0.17	0.27	0.27	0.47	0.65	0.81	0.85	5.86
1951	0.09	0.13	0.16	0.22	0.27	0.35	0.47	0.60	0.75	0.75	5.59
1952	0.20	0.29	0.47	0.69	0.90	0.57	0.57	0.83	0.90	0.90	10.92
1953	*****	*****	*****	*****	0.40	0.70	0.90	1.14	1.57	1.57	2.60
1954	0.03	0.05	0.08	0.15	0.24	0.44	0.60	1.15	1.24	1.30	5.60
1955	0.16	0.21	0.27	0.52	0.92	1.06	1.07	1.07	1.08	1.49	11.85
1956	0.20	0.28	0.39	0.54	0.59	0.60	0.61	0.65	0.65	0.65	4.30
1957	0.16	0.23	0.29	0.52	0.70	0.77	0.77	0.77	0.77	0.99	9.73
1958	0.10	0.16	0.18	0.21	0.32	0.56	0.59	0.69	0.82	0.84	11.04
1959	0.07	0.04	0.07	0.13	0.24	0.33	0.42	0.58	0.80	1.02	3.86
1960	0.05	0.07	0.09	0.14	0.27	0.51	0.63	0.78	1.41	1.76	5.15
1961	0.15	0.24	0.28	0.37	0.51	0.60	0.60	1.00	1.33	1.50	5.12
1962	0.06	0.09	0.11	0.20	0.39	0.54	0.75	1.10	1.15	1.37	7.08
1963	0.17	0.19	0.22	0.32	0.48	0.73	0.85	0.98	1.05	1.05	6.51
1964	0.05	0.07	0.10	0.19	0.34	0.41	0.42	0.70	0.98	1.00	4.31
1965	0.21	0.23	0.25	0.36	0.45	0.58	0.64	1.15	1.17	1.57	6.96
1966	0.08	0.14	0.16	0.23	0.32	0.47	0.50	0.92	1.40	2.27	5.79
1967	0.08	0.14	0.17	0.28	0.35	0.36	0.37	0.53	0.60	0.74	6.12
1968	0.02	0.06	0.09	0.15	0.25	0.39	0.39	0.45	0.65	0.86	3.30
1969	0.16	0.18	0.27	0.36	0.50	0.70	0.90	1.53	2.27	2.86	13.24
1970	0.03	0.06	0.09	0.14	0.25	0.41	0.54	0.72	0.70	0.86	6.27
1971	0.04	0.07	0.10	0.14	0.20	0.28	0.44	0.75	0.81	0.85	4.27
1972	0.04	0.07	0.09	0.13	0.23	0.27	0.45	0.62	0.62	0.62	3.28
1973	*****	*****	*****	0.29	0.34	0.50	0.64	0.80	0.85	1.00	8.53
1974	*****	*****	*****	*****	0.16	0.31	0.41	0.62	0.85	1.55	6.86

PRECIPITATION DEPTH-DURATION-FREQUENCY TABLE

STATION NO. BSN REFER SUR COO 1967 0	STATION NAME COALINGA LSE	ELEV	SFC	TWP	RNG	LOT	RMM	LATITUDE	LONGITUDE	COUNTY
		663	04	215	15E	J	M	36.128	120.344	FRESNO

RETURN PERIOD IN YEARS

MAXIMUM PRECIPITATION (IN) FOR INDICATED DURATION	DAYS	HOURS	MINUTES								
2	0.09	0.13	0.17	0.23	0.32	0.44	0.54	0.74	0.89	1.08	6.46
5	0.13	0.18	0.23	0.32	0.44	0.62	0.74	1.01	1.23	1.49	8.88
10	0.15	0.21	0.27	0.38	0.52	0.75	0.88	1.20	1.45	1.76	10.41
20	0.17	0.24	0.31	0.44	0.60	0.84	1.01	1.38	1.66	2.02	11.82
25	0.18	0.25	0.32	0.45	0.62	0.87	1.05	1.43	1.73	2.10	12.24
40	0.19	0.27	0.35	0.49	0.67	0.94	1.13	1.58	1.87	2.27	13.75
50	0.20	0.28	0.36	0.51	0.69	0.97	1.17	1.60	1.93	2.34	13.57
100	0.22	0.31	0.40	0.54	0.77	1.07	1.29	1.78	2.13	2.58	14.83
200	0.24	0.33	0.44	0.61	0.84	1.17	1.41	1.92	2.32	2.82	16.05
1000	0.28	0.40	0.52	0.73	0.99	1.39	1.68	2.29	2.76	3.35	18.79
10000	0.35	0.49	0.63	0.89	1.21	1.70	2.05	2.79	3.37	4.09	22.53
RMP	0.66	0.92	1.20	1.68	2.30	3.22	3.89	5.30	6.41	7.77	46.28

MEAN 0.098 0.139 0.181 0.254 0.347 0.485 0.586 0.799 0.945 1.171 6.892  
 COEFF. OF VAR. 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000 1.000  
 CALCULATED SKEW 0.480 0.500 1.349 1.194 1.697 1.158 0.561 0.477 1.402 1.172 0.776  
 REGIONAL SKEW 1.300 1.300 1.300 1.300 1.300 1.300 1.300 1.300 1.300 1.300 1.000  
 SKEW USED 1.300 1.300 1.300 1.300 1.300 1.300 1.300 1.300 1.300 1.300 1.000

SLUMP OF LOG INTENSITY / LOG TIME = -0.04 ; INTERCEPT (TIME=1 HOUR) = 0.346 ; COEFFICIENT OF DETERMINATION = 0.999  
 IMP. INTERCEPT / MEAN YR = 0.09025 ; AVERAGE CALC CV / USED CV = 1.022

KURTOSIS	2.373	2.635	4.877	3.644	7.132	5.620	3.239	3.731	6.249	5.112	3.178
N	31	31	31	32	38	35	38	35	35	35	35
RECORD YEAR	1965	1952	1952	1956	1955	1955	1955	1960	1969	1969	1941
RECORD MAXIMUM	0.210	0.290	0.470	0.540	0.920	1.060	1.070	1.530	2.270	2.660	14.210
NORMALIZED MAX	1.984	2.029	2.966	2.330	3.673	3.407	2.546	2.749	3.418	3.139	2.448
CALC. COEFF. VAR	0.168	0.500	0.540	0.484	0.450	0.348	0.323	0.333	0.396	0.405	0.434
REGIONAL COEFF. VAR	0.376	0.376	0.376	0.376	0.376	0.376	0.376	0.376	0.376	0.376	0.381
USED COEFF. VAR	0.376	0.376	0.376	0.376	0.376	0.376	0.376	0.376	0.376	0.376	0.381

MEAN/FA	0.0143	0.0202	0.0262	0.0368	0.0503	0.0704	0.0951	0.1150	0.1400	0.1600	1.0000
RPI0/FA	0.0215	0.0303	0.0394	0.0554	0.0757	0.1058	0.1279	0.1743	0.2105	0.2554	1.5107
RPI5/FA	0.0257	0.0362	0.0470	0.0660	0.0902	0.1262	0.1525	0.2078	0.2510	0.3045	1.7783
RPI10/FA	0.0287	0.0404	0.0525	0.0737	0.1008	0.1410	0.1704	0.2321	0.2804	0.3401	1.9685
RPI20/FA	0.0316	0.0445	0.0579	0.0813	0.1111	0.1594	0.1878	0.2559	0.3090	0.3749	2.1516
RPI50/FA	0.0410	0.0578	0.0751	0.1054	0.1441	0.2016	0.2436	0.3319	0.4009	0.4863	2.7264
RPI1000/FA	0.0501	0.0705	0.0917	0.1287	0.1740	0.2461	0.2975	0.4053	0.4895	0.5899	3.2696
RMP/FA	0.0951	0.1340	0.1740	0.2445	0.3342	0.4674	0.5649	0.7697	0.9296	1.1278	6.7150

PEARSON TYPE III DISTRIBUTION USED  
 PROBABLE MAXIMUM PRECIPITATION ESTIMATE BASED ON 15 STANDARD DEVIATIONS  
 WHERE N IS SMALL (25) RESULTS ARE NOT DEPENDABLE

# ENVIRONMENTAL SOLUTIONS, INC.

By VDI Date 6-1-90 Subject LANDFILL 13-18 DRAINAGE Sheet No. 54 of 59  
 Chkd. By RA Date 0 DESIGN Proj. No. 89-997







EXHIBIT 5



3/21/21  
10/21

102.711



See Plate 2  
Sheet 5 of 5

13-B

LHF  
⊙ LOCATION OF SITE

Table 2

MINIMUM RUNOFF COEFFICIENTS FOR BUILT-UP AREAS

RESIDENTIAL AREAS:	C = 0.55 to 0.70
HOTEL-APARTMENT AREAS:	C = 0.70 to 0.90
BUSINESS AREAS:	C = 0.80 to 0.90
INDUSTRIAL AREAS:	C = 0.80 to 0.90

*The type of soil, the type of open space and ground cover and the slope of the ground shall be considered in arriving at reasonable and acceptable runoff coefficients.*

Residential map in it

Table 3

APPROXIMATE AVERAGE VELOCITIES OF RUNOFF FOR CALCULATING TIME OF CONCENTRATION

TYPE OF FLOW	VELOCITY IN FPS FOR SLOPES (in percent) INDICATED			
	0-3%	4-7%	8-11%	12-15%
OVERLAND FLOW:				
Woodlands	1.0	2.0	3.0	3.5
Pastures	1.5	3.0	4.0	4.5
Cultivated	2.0	4.0	5.0	6.0
Pavements	5.0	12.0	15.0	18.0
OPEN CHANNEL FLOW:				
Improved Channels	Determine Velocity by Manning's Formula			
Natural Channel* (not well defined)	1.0	3.0	5.0	8.0

*\*These values vary with the channel size and other conditions so that the ones given are the averages of a wide range. Wherever possible, more accurate determinations should be made for particular conditions by Manning's formula.*

P.5B/59

PRECIPITATION DEPTH-DURATION-FREQUENCY TABLE

STATION NO. 4536 00  
 BSM ORDER SUB  
 COUNTY 4536 00  
 KETTLEMAN STATION

ELEV 308  
 SEC 25  
 TWP 17E  
 RANG L  
 LOT M  
 BSM 36.075  
 LONGITUDE 120.085  
 COUNTY CODE 16

RETURN PERIOD IN YEARS

RETURN PERIOD IN YEARS	10	20	30	40	50	60	80	100	150	200	300	600	3650
2	1.98	1.21	1.31	1.38	1.44	1.50	1.60	1.76	2.00	2.14	2.50	3.49	3650
5	1.35	1.71	1.89	2.00	2.09	2.16	2.33	2.53	2.93	3.10	3.58	4.98	6.08
10	1.59	2.05	2.28	2.42	2.53	2.64	2.83	3.06	3.56	3.74	4.35	5.98	8.35
20	1.81	2.38	2.65	2.82	2.95	3.08	3.30	3.52	4.17	4.35	4.98	6.98	9.79
25	1.90	2.48	2.77	2.94	3.08	3.21	3.45	3.67	4.36	4.54	5.17	7.16	11.12
40	2.05	2.70	3.01	3.20	3.36	3.50	3.76	3.99	4.75	4.93	5.57	7.55	11.53
50	2.12	2.80	3.13	3.33	3.48	3.64	3.90	4.14	4.94	5.12	5.77	7.75	12.37
100	2.34	3.10	3.48	3.70	3.88	4.05	4.36	4.59	5.50	5.68	6.35	8.03	12.76
200	2.55	3.41	3.82	4.07	4.27	4.45	4.78	5.03	6.06	6.23	6.91	8.87	13.95
1000	3.03	4.09	4.60	4.91	5.15	5.37	5.78	6.03	7.33	7.49	8.18	10.69	15.10
10000	3.71	5.05	5.70	6.09	6.38	6.66	7.17	7.42	9.10	9.23	9.92	12.54	17.67
PHP	7.05	9.67	10.72	11.69	12.05	12.58	13.55	14.32	17.25	17.68	18.91	21.11	27.19
MEAN	1.060	1.329	1.454	1.530	1.598	1.666	1.779	1.934	2.226	2.358	2.792	3.807	6.481
CLOCK HR. COR.	1.140	1.070	1.040	1.020	1.010	1.010	1.000	1.000	1.000	1.000	1.000	1.000	1.000
CALCULATED SKEW	1.603	1.605	1.608	1.608	1.607	1.607	1.607	1.607	1.607	1.607	1.607	1.607	1.607
REGIONAL SKEW USED	1.300	1.400	1.400	1.400	1.400	1.400	1.400	1.400	1.400	1.400	1.400	1.400	1.400
MEAN/A	3.212	3.150	2.880	3.426	3.574	3.701	6.396	6.095	6.012	5.746	4.328	7.584	5.922
RECORD YEAR	24	24	24	24	24	24	24	24	24	24	24	24	24
RECORD MAXIMUM	1956	1956	1962	1974	1974	1974	1969	1969	1969	1969	1969	1969	1969
NORMALIZED MAX	1.680	2.170	2.600	3.120	3.360	3.660	3.860	4.190	5.650	6.060	6.390	10.370	14.710
CALC. COEF. VAR	1.377	1.760	1.869	2.284	2.369	2.351	2.638	2.631	3.092	3.033	2.712	3.328	2.746
REGN. COEF. VAR	1.376	1.408	1.425	1.434	1.436	1.437	1.441	1.443	1.448	1.452	1.453	1.452	1.462
USED COEF. VAR	1.376	1.408	1.425	1.434	1.436	1.437	1.441	1.443	1.448	1.452	1.453	1.452	1.462
MEAN/A	1.633	2.051	2.243	2.361	2.466	2.570	2.744	2.984	3.434	3.638	4.307	5.876	1.0000
RP10/A	2.658	3.170	3.517	3.731	3.903	4.071	4.362	4.690	5.500	5.777	6.693	9.197	1.5107
RP25/A	2.931	3.832	4.271	4.542	4.754	4.939	5.269	5.669	6.772	7.005	7.982	1.1069	1.7783
RP50/A	3.274	4.316	4.822	5.134	5.375	5.608	6.019	6.481	7.615	7.895	8.905	1.2384	1.9885
RP100/A	3.609	4.789	5.362	5.714	5.983	6.244	6.704	7.074	8.490	8.766	9.798	1.3681	2.1516
RP1000/A	4.682	6.315	7.100	7.583	7.944	8.292	8.911	9.297	1.1308	1.1552	1.2621	1.7809	2.7264
RP10000/A	5.717	7.798	8.789	9.398	9.849	1.0282	1.1055	1.1443	1.4046	1.4242	1.5309	2.1769	3.2696
PHP/A	1.0837	1.4605	1.6543	1.7733	1.8594	1.9416	2.0899	2.2093	2.6615	2.7594	3.0991	4.3056	6.7150

PEARSON TYPE III DISTRIBUTION USED  
 PROBABLE MAXIMUM PRECIPITATION ESTIMATE BASED ON 15 STANDARD DEVIATIONS  
 WHERE N IS SMALL RESULTS ARE NOT DEPENDABLE

EXHIBIT 8



TABLE 5-6. VALUES OF THE ROUGHNESS COEFFICIENT  $n$   
(Boldface figures are values generally recommended in design)

Type of channel and description	Minimum	Normal	Maximum
<b>A. CLOSED CONDUITS FLOWING PARTLY FULL</b>			
<b>A-1. Metal</b>			
a. Brass, smooth	0.009	0.010	0.013
b. Steel			
1. Lockbar and welded	0.010	0.012	0.014
2. Riveted and spiral	0.013	0.016	0.017
c. Cast iron			
1. Coated	0.010	0.013	0.014
2. Uncoated	0.011	0.014	0.016
d. Wrought iron			
1. Black	0.012	0.014	0.015
2. Galvanized	0.013	0.016	0.017
e. Corrugated metal			
1. Subdrain	0.017	0.019	0.021
2. Storm drain	0.021	0.024	0.030
<b>A-2. Nonmetal</b>			
a. Lucite	0.008	0.009	0.010
b. Glass	0.009	0.010	0.013
c. Cement			
1. Neat, surface	0.010	0.011	0.013
2. Mortar	0.011	0.013	0.015
d. Concrete			
1. Culvert, straight and free of debris	0.010	0.011	0.013
2. Culvert with bends, connections, and some debris	0.011	0.013	0.014
3. Finished	0.011	0.012	0.014
4. Sewer with manholes, inlet, etc., straight	0.013	0.015	0.017
5. Unfinished, steel form	0.012	0.013	0.014
6. Unfinished, smooth wood form	0.012	0.014	0.016
7. Unfinished, rough wood form	0.015	0.017	0.020
e. Wood			
1. Stake	0.010	0.012	0.014
2. Laminated, treated	0.015	0.017	0.020
f. Clay			
1. Common drainage tile	0.011	0.013	0.017
2. Vitrified sewer	0.011	0.014	0.017
3. Vitrified sewer with manholes, inlet, etc.	0.013	0.015	0.017
4. Vitrified subdrain with open joint	0.014	0.016	0.018
g. Brickwork			
1. Glazed	0.011	0.013	0.015
2. Lined with cement mortar	0.012	0.015	0.017
h. Sanitary sewers coated with sewage slimes, with bends and connections	0.012	0.013	0.016
i. Paved invert, sewer, smooth bottom	0.016	0.019	0.020
j. Rubble masonry, cemented	0.018	0.025	0.030

TABLE 5-6. VALUES OF THE ROUGHNESS COEFFICIENT  $n$  (continued)

Type of channel and description	Minimum	Normal	Maximum
<b>B. LINED OR BUILT-UP CHANNELS</b>			
<b>B-1. Metal</b>			
a. Smooth steel surface			
1. Unpainted	0.011	0.012	0.014
2. Painted	0.012	0.013	0.017
3. Corrugated	0.021	0.025	0.030
<b>B-2. Nonmetal</b>			
a. Cement			
1. Neat, surface	0.010	0.011	0.013
2. Mortar	0.011	0.013	0.015
b. Wood			
1. Planed, untreated	0.010	0.012	0.014
2. Planed, creosoted	0.011	0.012	0.015
3. Unplaned	0.011	0.013	0.015
4. Plank with battens	0.012	0.015	0.018
5. Lined with roofing paper	0.010	0.014	0.017
c. Concrete			
1. Trowel finish	0.011	0.013	0.015
2. Float finish	0.013	0.015	0.016
3. Finished, with gravel on bottom	0.015	0.017	0.020
4. Unfinished	0.014	0.017	0.020
5. Gunite, good section	0.016	0.019	0.023
6. Gunite, wavy section	0.018	0.022	0.025
7. On good excavated rock	0.017	0.020	0.023
8. On irregular excavated rock	0.022	0.027	0.035
d. Concrete bottom float finished with sides of			
1. Dressed stone in mortar	0.015	0.017	0.020
2. Random stone in mortar	0.017	0.020	0.024
3. Cement rubble masonry, plastered	0.016	0.020	0.024
4. Cement rubble masonry	0.020	0.025	0.030
5. Dry rubble or riprap	0.020	0.030	0.035
e. Gravel bottom with sides of			
1. Formed concrete	0.017	0.020	0.025
2. Random stone in mortar	0.020	0.023	0.026
3. Dry rubble or riprap	0.023	0.033	0.036
f. Brick			
1. Glazed	0.011	0.013	0.015
2. In cement mortar	0.012	0.015	0.018
g. Masonry			
1. Cemented rubble	0.017	0.025	0.030
2. Dry rubble	0.023	0.032	0.035
h. Dressed ashlar	0.013	0.015	0.017
i. Asphalt			
1. Smooth	0.013	0.013	0.013
2. Rough	0.016	0.016	0.016
j. Vegetal lining	0.030	.....	0.500

EXH 179

P. 54/59



## METHOD OF CALCULATION

<b>Project Number:</b> 083-91887	<b>MADE BY:</b> PM	<b>Date:</b> 8-1-2011
<b>Project Name:</b> Kettleman Hills B-18 Phase IIIA	<b>CHECK BY:</b> RH	<b>SHEET 1 OF 3</b>
	<b>REVIEW BY:</b> RH	
<b>RE: TEMPORARY PHASE IIIA STORMWATER BERM AND CAPACITY OF NE B-18 CONTAINMENT BASIN DURING PHASE III CONSTRUCTION</b>		

### 1.0 OBJECTIVES

- Design the height of the proposed Phase IIIA temporary stormwater containment berm. This berm is required to be designed to function without failure to capture and retain the volume from the 24-hour, Probable Maximum Precipitation (PMP) storm event on the north side of the berm (i.e., this berm will contain stormwater run-off from the lower portion of the interim Phase IIIA waste slope and the surrounding areas).
- Evaluate the capacity versus demand of the existing NE B-18 Containment Basin during construction of Phase III. During the Phase III construction (i.e., before the South Containment Basin comes online), an outlet control system will be required during the 24-hour, PMP storm to prevent overtopping of the existing NE B-18 Containment Basin.

### 2.0 METHODOLOGY

The SCS Runoff Curve Number method was used to calculate the Phase IIIA interim drainage berm retention volume demand for the 24-hour, PMP storm event. This was compared to the proposed storage capacity of the Phase IIIA temporary basin to evaluate if the proposed berm is tall enough.

HEC-HMS modeling software (USACE) was used to evaluate the required outlet control peak flow rate to prevent overtopping of the existing NE B-18 Containment Basin during the Phase III construction.

### 3.0 ASSUMPTIONS

- The 24-hour PMP rainfall event equals 10.3 inches
- SCS Type 1 rainfall synthetic distribution was used
- SCS Curve Number (CN) of 81 was used for all basins

### 4.0 INTERIM PHASE IIIA DRAINAGE BERM CALCULATIONS

#### 4.1 Storage Capacity

The interim Phase IIIA drainage berm will be constructed 10 feet high and have a maximum storage capacity of 52,100 cubic feet on its north side. This storage capacity assumes a freeboard of 1 foot (i.e., the 52,100 cubic feet of storage capacity is for a 9-foot depth of water contained by the berm on its north side).

It should be noted that stormwater run-on contained by the interim Phase IIIA drainage berm on its south side will be clean stormwater and will have a maximum depth of approximately 2 feet during the 24-hour PMP. This maximum depth corresponds to the elevation difference between the toe of the south side of the berm and the local high point on the Phase IIIB lined "floor bench" that lies to the south. It follows that the south side of the interim Phase IIIA drainage berm has an unlimited stormwater run-on storage capacity since the top of this berm is much higher than the local high point to the south.



## METHOD OF CALCULATION

### 4.2 PMP Volume Calculation

The SCS Curve Number method was used to evaluate the runoff volume from the 24-hour, PMP storm event for the north side of the Phase IIIA interim drainage berm. This interim drainage berm will capture 0.85 acres of storm water (see Figure 1). A Curve Number, CN, of 81 was used.

$$Q = (P - 0.2S)^2 / (P + 0.8S)$$

Where: Q = runoff, in

P = rainfall (10.3 in)

S = potential maximum retention after runoff, in

Where: S = 1000/CN - 10

The estimated runoff was calculated to be 7.94 inches over the 0.85-acre drainage basin. The minimum required volume for the Phase IIIA interim drainage basin to contain the 24-hour PMP is therefore 24,500 cubic feet.

### 5.0 EXISTING NE B-18 CONTAINMENT BASIN CALCULATIONS

The existing NE B-18 Containment Basin is approximately 25 feet deep with a capacity of approximately 30 acre-feet. A HEC-HMS analysis was performed using the existing conditions of the basin. If the 24-hour, PMP storm event was to occur during the Phase III construction (i.e., before the South Containment Basin is online), it is predicted that runoff to the NE B-18 Containment Basin will exceed capacity by approximately 14 acre-feet. Therefore, an outlet control device will be used to prevent overtopping of this basin during the 24-hour, PMP storm event. Excess water will be conveyed through the outlet and into a gravity pipe that will convey the overflow to the site's existing East Retention Basin located approximately 2,000 feet to the north.

#### 5.1 Outlet Control System

HEC-HMS modeling software was used to calculate the peak flow rate required for an outlet control device set approximately 3 feet below the top of the existing NE B-18 Containment Basin embankment. Using a 21-inch orifice outlet device, it was calculated that a peak flow of 17 cfs was sufficient to prevent the basin from overtopping during the 24-hour PMP.

A preliminary minimum pipe size was calculated to convey the required 17 cfs from the NE B-18 Containment Basin. Pipe calculations were performed using the Federal Highway Administration software program Hydraulic Toolbox 2.1. A pipeline with a minimum slope of 1% and a Manning's coefficient of 0.010 was used to calculate the minimum size required to convey the required flow rate of 17 cfs. A minimum 21-inch inside diameter pipe is needed to convey the flow rate of 17 cfs.

### 6.0 CONCLUSIONS

The stormwater run-off volume from the 24-hour, PMP storm event captured on the north side of the proposed interim Phase IIIA drainage berm was calculated to be 24,500 cubic feet. The proposed interim Phase IIIA berm will be constructed to a height of 10 feet and will have a capacity of 52,100 cubic feet (assuming 1 foot of freeboard). Therefore, the proposed interim Phase IIIA drainage berm will have sufficient capacity to contain the flows from the 24-hour, PMP event with a freeboard greater than 1 foot.

The existing NE B-18 Containment Basin has a capacity of approximately 30 acre-feet. If the 24-hour, PMP storm event occurs during the construction of Phase III (i.e., before the South Containment Basin comes online), it is predicted that runoff to the existing NE B-18 Containment Basin will exceed its capacity by approximately 14 acre-feet. A 21-inch orifice outlet set approximately 3 feet below the top of the existing NE B-18 Containment Basin berm will prevent overtopping of this basin during the 24-hour,



## METHOD OF CALCULATION

PMP event. The peak flows from the orifice outlet will be 17 cfs. The excess water from the outlet system will be conveyed by gravity pipe to the site's existing East Retention Basin located approximately 2,000 feet to the north.

### 7.0 REFERENCES

Hydraulic Toolbox [computer software] 2011 Federal Highway Administration (FHWA), Version 2.1

Ernest F. Brater and Horace H. King 1976. Handbook of Hydraulics, 6<sup>th</sup> edition. McGraw-Hill Inc.

U.S Department of Commerce, National Oceanic and Atmospheric Administration, U.S. Army Corps of Engineers. 1999. *Hydrometeorological Report No. 59* Probable Maximum Precipitation for California.

HEC-HMS Hydrologic Modeling System [computer software] US Army Corps of Engineers Version 3.1.0

### 8.0 ATTACHMENTS

Figure 1: Watershed Area for Phase IIIA Temporary Stormwater Berm

Attachment 1: HEC-HMS Kettleman B-18 Basin Schematic

Attachment 2: HEC-HMS NE B-18 Containment Basin Outlet Control Discharge Results

Attachment 3: NE B-18 Containment Basin Conveyance Pipe Calculation Results




FIGURE 1  
**WATERSHED AREA FOR PHASE IIIA  
 TEMPORARY STORMWATER BERM**  
 KETTLEMAN HILLS FACILITY, LANDFILL UNIT B-18




## METHOD OF CALCULATION

Attachment 1

HEC-HMS Kettleman B-18 Basin Schematic

Attachment 2  
HEC-HMS  
B-18 Cover  
Basin Layout

HEC-HMS Basin Model Schematic





## METHOD OF CALCULATION

Attachment 2

HEC-HMS NE B-18 Containment Basin Outlet Control Discharge Results





Project: Kettleman\_B18\_Rev2  
Simulation Run: PMP24hr-Outlet Control Reservoir: NE B-18 Basin  
Start of Run: 01Feb2020, 01:00 Basin Model: B-18 Cover-Outlet Control  
End of Run: 02Feb2020, 13:00 Meteorologic Model: LocalPMP24hr  
Compute Time: 10Aug2011, 10:15:53 Control Specifications: 1Hr36Hr

Volume Units: AC-FT

#### Computed Results

Peak Inflow :	65.7 (CFS)	Date/Time of Peak Inflow :	01Feb2020, 08:00
Peak Outflow :	17.2 (CFS)	Date/Time of Peak Outflow :	02Feb2020, 01:00
Total Inflow :	43.8 (AC-FT)	Peak Storage :	28.3 (AC-FT)
Total Outflow :	19.9 (AC-FT)	Peak Elevation :	769.1 (FT)

Reservoir "NE B-18 Basin" Results for Run "PMP24hr-Outlet Control"



- - - Run:PMP24hr-Outlet Control Element:NE B-18 BASIN Result:Storage
- - - Run:PMP24hr-Outlet Control Element:NE B-18 BASIN Result:Pool Elevation
- Run:PMP24hr-Outlet Control Element:NE B-18 BASIN Result:Outflow
- - - Run:PMP24hr-Outlet Control Element:NE B-18 BASIN Result:Combined Flow

Project: Kettleman\_B18\_Rev2  
Simulation Run: PMP24hr-Outlet Control Reservoir: NE B-18 Basin

Start of Run: 01Feb2020, 01:00      Basin Model: B-18 Cover-Outlet C  
End of Run: 02Feb2020, 13:00      Meteorologic Model: LocalPMP24hr  
Compute Time: 10Aug2011, 10:15:53      Control Specifications: 1Hr36Hr

Date	Time	Inflow (CFS)	Storage (AC-FT)	Elevation (FT)	Outflow (CFS)
01Feb2020	01:00	0.0	0.0	746.0	0.0
01Feb2020	02:00	0.0	0.0	746.0	0.0
01Feb2020	03:00	1.3	0.1	746.2	0.0
01Feb2020	04:00	7.4	0.4	747.2	0.0
01Feb2020	05:00	14.9	1.3	749.3	0.0
01Feb2020	06:00	22.7	2.9	751.7	0.0
01Feb2020	07:00	32.4	5.2	754.2	0.0
01Feb2020	08:00	65.7	9.2	757.8	0.0
01Feb2020	09:00	44.1	13.7	761.1	0.0
01Feb2020	10:00	33.0	16.9	763.1	0.0
01Feb2020	11:00	27.6	19.4	764.6	0.0
01Feb2020	12:00	25.0	21.6	765.8	0.0
01Feb2020	13:00	23.3	23.6	766.8	0.0
01Feb2020	14:00	21.4	25.0	767.6	8.9
01Feb2020	15:00	20.7	25.9	768.0	11.9
01Feb2020	16:00	20.2	26.5	768.3	13.5
01Feb2020	17:00	19.8	27.0	768.5	14.6
01Feb2020	18:00	19.4	27.4	768.7	15.4
01Feb2020	19:00	19.0	27.7	768.9	16.0
01Feb2020	20:00	18.6	27.9	769.0	16.5
01Feb2020	21:00	18.3	28.0	769.0	16.8
01Feb2020	22:00	18.0	28.1	769.1	17.0
01Feb2020	23:00	17.7	28.2	769.1	17.1
02Feb2020	00:00	17.5	28.2	769.1	17.2
02Feb2020	01:00	17.1	28.3	769.1	17.2

Date	Time	Inflow (CFS)	Storage (AC-FT)	Elevation (FT)	Outflow (CFS)
02Feb2020	02:00	4.3	27.8	768.9	16.2
02Feb2020	03:00	1.0	26.7	768.4	14.0
02Feb2020	04:00	0.2	25.7	767.9	11.4
02Feb2020	05:00	0.1	24.9	767.5	8.5
02Feb2020	06:00	0.0	24.3	767.2	5.6
02Feb2020	07:00	0.0	24.0	767.0	2.6
02Feb2020	08:00	0.0	23.9	767.0	0.0
02Feb2020	09:00	0.0	23.9	767.0	0.0
02Feb2020	10:00	0.0	23.9	767.0	0.0
02Feb2020	11:00	0.0	23.9	767.0	0.0
02Feb2020	12:00	0.0	23.9	767.0	0.0
02Feb2020	13:00	0.0	23.9	767.0	0.0



## METHOD OF CALCULATION

Attachment 3

NE B-18 Containment Basin Conveyance Pipe Calculation Results

# Pipe Flow Results

## Project Data

Project Title: Kettleman B-18 Phase IIIA  
Designer: Golder  
Project Date: Wednesday, August 10, 2011  
Project Units: U.S. Customary Units

## Channel Analysis: 18" Pipe - 10 cfs

### Input Parameters

Channel Type: Circular  
Pipe Diameter: 1.5000 (ft)  
Longitudinal Slope: 0.0100 (ft/ft)  
Manning's n: 0.0100  
Flow: 10.0000 (cfs)

### Result Parameters

Depth: 0.9533 (ft)  
Area of Flow: 1.1848 (ft<sup>2</sup>)  
Wetted Perimeter: 2.7680 (ft)  
Hydraulic Radius: 0.4280 (ft)  
Average Velocity: 8.4402 (ft/s)  
Top Width: 1.4438 (ft)  
Froude Number: 1.6419  
Critical Depth: 1.2188 (ft)  
Critical Velocity: 8.8096 (ft/s)  
Critical Slope: 0.0054 (ft/ft)  
Critical Top Width: 1.1709 (ft)  
Calculated Max Shear Stress: 0.5949 (lb/ft<sup>2</sup>)  
Calculated Avg Shear Stress: 0.2671 (lb/ft<sup>2</sup>)

## Channel Analysis: 21" Pipe - 18 cfs

### Input Parameters

Channel Type: Circular  
Pipe Diameter: 1.7500 (ft)  
Longitudinal Slope: 0.0100 (ft/ft)  
Manning's n: 0.0100  
Flow: 18.0000 (cfs)

### Result Parameters

Depth: 1.2668 (ft)  
Area of Flow: 1.8647 (ft<sup>2</sup>)  
Wetted Perimeter: 3.5614 (ft)  
Hydraulic Radius: 0.5236 (ft)  
Average Velocity: 9.6531 (ft/s)  
Top Width: 1.5647 (ft)  
Froude Number: 1.5583  
Critical Depth: 1.5441 (ft)  
Critical Velocity: 9.6806 (ft/s)  
Critical Slope: 0.0069 (ft/ft)  
Critical Top Width: 1.1278 (ft)  
Calculated Max Shear Stress: 0.7905 (lb/ft<sup>2</sup>)  
Calculated Avg Shear Stress: 0.3267 (lb/ft<sup>2</sup>)

**APPENDIX J.4**  
**FINAL CLOSURE DRAINAGE**





Subject	Kettleman Hills
Landfill – B-18 Cover	
Hydrologic & Hydraulics	

Made by	PM
Checked by	RH
Approved by	[Signature]

Job	083-91887
Date	11/21/2008
Sheet	1 of 2

**OBJECTIVE:**

The cover system and drainage control systems for the existing Landfill B-18 are required to be designed to function without failure when subjected to capacity, hydrostatic and hydrodynamic loads resulting from a 24-hour, Probable Maximum Precipitation storm [CCR 22, 66264.25]. Design surface water conveyance channels and bench channels, design the proposed retention pond (Reservoir 1) and analyze the existing retention pond (Reservoir 2) for the Kettleman Hills B-18 Landfill cover configuration. All runoff from the B-18 Landfill configuration is to be routed to the proposed retention pond (Reservoir 1) located on the southeast section of the landfill or to the existing retention pond (Reservoir 2) located on the northeast section of the landfill.

**METHOD:**

The local PMP (Probable Maximum Precipitation) storm event results in a higher precipitation intensity and thus higher peak channel flow, the 6-hour PMP, was used to evaluate all channels. The 24-hour rainfall event for the PMP was used for evaluating retention volume. The 6-hour and 24-hour PMPs were derived from the Hydrometeorological Report No. 59 (Reference Attachment C). The surface water parameters as described below were used to model the Kettleman Hills B-18 Landfill. Figure 1 presents the watershed delineation map for sub-basin boundaries. Figures 2 & 3 present typical drainage channel geometries. Basin areas and curve numbers (CNs) were entered into HEC-HMS modeling software (USACE) and routed to calculate the peak flows for each basin. Kinematic wave transform methodology was used to develop hydrographs for each sub-basin except for offsite sub-basins Offsite 3, Offsite 4, and Offsite 5 which were modeled using the SCS unit hydrograph method. The peak flows were then used to size the landfill perimeter and bench channels, assuming normal depth. All model output can be found attached in this appendix.

**ASSUMPTIONS:**

- The 6-hour rainfall event for the local PMP equals 6.5 inches (used for designing channels). Ref. Attachment C.
- The 24-hour rainfall event for the PMP equals 10.3 inches (used for checking retention volume). Ref. Attachment C.
- SCS Type I rainfall synthetic distribution.
- Landfill final cover SCS Curve Numbers (CN):

Location	Soil Type	Hydrologic Soil Group	Assumed Cover	SCS CN
Landfill Final Cover	Mercey Loam	C	Herbaceous: fair cover	81
Natural Terrain (south)	Mercey Loam	C	Herbaceous: fair cover	81
Natural Terrain (west)	Mercey Loam	C	Herbaceous: good cover	74

- Manning's n for routing and channel design:

Channel Lining	Manning's n for Stability	Manning's n for Capacity
Grass	0.030	0.035
Turf Reinf. Mat	0.030	0.035
Rip-rap	0.035	0.040
Asphalt	0.016	0.016

- Grass lining was used with velocities up to 7 fps, turf reinforcement mat was used with velocities up to 10 fps or at directional changes in grass lined channels, and hard lined (asphalt or shotcrete) or riprap for velocities higher than 10 fps. Given the short term nature of the peak velocity during the conservatively assumed Local PMP, these velocities are considered acceptable.



Subject	Kettleman Hills
Landfill – B-18 Cover	
Hydrologic & Hydraulics	

Made by	PM
Checked by	RH
Approved by	[Signature]

Job	083-91887
Date	11/21/2008
Sheet	2 of 2

**CALCULATIONS:**

The HEC-HMS modeling software (USACE) was used to calculate flows at design points and the retention volume. All channel calculations were performed using a spreadsheet to calculate normal depth for both stability and capacity and FlowMaster to evaluate road/ditch sections.

**CONCLUSIONS/RESULTS:**

The proposed retention pond (Reservoir 1) and the existing retention pond (Reservoir 2) have the capacity to contain the PMP (Probable Maximum Precipitation) flows. Subbasin delineation can be found in **Figure 1**. Attached are spreadsheet and other calculations. A summary of subbasins can be found in **Table 1**, times of concentration can be found in **Table 2**, flow results from HEC-HMS in **Table 3**. Also attached are pond sizing calculations, HEC-HMS input & routing diagrams, and Flowmaster calculations for channels.

Based on the calculations, the maximum velocity for the bench channel on the landfill is 6.1 feet per second. This is below the design criteria of 7 feet per second for grass-lined channels. The closure access road will contain stormwater flows within the asphalt lined channel. The peak velocity within the asphalt-lined channel during a PMP, 6-hour event will be 23.4 feet per second which is below the maximum allowable velocity of 25 feet per second. The perimeter road channel will exceed the flow capacity of the roadside asphalt-lined channel. The peak PMP, 6-hour stormwater flows will be contained within the roadway. Velocities within the channel will be less than the maximum allowable 25 feet per second. During the 24-hour PMP, it is predicted that run-off to the existing retention basin (Reservoir 2) located on the north side of the proposed landfill will exceed capacity by approximately 2 AC-FT. In the event of a PMP storm event, the excess stormwater will have to be pumped to the proposed retention basin (Reservoir 1).

**REFERENCES:**

HEC-HMS Hydrologic Modeling System [computer software] US Army Corps of Engineers Version 3.1.0

Bentley FlowMaster [computer software] 2005 Bentley Systems Inc. Service Pack 3

Natural Resource Conservation Service. 1986. Technical Release 55: Urban Hydrology for Small Watersheds. United States Department of Agriculture.

U.S. Bureau of Reclamation (USBR). 1977. *Design of small dams 2<sup>nd</sup> ed.* Washington D.C. : United States Government Printing Office.

Ernest F. Brater and Horace H. King 1976. *Handbook of Hydraulics*, 6<sup>th</sup> edition. McGraw-Hill Inc.

U.S Department of Commerce, National Oceanic and Atmospheric Administration, U.S. Army Corps of Engineers. 1999. *Hydrometeorological Report No. 59 Probable Maximum Precipitation for California.*



KETTLEMAN HILLS  
B-18 LANDFILL HYDROLOGY  
KETTLEMAN HILLS, CA.


B-18 LANDFILL COVER  
BASIN MAP

PROJECT

TITLE

PROJECT No.	083-91887
FILE No.	08391887A001
REV. A   SCALE	1"=300'
DESIGN   PM	10/31/08
CADD   PM	10/31/01
CHECK	RH 11/4/08
REVIEW	

FIGURE 1



**Golder  
Associates**

SUBJECT **TYPICAL DRAINAGE CHANNELS**

Job No.

Made by **SAS**

Date

**9-11-08**

Ref.

**KHFB18**


Checked

**RH**

Sheet

**1 of 1**


Reviewed



**FIGURE 2.  
DRAINAGE BENCH & COVER ACCESS ROAD CHANNEL  
CONFIGURATIONS  
(TYPICAL)**

**Golder  
Associates**

SUBJECT <b>TYPICAL DRAINAGE CHANNELS</b>	
Job No.	Made by <b>SGS</b>
Ref. <b>KHF B18</b>	Checked <b>RA</b>
	Reviewed
	Date <b>9-11-08</b>
	Sheet <b>1</b> of <b>1</b>



**FIGURE 3.  
TYPICAL PERIMETER ACCESS ROAD CHANNEL  
CONFIGURATION**

**TABLE 1  
SUBBASIN SUMMARY TABLE**

Kettleman B-18 Hydrology  
Project Number: 083-91887

Date:	10/31/08
By:	PM
Chkd:	RH
Apprvd:	[Signature]

Design Storm: PMP - Recurrence Interval

Storm Duration (hours)	2-Year Depth (inches)	PMP Depth (inches)	Storm Distribution
24	0.34	10.39	I

Subbasin ID	Subbasin Area (ft <sup>2</sup> )	Subbasin Area (acres)	Subbasin Area (sq mile)	CN = 61 Covered Land (acres)	Open Rangeland HSG C (acres)	CN = 84 Pond Area (acres)	Composite SCS Curve No.	S = 1000 - 10 CN	Unit Runoff Q (in)	Runoff Volume (ac-ft)	Runoff Volume (ft <sup>3</sup> )
North 01	43,996	1.01	0.0018	1.01			CN = 81	2.35	7.94	0.87	29,100
North 02	175,111	4.02	0.0063	4.02			CN = 81	2.35	7.94	2.66	115,822
North 03	87,556	2.01	0.0031	2.01			CN = 81	2.35	7.94	1.33	57,911
North 04	133,904	3.06	0.0046	3.06			CN = 81	2.35	7.94	2.02	88,163
North 05	108,029	2.46	0.0039	2.46			CN = 81	2.35	7.94	1.64	71,453
North 06	159,430	3.66	0.0057	3.66			CN = 81	2.35	7.94	2.42	105,450
North 07	159,430	3.66	0.0057	3.66			CN = 81	2.35	7.94	2.42	105,450
North 08	157,252	3.61	0.0056	3.61			CN = 81	2.35	7.94	2.39	104,010
North 09	30,928	0.71	0.0011	0.71			CN = 81	2.35	7.94	0.47	20,456
North 10	212,137	4.87	0.0076	4.87			CN = 81	2.35	7.94	3.22	140,312
North 11	117,176	2.69	0.0042	2.69			CN = 81	2.35	7.94	1.78	77,503
North 12	59,242	1.36	0.0021	1.36			CN = 81	2.35	7.94	0.90	39,184
North 13	47,880	1.09	0.0017	1.09			CN = 81	2.35	7.94	0.72	31,405
North 14	59,877	1.37	0.0021	1.37			CN = 81	2.35	7.94	0.91	39,472
South 01	97,374	2.24	0.0035	2.24			CN = 81	2.35	7.94	1.48	64,536
South 02	99,317	2.28	0.0036	2.28			CN = 81	2.35	7.94	1.51	65,690
South 03	101,050	2.32	0.0036	2.32			CN = 81	2.35	7.94	1.53	66,843
South 04	82,328	1.89	0.0030	1.89			CN = 81	2.35	7.94	1.25	54,454
South 05	177,725	4.06	0.0064	4.06			CN = 81	2.35	7.94	2.70	117,551
South 06	68,989	1.57	0.0025	1.57			CN = 81	2.35	7.94	1.04	45,234
South 07	153,331	3.52	0.0055	3.52			CN = 81	2.35	7.94	2.33	101,417
South 08	158,556	3.64	0.0057	3.64			CN = 81	2.35	7.94	2.41	104,874
South 09	187,744	4.31	0.0087	4.31			CN = 81	2.35	7.94	2.85	124,178
South 10	117,612	2.70	0.0042	2.70			CN = 81	2.35	7.94	1.79	77,791
South 11	170,320	3.91	0.0061	3.91			CN = 81	2.35	7.94	2.59	112,653
South 12	230,868	5.30	0.0083	5.30			CN = 81	2.35	7.94	3.51	152,701
South 13	25,522	0.54	0.0008	0.54			CN = 81	2.35	7.94	0.36	15,558
OffSite 01	355,450	8.16	0.0118	8.16	8.16		CN = 74	3.51	7.03	4.78	208,097
OffSite 02	211,702	4.86	0.0076	4.86	4.86		CN = 81	2.35	7.94	3.21	140,024
OffSite 03	637,716	14.64	0.0259	14.64	14.64		CN = 81	2.35	7.94	9.68	421,800
OffSite 04	399,010	9.16	0.0143	9.16	9.16		CN = 84	1.90	6.32	6.35	276,684
OffSite 05	153,767	3.53	0.0055	3.53	3.53		CN = 84	1.90	6.32	2.45	105,626
<b>Total:</b>	<b>4,976,730</b>	<b>114.25</b>	<b>0.18</b>							<b>75.35</b>	<b>3,282,402</b>

TOTAL RUNOFF TO RESERVOIR 1 DURING PMP STORM: 31.8 AC-FT

TOTAL RUNOFF TO RESERVOIR 2 DURING PMP STORM: 34.1 AC-FT

STORAGE CAPACITY OF RESERVOIR 2: 32.5 AC-FT

EXCESS RUNOFF TO BE PUMPED OR DIVERTED OFF-SITE: 2.2 AC-FT

**TABLE 2  
BASIN TIME OF CONCENTRATION CALCULATIONS**

Date: 10/31/08  
By: PM  
Chkd: [Signature]  
Apprvd: [Signature]

Project Name : Kettleman Hydrology  
Project Number: 083-91887

Subbasin ID	Subbasin Area (sq mile)	Composite Curve Number	Total Lag (0.6 Tc) (min)	Total Travel Time (min)	Flow Segment 1				Flow Segment 2				Travel Time (min)		
					Type of Flow	Length (ft)	Slope (ft/ft)	Roughness Condition <sup>(1)</sup>	Typical Hydraulic Radius (Channel Only) (ft)	Type of Flow	Length (ft)	Slope (ft/ft)		Roughness Condition <sup>(1)</sup>	Typical Hydraulic Radius (Channel Only) (ft)
North 01	0.0019	81	0.0	0.0											
North 02	0.0063	81	0.0	0.0											
North 03	0.0031	81	0.0	0.0											
North 04	0.0046	81	0.0	0.0											
North 05	0.0039	81	0.0	0.0											
North 06	0.0057	81	0.0	0.0											
North 07	0.0057	81	0.0	0.0											
North 08	0.0056	81	0.0	0.0											
North 09	0.0011	81	0.0	0.0											
North 10	0.0076	81	0.0	0.0											
North 11	0.0042	81	0.0	0.0											
North 12	0.0021	81	0.0	0.0											
North 13	0.0017	81	0.0	0.0											
North 14	0.0021	81	0.0	0.0											
South 01	0.0035	81	0.0	0.0											
South 02	0.0036	81	0.0	0.0											
South 03	0.0036	81	0.0	0.0											
South 04	0.0030	81	0.0	0.0											
South 05	0.0064	81	0.0	0.0											
South 06	0.0025	81	0.0	0.0											
South 07	0.0055	81	0.0	0.0											
South 08	0.0057	81	0.0	0.0											
South 09	0.0067	81	0.0	0.0											
South 10	0.0042	81	0.0	0.0											
South 11	0.0061	81	0.0	0.0											
South 12	0.0083	81	0.0	0.0											
South 13	0.0008	81	0.0	0.0											
OffSite 01	0.0128	72	0.0	0.0											
OffSite 02	0.0076	81	0.0	0.0	Sheet	100.0	0.420	H	Range	1200.0	0.410	U	Unpaved	3.7	
OffSite 03	0.0229	81	5.1	8.5	Sheet	65.0	0.510	H	Range	688.0	0.180	U	Unpaved	1.5	
OffSite 04	0.0143	84	2.0	4.7	Sheet	95.0	0.020	B	Follow	80.0	0.020	U	Unpaved	0.1	
OffSite 05	0.0055	84	2.8	4.7											

Notes:

(1) Refer to Attachment A for Roughness Condition descriptions and Tc Coefficients.

**TABLE 3  
FLOW RESULTS FROM HEC-HMS**

Kettleman B-18 Hydrology  
Project Number: 083-91887

Date:	10/31/08
By:	PM
Chkd:	<i>KH</i>
Apprvd:	<i>[Signature]</i>

HEC-HMS Basin Model:	Kettleman B-18
HEC-HMS Met. Model:	Local PMF 6hr
HEC-HMS Control Specs:	15min 24hr

Hydrologic Element	Drainage Area (sq mile)	Peak Discharge (cfs)	Time of Peak	Total Volume (ac-ft)
North 01	0.002	9.1	2:45	0.4
North 02	0.006	35.9	2:45	1.5
North 03	0.003	17.6	2:45	0.7
North 04	0.005	27.4	2:45	1.1
North 05	0.004	22.2	2:45	0.9
North 06	0.006	32.4	2:45	1.3
North 07	0.008	32.5	2:45	1.3
North 08	0.006	31.8	2:45	1.3
North 09	0.001	6.3	2:45	0.3
North 10	0.006	43.3	2:45	1.8
North 11	0.004	23.9	2:45	1.0
North 12	0.002	12.0	2:45	0.5
North 13	0.002	9.7	2:45	0.4
North 14	0.002	11.9	2:45	0.5
South 01	0.004	19.9	2:45	0.8
South 02	0.004	20.5	2:45	0.8
South 03	0.004	20.6	2:45	0.8
South 04	0.003	17.1	2:45	0.7
South 05	0.006	36.4	2:45	1.5
South 06	0.003	14.3	2:45	0.6
South 07	0.006	31.4	2:45	1.3
South 08	0.006	32.5	2:45	1.3
South 09	0.007	38.2	2:45	1.6
South 10	0.004	23.9	2:45	1.0
South 11	0.006	34.8	2:45	1.4
South 12	0.008	47.3	2:45	1.9
South 13	0.001	4.6	2:45	0.2
Offsite 01	0.013	58.1	2:45	2.5
Offsite 02	0.008	43.3	2:45	1.8
Offsite 03	0.023	104.2	2:45	5.3
Offsite 04	0.014	69.6	2:45	3.6
Offsite 05	0.006	26.8	2:45	1.4
J N01-N02	0.008	45.0	2:45	1.8
J N03-N04	0.016	87.4	2:45	3.7
J N05	0.040	198.7	2:45	8.9
J N06-N14	0.048	228.0	2:45	10.8
J N08	0.011	59.3	2:45	2.6
J N09	0.012	65.6	2:45	2.9
J N11	0.012	63.3	2:45	2.8
J N12	0.026	136.9	2:45	6.2
J N13	0.028	142.8	2:45	6.6
J O1-O2	0.036	187.2	2:45	8.0
J S03	0.007	37.3	2:45	1.7
J S04	0.007	36.1	2:45	1.5
J S05	0.020	109.2	2:45	4.7
J S06	0.041	206.8	2:45	9.6
J S08	0.011	58.9	2:45	2.6
J S09	0.018	88.6	2:45	4.2
J S10	0.059	277.1	2:45	14.1
J S12	0.014	75.0	2:45	3.4
J S13	0.060	273.7	2:45	14.4
Reach-1	0.004	19.0	2:45	4.4
Reach-2	0.020	103.9	2:45	4.4
Reach-3	0.008	42.3	2:45	4.4
Reach-4	0.036	176.4	2:45	4.1
Reach-5	0.040	183.6	2:45	4.2
Reach-6	0.004	16.7	2:45	4.4
Reach-7	0.006	26.3	2:45	4.4
Reach-8	0.011	50.4	2:45	4.5
Reach-9	0.006	27.6	2:45	4.4
Reach-10	0.041	178.3	2:45	4.5
Reach-11	0.059	269.1	2:45	4.5
Reach-12	0.006	27.4	2:45	4.4
Reach-13	0.012	61.7	2:45	4.5
Reach-14	0.008	39.3	2:45	4.4
Reach-15	0.026	133.2	2:45	4.5
Reach-16	0.007	36.7	2:45	4.4
Reach-17	0.016	85.7	2:45	4.4



**TABLE 3  
FLOW RESULTS FROM HEC-HMS**

Kettleman B-18 Hydrology  
Project Number: 083-91887

Date:	10/31/08
By:	PM
Chkd:	<i>RH</i>
Apprvd:	<i>[Signature]</i>

HEC-HMS Basin Model:	Kettleman B-18
HEC-HMS Met. Model:	Local PMP 5hr
HEC-HMS Control Specs:	15min/24hr

Hydrologic Element	Drainage Area (sq mile)	Peak Discharge (cfs)	Time of Peak	Total Volume (ac-ft)
North 01	0.002	9.1	2:45	0.4
North 02	0.006	35.9	2:45	1.5
North 03	0.003	17.6	2:45	0.7
North 04	0.005	27.4	2:45	1.1
North 05	0.004	22.2	2:45	0.9
North 06	0.006	32.4	2:45	1.3
North 07	0.006	32.5	2:45	1.3
North 08	0.006	31.9	2:45	1.3
North 09	0.001	6.3	2:45	0.3
North 10	0.008	43.3	2:45	1.8
North 11	0.004	23.9	2:45	1.0
North 12	0.002	12.0	2:45	0.5
North 13	0.002	9.7	2:45	0.4
North 14	0.002	11.9	2:45	0.5
South 01	0.004	19.9	2:45	0.8
South 02	0.004	20.6	2:45	0.8
South 03	0.004	20.6	2:45	0.8
South 04	0.003	17.1	2:45	0.7
South 05	0.006	36.4	2:45	1.5
South 06	0.003	14.3	2:45	0.6
South 07	0.006	31.4	2:45	1.3
South 08	0.006	32.5	2:45	1.3
South 09	0.007	38.2	2:45	1.6
South 10	0.004	23.9	2:45	1.0
South 11	0.006	34.8	2:45	1.4
South 12	0.008	47.3	2:45	1.9
South 13	0.001	4.6	2:45	0.2
Offsite 01	0.013	58.1	2:45	2.5
Offsite 02	0.008	43.3	2:45	1.8
Offsite 03	0.023	104.2	2:45	5.3
Offsite 04	0.014	69.6	2:45	3.6
Offsite 05	0.006	26.8	2:45	1.4
J N01-N02	0.008	45.0	2:45	1.8
J N03-N04	0.016	87.4	2:45	3.7
J N05	0.040	196.7	2:45	8.9
J N06-N14	0.048	228.0	2:45	10.8
J N08	0.011	59.3	2:45	2.6
J N09	0.012	65.6	2:45	2.9
J N11	0.012	63.3	2:45	2.8
J N12	0.026	136.9	2:45	6.2
J N13	0.028	142.8	2:45	6.6
J O1-O2	0.036	187.2	2:45	8.0
J S03	0.007	37.3	2:45	1.7
J S04	0.007	36.1	2:45	1.5
J S05	0.020	109.2	2:45	4.7
J S06	0.041	206.8	2:45	9.6
J S08	0.011	58.9	2:45	2.6
J S09	0.018	88.6	2:45	4.2
J S10	0.059	277.1	2:45	14.1
J S12	0.014	75.0	2:45	3.4
J S13	0.060	273.7	2:45	14.4
Reach-1	0.004	19.0	2:45	4.4
Reach-2	0.020	103.9	2:45	4.4
Reach-3	0.008	42.3	2:45	4.4
Reach-4	0.036	176.4	2:45	4.1
Reach-5	0.040	183.6	2:45	4.2
Reach-6	0.004	16.7	2:45	4.4
Reach-7	0.006	26.3	2:45	4.4
Reach-8	0.011	50.4	2:45	4.5
Reach-9	0.005	27.5	2:45	4.4
Reach-10	0.041	178.3	2:45	4.5
Reach-11	0.059	269.1	2:45	4.5
Reach-12	0.006	27.4	2:45	4.4
Reach-13	0.012	61.7	2:45	4.5
Reach-14	0.008	39.3	2:45	4.4
Reach-15	0.026	133.2	2:45	4.5
Reach-16	0.007	36.7	2:45	4.4
Reach-17	0.016	85.7	2:45	4.4

**Table 4**  
**Channel Hydraulic Calculations**


Date: 10/3/08  
By: PM  
Chkd: RHA  
Apprvd: [Signature]

Kettleman B-18 Hydrology

Reach Designation	Q/MP from HEC-HMS (cfs)	HEC HMS Element ID for Q	Channel Design Geometry					Channel Roughness Parameters				Hydraulic Calculations			
			Approximate Channel Length (ft)	Channel Slope (ft/ft)	Left Side Slope (H:1V)	Right Side Slope (H:1V)	Bottom Width (ft)	Minimum Channel Depth (ft)	Design Channel Lining	Manning's 'n' for Capacity (Depth Calculation)	Manning's 'n' for Stability (Velocity Calculation)	Maximum Velocity (ft/sec)	Maximum Normal Depth (ft)	Froude Number	Normal Depth Shear Stress (lb/ft <sup>2</sup> )
Bench S01	19.9	South 01	770	0.020	2.0	3.5	12	2.0	G	0.035	0.030	3.7	0.45	1.04	0.56
Bench S02	20.5	South 02	910	0.020	2.0	3.5	12	2.0	G	0.035	0.030	3.7	0.46	1.05	0.57
Bench S03	16.7	Reach-5	1000	0.020	2.0	3.5	12	2.0	G	0.035	0.030	3.4	0.41	0.89	0.51
Cover S04	19.0	Reach-1	415	0.080	1.0	3.5	35	2.0	B	0.016	0.016	12.9	0.73	3.75	3.64
Cover S05	36.7	Reach-16	175	0.080	1.0	3.5	35	2.0	G	0.035	0.030	7.1	0.04	1.80	0.21
Bench S06	36.4	South 05	1150	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.5	0.65	1.10	0.81
Cover S07	103.9	Reach-2	175	0.080	2.0	3.5	35	2.0	B	0.016	0.016	8.5	1.64	2.81	8.19
Bench S08	31.4	South 07	990	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.3	0.59	1.08	0.74
Bench S09	26.3	Reach-7	980	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.4	0.53	0.93	0.66
Bench S10	50.4	Reach-8	1050	0.020	2.0	3.5	12	2.0	G	0.035	0.030	5.1	0.78	0.98	0.97
Perimeter S06	178.3	Reach-10	1290	0.014	2.0	3.5	25	3.0	G	0.035	0.030	5.3	2.84	0.93	2.48
Bench S11	34.8	South 11	975	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.5	0.63	1.09	0.79
Bench S12	27.6	Reach-9	1280	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.1	0.55	0.93	0.69
Bench S13	4.6	South 13	450	0.020	2.0	3.5	25	3.0	G	0.035	0.030	2.1	0.19	0.91	0.24
Perimeter S10	269.1	Reach-11	450	0.047	2.0	3.5	25	3.0	G	0.035	0.030	9.0	2.73	1.67	8.01
Bench N01	9.1	North 01	280	0.020	2.0	3.5	12	2.0	G	0.035	0.030	2.7	0.29	0.97	0.35
Bench N02	35.9	North 02	1050	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.5	0.64	1.10	0.80
Perimeter N02	42.3	Reach-3	610	0.060	2.0	3.5	25	3.0	B	0.016	0.016	15.3	0.85	3.44	3.18
Bench N03	17.6	North 03	590	0.020	2.0	3.5	12	2.0	G	0.035	0.030	3.5	0.42	1.03	0.52
Bench N04	27.4	North 04	880	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.1	0.55	1.07	0.69
Perimeter N04	85.7	Reach-17	220	0.056	2.0	3.5	25	3.0	B	0.016	0.016	18.0	1.24	3.46	4.33
Offsite-2 Ditch	43.3	Offsite 02	1010	0.075	3.0	3.0	0	2.0	B	0.016	0.016	15.2	0.97	3.84	4.54
Perimeter O2	178.4	Reach-4	660	0.026	2.0	3.5	25	3.0	G	0.035	0.030	6.4	2.67	1.23	4.33
Bench N05	22.2	North 05	875	0.020	2.0	3.5	12	2.0	G	0.035	0.030	3.8	0.48	1.05	0.60
Perimeter N05	183.6	Reach-5	1175	0.060	2.0	3.5	25	3.0	G	0.035	0.030	8.7	2.51	1.80	9.49
Bench N06	32.4	North 06	1175	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.4	0.60	1.09	0.75
Bench N07	32.5	North 07	955	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.1	0.55	0.93	0.69
Bench N08	27.4	Reach-12	990	0.020	2.0	3.5	12	2.0	B	0.016	0.016	17.6	1.00	3.70	4.18
Perimeter N09	61.7	Reach-13	695	0.067	2.0	3.5	25	3.0	B	0.016	0.016	4.9	0.71	1.12	0.89
Bench N10	43.3	North 10	1180	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.7	0.62	1.11	0.77
Bench N11	39.3	Reach-14	640	0.020	2.0	3.5	12	2.0	G	0.035	0.030	4.7	0.62	1.11	0.77
Perimeter N12	133.2	Reach-15	435	0.080	2.0	3.5	25	3.0	B	0.016	0.016	23.0	1.41	4.20	7.04

Attachment B  
 HEC-HMS Screen Captures and Inputs

HEC-HMS Basin Model Schematic



**KETTLEMAN B-18 BASIN**

**Attachment B  
HEC-HMS Screen Captures and Inputs**

Sub Basin	Area (mi <sup>2</sup> )
North 01	0.001600
North 02	0.003300
North 03	0.003100
North 04	0.004800
North 05	0.003900
North 06	0.005700
North 07	0.005700
North 08	0.005600
North 09	0.003100
North 10	0.007600
North 11	0.004200
North 12	0.002100
North 13	0.007100
North 14	0.002100
South 01	0.003500
South 02	0.003600
South 03	0.003600
South 04	0.003900
South 05	0.006400
South 06	0.002500
South 07	0.005500
South 08	0.005700
South 09	0.006700
South 10	0.004200
South 11	0.006100
South 12	0.009300
South 13	0.000900
Offsite 1	0.012800
Offsite 2	0.007600
Offsite 3	0.022900
Offsite 4	0.014300
Offsite 5	0.005500

Subbasin	Loss			Impervious (%)
	SCS Curve Number	Abstraction (in)	Curve Number	
North 01	81		81	0
North 02	81		81	0
North 03	81		81	0
North 04	81		81	0
North 05	81		81	0
North 06	81		81	0
North 07	81		81	0
North 08	81		81	0
North 09	81		81	0
North 10	81		81	0
North 11	81		81	0
North 12	81		81	0
North 13	81		81	0
North 14	81		81	0
South 01	81		81	0
South 02	81		81	0
South 03	81		81	0
South 04	81		81	0
South 05	81		81	0
South 06	81		81	0
South 07	81		81	0
South 08	81		81	0
South 09	81		81	0
South 10	81		81	0
South 11	81		81	0
South 12	81		81	0
South 13	81		81	0
Offsite 1	74		74	0
Offsite 2	81		81	0
Offsite 3	81		81	0
Offsite 4	84		84	0
Offsite 5	84		84	0


Transform	
SCS Unit Hydrograph	Lag Time (min)
Subbasin	
Offsite 3	5.1
Offsite 4	2.8
Offsite 5	2.8

**Attachment B**  
**HEC-HMS Screen Captures and Inputs**

Kinematic Wave Transform (Main Channel)									
Subbasin	Route Upstream	Route Method	Length (ft)	Slope (ft/ft)	subreaches	Shape	Manning's n	Width (ft)	Side Slope (H:1V)
North 01	No	Kinematic Wave	290	0.065	5	Trapezoid	0.035	12	3.25
North 02	No	Kinematic Wave	1050	0.020	5	Trapezoid	0.035	12	3.25
North 03	No	Kinematic Wave	590	0.055	5	Trapezoid	0.035	12	3.25
North 04	No	Kinematic Wave	880	0.020	5	Trapezoid	0.035	12	3.25
North 05	No	Kinematic Wave	875	0.026	5	Trapezoid	0.035	12	3.25
North 06	No	Kinematic Wave	1175	0.050	5	Trapezoid	0.035	12	3.25
North 07	No	Kinematic Wave	955	0.020	5	Trapezoid	0.035	12	3.25
North 08	No	Kinematic Wave	990	0.020	5	Trapezoid	0.035	12	3.25
North 09	No	Kinematic Wave	250	0.057	5	Trapezoid	0.035	12	3.25
North 10	No	Kinematic Wave	1160	0.022	5	Trapezoid	0.035	12	3.25
North 11	No	Kinematic Wave	640	0.020	5	Trapezoid	0.035	12	3.25
North 12	No	Kinematic Wave	695	0.057	5	Trapezoid	0.035	12	3.25
North 13	No	Kinematic Wave	435	0.080	5	Trapezoid	0.035	12	3.25
North 14	No	Kinematic Wave	290	0.042	5	Trapezoid	0.035	12	3.25
South 01	No	Kinematic Wave	770	0.020	5	Trapezoid	0.035	12	3.25
South 02	No	Kinematic Wave	910	0.020	5	Trapezoid	0.035	12	3.25
South 03	No	Kinematic Wave	1000	0.020	5	Trapezoid	0.035	12	3.25
South 04	No	Kinematic Wave	615	0.080	5	Trapezoid	0.035	12	3.25
South 05	No	Kinematic Wave	1150	0.020	5	Trapezoid	0.035	12	3.25
South 06	No	Kinematic Wave	650	0.007	5	Trapezoid	0.035	12	3.25
South 07	No	Kinematic Wave	590	0.020	5	Trapezoid	0.035	12	3.25
South 08	No	Kinematic Wave	980	0.020	5	Trapezoid	0.035	12	3.25
South 09	No	Kinematic Wave	1050	0.020	5	Trapezoid	0.035	12	3.25
South 10	No	Kinematic Wave	1290	0.014	5	Trapezoid	0.035	12	3.25
South 11	No	Kinematic Wave	975	0.020	5	Trapezoid	0.035	12	3.25
South 12	No	Kinematic Wave	1280	0.020	5	Trapezoid	0.035	12	3.25
South 13	No	Kinematic Wave	450	0.047	5	Trapezoid	0.035	12	3.25
Offsite 1	No	Kinematic Wave	1180	0.075	5	Trapezoid	0.035	12	3.25
Offsite 2	No	Kinematic Wave	1010	0.050	5	Trapezoid	0.035	12	3.25

Routing Kinematic Wave Channel									
Reach	Length (ft)	Slope (ft/ft)	Manning's n	subreaches	Shape	Diameter (ft)	Width (ft)	Side Slope (H:1V)	
Reach-1	415	0.080	0.035	2	Trapezoid		12	3.25	
Reach-2	665	0.062	0.035	2	Trapezoid		12	3.25	
Reach-3	610	0.060	0.035	2	Trapezoid		12	3.25	
Reach-4	650	0.026	0.035	2	Trapezoid		12	3.25	
Reach-5	1175	0.080	0.035	2	Trapezoid		12	3.25	
Reach-6	1000	0.020	0.035	2	Trapezoid		12	3.25	
Reach-7	980	0.020	0.035	2	Trapezoid		12	3.25	
Reach-8	1050	0.020	0.035	2	Trapezoid		12	3.25	
Reach-9	1280	0.020	0.035	2	Trapezoid		12	3.25	
Reach-10	1290	0.014	0.035	2	Trapezoid		12	3.25	
Reach-11	450	0.047	0.035	2	Trapezoid		12	3.25	
Reach-12	990	0.020	0.035	2	Trapezoid		12	3.25	
Reach-13	695	0.067	0.035	2	Trapezoid		12	3.25	
Reach-14	640	0.020	0.035	2	Trapezoid		12	3.25	
Reach-15	435	0.080	0.035	2	Trapezoid		12	3.25	
Reach-16	175	0.080	0.035	2	Trapezoid		12	3.25	
Reach-17	220	0.065	0.035	2	Trapezoid		12	3.25	


Attachment C - Local Storm



**Figure 13.21.** California local-storm PMP precipitation estimates for 1 mi<sup>2</sup>, 1 hour (inches). Dashed lines are drainage divides. Same as Figure 9.23.

Figure 13.21 from HMR No. 59 is used to derive the 6 hour PMP.

**Attachment C - General Storm**



Project: Kettleman\_Final\_10-08  
Simulation Run: PMP24hr Reservoir: Reservoir-1

Start of Run: 01Feb2020, 01:00 Basin Model: Final Cover  
End of Run: 02Feb2020, 13:00 Meteorologic Model: LocalPMP24hr  
Compute Time: 03Nov2008, 09:31:12 Control Specifications: 1Hr36Hr

Volume Units: AC-FT

Computed Results

Peak Inflow :	47.1 (CFS)	Date/Time of Peak Inflow :	01Feb2020, 08:00
Peak Outflow :	0.0 (CFS)	Date/Time of Peak Outflow :	01Feb2020, 01:00
Total Inflow :	31.8 (AC-FT)	Peak Storage (CAPACITY)	48 <del>31.8</del> (AC-FT)
Total Outflow :	0.0 (AC-FT)	Peak Elevation :	857 <del>849.9</del> (FT)



Project: Kettleman\_Final\_10-08  
Simulation Run: PMP24hr Reservoir: Reservoir-2

Start of Run:	01Feb2020, 01:00	Basin Model:	Final Cover
End of Run:	02Feb2020, 13:00	Meteorologic Model:	LocalPMP24hr
Compute Time:	03Nov2008, 09:31:12	Control Specifications:	1Hr36Hr

Volume Units: AC-FT

Computed Results

Peak Inflow :	52.0 (CFS)	Date/Time of Peak Inflow :	01Feb2020, 08:00
Peak Outflow :	19.0 (CFS)	Date/Time of Peak Outflow :	02Feb2020, 01:00
Total Inflow :	34.1 (AC-FT)	Peak Storage :	32.5 (AC-FT)
Total Outflow :	2.2 (AC-FT)	Peak Elevation :	771.0 (FT)



---

## Worksheet for Cover Road Reach 1

---

### Results

Velocity Head	2.57	ft
Specific Energy	3.30	ft
Froude Number	3.75	
Flow Type	Supercritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	0.73	ft
Critical Depth	1.54	ft
Channel Slope	0.08000	ft/ft
Critical Slope	0.00671	ft/ft



## Worksheet for Cover Road Reach 2

### Project Description

Friction Method                      Manning Formula  
 Solve For                              Normal Depth

### Input Data

Channel Slope                              0.08000    ft/ft  
 Discharge                                    103.9    ft<sup>3</sup>/s ✓  
 Section Definitions

Station (ft)	Elevation (ft)
0+00.0	820.00
0+02.0	818.00
0+37.0	818.00
0+40.0	816.50
0+45.3	818.00
0+52.3	820.00

### Roughness Segment Definitions

Start Station	Ending Station	Roughness Coefficient
(0+00.0, 820.00)	(0+02.0, 818.00)	0.030
(0+02.0, 818.00)	(0+37.0, 818.00)	0.022
(0+37.0, 818.00)	(0+45.3, 818.00)	0.016
(0+45.3, 818.00)	(0+52.3, 820.00)	0.030

### Results

Normal Depth                              1.64    ft  
 Elevation Range                          816.50 to 820.00 ft  
 Flow Area                                    12.30    ft<sup>2</sup>  
 Wetted Perimeter                          44.57    ft  
 Top Width                                    43.93    ft  
 Normal Depth                              1.64    ft  
 Critical Depth                              1.92    ft  
 Critical Slope                              0.00812    ft/ft  
 Velocity                                      8.45    ft/s ✓

---

## Worksheet for Cover Road Reach 2

---

### Results

Velocity Head	1.11	ft
Specific Energy	2.75	ft
Froude Number	2.81	
Flow Type	Supercritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	1.64	ft
Critical Depth	1.92	ft
Channel Slope	0.08000	ft/ft
Critical Slope	0.00812	ft/ft

---

## Cross Section for Cover Road Reach 2

---


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Channel Slope	0.08000	ft/ft
Normal Depth	1.64	ft
Discharge	103.9	ft <sup>3</sup> /s

### Cross Section Image



## Worksheet for Perimeter Road Reach 3

### Project Description

Friction Method                      Manning Formula  
 Solve For                                Normal Depth

### Input Data

Channel Slope                            0.06000    ft/ft  
 Discharge                                42.3        ft<sup>3</sup>/s ✓  
 Section Definitions

Station (ft)	Elevation (ft)
0+00.0	820.00
0+08.0	816.00
0+10.0	817.00
0+35.0	816.50
0+38.0	814.50
0+40.0	814.50
0+43.0	816.50
0+50.0	818.50

### Roughness Segment Definitions

Start Station	Ending Station	Roughness Coefficient
(0+00.0, 820.00)	(0+10.0, 817.00)	0.035
(0+10.0, 817.00)	(0+35.0, 816.50)	0.035
(0+35.0, 816.50)	(0+43.0, 816.50)	0.016
(0+43.0, 816.50)	(0+50.0, 818.50)	0.035

### Results

Normal Depth                            0.85    ft  
 Elevation Range                        814.50 to 820.00 ft  
 Flow Area                                2.77    ft<sup>2</sup>  
 Wetted Perimeter                        5.06    ft  
 Top Width                                4.54    ft  
 Normal Depth                            0.85    ft  
 Critical Depth                            1.66    ft ✓



---

## Worksheet for Perimeter Road Reach 3

---

### Results

Critical Slope	0.00447	ft/ft
Velocity	15.25	ft/s ✓
Velocity Head	3.61	ft
Specific Energy	4.46	ft
Froude Number	3.44	
Flow Type	Supercritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	0.85	ft
Critical Depth	1.66	ft
Channel Slope	0.06000	ft/ft
Critical Slope	0.00447	ft/ft





---

## Worksheet for Perimeter Road Reach 4

---

### Results

Critical Slope	0.01656	ft/ft
Velocity	5.99	ft/s ✓
Velocity Head	0.56	ft
Specific Energy	3.23	ft
Froude Number	1.23	
Flow Type	Supercritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	2.67	ft
Critical Depth	2.78	ft
Channel Slope	0.02600	ft/ft
Critical Slope	0.01656	ft/ft

## Cross Section for Perimeter Road Reach 4


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Channel Slope                            0.02600    ft/ft  
Normal Depth                            2.67        ft  
Discharge                                176.4       ft<sup>3</sup>/s

### Cross Section Image





---

## Worksheet for Perimeter Road Reach 5

---

### Results

Critical Slope	0.01635	ft/ft
Velocity	7.91	ft/s ✓
Velocity Head	0.97	ft
Specific Energy	3.49	ft
Froude Number	1.80	
Flow Type	Supercritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	2.51	ft
Critical Depth	2.81	ft
Channel Slope	0.06000	ft/ft
Critical Slope	0.01635	ft/ft

## Cross Section for Perimeter Road Reach 5


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Channel Slope    0.06000    ft/ft  
Normal Depth    2.51        ft  
Discharge    183.6       ft<sup>3</sup>/s

### Cross Section Image





---

## Worksheet for Bench Reach 6

---

### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035	
Channel Slope	0.02000	ft/ft
Left Side Slope	2.00	ft/ft (H:V)
Right Side Slope	3.50	ft/ft (H:V)
Bottom Width	12.00	ft
Discharge	16.7	ft <sup>3</sup> /s ✓

### Results

Normal Depth	0.41	ft
Flow Area	5.37	ft <sup>2</sup>
Wetted Perimeter	14.41	ft
Top Width	14.25	ft
Critical Depth	0.38	ft
Critical Slope	0.02562	ft/ft ✓
Velocity	3.11	ft/s ✓
Velocity Head	0.15	ft
Specific Energy	0.56	ft
Froude Number	0.89	
Flow Type	Subcritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	0.41	ft
Critical Depth	0.38	ft
Channel Slope	0.02000	ft/ft
Critical Slope	0.02562	ft/ft

---

## Cross Section for Bench Reach 6

---

### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035
Channel Slope	0.02000 ft/ft
Normal Depth	0.41 ft
Left Side Slope	2.00 ft/ft (H:V)
Right Side Slope	3.50 ft/ft (H:V)
Bottom Width	12.00 ft
Discharge	16.7 ft <sup>3</sup> /s

### Cross Section Image



V: 1  
H: 1

---

## Worksheet for Bench Reach 7

---

### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035
Channel Slope	0.02000 ft/ft
Left Side Slope	2.00 ft/ft (H:V)
Right Side Slope	3.50 ft/ft (H:V)
Bottom Width	12.00 ft
Discharge	26.3 ft <sup>3</sup> /s ✓

### Results

Normal Depth	0.53 ft
Flow Area	7.20 ft <sup>2</sup>
Wetted Perimeter	15.14 ft
Top Width	14.94 ft
Critical Depth	0.51 ft
Critical Slope	0.02351 ft/ft
Velocity	3.66 ft/s ✓
Velocity Head	0.21 ft
Specific Energy	0.74 ft
Froude Number	0.93
Flow Type	Subcritical

### GVF Input Data

Downstream Depth	0.00 ft
Length	0.00 ft
Number Of Steps	0

### GVF Output Data

Upstream Depth	0.00 ft
Profile Description	
Profile Headloss	0.00 ft
Downstream Velocity	Infinity ft/s
Upstream Velocity	Infinity ft/s
Normal Depth	0.53 ft
Critical Depth	0.51 ft
Channel Slope	0.02000 ft/ft
Critical Slope	0.02351 ft/ft

---

---

## Cross Section for Bench Reach 7

---

### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035
Channel Slope	0.02000 ft/ft
Normal Depth	0.53 ft
Left Side Slope	2.00 ft/ft (H:V)
Right Side Slope	3.50 ft/ft (H:V)
Bottom Width	12.00 ft
Discharge	26.3 ft <sup>3</sup> /s

### Cross Section Image



V:1  
H:1

---

## Worksheet for Bench Reach 8

---

### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035	
Channel Slope	0.02000	ft/ft
Left Side Slope	2.00	ft/ft (H:V)
Right Side Slope	3.50	ft/ft (H:V)
Bottom Width	12.00	ft
Discharge	50.4	ft <sup>3</sup> /s ✓

### Results

Normal Depth	0.78	ft
Flow Area	11.03	ft <sup>2</sup>
Wetted Perimeter	16.58	ft
Top Width	16.29	ft
Critical Depth	0.77	ft
Critical Slope	0.02089	ft/ft ✓
Velocity	4.57	ft/s ✓
Velocity Head	0.32	ft
Specific Energy	1.10	ft
Froude Number	0.98	
Flow Type	Subcritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	0.78	ft
Critical Depth	0.77	ft
Channel Slope	0.02000	ft/ft
Critical Slope	0.02089	ft/ft

---

## Cross Section for Bench Reach 8

---


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035
Channel Slope	0.02000 ft/ft
Normal Depth	0.78 ft
Left Side Slope	2.00 ft/ft (H:V)
Right Side Slope	3.50 ft/ft (H:V)
Bottom Width	12.00 ft
Discharge	50.4 ft <sup>3</sup> /s

### Cross Section Image



V:1  
H:1

## Worksheet for Bench Reach 9

### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035
Channel Slope	0.02000 ft/ft
Left Side Slope	2.00 ft/ft (H:V)
Right Side Slope	3.50 ft/ft (H:V)
Bottom Width	12.00 ft
Discharge	27.6 ft <sup>3</sup> /s ✓

### Results

Normal Depth	0.55 ft
Flow Area	7.42 ft <sup>2</sup>
Wetted Perimeter	15.23 ft
Top Width	15.02 ft
Critical Depth	0.53 ft
Critical Slope	0.02329 ft/ft
Velocity	3.72 ft/s ✓
Velocity Head	0.21 ft
Specific Energy	0.76 ft
Froude Number	0.93
Flow Type	Subcritical

### GVF Input Data

Downstream Depth	0.00 ft
Length	0.00 ft
Number Of Steps	0

### GVF Output Data

Upstream Depth	0.00 ft
Profile Description	
Profile Headloss	0.00 ft
Downstream Velocity	Infinity ft/s
Upstream Velocity	Infinity ft/s
Normal Depth	0.55 ft
Critical Depth	0.53 ft
Channel Slope	0.02000 ft/ft
Critical Slope	0.02329 ft/ft

---

## Cross Section for Bench Reach 9

---


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035	
Channel Slope	0.02000	ft/ft
Normal Depth	0.55	ft
Left Side Slope	2.00	ft/ft (H:V)
Right Side Slope	3.50	ft/ft (H:V)
Bottom Width	12.00	ft
Discharge	27.6	ft <sup>3</sup> /s

### Cross Section Image



V:1  
H:1





---

## Worksheet for Perimeter Road Reach 10

---

### Results

Critical Slope	0.01660	ft/ft
Velocity	4.95	ft/s ✓
Velocity Head	0.38	ft
Specific Energy	3.22	ft
Froude Number	0.93	
Flow Type	Subcritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	2.84	ft
Critical Depth	2.79	ft
Channel Slope	0.01400	ft/ft
Critical Slope	0.01660	ft/ft

## Cross Section for Perimeter Road Reach 10


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Channel Slope                            0.01400    ft/ft  
Normal Depth                            2.84        ft  
Discharge                                178.3      ft<sup>3</sup>/s

### Cross Section Image





---

## Worksheet for Perimeter Road Reach 11

---

### Results

Critical Slope	0.01525	ft/ft
Velocity	8.44	ft/s ✓
Velocity Head	1.11	ft
Specific Energy	3.84	ft
Froude Number	1.67	
Flow Type	Supercritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	2.73	ft
Critical Depth	3.07	ft
Channel Slope	0.04700	ft/ft
Critical Slope	0.01525	ft/ft

## Cross Section for Perimeter Road Reach 11


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Channel Slope                            0.04700    ft/ft  
Normal Depth                            2.73        ft  
Discharge                                269.1       ft<sup>3</sup>/s

### Cross Section Image



---

## Worksheet for Bench Reach 12

---

### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035	
Channel Slope	0.02000	ft/ft
Left Side Slope	2.00	ft/ft (H:V)
Right Side Slope	3.50	ft/ft (H:V)
Bottom Width	12.00	ft
Discharge	27.4	ft <sup>3</sup> /s ✓

### Results

Normal Depth	0.55	ft
Flow Area	7.39	ft <sup>2</sup>
Wetted Perimeter	15.21	ft
Top Width	15.01	ft
Critical Depth	0.52	ft
Critical Slope	0.02332	ft/ft
Velocity	3.71	ft/s ✓
Velocity Head	0.21	ft
Specific Energy	0.76	ft
Froude Number	0.93	
Flow Type	Subcritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	0.55	ft
Critical Depth	0.52	ft
Channel Slope	0.02000	ft/ft
Critical Slope	0.02332	ft/ft

---

## Cross Section for Bench Reach 12

---


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035
Channel Slope	0.02000 ft/ft
Normal Depth	0.55 ft
Left Side Slope	2.00 ft/ft (H:V)
Right Side Slope	3.50 ft/ft (H:V)
Bottom Width	12.00 ft
Discharge	27.4 ft <sup>3</sup> /s

### Cross Section Image



V:1  
H:1



## Worksheet for Perimeter Road Reach 13

### Project Description

Friction Method                      Manning Formula  
 Solve For                              Normal Depth

### Input Data

Channel Slope    0.06700    ft/ft  
 Discharge    61.7    ft<sup>3</sup>/s    ✓  
 Section Definitions

Station (ft)	Elevation (ft)
0+00.0	820.00
0+08.0	816.00
0+10.0	817.00
0+35.0	816.50
0+38.0	814.50
0+40.0	814.50
0+43.0	816.50
0+50.0	818.50

### Roughness Segment Definitions

Start Station	Ending Station	Roughness Coefficient
(0+00.0, 820.00)	(0+10.0, 817.00)	0.035
(0+10.0, 817.00)	(0+35.0, 816.50)	0.035
(0+35.0, 816.50)	(0+43.0, 816.50)	0.016
(0+43.0, 816.50)	(0+50.0, 818.50)	0.035

### Results

Normal Depth    1.00    ft  
 Elevation Range                                        814.50 to 820.00 ft  
 Flow Area    3.51    ft<sup>2</sup>  
 Wetted Perimeter                                       5.61    ft  
 Top Width    5.01    ft  
 Normal Depth     1.00    ft  
 Critical Depth     2.20    ft

---

## Worksheet for Perimeter Road Reach 13

---

### Results

Critical Slope	0.00477	ft/ft
Velocity	17.58	ft/s ✓
Velocity Head	4.80	ft
Specific Energy	5.80	ft
Froude Number	3.70	
Flow Type	Supercritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	1.00	ft
Critical Depth	2.20	ft
Channel Slope	0.06700	ft/ft
Critical Slope	0.00477	ft/ft

## Cross Section for Perimeter Road Reach 13


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Channel Slope                            0.06700    ft/ft  
Normal Depth                            1.00    ft  
Discharge                                61.7    ft<sup>3</sup>/s

### Cross Section Image



---

## Worksheet for Bench Reach 14

---

### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035	
Channel Slope	0.02000	ft/ft
Left Side Slope	2.00	ft/ft (H:V)
Right Side Slope	3.50	ft/ft (H:V)
Bottom Width	12.00	ft
Discharge	39.3	ft <sup>3</sup> /s ✓

### Results

Normal Depth	0.68	ft
Flow Area	9.35	ft <sup>2</sup>
Wetted Perimeter	15.97	ft
Top Width	15.71	ft
Critical Depth	0.66	ft
Critical Slope	0.02184	ft/ft
Velocity	4.20	ft/s ✓
Velocity Head	0.27	ft
Specific Energy	0.95	ft
Froude Number	0.96	
Flow Type	Subcritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	0.68	ft
Critical Depth	0.66	ft
Channel Slope	0.02000	ft/ft
Critical Slope	0.02184	ft/ft

---

## Cross Section for Bench Reach 14


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035
Channel Slope	0.02000 ft/ft
Normal Depth	0.68 ft
Left Side Slope	2.00 ft/ft (H:V)
Right Side Slope	3.50 ft/ft (H:V)
Bottom Width	12.00 ft
Discharge	39.3 ft <sup>3</sup> /s

### Cross Section Image



V: 1  
H: 1



---

## Worksheet for Perimeter Road Reach 15

---

### Results

Critical Slope	0.00444	ft/ft
Velocity	22.98	ft/s ✓
Velocity Head	8.21	ft
Specific Energy	9.62	ft
Froude Number	4.20	
Flow Type	Supercritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	1.41	ft
Critical Depth	2.63	ft
Channel Slope	0.08000	ft/ft
Critical Slope	0.00444	ft/ft

## Cross Section for Perimeter Road Reach 15


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Channel Slope                            0.08000    ft/ft  
Normal Depth                            1.41        ft  
Discharge                                133.2       ft<sup>3</sup>/s

### Cross Section Image





---

## Worksheet for Bench Reach 16

---

### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035
Channel Slope	0.08000 ft/ft
Left Side Slope	2.00 ft/ft (H:V)
Right Side Slope	3.50 ft/ft (H:V)
Bottom Width	12.00 ft
Discharge	36.7 ft <sup>3</sup> /s ✓

### Results

Normal Depth	0.43 ft
Flow Area	5.70 ft <sup>2</sup>
Wetted Perimeter	14.54 ft
Top Width	14.38 ft
Critical Depth	0.63 ft
Critical Slope	0.02211 ft/ft
Velocity	6.43 ft/s ✓
Velocity Head	0.64 ft
Specific Energy	1.08 ft
Froude Number	1.80
Flow Type	Supercritical

### GVF Input Data

Downstream Depth	0.00 ft
Length	0.00 ft
Number Of Steps	0

### GVF Output Data

Upstream Depth	0.00 ft
Profile Description	
Profile Headloss	0.00 ft
Downstream Velocity	Infinity ft/s
Upstream Velocity	Infinity ft/s
Normal Depth	0.43 ft
Critical Depth	0.63 ft
Channel Slope	0.08000 ft/ft
Critical Slope	0.02211 ft/ft

---

---

## Cross Section for Bench Reach 16

---


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Roughness Coefficient	0.035
Channel Slope	0.08000 ft/ft
Normal Depth	0.43 ft
Left Side Slope	2.00 ft/ft (H:V)
Right Side Slope	3.50 ft/ft (H:V)
Bottom Width	12.00 ft
Discharge	36.7 ft <sup>3</sup> /s

### Cross Section Image



V: 1  
H: 1



---

## Worksheet for Perimeter Road Reach 17

---

### Results

Critical Slope	0.00478	ft/ft
Velocity	17.96	ft/s ✓
Velocity Head	5.01	ft
Specific Energy	6.25	ft
Froude Number	3.46	
Flow Type	Supercritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	1.24	ft
Critical Depth	2.42	ft
Channel Slope	0.05600	ft/ft
Critical Slope	0.00478	ft/ft

## Cross Section for Perimeter Road Reach 17


### Project Description

Friction Method                      Manning Formula  
Solve For                                Normal Depth

### Input Data

Channel Slope                            0.05600    ft/ft  
Normal Depth                            1.24        ft  
Discharge                                85.7        ft<sup>3</sup>/s


### Cross Section Image



# HY-8 Culvert Analysis Report

**Water Surface Profile Plot for Culvert: Culvert 1**

**Crossing - JSO5, Design Discharge - 110.0 cfs**  
**Culvert - Culvert 1, Culvert Discharge - 110.0 cfs**



**Site Data - Culvert 1**

Site Data Option: Culvert Invert Data  
Inlet Station: 0.00 ft  
Inlet Elevation: 914.00 ft  
Outlet Station: 70.00 ft  
Outlet Elevation: 910.00 ft  
Number of Barrels: 2

**Culvert Data Summary - Culvert 1**

Barrel Shape: Circular  
Barrel Diameter: 3.00 ft  
Barrel Material: Smooth HDPE  
Embedment: 0.00 in  
Barrel Manning's n: 0.0120  
Inlet Type: Conventional  
Inlet Edge Condition: Square Edge with Headwall  
Inlet Depression: None






**Table 2 - Summary of Culvert Flows at Crossing: JSO5**

Headwater Elevation (ft)	Total Discharge (cfs)	Culvert 1 Discharge (cfs)	Roadway Discharge (cfs)	Iterations
918.32	110.00	110.00	0.00	1
918.32	110.00	110.00	0.00	1
918.32	110.00	110.00	0.00	1
918.32	110.00	110.00	0.00	1
918.32	110.00	110.00	0.00	1
918.32	110.00	110.00	0.00	1
918.32	110.00	110.00	0.00	1
918.32	110.00	110.00	0.00	1
918.32	110.00	110.00	0.00	1
918.32	110.00	110.00	0.00	1
918.32	110.00	110.00	0.00	1
919.00	124.86	124.86	0.00	Overtopping

**Water Surface Profile Plot for Culvert: Culvert 1**

**Crossing - J 01-02, Design Discharge - 188.0 cfs**

**Culvert - Culvert 1, Culvert Discharge - 78.0 cfs**



**Site Data - Culvert 1**

Site Data Option: Culvert Invert Data

Inlet Station: 0.00 ft

Inlet Elevation: 854.00 ft

Outlet Station: 60.00 ft

Outlet Elevation: 853.00 ft

Number of Barrels: 1

**Culvert Data Summary - Culvert 1**

Barrel Shape: Circular

Barrel Diameter: 3.00 ft

Barrel Material: Smooth HDPE

Embedment: 0.00 in

Barrel Manning's n: 0.0120

Inlet Type: Conventional

Inlet Edge Condition: Square Edge with Headwall

Inlet Depression: None

**Table 3 - Culvert Summary Table: Culvert 1**

Total Discharge (cfs)	Culvert Discharge (cfs)	Headwater Elevation (ft)	Inlet Control Depth (ft)	Outlet Control Depth (ft)	Flow Type	Normal Depth (ft)	Critical Depth (ft)	Outlet Depth (ft)	Tailwater Depth (ft)	Outlet Velocity (ft/s)	Tailwater Velocity (ft/s)
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185
188.00	78.04	860.81	6.807	6.807	5-S2n	2.096	2.775	2.310	1.959	13.387	12.185

\*\*\*\*\*  
 Inlet Elevation (invert): 854.00 ft,    Outlet Elevation (invert): 853.00 ft

Culvert Length: 60.01 ft,    Culvert Slope: 0.0167


\*\*\*\*\*

**Table 4 - Summary of Culvert Flows at Crossing: J 01-02**

Headwater Elevation (ft)	Total Discharge (cfs)	Culvert 1 Discharge (cfs)	Roadway Discharge (cfs)	Iterations
860.81	188.00	78.04	109.94	8
860.81	188.00	78.04	109.94	2
860.81	188.00	78.04	109.94	2
860.81	188.00	78.04	109.94	2
860.81	188.00	78.04	109.94	2
860.81	188.00	78.04	109.94	2
860.81	188.00	78.04	109.94	2
860.81	188.00	78.04	109.94	2
860.81	188.00	78.04	109.94	2
860.81	188.00	78.04	109.94	2
860.81	188.00	78.04	109.94	2
860.00	71.29	71.29	0.00	Overtopping

### Water Surface Profile Plot for Culvert: Culvert

Crossing - JS13, Design Discharge - 274.0 cfs  
Culvert - Culvert, Culvert Discharge - 274.0 cfs



### Site Data - Culvert

Site Data Option: Culvert Invert Data  
Inlet Station: 0.00 ft  
Inlet Elevation: 869.00 ft  
Outlet Station: 70.00 ft  
Outlet Elevation: 868.00 ft  
Number of Barrels: 4

### Culvert Data Summary - Culvert

Barrel Shape: Circular  
Barrel Diameter: 3.00 ft  
Barrel Material: Smooth HDPE  
Embedment: 0.00 in  
Barrel Manning's n: 0.0120  
Inlet Type: Conventional  
Inlet Edge Condition: Square Edge with Headwall  
Inlet Depression: None

**Table 5 - Culvert Summary Table: Culvert**

Total Discharge (cfs)	Culvert Discharge (cfs)	Headwater Elevation (ft)	Inlet Control Depth (ft)	Outlet Control Depth (ft)	Flow Type	Normal Depth (ft)	Critical Depth (ft)	Outlet Depth (ft)	Tailwater Depth (ft)	Outlet Velocity (ft/s)	Tailwater Velocity (ft/s)
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317
274.00	274.00	874.69	5.692	5.084	4-FFf	2.017	2.622	2.017	2.271	13.568	22.317


\*\*\*\*\*  
 Inlet Elevation (invert): 869.00 ft,    Outlet Elevation (invert): 868.00 ft  
 Culvert Length: 70.01 ft,    Culvert Slope: 0.0143  
 \*\*\*\*\*

**Table 6 - Summary of Culvert Flows at Crossing: JS13**

Headwater Elevation (ft)	Total Discharge (cfs)	Culvert Discharge (cfs)	Roadway Discharge (cfs)	Iterations
874.69	274.00	274.00	0.00	1
874.69	274.00	274.00	0.00	1
874.69	274.00	274.00	0.00	1
874.69	274.00	274.00	0.00	1
874.69	274.00	274.00	0.00	1
874.69	274.00	274.00	0.00	1
874.69	274.00	274.00	0.00	1
874.69	274.00	274.00	0.00	1
874.69	274.00	274.00	0.00	1
874.69	274.00	274.00	0.00	1
874.69	274.00	274.00	0.00	1
875.00	285.05	285.05	0.00	Overtopping

**Water Surface Profile Plot for Culvert: Culvert 1**

**Crossing - JN06-N14, Design Discharge - 228.0 cfs**  
**Culvert - Culvert 1, Culvert Discharge - 97.1 cfs**



**Site Data - Culvert 1**

Site Data Option: Culvert Invert Data  
Inlet Station: 0.00 ft  
Inlet Elevation: 762.00 ft  
Outlet Station: 60.00 ft  
Outlet Elevation: 760.00 ft  
Number of Barrels: 1

**Culvert Data Summary - Culvert 1**

Barrel Shape: Circular  
Barrel Diameter: 3.00 ft  
Barrel Material: Smooth HDPE  
Embedment: 0.00 in  
Barrel Manning's n: 0.0120  
Inlet Type: Conventional  
Inlet Edge Condition: Square Edge with Headwall  
Inlet Depression: None






**Table 8 - Summary of Culvert Flows at Crossing: JN06-N14**

Headwater Elevation (ft)	Total Discharge (cfs)	Culvert 1 Discharge (cfs)	Roadway Discharge (cfs)	Iterations
771.48	228.00	97.07	130.89	11
771.48	228.00	97.07	130.89	2
771.48	228.00	97.07	130.89	2
771.48	228.00	97.07	130.89	2
771.48	228.00	97.07	130.89	2
771.48	228.00	97.07	130.89	2
771.48	228.00	97.07	130.89	2
771.48	228.00	97.07	130.89	2
771.48	228.00	97.07	130.89	2
771.48	228.00	97.07	130.89	2
771.48	228.00	97.07	130.89	2
770.00	87.19	87.19	0.00	Overtopping

**Water Surface Profile Plot for Culvert: Culvert 1**

**Crossing - JN13, Design Discharge - 143.0 cfs**  
**Culvert - Culvert 1, Culvert Discharge - 92.6 cfs**



**Site Data - Culvert 1**

Site Data Option: Culvert Invert Data

Inlet Station: 0.00 ft

Inlet Elevation: 767.00 ft

Outlet Station: 60.00 ft

Outlet Elevation: 766.00 ft

Number of Barrels: 1

**Culvert Data Summary - Culvert 1**

Barrel Shape: Circular

Barrel Diameter: 3.00 ft

Barrel Material: Smooth HDPE

Embedment: 0.00 in

Barrel Manning's n: 0.0120

Inlet Type: Conventional

Inlet Edge Condition: Square Edge with Headwall

Inlet Depression: None

**Table 9 - Culvert Summary Table: Culvert 1**

Total Discharge (cfs)	Culvert Discharge (cfs)	Headwater Elevation (ft)	Inlet Control Depth (ft)	Outlet Control Depth (ft)	Flow Type	Normal Depth (ft)	Critical Depth (ft)	Outlet Depth (ft)	Tailwater Depth (ft)	Outlet Velocity (ft/s)	Tailwater Velocity (ft/s)
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424
143.00	92.62	775.81	8.807	6.979	5-S2n	2.446	3.000	2.587	1.458	14.337	23.424

\*\*\*\*\*  
 Inlet Elevation (invert): 767.00 ft,    Outlet Elevation (invert): 766.00 ft

Culvert Length: 60.01 ft,    Culvert Slope: 0.0167

\*\*\*\*\*

**Table 10 - Summary of Culvert Flows at Crossing: JN13**

Headwater Elevation (ft)	Total Discharge (cfs)	Culvert 1 Discharge (cfs)	Roadway Discharge (cfs)	Iterations
775.81	143.00	92.62	50.35	12
775.81	143.00	92.62	50.35	2
775.81	143.00	92.62	50.35	2
775.81	143.00	92.62	50.35	2
775.81	143.00	92.62	50.35	2
775.81	143.00	92.62	50.35	2
775.81	143.00	92.62	50.35	2
775.81	143.00	92.62	50.35	2
775.81	143.00	92.62	50.35	2
775.81	143.00	92.62	50.35	2
775.81	143.00	92.62	50.35	2
775.00	87.02	87.02	0.00	Overtopping

**APPENDIX K**  
**LCRS ANALYSES**

**APPENDIX K.1**

**LCRS CAPACITY**


**APPENDIX K.2**

**GEOTEXTILE FILTER CAPACITY**

**APPENDIX K.1**  
**LCRS CAPACITY**



Subject: Kettleman Hills Facility Landfill Unit B-18
LCRS Calculations

Made by: RJS
Checked by: RH
Reviewed by: SS 

Job No.: 083-91887
Date: 04/23/2008
Sheet No.: 1 of 1

**OBJECTIVE:**

Evaluate if the existing Landfill B-18 Leachate Collection and Removal System (LCRS) will be sufficient to support the proposed Phase III expansion. Also confirm that the maximum head on the base liner will not exceed 12 inches at any point.

Compare capacity calculations with measured leachate volumes.

**METHOD:**

The original LCRS calculations performed by ESI (1990) assumed that 100% of the rainwater falling on B-18 would infiltrate into the LCRS. This assumption is very conservative and no longer valid as the current B-18 waste mass has significant absorptive capacity and given the climatic conditions much of the rainfall will either runoff and be collected or evaporate.

Perform calculations similar to the Phase I and II LCRS calculations to confirm the transmissivity of the LCRS geocomposite is adequate to convey the potential leachate (equal to rainfall volume) to the sump. Compute the capacity of the LCRS gravel around the sump to convey leachate and compare to potential maximum leachate volumes and historical recorded leachate generation rates.

**CALCULATIONS:**

Following the calculation approach used by ESI (see Pages 3 to 5 in Attachment 1), confirm the increased slope length (i.e. greater capture area) is able to convey the annualized average leachate volume (assuming all rainfall becomes leachate). The flow length for the base considers the contributory flow from the upstream slope. Flow paths are shown on Figure 1 in Attachment 2. Based on the calculations the geocomposite is capable of conveying the annual rainfall to the sump.

Sump capacity was determined by Darcy's Law where the capacity (Q) is equal to the permeability (k) multiplied by the cross sectional area of the LCRS gravel (A) multiplied by the gradient of the floor (i). The capacity of the B-18 sump perimeter is approximately 9,000 gallons per day for each sump. Historic records (see Figure 2) indicate that the average flow is approximately 200 gallons per day maximum (Sump IB) with a maximum measured generation rate of approximately 6,000 gallons per day. The maximum flow rate resulted from exposing an area of geocomposite during a storm event allowing runoff to enter the LCRS system. The geocomposite is typically covered by protective geomembrane, operations layer and waste which limit the flow. Based on the observation the LCRS system is capable of conveying much larger volumes than typically encountered.

**CONCLUSIONS/RESULTS:**

The LCRS system is capable of conveying the expected leachate volumes. The geocomposite is shown to be capable of conveying the leachate to the sump without exceeding 12 inches of head on the liner. The original calculations are shown in Attachment 1, and the updated calculations are shown in Attachment 2.




REV	DATE	DESCRIPTION	DESIGN	CHECK	APPROVE
1	11/20/20	ISSUED FOR PERMITTING	KJK	KJK	SDS
2	11/20/20	ISSUED FOR PERMITTING	KJK	KJK	SDS

**Golden Associates**  
 220 Commercial, Suite 200  
 Irvine, California 92602  
 (714) 608-4400


**CHEMICAL WASTE MANAGEMENT  
 KETTLEMAN HILLS FACILITY**  
 35251 OLD SKYLINE ROAD  
 KETTLEMAN CITY, CALIFORNIA 92539  
 (569) 386-9711

**B-18 CLASS I LANDFILL  
 PHASE III EXPANSION AND FINAL  
 CLOSURE**  
 BASE LINER PLAN


SHEET NO. 10  
 OF 10




- NOTES:**
1. GRADES SHOWN ARE TOP OF CLAY LINER.
  2. PROPOSED PRIMARY LACS ARE INSTALLED TO PREVENT LEACHATE FROM PENETRATING THE CLAY LINER TO UNDERLYING PERMEABLE MATERIALS.
  3. 18" O.D. PRIMARY LACS ARE INSTALLED TO DRAW RUN-ON FROM THE LANDFILL. PROFESSIONAL DESIGNERS SHALL VERIFY THE LOCATION OF THE CUT SIDE OF THE LACS. INSTALLED LACS WILL BE CUT INTO THE NATURAL GRADE.
  4. END OF PIPE W/TEE AND GATE VALVES ON EACH BRANCH, EXTEND PIPE TO EDGE OF SUBSTRATE CELLING.



**FIGURE 1  
 LACS FLOW  
 PATHS**  
 ISSUED FOR PERMITTING



**Figure 2 - Historical Leachate Removal Rates from Landfill B-18**



# Attachment 1

Original LCRS Calculations

# ENVIRONMENTAL SOLUTIONS, INC.

By WPI Date 8-13-90 Subject LANDFILL B-18 LCPS Sheet No. 1 of 22  
Chkd. By GSC Date 8/13/90 EVALUATION Proj. No. 89-977

## TABLE OF CONTENT

DESIGN CRITERIA	2/23
LCR SYSTEM CAPACITY (ANNUAL LEACHATE GENERATION)	3/23
LCR SYSTEM CAPACITY (SURFACE WATER GENERATION)	10/23
FILTER - RETENTION CAPACITY	13/23
GEOTEXTILE PERMEABILITY	16/23
GEOTEXTILE PUNCTURE RESISTANCE	18/23
CONCLUSION	18/23
EXHIBITS	19/23

# ENVIRONMENTAL SOLUTIONS, INC.

By TAPIL Date 8-10-90 Subject LANDFILL B-18 LCRS Sheet No. 2 of 33  
Chkd. By GSC Date 8/13/90 EVALUATION Proj. No. 89-977

1  
2 PURPOSE : TO EVALUATE THE CAPACITY OF THE LCR  
3  
4 SYSTEM AND THE GEOTEXTILE DESIGN IN THE PRIMARY LCRS.  
5

6 CRITERIA : THE LCR SYSTEM CAPACITY SHOULD BE  
7  
8 SUFFICIENT TO HANDLE THE FLOW OF  
9

10 1. LEACHATE GENERATED BY ANNUAL PRECIPITATION.  
11

12 2. SURFACE WATER OF A 100-YR STORM IN 24-HOUR PERIOD.  
13

14 REFERENCE = 1 GEOSYNTHETIC DESIGN GUIDANCE FOR HAZARDOUS  
15

16 WASTE LANDFILL CELL AND SURFACE IMPROVEMENTS  
17

18 EPA/600/2-37/097 BY SOIL & MATERIAL ENGINEERS INC. <sup>DEC. 88</sup>  
19

20 2 ENGINEERING REPORT, LANDFILL B-19, PHASE II & III  
21

22 BY DOMINIQUE & ASSOCIATES, INC. OCT 1988  
23

24 3. SOIL MECHANICS LAMBEE & WHITMAN  
25

26 4. DESIGN WITH GEOSYNTHETICS KOERNER, 1986  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 7-30-90 Subject LANDFILL B-18, LCPS Sheet No. 3 of 23  
 Chkd. By CSC Date 8/13/90 EVALUATION Proj. No. 89-977

## LCR SYSTEM CAPACITY FOR ANNUAL LEACHATE GENERATION

BASED ON KETTLEMAN STATION RECORD (EXHIBIT 1), THE AVERAGE ANNUAL PRECIPITATION RATE IS 6.48 IN. TO BE CONSERVATIVE, ASSUME 100% OF THE RAINFALL WILL INFILTRATE THROUGH THE LANDFILL. THE LEACHATE GENERATION RATE IS THEREFORE



$$q = \frac{6.48}{365 \times 24 \times 60 \times 60 \times 12} = 1.71 \times 10^{-8} \text{ ft/sec}$$

ASSUME EACH LEACHATE SUMP WILL BE OPERATED INDEPENDENTLY, THE REQUIRED TRANSMISSIVITY OF A STRIP ALONG THE LONGEST FLOW PATH IN EACH CELL MAY BE ESTIMATED USING THE FOLLOWING FORMULA:

$$Q_{REQ} = \frac{q \cdot l}{i}$$

WHERE

$l$  = LENGTH OF LONGEST FLOW PATH  
 $i$  = HYDRAULIC GRADIENT  
 $Q_{REQ}$  = TRANSMISSIVITY



# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 7-30-90 Subject LANDFILL B-18, LCRS Sheet No. 4 of 23  
 Chkd. By GSC Date 8/13/90 EVALUATION Proj. No. 89-977

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21
BASED ON	THE ANNUAL	LEACHATE	GENERATION	RATE,	THE	REQUIRED	TRANSMISSIVITY	FOR EACH	CELL	ARE	CALCULATED	AS FOLLOWS:								
SUMP	$L_4$	$\Delta H$	$L$	$i$	$K$															
IA SLOPE	220	113	247	0.51																
IA <u>BOTTOM</u>	420	10	420	0.024																
IB SLOPE	230	92	248	0.4																
IB <u>BOTTOM</u>	800	20	800	<u>0.025</u>																
IA SLOPE	90	44	100	0.49																
IA <u>BOTTOM</u>	600	16	600	0.027																
IB SLOPE	90	46	101	0.51																
IB <u>BOTTOM</u>	710	16	710	<u>0.025</u>																

TEST RESULTS FOR A GEOCOMPOSITE (GEOTEXTILE/GEONET/GEOTEXTILE) PLACED BETWEEN TWO LAYERS OF SOILS ARE AS FOLLOWS

$i$	TEST	SEE EXHIBIT Z AT PRESSURE OF 75000PSF
0.25	$5 \times 10^{-5} \text{ m}^2/\text{sec}$	}
0.5	$4 \times 10^{-5} \text{ m}^2/\text{sec}$	

BY COMPARING THE TEST RESULTS USING HIGHER GRADIENT FOR THE SLOPES AND LOWER GRADIENT FOR THE BOTTOMS OF THE LANDFILL WITH THE REQUIRED TRANSMISSIVITY,

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-11-90 Subject LANDFILL B-18 Sheet No. 5 of 23  
Chkd. By GSC Date 8/12/90 LCRS EVALUATION Proj. No. 89-977

1  
2 THE TEST RESULTS ARE MUCH HIGHER FOR THE SLOPE PORTION  
3  
4 BUT ONLY SLIGHTLY HIGHER FOR THE BOTTOM PORTION HOWEVER, THE  
5  
6 ASSUMPTION OF 100 % OF THE PRECIPITATION WILL  
7  
8 PERCOLATE THROUGH THE WASTE IS VERY CONSERVATIVE.  
9  
10 FURTHERMORE, THE TRANSMISSIVITY FOR THE B-18  
11  
12 GEOCOMPOSITE SYSTEM IS EXPECTED TO BE HIGHER  
13  
14 THAN THE REPORTED VALUES BECAUSE THE GEOCOMPOSITE  
15  
16 SYSTEM FOR THE B-18 LANDFILL WILL BE PLACED BELOW A GRANULAR  
17  
18 LAYER AND ATOP A HOPE LAYER WHICH WILL BE LESS  
19  
20 RESTRICTIVE FOR FLUID FLOW THAN THE SOIL LAYERS USED  
21  
22 IN THE TEST. THEREFORE, THE CAPACITY OF THE  
23  
24 LCRS IS CONSIDERED ADEQUATE.

25  
26 (RESULTS ARE COMPARED TO TREVIRA 1125  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36



# ENVIRONMENTAL SOLUTIONS, INC.

By WPL Date 8-10-90 Subject LANDFILL B-18 Sheet No. 6 of 23  
 Chkd. By ES Date 8/12/90 LCRS EVALUATION Proj. No. 89-977

PER DARCY'S LAW, THE REQUIRED TRANSMISSIVITY,  
 ALONG THE PERIMETER OF THE LEACHATE SUMP  
 MAY BE EXPRESSED BY

$$Q = k i A$$

$$= k i w t$$

$$Q_{REQ} = \frac{Q}{w i}$$

WHERE  $w$  IS THE PERIMETER OF THE LEACHATE SUMP.

BASED ON THE AVERAGE ANNUAL PRECIPITATION OF 6.48 IN

THE RUN-OFF VOLUME FOR EACH SUMP IS

SUMP	$i$ ft/yr	RUN-OFF AREA (ACRES)	VOLUME <sup>(1)</sup> (cfs)
IA	$1.7 \times 10^{-8}$	90	$6.7 \times 10^{-3}$
IB	↓	125	$9.2 \times 10^{-3}$
IIA		16.9	$1.3 \times 10^{-2}$
IIB		15.1	$1.1 \times 10^{-2}$

(1) VOLUME =  $C i A$

WHERE  $i = \frac{6.48}{365 \times 24} = 7.4 \times 10^{-4} \text{ IN/HR}$

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-10-90 Subject LANDFILL B-18 Sheet No. 7 of 23  
 Chkd. By GSC Date 8/13/90 LCRS EVALUATION Proj. No. 89-977

BASED ON THE ANNUAL LEACHATE GENERATION RATE, THE REQUIRED TRANSMISSIVITY FOR EACH SOUP IS CALCULATED AS FOLLOWS:

PHASE	W (ft)	i	Q (G/S)	Q <sub>REQ</sub> (M <sup>3</sup> /SEC)	OVERBURDEN (PSF)	Q <sub>TEST</sub> <sup>(1)</sup> (M <sup>3</sup> /SEC)
IA	550	0.02	$6.7 \times 10^3$	$5.7 \times 10^5$	21275	$6.5 \times 10^5$
IB	540	0.02	$9.2 \times 10^3$	$8.2 \times 10^6$	21275	$6.5 \times 10^5$
IA	600	0.02	$1.3 \times 10^2$	$1.1 \times 10^4$	13225	$1.4 \times 10^4$
IB	650	0.02	$1.1 \times 10^2$	$7.9 \times 10^5$	13225	$1.3 \times 10^4$

(1) EXHIBIT 2

Q<sub>TEST</sub> > Q<sub>REQ</sub> IN ALL CASES

BASED ON THE ABOVE CALCULATION, THE GEOCOMPOSITE CAPACITY ALONE IN PHASE IB SOUP WILL NOT BE SUFFICIENT TO HANDLE THE FLOW. THEREFORE, HYDRAULIC HEAD IS EXPECTED TO BUILD UP IN THE GRANULAR DRAINAGE LAYER. BASED ON MINIMUM TECHNOLOGY GUIDANCE, THE HYDRAULIC HEAD BUILD-UP ATOP THE LCRS CANNOT EXCEED 12" AT ALL TIME.

# ENVIRONMENTAL SOLUTIONS, INC.

By WPL Date 7-31-90 Subject LANDFILL B-B LCRS Sheet No. 8 of 23

Chkd. By GCC Date 8/12/90 EVALUATION Proj. No. 89-977

## GRANULAR DRAINAGE LAYER

THE MAXIMUM HYDRAULIC HEAD IN THE DRAINAGE LAYER  
CAN BE ESTIMATED USING THE FORMULA:

$$h_{max} = \frac{L}{2n} \left[ \sqrt{\frac{e}{K_s} + \tan^2 \theta} - \tan \theta \right] \quad \begin{matrix} \text{(REF. 1)} \\ \text{EQ. (3-6)} \end{matrix}$$

WHERE

L = EFFECTIVE FLOW LENGTH OF THE LCR

n = POROSITY OF DRAINAGE LAYER = 0.4 (REF 2)

e = INFILTRATION RATE

$\theta$  = HYDRAULIC GRADIENT

$K_s$  = DRAINAGE LAYER PERMEABILITY = 0.5 cm/sec (REF 2)  
= 0.19 in/sec

# ENVIRONMENTAL SOLUTIONS, INC.

By JTC Date 8-14-90 Subject LANDFILL B-18 Sheet No. 9 of 23  
Chkd. By GSC Date 8/15/90 LCRS EVALUATION Proj. No. 89-977

1  
2 BASED ON AVERAGE ANNUAL PRECIPITATION OF 648 IN, THE  
3  
4 INFILTRATION RATE  $e$  IS  
5

$$6 \quad e = \frac{6.48}{365 \times 24 \times 3600} = 2.1 \times 10^{-7} \text{ in/sec}$$

$$7 \quad L = 110 \quad \quad \quad \delta = 0.02$$

$$8 \quad \therefore h = \frac{110 \times 12}{2 \times 0.4} \left[ \sqrt{\frac{2.1 \times 10^{-7}}{0.19} + 0.02^2} - 0.02 \right]$$
$$9 \quad = 0.04'' \ll 12'' \quad \text{OK.}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By ups Date 7-30-90 Subject LANDFILL B-18 LCRC Sheet No. 10 of 23  
 Chkd. By GSC Date 8/13/90 EVALUATION Proj. No. 89-977

## LCR SYSTEM CAPACITY FOR SURFACE WATER FLOW

BASED ON KETTLEMAN STATION RECORD, THE 24-HOUR RAINFALL

OF A 100%-YEAR STORM IS 2.34 IN (EXHIBIT 1).

THE SURFACE WATER RUN-OFF IN EACH CELL IS CALCULATED

AS FOLLOWS:

SUMP	RUNOFF AREA (ACRES)	VOLUME <sup>(1)</sup> (CF)
IA	9.0	0.88
IB	12.5	1.22
IIA	16.9	1.65
IIB	15.1	1.47

$$(1) \text{ VOLUME} = C L A \quad C = \frac{2.34}{24} = 0.09 \text{ IN/HR}$$

BASED ON THE 24-HR 100-YR STORM RUN-OFF VOLUME, THE

REQUIRED TRANSMISSIVITY FOR EACH SUMP IS CALCULATED

AS FOLLOWS:

PHASE	W (FT)	L	Q (CF)	$\sigma_{REQ}$ ( $\text{M}^2/\text{SEC}$ )	OVERBURDEN (PSF)	$C_{TEST}$ <sup>(1)</sup> ( $\text{M}^2/\text{SEC}$ )
IA	540	0.02	0.88	$7.6 \times 10^{-3}$	21275	$6.5 \times 10^{-5}$
IB	520	0.02	1.22	$1.1 \times 10^{-2}$	21275	$6.5 \times 10^{-5}$
IIA	600	0.02	1.65	$1.3 \times 10^{-2}$	13275	$1.4 \times 10^{-4}$
IIB	650	0.02	1.47	$1.1 \times 10^{-2}$	13275	$1.4 \times 10^{-4}$

(1) EXHIBIT 2

# ENVIRONMENTAL SOLUTIONS, INC.

By JPC Date 8-10-90 Subject LANDFILL B-13 Sheet No. 11 of 73  
Chkd. By ESC Date 8/13/90 LCPS EVALUATION Proj. No. 89-977

1  
2 BASED ON THE ABOVE CALCULATION, THE GEOCOMPOSITE  
3  
4 ABOVE IS NOT CAPABLE TO HANDLE THE SURFACE WATER  
5  
6 FROM A 100-YEAR STORM. THEREFORE, HYDRAULIC HEAD IS  
7  
8 EXPECTED TO BUILD UP IN THE LEACHATE SUMP  
9  
10  
11 THE INFILTRATION RATE FOR A 24-HR 100-YR STORM  
12  
13 IS

$$e = \frac{234}{24 \times 3600} = 2.71 \times 10^{-5} \text{ IN/SEC}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By 77i Date 7-30-90 Subject LANDFILL B-18, LCPS Sheet No. 12 of 23  
Chkd. By GSC Date 8/15/90 EVALUATION Proj. No. 89-977

1  
2 BASED ON A 100-YR STORM IN A 24 HOUR PERIOD,  
3  
4 THE HYDRAULIC HEAD BUILT UP IN EACH SOU IS  
5  
6 CALCULATED AS FOLLOWS =  
7

8 PHASE	L (ft)	Z	h(max) (in)
9 IA	100	0.02	4.9
10 IB	110	0.02	5.4
11 IA	100	0.02	4.9
12 IB	130	0.02	6.4

13  
14  
15  
16 (1) L = EF  
17

18 THE HYDRAULIC HEAD BUILT UP IN THE GRANULAR  
19 LAYER WILL BE LESS THAN 12". THEREFORE, THE  
20 HYDRAULIC HEAD BUILT-UP WILL BE LESS THAN THE  
21  
22 MTG (MINIMUM TECHNOLOGY GUIDANCE) CRITERIA OF NO MORE  
23  
24 THAN 1 FOOT OF LEACHATE ACTING ON THE LAYER  
25  
26 AT ALL TIME.  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

# Attachment 2

Updated LCRS Calculations



# LCRS Calculations

by: RJS  
 Checked: RH  
 Reviewed: SS

Avg. Annual Rainfall = 6.48 in  
 Average Leachate gen. Rate = 1.71E-08 ft/sec/ft<sup>2</sup>

Area	$\Delta L$	i	Required Transmissivity (m <sup>2</sup> /sec)	Geocomposite transmissivity (m <sup>2</sup> /sec)	Drainage layer Transmissivity (m <sup>2</sup> /sec)	Total Transmissivity (m <sup>2</sup> /sec)	Required Capacity met?
IA Slope	400	0.411	1.55E-06	4.00E-05	4.00E-05	4.00E-05	yes
IA Bottom	675	0.024	4.51E-05	5.00E-05	3.05E-05	8.05E-05	yes
IB Slope	425	0.363	1.86E-06	4.00E-05	4.00E-05	4.00E-05	yes
IB Bottom	1100	0.026	6.78E-05	5.00E-05	3.05E-05	8.05E-05	yes
I/A Slope	275	0.354	1.24E-06	4.00E-05	4.00E-05	4.00E-05	yes
I/A Bottom	850	0.026	5.18E-05	5.00E-05	3.05E-05	8.05E-05	yes
I/B Slope	450	0.406	1.76E-06	4.00E-05	4.00E-05	4.00E-05	yes
I/B Bottom	875	0.028	5.06E-05	5.00E-05	3.05E-05	8.05E-05	yes

Adequacy of system along perimeter of leachate sump

Sump	Leachate generation	Run-off Area (acres)	w (ft)	i	Potential Leachate Volume (cfs)	Drainage Layer		Sump Capacity		Adequate Sump Capacity	
						Hydraulic Conductivity (in <sup>2</sup> /sec)	(cfs) Q = kIA	(gallons/day)	Capacity	Capacity	Capacity
IA	1.71E-08	12.9	550	0.02	9.6E-03	0.19	1.5E-02	9,380	9,380	yes	yes
IB	1.71E-08	19.7	540	0.02	1.5E-02	0.19	1.4E-02	9,209	9,209	no	no
I/A	1.71E-08	17.8	600	0.02	1.3E-02	0.19	1.6E-02	10,233	10,233	yes	yes
I/B	1.71E-08	17.5	650	0.02	1.3E-02	0.19	1.7E-02	11,085	11,085	yes	yes

Leachate generation assumes all rainfall will be collected as leachate.

Note: the leachate flow capacity for each sump is in excess of 9,000 gallons per day. Based on historic measurements the maximum leachate generation rate has been approximately 6,000 gallons per day. This peak generation was measured during a one month period and can be attributed to an exposure of the geocomposite. Leachate generation has typically been less than 200 gallons per day, on average (January 2001 to December 2007). Given the dry nature of the facility and that the existing waste is below field capacity, the leachate generation rate is expected to remain in the 200 to 300 gallons per day per sump (maximum). The construction of Phase III is not expected to result in significantly larger volumes of leachate.

**APPENDIX K.2**  
**GEOTEXTILE FILTER CAPACITY**

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-10-90 Subject LANDFILL B-18 LCPS Sheet No. 13 of 23  
Chkd. By GSC Date 8/13/90 EVALUATION Proj. No. 89-977

## FILTER - RETENTION CAPACITY

THE FILTER-RETENTION CAPACITY COMPUTATION IS NOT NECESSARY FOR THE GEOTEXTILE PLACED IN THE SECONDARY LCPS BECAUSE INSUFFICIENT WATER FLOW IS EXPECTED IN THE LCPS TO CAUSE SOIL PARTICLES MOVEMENT. FOR THE PRIMARY LCPS, A LAYER OF GEOTEXTILE IS PLACED BETWEEN THE OPERATION LAYER AND THE DRAINAGE LAYER. SINCE THE OPERATION LAYER MATERIAL WILL BE NON-COHESIVE, IT IS ASSUMED THAT THE GRAIN SIZE CHARACTERISTICS ARE SIMILAR TO THE ON-SITE SANDSTONE MATERIALS. THE CALCULATION IS NOT REQUIRED FOR THE SLOPE PORTION OF THE LANDFILL BECAUSE THE POTENTIAL FOR HYDRAULIC HEAD BUILT-UP ON SLOPE IS UNLIKELY.

## CRITERION 1 - RETENTION CAPACITY

FOR SOIL LESS THAN 50% PASSING #200 SIEVE  
AOS OF FABRIC > NO 30 SIEVE  
(SEE EXHIBIT 3 - SANDSTONE GRAIN SIZE CHARACTERISTIC)

		SIEVE #	
AOS OF FABRIC	(TREVIRA 1155)	= 120 - 170	> 30 OK
	(TREVIRA 1120)	= 70 - 100	> 30 OK

REF = EXHIBIT 4

# ENVIRONMENTAL SOLUTIONS, INC.

By WPS Date 8-11-90 Subject LANDFILL B-18 LCPS Sheet No. 14 of 23  
Chkd. By GSC Date 8/13/90 EVALUATION Proj. No. 89-917

## CRITERION 2 - FLOWING THROUGH & CLOGGING

$$c) \frac{D_{95}}{d_{85}} < 2 \quad \text{FLOWING THROUGH CRITERION (REF 1 EQ. 3.11)}$$

$$c) \frac{D_{95}}{d_{15}} > 2 \quad \text{CLOGGING CRITERION (REF 1 EQ. 3.12)}$$

FOR THE SANDSTONE MATERIALS, (EXHIBIT 3), THE AVERAGE  $d_{85}$  &  $d_{15}$  IS 0.46 mm AND 0.075 OR LESS, RESPECTIVELY;

AND  $D_{95}$  FOR TREVIRA 1155 RANGES FROM 0.125 ~ 0.088.  
(EXHIBIT 4) (5)  
THEREFORE (5) MP

$$\frac{D_{95}}{d_{85}} = \frac{0.125}{0.46} = 0.27 < 2 \quad \text{OK}$$

$$\frac{D_{95}}{d_{15}} = \frac{0.088}{< 0.075} = 1.17 \text{ OR GREATER } \text{ SHOULD BE } > 2$$

FOR TREVIRA 1125  $D_{95}$  RANGES FROM 0.21 TO 0.149 (EXHIBIT 4) (5) MP

THEREFORE

$$\frac{D_{95}}{d_{85}} = \frac{0.21}{0.46} = 0.46 < 2 \quad \text{OK}$$

$$\frac{D_{95}}{d_{15}} = \frac{0.149}{0.06} = 2.5 > 2 \quad \text{OK}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By Jpi Date 8-11-90 Subject LANDFILL E-13 LCPS Sheet No. 15 of 23

Chkd. By GS Date 9/13/90 EVALUATION Proj. No. 89-977

## CRITERION 3. - EXCESSIVE LOSS OF FINES

ASSUME THE SANDSTONE MATERIAL WILL BECOME DENSE ( $D_r > 80\%$ )

AFTER WATER PERCOLATING THROUGH THE LAYER (JETTING EFFECT).

COEFFICIENT OF UNIFORMITY OF THE MATERIAL

$$CU = \frac{d_{60}}{d_{10}} > 3 \quad d_{60} = 0.25 \sim 0.28 \text{ mm} \quad CV = \frac{0.28}{0.06} = 4.7$$
$$d_{10} = < 0.06$$

THEREFORE :

$$\frac{18 d_{50}}{CU} = \frac{18 \times 0.2}{4.7} = 0.77 > 0.95 \quad \begin{matrix} \text{TREVIRA} \\ 1155 \end{matrix} \quad \begin{matrix} \text{TREVIRA} \\ 1125 \end{matrix} \quad (0.25 \sim 0.28 \text{ mm}), (0.21 \sim 0.149) \quad \text{OK}$$

USING A MORE RESTRICTIVE CRITERION BY ASSUMING THE

SANDSTONE IS LOOSE, THUS

$$\frac{9 d_{50}}{CU} = \frac{9 \times 0.21}{4.7} = 0.38 > 0.95 \quad \text{OK}$$

# ENVIRONMENTAL SOLUTIONS, INC.

By JPL Date 8-13-90 Subject LANDFILL B-1B Sheet No. 16 of 23  
Chkd. By GSC Date 8/13/90 LCRS EVALUATION Proj. No. 89-977

## PERMEABILITY

THE PERMEABILITY OF THE GEOTEXTILE SHOULD BE  
GREATER THAN THE PERMEABILITY OF THE OPERATION LAYER  
BASED ON GRBIN SIZE CHARACTERISTICS OF THE OPERATION  
LAYER MATERIAL, THE PERMEABILITY OF THE MATERIAL MAY  
BE ESTIMATED AS:

$$k_{\text{SOIL}} = C D_{10}^2 \quad C=100 \quad (\text{REF 3 EQ 19-9})$$
$$= 100 \times 0.006^2 \quad D_{10} < 0.006 \text{ cm} \quad \text{EXHIBIT 3}$$
$$= 0.0036 \text{ cm/sec}$$

$\therefore k_{\text{SOIL}} < 0.0036 \text{ cm/sec} < k_{\text{fabric}} \text{ (TREVIRA 1125 = 0.59 cm/sec)}$  ✓

## PUNCTURE RESISTANCE

BASED ON REFERENCE 4, THE TENSILE FORCE IN  
THE GEOTEXTILE T MAY BE ESTIMATED AS

$$T = \pi (d_i d_a) P' S'$$

WHERE

$d_i$  : INITIAL AVERAGE VOID DIAMETER OF THE  
GEOTEXTILE. = 0.21 mm = 0.008 in (TREVIRA 1120) (EXHIBIT 3)

$d_a$  : AVERAGE DIAMETER OF THE MATERIAL / USE  $d_{50} = 0.2 \text{ mm}$   
= 0.008 in

# ENVIRONMENTAL SOLUTIONS, INC.

By Jpi Date 8-13-90 Subject LANDFILL B-18 Sheet No. 17 of 23  
Chkd. By SSC Date 8/13/90 LCPS EVALUATION Proj. No. 89-977

1  
2  $P' = \text{OVERBURDEN PRESSURE} = 210 \times 115 = 168 \text{ psf}$

3  
4  $S' = \text{SHAPE FACTOR USE 1 FOR SHARP OBJECT (CONSERVATIVE)}$

5  
6  
7  $T = \pi \times 0.008 \times 0.008 \times 168 \times 1 = 0.03 \text{ lb}$

8  
9  
10 PUNCTURE STRENGTH FOR TFEVIB 1120 = 100 lb  $\gg 0.03 \text{ lb}$  O.K.

11  
12 CONSIDER THE PUNCTURE POTENTIAL FROM THE GRANULAR DRAINAGE  
13 LAYER.

14  
15  $S' = 0.6$  CRUSHED STONE (REF 2)

16  
17  $d_a = 0.25$  CRUSHED STONE (REF 2)

18  
19  
20  $T = \pi \times 0.008 \times 0.25 \times 168 \times 0.6 = 0.6 \text{ lb} \ll 100 \text{ lb}$

21  
22  
23 RETENTION CAPACITY AND POTENTIAL FOR CLOGGING AND EXCESSIVE  
24 LOSS OF FINES ARE NO CONCERN FOR THE GEOTEXTILE

25  
26  
27 UNDER THE GRANULAR DRAINAGE LAYER BECAUSE OF

28  
29 LACK OF FINES IN THE GRADATION OF THE GRANULAR  
30 MATERIALS (SEE SPECIFICATION 2.03, LESS THAN 5%

31  
32 OF THE MATERIAL WILL PASS # 100 SIEVE)

# ENVIRONMENTAL SOLUTIONS, INC.

By Jpi Date 8-15-90 Subject LANDFILL B-18

Sheet No. 10 of 23

Chkd. By GSC Date 8/13/90 LCRS EVALUATION

Proj. No. 89-977

## CONCLUSION

THE CAPACITY OF THE LCRS AND THE GEOTEXTILE DESIGN IN THE PRIMARY LCRS HAVE BEEN EVALUATED. BASED ON THE CALCULATION PERFORMED, THE LCRS CAPACITY IS CONSIDERED ADEQUATE TO HANDLE LEACHATE FLOW THAT MAY GENERATED DURING LANDFILL OPERATION. THE CALCULATION ALSO INDICATED THAT THE GEOTEXTILE <sup>(TREVIRA 112E)</sup> USED IN THE PRIMARY LCRS HAS MET THE CRITERIA FOR RETENTION, CLOGGING, AND PREVENTION OF EXCESSIVE LOSS OF FINES.





20/23

TABLE 3. HYDRAULIC TRANSMISSIVITY ( $M^2/Sec \times 10^{-3}$ )  
SOIL/TREVIRA 1120/PN3000 GEONET/TREVIRA 1120/SOIL

By FLUID SYSTEM, INC, CINCINNATI, OHIO.

GRADIENT = 0.25

Specimen	5,000 psf	10,000 psf	15,000 psf	20,000 psf	25,000 psf
1.	0.41	0.16	0.07	0.04	0.02
2.	0.42	0.17	0.08	0.05	0.04
3.	0.48	0.23	0.14	0.11	0.09
Avg:	0.44	0.19	0.10	0.07	0.05
SD:	0.04	0.04	0.04	0.04	0.04

GRADIENT = 0.50

Specimen	5,000 psf	10,000 psf	15,000 psf	20,000 psf	25,000 psf
1.	0.36	0.14	0.08	0.03	0.02
2.	0.37	0.14	0.08	0.04	0.03
3.	0.40	0.18	0.11	0.07	0.06
Avg:	0.38	0.15	0.09	0.05	0.04
SD:	0.02	0.02	0.02	0.02	0.02

GRADIENT = 0.75


Specimen	5,000 psf	10,000 psf	15,000 psf	20,000 psf	25,000 psf
1.	0.32	0.14	0.06	0.04	0.03
2.	0.32	0.14	0.06	0.05	0.03
3.	0.35	0.16	0.08	0.06	0.05
Avg:	0.33	0.15	0.07	0.05	0.04
SD:	0.02	0.01	0.01	0.01	0.01

GRADIENT = 1.0

Specimen	5,000 psf	10,000 psf	15,000 psf	20,000 psf	25,000 psf
1.	0.26	0.12	0.05	0.03	0.03
2.	0.26	0.12	0.06	0.04	0.03
3.	0.29	0.14	0.07	0.05	0.04
Avg:	0.27	0.13	0.06	0.04	0.03
SD:	0.02	0.01	0.01	0.01	0.01

89-977/FIG D.2.7/GSID/U18-9 REV. 8/7/90

SYMBOL	TEST PIT TYPE	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE	USCS
+ ——— +	TP-1, B-1	7.0	--	--	18-9	Sandstone	SM
Δ ----- Δ	TP-42, B-1	6.0	--	--	18-9	Sandstone	SM




COBBLES	GRAVEL		SAND			SILT AND CLAY FRACTION
	coarse	fine	coarse	medium	fine	

FIGURE D.2.7  
**GRAIN SIZE DISTRIBUTION**  
**STRATIGRAPHIC UNIT 18-9**  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**

89-977/Fig D.2.8/G-S/D/U/18-11 REV. 8/7/90

SYMBOL	BORING	DEPTH (ft.)	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRATIGRAPHIC UNIT	MATERIAL TYPE	USCS
○—○	L18-B	37.0-39.5	--	--	18-11	Sandstone	SM



COBBLES	GRAVEL		SAND			SILT AND CLAY FRACTION
	coarse	fine	coarse	medium	fine	

**FIGURE D.2.8**  
**GRAIN SIZE DISTRIBUTION**  
**STRATIGRAPHIC UNIT 18-11**  
  
 LANDFILL UNIT B-18  
 KETTLEMAN HILLS FACILITY  
**ENVIRONMENTAL SOLUTIONS, INC.**

PERMEABILITY DATA IS BASED ON TREVIRA 1120

# Trevira® Spunbond nonwoven engineering products are highly needed fabrics with excellent tensile properties, high filtration potential and outstanding permeability.

Trevira® Spunbond Type 11 products are 100% continuous filament polyester nonwoven needlepunched engineering fabrics. They deliver a combination of advantages unmatched by any other spunbonded geotextiles. They're resistant to freeze-thaw, soil chemicals and ultraviolet light exposure.

Trevira® Spunbond nonwoven engineering fabrics offer excellent performance where the requirement is tensile reinforcement, planar flow, filtration, or separation. They are ideal for roadways, railbeds, drainage systems, pondliners, retaining walls. And much more.



The information contained herein is offered free of charge, and is, to our best knowledge, true and accurate; however, all recommendations or suggestions are made without guarantee, since the conditions of use are beyond our control. There is no expressed warranty and no implied warranty of merchantability or of fitness for purpose of the product or products described herein. In submitting this information, no liability is assumed or license or other rights implied given with respect to the use of the information.

TYPICAL PHYSICAL PROPERTIES OF TREVIRA® TYPE 11 PRODUCTS

Fabric Property	Unit	Test Method	1112	1114	1120	1125	1135	1145	1155
Fabric Weight	oz/yd <sup>2</sup>	ASTM D-3776	3.5	4.2	6.0	7.5	10.5	13.5	16.5
Thickness, t	mils	ASTM D-1777	60	70	95	115	150	175	215
Grab Strength (MD/CD) <sup>1)</sup>	lbs	ASTM D-4632	120/95	150/115	230/180	305/235	420/350	500/425	650/750
Grab Elongation (MD/CD) <sup>1)</sup>	%	ASTM D-4632	65/75	65/70	65/75	65/75	65/75	70/75	70/75
Trapezoid Tear Strength (MD/CD) <sup>1)</sup>	lbs	ASTM D-4533	50/40	55/50	80/75	105/90	145/130	185/170	215/190
Puncture Resistance	lbs	ASTM D-4833	55	65	100	115	160	180	230
Mullen Burst Strength	psi	ASTM D-3786	195	230	345	400	590	750	900
Water Flow Rate	gpm/ft <sup>2</sup>	ASTM D-4491	200	200	180	150	120	90	75
Permittivity, $\Psi$	sec <sup>-1</sup>	ASTM D-4491	2.71	2.71	2.44	2.04	1.63	1.22	1.02
Permeability, k	cm/sec	k = $\Psi$ t	.41	.48	.59	.59	.62	.54	.56
AOS	Sieve Size mm	ASTM D-4751	70-100 210-149	70-100 210-149	70-100 210-149	70-100 210-149	70-100 210-125	100-120 149-125	120-170 125-088
Standard Roll Widths <sup>2)</sup>	ft		12.5 and 15.0						
Standard Roll Length <sup>2)</sup>	ft		400	400	300	300	300	300	300

<sup>1)</sup>MD = Machine Direction, CD = Cross Machine Direction.

<sup>2)</sup>Other width and length rolls are available upon request.

MINIMUM AVERAGE ROLL VALUES (WEAKEST PRINCIPAL DIRECTION) OF TREVIRA® TYPE 11 PRODUCTS

Fabric Property	Unit	Test Method	1112	1114	1120	1125	1135	1145	1155
Fabric Weight	oz/yd <sup>2</sup>	ASTM D-3776	3.3	4.0	5.7	7.1	10.0	13.0	16.0
Thickness, t	mils	ASTM D-1777	50	55	80	95	130	155	200
Grab Strength	lbs	ASTM D-4632	80	100	160	210	300	375	500
Grab Elongation	%	ASTM D-4632	50	50	50	50	50	50	50
Trapezoid Tear Strength	lbs	ASTM D-4533	30	40	60	75	100	130	160
Puncture Resistance	lbs	ASTM D-4833	40	45	80	95	130	155	195
Mullen Burst Strength	psi	ASTM D-3786	170	190	305	360	530	700	825
Water Flow Rate	gpm/ft <sup>2</sup>	ASTM D-4491	150	150	130	100	80	60	40
Permittivity, $\Psi$	sec <sup>-1</sup>	ASTM D-4491	2.03	2.03	1.76	1.36	1.08	0.81	0.54
Permeability, k	cm/sec	k = $\Psi$ t	.26	.28	.36	.33	.36	.32	.28
AOS <sup>3)</sup>	Sieve Size mm	ASTM D-4751							

23/23

**APPENDIX L**  
**RISER PIPE ANALYSES**



**Kettleman Hills Facility – Landfill Unit B-18  
RISER PIPES**

Project No.: 083-91887

Made By: EH

Date: 02-23-2010 (Revision 1)

Checked By: RH

Sheet: 1 of 2

Reviewed By: SS

**Objectives:**

1. Evaluate the ability of the existing vertical LCRS riser pipes and underlying clay liner to withstand loading from an additional 90 vertical feet of waste placed above the original top of waste grade to the proposed Phase III top of waste grade.
2. Evaluate the ability of the existing sideslope riser pipes to withstand loading from an additional 90 vertical feet of waste placed above the original top of waste grade to the proposed Phase III top of waste grade.

**Given:**

The currently-permitted maximum waste height in the vicinity of the vertical and sideslope riser pipes is approximately 210 feet. The proposed Phase III expansion will increase this maximum waste height to approximately 300 feet (i.e., an approximately 90-foot increase). The as-built locations and configurations of the existing piping as well as the pipe materials and properties are shown on the Phases I and II construction drawings in Appendix A.1. The construction drawings in Appendix A.2 show the proposed final waste configuration.

**Assumptions and Methodology:**

The assumptions and methodology used to evaluate the existing vertical and sideslope riser pipes follows that of ESI (1990) for the original design of B-18. Golder has updated ESI's previous calculations to reflect the increased waste height (the methods utilized in the calculations are taken directly from the 1990 ESI calculations).

**Summary of Results:**

The calculations for the riser pipes are presented in Attachment A. The vertical riser pipe calculations are shown on pages 1 thru 11 while the sideslope riser pipe calculations are shown on pages 12 thru 17. The calculations indicate the following:

1. Vertical riser pipes: the existing vertical riser pipes and underlying clay liner are anticipated to have sufficient strength to resist the additional pressures from 90 extra feet of waste.
2. Sideslope riser pipes: the existing 8-inch-diameter steel riser pipes are anticipated to deflect a maximum of approximately 0.9% of their diameter under the full height of waste (300 feet), which is an acceptable deflection. As in the original design (ESI, 1990), the 8-inch-diameter HDPE riser pipes are anticipated to deflect more than 20% of their diameter (i.e., 21% to 34%). This amount of deflection exceeds the manufacturer's recommended maximum, but since the HDPE pipe is a backup to the steel pipe, it is considered acceptable for the sideslope riser application.
3. The proposed design provides for a transition from carbon steel pipe to a HDPE pipe. During the B-18 Phases I and II construction in the early 1990s, steel pipes were used due to the anticipated high loads and relatively new use of HPDE pipe. Since this time, however,



**Kettleman Hills Facility – Landfill Unit B-18  
RISER PIPES**

Project No.: 083-91887

Made By: EH

Date: 02-23-2010 (Revision 1)

Checked By: RH

Sheet: 2 of 2

Reviewed By: SS

HDPE pipes are commonly used for LCRS riser pipes, including Landfill B-17 and Landfill B-19 Phase 1A at the Kettleman Hills Facility. Based on Golder's experience, there is little movement of the LCRS riser pipes once these pipes have been confined by soil cover/operations layer. This would be particularly true for the vadose and secondary riser pipes which are placed within excavated trenches and are below the weakest liner interface. For the primary riser pipe, movement of the waste could result in deflection of the LCRS riser. However, the movement of the waste (due to settlement) would primarily be down slope. Down slope movement would not result in significant shear on the LCRS riser; in fact the slip connection between the HDPE and steel pipes would allow for stress release if compression forces develop due to waste settlement. Additionally, it should be noted that the magnitude of settlement for the Class I waste in B-18 is relatively small compared with that of Class III municipal solid wastes. In summary, Golder believes that the riser pipes will not be subjected to shear forces that could damage the pipes and, therefore, the pipes will perform as designed. In the unlikely event of a failure at the steel/HDPE transition, the design includes redundant primary and secondary riser pipe systems which do not include the transition from steel to HDPE.

**Reference:**

Environmental Solutions Inc. (ESI), "Engineering and Design Report, Landfill Unit B-18, Phases I and II and Final Closure, Kettleman Hills Facility," August 1990.



# Attachment A

## Riser Pipe Calculations

# ENVIRONMENTAL SOLUTIONS, INC.

Attachment A


By GSC Date 7/27/90 Subject BEARING CAPACITY

Sheet No. 5 of 29

Chkd. By Jim Date 8/15/90 VERTICAL RISER FOR

Proj. No. 89-77

Modified By: Goldar 5/18/08 KETTLEMAN LANDFILL



Objective : To calculate the available bearing capacity of the clay liner and design the riser base dimension

RESULTS FROM UU TEST OF MODIFIED PROCTOR FOR CLAYSTONE

INDICATE  $\phi = 8^\circ$   $c = 3600$  psf --- CLAY LINER  
 USE  $c = 3600$  psf for design

Native Formation  $\phi = 36^\circ$

- Check squeezing effect to clay liner  
 Ref: "Foundation design & Construction" by Hamlington P. 211  
 See attachment # page 23 Goldar

$$\frac{B+8}{5}$$

Thickness of clay layer

Assuming max.  $B = 10'$

$$\frac{10+8}{5} = \frac{18}{5} = 3.6 < 6$$

Therefore, no squeezing effect is considered.

- Check allowable bearing pressure for clay liner

$$q_u = cN_c + \gamma'd$$

where  $c$  = undrained shear strength  
 $N_c = 6(1 + 0.2 D/B)$  or limit to 9.0  
 $D$  = Depth of footing below ground  
 $B$  = width of foot  
 $\gamma'$  = effective unit weight of soil  
 $d$  = Thickness of footing

$$= 9c + \gamma'd$$

$$= 9 \times 3600 \text{ psf} + 115 \times 2 \text{ psf}$$

$$= 32400 + 230 = 32630 \text{ psf or } 32.6 \text{ ksf}$$

## ENVIRONMENTAL SOLUTIONS, INC.

By GSC Date 7/27/90 Subject BEARING CAPACITY Sheet No. 2 of 26  
 Chkd. By Jpi Date 8/15/90 VERTICAL RISER BASE Proj. No. 89-977  
 Modified By: Golden 5/18/08

Use factor of safety of 2.0

$$\text{Allowable bearing pressure at top of upper liner} \\ = \frac{32.6}{2} = 16.3 \text{ ksf}$$

Assume use 8 x 8 riser base, and 30° transfer of load from the base at top of gravel to top of clay liner

$$\text{Area at top of clay liner} = (8+8)^2 - \left(\frac{2+8}{2}\right)^2 \pi \\ = 256 - 78.5 \\ = 177.5$$

Top load at base include weight of base

$$= \frac{184.4}{302.5} \text{ Kips} \quad (\text{Ref. to ~~Locate Sand Riser~~ Calculations P. 3 & 4 of 14 pages 5-7)$$

Pressure exerted on top of upper clay liner

$$= \frac{\frac{184.4}{302.5}}{177.5} = \frac{1.7}{177.5} \text{ ksf} < 16.3 \text{ ksf}$$

O.K.

For worst case if clay strength be  $c = 2000 \text{ psf}$

$$q_u = 9 \times 2000 + (115 - 62.4) \times 2 \\ = 18000 + 105 \\ = 18105 \text{ psf or } 18.1 \text{ ksf}$$

$$q_{\text{allowable}} = \frac{18.1}{2} = 9.1 \text{ ksf}$$

$$\text{Applied pressure} = \frac{1.7}{177.5} \text{ ksf} < 9.1 \text{ ksf} \quad \text{O.K.}$$

# ENVIRONMENTAL SOLUTIONS, INC.

Attachment A

By GSC Date 7/27/90 Subject BEARING CAPACITY

Sheet No. 8 of 28

Chkd. By Jim Date 8/15/90

Proj. No. 89-977

Modified By: Golder 5/18/08

For 6 x 6 riser base

$$\begin{aligned} \text{Area at top clay liner} &= (6+8)^2 - \left(\frac{2+8}{2}\right)^2 \pi \\ &= 196 - 78.5 \\ &= 117.5 \text{ ft}^2 \end{aligned}$$

$$\text{Pressure exerted on clay liner} = \frac{302.5}{117.5} = 2.57 \text{ KSF} < 9.1 \text{ KSF}$$

O.K.

- Check consolidation settlement

$$\begin{aligned} \text{The weight of fill above the clay liner} &= \cancel{237} \times 118 \\ &= 300 \times 115 + 7 \times 130 \\ &= 35410 \text{ PSF (35.4 KSF)} \end{aligned}$$

$$\text{Additional pressure due to riser} = 1.56 \text{ KSF}$$

Based on consolidation test results (see attached test results)

An additional settlement of 0.5 percent may be expected

$$\therefore 0.5\% \times 8' = 0.04 \text{ inch (at base of riser)}$$

pages 24-25

# ENVIRONMENTAL SOLUTIONS, INC.

Attachment A

By GSC Date 7/27/90 Subject VERTICAL RISER Sheet No. 8 of 29  
 Chkd. By mp Date 8/15/90 KETTLEMAN LANDFILL Proj. No. 89-977  
 Modified By: Goldner 5/18/08

- Check settlement in the gravel layer below the base of vertical riser

Elastic settlement:

Vertical stress at bottom of riser base

$$\sigma_v = 277 \times 0.115 + 184.4 / [6 \times 6 - (\frac{\pi}{4})^2] \text{ ksf}$$

$$\text{Goldner} = 278 \times 5.6$$

$$= 32.9 \text{ ksf}$$

Typical value of  $E_s$  for sand and gravel (see attachment p. 26)

Assume  $E_s = 14 \text{ ksi}$

$$= 2016 \text{ ksf}$$

$$\epsilon = \frac{\sigma_v}{E} = \frac{32.9}{2016} = 0.016$$

$$\therefore \text{Elastic settlement} = 0.016 \times 7' = 1.67'' \text{ (0.139')}$$

$$= 1.37 \text{ inches}$$

## CONCLUSIONS:

1.) WITH A 6'x6' VERTICAL RISER BASE, THE PRESSURE EXERTED ON CLAY LINER BENEATH THE BASE IS ABOUT Goldner 1.67 ksf. THIS COMPARES WITH A ULTIMATE BEARING CAPACITY OF AT LEAST 18.1 ksf FOR THE CLAY LINER. IT PROVIDES A FACTOR OF SAFETY OF AT LEAST 1.67 AGAINST BEARING FAILURE FOR THE RISER BASE. Goldner

2.) IT IS ANTICIPATED THAT THERE WILL BE A DIFFERENTIAL MOVEMENT BETWEEN THE RISER BASE AND THE BOTTOM STEEL PIPE INSERT. THE MOVEMENT IS EXPECTED TO BE ABOUT 1.67 INCHES DUE TO THE ELASTIC DEFORMATION OF THE GRAVEL LAYER BENEATH THE BASE.

Goldner

**Golder  
Associates**

SUBJECT Attachment A - B-18 Riser Pipes

Job No.  
Ref. 083-91887

Made by EH  
Checked RH  
Reviewed

Date 04/11/08  
Sheet 5 of 26

TO BE CONSERVATIVE, IT IS ASSUMED THAT DOWNDRAG FORCE DUE TO WASTE SETTLEMENT WILL BE TRANSFERRED TO THE STEEL PIPES THROUGH CONTACT BETWEEN THE TWO PIPES. USING A AREA OF 10% OF THE STEEL PIPE, THE DOWNDRAG FORCE IS:

$$F_D = \int_{H_1}^{H_2} (PK_0 \gamma \tan \delta) z \, dz$$

$$= \frac{K_0 \gamma (H_1 + H_2)}{2} \cdot (H_2 - H_1) \cdot \pi \cdot \frac{24}{12} \cdot \tan \delta \cdot 10\%$$

$$= \frac{(1 - \sin 27^\circ) \cdot 115 \cdot (90 + 300)}{2} \cdot (300 - 90) \cdot \pi \cdot 2 \cdot \tan \delta \cdot 10\%$$

$$= 255.8 \text{ kips}$$

WEIGHT OF STEEL PILE SCH 40

$$W_p = 171 \cdot 210 = 35.9 \text{ kips}$$

WEIGHT OF HDPE PIPE

$$W_H = 15.5 \cdot 210 = 3.3 \text{ kips}$$

TOTAL FORCE

$$F = 255.8 + 35.9 + 3.3 = 295 \text{ kips}$$

A 6x6x1.5 CONCRETE PAD USED

CHECK ON ORIGINAL DESIGN OF THE RISER FOUNDATION.

BEARING PLATE FOR THE STEEL PIPE

CIRCUMFERENCE OF VERTICAL RISER

$$C = (24 - 0.687) \times \pi = 73.24 \text{ in}$$

$$\text{CONTACT AREA} = 73.24 \cdot 0.687 = 50.3 \text{ in}^2$$

$$\text{WEIGHT OF PIPE} + \text{DOWNDRAW} = 35.9 + 255.8 = 291.7 \text{ kips}$$

$$\text{BEARING PRESSURE AT STEEL PLATE} = \frac{291.7}{73.24} = 3.98 \text{ kips/in}$$

$$\text{BEARING PRESSURE @ CONCRETE} = \frac{295}{\frac{\pi}{4}(36^2 - 19^2)} = 0.401 \text{ ksi}$$

3000 PSI CONCRETE USED

$$\text{ALLOWABLE BEARING PRESSURE} = 0.5 \cdot 3000 = 1500 \text{ psi} > 401 \text{ psi}$$

$$\text{ALLOWABLE SHEAR STRESS IN BEARING PLATE} = 0.4 F_y$$


USE A36 STEEL  $F_y = 36 \text{ ksi}$

$$\therefore F_v = 0.4 \cdot 36 = 14.4 \text{ ksi} > \frac{291.7}{50.3} = 5.8 \text{ ksi} \quad \underline{\underline{\text{OK}}}$$

A 6x6x1.5 CONCRETE PAD USED

$$W = 6 \cdot 6 \cdot 1.5 \cdot 144 - \frac{\pi}{4} \left( \frac{19}{12} \right)^2 \cdot 1.5 \cdot 144$$

$$= 7.35 \text{ kips}$$



TOTAL DEAD :  $295 + 7.35 = 302.35 \text{ kips}$

$f'_c = 3000 \text{ psi}$ ,  $f_y = 60,000 \text{ psi}$ ,  $d = 1.5 - 0.25 - \left( \frac{0.5}{2} \right) / 12 = 1.23' = 14.76''$

$$q_u = \frac{1.4 \cdot 302.35}{34.03} = 12.44 \text{ ksf}$$

CRITICAL SHEAR :

ONE-WAY SHEAR

$$V_u = q_u \cdot b \cdot (2.21 - d)$$

$$= 12.44 \cdot 6 \cdot (2.21 - 1.23)$$

$$= 73.15 \text{ kips}$$

$$V_c = \phi \cdot 2 \sqrt{f'_c} \cdot b \cdot d$$

$$= 0.85 \cdot 2 \cdot \sqrt{3000} \cdot (6 \cdot 12) \cdot (1.23 \cdot 12)$$

$$= 98.9 \text{ kips} > V_u \quad \underline{\text{OK}}$$

TWO-WAY SHEAR

$$V_u = q_u \cdot \left( b^2 - \left( \frac{19+d}{12} \right)^2 \right)$$

$$= 12.44 \cdot \left( 6^2 - \left( \frac{19+14.76}{12} \right)^2 \right)$$

$$= 349.4 \text{ kips}$$



**Golder  
Associates**

SUBJECT Attachment A - B-18 Riser Pipes

Job No.  
Ref. 083-91887

Made by  
Checked  
Reviewed  
EM  
RH

Date 04/11/08  
Sheet 8 of 26

$$V_c = \phi \cdot 4 \sqrt{f_c'} b_o d$$

$$b_o = 4 \cdot (19 + d) = 4 \cdot (19 + 14.76) = 135.04$$

$$V_c = 0.85 \cdot 4 \cdot \sqrt{3000} \cdot 135.04 \cdot 14.76$$

$$= 371 \text{ kips} > 349.4 \text{ kips}$$

BENDING

CRITICAL BENDING MOMENT :

$$M_u = P_u \cdot \frac{(2 \cdot 21 - d)^2}{2}$$

$$= 12.44 \cdot \frac{(2 \cdot 21 - 1.23)^2}{2}$$

$$= 5.97 \text{ ft-kips}$$

PERCENTAGE OF STEEL REQUIRED

$$\rho = \frac{1}{m} \left( 1 - \sqrt{1 - \frac{2m R_u}{f_y}} \right)$$

WHERE  $m = \frac{f_y}{0.85 f_c'} = \frac{60000}{0.85 \cdot 3000} = 23.5$

$$R_u = \frac{M_u}{\phi b d^2} = \frac{5.97 \cdot 12 \cdot 1000}{0.9 \cdot 12 \cdot 14.76} = 30.45$$

$$\rho = \frac{1}{23.5} \left( 1 - \sqrt{1 - \frac{2 \cdot 23.5 \cdot 30.45}{60000}} \right)$$

$$= 0.00051 = 0.051 \%$$

**Golder  
Associates**

SUBJECT Attachment A - B-13 Riser Pipes

Job No.  
Ref. 083-91887

Made by  
Checked EH  
Reviewed RH

Date 04/11/08  
Sheet 9 of 26

# 5 RE-BAR @ 6" C/C BW USED

$$A_s = 0.62 \text{ in}^2$$

$$\rho = \frac{0.62}{bd} = \frac{0.62}{12 \cdot 14.76} = 0.35\% > 0.051\% \text{ OK}$$

LOWER VERTICAL RISER

PRESSURE AT TOP OF PIPE

$$\text{OVERBURDEN} = 300 \cdot 115 = 34500 \text{ psf}$$

$$\text{BEARING PRESSURE} = 4950 \text{ psf}$$

PRESSURE AT BOTTOM OF PIPE

$$\text{OVERBURDEN} = 34500 + 7 \cdot 130 = 35410 \text{ psf}$$

$$\text{BEARING PRESSURE} = 1017 \text{ psf}$$

LATERAL PRESSURE UNDER AT-REST CONDITION

$$K_0 = (1 - \sin \phi) = (1 - \sin 40^\circ) = 0.35$$

$$P_T = 0.35 \cdot (34500 + 4950) = 13808 \text{ psf}$$

$$P_B = 0.35 \cdot (35410 + 1017) = 12747 \text{ psf}$$

RING COMPRESSION AT TOP OF PIPE

$$P = \frac{13808}{2} \cdot D$$
$$= 6904D$$

**Golder  
Associates**

SUBJECT Attachment A - B-18 Riser Pipes

Job No.  
Ref. 083-91997

Made by EH  
Checked RH  
Reviewed

Date 04/11/08  
Sheet 11 of 26

18" STAINLESS STEEL PIPE ( $E = 28 \times 10^6$  PSI) USED

NOMINAL DIAMETER	OD	ID	$t$	$r$	$I$
18	18	16.5	0.75	8.625	0.035

$$\therefore P = 69.04 \cdot \left(\frac{18}{12}\right) = 10356 \text{ lb/ft} = 863 \text{ lb/in}$$

$$\text{STRESS IN PIPE WALL} = \frac{863}{0.75} = 1150.7 \text{ psi}$$

A FS of 3 IS REQUIRED TO AVOID COLLAPSING OF THE PIPE

THE MAX. CRITICAL PRESSURE IS:

$$P_{CR} = \frac{3EI}{R^3} = \frac{24EI}{R^3}$$

$$FS = \frac{P_{CR}}{P} = \frac{24 \cdot 28 \times 10^6 \cdot 0.035}{(8.625 \cdot 2)^3 \cdot 1150.7} = 3.98 > 3. \quad \underline{\underline{OK}}$$

**Golder  
Associates**

SUBJECT Attachment A - B-1B Riser Pipes

Job No.  
Ref. 083-91887

Made by  
Checked  
Reviewed  
EH  
RH

Date 04/11/08  
Sheet 12 of 26

PIPE DEFLECTION MAY BE DETERMINED BY THE IOWA'S EQUATION:

$$\Delta_x = \frac{KW^3}{EI + 0.061E' r^3} \cdot D_e = \text{pipe deflection}$$

WHERE:

$D_e$  = DEFLECTION FACTOR (= 1.5)

$K$  = BENDING COEFFICIENT (= 0.1)

$W$  = DESIGN LOAD

$r$  = MEAN RADIUS OF PIPE ( $= \frac{OD - t}{2}$ )

$E$  = MODULUS OF PIPE (= 20,000 psi)

$I$  = MOMENT INERTIA OF PIPE ( $= \frac{t^3}{12}$ )

$E'$  = MODULUS OF SOIL REACTION (= 1000 psi)

(COARSE GRAVEL MODERATELY COMPACTED)

**Golder  
Associates**

SUBJECT Attachment A - B-18 Riser Pipes		
Job No.	Made by EH	Date 6/11/08
Ref. 083-91887	Checked RH	Sheet 13 of 26
	Reviewed	

DEFLECTION OF THE SLOPE RISER

(1) 8"  $\phi$  DUCTILE IRON PIPE (SCH 80)

NOMINAL DIAMETER	OD	ID	t	r	I
8"	8.625	7.625	0.5	4.063	0.010

$E = 24 \times 10^6$  FOR DUCTILE IRON PIPE

TRENCH CONDITION

WASTE FILL OVERBURDEN

$$q_f = 115 \times 300 = 34500 \text{ psf}$$

PRESSURE AT TOP OF PIPES DUE TO WASTE FILL

$$\begin{aligned} \sigma_{v1} &= q_f C_{\mu s} \\ &= q_f \cdot e^{-2K_{\mu} (H/B_d)} \\ &= 34500 \cdot e^{-2 \cdot 0.165 \cdot \left( \frac{18 - 3 - 8.625}{18} \right)} \\ &= 30694 \text{ psf} \end{aligned}$$

PRESSURE AT TOP OF PIPE DUE TO TRENCH BACKFILL

$$\begin{aligned} \sigma_{v2} &= B_d \cdot \gamma \cdot C_d \\ &= 1.5 \cdot 130 \cdot \frac{1 - e^{-2 \cdot 0.165 \cdot (6.375/18)}}{2 \cdot 0.165} \\ &= 65 \text{ psf} \end{aligned}$$

TOTAL PRESSURE AT TOP OF PIPE

$$\sigma_{v0} = 30694 + 65 = 30759 \text{ psf}$$

INCREASE OF STRESS DUE TO VERTICAL RISER :

$$\Delta \sigma = \frac{1837}{13^2 - \left( \frac{7+17}{13} \right)^2 \frac{17}{4}} = 1111 \text{ psf}$$

$$\sigma_v = 30759 + 1111 = 31870 \text{ psf}$$

FORCE PER UNIT LENGTH OF PIPE

$$\begin{aligned} W &= \sigma_v \cdot B_c \\ &= 31870 \cdot \frac{8.625}{12} \\ &= 22906 \text{ lb/ft} \\ &= 1909 \text{ lb/in} \end{aligned}$$

$$\therefore \delta y = \frac{K W r^3}{EI + 0.061 E r^3} \cdot D_c$$

$$\begin{aligned} &= \frac{0.1 \times 1909 \times 4.063^3}{24 \cdot 10^6 \times \frac{0.5^3}{12} + 0.061 \times 1000 \times 4.063^3} \cdot 1.5 \\ &= 0.079 \end{aligned}$$

$$\therefore \frac{\delta y}{D} = \frac{0.079}{8.625} = 0.9 \% \ll 5 \% \quad \underline{\underline{OK}}$$

POSITIVE PROJECTION

TOTAL VERTICAL STRESS AT TOP OF PIPE

$$\sigma_v = \sigma_{v1} + \sigma_0 = 34500 + 1017 = 35517$$

FORCE PER UNIT LENGTH OF PIPE

$$\begin{aligned} W &= \sigma_v B_c \\ &= 35517 \cdot \frac{8.625}{12} \\ &= 25527 \text{ lb/ft} \\ &= 2127 \text{ lb/in} \end{aligned}$$



**Golder  
Associates**

SUBJECT Attachment A - B-18 Riser Pipes		
Job No.	Made by	Date
Ref. 083-91887	EH RH	04/11/08
	Checked	Sheet
	Reviewed	16 of 26

$$\Delta y = \frac{0.1 \times 2127 \cdot 4.063^3}{24 \times 10^6 \times \frac{0.5^3}{12} + 0.061 \cdot 1000 \cdot 4.063^3} = 0.08''$$

$$\frac{\Delta y}{D} = \frac{0.08}{8.625} = 0.7\% \ll 5\% \quad \text{OK} \quad \#$$

(2)

CHECK DEFLECTION OF THE 8" HDPE PIPE (SDR=8.3), THE HDPE PIPE HAS THE FOLLOWING PROPERTIES:

NOMINAL DIAMETER	OD	ID	t	r	I	E
8"	8.625	6.549	1.039	3.793	0.093	20,000 psi

IN TRENCH CONDITION, THE NOMINAL PRESSURE AT TOP OF PIPE IS 30759 psf (= 213.6 psi)

FORCE PER UNIT LENGTH OF PIPE

$$W = 30759 \cdot \frac{8.625}{12} = 22108 \text{ lb/ft}$$

$$= 1842.3 \text{ lb/in}$$

$$\Delta y = \frac{0.1 \times 1842.3 \times 3.793^3}{20000 \times 0.093 + 0.061 \times 1000 \times 3.793^3} \cdot 1.5 = 2.91''$$

$$\frac{\Delta y}{D} = \frac{2.91}{8.625} = 34\%$$

THE FOLLOWING IS BASED ON THE PROCEDURES SUGGESTED BY THE HDPE PIPE MANUFACTURER (pages 18-22)

TOTAL EXTERNAL PRESSURE AT TOP OF PIPE:

$$P_t = 213.6 \text{ psi (see page 16)}$$

EXAMINE SHORT-TERM WALL CRUSHING:

$$S_A = \frac{(SOR-1)P_t}{2} = \frac{(8.3-1) \times 213.6}{2} = 780 \text{ psi} < 1500 \text{ psi}$$

CALCULATE THE CRITICAL COLLAPSE PRESSURE:

$$P_c = \frac{2.32 \cdot 20000}{8.3^3} = 81$$

EXAMINE WALL-BUCKLING OF THE PIPE SOIL SYSTEM

$$\text{ASSUME } P_{CB} = P_t$$

THE REQUIRED SOIL MODULUS  $E'$  TO RESIST BUCKLING IS:

$$E' = \frac{213.6^2}{0.64 \cdot 81} = 880 \text{ psi}$$

SINCE THE PIPE IS SURROUNDED BY GRAVEL, TO BE CONSERVATIVE, A SOIL MODULUS OF 1000 psi IS USED:

$$\text{PIPE DEFLECTION} = \% \text{ SOIL STRAIN} = \frac{213.6}{1000} \cdot 100 = 21\% > 2\%$$

THE DEFLECTION EXCEEDS THE MANUFACTURER'S RECOMMENDED ALLOWABLE DEFLECTION. SINCE THE HDPE PIPE SYSTEM IS A REDUNDANT SYSTEM, IT CAN BE REPLACED BY THE STEEL PIPE ALONGSIDE THE HDPE PIPE.

18/26

# DRISCOPIPE® 8600

## ULTRA-HIGH MOLECULAR WEIGHT HIGH DENSITY POLYETHYLENE

### Dimensions and Pressure Ratings

#### ORDERING INFORMATION

- PRICE** Prices subject to change without notice.
- FREIGHT**
  1. All prices F.O.B. shipping point.
  2. Less than truckload shipments will be shipped freight collect, or freight pre-paid and charged, from point of origin.
- TERMS AND CONDITIONS** Net 30 days. All orders are subject to Phillips Driscopipe, Inc.'s acceptance and to the terms and conditions contained in its then current Sales Order Acknowledgement form.
- SPECIAL QUOTATIONS** Pricing for special sizes, dimensions, lengths, special packaging, special handling, and special "shop" alterations available upon request.
- HOW TO ORDER** When ordering, please provide the following information:
  1. Name and address of your organization
  2. Your Purchase Order number
  3. Nominal size
  4. Footage or number required
  5. Preferred method of shipment
  6. Shipping destination
  7. Desired delivery date

NOTE: Standard Length is 40 feet for all sizes.

FOR ADDITIONAL INFORMATION ON PRICES, SIZES OR FUSION EQUIPMENT CONTACT:



**PHILLIPS DRISCOPIPE, INC.**  
A SUBSIDIARY OF PHILLIPS PETROLEUM COMPANY

To Request Additional Product Literature Only:  
Phone: (214) 783-2690

To Place an Order, Verify the Status of an Order, or Request Contact by a Sales Representative:

Mail: Attn: Customer Service Department  
P.O. Box 83-3866  
2929 North Central Expressway  
Suite 100  
Richardson, TX, USA 75083

Phone: U.S. Domestic Toll Free 800 527-0662;  
Texas Toll Free 800 442-3802;

TWX: 910-867-4818 • Telecopier: 214 783-2617

PLANT LOCATIONS: Watsonville, CA • Pryor, OK  
• Williamstown, KY •  
Brownwood, TX • Startex, SC

YOUR LOCAL DISTRIBUTOR

**PIPE LINE SALES**  
23761 Via Calzada  
Mission Viejo, CA 92691  
714 770-1875

**LOW PRESSURE**

NOMINAL SIZE	DIMENSIONS-INCHES			SDR	NOMINAL WEIGHT LBS/100'	JOINT LENGTH FT.	DESIGN PRESSURE PSI-73.4°F
	NOMINAL OD	APPROX. ID	MINIMUM WALL				
3"	3.500	3.300	0.100	35	46	40	47
4"	4.500	4.200	0.150	30	88	40	55
4"	4.500	4.026	0.237	19.0	135	40	89
5"	5.250	4.926	0.162	32.5	111	40	51
5"	5.563	5.047	0.258	21.5	183	40	78
6"	6.625	6.217	0.204	32.5	176	40	51
7"	7.125	6.687	0.219	32.5	203	40	51
7"	7.125	6.333	0.396	18	357	40	94
8"	8.625	8.095	0.265	32.5	297	40	51
10"	10.750	10.088	0.331	32.5	463	40	51
10"	10.750	10.022	0.364	29.5	507	40	56
12"	12.750	11.940	0.405	31.5	671	40	52
14"	14.000	13.138	0.431	32.5	784	40	51
18"	16.000	15.018	0.492	32.5	1023	40	51
18"	16.000	15.000	0.500	32.0	1039	40	52
18"	18.000	16.892	0.554	32.5	1296	40	51
20"	20.000	18.806	0.597	33.5	1554	40	49
20"	20.000	18.770	0.615	32.5	1599	40	51
22"	21.500	20.176	0.662	32.5	1850	40	51
24"	24.000	22.524	0.738	32.5	2303	40	51
28"	27.953(1)	26.233	0.860	32.5	3125	40	51
32"	31.496(2)	29.558	0.969	32.5	3987	40	51
36"	36.000	33.784	1.108	32.5	5185	40	51
42"	42.000	39.416	1.292	32.5	7054	40	51
48"	47.244(3)	44.336	1.454	32.5	8930	40	51

(1) 710 MM (2) 800 MM (3) 1200 MM

**65 psi**

NOMINAL SIZE	DIMENSIONS			SDR	NOMINAL WEIGHT LBS/100'	JOINT LENGTH FT.
	NOMINAL OD	APPROX. ID	MINIMUM WALL			
6"	6.625	6.065	0.280	23.5 (71 psi)	238	40
8"	8.625	7.981	0.322	27 (62 psi)	359	40
10"	10.750	9.900	0.425	25.3	588	40
20"	20.000	18.418	0.791	25.3	2037	40
24"	24.000	22.102	0.949	25.3	2933	40
28"	27.953(1)	25.743	1.105	25.3	3978	40
36"	36.000	32.572	1.714	21	7877	40
48"	47.244(3)	43.610	1.817	26	11068	40

(1) 710 mm (3) 1200 mm

**110 psi**

NOMINAL SIZE	DIMENSIONS-INCHES			SDR	NOMINAL WEIGHT LBS/100'	COIL OR JOINT LENGTH FT.
	NOMINAL OD	APPROX. ID	MINIMUM WALL			
1 1/2"	1.900	1.610	0.145	13.1	34	500
2"	2.375	2.069	0.153	15.5	46	300
3"	3.500	3.068	0.216	16 (107 psi)	95	40
3"	3.500	3.048	0.226	15.5	99	40
4"	4.500	3.920	0.290	15.5	164	40
6"	6.625	5.771	0.427	15.5	355	40
8"	8.625	7.513	0.556	15.5	601	40
10"	10.750	9.362	0.694	15.5	935	40
12"	12.750	11.104	0.823	15.5	1315	40
14"	14.000	12.194	0.903	15.5	1584	40
16"	16.000	13.936	1.032	15.5	2069	40
18"	18.000	15.678	1.161	15.5	2619	40
22"	21.500	18.726	1.387	15.5	3737	40
24"	24.000	20.904	1.548	15.5	4656	40

**130 psi**

NOMINAL SIZE	DIMENSIONS-INCHES			SDR	NOMINAL WEIGHT LBS/100'	JOINT LENGTH FT.	DESIGN PRESSURE PSI-73.4°F
	NOMINAL OD	APPROX. ID	MINIMUM WALL				
3"	3.500	2.982	0.259	13.5	112	40	130
4"	4.500	3.834	0.333	13.5	186	40	130
6"	6.625	5.643	0.491	13.5	403	40	130
8"	8.625	7.347	0.639	13.5	683	40	130

NOTE: Approximate ID = Nominal OD - 2 x Minimum Wall  
 SDR (Standard Dimension Ratio) = OD + Minimum Wall  
 \*These sizes are also Schedule 40 dimensions.  
 Pressure rating computed on the basis of the following:

$$P = \frac{2S}{SDR-1} @ 73.4°F$$

Where:  
 Dp = Nominal OD of Pipe, inches  
 t = Minimum Wall Thickness  
 S = Hydrostatic Design Stress, 800 psi  
 P = Pressure Rating, psi @173.4°F

NOTE:  
 Approximate ID = Dp - 2t  
 SDR (Standard Dimension Ratio) =  $\frac{Dp}{t}$

**160 psi**

NOMINAL SIZE	DIMENSIONS-INCHES			SDR	NOMINAL WEIGHT LBS/100'	COIL OR JOINT LENGTH FT.
	NOMINAL OD	APPROX. ID	MINIMUM WALL			
3/4"	1.050	0.860	0.095	11	12	500
1"	1.315	1.075	0.120	11	19	500
1 1/4"	1.660	1.348	0.151	11	31	500
1 1/2"	1.900	1.554	0.173	11	40	500
2"	2.375	1.943	0.216	11	62	350
3"	3.500	2.864	0.318	11	135	40
4"	4.500	3.682	0.409	11	224	40
5"	5.563	4.551	0.506	11	342	40
6"	6.625	5.421	0.602	11	485	40
8"	8.625	7.057	0.784	11	823	40
10"	10.750	8.796	0.977	11	1278	40
12"	12.750	10.432	1.159	11	1798	40
14"	14.000	11.454	1.273	11	2168	40
16"	16.000	13.090	1.455	11	2833	40
18"	18.000	14.728	1.638	11	3583	40
22"	21.500	17.590	1.955	11	5114	40
24"	24.000	19.636	2.182	11	6372	40

**190 psi**

NOMINAL SIZE	DIMENSIONS-INCHES			SDR	NOMINAL WEIGHT LBS/100'	COIL OR JOINT LENGTH FT.
	NOMINAL OD	APPROX. ID	MINIMUM WALL			
3/4"	1.050	0.824	0.113	9.33	14	300
1"	1.315	1.033	0.141	9.33	22	300
1 1/4"	1.660	1.304	0.178	9.33	35	500
2"	2.375	1.865	0.255	9.33	72	350
3"	3.500	2.750	0.375	9.33	157	40
4"	4.500	3.536	0.482	9.33	259	40
6"	6.625	5.205	0.710	9.33	562	40

**220 psi**

NOMINAL SIZE	DIMENSIONS-INCHES			SDR	NOMINAL WEIGHT LBS/100'	JOINT LENGTH FT.
	NOMINAL OD	APPROX. ID	MINIMUM WALL			
8"	8.625	6.547	1.039	8.3	1054	40
14"	14.000	10.164	1.918	7.3 (254 psi)	3096	40

**STANDARD PACKAGING FOR DRISCOPE® 8600 INDUSTRIAL PIPE**

PIPE DESCRIPTION	BUNDLE			TRUCK LOAD BUNDLED		40' FT. FLOAT TRUCKLOAD - LOOSE		
	NOMINAL SIZE	O.D.	JOINTS	LINEAR FEET	BUNDLES	LINEAR FEET	JOINTS	LINEAR FEET
2"	2.375	88	3,520	14	49,280			
3"	3.500	46	1,840	14	25,760			
4"	4.500	27	1,080	14	15,120			
5"	5.563	15	600	14	8,400			
6"	6.625	11	440	14	6,160			
7"	7.125	11	440	12	5,280			
8"	8.625	8	320	12	3,840			
10"	10.750					80	3,200	
12"	12.750					59	2,360	
14"	14.000					48	1,920	
16"	16.000					35	1,400	
18"	18.000					28	1,120	
20"	20.000					20	800	
22"	21.500					18	720	
24"	24.000					16	640	
28"	27.953					10	400	
32"	31.496					9	360	
36"	36.000					6	240	
42"	42.000					4	160	
48"	47.244					4	160	

NOTE: OBTAIN TRUCK LOAD WEIGHT BY MULTIPLYING LINEAR FEET TIMES PIPE WEIGHT PER FOOT.

Burial Design Guidelines: By combining the Burial Design Considerations with the Total External Soil Pressure, calculated by components, the designer can select the proper pipe SDR and specify the soil density to engineer into the pipeline the desired performance of the "pipe-soil" system. The following guidelines are presented for evaluation when designing a specific Driscopipe system. Because various parameters are available, in different situations, the guidelines may be approached in a mixed order or the equations may require mathematical re-arrangement. These guidelines, along with the following notes and sample problem, should be helpful:

1. Calculate by components the total external soil pressure  $P_t$  at the top of the pipe.
2. Examine Short Term Wall Crushing by calculating the compressive stress in the wall of the pipe at the springline:

$$S_A = \frac{(\text{SDR}-1) P_t}{2} \quad \begin{array}{l} \text{(a) If } S_A < 1500 \text{ psi proceed to \#3} \\ \text{(b) If } S_A > 1500 \text{ psi consider a heavier} \\ \text{pipe wall} \end{array}$$

3. Calculate the critical-collapse pressure,  $P_c$ , from this formula using the time dependent modulus of elasticity,  $E$ , rated at the stress level calculated above in #2. (see Chart 25).

$$P_c = \frac{2.32 E}{(\text{SDR})^3}$$

4. Examine Wall-Buckling of the pipe-soil system. By assuming the critical-buckling pressure,  $P_{cb}$ , equals the pressure at the top of the pipe,  $P_t$ , (see #1), and by using the critical pressure,  $P_c$ , calculated in #3, the basic soil modulus,  $E'$ , required to resist buckling can be calculated by:

$$E' = \frac{(P_{cb})^2}{.64 (P_c)}$$

5. To safeguard against wall buckling, multiply  $E'$  by a reasonable safety factor (S.F.) equal to or greater than 2.0.

$$E'_{\text{MIN}} = (E')(S.F.)$$

6. Calculate pipe deflection based upon the principle that its deflection will be the same as the backfill surrounding the pipe under the influence of the soil pressure at the top of the pipe:

$$\% \text{ Soil Strain} = \xi_s = \frac{P_t}{E'_{\text{MIN}}} \times 100$$


7. Examine allowable Ring Deflection for the specific SDR under consideration to insure the pipe deflection (#6) is less than the allowable deflection for that SDR. (See Chart 27).

- If the actual deflection exceeds the permissible value, increase  $E'$ , the soil strength modulus, and re-calculate #6. The other alternative is to consider another SDR at #1.

Design by Ring Deflection: Ring deflection is defined as the ratio of the vertical change in diameter to the original diameter. It is often expressed as a percentage. Ring deflection for buried Driscopipe is conservatively the same as (no more than) the vertical compression of the soil envelope around the pipe. Design by ring deflection matches the ability of Driscopipe to accommodate, without structural distress, the vertical compression of the soil enveloping the buried pipeline. *Design by ring deflection comprises a calculation of vertical soil strain to insure it will be less than the allowable ring deflection of the pipe.* See Chart 27. The tabulation shows that with lower values of SDR, the allowable deflection is less. For installations which require this thicker wall to resist the external soil pressure, actual ring deflection can easily be limited to the tabular values by proper compaction of the backfill around the pipe. The recommended allowable deflection for the various SDR's are:

CHART 27

SDR	ALLOWABLE RING DEFLECTION
32.5	8.1%
26.0	6.5%
21.0	5.2%
19.0	4.7%
17.0	4.2%
15.8	3.9%
13.5	3.4%
11.0	2.7%




$$\% \text{ RING DEFLECTION} = \left( 1 - \frac{D_{\text{MIN}}}{D_0} \right) \times 100\%$$

The allowable ring deflection of polyethylene pipe is a function of the allowable tangential strain in the outer surface of the pipe wall. A conservative limit of 1 - 1½% tangential strain in the outer surface of the pipe wall due to vertical deflection of the pipe "ring" by soil compression can be understood by comparing two pipes of the same diameter but different wall thickness.

Assume each of the pipes is equally deflected under loads required to achieve that result. The tangential surface strain developed in the thickwall pipe is much greater than the surface strain in the thinwall pipe. The tangential strain varies directly as the wall thickness (i.e.: distance from the neutral axis) and is proportional to the amount of ring deflection. For a given ring deflection, the thicker the wall, the higher the strain.

Alternately, assume that each of the pipes are subjected to loads such that the tangential surface strain in the pipe's wall surface is equal for both pipes. For equal surface strain, the degree of vertical deflection of the pipe ring is different for the two pipes. Under these circumstances, the degree of deflection would be less for the thickwall pipe and greater for the thinwall pipe.


CHART 25  
 TIME DEPENDENT MODULUS OF ELASTICITY FOR  
 POLYETHYLENE PIPE VS. STRESS INTENSITY (73.4°F)



NOTE: The short term modulus of elasticity of Driscopipe per ASTM D 638 is approximately 100,000 psi. Due to the cold flow (creep) characteristic of the pipe material, this modulus is dependent upon the stress intensity and the time duration of the applied stress.

22/26

CHART 26  
 PLOT OF VERTICAL STRESS-STRAIN DATA FOR TYPICAL  
 TRENCH BACKFILL (EXCEPT CLAY) FROM ACTUAL TESTS.\*



EXAMPLE  
 FIND:  $E'$  @ 2000 PSF AND 80% DENSITY  
 FORMULA:  $E' = Pt/\epsilon_s$   
 CALCULATIONS:  $E' = 2000 \text{ PSF} / 0.18 = 11111 \text{ PSF} = 771 \text{ psi}$

NOTE: The curves shown on this chart are sample curves for a granular soil. If other types of soil are used for backfill, such as clay or clay loam, curves should be developed from laboratory test data for the material used. Soil pressures greater than 4000 psf may be examined by extrapolating the slope of the curve or by generating curves by testing at those higher soil pressures. Probable error of curves is about half the distance between adjacent lines.

\*TESTS PERFORMED AT THE  
 UTAH STATE UNIVERSITY  
 EXPERIMENT STATION

underside of a pad foundation and the top of the soft clay exceeds half the width of the foundation, the resistance of the stiff layer in




FIG. 4.3. CLOSE-SPACED FOUNDATIONS

forming a natural raft should be allowed for by the following procedure—

Pressure on surface of buried soft stratum =  $q$

$$= \frac{W - P_s}{A} \quad (4.3)$$

where  $W$  = total load at base of foundation

$P_s$  = perimeter shearing resistance

$A$  = peripheral area of stiff clay  $\times$  shear strength of stiff clay  
 $A$  = base area of foundation.

The value of  $q$  should not exceed the safe bearing capacity of the soft clay. Also, as in all cases of foundations on clay soils, the settlement of the foundation due to consolidation within both the stiff and the soft strata should be considered. The peripheral area of stiff clay is obtained by multiplying the peripheral length of the foundation by the depth of stiff clay below foundation level. It is inadvisable to allow for any transfer of load from the foundation sides to the stiff clay because shrinkage of the soil or of the foundation concrete, or a combination of both, will open up a gap between the soil and the concrete. If the zone of soil affected by seasonal moisture content changes extends below foundation level, cracking of the soil in the dry season will destroy the perimeter shearing resistance. Therefore, the latter should be calculated only over the thickness of the clay layer below the zone of seasonal moisture changes.

FOUNDATIONS CONSTRUCTED ON A THIN CLAY STRATUM

When foundations are constructed on a thin surface stratum of clay overlying a relatively rigid stratum, there may be a tendency for the thin layer to be squeezed from beneath the foundation, particularly if the soft layer is of varying thickness. Fig. 4.4 shows a foundation of width  $B$  on a thin clay layer overlying a stratum of different characteristics and appreciably higher bearing capacity, for example a sand layer. The net ultimate bearing capacity of the thin clay layer is given by the formulae—  
 For a strip foundation of width  $B$ :




FIG. 4.4. FOUNDATION ON THIN CLAY LAYER

$$q_{nr} = \left( \frac{B}{2d} + \pi + 1 \right) c \quad \text{for } \frac{B}{d} \geq 2 \quad (4.4)$$

For a circular foundation of diameter  $B$ :

$$q_{nr} = \left( \frac{B}{3d} + \pi + 1 \right) c \quad \text{for } \frac{B}{d} \geq 6 \quad (4.5)$$

For smaller values of  $B/d$  than those given above,  $q_{nr}$  can be obtained from equations 2.11 and 2.12, i.e. the formulae for a thick clay layer.

It should also be noted that, with a thin clay layer, plastic deformation resulting from overstressing begins at a lower foundation pressure than with a thick clay layer. For both strip and circular foundations, the maximum shear stress induced in the clay stratum is approximately  $\frac{1}{2}q_n$ .

Spread Foundations Carrying Eccentric Loading

Examples of foundations subject to eccentric loading are column foundations to tall buildings where wind pressures cause appreciable bending moments at the base of the columns, foundations of stanchions carrying brackets supporting travelling crane girders, and the foundations of retaining walls.


The pressure distribution below eccentrically loaded foundations is assumed to be linear as shown in Fig. 4.5 (a), and the maximum pressure must not exceed the maximum pressure permissible for a centrally loaded foundation. For the pad foundation shown in Fig. 4.5 (a), where the resultant falls within the middle third of the base,

$$\text{Maximum pressure} = q_{max} = \frac{W}{BL} + \frac{My}{I} \quad (4.6)$$

2w/26



24/26




BORING : DT-C, B-1                      DESCRIPTION : silty CLAYSTONE, yellow brn (CH)  
 DEPTH (ft) : 8                              LIQUID LIMIT : 76  
 SPEC. GRAVITY : 2.79                      PLASTIC LIMIT : 45

	<u>MOISTURE CONTENT (%)</u>	<u>DRY DENSITY (pcf)</u>	<u>PERCENT SATURATION</u>	<u>VOID RATIO</u>
INITIAL	28.1	89.4	83	.949
FINAL	30.5	94.1	100	.852

Remark : July 1990

Project ESK-101A	Kettleman
Wahler Associates	CONSOLIDATION TEST                      Figure No.

25/26



BORING : DT-A, B-2  
 DEPTH (ft) : 5  
 SPEC. GRAVITY : 2.84

DESCRIPTION : silty CLAYSTONE, yellow brn (CH)  
 LIQUID LIMIT : 82  
 PLASTIC LIMIT : 54

	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	27.3	93.1	86	.906
FINAL	29.9	95.9	100	.851

Remark : July 1990

Project ESK-101A	Kettleman	
Wahler Associates	CONSOLIDATION TEST	Figure No.

mulation  
 Analysis &  
 Design  
 by  
 J.E. Bowles

Table 2-3. Typical range of values for the static stress-strain modulus  $E_s$  for selected soils. Field values depend on stress history, water content, density, etc.

Soil	$E_s$	
	ksi	kg/cm <sup>2</sup>
Clay		
Very soft	0.05-0.4	3-30
Soft	0.2-0.6	20-40
Medium	0.6-1.2	45-90
Hard	1-3	70-200
Sandy	4-6	300-425
Glacial fill	1.5-22	100-1,600
Loess	2-8	150-600
Sand		
Silty	1-3	50-200
Loose	1.5-3.5	100-250
Dense	7-12	500-1,000
Sand and gravel		
Dense	14-28	800-2,000
Loose	7-20	500-1,400
Shales	20-2,000	1,400-14,000
Silt	0.3-3	20-200

2880 - 28800 ksf

Table 2-4. Typical range of values for Poisson's ratio  $\mu$

Type of soil	$\mu$
Clay, saturated	0.4-0.5
Clay, unsaturated	0.1-0.3
Sandy clay	0.2-0.3
Silt	0.3-0.35
Sand (dense)	0.2-0.4
Coarse (void ratio = 0.4-0.7)	0.15
Fine-grained (void ratio = 0.4-0.7)	0.25
Rock	0.1-0.4 (depends somewhat on type of rock)
Loess	0.1-0.3
Ice	0.36
Concrete	0.15

26/26




Figure 2-8. Elastic properties of soil.

The stress-strain modulus is computed from mechanics of materials (refer to Fig. 2-8a; typical values in Table 2-3) as

$$E_s = \frac{\text{stress}}{\text{strain}} = \frac{\sigma}{\epsilon} \quad (d)$$

Poisson's ratio is defined as the ratio of lateral strain  $\epsilon_3$  to longitudinal strain  $\epsilon_1$  when the applied stress is uniaxial (refer to Fig. 2-8b; typical values in Table 2-4).

$$\mu = \frac{\epsilon_3}{\epsilon_1} \quad (e)$$

The modulus of subgrade reaction is defined as the ratio of stress to deformation (refer to Fig. 2-8c)

$$k_s = \frac{\sigma}{\delta} \quad (2-17)$$

The shearing modulus  $G$ , defined as the ratio of shear stress to shear strain, is related to  $E_s$  and  $\mu$  as follows:

$$G = \frac{\text{shear stress}}{\text{shear strain}} = \frac{s}{\epsilon_s} = \frac{E_s}{2(1 + \mu)} \quad (f)$$

**APPENDIX M**  
**COVER INFILTRATION ANALYSES**



**Kettleman Hills Facility – Landfill Unit B-18  
COVER INFILTRATION**

Project No.: 083-91887

Made By: RH

Date: 5-15-2008

Checked By: SS

Sheet: 1 of 2

Reviewed By: SS 

**Objective:**

To estimate the amount of infiltration into and through the proposed (and permitted) final cover system for Landfill B-18.

**Given:**

The proposed B-18 final cover system consists of the following components (from top to bottom):

- 2.5-foot-thick (minimum) vegetative cover soil;
- 12-oz/sy nonwoven geotextile (transmissivity  $\geq 0.03$  gallons/minute/foot);
- 40-mil textured high-density polyethylene (HDPE) geomembrane; and
- 1-foot-thick (minimum) foundation layer soil (permeability  $\leq 1 \times 10^{-5}$  cm/sec).

The proposed B-18 final cover slopes have an inclination of 3.5H:1V (horizontal:vertical), or 28.6%, between benches and an average overall inclination of approximately 4H:1V, or 25%, including the benches.

**Method:**

In May 1995, Golder performed water balance analyses for the cover system of the Combined Closure Area at the Kettleman Hills Facility (KHF). These analyses are also applicable to the proposed B-18 closure cover since: 1) the cover system of the Combined Closure Area is identical to that proposed for B-18, 2) the Combined Closure Area and B-18 are both located at the KHF, and 3) the water balance analyses are conducted on a per-acre basis. The results of Golder's May 1995 water balance analyses were previously presented and approved for closure of the Combined Closure Area. For this evaluation, Golder has followed the same approach using the Hydrologic Evaluation of Landfill Performance (HELP) Version 3.07 computer program (Schroeder et al., 1997) to perform the water balance modeling of the final cover system. The HELP program performs water balance calculations by taking into account factors such as infiltration, evapotranspiration, runoff, soil moisture storage, and lateral subsurface drainage.

**Assumptions:**

The primary assumptions used by Golder in performing the water balance modeling of the Combined Closure Area (1995) and Landfill B-18's final cover system were:

1. The HELP program's default climate data for Fresno, CA were used to model the climate conditions at the KHF. This is considered a conservative assumption since the mean annual rainfall in Fresno is approximately 50% greater than at the KHF (RUST E&I, 1995). For comparison Golder also evaluated the cover using the default climate data for Bakersfield, CA which has an mean annual rainfall of 5.72 inches, slightly less than KHF.
2. The permeability of the vegetative cover soil ranges from  $1.9 \times 10^{-4}$  cm/sec (Soil Texture 9).
3. The HDPE geomembrane has 0.50 holes per acre resulting from manufacturing flaws (where the hole diameter = 1 mm), has 1.0 hole per acre resulting from installation defects (where the hole area =  $1 \text{ cm}^2$ ), and has an "excellent" placement quality.



**Kettleman Hills Facility – Landfill Unit B-18  
COVER INFILTRATION**

Project No.: 083-91887

Made By: RH

Date: 5-15-2008

Checked By: SS

Sheet: 2 of 2

Reviewed By: SS *[Signature]*

**Calculations and Results:**

The output files from the HELP program runs are contained in Attachment #1. The results of the water balance calculations performed using the HELP program are summarized in the table below:

Cover Slope (%)	Vegetative Cover Soil Permeability (cm/sec)	Geotextile Permeability (cm/sec)	Avg. /Max. Head on Geomembrane (inches)	Average Infiltration Rate Through Cover (inches/year)
Fresno Climate Data				
25	$1.9 \times 10^{-4}$	0.25	0.012/3.84	0.00003
Bakersfield Climate Data				
25	$1.9 \times 10^{-4}$	0.25	0.00/0.03	0.00000

**Conclusions:**

Based on the above-tabulated results of the water balance analyses conducted using the HELP Model 3.07, the proposed cover system for B-18 is anticipated to have a maximum head of between 3 and 4 inches on the geomembrane during peak precipitation years (i.e. comparable to Fresno). This amount of head is considered acceptable and is not anticipated to compromise the stability of the final cover system. Furthermore, the average infiltration rate through the geomembrane is anticipated to be approximately 0.00003 inches/year. This infiltration rate is very low and therefore considered acceptable and consistent with prior approvals. As expected, the Bakersfield climate data results in lower head on the geomembrane and less infiltration; however, both provide acceptable results.

**References:**

RUST Environment & Infrastructure (RUST E&I), "Kettleman Hills Facility, Combined Closure Plan," June 1995.  
 Schroeder, P.R., Aziz, N.M., Lloyd, C.M., and Zappi, P.A., 1994, "The Hydrologic Evaluation of Landfill Performance (HELP) Model: User's Guide for Version 3," EPA/600/R-94/168a, September 1994, U.S. Environmental Protection Agency Office of Research and Development, Washington, DC.

```

*****
*****
**
**
**          HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE          **
**          HELP MODEL VERSION 3.07 (1 NOVEMBER 1997)              **
**          DEVELOPED BY ENVIRONMENTAL LABORATORY                  **
**          USAE WATERWAYS EXPERIMENT STATION                      **
**          FOR USEPA RISK REDUCTION ENGINEERING LABORATORY        **
**
**
*****
*****

```

```

PRECIPITATION DATA FILE:  C:\HELP3\P4B18.D4
TEMPERATURE DATA FILE:   C:\HELP3\T7B18.D7
SOLAR RADIATION DATA FILE: C:\HELP3\SR13B18.D13
EVAPOTRANSPIRATION DATA:  C:\HELP3\E11B18.D11
SOIL AND DESIGN DATA FILE: C:\HELP3\SDD10B18.D10
OUTPUT DATA FILE:         C:\HELP3\B18 CC.OUT

```

TIME: 23:22      DATE: 11/17/2008

```

*****
TITLE:  Landfill B-18 Closure Infiltration Evaluation
        (Fresno Climate Data)
*****

```

NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE  
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1  
-----

```

          TYPE 1 - VERTICAL PERCOLATION LAYER
          MATERIAL TEXTURE NUMBER 9
THICKNESS           = 30.00 INCHES
POROSITY             = 0.5010 VOL/VOL
FIELD CAPACITY      = 0.2840 VOL/VOL
WILTING POINT       = 0.1350 VOL/VOL
INITIAL SOIL WATER  = 0.1684 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.19E-03 CM/SEC
NOTE: SATURATED HYDRAULIC CONDUCTIVITY IS MULTIPLIED BY 2.36
      FOR ROOT CHANNELS IN TOP HALF OF EVAPORATIVE ZONE.

```

LAYER 2

-----

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 0

THICKNESS	=	0.15	INCHES
POROSITY	=	0.3510	VOL/VOL
FIELD CAPACITY	=	0.1740	VOL/VOL
WILTING POINT	=	0.1070	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.1474	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.25000	CM/SEC
SLOPE	=	25.00	PERCENT
DRAINAGE LENGTH	=	300.0	FEET

LAYER 3

-----

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 0

THICKNESS	=	0.04	INCHES
POROSITY	=	0.0000	VOL/VOL
FIELD CAPACITY	=	0.0000	VOL/VOL
WILTING POINT	=	0.0000	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.0000	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	1.00E-12	CM/SEC
FML PINHOLE DENSITY	=	0.50	HOLES/ACRE
FML INSTALLATION DEFECTS	=	1.00	HOLES/ACRE
FML PLACEMENT QUALITY	=	2	- EXCELLENT

LAYER 4

-----

TYPE 3 - BARRIER SOIL LINER

MATERIAL TEXTURE NUMBER 0

THICKNESS	=	24.00	INCHES
POROSITY	=	0.4190	VOL/VOL
FIELD CAPACITY	=	0.3070	VOL/VOL
WILTING POINT	=	0.1800	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4190	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	1.00E-05	CM/SEC



GENERAL DESIGN AND EVAPORATIVE ZONE DATA  
-----

NOTE: SCS RUNOFF CURVE NUMBER WAS COMPUTED FROM DEFAULT  
SOIL DATA BASE USING SOIL TEXTURE # 9 WITH A  
POOR STAND OF GRASS, A SURFACE SLOPE OF 25.0%  
AND A SLOPE LENGTH OF 300. FEET.

SCS RUNOFF CURVE NUMBER	=	88.10	
FRACTION OF AREA ALLOWING RUNOFF	=	100.0	PERCENT
AREA PROJECTED ON HORIZONTAL PLANE	=	1.000	ACRES
EVAPORATIVE ZONE DEPTH	=	30.1	INCHES
INITIAL WATER IN EVAPORATIVE ZONE	=	5.064	INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE	=	15.065	INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE	=	4.061	INCHES
INITIAL SNOW WATER	=	0.000	INCHES
INITIAL WATER IN LAYER MATERIALS	=	15.129	INCHES
TOTAL INITIAL WATER	=	15.129	INCHES
TOTAL SUBSURFACE INFLOW	=	0.00	INCHES/YEAR

EVAPOTRANSPIRATION AND WEATHER DATA  
-----

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM  
FRESNO CALIFORNIA

STATION LATITUDE	=	36.46	DEGREES
MAXIMUM LEAF AREA INDEX	=	1.50	
START OF GROWING SEASON (JULIAN DATE)	=	65	
END OF GROWING SEASON (JULIAN DATE)	=	320	
EVAPORATIVE ZONE DEPTH	=	30.1	INCHES
AVERAGE ANNUAL WIND SPEED	=	6.40	MPH
AVERAGE 1ST QUARTER RELATIVE HUMIDITY	=	70.00	%
AVERAGE 2ND QUARTER RELATIVE HUMIDITY	=	49.00	%
AVERAGE 3RD QUARTER RELATIVE HUMIDITY	=	46.00	%
AVERAGE 4TH QUARTER RELATIVE HUMIDITY	=	72.00	%

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING  
COEFFICIENTS FOR FRESNO CALIFORNIA

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
-----	-----	-----	-----	-----	-----
2.05	1.85	1.61	1.15	0.31	0.08
0.01	0.02	0.16	0.43	1.24	1.61

Mean Annual Precipitation (Inches)= 10.52

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING  
 COEFFICIENTS FOR FRESNO CALIFORNIA

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
45.50	50.50	54.30	60.10	67.70	75.00
81.00	78.90	74.10	64.80	53.20	45.30

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING  
 COEFFICIENTS FOR FRESNO CALIFORNIA  
 AND STATION LATITUDE = 36.46 DEGREES

\*\*\*\*\*

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 100

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
PRECIPITATION						
TOTALS	2.23	1.93	1.68	1.12	0.34	0.08
	0.02	0.02	0.21	0.45	1.12	1.57
STD. DEVIATIONS	1.31	1.28	1.03	0.90	0.38	0.13
	0.04	0.06	0.32	0.54	0.96	0.86
RUNOFF						
TOTALS	0.062	0.056	0.035	0.015	0.000	0.000
	0.000	0.000	0.001	0.007	0.019	0.013
STD. DEVIATIONS	0.128	0.110	0.093	0.040	0.001	0.000
	0.000	0.000	0.004	0.021	0.069	0.033
EVAPOTRANSPIRATION						
TOTALS	1.143	1.626	2.091	1.581	1.582	0.145
	0.015	0.016	0.144	0.280	0.542	0.787
STD. DEVIATIONS	0.165	0.268	0.658	0.775	0.888	0.214
	0.036	0.059	0.257	0.377	0.369	0.252

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
--	---------	---------	---------	---------	---------	---------

LATERAL DRAINAGE COLLECTED FROM LAYER 2

TOTALS	0.0749 0.0000	0.2288 0.0000	0.1979 0.0000	0.0664 0.0000	0.0208 0.0000	0.0006 0.0039
STD. DEVIATIONS	0.3161 0.0000	0.5221 0.0000	0.4164 0.0001	0.1268 0.0001	0.0293 0.0000	0.0046 0.0271

PERCOLATION/LEAKAGE THROUGH LAYER 4

TOTALS	0.0000 0.0000	0.0000 0.0000	0.0000 0.0000	0.0000 0.0000	0.0000 0.0000	0.0000 0.0000
STD. DEVIATIONS	0.0000 0.0000	0.0001 0.0000	0.0000 0.0000	0.0000 0.0000	0.0000 0.0000	0.0000 0.0000

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 3

AVERAGES	0.0272 0.0000	0.0787 0.0000	0.0332 0.0000	0.0020 0.0000	0.0006 0.0000	0.0000 0.0001
STD. DEVIATIONS	0.1435 0.0000	0.3015 0.0000	0.1517 0.0000	0.0038 0.0000	0.0008 0.0000	0.0001 0.0009

\*\*\*\*\*  
\*\*\*\*\*

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 100

	INCHES	CU. FEET	PERCENT
PRECIPITATION	10.76 ( 2.688)	39053.7	100.00
RUNOFF	0.208 ( 0.2277)	755.31	1.934
EVAPOTRANSPIRATION	9.951 ( 1.9427)	36121.62	92.492
LATERAL DRAINAGE FROM LAYER 2	0.59327 ( 1.06331)	2153.569	5.51438
PERCOLATION THROUGH LAYER 4	0.00003 ( 0.00008)	0.095	0.00024
AVERAGE HEAD ON TOP OF LAYER 3	0.012 ( 0.036)		
CHANGE IN WATER STORAGE	0.006 ( 1.5550)	23.11	0.059

.001 mm INFILTRATION THROUGH COVER.

AVERAGE HEAD

\*\*\*\*\*  
 \*\*\*\*\*

PEAK DAILY VALUES FOR YEARS 1 THROUGH 100

	(INCHES)	(CU. FT.)
PRECIPITATION	2.24	8131.200
RUNOFF	0.562	2039.3490
DRAINAGE COLLECTED FROM LAYER 2	0.14244	517.04419
PERCOLATION/LEAKAGE THROUGH LAYER 4	0.000024	0.08696
AVERAGE HEAD ON TOP OF LAYER 3	3.838	MAX DAILY
MAXIMUM HEAD ON TOP OF LAYER 3	7.430	MAXIMUM
LOCATION OF MAXIMUM HEAD IN LAYER 2 (DISTANCE FROM DRAIN)	0.0 FEET	
SNOW WATER	2.06	7478.9429
MAXIMUM VEG. SOIL WATER (VOL/VOL)		0.3638
MINIMUM VEG. SOIL WATER (VOL/VOL)		0.1349

\*\*\* Maximum heads are computed using McEnroe's equations. \*\*\*

Reference: Maximum Saturated Depth over Landfill Liner  
 by Bruce M. McEnroe, University of Kansas  
 ASCE Journal of Environmental Engineering  
 Vol. 119, No. 2, March 1993, pp. 262-270.

\*\*\*\*\*  
 \*\*\*\*\*

FINAL WATER STORAGE AT END OF YEAR 100

LAYER	(INCHES)	(VOL/VOL)
1	5.6873	0.1896
2	0.0222	0.1477
3	0.0000	0.0000
4	10.0560	0.4190
SNOW WATER	0.000	

\*\*\*\*\*  
 \*\*\*\*\*



LAYER 2

-----

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 0

THICKNESS	=	0.15	INCHES
POROSITY	=	0.3510	VOL/VOL
FIELD CAPACITY	=	0.1740	VOL/VOL
WILTING POINT	=	0.1070	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.1478	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.250000000000	CM/SEC
SLOPE	=	25.00	PERCENT
DRAINAGE LENGTH	=	300.0	FEET

LAYER 3

-----

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 0

THICKNESS	=	0.04	INCHES
POROSITY	=	0.0000	VOL/VOL
FIELD CAPACITY	=	0.0000	VOL/VOL
WILTING POINT	=	0.0000	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.0000	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.999999982000E-13	CM/SEC
FML PINHOLE DENSITY	=	0.50	HOLES/ACRE
FML INSTALLATION DEFECTS	=	1.00	HOLES/ACRE
FML PLACEMENT QUALITY	=	2	EXCELLENT

LAYER 4

-----

TYPE 3 - BARRIER SOIL LINER

MATERIAL TEXTURE NUMBER 0

THICKNESS	=	24.00	INCHES
POROSITY	=	0.4190	VOL/VOL
FIELD CAPACITY	=	0.3070	VOL/VOL
WILTING POINT	=	0.1800	VOL/VOL
INITIAL SOIL WATER CONTENT	=	0.4190	VOL/VOL
EFFECTIVE SAT. HYD. COND.	=	0.999999975000E-05	CM/SEC

GENERAL DESIGN AND EVAPORATIVE ZONE DATA  
-----

NOTE: SCS RUNOFF CURVE NUMBER WAS USER-SPECIFIED.

SCS RUNOFF CURVE NUMBER	=	88.10	
FRACTION OF AREA ALLOWING RUNOFF	=	100.0	PERCENT
AREA PROJECTED ON HORIZONTAL PLANE	=	1.000	ACRES
EVAPORATIVE ZONE DEPTH	=	30.1	INCHES
INITIAL WATER IN EVAPORATIVE ZONE	=	4.381	INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE	=	15.065	INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE	=	4.061	INCHES
INITIAL SNOW WATER	=	0.000	INCHES
INITIAL WATER IN LAYER MATERIALS	=	14.446	INCHES
TOTAL INITIAL WATER	=	14.446	INCHES
TOTAL SUBSURFACE INFLOW	=	0.00	INCHES/YEAR

EVAPOTRANSPIRATION AND WEATHER DATA  
-----

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM  
BAKERSFIELD CALIFORNIA

STATION LATITUDE	=	35.42	DEGREES
MAXIMUM LEAF AREA INDEX	=	1.50	
START OF GROWING SEASON (JULIAN DATE)	=	44	
END OF GROWING SEASON (JULIAN DATE)	=	331	
EVAPORATIVE ZONE DEPTH	=	30.1	INCHES
AVERAGE ANNUAL WIND SPEED	=	6.40	MPH
AVERAGE 1ST QUARTER RELATIVE HUMIDITY	=	67.00	%
AVERAGE 2ND QUARTER RELATIVE HUMIDITY	=	42.00	%
AVERAGE 3RD QUARTER RELATIVE HUMIDITY	=	38.00	%
AVERAGE 4TH QUARTER RELATIVE HUMIDITY	=	63.00	%

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING  
COEFFICIENTS FOR BAKERSFIELD CALIFORNIA

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
-----	-----	-----	-----	-----	-----
0.98	1.07	0.87	0.70	0.24	0.07
0.01	0.05	0.13	0.30	0.65	0.65

Mean Annual Precipitation (Inches)= 5.72

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING  
 COEFFICIENTS FOR BAKERSFIELD CALIFORNIA

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
48.20	53.20	57.10	62.70	70.80	78.30
84.50	82.40	77.30	68.00	56.20	48.20

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING  
 COEFFICIENTS FOR BAKERSFIELD CALIFORNIA  
 AND STATION LATITUDE = 35.42 DEGREES

\*\*\*\*\*

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 100

	JAN/JUL	FEB/AUG	MAR/SEP	APR/OCT	MAY/NOV	JUN/DEC
PRECIPITATION						
TOTALS	1.10	1.13	0.93	0.72	0.24	0.08
	0.01	0.05	0.14	0.27	0.70	0.65
STD. DEVIATIONS	0.65	0.82	0.61	0.56	0.28	0.23
	0.04	0.20	0.22	0.45	0.64	0.43
RUNOFF						
TOTALS	0.002	0.005	0.005	0.001	0.000	0.001
	0.000	0.002	0.000	0.001	0.004	0.000
STD. DEVIATIONS	0.009	0.017	0.018	0.007	0.002	0.007
	0.000	0.019	0.000	0.009	0.021	0.001
EVAPOTRANSPIRATION						
TOTALS	0.654	0.961	1.377	1.236	0.472	0.082
	0.022	0.045	0.116	0.160	0.382	0.451
STD. DEVIATIONS	0.249	0.303	0.556	0.805	0.476	0.208
	0.088	0.185	0.190	0.244	0.303	0.243



JAN/JUL    FEB/AUG    MAR/SEP    APR/OCT    MAY/NOV    JUN/DEC  
 -----  
 LATERAL DRAINAGE COLLECTED FROM LAYER 2

TOTALS	0.0000	0.0007	0.0072	0.0048	0.0009	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
STD. DEVIATIONS	0.0000	0.0072	0.0509	0.0323	0.0056	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000

PERCOLATION/LEAKAGE THROUGH LAYER 4

TOTALS	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
STD. DEVIATIONS	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000

-----  
 AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)  
 -----

DAILY AVERAGE HEAD ON TOP OF LAYER 3

AVERAGES	0.0000	0.0000	0.0002	0.0001	0.0000	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
STD. DEVIATIONS	0.0000	0.0002	0.0015	0.0010	0.0002	0.0000
	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000

\*\*\*\*\*  
 \*\*\*\*\*

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 100

	INCHES		CU. FEET	PERCENT
	-----	-----	-----	-----
PRECIPITATION	6.00	( 1.635)	21768.7	100.00
RUNOFF	0.021	( 0.0412)	77.75	0.357
EVAPOTRANSPIRATION	5.958	( 1.5587)	21628.86	99.357
LATERAL DRAINAGE FROM LAYER 2	0.01381	( 0.09400)	50.141	0.23034
PERCOLATION THROUGH LAYER 4	0.00000	( 0.00000)	0.001	0.00000
AVERAGE HEAD ON TOP OF LAYER 3	0.000	( 0.000)		
CHANGE IN WATER STORAGE	0.003	( 0.6911)	12.00	0.055

0.00 INFILTRATION THROUGH COVER

AVERAGE HEAD

\*\*\*\*\*  
 \*\*\*\*\*

PEAK DAILY VALUES FOR YEARS 1 THROUGH 100

	(INCHES)	(CU. FT.)
PRECIPITATION	1.62	5880.600
RUNOFF	0.195	707.0040
DRAINAGE COLLECTED FROM LAYER 2	0.03062	111.16240
PERCOLATION/LEAKAGE THROUGH LAYER 4	0.000000	0.00062
AVERAGE HEAD ON TOP OF LAYER 3	0.028	MAX DAILY
MAXIMUM HEAD ON TOP OF LAYER 3	0.052	MAXIMUM
LOCATION OF MAXIMUM HEAD IN LAYER 2 (DISTANCE FROM DRAIN)	0.0 FEET	
SNOW WATER	0.21	763.4433
MAXIMUM VEG. SOIL WATER (VOL/VOL)		0.2910
MINIMUM VEG. SOIL WATER (VOL/VOL)		0.1349

\*\*\* Maximum heads are computed using McEnroe's equations. \*\*\*

Reference: Maximum Saturated Depth over Landfill Liner  
 by Bruce M. McEnroe, University of Kansas  
 ASCE Journal of Environmental Engineering  
 Vol. 119, No. 2, March 1993, pp. 262-270.

\*\*\*\*\*  
 \*\*\*\*\*

FINAL WATER STORAGE AT END OF YEAR 100

LAYER	(INCHES)	(VOL/VOL)
1	4.6981	0.1566
2	0.0221	0.1474
3	0.0000	0.0000
4	10.0560	0.4190
SNOW WATER	0.000	

\*\*\*\*\*  
 \*\*\*\*\*

**APPENDIX N**  
**FROST AND BIOTIC PROTECTION EVALUATION**

**APPENDIX N.1      FROST PENETRATION EVALUATION**  
**APPENDIX N.2      BIOTIC PROTECTION EVALUATION**

**APPENDIX N.1**  
**FROST PENETRATION EVALUATION**



**Kettleman Hills Facility – Landfill Unit B-18  
FROST PENETRATION**

Project No.: 083-91887

Made By: RH

Date: 5-19-2008

Checked By: SS

Sheet: 1 of 1

Reviewed By: SS

**Objective:**

To evaluate the potential frost penetration effects on the proposed (and permitted) cover system for Landfill B-18.

**Given:**

The proposed B-18 final cover system consists of the following components (from top to bottom):

- 2.5-foot-thick (minimum) vegetative cover soil;
- 12-oz/sy nonwoven geotextile (transmissivity  $\geq 0.03$  gallons/minute/foot);
- 40-mil textured high-density polyethylene (HDPE) geomembrane; and
- 1-foot-thick (minimum) foundation layer soil (permeability  $\leq 1 \times 10^{-5}$  cm/sec).

**Findings:**

Based on a regional published map (USEPA, 1989) of frost penetration depths for the United States shown in Attachment #1, the average depth of frost penetration at the Kettleman Hills Facility (KHF) is anticipated to be approximately 2 inches. Another regional published map (NAVFAC, 1986) of frost penetration depths for the United States shows the extreme frost penetration depth at the KHF to be between 0 and 5 inches (see Attachment #2).

**Conclusions:**

Since the proposed B-18 final cover does not contain a clay liner component, degradation of the final cover due to frost penetration is not a concern. Furthermore, available data on frost penetration depths (USEPA, 1989; NAVFAC, 1986) indicate that no more than approximately 0.5 feet of frost penetration is anticipated at the KHF. Hence, any frost penetration will be confined to the uppermost portion of the vegetative cover soil layer. This degree of frost penetration is not anticipated to affect the performance of the B-18 final cover system.

**References:**

United States Environmental Protection Agency (USEPA), "Technical Guidance Document: Final Covers on Hazardous Waste Landfills and Surface Impoundments," EPA/530-SW-89-047, July 1989.

Naval Facilities Engineering Command (NAVFAC), "Design Manual 7.01 – Soil Mechanics," September 1, 1986.

**ATTACHMENT #1**  
**FROST PENETRATION EVALUATION**

United States  
Environmental Protection  
Agency


Office of Solid Waste and  
Emergency Response  
Washington DC 20460

EPA/530-SW-89-047  
July 1989



# Technical Guidance Document:

## Final Covers on Hazardous Waste Landfills and Surface Impoundments



EPA/530-SW-89-047  
July 1989

TECHNICAL GUIDANCE DOCUMENT

FINAL COVERS ON HAZARDOUS WASTE LANDFILLS  
AND SURFACE IMPOUNDMENTS

Office of Solid Waste and Emergency Response  
U.S. Environmental Protection Agency  
Washington, DC 20460

In cooperation with

RISK REDUCTION ENGINEERING LABORATORY  
OFFICE OF RESEARCH AND DEVELOPMENT  
U.S. ENVIRONMENTAL PROTECTION AGENCY  
CINCINNATI, OHIO 45268






Figure 6. Regional average depth of frost penetration in inches (Stewart, et al., 1975).

Stewart, B. A., et al. 1975. Control of Water Pollution from Cropland: Volume 1 - A Manual for Guideline Development. USDA Report No. ARS-H-5-1. U. S. Dept. of Agriculture, Hyattsville, MD.

Thornburg, A. A. 1979. Plant Materials for Use on Surface Mined Lands. TP-157 and EPA-600/7-79-134. Soil Conservation Service, U.S. Department of Agriculture, Washington, D.C.

Wright, M. J. (Ed.). 1976. Plant Adaptation to Mineral Stress in Problem Soils. Cornell University Agricultural Experiment Station. Ithaca, NY.

\*U.S. GOVERNMENT PRINTING OFFICE: 1989-648-163/00303

**ATTACHMENT #2**  
**FROST PENETRATION EVALUATION**


Naval Facilities Engineering Command  
200 Stovall Street  
Alexandria, Virginia 22322-2300

APPROVED FOR PUBLIC RELEASE

))

Soil Mechanics  
DESIGN MANUAL 7.01

REVALIDATED BY CHANGE 1 SEPTEMBER 1986



Kettleman Hills Facility

FIGURE 7  
Extreme Frost Penetration (in inches) Based Upon State Average

**APPENDIX N.2**  
**BIOTIC PROTECTION EVALUATION**



**Kettleman Hills Facility – Landfill Unit B-18  
BIOTIC PROTECTION**

Project No.: 083-91887

Made By: RH

Date: 5-19-2008

Checked By: SS

Sheet: 1 of 1

Reviewed By: SS

**Objective:**

To evaluate the effects of burrowing rodents on the proposed (and permitted) cover system for Landfill B-18.

**Given:**

The proposed B-18 final cover system consists of the following components (from top to bottom):

- 2.5-foot-thick (minimum) vegetative cover soil;
- 12-oz/sy nonwoven geotextile (transmissivity  $\geq 0.03$  gallons/minute/foot);
- 40-mil textured high-density polyethylene (HDPE) geomembrane; and
- 1-foot-thick (minimum) foundation layer soil (permeability  $\leq 1 \times 10^{-5}$  cm/sec).

**Conclusions:**

Based on the recommendations provided by Biosystems Analysis, Inc. in their August 4, 1989 letter to the Kettleman Hills Facility (KHF), the 40-mil HDPE geomembrane component of the B-18 final cover is expected to constrain any rodent burrowing to the overlying vegetative cover soil layer. A copy of the Biosystems Analysis, Inc. August 4, 1989 letter is presented in Attachment #1. Past experience at the KHF indicates that HDPE geomembrane is an effective barrier to rodent burrowing. Hence, the 40-mil HDPE geomembrane component of the B-18 final cover is anticipated to fully discourage and/or prevent animals from burrowing through the final cover system.

**ATTACHMENT #1**  
**BIOTIC PROTECTION EVALUATION**




Attachment #1  
p. 1/1

10F1

RECEIVED

AUG 09 1989

C. W. M



August 4, 1989

Christopher W. Hansen  
Chemical Waste Management, Inc.  
Kettleman Hills Facility  
P.O. Box 471  
Kettleman City, CA 93239

RE: Mitigation for Rodent Burrowing in Closure Cap<sup>s</sup>

Dear Chris:

We talked this morning about rodents burrowing into cover systems of closed waste management units at the Kettleman Hills Facility. I understand that some of your cover system cross sections contain compacted clay overlain by 1.5 feet or more of vegetative soil. You are concerned about rodents burrowing through the clay and impacting the integrity of the cover system.

As we discussed, the placement of a layer of HDPE geonet between the clay and the vegetative soil should completely discourage or prevent the animals from burrowing into the compacted clay. These animals will encounter the geonet, and will then constrain any burrowing to the overlying vegetative layer.

Please call if you have any questions.

Sincerely,  
BIOSYSTEMS ANALYSIS, INC.

  
Sue G. Orloff  
Wildlife Biologist

**APPENDIX O**  
**TECHNICAL SPECIFICATIONS**

**APPENDIX O.1**

**PHASE III SPECIFICATIONS**

**APPENDIX O.2**

**FINAL CLOSURE SPECIFICATIONS**

**APPENDIX O.1**  
**PHASE III SPECIFICATIONS**

**Golder Associates Inc.**

230 Commerce, Suite 200  
Irvine, California 92602  
Telephone (714) 508-4400  
Fax (714) 508-4401  
www.golder.com



**TECHNICAL SPECIFICATIONS  
LANDFILL UNIT B-18 PHASE III  
KETTLEMAN HILLS FACILITY  
KETTLEMAN CITY, CALIFORNIA**

***Prepared for:***

Chemical Waste Management, Inc.  
Kettleman Hills Facility  
35251 Old Skyline Road  
Kettleman City, California 93239

***Prepared by:***

Golder Associates Inc.  
230 Commerce, Suite 200  
Irvine, California 92602

November 2008  
Revision 1: February 2010  
Revision 2: August 2011

Project No.: 083-91887

## SECTION 01010

### SUMMARY OF WORK

#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. The section describes the general requirements for the construction of Phase III of Landfill Unit B-18 at the Kettleman Hills Facility located outside of Kettleman City, California. The Work will consist of excavation, engineered fill placement, subgrade preparation, installation of a double-composite geosynthetic sideslope liner system, placement of operations layer soil, extending sideslope riser pipes, and installing surface water drainage structures.

##### 1.02 CONTRACTOR'S RESPONSIBILITIES:

- A. Start, lay out, construct, and complete the Project in accordance with the Contract Documents;
- B. Provide a competent superintendent, capable of reading and understanding the Contract Documents, who shall receive instructions from the OWNER or his authorized representative. The superintendent shall have full authority to execute the Work in accordance with the Contract Documents;
- C. The CONTRACTOR shall be responsible for transporting, permitting, and/or conveying all required construction water.
- D. Pay costs of legally required sales, consumer, and use taxes, and governmental fees.
- E. Forward submittals and communications to the CONSTRUCTION MANAGER. Where applicable, the CONSTRUCTION MANAGER will coordinate submittals and communications with the representatives who will give approvals and directions through the CONSTRUCTION MANAGER.
- F. Maintain order, safe practices and proper conduct at all times among CONTRACTOR's employees. The OWNER, and its authorized representative, may require that disciplinary action be taken against an employee of the CONTRACTOR for disorderly, improper, and unsafe conduct. Should an employee of the CONTRACTOR be dismissed from his duties for misconduct, incompetence, or unsafe practice, or combination thereof, that employee should not be rehired for the duration of the Work.
- G. Coordinate prosecution of the Work with the utilities, private utilities, or OWNER performing work on or adjacent to the work site; either eliminate, or minimize as far as possible, delays in the Work and conflicts with those utilities or contractors. Coordinate utility activities, and activities of OWNER, with the CONSTRUCTION MANAGER. Schedule private utility and public utility work relying on survey points, lines, and grades established by the CONTRACTOR to occur immediately after those points, lines and grades have been established. Confirm coordinate

measures for each individual case with the CONSTRUCTION MANAGER by memorandum.

- J. Coordinate activities of the several trades, suppliers, and subcontractors, if any, performing the Work.
- K. Obtain all necessary building and construction permits. Permit fees will be paid by the OWNER.

### 1.03 RESERVED

### 1.04 CONFORMANCE

- A. Work shall conform to the following Drawings that form a part of these Contract Documents.

<u>SHEET NO.</u>	<u>TITLE</u>
T-1	TITLE SHEET
C-1	SITE PLAN
C-2	EXISTING CONDITIONS (AS OF MARCH 28, 2008)
C-3	BASE LINER PLAN
C-4	FINAL CLOSURE PLAN
C-5	CROSS-SECTIONS A TO D
C-6	CROSS-SECTIONS E TO I
C-7	PHASE III BASE LINER CONSTRUCTION DETAILS
C-8	PHASE III LCRS DETAILS
C-9	DRAINAGE DETAILS
C-10	CLOSURE DETAILS

### 1.05 DEFINITIONS

**OWNER** The term OWNER means Kettleman Hills Facility with whom the CONTRACTOR has entered into the Agreement and for whom the Work is to be provided.

**CONSTRUCTION MANAGER** The term CONSTRUCTION MANAGER means the representative of the OWNER for the purpose of administration and inspection of the Work. The CONSTRUCTION MANAGER may be a member or group of the staff or may be an external firm. The OWNER will inform the CONTRACTOR in writing at the start of the Work who the CONSTRUCTION MANAGER will be. During the period of Work the CONSTRUCTION MANAGER will act as an authorized representative of the OWNER.

**DESIGN ENGINEER** The term DESIGN ENGINEER means Golder Associates Inc., the firm responsible for the design and preparation of the construction drawings and specifications. The

DESIGN ENGINEER is responsible for approving all design changes, modifications, or clarifications encountered during construction.

**CQA CONSULTANT**

The term CQA CONSULTANT means the representative of the OWNER for the purpose of conducting CQA testing, monitoring, documenting, and reporting.

**CONTRACTOR**

The term CONTRACTOR means the firm that is responsible prosecuting the Work. The CONTRACTOR's responsibilities include the Work of any and all subcontractors and suppliers.

**Geosynthetics  
CONTRACTOR**

The term Geosynthetics CONTRACTOR means the firm that is responsible for the supply and installation of all geosynthetics including the Work of all of the subcontractors and suppliers. The Geosynthetics Installer may work directly for the OWNER or as a subcontractor to the CONTRACTOR. The Geosynthetics CONTRACTOR is also referred to as the CONTRACTOR.

**Work**

The term Work means the entire completed construction or various separately identifiable parts, thereof, required to be furnished under the Contract Documents. Work includes any and all labor, services, materials, equipment, tools, supplies, and facilities required by the Contract Documents and necessary for the completion of the project. Work is the result of performing services, furnishing labor and furnishing and incorporating materials and equipment into the construction, all as required by the Contract Documents.

**Working day**

A calendar day, exclusive of Saturdays, Sundays, and OWNER's recognized legal holidays, on which weather and other conditions not under the control of the CONTRACTOR will permit construction operations to proceed for the major part of the day with the normal working force engaged in performing the controlling item or items of work which would be in progress at that time. The working day is subject to the conditions and work restrictions outlined in these Specifications.

**Regular  
Working Hours**

Between 6:30 a.m. and 6:00 p.m. on allowable work days.

Calendar Days                      Each day of the year including all OWNER approved holidays.

#### **1.06 CONTRACT TIMES**

- A. The CONTRACTOR shall commence Work in accordance with Section 18 of the General Conditions and Section 7 of the Standard Contract.

#### **1.07 CONTRACTOR USE OF WORK SITE**

- A. Confine work site operations to areas permitted by law, ordinances, permits, and the Contract Documents. The CONTRACTOR shall ensure that all persons under his control (including Subcontractors, their workers and agents) are kept within the boundaries of the Site and shall be responsible for any acts of trespass or damage to property by persons who are under his control. Consider the safety of the Work, and that of people and property on and adjacent to work site, when determining amount, location, movement, and use of materials and equipment on work site.
- B. The CONTRACTOR shall be responsible for protecting private and public property including pavements, drainage culverts, electricity, highway, telephone and similar property and making good of, or paying for, all damage caused thereto. Control of erosion throughout the project is of prime importance and is the responsibility of the CONTRACTOR. The CONTRACTOR shall comply with the requirements of the Storm Water Pollution Prevention Plan (SWPPP) provided by the OWNER for the Kettleman Hills Facility and prepare and submit a SWPPP specific to the Work in accordance with requirements of local or state agencies (see Section 01300). The CONTRACTOR shall provide and maintain all necessary measures to control erosion during progress of the Work to the satisfaction of the CONSTRUCTION MANAGER and all applicable Laws and Regulations and remove such measures and debris upon completion of the project. All provisions for erosion and sedimentation control apply equally to all areas of the Work.
- C. CONTRACTOR shall promptly notify OWNER and CONSTRUCTION MANAGER in writing of any subsurface or latent physical conditions at the Site which differ materially from those indicated or referred to in the Contract Documents. CONSTRUCTION MANAGER will promptly review those conditions and advise OWNER in writing if further investigations or tests are necessary. Promptly thereafter, OWNER shall obtain the necessary additional investigations and tests and furnish copies to the CONSTRUCTION MANAGER and CONTRACTOR. If CONSTRUCTION MANAGER finds that the results of such investigations or tests indicate that there are subsurface and latent physical conditions which differ materially from those intended in the Contract Documents, and which could not reasonably have been anticipated by CONTRACTOR, a Change Order shall be issued incorporating the necessary revisions.

#### **1.08 PRESERVATION OF SCIENTIFIC INFORMATION**

- A. Federal and State legislation provides for the protection, preservation, and collection of data having scientific, prehistoric, historical, or archaeological value (including relics and specimens) which might otherwise be lost due to alteration of the terrain as a result of any construction work.



- B. If evidence of such information is discovered during the course of the Work, the CONTRACTOR shall notify the CONSTRUCTION MANAGER immediately, giving the location and nature of the findings. Written confirmation shall be forwarded within two (2) working days. The CONTRACTOR shall exercise care so as not to damage artifacts uncovered during excavation operations, and shall provide such cooperation and assistance as may be necessary to preserve the findings for removal or other disposition by the OWNER's representative or Government agency.
- C. Where appropriate, by reason of a discovery, the OWNER may order delays in the time of performance, or changes in the Work, or both. If such delays, or changes, or both, are ordered, the time of performance and contract price shall be adjusted in accordance with the applicable clauses of the Contract.

#### **1.09 EXISTING UTILITIES**

- A. The CONTRACTOR shall be responsible for locating, protecting, flagging, and identifying all existing utilities. The CONTRACTOR shall request that Underground Service Alert (USA) locate and identify the existing utilities. The request shall be made 48 hours in advance.
- B. Costs resulting from damage to utilities shall be borne by the CONTRACTOR. Costs of damage shall include repair and incidental costs resulting from the unscheduled loss of utility service to affected parties.
- C. The CONTRACTOR shall immediately stop work and notify the CONSTRUCTION MANAGER of all utilities encountered or damaged. The CONTRACTOR shall also provide the CONSTRUCTION MANAGER with the exact location of any utilities encountered during construction.
- D. If specified by the CONSTRUCTION MANAGER, utility pot holes shall be carefully dug by the CONTRACTOR to identify the presence of underground utilities.
- E. Damage to utilities by the CONTRACTOR during pothole operations shall be born by the CONTRACTOR.

#### **PART 2 PRODUCTS**

(Not Used)

#### **PART 3 EXECUTION**

(Not Used)

**END OF SECTION**

## SECTION 01032

### INTENT OF DRAWINGS AND SPECIFICATIONS

#### PART 1 GENERAL

##### 1.01 CONTRACT DRAWINGS AND SPECIFICATIONS

- A. The intent of the Drawings and Specifications is to prescribe a complete work which the CONTRACTOR shall perform in a manner acceptable to the OWNER and in full compliance with the terms of the Contract.
- B. The Drawings show general arrangements for the work which shall be used by the CONTRACTOR in the preparation of shop and field drawings. Particular care shall be given to all layouts to make sure all equipment is accessible for operation.
- C. The CONTRACTOR shall provide the OWNER with a complete and operable system, even though the Drawings and Specifications may not specifically call out all items of work required of the CONTRACTOR to complete his tasks, incidental appurtenances, materials, and the like and maintenance.
- D. The CONTRACTOR is to perform the Work in accordance with the cross-sections, thickness, gradients and dimensions shown on the Drawings. Any deviations must be approved by the DESIGN ENGINEER prior to doing the work.
- E. The dimensions on the Drawings are presumed to be correct, but the CONTRACTOR shall be required to check carefully all dimensions prior to beginning the Work. If errors or omissions are discovered by the CONTRACTOR, the CONTRACTOR shall immediately notify the CONSTRUCTION MANAGER in writing and await the CONSTRUCTION MANAGER's notification before proceeding.

##### 1.02 PRECEDENCE OF CONTRACT DOCUMENTS

- A. If there is a conflict between Contract Documents, the document highest in precedence shall control. The precedence, unless otherwise stipulated by the OWNER, shall be:
  - 1. Permits.
  - 2. Special Provisions.
  - 3. General Terms and Conditions.
  - 4. Construction Drawings.
  - 5. Technical Specifications.
  - 6. Construction Quality Assurance (CQA) Plan.

### **1.03 CHANGES TO DRAWINGS, SPECIFICATIONS AND CQA PLAN**

- A. It is inherent in the nature of construction that some changes in the Drawings, Specifications, and/or CQA Plan may be necessary during the course of construction to adjust them to field conditions, and it is the essence of the Contract to recognize a normal and expected margin of change. The CONSTRUCTION MANAGER shall have the right to make such changes, from time to time, in the Drawings, in the character of the Work as may be necessary or desirable to insure the completion of the Work in the most satisfactory manner without invalidating the Contract.
  
- B. Design and specification changes will only be made with written agreement of the Design Engineer, Owner and Contractor. Design and specification changes which affect the containment or environmental controls shall also require approval of the Regional Water Quality Control Board (RWQCB).

#### **PART 2 PRODUCTS**

(Not Used)

#### **PART 3 EXECUTION**

(Not Used)

**END OF SECTION**

## **SECTION 01300**

### **SUBMITTALS**

#### **PART 1 GENERAL**

##### **1.01 SUBMITTAL PROCEDURES**

- A. Transmit each submittal with cover letter to the OWNER.
- B. Each submittal shall have a unique submittal number.
- C. Submittals shall be numbered sequentially. Re-submittals shall have original number with an alphabetic suffix (A, B, C, etc.) to indicate the sequence of the re-submittal.
- D. Identify Project, CONTRACTOR, Subcontractor or supplier; pertinent Drawing sheet and detail number(s), and specification Section number, as appropriate.
- E. Identify variations from Contract Documents and Product or system limitations that may be detrimental to successful performance of the completed Work.
- F. Provide space for DESIGN ENGINEER and/or CQA CONSULTANT review stamps.
- G. Revise and resubmit submittals as required, identify all changes made since previous submittal.
- H. Distribute copies of reviewed submittals to concerned parties. Instruct parties to promptly report any inability to comply with provisions.
- I. When catalog pages are submitted, applicable items shall be clearly identified.
- J. An electronic copy (preferred) or three (3) hard copies of each submittal shall be provided to the OWNER. The OWNER will not accept submittals from anyone other than the CONTRACTOR.
- K. The CONTRACTOR shall review all submittal packages prior to transmittal to OWNER for completeness and accuracy.

##### **1.02 CHECK OF RETURNED SUBMITTALS AND WAIVER OF CLAIMS**

- A. The CONTRACTOR shall check and review the submittals returned for correction and ascertain whether the required corrections result in extra cost above that included in the Contract, and shall give written notice to the CONSTRUCTION MANAGER within five (5) working days if, in the CONTRACTOR's estimation, extra costs result from the corrections. The CONTRACTOR's failure to give such written notice before the starting of the Work covered by returned submittal constitutes a waiver by the CONTRACTOR of claims for extra costs resulting from required corrections. Payment based on such written notice is not approved until authorized by the OWNER.

### **1.03 PRODUCT DATA SUBMISSION**

- A. For each product item included in the Work, include the manufacturer's name and address, the trade or brand name, all conditions of manufacturer's guarantee and warranty, information to fully describe each item, and supplementary information as may be required for approval. Mark catalog cuts, brochures, and data to indicate the items proposed and the intended use. Clearly mark product parameters which were specifically called out on the original specifications.

### **1.04 EQUIPMENT DATA SUBMISSION**

- A. Submit complete technical, performance, and catalog information for every item of civil, mechanical, and electrical equipment and machinery proposed for installation in the Work. Include information on performance and operating curves, ratings, capacities, characteristics, power efficiencies, manufacturers' standard guarantees and warranties with the terms and conditions fully described, and all other information to fully illustrate and describe the items as may be specified or required for approval.

### **1.05 SUBMITTAL REVIEW AND ACCEPTANCE**

- A. The submittal review period shall be ten (10) consecutive work days in length and shall commence on the first working day immediately following the date of arrival of the submittal or re-submittal in the OWNER's office. The time required for mail delivery of the submittal or re-submittal back to the CONTRACTOR shall not be considered a part of the submittal review period.
- B. The acceptance of drawings and data submitted by the CONTRACTOR will cover only general conformity to the Drawings and Specifications, external connections, and dimensions which affect the layout. The DESIGN ENGINEER's and/or CQA CONSULTANT's review of submittals shall not relieve the CONTRACTOR from responsibility for errors, omissions, or deviations, nor responsibility for compliance with the contract documents.

### **1.06 RE-SUBMITTALS**

- A. When the drawings and data are returned marked "AMEND AND RESUBMIT" or "REJECTED, SEE REMARKS," the corrections shall be made as noted thereon and as instructed by the DESIGN ENGINEER's and/or CQA CONSULTANT's and shall be resubmitted.
- B. When corrected copies are resubmitted, the CONTRACTOR shall highlight or otherwise direct specific attention to all revisions and shall list separately those revisions made other than those called for on previous submissions.
- C. The need for more than one resubmission shall not entitle the CONTRACTOR to extension of the Contract Time.

### **1.07 COSTS FOR SUBMITTALS**

- A. All costs for the preparation, correction, and delivery of the submittals are considered incidental to the contract and shall be included in CONTRACTOR's costs.

## **PART 2 PRODUCTS**

(Not Used)

## **PART 3 EXECUTION**

### **3.01 MATERIALS REQUIRING SUBMITTALS**

- A. The following materials shall require submittals.
  - 1. Material certifications and product data for all geosynthetics;
  - 2. Material quality control data for all geosynthetics;
  - 3. Material certifications and product data for piping;
  - 4. Material quality control data for piping; and
  - 5. Items not fully detailed and specified in the Contract Drawings or these Specifications.

### **3.02 ITEMS NOT REQUIRING SUBMITTALS**

- A. A submittal is not required for products and equipment completely specified or salvaged on-site. A submittal is required if the product has not been completely specified or when the specified product is not available within the construction schedule. Substitutions requested by the CONTRACTOR require a submittal.

### **3.03 CONSTRUCTION SCHEDULE**

- A. At the pre-construction meeting, the CONTRACTOR shall submit to the CONSTRUCTION MANAGER for review a schedule of the proposed construction operations. The construction schedule shall indicate the sequence of the Work indicating the time of completion of each component of the Work.
- B. Submit initial progress schedule in duplicate within ten (10) days after Effective Date of Agreement for CONSTRUCTION MANAGER to review.
- C. Revise and resubmit as required.
- D. Submit revised schedules with each Application for Payment, identifying changes since previous version.
- E. Submit a horizontal bar chart with separate line for each major section of Work or operation, identifying first work day of each week. Include on the bar chart construction/placement rates for all the major items of Work. CONTRACTOR shall develop proposed Construction Schedule on basis of a five or six day working week. Sufficient labor, equipment, and materials shall be provided by CONTRACTOR to complete the Work on a five or six day per week basis. Night work and work on Sundays will only be approved by the OWNER if the Work falls behind the approved Construction Schedule.

- F. Show complete sequence of construction by activity, identifying Work of separate stages and other logically grouped activities. Indicate the start date, finish date, and duration. At a minimum, the following activities must be shown on the project schedule:
1. Mobilization;
  2. Excavation;
  3. Subgrade preparation;
  4. Placement of the clay liner;
  5. Installation of the geomembranes;
  6. Installation of the geocomposites;
  7. Placement of the operations layer soil;
  8. Construction of surface water controls;
  9. Construction of new riser pipes and pads; and
  10. Demobilization and site clean-up.
- G. Indicate estimated percentage of completion for each item of Work at each submission with Application for Payment.
- H. Indicate submittal dates required for shop drawings, product data, samples and product delivery dates.
- I. The Construction Schedule as approved by the OWNER will be an integral part of the Contract, and will establish interim Contract completion dates for various activities. Should an activity not be completed within ten (10) days after the stated Schedule date, the CONSTRUCTION MANAGER shall have the option to recommend to the CONTRACTOR to expedite completion of the activity by whatever means deemed appropriate and necessary, without additional compensation to the CONTRACTOR.
- J. Should any activity be twenty (20) or more working days behind Schedule, the OWNER shall have the right to perform the activity or to have the activity performed by whatever method the OWNER deems appropriate. Costs incurred by the OWNER in connection with expediting construction activities under this Paragraph shall be reimbursed to the OWNER by the CONTRACTOR.
- K. It is expressly understood and agreed that failure by the OWNER to exercise the option to either order the CONTRACTOR to expedite an activity or to expedite the activity by other means shall not be considered precedent-setting for any other activities. The Work shall be executed in strict accordance with the Construction Schedule unless a variance has been received by the CONSTRUCTION MANAGER and approved by the OWNER.

#### **3.04 PROGRESS REPORTS**

- A. The CONTRACTOR shall submit progress reports as requested indicating work performed and completed that week, quantity of material used, and equipment used to perform the Work.
- B. A progress report shall also be furnished to the ENGINEER with each application for progress payment. If the Work falls behind schedule, the CONTRACTOR shall submit additional progress reports at such intervals as the CONSTRUCTION MANAGER may request.
- C. Each progress report shall include sufficient narrative to describe current and anticipated delaying factors, their effect on the construction schedule, and proposed corrective actions.

Work reported complete, but which is not readily apparent as complete to the CONSTRUCTION MANAGER, must be substantiated with satisfactory evidence.

- D. Each progress report shall also include a graphic schedule marked to indicate actual progress. Revised schedules shall be included when warranted.

### 3.05 MANUFACTURER'S CERTIFICATES

- A. When specified in individual Specification Sections, submit manufacturers' certificate to the CQA CONSULTANT for review, in quantities specified for Product Data.
- B. Indicate whether material or product conforms to or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.
- C. Certificates may be recent or previous test results on material or Product, but must be acceptable to the CONSTRUCTION MANAGER.

### 3.06 RECORD SURVEY AND DRAWINGS

- A. The CONTRACTOR shall keep a set of construction drawings on the job and mark in red pencil the as-built conditions.
- B. A complete and accurate set of record drawings shall be signed and dated by the CONTRACTOR and shall be labeled with the following, "These record drawings completely and truly represent the contract work as installed."
- C. Record drawings shall be delivered to the CONSTRUCTION MANAGER prior to final acceptance of the work by the CONSTRUCTION MANAGER.
- D. Record drawings shall show all changes in "clouds" to clearly identify any deviations from the plans.
- E. Any utilities uncovered during construction shall be identified on the record drawings.
- F. The record survey shall be performed by the CONTRACTOR in accordance with Section 01400, Part 1.04 and shall meet the requirements of these Specifications and the CQA Plan and include, but not be limited to:
  - 1. edges, bottom, and limits of anchor trenches;
  - 2. limits of excavation and fill;
  - 3. final subgrades (including geologic mapping developed by CQA Consultant);
  - 4. top of compacted clay liner;
  - 5. HDPE geomembrane panel layouts and intersections;
  - 6. destructive seam test locations on HDPE geomembranes;
  - 7. location and crown elevations of piping;
  - 8. top of operations layer soil;
  - 9. grade breaks;
  - 10. appurtenant structures (e.g., riser pads); and
  - 11. layout and flow line elevations of surface water control structures.



- G. Survey of the excavated subgrades (including geologic mapping), Clay Liner, and Operations Layer surfaces shall be on a grid with a maximum spacing of 50 feet or an equivalent method approved by the CQA CONSULTANT, with additional elevations at slope change locations. The elevations for the subgrade, top of Clay Liner, and top of Operations Layer shall be at the same grid locations and shall be used to document thickness conformance. The record survey shall include locations and elevations of all other work as directed by the CONSTRUCTION MANAGER.
  
- H. Record drawings shall be prepared to scale, with the scale clearly marked. Record drawings of details may not be to scale, but all dimensions shall be clearly identified. Record drawings shall be submitted to the CQA CONSULTANT for review and approval. Record drawings shall be provided on Bond and electronically in AutoCAD 2005 format or more recent. The DESIGN ENGINEER will provide the base AutoCAD file map. Different elements of the work shall be presented on different layers in the base AutoCAD file provided by the DESIGN ENGINEER.

### **3.07 HEALTH AND SAFETY PLAN**

- A. The CONTRACTOR shall submit a Health and Safety Plan in accordance with Section 01810 of these Specifications.

### **3.08 STORM WATER POLLUTION PREVENTION PLAN (SWPPP)**

- A. The CONTRACTOR shall prepare and submit a SWPPP specific to the work to the OWNER for approval. The SWPPP shall be consistent with the provisions of the "California Construction Best Management Practice Handbook," the site National Pollutant Discharge Elimination System (NPDES) site permit, and the Kettleman Hills Facility SWPPP. The SWPPP shall include specific measures to protect the Work and comply with the regulations, including specific erosion and sediment controls. The CONTRACTOR is responsible to control storm water run-on, run-off, erosion, and sediment to such an extent as needed to maintain compliance with the SWPPP and protect the Work, protect adjacent landfill operations, and adjacent structures.

**END OF SECTION**

## SECTION 01400

### CONSTRUCTION QUALITY CONTROL

#### PART 1 GENERAL

##### 1.01 CONSTRUCTION QUALITY CONTROL

- A. The CONTRACTOR shall be responsible for construction quality control of the Work and all appurtenances as described in these Specifications.
- B. The CONTRACTOR shall monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce Work of specified quality.
- C. The CONTRACTOR shall comply fully with manufacturers' instructions, including each step in sequence.
- D. Should manufacturers' instructions conflict with Contract Documents, the CONTRACTOR shall request clarification from CONSTRUCTION MANAGER before proceeding.
- E. The CONTRACTOR shall comply with specified standards as a minimum quality for the Work except when more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
- F. The CONTRACTOR shall perform work using persons qualified to produce workmanship of specified quality.
- G. The CONTRACTOR shall secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion or disfigurement.
- H. The CONSTRUCTION MANAGER shall determine and decide all questions which may arise as to the quality and acceptability of materials and Work performed; the manner of performance and the rate of progress of said Work; the interpretations of the Contract Documents relating to the Work; the acceptable fulfillment of the Contract Documents on the part of the CONTRACTOR; and the amount and quantity of the several kinds of Work performed and materials which are to be paid for under the Contract.
- I. All materials and equipment shall be new and of the specified quality and equal to the samples found to be acceptable by the CQA CONSULTANT, if samples have been submitted.
- J. The Work shall be done and completed in a thorough, workmanlike manner, notwithstanding omissions in the Contract Documents; and it shall be the duty of the CONTRACTOR to call the CONSTRUCTION MANAGER's attention to apparent errors or omissions and request instructions in writing before proceeding with the Work.

- K. The CONSTRUCTION MANAGER may, by appropriate written instructions, correct errors and omissions. Instructions and corrections shall be as binding upon the CONTRACTOR as though contained in the original Contract Documents.

#### **1.02 CONSTRUCTION QUALITY ASSURANCE**

- A. Materials, equipment, methods of construction and workmanship shall be subject to the inspection of the CQA CONSULTANT as outlined in the CQA Plan. Defective materials, equipment, or work shall be replaced, corrected or otherwise made good by the CONTRACTOR at the CONTRACTOR's own expense.
- B. On all questions concerning the acceptability of materials or equipment, execution of the Work, and the determination of costs, the decision of the CONSTRUCTION MANAGER shall be final and binding upon all parties.
- C. The CONTRACTOR shall at all times maintain proper facilities and provide safe access to all parts of the Work, to the shops wherein the Work is in preparation, and to all warehouses and storage yards wherein materials and equipment are stored, for purposes of inspection by the CQA CONSULTANT.
- D. The CONTRACTOR shall provide incidental labor and facilities to provide access to Work to be tested, to obtain and handle samples at the Site or at source of products to be tested, and to facilitate tests and inspections.
- E. Notify CQA CONSULTANT 24 hours prior to expected time for operations requiring inspection services.
- F. Retesting required because of non-conformance to specified requirements shall be performed by the CQA CONSULTANT on instructions by the CONSTRUCTION MANAGER. Payment for retesting will be charged to the CONTRACTOR by deducting inspection or testing charges from the Contract Price.
- G. Employment of CQA CONSULTANT by OWNER shall in no way relieve the CONTRACTOR of obligations to perform Work in accordance with requirements of Contract Documents.

#### **1.03 MANUFACTURERS' FIELD SERVICES AND REPORTS**

- A. When specified in individual Specification Sections, required material or Product suppliers or manufacturers shall provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, and quality of workmanship as applicable, and to initiate instructions when necessary.
- B. Individuals shall report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions.

#### **1.04 SURVEYING**

- A. At least two control monuments shall be established by the CONTRACTOR at locations convenient for daily tie-in. The vertical and horizontal controls for these

control points shall be established within normal land surveying standards. The CONTRACTOR shall use these control points in laying out and providing ongoing geometric control of the work. The control monuments shall be shown on all record drawings.

- B. Surveying shall be performed under the direct supervision of a licensed land surveyor or registered civil engineer authorized to practice land surveying under Chapter 15, Article 3, Section 8731 of the Professional Engineering Act of California, as amended January 1, 1992 who may also be the senior surveyor on site. The survey crew shall consist of the senior surveyor and as many surveying assistants as required to satisfactorily undertake the work. Personnel shall be experienced in all aspects of surveying, including detailed, accurate documentation.
- C. The survey instruments used for this work shall be sufficiently precise and accurate to meet the needs of the project. Survey instruments shall be capable of reading to a precision of 0.01 feet and with a setting accuracy of 10 seconds. Calibration certificates for survey instruments shall be submitted on request to the CQA CONSULTANT prior to the initiation of surveying activities.
- D. It shall be the CONTRACTOR's sole responsibility to control the Work so that all of the geometric requirements of the project are met. The CONTRACTOR shall immediately notify the CONSTRUCTION MANAGER and the CQA CONSULTANT of any discrepancy found in the Work. It will be the CONSTRUCTION MANAGER's sole prerogative to approve or reject work which does not meet the requirements contained in these Specifications and the Drawings, but which, in the CONSTRUCTION MANAGER's sole opinion, may nevertheless meet the intention of the Contract Documents.
- E. The CONTRACTOR shall be responsible for the accuracy of all work and shall maintain all reference points, stakes, etc., throughout the life of the project. Damaged or destroyed points, bench marks or stakes, or any reference points made inaccessible by the progress of the construction shall be replaced or transferred by the CONTRACTOR. Any of the above points shall be referenced by ties to acceptable objects and recorded. Any alternations or revisions in the ties shall be so noted and the information furnished to the CONSTRUCTION MANAGER immediately. All computations necessary to establish the exact position of the work from control points shall be made and preserved by the CONTRACTOR. All computations, survey notes and other records necessary to accomplish the work shall be neatly made and shall be made available onsite for review by the CQA CONSULTANT.
- F. During the progress of the construction work, the CONTRACTOR shall be required to furnish all of the surveying and state-out incidental to the proper location by line and grade for each phase of the work. For any operation requiring extreme accuracy, the CONTRACTOR shall restake with pins or other acceptable hubs located directly adjacent to the work at a spacing approved by the CONSTRUCTION MANAGER.

## **PART 2 PRODUCTS**

(Not Used)

**PART 3 EXECUTION**

(Not Used)

**END OF SECTION**

## **SECTION 01402**

### **CONTROL OF WORK**

#### **PART 1 GENERAL**

##### **1.01 AUTHORITY OF THE CONSTRUCTION MANAGER**

- A. The CONSTRUCTION MANAGER will decide all questions which may arise as to the quality and acceptability of materials furnished and work performed; all questions which may arise as to the interpretation of the Drawings and Specifications; and all questions as to the satisfactory and acceptable fulfillment of the Contract on the part of the CONTRACTOR.
- B. The OWNER shall have the authority to stop the Work if odor or dust becomes a nuisance.

##### **1.02 AUTHORITY OF THE CQA CONSULTANT**

- A. The CQA CONSULTANT employed by the OWNER shall be authorized to monitor all work done and materials and equipment furnished. Such monitoring may extend to all or part of the Work, and to the preparation, fabrication, or manufacture of the materials and equipment to be used. The CQA CONSULTANT will not alter or waive the provisions of the Contract Documents.
- B. The CQA CONSULTANT will keep the CONSTRUCTION MANAGER informed as to the progress of the Work and the manner in which it is being done; also, the CQA CONSULTANT will call the CONTRACTOR's attention to non-conformance with the Contract Documents that the CQA CONSULTANT may have observed. The CQA CONSULTANT will not approve or accept any portion of the Work, issue instructions contrary to the Contract Documents, or act as foreman for the CONTRACTOR. The CQA CONSULTANT may reject defective materials, equipment, or work subject to final decision of the CONSTRUCTION MANAGER.
- C. The CONSTRUCTION MANAGER may delegate additional authority to the CQA CONSULTANT. In such cases, the CONSTRUCTION MANAGER will notify the CONTRACTOR of such action.

##### **1.03 COORDINATION AND INTERPRETATION OF DRAWINGS AND SPECIFICATIONS**

- A. The Specifications, General Conditions, Special Conditions, CQA Plan, Contract Change Orders, and all supplementary documents are essential parts of the Contract, and a requirement occurring in one is as binding as though occurring in all. They are intended to be coordinated and to describe and provide for a complete work.
- B. Should it appear that the Work or other matters relative thereto are not sufficiently detailed or explained in the Contract Documents, the CONTRACTOR shall apply to the CONSTRUCTION MANAGER for such further explanations as may be necessary and shall conform to them as part of the Contract.

- C. In the event of a doubt or question arising regarding the true meaning of the Contract Document, reference shall be made to the CONSTRUCTION MANAGER, whose decision thereon shall be final.
- D. In the event of a discrepancy between a drawing and the figures written thereon, and/or the Drawings and the Specifications, the CONTRACTOR shall notify the CONSTRUCTION MANAGER in writing and wait for approval before proceeding. Scaled dimensions shall not be used in the performance of the Work.

## **PART 2 PRODUCTS**

(Not Used)

## **PART 3 EXECUTION**

### **3.01 PERFORMANCE REQUIREMENTS**

- A. The CONTRACTOR shall furnish the CONSTRUCTION MANAGER with every reasonable facility for ascertaining whether or not the Work as performed is in accordance with the requirements and intent of the Specifications and Contract.
- B. Should a work be covered before acceptance or consent of the CONSTRUCTION MANAGER, it must, if required by the CONSTRUCTION MANAGER, be uncovered for examination at the CONTRACTOR's expense.

**END OF SECTION**

## **SECTION 01565**

### **TEMPORARY FACILITIES**

#### **PART 1 GENERAL**

##### **1.01 SUMMARY**

- A. The CONTRACTOR shall provide all temporary facilities and utilities required for prosecuting the Work, protection of employees and the public, protection of the Work from damage by fire, weather or vandalism, and such other facilities as may be specified or required by an applicable law, ordinance, rule, or regulation.
- B. The CONTRACTOR must provide their own office space for their needs if necessary. The location of the office shall be approved by the OWNER.

##### **1.02 ELECTRICAL SERVICE**

- A. Electrical power is not available at the site. The CONTRACTOR shall arrange for temporary electric connection or supply a generator capable of providing the power required to operate tools or equipment or to provide area lighting as needed. Temporary power whether supplied by a utility company or by a generator shall conform to the requirements of the 1993 National Electrical Code, the 1993 National Electrical Safety Code, and all applicable national standards, local regulations and ordinances.
- B. The allowable hours of generator operation is the same as the regular working hours for the project. All generators shall be fitted with a residential quality muffler.

##### **1.03 FIRST AID**

- A. First aid kits meeting the minimum requirements of the Occupational Safety and Health Administration shall be provided in a readily accessible location or locations indicated in the CONTRACTOR's Health and Safety Plan as outlined in Section 01810 of these Specifications.

##### **1.04 CONSTRUCTION FACILITIES**

- A. Construction hoists, elevators, scaffolds, stages, shoring and similar temporary facilities shall be of ample size and capacity to adequately support and move the loads to which they will be subjected. Railings, enclosures, safety devices, and controls required by law or for adequate protection of life and property shall be provided.

##### **1.05 STAGING AND SHORING**

- A. Temporary supports shall be designed with an adequate safety factor to assure stability and adequate load bearing capacity.
- B. Trenches greater in depth than four (4) feet shall be shored or sloped according to OSHA requirements.



#### **1.06 TEMPORARY ENCLOSURES**

- A. When any activity hazardous to property or the health of employees and the public is in progress, the area of activity shall be enclosed adequately to contain the dust, overspray, or other hazard. In the event there are not permanent enclosures in the area, or such enclosures are incomplete or inadequate, the CONTRACTOR shall provide suitable temporary enclosures.

#### **1.07 WARNING DEVICES AND BARRICADES**

- A. The CONTRACTORS shall adequately identify and guard all hazardous areas, holes, pits, and conditions by visual warning devices and physical barriers. Such devices shall, as a minimum, conform to the requirements of OSHA and Cal-OSHA.

#### **1.08 HAZARDS IN PUBLIC ACCESS AREAS**

- A. Trenches and other essentially continuous excavations in public access areas, running parallel to the general flow of traffic, shall be marked at reasonable intervals by traffic cones, barricades, or other suitable visual markers during daylight hours. During hours of darkness, these markers shall be provided with either torches, flashers or other adequate lights.

#### **1.09 FIRE EXTINGUISHERS**

- A. A sufficient number of fire extinguishers of the type and capacity required to protect the site and ancillary facilities shall be provided in readily accessible locations.

#### **1.10 ODOR CONTROL**

- A. The CONTRACTOR shall comply with the provisions for control of odor and emissions as required by the MDAQMD or the OWNER.

#### **1.11 SANITATION FACILITIES**

- A. CONTRACTOR shall provide and maintain ample field latrines and ablution accommodations in accordance with OSHA requirements for all workers employed on the project under the contract. Field latrines and ablution accommodations shall be provided and maintained in a sanitary condition at all times during the work on this project.

#### **1.12 MATERIAL STORAGE**

- A. A materials storage area shall be designated to the CONTRACTOR by the CONSTRUCTION MANAGER. The CONTRACTOR is responsible for security of all of his materials and equipment.

### **PART 2 PRODUCTS**

(Not Used)

**PART 3 EXECUTION**

(Not Used)

**END OF SECTION**

## SECTION 01810

### SAFETY PROCEDURES

#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. This section establishes minimum safety requirements and guidelines for the performance of the Work.
- B. The CONTRACTOR is advised that decomposing waste produces landfill gas which is potentially flammable or explosive.
- C. The CONTRACTOR shall submit a Health and Safety Plan and a copy of their Injury and Illness Prevention Program to the OWNER for review prior to beginning work.
- D. The CONTRACTOR shall hold mandatory daily tailgate safety meetings on the site, as well as formal weekly safety meetings.

##### 1.02 GENERAL REQUIREMENTS

- A. The CONTRACTOR shall have sole responsibility and liability for the safety, efficiency, and adequacy of the CONTRACTOR's personnel, equipment and methods, and for any damage or injury resulting from their failure, or improper maintenance, use, or operation.
- B. The CONTRACTOR shall be solely and completely responsible for the conditions at the Work area arising from the CONTRACTOR's execution of the Work. This requirement shall apply continuously and not be limited to normal working hours.
- C. The CONTRACTOR shall provide all personnel working on the project with orientation and training on the potential hazards anticipated and the appropriate use of safety equipment.
- D. Neither the OWNER nor the CONSTRUCTION MANAGER shall have liability resulting from injury or death to CONTRACTOR's employees or subcontractors and their employees.
- E. A health and safety officer, employed by the CONTRACTOR, shall be present at all times during construction of underground facilities. The health and safety officer may be the site superintendent or other responsible regular employee of the CONTRACTOR provided he has had special health and safety training, and shall have responsibility for the enforcement of the Health and Safety Plan, particularly as it applies to drilling activities. The health and safety officer shall be identified by name in the Health and Safety Plan.
- F. Many gases are heavier than air and settle in low areas such as trenches and excavations, therefore additional precautions shall be observed in these areas. Specifically, the need for constant O<sub>2</sub> monitoring, forced ventilation, combustible gas monitoring, VOC monitoring, respiratory protective equipment, etc. shall be

determined by the CONTRACTOR. The CONSTRUCTION MANAGER may impose additional requirements when deemed necessary for worker safety.

### **1.03 HEALTH AND SAFETY PLAN**

- A. The CONTRACTOR shall develop and maintain for the duration of work activities at the site, a written, site specific Health and Safety Plan for landfill operations that will effectively incorporate and implement all applicable requirements. The plan will meet the requirements of CCR Title 8 Section 5192.
- B. In addition to requirements set forth in other sections, the CONTRACTOR's Health and Safety Plan shall contain provisions for aspects of protection against bodily injury from heavy construction equipment, tools and equipment required to construct the system.
- C. The Health and Safety Plan shall include the location and route to the nearest hospital or emergency facility. All CONTRACTOR employees and subcontractors working on the project shall be thoroughly familiar with the emergency route.
- D. In the event the Health and Safety Plan is determined by the CONSTRUCTION MANAGER, OWNER or the State or Federal Regulatory Agencies to be inadequate to protect the employees and the public, the plan shall be modified prior to the beginning of the Work to meet the minimum requirements of the OWNER or the State or Federal Regulatory Agencies at no additional cost to the OWNER.
- E. Acceptance of the CONTRACTOR's Health and Safety Plan by the OWNER does not release the CONTRACTOR of liability in the event of an accident or injury, nor does it place any liability on the CONSTRUCTION MANAGER or OWNER.
- F. Provisions shall be made to protect against ingestion, absorption or inhalation of hazardous compounds and for the handling of refuse in a safe, sanitary, and proper manner.
- G. The CONTRACTOR's Health and Safety Plan shall contain trenching and excavation safety guidelines particular to landfill work.

### **1.04 REGULATORY REQUIREMENTS**

- A. The CONTRACTOR shall comply with provisions of safety regulatory bodies including, but not necessarily limited to:
  - 1. OSHA/Cal-OSHA regulations for construction
  - 2. 29 Code of Federal Regulations (CFR) 1926/1910 and CFR 1910.120
  - 3. Title 8 California Code of Regulations, in particular Section 5192.
  - 4. All other applicable federal, state, county and local laws, ordinances, codes, the requirements
- B. If any of these requirements are in conflict, the more stringent requirement shall apply. The CONTRACTOR's failure to be thoroughly familiarized with the aforementioned safety and health provisions shall not relieve the CONTRACTOR of

responsibility for full compliance with the obligations and requirements set forth herein.

- C. The CONTRACTOR shall conform to the rules and regulations of the State Construction Safety regulations pertaining to excavations and trenches. A copy of the regulations is available at the OWNER.

#### **1.05 SPECIAL SAFETY CONSIDERATION RELATED TO LANDFILL WORK**

- A. Portions of the Work involve excavation and removal of and construction near hazardous waste.
- B. The landfill may contain leachate water contaminated with substances found in the landfill which may be corrosive, toxic, carcinogenic, mutagenic or otherwise hazardous.

#### **PART 2 PRODUCTS**

(Not Used)

#### **PART 3 EXECUTION**

##### **3.01 GENERAL REQUIREMENTS**

- A. The CONTRACTOR shall assume full responsibility to assure that during construction his employees, subcontractors and their employees follow the Health and Safety Plan.
- B. The CONTRACTOR shall hold mandatory weekly safety meetings on the site. The CONTRACTOR shall notify the CONSTRUCTION MANAGER of the time and place of all meetings and allow the CONSTRUCTION MANAGER to participate. Meetings should reiterate safety measures to be taken and discuss any violations committed and preventive measures to avoid future violations.
- C. The CONTRACTOR shall require all personnel on the site to wear the appropriate personnel protective equipment such as steel toe boots, hard hats, orange safety vests, safety belts and lanyards, and others.
- D. The CONTRACTOR shall provide appropriate fall protection (i.e., harness and shock absorbing lanyard) that must be worn and secured to a stationary object when working within a distance of ten 10 feet of an excavation greater than eight (8) inches in diameter or deeper than four (4) feet.
- E. No smoking or consumption of alcohol or any drug which could impair sight, balance or judgment is permitted on the job.

##### **3.02 TRENCHING SAFETY**

- A. The CONTRACTOR shall complete each excavated trench prior to the end of the working day. A trench shall be considered complete if it has been backfilled to the landfill surface.

- B. Any time excavations and trenching exceed four (4) feet in depth, shoring, bracing or sloping of the side walls is required prior to entry. If sloping is the method used, side walls of the trench shall be sloped at a 2H:1V slope (Cal-OSHA requirement).
- C. Welding is to be avoided within the barricaded area. If HDPE pipe welding is performed in the trench, continuous methane monitoring shall be performed.
- D. Solvent cleaning, gluing or bonding of pipe shall be done, to the extent practicable, outside the trench.
- E. All trenches shall be backfilled as soon as practical after excavation, and under no circumstances shall a trench remain open after the crew has left the vicinity of the trench. A maximum of 300 feet of trench may be exposed at any one time. All exposed refuse must be covered at the end of each day using cover soil or a tarp.
- F. Electric motors shall not be used in trenches. Pneumatic operated tools shall be used in the trench.

### **3.03 VIOLATIONS**

- A. Should any health and safety violations be called to the CONTRACTOR's attention by anyone, the CONTRACTOR shall immediately correct the violations.
- B. If the CONTRACTOR violates any health and safety rule or regulation, the OWNER may issue an order to stop all work until the violations are remedied. The CONTRACTOR shall not be entitled to any extension of the time or any claim for damage or to any compensation for either the directive or the work suspension order. A decision by the OWNER not to order discontinuance of any or all of the CONTRACTOR's operations shall not relieve the CONTRACTOR of responsibility for safety.

**END OF SECTION**

## SECTION 02105

### EROSION CONTROL

#### PART 1 GENERAL

##### 1.01 DESCRIPTION

- A. This section describes the general requirements for erosion control measures associated with lining materials for drainage channels.

#### PART 2 PRODUCTS

##### 2.01 EROSION CONTROL BLANKET

Permanent Turf Reinforcement Mat shall be Propex Landlok 407, or equivalent. To be used in drainage channels at the locations shown on the Plans.

#### PART 3 EXECUTION

##### 3.01 GENERAL

- A. Grade and compact area of installation and remove all rocks, clods, vegetation or other obstructions so that the installed mat will have direct contact with soil surface. Prepare seedbed by loosening 2-3 inches of topsoil. Incorporate amendments such as fertilizer into soil.
- B. For temporary erosion control mat, apply seed to soil surface before installing blanket/mat. For permanent erosion control mat, apply seeding after installation and prior to filling mat with soil.
- C. The CONTRACTOR shall install the permanent and temporary control mats in accordance with the manufacturer's recommendations. In general the installation should include:
1. Anchor trenches or check slots (6-inches deep) at 30 foot intervals along the trench.
  2. Longitudinal anchor trenches (4-inches deep) to secure outside edges.
  3. Anchor erosion control mat with U-shaped wire staples. Staples shall be a minimum of 6-inches in length and have sufficient ground penetration to resist pullout. Longer anchors may be required. Anchors for the permanent erosion control mat shall be installed with a minimum of 2 anchors per square yard. Temporary erosion control mats shall be installed with a minimum of 1.5 anchors per square yard.

4. After installation of permanent erosion control mat, apply seed and apply  $\frac{1}{2}$  to  $\frac{3}{4}$  inches of fine soil into the mat to completely fill the voids. Use backside of rake, or similar, to smooth soil fill in order to just expose the top netting.

**END OF SECTION**



## SECTION 02110

### SITE CLEARING, GRUBBING AND STRIPPING

#### PART 1 GENERAL

##### 1.01 DESCRIPTION

- A. This section describes the general requirements for site clearing, grubbing and stripping associated with the construction of Phase III of Landfill B-18 at the Kettleman Hills Facility.
- B. Clearing, grubbing and stripping shall be performed to remove organic, soft, loose, and deleterious materials and expose a firm, unyielding subgrade.

##### 1.02 RELATED SECTIONS

- A. Section 02200 - Earthwork
- B. Section 02751 - HDPE Geomembranes

#### PART 2 PRODUCTS

- A. Organic, soft, loose and deleterious materials includes, but is not limited to, vegetative growth, non-engineered fills, alluvial deposits, soft, loose, or saturated subgrade soils, refuse, and construction debris.

#### PART 3 EXECUTION

##### 3.01 PROTECTION

- A. Locate, identify, and protect utilities that remain from damage.
- B. Protect existing groundwater monitoring wells and piezometers from damage or displacement.

##### 3.02 CLEARING

- A. Clear areas required for access to site and execution of work.
- B. Earthwork CONTRACTOR shall remove all organic and deleterious material, and trash from the subgrade surface. Vegetative growth greater than 1 inch in dimension shall be removed to a depth of 6 inches below the subgrade surface.
- C. The Earthwork CONTRACTOR shall consider that clearing, grubbing, and stripping will necessitate the use of manual labor to remove all organic and deleterious material from the subgrade surface.
- D. The Earthwork CONTRACTOR shall remove soft, loose, or saturated materials as approved by the CQA CONSULTANT. The materials shall be removed until a firm, unyielding subgrade, approved by the CQA CONSULTANT, is exposed.

- E. All removed materials shall be disposed of onsite in an area designated by the PROJECT MANAGER. No accumulation of flammable material shall remain on or adjacent to the construction area.
- F. The Earthwork CONTRACTOR shall expose existing liner terminations as required on the Drawings. The Work may require hand excavation to avoid damage to the existing liner. Any damage to the existing liner shall be repaired by the Earthwork CONTRACTOR at no additional cost to the OWNER.

**END OF SECTION**

## **SECTION 02200**

### **EARTHWORK**

#### **PART 1 GENERAL**

##### **1.01 SUMMARY**

- A. The Earthwork CONTRACTOR shall furnish all labor, materials, equipment and incidentals necessary to perform all excavation, backfilling, compaction and grading required to complete the work shown on the Drawings and specified herein. The Work shall include, but not necessarily be limited to, survey and staking, borrow excavation and hauling, excavation for trenches, fill placement and compaction, grading, and all related work.
- B. The Earthwork CONTRACTOR shall comply with the safety procedures given in Section 01810 of these Specifications.

##### **1.02 RELATED SECTIONS**

- A. Section 01300 - Submittals
- B. Section 01400 - Construction Quality Control
- C. Section 02110 - Site Clearing, Grubbing and Stripping.
- D. Section 02220 - Compacted Clay Liner
- E. Section 02751 - HDPE Geomembranes

##### **1.03 REFERENCE STANDARDS**

- A. American Society for Testing and Materials (ASTM), latest editions:
  - 1. ASTM D422 - Test Method for Particle Size Analysis of Soils.
  - 2. ASTM D1556 - Test Method for Density of Soil In-Place by the Sand Cone Method.
  - 3. ASTM D1557 - Test Methods for Moisture-Density Relations of Soils and Soil Aggregate Mixtures Using 10-lb. Rammer and 18-inch Drop.
  - 4. ASTM D2216 - Standard Test Method for Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass.
  - 5. ASTM D2419 - Test Method for Sand Equivalent Value of Soil/Fine Aggregate.
  - 6. ASTM D2497 - Standard Test Method for Classification of Soils for Engineering Purposes.
  - 7. ASTM D2937 - Standard Test Method for Density of Soil in Place by the Drive-Cylinder Method.
  - 8. ASTM D6938 -- In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth).

B. Standard Specifications for Public Works Construction (SSPWC).

**1.04 QUALITY ASSURANCE/CONTROL**

- A. The Earthwork CONTRACTOR shall adhere to the requirements of Section 01400 of these Specifications.
- B. Compaction testing of engineered fill and backfill shall be performed by the CQA CONSULTANT. Testing shall be performed at locations to be determined by the CQA CONSULTANT, in order to determine if the soils meet the compaction requirements. Costs for testing to verify compaction and soil moisture content will be assumed by the OWNER. The cost of retesting, should corrections to construction be required, shall be the responsibility of the Earthwork CONTRACTOR.
- C. The OWNER shall have complete authority to order immediate stoppage of work due to use of improper construction procedures, or for any reason that in his sole opinion, may result in a defective work.

**1.05 DEFINITIONS**

- A. Excavation: Consists of the removal of material encountered to subgrade elevations and the reuse or disposal of materials removed.
- B. Subgrade: The surface upon which structures/systems/fills are constructed.
- C. Borrow: Soil material obtained from other than the excavation.
- D. Unauthorized excavation consists of removing materials beyond indicated subgrade elevations or dimensions without direction by the PROJECT MANAGER. Unauthorized excavation, as well as remedial work directed by the PROJECT MANAGER, shall solely be at the Earthwork CONTRACTOR's expense.
- E. Utilities include on-site above ground and underground pipes, conduits, ducts, and cables, as well as underground services.

**1.06 SAFETY**

- A. CONTRACTOR is solely responsible for performing work in a safe manner and complying with all applicable local, state and federal codes, ordinances, laws, and regulations.
- B. CONTRACTOR shall comply with the requirements of the Health and Safety Plan.

**PART 2 PRODUCTS**

**2.01 MATERIALS**

- A. Structural Fill
  - 1. Structural Fill shall be removed from the on-site borrow area(s) designated by the OWNER. Material shall be predominantly free from roots, wood, organic matter,

refuse or other deleterious matter, and shall not contain particles over 6 inches in greatest dimension.

2. The OWNER has designated on-site borrow source(s) for the CONTRACTOR. The CONTRACTOR shall be responsible for excavating, loading, hauling, placing and compacting the material from the designated borrow source(s).

**B. Clay Liner (see Section 02220)**

**C. Operations Layer (see Section 02228)**

**D. Trench Backfill**

1. Trench Backfill shall be removed from the on-site borrow area(s) designated by the OWNER. Material shall be predominantly free from roots, wood, organic matter, refuse or other deleterious matter, and shall not contain particles over 1 inch in greatest dimension.
2. The OWNER has designated on-site borrow source(s) for the CONTRACTOR. The CONTRACTOR shall be responsible for excavating, loading, hauling, placing and compacting the material from the designated borrow source(s).

**E. Water**

1. Water shall be potable water or reclaimed water approved for use by OWNER.
2. The OWNER will provide water for dust control and soil preparation to the Earthwork CONTRACTOR at no cost to the Earthwork CONTRACTOR.
3. The CONTRACTOR shall only obtain water from sources designated by the OWNER.

**PART 3 EXECUTION**

**3.01 GENERAL**

- A. The Earthwork CONTRACTOR shall be solely responsible for the satisfactory completion of all earthwork in accordance with the Drawings and Specifications.
- B. Equipment used in the excavation, transport, placement and compaction of all materials used in construction will be standard of practice grading machinery of known specifications suitable for performing the required work in a timely and efficient manner.
- C. All material considered by the CQA CONSULTANT to be unsuitable for use in the construction of the earthwork shall be removed. All materials incorporated as part of engineered fill must be inspected and placement must be observed by the CQA CONSULTANT. Unsuitable material shall be disposed of in the designated area.
- D. Where work is interrupted by heavy rains, earthwork operations shall not be resumed until observations and field tests by the CQA CONSULTANT indicate the moisture

- content and density of the in-place fills and/or materials intended for placement are within the specified requirements.
- E. If any unanticipated earth conditions of an adverse or potentially adverse nature are encountered during grading, the Earthwork CONTRACTOR shall immediately notify the CQA CONSULTANT. The CQA CONSULTANT and DESIGN ENGINEER shall investigate, analyze, and make recommendations to mitigate these conditions.
  - F. Throughout construction, all excavated and/or fill areas shall be graded to provide positive drainage and prevent ponding of water. Surface water shall be controlled to avoid damage to adjoining properties or to finished work on the site.
  - G. No heavy equipment shall be permitted to operate within 3 feet of existing wellheads or piping. Compaction of material within these limits shall be completed with hand equipment.
  - H. The Earthwork CONTRACTOR shall apply water to any exposed earthen areas during construction to minimize airborne dust. This shall include active and inactive excavation areas, haul roads, and any non-vegetated stockpiles. The Earthwork CONTRACTOR shall be responsible for complying with all state and local regulations regarding dust and/or air quality.
  - I. Earthwork CONTRACTOR shall not use "paddle-wheel" (i.e., Caterpillar 613 or equivalent) equipment to excavate soils.
  - J. Earthwork CONTRACTOR shall provide manned traffic control (e.g., flagman) at locations identified by Owner and/or Contractor as being a potential safety hazard.

### 3.02 CONTROL OF WATER

- A. The Earthwork CONTRACTOR shall excavate and backfill in a manner and sequence that will provide proper drainage at all times. The Earthwork CONTRACTOR shall remove all water, including runoff and run-on collected from rainwater encountered during excavation, to a location approved by the PROJECT MANAGER, by pumps, drains, and other approved methods.
- B. The Earthwork CONTRACTOR shall take all necessary precautions to preclude the accidental discharge of fuel, oil, etc. and to prevent such accidents that may endanger the environment. The Earthwork CONTRACTOR will be responsible for the cost of remediating the results of any such discharges or accidents.

### 3.03 BORROW

- A. CONTRACTOR shall submit the proposed limits of the borrow area to the OWNER for approval prior to the commencement of the Work. The maximum limits of the borrow area are shown on the Drawings.
- B. The gradients of the borrow slopes and the depth of the borrow excavation should not exceed those specified on the Drawings. If the slopes are constructed steeper or the depth of the borrow excavation is greater than that specified on the Drawings, the CONTRACTOR shall reconstruct the slopes/refill the bottom to the gradients/depth

specified by backfilling and compacting material in accordance with the requirements for engineered fill in this Section. The cost to reconstruct the slopes/refill the bottom will be borne solely by the CONTRACTOR.

- C. The CONTRACTOR shall maintain a secure work site at all times.

### **3.04 STRUCTURAL FILL**

- A. Prior to placing structural fill, CONTRACTOR shall clear and grub the area in accordance with Section 02110 of these Specifications. CONTRACTOR shall also remove uncertified existing fills, disturbed soils and deleterious materials from the area to the satisfaction of the CQA CONSULTANT.
- B. The ground surface (i.e. areas with less than 10% slope) to receive fill shall be over excavated a minimum of 2 feet. The base of the excavation shall be scarified to a depth of 8 inches. The scarified ground surface shall then be brought to within 3 percent of optimum moisture content, mixed as required, and compacted to a minimum of 90 percent of the maximum dry density as determined by ASTM D1557. Excavated soil may be used for filling the excavation if placed in accordance with the structural fill requirements. If the scarified zone is greater than 12 inches in depth, the excess shall be removed, placed in loose lifts not to exceed 8 inches in loose thickness. Prior to fill placement, the ground surface to receive fill shall be stabilized and inspected by the CQA CONSULTANT.
- C. Fill placed against existing slopes (i.e., areas with greater than 10% slope) shall be keyed into the slope. Keys shall extend a minimum of 6 feet horizontally into the existing slope. The keys shall form a series of steps in the existing fill.
- D. Fill shall be placed in loose lifts not to exceed 8-inches thick, brought to a uniform moisture content within 3 percent of optimum, and compacted to 90 percent of the maximum dry density as determined by ASTM D1557.
- E. Where tests indicate the moisture content or density of any layer of fill or portion thereof is below the Project requirements, the particular layer or portion thereof shall be reworked until the required moisture or density has been attained. No additional fill shall be placed over an area until the prior fill lift has been tested and meets the present requirements to the satisfaction of the CQA CONSULTANT.
- F. In the event of rain or other reason, if the moisture content of previously placed fill material or processed soils intended for placement is more than 3 percent above optimum as determined by ASTM D1557, the fill material shall be aerated by blading, disking, or other satisfactory method until the moisture content complies with the requirements of this Section. Any previously compacted materials which are disturbed (aerated, bladed, etc.) to reduce or increase the moisture content must be recompacted to the Specifications and to the satisfaction of the CQA CONSULTANT once specified moisture contents are attained.

### **3.05 SURFACE PREPARATION**

- A. All surfaces to be overlain by geosynthetics shall be smooth, uniformly sloped (minimum 5%), firm, and free of rocks, protrusions, or depressions greater than 0.5-

inch in maximum dimension. The Earthwork CONTRACTOR shall consider that manual removal/repair of unacceptable areas may be required and shall be considered inherent to the work described herein.

### **3.06 TRENCH EXCAVATION AND BACKFILL**

- A. All trenches shall be excavated to lines and grades and dimensions indicated on the Drawings. All trench excavation, backfill, and compaction shall be in accordance with pertinent provisions of this Section.
- B. All pipe work placed inside the trenches shall have a minimum of 8-inch clearance from any protrusions from the trench side walls or bottom.
- C. The Earthwork CONTRACTOR shall backfill excavated trenches as promptly as progress of the work permits and immediately after the pipe has been laid, jointed, and tested.
- D. The trench bottom shall be compacted to provide a uniform bed for the pipe. Backfill material shall be placed around the pipe and shall be compacted by hand-tamping, or methods acceptable to the CQA CONSULTANT.
- E. The Earthwork CONTRACTOR shall compact the select engineered fill for trench backfill to at least 90 percent of the maximum dry density and within 3 percent of the optimum moisture content as determined in accordance with ASTM D1557.
- F. Trench backfill shall be placed as shown on the Drawings. The backfill shall not be placed at ambient temperatures below 41°F nor above 100°F unless otherwise specified. The material shall be placed in a manner that does not cause movement or excessive wrinkling of, or induce excessive wrinkling of the geosynthetics. The CONTRACTOR shall not operate equipment directly on any geosynthetics.

### **3.07 TOLERANCES**

- A. All material limits shall be constructed within a tolerance of  $\pm 1.0$  ft for horizontal State Plane coordinates, 0 to +0.1 ft vertical for reference to mean sea level (MSL), and 0 to +0.1 ft where dimensions are shown or specified as a minimum. The plane of the surface shall not vary more than 0.10 feet when measured with a 10-foot straight edge.

### **3.08 EXCAVATION BELOW GRADE**

- A. All excavation shall be performed within the limits of the work to the lines, grades, and elevations indicated and specified herein. The Earthwork CONTRACTOR shall not excavate or remove materials beyond indicated subgrade elevations or dimensions without the approval of the PROJECT MANAGER. The Earthwork CONTRACTOR shall backfill and compact any unauthorized excavation to the satisfaction of the PROJECT MANAGER at no additional cost to the OWNER.
- B. When acceptable to the PROJECT MANAGER, lean concrete may be used to bring the bottom elevation of excavations under footings or trenches to correct elevations.

**END OF SECTION**



## SECTION 02220

### COMPACTED CLAY LINER

#### PART 1 GENERAL

##### 1.01 SCOPE OF WORK

- A. Furnish all labor, materials, tools, supervision, transportation, and installation equipment necessary for the construction of the Compacted Clay Liner (CCL), as specified herein, as shown on the Construction Drawings, and in accordance with the Construction Quality Assurance (CQA) Plan.
- B. Contractor shall construct the CCL to the elevations, lines, grades, and dimensions as shown on the Plans and described in the Specifications, unless otherwise directed by the Engineer.
- C. Process, moisture condition, and transport clay from stockpiled low permeability clay source.
- D. Construct the CCL in conjunction with the installation and construction of the other components of the liner system.
- E. Contractor shall use clay from the approved Pecten claystone borrow source shown on the Construction Drawings. Alternate clay sources which meet the requirements of this Section may be used if approved by the Owner and Engineer, the Regional Water Quality Control Board (RWQCB), and the Department of Toxic Substances Control (DTSC).
- F. The clay borrow source may contain some gypsum debris. The Contractor shall remove large and easily recognizable pieces of gypsum and debris. Gypsum and debris must be removed prior to clay placement. Removal is considered part of the cost of clay placement.

##### 1.02 RELATED SECTIONS

- A. Section 01300 – Submittals.
- B. Section 01402 – Control of the Work.
- C. Section 02200 – Earthwork.
- D. Section 02751 – HDPE Geomembranes.

##### 1.03 REFERENCES

- A. ASTM D422 - Standard Test Method for Particle Size Analysis of Soils.
- B. ASTM D854 - Standard Test Methods for Specific Gravity of Soils.

- C. ASTM D1140 - Standard Test Methods for Amount of Material in Soils Finer than the No. 200 Sieve.
- D. ASTM D1556 - Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method.
- E. ASTM D1557 - Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort.
- F. ASTM D1587 - Standard Practice for Thin-Walled Tube Geotechnical Sampling of Soils.
- G. ASTM D2216 - Standard Test Method for Laboratory Determination of Water (Moisture) Content of Soil, Rock, and Soil-Aggregate Mixtures.
- H. ASTM D2487 - Standard Test Method for Classification of Soils for Engineering Purposes (Unified Soil Classification System).
- I. ASTM D4318 - Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.
- J. ASTM D5084 - Standard Test Methods for Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter.
- K. ASTM D6938 - Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth).

#### **1.04 REGULATORY REQUIREMENTS**

Permits: Contractor shall obtain and comply with the appropriate local, state, and federal permits and licenses required for all Work performed on the site.

#### **1.05 QUALITY ASSURANCE**

- A. Construction Quality Assurance (CQA) monitoring shall be the responsibility of the Owner or Owner's Representative in accordance with the approved CQA Plan.
- B. Quality control testing associated with filling and compaction operations shall be performed by the Owner or Owner's Representative in compliance with the CQA Plan and this Specification. The Contractor shall assist the Owner or Owner's Representative in obtaining clay samples at the frequencies provided in the CQA Plan.
- C. Contractor shall give advance notice of at least 24 hours to the Owner or Owner's Representative when ready for compaction or subgrade testing and inspection.
- D. Contractor shall give advance notice of at least 24 hours to the Owner or Owner's Representative prior to commencement of proof rolling.

#### **1.06 TOLERANCES**

- A. The final surface of the finished clay liner shall be within +0.0 feet to +0.2 feet of the design thickness. The Contractor shall not be reimbursed for material that exceeds +0.2 feet.

## **PART 2 PRODUCTS**

### **2.01 CLAY**

- A. The clay liner material shall be obtained from the Pecten Claystone borrow source as shown on the Construction Drawings. Based on field permeability testing completed by Geosyntec in 2008, the Pecten Claystone, when processed, has a field permeability of less than  $1 \times 10^{-7}$  cm/sec.
- B. Clay liner material shall:
  - 1. Be clean soil free of debris, rocks, any particles greater than 1 inch in maximum dimension, and other deleterious material.
  - 2. Be classified as CH, CL, ML, SM, or SC in accordance with ASTM D2487.
  - 3. Have a minimum of 30 percent passing the #200 sieve.
- C. The in-situ Pecten Claystone may not meet the requirements of this Specification for moisture content. Processing of this material shall be required prior to its placement. At a minimum, the Contractor shall process and moisture condition the clay in accordance with the "Test Fill and Infiltrometer Test Results" report for the Phases I and II clay liner (Environmental Solutions, Inc.; 1992). The Contractor may elect to use alternative processing and moisture conditioning methods. Alternative methods may require a test pad and field permeability test (i.e., Sealed Double-Ring Infiltrometer) to demonstrate that this Specification is met as well as to evaluate the appropriate compaction specification and associated correction factor.
- D. If another clay source (other than the Pecten Claystone) is required to complete the work, that alternative clay source shall be approved by the Owner, Engineer, RWQCB, and DTSC. In order to obtain said approval, clay material obtained from the alternative source shall be laboratory and field tested to demonstrate that the clay meets the requirements in items 2.01 A and B of this Section. It should be noted that the field permeability test requires a minimum of 8 weeks to complete.

### **2.02 EQUIPMENT**

- A. Provide equipment to transport clay from borrow source to project site.
- B. Provide heavy compaction equipment sufficient to obtain the densities specified. Equipment shall be similar to that used for the Phases I and II clay liner test pad construction (reference Environmental Solutions, Inc. 1992 report).
- C. Locations inaccessible to heavy equipment shall be compacted by means of manually controlled pneumatic or vibrating tampers or by Owner-approved equivalent methods to achieve specified densities.

- D. Operate compaction equipment in strict accordance with the manufacturer's instructions and recommendations. If inadequate densities are obtained, provide larger and/or different types of additional equipment at no cost to the Owner.
- E. Provide water application equipment free of leaks and equipped with a distributor bar or other accepted device to ensure uniform application.
- F. Provide processing equipment suitable for providing a material that has uniform moisture content.

### **PART 3 EXECUTION**

#### **3.01 GENERAL**

The Contractor shall:

- A. Excavate, process for size and moisture content, and stockpile clay from the approved borrow source.
- B. Transport processed and moisture conditioned clay from stockpile to the project area.
- C. Verify that the survey control system is installed and properly protected from construction operations prior to all earthwork, including clay placement.
- D. Placement of successive clay layers shall not begin until the Owner or CQA Consultant has accepted the previous layer. Any damage to the previous layer or deterioration subsequent to acceptance shall be repaired by the Contractor to the satisfaction of the Owner or CQA Consultant at the expense of the Contractor.
- E. Fill and compact all holes and other depressions prior to placement of clay.
- F. Fill areas to contours and elevations shown on the Drawings.
- G. Maintain surface of clay at the minimum grades for drainage shown on the Drawings.
- H. Place and compact clay in continuous layers not exceeding 6 inches in compacted thickness. The CONTRACTOR shall implement a systematic method to ensure lift thickness is in compliance with this Specification. Preferred systems include laser levels and global positioning system (GPS). If lath stakes are utilized in the control of grades / thickness then the CONTRACTOR shall ensure recovery of all stakes by implementing a control numbering system. Grade control systems shall be approved by the CQA CONSULTANT.
- I. Material incorporated into clay, determined by the OWNER or CQA CONSULTANT to be in violation of Specification requirements, shall be removed by the CONTRACTOR at the CONTRACTOR's expense.
- J. Protect stockpiles so that stockpiled material remains in a condition suitable for use on the project.

- K. Transport borrow materials over land or roads designated by the OWNER or CQA CONSULTANT. Perform perimeter/access road maintenance including dust control by sprinkling with water as needed or by other suitable means accepted by the Owner or CQA CONSULTANT. Additionally, road maintenance shall include periodic grading, as necessary, to remove ruts and to maintain construction access roads in a safe and sound condition.
- L. Obey all applicable laws where borrow materials are transported along public roads, including but not limited to, laws relating to vehicle speed, vehicle weight, and covering of loads.

### 3.02 COMPACTED CLAY LINER

- A. Work associated with construction of the CCL includes: processing and moisture conditioning clay from borrow sources, any supplementary processing and moisture conditioning of clay at the area of placement to achieve the required moisture content and texture, spreading and compaction of clay layers, and protection of the completed work. The work also includes supplying of all labor and equipment necessary to achieve the construction in accordance with the Drawings and Specifications or as directed by the OWNER or CQA CONSULTANT.
- B. The CONTRACTOR shall be responsible for verification that material that does not meet the Specifications is removed from the clay prior to placement.
- C. The clay material shall be compacted to a dry density and moisture content that lies within the compaction window bounded by the following 4 points on a moisture content-dry density plot (where optimum moisture and maximum dry density are obtained using the ASTM D1557 test method):
  - a. 2 percent above the optimum moisture content for a relative compaction of 90 percent.
  - b. 5 percent above the optimum moisture content for a relative compaction of 90 percent.
  - c. 3 percent above the optimum moisture content for a relative compaction of 97 percent.
  - d. 1 percent above the optimum moisture content for a relative compaction of 98 percent.

Up to 20 percent of the moisture content-dry density compaction tests per equipment spread per day are allowed to lie slightly outside of the compaction window defined above if the following conditions are met:

- a. The moisture content is within  $\pm 0.5$  percent of the specified compaction window.
- b. The relative compaction is within  $-0.5$  percent of the specified compaction window.

- c. The average for all acceptable tests per equipment spread per day falls within the compaction window described above.

Moisture content and dry density shall be used as an indicator, but the primary requirement for the clay liner is a maximum permeability of  $1 \times 10^{-7}$  cm/sec.

- D. Changes to the above compaction specification shall require approval of the Owner, Engineer, CQA Consultant, RWQCB, and DTSC. Modifications will likely require demonstration through a test pad and field permeability test that the modified procedures are acceptable.
- E. Clay shall be compacted with a Caterpillar 825 Sheepsfoot Compactor or Rex 3-35 Pad Foot Compactor (or heavier equipment) with a minimum of four complete passes.
- F. CONTRACTOR shall take adequate measurements to prevent moisture loss from and desiccation of the CCL.
- G. CONTRACTOR shall scarify the top of each lift and confirm the moisture content is acceptable prior to placement of the overlying lift.
- H. Clay shall not be placed and compacted if the ambient air temperature drops below 32°F.
- I. CONTRACTOR shall seal the last and uppermost layer of CCL, after achieving the compaction and permeability requirements, with two passes of a single drum smooth roller. The final lift shall be suitable for placement of the geomembrane liner (Section 02751).
- J. Where test results indicate that the lift thickness, maximum particle size, in-place density/moisture content, and/or permeability of any portion of the clay does not meet the specified requirements, that particular portion shall be re-tested by the OWNER or CQA CONSULTANT and/or re-worked or replaced by the CONTRACTOR at his expense until the required condition has been attained and the resulting product meets or exceeds the Specification requirements. No additional fill shall be placed over an area until the existing fill has been tested horizontally and vertically and determined by the OWNER or CQA CONSULTANT to meet the requirements of this Specification.
- K. Upon placement, if test results indicate densities or moisture contents outside the specified compaction window, then two additional field density/moisture content tests shall be conducted in the immediate area. If either of these tests fail to meet the compaction requirements, the area shall be considered inadequate and shall be reworked by the CONTRACTOR. Any reworked areas shall be re-tested by the OWNER or CQA CONSULTANT to assure the reworked area meets the density and moisture content requirements.
- L. If the laboratory permeability value exceeds  $1.0 \times 10^{-7}$  cm/sec, then two (2) additional tests of the same type shall be taken by the OWNER or CQA CONSULTANT in the immediate vicinity. If either of the additional tests fails to meet the minimum requirements, the area represented by the test shall be considered inadequate and shall be removed or reprocessed and recompacted by the CONTRACTOR at his expense.

- M. If at any time the OWNER or CQA CONSULTANT observes an uncompacted lift thickness in excess of eight inches or observes materials being placed without the required mixing, processing, or stockpiling, the CONTRACTOR shall immediately discontinue placing additional fills in that area. For an over-thick lift, the CONTRACTOR shall immediately blade the surface to reduce the lift to an acceptable thickness at his expense.
- N. Prior to placement of the geomembrane liner, all clay surfaces shall be observed for any particles greater than 1 inch in size, and oversize materials shall be removed. The final surface shall be rolled smooth to remove protrusions of ½ inch or greater, to the satisfaction of the CQA Consultant and the Geosynthetics CONTRACTOR.

**END OF SECTION**

[ THIS PAGE WAS INTENTIONALLY LEFT BLANK ]



## SECTION 02228

### OPERATIONS LAYER

#### PART 1: GENERAL

##### 1.01 DESCRIPTION

- A. This section describes the requirements for placement of operations layer material associated with the performance of the Work.

##### 1.02 SUBMITTALS

- A. An earthwork operations plan and schedule shall be submitted to the Owner.

##### 1.03 QUALITY ASSURANCE

- A. The Contractor shall make allowances for sampling and testing by the CQA Engineer in both his production operations and schedule.

##### 1.04 TOLERANCES

- A. The final surface of the finished operations layer shall be within +0.0 feet to +0.2 feet of the design thickness. The Contractor shall not be reimbursed for material that exceeds +0.2 feet.

#### PART 2: PRODUCTS

##### 2.01 OPERATIONS LAYER MATERIAL

- A. Materials shall consist of on-site soil materials meeting the requirements for Structural Fill in Section 02200 of these Specifications with the additional particle size requirements in Articles 2.01.B and 2.01.C below.
- B. The maximum particle size for the operations layer material shall be as follows:
- Material to be placed on or within 0.5-feet of the geosynthetic liner: 1-inch in largest dimension;
  - Material to be placed at a distance greater than 0.5 feet of geosynthetic liner: 2-inches in largest dimension.
- C. Material shall form a firm and stable base when placed.

**PART 3: EXECUTION**

**3.01 PLACEMENT OF OPERATIONS LAYER**

- A. Operations layer shall be placed over the geocomposite across the base area to the extent and thicknesses shown on the drawings. On the sideslopes, operations layer shall be placed up the slopes a maximum of 10 vertical feet ahead of the rising waste mass. The final elevation of the operations layer shall be approximately 2 feet above the permitted waste level.
- B. Prior to placement of operations layer material, final inspection of the geocomposite by the CQA Engineer will be made to verify integrity.
- C. Hauling and placing equipment shall operate on a minimum of 3 feet of material over any geosynthetic layer. Equipment with maximum ground pressure of 6 psi may operate on a minimum of 1 foot of material.
- D. The Contractor shall take steps to minimize wrinkle generation in the geosynthetic materials during placement of the operations layer. These measures may include placing material in the early morning hours when the geosynthetic materials are cool and monitoring and walking out wrinkles in the geosynthetic materials that appear at the face of the placement operation. Wrinkles which may fold and or crease shall be removed and repaired in accordance with the specifications.
- E. There is no compaction requirement for operations layer placement.

**END OF SECTION**

## SECTION 02725

### HDPE PIPE

#### PART 1 GENERAL

##### 1.01 DESCRIPTION

- A. This section describes the requirements for the manufacture, supply, installation, and quality control (QC) of high density polyethylene (HDPE) pipes, fittings and connections.

##### 1.02 SUBMITTALS

- A. Prior to the delivery of any HDPE pipe to the site, Earthwork CONTRACTOR shall submit to ENGINEER for review and approval complete, detailed shop drawings of all HDPE pipe and fittings, a list of materials to be furnished, the name of the pipe manufacturer, and the manufacturer's recommendations for handling, storage, and installation.
- B. Earthwork CONTRACTOR shall also submit the pipe manufacturer's certification of compliance with the Specifications, including certification that stress regression testing has been performed in accordance with ASTM D2837, for all HDPE pipe materials delivered to the site.
- C. In addition to the certification cited above, Earthwork CONTRACTOR shall submit in writing the following documentation of the pipe manufacturer on the raw materials used to manufacture the pipe and fittings:
1. certificate of compliance stating the specific resin, its source, and the information required by ASTM D3350; if in-plant blending of the resin is performed, the pipe manufacturer shall provide a certificate of compliance stating that the blended resin meets the requirements of ASTM D3350; and
  2. certificate of compliance stating that no recycled resin was used in manufacturing the pipe except for a small percentage (i.e., less than 10 percent) of resin generated in the pipe manufacturer's own plant from production using the same resin as the recycled material.

##### 1.03 REFERENCES

- A. The American Society for Testing and Materials (ASTM), latest editions:
1. ASTM D1603 – Standard Test Method for Carbon Black in Olefin Plastics
  2. ASTM D1693 – Standard Test Method for Environmental Stress-Cracking of Ethylene Plastics
  3. ASTM D2657 – Standard Practice for Heat-Joining for Polyolefin Pie and Fittings
  4. ASTM D2837 – Test Method for Obtaining Hydrostatic Design Basis for Thermoplastic Pipe Materials

5. ASTM D3350 – Standard Specification for Polyethylene Plastics Pipe and Fittings Materials
6. ASTM F714 – Standard Specification for Polyethylene (PE) Plastics Pipe (SDR-PR) Based on Outside Diameter

#### **1.04 RELATED SECTIONS**

- A. Section 02200 - Earthwork

### **PART 2 PRODUCTS**

#### **2.01 MATERIALS**

- A. HDPE pipe shall be of the diameter and SDR rating (per ASTM F714) as indicated on the plans.
- B. The HDPE pipe and fittings shall be manufactured from new, high molecular weight, high density polyethylene (HDPE) resin conforming to ASTM D3350 (Type III, Class C Category 5, Grade P 64), pipe cell classification PE 345464C according to ASTM D3350, and having a Plastic Pipe Institute (PPI) Rating of PE 3408. The resin shall be pre-compounded. In plant blending of non-compounded resins shall be permitted if the manufacturer provides a certificate of compliance that the blended resin conforms to the requirements of the Specifications. Pipe and fittings shall be manufactured from the same resin and by the same manufacturer.
- C. The polyethylene compound shall contain a minimum of 2 percent carbon black (per ASTM D1603) to withstand outdoor exposure without loss of properties.
- D. The polyethylene compound shall have a minimum resistance of 5,000 hours when tested for environmental stress crack in accordance with requirements of ASTM D1693.

#### **2.02 HDPE PIPE AND PIPE FITTINGS**

- A. Earthwork CONTRACTOR shall provide HDPE pipe having the nominal diameters specified herein and shown on the Drawings.
- B. HDPE pipe and fittings shall have a minimum hydrostatic design basis (HDB) of 1,600 pounds per square inch (psi) when determined in accordance with ASTM D2837 unless otherwise indicated herein or on the Drawings.
- C. HDPE pipe shall be supplied in standard laying lengths not exceeding 50 feet.
- D. HDPE pipes and fittings shall be homogeneous throughout and free of visible cracks, holes, (i.e., other than intentional manufactured perforations), foreign inclusions, or other deleterious effects, and shall be uniform in color, density, melt index, and other physical properties.
- E. Fittings at each end of pipes shall consist of HDPE end caps unless indicated otherwise herein or on the Drawings.

## 2.03 LABELING

- A. The following shall be continuously indent-printed on the HDPE pipe, or spaced at intervals not exceeding 5 feet:
1. name and/or trademark of the pipe manufacturer;
  2. nominal pipe size;
  3. pipe stiffness;
  4. the letters PE followed by the polyethylene grade per ASTM D3350, and by the Hydrostatic Design Basis in 100's of psi (e.g., PE 3408);
  5. test method references (e.g., ASTM D2412); and
  6. a production code from which the date and place of manufacture can be determined.

## PART 3 EXECUTION

### 3.01 GENERAL

- A. Transportation of HDPE pipe and fittings shall be the responsibility of Earthwork CONTRACTOR. Earthwork CONTRACTOR shall be liable for all damage incurred prior to and during transportation to the site.
- B. Handling, storage, and care of the HDPE pipe and fittings prior to and following installation at the site is the responsibility of Earthwork CONTRACTOR. Earthwork CONTRACTOR shall be liable for all damage to the material incurred prior to final acceptance of the project by OWNER.
- C. Earthwork CONTRACTOR shall be responsible for storage of HDPE pipe and fittings at the site. Pipe and fittings shall be stored on clean level ground, preferable turf or sand, free of sharp objects which could damage the pipe. Stacking shall be limited to a height that will not cause excessive deformation of the bottom layers of pipe under anticipated temperature conditions. Where necessary, due to ground conditions, the pipe shall be stored on wooden sleepers, spaced suitable and of such width as not to allow deformation of the pipe at the point of contact with the sleeper or between supports. The pipe shall be stored out of direct sunlight (i.e., to minimize pipe bowing). Earthwork CONTRACTOR shall also comply with the pipe manufacturer's recommendations for handling, storage, and installation of HDPE pipe and fittings.
- D. Earthwork CONTRACTOR shall exercise care when transporting, handling and placing HDPE pipe and fittings such that they will not be cut, kinked, twisted, or otherwise damaged. Ropes, fabric, or rubber-protected slings and straps shall be used when handling pipe. Slings, straps, etc., shall not be positioned at butt-fused joints. Chains, cables or hooks shall not be inserted into the pipe ends as a means of handling pipe. Pipe or fittings shall not be dropped onto rocky or unprepared ground. Under no circumstances shall pipe or fittings be dropped into trenches, or dragged over sharp objects.
- E. Earthwork CONTRACTOR shall carefully examine all pipe and fittings for cracks, damage, or defects before installation. Defective or damaged materials shall be immediately removed from the site and replaced at no additional cost to OWNER.
- F. The maximum allowable depth of cuts, gouges or scratches on the exterior surface of pipe or fittings is 10 percent of the wall thickness. The interior of the pipe and fittings shall be

free of cuts, gouges and scratches. CQA CONSULTANT will inspect all pipes. Sections of pipe with excessive cuts, gouges or scratches will be rejected and Earthwork CONTRACTOR shall be required to remove and replace the rejected pipe, at no additional cost to OWNER.

- G. Whenever pipe laying is not actively in progress, the open end of pipe that has been placed shall be closed using a watertight cap.
- H. The interior of all pipe and fittings shall be inspected and any foreign material shall be completely removed from the pipe interior before it is moved into final position.
- I. Field-cutting of pipes, when required, shall be made with a machine specifically designed for cutting pipe. Cuts shall be carefully made, without damage to pipe or lining, so as to leave a smooth end at right angles to the axis of pipe. Cutter ends shall be tapered and sharp edges filed off smooth. Flame cutting will not be allowed.
- J. No pipe shall be laid until CQA CONSULTANT has observed the condition of the pipe.
- K. No pipe shall be brought into position until the preceding length has been bedded and secured in its final position.
- L. Blocking under piping shall not be permitted unless specifically accepted by PROJECT MANAGER for special conditions or as indicated on the Drawings.
- M. Pipe will be inspected in the field before and after placement in the trench. If upon inspection, pipe is found not to be in compliance with the Specifications, it shall be subject to rejection. Any corrective work shall be approved by CQA CONSULTANT. The costs for the corrective work shall be at Earthwork CONTRACTOR's sole expense. Pipe shall be laid to the line and grade shown on the Drawings, with uniform bearing under the full length of the barrel of the pipe. Any pipe which is not in true alignment or shows any undue settlement after laying shall be taken up and relaid at Earthwork CONTRACTOR's sole expense. The joining of the pipe shall be in accordance with the manufacturer's written instructions and the Specifications, as approved by PROJECT MANAGER.
- N. All placed pipes shall be surveyed along the top of the pipe to complete the record drawings prior to backfilling. All start points, angle joints, junctions, connections, and end points of the pipe shall be surveyed. All survey work shall conform to the quality and practice required by CQA CONSULTANT, specified herein, and in the CQA Plan.
- O. Both during the construction period and immediately prior to acceptance of the construction work by OWNER, Earthwork CONTRACTOR shall keep the pipe free-draining and free of rocks, soil, and debris.
- P. Earthwork CONTRACTOR shall provide all necessary adapters and/or pipe connection pieces required when connecting different types and sizes of pipe or when connecting pipe made by different manufacturers. Earthwork CONTRACTOR shall weld flanges to existing Stainless Steel pipes in Phase II for connection of new HDPE pipe.

- Q. HDPE pipe shall be jointed with butt fusion joints or eletro-fusion couplers. All joints shall be made in strict compliance with the pipe manufacturer's recommendations and ASTM D2657. Use of adhesives or solvents in the joints will not be allowed.
  
- R. Testing of the HDPE pipe after backfilling and compaction shall be required. Testing shall be performed by Earthwork CONTRACTOR and shall include pulling a test mandrel through the pipe, as specified in Section 306-1.2.12 of the SSPWC. This test will be used to ensure that the pipe has not been excessively deformed, crushed, or blocked during backfilling. Alternative test procedures will require approval by PROJECT MANAGER. Any corrections required due to test failure as evaluated by CQA CONSULTANT, shall be at Earthwork CONTRACTOR's sole expense.

**END OF SECTION**

## SECTION 02751

### HDPE GEOMEMBRANES

#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. This Section describes the requirements for the manufacture, supply, installation, and quality assurance/quality control (QA/QC) of high density polyethylene (HDPE) geomembranes associated with the construction of Phase III of Landfill Unit B-18 at the Kettleman Hills Facility.
- B. The following two types of HDPE geomembranes shall be used for the Project:
  - 1. 60-mil double-sided textured HDPE geomembrane shall be used for the primary and secondary geomembranes in the Phase III composite sideslope base liner system.
  - 2. 40-mil smooth HDPE geomembrane for the protective cover shall be used for:
    - i. White protective liner for the Phase III composite sideslope liner system.
    - ii. The liner for the South Stormwater Containment Basin.

##### 1.02 RELATED SECTIONS

- A. Section 1300 - Submittals.
- B. Section 02200 - Earthworks.
- C. Section 02752 - Geotextiles.
- D. Section 02774 - Geocomposite.

##### 1.03 REFERENCES

- A. "Construction Quality Assurance (CQA) Plan for Landfill Unit B-18, Phase III Construction, Kettleman Hills Facility, Kettleman City, California," prepared by Golder Associates Inc., Revision 1, dated February 2010.
- B. Latest version of the following American Society for Testing and Materials (ASTM) standards:
  - 1. ASTM D792 - Specific Gravity (Relative Density) and Density of Plastics by Displacement.
  - 2. ASTM D1004 - Test Method for Initial Tear Resistance of Plastic Film and Sheeting.



3. ASTM D1238 - Test Method for Melt Flow Rates of Thermoplastics by Extrusion Plastometer.
  4. ASTM D1505 - Test Method for Density of Plastics by the Density-Gradient Technique.
  5. ASTM D1603 - Test Method for Carbon Black in Olefin Plastics.
  6. ASTM D3895 - Test Method for Oxidative Induction Time of Polyolefins by Thermal Analysis.
  7. ASTM D4218 - Test Method for Determination of Carbon Black Content in Polyethylene Compounds by the Muffle-Furnace Technique.
  8. ASTM D4833 - Test Method for Index Puncture Resistance of Geotextiles, Geomembranes and Related Products.
  9. ASTM D5199 - Test Method for Measuring Nominal Thickness of Geotextiles and Geomembranes.
  10. ASTM D5321 - Test Method for Determining the Coefficient of Soil and Geosynthetic or Geosynthetic and Geosynthetic Friction by the Direct Shear Method.
  11. ASTM D5397 - Procedure to Perform a Single Point Notched Constant Tensile Load – (SP-NCTL) Test: Appendix.
  12. ASTM D5596 - Test Method for Microscopic Evaluation of the Dispersion of Carbon Black in Polyolefin Geosynthetics.
  13. ASTM D5721 - Practice for Air-Oven Aging of Polyolefin Geomembranes.
  14. ASTM D5885 - Test Method of Oxidative Induction Time of Polyolefin Geosynthetics by High Pressure Differential Scanning Calorimetry.
  15. ASTM D5994 - Test Method for Measuring the Core Thickness of Textured Geomembranes.
  16. ASTM D6693 - Test Method for Determining Tensile Properties of Nonreinforced Polyethylene and Nonreinforced Flexible Polypropylene Geomembranes.
  17. ASTM D7238 - Test Method for Effect of Exposure of Unreinforced Polyolefin Geomembrane Using Fluorescent UV Condensation Apparatus.
  18. ASTM D7466 - Test Method for Measuring the Asperity Height of Textured Geomembranes.
- C. Latest version of the following Geosynthetic Research Institute (GRI) standards:
1. GM10 - The Stress Crack Resistance of HDPE Geomembrane Sheet.
  2. GM13 - Test Methods, Test Properties and Testing Frequency for High Density Polyethylene (HDPE) Smooth and Textured Geomembranes.

#### **1.04 PRE-QUALIFICATION**

- A. The Geosynthetic CONTRACTOR shall pre-qualify for geomembrane installation by providing the following documentation:

1. The Geosynthetic CONTRACTOR shall have a minimum of 10,000,000 square feet (sf) of polyethylene geomembrane cumulative installation experience.
2. The Geosynthetic CONTRACTOR shall provide at least three references from prior geomembrane installation projects in excess of 500,000 sf including the following information:
  - a. Client's name, address, phone number, and contact/representative's name.
  - b. Project site name, location, and description.
  - c. Geomembrane type and quantity installed.

#### 1.05 SUBMITTALS

- A. Submittals shall be provided in general accordance with Section 01300.
- B. HDPE Resin: Furnish the following in writing to the CQA CONSULTANT a minimum of 7 calendar days prior to geomembrane shipment to the site:
  1. Statement of production dates and origin of resin used to manufacture the geomembrane for the Project.
  2. Certification stating all resin is from the same Manufacturer and that no reclaimed polymer was added to the resin during the manufacturing of the geomembrane and that recycled polymer does not exceed 2 percent by weight.
  3. Copies of the quality control certificates issued by the Manufacturer and resin supplier indicating that the resin used to manufacture the geomembrane meets the requirements of these Specifications. These certifications shall contain manufacturing quality control test results, including specific gravity (ASTM D792 or D1505) and melt index (ASTM D1238, Condition E).
- C. Manufacturing Quality Control: A copy of the Manufacturer's quality control program shall be submitted to the CQA CONSULTANT a minimum of 7 calendar days prior to geomembrane shipment to the site. Quality control testing shall be performed by the Manufacturer in accordance with GRI-GM13 and as approved by the CQA CONSULTANT. Prior to delivery, the following shall be submitted to the CQA CONSULTANT for review:
  1. Certificates for each shift's production of geomembrane.
  2. Copies of quality control certificates issued by the Manufacturer. The quality control certificates shall include:
    - a. Roll numbers, lot numbers, and identification;
    - b. Sampling procedures; and
    - c. Results of quality control tests, including descriptions of the test methods used.
  3. The results of the manufacturing quality control tests shall meet or exceed the property values listed in Table 02751-1.

4. Geomembrane delivery, storage, handling, and installation instructions.
  5. Extrudate Beads and/or Rod:
    - a. Statement of production dates.
    - b. Certification stating all extrudate is from one Manufacturer, is the same resin type, and was obtained from the same resin supplier as the resin used to manufacture the geomembrane rolls.
    - c. Copies of quality control certificates issued by the Manufacturer including test results for specific gravity (ASTM D792 or D1505) and melt index (ASTM D1238, Condition E).
- D. Geomembrane Installer: Prior to mobilization of the Geosynthetic CONTRACTOR to the site, the following information shall be submitted:
1. Shop drawings indicating panel layout and field seams at least 14 calendar days prior to installation of geomembrane.
  2. Installation schedule.
  3. Copy of Geosynthetic CONTRACTOR's letter of approval or license by the geomembrane Manufacturer.
  4. Installation capabilities, including:
    - a. Information on equipment proposed for the Project;
    - b. Average daily production anticipated for the Project; and
    - c. Quality control procedures.
  5. Copy of the geomembrane Manufacturer's quality control/quality assurance program.
  6. Resume of the Field Superintendent to be assigned to the Project, including dates and duration of employment.
  7. Resumes of all personnel who will perform seaming operations on the Project, including dates and duration of employment.
  8. The geomembrane installation crew shall have the following experience:
    - a. The Field Superintendent shall have supervised the installation of a minimum of 2,000,000 sf of polyethylene geomembrane.
    - b. The Master Seamer shall have seamed a minimum of 1,000,000 sf of polyethylene geomembrane using the same type of seaming apparatus to be used for the Project.
    - c. All other seaming personnel shall have seamed at least 100,000 sf of polyethylene geomembrane using the same type of seaming apparatus to be used for the Project. Personnel who have seamed less than 100,000 sf of polyethylene geomembrane shall be allowed to seam only under the direct supervision of the Master Seamer or Field Superintendent.

- E. During the installation, the Geosynthetic CONTRACTOR shall be responsible for the timely submission to the CQA CONSULTANT of subgrade acceptance certificates, signed by the Geosynthetic CONTRACTOR, for each area to be covered by geomembrane.
- F. The Geosynthetic CONTRACTOR shall furnish the OWNER upon completion of the Project:
  - 1. A warranty provided by the Manufacturer against defects in material. Warranty conditions concerning limits of liability shall be evaluated and must be acceptable to the OWNER.
  - 2. A 1-year warranty provided by the Geosynthetic CONTRACTOR against defects in workmanship. Warranty conditions concerning limits of liability shall be evaluated and must be acceptable to the OWNER.
  - 3. As-built panel drawings in compliance with Section 01052.
- G. Certificate of calibration less than 12 months old shall be submitted prior to installation for all field tensiometers to be used for the Project.

## **1.06 QUALITY ASSURANCE**

- A. Perform work in accordance with Section 01400, Section 01410, the Geosynthetic CONTRACTOR'S Quality Control Program, and the Project's CQA Plan.

## **PART 2 PRODUCTS**

### **2.01 MATERIALS**

- A. The geomembrane shall be comprised of high density polyethylene (HDPE) material as indicated on the Drawings, manufactured of new, first-quality products designed and manufactured specifically for the purpose of liquid containment in hydraulic structures.
- B. The geomembrane shall be produced free of holes, blisters, undispersed raw materials, or any sign of contamination by foreign matter. Any such defect shall be repaired in accordance with the repair procedures in Item 3.06 of this Section.
- C. The geomembrane shall be manufactured with a minimum 15.0-foot seamless width. There shall be no factory seams.
- D. The geomembrane shall be either HDPE 60-mils thick and textured on both sides or HDPE 40-mils thick and smooth on both sides, as indicated on the Drawings. White liner shall be provided for the protective cover.
- E. The geomembrane shall be supplied in rolls. Folds shall not be permitted.
- F. Requirements for the HDPE geomembrane properties are presented in Table 02751-1..
- G. Resin:

1. Shall be HDPE, new, first-quality, compounded and manufactured specifically for producing HDPE geomembrane.
2. Do not intermix resin types.
3. Shall meet the following additional requirements:

Property	Test Method	Minimum Test Frequency	Required
Specific Gravity <sup>(1)</sup>	ASTM D792, Method B or ASTM D1505	1 per resin batch	≥ 0.932
Melt Index	ASTM D1238, Condition E	1 per resin batch	≤ 1.0 g per 10 minutes
Note: (1) Resin without carbon black			

H. Extrudate Rod or Bead:

1. Shall be made from same resin as the geomembrane.
2. Additives shall be thoroughly dispersed.
3. Shall be free of contamination by moisture or foreign matter.
4. Shall meet the following requirements:

Property	Test Method	Minimum Test Frequency	Required
Specific Gravity	ASTM D792, Method B or ASTM D1505	1 per resin batch	≥ 0.940
Carbon Black Content	ASTM D1603	1 per resin batch	2.0 - 3.0%
Melt Index	ASTM D1238, Condition E	1 per resin batch	≤ 1.0 g per 10 minutes

**2.02 DELIVERY, STORAGE, AND HANDLING**

- A. Handling, storage, and care of the geomembrane following transportation to the site shall be the responsibility of the Geosynthetic CONTRACTOR. The Geosynthetic CONTRACTOR shall be liable for all damage to the materials incurred prior to final acceptance of the liner system by the CQA CONSULTANT and OWNER.
- B. Conform to the Manufacturer's requirements to prevent damage to the geomembrane.
- C. Delivery:
  1. Deliver materials to the site only after the CQA CONSULTANT and the OWNER approve all of the required submittals.
  2. All rolls of geomembrane delivered to the site shall be identified at the factory with the following:
    - a. Manufacturer's name.

- b. Product identification and thickness.
  - c. Lot number.
  - d. Roll number.
  - e. Roll dimensions and weight.
3. Separate damaged rolls from undamaged rolls and store at locations designated by the OWNER until proper disposition of material is determined by the OWNER and CQA CONSULTANT.
  4. The OWNER shall be the final authority regarding damage.
  5. Separate rolls without proper documentation and store until CQA CONSULTANT and OWNER approval is received.
- D. On-Site Storage:
1. Store in space allocated by the OWNER.
  2. Protect from puncture, dirt, grease, water, moisture, mud, mechanical abrasions, excessive heat, and any other damage.
  3. Store on a level prepared surface (not on wooden pallets).
  4. Stack per Manufacturer's recommendations but no more than three rolls high.
- E. On-Site Handling:
1. Use appropriate handling equipment to load, move, or deploy geomembrane rolls. Appropriate handling equipment includes cloth chokers and spreader bar for loading and spreader and roll bars for deployment. Dragging panels on the ground surface shall not be permitted.
  2. Do not fold geomembrane material; folded material shall be rejected.
  3. The Geosynthetic CONTRACTOR is responsible for storage and transporting material from the storage area to the work area.
- F. Damaged Geomembrane:
1. Geomembrane damage shall be documented by the CQA CONSULTANT.
  2. Damaged geomembrane shall be repaired, if possible, in accordance with this Section or shall be replaced at no additional cost to the OWNER.

## 2.03 EQUIPMENT

- A. Welding equipment and accessories shall meet the following requirements:
1. Equipped with gauges showing temperatures both in apparatus and at nozzle (extrusion welders) or at wedge (fusion welders).
  2. Maintain adequate number of welding machines to avoid delaying the Work.
  3. Use power source(s) capable of providing constant voltage under combined-line load.

4. Provide secondary containment to catch spilled fuel under electric generators, if located on geomembrane.
- B. Provide calibrated tensiometer(s) capable of quantitatively measuring geomembrane seam strength:
1. Equipped with gauge accurate to  $\pm 2$  lbs per inch of geomembrane width and capable of pulling at 2 inches per minute and 20 inches per minute.
  2. Provide one-inch wide die for cutting test specimens.
  3. Provide a certificate of calibration for each tensiometer showing that each tensiometer has been calibrated within the past 12 months.

### **PART 3 EXECUTION**

#### **3.01 EXAMINATION**

- A. The Geosynthetic CONTRACTOR shall document in writing that the surface upon which the geomembrane will be installed is acceptable. In so doing, the Geosynthetic CONTRACTOR shall assume full liability for the accepted surface.
- B. The beginning of geomembrane installation means acceptance of existing conditions. The Geosynthetic CONTRACTOR shall be responsible for maintenance of the geomembrane-covered subgrade once installation of geomembrane begins.

#### **3.02 PREPARATION**

- A. Maintain the surface suitability and integrity until the lining installation is completed and accepted.
- B. Repair rough areas and any damage to the subgrade caused by installation of the lining and fill any ruts in subgrade caused by equipment prior to geomembrane deployment.
- C. To avoid sharp bends in the geomembrane, bevel the leading edges of the anchor trenches.
- D. Subgrade shall be smooth, uniform, firm, and free of rocks or other debris. For deployment over soil subgrade, the subgrade shall not contain any protrusions that are greater than 0.25 inches in height from the finished subgrade surface.

#### **3.03 DEPLOYMENT**

- A. Geomembrane shall not be deployed:
1. During precipitation.
  2. In the presence of excessive moisture.
  3. In areas of ponded water.
  4. In the presence of excessive winds (i.e., greater than 20 mph).
  5. In excessive heat (i.e., greater than 110° F) or cold (i.e., less than 40°F), unless the Geosynthetic CONTRACTOR is able to demonstrate (i.e., through trial

seams) to the satisfaction of the CQA CONSULTANT that acceptable welds can be made in these temperatures. See Items 3.04.O and 3.04.P of this Section for cold weather and hot weather seaming procedures, respectively.

- B. Each panel shall be marked with an "identification code" (number and/or letter) consistent with the layout plan. The identification code shall be simple and logical. The number of panels deployed in one day shall be limited by the number of panels which can be seamed on that same day. All deployed panels shall be seamed to adjacent panels by the end of each day.
  
- C. The following is the acceptable method of deployment:
  - 1. Use equipment which will not damage geomembrane by handling, trafficking, leakage of hydrocarbons, or any other means.
  - 2. Do not allow personnel working on geomembrane to wear damaging shoes or engage in activities that could damage geomembrane.
  - 3. Smoking on the geomembrane is prohibited.
  - 4. Round sharp corners of clamps and other metal tools used in the work area.
  - 5. Do not allow clamps and other metal tools to be tossed or thrown.
  - 6. Unroll panels using a method that protects geomembrane from scratches and crimps and protects the soil surface and any underlying geosynthetics from damage.
  - 7. Use a method to minimize geomembrane wrinkles, especially differential wrinkles between adjacent panels.
  - 8. Place adequate hold-downs to prevent uplift by wind.
  - 9. Use hold-downs that will not damage geomembrane (such as sandbags).
  - 10. Use continuous hold-downs along leading edges to minimize risk of wind flow under panels.
  - 11. Panels shall be deployed perpendicular to slope elevation contours and the number of seams shall be minimized.
  - 12. Protect geomembrane in heavy traffic areas by geotextile, extra geomembrane, or other suitable materials.
  - 13. Vehicular traffic shall not be allowed on the geomembrane.
  - 14. Panels deployed on grades steeper than 12% shall extend a minimum of 3 feet beyond the crest or toe of that grade.
  - 15. Shingle or overlap panels in a downward direction to facilitate drainage.
  - 16. Rub sheets used during installation shall be removed prior to placement of subsequent panels.
  
- D. Visually inspect sheet surface during unrolling of geomembrane and mark faulty or suspect areas for repair or testing. Replace faulty (requires more than one patch per 200 square feet) geomembrane stock at no additional cost to the OWNER.



### 3.04 FIELD SEAMING

- A. Orient seams perpendicular to slope elevation contours, i.e., orient down (not across) slope and use seam numbering system compatible with panel number system.
- B. Minimize the number of field seams, especially in corners, odd-shaped geometric locations, sumps, and outside corners.
- C. Overlap panels by a minimum of 3 inches for extrusion welding and 4 inches for fusion welding. Use procedures to temporarily bond adjacent panels together that do not damage the geomembrane and that are not detrimental to the material to be seamed.
- D. Do not use solvents or adhesives unless product is approved in writing by the OWNER.
- E. For the base liners, no horizontal seams shall be allowed on grades steeper than 12% or within 3 feet of the crest or toe of slopes. A horizontal seam is defined as more than half of the panel width.
- F. Clean geomembrane surface of grease, moisture, dust, dirt, debris, or other foreign material prior to welding.
- G. Prior to any extrusion welding, the geomembrane seam or repair shall be prepared as follows:
  - 1. Clean surface of oxidation by disc grinder or equivalent not more than ½ hour before seaming; use number 80 grit sandpaper for the disc grinder. Bevel edges of geomembrane before bonding and provide continuous tacking in repair areas.
  - 2. Repair area where excessive grinding substantially reduces sheet thickness by more than 4 mils beyond extent of weld.
  - 3. Clean grinding dust around weld area after grinding.
  - 4. The following procedure shall be followed for wrinkles and fishmouths:
    - a. Cut along the ridge of the wrinkle or fishmouth.
    - b. Overlap a minimum of 3 inches and weld.
    - c. Any portion where the overlap is less than 3 inches shall be patched with an oval or round patch of geomembrane that extends a minimum of 6 inches beyond the cut in all directions.
  - 5. If required, a firm, dry substrate (piece of geomembrane or other material) may be placed directly under the seam overlap to achieve proper support.
  - 6. Keep water from intercepting the weld during and immediately after welding the seam.
  - 7. For existing welds, or welds that are over 3 minutes old, grind the existing weld two inches back from point of termination and restart welding on ground weld.

- H. At least one spare operable seaming apparatus shall be maintained for every three seaming teams. Place protective fabric or piece of geomembrane beneath hot welding apparatus when resting on geomembrane lining and use an electric generator capable of providing constant voltage under combined line load. The electric generator shall generally be located outside of the lined area. Provide protective lining and secondary containment large enough to catch spilled fuel under electric generators when located on the geomembrane. The welding apparatus shall be equipped with gauges giving temperatures in apparatus and at nozzle/wedge.
- 1. For extrusion welding, purge welding apparatus of heat-degraded extrudate before welding if extruder is stopped for longer than two minutes. All purged extrudate shall be disposed of off the geomembrane. Each extruder shoe shall be inspected daily for wear to assure that its offset is the same as the geomembrane thickness. Repair or replace worn shoes, damaged or misaligned armature brushes, nozzle contamination, or other worn or damaged parts. Avoid stop-start welding. Remove extrudate rod from welder when not using welder for long periods (over two hours). No welding may commence on the liner until the field trial seam sample made by that equipment and seamer passes destructive testing.
- J. Test and set "hot air system" using scrap material at least each day prior to commencing seaming and adjust hot air velocity to preclude wind effects. Adjust contact pressure rollers to prevent surface ripples in sheet. No equipment shall be used for welding the geomembrane until a field trial seam sample made by that equipment and seamer has passed destructive testing.
- K. In performing hot wedge welding, the welding machines shall be dual-tracked automated vehicular mounted devices equipped with gauges giving applicable temperatures and pressures. The edge of cross seams shall be ground to a smooth incline (top and bottom) prior to welding. A smooth insulating plate or fabric shall be placed beneath the hot welding apparatus after usage. Protect against moisture buildup between sheets. If welding across cross seams, conduct field trial seams at least every two hours.
- L. Field trial seams shall be performed, per seaming apparatus and per seamer, on pieces of geomembrane to verify adequate seaming conditions at the following frequency:
  - 1. At the beginning of each seaming period.
  - 2. At least once every five hours.
  - 3. At the discretion of the CQA CONSULTANT.
- M. Make the trial seams at the work area and in contact with the soil subgrade or the geosynthetic component that the geomembrane will be deployed over (i.e., the same condition as the geomembrane to be seamed). The trial seam sample shall be at least 42-inches long and 12-inches wide with the seam centered lengthwise. A one-foot length of each trial seam sample shall be submitted to the CQA CONSULTANT for archive. Cut 1-inch wide specimens and test at least three for peel adhesion and two for bonded seam strength (shear). Specimens that will be subjected to peel and shear tests shall be selected alternately from the trial weld sample. Each double wedge welded seam specimen shall be tested for peel on both sides of the weld. A specimen passes when:

1. The break is film-tear bond (FTB), as defined in publication EPA/600/2-88/052 ("Lining of Waste Containment and Other Impoundment Facilities"), Appendix N.
  2. The break is ductile.
  3. The strength of breaks for the trial seam testing shall conform to the values listed in Table 02751-1, included at the end of this Section.
- N. A trial seam sample passes when all specimens have passing results in peel and shear tests. If a specimen fails (one of the specimens fails in either peel or shear mode), the trial seam procedure shall be repeated in its entirety. If the repeated trial seam fails, the seaming apparatus or operator may not weld until the deficiencies or conditions are corrected and two consecutive passing field trial seams are achieved.
- O. The following procedures shall be followed during cold weather conditions.
1. Geomembrane surface temperatures shall be determined by the CQA CONSULTANT at intervals of at least once per 100 feet of seam length to determine if preheating is required. For extrusion welding, preheating is required if the surface temperature of the geomembrane is below 32°F.
  2. For fusion welding, preheating may be waived by the OWNER based upon a recommendation by the CQA CONSULTANT, if the Geosynthetic CONTRACTOR demonstrates to the CQA CONSULTANT'S satisfaction that welds of equivalent quality may be obtained without preheating at the expected temperature of installation.
  3. If preheating is required, the CQA CONSULTANT shall observe all areas of geomembrane that have been preheated by a hot air device prior to seaming to ensure that they have not been overheated.
  4. Care shall be taken to confirm that the surface temperatures are not lowered below the minimum surface temperatures specified for welding due to winds or other adverse conditions. It may be necessary to provide wind protection for the seam area.
  5. All preheating devices shall receive approval by the CQA CONSULTANT prior to use.
  6. Additional destructive tests shall be taken at an interval between 250 and 500 feet of seam length, at the discretion of the CQA CONSULTANT.
  7. Sheet grinding may be performed before preheating, if applicable.
  8. Trial seaming shall be conducted under the same ambient temperature and preheating conditions as the production seams. Under cold weather conditions, new trial seams shall be conducted if the ambient temperature drops by more than 10°F from the initial trial seam test conditions. Such new trial seams shall be conducted upon completion of seams in progress during the temperature drop.
- P. The following procedures shall be followed during hot weather conditions.
1. At ambient temperatures above 110°F, no seaming of the geomembrane shall be permitted unless the Geosynthetic CONTRACTOR can demonstrate to the satisfaction of the CQA CONSULTANT that the geomembrane seam quality is not compromised. Trial seaming shall be conducted under the same ambient

temperature conditions as the production seams. At the option of the CQA CONSULTANT, additional destructive testing may be required for any suspect areas.

### 3.05 FIELD QUALITY CONTROL

A. The Geosynthetic CONTRACTOR shall designate a full-time Quality Control (QC) Technician who shall be responsible for supervising and/or conducting the field quality control program. The QC Technician shall not be replaced without written authorization by the OWNER.

#### B. Non-Destructive Seam Testing

1. The Geosynthetic CONTRACTOR shall non-destructively test field welds for continuity over their full length. The non-destructive testing shall be performed concurrently with seaming work progress, not at the completion of all seaming. Any defects located in the seam shall be repaired in accordance with Item 3.06 of this Section. The following non-destructive testing procedures shall be used to test the field seams for continuity.

- a. Vacuum box testing for extrusion welds.
- b. Air pressure testing for dual-wedge fusion seams.

#### 2. Vacuum Box Testing

a. The vacuum box testing equipment shall consist of the following:

- i. Rigid housing; transparent viewing window; a soft rubber gasket attached to the bottom of the housing; porthole or valve assembly; and a vacuum gauge.
- ii. A vacuum pump capable of applying 5 psi gage pressure of vacuum to the box.
- iii. A bucket of soapy solution and applicator.

b. The procedure for vacuum testing shall be as follows:

- i. Clean window, gasket surfaces, and check box assembly for leaks.
- ii. Energize vacuum pump and reduce tank pressure to approximately 5 psi.
- iii. Wet a strip of geomembrane seam approximately 12 inches by 30 inches (length of box) with soapy solution.
- iv. Place box over wetted area and compress.
- v. Close bleed valve and open vacuum valve.
- vi. Ensure that a leak-tight seal is created.
- vii. Examine length of weld through viewing window for presence of soap bubbles for a period of not less than 10 seconds.
- viii. If no bubbles appear after 10 seconds, close vacuum valve and open bleed valve, move box over next adjoining area with minimum three inches overlap from the previous tested area and repeat process.
- ix. Areas where soap bubbles appear shall be marked by the CQA CONSULTANT with a defect code. The Geosynthetic

CONTRACTOR shall then repair these areas in accordance with Item 3.06 of this Section and then retest the repaired area.

3. Air Pressure Testing (Dual-Wedge Fusion Seams Only)

a. The air pressure testing equipment shall consist of the following:

- i. An air pump, equipped with pressure gauge having an accuracy of 1 psi, capable of generating and sustaining a pressure of 30 psi, and mounted on a cushion to protect the geomembrane.
- ii. Rubber hose with fittings and connections.
- iii. Sharp hollow needle or other pressure feed device approved by the OWNER.

b. To perform the test:

- i. Seal both ends of the seam to be tested.
- ii. Insert a needle or other approved pressure feed device into air tunnel created by dual-wedge seaming and insert a protective cushion between air pump and underlying geomembrane.
- iii. Energize air pump to 28 to 30 psi, close valve, and sustain pressure for a minimum of 5 minutes.
- iv. If loss of air pressure in the tunnel exceeds 2 psi over 5 minutes or if this pressure does not stabilize, locate the faulty seam area and repair in accordance with Item 3.06 of this Section.
- v. Release pressure at opposite end of seam from gauge (i.e., by cutting the seam) to verify that the seam is not blocked.
- vi. Remove approved pressure feed device and seal penetration holes by extrusion welding.

C. Destructive Seam Testing

1. For destructive seam testing, the CQA CONSULTANT shall be provided with a minimum of one sample per 500 feet of seam length by each welding apparatus. The location shall be selected by the CQA CONSULTANT; the Geosynthetic CONTRACTOR shall not be informed of the destructive sample location in advance. The Geosynthetic CONTRACTOR shall visually observe, mark, and repair suspect welds before release of a section to the CQA CONSULTANT for destructive sample marking. Cut destructive samples as seaming and non-destructive testing progresses, prior to completion of geomembrane installation. The CQA CONSULTANT shall mark destructive samples with consecutive numbering, location, apparatus I.D., technician I.D., Engineer I.D., and apparatus settings and date. Record, in written form, weld and test date, time, location, seam number, ambient temperatures, machine settings, technician I.D., apparatus I.D., and pass or fail description. The Geosynthetic CONTRACTOR shall immediately repair holes in geomembrane resulting from obtaining destructive samples and shall vacuum test the resulting patches. The size of destructive samples shall be 12 inches wide by 44 inches long with the seam centered lengthwise.
2. Two 1-inch wide specimens shall be taken, one at each end of the sample, and tested by the Geosynthetic CONTRACTOR for peel and shear in the field prior

- to CQA destructive testing. If any of these specimens fail, the Geosynthetic CONTRACTOR shall track the failure immediately. The remaining sample shall be cut into three 14-inch long by 12-inch wide pieces and distributed as follows:
- a. To the CQA CONSULTANT for destructive testing.
  - b. To the CQA CONSULTANT for archive.
  - c. To the Geosynthetic CONTRACTOR for its use.
3. Ten 1-inch wide specimens shall be taken from one piece. Five specimens shall be tested for peel and five for shear in accordance with the CQA Plan. Specimens that will be subjected to peel and shear tests shall be selected alternately from the sample. Each fusion wedge welded seam specimen shall be tested for peel on both sides of the weld. A destructive sample shall be considered passing when all 10 specimens meet the following criteria:
- a. The break is FTB.
  - b. The break is ductile.
  - c. The strength of breaks for the trial seam testing shall conform to the values listed in Table 02751-1, included at the end of this Section.
4. In the event of sample failure, the procedures for failed seam tracking are:
- a. Retrace welding path a minimum of 10 feet in both directions from the failed test location and remove (at these locations) a one inch wide specimen for testing. Repeat tracking procedures until the Geosynthetic CONTRACTOR is confident of seam quality.
  - b. Obtain destructive samples from each side of the welding path and give samples to the CQA CONSULTANT for destructive testing.
  - c. Repeat process if additional tests fail.
  - d. Reconstruct seam between passing test locations to the satisfaction of the CQA CONSULTANT.
  - e. Reconstruction may be one of the following:
    - i. Cut out old seam, reposition panel and re-seam.
    - ii. Add cap strip.
  - f. Cut additional destructive samples from reconstruction at discretion of CQA CONSULTANT.
  - g. If additional destructive sample results are not acceptable, repeat process until reconstructed seam is judged satisfactory by the CQA CONSULTANT.
- D. For final seaming inspection, check the seams and surface of geomembrane for defects, holes, blisters, undispersed raw materials, or signs of contamination by foreign matter. Brush, blow, or wash geomembrane surface if dirt inhibits inspection.

The CQA CONSULTANT shall decide if cleaning of geomembrane surface and welds is needed to facilitate inspection. Distinctively mark repair areas and indicate required type of repair.

- E. At the discretion of the OWNER, the 40-mil smooth HDPE geomembrane seams may not require non-destructive or destructive testing.

### **3.06 REPAIR PROCEDURES**

- A. The geomembrane shall be inspected before and after seaming for evidence of defects, holes, blisters, undispersed raw materials, and any sign of contamination by foreign matter. The surface of the geomembrane shall be clean at the time of inspection. The geomembrane surface shall be swept or washed by the Geosynthetic CONTRACTOR if surface contamination inhibits inspection. The Geosynthetic CONTRACTOR shall ensure that an inspection of the geomembrane precedes any seaming of that section.
- B. Remove damaged geomembrane and replace with acceptable geomembrane materials if damage cannot be satisfactorily repaired.
- C. Repair, removal, and replacement shall be at the Geosynthetic CONTRACTOR'S expense.
- D. Repair any portion of the geomembrane exhibiting a flaw, or failing a destructive or non-destructive test. The Geosynthetic CONTRACTOR shall be responsible for repair of damaged or defective areas. Agreement upon the appropriate repair method shall be decided between the CQA CONSULTANT and the Geosynthetic CONTRACTOR. Procedures available include:
  - 1. Patching: Used to repair holes (over ¼-inch diameter), tears (over ¼-inch long), undispersed raw materials, and contamination by foreign matter.
  - 2. Grinding and welding: Used to repair pinholes, blemishes, and over-grinding.
  - 3. Capping: Used to repair large lengths of failed seams.
  - 4. Removing the seam and replacing with a strip of new material.
- E. In addition, the following procedures shall be observed:
  - 1. Geomembrane surfaces to be repaired shall be abraded (extrusion welds only) no more than ½ hour prior to the repair.
  - 2. All geomembrane surfaces shall be clean and dry at the time of repair.
  - 3. The repair procedures, materials, and techniques shall be approved in advance of the specific repair by the CQA CONSULTANT.
  - 4. Extend patches or caps at least 6 inches beyond the edge of the defect, i.e., be a minimum of 12 inches in diameter, and round all corners of material to be patched.
  - 5. Bevel the edge of the patch and do not cut patch with repair sheet in contact with geomembrane. Temporary bond the patch to the geomembrane with an approved method, extrusion weld the patch, and then vacuum test the repair.

**F. Repair Verification:**

1. The CQA CONSULTANT shall number and log each repair.
2. Non-destructively test each repair using methods specified in this Section.
3. Provide daily documentation of non-destructive and destructive testing to the CQA CONSULTANT. The documentation shall identify seams that initially failed testing and include any evidence that these seams were repaired and retested successfully.

**3.07 ACCEPTANCE**

A. The Geosynthetic CONTRACTOR shall retain ownership and responsibility for the geomembrane until acceptance by the OWNER.

B. Acceptance Criteria: The following shall be completed:

1. Verification of adequacy of field seams, repairs, and testing by the CQA CONSULTANT.
2. All submittals.
3. "As-built" drawings approved and final drawings submitted.
4. Construction area cleaned.
5. Final field inspection.
6. Warranty signed over to the OWNER.

C. Field Inspections: Inspect the completed work with the OWNER; defects, wrinkles, suspicious looking welds shall be noted and marked; document, correct, and arrange further field inspections until no further corrective action is necessary.



**TABLE 02751-1  
REQUIRED PHYSICAL PROPERTIES OF 40- and 60-MIL HDPE GEOMEMBRANE**

PROPERTY	METHOD	VALUE	
		60 mil Textured HDPE	40 mil Smooth HDPE
Thickness, mil	ASTM D 5994	- 57 mils minimum average - 54 mils lowest individual value for 8 out of 10 specimens - 51 mils lowest individual value for any of the 10 specimens	- 36 minimum average
Sheet Density (min. avg.)	ASTM D 792 or ASTM D 1505	0.940 g/cc	0.940
Asperity Height, mil <sup>(1)</sup>	ASTM D7466	- 10 mils minimum average - 8 of 10 readings ≥ 7 mils - lowest individual reading ≥ 5 mils	Not Applicable (N/A)
Tensile Properties (min. avg.) <sup>(2)</sup> • Tension at Yield (lb/in) • Strain at Yield (%) • Tension at Break (lb/in) • Strain at Break (%)	ASTM D6693 Type IV	126 lb/in 12% 90 lb/in 100%	84 lb/in 12% 60 lb/in 100%
Tear Resistance, lbs. (min. avg.)	ASTM D1004, Die C	42 lbs	28 lbs
Oxidative Induction Time (OIT) (min. avg.) • Standard OIT, or • High Pressure OIT	ASTM D3895 ASTM D5885	100 minutes 400 minutes	100 minutes 400 minutes
Oven Aging at 85°C (min. avg.) • Standard OIT (min. avg.), % retained after 90 days, or • High Pressure OIT (min. avg.), % retained after 90 days	ASTM D5721 ASTM D3895 ASTM D5885	55% retained after 90 days 80% retained after 90 days	55% retained after 90 days 80% retained after 90 days
UV Resistance (min. avg.) • High Pressure OIT (min. avg.), retained after 1,600 hr	GRI-GM11 ASTM D5885	50% retained after 1,600 hours	50% retained after 1,600 hours
Stress Crack Resistance (min.) <sup>(3)</sup>	ASTM D5397 (Appendix)	300 hours with no failures	300 hours with no failures
Puncture Resistance, lbs. (min. avg.)	ASTM D4833	90 lbs	60 lbs
Carbon Black Content (range)	ASTM D1603	2.0 – 3.0%	N/A
Carbon Black Dispersion	ASTM D5596	- min 9 out of 10 specimens in Cat. 1 or 2 - all in Cat. 1, 2, or 3	N/A
Seam Strength (min. avg.) • Peel (lb/in) • Shear (lb/in)	ASTM D6392	90 lb/in 120 lb/in	60 lb/in 80 lb/in

- Notes:
- (1) Alternate the measurement side for double-sided textured sheets.
  - (2) Elongation at yield and elongation at break shall be calculated using a gage length of 1.3 inches and 2.0 inches, respectively.
  - (3) Test is not applicable for textured geomembranes. Test should be performed on the smooth edges of textured rolls or on smooth rolls made from same formulation as textured rolls.

**END OF SECTION**

## **SECTION 02752**

### **GEOTEXTILES**

#### **PART 1 GENERAL**

##### **1.01 DESCRIPTION**

- A. This section describes the general requirements for the manufacture, supply, installation, and quality control (QC) of geotextiles.

##### **1.02 RELATED SECTIONS**

- A. Section 02200 – Earthwork
- B. Section 02751 – HDPE Geomembranes

##### **1.03 REFERENCES**

- A. Latest version of the following American Society for Testing and Materials (ASTM) standards:
  - 1. ASTM D4355. Standard Test Method for Deterioration of Geotextiles by Exposure to Light, Moisture and Heat in a Xenon Arc Type Apparatus.
  - 2. ASTM D4632. Standard Test Method for Breaking Load and Elongation of Geotextiles (Grab Method).
  - 3. ASTM D4833. Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products.
  - 4. ASTM D4873. Standard Guide for Identification, Storage, and Handling of Geotextiles.
  - 5. ASTM D5199. Standard Test Method for Measuring Geotextiles.
  - 6. ASTM D5261. Standard Test Method for Measuring Mass Per Unit Area of Geotextiles.

##### **1.04 SUBMITTALS**

- A. Quality Control Submittals:
  - 1. A copy of the manufacturer's quality control (QC) plan.
  - 2. Manufacturing QC certificates for each production run. The certificates shall identify the origin and the manufacturer of the resin. The certificates shall be signed by responsible parties employed by the manufacturer (such as the production manager). Tests shall be performed at the frequency indicated in the manufacturer's QC Plan.
  - 3. The QC certificates shall include roll numbers and identification, sampling procedures, and results of quality control tests verifying that each of the properties

listed in Table 02752-1 is met. Samples shall be tested at a minimum frequency of once every 100,000 sf. The manufacturer quality control tests to be performed include the tests specified in Article 2.01 of this section.

4. Manufacturer's certification that the geotextile products meet or exceed specified requirements and are 100% free of needles.
- B. The Geosynthetic CONTRACTOR shall submit the following.
    1. Installation plan; and
    2. Proposed seam stitching methods.
  - C. Submittals shall be in accordance with Section 01300.

#### **1.05 QUALITY ASSURANCE**

- A. Perform work in accordance with the CQA Plan.

#### **1.06 QUALIFICATIONS**

- A. Geotextile shall be supplied by a geotextile manufacturer meeting the following qualification requirements:
  1. The geotextile manufacturer shall be responsible for the production and delivery of geotextile rolls and shall be a well-established firm with more than two years experience in the manufacture of geotextiles. The geotextile manufacturer shall submit a statement to the CQA CONSULTANT listing:
    - a. Certified minimum average roll property values of the proposed geotextiles and the test methods used to determine those properties.
    - b. Projected delivery date of the material for this project.
- B. The Geosynthetic CONTRACTOR shall meet the requirements of the CQA Plan.

### **PART 2 PRODUCTS**

#### **2.01 MATERIALS**

- A. Non-woven geotextiles shall have the following minimum average roll value (MARV) properties:

**TABLE 02752-1**

**REQUIRED PHYSICAL PROPERTIES OF GEOTEXTILE**

<b>Fabric Property</b>	<b>ASTM Test Method</b>	<b>Manufacturer QC Test Frequency <sup>(1)</sup></b>	<b>Required Test Values</b>
Mass Per Unit Area (min. ave.)	D5261	1 per 100,000 sf	12 oz/sy
Grab Strength (min. ave.)	D4632	1 per 100,000 sf	300 lbs
Puncture Strength (min. ave.)	D4833	1 per 100,000 sf	150 lbs
UV Resistance (min.)	D4355	1 per resin formulation	70 percent <sup>(2)</sup>

Notes: (1) Manufacturer may elect to provide certification of values for geotextiles.  
(2) After 500 hours of exposure.

- B. Geotextile shall be non-woven, needle-punched polyester or polypropylene fabric free from needles or other foreign material.

**2.02 DELIVERY, STORAGE, AND HANDLING**

- A. Handling, storage, and care of the geotextiles following transportation to the site shall be the responsibility of the CONTRACTOR. The CONTRACTOR shall be liable for all damage to the materials incurred prior to final acceptance of the liner system by the CQA CONSULTANT.
- B. The CONTRACTOR shall be responsible for storage of the geotextile at the site after the material is delivered. The geotextile shall be stored off the ground and out of direct sunlight, and shall be protected from mud, dirt, dust, and any additional storage procedures required by the Geotextile manufacturer.
- C. All rolls of geotextile shall be identified at the factory with the following:
  - 1. Manufacturer's name
  - 2. Product identification
  - 3. Lot Number
  - 4. Roll number
  - 5. Roll dimensions
- D. Geotextiles shall be handled in a manner as to ensure they are not damaged in any way.
- E. Precautions shall be taken to prevent damage to underlying materials during placement of the geotextile.
- F. After unwrapping the geotextile from its cover, the geotextile shall not be left exposed for a period in excess of 30 days.

## **PART 3 EXECUTION**

### **3.01 INSTALLATION**

- A. Geotextile seams shall be continuously sewn or heat bonded. Geotextile seams shall be overlapped a minimum of 6 inches prior to sewing. No horizontal seams shall be allowed on slopes steeper than 5 horizontal to 1 vertical.
- B. Polymeric thread, with chemical resistance properties equal to or exceeding those of the geotextile, shall be used for all sewing. The seams shall be sewn using Stitch Type 401. The seam type shall be Federal Standard Type SSa-1.
- C. The CONTRACTOR shall examine the entire geotextile surface after installation to ensure that no potentially harmful foreign objects are present. Such foreign objects shall be removed and damaged geotextile shall be repaired or replaced at no cost to OWNER.
- D. Use care not to damage underlying materials during installation.
- E. Prevent the geotextile from accumulating excessive dust.
- F. The CONTRACTOR shall be responsible for field handling, storing, deploying, seaming or connecting, temporary restraining (against wind), anchoring, and other aspects of geotextile installation. Specifically, the CONTRACTOR shall follow the guidelines in ASTM D4873 regarding the placement, handling and storage of geotextiles.
- G. The CONTRACTOR shall accept and retain full responsibility for all materials and installation and shall be held responsible for any defects in the completed system.
- H. No equipment shall operate directly on the geotextile.
- I. Use sandbags or other acceptable anchorage to prevent wind uplift.

### **3.02 REPAIRS**

- A. Any holes or tears in the geotextile shall be repaired using a geotextile patch consisting of the same geotextile.
  - 1. On slopes inclined steeper than 10 horizontal to 1 vertical, patches shall be sewn into place with a minimum 6-inch overlap.
  - 2. On slopes inclined at 10 horizontal to 1 vertical or less, patches may be heat-bonded with a 6-inch overlap in all directions.

**END OF SECTION**

## **SECTION 02774**

### **GEOCOMPOSITE**

#### **PART 1 GENERAL**

##### **1.01 DESCRIPTION**

- A. This section describes the general requirements for the manufacture, supply, installation, and quality control (QC) of geocomposite.

##### **1.02 RELATED SECTIONS**

- A. Section 02200 - Earthworks
- B. Section 02751 - HDPE Geomembranes
- C. Section 02752 - Geotextiles

##### **1.03 REFERENCES**

- A. Latest version of the following American Society for Testing and Materials (ASTM) standards:
  - 1. ASTM D413. Standard Test Method for Rubber Property-Adhesion to Flexible Substrate
  - 2. ASTM D792. Test Method for Specific Gravity and Density of Plastics by Displacement
  - 3. ASTM F904. Standard Test Method for Comparison of Bond Strength or Ply Adhesion of Similar Laminates Made from Flexible Materials
  - 4. ASTM D1238. Standard Test Method for Flow Rates of Thermoplastics by Extrusion Plastometer
  - 5. ASTM D1505. Standard Test Method for Density of Plastics by Density - Gradient Technique
  - 6. ASTM D1603. Test Method for Carbon Black in Olefin Plastics
  - 7. ASTM D3786. Standard Text Method for Hydraulic Bursting Strength of Knitted Goods and Non-woven Fabrics: Diaphragm Bursting Strength Test Method
  - 8. ASTM D4491. Standard Test Methods for Water Permeability of Geotextiles by Permittivity
  - 9. ASTM D4533. Standard Test Method for Trapezoid Testing Strength of Geotextiles

10. ASTM D4632. Standard Test Method for Breaking Load and Elongation of Geotextiles (Grab Method)
11. ASTM D4716. Standard Test Method for Constant Head Hydraulic Transmissivity (in-plane flow) of Geotextiles and Geotextile Related Products
12. ASTM D4751. Standard Test Method for Determining Apparent Opening Size of a Geotextile
13. ASTM D4833. Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products
14. ASTM D5199. Standard Test Method for Measuring Nominal Thickness of Geotextiles and Geomembranes
15. ASTM D5261. Standard Test Method for Weight (Mass) Per Unit Area of Geotextiles

#### **1.04 SUBMITTALS**

- A. Geosynthetic CONTRACTOR shall submit to the CQA CONSULTANT the following documentation on the raw materials used to manufacture the geocomposite:
  1. Quality control certificates issued by the raw material supplier including the production dates of the raw material used to manufacture geocomposite for the project.
  2. Results of tests conducted by the manufacturer to verify the quality of the resin used to manufacture the geocomposite rolls assigned to the project and the origin of the resin and quality control certificates issued by the resin supplier.
  3. Certification that no reclaimed polymer was used in the manufacturing of the geocomposite to be used for the project and that recycled material reworked from the manufacturing process does not exceed 10 percent by weight.
- B. A copy of the manufacturer's Quality Control (QC) Program.
- C. Quality control certificates for test results at the sampling frequency indicated by the manufacturer's QC Plan shall be submitted.
  1. Manufacturing quality control certificates for each shift's production shall be signed by responsible parties employed by the manufacturer (such as the production manager).
  2. The quality control certificates shall include:
    - a. Roll numbers and identification;
    - b. Sampling procedures; and

- c. Results of the quality control tests verifying each of the properties listed in Table 02774-1.

D. Submittals shall be provided in general accordance with Section 01300.

## 1.05 QUALITY ASSURANCE

- A. Perform work in accordance with manufacturer's instructions and the CQA Plan.

## 1.06 QUALIFICATIONS

- A. Manufacturer shall be a well-established firm with more than two years of experience in the manufacture of geocomposites.
- B. Geosynthetic CONTRACTOR shall meet the requirements of the CQA Plan.

## PART 2 PRODUCTS

### 2.01 MATERIALS

- A. The geocomposite to be used on the project shall comprise HDPE bi-planar geonet drainage material with a non-woven, needle-punched geotextile bonded to the top and bottom. The geotextile will be thermally bonded to the geonet component of the geocomposite. Chemical bonding is not allowed.
- B. Geocomposite shall meet the minimum properties listed in Table 02774-1.

### 2.02 DELIVERY, STORAGE, AND HANDLING

- A. The Geosynthetic CONTRACTOR shall be responsible for handling, storage, and care of the geocomposites following transportation to the site. The Geosynthetic CONTRACTOR shall be liable for all damage to the materials incurred prior to final acceptance of the liner system by the CQA CONSULTANT.
- B. The geocomposite shall be stored off the ground and out of direct sunlight, and shall be protected from mud, dirt, dust, and any additional storage procedures required by the manufacturer.
- C. All rolls of geocomposite shall be identified at the factory with the following:
  - 1. Manufacturer's name
  - 2. Product identification
  - 3. Lot Number
  - 4. Roll number
  - 5. Roll dimensions
- D. The geocomposites shall be handled in such a manner as to ensure they are not damaged in any way.



- E. Precautions shall be taken to prevent damage to underlying layers during placement of the geocomposite.
- F. After unwrapping the geocomposite from its cover, the geocomposite shall not be left exposed for a period in excess of 30 days.

### **PART 3 EXECUTION**

#### **3.01 EXAMINATION**

- A. Verify that other work is complete over the areas where the geocomposite is to be deployed.

#### **3.02 PREPARATION**

- A. Protect elements surrounding the work of this section from damage.

#### **3.03 INSTALLATION**

- A. The geocomposite shall be installed in accordance with the manufacturer's recommended procedures and the CQA Plan.
- B. The CQA CONSULTANT shall verify that all geocomposite rolls and underlying layers are free from deleterious material or debris prior to the geocomposite deployment. Dirt entrapped in the geocomposite following deployment shall be cleaned or affected geocomposite removed and replaced prior to placement of successive layers.
- C. The Geosynthetic CONTRACTOR is responsible for anchoring exposed geocomposite to protect against wind damage until subsequent layers are placed.
- D. The geocomposite shall not be welded to the geomembrane unless specified otherwise.
- E. The geocomposite shall only be cut utilizing methods and tools (i.e., a hooked utility blade) which will not damage the geocomposite.
- F. The geonet component of the geocomposite shall be overlapped a minimum of 4 inches between adjacent panels and shall be fastened by nylon ties. Ties shall be yellow or white for easy inspection. No metallic materials are allowed. Ties shall be placed every 5 feet along the lengths of adjacent panels, every 6 in. across butt-seams, and every 6 in. in any anchor trench.
- G. In general, butt-seams will only be allowed on grades less than 15%. Butt-seams shall be overlapped a minimum of two feet and be secured with two rows of ties a minimum of 6 in. apart. Ties shall be spaced at six inch intervals and staggered between rows.
- H. The top geotextile component shall be overlapped a minimum of 6 in. and shall be continuously sewn. Leister seaming shall be allowed following a field demonstration of performance and approval by the Design Engineer.

- I. Polymeric thread, with chemical resistance properties equal to or exceeding those of the geotextile, shall be used for all sewing. The seams shall be sewn using Stitch Type 401. The seam type shall be Federal Standard Type SSa-1.
- J. The Geosynthetic CONTRACTOR shall be responsible for field handling, storing, deploying, seaming or joining, temporary restraining (against wind), anchoring, and other aspects of geocomposite installation.
- K. The Geosynthetic CONTRACTOR shall accept and retain full responsibility for all materials and installation and shall be held responsible for any defects in the completed systems.

#### **3.04 REPAIRS**

- A. Any defects observed in the geocomposite shall be brought to the attention of the CQA CONSULTANT.
- B. Holes or tears in the geocomposite shall be repaired with geocomposite patches extending 2 feet beyond the edges of the hole or tear. The patch shall be secured in place by using approved ties spaced at 6 inches. The ties shall extend through the geonet component of the patch and through the geotextile and geonet components of the geocomposite requiring repair. The upper geotextile component of the patch shall be heat bonded to the geotextile component of the geocomposite requiring repair.
- C. If only the upper geotextile is damaged, then it may be repaired by heat-bonding a geotextile patch of equal weight.

#### **3.05 FIELD QUALITY CONTROL**

- A. Field inspection and testing shall be performed in accordance with the CQA Plan.

#### **3.06 PROTECTION**

- A. Do not permit traffic over any of the Products related to this Section.
- B. The CONTRACTOR shall place all soil materials in such a manner as to ensure that:
  - 1. The geocomposite and underlying materials are not damaged;
  - 2. Minimal slippage occurs between the geocomposite and the underlying geosynthetic layers; and
  - 3. Excess tensile stresses are not developed in the geocomposite.

**TABLE 02774-1  
GEOCOMPOSITE PROPERTY VALUES**

PROPERTY	UNITS	SPECIFIED VALUES	TEST METHOD
<b>Geonet Component:</b>			
Thickness	mils	200	ASTM D-751 or ASTM D-5199
Density	g/cc	0.940	ASTM D-792 or ASTM D-1505
Carbon Black Content (range)	%	2-3	ASTM D-1603
<b>Geotextile Component:</b>			
Mass	oz/yd <sup>2</sup>	8	ASTM D-5261
Grab Tensile	Lb	220	ASTM D-4632
Puncture	Lb	120	ASTM D-4833
AOS	Mm	0.180	ASTM D-4751
Permeability	Sec <sup>-1</sup>	1.5	ASTM D-4491
UV Resistance)	% retained after 500 hr.	70	ASTM D-4355
<b>Finished Geocomposite:</b>			
Transmissivity	m <sup>2</sup> /sec	1 x 10 <sup>-3</sup> (see notes 1 and 2 below)	ASTM D-4716
Peel Strength	lb/in.	0.75	GRI GC7

Notes:

1. Required value shall be taken from manufacturer's standard material specification sheet for the selected geonet/geocomposite material. Geonet/geocomposite selection shall be based on the material's ability to meet or exceed the transmissivity identified in the site's design.
2. Transmissivity shall be measured in a 12-inch by 12-inch box with the geocomposite between steel plates under a normal stress of 15,000 psf and a hydraulic gradient of 0.1. A seating time of 15 minutes shall be used.
3. The geotextile component shall conform to the requirements contained in Section 02752 of these Specifications, except that the values listed in Table 02774-1 above take precedence over those in Section 02752.

**END OF SECTION**

**APPENDIX O.2**  
**FINAL CLOSURE SPECIFICATIONS**

**Golder Associates Inc.**

230 Commerce, Suite 200  
Irvine, California 92602  
Telephone (714) 508-4400  
Fax (714) 508-4401  
www.golder.com



**TECHNICAL SPECIFICATIONS  
LANDFILL UNIT B-18 FINAL CLOSURE  
KETTLEMAN HILLS FACILITY  
KETTLEMAN CITY, CALIFORNIA**

***Prepared for:***

Waste Management, Inc.  
Kettleman Hills Facility  
35251 Old Skyline Road  
Kettleman City, California 93239

***Prepared by:***

Golder Associates Inc.  
230 Commerce, Suite 200  
Irvine, California 92602

November 2008  
Revision 0

Project No.: 083-91887

## TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
Section 01010 - Summary of Work .....	01010-1
Section 01032 - Intent of Drawings and Specifications.....	01032-1
Section 01300 - Submittals .....	01300-1
Section 01400 - Construction Quality Control .....	01400-1
Section 01402 - Control of Work.....	01402-1
Section 01565 - Temporary Facilities .....	01565-1
Section 01810 - Safety Procedures .....	01810-1
Section 02105 - Erosion Control.....	02105-1
Section 02110 - Site Clearing, Grubbing, and Stripping .....	02110-1
Section 02200 - Earthworks .....	02200-1
Section 02751 - HDPE Geomembranes .....	02751-1
Section 02752 - Geotextiles .....	02752-1
Section 02932 - Revegetation .....	02932-1

## SECTION 01010

### SUMMARY OF WORK

#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. The section describes the general requirements for the final closure construction of Landfill Unit B-18 at the Kettleman Hills Facility located outside of Kettleman City, California. The Work will consist of excavation, engineered fill placement, subgrade preparation, installation of a composite geosynthetic liner system, and placement of a vegetative cover soil layer.

##### 1.02 CONTRACTOR'S RESPONSIBILITIES:

- A. Start, lay out, construct, and complete the Project in accordance with the Contract Documents;
- B. Provide a competent superintendent, capable of reading and understanding the Contract Documents, who shall receive instructions from the OWNER or his authorized representative. The superintendent shall have full authority to execute the Work in accordance with the Contract Documents;
- C. The CONTRACTOR shall be responsible for transporting, permitting, and/or conveying all required construction water.
- D. Pay costs of legally required sales, consumer, and use taxes, and governmental fees.
- E. Forward submittals and communications to the CONSTRUCTION MANAGER. Where applicable, the CONSTRUCTION MANAGER will coordinate submittals and communications with the representatives who will give approvals and directions through the CONSTRUCTION MANAGER.
- F. Maintain order, safe practices and proper conduct at all times among CONTRACTOR's employees. The OWNER, and its authorized representative, may require that disciplinary action be taken against an employee of the CONTRACTOR for disorderly, improper, and unsafe conduct. Should an employee of the CONTRACTOR be dismissed from his duties for misconduct, incompetence, or unsafe practice, or combination thereof, that employee should not be rehired for the duration of the Work.
- G. Coordinate prosecution of the Work with the utilities, private utilities, or OWNER performing work on or adjacent to the work site; either eliminate, or minimize as far as possible, delays in the Work and conflicts with those utilities or contractors. Coordinate utility activities, and activities of OWNER, with the CONSTRUCTION MANAGER. Schedule private utility and public utility work relying on survey points, lines, and grades established by the CONTRACTOR to occur immediately after those points, lines and grades have been established. Confirm coordinate measures for each individual case with the CONSTRUCTION MANAGER by memorandum.





CQA CONSULTANT	The term CQA CONSULTANT means the representative of the OWNER for the purpose of conducting CQA testing, monitoring, documenting, and reporting.
CONTRACTOR	The term CONTRACTOR means the firm that is responsible prosecuting the Work. The CONTRACTOR's responsibilities include the Work of any and all subcontractors and suppliers.
Geosynthetics CONTRACTOR	The term Geosynthetics CONTRACTOR means the firm that is responsible for the supply and installation of all geosynthetics including the Work of all of the subcontractors and suppliers. The Geosynthetics Installer may work directly for the OWNER or as a subcontractor to the CONTRACTOR. The Geosynthetics CONTRACTOR is also referred to as the CONTRACTOR.
Work	The term Work means the entire completed construction or various separately identifiable parts, thereof, required to be furnished under the Contract Documents. Work includes any and all labor, services, materials, equipment, tools, supplies, and facilities required by the Contract Documents and necessary for the completion of the project. Work is the result of performing services, furnishing labor and furnishing and incorporating materials and equipment into the construction, all as required by the Contract Documents.
Working day	A calendar day, exclusive of Saturdays, Sundays, and OWNER's recognized legal holidays, on which weather and other conditions not under the control of the CONTRACTOR will permit construction operations to proceed for the major part of the day with the normal working force engaged in performing the controlling item or items of work which would be in progress at that time. The working day is subject to the conditions and work restrictions outlined in these Specifications.
Regular Working Hours	Between 6:30 a.m. and 6:00 p.m. on allowable work days.
Calendar Days	Each day of the year including all OWNER approved holidays.

#### **1.06 CONTRACT TIMES**

- A. The CONTRACTOR shall commence Work in accordance with Section 18 of the General Conditions and Section 7 of the Standard Contract.

#### **1.07 CONTRACTOR USE OF WORK SITE**

- A. Confine work site operations to areas permitted by law, ordinances, permits, and the Contract Documents. The CONTRACTOR shall ensure that all persons under his control (including Subcontractors, their workers and agents) are kept within the boundaries of the Site and shall be responsible for any acts of trespass or damage to property by persons who are under his control. Consider the safety of the Work, and that of people and property on and adjacent to work site, when determining amount, location, movement, and use of materials and equipment on work site.
- B. The CONTRACTOR shall be responsible for protecting private and public property including pavements, drainage culverts, electricity, highway, telephone and similar property and making good of, or paying for, all damage caused thereto. Control of erosion throughout the project is of prime importance and is the responsibility of the CONTRACTOR. The CONTRACTOR shall comply with the requirements of the Storm Water Pollution Prevention Plan (SWPPP) provided by the OWNER for the Kettleman Hills Facility and prepare and submit a SWPPP specific to the Work in accordance with requirements of local or state agencies (see Section 01300). The CONTRACTOR shall provide and maintain all necessary measures to control erosion during progress of the Work to the satisfaction of the CONSTRUCTION MANAGER and all applicable Laws and Regulations and remove such measures and debris upon completion of the project. All provisions for erosion and sedimentation control apply equally to all areas of the Work.
- C. CONTRACTOR shall promptly notify OWNER and CONSTRUCTION MANAGER in writing of any subsurface or latent physical conditions at the Site which differ materially from those indicated or referred to in the Contract Documents. CONSTRUCTION MANAGER will promptly review those conditions and advise OWNER in writing if further investigations or tests are necessary. Promptly thereafter, OWNER shall obtain the necessary additional investigations and tests and furnish copies to the CONSTRUCTION MANAGER and CONTRACTOR. If CONSTRUCTION MANAGER finds that the results of such investigations or tests indicate that there are subsurface and latent physical conditions which differ materially from those intended in the Contract Documents, and which could not reasonably have been anticipated by CONTRACTOR, a Change Order shall be issued incorporating the necessary revisions.

#### **1.08 PRESERVATION OF SCIENTIFIC INFORMATION**

- A. Federal and State legislation provides for the protection, preservation, and collection of data having scientific, prehistoric, historical, or archaeological value (including relics and specimens) which might otherwise be lost due to alteration of the terrain as a result of any construction work.
- B. If evidence of such information is discovered during the course of the Work, the CONTRACTOR shall notify the CONSTRUCTION MANAGER immediately, giving

the location and nature of the findings. Written confirmation shall be forwarded within two (2) working days. The CONTRACTOR shall exercise care so as not to damage artifacts uncovered during excavation operations, and shall provide such cooperation and assistance as may be necessary to preserve the findings for removal or other disposition by the OWNER's representative or Government agency.

- C. Where appropriate, by reason of a discovery, the OWNER may order delays in the time of performance, or changes in the Work, or both. If such delays, or changes, or both, are ordered, the time of performance and contract price shall be adjusted in accordance with the applicable clauses of the Contract.

**1.09 EXISTING UTILITIES**

- A. The CONTRACTOR shall be responsible for locating, protecting, flagging, and identifying all existing utilities. The CONTRACTOR shall request that Underground Service Alert (USA) locate and identify the existing utilities. The request shall be made 48 hours in advance.
- B. Costs resulting from damage to utilities shall be borne by the CONTRACTOR. Costs of damage shall include repair and incidental costs resulting from the unscheduled loss of utility service to affected parties.
- C. The CONTRACTOR shall immediately stop work and notify the CONSTRUCTION MANAGER of all utilities encountered or damaged. The CONTRACTOR shall also provide the CONSTRUCTION MANAGER with the exact location of any utilities encountered during construction.
- D. If specified by the CONSTRUCTION MANAGER, utility pot holes shall be carefully dug by the CONTRACTOR to identify the presence of underground utilities.
- E. Damage to utilities by the CONTRACTOR during pothole operations shall be born by the CONTRACTOR.

**PART 2 PRODUCTS**

(Not Used)

**PART 3 EXECUTION**

(Not Used)

**END OF SECTION**

## SECTION 01032

### INTENT OF DRAWINGS AND SPECIFICATIONS

#### PART 1 GENERAL

##### 1.01 CONTRACT DRAWINGS AND SPECIFICATIONS

- A. The intent of the Drawings and Specifications is to prescribe a complete work which the CONTRACTOR shall perform in a manner acceptable to the OWNER and in full compliance with the terms of the Contract.
- B. The Drawings show general arrangements for the work which shall be used by the CONTRACTOR in the preparation of shop and field drawings. Particular care shall be given to all layouts to make sure all equipment is accessible for operation.
- C. The CONTRACTOR shall provide the OWNER with a complete and operable system, even though the Drawings and Specifications may not specifically call out all items of work required of the CONTRACTOR to complete his tasks, incidental appurtenances, materials, and the like and maintenance.
- D. The CONTRACTOR is to perform the Work in accordance with the cross-sections, thickness, gradients and dimensions shown on the Drawings. Any deviations must be approved by the DESIGN ENGINEER prior to doing the work.
- E. The dimensions on the Drawings are presumed to be correct, but the CONTRACTOR shall be required to check carefully all dimensions prior to beginning the Work. If errors or omissions are discovered by the CONTRACTOR, the CONTRACTOR shall immediately notify the CONSTRUCTION MANAGER in writing and await the CONSTRUCTION MANAGER's notification before proceeding.

##### 1.02 PRECEDENCE OF CONTRACT DOCUMENTS

- A. If there is a conflict between Contract Documents, the document highest in precedence shall control. The precedence shall be:
  - 1. Permits.
  - 2. Special Provisions.
  - 3. General Terms and Conditions.
  - 4. Construction Drawings.
  - 5. Technical Specifications.

##### 1.03 CHANGES TO DRAWINGS

- A. It is inherent in the nature of construction that some changes in the Drawings and Specifications may be necessary during the course of construction to adjust them to field conditions, and it is the essence of the Contract to recognize a normal and expected margin of change. The CONSTRUCTION MANAGER shall have the right

to make such changes, from time to time, in the Drawings, in the character of the Work as may be necessary or desirable to insure the completion of the Work in the most satisfactory manner without invalidating the Contract.

**PART 2 PRODUCTS**

(Not Used)

**PART 3 EXECUTION**

(Not Used)

**END OF SECTION**

## **SECTION 01300**

### **SUBMITTALS**

#### **PART 1 GENERAL**

##### **1.01 SUBMITTAL PROCEDURES**

- A. Transmit each submittal with cover letter to the OWNER.
- B. Each submittal shall have a unique submittal number.
- C. Submittals shall be numbered sequentially. Re-submittals shall have original number with an alphabetic suffix (A, B, C, etc.) to indicate the sequence of the re-submittal.
- D. Identify Project, CONTRACTOR, Subcontractor or supplier; pertinent Drawing sheet and detail number(s), and specification Section number, as appropriate.
- E. Identify variations from Contract Documents and Product or system limitations that may be detrimental to successful performance of the completed Work.
- F. Provide space for DESIGN ENGINEER and/or CQA CONSULTANT review stamps.
- G. Revise and resubmit submittals as required, identify all changes made since previous submittal.
- H. Distribute copies of reviewed submittals to concerned parties. Instruct parties to promptly report any inability to comply with provisions.
- I. When catalog pages are submitted, applicable items shall be clearly identified.
- J. An electronic copy (preferred) or three (3) hard copies of each submittal shall be provided to the OWNER. The OWNER will not accept submittals from anyone other than the CONTRACTOR.
- K. The CONTRACTOR shall review all submittal packages prior to transmittal to OWNER for completeness and accuracy.

##### **1.02 CHECK OF RETURNED SUBMITTALS AND WAIVER OF CLAIMS**

- A. The CONTRACTOR shall check and review the submittals returned for correction and ascertain whether the required corrections result in extra cost above that included in the Contract, and shall give written notice to the CONSTRUCTION MANAGER within five (5) working days if, in the CONTRACTOR's estimation, extra costs result from the corrections. The CONTRACTOR's failure to give such written notice before the starting of the Work covered by returned submittal constitutes a waiver by the CONTRACTOR of claims for extra costs resulting from required corrections. Payment based on such written notice is not approved until authorized by the OWNER.

### **1.03 PRODUCT DATA SUBMISSION**

- A. For each product item included in the Work, include the manufacturer's name and address, the trade or brand name, all conditions of manufacturer's guarantee and warranty, information to fully describe each item, and supplementary information as may be required for approval. Mark catalog cuts, brochures, and data to indicate the items proposed and the intended use. Clearly mark product parameters which were specifically called out on the original specifications.

### **1.04 EQUIPMENT DATA SUBMISSION**

- A. Submit complete technical, performance, and catalog information for every item of civil, mechanical, and electrical equipment and machinery proposed for installation in the Work. Include information on performance and operating curves, ratings, capacities, characteristics, power efficiencies, manufacturers' standard guarantees and warranties with the terms and conditions fully described, and all other information to fully illustrate and describe the items as may be specified or required for approval.

### **1.05 SUBMITTAL REVIEW AND ACCEPTANCE**

- A. The submittal review period shall be ten (10) consecutive work days in length and shall commence on the first working day immediately following the date of arrival of the submittal or re-submittal in the OWNER's office. The time required for mail delivery of the submittal or re-submittal back to the CONTRACTOR shall not be considered a part of the submittal review period.
- B. The acceptance of drawings and data submitted by the CONTRACTOR will cover only general conformity to the Drawings and Specifications, external connections, and dimensions which affect the layout. The DESIGN ENGINEER's and/or CQA CONSULTANT's review of submittals shall not relieve the CONTRACTOR from responsibility for errors, omissions, or deviations, nor responsibility for compliance with the contract documents.

### **1.06 RE-SUBMITTALS**

- A. When the drawings and data are returned marked "AMEND AND RESUBMIT" or "REJECTED, SEE REMARKS," the corrections shall be made as noted thereon and as instructed by the DESIGN ENGINEER's and/or CQA CONSULTANT's and shall be resubmitted.
- B. When corrected copies are resubmitted, the CONTRACTOR shall highlight or otherwise direct specific attention to all revisions and shall list separately those revisions made other than those called for on previous submissions.
- C. The need for more than one resubmission shall not entitle the CONTRACTOR to extension of the Contract Time.

### **1.07 COSTS FOR SUBMITTALS**

- A. All costs for the preparation, correction, and delivery of the submittals are considered incidental to the contract and shall be included in CONTRACTOR's costs.

## **PART 2 PRODUCTS**

(Not Used)

## **PART 3 EXECUTION**

### **3.01 MATERIALS REQUIRING SUBMITTALS**

- A. The following materials shall require submittals.
  - 1. Material certifications and product data for all geosynthetics;
  - 2. Material quality control data for all geosynthetics;
  - 3. Material certifications and product data for piping;
  - 4. Material quality control data for piping; and
  - 5. Items not fully detailed and specified in the Contract Drawings or these Specifications.

### **3.02 ITEMS NOT REQUIRING SUBMITTALS**

- A. A submittal is not required for products and equipment completely specified or salvaged on-site. A submittal is required if the product has not been completely specified or when the specified product is not available within the construction schedule. Substitutions requested by the CONTRACTOR require a submittal.

### **3.03 CONSTRUCTION SCHEDULE**

- A. At the pre-construction meeting, the CONTRACTOR shall submit to the CONSTRUCTION MANAGER for review a schedule of the proposed construction operations. The construction schedule shall indicate the sequence of the Work indicating the time of completion of each component of the Work.
- B. Submit initial progress schedule in duplicate within ten (10) days after Effective Date of Agreement for CONSTRUCTION MANAGER to review.
- C. Revise and resubmit as required.
- D. Submit revised schedules with each Application for Payment, identifying changes since previous version.
- E. Submit a horizontal bar chart with separate line for each major section of Work or operation, identifying first work day of each week. Include on the bar chart construction/placement rates for all the major items of Work. CONTRACTOR shall develop proposed Construction Schedule on basis of a five or six day working week. Sufficient labor, equipment, and materials shall be provided by CONTRACTOR to complete the Work on a five or six day per week basis. Night work and work on Sundays will only be approved by the OWNER if the Work falls behind the approved Construction Schedule.



- F. Show complete sequence of construction by activity, identifying Work of separate stages and other logically grouped activities. Indicate the start date, finish date, and duration. At a minimum, the following activities must be shown on the project schedule:
1. Mobilization;
  2. Excavation;
  3. Subgrade preparation;
  4. Placement of the geomembrane;
  5. Installation of the geotextile;
  6. Placement of the vegetative cover soil;
  7. Hydroseeding of the final cover; and
  8. Demobilization and site clean-up.
- G. Indicate estimated percentage of completion for each item of Work at each submission with Application for Payment.
- H. Indicate submittal dates required for shop drawings, product data, samples and product delivery dates.
- I. The Construction Schedule as approved by the OWNER will be an integral part of the Contract, and will establish interim Contract completion dates for various activities. Should an activity not be completed within ten (10) days after the stated Schedule date, the CONSTRUCTION MANAGER shall have the option to recommend to the CONTRACTOR to expedite completion of the activity by whatever means deemed appropriate and necessary, without additional compensation to the CONTRACTOR.
- J. Should any activity be twenty (20) or more working days behind Schedule, the OWNER shall have the right to perform the activity or to have the activity performed by whatever method the OWNER deems appropriate. Costs incurred by the OWNER in connection with expediting construction activities under this Paragraph shall be reimbursed to the OWNER by the CONTRACTOR.
- K. It is expressly understood and agreed that failure by the OWNER to exercise the option to either order the CONTRACTOR to expedite an activity or to expedite the activity by other means shall not be considered precedent-setting for any other activities. The Work shall be executed in strict accordance with the Construction Schedule unless a variance has been received by the CONSTRUCTION MANAGER and approved by the OWNER.

### 3.04 PROGRESS REPORTS

- A. The CONTRACTOR shall submit progress reports as requested indicating work performed and completed that week, quantity of material used, and equipment used to perform the Work.
- B. A progress report shall also be furnished to the ENGINEER with each application for progress payment. If the Work falls behind schedule, the CONTRACTOR shall submit additional progress reports at such intervals as the CONSTRUCTION MANAGER may request.
- C. Each progress report shall include sufficient narrative to describe current and anticipated delaying factors, their effect on the construction schedule, and proposed corrective actions. Work reported complete, but which is not readily apparent as complete to the CONSTRUCTION MANAGER, must be substantiated with satisfactory evidence.

- D. Each progress report shall also include a graphic schedule marked to indicate actual progress. Revised schedules shall be included when warranted.

### **3.05 MANUFACTURER'S CERTIFICATES**

- A. When specified in individual Specification Sections, submit manufacturers' certificate to the CQA CONSULTANT for review, in quantities specified for Product Data.
- B. Indicate whether material or product conforms to or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.
- C. Certificates may be recent or previous test results on material or Product, but must be acceptable to the CONSTRUCTION MANAGER.

### **3.06 RECORD SURVEY AND DRAWINGS**

- A. The CONTRACTOR shall keep a set of construction drawings on the job and mark in red pencil the as-built conditions.
- B. A complete and accurate set of record drawings shall be signed and dated by the CONTRACTOR and shall be labeled with the following, "These record drawings completely and truly represent the contract work as installed."
- C. Record drawings shall be delivered to the CONSTRUCTION MANAGER prior to final acceptance of the work by the CONSTRUCTION MANAGER.
- D. Record drawings shall show all changes in "clouds" to clearly identify any deviations from the plans.
- E. Any utilities uncovered during construction shall be identified on the record drawings.
- F. The record survey shall be performed by the CONTRACTOR in accordance with Section 01400, Part 1.04 and shall meet the requirements of these Specifications and the CQA Plan and include, but not be limited to:
  - 1. edges, bottom, and limits of anchor trenches;
  - 2. limits of excavation and fill;
  - 3. subgrades;
  - 4. HDPE panel layout, intersections;
  - 5. destructive test locations on HDPE geomembrane;
  - 6. location and crown elevations of piping;
  - 7. top of the vegetative cover soil layer;
  - 8. grade breaks; and
  - 9. layout and flow line elevations of surface water control structures.
- G. Survey of the excavated subgrades and Operations Layer surfaces shall be on a grid with a maximum spacing of 50 feet or an equivalent method approved by the CQA CONSULTANT, with additional elevations at slope change locations. The elevations for the subgrade and top of the Operations Layer shall be at the same grid locations and shall be used to document thickness conformance. The record survey shall include locations and elevations of all other work as directed by the CONSTRUCTION MANAGER.

- H. Record drawings shall be prepared to scale, with the scale clearly marked. Record drawings of details may not be to scale, but all dimensions shall be clearly identified. Record drawings shall be submitted to the CQA CONSULTANT for review and approval. Record drawings shall be provided on Bond and electronically in AutoCAD 2005 format or more recent. The DESIGN ENGINEER will provide the base AutoCAD file map. Different elements of the work shall be presented on different layers in the base AutoCAD file provided by the DESIGN ENGINEER.

### **3.07 HEALTH AND SAFETY PLAN**

- A. The CONTRACTOR shall submit a Health and Safety Plan in accordance with Section 01810 of these Specifications.

### **3.08 STORM WATER POLLUTION PREVENTION PLAN (SWPPP)**

- A. The CONTRACTOR shall prepare and submit a SWPPP specific to the work to the OWNER for approval. The SWPPP shall be consistent with the provisions of the "California Construction Best Management Practice Handbook," the site National Pollutant Discharge Elimination System (NPDES) site permit, and the Kettleman Hills Facility SWPPP. The SWPPP shall include specific measures to protect the Work and comply with the regulations, including specific erosion and sediment controls. The CONTRACTOR is responsible to control storm water run-on, run-off, erosion, and sediment to such an extent as needed to maintain compliance with the SWPPP and protect the Work, protect adjacent landfill operations, and adjacent structures.

**END OF SECTION**

## SECTION 01400

### CONSTRUCTION QUALITY CONTROL

#### PART 1 GENERAL

##### 1.01 CONSTRUCTION QUALITY CONTROL

- A. The CONTRACTOR shall be responsible for construction quality control of the Work and all appurtenances as described in these Specifications.
- B. The CONTRACTOR shall monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce Work of specified quality.
- C. The CONTRACTOR shall comply fully with manufacturers' instructions, including each step in sequence.
- D. Should manufacturers' instructions conflict with Contract Documents, the CONTRACTOR shall request clarification from CONSTRUCTION MANAGER before proceeding.
- E. The CONTRACTOR shall comply with specified standards as a minimum quality for the Work except when more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
- F. The CONTRACTOR shall perform work using persons qualified to produce workmanship of specified quality.
- G. The CONTRACTOR shall secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion or disfigurement.
- H. The CONSTRUCTION MANAGER shall determine and decide all questions which may arise as to the quality and acceptability of materials and Work performed; the manner of performance and the rate of progress of said Work; the interpretations of the Contract Documents relating to the Work; the acceptable fulfillment of the Contract Documents on the part of the CONTRACTOR; and the amount and quantity of the several kinds of Work performed and materials which are to be paid for under the Contract.
- I. All materials and equipment shall be new and of the specified quality and equal to the samples found to be acceptable by the CQA CONSULTANT, if samples have been submitted.
- J. The Work shall be done and completed in a thorough, workmanlike manner, notwithstanding omissions in the Contract Documents; and it shall be the duty of the CONTRACTOR to call the CONSTRUCTION MANAGER's attention to apparent errors or omissions and request instructions in writing before proceeding with the Work.

- K. The CONSTRUCTION MANAGER may, by appropriate written instructions, correct errors and omissions. Instructions and corrections shall be as binding upon the CONTRACTOR as though contained in the original Contract Documents.

#### **1.02 CONSTRUCTION QUALITY ASSURANCE**

- A. Materials, equipment, methods of construction and workmanship shall be subject to the inspection of the CQA CONSULTANT as outlined in the CQA Plan. Defective materials, equipment, or work shall be replaced, corrected or otherwise made good by the CONTRACTOR at the CONTRACTOR's own expense.
- B. On all questions concerning the acceptability of materials or equipment, execution of the Work, and the determination of costs, the decision of the CONSTRUCTION MANAGER shall be final and binding upon all parties.
- C. The CONTRACTOR shall at all times maintain proper facilities and provide safe access to all parts of the Work, to the shops wherein the Work is in preparation, and to all warehouses and storage yards wherein materials and equipment are stored, for purposes of inspection by the CQA CONSULTANT.
- D. The CONTRACTOR shall provide incidental labor and facilities to provide access to Work to be tested, to obtain and handle samples at the Site or at source of products to be tested, and to facilitate tests and inspections.
- E. Notify CQA CONSULTANT 24 hours prior to expected time for operations requiring inspection services.
- F. Retesting required because of non-conformance to specified requirements shall be performed by the CQA CONSULTANT on instructions by the CONSTRUCTION MANAGER. Payment for retesting will be charged to the CONTRACTOR by deducting inspection or testing charges from the Contract Price.
- G. Employment of CQA CONSULTANT by OWNER shall in no way relieve the CONTRACTOR of obligations to perform Work in accordance with requirements of Contract Documents.

#### **1.03 MANUFACTURERS' FIELD SERVICES AND REPORTS**

- A. When specified in individual Specification Sections, required material or Product suppliers or manufacturers shall provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, and quality of workmanship as applicable, and to initiate instructions when necessary.
- B. Individuals shall report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions.

#### **1.04 SURVEYING**

- A. At least two control monuments shall be established by the CONTRACTOR at locations convenient for daily tie-in. The vertical and horizontal controls for these

control points shall be established within normal land surveying standards. The CONTRACTOR shall use these control points in laying out and providing ongoing geometric control of the work. The control monuments shall be shown on all record drawings.

- B. Surveying shall be performed under the direct supervision of a licensed land surveyor or registered civil engineer authorized to practice land surveying under Chapter 15, Article 3, Section 8731 of the Professional Engineering Act of California, as amended January 1, 1992 who may also be the senior surveyor on site. The survey crew shall consist of the senior surveyor and as many surveying assistants as required to satisfactorily undertake the work. Personnel shall be experienced in all aspects of surveying, including detailed, accurate documentation.
- C. The survey instruments used for this work shall be sufficiently precise and accurate to meet the needs of the project. Survey instruments shall be capable of reading to a precision of 0.01 feet and with a setting accuracy of 10 seconds. Calibration certificates for survey instruments shall be submitted on request to the CQA CONSULTANT prior to the initiation of surveying activities.
- D. It shall be the CONTRACTOR's sole responsibility to control the Work so that all of the geometric requirements of the project are met. The CONTRACTOR shall immediately notify the CONSTRUCTION MANAGER and the CQA CONSULTANT of any discrepancy found in the Work. It will be the CONSTRUCTION MANAGER's sole prerogative to approve or reject work which does not meet the requirements contained in these Specifications and the Drawings, but which, in the CONSTRUCTION MANAGER's sole opinion, may nevertheless meet the intention of the Contract Documents.
- E. The CONTRACTOR shall be responsible for the accuracy of all work and shall maintain all reference points, stakes, etc., throughout the life of the project. Damaged or destroyed points, bench marks or stakes, or any reference points made inaccessible by the progress of the construction shall be replaced or transferred by the CONTRACTOR. Any of the above points shall be referenced by ties to acceptable objects and recorded. Any alternations or revisions in the ties shall be so noted and the information furnished to the CONSTRUCTION MANAGER immediately. All computations necessary to establish the exact position of the work from control points shall be made and preserved by the CONTRACTOR. All computations, survey notes and other records necessary to accomplish the work shall be neatly made and shall be made available onsite for review by the CQA CONSULTANT.
- F. During the progress of the construction work, the CONTRACTOR shall be required to furnish all of the surveying and state-out incidental to the proper location by line and grade for each phase of the work. For any operation requiring extreme accuracy, the CONTRACTOR shall restake with pins or other acceptable hubs located directly adjacent to the work at a spacing approved by the CONSTRUCTION MANAGER.

## **PART 2 PRODUCTS**

(Not Used)

**PART 3 EXECUTION**

(Not Used)

**END OF SECTION**

## SECTION 01402

### CONTROL OF WORK

#### PART 1 GENERAL

##### 1.01 AUTHORITY OF THE CONSTRUCTION MANAGER

- A. The CONSTRUCTION MANAGER will decide all questions which may arise as to the quality and acceptability of materials furnished and work performed; all questions which may arise as to the interpretation of the Drawings and Specifications; and all questions as to the satisfactory and acceptable fulfillment of the Contract on the part of the CONTRACTOR.
- B. The OWNER shall have the authority to stop the Work if odor or dust becomes a nuisance.

##### 1.02 AUTHORITY OF THE CQA CONSULTANT

- A. The CQA CONSULTANT employed by the OWNER shall be authorized to monitor all work done and materials and equipment furnished. Such monitoring may extend to all or part of the Work, and to the preparation, fabrication, or manufacture of the materials and equipment to be used. The CQA CONSULTANT will not alter or waive the provisions of the Contract Documents.
- B. The CQA CONSULTANT will keep the CONSTRUCTION MANAGER informed as to the progress of the Work and the manner in which it is being done; also, the CQA CONSULTANT will call the CONTRACTOR's attention to non-conformance with the Contract Documents that the CQA CONSULTANT may have observed. The CQA CONSULTANT will not approve or accept any portion of the Work, issue instructions contrary to the Contract Documents, or act as foreman for the CONTRACTOR. The CQA CONSULTANT may reject defective materials, equipment, or work subject to final decision of the CONSTRUCTION MANAGER.
- C. The CONSTRUCTION MANAGER may delegate additional authority to the CQA CONSULTANT. In such cases, the CONSTRUCTION MANAGER will notify the CONTRACTOR of such action.

##### 1.03 COORDINATION AND INTERPRETATION OF DRAWINGS AND SPECIFICATIONS

- A. The Specifications, General Conditions, Special Conditions, CQA Plan, Contract Change Orders, and all supplementary documents are essential parts of the Contract, and a requirement occurring in one is as binding as though occurring in all. They are intended to be coordinated and to describe and provide for a complete work.
- B. Should it appear that the Work or other matters relative thereto are not sufficiently detailed or explained in the Contract Documents, the CONTRACTOR shall apply to the CONSTRUCTION MANAGER for such further explanations as may be necessary and shall conform to them as part of the Contract.



- C. In the event of a doubt or question arising regarding the true meaning of the Contract Document, reference shall be made to the CONSTRUCTION MANAGER, whose decision thereon shall be final.
- D. In the event of a discrepancy between a drawing and the figures written thereon, and/or the Drawings and the Specifications, the CONTRACTOR shall notify the CONSTRUCTION MANAGER in writing and wait for approval before proceeding. Scaled dimensions shall not be used in the performance of the Work.

## **PART 2 PRODUCTS**

(Not Used)

## **PART 3 EXECUTION**

### **3.01 PERFORMANCE REQUIREMENTS**

- A. The CONTRACTOR shall furnish the CONSTRUCTION MANAGER with every reasonable facility for ascertaining whether or not the Work as performed is in accordance with the requirements and intent of the Specifications and Contract.
- B. Should a work be covered before acceptance or consent of the CONSTRUCTION MANAGER, it must, if required by the CONSTRUCTION MANAGER, be uncovered for examination at the CONTRACTOR's expense.

**END OF SECTION**

## SECTION 01565

### TEMPORARY FACILITIES

#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. The CONTRACTOR shall provide all temporary facilities and utilities required for prosecuting the Work, protection of employees and the public, protection of the Work from damage by fire, weather or vandalism, and such other facilities as may be specified or required by an applicable law, ordinance, rule, or regulation.
- B. The CONTRACTOR must provide their own office space for their needs if necessary. The location of the office shall be approved by the OWNER.

##### 1.02 ELECTRICAL SERVICE

- A. Electrical power is not available at the site. The CONTRACTOR shall arrange for temporary electric connection or supply a generator capable of providing the power required to operate tools or equipment or to provide area lighting as needed. Temporary power whether supplied by a utility company or by a generator shall conform to the requirements of the 1993 National Electrical Code, the 1993 National Electrical Safety Code, and all applicable national standards, local regulations and ordinances.
- B. The allowable hours of generator operation is the same as the regular working hours for the project. All generators shall be fitted with a residential quality muffler.

##### 1.03 FIRST AID

- A. First aid kits meeting the minimum requirements of the Occupational Safety and Health Administration shall be provided in a readily accessible location or locations indicated in the CONTRACTOR's Health and Safety Plan as outlined in Section 01810 of these Specifications.

##### 1.04 CONSTRUCTION FACILITIES

- A. Construction hoists, elevators, scaffolds, stages, shoring and similar temporary facilities shall be of ample size and capacity to adequately support and move the loads to which they will be subjected. Railings, enclosures, safety devices, and controls required by law or for adequate protection of life and property shall be provided.

##### 1.05 STAGING AND SHORING

- A. Temporary supports shall be designed with an adequate safety factor to assure stability and adequate load bearing capacity.
- B. Trenches greater in depth than four (4) feet shall be shored or sloped according to OSHA requirements.

#### **1.06 TEMPORARY ENCLOSURES**

- A. When any activity hazardous to property or the health of employees and the public is in progress, the area of activity shall be enclosed adequately to contain the dust, overspray, or other hazard. In the event there are not permanent enclosures in the area, or such enclosures are incomplete or inadequate, the CONTRACTOR shall provide suitable temporary enclosures.

#### **1.07 WARNING DEVICES AND BARRICADES**

- A. The CONTRACTORS shall adequately identify and guard all hazardous areas, holes, pits, and conditions by visual warning devices and physical barriers. Such devices shall, as a minimum, conform to the requirements of OSHA and Cal-OSHA.

#### **1.08 HAZARDS IN PUBLIC ACCESS AREAS**

- A. Trenches and other essentially continuous excavations in public access areas, running parallel to the general flow of traffic, shall be marked at reasonable intervals by traffic cones, barricades, or other suitable visual markers during daylight hours. During hours of darkness, these markers shall be provided with either torches, flashers or other adequate lights.

#### **1.09 FIRE EXTINGUISHERS**

- A. A sufficient number of fire extinguishers of the type and capacity required to protect the site and ancillary facilities shall be provided in readily accessible locations.

#### **1.10 ODOR CONTROL**

- A. The CONTRACTOR shall comply with the provisions for control of odor and emissions as required by the MDAQMD or the OWNER.

#### **1.11 SANITATION FACILITIES**

- A. CONTRACTOR shall provide and maintain ample field latrines and ablution accommodations in accordance with OSHA requirements for all workers employed on the project under the contract. Field latrines and ablution accommodations shall be provided and maintained in a sanitary condition at all times during the work on this project.

#### **1.12 MATERIAL STORAGE**

- A. A materials storage area shall be designated to the CONTRACTOR by the CONSTRUCTION MANAGER. The CONTRACTOR is responsible for security of all of his materials and equipment.

### **PART 2 PRODUCTS**

(Not Used)

**PART 3 EXECUTION**

(Not Used)

**END OF SECTION**

## SECTION 01810

### SAFETY PROCEDURES

#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. This section establishes minimum safety requirements and guidelines for the performance of the Work.
- B. The CONTRACTOR is advised that decomposing refuse produces landfill gas which is approximately 50 percent methane (natural gas) by volume, and is potentially flammable or explosive.
- C. The CONTRACTOR shall submit a Health and Safety Plan and a copy of their Injury and Illness Prevention Program to the OWNER for review prior to beginning work.
- D. The CONTRACTOR shall hold mandatory daily tailgate safety meetings on the site, as well as formal weekly safety meetings.

##### 1.02 GENERAL REQUIREMENTS

- A. The CONTRACTOR shall have sole responsibility and liability for the safety, efficiency, and adequacy of the CONTRACTOR's personnel, equipment and methods, and for any damage or injury resulting from their failure, or improper maintenance, use, or operation.
- B. The CONTRACTOR shall be solely and completely responsible for the conditions at the Work area arising from the CONTRACTOR's execution of the Work. This requirement shall apply continuously and not be limited to normal working hours.
- C. The CONTRACTOR shall provide all personnel working on the project with orientation and training on the potential hazards anticipated and the appropriate use of safety equipment.
- D. Neither the OWNER nor the CONSTRUCTION MANAGER shall have liability resulting from injury or death to CONTRACTOR's employees or subcontractors and their employees.
- E. A health and safety officer, employed by the CONTRACTOR, shall be present at all times during construction of underground facilities. The health and safety officer may be the site superintendent or other responsible regular employee of the CONTRACTOR provided he has had special health and safety training, and shall have responsibility for the enforcement of the Health and Safety Plan, particularly as it applies to drilling activities. The health and safety officer shall be identified by name in the Health and Safety Plan.
- F. Many gases are heavier than air and settle in low areas such as trenches and excavations, therefore additional precautions shall be observed in these areas. Specifically, the need for constant O<sub>2</sub> monitoring, forced ventilation, combustible gas

monitoring, VOC monitoring, respiratory protective equipment, etc. shall be determined by the CONTRACTOR. The CONSTRUCTION MANAGER may impose additional requirements when deemed necessary for worker safety.

### **1.03 HEALTH AND SAFETY PLAN**

- A. The CONTRACTOR shall develop and maintain for the duration of work activities at the site, a written, site specific Health and Safety Plan for landfill operations that will effectively incorporate and implement all applicable requirements. The plan will meet the requirements of CCR Title 8 Section 5192.
- B. In addition to requirements set forth in other sections, the CONTRACTOR's Health and Safety Plan shall contain provisions for aspects of protection against bodily injury from heavy construction equipment, tools and equipment required to construct the system.
- C. The Health and Safety Plan shall include the location and route to the nearest hospital or emergency facility. All CONTRACTOR employees and subcontractors working on the project shall be thoroughly familiar with the emergency route.
- D. In the event the Health and Safety Plan is determined by the CONSTRUCTION MANAGER, OWNER or the State or Federal Regulatory Agencies to be inadequate to protect the employees and the public, the plan shall be modified prior to the beginning of the Work to meet the minimum requirements of the OWNER or the State or Federal Regulatory Agencies at no additional cost to the OWNER.
- E. Acceptance of the CONTRACTOR's Health and Safety Plan by the OWNER does not release the CONTRACTOR of liability in the event of an accident or injury, nor does it place any liability on the CONSTRUCTION MANAGER or OWNER.
- F. Provisions shall be made to protect against ingestion, absorption or inhalation of hazardous compounds and for the handling of refuse in a safe, sanitary, and proper manner.
- G. The CONTRACTOR's Health and Safety Plan shall contain trenching and excavation safety guidelines particular to landfill work.

### **1.04 REGULATORY REQUIREMENTS**

- A. The CONTRACTOR shall comply with provisions of safety regulatory bodies including, but not necessarily limited to:
  - 1. OSHA/Cal-OSHA regulations for construction
  - 2. 29 Code of Federal Regulations (CFR) 1926/1910 and CFR 1910.120
  - 3. Title 8 California Code of Regulations, in particular Section 5192.
  - 4. All other applicable federal, state, county and local laws, ordinances, codes, the requirements
- B. If any of these requirements are in conflict, the more stringent requirement shall apply. The CONTRACTOR's failure to be thoroughly familiarized with the aforementioned safety and health provisions shall not relieve the CONTRACTOR of

responsibility for full compliance with the obligations and requirements set forth herein.

- C. The CONTRACTOR shall conform to the rules and regulations of the State Construction Safety regulations pertaining to excavations and trenches. A copy of the regulations is available at the OWNER.

#### **1.05 SPECIAL SAFETY CONSIDERATION RELATED TO LANDFILL WORK**

- A. Portions of the Work involve excavation and removal of and construction near hazardous waste.
- B. The landfill may contain leachate water contaminated with substances found in the landfill which may be corrosive, toxic, carcinogenic, mutagenic or otherwise hazardous.

#### **PART 2 PRODUCTS**

(Not Used)

#### **PART 3 EXECUTION**

##### **3.01 GENERAL REQUIREMENTS**

- A. The CONTRACTOR shall assume full responsibility to assure that during construction his employees, subcontractors and their employees follow the Health and Safety Plan.
- B. The CONTRACTOR shall hold mandatory weekly safety meetings on the site. The CONTRACTOR shall notify the CONSTRUCTION MANAGER of the time and place of all meetings and allow the CONSTRUCTION MANAGER to participate. Meetings should reiterate safety measures to be taken and discuss any violations committed and preventive measures to avoid future violations.
- C. The CONTRACTOR shall require all personnel on the site to wear the appropriate personnel protective equipment such as steel toe boots, hard hats, orange safety vests, safety belts and lanyards, and others.
- D. The CONTRACTOR shall provide appropriate fall protection (i.e., harness and shock absorbing lanyard) that must be worn and secured to a stationary object when working within a distance of ten 10 feet of an excavation greater than eight (8) inches in diameter or deeper than four (4) feet.
- E. No smoking or consumption of alcohol or any drug which could impair sight, balance or judgment is permitted on the job.

##### **3.02 TRENCHING SAFETY**

- A. The CONTRACTOR shall complete each excavated trench prior to the end of the working day. A trench shall be considered complete if it has been backfilled to the landfill surface.

- B. Any time excavations and trenching exceed four (4) feet in depth, shoring, bracing or sloping of the side walls is required prior to entry. If sloping is the method used, side walls of the trench shall be sloped at a 2:1 slope (Cal-OSHA requirement).
- C. Welding is to be avoided within the barricaded area. If HDPE pipe welding is performed in the trench, continuous methane monitoring shall be performed.
- D. Solvent cleaning, gluing or bonding of pipe shall be done, to the extent practicable, outside the trench.
- E. All trenches shall be backfilled as soon as practical after excavation, and under no circumstances shall a trench remain open after the crew has left the vicinity of the trench. A maximum of 300 feet of trench may be exposed at any one time. All exposed refuse must be covered at the end of each day using cover soil or a tarp.
- F. Electric motors shall not be used in trenches. Pneumatic operated tools shall be used in the trench.

### **3.03 VIOLATIONS**

- A. Should any health and safety violations be called to the CONTRACTOR's attention by anyone, the CONTRACTOR shall immediately correct the violations.
- B. If the CONTRACTOR violates any health and safety rule or regulation, the OWNER may issue an order to stop all work until the violations are remedied. The CONTRACTOR shall not be entitled to any extension of the time or any claim for damage or to any compensation for either the directive or the work suspension order. A decision by the OWNER not to order discontinuance of any or all of the CONTRACTOR's operations shall not relieve the CONTRACTOR of responsibility for safety.

**END OF SECTION**



## SECTION 02105

### EROSION CONTROL

#### PART 1 GENERAL

##### 1.01 DESCRIPTION

- A. This section describes the general requirements for erosion control measures associated with lining materials for drainage channels.

#### PART 2 PRODUCTS

##### 2.01 EROSION CONTROL BLANKET

Permanent Turf Reinforcement Mat shall be Propex Landlok 407, or equivalent. To be used in Type IB, II and IV channels.

Temporary Erosion Control Mat shall be SI Geosolutions ECB CS2, or equivalent. To be used in Type IA channels.

#### PART 3 EXECUTION

##### 3.01 GENERAL

- A. Grade and compact area of installation and remove all rocks, clods, vegetation or other obstructions so that the installed mat will have direct contact with soil surface. Prepare seedbed by loosening 2-3 inches of topsoil. Incorporate amendments such as fertilizer into soil.
- B. For temporary erosion control mat, apply seed to soil surface before installing blanket/mat. For permanent erosion control mat, apply seeding after installation and prior to filling mat with soil.
- C. The CONTRACTOR shall install the permanent and temporary control mats in accordance with the manufacturer's recommendations. In general the installation should include:
1. Anchor trenches or check slots (6-inches deep) at 30 foot intervals along the trench.
  2. Longitudinal anchor trenches (4-inches deep) to secure outside edges.
  3. Anchor erosion control mat with U-shaped wire staples. Staples shall be a minimum of 6-inches in length and have sufficient ground penetration to resist pullout. Longer anchors may be required. Anchors for the permanent erosion control mat shall be installed with a minimum of 2 anchors per

square yard. Temporary erosion control mats shall be installed with a minimum of 1.5 anchors per square yard.

4. After installation of permanent erosion control mat, apply seed and apply  $\frac{1}{2}$  to  $\frac{3}{4}$  inches of fine soil into the mat to completely fill the voids. Use backside of rake, or similar, to smooth soil fill in order to just expose the top netting.

**END OF SECTION**

## SECTION 02110

### SITE CLEARING, GRUBBING AND STRIPPING

#### PART 1 GENERAL

##### 1.01 DESCRIPTION

- A. This section describes the general requirements for site clearing, grubbing and stripping associated with final closure construction of Landfill B-18 at the Kettleman Hills Facility.
- B. Clearing, grubbing and stripping shall be performed to remove organic, soft, loose, and deleterious materials and expose a firm, unyielding subgrade.

##### 1.02 RELATED SECTIONS

- A. Section 02200 - Earthwork
- B. Section 02751 - HDPE Geomembrane

#### PART 2 PRODUCTS

- A. Organic, soft, loose and deleterious materials includes, but is not limited to, vegetative growth, non-engineered fills, alluvial deposits, soft, loose, or saturated subgrade soils, refuse, and construction debris.

#### PART 3 EXECUTION

##### 3.01 PROTECTION

- A. Locate, identify, and protect utilities that remain from damage.
- B. Protect groundwater monitoring wells and piezometers, and landfill gas extraction wells and monitoring probes from damage or displacement.

##### 3.02 CLEARING

- A. Clear areas required for access to site and execution of work.
- B. Earthwork CONTRACTOR shall remove all organic and deleterious material, and trash from the subgrade surface. Vegetative growth greater than 1 inch in dimension shall be removed to a depth of 6 inches below the subgrade surface.
- C. The Earthwork CONTRACTOR shall consider that clearing, grubbing, and stripping will necessitate the use of manual labor to remove all organic and deleterious material from the subgrade surface.
- D. The Earthwork CONTRACTOR shall remove soft, loose, or saturated materials as approved by the CQA CONSULTANT. The materials shall be removed until a firm, unyielding subgrade, approved by the CQA CONSULTANT, is exposed.

- E. All removed materials shall be disposed of onsite in an area designated by the PROJECT MANAGER. No accumulation of flammable material shall remain on or adjacent to the construction area.
- F. The Earthwork CONTRACTOR shall expose existing liner terminations as required on the Drawings. The Work may require hand excavation to avoid damage to the existing liner. Any damage to the existing liner shall be repaired by the Earthwork CONTRACTOR at no additional cost to the OWNER.

**END OF SECTION**

## **SECTION 02200**

### **EARTHWORK**

#### **PART 1 GENERAL**

##### **1.01 SUMMARY**

- A. This section describes the general requirements for earthworks associated with the final closure construction of Landfill B-18 at the Kettleman Hills Facility.
- B. The Earthwork CONTRACTOR shall furnish all labor, materials, equipment and incidentals necessary to perform all excavation, backfilling, compaction and grading required to complete the work shown on the Drawings and specified herein. The Work shall include, but not necessarily be limited to, survey and staking, borrow excavation and hauling, excavation for trenches, fill placement and compaction, grading, and all related work.
- C. The Earthwork CONTRACTOR shall comply with the safety procedures given in Section 01810 of these Specifications.

##### **1.02 RELATED SECTIONS**

- A. Section 01300 - Submittals
- B. Section 01400 - Construction Quality Control
- C. Section 02110 - Site Clearing, Grubbing and Stripping.
- D. Section 02720 – Drainage Facilities
- E. Section 02751 - HDPE Geomembranes

##### **1.03 REFERENCE STANDARDS**

- A. American Society for Testing and Materials (ASTM), latest editions:
  - 1. ASTM D422 - Test Method for Particle Size Analysis of Soils.
  - 2. ASTM D1556 - Test Method for Density of Soil In-Place by the Sand Cone Method.
  - 3. ASTM D1557 - Test Methods for Moisture-Density Relations of Soils and Soil Aggregate Mixtures Using 10-lb. Rammer and 18-inch Drop.
  - 4. ASTM D2216 - Standard Test Method for Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass
  - 5. ASTM D2419 - Test Method for Sand Equivalent Value of Soil/Fine Aggregate.
  - 6. ASTM D2497 - Standard Test Method for Classification of Soils for Engineering Purposes.
  - 7. ASTM D2922 - Test Methods for Density of Soil and Soil Aggregate in Place by Nuclear Methods (Shallow Depth).

8. ASTM D2937 - Standard Test Method for Density of Soil in Place by the Drive-Cylinder Method
  9. ASTM D3017 - Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth).
- B. Standard Specifications for Public Works Construction (SSPWC).

#### 1.04 QUALITY ASSURANCE/CONTROL

- A. The Earthwork CONTRACTOR shall adhere to the requirements of Section 01400 of these Specifications.
- B. Compaction testing of engineered fill and backfill shall be performed by the CQA CONSULTANT. Testing shall be performed at locations to be determined by the CQA CONSULTANT, in order to determine if the soils meet the compaction requirements. Costs for testing to verify compaction and soil moisture content will be assumed by the OWNER. The cost of retesting, should corrections to construction be required, shall be the responsibility of the Earthwork CONTRACTOR.
- C. The OWNER shall have complete authority to order immediate stoppage of work due to use of improper construction procedures, or for any reason that in his sole opinion, may result in a defective work.

#### 1.05 DEFINITIONS

- A. Excavation: Consists of the removal of material encountered to subgrade elevations and the reuse or disposal of materials removed.
- B. Subgrade: The surface upon which structures/systems/fills are constructed.
- C. Borrow: Soil material obtained from other than the excavation.
- D. Unauthorized excavation consists of removing materials beyond indicated subgrade elevations or dimensions without direction by the PROJECT MANAGER. Unauthorized excavation, as well as remedial work directed by the PROJECT MANAGER, shall solely be at the Earthwork CONTRACTOR's expense.
- E. Utilities include on-site above ground and underground pipes, conduits, ducts, and cables, as well as underground services.

#### 1.06 SAFETY

- A. CONTRACTOR is solely responsible for performing work in a safe manner and complying with all applicable local, state and federal codes, ordinances, laws, and regulations.
- B. CONTRACTOR shall comply with the requirements of the Health and Safety Plan.

## **PART 2 PRODUCTS**

### **2.01 MATERIALS**

#### **A. Structural Fill**

1. Structural Fill shall be removed from the on-site borrow area(s) designated by the OWNER. Material shall be predominantly free from roots, wood, organic matter, refuse or other deleterious matter, and shall not contain particles over 6 inches in greatest dimension.
2. The OWNER has designated on-site borrow source(s) for the CONTRACTOR. The CONTRACTOR shall be responsible for excavating, loading, hauling, placing and compacting the material from the designated borrow source(s).

#### **B. Foundation Layer**

1. Foundation Layer is structural fill placed within 1-foot of HDPE geomembrane.
2. In addition to the structural fill requirements, Foundation layer shall not contain particles over 1 inch in greatest dimension and have a hydraulic conductivity of less than or equal to  $1 \times 10^{-5}$  cm/sec as determined by ASTM D5084.

#### **C. Vegetative Cover**

1. Vegetative Cover shall be removed from the on-site borrow area(s) designated by the OWNER. Material shall contain no particles over 3 inches in greatest dimension.
2. The OWNER has designated on-site borrow source(s) for the CONTRACTOR. The CONTRACTOR shall be responsible for excavating, loading, hauling, placing and compacting the material from the designated borrow source(s).

#### **D. Trench Backfill**

1. Trench Backfill shall be removed from the on-site borrow area(s) designated by the OWNER. Material shall be predominantly free from roots, wood, organic matter, refuse or other deleterious matter, and shall not contain particles over 1 inch in greatest dimension.
2. The OWNER has designated on-site borrow source(s) for the CONTRACTOR. The CONTRACTOR shall be responsible for excavating, loading, hauling, placing and compacting the material from the designated borrow source(s).

#### **E. Water**

1. Water shall be potable water or reclaimed water approved for use by OWNER.
2. The OWNER will provide water for dust control and soil preparation to the Earthwork CONTRACTOR at no cost to the Earthwork CONTRACTOR.

3. The CONTRACTOR shall only obtain water from sources designated by the OWNER.

### **PART 3 EXECUTION**

#### **3.01 GENERAL**

- A. The Earthwork CONTRACTOR shall be solely responsible for the satisfactory completion of all earthwork in accordance with the Drawings and Specifications.
- B. Equipment used in the excavation, transport, placement and compaction of all materials used in construction will be standard of practice grading machinery of known specifications suitable for performing the required work in a timely and efficient manner.
- C. All material considered by the CQA CONSULTANT to be unsuitable for use in the construction of the earthwork shall be removed. All materials incorporated as part of engineered fill must be inspected and placement must be observed by the CQA CONSULTANT. Unsuitable material shall be disposed of in the designated area.
- D. Where work is interrupted by heavy rains, earthwork operations shall not be resumed until observations and field tests by the CQA CONSULTANT indicate the moisture content and density of the in-place fills and/or materials intended for placement are within the specified requirements.
- E. If any unanticipated earth conditions of an adverse or potentially adverse nature are encountered during grading, the Earthwork CONTRACTOR shall immediately notify the CQA CONSULTANT. The CQA CONSULTANT and DESIGN ENGINEER shall investigate, analyze, and make recommendations to mitigate these conditions.
- F. Throughout construction, all excavated and/or fill areas shall be graded to provide positive drainage and prevent ponding of water. Surface water shall be controlled to avoid damage to adjoining properties or to finished work on the site.
- G. No heavy equipment shall be permitted to operate within 3 feet of existing wellheads or piping. Compaction of material within these limits shall be completed with hand equipment.
- H. The Earthwork CONTRACTOR shall apply water to any exposed earthen areas during construction to minimize airborne dust. This shall include active and inactive excavation areas, haul roads, and any nonvegetated stockpiles. The Earthwork CONTRACTOR shall be responsible for complying with all state and local regulations regarding dust and/or air quality.
- I. Earthwork CONTRACTOR **shall not** use "paddle-wheel" (i.e., Caterpillar 613 or equivalent) equipment to excavate soils.
- J. Earthwork CONTRACTOR shall provide manned traffic control (e.g., flagman) at locations identified by Owner and/or Contractor as being a potential safety hazard.



### **3.02 CONTROL OF WATER**

- A. The Earthwork CONTRACTOR shall excavate and backfill in a manner and sequence that will provide proper drainage at all times. The Earthwork CONTRACTOR shall remove all water, including runoff and run-on collected from rainwater encountered during excavation, to a location approved by the PROJECT MANAGER, by pumps, drains, and other approved methods.
- B. The Earthwork CONTRACTOR shall take all necessary precautions to preclude the accidental discharge of fuel, oil, etc. and to prevent such accidents that may endanger the environment. The Earthwork CONTRACTOR will be responsible for the cost of remediating the results of any such discharges or accidents.

### **3.03 BORROW**

- A. CONTRACTOR shall submit the proposed limits of the borrow area to the OWNER for approval prior to the commencement of the Work. The maximum limits of the borrow area are shown on the Drawings.
- B. The gradients of the borrow slopes and the depth of the borrow excavation should not exceed those specified on the Drawings. If the slopes are constructed steeper or the depth of the borrow excavation is greater than that specified on the Drawings, the CONTRACTOR shall reconstruct the slopes/refill the bottom to the gradients/depth specified by backfilling and compacting material in accordance with the requirements for engineered fill in this Section. The cost to reconstruct the slopes/refill the bottom will be borne solely by the CONTRACTOR.
- C. The CONTRACTOR shall maintain a secure work site at all times.

### **3.04 STRUCTURAL FILL**

- A. Prior to placing structural fill, CONTRACTOR shall clear and grub the area in accordance with Section 02110 of these Specifications. CONTRACTOR shall also remove uncertified existing fills, disturbed soils and deleterious materials from the area to the satisfaction of the CQA CONSULTANT.
- B. The ground surface (i.e. areas with less than 10% slope) to receive fill shall be over excavated a minimum of 2 feet. The base of the excavation shall be scarified to a depth of 8 inches. The scarified ground surface shall then be brought to within 3 percent of optimum moisture content, mixed as required, and compacted to a minimum of 90 percent of the maximum dry density as determined by ASTM D1557. Excavated soil may be used for filling the excavation if placed in accordance with the structural fill requirements. If the scarified zone is greater than 12 inches in depth, the excess shall be removed, placed in loose lifts not to exceed 8 inches in loose thickness. Prior to fill placement, the ground surface to receive fill shall be stabilized and inspected by the CQA CONSULTANT.
- C. Fill placed against existing slopes (i.e. areas with greater than 10% slope) shall be keyed into the slope. Keys shall extend a minimum of 6 feet horizontally into the existing slope. The keys shall form a series of steps in the existing fill.

- D. Fill shall be placed in loose lifts not to exceed 8-inches thick, brought to a uniform moisture content within 4 percent of optimum (3 percent for Foundation Layer), and compacted to 90 percent of the maximum dry density as determined by ASTM D1557.
- E. Where tests indicate the moisture content or density of any layer of fill or portion thereof is below the Project requirements, the particular layer or portion thereof shall be reworked until the required moisture or density has been attained. No additional fill shall be placed over an area until the prior fill lift has been tested and meets the present requirements to the satisfaction of the CQA CONSULTANT.
- F. In the event of rain or other reason, if the moisture content of previously placed fill material or processed soils intended for placement is more than 4 percent above optimum as determined by ASTM D1557, the fill material shall be aerated by blading, disking, or other satisfactory method until the moisture content complies with the requirements of this Section. Any previously compacted materials which are disturbed (aerated, bladed, etc.) to reduce or increase the moisture content must be recompacted to the Specifications and to the satisfaction of the CQA CONSULTANT once specified moisture contents are attained.

### 3.05 VEGETATIVE COVER

- A. Vegetative cover layer shall be placed as shown on the Drawings. Soils shall not be placed over geosynthetic materials at ambient temperatures below 41 degrees F nor above 100 degrees F unless otherwise specified. The soils shall be placed in a manner which does not cause excessive movement or wrinkling of the geosynthetics.
- B. Vegetative cover layer shall be placed and compacted by tracking with the low ground-pressure pressure dozer used for placement or other relatively light-compaction equipment wherever the soil thickness is less than 3 feet. The equipment used to spread and compact the backfill shall not exert a ground pressure in excess of 6 psi on no less than 1 foot of material. Manually operated compaction equipment may be required in constricted locations and directly adjacent to sensitive structures.
- C. Hauling and spreading equipment for the vegetative cover layer shall operate on a minimum of 3 feet of soil above a geosynthetic layer. Low-ground pressure (i.e., less than 6 psi) spreading equipment may operate on a minimum of one foot of soil above a geosynthetic layer.
- D. Fill shall be placed in loose lifts not to exceed 8-inches thick, brought to a uniform moisture content within 3 percent of optimum, and compacted between 85 to 90 percent of the maximum dry density as determined by ASTM D1557.
- E. Where tests indicate the moisture content or density of any layer of fill or portion thereof is below the Project requirements, the particular layer or portion thereof shall be reworked until the required moisture or density has been attained. No additional fill shall be placed over an area until the prior fill lift has been tested and meets the present requirements to the satisfaction of the CQA CONSULTANT.
- F. In the event of rain or other reason, if the moisture content of previously placed fill material or processed soils intended for placement is more than 3 percent above

optimum as determined by ASTM D1557, the fill material shall be aerated by blading, disking, or other satisfactory method until the moisture content is within four percent of optimum moisture content as determined by ASTM D1557. Any previously compacted materials which are disturbed (aerated, bladed, etc.) to reduce or increase the moisture content must be recompacted to the Specifications and to the satisfaction of the CQA CONSULTANT once specified moisture contents are attained.

### **3.06 SURFACE PREPARATION**

- A. All surfaces to be overlain by geosynthetics shall be smooth, uniformly sloped (minimum 5%), firm, and free of rocks, protrusions, or depressions greater than 0.5-inch in maximum dimension. The Earthwork CONTRACTOR shall consider that manual removal/repair of unacceptable areas may be required and shall be considered inherent to the work described herein.

### **3.07 TRENCH EXCAVATION AND BACKFILL**

- A. All trenches shall be excavated to lines and grades and dimensions indicated on the Drawings. All trench excavation, backfill, and compaction shall be in accordance with pertinent provisions of this Section.
- B. All pipe work placed inside the trenches shall have a minimum of 8-inch clearance from any protrusions from the trench side walls or bottom.
- C. The Earthwork CONTRACTOR shall backfill excavated trenches as promptly as progress of the work permits and immediately after the pipe has been laid, jointed, and tested.
- D. The trench bottom shall be compacted to provide a uniform bed for the pipe. Backfill material shall be placed around the pipe and shall be compacted by hand-tamping, or methods acceptable to the CQA CONSULTANT.
- E. The Earthwork CONTRACTOR shall compact the select engineered fill for trench backfill to at least 90 percent of the maximum dry density and within 4 percent of the optimum moisture content as determined in accordance with ASTM D1557.
- F. Trench backfill shall be placed as shown on the Drawings. The backfill shall not be placed at ambient temperatures below 41°F nor above 100°F unless otherwise specified. The material shall be placed in a manner that does not cause movement or excessive wrinkling of, or induce excessive wrinkling of the geosynthetics. The CONTRACTOR shall not operate equipment directly on any geosynthetics.

### **3.08 TOLERANCES**

- A. All material limits shall be constructed within a tolerance of  $\pm 1.0$  ft for horizontal state plan coordinates, 0 to +0.1 ft vertical for reference to mean sea level (MSL), and 0 to +0.1 ft where dimensions are shown or specified as a minimum. The plane of the surface shall not vary more than 0.10 feet when measured with a 10-foot straight edge.

### **3.09 EXCAVATION BELOW GRADE**

- A. All excavation shall be performed within the limits of the work to the lines, grades, and elevations indicated and specified herein. The Earthwork CONTRACTOR shall not excavate or remove materials beyond indicated subgrade elevations or dimensions without the approval of the PROJECT MANAGER. The Earthwork CONTRACTOR shall backfill and compact any unauthorized excavation to the satisfaction of the PROJECT MANAGER at no additional cost to the OWNER.
- B. When acceptable to the PROJECT MANAGER, lean concrete may be used to bring the bottom elevation of excavations under footings or trenches to correct elevations.

**END OF SECTION**

## SECTION 02751

### HDPE GEOMEMBRANES

#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. This section describes the requirements for the manufacture, supply, installation, and quality control (QC) of high density polyethylene (HDPE) geomembrane associated with the final closure construction at the Kettleman Hills Facility, Landfill B-18.

##### 1.02 RELATED SECTIONS

- A. Section 02200 - Earthwork

##### 1.03 REFERENCES

- A. Latest Version of American Society for Testing and Materials (ASTM) standards:
1. ASTM D638 - Test Method for Tensile Properties of Plastics
  2. ASTM D792 - Specific Gravity (Relative Density) and Density of Plastics
  3. ASTM D1004 - Test Method for Initial Tear Resistance of Plastic Film and Sheeting
  4. ASTM D1238 - Test Method for Flow Rates of Thermoplastics by Extrusion Plastometer
  5. ASTM D1505 - Test Method for Density of Plastics by Density-Gradient Technique
  6. ASTM D1603 - Test Method for Carbon Black in Olefin Plastics
  7. ASTM D3895 - Test Method for Oxidative Induction Time of Polyolefins by Thermal Analysis
  8. ASTM D4218 - Test Method for Determination of Carbon Black Content in Polyethylene Compounds by the Muffle-Furnace Technique
  9. ASTM D4833 - Test Method for Index Puncture Resistance of Geotextiles, Geomembranes and Related Products
  10. ASTM D5199 - Test Method for Measuring Nominal Thickness of Geotextiles and Geomembranes
  11. ASTM D5321 - Test Method for Determining the Coefficient of Soil and Geosynthetic or Geosynthetic and Geosynthetic Friction by the Direct Shear Method

12. ASTM D 5397 - Procedure to Perform a Single Point Notched Content Tensile Load – Appendix (SP-NCTL) Test
13. ASTM D5596 - Test Method for Microscopic Evaluation of the Dispersion of Carbon Black in Polyolefin Geosynthetics
14. ASTM D5721 - Practice for Air-Oven Aging of Polyolefin Geomembranes
15. ASTM D5885 - Test Method of Oxidative Induction Time of Polyolefin Geosynthetics by High Pressure Differential Scanning Colorimetry
16. ASTM D5994 - Test Method for Measuring Core Thickness of Textured Geomembranes

B. Geosynthetics Research Institute (GRI):

1. GRI-GM 10 - Specification for the Stress Crack Resistance of Geomembrane Sheet
2. GRI-GM11 - Accelerated Weathering of Geomembranes Using a Fluorescent UVA – Condensation Exposure Device
3. GRI-GM12 - Measurement of the Asparity Height of Textured Geomembranes Using a Depth Gage.
4. GRI-GM13 - Test Properties, Testing Frequency and Recommended Warranty for High Density Polyethylene (HDPE) Smooth and Textured Geomembranes

#### 1.04 PRE-QUALIFICATION

- A. The Geosynthetic CONTRACTOR shall pre-qualify for geomembrane installation by providing the following documentation:
1. The Geosynthetic CONTRACTOR shall have a minimum of 10,000,000 square feet (sf) of polyethylene geomembrane cumulative installation experience.
  2. The Geosynthetic CONTRACTOR shall provide at least three references from prior installation projects in excess of 500,000 sf including the following information:
    - a. Client's name, address, phone number and contact or representatives name.
    - b. Project site and description.
    - c. Geomembrane type and quantity installed.

#### 1.05 SUBMITTALS

- A. Submittals shall be provided in general accordance with Section 01300.
- B. HDPE Resin: Furnish the following in writing to the CQA CONSULTANT a minimum of seven calendar days prior to geomembrane shipment to the site:

1. Statement of production dates and origin of resin used to manufacture the geomembrane for the project.
  2. Certification stating all resin is from the same manufacturer and that no reclaimed polymer was added to the resin during the manufacturing of the geomembrane and that recycled polymer does not exceed 2 percent by weight.
  3. Copies of the quality control certificates issued by the manufacturer and resin supplier indicating that the resin used to manufacture the geomembrane meets these specifications. These shall contain manufacturing quality control test results including specific gravity (ASTM D792 or D1505) and melt index (ASTM D1238, Condition E).
- C. Manufacturing Quality Control: A copy of the manufacturer's quality control program shall be submitted to the CQA CONSULTANT a minimum of seven calendar days prior to geomembrane shipment to the site. Quality control testing shall be performed by the manufacturer in accordance with GRI-GM13 and as approved by the CQA CONSULTANT. Prior to delivery the following shall be submitted to the CQA CONSULTANT for review:
1. Certificates for each shift's production of geomembrane.
  2. Copies of quality control certificates issued by the manufacturer. The quality control certificates shall include:
    - a. Roll numbers and identification;
    - b. Sampling procedures; and
    - c. Results of quality control tests, including descriptions of the test methods used.
  3. The results of the manufacturing quality control tests shall meet or exceed the property values listed in Table 02751-1.
  4. Geomembrane delivery, storage, handling and installation instructions.
  5. Extrudate Beads and/or Rod:
    - a. Statement of production dates.
    - b. Certification stating all extrudate is from one manufacturer, is the same resin type, and was obtained from the same resin supplier as the resin used to manufacture the geomembrane rolls.
    - c. Copies of quality control certificates issued by the manufacturer including test results for specific gravity ASTM D792 and melt index ASTM 1288 Condition E.
- D. Geomembrane Installer: Prior to mobilization of the Geosynthetic CONTRACTOR to the site, the following information shall be submitted:

1. Shop drawings indicating panel layout and field seams 14 calendar days prior to installation of geomembrane.
2. Installation schedule.
3. Copy of Geosynthetic CONTRACTOR's letter of approval or license by the geomembrane manufacturer.
4. Installation capabilities, including:
  - a. Information on equipment proposed for this project;
  - b. Average daily production anticipated for this project; and
  - c. Quality control procedures.
5. Provide copies of the quality control/quality assurance program for the manufacturer of the geomembrane liner.
6. Resume of the superintendent to be assigned to this project, including dates and duration of employment.
7. Resumes of all personnel who will perform seaming operations on this project, including dates and duration of employment.
8. The installation crew shall have the following experience.
  - a. The superintendent shall have supervised the installation of a minimum of 2,000,000 ft<sup>2</sup> of polyethylene geomembrane and 500,000 ft<sup>2</sup> of geotextile.
  - b. The master seamer shall have experience seaming a minimum of 1,000,000 ft<sup>2</sup> of polyethylene geomembrane using the same type of seaming apparatus to be used at this site.
  - c. All other seaming personnel shall have seamed at least 100,000 ft<sup>2</sup> of polyethylene geomembrane using the same type of seaming apparatus to be used at this site. Personnel who have seamed less than 100,000 ft<sup>2</sup> of polyethylene geomembrane shall be allowed to seam only under the direct supervision of the master seamer or Superintendent.
- E. During the installation, the Geosynthetic CONTRACTOR shall be responsible for the timely submission to the CQA CONSULTANT of subgrade acceptance certificates, signed by the Installer, for each area to be covered by geomembrane.
- F. The Geosynthetic CONTRACTOR shall furnish the OWNER upon completion of the project:
  - I. A warranty provided by the manufacturer in accordance with GRI-GM13 against defects in material. Warranty conditions concerning limits of liability will be evaluated and must be acceptable to the OWNER.



2. A 1-year warranty provided by the Geosynthetic CONTRACTOR against defects in workmanship. Warranty conditions concerning limits of liability will be evaluated and must be acceptable to the OWNER.
  3. As-built panel drawings in compliance with Section 01400.
- E. Certificate of calibration less than 12 months old shall be submitted prior to installation for all field tensiometers.

## 1.06 QUALITY ASSURANCE

- A. Perform work in accordance with Section 01400, the Geosynthetic CONTRACTOR's Quality Control Program, and CQA Plan.

## PART 2 PRODUCTS

### 2.01 MATERIALS

- A. The geomembrane shall be comprised of high density polyethylene (HDPE) material as indicated on the drawings, manufactured of new, first-quality products designed and manufactured specifically for the purpose of liquid containment in hydraulic structures.
- B. The geomembrane shall be produced free of holes, blisters, undispersed raw materials, or any sign of contamination by foreign matter. Any such defect shall be repaired in accordance with the repair procedures in Article 3.06.
- C. The geomembrane shall be manufactured with a minimum of 15.0 feet seamless width. There shall be no factory seams.
- D. The geomembrane shall be HDPE 40-mil thick and textured on both sides as indicated on the Drawings.
- E. The geomembrane shall be supplied in rolls. Folds will not be permitted.
- F. Specifications for the HDPE geomembrane properties are presented in Table 02751-1.
- G. Resin:
1. Shall be HDPE, new, first quality, compounded and manufactured specifically for producing HDPE geomembrane.
  2. Do not intermix resin types.
  3. Shall meet the following additional requirements:

Test	Test Designation	Minimum Frequency	Requirements
Specific Gravity <sup>(1)</sup>	ASTM D 792 Method A	(2)	≥ 0.932
Melt Index	ASTM D 1238 Condition E	(2)	≤ 1.0 g per 10 minutes

Notes:  
(1) Resin without carbon black  
(2) 1 test per resin batch

H. Extrudate Rod or Bead:

1. Shall be made from same resin as the geomembrane.
2. Additives shall be thoroughly dispersed.
3. Shall be free of contamination by moisture or foreign matter.
4. Shall meet the following requirements:

Test	Test Designation	Minimum Frequency	Requirements
Specific Gravity	ASTM D 792 Method A	(1)	≥ 0.940
Carbon Black Content	ASTM D 1603	(1)	2-3%
Melt Index	ASTM D 1238 Condition E	(1)	≤ 1.0 g per 10 minutes
Notes: (1) 1 test per resin batch.			

**2.02 DELIVERY, STORAGE AND HANDLING**

- A. Handling, storage, and care of the geomembrane following transportation to the site shall be the responsibility of the Geosynthetic CONTRACTOR. The Geosynthetic CONTRACTOR shall be liable for all damage to the materials incurred prior to final acceptance of the liner system by the CQA ENGINEER.
- B. Conform to the manufacturer's requirements to prevent damage to geomembrane.
- C. Delivery:
  1. Deliver materials to the site only after the CQA CONSULTANT and the OWNER approve required submittals.
  2. All rolls of geomembrane delivered to the site shall be identified at the factory with the following:
    - a. Manufacturer's name
    - b. Product identification and thickness
    - c. Lot number
    - d. Roll number
    - e. Roll dimensions

3. Separate damaged rolls from undamaged rolls and store at locations designated by the OWNER until proper disposition of material is determined by the OWNER the CQA CONSULTANT.
4. The OWNER will be the final authority regarding damage.
5. Separate rolls without proper documentation and store until CQA CONSULTANT approval is received.

D. On-Site Storage:

1. Store in space allocated by the OWNER.
2. Protect from puncture, dirt, grease, water, moisture, mud, mechanical abrasions, excessive heat or other damage.
3. Store on level prepared surface (not on wooden pallets).
4. Stack per manufacturer's recommendation but no more than three rolls high.

E. On-Site Handling:

1. Use appropriate handling equipment to load, move or deploy geomembrane rolls. Appropriate handling equipment includes cloth chokers and spreader bar for loading, spreader and roll bars for deployment. Dragging panels on ground surface will not be permitted.
2. Do not fold geomembrane material; folded material shall be rejected.
3. The Geosynthetic CONTRACTOR is responsible for storage, and transporting material from storage area to liner facility.

F. Damaged Geomembrane:

1. Geomembrane damage will be documented by the CQA CONSULTANT.
2. Damaged geomembrane shall be repaired, if possible, in accordance with these specifications or shall be replaced at no additional cost to the OWNER.

## 2.03 EQUIPMENT

A. Welding equipment and accessories shall meet the following requirements:

1. Equipped with gauges showing temperatures both in apparatus and at nozzle (extrusion welder) or at wedge (fusion welder).
2. Maintain adequate number of welding apparatus to avoid delaying work.
3. Use power source capable of providing constant voltage under combined-line load.

4. Provide secondary containment to catch spilled fuel under electric generator, if located on geomembrane.
- B. Provide calibrated tensiometer capable of quantitatively measuring geomembrane strength:
1. Equipped with gauge accurate to  $\pm 2$  lbs per inch of geomembrane width and capable of pulling at 2 inches per minute and 20 inches per minute.
  2. Provide one inch die for cutting sample specimens.
  3. Provide certificate of tensiometer calibration within the past 12 months.

### **PART 3 EXECUTION**

#### **3.01 EXAMINATION**

- A. The Geosynthetic CONTRACTOR shall document in writing that the surface on which the geomembrane will be installed is acceptable. In so doing the Geosynthetic CONTRACTOR shall assume full liability for the accepted surface.
- B. The beginning of installation means acceptance of existing conditions. The Geosynthetic CONTRACTOR shall be responsible for maintenance of the geomembrane covered subgrade once installation of geomembrane begins.

#### **3.02 PREPARATION**

- A. Maintain the surface suitability and integrity until the lining installation is completed and accepted.
- B. Repair rough areas and any damage to the subgrade caused by installation of the lining and fill any ruts in subgrade caused by equipment prior to geomembrane deployment.
- C. To avoid sharp bends in the geomembrane, bevel the leading edges of the anchor trench.
- D. Subgrade shall be smooth, uniform, firm and free from rocks or other debris. For deployment over soil subgrade, no rocks or protrusions greater than 0.5 inch in diameter shall be exposed at the subgrade surface.

#### **3.03 DEPLOYMENT**

- A. Geomembrane shall not be deployed:
1. During precipitation;
  2. In the presence of excessive moisture;
  3. In areas of ponded water;
  4. In the presence of excessive winds (i.e., greater than 20 mph); and

5. In excessive heat (i.e., greater than 110° F) or cold (i.e., less than 40° F).
- B. Each panel shall be marked with an "identification code" (number or letter) consistent with the layout plan. The identification code shall be simple and logical. The number of panels deployed in one day shall be limited by the number of panels which can be seamed on the same day. All deployed panels shall be seamed to adjacent panels by the end of each day.
- C. The following is the acceptable method of deployment:
1. Use equipment which will not damage geomembrane by handling, trafficking, leakage of hydrocarbons or other means.
  2. Do not allow personnel working on geomembrane to wear damaging shoes, or engage in activities that could damage geomembrane.
  3. Smoking on the liner is prohibited.
  4. Round sharp corners of clamps and other metal tools used in the work area.
  5. Do not allow clamps and other metal tools to be tossed or thrown.
  6. Unroll panels with a method that protects geomembrane from scratches and crimps and protects soil surface and underlying geotextile from damage.
  7. Use a method to minimize wrinkles, especially differential wrinkles between adjacent panels.
  8. Place adequate hold-downs to prevent uplift by wind.
  9. Use hold-downs that will not damage geomembrane such as sandbags.
  10. Use continuous hold-downs along leading edges to minimize risk of wind flow under panels.
  11. Panels shall be deployed perpendicular to slope elevation contours and the generation of seams shall be minimized.
  12. Protect geomembrane in heavy traffic areas by geotextile, extra geomembrane or other suitable materials.
  13. Do not allow vehicular traffic on geomembrane surface.
  14. Panels deployed on grades steeper than 12% shall extend a minimum of 3 feet beyond the crest or toe of that grade.
  15. Shingles or overlap panels in a downward direction to facilitate drainage.
  16. Rub sheets used during installation shall be removed prior to placement of subsequent panels.

- D. Visually inspect sheet surface during unrolling of geomembrane and mark faulty or suspect areas for repair or test. Replace faulty (requires more than one patch per 200 square feet) geomembrane stock at no additional cost to the OWNER.

### 3.04 FIELD SEAMING

- A. Orient seams perpendicular to slope elevation contours, i.e., orient down (not across) slope and use seam numbering system compatible with panel number system.
- B. Minimize the number of field seams in corners, odd-shaped geometric locations, sumps, and outside corners.
- C. Overlap panels by a minimum of 3 inches for extrusion welding and 4 inches for fusion welding. Use procedures to temporarily bond adjacent panels together that do not damage the geomembrane and that are not detrimental to seam weld material for extension welding.
- D. Do not use solvent or adhesive unless product is approved in writing by the OWNER.
- E. No horizontal seams shall be allowed on grades steeper than 12% or within 3 feet of the crest or toe of slopes. A horizontal seam is defined as more than half of the panel width.
- F. Clean surface of grease, moisture, dust, dirt, debris or other foreign material.
- G. Prior to any extrusion welding, the geomembrane seam or repair shall be prepared as follows:
  - 1. Clean surface of oxidation by disc grinder or equivalent not more than one hour before seaming; use number 80 grit sandpaper for the disc grinder. Bevel edges of geomembrane before bonding and provide continuous tacking in repair areas.
  - 2. Repair area where excessive grinding substantially reduces sheet thickness by more than 4 mils beyond extent of weld.
  - 3. Clean grinding dust around weld area after grinding.
  - 4. The following procedure shall be followed for wrinkles and fishmouths.
    - a. Cut along the ridge of the wrinkle or fishmouth.
    - b. Overlap a minimum of 3 inches and seam.
    - c. Any portion where the overlap is less than 3 inches shall be patched with an oval or round patch of geomembrane that extends a minimum of 6 inches beyond the cut in all directions.
  - 5. If required, a firm, dry substrate (piece of geomembrane or other material) may be placed directly under the seam overlap to achieve proper support.

6. Keep water from intercepting the weld during and immediately after welding the seam.
  7. For existing welds, or welds that are over 3 minutes old, grind the existing weld two inches back from point of termination and restart welding on ground weld.
- H. At least one spare operable seaming apparatus shall be maintained for every three seaming teams. Place protective fabric or piece of geomembrane beneath hot welding apparatus when resting on geomembrane lining and use an electric generator capable of providing constant voltage under combined line load. The electric generator shall generally be located outside of liner. Provide protective lining and secondary containment large enough to catch spilled fuel under electric generators when located on the liner. The welding apparatus shall be equipped with gauges giving temperatures in apparatus and at nozzle.
- I. For extrusion welding, purge welding apparatus of heat-degraded extrudate before welding if extruder is stopped for longer than five minutes. All purged extrudate shall be disposed of off the geomembrane. Each extruder shoe shall be inspected daily for wear to assure that its offset is the same as the geomembrane thickness. Repair or replace worn shoes, damaged or misaligned armature brushes, nozzle contamination, or other worn or damaged parts. Avoid stop-start welding. Remove extrudate rod from welder when not using welder for long period (over two hours). No welding may commence on the liner until the field trial seam sample, made by that equipment and seamer, passes destructive testing.
- J. Test and set "hot air system" using scrap material at least each day prior to commencing seaming and adjust hot air velocity to preclude wind effects. Adjust contact pressure rollers to prevent surface ripples in sheet. No equipment shall be used for welding the geomembrane until a field trial seam sample made by that equipment has passed destructive testing.
- K. In performing hot wedge welding, the welding apparatus shall be automated vehicular mounted devices equipped with gauges giving applicable temperatures and pressures. The edge of cross seams shall be ground to a smooth incline (top and bottom) prior to welding. A smooth insulating plate or fabric shall be placed beneath the hot welding apparatus after usage. Protect against moisture buildup between sheets. If welding across cross seams, conduct field test seams at least every two hours, otherwise once prior to start of work and once at mid-day. No equipment is allowed to commence welding on geomembrane until the field trial seam sample made by that equipment has passed destructive testing.
- L. Field trial seams shall be conducted, per seaming apparatus and per seamer, on pieces of geomembrane liner to verify adequate seaming conditions at the following frequency:
1. At beginning of each seaming period.
  2. At least once every five hours.
  3. At the discretion of the CQA CONSULTANT.

- M. Make the trial seams at area of seaming and in contact with subgrade or GCL (same condition as the liner to be seamed). The seam sample shall be at least 42-inches long and 12-inches wide with the seam centered lengthwise. A one foot length of each trial seam sample shall be submitted to the CQA CONSULTANT for archive. Cut three 1-inch wide specimens and test two for peel adhesion, and one for bonded seam strength (shear). Each double wedge fusion seam specimen shall be tested for peel on both sides of the weld. A specimen passes when:
1. The break is film tearing bond (FTB) conforming to National Sanitation Foundation (NSF) Standard 54, Definition 2.15.
  2. The break is ductile.
  3. The strength of breaks for the trial seam testing shall conform to the values listed in Table 02751-1, included at the end of this section.
- N. A trial seam sample passes when all specimens have passing results in peel and shear tests. If a specimen fails (one of the specimens fails in either peel or shear mode), the trial seam procedure shall be repeated in its entirety. If the repeated trial seam fails, the seaming apparatus or operator may not weld until the deficiencies or conditions are corrected and two consecutive passing field trial seams are achieved.
- O. The following procedures shall be followed during cold weather conditions.
1. Geomembrane surface temperatures shall be determined by the CQA CONSULTANT at intervals of at least once per 100 feet of seam length to determine if preheating is required. For extrusion welding, preheating is required if the surface temperature of the geomembrane is below 32° F.
  2. For fusion welding, preheating may be waived by the OWNER based upon a recommendation by the CQA CONSULTANT, if the Geosynthetic CONTRACTOR demonstrates to the CQA CONSULTANT's satisfaction that welds of equivalent quality may be obtained without preheating at the expected temperature of installation.
  3. If preheating is required, the CQA CONSULTANT will observe all areas of geomembrane that have been preheated by a hot air device prior to seaming, to ensure that they have not been overheated.
  4. Care shall be taken to confirm that the surface temperatures are not lowered below the minimum surface temperatures specified for welding due to winds or other adverse conditions. It may be necessary to provide wind protection for the seam area.
  5. All preheating devices shall receive approval by the CQA CONSULTANT prior to use.
  6. Additional destructive tests will be taken at an interval between 250 and 500 feet of seam length, at the discretion of the CQA CONSULTANT.
  7. Sheet grinding may be performed before preheating, if applicable.



8. Trial seaming shall be conducted under the same ambient temperature and preheating conditions as the production seams. Under cold weather conditions, new trial seams shall be conducted if the ambient temperature drops by more than 10° F from the initial trial seam test conditions. Such new trial seams shall be conducted upon completion of seams in progress during the temperature drop.
- P. The following procedures shall be followed during warm weather conditions.
1. At ambient temperatures above 104° F, no seaming of the geomembrane shall be permitted unless the Geosynthetic CONTRACTOR can demonstrate to the satisfaction of the CQA CONSULTANT that the geomembrane seam quality is not compromised. Trial seaming shall be conducted under the same ambient temperature conditions as the production seams. At the option of the CQA CONSULTANT, additional destructive testing may be required for any suspected areas.

### 3.05 FIELD QUALITY CONTROL

- A. The Geosynthetic CONTRACTOR shall designate a full-time quality control (QC) technician who shall be responsible for supervising and/or conducting the field quality control program. The QC technician may not be replaced without written authorization by the OWNER.
- B. Non-Destructive Seam Testing
1. The Geosynthetic CONTRACTOR shall non-destructively test field welds for continuity over their full length using vacuum test units. The non-destructive testing shall be performed concurrently with seaming work progress, not at the completion of all seaming. Any defects located in the seam shall be repaired in accordance with Article 3.06. The following non-destructive testing procedures shall be used to test the field seams for continuity.
    - a. Vacuum box testing for extrusion welds.
    - b. Air pressure testing for double fusion seams.
  2. Vacuum Box Testing
    - a. The vacuum box testing equipment shall comprise the following.
      - i. Rigid housing; transparent viewing window; a soft rubber gasket attached to bottom of housing; porthole or valve assembly; and a vacuum gauge.
      - ii. A vacuum pump capable of applying 5 psi gage pressure of vacuum to the box.
      - iii. A bucket of soapy solution and applicator.
    - b. The procedure for vacuum testing is as follows:
      - i. Clean window, gasket surfaces, and check for leaks.

sample marking. Cut destructive samples as seaming and nondestructive testing progresses, prior to completion of liner installation. The CQA CONSULTANT will mark destructive samples with consecutive numbering, location, apparatus I.D., technician I.D., Engineer I.D., and apparatus settings and date. Record, in written form, weld and test date, time, location, seam number, ambient temperatures, machine settings, technician I.D., apparatus I.D., and pass or fail description. The Geosynthetic CONTRACTOR shall immediately repair holes in geomembrane resulting from obtaining destructive samples and vacuum test patches. The size of destructive samples shall be 12 inches wide by 44 inches long with seam centered lengthwise.

2. Two 1-inch wide specimens shall be taken from each side of the sample and tested by the Geosynthetic CONTRACTOR for peel and shear in the field prior to CQA destructive testing. If any of these specimens fail, the Geosynthetic CONTRACTOR shall track the failure immediately. The remaining sample shall be cut into three 14-inch long by 12 inches wide pieces and distributed as follows:
  - a. To the CQA CONSULTANT for destructive testing.
  - b. To the CQA CONSULTANT for archive.
  - c. To the Geosynthetic CONTRACTOR for its use.
3. Ten 1-inch wide specimens shall be taken from one piece. Five specimens shall be tested for peel and five for shear in accordance with the CQA Plan, with test results meeting the requirements of Table 02751-1, included at the end of this section. In the event of failure, the procedures for failed seam tracking are:
  - a. Retrace welding path a minimum of 10 feet in both directions from the failed test location and remove (at these locations) a one inch wide specimen for testing. Repeat tracking procedures until the Geosynthetic CONTRACTOR is confident of seam quality.
  - b. Obtain destructive samples from each side of the welding path and give samples to the CQA CONSULTANT for destructive testing.
  - c. Repeat process if additional tests fail.
  - d. Reconstruct seam between passing test locations to satisfaction of the CQA CONSULTANT.
  - e. Reconstruction may be one of the following:
    - i. Cut out old seam, reposition panel and re-seam.
    - ii. Add cap strip.
  - f. Cut additional destructive samples from reconstruction at discretion of CQA CONSULTANT.

- g. If additional destructive sample results are not acceptable, repeat process until reconstructed seam is judged satisfactory by the CQA CONSULTANT.
- D. For final seaming inspection, check the seams and surface of geomembrane for defects, holes, blisters, undispersed raw materials, or signs of contamination by foreign matter. Brush, blow, or wash geomembrane surface if dirt inhibits inspection. The CQA CONSULTANT shall decide if cleaning of geomembrane surface and welds is needed to facilitate inspection. Distinctively mark repair areas and indicate required type of repair.

### 3.06 REPAIR PROCEDURES

- A. The geomembrane will be inspected before and after seaming for evidence of defects, holes, blisters, undispersed raw materials, and any sign of contamination by foreign matter. The surface of the geomembrane shall be clean at the time of inspection. The geomembrane surface shall be swept or washed by the Geosynthetic CONTRACTOR if surface contamination inhibits inspection. The Geosynthetic CONTRACTOR shall ensure that an inspection of the geomembrane precedes any seaming of that section.
- B. Remove damaged geomembrane and replace with acceptable geomembrane materials if damage cannot be satisfactorily repaired.
- C. Repair, removal and replacement shall be at the Geosynthetic CONTRACTOR's expense.
- D. Repair any portion of the geomembrane exhibiting a flaw, or failing a destructive or non-destructive test. The Geosynthetic CONTRACTOR shall be responsible for repair of damaged or defective areas. Agreement upon the appropriate repair method shall be decided between the CQA CONSULTANT and the Geosynthetic CONTRACTOR. Procedures available include:
  - 1. Patching: Used to repair holes (over 1/4-inch diameter), tears (over 1/4 inch long), undispersed raw materials, and contamination by foreign matter.
  - 2. Grinding and welding: Used to repair pinholes, blemishes and over-grinding.
  - 3. Capping: Used to repair large lengths of failed seams.
  - 4. Removing the seam and replacing with a strip of new material.
- E. In addition, the following procedures shall be observed.
  - 1. Geomembrane surfaces to be repaired shall be abraded (extrusion welds only) no more than 1/2 hour prior to the repair.
  - 2. All geomembrane surfaces shall be clean and dry at the time of repair.
  - 3. The repair procedures, materials, and techniques shall be approved in advance of the specific repair by the CQA CONSULTANT.

4. Extend patches or caps at least 6 inches beyond the edge of the defect, i.e., be a minimum of 12 inches in diameter, and round all corners of material to be patched.
5. Bevel the edge of the patch and do not cut patch with repair sheet in contact with geomembrane. Temporary bond the patch to the geomembrane with an approved method, extrusion weld the patch and then vacuum test the repair.

F. Repair Verification:

1. Number and log each patch repair (performed by the CQA CONSULTANT).
2. Non-destructively test each repair using methods specified in this Section.
3. Provide daily documentation of non-destructive and destructive testing to the CQA CONSULTANT. The documentation shall identify seams that initially failed the test and include the evidence that these seams were repaired and retested successfully.

### 3.07 ACCEPTANCE

- A. The Geosynthetic CONTRACTOR shall retain OWNERSHIP and responsibility for the geomembrane until acceptance by the OWNER.
- B. Acceptance Criteria: The following shall be completed:
  1. Verification of adequacy of field seams, repairs and testing by the CQA CONSULTANT.
  2. All submittals.
  3. "As-built" drawings, approved and final drawings submitted.
  4. Construction area cleaned.
  5. Final field inspection
  6. Warranty signed over to the OWNER.
- C. Field Inspections: Inspect the completed work with the OWNER; defects, wrinkles, suspicious looking welds shall be noted and marked; document, correct and arrange further field inspections until no corrective action is necessary.

**TABLE 02751-1  
REQUIRED PHYSICAL PROPERTIES OF 40-MIL  
TEXTURED HDPE GEOMEMBRANE**

PROPERTY	METHOD	VALUE
Thickness, mil.	ASTM D 5994	- 38 minimum average - 36 lowest indiv. value for 8 out of 10 specimens - 34 lowest indiv. value for any of the 10 specimens
Sheet Density (min.)	ASTM D 792 or ASTM D 1505	0.940
Asperity Height (min. ave.)	GM12	10 mil
Min. Ave. Tensile Properties <sup>(1)</sup> <ul style="list-style-type: none"> <li>• Tension at Yield (lb/in)</li> <li>• Strain at Yield (%)</li> <li>• Tension at Break (lb/in)</li> <li>• Strain at Break (%)</li> </ul>	ASTM D 6693	84 12 60 100
Tear Resistance, lbs. (min. ave.)	ASTM D1004, Die C	28
Oxidative Induction Time (OIT) (min. ave.) <ul style="list-style-type: none"> <li>• Standard OIT, or</li> <li>• High Pressure OIT</li> </ul>	ASTM D3895 ASTM D5885	100 minutes 400 minutes
Oven Aging at 85°C <ul style="list-style-type: none"> <li>• Standard OIT (min. ave.), % retained after 90 days, or</li> <li>• High Pressure OIT (min. ave.), % retained after 90 days</li> </ul>	ASTM D5721 ASTM D3895 ASTM D5885	55% 80%
UV Resistance <ul style="list-style-type: none"> <li>• High Pressure OIT (min. ave.)</li> </ul>	GRI-GM11 ASTM D5885	50%
Stress Crack Resistance (min. hours with no failures)	ASTM D5397 (Appendix)	300
Puncture Resistance, lbs. (min. ave.)	ASTM D4833	60
Carbon Black Content (allowable range in percent)	ASTM D1603	2.0 – 3.0
Carbon Black Dispersion	ASTM D5596	- minimum 9 out of 10 specimens in category 1 or 2 - all 10 specimens in Category 1, 2, or 3
Seam Strength <ul style="list-style-type: none"> <li>• Peel (lb/in) (fusiou/ ext.)</li> <li>• Shear (lb/in)</li> </ul>	ASTM D4437	65 / 52 81

Notes: (1) Elongation at yield and elongation at break shall be calculated using a gage length of 1.3 inches and 2.0 inches, respectively.

**END OF SECTION**

## **SECTION 02752**

### **GEOTEXTILES**

#### **PART 1 GENERAL**

##### **1.01 DESCRIPTION**

- A. This section describes the general requirements for the manufacture, supply, installation, and quality control (QC) of geotextiles.

##### **1.02 RELATED SECTIONS**

- A. Section 02220 – Earthwork
- B. Section 02751 – HDPE Geomembranes

##### **1.03 REFERENCES**

- A. Latest version of the American Society for Testing and Materials (ASTM) standards:
  - 1. ASTM D4355. Standard Test Method for Deterioration of Geotextiles by Exposure to Light, Moisture and Heat in a Xenon Arc Type Apparatus.
  - 2. ASTM D4632. Standard Test Method for Breaking Load and Elongation of Geotextiles (Grab Method)
  - 3. ASTM D4833. Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products
  - 4. ASTM D4873. Standard Guide for Identification, Storage, and Handling of Geotextiles.
  - 5. ASTM D5199. Standard Test Method for Measuring Geotextiles
  - 6. ASTM D5261. Standard Test Method for Measuring Mass Per Unit Area of Geotextiles.

##### **1.04 SUBMITTALS**

- A. Quality Control Submittals:
  - 1. A copy of the manufacturer's quality control (QC) plan.
  - 2. Manufacturing QC certificates for each production run. The certificates shall identify the origin and the manufacturer of the resin. The certificates shall be signed by responsible parties employed by the manufacturer (such as the production manager). Tests shall be performed at the frequency indicated in the manufacturer's QC Plan.
  - 3. The QC certificates shall include roll numbers and identification, sampling procedures, and results of quality control tests verifying that each of the properties listed in Table 02752-1 is met. Samples shall be tested at a minimum frequency of

once every 100,000 sf. The manufacturer quality control tests to be performed include the tests specified in Article 2.01 of this section.

4. Manufacturer's certification that the geotextile products meet or exceed specified requirements and are 100% free of needles.
- B. The Geosynthetic CONTRACTOR shall submit the following.
1. Installation plan; and
  2. Proposed seam stitching methods.
- C. Submittals shall be in accordance with Section 01300.

#### **1.05 QUALITY ASSURANCE**

- A. Perform work in accordance with the CQA Plan.

#### **1.06 QUALIFICATIONS**

- A. Geotextile shall be supplied by a geotextile manufacturer meeting the following qualification requirements:
1. The geotextile manufacturer shall be responsible for the production and delivery of geotextile rolls and shall be a well-established firm with more than two years experience in the manufacture of geotextiles. The geotextile manufacturer shall submit a statement to the CQA CONSULTANT listing:
    - a. Certified minimum average roll property values of the proposed geotextiles and the test methods used to determine those properties.
    - b. Projected delivery date of the material for this project.
- B. The Geosynthetic CONTRACTOR shall meet the requirements of the CQA Plan.

## PART 2 PRODUCTS

### 2.01 MATERIALS

- A. Non-woven geotextiles shall have the following minimum average roll value (MARV) properties:

TABLE 02752-1

#### REQUIRED PHYSICAL PROPERTIES OF GEOTEXTILE

Fabric Property	ASTM Test Method	Manufacturer QC Test Frequency <sup>(1)</sup>	Required Test Values
Mass Per Unit Area (min. ave.)	D-5261	1 per 100,000 sf	12 oz/sy
Grab Strength (min. ave.)	D-4632	1 per 100,000 sf	300 lbs
Puncture Strength (min. ave.)	D-4833	1 per 100,000 sf	180 lbs
UV Resistance	D-4355	1 per resin formulation	70 percent <sup>(2)</sup>

Notes: (1) Manufacturer may elect to provide certification of values for geotextiles.

(2) After 500 hours of exposure.

- B. Geotextile shall be non-woven, needle-punched polyester or polypropylene fabric free from needles or other foreign material.

### 2.02 DELIVERY, STORAGE, AND HANDLING

- A. Handling, storage, and care of the geotextiles following transportation to the site shall be the responsibility of the CONTRACTOR. The CONTRACTOR shall be liable for all damage to the materials incurred prior to final acceptance of the liner system by the CQA CONSULTANT.
- B. The CONTRACTOR shall be responsible for storage of the geotextile at the site after the material is delivered. The geotextile shall be stored off the ground and out of direct sunlight, and shall be protected from mud, dirt, dust, and any additional storage procedures required by the Geotextile manufacturer.
- C. All rolls of geotextile shall be identified at the factory with the following:
1. Manufacturer's name
  2. Product identification
  3. Lot Number
  4. Roll number
  5. Roll dimensions
- D. Geotextiles shall be handled in a manner as to ensure they are not damaged in any way.



- E. Precautions shall be taken to prevent damage to underlying materials during placement of the geotextile.
- F. After unwrapping the geotextile from its cover, the geotextile shall not be left exposed for a period in excess of 30 days.

### **PART 3 EXECUTION**

#### **3.01 INSTALLATION**

- A. Geotextile seams shall be continuously sewn or heat bonded. Geotextile seams shall be overlapped a minimum of 6 inches prior to sewing. No horizontal seams shall be allowed on slopes steeper than 5 horizontal to 1 vertical.
- B. Polymeric thread, with chemical resistance properties equal to or exceeding those of the geotextile, shall be used for all sewing. The seams shall be sewn using Stitch Type 401. The seam type shall be Federal Standard Type SSa-1.
- C. The CONTRACTOR shall examine the entire geotextile surface after installation to ensure that no potentially harmful foreign objects are present. Such foreign objects shall be removed and damaged geotextile shall be repaired or replaced at no cost to OWNER.
- D. Use care not to damage underlying materials during installation.
- E. Prevent the geotextile from accumulating excessive dust.
- F. The CONTRACTOR shall be responsible for field handling, storing, deploying, seaming or connecting, temporary restraining (against wind), anchoring, and other aspects of geotextile installation. Specifically, the CONTRACTOR shall follow the guidelines in ASTM D 4873 regarding the placement, handling and storage of geotextiles.
- G. The CONTRACTOR shall accept and retain full responsibility for all materials and installation and shall be held responsible for any defects in the completed system.
- H. No equipment shall operate directly on the geotextile.
- I. Use sandbags or other acceptable anchorage to prevent wind uplift.

#### **3.02 REPAIRS**

- A. Any holes or tears in the geotextile shall be repaired using a geotextile patch consisting of the same geotextile.
  - 1. On slopes inclined steeper than 10 horizontal to 1 vertical, patches shall be sewn into place with a minimum 6-inch overlap.
  - 2. On slopes inclined at 10 horizontal to 1 vertical or less, patches may be heat-bonded with a 6-inch overlap in all directions.

**END OF SECTION**

## **SECTION 02932**

### **REVEGETATION**

#### **PART 1 GENERAL**

##### **1.01 SUMMARY**

- A. This section describes the general requirements for vegetating areas associated with the final closure construction at the Kettleman Hills Facility Landfill B-18.
- B. The CONTRACTOR shall furnish all labor, materials, tools, equipment, supervision, transportation, manufacturing and installation services necessary to vegetate areas of the final cover as required.

##### **1.02 RELATED SECTIONS**

- A. Section 01300 - Submittals
- B. Section 02200 - Earthwork

##### **1.03 REFERENCES**

- A. State of California Department of Transportation (CALTRANS) Standard Specifications, latest editions.

##### **1.04 SUBMITTALS**

- A. Submit the seed mix a minimum of 2 weeks prior to starting of vegetation work for review by the CQA Consultant.
- B. Submittals shall be in accordance with Section 01300.

##### **1.05 QUALITY ASSURANCE**

CQA Consultant to verify adequate seed application.

#### **PART 2 PRODUCTS**

##### **2.01 SEED/ FERTILIZER**

- A. The seed shall be a mixture of Zorro Fescue (*Festuca megalura*) at a rate of 4.0 lbs/acre and Panoche Red Brome (*Bromus rubens*) as a rate of 12.0 lbs/acre. Seed shall have been tested for purity and germination not more than 12 months prior to the application of the seed. The test results from seed testing shall be delivered to the Owner prior to applying the seed. Seed labels furnished by the seed vendors supplying the seed shall indicate the purity, germination and pure live seed as determined by testing.

- B. Fertilizer shall be either 15-15-15 or 16-20-0 applied at a rate of 500 lbs/acre.

### **PART 3 EXECUTION**

#### **3.01 PREPARATION**

- A. The area to be seeded should be weed free and have a firm seed bed which has previously been roughened by scarifying, disking, harrowing, or otherwise worked to a depth of two to four inches. The seed bed may be prepared when earth moving work is completed.
- B. The vegetated soil layer should be seeded with the seed mix listed in Section 2.01.
- C. The vegetated soil layer should be fertilized with the fertilizer listed in Section 2.01. The fertilizer should be distributed uniformly over the seed bed and incorporated into the soil. Incorporation of the fertilizer may be done as part of the seedbed preparation or as part of the seeding operation unless the seed is broadcast. If fertilizing is a part of the seed bed preparation, it should not be performed more than 15 days prior to seeding.
- D. If the Contractor elects to Drill/Cultipacker, a straw mulch shall be applied at a rate of 4,000 lbs/acre to stabilize the soil and retain moisture during seed germination. At least 50 percent of the applied straw should be more than six inches in length. The mulch should be applied immediately after seeding. To prevent removal of straw by wind, the mulch shall be anchored using either mulching rollers or disks. If disks are used for anchoring they should be dull and run straight.
- E. If the Contractor elects to hydro-seed, a minimum of 525 pounds of fiber per acre shall be mixed and applied with the seed, and fertilizer may be mixed with the seed and fiber and applied in the hydro-seeding operation. The fiber shall be furnished and applied at the Contractor's expense. Mixing of materials for application with hydro-seeding equipment shall be performed in a tank with a built-in continuous agitation system of sufficient operating capacity to produce a homogeneous mixture and a discharge system which will apply the mixture at a continuous and uniform rate. The tank shall have a minimum capacity of 1,000 gallons. A dispersing agent may be added to the mixture provided the Contractor furnishes evidence that the additive is not harmful. Any material considered harmful, as determined by the Engineer, shall not be used. Any mixture containing stabilizing emulsion shall not be applied during rainy weather or when soil temperatures are below 40° F. Pedestrians or equipment shall not be permitted to enter areas where mixtures containing stabilizing emulsion have been applied.

**END OF SECTION**

**APPENDIX P  
CQA PLAN**

**APPENDIX P.1**

**PHASE III CQA PLAN**

**APPENDIX P.2**

**FINAL CLOSURE CQA PLAN**

**APPENDIX P.1**  
**PHASE III CQA PLAN**

**Golder Associates Inc.**

230 Commerce, Suite 200  
Irvine, California 92602  
Telephone (714) 508-4400  
Fax (714) 508-4401  
www.golder.com



**CONSTRUCTION QUALITY ASSURANCE (CQA) PLAN  
FOR  
LANDFILL UNIT B-18 PHASE III EXPANSION  
KETTLEMAN HILLS FACILITY  
KETTLEMAN CITY, CALIFORNIA**

*Prepared for:*

**Chemical Waste Management, Inc.**  
Kettleman Hills Facility  
35251 Old Skyline Road  
Kettleman City, California 93239

*Prepared by:*

**Golder Associates Inc.**  
230 Commerce, Suite 200  
Irvine, California 92602

November 2008  
Revision 1: February 2010  
Revision 2: May 2011

Project No.: 083-91887

**TABLE OF CONTENTS**

<u>SECTION</u>	<u>PAGE</u>
Engineer's Certification	iv
1. INTRODUCTION.....	1
1.1 Purpose .....	1
1.2 CQA Consultant.....	2
1.3 Project Organization.....	2
1.4 Reference Documents .....	2
1.5 Definitions .....	2
2. GENERAL REQUIREMENTS .....	5
2.1 Meetings .....	5
2.1.1 Pre-Construction Meeting .....	5
2.1.2 Progress Meetings .....	6
2.1.3 Weekly Meetings.....	6
2.1.4 Other Meetings.....	6
2.2 Responsibilities of Construction Quality Assurance Staff.....	6
2.2.1 Communications with the Contractor.....	6
2.2.2 Communications with the Owner .....	6
2.2.3 Responsibilities of the CQA Manager.....	6
2.2.4 Responsibilities of the CQA Officer .....	7
2.2.5 Responsibilities of the Design Engineer.....	7
2.2.6 Responsibilities of the CQA Monitors .....	7
2.3 Control of Documents, Records, and Forms.....	7
2.3.1 Project Control of Contract Documents .....	7
2.3.2 Project Control of As-Built Information .....	7
2.3.3 Project Control of Forms .....	8
2.3.4 Processing Daily Reports .....	8
2.3.5 Processing Test Reports .....	8
2.3.6 Processing Project Records .....	8
2.4 Documentation and Control of Non-Conformance .....	8
2.4.1 Observation of Non-Conformance .....	8
2.4.2 Determining Extent of Non-Conformance .....	8
2.4.3 Documenting Non-Conformance .....	8
2.4.4 Corrective Measures.....	9
2.4.5 Verification of Corrective Measures .....	9
2.5 Construction Monitoring .....	9
2.5.1 Monitoring Priorities .....	9
2.5.2 Discrepancies.....	9
2.6 Materials Quality Verification.....	9
2.6.1 General .....	9
2.6.2 Material Submittals .....	10
2.6.3 Certificates of Compliance and Conformance.....	10
2.7 Equipment Control.....	10
2.7.1 Equipment List .....	10
2.7.2 Calibration of Equipment and Materials .....	10

**TABLE OF CONTENTS (continued)**

<u>SECTION</u>	<u>PAGE</u>
3. CONSTRUCTION QUALITY ASSURANCE FOR EARTHWORK.....	11
3.1 General.....	11
3.2 Earthwork Construction Testing.....	11
3.2.1 Test Standards .....	11
3.2.2 Test Frequencies.....	12
3.2.3 Soil Sample Numbering .....	13
3.2.4 Soil Sample Tagging .....	14
3.2.5 Soil Sample Processing .....	14
3.3 Field Density Tests.....	14
3.3.1 Test Numbering.....	14
3.3.2 Test Locations .....	15
3.4 Monitoring and Testing Requirements .....	15
3.4.1 Clearing, Grubbing, and Stripping .....	15
3.4.2 Stockpiling and Soil Management.....	15
3.4.3 Excavation .....	16
3.4.4 Structural Fill.....	16
3.4.5 Compacted Clay Liner.....	17
3.4.6 Geosynthetics Subgrade Preparation .....	17
3.4.7 Operations Layer .....	18
3.4.8 Trenching and Backfilling.....	18
4. CONSTRUCTION QUALITY ASSURANCE FOR GEOSYNTHETICS.....	19
4.1 General.....	19
4.2 Geomembrane .....	19
4.2.1 Delivery, Storage, and Handling .....	19
4.2.2 Conformance Testing .....	20
4.2.3 Geomembrane Installation.....	21
4.2.4 Construction Testing .....	24
4.2.5 Repairs.....	26
4.2.6 Folded Material .....	27
4.2.7 Geomembrane Anchor Trench .....	27
4.2.8 Geomembrane Acceptance.....	27
4.2.9 Qualifications .....	28
4.3 Geotextiles .....	29
4.3.1 Delivery, Storage, and Handling .....	29
4.3.2 Conformance Testing .....	29
4.3.3 Geotextile Installation .....	30
4.3.4 Repairs.....	31
4.4 Geocomposite .....	31
4.4.1 Delivery, Storage, and Handling .....	31
4.4.2 Conformance Testing .....	31
4.4.3 Geocomposite Installation.....	32
4.4.4 Repairs.....	33
5. CONSTRUCTION QUALITY ASSURANCE FOR HDPE PIPE .....	34
5.1 General.....	34



**TABLE OF CONTENTS (continued)**

<u>SECTION</u>	<u>PAGE</u>
5.2 Construction Monitoring .....	34
5.2.1 Delivery, Handling, and Storage .....	34
5.2.2 Fusion Welding .....	34
5.2.3 Slip Joints .....	35
6. CONSTRUCTION QUALITY ASSURANCE FOR EROSION CONTROL .....	36
6.1 Introduction .....	36
6.2 Construction Monitoring .....	36
6.2.1 Temporary Erosion Control .....	36
6.2.2 Permanent Erosion Control Measures .....	36
7. CONSTRUCTION QUALITY ASSURANCE FOR DRAINAGE FACILITIES .....	37
7.1 Introduction .....	37
7.2 Construction Monitoring .....	37
7.2.1 Drainage Channels .....	37
7.2.2 Drop Inlets and Culverts .....	37
7.2.3 Diversion Berms .....	37
8. DOCUMENTATION .....	38
8.1 Daily Record Keeping .....	38
8.1.1 Daily Record of Construction Progress .....	38
8.1.2 Observation and Test Data Sheets .....	39
8.1.3 Non-Conformance Reports .....	39
8.2 Weekly Progress Reports .....	39
8.3 Photographs .....	40
8.4 Design and Specification Changes .....	40
8.5 Final Construction Quality Assurance Report .....	40


**LIST OF TABLES**

Table 3-1 Structural Fill Conformance Testing Frequencies .....	12
Table 3-2 Clay Liner Conformance Testing Frequencies .....	13
Table 4-1 High Density Polyethylene (HDPE) Geomembrane Conformance Testing Frequencies .....	20
Table 4-2 Non-woven Geotextile Conformance Testing Frequencies .....	29
Table 4-3 Geocomposite Conformance Testing Frequencies .....	32

**ENGINEER'S CERTIFICATION**

In accordance with the requirements of California Code of Regulations (CCR) Title 22 Section 66264.19, this Construction Quality Assurance (CQA) Plan has been developed under the direction of a Civil Engineer registered in the State of California.

I hereby certify that this CQA Plan was developed under my direct supervision.



5-2-2011

Ryan Hillman, P.E.

Date

RCE No. 071988

Expires: 03-31-2012

## **1. INTRODUCTION**

### **1.1 Purpose**

The purpose of this document is to describe the Construction Quality Assurance (CQA) procedures required during the Phase III expansion of Landfill Unit B-18 (B-18) at the Kettleman Hills Facility in Kettleman City, California. This CQA Plan establishes procedures to document that the construction is performed in accordance with the approved engineering standards and specifications, meets the appropriate regulatory requirements (i.e., California Code of Regulations Title 22 §66264.19 and Title 27 §20323 and §20324), and that the necessary documentation is developed for submittal to the regulators. This CQA Plan shall be implemented under the direction of a CQA Officer who is a registered Civil Engineer in the State of California.

This CQA Plan is a guidance document that contains general and specific work element requirements for monitoring construction. General requirements include the organization and responsibilities of CQA personnel, documentation control, and reporting procedures. Specific work elements include the following:

- Clearing, Grubbing, and Stripping;
- Stockpiling and Soil Management;
- Excavation;
- Subgrade Preparation;
- Earthfill;
- Compacted Clay Liner;
- Geomembranes;
- Geotextiles;
- Drainage Geocomposites;
- Operations Layer;
- Piping; and
- Culverts/Drainage Channels.

The CQA Consultant will prepare a Final CQA Report upon completion of construction. The Final CQA Report will include information generated through the CQA program and will document the extent to which construction was performed in accordance with the intent of the Contract Documents and design. The CQA Consultant will be required to submit the Final CQA Report within one week of substantial completion of construction.

## 1.2 CQA Consultant

The CQA Consultant has the primary responsibility of implementing and managing the CQA program described herein and will document to the appropriate regulatory agencies that construction of the facility was performed in accordance with the design and the Contract Documents. Specific responsibilities for the CQA Consultant's site personnel are presented in Section 2.2.

## 1.3 Project Organization

The project will be completed by Contractors performing earthworks construction, geosynthetic materials installation, and construction of associated ancillary facilities. The CQA Consultant will be independent of the Contractors and will report directly to the Owner's Project Manager.

## 1.4 Reference Documents

The latest editions of the following reference documents provide background information and support this CQA Plan:

*American Society for Testing and Materials (ASTM), Annual Book of ASTM Standards, Section 4, Construction, Volume 04.02, Concrete and Aggregates.*

*American Society for Testing and Materials (ASTM), Annual Book of ASTM Standards, Section 4, Construction, Volume 04.08, Soil and Rock(I), and Volume 04.09, Soil and Rock (II); Geosynthetics.*

*American Society for Testing and Materials (ASTM), Annual Book of ASTM Standards, Section 8, Plastics, Volumes 08.01, Plastics (I), Volume 08.02, Plastics (II), and Volume 08.03, Plastics (III).*

*California Code of Regulations (CCR), Titles 22 (Social Security) and 27 (Environmental Protection).*

*Standard Specifications for Public Works Construction, Joint Cooperative Committee of the Southern California Chapter, American Public Works Association And Southern California Districts, Associated General Contractors of California, Building News.*

## 1.5 Definitions

Whenever the terms listed below are used, the intent and meaning shall be interpreted as indicated.

**ACI:** American Concrete Institute.

**AISC:** American Institute of Steel Construction.

**ASTM:** American Society for Testing and Materials.

**Construction Manager:** The individual or firm responsible for administering the construction contract and providing overall construction management for the project. The construction manager is the primary contact on the project site representing the Owner.

**Construction Quality Assurance (CQA):** A planned and systematic pattern of procedures and documentation designed to provide confidence that items of work or services meet the requirements of the Contract Documents. Construction quality assurance includes verifying that the Contractor is performing the quality control requirements of the Specifications.

**CQA Consultant:** See Section 1.2

**CQA Manager:** Authorized representative of the CQA Consultant responsible for managing the CQA program.

**CQA Monitors:** Authorized representatives of the CQA Consultant responsible for observing and documenting activities related to CQA during construction.

**CQA Officer:** Authorized representative of the CQA Consultant and a California-Registered Civil Engineer responsible for certifying that construction was performed in accordance with the intent of the Contract Documents and design.

**Construction Quality Control:** Those actions which provide a means to measure and regulate the characteristics of an item or service to comply with the requirements of the Contract Documents. Quality control will be performed by the Contractor/Geosynthetics Contractor, except where designated in the Specifications.

**Contract Drawings:** The official plans, profiles, typical cross-sections, elevations, and details, as well as their amendments and supplemental drawings, that show the locations, character, dimensions, and details of the work to be performed. Contract Drawings are also referred to as the "Plans."

**Contract Documents:** The official set of documents issued by the Owner, which includes bidding requirements, contract forms, contract conditions, Specifications, Contract Drawings, addenda, and contract modifications.

**Contractor:** The person or persons, firm, partnership, corporation, or any combination of these or any combination of private, municipal, or public entities who, as an independent Contractor, has entered into a contract with the Owner and who is referred to throughout the Contract Documents by singular number and masculine gender.

**Contract Specifications:** The requirements for products, materials, and workmanship upon which the contract is based. Contract Specifications are also referred to as the "Specifications."

**Design Engineer:** The individuals or firms responsible for the project's design and preparation of the Plans and Specifications. The Design Engineer is also referred to as the "Designer" or "Engineer." The Design Engineer for the Phase III expansion of Landfill Unit B-18 is Golder Associates Inc. of Irvine, California.

**Earthwork:** A construction activity involving the use of soil materials as defined in the Specifications and Section 3 of this document.

**Flexible Membrane Liner (FML):** A synthetic lining material, also referred to as geomembrane, membrane, liner, or sheet.

**Geosynthetics Contractor:** Also referred to as the "Installer." The person or firm responsible for installation of geosynthetic components. This definition applies to any party installing geomembrane,

geotextile, geocomposite, geosynthetic clay liner, or any other geosynthetic material, even if it is not their primary function.

**GRI:** Geosynthetics Research Institute.

**Non-Conformance:** A deficiency in characteristic, documentation, or procedure that renders the quality of an item or activity unacceptable or indeterminate. Examples of non-conformance include, but are not limited to, physical defects, test failures, and inadequate documentation.

**Owner:** Waste Management, Inc. – Kettleman Hills Facility.

**Owner's Project Manager:** Authorized representative of the Owner responsible for planning, organizing, and control of the design and construction activities. Responsibilities include scheduling, cost control, engineering, procurement, and contracting functions. Referred to as the "Project Manager" in this document.

**Panel:** A unit area of the FML that is seamed in the field or in the fabricator's plant.

**Procedure:** A document that specifies or describes how an activity is to be performed.

**Project Documents:** Contractor submittals, Construction Drawings, Record Drawings, Specifications, shop drawings, construction quality control and quality assurance plans, health and safety plans, and project schedules.

**Record Drawings:** Drawings recording the constructed dimensions, details, and coordinates of the project. Also referred to as "as-builts."

**SSPWC:** Standard Specifications for Public Works Construction.

**Testing:** Verification that an item meets specified requirements by subjecting that item to a set of physical, chemical, environmental, or operating conditions.

**Testing Laboratory:** A laboratory capable of conducting the tests required by this CQA Plan and the Specifications.

## **2. GENERAL REQUIREMENTS**

### **2.1 Meetings**

In order to facilitate construction and to clearly define construction goals and activities, close coordination between the Owner, Design Engineer, CQA Consultant, and Contractor is essential. To meet this objective, pre-construction and progress meetings will be held.

#### **2.1.1 Pre-Construction Meeting**

Following the bid award, a pre-construction meeting will be held at the site. Attendees at this meeting will include the Owner, Contractor, Design Engineer, CQA Consultant, agencies, and others designated by the Owner. The primary purposes of the pre-construction meeting will be to:

- Review the Plans, Specifications, this CQA Plan, work area security, health and safety procedures, and related issues.
- Provide all parties with relevant project documents.
- Review responsibilities and qualifications of each party.
- Define lines of communication and authority.
- Establish reporting and documenting procedures.
- Review procedures for handling submittals.
- Review testing equipment and procedures.
- Review procedures for field directives and change orders.
- Establish testing protocols and procedures for correcting and documenting construction or non-conformance.
- Establish the weekly meeting schedule.
- Discuss work areas, stockpile areas, lay down areas, access roads, haul roads, and related items.
- Review the project schedule and critical path items.
- Review the Contractor's work plan.

The pre-construction meeting will be documented by the CQA Manager. Copies of the minutes and other pertinent material will be prepared and provided to the relevant parties.

### 2.1.2 Progress Meetings

Informal progress meetings will be held each morning before the start of work. At a minimum, these meetings will be attended by the CQA Monitor and Contractor. The purpose of these meetings will be to:

- Discuss problems and resolutions.
- Review test data.
- Discuss the Contractor's personnel and equipment assignments for the day.
- Review the previous day's activities and accomplishments.
- Resolve any outstanding problems or disputes.

### 2.1.3 Weekly Meetings

Throughout the duration of construction, scheduled weekly meetings will be held. The Project Manager, Construction Manager, CQA Manager, and Contractor will be present. These meetings will be held to discuss progress, problems, construction schedule, changes, test data, health and safety, environmental issues, and any other issues necessary. The Project Manager will prepare the agenda for each meeting and prepare meeting minutes for distribution to the relevant parties.

### 2.1.4 Other Meetings

As required, other meetings may be held to plan work items and/or to discuss problems or non-conformance. These meetings will be attended by parties as directed by the Owner. If the problem requires a design modification and subsequent change order, the Engineer and Project Manager should be present. These meetings will be documented as directed by the Project Manager.

## 2.2 Responsibilities of Construction Quality Assurance Staff

### 2.2.1 Communications with the Contractor

Only the individuals assigned to this project, as defined in this document, can communicate with the Contractor. Communications of an official nature must be clear, direct, and professional. When written communications are required, they must be documented on the appropriate forms. Formal letters to the Contractor should normally be signed by the CQA Manager and reviewed by the Owner.

### 2.2.2 Communications with the Owner

Only those individuals assigned to this project, as defined in this document, can communicate with representatives of the Owner. All communications must be through proper channels as defined during the project's pre-construction meeting. Communications of an official nature must be written, clear, direct, and professional.

### 2.2.3 Responsibilities of the CQA Manager

The CQA Manager administers the CQA program. CQA procedures and reports must be reviewed by the CQA Manager for compliance with this CQA Plan. The CQA Manager acts as an auditor to



monitor and document the proper and complete implementation of the CQA program. The CQA Manager has authority to identify deficiencies and implement corrective action to the CQA program. The CQA Manager collects, distributes, and addresses the disposition of Contractor submittals approved by the Design Engineer. The CQA Manager coordinates testing with independent testing laboratories and maintains the Record Drawings. The CQA Manager reports directly to the Construction Manager. The CQA Manager will aid in preparing the Final CQA Report for the project under the direction of the CQA Officer.

#### **2.2.4 Responsibilities of the CQA Officer**

The CQA Officer is responsible for documenting and certifying to the Department of Toxic Substances Control (DTSC) and the Regional Water Quality Control Board (RWQCB) that the construction was performed in accordance with the intent of the design and the Contract Documents. The CQA Officer may also be the CQA Manager.

#### **2.2.5 Responsibilities of the Design Engineer**

The Design Engineer is responsible for site engineering services related to the project's design. Those services include reviewing Contractor submittals, resolving technical issues related to construction, providing interpretation of the Plans and Specifications, and approving substantial design modifications and technical revisions.

#### **2.2.6 Responsibilities of the CQA Monitors**

The CQA Monitors implement the CQA program under the direction of the CQA Manager. The CQA Monitors perform the construction monitoring and construction materials testing. The CQA Monitors maintain the documentation and test data summaries related to construction monitoring and construction materials testing. The CQA Monitors report directly to the CQA Manager.

### **2.3 Control of Documents, Records, and Forms**

#### **2.3.1 Project Control of Contract Documents**

The Contract Documents, including the Specifications, Plans, and change orders, are controlled by the Construction Manager. The Construction Manager maintains one or more copies of the most current set of Contract Documents for use by the CQA Consultant. Upon issuance of new copies or revisions, it is the responsibility of the Construction Manager to notify the Contractor of the revisions, provide revised Contract Documents, and order the recall of superseded copies of the Contract Documents. The Construction Manager also provides the latest revised set of Contract Documents to the CQA Consultant.

#### **2.3.2 Project Control of As-Built Information**

As-built information generated by the Contractor and CQA Consultant is controlled by the CQA Manager. During the progress of the work, the CQA Manager obtains as-built information provided from the CQA Monitors, Contractor, surveyors, or others and compiles the as-built data into one set of drawings. The as-built drawing set must be maintained on site and be clearly marked as "Record Drawings."

### 2.3.3 Project Control of Forms

Daily report forms, test report forms, and other project forms are controlled by the CQA Manager, who maintains a master of each form for copies. Upon issuance of a new form, the CQA Manager must recall and remove all superseded copies along with the master, notify the CQA Monitors, and provide new copies for their use.

### 2.3.4 Processing Daily Reports

The CQA Monitors write a daily record of work progress. These daily reports are reviewed by the CQA Manager for legibility, clarity, traceability, and completeness. The review must be evidenced by a signature of the reviewer. Daily reports are submitted to the Construction Manager on a daily basis and are maintained at the site. A weekly summary construction report will be prepared by the CQA Manager and submitted on a weekly basis to the Construction Manager.

### 2.3.5 Processing Test Reports

A test report must be completed by the CQA Monitors whenever testing is performed. The test reports must be reviewed by the CQA Manager. The review includes a check for mathematical accuracy, conformance to test requirements, conformance to the Specifications, and for clarity, legibility, traceability, and completeness. The review must be evidenced by a signature of the reviewer. Test reports (or summaries) from independent testing laboratories will also be transmitted to the CQA Manager for review.

### 2.3.6 Processing Project Records

Project records are completed as needed. Use of the project records is limited to the scope for which they are intended. The record must be completed by filling in all of the blanks provided on the form, followed by the signature of the individual completing the form. All project records must be maintained at the site.

## 2.4 Documentation and Control of Non-Conformance

### 2.4.1 Observation of Non-Conformance

Whenever a non-conformance is discovered or observed in the construction process, product, job-related materials, documentation, or elsewhere, the CQA Manager and CQA Monitors should first notify the Contractor's foreman/superintendent supervising the work in question. The CQA Manager should then notify the Construction Manager.

### 2.4.2 Determining Extent of Non-Conformance

Whenever a non-conformance is discovered or observed in the construction process, product, job-related materials, documentation, or elsewhere, the CQA Consultant will determine the extent of the non-conformance. The extent of the deficiency may be determined by additional sampling, testing, observations, review of records, or any other means deemed appropriate.

### 2.4.3 Documenting Non-Conformance

All non-conformance must be documented in writing on the daily records, logs, and elsewhere, as appropriate. This documentation must occur immediately upon determining the extent of the non-

conformance. For a non-conformance that is considered serious or complex in nature, or which requires an engineering evaluation, a Non-Conformance Report will be prepared and issued to the Construction Manager and Contractor.

#### 2.4.4 Corrective Measures

For a straightforward or routine non-conformance, corrective measures will be determined by direction from the Specifications. If no direction exists in the Specifications, the Construction Manager, CQA Manager, and Contractor will discuss construction methods to correct the deficiency. For Non-Conformance Reports that require an engineering evaluation, the Design Engineer must determine corrective measures. A copy of the Non-Conformance Report, with the Design Engineer's corrective measure determination, will be forwarded to the Construction Manager, CQA Manager, and Contractor for implementation of the corrective action.

#### 2.4.5 Verification of Corrective Measures

Upon notification by the Contractor that a corrective measure is complete, the CQA Manager will verify its completion. The verification must be accomplished by observations or re-testing and documented photographically. Written documentation of the corrective measures must be made by the CQA Manager on daily reports, logs, forms, and, if applicable, the Non-Conformance Report. Verification of corrective measures will be reviewed by the Construction Manager. Corrective action measures that require an engineering evaluation will be reviewed and verified by the Design Engineer.

### 2.5 Construction Monitoring

#### 2.5.1 Monitoring Priorities

Before commencement of construction, the CQA Manager will establish a list of monitoring priorities. This list will include the various construction activities and the monitoring priority of those activities. The monitoring priorities may change during construction, based upon the Contractor's performance and/or the Owner's request. Changes in the monitoring priorities must be approved by the CQA Manager.

#### 2.5.2 Discrepancies

CQA testing must be conducted in accordance with this CQA Plan. However, discrepancies that occur between this document and other construction documents must be resolved. The document that requires the most frequent tests or more stringent requirements will govern, unless otherwise specified by the Design Engineer and/or CQA Manager.

### 2.6 Materials Quality Verification

#### 2.6.1 General

Material sources will be identified and samples tested to determine if the material meets the requirements of the Specifications. Definitions and requirements of materials are provided in the Specifications. Test samples will be obtained in accordance with applicable ASTM and GRI standards. Archive samples and test results of the test samples will be maintained and stored at the project site. The CQA Monitors will establish and maintain a materials quality verification list. This

list will include material sources, sample locations, testing requirements, test results, and verification action items.

### 2.6.2 Material Submittals

Material submittals may be used by the CQA Consultant to establish the acceptability of materials. When material sample submittals are required, they will be made available to the CQA Consultant by the Contractor. Acceptance and proper review of material submittals are the responsibility of the CQA Manager.

### 2.6.3 Certificates of Compliance and Conformance

Certificates of compliance and conformance may be used by the CQA Manager to establish the acceptability of materials. These certificates generally state that the material is in compliance or conformance with a particular code, standard, or specification. These certificates may be used for acceptance of a product before or in lieu of testing, if allowed by the Specifications.

## 2.7 Equipment Control

### 2.7.1 Equipment List

Before the start of construction, the CQA Manager will complete a list of all measuring, sampling, and testing equipment being used at the site. As new equipment becomes available during the course of the project, it must be added to the list. When more than one type of equipment is available, a unique number will be affixed to each piece to maintain identity. The equipment list will be maintained in the project files and contains the following information:

- Type of equipment;
- Serial number or identifying number;
- Date item received at site;
- Use of the equipment; and
- Date removed from service.

### 2.7.2 Calibration of Equipment and Materials

Before placing a piece of testing equipment into service, its accuracy must be established and calibrated by the CQA Manager or CQA Monitor. Types of equipment requiring calibration include: nuclear gauges, sand cone devices, sand to be used in sand cones, and scales. The calibration procedures and frequencies must be per the equipment manufacturer's instructions or ASTM standards. Whenever the equipment is suspect or is producing questionable results, it must be removed from service immediately and re-calibrated.

### 3. CONSTRUCTION QUALITY ASSURANCE FOR EARTHWORK

#### 3.1 General

This section describes CQA procedures for earthwork operations. The scope of earthwork and related CQA includes the following elements:

- Clearing, Grubbing, and Stripping;
- Stockpiling and Soil Management;
- Excavation;
- Structural Fill;
- Subgrade Preparation;
- Compacted Clay Liner;
- Operations Layer; and
- Trench Excavation and Backfill.

#### 3.2 Earthwork Construction Testing

##### 3.2.1 Test Standards

The latest editions of the following test standards apply as called out in this document or the Specifications:

<u>Standard</u>	<u>Test Description</u>
ASTM D422	Standard Test Method for Particle Size Analysis of Soils
ASTM D1556	Standard Test Method for Density and Unit Weight of Soil in Place by the Sand Cone Method
ASTM D1557	Standard Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort
ASTM D1587	Standard Practice for Thin-Walled Tube Geotechnical Sampling of Soils
ASTM D2216	Standard Test Method of Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass
ASTM D2487	Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D2488	Standard Practice for Description and Identification of Soils (Visual-Manual Procedure)
ASTM D2937	Standard Test Method for Density of Soil in Place by the Drive-Cylinder Method

ASTM D4318	Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D5084	Standard Test Method for Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter
ASTM D6938	Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth)

3.2.2 Test Frequencies

Tables 3-1 and 3-2 establish the test frequencies for earthwork CQA. The test frequencies listed establish a minimum number of required tests. Extra testing must be conducted whenever work or materials are suspect, marginal, or of poor quality. Extra testing may also be performed to provide additional data for engineering evaluation. Any re-tests performed as a result of a failing test do not contribute to the total number of tests performed in satisfying the minimum test frequency.

The Final CQA Report shall include tables similar to Tables 3-1 and 3-2 that document compliance with the testing frequencies and that document test results that comply with the Specifications.

**TABLE 3-1  
 STRUCTURAL FILL CONFORMANCE  
 TESTING FREQUENCIES**

ASTM Test Method	ASTM Designation	Frequency	Frequency (Bench Fill/Trench)
<b>Prior to Placement:</b>			
Moisture-Density Relationship <sup>1</sup>	D1557	1 Per 10,000 CY or Each Material Type (minimum of 2)	1 Per Material Type
Sieve Analysis	D422	1 Per 10,000 CY or Each Material Type	1 Per Material Type
Atterberg Limits	D4318	1 Per 10,000 CY or Each Material Type	1 Per Material Type
<b>During / After Placement:</b>			
Nuclear Water Content and Density <sup>2</sup>	D6938	1 Per 1,000 CY Per 1.5 Vertical Feet	1 Per Lift Per 200 Linear Feet
Sand Cone Test or Drive Cylinder Test <sup>3</sup>	D1556 D2937	1 Per 20 Nuclear Density Tests	1 Per 10 Nuclear Density Tests

Notes to Table 3-1:

1. Perform a Check Point (one point selected at near optimum and compared to the ASTM D1557 curve) at least once for every 10,000 cubic yards of material placed.
2. Tests shall be performed on an even grid to provide adequate testing coverage. For large fills in small areas, the testing frequency shall be increased as necessary to ensure testing for each lift of soil placed.
3. Drive cylinder tests may be performed on clay or silt samples only.

**TABLE 3-2  
 CLAY LINER CONFORMANCE TESTING FREQUENCIES**

ASTM Test Method	ASTM Designation	Frequency	Frequency (Bench Fill/Trench)
<b>Prior to Placement:</b>			
Moisture-Density Relationship <sup>1</sup>	D1557	1 Per 5,000 CY or Each Material Type (minimum of 2)	1 Per Material Type
Sieve Analysis	D422	1 Per 5,000 CY or Each Material Type	1 Per Material Type
Atterberg Limits	D4318	1 Per 5,000 CY or Each Material Type	1 Per Material Type
Hydraulic Conductivity	D5084	1 Per 5,000 CY or Each Material Type	1 Per Material Type
<b>During / After Placement:</b>			
Nuclear Water Content and Density <sup>2</sup>	D6938	1 Per 500 CY or Per Lift, whichever is greater	1 Per Lift Per 200 Linear Feet
Sand Cone Test or Drive Cylinder Test	D1556 D2937	1 Per 20 Nuclear Density Tests	1 Per 10 Nuclear Density Tests
Hydraulic Conductivity	D5084	1 Per 1,000 CY or Per Lift, whichever is greater	1 Per 200 Linear Feet

Notes to Table 3-2:

1. Perform a Check Point (one point selected at near optimum and compared to the ASTM D1557 curve) at least once for every 10,000 cubic yards of material placed.
2. Tests shall be performed on an even grid to provide adequate testing coverage. For large fills in small areas, the testing frequency shall be increased as necessary to ensure testing for each lift of soil placed.

3.2.3 Soil Sample Numbering

The CQA Monitor will maintain soil sample numbers in a master log to be maintained at the site. Sample numbers will begin at 001 and proceed upward. No sample number can be repeated and re-tests of a failing sample will be given the original number with a letter suffix (i.e., re-tests for a failing sample 021 would be: 021A, 021B, etc.). Information contained in the master log of test samples will include:

- Sample number;
- Test(s) to be performed;
- Dated sampled;
- CQA Monitor obtaining sample;
- Location sampled;
- Location of testing (on-site vs. off-site);

- Date sample sent off-site;
- Date test results received;
- Site testing CQA Monitor;
- Date testing completed at site; and
- Test results and remarks.

#### 3.2.4 Soil Sample Tagging

The CQA Monitor is responsible for maintaining sample identification for all soil samples while on site, from the time of sampling through the completion of testing. The CQA Monitor must place a sample tag on the soil sample container immediately upon sampling. This tag must remain with the soil sample throughout processing. The tag will contain the following information:

- Sample number;
- Material type;
- Project name and project number;
- Sampling CQA Monitor;
- Date sampled; and
- Test(s) to be performed.

#### 3.2.5 Soil Sample Processing

The CQA Monitor is responsible for the timely processing of soil test samples. The CQA Manager will determine which samples are tested on-site and which are tested off-site. This determination will be made based on available manpower, available equipment, complexity of testing, and the desired turnaround time for results. For expediency, samples to be tested off-site should be shipped the same day they are collected.

### 3.3 Field Density Tests

#### 3.3.1 Test Numbering

The CQA Monitor is responsible for maintaining test numbers and results for field density tests performed using the nuclear gauge (ASTM D6938), sand cone (ASTM D1556), and drive cylinder (ASTM D2937). All other testing is identified through the sample number (Section 3.2.3). The CQA Monitor will maintain field books that identify soil segments, test data, the CQA Monitor performing the test, and the sequential test number. Each soil segment will have a unique series of numbers. No test number can be repeated for a given soil segment, and re-tests of failing tests must be given a letter suffix along with the original test number (i.e., re-tests for a failing test 1201 would be: 1201A, 1201B, etc.). Test data and results must be filled out on the field density test form.



### 3.3.2 Test Locations

The intent of the CQA program is to provide confidence that the earthwork materials and work conform to the requirements of the Specifications. To meet this intent, the CQA Monitor will perform density tests of earthfills during construction. Density tests must be located at various elevations and uniformly dispersed throughout the entire plan dimensions of the fill. Density test locations must be chosen without bias; however, additional testing can be performed in any areas that are suspect, marginal, or appear to be of poor quality. During the progress of the work, density test locations will be plotted on a drawing by the CQA Monitor to document that no significant areas are left untested. This drawing will be included in the Final CQA Report.

### 3.4 Monitoring and Testing Requirements

Earthwork components of the construction are summarized in Section 3.1. Each component has specific construction requirements that must be monitored. The following sections list monitoring requirements for each type of earthwork.

#### 3.4.1 Clearing, Grubbing, and Stripping

- Document that erosion and sediment control silt fences, straw bale barriers, and other measures are securely in place prior to initiating clearing, grubbing, and stripping operations in any area.
- Document that existing plant life designated to remain is protected against damage during construction.
- Document that clearing and stripping in areas required for site access and execution of the work is complete.
- Document that vegetation, roots, and highly organic soil within the work area are removed to the appropriate extent.

#### 3.4.2 Stockpiling and Soil Management

- Review the Contractor's approved work plan submittal. Verify stockpile locations, stockpile dimensions, clay mixing areas, haul routes, material segregation procedures, and erosion, sediment, and drainage control measures. Determine and note corrective action items, if applicable.
- Document that stockpile locations have been cleared, grubbed, and stripped in accordance with Section 3.4.1 of this CQA Plan and the Specifications.
- Document that stockpile subgrades are surveyed prior to stockpiling.

The CQA Monitor will maintain a separate soil test data summary sheet for the specific purpose of soil classification of stockpiled materials.

- During excavation, hauling, and stockpiling operations, continually identify and verify material classifications in general accordance with ASTM D2487 (Unified Soil Classification System) and ASTM D2488 as necessary to characterize material stockpile designations.

- Observe that stockpiles are constructed with slopes no greater than 2H:1V (horizontal:vertical) and that the top surface maintains a minimum 5 percent grade. The Contractor shall include 15-foot-wide drainage benches every 50 vertical feet on all stockpiles.

#### 3.4.3 Excavation

- Document that construction staking is performed before work and that survey bench marks with elevations are secured outside the work area.
- If applicable, document that the Contractor has notified Underground Service Alert to identify and locate underground utilities.
- Document that excavated materials are segregated into proper stockpiles.
- Coordinate with the Contractor to perform excavation verification surveys upon completion of excavating operations. Verify corrective action measures as determined by verification surveys. Verification surveys will also be used to determine limits of excavation for measurement and payment applications. Submit a copy of verification surveys to the Construction Manager.
- Document that unsuitable materials are removed from areas that will receive earthfill. Unsuitable materials include uncertified existing fills, disturbed soils, weak/highly compressible soils, and deleterious materials.
- Prepare a geologic map and geotechnical report of the subgrade for inclusion in the final certification report. Mapping shall be performed by a competent person under the supervision of a California Certified Engineering Geologist.

#### 3.4.4 Structural Fill

- Monitor that subgrade for placement of soil is consistent with the Specifications.
- Monitor that construction staking is performed before the beginning of the work and that survey bench marks with elevations are secured outside the work area.
- Perform visual and manual soil classifications (ASTM D2488) to verify that the material source is suitable for structural fill. Verify that the material is free of organic and oversized materials and perform classifications continually during excavation of borrow materials.
- Perform moisture-density relationship testing (ASTM D1557) to determine the maximum dry density and optimum moisture content for structural fill materials. Perform tests at the testing frequencies specified in Table 3-1.
- Monitor that structural fill materials are placed in loose lifts not exceeding 8-inches thick and are then properly compacted.
- Perform nuclear density-moisture tests (ASTM D6938) to document that each lift is compacted to the appropriate relative compaction, as stipulated in the Specifications. Perform tests at the testing frequencies specified in Table 3-1.
- Monitor that soil materials are kept within the specified moisture content range listed in the Specifications. Monitor that soil materials that are wet and over the optimum moisture content (as determined by ASTM D1557) are properly aerated and processed to

bring the moisture content of the material into the acceptable range. Monitor that soils that are dry and below the optimum moisture content (as determined by ASTM D1557) are properly moisture conditioned and processed to bring the moisture content into the acceptable range.

- Monitor that desiccated structural fills are properly repaired or removed before placing subsequent lifts.
- Monitor that final structural fill surfaces are free of ruts, gouges, and other features that might contribute to erosion and sediment run-off.
- During fill operations, field-verify lines, grades, and dimensions using hand-held levels, range poles, and measuring tapes.
- Coordinate with the Contractor to perform verification surveys at the completion of structural fill placement. Verify corrective action measures as determined by verification surveys. Verification surveys will also be used to determine the limits of structural fill for measurement and payment applications. Submit copies of verification surveys to the Construction Manager.

#### 3.4.5 Compacted Clay Liner

- Monitor that material borrow sources are suitable for compacted clay liner.
- Monitor that processing and moisture conditioning of the compacted clay liner are in conformance with the Specifications.
- Monitor that grade control construction staking is performed before the work.
- Monitor that the proper number of passes are made with an approved compactor.
- Monitor lift thickness and other construction procedures as covered in the Specifications and verify that test results are in accordance with the Specifications.
- Perform tests at the frequencies specified in Table 3-2.

#### 3.4.6 Geosynthetics Subgrade Preparation

- Monitor that the subgrade is free of organic and oversized materials and meets the requirements of the Specifications.
- Monitor that grade control construction staking is performed prior to the work.
- Perform moisture-density relationship testing (ASTM D1557) to determine the maximum dry density and optimum moisture content of subgrade materials.
- Monitor that angular or sharp rocks, rocks that protrude more than 0.5 inches, and other debris that could damage the overlying geomembrane are removed from the surface of the subgrade. Verify that the subgrade is free of irregularities and is steel drum rolled smooth prior to geomembrane placement.

- Monitor that the final surface provides continuous and intimate contact with the overlying geomembrane.
- Coordinate with the Contractor to perform subgrade verification surveys upon completion of the subgrade preparation. Verify corrective action measures as determined by the verification surveys. Verification surveys will also be used to determine the limits of the subgrade preparation for measurement and payment applications. Submit copies of verification surveys to the Construction Manager.

#### 3.4.7 Operations Layer

- Monitor that the material source is suitable for the operations layer and is free of organic or other deleterious materials and free of oversized particles, as defined by the Specifications.
- Monitor that grade control construction staking is performed before the work.
- Verify that the operations layer and is placed in a manner that does not damage the underlying geosynthetic layers.
- Coordinate with the Contractor to perform operations layer verification surveys upon completion of placement operations. Verify corrective action measures as determined by the verification surveys. Verification surveys will also be used to determine the limits of the operations layer for measurement and payment applications. Submit a copy of verification surveys to the Construction Manager.

#### 3.4.8 Trenching and Backfilling

- Monitor that construction staking is performed before the work and that survey bench marks with elevations are secured outside the work area.
- Monitor that trenches are excavated in accordance with the dimensional cross-sections and design elevations shown on the Plans.
- Monitor profile surveys conducted by the Contractor during trenching operations.
- Perform moisture-density relationship testing (ASTM D1557) to determine the maximum dry density and optimum moisture content of soil materials that will be used as backfill.
- Perform nuclear density-moisture tests (ASTM D6938) to verify that backfill materials are moisture conditioned and compacted in accordance with the Specifications.

## **4. CONSTRUCTION QUALITY ASSURANCE FOR GEOSYNTHETICS**

### **4.1 General**

The objectives of the geosynthetics CQA program are to assure that: (i) proper construction techniques and procedures are used, and (ii) the project is completed in accordance with the Plans and Specifications. The intents of the CQA program are to: (i) identify and define problems that may occur during construction, and (ii) document that these problems are corrected before construction is complete.

This section describes CQA procedures for the installation of geosynthetic components. The following geosynthetics will be utilized for this project:

- 60-mil HDPE geomembrane (textured on both sides);
- Non-woven geotextile; and
- Double-sided geocomposite.

CQA for the geosynthetics installations will be performed to monitor that geosynthetics are installed in accordance with the design. Construction must be conducted in accordance with the Plans and Specifications. To monitor compliance, the CQA Manager will: (i) review the Contractor's quality control submittals; (ii) perform material conformance testing; (iii) monitor construction testing; and (iv) monitor installations. Conformance testing refers to activities that take place before geosynthetics installation. Construction testing includes activities that occur during geosynthetics installation.

The CQA testing will be conducted in accordance with this CQA Plan and the project's Plans and Specifications. If a discrepancy exists in the testing requirements, the document that requires the most stringent testing will govern.

### **4.2 Geomembrane**

#### **4.2.1 Delivery, Storage, and Handling**

Upon delivery of geomembrane, the CQA Monitor will:

- Observe geomembrane rolls for damage during shipping and handling, identify and mark any damaged materials, and document that damaged materials are set aside.
- Observe that the geomembrane is stored in accordance with the Specifications and is protected from puncture, dirt, grease, water, moisture, mud, mechanical abrasions, excessive heat, direct sunlight, and other damage.
- Document that all manufacturing documentation required by the Specifications has been received.
- Complete the geosynthetics inventory form for all geomembrane materials received.

Damaged geomembrane may be rejected. If rejected, document that material is removed from the site or stored at a location separate from accepted geomembrane. Geomembrane that does not have

proper documentation from the manufacturer must be stored at a separate location until all documentation has been received, reviewed, and accepted.

4.2.2 Conformance Testing

**Geomembrane Material Tests.** Geomembrane samples will be obtained for conformance testing in accordance with Table 4-1. The material will be sampled at the site by the CQA Monitor or at the manufacturing plant under the direction of the CQA Consultant. The samples will be forwarded to an independent testing laboratory for the following conformance tests:

**TABLE 4-1  
 HIGH DENSITY POLYETHYLENE (HDPE) GEOMEMBRANE  
 CONFORMANCE TESTING FREQUENCIES**

Property	Test Method	Conformance Test Frequency <sup>(6)</sup>
Thickness (min. avg.)	ASTM D5994	1 per 250,000 sf
Asperity Height (min. avg.) <sup>(1)</sup>	GRI GM 12	1 per 250,000 sf
Melt Flow Index	ASTM 1238	1 per 250,000 sf
Sheet Density (min avg.)	ASTM D792 or ASTM D1505	1 per 250,000 sf
Tensile Properties <sup>(2)</sup> (min. avg.) <ul style="list-style-type: none"> <li>• Yield strength</li> <li>• Break strength</li> <li>• Yield elongation</li> <li>• Break elongation</li> </ul>	ASTM D6693 Type IV	1 per 250,000 sf
Puncture Resistance (min. avg.)	ASTM D4833	1 per 250,000 sf
Carbon Black Content (range)	ASTM D1603 <sup>(3)</sup>	1 per 250,000 sf
Carbon Black Dispersion <sup>(4)</sup>	ASTM D2663 ASTM D5596	1 per 250,000 sf
Interface Shear Strength <sup>(5)</sup> <ul style="list-style-type: none"> <li>• geocomposite / geomembrane</li> <li>• clay liner / geomembrane</li> </ul>	ASTM D6243	1 per project

Notes to Table 4-1:

- (1) Applies only to textured geomembranes. Alternate the measurement side for double-sided textured sheets.
- (2) Machine direction (MD) and cross machine direction (XMD) average values shall be on the basis of 5 test specimens in each direction:
  - Yield elongation is calculated using a gage length of 1.3 inches.
  - Break elongation is calculated using a gage length of 2.0 inches.
- (3) Other methods such as D4218 (muffle furnace) or microwave methods are acceptable if an appropriate correlation to D1603 (tube furnace) can be established.
- (4) Carbon black dispersion (only near spherical agglomerates) for 10 different views.
- (5) Interface shear strength tests shall be tested at normal loads of 1,000; 4,000; 8,000; and 15,000 pounds per square foot. Results of the testing shall be forwarded to the Engineer for review and approval. Test reports shall include peak and large-displacement (2.5 inches) shear stress values.
- (6) Minimum testing frequency shall be one sample per lot.

The CQA Manager will review all conformance test results and report any non-conformance to the Construction Manager and Contractor.

The Final CQA Report shall include a table similar to Table 4-1 documenting compliance with the testing frequencies and results documenting compliance with the Specifications.

**Sampling Procedure.** Samples will be taken across the entire roll width. Samples may be cut for shipping purposes, but a minimum of five square feet must be sent to the testing laboratory. Samplers must mark the machine direction and the manufacturer's roll identification number on the sample (each piece). Samplers will also assign a conformance test number to the sample and mark the sample with that number.

#### 4.2.3 Geomembrane Installation

**Surface Preparation.** The soil surface must be prepared in accordance with the Specifications. Before geomembrane installation, the subgrade will be inspected by the CQA Monitor and Geosynthetics Contractor. The CQA Monitor must check the following:

- All lines and grades for the soil surface have been verified by the Contractor.
- The soil surface has been rolled/compacted and is free of surface irregularities, loose soil, and protrusions.
- The soil surface is firm and does not contain stones or other objects that could damage the geomembrane.
- The anchor trench dimensions have been checked and the trenches are free of sharp objects and stones.
- There are no excessively soft areas.
- The soil surface is not saturated and no standing water is present.
- The soil surface is not desiccated.
- All construction stakes, if utilized, have been removed and accounted for and there is no debris, rocks, or any other objects in or on the soil surface.
- The Geosynthetics Contractor has certified in writing that the surface on which the geomembrane will be installed is acceptable.

**Panel Placement.** Before installing any of the geomembrane, the Geosynthetics Contractor must submit drawings in accordance with the Specifications. These drawings will show the proposed layout of the panels, including panel identification numbers, field seams, and any other details that do not conform to the Plans.

The CQA Monitor will maintain an up to date panel layout drawing that shows the following: (i) roll numbers; (ii) panel numbers; (iii) seam numbers; (iv) test locations; (v) repair locations; and, (vi) non-destructive testing information.

During panel placement operations, the CQA Monitor will:

- Record panel numbers and dimensions on the panel/seam log.

- Observe the panel surface as it is deployed and record all panel defects and defect corrective actions (panel rejected, patch installed, extrudate placed over the defect, etc.) on the repair sheet. Verify that corrective actions are made in accordance with the Specifications.
- Monitor that equipment used during deployment operations does not damage the geomembrane. Verify that equipment used on the geomembrane does not leak hydrocarbons onto the geomembrane or that corrective measures are taken to prevent leakage.
- Observe that the surface beneath the geomembrane has not deteriorated since previous acceptance. Verify that no stones, construction debris, or other items are beneath the geomembrane that could damage the geomembrane.
- Monitor that the geomembrane is not dragged across an unprotected surface. If the geomembrane is dragged across an unprotected surface, the geomembrane must be inspected for scratches and repaired or rejected, if necessary.
- Record weather conditions including temperature, wind speed and direction, and humidity. Verify that the geomembrane is not deployed in the presence of excess moisture (fog, dew, mist, etc.). In addition, verify that the geomembrane is not placed when the air temperature is less than 40° F or when standing water or frost is on the ground.
- Monitor that crews working on the geomembrane do not smoke, do not wear shoes that could damage the liner, and do not engage in activities that could damage the geomembrane.
- Monitor that methods used to deploy the geomembrane minimize wrinkles and that panels are anchored to prevent movement by the wind. Verify that the Geosynthetics Contractor corrects any damage resulting to or from windblown geomembrane.
- Monitor that no more panels are deployed than can be seamed on the same day.
- The CQA Monitor must inform both the Geosynthetics Contractor and the CQA Manager if any of the above conditions are not met.

**Field Seaming.** Before the start of geomembrane welding and during welding operations, each welder and welding apparatus will be tested in accordance with the Specifications to verify that the equipment is functioning properly. One trial weld will be taken before the start of work and one at mid-shift. The trial weld sample will be at least 42-inches-long and 12-inches-wide, with the seam centered lengthwise. The CQA Monitor will observe all welding operations and verify that the Geosynthetics Contractor quantitatively tests each trial weld for peel adhesion and bonded seam strength (ASTM D6392). (Peel adhesion tests will be referred to as “peel” and bonded seam strength tests will be referred to as “shear” in this document.) The main purposes of the trial weld tests are to evaluate seam strength and to confirm that each welding machine is working properly. Shear tests measure the continuity of tensile strength through the seam and into the parent material. Peel tests measure the strength of the bond created by the welding process.

The results of the peel and shear tests on trial welds will be recorded on the trial weld form. Trial welds must be completed under conditions similar to those under which the panels will be welded.



Trial welds must meet specified requirements for peel and shear and the failure must be ductile or a film tearing bond (FTB) for a wedge weld. An FTB failure occurs when the test specimen breaks at the edge of the outside of the seam but not within that seam. If at any time the CQA Monitor believes that a welding machine is not functioning properly, a trial weld by that machine must be performed and tested. If there are wide changes in temperature ( $> 30^{\circ}\text{F}$ ), humidity, or wind speed, another trial weld must be performed and tested. The trial weld must be allowed to cool to ambient temperature before it is tested.

During geomembrane welding operations, the CQA Monitor will:

- Monitor that the Geosynthetics Contractor has an appropriate number of welding machines and spare parts necessary to perform the work.
- Monitor that equipment used for welding will not damage the geomembrane.
- Monitor that extrusion welders are purged before beginning a weld so that all heat-degraded extrudate is removed from the nozzle of the extrusion welder.
- Monitor that seam grinding is completed less than 1 hour before seam welding and that the upper sheet is beveled (extrusion welding only).
- Monitor that the ambient temperature measured 6-inches above the geomembrane surface is between  $40^{\circ}\text{F}$  and  $110^{\circ}\text{F}$ .
- Monitor that the ends of extrusion welds that are more than 5 minutes old are ground to expose new material before restarting a weld.
- Monitor that contact surfaces of the panels are clean and free of dust, grease, dirt, debris, and moisture before welding.
- Monitor that welds are free of dust, rocks, and other debris.
- Monitor that cross seams are ground to a smooth incline before welding (fusion welding only).
- Monitor that all seams are overlapped a minimum of 3 inches or in accordance with the manufacturer's recommendations, whichever is more stringent.
- Monitor that solvents or adhesives are not present in the seam area.
- Monitor that procedures used to temporarily hold the panels together do not damage the panels and do not preclude CQA testing.
- Monitor that strips of geomembrane, wide enough and long enough to protect the hot wedge welder from running on the subgrade, are placed below the geomembrane. These strips may be as long as the seam itself or shorter and moved with the seaming equipment. If necessary, a firm material such as a flat board or similar hard surface may be placed directly under the weld overlap to achieve firm support.
- Monitor that panels are being welded in accordance with the Plans and Specifications.

- Monitor that there is no free moisture in the weld area.
- Measure surface temperature of the panels every 2 hours.

#### 4.2.4 Construction Testing

**Nondestructive Seam Testing.** The purpose of nondestructive geomembrane seam testing is to detect discontinuities or holes in the seams. Nondestructive geomembrane seam tests include vacuum box and air pressure testing. Nondestructive testing must be performed over the entire length of each seam.

It is the Geosynthetics Contractor's responsibility to perform all nondestructive testing as part of their quality control (QC) program. The CQA Monitor's responsibility is to observe and document that the Geosynthetics Contractor's QC testing is in compliance with the Specifications and to document seam defects and repairs.

Nondestructive seam testing procedures are described below:

- For welds tested by the vacuum box method, the weld is placed under suction utilizing a vacuum box constructed with rigid sides, a transparent top for viewing the seams, a neoprene rubber gasket attached to the bottom of the rigid sides, a vacuum gauge on the inside, and a valve assembly attached to a vacuum hose connection. The box is placed over a seam section which has been thoroughly saturated with a soapy water solution (1 oz. soap to 1 gallon water). The rubber gasket on the bottom of the box must fit snugly against the soaped seam section of the panel to ensure a leak-tight seal.
- A vacuum pump is energized and the vacuum box pressure reduced to approximately 5 psi gauge. Any pinholes, porosity, or non-bonded areas are detected by the appearance of soap bubbles in the vicinity of the defect. Dwell time must not be less than 10 seconds.
- Air pressure testing is used to test double wedge seams that have an enclosed air channel between them. Both ends of the air channel must be sealed. A pressure feed device, usually a hollow needle equipped with a pressure gauge, is inserted into one end of the channel. Air is then pumped into the channel to a minimum pressure of 25 to 30 psi. The air channel must sustain this pressure for 5 minutes without losing more than 2 psi. Following the 5-minute hold time, the opposite end of the tested seam must be punctured to release the air. The pressure gauge must return to zero; if it does not return to zero a blockage is likely present in the seam channel. Locate the blockage and test the seam on both sides of the blockage. The penetration holes must be sealed after testing.

During nondestructive seam testing, the CQA Monitor will:

- Review the Specifications regarding test procedures.
- Monitor that equipment operators are fully trained and qualified to perform their work.
- Monitor that test equipment meets the Specifications.
- Monitor that the entire length of each seam is tested in accordance with the Specifications.

- Observe testing and record results on the panel/seam log and the panel layout drawing.
- Identify any failed areas by marking the area with a waterproof marker compatible with the geomembrane, inform the Geosynthetics Contractor of any required repairs, and record the repair on the panel/seam log.
- Monitor that all repairs are completed and tested in accordance with the Specifications.
- Record all completed and tested repairs on a repair sheet and the panel layout drawing.

**Destructive Seam Sampling Procedures and Field Testing.** Destructive seam samples will be taken at intervals of at least one per 500 linear feet of geomembrane seam. However, additional samples will be taken if the CQA Monitor suspects that a seam does not meet the Specification's requirements. Reasons for taking additional samples may include, but are not limited to:

1. Wrinkling in the seam area.
2. Excess crystallinity.
3. Suspect seaming equipment or techniques.
4. Weld contamination.
5. Insufficient overlap.
6. Adverse weather conditions.
7. Failing tests.

The CQA Monitor will select the locations from where seam samples will be cut for destructive laboratory testing as follows:

- A minimum of one test per 500 feet of seam length. This is an average frequency for the entire installation; individual samples may be taken at greater or lesser intervals. The testing frequency will be increased if welding operations are conducted in temperatures below 40° F. This increase will be agreed to by the Construction Manager, CQA Manager, and Geosynthetics Contractor.
- A maximum frequency must be agreed to by the Construction Manager, CQA Manager, and Geosynthetics Contractor at the pre-construction meeting. However, if the number of failed samples exceeds 5 percent of the tested samples, this frequency may be increased at the discretion of the CQA Manager. Samples taken as the result of failed tests do not count toward the total number of required tests.

The CQA Monitor will not inform the Geosynthetics Contractor in advance of selecting the destructive sample locations.

The Geosynthetics Contractor will remove the destructive samples at locations identified by the CQA Monitor and field test the specimens for peel and shear before the samples are shipped off-site for laboratory testing. During sampling procedures the CQA Monitor will:

- Observe sample cutting.
- Mark each specimen and sample with an identifying number which contains the seam number, destructive sample test number, welder, and date and time welded.
- Record sample locations on the panel layout drawing and panel-seam logs.

- Record the sample locations, weather conditions, and reasons samples were taken (e.g., random sample, visual appearance, result of a previous failure, etc.) in the destructive seam test form.

At each location, obtain two seam specimens that are 44-inches apart. The specimens should be 1-inch wide and 12-inches long with the weld centered across the length of the specimen. The Geosynthetics Contractor must test these samples to failure in the field using a tensiometer capable of quantitatively measuring shear and peel strengths. For double wedge welding, the Geosynthetics Contractor must test both welds. The CQA Monitor will observe the tests. Geomembrane seam specimens pass when the break is a ductile FTB and the seam strength meets the specified values.

If one or both of the 1-inch specimens fails in either peel or shear, the Geosynthetics Contractor can, at his discretion: (1) reconstruct the entire seam between passed test locations; or (2) take another test sample 10 feet from the point of the failed test and repeat this procedure. If the second test passes, the Geosynthetics Contractor can either reconstruct or cap strip the seam between the two passed test locations. If subsequent tests fail, the sampling and testing procedure is repeated until the length of the poor quality seam is established. Repeated failures indicate that either the seaming equipment or operator is not performing properly and that appropriate corrective action must be taken immediately.

Once the field test specimens have passed, a sample must be recovered for laboratory testing from between the passing field specimen locations. The sample must be 42-inches long and 12-inches wide, with the weld centered along the length of the sample. The sample must be divided into three sections: one 12-inch by 12-inch section for the Geosynthetics Contractor, one 12-inch by 18-inch section for laboratory testing, and one 12-inch by 12-inch section for the Owner to archive. Record the results of field testing on the destructive seam test form and the panel/seam log.

**Third Party Laboratory Testing.** The CQA destructive seam samples can be shipped to the testing laboratory to verify seam quality. The laboratory will test five specimens from each sample in both shear and peel modes of failure. Minimum required test values are presented in the Specifications. The testing laboratory must provide verbal test results within 24 hours to the CQA Manager and written certified test results within 5 days.

The CQA Manager must immediately notify the Construction Manager and Geosynthetics Contractor in the event of failed seam test results.

If a laboratory test fails in either peel or shear, the Geosynthetics Contractor must either reconstruct the entire seam or recover additional samples at least 10 feet on either side of the failed sample for retesting. This process is repeated until passed tests bracket the failed seam section. All seams must be bounded by locations from which passing laboratory tests have been taken. Laboratory testing governs seam acceptance. In no case can field testing of repaired seams be used for final acceptance.

#### 4.2.5 Repairs

Portions of geomembrane panels and seams that contain: (1) a flaw; (2) a destructive test; or (3) nondestructive test cuts or holes must be repaired in accordance with the Specifications. The CQA Monitor must locate and record all repairs on the repair sheet and panel layout drawing. Acceptable repair techniques include the following:

- **Patching:** used to repair large holes, tears, large panel defects, undispersed raw materials, welds, contamination by foreign matter, and destructive sample locations.

- **Extrusion:** used to repair small defects in the panels and seams. In general, this procedure should be used for defects less than 2-inches in the largest dimension.
- **Capping:** used to repair failed welds or to cover seams where welds cannot be nondestructively tested.
- **Removal:** used to replace areas with large defects where preceding methods are not appropriate. Also used to remove excess material (wrinkles, fishmouths, intersections, etc.) from the installed geomembrane. Areas of removal shall be patched or capped.

Repair procedures include the following:

- Abrade geomembrane surfaces to be repaired (extrusion welds only) no more than 1 hour before the repair.
- Clean and dry all surfaces at the time of repair.
- Monitor acceptance of the repair procedures, materials, and techniques by the CQA Monitor in advance of the specific repair.
- Extend patches or caps at least 6 inches beyond the edge of the defect and round all corners of material to be patched and the patches to a radius of at least 3 inches. Bevel the top edges of patches before extrusion welding.

#### 4.2.6 Folded Material

Geomembrane with excessive folding (i.e., creased), as determined by the CQA Consultant, must be removed.

#### 4.2.7 Geomembrane Anchor Trench

The geomembrane anchor trench should be left open until seaming is completed. Expansion and contraction of the geomembrane should be accounted for in the liner placement. The anchor trench should be filled in the morning when temperatures are coolest to reduce bridging of the geomembrane.

#### 4.2.8 Geomembrane Acceptance

The Contractor retains all ownership and responsibility for the geomembrane until acceptance by the Owner. In the event the Contractor is responsible for placing cover over the geomembrane, the Contractor retains all ownership and responsibility for the geomembrane until all required documentation is complete and the cover material is placed. After panels are placed, seamed, tested successfully, and repairs made, the completed installation will be walked by the CQA Monitor and Contractor. Any damage or defects found during this inspection will be repaired by the Geosynthetics Contractor. The installation will not be accepted until it meets the requirements of both parties. In addition, the geomembrane will be recommended for acceptance by the CQA Manager only when the following have been completed:

- The installation is finished.

- All seams have been inspected and verified to be acceptable and all required laboratory and field tests have been completed and reviewed.
- All required Contractor-supplied documentation has been received and reviewed.
- All as-built drawings have been reviewed and verified by the CQA Manager to show the true panel dimensions, the locations of all seams, trenches, pipes, appurtenances, and destructive test locations.

#### 4.2.9 Qualifications

Proper layout, seaming, and testing of the geomembrane requires skill and experience. As such, the integrity of the geomembrane is dependent upon the installers. In order to assure a minimum level of experience and expertise, the following experience standards have been established in the Specifications:

**Manufacturer/Fabricator/Installer.** The Specifications list the required qualifications for the geomembrane manufacturer / fabricator / installer companies. The CQA Manager must verify qualifications of the manufacturer, fabricator, and installer through review of Engineer-approved project submittals.

**Installation Superintendent.** The installation field superintendent must have been responsible for the completed installation of a minimum of 5,000,000 square feet of polyethylene geomembrane in the past 5 years utilizing the type of seaming techniques and apparatus proposed for use on this project. A resume with references and phone numbers of satisfactory installations is required. Any superintendent proposed for this project must be present whenever geomembrane is installed.

**Master Seamer and Other Welders.** The master seamer must have demonstrated expertise on previous geomembrane installations. The master seamer must have successfully welded a minimum of 1,000,000 square feet of polyethylene geomembrane within the past 3 years. A resume for this work, with references and phone numbers, is required. Other welders are required to have welded a minimum of 100,000 square feet of geomembrane within the past 3 years. Resumes for all welders, with references and phone numbers, are required. Personnel that have welded less than 100,000 square feet of geomembrane within the past 3 years will only be allowed to weld under the direct supervision of either the master seamer or the installation superintendent.

**CQA Manager Qualifications.** The CQA Manager must have provided CQA services on a minimum of 1,000,000 square feet of polyethylene installations or be level II certified in geosynthetics installations by National Institute for Certification in Engineering Technologies (NICET). The CQA Manager must provide verification of this experience by references in a current resume.

### 4.3 Geotextiles

#### 4.3.1 Delivery, Storage, and Handling

During delivery of geotextiles the CQA Monitor will:

- Monitor that equipment used to unload the rolls does not damage the geotextile.
- Monitor that rolls are wrapped in impermeable and opaque protective covers.
- Monitor that care is used to unload the rolls.
- Monitor that all documentation required by the Specifications has been received.
- Monitor that each roll is marked or tagged with the following information: manufacturer's name; project identification; lot number; roll number; and roll dimensions. Log this information on the geosynthetic inventory form.
- Monitor that materials are stored in a location that will protect the rolls from ultraviolet light exposure, precipitation, mud, dirt, dust, puncture, cutting, or any other damaging or deleterious conditions.

Any damaged rolls may be rejected. Monitor that rejected material is removed from the site and stored at a location separate from accepted rolls. Geotextile rolls which do not have proper manufacturer's documentation must also be stored at a separate location until all documentation has been received and approved.

#### 4.3.2 Conformance Testing

**Geotextile Material Tests.** The CQA Manager will arrange to obtain geotextile conformance test samples as indicated in Table 4-2. These samples will be sent to the testing laboratory for the following conformance tests:

**TABLE 4-2  
NON-WOVEN GEOTEXTILE CONFORMANCE TESTING FREQUENCIES**

Property	Test Method	Conformance Test Frequency <sup>(1)</sup>
Mass/Unit Area (min. avg.)	ASTM D5261	1 per 250,000 sf
Apparent Opening Size <sup>2</sup> (max.)	ASTM D4751	1 per project
Grab Strength (min. avg.)	ASTM D4632	1 per 250,000 sf
Permittivity <sup>2</sup> (min.)	ASTM D4491	1 per project
Puncture Strength (min. avg.)	ASTM D4833	1 per 250,000 sf

Notes to Table 4-2:

- (1) Minimum testing frequency shall be one sample per lot.
- (2) AOS and permittivity shall only be tested for geotextiles used in filter applications.

The CQA Manager will review all conformance test results and report any non-conformance to the Construction Manager and Contractor.

The Final CQA Report shall include a table similar to Table 4-2 documenting compliance with the testing frequencies and results documenting compliance with the Specifications.

**Sampling Procedure.** Samples will be obtained across the entire roll width and will be 3-feet long. Samplers must mark the manufacturer's roll identification number and the machine direction on the sample. Samplers will also assign a conformance test number to the sample and mark the sample with that number.

#### 4.3.3 Geotextile Installation

**Surface Preparation.** Before geotextile installation, the CQA Monitor will:

- Monitor that all lines and grades have been verified by the Contractor.
- Monitor that the subgrade has been prepared in accordance with the Specifications and that the geomembrane installation and all associated documentation has been completed.
- Monitor that soil or geomembrane surfaces do not contain stones that could damage the geotextile.
- Monitor that there are no excessively soft areas in soil surfaces that could damage the geotextile.

**Geotextile Placement and Seaming.** During geotextile placement and seaming operations, the CQA Monitor will:

- Observe the geotextile as it is deployed and record all defects and defect corrective actions (panel rejected, patch installed, etc.). Verify that corrective actions are performed in accordance with the Specifications.
- Monitor that equipment used does not damage the geotextile by handling, equipment transit, leakage of hydrocarbons, or other means.
- Monitor that crews working on the geotextile do not smoke, do not wear shoes that could damage the geotextile, and do not engage in activities that could damage the geotextile.
- Monitor that the geotextile is securely anchored in an anchor trench and is temporarily anchored to prevent movement by the wind.
- Monitor that adjacent panels are overlapped and seamed in accordance with the Specifications.
- Monitor that the geotextile is not exposed to direct sunlight for more than 5 days.
- Examine the geotextile after installation to ensure that no potentially harmful foreign objects are present.
- The CQA Monitor must inform both the CQA Manager and Contractor if the above conditions are not met.



#### 4.3.4 Repairs

Repair procedures include:

- Patching: used to repair large holes, tears, and small defective areas.
- Removal: used to replace large defective areas where the preceding method is not appropriate.

#### 4.4 Geocomposite

##### 4.4.1 Delivery, Storage, and Handling

During delivery of geocomposite the CQA Monitor will:

- Monitor that equipment used to unload the rolls does not damage the geocomposite.
- Monitor that care is used to unload the rolls.
- Monitor that all documentation required by the Specifications has been received.
- Monitor that each roll is marked or tagged with the following information: manufacturer's name; project identification; lot number; roll number; and roll dimensions. Record this information on the geosynthetic inventory log.
- Monitor that the geosynthetic inventory log is completed.
- Monitor that materials are stored in a location that will protect the rolls from ultraviolet light exposure, precipitation, mud, dirt, dust, puncture, cutting, or any other damaging or deleterious conditions.

Any damaged rolls may be rejected. Verify that rejected material is removed from the site or stored at a location separate from accepted rolls. Geocomposite rolls that do not have proper manufacturer's documentation must also be stored at a separate location until all documentation has been received and approved.

##### 4.4.2 Conformance Testing

**Geocomposite Material Tests.** The CQA Manager will arrange to obtain geocomposite conformance test samples as indicated in Table 4-3. These samples will be sent to the testing laboratory for the following conformance tests:

**TABLE 4-3  
GEOCOMPOSITE CONFORMANCE TESTING FREQUENCIES**

<b>Property</b>	<b>Test Method</b>	<b>Conformance Test Frequency</b>
Density (min. avg.)	ASTM D792 or ASTM D1505	1 per 250,000 sf
Thickness (min. avg.)	ASTM D751 or ASTM D5199	1 per 250,000 sf
Carbon Black Content (range)	ASTM D1603	1 per 250,000 sf
Mass/Unit Area (min. avg.)	ASTM D5261	1 per 250,000 sf
Peel Strength (min. avg.)	GRI GC7	1 per 250,000 sf
Transmissivity <sup>(1)</sup> (min. avg.)	ASTM D4716	1 per project

Note to Table 4-3:

(1) Transmissivity shall be measured in a 12-inch by 12-inch box between steel plates under a normal stress of 15,000 psf and a hydraulic gradient of 0.1. A seating time of 15 minutes shall be used.

The CQA Manager will review all conformance test results and report any non-conformance to the Construction Manager.

The Final CQA Report shall include a table similar to Table 4-3 documenting compliance with the testing frequencies and results documenting compliance with the Specifications.

**Sampling Procedure.** Samples will be obtained across the entire roll width and will be 3-feet long. Samplers must mark the manufacturer's roll identification number and the machine direction on the sample. Samplers will also assign a conformance test number to the sample and mark the sample with that number.

#### 4.4.3 Geocomposite Installation

**Surface Preparation.** Before geocomposite installation, the CQA Monitor will:

- Monitor that all lines and grades have been verified by the Contractor.
- Monitor that the geomembrane has been prepared in accordance with the Specifications and all associated documentation has been completed.
- Monitor that soil or geomembrane surfaces do not contain stones that could damage the geocomposite.
- Monitor that there are no excessively soft areas in soil surfaces that could damage the geocomposite.
- Observe that all construction stakes have been removed.
- Monitor that all aspects of surface preparation have been performed according to the Specifications.

**Geocomposite Placement.** During geocomposite placement, the CQA Monitor will:

- Observe the geocomposite as it is deployed and record all defects and defect corrective actions (panel rejected, patch installed, etc.). Verify that corrective actions are performed in accordance with the Specifications.
- Monitor that equipment used does not damage the geocomposite by handling, equipment transit, leakage of hydrocarbons, or other means.
- Monitor that crews working on the geocomposite do not smoke, do not wear shoes that could damage the geocomposite, and do not engage in activities that could damage the geocomposite.
- Monitor that the geocomposite is securely anchored to prevent movement by the wind.
- Monitor that adjacent panels are overlapped and seamed in accordance with the Specifications.
- Examine the geocomposite after installation to ensure that no potentially harmful foreign objects are present.

The CQA Monitor must inform both the CQA Manager and Contractor if the above conditions are not met.

#### 4.4.4 Repairs

Repair procedures for geocomposite include:

- **Patching:** used to repair large holes, tears, and small defective areas.
- **Removal:** used to replace large defective areas where the preceding method is not appropriate.

## **5. CONSTRUCTION QUALITY ASSURANCE FOR HDPE PIPE**

### **5.1 General**

This section describes CQA procedures for HDPE pipe installations. Solid HDPE pipe will be utilized to construct the LCRS riser extensions.

CQA for the HDPE pipe installations will be performed to verify that HDPE pipe systems are installed in accordance with the design. Construction must be conducted in accordance with the Plans and Specifications. To monitor compliance, the CQA Consultant will: (1) review the Contractor's quality control submittals; (2) monitor construction testing; and (3) monitor installations.

All construction testing will be conducted in accordance with the Specifications.

### **5.2 Construction Monitoring**

The following sections list monitoring requirements during HDPE pipe operations.

#### **5.2.1 Delivery, Handling, and Storage**

- Monitor that chains, end hooks, cable slings, or any other devices that may scar the pipe are not used to handle pipe. Wide nylon web slings are recommended to handle the pipe.
- Monitor that the pipe is not damaged during handling operations and that damaged pipe is separated from accepted pipe.
- Monitor that pipe out-of-roundness will not occur due to excessive stacking heights when the pipe is stored at the site.
- Monitor that the pipe is not damaged by sharp rocks or excessive abrasion when the pipe is pulled into place during fusion welding and installation operations.

#### **5.2.2 Fusion Welding**

- Before pipe fusion welding operations and installations, verify that solid pipe, perforated pipe, fittings, and flanged couplings comply with the product requirements of the Specifications.
- Monitor that certified fusion welding operators will be performing the welding.
- Monitor that caution is taken to prevent water from coming in contact with the pipe and heater plates during welding operations. A shelter may be required for the fusion welding machine to allow operations to continue in adverse weather conditions.
- Monitor that heater plate surface temperatures are maintained between 375°F and 400°F for both coated plates and uncoated plates. Monitor that the operator checks the heater plate surface temperatures with a pyrometer.
- Monitor that inside and outside of pipe ends are cleaned to remove dirt, water, grease, and other foreign material.

- Monitor that pipe ends are squarely faced with the facing tool of the fusion welding machine.
- Monitor that pipe ends line up in the fusion welding machine and that the pipe ends meet squarely and completely over the entire surface to be welded. Monitor at this point that the pipe is securely clamped into place so that the pipe does not move during the fusion welding process.
- Monitor that the heater plate is clean and maintains the appropriate temperature. Monitor that the heater plate is inserted between the aligned pipe ends and that the pipe ends are firmly brought into contact with the heater plate. NO PRESSURE should be applied to achieve the melt pattern.
- Monitor that the pipe ends are allowed to heat and soften. As the pipe heats and softens a melt bead begins to roll back from the contact point of the heater plate and the pipe ends.
- Monitor that the heater plate is removed quickly and cleanly when the appropriate melt bead is achieved and that no melted pipe material sticks to the heater plate. If melted material sticks to the heater plate, Monitor that this joint is discontinued, the heater plate is cleaned, the pipe ends are re-faced, and that the joint is re-started.
- Monitor that the melted pipe ends are rapidly joined together and that enough pressure is applied to the joint to form a melt bead 1/8-inch to 3/16-inch in diameter around the entire circumference of the pipe. Pressure is critical to cause the heated material of each pipe end to flow together.
- Monitor that the joint is allowed to cool and solidify properly before the pipe is released from the fusion welding machine. Cooling and solidification is completed when a person's finger can remain comfortably on the bead.
- Examine the joint when the pipe is released from the fusion welding machine to verify that the weld is completely around the entire circumference of the pipe.

### 5.2.3 Slip Joints

- Monitor that all joints extend to the minimum overlap and comply with the requirements of the Plans and Specifications.
- Monitor that there is a snug fit with zero air gaps surrounding the connection.

## **6. CONSTRUCTION QUALITY ASSURANCE FOR EROSION CONTROL**

### **6.1 Introduction**

This section describes CQA procedures for temporary and permanent erosion control installations.

CQA for the temporary and permanent erosion control measures will be performed to verify that the Contractor complies with the requirements of the project's Stormwater Pollution Prevention Plan (SWPPP) and that the permanent erosion control measures are installed in accordance with the design. Construction must be conducted in accordance with the Plans and Specifications. To monitor compliance, the CQA Consultant will: (1) review the Contractor's quality control submittals, and (2) monitor installations.

### **6.2 Construction Monitoring**

#### **6.2.1 Temporary Erosion Control**

- Monitor that the Contractor implements temporary erosion control measures in compliance with the project's SWPPP.

#### **6.2.2 Permanent Erosion Control Measures**

##### *Straw Wattles*

- Review the Contractor's submittals for the straw wattles and verify that the material complies with the manufacturer's recommendations and the Specifications.
- Monitor that the Contractor installs the straw wattles at the locations indicated on the Plans.
- Monitor that the Contractor installs the straw wattles in accordance with the manufacturer's recommendations.

## **7. CONSTRUCTION QUALITY ASSURANCE FOR DRAINAGE FACILITIES**

### **7.1 Introduction**

This section describes CQA procedures for the surface water drainage facilities. The drainage facilities consist of various types of drainage channels, drop inlets, culverts, and diversion berms.

CQA for the drainage facilities installation will be performed to verify that these facilities are constructed in accordance with the Plans and Specifications. To monitor compliance, the CQA program will: (1) review the Contractor's quality control submittals; (2) monitor construction testing; and (3) monitor installations.

Construction testing will be conducted in accordance with the Specifications.

### **7.2 Construction Monitoring**

#### **7.2.1 Drainage Channels**

- Monitor that grade control construction staking for the drainage channels is performed before the work.
- Monitor that the drainage channels are constructed in accordance with the Drawings and Specifications.
- Monitor that the subgrades of the drainage channels are dry, firm, and unyielding and do not have loose or extraneous material.
- Document that drainage ditches are graded and sloped in accordance with the Plans and Specifications. Review verification surveys and notify the Contractor of areas needing repair. Submit copies of verification surveys to the Construction Manager.

#### **7.2.2 Drop Inlets and Culverts**

- Review the Contractor's submittals for the piping and drop inlets for compliance with the Specifications.
- Monitor that the Contractor has excavated pipe trenches to the proper depth.
- Monitor that the Contractor has graded the slope of the pipe trenches to uniform gradient.
- Monitor that the pipe subgrades are firm and unyielding and do not have loose or extraneous material.
- Monitor and test backfilling of pipe trenches.
- Verify that inlets to drainage structures are smooth and prevent ponding.

#### **7.2.3 Diversion Berms**

- Monitor that the material used to construct the diversion berms complies with the Specifications for structural fill.

## **8. DOCUMENTATION**

This CQA Plan requires thorough monitoring and documentation of the construction activities. The CQA Manager will document that the CQA requirements have been addressed and satisfied. Documentation will consist of daily record keeping, testing and installation reports, non-conformance reports (if necessary), progress reports, photographic records, design and Specification revisions, and a Final CQA Report.

### **8.1 Daily Record Keeping**

At a minimum, daily records will consist of a daily record of construction progress, daily construction report, observation and test data sheets, and, as needed, non-conformance/corrective measure reports. All forms will have peer review.

#### **8.1.1 Daily Record of Construction Progress**

The daily field report will summarize ongoing construction and discussions with the Contractor and will be prepared by the CQA Manager and CQA Monitor. At a minimum, the report will include the following:

1. Date, project name, project number, and location.
2. A unique number for cross-referencing and document control.
3. Weather data.
4. A description of ongoing construction for the day in the area of the CQA Monitor's responsibility.
5. An inventory of equipment utilized by the Contractor.
6. Significant items of discussion and names of parties involved in these discussions.
7. A brief description of tests and observations, identified as passing or failing, or, in the event of failure, a retest.
8. Areas of non-conformance/corrective actions, if any (non-conformance/corrective action form to be attached).
9. Summary of materials received and quality control documentation.
10. Follow-up information on previously reported problems or deficiencies.
11. Record of site visitors involved with the project.
12. Signature of CQA Manager and/or CQA Monitor.
13. Signature of the peer reviewer.



### 8.1.2 Observation and Test Data Sheets

Observation and test data sheets should include the following information as is appropriate for the form being used.

1. Date, project name, project number, and location.
2. A unique number for cross-referencing and document control.
3. Weather data, as applicable.
4. A reduced scale site plan showing sample and test locations.
5. Test equipment calibrations, if applicable.
6. A summary of test results identified as passing, failing, or, in the event of a failed test, retest.
7. Completed calculations.
8. Signature of the CQA Manager and/or CQA Monitor.
9. Signature of the peer reviewer.

### 8.1.3 Non-Conformance Reports

In the event of a non-conformance event, a non-conformance verification report form will be included with the daily report. Procedures for implementing and resolving any non-conformities to the Contract Documents are outlined in Section 2.4 of this CQA Plan.

## 8.2 Weekly Progress Reports

The CQA Manager will prepare weekly progress reports summarizing construction and CQA activities. These reports will contain, at a minimum, the following information:

- The date, project name, project number, and location.
- A summary of work activities completed in the last week and those expected to be performed in the next week.
- A summary of deficiencies and/or defects and resolutions.
- Ongoing summary of changes and/or change orders to the work.
- The signature of the CQA Manager.
- On the fourth week of each month the report will include a summary of on-site and third party laboratory test results.

### 8.3 Photographs

Construction activities will be photographed. Photographs will show any significant problems encountered and corrective actions and will document the construction progress. The photographs will be identified by location, date, and photographer. The photographer should document the subject or the photograph, either on the back of the picture or in a photograph log.

### 8.4 Design and Specification Changes

Design and Specification changes may be required during construction. Design and Specification changes will only be made with the written agreement of the Design Engineer, Owner, and Contractor. Design and specification changes which affect the containment system or environmental controls shall also require approval of the Regional Water Quality Control Board (RWQCB). These changes will be made by change order to the contract. When change orders are issued, they will be prepared by the Construction Manager. The Construction Manager will distribute change orders for signature and execution to the required parties.

### 8.5 Final Construction Quality Assurance Report

The CQA Manager and CQA Officer shall submit two Final CQA Reports for Phase III: one report for the Phase IIIA construction and one report for the Phase IIIB construction. These reports shall be submitted at the completion of construction of each Phase and shall document that the work for each Phase has been performed in compliance with the Plans and Specifications.

At a minimum, each Final CQA Report will contain:

- Daily Field Reports per Section 8.1.1.
- Inspection data sheets that contain observations and a record of field and laboratory tests per Section 8.1.2.
- A summary of the construction activities.
- A tabular summary of the laboratory and field test results demonstrating construction is in compliance with the Specifications.
- Sampling and testing location drawings.
- A description of significant construction problems and the resolution of these problems.
- A list of changes from the Plans and Specifications and the justifications for these changes.
- As-built (record) drawings.
- A statement of compliance with the Contract Documents and design intent that is signed and stamped by the CQA Officer.

The as-built drawings will accurately show the constructed location of the work items, including the location of piping, anchor trenches, etc. All surveying and base maps required for the development of the as-built drawings will be prepared by the Contractor. The CQA Manager will review and verify that the as-builts are correct.

**APPENDIX P.2**  
**FINAL CLOSURE CQA PLAN**

**Golder Associates Inc.**

230 Commerce, Suite 200  
Irvine, California 92602  
Telephone (714) 508-4400  
Fax (714) 508-4401  
www.golder.com



**CONSTRUCTION QUALITY ASSURANCE (CQA) PLAN  
FOR  
LANDFILL UNIT B-18 FINAL CLOSURE  
KETTLEMAN HILLS FACILITY  
KETTLEMAN CITY, CALIFORNIA**

*Prepared for:*

**Chemical Waste Management, Inc.**  
Kettleman Hills Facility  
35251 Old Skyline Road  
Kettleman City, California 93239

*Prepared by:*

**Golder Associates Inc.**  
230 Commerce, Suite 200  
Irvine, California 92602

November 2008  
Revision 0

Project No.: 083-91887

## TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
Engineer's Certification	iv
1. INTRODUCTION.....	1
1.1 Purpose .....	1
1.2 CQA Consultant.....	1
1.3 Project Organization.....	2
1.4 Reference Documents .....	2
1.5 Definitions .....	2
2. GENERAL REQUIREMENTS .....	5
2.1 Meetings .....	5
2.1.1 Pre-Construction Meeting .....	5
2.1.2 Progress Meetings .....	6
2.1.3 Weekly Meetings.....	6
2.1.4 Other Meetings.....	6
2.2 Responsibilities of Construction Quality Assurance Staff.....	6
2.2.1 Communications with the Contractor.....	6
2.2.2 Communications with the Owner .....	6
2.2.3 Responsibilities of the CQA Manager.....	6
2.2.4 Responsibilities of the CQA Officer .....	7
2.2.5 Responsibilities of the Design Engineer.....	7
2.2.6 Responsibilities of the CQA Monitors .....	7
2.3 Control of Documents, Records, and Forms.....	7
2.3.1 Project Control of Contract Documents .....	7
2.3.2 Project Control of As-Built Information .....	7
2.3.3 Project Control of Forms .....	8
2.3.4 Processing Daily Reports .....	8
2.3.5 Processing Test Reports .....	8
2.3.6 Processing Project Records .....	8
2.4 Documentation and Control of Non-Conformance .....	8
2.4.1 Observation of Non-Conformance .....	8
2.4.2 Determining Extent of Non-Conformance .....	8
2.4.3 Documenting Non-Conformance .....	8
2.4.4 Corrective Measures.....	9
2.4.5 Verification of Corrective Measures .....	9
2.5 Construction Monitoring.....	9
2.5.1 Monitoring Priorities .....	9
2.5.2 Discrepancies.....	9
2.6 Materials Quality Verification.....	9
2.6.1 General .....	9
2.6.2 Material Submittals .....	10
2.6.3 Certificates of Compliance and Conformance.....	10
2.7 Equipment Control.....	10
2.7.1 Equipment List .....	10
2.7.2 Calibration of Equipment and Materials .....	10

**TABLE OF CONTENTS (continued)**

<u>SECTION</u>	<u>PAGE</u>
3. CONSTRUCTION QUALITY ASSURANCE FOR EARTHWORK.....	11
3.1 General.....	11
3.2 Earthwork Construction Testing.....	11
3.2.1 Test Standards .....	11
3.2.2 Test Frequencies .....	12
3.2.3 Soil Sample Numbering .....	14
3.2.4 Soil Sample Tagging .....	15
3.2.5 Soil Sample Processing .....	15
3.3 Field Density Tests.....	15
3.3.1 Test Numbering .....	15
3.3.2 Test Locations .....	15
3.4 Monitoring and Testing Requirements .....	16
3.4.1 Clearing, Grubbing, and Stripping .....	16
3.4.2 Stockpiling and Soil Management.....	16
3.4.3 Excavation .....	17
3.4.4 Structural Fill/Foundation Layer .....	17
3.4.5 Geosynthetics Subgrade Preparation.....	18
3.4.6 Vegetative Cover Soil.....	18
3.4.7 Trenching and Backfilling.....	19
4. CONSTRUCTION QUALITY ASSURANCE FOR GEOSYNTHETICS.....	20
4.1 General.....	20
4.2 Geomembrane .....	20
4.2.1 Delivery, Storage, and Handling .....	20
4.2.2 Conformance Testing .....	21
4.2.3 Geomembrane Installation.....	22
4.2.4 Construction Testing .....	25
4.2.5 Repairs.....	27
4.2.6 Folded Material .....	28
4.2.7 Geomembrane Anchor Trench .....	28
4.2.8 Geomembrane Acceptance .....	28
4.2.9 Qualifications .....	29
4.3 Geotextiles .....	30
4.3.1 Delivery, Storage, and Handling .....	30
4.3.2 Conformance Testing .....	30
4.3.3 Geotextile Installation .....	31
4.3.4 Repairs.....	32
5. CONSTRUCTION QUALITY ASSURANCE FOR EROSION CONTROL.....	33
5.1 Introduction.....	33
5.2 Construction Monitoring.....	33
5.2.1 Temporary Erosion Control.....	33
5.2.2 Permanent Erosion Control Measures .....	33
6. CONSTRUCTION QUALITY ASSURANCE FOR DRAINAGE FACILITIES.....	35
6.1 Introduction.....	35

**TABLE OF CONTENTS (continued)**

<u>SECTION</u>	<u>PAGE</u>
6.2 Construction Monitoring .....	35
6.2.1 Drainage Channels.....	35
6.2.2 Drop Inlets and Culverts.....	35
6.2.3 Diversion Berms.....	35
7. DOCUMENTATION .....	36
7.1 Daily Record Keeping .....	36
7.1.1 Daily Record of Construction Progress .....	36
7.1.2 Observation and Test Data Sheets .....	37
7.1.3 Non-Conformance Reports.....	37
7.2 Weekly Progress Reports .....	37
7.3 Photographs .....	38
7.4 Design and Specification Changes .....	38
7.5 Final Construction Quality Assurance Report .....	38


**LIST OF TABLES**


Table 3-1 Structural Fill and Foundation Layer Conformance Testing Frequencies .....	13
Table 3-2 Vegetative Cover Soil Conformance Testing Frequencies .....	14
Table 4-1 High Density Polyethylene (HDPE) Geomembrane Conformance Testing Frequencies.....	21
Table 4-2 Non-woven Geotextile Conformance Testing Frequencies .....	30

**ENGINEER'S CERTIFICATION**

In accordance with the requirements of California Code of Regulations (CCR) Title 22 Section 66264.19, this Construction Quality Assurance (CQA) Plan has been developed under the direction of a Civil Engineer registered in the State of California.

I hereby certify that this CQA Plan was developed under my direct supervision.

  
\_\_\_\_\_  
Scott G. Sumner, P.E.      RCE No. 049769      Expires: 09-30-2010

      11-17-08      Date



## **1. INTRODUCTION**

### **1.1 Purpose**

The purpose of this document is to describe the Construction Quality Assurance (CQA) procedures required during the final closure construction of Landfill Unit B-18 (B-18) at the Kettleman Hills Facility in Kettleman City, California. This CQA Plan establishes procedures to document that the construction is performed in accordance with the approved engineering standards and specifications, meets the appropriate regulatory requirements (i.e., California Code of Regulations Title 22 §66264.19 and Title 27 §20323 and §20324), and that the necessary documentation is developed for submittal to the regulators. This CQA Plan shall be implemented under the direction of a CQA Officer who is a registered Civil Engineer in the State of California.

This CQA Plan is a guidance document that contains general and specific work element requirements for monitoring construction. General requirements include the organization and responsibilities of CQA personnel, documentation control, and reporting procedures. Specific work elements include the following:

- Clearing, Grubbing, and Stripping;
- Stockpiling and Soil Management;
- Excavation;
- Subgrade Preparation;
- Earthfill;
- Geomembranes;
- Geotextiles; and
- Culverts/Drainage Channels.

The CQA Consultant will prepare a Final CQA Report upon completion of construction. The Final CQA Report will include information generated through the CQA program and will document the extent to which construction was performed in accordance with the intent of the Contract Documents and design. The CQA Consultant will be required to submit the Final CQA Report within one week of substantial completion of construction.

### **1.2 CQA Consultant**

The CQA Consultant has the primary responsibility of implementing and managing the CQA program described herein and will document to the appropriate regulatory agencies that construction of the facility was performed in accordance with the design and the Contract Documents. Specific responsibilities for the CQA Consultant's site personnel are presented in Section 2.2.

### 1.3 Project Organization

The project will be completed by Contractors performing earthworks construction, geosynthetic materials installation, and construction of associated ancillary facilities. The CQA Consultant will be independent of the Contractors and will report directly to the Owner's Project Manager.

### 1.4 Reference Documents

The latest editions of the following reference documents provide background information and support this CQA Plan:

*American Society for Testing and Materials (ASTM), Annual Book of ASTM Standards, Section 4, Construction, Volume 04.02, Concrete and Aggregates.*

*American Society for Testing and Materials (ASTM), Annual Book of ASTM Standards, Section 4, Construction, Volume 04.08, Soil and Rock(I), and Volume 04.09, Soil and Rock (II); Geosynthetics.*

*American Society for Testing and Materials (ASTM), Annual Book of ASTM Standards, Section 8, Plastics, Volumes 08.01, Plastics (I), Volume 08.02, Plastics (II), and Volume 08.03, Plastics (III).*

*California Code of Regulations (CCR), Titles 22 (Social Security) and 27 (Environmental Protection).*

*Standard Specifications for Public Works Construction, Joint Cooperative Committee of the Southern California Chapter, American Public Works Association And Southern California Districts, Associated General Contractors of California, Building News.*

### 1.5 Definitions

Whenever the terms listed below are used, the intent and meaning shall be interpreted as indicated.

**ACI:** American Concrete Institute.

**AISC:** American Institute of Steel Construction.

**ASTM:** American Society for Testing and Materials.

**Construction Manager:** The individual or firm responsible for administering the construction contract and providing overall construction management for the project. The construction manager is the primary contact on the project site representing the Owner.

**Construction Quality Assurance (CQA):** A planned and systematic pattern of procedures and documentation designed to provide confidence that items of work or services meet the requirements of the Contract Documents. Construction quality assurance includes verifying that the Contractor is performing the quality control requirements of the Specifications.

**CQA Consultant:** See Section 1.2

**CQA Manager:** Authorized representative of the CQA Consultant responsible for managing the CQA program.

**CQA Monitors:** Authorized representatives of the CQA Consultant responsible for observing and documenting activities related to CQA during construction.

**CQA Officer:** Authorized representative of the CQA Consultant and a California-Registered Civil Engineer responsible for certifying that construction was performed in accordance with the intent of the Contract Documents and design.

**Construction Quality Control:** Those actions which provide a means to measure and regulate the characteristics of an item or service to comply with the requirements of the Contract Documents. Quality control will be performed by the Contractor/Geosynthetics Contractor, except where designated in the Specifications.

**Contract Drawings:** The official plans, profiles, typical cross-sections, elevations, and details, as well as their amendments and supplemental drawings, that show the locations, character, dimensions, and details of the work to be performed. Contract Drawings are also referred to as the "Plans."

**Contract Documents:** The official set of documents issued by the Owner, which includes bidding requirements, contract forms, contract conditions, Specifications, Contract Drawings, addenda, and contract modifications.

**Contractor:** The person or persons, firm, partnership, corporation, or any combination of these or any combination of private, municipal, or public entities who, as an independent Contractor, has entered into a contract with the Owner and who is referred to throughout the Contract Documents by singular number and masculine gender.

**Contract Specifications:** The requirements for products, materials, and workmanship upon which the contract is based. Contract Specifications are also referred to as the "Specifications."

**Design Engineer:** The individuals or firms responsible for the project's design and preparation of the Plans and Specifications. The Design Engineer is also referred to as the "Designer" or "Engineer." The Design Engineer for the Final Closure of Landfill Unit B-18 is Golder Associates Inc. of Irvine, California.

**Earthwork:** A construction activity involving the use of soil materials as defined in the Specifications and Section 3 of this document.

**Flexible Membrane Liner (FML):** A synthetic lining material, also referred to as geomembrane, membrane, liner, or sheet.

**Geosynthetics Contractor:** Also referred to as the "Installer." The person or firm responsible for installation of geosynthetic components. This definition applies to any party installing geomembrane, geotextile, geocomposite, geosynthetic clay liner, or any other geosynthetic material, even if it is not their primary function.

**GRI:** Geosynthetics Research Institute.

**Non-Conformance:** A deficiency in characteristic, documentation, or procedure that renders the quality of an item or activity unacceptable or indeterminate. Examples of non-conformance include, but are not limited to, physical defects, test failures, and inadequate documentation.

**Owner:** Waste Management, Inc. – Kettleman Hills Facility.

**Owner's Project Manager:** Authorized representative of the Owner responsible for planning, organizing, and control of the design and construction activities. Responsibilities include scheduling, cost control, engineering, procurement, and contracting functions. Referred to as the "Project Manager" in this document.

**Panel:** A unit area of the FML that is seamed in the field or in the fabricator's plant.

**Procedure:** A document that specifies or describes how an activity is to be performed.

**Project Documents:** Contractor submittals, Construction Drawings, Record Drawings, Specifications, shop drawings, construction quality control and quality assurance plans, health and safety plans, and project schedules.

**Record Drawings:** Drawings recording the constructed dimensions, details, and coordinates of the project. Also referred to as "as-builts."

**SSPWC:** Standard Specifications for Public Works Construction.

**Testing:** Verification that an item meets specified requirements by subjecting that item to a set of physical, chemical, environmental, or operating conditions.

**Testing Laboratory:** A laboratory capable of conducting the tests required by this CQA Plan and the Specifications.

## 2. GENERAL REQUIREMENTS

### 2.1 Meetings

In order to facilitate construction and to clearly define construction goals and activities, close coordination between the Owner, Design Engineer, CQA Consultant, and Contractor is essential. To meet this objective, pre-construction and progress meetings will be held.

#### 2.1.1 Pre-Construction Meeting

Following the bid award, a pre-construction meeting will be held at the site. Attendees at this meeting will include the Owner, Contractor, Design Engineer, CQA Consultant, agencies, and others designated by the Owner. The primary purposes of the pre-construction meeting will be to:

- Review the Plans, Specifications, this CQA Plan, work area security, health and safety procedures, and related issues.
- Provide all parties with relevant project documents.
- Review responsibilities and qualifications of each party.
- Define lines of communication and authority.
- Establish reporting and documenting procedures.
- Review procedures for handling submittals.
- Review testing equipment and procedures.
- Review procedures for field directives and change orders.
- Establish testing protocols and procedures for correcting and documenting construction or non-conformance.
- Establish the weekly meeting schedule.
- Discuss work areas, stockpile areas, lay down areas, access roads, haul roads, and related items.
- Review the project schedule and critical path items.
- Review the Contractor's work plan.

The pre-construction meeting will be documented by the CQA Manager. Copies of the minutes and other pertinent material will be prepared and provided to the relevant parties.

### 2.1.2 Progress Meetings

Informal progress meetings will be held each morning before the start of work. At a minimum, these meetings will be attended by the CQA Monitor and Contractor. The purpose of these meetings will be to:

- Discuss problems and resolutions.
- Review test data.
- Discuss the Contractor's personnel and equipment assignments for the day.
- Review the previous day's activities and accomplishments.
- Resolve any outstanding problems or disputes.

### 2.1.3 Weekly Meetings

Throughout the duration of construction, scheduled weekly meetings will be held. The Project Manager, Construction Manager, CQA Manager, and Contractor will be present. These meetings will be held to discuss progress, problems, construction schedule, changes, test data, health and safety, environmental issues, and any other issues necessary. The Project Manager will prepare the agenda for each meeting and prepare meeting minutes for distribution to the relevant parties.

### 2.1.4 Other Meetings

As required, other meetings may be held to plan work items and/or to discuss problems or non-conformance. These meetings will be attended by parties as directed by the Owner. If the problem requires a design modification and subsequent change order, the Engineer and Project Manager should be present. These meetings will be documented as directed by the Project Manager.

## **2.2 Responsibilities of Construction Quality Assurance Staff**

### 2.2.1 Communications with the Contractor

Only the individuals assigned to this project, as defined in this document, can communicate with the Contractor. Communications of an official nature must be clear, direct, and professional. When written communications are required, they must be documented on the appropriate forms. Formal letters to the Contractor should normally be signed by the CQA Manager and reviewed by the Owner.

### 2.2.2 Communications with the Owner

Only those individuals assigned to this project, as defined in this document, can communicate with representatives of the Owner. All communications must be through proper channels as defined during the project's pre-construction meeting. Communications of an official nature must be written, clear, direct, and professional.

### 2.2.3 Responsibilities of the CQA Manager

The CQA Manager administers the CQA program. CQA procedures and reports must be reviewed by the CQA Manager for compliance with this CQA Plan. The CQA Manager acts as an auditor to

monitor and document the proper and complete implementation of the CQA program. The CQA Manager has authority to identify deficiencies and implement corrective action to the CQA program. The CQA Manager collects, distributes, and addresses the disposition of Contractor submittals approved by the Design Engineer. The CQA Manager coordinates testing with independent testing laboratories and maintains the Record Drawings. The CQA Manager reports directly to the Construction Manager. The CQA Manager will aid in preparing the Final CQA Report for the project under the direction of the CQA Officer.

#### 2.2.4 Responsibilities of the CQA Officer

The CQA Officer is responsible for documenting and certifying to the Department of Toxic Substances Control (DTSC) and the Regional Water Quality Control Board (RWQCB) that the construction was performed in accordance with the intent of the design and the Contract Documents. The CQA Officer may also be the CQA Manager.

#### 2.2.5 Responsibilities of the Design Engineer

The Design Engineer is responsible for site engineering services related to the project's design. Those services include reviewing Contractor submittals, resolving technical issues related to construction, providing interpretation of the Plans and Specifications, and approving substantial design modifications and technical revisions.

#### 2.2.6 Responsibilities of the CQA Monitors

The CQA Monitors implement the CQA program under the direction of the CQA Manager. The CQA Monitors perform the construction monitoring and construction materials testing. The CQA Monitors maintain the documentation and test data summaries related to construction monitoring and construction materials testing. The CQA Monitors report directly to the CQA Manager.

### 2.3 Control of Documents, Records, and Forms

#### 2.3.1 Project Control of Contract Documents

The Contract Documents, including the Specifications, Plans, and change orders, are controlled by the Construction Manager. The Construction Manager maintains one or more copies of the most current set of Contract Documents for use by the CQA Consultant. Upon issuance of new copies or revisions, it is the responsibility of the Construction Manager to notify the Contractor of the revisions, provide revised Contract Documents, and order the recall of superseded copies of the Contract Documents. The Construction Manager also provides the latest revised set of Contract Documents to the CQA Consultant.

#### 2.3.2 Project Control of As-Built Information

As-built information generated by the Contractor and CQA Consultant is controlled by the CQA Manager. During the progress of the work, the CQA Manager obtains as-built information provided from the CQA Monitors, Contractor, surveyors, or others and compiles the as-built data into one set of drawings. The as-built drawing set must be maintained on site and be clearly marked as "Record Drawings."

### 2.3.3 Project Control of Forms

Daily report forms, test report forms, and other project forms are controlled by the CQA Manager, who maintains a master of each form for copies. Upon issuance of a new form, the CQA Manager must recall and remove all superseded copies along with the master, notify the CQA Monitors, and provide new copies for their use.

### 2.3.4 Processing Daily Reports

The CQA Monitors write a daily record of work progress. These daily reports are reviewed by the CQA Manager for legibility, clarity, traceability, and completeness. The review must be evidenced by a signature of the reviewer. Daily reports are submitted to the Construction Manager on a daily basis and are maintained at the site. A weekly summary construction report will be prepared by the CQA Manager and submitted on a weekly basis to the Construction Manager.

### 2.3.5 Processing Test Reports

A test report must be completed by the CQA Monitors whenever testing is performed. The test reports must be reviewed by the CQA Manager. The review includes a check for mathematical accuracy, conformance to test requirements, conformance to the Specifications, and for clarity, legibility, traceability, and completeness. The review must be evidenced by a signature of the reviewer. Test reports (or summaries) from independent testing laboratories will also be transmitted to the CQA Manager for review.

### 2.3.6 Processing Project Records

Project records are completed as needed. Use of the project records is limited to the scope for which they are intended. The record must be completed by filling in all of the blanks provided on the form, followed by the signature of the individual completing the form. All project records must be maintained at the site.

## 2.4 Documentation and Control of Non-Conformance

### 2.4.1 Observation of Non-Conformance

Whenever a non-conformance is discovered or observed in the construction process, product, job-related materials, documentation, or elsewhere, the CQA Manager and CQA Monitors should first notify the Contractor's foreman/superintendent supervising the work in question. The CQA Manager should then notify the Construction Manager.

### 2.4.2 Determining Extent of Non-Conformance

Whenever a non-conformance is discovered or observed in the construction process, product, job-related materials, documentation, or elsewhere, the CQA Consultant will determine the extent of the non-conformance. The extent of the deficiency may be determined by additional sampling, testing, observations, review of records, or any other means deemed appropriate.

### 2.4.3 Documenting Non-Conformance

All non-conformance must be documented in writing on the daily records, logs, and elsewhere, as appropriate. This documentation must occur immediately upon determining the extent of the non-



conformance. For a non-conformance that is considered serious or complex in nature, or which requires an engineering evaluation, a Non-Conformance Report will be prepared and issued to the Construction Manager and Contractor.

#### 2.4.4 Corrective Measures

For a straightforward or routine non-conformance, corrective measures will be determined by direction from the Specifications. If no direction exists in the Specifications, the Construction Manager, CQA Manager, and Contractor will discuss construction methods to correct the deficiency. For Non-Conformance Reports that require an engineering evaluation, the Design Engineer must determine corrective measures. A copy of the Non-Conformance Report, with the Design Engineer's corrective measure determination, will be forwarded to the Construction Manager, CQA Manager, and Contractor for implementation of the corrective action.

#### 2.4.5 Verification of Corrective Measures

Upon notification by the Contractor that a corrective measure is complete, the CQA Manager will verify its completion. The verification must be accomplished by observations or re-testing and documented photographically. Written documentation of the corrective measures must be made by the CQA Manager on daily reports, logs, forms, and, if applicable, the Non-Conformance Report. Verification of corrective measures will be reviewed by the Construction Manager. Corrective action measures that require an engineering evaluation will be reviewed and verified by the Design Engineer.

### 2.5 Construction Monitoring

#### 2.5.1 Monitoring Priorities

Before commencement of construction, the CQA Manager will establish a list of monitoring priorities. This list will include the various construction activities and the monitoring priority of those activities. The monitoring priorities may change during construction, based upon the Contractor's performance and/or the Owner's request. Changes in the monitoring priorities must be approved by the CQA Manager.

#### 2.5.2 Discrepancies

CQA testing must be conducted in accordance with this CQA Plan. However, discrepancies that occur between this document and other construction documents must be resolved. The document that requires the most frequent tests or more stringent requirements will govern, unless otherwise specified by the Design Engineer and/or CQA Manager.

### 2.6 Materials Quality Verification

#### 2.6.1 General

Material sources will be identified and samples tested to determine if the material meets the requirements of the Specifications. Definitions and requirements of materials are provided in the Specifications. Test samples will be obtained in accordance with applicable ASTM and GRI standards. Archive samples and test results of the test samples will be maintained and stored at the project site. The CQA Monitors will establish and maintain a materials quality verification list. This

list will include material sources, sample locations, testing requirements, test results, and verification action items.

### 2.6.2 Material Submittals

Material submittals may be used by the CQA Consultant to establish the acceptability of materials. When material sample submittals are required, they will be made available to the CQA Consultant by the Contractor. Acceptance and proper review of material submittals are the responsibility of the CQA Manager.

### 2.6.3 Certificates of Compliance and Conformance

Certificates of compliance and conformance may be used by the CQA Manager to establish the acceptability of materials. These certificates generally state that the material is in compliance or conformance with a particular code, standard, or specification. These certificates may be used for acceptance of a product before or in lieu of testing, if allowed by the Specifications.

## 2.7 Equipment Control

### 2.7.1 Equipment List

Before the start of construction, the CQA Manager will complete a list of all measuring, sampling, and testing equipment being used at the site. As new equipment becomes available during the course of the project, it must be added to the list. When more than one type of equipment is available, a unique number will be affixed to each piece to maintain identity. The equipment list will be maintained in the project files and contains the following information:

- Type of equipment;
- Serial number or identifying number;
- Date item received at site;
- Use of the equipment; and
- Date removed from service.

### 2.7.2 Calibration of Equipment and Materials

Before placing a piece of testing equipment into service, its accuracy must be established and calibrated by the CQA Manager or CQA Monitor. Types of equipment requiring calibration include: nuclear gauges, sand cone devices, sand to be used in sand cones, and scales. The calibration procedures and frequencies must be per the equipment manufacturer's instructions or ASTM standards. Whenever the equipment is suspect or is producing questionable results, it must be removed from service immediately and re-calibrated.

### 3. CONSTRUCTION QUALITY ASSURANCE FOR EARTHWORK

#### 3.1 General

This section describes CQA procedures for earthwork operations. The scope of earthwork and related CQA includes the following elements:

- Clearing, Grubbing, and Stripping;
- Stockpiling and Soil Management;
- Excavation;
- Structural Fill/Foundation Layer;
- Subgrade Preparation;
- Vegetative Cover Soil; and
- Trench Excavation and Backfill.

#### 3.2 Earthwork Construction Testing

##### 3.2.1 Test Standards

The latest editions of the following test standards apply as called out in this document or the Specifications:

<u>Standard</u>	<u>Test Description</u>
ASTM D422	Standard Test Method for Particle Size Analysis of Soils
ASTM D1556	Standard Test Method for Density and Unit Weight of Soil in Place by the Sand Cone Method
ASTM D1557	Standard Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort
ASTM D1587	Standard Practice for Thin-Walled Tube Geotechnical Sampling of Soils
ASTM D2216	Standard Test Method of Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass
ASTM D2487	Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D2488	Standard Practice for Description and Identification of Soils (Visual-Manual Procedure)
ASTM D2937	Standard Test Method for Density of Soil in Place by the Drive-Cylinder Method
ASTM D4318	Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils

ASTM D5084	Standard Test Method for Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter
ASTM D6938	Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth)

### 3.2.2 Test Frequencies

Tables 3-1 and 3-2 establish the test frequencies for earthwork CQA. The test frequencies listed establish a minimum number of required tests. Extra testing must be conducted whenever work or materials are suspect, marginal, or of poor quality. Extra testing may also be performed to provide additional data for engineering evaluation. Any re-tests performed as a result of a failing test do not contribute to the total number of tests performed in satisfying the minimum test frequency.

The Final CQA Report shall include tables similar to Tables 3-1 and 3-2 that document compliance with the testing frequencies and that document test results that comply with the Specifications.

**TABLE 3-1  
 STRUCTURAL FILL AND FOUNDATION LAYER CONFORMANCE  
 TESTING FREQUENCIES**

ASTM Test Method	ASTM Designation	Frequency (Structural Fill and Foundation Layer)	Frequency (Bench Fill/Trench)
Prior to Placement:			
Moisture-Density Relationship <sup>1</sup>	D1557	1 Per 10,000 CY or Each Material Type (minimum of 2)	1 Per Material Type
Sieve Analysis	D422	1 Per 30,000 CY or Each Material Type	-
Atterberg Limits	D4318	1 Per 30,000 CY or Each Material Type	-
During / After Placement:			
Nuclear Water Content and Density <sup>2</sup>	D6938	1 Per 1,000 CY Per 1.5 Vertical Feet	1 Per Lift Per 200 Linear Feet
Sand Cone Test or Drive Cylinder Test <sup>3</sup>	D1556 D2937	1 Per 20 Nuclear Density Tests	1 Per 10 Nuclear Density Tests
Test Pit to Confirm Cover Thickness (for existing Interim Cover Only)	-	1 per 100,000 SF	-
Hydraulic Conductivity (Foundation Layer Only) <sup>4</sup>	D5084	1 per 100,000 SF	-

Notes to Table 3-1:

1. Perform a Check Point (one point selected at near optimum and compared to the ASTM D1557 curve) at least once for every 10,000 cubic yards of material placed.
2. Tests shall be performed on an even grid to provide adequate testing coverage. For large fills in small areas, the testing frequency shall be increased as necessary to ensure testing for each lift of soil placed.
3. Drive cylinder tests may be performed on clay or silt samples only.
4. Hydraulic conductivity tests shall be conducted on relatively undisturbed samples obtained using a thin-walled sampler (i.e., Shelby tube) with a minimum diameter of 3 inches.

**TABLE 3-2  
 VEGETATIVE COVER SOIL CONFORMANCE TESTING FREQUENCIES**

ASTM Test Method	ASTM Designation	Frequency	Frequency (Bench Fill/Trench)
Prior to Placement:			
Moisture-Density Relationship <sup>1</sup>	D1557	1 Per 10,000 CY or Each Material Type (minimum of 2)	1 Per Material Type
During / After Placement:			
Nuclear Water Content and Density <sup>2</sup>	D6938	1 Per 1,000 CY Per 1.5 Vertical Feet	1 Per Lift Per 200 Linear Feet
Sand Cone Test or Drive Cylinder Test <sup>3</sup>	D1556 D2937	1 Per 20 Nuclear Density Tests	1 Per 10 Nuclear Density Tests

Notes to Table 3-2:

1. Perform a Check Point (one point selected at near optimum and compared to the ASTM D1557 curve) at least once for every 10,000 cubic yards of material placed.
2. Tests shall be performed on an even grid to provide adequate testing coverage. For large fills in small areas, the testing frequency shall be increased as necessary to ensure testing for each lift of soil placed.
3. Drive cylinder tests may be performed on clay or silt samples only.

### 3.2.3 Soil Sample Numbering

The CQA Monitor will maintain soil sample numbers in a master log to be maintained at the site. Sample numbers will begin at 001 and proceed upward. No sample number can be repeated and re-tests of a failing sample will be given the original number with a letter suffix (i.e., re-tests for a failing sample 021 would be: 021A, 021B, etc.). Information contained in the master log of test samples will include:

- Sample number;
- Test(s) to be performed;
- Dated sampled;
- CQA Monitor obtaining sample;
- Location sampled;
- Location of testing (on-site vs. off-site);
- Date sample sent off-site;
- Date test results received;
- Site testing CQA Monitor;
- Date testing completed at site; and

- Test results and remarks.

#### 3.2.4 Soil Sample Tagging

The CQA Monitor is responsible for maintaining sample identification for all soil samples while on site, from the time of sampling through the completion of testing. The CQA Monitor must place a sample tag on the soil sample container immediately upon sampling. This tag must remain with the soil sample throughout processing. The tag will contain the following information:

- Sample number;
- Material type;
- Project name and project number;
- Sampling CQA Monitor;
- Date sampled; and
- Test(s) to be performed.

#### 3.2.5 Soil Sample Processing

The CQA Monitor is responsible for the timely processing of soil test samples. The CQA Manager will determine which samples are tested on-site and which are tested off-site. This determination will be made based on available manpower, available equipment, complexity of testing, and the desired turnaround time for results. For expediency, samples to be tested off-site should be shipped the same day they are collected.

### 3.3 Field Density Tests

#### 3.3.1 Test Numbering

The CQA Monitor is responsible for maintaining test numbers and results for field density tests performed using the nuclear gauge (ASTM D6938), sand cone (ASTM D1556), and drive cylinder (ASTM D2937). All other testing is identified through the sample number (Section 3.2.3). The CQA Monitor will maintain field books that identify soil segments, test data, the CQA Monitor performing the test, and the sequential test number. Each soil segment will have a unique series of numbers. No test number can be repeated for a given soil segment, and re-tests of failing tests must be given a letter suffix along with the original test number (i.e., re-tests for a failing test 1201 would be: 1201A, 1201B, etc.). Test data and results must be filled out on the field density test form.

#### 3.3.2 Test Locations

The intent of the CQA program is to provide confidence that the earthwork materials and work conform to the requirements of the Specifications. To meet this intent, the CQA Monitor will perform density tests of earthfills during construction. Density tests must be located at various elevations and uniformly dispersed throughout the entire plan dimensions of the fill. Density test locations must be chosen without bias; however, additional testing can be performed in any areas that are suspect, marginal, or appear to be of poor quality. During the progress of the work, density test

locations will be plotted on a drawing by the CQA Monitor to document that no significant areas are left untested. This drawing will be included in the Final CQA Report.

### **3.4 Monitoring and Testing Requirements**

Earthwork components of the construction are summarized in Section 3.1. Each component has specific construction requirements that must be monitored. The following sections list monitoring requirements for each type of earthwork.

#### **3.4.1 Clearing, Grubbing, and Stripping**

- Document that erosion and sediment control silt fences, straw bale barriers, and other measures are securely in place prior to initiating clearing, grubbing, and stripping operations in any area.
- Document that existing plant life designated to remain is protected against damage during construction.
- Document that clearing and stripping in areas required for site access and execution of the work is complete.
- Document that vegetation, roots, and highly organic soil within the work area are removed to the appropriate extent.

#### **3.4.2 Stockpiling and Soil Management**

- Review the Contractor's approved work plan submittal. Verify stockpile locations, stockpile dimensions, haul routes, material segregation procedures, and erosion, sediment, and drainage control measures. Determine and note corrective action items, if applicable.
- Document that stockpile locations have been cleared, grubbed, and stripped in accordance with Section 3.4.1 of this CQA Plan and the Specifications.
- Document that stockpile subgrades are surveyed prior to stockpiling.

The CQA Monitor will maintain a separate soil test data summary sheet for the specific purpose of soil classification of stockpiled materials.

- During excavation, hauling, and stockpiling operations, continually identify and verify material classifications in general accordance with ASTM D2487 (Unified Soil Classification System) and ASTM D2488 as necessary to characterize material stockpile designations.
- Observe that stockpiles are constructed with slopes no greater than 2H:1V (horizontal:vertical) and that the top surface maintains a minimum 5 percent grade. The Contractor shall include 15-foot-wide drainage benches every 50 vertical feet on all stockpiles.



### 3.4.3 Excavation

- Document that construction staking is performed before work and that survey bench marks with elevations are secured outside the work area.
- If applicable, document that the Contractor has notified Underground Service Alert to identify and locate underground utilities.
- Document that excavated materials are segregated into proper stockpiles.
- Coordinate with the Contractor to perform excavation verification surveys upon completion of excavating operations. Verify corrective action measures as determined by verification surveys. Verification surveys will also be used to determine limits of excavation for measurement and payment applications. Submit a copy of verification surveys to the Construction Manager.
- Document that unsuitable materials are removed from areas that will receive earthfill. Unsuitable materials include uncertified existing fills, disturbed soils, weak/highly compressible soils, and deleterious materials.

### 3.4.4 Structural Fill/Foundation Layer

- Monitor that subgrade for placement of soil is consistent with the Specifications.
- Monitor that construction staking is performed before the beginning of the work and that survey bench marks with elevations are secured outside the work area.
- Perform visual and manual soil classifications (ASTM D2488) to verify that the material source is suitable for structural fill. Verify that the material is free of organic and oversized materials and perform classifications continually during excavation of borrow materials.
- Perform moisture-density relationship testing (ASTM D1557) to determine the maximum dry density and optimum moisture content for structural fill/foundation layer materials. Perform tests at the testing frequencies specified in Table 3-1.
- Monitor that structural fill materials are placed in loose lifts not exceeding 8-inches thick and are then properly compacted.
- Perform nuclear density-moisture tests (ASTM D6938) to document that each lift is compacted to the appropriate relative compaction, as stipulated in the Specifications. Perform tests at the testing frequencies specified in Table 3-1.
- Monitor that soil materials are kept within the specified moisture content range listed in the Specifications. Monitor that soil materials that are wet and over the optimum moisture content (as determined by ASTM D1557) are properly aerated and processed to bring the moisture content of the material into the acceptable range. Monitor that soils that are dry and below the optimum moisture content (as determined by ASTM D1557) are properly moisture conditioned and processed to bring the moisture content into the acceptable range.

- Monitor that desiccated structural fills are properly repaired or removed before placing subsequent lifts.
- Monitor that final structural fill/foundation layer surfaces are free of ruts, gouges, and other features that might contribute to erosion and sediment run-off.
- During fill operations, field-verify lines, grades, and dimensions using hand-held levels, range poles, and measuring tapes.
- Coordinate with the Contractor to perform verification surveys at the completion of structural fill/foundation layer operations. Verify corrective action measures as determined by verification surveys. Verification surveys will also be used to determine the limits of structural fill/foundation layer for measurement and payment applications. Submit copies of verification surveys to the Construction Manager.

#### 3.4.5 Geosynthetics Subgrade Preparation

- Monitor that the subgrade is free of organic and oversized materials and meets the requirements of the Specifications.
- Monitor that grade control construction staking is performed prior to the work.
- Perform moisture-density relationship testing (ASTM D1557) to determine the maximum dry density and optimum moisture content of subgrade materials.
- Monitor that angular or sharp rocks, rocks that protrude more than 0.5 inches, and other debris that could damage the overlying geomembrane are removed from the surface of the subgrade. Verify that the subgrade is free of irregularities and is steel drum rolled smooth prior to geomembrane placement.
- Monitor that the final surface provides continuous and intimate contact with the overlying geomembrane.
- Coordinate with the Contractor to perform subgrade verification surveys upon completion of the subgrade preparation. Verify corrective action measures as determined by the verification surveys. Verification surveys will also be used to determine the limits of the subgrade preparation for measurement and payment applications. Submit copies of verification surveys to the Construction Manager.

#### 3.4.6 Vegetative Cover Soil

- Monitor that the material source is suitable for the vegetative cover soil layer and is free of organic or other deleterious materials and free of over-sized particles as described in the Specifications.
- Monitor that grade control construction staking is performed before the work.
- Verify that the vegetative cover soil is placed in a manner that does not damage the underlying geosynthetic layers.

- Coordinate with the Contractor to perform vegetative cover soil verification surveys upon completion of placement operations. Verify corrective action measures as determined by the verification surveys. Verification surveys will also be used to determine the limits of the vegetative cover soil for measurement and payment applications. Submit copies of verification surveys to the Construction Manager.

#### 3.4.7 Trenching and Backfilling

- Monitor that construction staking is performed before the work and that survey bench marks with elevations are secured outside the work area.
- Monitor that trenches are excavated in accordance with the dimensional cross-sections and design elevations shown on the Plans.
- Monitor profile surveys conducted by the Contractor during trenching operations.
- Perform moisture-density relationship testing (ASTM D1557) to determine the maximum dry density and optimum moisture content of soil materials that will be used as backfill.
- Perform nuclear density-moisture tests (ASTM D6938) to verify that backfill materials are moisture conditioned and compacted in accordance with the Specifications.

## **4. CONSTRUCTION QUALITY ASSURANCE FOR GEOSYNTHETICS**

### **4.1 General**

The objectives of the geosynthetics CQA program are to assure that: (i) proper construction techniques and procedures are used, and (ii) the project is completed in accordance with the Plans and Specifications. The intents of the CQA program are to: (i) identify and define problems that may occur during construction, and (ii) document that these problems are corrected before construction is complete.

This section describes CQA procedures for the installation of geosynthetic components. The following geosynthetics will be utilized for this project:

- Non-woven geotextile; and
- 40-mil HDPE geomembrane (textured on both sides).

CQA for the geosynthetics installations will be performed to monitor that geosynthetics are installed in accordance with the design. Construction must be conducted in accordance with the Plans and Specifications. To monitor compliance, the CQA Manager will: (i) review the Contractor's quality control submittals; (ii) perform material conformance testing; (iii) monitor construction testing; and (iv) monitor installations. Conformance testing refers to activities that take place before geosynthetics installation. Construction testing includes activities that occur during geosynthetics installation.

The CQA testing will be conducted in accordance with this CQA Plan and the project's Plans and Specifications. If a discrepancy exists in the testing requirements, the document that requires the most stringent testing will govern.

### **4.2 Geomembrane**

#### **4.2.1 Delivery, Storage, and Handling**

Upon delivery of geomembrane, the CQA Monitor will:

- Observe geomembrane rolls for damage during shipping and handling, identify and mark any damaged materials, and document that damaged materials are set aside.
- Observe that the geomembrane is stored in accordance with the Specifications and is protected from puncture, dirt, grease, water, moisture, mud, mechanical abrasions, excessive heat, direct sunlight, and other damage.
- Document that all manufacturing documentation required by the Specifications has been received.
- Complete the geosynthetics inventory form for all geomembrane materials received.

Damaged geomembrane may be rejected. If rejected, document that material is removed from the site or stored at a location separate from accepted geomembrane. Geomembrane that does not have proper documentation from the manufacturer must be stored at a separate location until all documentation has been received, reviewed, and accepted.

4.2.2 Conformance Testing

**Geomembrane Material Tests.** Geomembrane samples will be obtained for conformance testing in accordance with Table 4-1. The material will be sampled at the site by the CQA Monitor or at the manufacturing plant under the direction of the CQA Consultant. The samples will be forwarded to an independent testing laboratory for the following conformance tests:

**TABLE 4-1  
 HIGH DENSITY POLYETHYLENE (HDPE) GEOMEMBRANE  
 CONFORMANCE TESTING FREQUENCIES**

Property	Test Method	Conformance Test Frequency <sup>(6)</sup>
Thickness (min. avg.)	ASTM D5994	1 per 250,000 sf
Asperity Height (min. avg.) <sup>(1)</sup>	GRI GM 12	1 per 250,000 sf
Melt Flow Index	ASTM 1238	1 per 250,000 sf
Sheet Density (min avg.)	ASTM D792 or ASTM D1505	1 per 250,000 sf
Tensile Properties <sup>(2)</sup> (min. avg.) <ul style="list-style-type: none"> <li>• Yield strength</li> <li>• Break strength</li> <li>• Yield elongation</li> <li>• Break elongation</li> </ul>	ASTM D6693 Type IV	1 per 250,000 sf
Puncture Resistance (min. avg.)	ASTM D4833	1 per 250,000 sf
Carbon Black Content (range)	ASTM D1603 <sup>(3)</sup>	1 per 250,000 sf
Carbon Black Dispersion <sup>(4)</sup>	ASTM D2663 ASTM D5596	1 per 250,000 sf
Interface Shear Strength <sup>(5)</sup> <ul style="list-style-type: none"> <li>• cover soil / geotextile</li> <li>• geotextile / geomembrane</li> <li>• geomembrane / foundation layer</li> </ul>	ASTM D6243	1 per project

Notes to Table 4-1:

- (1) Alternate the measurement side for double sided textured sheets.
- (2) Machine direction (MD) and cross machine direction (XMD) average values shall be on the basis of 5 test specimens in each direction:
  - Yield elongation is calculated using a gage length of 1.3 inches.
  - Break elongation is calculated using a gage length of 2.0 inches.
- (3) Other methods such as D4218 (muffle furnace) or microwave methods are acceptable if an appropriate correlation to D1603 (tube furnace) can be established.
- (4) Carbon black dispersion (only near spherical agglomerates) for 10 different views.
- (5) Interface shear strength tests shall be tested at normal loads of 200; 500; 1,000; and 2,000 pounds per square foot. Results of the testing shall be forwarded to the Engineer for review and approval. Test reports shall include peak and large-displacement (2.5 inches) shear stress values.
- (6) Minimum testing frequency shall be one sample per lot.

The CQA Manager will review all conformance test results and report any non-conformance to the Construction Manager and Contractor.

The Final CQA Report shall include a table similar to Table 4-1 documenting compliance with the testing frequencies and results documenting compliance with the Specifications.

**Sampling Procedure.** Samples will be taken across the entire roll width. Samples may be cut for shipping purposes, but a minimum of five square feet must be sent to the testing laboratory. Samplers must mark the machine direction and the manufacturer's roll identification number on the sample (each piece). Samplers will also assign a conformance test number to the sample and mark the sample with that number.

#### 4.2.3 Geomembrane Installation

**Surface Preparation.** The soil surface must be prepared in accordance with the Specifications. Before geomembrane installation, the subgrade will be inspected by the CQA Monitor and Geosynthetics Contractor. The CQA Monitor must check the following:

- All lines and grades for the soil surface have been verified by the Contractor.
- The soil surface has been rolled/compacted and is free of surface irregularities, loose soil, and protrusions.
- The soil surface is firm and does not contain stones or other objects that could damage the geomembrane.
- The anchor trench dimensions have been checked and the trenches are free of sharp objects and stones.
- There are no excessively soft areas.
- The soil surface is not saturated and no standing water is present.
- The soil surface is not desiccated.
- All construction stakes, if utilized, have been removed and accounted for and there is no debris, rocks, or any other objects in or on the soil surface.
- The Geosynthetics Contractor has certified in writing that the surface on which the geomembrane will be installed is acceptable.

**Panel Placement.** Before installing any of the geomembrane, the Geosynthetics Contractor must submit drawings in accordance with the Specifications. These drawings will show the proposed layout of the panels, including panel identification numbers, field seams, and any other details that do not conform to the Plans.

The CQA Monitor will maintain an up to date panel layout drawing that shows the following: (i) roll numbers; (ii) panel numbers; (iii) seam numbers; (iv) test locations; (v) repair locations; and, (vi) non-destructive testing information.

During panel placement operations, the CQA Monitor will:

- Record panel numbers and dimensions on the panel/seam log.
- Observe the panel surface as it is deployed and record all panel defects and defect corrective actions (panel rejected, patch installed, extrudate placed over the defect, etc.)

on the repair sheet. Verify that corrective actions are made in accordance with the Specifications.

- Monitor that equipment used during deployment operations does not damage the geomembrane. Verify that equipment used on the geomembrane does not leak hydrocarbons onto the geomembrane or that corrective measures are taken to prevent leakage.
- Observe that the surface beneath the geomembrane has not deteriorated since previous acceptance. Verify that no stones, construction debris, or other items are beneath the geomembrane that could damage the geomembrane.
- Monitor that the geomembrane is not dragged across an unprotected surface. If the geomembrane is dragged across an unprotected surface, the geomembrane must be inspected for scratches and repaired or rejected, if necessary.
- Record weather conditions including temperature, wind speed and direction, and humidity. Verify that the geomembrane is not deployed in the presence of excess moisture (fog, dew, mist, etc.). In addition, verify that the geomembrane is not placed when the air temperature is less than 40° F or when standing water or frost is on the ground.
- Monitor that crews working on the geomembrane do not smoke, do not wear shoes that could damage the liner, and do not engage in activities that could damage the geomembrane.
- Monitor that methods used to deploy the geomembrane minimize wrinkles and that panels are anchored to prevent movement by the wind. Verify that the Geosynthetics Contractor corrects any damage resulting to or from windblown geomembrane.
- Monitor that no more panels are deployed than can be seamed on the same day.
- The CQA Monitor must inform both the Geosynthetics Contractor and the CQA Manager if any of the above conditions are not met.

**Field Seaming.** Before the start of geomembrane welding and during welding operations, each welder and welding apparatus will be tested in accordance with the Specifications to verify that the equipment is functioning properly. One trial weld will be taken before the start of work and one at mid-shift. The trial weld sample will be at least 42-inches-long and 12-inches-wide, with the seam centered lengthwise. The CQA Monitor will observe all welding operations and verify that the Geosynthetics Contractor quantitatively tests each trial weld for peel adhesion and bonded seam strength (ASTM D6392). (Peel adhesion tests will be referred to as “peel” and bonded seam strength tests will be referred to as “shear” in this document.) The main purposes of the trial weld tests are to evaluate seam strength and to confirm that each welding machine is working properly. Shear tests measure the continuity of tensile strength through the seam and into the parent material. Peel tests measure the strength of the bond created by the welding process.

The results of the peel and shear tests on trial welds will be recorded on the trial weld form. Trial welds must be completed under conditions similar to those under which the panels will be welded. Trial welds must meet specified requirements for peel and shear and the failure must be ductile or a film tearing bond (FTB) for a wedge weld. An FTB failure occurs when the test specimen breaks at

the edge of the outside of the seam but not within that seam. If at any time the CQA Monitor believes that a welding machine is not functioning properly, a trial weld by that machine must be performed and tested. If there are wide changes in temperature ( $> 30^{\circ}\text{F}$ ), humidity, or wind speed, another trial weld must be performed and tested. The trial weld must be allowed to cool to ambient temperature before it is tested.

During geomembrane welding operations, the CQA Monitor will:

- Monitor that the Geosynthetics Contractor has an appropriate number of welding machines and spare parts necessary to perform the work.
- Monitor that equipment used for welding will not damage the geomembrane.
- Monitor that extrusion welders are purged before beginning a weld so that all heat-degraded extrudate is removed from the nozzle of the extrusion welder.
- Monitor that seam grinding is completed less than 1 hour before seam welding and that the upper sheet is beveled (extrusion welding only).
- Monitor that the ambient temperature measured 6-inches above the geomembrane surface is between  $40^{\circ}\text{F}$  and  $110^{\circ}\text{F}$ .
- Monitor that the ends of extrusion welds that are more than 5 minutes old are ground to expose new material before restarting a weld.
- Monitor that contact surfaces of the panels are clean and free of dust, grease, dirt, debris, and moisture before welding.
- Monitor that welds are free of dust, rocks, and other debris.
- Monitor that cross seams are ground to a smooth incline before welding (fusion welding only).
- Monitor that all seams are overlapped a minimum of 3 inches or in accordance with the manufacturer's recommendations, whichever is more stringent.
- Monitor that solvents or adhesives are not present in the seam area.
- Monitor that procedures used to temporarily hold the panels together do not damage the panels and do not preclude CQA testing.
- Monitor that strips of geomembrane, wide enough and long enough to protect the hot wedge welder from running on the subgrade, are placed below the geomembrane. These strips may be as long as the seam itself or shorter and moved with the seaming equipment. If necessary, a firm material such as a flat board or similar hard surface may be placed directly under the weld overlap to achieve firm support.
- Monitor that panels are being welded in accordance with the Plans and Specifications.
- Monitor that there is no free moisture in the weld area.



- Measure surface temperature of the panels every 2 hours.

#### 4.2.4 Construction Testing

**Nondestructive Seam Testing.** The purpose of nondestructive geomembrane seam testing is to detect discontinuities or holes in the seams. Nondestructive geomembrane seam tests include vacuum box and air pressure testing. Nondestructive testing must be performed over the entire length of each seam.

It is the Geosynthetics Contractor's responsibility to perform all nondestructive testing as part of their quality control (QC) program. The CQA Monitor's responsibility is to observe and document that the Geosynthetics Contractor's QC testing is in compliance with the Specifications and to document seam defects and repairs.

Nondestructive seam testing procedures are described below:

- For welds tested by the vacuum box method, the weld is placed under suction utilizing a vacuum box constructed with rigid sides, a transparent top for viewing the seams, a neoprene rubber gasket attached to the bottom of the rigid sides, a vacuum gauge on the inside, and a valve assembly attached to a vacuum hose connection. The box is placed over a seam section which has been thoroughly saturated with a soapy water solution (1 oz. soap to 1 gallon water). The rubber gasket on the bottom of the box must fit snugly against the soaped seam section of the panel to ensure a leak-tight seal.
- A vacuum pump is energized and the vacuum box pressure reduced to approximately 5 psi gauge. Any pinholes, porosity, or non-bonded areas are detected by the appearance of soap bubbles in the vicinity of the defect. Dwell time must not be less than 10 seconds.
- Air pressure testing is used to test double wedge seams that have an enclosed air channel between them. Both ends of the air channel must be sealed. A pressure feed device, usually a hollow needle equipped with a pressure gauge, is inserted into one end of the channel. Air is then pumped into the channel to a minimum pressure of 25 to 30 psi. The air channel must sustain this pressure for 5 minutes without losing more than 2 psi. Following the 5-minute hold time, the opposite end of the tested seam must be punctured to release the air. The pressure gauge must return to zero; if it does not return to zero a blockage is likely present in the seam channel. Locate the blockage and test the seam on both sides of the blockage. The penetration holes must be sealed after testing.

During nondestructive seam testing, the CQA Monitor will:

- Review the Specifications regarding test procedures.
- Monitor that equipment operators are fully trained and qualified to perform their work.
- Monitor that test equipment meets the Specifications.
- Monitor that the entire length of each seam is tested in accordance with the Specifications.
- Observe testing and record results on the panel/seam log and the panel layout drawing.

- Identify any failed areas by marking the area with a waterproof marker compatible with the geomembrane, inform the Geosynthetics Contractor of any required repairs, and record the repair on the panel/seam log.
- Monitor that all repairs are completed and tested in accordance with the Specifications.
- Record all completed and tested repairs on a repair sheet and the panel layout drawing.

**Destructive Seam Sampling Procedures and Field Testing.** Destructive seam samples will be taken at intervals of at least one per 500 linear feet of geomembrane seam. However, additional samples will be taken if the CQA Monitor suspects that a seam does not meet the Specification's requirements. Reasons for taking additional samples may include, but are not limited to:

1. Wrinkling in the seam area.
2. Excess crystallinity.
3. Suspect seaming equipment or techniques.
4. Weld contamination.
5. Insufficient overlap.
6. Adverse weather conditions.
7. Failing tests.

The CQA Monitor will select the locations from where seam samples will be cut for destructive laboratory testing as follows:

- A minimum of one test per 500 feet of seam length. This is an average frequency for the entire installation; individual samples may be taken at greater or lesser intervals. The testing frequency will be increased if welding operations are conducted in temperatures below 40° F. This increase will be agreed to by the Construction Manager, CQA Manager, and Geosynthetics Contractor.
- A maximum frequency must be agreed to by the Construction Manager, CQA Manager, and Geosynthetics Contractor at the pre-construction meeting. However, if the number of failed samples exceeds 5 percent of the tested samples, this frequency may be increased at the discretion of the CQA Manager. Samples taken as the result of failed tests do not count toward the total number of required tests.

The CQA Monitor will not inform the Geosynthetics Contractor in advance of selecting the destructive sample locations.

The Geosynthetics Contractor will remove the destructive samples at locations identified by the CQA Monitor and field test the specimens for peel and shear before the samples are shipped off-site for laboratory testing. During sampling procedures the CQA Monitor will:

- Observe sample cutting.
- Mark each specimen and sample with an identifying number which contains the seam number, destructive sample test number, welder, and date and time welded.
- Record sample locations on the panel layout drawing and panel-seam logs.

- Record the sample locations, weather conditions, and reasons samples were taken (e.g., random sample, visual appearance, result of a previous failure, etc.) in the destructive seam test form.

At each location, obtain two seam specimens that are 44-inches apart. The specimens should be 1-inch wide and 12-inches long with the weld centered across the length of the specimen. The Geosynthetics Contractor must test these samples to failure in the field using a tensiometer capable of quantitatively measuring shear and peel strengths. For double wedge welding, the Geosynthetics Contractor must test both welds. The CQA Monitor will observe the tests. Geomembrane seam specimens pass when the break is a ductile FTB and the seam strength meets the specified values.

If one or both of the 1-inch specimens fails in either peel or shear, the Geosynthetics Contractor can, at his discretion: (1) reconstruct the entire seam between passed test locations; or (2) take another test sample 10 feet from the point of the failed test and repeat this procedure. If the second test passes, the Geosynthetics Contractor can either reconstruct or cap strip the seam between the two passed test locations. If subsequent tests fail, the sampling and testing procedure is repeated until the length of the poor quality seam is established. Repeated failures indicate that either the seaming equipment or operator is not performing properly and that appropriate corrective action must be taken immediately.

Once the field test specimens have passed, a sample must be recovered for laboratory testing from between the passing field specimen locations. The sample must be 42-inches long and 12-inches wide, with the weld centered along the length of the sample. The sample must be divided into three sections: one 12-inch by 12-inch section for the Geosynthetics Contractor, one 12-inch by 18-inch section for laboratory testing, and one 12-inch by 12-inch section for the Owner to archive. Record the results of field testing on the destructive seam test form and the panel/seam log.

**Third Party Laboratory Testing.** The CQA destructive seam samples can be shipped to the testing laboratory to verify seam quality. The laboratory will test five specimens from each sample in both shear and peel modes of failure. Minimum required test values are presented in the Specifications. The testing laboratory must provide verbal test results within 24 hours to the CQA Manager and written certified test results within 5 days.

The CQA Manager must immediately notify the Construction Manager and Geosynthetics Contractor in the event of failed seam test results.

If a laboratory test fails in either peel or shear, the Geosynthetics Contractor must either reconstruct the entire seam or recover additional samples at least 10 feet on either side of the failed sample for retesting. This process is repeated until passed tests bracket the failed seam section. All seams must be bounded by locations from which passing laboratory tests have been taken. Laboratory testing governs seam acceptance. In no case can field testing of repaired seams be used for final acceptance.

#### 4.2.5 Repairs

Portions of geomembrane panels and seams that contain: (1) a flaw; (2) a destructive test; or (3) nondestructive test cuts or holes must be repaired in accordance with the Specifications. The CQA Monitor must locate and record all repairs on the repair sheet and panel layout drawing. Acceptable repair techniques include the following:

- Patching: used to repair large holes, tears, large panel defects, undispersed raw materials, welds, contamination by foreign matter, and destructive sample locations.

- Extrusion: used to repair small defects in the panels and seams. In general, this procedure should be used for defects less than 2-inches in the largest dimension.
- Capping: used to repair failed welds or to cover seams where welds cannot be nondestructively tested.
- Removal: used to replace areas with large defects where preceding methods are not appropriate. Also used to remove excess material (wrinkles, fishmouths, intersections, etc.) from the installed geomembrane. Areas of removal shall be patched or capped.

Repair procedures include the following:

- Abrade geomembrane surfaces to be repaired (extrusion welds only) no more than 1 hour before the repair.
- Clean and dry all surfaces at the time of repair.
- Monitor acceptance of the repair procedures, materials, and techniques by the CQA Monitor in advance of the specific repair.
- Extend patches or caps at least 6 inches beyond the edge of the defect and round all corners of material to be patched and the patches to a radius of at least 3 inches. Bevel the top edges of patches before extrusion welding.

#### 4.2.6 Folded Material

Geomembrane with excessive folding (i.e., creased), as determined by the CQA Consultant, must be removed.

#### 4.2.7 Geomembrane Anchor Trench

The geomembrane anchor trench should be left open until seaming is completed. Expansion and contraction of the geomembrane should be accounted for in the liner placement. The anchor trench should be filled in the morning when temperatures are coolest to reduce bridging of the geomembrane.

#### 4.2.8 Geomembrane Acceptance

The Contractor retains all ownership and responsibility for the geomembrane until acceptance by the Owner. In the event the Contractor is responsible for placing cover over the geomembrane, the Contractor retains all ownership and responsibility for the geomembrane until all required documentation is complete and the cover material is placed. After panels are placed, seamed, tested successfully, and repairs made, the completed installation will be walked by the CQA Monitor and Contractor. Any damage or defects found during this inspection will be repaired by the Geosynthetics Contractor. The installation will not be accepted until it meets the requirements of both parties. In addition, the geomembrane will be recommended for acceptance by the CQA Manager only when the following have been completed:

- The installation is finished.

- All seams have been inspected and verified to be acceptable and all required laboratory and field tests have been completed and reviewed.
- All required Contractor-supplied documentation has been received and reviewed.
- All as-built drawings have been reviewed and verified by the CQA Manager to show the true panel dimensions, the locations of all seams, trenches, pipes, appurtenances, and destructive test locations.

#### 4.2.9 Qualifications

Proper layout, seaming, and testing of the geomembrane requires skill and experience. As such, the integrity of the geomembrane is dependent upon the installers. In order to assure a minimum level of experience and expertise, the following experience standards have been established in the Specifications:

**Manufacturer/Fabricator/Installer.** The Specifications list the required qualifications for the geomembrane manufacturer / fabricator / installer companies. The CQA Manager must verify qualifications of the manufacturer, fabricator, and installer through review of Engineer-approved project submittals.

**Installation Superintendent.** The installation field superintendent must have been responsible for the completed installation of a minimum of 5,000,000 square feet of polyethylene geomembrane in the past 5 years utilizing the type of seaming techniques and apparatus proposed for use on this project. A resume with references and phone numbers of satisfactory installations is required. Any superintendent proposed for this project must be present whenever geomembrane is installed.

**Master Seamer and Other Welders.** The master seamer must have demonstrated expertise on previous geomembrane installations. The master seamer must have successfully welded a minimum of 1,000,000 square feet of polyethylene geomembrane within the past 3 years. A resume for this work, with references and phone numbers, is required. Other welders are required to have welded a minimum of 100,000 square feet of geomembrane within the past 3 years. Resumes for all welders, with references and phone numbers, are required. Personnel that have welded less than 100,000 square feet of geomembrane within the past 3 years will only be allowed to weld under the direct supervision of either the master seamer or the installation superintendent.

**CQA Manager Qualifications.** The CQA Manager must have provided CQA services on a minimum of 1,000,000 square feet of polyethylene installations or be level II certified in geosynthetics installations by National Institute for Certification in Engineering Technologies (NICET). The CQA Manager must provide verification of this experience by references in a current resume.

### 4.3 Geotextiles

#### 4.3.1 Delivery, Storage, and Handling

During delivery of geotextiles the CQA Monitor will:

- Monitor that equipment used to unload the rolls does not damage the geotextile.
- Monitor that rolls are wrapped in impermeable and opaque protective covers.
- Monitor that care is used to unload the rolls.
- Monitor that all documentation required by the Specifications has been received.
- Monitor that each roll is marked or tagged with the following information: manufacturer's name; project identification; lot number; roll number; and roll dimensions. Log this information on the geosynthetic inventory form.
- Monitor that materials are stored in a location that will protect the rolls from ultraviolet light exposure, precipitation, mud, dirt, dust, puncture, cutting, or any other damaging or deleterious conditions.

Any damaged rolls may be rejected. Monitor that rejected material is removed from the site and stored at a location separate from accepted rolls. Geotextile rolls which do not have proper manufacturer's documentation must also be stored at a separate location until all documentation has been received and approved.

#### 4.3.2 Conformance Testing

**Geotextile Material Tests.** The CQA Manager will arrange to obtain geotextile conformance test samples as indicated in Table 4-2. These samples will be sent to the testing laboratory for the following conformance tests:

**TABLE 4-2  
NON-WOVEN GEOTEXTILE CONFORMANCE TESTING FREQUENCIES**

Property	Test Method	Conformance Test Frequency <sup>(1)</sup>
Mass/Unit Area (min. avg.)	ASTM D5261	1 per 250,000 sf
Apparent Opening Size (max.)	ASTM D4751	1 per project
Grab Strength (min. avg.)	ASTM D4632	1 per 250,000 sf
Permittivity (min.)	ASTM D4491	1 per project
Puncture Strength (min. avg.)	ASTM D4833	1 per 250,000 sf

Note to Table 4-2:

(1) Minimum testing frequency shall be one sample per lot.

The CQA Manager will review all conformance test results and report any non-conformance to the Construction Manager and Contractor.

The Final CQA Report shall include a table similar to Table 4-2 documenting compliance with the testing frequencies and results documenting compliance with the Specifications.

**Sampling Procedure.** Samples will be obtained across the entire roll width and will be 3-feet long. Samplers must mark the manufacturer's roll identification number and the machine direction on the sample. Samplers will also assign a conformance test number to the sample and mark the sample with that number.

#### 4.3.3 Geotextile Installation

**Surface Preparation.** Before geotextile installation, the CQA Monitor will:

- Monitor that all lines and grades have been verified by the Contractor.
- Monitor that the subgrade has been prepared in accordance with the Specifications and that the geomembrane installation and all associated documentation has been completed.
- Monitor that soil or geomembrane surfaces do not contain stones that could damage the geotextile.
- Monitor that there are no excessively soft areas in soil surfaces that could damage the geotextile.

**Geotextile Placement and Seaming.** During geotextile placement and seaming operations, the CQA Monitor will:

- Observe the geotextile as it is deployed and record all defects and defect corrective actions (panel rejected, patch installed, etc.). Verify that corrective actions are performed in accordance with the Specifications.
- Monitor that equipment used does not damage the geotextile by handling, equipment transit, leakage of hydrocarbons, or other means.
- Monitor that crews working on the geotextile do not smoke, do not wear shoes that could damage the geotextile, and do not engage in activities that could damage the geotextile.
- Monitor that the geotextile is securely anchored in an anchor trench and is temporarily anchored to prevent movement by the wind.
- Monitor that adjacent panels are overlapped and seamed in accordance with the Specifications.
- Monitor that the geotextile is not exposed to direct sunlight for more than 5 days.
- Examine the geotextile after installation to ensure that no potentially harmful foreign objects are present.
- The CQA Monitor must inform both the CQA Manager and Contractor if the above conditions are not met.

#### 4.3.4 Repairs

Repair procedures include:

- Patching: used to repair large holes, tears, and small defective areas.
- Removal: used to replace large defective areas where the preceding method is not appropriate.



## **5. CONSTRUCTION QUALITY ASSURANCE FOR EROSION CONTROL**

### **5.1 Introduction**

This section describes CQA procedures for temporary and permanent erosion control installations.

CQA for the temporary and permanent erosion control measures will be performed to verify that the Contractor complies with the requirements of the project's Stormwater Pollution Prevention Plan (SWPPP) and that the permanent erosion control measures are installed in accordance with the design. Construction must be conducted in accordance with the Plans and Specifications. To monitor compliance, the CQA Consultant will: (1) review the Contractor's quality control submittals, and (2) monitor installations.

### **5.2 Construction Monitoring**

#### **5.2.1 Temporary Erosion Control**

- Monitor that the Contractor implements temporary erosion control measures in compliance with the project's SWPPP.

#### **5.2.2 Permanent Erosion Control Measures**

##### *Erosion Mats*

- Review the Contractor's submittals for the erosion mats and verify that the material complies with the manufacturer's recommendations and the Specifications.
- Monitor that the Contractor installs the erosion mats at the locations indicated on the Plans.
- Monitor that the Contractor installs the erosion mats prior to revegetation of the final cover.
- Monitor that the Contractor installs the erosion mats in accordance with the manufacturer's recommendations.

##### *Straw Wattles*

- Review the Contractor's submittals for the straw wattles and verify that the material complies with the manufacturer's recommendations and the Specifications.
- Monitor that the Contractor installs the straw wattles at the locations indicated on the Plans.
- Monitor that the Contractor installs the straw wattles prior to revegetation of the final cover.
- Monitor that the Contractor installs the straw wattles in accordance with the manufacturer's recommendations.

##### *Revegetation*

- Review the Contractor's submittals for the hydroseed mix design and straw mulch for compliance with the Specifications.
- Monitor that the Contractor evenly and uniformly distributes the hydroseed mixture over the final cover and that there are no bare spots.
- Monitor that the Contractor evenly and uniformly distributes the straw mulch in accordance with the Specifications.
- Monitor that the Contractor irrigates the revegetated areas during construction.

## **6. CONSTRUCTION QUALITY ASSURANCE FOR DRAINAGE FACILITIES**

### **6.1 Introduction**

This section describes CQA procedures for the surface water drainage facilities. The drainage facilities consist of various types of drainage channels, drop inlets, culverts, and diversion berms.

CQA for the drainage facilities installation will be performed to verify that these facilities are constructed in accordance with the Plans and Specifications. To monitor compliance, the CQA program will: (1) review the Contractor's quality control submittals; (2) monitor construction testing; and (3) monitor installations.

Construction testing will be conducted in accordance with the Specifications.

### **6.2 Construction Monitoring**

#### **6.2.1 Drainage Channels**

- Monitor that grade control construction staking for the drainage channels is performed before the work.
- Monitor that the drainage channels are constructed in accordance with the Drawings and Specifications.
- Monitor that the subgrades of the drainage channels are dry, firm, and unyielding and do not have loose or extraneous material.
- Document that drainage ditches are graded and sloped in accordance with the Plans and Specifications. Review verification surveys and notify the Contractor of areas needing repair. Submit copies of verification surveys to the Construction Manager.

#### **6.2.2 Drop Inlets and Culverts**

- Review the Contractor's submittals for the piping and drop inlets for compliance with the Specifications.
- Monitor that the Contractor has excavated pipe trenches to the proper depth.
- Monitor that the Contractor has graded the slope of the pipe trenches to uniform gradient.
- Monitor that the pipe subgrades are firm and unyielding and do not have loose or extraneous material.
- Monitor and test backfilling of pipe trenches.
- Verify that inlets to drainage structures are smooth and prevent ponding.

#### **6.2.3 Diversion Berms**

- Monitor that the material used to construct the diversion berms complies with the Specifications for structural fill.

## 7. DOCUMENTATION

This CQA Plan requires thorough monitoring and documentation of the construction activities. The CQA Manager will document that the CQA requirements have been addressed and satisfied. Documentation will consist of daily record keeping, testing and installation reports, non-conformance reports (if necessary), progress reports, photographic records, design and Specification revisions, and a Final CQA Report.

### 7.1 Daily Record Keeping

At a minimum, daily records will consist of a daily record of construction progress, daily construction report, observation and test data sheets, and, as needed, non-conformance/corrective measure reports. All forms will have peer review.

#### 7.1.1 Daily Record of Construction Progress

The daily field report will summarize ongoing construction and discussions with the Contractor and will be prepared by the CQA Manager and CQA Monitor. At a minimum, the report will include the following:

1. Date, project name, project number, and location.
2. A unique number for cross-referencing and document control.
3. Weather data.
4. A description of ongoing construction for the day in the area of the CQA Monitor's responsibility.
5. An inventory of equipment utilized by the Contractor.
6. Significant items of discussion and names of parties involved in these discussions.
7. A brief description of tests and observations, identified as passing or failing, or, in the event of failure, a retest.
8. Areas of non-conformance/corrective actions, if any (non-conformance/corrective action form to be attached).
9. Summary of materials received and quality control documentation.
10. Follow-up information on previously reported problems or deficiencies.
11. Record of site visitors involved with the project.
12. Signature of CQA Manager and/or CQA Monitor.
13. Signature of the peer reviewer.

### 7.1.2 Observation and Test Data Sheets

Observation and test data sheets should include the following information as is appropriate for the form being used.

1. Date, project name, project number, and location.
2. A unique number for cross-referencing and document control.
3. Weather data, as applicable.
4. A reduced scale site plan showing sample and test locations.
5. Test equipment calibrations, if applicable.
6. A summary of test results identified as passing, failing, or, in the event of a failed test, retest.
7. Completed calculations.
8. Signature of the CQA Manager and/or CQA Monitor.
9. Signature of the peer reviewer.

### 7.1.3 Non-Conformance Reports

In the event of a non-conformance event, a non-conformance verification report form will be included with the daily report. Procedures for implementing and resolving any non-conformities to the Contract Documents are outlined in Section 2.4 of this CQA Plan.

## 7.2 Weekly Progress Reports

The CQA Manager will prepare weekly progress reports summarizing construction and CQA activities. These reports will contain, at a minimum, the following information:

- The date, project name, project number, and location.
- A summary of work activities completed in the last week and those expected to be performed in the next week.
- A summary of deficiencies and/or defects and resolutions.
- Ongoing summary of changes and/or change orders to the work.
- The signature of the CQA Manager.
- On the fourth week of each month the report will include a summary of on-site and third party laboratory test results.

### **7.3 Photographs**

Construction activities will be photographed. Photographs will show any significant problems encountered and corrective actions and will document the construction progress. The photographs will be identified by location, date, and photographer. The photographer should document the subject or the photograph, either on the back of the picture or in a photograph log.

### **7.4 Design and Specification Changes**

Design and Specification changes may be required during construction. Design and Specification changes will only be made with the written agreement of the Design Engineer, Owner, and Contractor. These changes will be made by change order to the contract. When change orders are issued, they will be prepared by the Construction Manager. The Construction Manager will distribute change orders for signature and execution to the required parties.

### **7.5 Final Construction Quality Assurance Report**

At the completion of the project, the CQA Manager and CQA Officer will submit a Final CQA Report. This report will document that the work has been performed in compliance with the Plans and Specifications.

At a minimum, the Final CQA Report will contain:

- Daily Field Reports per Section 7.1.1.
- Inspection data sheets that contain observations and a record of field and laboratory tests per Section 7.1.2.
- A summary of the construction activities.
- A tabular summary of the laboratory and field test results demonstrating construction is in compliance with the Specifications.
- Sampling and testing location drawings.
- A description of significant construction problems and the resolution of these problems.
- A list of changes from the Plans and Specifications and the justifications for these changes.
- As-built (record) drawings.
- A statement of compliance with the Contract Documents and design intent that is signed and stamped by the CQA Officer.

The as-built drawings will accurately show the constructed location of the work items, including the location of piping, anchor trenches, etc. All surveying and base maps required for the development of the as-built drawings will be prepared by the Contractor. The CQA Manager will review and verify that the as-builts are correct.