

NASA-CR-132232) LH2 PUMP COMPONENT
DEVELOPMENT TESTING IN THE ELECTRIC PUMP
ROOM AT TEST CELL C INDUCER NO. 1
Final (Aerojet-General Corp., Sacramento,
Calif.) 400 p HC \$22.00 CSCL 13K

N8300R:72-101

N73-24530

Unclas
17747

G3/15

405

ENGINEERING OPERATIONS REPORT

FINAL REPORT

LH₂ PUMP COMPONENT DEVELOPMENT TESTING
IN THE ELECTRIC PUMP ROOM AT TEST CELL "C"
INDUCER NO. 1

Niewer

DRA

PROJECT 121

MAY 1972

- F. X. Andrews
- J. J. Brunner
- K. G. Kirk
- J. P. Mathews
- T. Nishioka

APPROVED:

E. K. Bair

E. K. Bair, Manager
Turbo pump Department

CLASSIFICATION CATEGORY
UNCLASSIFIED
<i>[Signature]</i> 3-27-72
CLASSIFYING OFFICER DATE

405

TABLE OF CONTENTS

	<u>PAGE</u>
I. INTRODUCTION -----	1
II. SUMMARY AND CONCLUSIONS-----	2
III. PROGRAM OBJECTIVES-----	4
IV. FLOW SYSTEM-----	5
V. TEST ARTICLE DESCRIPTION-----	7
VI. FACILITY DESCRIPTION-----	13
VII. CONTROL SYSTEM-----	17
VIII. INSTRUMENTATION-----	25
IX. DATA PROCESSING-----	47
X. TEST PROGRAM-----	61
XI. RESULTS-----	74
XII. REFERENCES-----	98

I

LIST OF APPENDICES

- A LH₂ Pump Test Data Reduction Program

- B Chronology for Experimental Plan 1 - First Day (12-8-71)

- C Chronology for Experimental Plan 1 - Second Day (12-10-71)

- D Chronology for Experimental Plan 2 - First Day (12-15-71)

- E Chronology for Experimental Plan 2 - Second Day (12-16-71)

- F Chronology for Experimental Plan 2 - Third Day (12-17-71)

- G Chronology for Experimental Plan 2A - (12-22-71)

- H Inducer No. 1 - Cavitation Test Data

LIST OF FIGURES

<u>FIGURE NO.</u>		<u>PAGE</u>
1	LCR Operational Systems, CEL Inducer Tests	6
2	Test Article, Cross Section	8
3	Inducer	10
4	Impeller and Unshrouded Tooling Verification Piece	11
5	Typical Dewar Pressurization Controller	19
6	Q/N Controller (C-8)	21
7	RPM Controller	22
8	Pump Assembly Instrumentation Location	33
9	Kaman Nuclear System	40
10	Bently Nevada System	41
11	RTT, Bearing Fluid	43
12	Narrow Band Data	45
13	Wide Band Data	46
14	LH ₂ Pump Supply System	49
15	Fluid Conditioner Throttling Process	50
16	Hypothetical Tank Condition	55
17	LH ₂ Pump Component Development Test Operating Conditions	73
18	Overall Normalized Isentropic Head Rise vs Q_D/N	75
19	Overall Head Coefficient vs Discharge Flow Coefficient	77
20	Efficiency vs Flow Parameter Q_D/N	79
21	Inducer Tip Static Head Rise vs Flow Parameter Q_S/N	80

LIST OF FIGURES (Continued)

<u>FIGURE NO.</u>		<u>PAGE</u>
22	Impeller Head Coefficient vs Discharge Flow Coefficient	82
23	Housing Head Loss Coefficient vs Discharge Flow Coefficient	84
24	Radial Force Parameter vs Q_D/N	86
25	Radial Thrust Parameter, Axial Thrust and Head Coefficient vs Net Positive Suction Pressure	88
26	Vapor Fraction β vs Normalized Inlet Flow at Head Breakdown	92
27	High Speed Test - Speed vs Time	96
28	High Speed Test - Radial Displacement and Frequency vs Speed	97

LIST OF TABLES

	<u>PAGE</u>
I Pump Instrumentation	26
II Facility Instrumentation	29
III Cavitation Data Correlation	91

I. INTRODUCTION

The NERVA Engine requirements dictates the turbopumps within the system shall have certain performance characteristics. To ascertain the performance of the pump characteristics and to identify any problems associated with its performance, early component testing of various pump configurations was desirable and was accomplished to support the design selection of the pump for the NERVA Turbopump.

The NERVA Pump will be a two stage centrifugal pump with both stages having backswept impellers and an inducer upstream of the first stage impeller.

The component tests conducted at Test Cell "C" investigated the performance of the first stage components. The first stage configuration tested consisted of an inducer, impeller and a vaned diffuser followed by a pump volute.

The test program completed on 22 December 1971 provided demonstration of the ability of the design selected for the NERVA Turbopump to meet the requirement imposed by the NERVA Engine.

All testing was conducted at the Nuclear Rocket Development Station, Jackass Flats, Nevada

II. SUMMARY AND CONCLUSIONS

The LH₂ Pump Component Development Testing was conducted during the first quarter of Contract 1972. All objectives of the program were successfully accomplished in the three experimental plans including:

1. Provision of performance data of various pump components under consideration for the NERVA turbopump.
2. Provision of cavitating performance data of the initial configuration inducer.

During the test program the following was demonstrated:

1. The non-cavitating performance of the overall test article and individual components agreed with the pretest prediction and met or exceeded the design requirements. The predicted overall head coefficient (ψ_{ov}) at design was .54. The actual value at design was .565.
2. The cavitation performance agreed with the pretest predictions and exceeded the design requirements. The empirical relationship for Net Positive Suction Pressure (NPSP) at breakdown for the LH₂ pump was:

$$NPSP = \left[\frac{P_V}{130} - 0.076 \right] \left[\frac{N}{1000} - 153.1 + 525 \left(\frac{Q}{N} \right) - 450 \left(\frac{Q}{N} \right)^2 \right]$$

where:

- N = pump speed
 Q = volumetric flow rate
 P_V = vapor pressure

3. The test rig shaft critical speed of 29,250 rpm agreed with the pretest predicted critical speed of 30,000 rpm.

4. The radial thrust agreed with pretest predicted value of .18 for the radial force parameter $\left(\frac{\text{Radial Force}}{\text{Ave Impeller Static Pressure Rise}}\right)$.

5. The axial thrust was within the capabilities of the bearings. It reached momentary peak magnitudes of 3400 lbs toward pump inlet at the highest speed, lowest Q/N value and lowest suction pressures tested. High thrust magnitudes of approximately 1000 lbs toward coupling were obtained at high suction pressures, high values of Q/N, and low speed.

III. PROGRAM OBJECTIVES

The overall objective of the LH₂ Pump Component Development Program was to investigate performance characteristics of various pump components and configurations under consideration for the NERVA Turbopump.

The main objective of this program was to investigate inducer performance. It also provided a means to establish the performance characteristics of the first stage impeller, pump volute, and a portion of the internal instrumentation being considered for use on the NERVA Turbopump.

The test article was limited to the first stage of the NERVA Turbopump by the available power of the electric drive system. It was felt that the performance of the crossover and the second stage housing could be accurately predicted from the results of the Pump Air Test Program (Reference 1*).


*References are listed in Section XII.

IV. FLOW SYSTEM

The electric pump room schematic for the pump test program is shown in Figure 1. Liquid hydrogen was provided to the pump from either Dewar 4 or 5. The inlet flow to the pump was measured by a Venturi, KF-4. Low flow rate measurements, less than five pounds per second, were measured by diverting the suction flow through Valve K-130 and measuring the flow through a turbine type Flow Meter KF-130A during chilldown. Provisions were provided to either divert the liquid hydrogen flow around or through the pump rig by Valves C-4 and C-214. The inlet line as shown in Figure 1, had provisions to use a fluid conditioner for suction pressure throttling. Valve K-3 was utilized to control the upstream pressure of the fluid conditioner. The pump inlet line also had a bellows with a removable liner which permitted investigating the effect of the bellows on suction performance.

The pump discharge line had a turbine type flow meter, CF-6, to measure discharge flow rate. The pump impedance was controlled by Valve C-8 in the pump discharge line. The bypass line was teed off the pump discharge line and Valve C-106 controlled the bypass flow. The pump rig bearing coolant flow was either diverted out through the flare stack utilizing Valve C-231 or returned to the suction line through the return manifold utilizing Valve C-221.

The pump rig was powered by the electric motors located adjacent to the electric pump room in the motor drive building.



- ELECTRIC DRIVE SYSTEM**
- UI-12 DC MOTOR NO 1 } FIELD CURRENT
 - UI-22 DC MOTOR NO 2 } FIELD CURRENT
 - UH-11 DC GENERATOR NO 1 } ARMATURE VOLTAGE
 - UH-21 DC GENERATOR NO 2 } ARMATURE VOLTAGE
 - UI-11 DC GEN / MOTOR NO 1 } ARMATURE CURRENT
 - UI-21 DC GEN / MOTOR NO 2 } ARMATURE CURRENT
 - UH-1 AC SYNCH MOTOR - LINE VOLTAGE
 - UI-2 AC SYNCH MOTOR - LINE CURRENT
 - UI-3 AC SYNCH MOTOR - POWER FACTOR

- PUMP INTERNAL**
- CT-701 - PUMP HOUSING TEMP
 - CT-703 - BEARING HOUSING TEMP
 - CT-704 - FORWARD BEARING FLUID TEMP
 - CT-706 - AFT BEARING FLUID TEMP
 - CP-700 - PUMP DISCHARGE PRESSURE
 - CP-700D - PUMP HEAD RISE
 - CP-702 - BEARING COOLANT FLOW gpm
 - CP-700 - PUMP SHAFT SPEED

- W-121 UTIL BLDG
- W-125 LN₂ DEWAR T
- W-127 DEWAR 4 & 5 T
- W-144 BORATED WATER TANK T
- W-123 CEL & MDT T
- W-123 FILL STATION D
- W-143 DEWAR 4 & 5 D
- W-110 H.P. BOTTLES T
- W-113 DEWAR 3 T
- W-115 H.P. BOTTLES EAST D
- W-117 H.P. BOTTLES WEST D
- W-133 CRYO LINE T
- W-135 DEWAR 2 UPPER T
- W-141 DEWAR 1 UPPER T
- W-231 H₂ UNLOAD D
- W-137 DEWAR 2 LOWER D
- W-139 DEWAR 1 LOWER D

N8300R:72-101
 May 1972
 Page 6


REV	DATE	DESCRIPTION	DATE	APPROV
REVISION				
1	20788	TCC CEL INDUCER TESTS LCR OPERATIONAL SYSTEMS		
EDSK-0463				

V. TEST ARTICLE DESCRIPTION

The Test Article was a single stage centrifugal pump assembly. It was mounted on a heavy steel support frame which had adjusting screws for precision alignment of the pump shaft with the gear box high speed drive shaft. The pump support frame was bolted to the concrete and steel pedestal in the Electric Pump Room (EPR). The test article was mechanically connected to the gear box drive shaft by a ball spline coupling which allowed for a small amount of misalignment, such as that due to dimensional changes from ambient conditions to cryogenic operation conditions.

The first stage pump assembly is shown in cross section by Figure 2. The assembly drawing for the pump was ANSC Drawing 1139300, "LH₂ Test Rig Assembly - 1st Stage." (Reference 3) The major parts of the pump rig are described below:

INLET SPOOL HOUSING - This spool had a 9.5 inch inside diameter flange at the facility interface which was the inlet line bellows. There were two spool housings which were interchangeable; one had four internal struts, two of which housed displacement probes that sense the position of the inducer spinner in the vertical and horizontal planes. The inducer spinner used with the strutted inlet spool had a truncated conical cross section rather than the elliptical cross section shown in Figure 2. The spinner sides were perpendicular to the displacement probes and had a known depth spotface machined into it to allow calibration of the displacement probes during operation at LH₂ temperatures. The strutted spool was part number 1138562-1 (Reference 4), and the non-strutted spool was part number 1138561-1 (Reference 5).



TEST ARTICLE CROSS SECTION
FIGURE 2


INDUCER - The inducer was part number 1138588-1 (Reference 6) and is shown in Figure 3 without the spinner. The inducer design parameters are:


Inlet Tip Diameter	6.86 in.
Inlet Hub/Tip Ratio	0.398 in.
Inlet Tip Blade Angle (Camber line)	8.2°
Discharge Tip Diameter	6.46 in.
Discharge Hub/Tip Ratio	0.683 in.
Discharge Blade Angle	
Tip	16°
Mean	18.3°
Hub	24°
Blade Number	4 + 4
Inlet Tip Flow Coefficient	0.076
Discharge Tip Head Coefficient (Based on $\eta_h = 0.85$)	0.210

IMPELLER - The impeller was part number 1138550-1 (Reference 7) and is shown in Figure 4. The unshrouded tooling verification piece is also shown. This first stage impeller is backswept and shrouded with the following design parameters:


Discharge Diameter	10.75 in.
Discharge Part Width	0.52 in.
Discharge Blade Angle	30°
Blade Number	8
Inlet Tip Diameter	6.53
Hub/Tip Ratio	0.70
Blade Inlet Angle	
Tip	16°
Mean	21°
Hub	26°
Discharge Flow Coefficient	0.105

INDUCER





Impeller



Unshrouded Tooling
Verification Piece

PUMP DISCHARGE HOUSING VOLUTE - The volute was part number 1138600-4 (Reference 8) and has internal vanes. There were three housings built onto the volute near the discharge flange. Two of these contained filters and orifices that were used to externally route pump discharge pressure LH₂ back to the two sets of pump bearings for bearing coolant. The volute design parameters are:

Volute Base Circle Diameter	16.0 in.
Volute Throat Area	11.45 sq. in.
Discharge Line Inside Diameter	4.75 in.

POWER TRANSMISSION - The power transmission was composed of many parts as shown on assembly drawing 1139300 (Reference 3). The main housing supported the bearing cartridges, each of which held the two sets of preloaded 65mm duplex ball bearings that supported the main shaft. The inducer and impeller were cantilever mounted with respect to the two sets of bearings. There was no balance piston arrangements on this first stage assembly pump nor a separate thrust bearing. All axial loads were carried by the aft ball bearing assembly. The bearings were cooled by LH₂ from the pump discharge. The coolant was controlled and contained by a series of labyrinths and dynamic seals.

PUMP/FACILITY INTERFACES - The LH₂ that flowed around the back side of the impeller, as well as both bearing coolant LH₂ flows, discharged from the pump assembly at the 2.125-inch inside diameter flange known as the Main Drain Line. The main pump shaft had two dynamic seals on the aft end that had a drain line connection between them. This was to route any seal leakage hydrogen to the flare stack through the 3/4 inch tubing line known as the Seal Drain Line.

VI. FACILITY DESCRIPTION

The LH₂ Pump Component Development Program was conducted within the Test Cell "C" complex at NRDS. The test program required the use of the Motor Drive Building (MDB), the Electric Pump Room (EPR), the Cryogenic Evaluation Laboratory (CEL), the Local Control Room (LCR) and their associated support systems.

The Electric Drive System (ELD) provided rotational energy and speed control for the test article. The ELD could drive the pump from a low speed of a few rpm to the pump limit of 30,000.

The ELD was rated at 5,000 horsepower at its design speed of 514 rpm which corresponds to a pump speed of 34,645 rpm. After allowing for electrical losses in the D.C. generators/D.C. motors and mechanical losses the gear box, there was approximately 4,400 horsepower available at the pump shaft. At reduced speeds, the ELD was limited by the D. C. motor armature current. The ELD was rated at 100% load for continuous operation and at 125% load for a 2-hour duration.

The Test Cell "C" Electric Drive System was an eight-machine electro mechanical rotary converter capable of providing variable output shaft speeds to the test article in the Electric Pump Room (EPR). The eight machines of the Electric Drive system were permanently mounted in a metal-type building known as the Motor Drive Building (MDB). The machines were arranged in two ranks of equipment that form two common shaft systems. The first rank of five machines consisted of a constant speed synchronous motor driving two separately excited D.C. generators through rigid flange couplings on either side of the motor. Outboard of each large D.C. generator on the main shaft, a smaller generator was connected through flexible couplings. The rotating members of this first

rank of 5 machines were supported on four bearings in large pedestal supports which contained oil sumps for self lubrication of the bearings. The second rank of three machines consisted of two D.C. motors and a speed increasing gear box. The two motors and the gear box were connected together by means of rigid flange couplings and the rotors were supported on three bearings in large pedestal supports similar to the first rank of machines.

The gear box was manufactured by the General Electric Generator and Gear Department and was designated type DT-383-A Speed Increasing Gear. The 6 1/2-ton gear box was rated for 6000 horsepower and 514 rpm input shaft speed with 2,481 rpm intermediate shaft speed and 34,645 rpm output shaft speed, or overall ratio of 1:67.4. This gear unit was a double stage speed increasing gear with twin intermediate power branches. Input and output shafts were in line and the intermediate shafts were symmetrically located in the same horizontal plane on either side of the input and output shaft centerline.

The test program used basically the existing CEL flow loop. The required modifications of the facility were accomplished so that the least amount of effort would be required to restore the system to its original configuration. The flow loop is described in Section IV.

The Dewar 4 and 5 system was used with one dewar (Run) storing and supplying LH₂ to the pump inlet at the required pressure and temperature while the other dewar (Catch) was collecting and storing the recovered LH₂ from the pump discharge.

Dewars 4 and 5 were identical in construction and were spherical, double walled, vacuum-jacketed, perlite insulated LH₂ storage vessels. The inner vessel had a total volume of 55,000 gallons, while the 100% level point was 50,000 gallons of LH₂ which allowed for a 10% ullage gas volume. The maximum allowable working pressure was 100 psig.

The LH₂ supply line from the dewars to the pump inlet was vacuum-jacketed and foam-insulated and included remotely-operated valves (K-1, K-2, K-103, K-3, K-130, C-4), branch line remotely-operated valves (K-55, K-403, K-402, C-214, C-221), relief valves (KS-1055, KS-1004), LH₂ flowmeters (KF-130, KF-4), filter (KM-1003), and associated pressure and temperature instrumentation.

The main LH₂ filter, KM-1003, was located in the LH₂ supply line downstream of K-3 and K-130. This filter was a ten-inch, 150 lb ASA, in-line, cone-type filter by Capital Westward. The filtration specifications were: 100% removal of all particulates greater than 150 microns in size and 98% removal of 100 micron size particulates. The filter was designed to flow 200 lbs/sec of LH₂ with a 5 psid pressure drop.

There was a flange location 53 inches upstream of the pump inlet flange where a fluid conditioner was installed for pump cavitation tests to drop the pump inlet NPSP. Two fluid conditioners (47 hole and 21 hole) and an open spool section were fabricated to fit in this location. The fluid conditioners had the following part numbers: 47 Hole, 1440038 (Reference 9); 21 Hole, 1440037 (Reference 10).

The pump discharge piping provides the flow path back to Dewar 4 and 5 catch and storage system and provided a pump back pressure impedance source with valve C-8 and a pump discharge vent line to the flare stack with valve C-106.

The pump discharge line was vacuum-jacketed and foam-insulated and included remotely-operated valve (C-8), branch line remotely-operated valves (C-106, C-56), relief valves (CS-1200, CS-1056), LH₂ flowmeter (CF-6), and associated pressure and temperature instrumentation.

The LH₂ return line from the pump and CEL piping from C-8 to Dewars 4 and 5 was vacuum-jacketed and included remotely-operated valves (C-111, C-11, C-12), branch line remotely-operated valve (C-408), relief valves (CS-1111, CS-1201, CS-1202), and associated pressure and temperature instrumentation.

The operation of the system was accomplished from the LCR which was located approximately 500 feet from the EPR. The LCR required some modification to accommodate the instrumentation necessary to conduct this test.

A more detailed description of the facility can be found in Section 2.3 of Reference 2.

VII. CONTROL SYSTEMS

The controls for the CEL tests originated in the LCR; none come from the R-CP Control Room. The R-CP powerhouse still had the normal controls for the ELR air conditioning, the pumps for makeup water to the elevated water tank, and TCC diesel generator and electrical switchgear.

The general types of control valves used for the CEL Inducer Tests were as follows:

- a. Analog valve with servo-hydraulic actuator (typically Moog)
- b. Analog valve with servo-pneumatic actuator (typically Mason-Neillan)
- c. Analog jog valve with electric motor actuator (typically Limitorque)
- d. Binary valve with solenoid pilot valve which utilized hydraulic actuating fluid
- e. Binary valve with solenoid pilot valve which utilized pneumatic actuating fluid
- f. Binary valve with electric motor actuator
- g. Binary valve which was a solenoid valve
- h. Generator field current control which indirectly controlled pump speed.


Pressurization was performed with an analog control system, where the controlled parameter was the pressure in the vessel and the control element was an analog valve which controlled the flow rate from the tank farm to the vessel. All of these systems used the simplest possible controller compensation. It consisted of amplification of the error signal. This led to a pressure with an error which was proportional to the liquid flow rate and inversely proportional to tank farm pressure and controller amplification. In all cases, the amplification could be made large enough so that the steady-state error did not compromise the effective utilization of the system with the attainable values

of liquid flow rate and tank farm pressure. Pressurization systems of the type described were used to pressurize Dewars 4 and 5. Dewars 4 and 5 were pressurized by analog control valve K-53. Figure 5 is a functional block diagram of the dewar pressurization control system. The two modes of operation were Position and Pressure. L-53 was operated in Position Control Mode to a nominal pressure of 40 to 70 psig. K-53 was operated in Pressure Control Mode with a nominal pressure demand of 40 to 100 psig.

In position mode, L-53 and K-53 were operated with position feedback only. In Pressure Control, the measured pressure (KP-61 or KP-62) was compared to the manually demanded pressure to generate the actuating signal. A selector switch in the feedback loop allowed selection of Dewar 4, Dewar 5 or auctioneered pressure as the measured parameter. The auctioneer selected the higher output of the two as the measured feedback pressure, but was not used for CEL testing.

The other valve which had a control feedback for closed loop operation, as well as Position Control, was C-8 (Q/N control). C-8 was a six-inch Annin plug valve with flow under the plug of the 240 C_v equal percentage trim valve. The Q/N controller was located at the CTO console and had the Q/N demand as well as the position demand potentiometer.

In Q/N control, the valve maintained the position required to keep the measured Q/N signal equal to the demanded Q/N. The Q signal was obtained from the turbine flowmeter, CF-6, which was really a volumetric flow measurement (gpm) which had been signal conditioned for 0 to 10 volts to be expressed as 0-100 lbs per second LH₂ (at a density of 4.3 lbs/ft³). The N signal was



DEWARS 4 & 5 (K-53)

$$\frac{K_c 53}{P_e} = \frac{6.6}{\left(\frac{s}{200} + 1\right)} \frac{\%}{PSI}$$

TYPICAL DEWAR PRESSURIZATION CONTROLLER


obtained from the DC tachometer, SUQ-002, driven from the gear box intermediate speed shaft and was signal conditioned to be expressed as 0-40,000 rpm. The generated Q/N (from the Q/N chassis) was ranged for 0-1 gpm/rpm Q/N, but the controller responded within a Q/N range of only .1 to .5. The C-8 Q/N controller circuit is shown in Figure 6.

The pump controller controlled the field current of the D.C. generators which indirectly controlled the pump speed as shown in Figure 7. This was the RPM controller and was located at the CTO console and contained the RPM demand and the Manual demand potentiometers.

The local controller in the MDB had a demand potentiometer and provided a signal to the Silicon Controlled Rectifiers (SCR) which was the power source for the generator field windings and maintained the field current at the required steady level. The SCR had inherent closed loop control of the generator field current of which it was an integral part.

In the Manual Control Mode, the LCR Generator Armature Voltage controller provided the demand signal to the local controller rather than the local demand potentiometer. The VGA signal was displayed on the RPM chassis meter and was obtained from channel UH-011 which was the measured voltage generator #1 field and was ranged -500 vdc to +600 vdc.


In the RPM mode, the LCR Speed Controller put out a demand to the Generator Armature Voltage Controller until the measured speed was equal to the demanded speed; this was a closed loop controller using RPM as the feedback signal. The feedback RPM signal was the value of speed channel SUQ-002, which was the D.C. tachometer driven from the intermediate speed shaft of the gear box. This channel was ranged for 0-40,000 rpm.



NOTES:
 RELAYS SHOWN IN POSITION CONTROL.
 □ = FRONT PANEL CONTROL SWITCHES TO POSITION CONTROL ON E.S.D.

$$* \frac{\Delta C-C-8}{KAN-\Delta \dot{W}} = \frac{1.5 \left(\frac{S}{16} + 1 \right)}{S \left(\frac{S}{100} + 1 \right)} \frac{90}{\#/\text{SEC}}$$
 * SUBJECT TO CHANGE ON FIRST DAY OF EP-1

Q/N CONTROLLER (C-8)



The RPM controller was a closed loop controller which was closed around an open loop controller, VGA (Generator Armature Voltage), which was the demand for the closed loop MDB local controller, IGF (Generator Field Current).

The RPM controller speed demand had an additional circuit within it which limited the rate of change of the RPM demand potentiometer signal seen by the RPM controller. This limiter was a ramp rate generator which had a potentiometer to adjust the rate from 0 rpm/sec to 5,000 rpm/sec for both increasing and decreasing speed demands. When an emergency shutdown occurred, relays were set up so that the RPM controller mode was automatically selected, even if Manual Generator Armature voltage mode had been manually selected. A preset decreasing ramp rate was switched to become the demanded input to the RPM controller. This preset value was adjustable from inside the chassis, but was set at a nominal 4,000 rpm/sec. This rate was adjusted to provide a maximum deceleration rate for the pump without exceeding the armature current which would trip the D.C. breakers.

Valve C-106 operated normally in Position Control from a potentiometer in the Q/N controller chassis at the CTO console. C-106 was a 3 1/2-inch Rocketdyne LHBV butterfly valve which had a throat diameter of 3.46 inches and had a servo-hydraulic actuator. In addition to the Manual Position Control mode, there was a special Q/N sensing circuit and relays which allowed the valve to be switched to a preset open demand whenever the measured Q/N became less than the set point of the special Q/N sensing circuit. The preset opening potentiometer was inside of the Q/N chassis, but there were two front panel switch/lights which controlled this special Q/N sensing circuit: One

was a lamp indication "LOW Q/N" which illuminated whenever the measured Q/N was less than the adjustable set point Q/N. The other was a split screen switch labeled "RUN" and "RESET". "RESET" allowed resetting of the low Q/N trip and allowed normal Position Control of C-106. "RUN" allowed the low Q/N sensing circuit to step C-106 to the preset position when measured Q/N dropped below the sensing point Q/N. For normal operation the circuit was in RESET until significant pump speed and flow were obtained to have a steady and larger than .15 value of Q/N, at which time it was switched to RUN. At the end of a run when pump speed and flow was decreasing, the switch was placed to RESET so that C-106 could not step open as the Q/N signal became unreliable. While C-106 was in the RUN mode, the manual demand potentiometer was normally demanding the valve to 0% but should a C-8 failure occur and the measured Q/N decrease to the set point, C-106 would step to the preset demand, and provide a liquid hydrogen bypass flow to prevent stalling the pump.

Valve C-231 operated in Position Control from a potentiometer located in the Q/N controller chassis at the CTO console in the LCR. C-231 was a four-inch Annin plug valve with flow under the plug of the 195 C_v linear trim valve.

Valve K-3 operated in Position Control from a potentiometer located in the RPM Controller chassis at the CTO console. K-3 was a eight-inch Hadley Butterfly with a 3400 C_v .

Valve K-130 operated in Position Control from a potentiometer located at the FLO console. K-130 was a two-inch Annin plug valve with the flow over the plug of the 46 C_v linear trim valve.

VIII. INSTRUMENTATION

A. General

The measurements related to the test article are shown in Table I and Table II, Pump Instrumentation and Facility Instrumentation. Table I and Table II reflects the instrumentation required by the test article supplier for EP-1. Figure 8 shows the location of the instrumentation on the test article and Figure 1 shows the relative location of instrumentation on the facility flow loop.

The following revisions or changes were made for EP-2:

1. Ranges on CP 706 and CP 710 were changed to 0 to 750 psig.
2. The following channels were relocated to measure diffuser inlet conditions and with the range of the measurement of 0 to 1000 psig.

<u>Parameter</u>	<u>Location</u>
CP 718	$\theta = 65^\circ$
CP 719	$\theta = 345^\circ$
CP 720	$\theta = 225^\circ$
CP 721	$\theta = 145^\circ$

3. Parameter CT 702 was deleted due to temperature transducer failure.
4. Range of UQ 003 was changed to 0 to 40000 rpm.

The following revision or changes were made for EP-2A:

1. Parameter CT 700 and CT 701 were deleted due to temperature transducer failure.
2. Range on CT 508 was changed to $35^\circ\text{R} - 590^\circ\text{R}$.
3. Range on KF 130 flow measurement was changed to 0-15 pounds per second.

TABLE I

PUMP INSTRUMENTATION

<u>Narrow Band Channel</u>	<u>Range Narrow Band</u>	<u>Wide Band Channel</u>	<u>Range Wide Band</u>	<u>Description</u>	<u>Oscilloscope</u>	<u>Sanborn</u>	<u>Meter</u>
		+ CD 700.-C	$\pm .010$; 0-10KHZ	Displacement, Radial, Spinner, $\theta = 0^\circ$; Bently 304QB-7102-01 (05324-1138565-2)	X		
		+ CD 701.-C	$\pm .010$; 0-10KHZ	Displacement, Radial, Spinner, $\theta = 90^\circ$; Bently 304QB-7102-01 (05324-1138565-2)	X		
		CD 702.-C	$\pm .010$; 0-10KHZ	Displacement, Shaft Bearing Cavity $\theta = 0^\circ$; Kaman KD 1100-23	X		
		CD 703.-C	$\pm .010$; 0-10KHZ	Displacement, Shaft Bearing Cavity $\theta = 90^\circ$; Kaman KD 1100-23	X		
		CD 704.-C	$\pm .010$; 0-10KHZ	Displacement, Shaft Bearing Cavity $\theta = 270^\circ$; Bently 304QB-7101-01 (5324-1138565-1)	X		
		CD 705.-C	$\pm .010$; 0-10KHZ	Displacement, Shaft Aft End, $\theta = 0^\circ$; Kaman KD 1100-23	X		
		CD 706.-C	$\pm .010$; 0-10KHZ	Displacement, Shaft Aft End, $\theta = 90^\circ$; Kaman KD 1100-23	X		
		+ CD 707.-C	$\pm .010$; 0-10KHZ	Displacement, Shaft Aft End, $\theta = 180^\circ$; Bently 204QB-7101-01	X		
		+ CD 708.-C	$\pm .010$; 0-10KHZ	Displacement, Shaft Aft End, $\theta = 270^\circ$; Bently 304QB-7101-01	X		
		CA 700.-C	$\pm 50g's$, 0-2KHZ	Acceleration, Radial $\theta = 175^\circ$			
		CA 701.-C	$\pm 50g's$, 0-2KHZ	Acceleration, Radial $\theta = 265^\circ$			
		CA 702.-C	$\pm 50g's$, 0-2KHZ	Acceleration, Axial $\theta = 225^\circ$			
CT 700.-C	35-590°R			Temperature, Pump housing .20, $\theta = 288^\circ$; Mod. 108 MA 4A		X	
CT 701.-C	35-590°R			Temperature, Pump housing .30, $\theta = 270^\circ$; Mod. 108 MA 4A		X	
CT 702.-C	35-590°R			Temperature, Pump housing, .40, $\theta = 252^\circ$; Mod. 108 MA 4A		X	

PUMP INSTRUMENTATION

<u>Narrow Band Channel</u>	<u>Range Narrow Band</u>	<u>Wide Band Channel</u>	<u>Range Wide Band</u>	<u>Description</u>	<u>Oscilloscope</u>	<u>Sanborn</u>	<u>Meter</u>
CT 703.-C	35-590°R			Temperature, Bearing housing		X	X
CT 704.-C	35-100°R			Temperature, Fluid forward bearing, $\theta = 0^\circ$, Mod. 150 LM S/N 880001			X
CT 705.-C	35-100°R			Temperature, Fluid forward bearing, $\theta = 180^\circ$, Mod. 150 LM		X	
CT 706.-C	35-100°R			Temperature, Fluid aft bearing, $\theta = 135^\circ$, Mod. 150 LM			X
CT 707.-C	35-100°R			Temperature, Fluid aft bearing, $\theta = 315^\circ$, Mod. 150 LM		X	
CP 700.-C	0-1000 psig			Pressure, Pump discharge flange suction side			X
CP 701.-C	0-1000 psig			Pressure, Pump discharge flange motor side		X	
CP 702.-C	0-1000 psig			Pressure, Filter exit bearing feed			
CP 703.-C	0-1000 psig			Pressure, Bearing housing		X	
CP 704.-C	0-100 psig			Pressure, Bearing aft cavity			
CP 705.-C	0-200 psig			Pressure, Impeller contour, inducer discharge $\theta = 85^\circ$		X	
CP 706.-C	0-500 psig			Pressure, Impeller contour, R = 4.0, $\theta = 65^\circ$			
CP 707.-C	0-750 psig			Pressure, Impeller contour, R = 4.8, $\theta = 45^\circ$			
CP 708.-C	0-1000 psig			Pressure, Impeller contour, impeller tip $\theta = 25^\circ$			
CP 709.-C	0-200 psig			Pressure, Impeller contour, inducer discharge $\theta = 345^\circ$			
CP 710.-C	0-500 psig			Pressure, Impeller contour, R = 4.0, $\theta = 325^\circ$			
CP 711.-C	0-750 psig			Pressure, Impeller contour, R = 4.8, $\theta = 305^\circ$			
CP 712.-C	0-1000 psig			Pressure, Impeller contour, impeller tip, $\theta = 105^\circ$		X	
CP 713.-C	0-1000 psig			Pressure, Diffuser vane inlet, $\theta = 25^\circ$			
CP 714.-C	0-1000 psig			Pressure, Diffuser vane inlet, $\theta = 305^\circ$			
CP 715.-C	0-1000 psig			Pressure, Diffuser vane inlet, $\theta = 265^\circ$			

PUMP INSTRUMENTATION

<u>Narrow Band Channel</u>	<u>Range Narrow Band</u>	<u>Wide Band Channel</u>	<u>Range Wide Band</u>	<u>Description</u>	<u>Oscilloscope</u>	<u>Sanborn</u>	<u>Meter</u>
CP 716.-C	0-1000 psig			Pressure, Diffuser vane inlet, $\theta = 185^\circ$			
CP 717.-C	0-1000 psig			Pressure, Diffuser vane inlet, $\theta = 105^\circ$			
CP 718.-C	0-1000 psig			Pressure, Diffuser vane discharge, $\theta = 125^\circ$			
CP 719.-C	0-1000 psig			Pressure, Diffuser vane discharge, $\theta = 45^\circ$			
CP 720.-C	0-1000 psig			Pressure, Diffuser vane discharge, $\theta = 325^\circ$			
CP 721.-C	0-1000 psig			Pressure, Diffuser vane discharge, $\theta = 285^\circ$			
CP 722.-C	0-1000 psig			Pressure, Diffuser vane discharge, $\theta = 205^\circ$			
CP 723.-C	0-200 psig			Pressure, Impeller back cavity, $\theta = 90^\circ$			X
CP 724.-C	0-1000 psig			Pressure, Impeller back distribution R = 4.1 $\theta = 65^\circ$			
CP 725.-C	0-1000 psig			Pressure, Impeller back distribution R = 4.8 $\theta = 45^\circ$			
CP 726.-C	0-1000 psig			Pressure, Impeller back tip $\theta = 25^\circ$			X
CP 727.-C	0-1000 psig			Pressure, Impeller back distribution, R = 4.1 $\theta = 325^\circ$			
CP 728.-C	0-1000 psig			Pressure, Impeller back distribution, R = 4.8 $\theta = 305^\circ$			
CP 729.-C	0-1000 psig			Pressure, Impeller back tip $\theta = 105^\circ$			
CP 702.D.-C	0-750 psi			Differential pressure, bearing feed orifice #1			X
CP 730.D.-C	0-750 psi			Differential pressure, bearing feed orifice #2			
CP 700.D.-C	0-1000 psi			Differential pressure, pump pressure rise, from CP 700.-C to CP 508.-C			X X*
CQ 700.-C	0-40,000 RPM			Pump shaft speed			X
CP 701N-C	0-250 psig			Pressure Pump Discharge Flange Motor Side, Narrow Range			X

*Visual readout on the X-Y plotter (the y coordinate)

+CD 707.-C and CD 708.-C to be connected when CD 700.-C and CD 701.C is not being used.

N8300R:72-101
 May 1972
 Page 28

TABLE II

FACILITY INSTRUMENTATION

<u>Narrow Band Channel</u>	<u>Range Narrow Band</u>	<u>Wide Band Channel</u>	<u>Range Wide Band</u>	<u>Description</u>	<u>Oscilloscope</u>	<u>Sanborn</u>	<u>Meter</u>
		CP 511.W.-C	0-100 psi, 0-5000 HZ	Pressure, Pump Suction Kistler, High Freq			
		CP 542.W.-C	0-1000 psi 0-5000 HZ	Pressure, Pump Discharge, Kistler, High Freq			
KT 071.-C	35-49°R			Temperature, Dewar 4		X	
KT 072.-C	35-49°R			Temperature, Dewar 5		X	
KT 130.-C	35-54°R			Temperature, Flowmeter Inlet KF 130			
KT 004.-C	35-54°R			Temperature, Pump Suction Venturi KF-4			
CT 003.-C	35-590°R			Temperature, Chill Line Inlet		X	
CT 505.-C	35-54°R			Temperature, Fluid Conditioner Inlet		X	X
CT 505. A.-C	35-45°R			Temperature, Fluid Conditioner Inlet, Special Channel			
CT 506. -C	35-45°R			Temperature, Pump Suction $\theta = 45^\circ$, Special Channel			
CT 507.-C	35-54°R			Temperature, Pump Suction $\theta = 135^\circ$		X	X
CT 508.-C	35-54°R			Temperature, Pump Suction $\theta = 225^\circ$			
CT 509.-C	35-590°R			Temperature, Pump Suction $\theta = 315^\circ$			
CT 542.-C	35-100°R			Temperature, Pump Discharge		X	X
CT 006.-C	35-100°R			Temperature, Flowmeter, Pump Discharge CF-6			
CT 220.-C	35-590°R			Temperature, Main Leakage Oriface			
IP 101.-C	25-28 in Hg			Pressure Barometric (Req. to obtain absolute)			
SKP 061.-C	0-150 psig			Pressure, Dewar 4		X	
SKP 062.-C	0-150 psig			Pressure, Dewar 5		X	

FACILITY INSTRUMENTATION

<u>Narrow Band Channel</u>	<u>Range Narrow Band</u>	<u>Wide Band Channel</u>	<u>Range Wide Band</u>	<u>Description</u>	<u>Oscilloscope</u>	<u>Sanborn</u>	<u>Meter</u>
KP 130.-C	0-100 psig			Pressure, Chill Flowmeter Inlet KF 130		X	
KP 004.-C	0-150 psig			Pressure, Venturi, Pump Suction KF 004			
CP 003.-C	0-100 psig			Pressure, Chill Line Inlet			
CP 505.-C	0-100 psig			Pressure, Fluid Conditioner Inlet		X	X
CP 505.A.-C	0-50 psig			Pressure, Fluid Conditioner Inlet, Special Channel			
CP 506.-C	0-50 psig			Pressure, Pump Suction $\theta = 0^\circ$, Special Channel			
CP 507.-C	0-100 psig			Pressure, Pump Suction $\theta = 90^\circ$		X	X*
CP 508.-C	0-100 psig			Pressure, Pump Suction $\theta = 180^\circ$			
CP 509.-C	0-100 psig			Pressure, Pump Suction $\theta = 270^\circ$			
SCP 220.-C	0-200 psig			Pressure, Main Leakage Oriface		X	
CP 541.-C	0-1000 psig			Pressure, Pump discharge line		X	X
KP 004.D.-C	0-25 psi			Differential Pressure, Pump Suction Venturi			
CP 220.D.-C	0-10 psi			Differential Pressure, Main Leakage Oriface			
SCF 006.-C	0-100 P/S			Flow, Pump Discharge		X	X*
KF 130.-C	0-5 P/S			Flow, Chilldown		X	
CR 106A.-C	0-100%			Stem Position, Pump bypass valve			
CB 221.-C	(a)			Open/closed indication (OBV), main leakage line			
CR 231A.-C	0-100%			Stem Position, Main Leakage to flare valve (ACV)		X	
CR 008A.-C	0-100%			Stem Position, Flow Control Valve (ACV)		X	

FACILITY INSTRUMENTATION

<u>Narrow Band Channel</u>	<u>Range Narrow Band</u>	<u>Wide Band Channel</u>	<u>Range Wide Band</u>	<u>Description</u>	<u>Oscilloscope</u>	<u>Sanborn</u>	<u>Meter</u>
KR 003A.-C	0-100%			Stem Position, Suction line impedance valve		X	
CB 214.-C	(a)			Open/close indication (OBV), chill line			
KR 130.-C	0-100%			Stem position, chill Bypass Valve			
SUQ 001.-C	0-40000 RPM			Electric Drive High Speed Pinion Rotation		X	
SUI 011.-C	+ 10000 ADC			Current Electric Motor Armature, Motor #1			
UI 021.-C	0-50000 ADC			Current Electric Motor Armature, Motor #2			
CP 006.-C	0-1000 psig			Pressure Pump Discharge Flowmeter			
CP 008.-C	0-1000 psig			LH ₂ Recirculation Pressure Upstream of C-8			X
CP 009.-C	0-1000 psig			LH ₂ Pressure Downstream of C-8			X
CR 011A-CJ	0-100%			C-11 Stem Position			X
CR 012A-CJ	0-100%			C-12 Stem Position			X
CT 007.-C	35-54°R			LH ₂ Temperature Between Vacuum Vessels & FE-24			X
CT 106.-6	35-590°R			C-106, LH ₂ Line Vent Temperature			X
CT 111.-C	35-590°R			C-109, LH ₂ Return Line Vent Temperature			X
KL 001.-C	1.0-31.6 KPH			Dewar 4, Level - Reflectometer			X
KL 002.-C	1.0-31.6 KPH			Dewar 5, Level - Reflectometer			X
KP 003.-C	0-150 psig			Pressure Upstream of K-3			X
KP 053.-C	0-3500 psig			Dewar Pressurization Control Pressure		X	X
KR 053A-CH	0-100%			K-53 stem position			X
KT 001.-C	35-54°R			Dewar 4, Outlet Temperature			X
KT 002	35-54°R			Dewar 5, Outlet Temperature			X
IV 801U-C	0-1.0 GPM/RPM			Measured Q/N			X
KX 001.-C	2.9-29 KPH			Dewar 4 Level, Carbon Resistor			
KX 002.-C	.73-29 KPH			Dewar 5 Level, Carbon Resistor			


FACILITY INSTRUMENTATION

<u>Narrow Band Channel</u>	<u>Range Narrow Band</u>	<u>Wide Band Channel</u>	<u>Range Wide Band</u>	<u>DESCRIPTION</u>	<u>Oscilloscope</u>	<u>Sanborn</u>	<u>Meter</u>
QP 020.-CE	0-3500 psig			He Header Supply Pressure			
QP 030.-CE	0-3500 psig			GH ₂ Upstream of K-50 pressure			
QP 040.-CE	0-3500 psig			N ₂ Run Supply Header Pressure			
QP-050.-CE	0-3500 psig			GN ₂ Room Inerting header supply pressure			
UH 001.-C	0-15K VAC			AC Input Line Voltage Monitor			X
SUH 011.-C	+ 600 VAC			DC Generator #1, Armature Voltage		X	X
UH 021.-C	+ 600 VAC			DC Generator #2, Armature Voltage		X	X
UI 002.-C	0-300 amp			Syne Motor AC Current Monitor & Alarm			X
UI 003.-C	0-200 amp			Syne Motor DC Field Current Monitor			X
UI 012.-C	0-20 amp			DC Motor #1 Field Current Monitor			X
UI 022.-C	0-20 amp			DC Motor #2 Field Current Monitor			X
UI 031.-C	+ 50 amp			DC Generator #1 & #2 Field Current Feedback			
SUQ 002.-C	0-40000 rpm			Intermediate Gear, DC Tach			
UQ 003.-C	0-593.45 rpm			Electric Drive Input Gear Speed			
UT 551.-C	460-853.3°R			Gear Box Inboard Output Shaft Bearing Temperature			
UT 552.-C	460-853.3°R			Gear Box Outboard Output Shaft Bearing Temperature			


*Visual readout on X-Y plotter (SCF 006.-C reflects meter also).

(a) On digital printout parameter noted as VALV with range from 0 to 3.

Digit	0	1	2	3
C-221	Open	Closed	Open	Closed
C-214	Open	Open	Closed	Closed



33



PUMP ASSY INSTRUMENTATION LOCATION
 CHANNEL NO. S' CRT WITH CP-PRESS, CT-TEMP, CD-DISPL., CA-ACCEL.,
 CO-SPEED
 LOC. WITHOUT CHANNEL NO. ARE NOT INSTRUMENTATED
 LETTERS A, B, C, D, E, F, G REF LAYOUT B-1000 SECT N420

SCALE NONE
 ENTS: 12/7/70 SHT 10F 5
 4/11/71

N8300R:72-101
 May 1972
 Page 33

FIGURE 8





FIG. 8 (REV'D)
 N8300R:72-101
 May 1972
 Page 34
 SHT 2 OF 5



SECTION B-B

FIG 8 (cont'd)
 N8300R:72-101
 May 1972
 Page 35

SMT 30FS






FIG 8 (cont'd)
 N8300R:72-101
 May 1972
 Page 36.



N8300R:72-101
 May 1972
 Page 37

SNT 5065

FIG 8 (CONT'D)

B. Discrepancies

In the review of the data, the following discrepancies were noted during the test series:

1. Parameters CT 700, CT 701, and CT 702 showed intermittent radical performance due to transducer failure; however, prior to the failure it provided accurate measurements.
2. Parameter UQ 700 and UQ 003 initially for EP-1 were not registering. This was caused by VIDAR adjustment. For all performance calculations, SUQ 002 should be used.
3. Parameter CP 006 measurement was incorrect until EP-2A.
4. Accelerometer CA 701 data shows indication of grounding of the transducer during EP-2.
5. Displacement measurement CD 706 has a drifting problem during EP-2A.

C. Wide Band

The wide band measurements were recorded on a fourteen track recorder. Twelve tracks were used to record data (1 channel/track), one channel for F.M. Servo-Control, and the other was used for direct record time code.

The twelve measurements on the wide band tape were three accelerometers, two high frequency pressure (piezoelectric type), and at any given time seven of the nine displacement measurements. If CD 700 and CD 701 were being recorded, than CD 707 and CD 708 were not recorded.

The associated conditioning equipments, charge amplifiers, proximeters (Bentley) and modulator/demodulators (Kaman) were located inside the Electric Pump Room.

D. Narrow Band

The narrow band data were recorded through the DDP-116 at ten sample per second and also through the multiplex system. Within the narrow band measurements certain parameters were considered accurate and certain parameters were considered "special channels".

The following channels were considered accurate parameters and received their final set up, including the DDP-116 computer system, no earlier than seven days prior to EP-1:

CP-006.-C	CP-701.-C	SKP-061.-CE	KT-071.-C
CP-700.-C	CP-703.-C	SKP-062.-CE	KT-072.-C
CP-700D-C	CP-723.-C	KP-130.-C	

The "special channel" or high accurate channels received their final set up, including the DDP-116 computer system, no earlier than one day prior to test date. The parameters and the accuracy are as follows:

CP-505A-C	$\pm 0.5\%$
CP-506.-C	$\pm 0.5\%$
CT-505A-C	0.1°R
CT-506.-C	0.1°R

The stimulus applied to the above pressure transducers were at 0%, 20%, 40%, 60%, 80%, and 100% of the required full scale reading and the results were recorded and checked by NRT0 personnel.

The temperature measurements, platinum resistance type, were set up at 37.5°R and the results recorded and checked at 0% and 100%.

Post check of three temperature transducers, CT-505A-C, CT-506.-C, and CT-542.-C, were accomplished at NRT0 Laboratory. The transducers were checked at the liquid nitrogen point and at ice point and found to be within $\pm 0.03^{\circ}\text{R}$.

E. Pump Instrumentation - Internal

1. Proximity Probes

Proximity probes (displacement) were used in the test article to measure shaft dynamics. Proximity systems from two manufacturers were utilized during the program, Kaman Nuclear and Bentley Nevada. For better resolution, both systems required a zero bias circuit. The circuit used are shown in Figures 9 and Figure 10.

KAMAN NUCLEAR SYSTEM





FIGURE 9
N8300R:72-101
May 1972
Page 40

TAD

BENTLY NEVADA SYSTEM



Both systems use the eddy current concept to measure displacement; however, each uses different conditioning equipment that are not interchangeable. The carrier frequency used in both systems is one mega hertz, with a system frequency response capable to one hundred kilo hertz.

The proximity systems, Bentley and Kaman, do not have a temperature compensation network which would compensate for the large temperature differential from ambient to liquid hydrogen. The zero shift was compensated by adjusting the zero suppression or sensitivity potentiometer at operating temperature by viewing the output through an oscilloscope.



The conditioning equipment of both systems did suffer from malfunction. Two Kaman modulators and demodulators showed erratic behavior and had to be replaced. The S/8-4 power supply supplied for the Bentley system had voltage fluctuations that were too great and had to be replaced with a more constant power supply.

2. Temperature Probes

Platinum resistance temperature sensors were installed downstream of the support bearings. These temperature sensors were used to measure the fluid temperature discharging from the bearings as an indication of incipient bearing failure. The sensor, as shown in Figure 11, is 0.875 inches in length 0.16 inches in diameter, 9.0 inches of 0.085 diameter sheath cabling.

These sensors could not readily be assembled and disassembled into the test article due to the necessity of swaglocking, for the purpose of sealing, on to the sheath. This necessitated the sensor be assembled into the test article just once.

Platinum resistance surface temperature sensors were installed into the pump housing to measure housing metal temperature. These sensors were 0.30 inches in length and 0.25 inches in diameter with one foot of teflon covered cabling. (Rosemount Model Number 108MA-4A).



RTT, BEARING FLUID

The surface temperature sensors failed during the test series. All the sensors failed due to the thermal stresses going from ambient to liquid hydrogen temperature. Reviewing the specification from the vendor, the sensors should have been used down to liquid nitrogen and not to liquid hydrogen temperatures.

All the sensors mentioned in the foregoing paragraphs had ice point resistance of four hundred ohms.

3. Speed Probe

The shaft rotational speed in the test article was monitored by the usage of a Kaman Nuclear proximity probe. The results from this probe was very favorable. The probes correlation of shaft speed with the data from the D.C. tachometer, on the drive shaft, was very good and were within ± 50 rpm. The data as indicated from the Sanborn chart shows that the resolution of shaft speed was very good at low speeds.

F. Data Acquisition


The data acquired was recorded either on wide-band tape or narrow band tape. The data recorded on X-Y plotters and strip charts (Sanborn) not considered permanent records.

The flow of data from measurement to recording for the narrow band data is depicted in Figure 12. The narrow-band tape in this case is the engineering units tape. In a parallel system, not depicted, the data was also recorded on the multiplex system as a backup to the DDP-116 recording system.

The engineering units tape was than used as data input to a performance analysis program in Sacramento.

The flow of data from measurement to recording for the wide-band data is depicted in Figure 13. As shown, the system after a given test, can be played back into the oscilloscope for a "quick look" analysis.

NARROW BAND DATA




N8300R:72-101
May 1972
Page 45

FIGURE 12

TAD

WIDE BAND DATA



N8300R: 72-101
May 1972
Page 46

FIGURE 13

IX. DATA PROCESSING

A. DATA REDUCTION

Analog data from the LH₂ pump test was digitized during testing and stored on magnetic tape using the DDP-116 computer at NRDS. The data on these tapes was converted into unformatted records compatible with UNIVAC 1108 FORTRAN. These converted tapes were utilized as the source of data for the data reduction program described here. The converted data tapes contained one unformatted record, with time as the first data item, for each time point of the test. The sampling rate for all of the low band LH₂ pump test data was ten samples per second.

Essentially two types of data were processed from the LH₂ pump tests. The first type of data processed was that from the head-capacity mapping tests. Data from these tests covered a relatively short (approximately two second) steady state time span. The second type of data processed was that from the cavitation tests. Cavitation data was of a transient nature covering a longer (approximately thirty sec.) time span.

Provisions were made in the data reduction program for averaging redundant data channels and for averaging input data over a specified time period. For both the cavitation and mapping tests, input data was averaged over a one second time interval (ten data samples) and where possible, redundant channels were averaged. Justification for averaging the transient cavitation data was that the rate of change of control parameters was slow compared to the averaging period.

Computed information provided by the data reduction program may be divided into the following categories:

1. Suction Performance
2. Pump Performance
 - a. Isentropic Head
 - b. Impeller Discharge Flow Coefficient
 - c. Stage Head Coefficient
 - d. Impeller Discharge Total Head Coefficient
 - e. Housing Losses
3. Radial Load

The details of each of these sections of the data reduction program are discussed below.

A listing of the data reduction program together with an example case appears in Appendix A.


1. Suction Performance

Cavitating and noncavitating suction performance of the pump as discussed in this report is based on the following test data and method of analysis.


Shown in Figure 14 is a sketch of the LH₂ pump supply system and the data measurement points used in the suction performance calculations.

The thermodynamic process from Station 1 to Station 2 is shown on the T-S diagram of Figure 15. It is assumed that from Station 1 to Station 2 the fluid undergoes adiabatic throttling.

LH₂ PUMP SUPPLY SYSTEM



FLUID CONDITIONER THROTTLING PROCESS



E

Then from the first law, i.e., conservation of energy

$$h_2' = h_1 + \frac{V_1^2}{2gJ} = h_2 + \frac{V_2^2}{2gJ}$$

In some cases it may also be assumed that the flow from the tank to Station 1 is adiabatic. In this case

$$h_2' = h_1' = h_{TK}$$

In reality $h_1' \neq h_{TK}$ due to measurement errors in pressure and/or temperature and due to some small heat leak in the suction line. For two-phase calculations at the pump inlet, either h_{TK} or h_1' may be selected for the reference stagnation enthalpy. For the results presented in this report, h_1' was used as the reference enthalpy for two phase pump inlet conditions, i.e.

$$h_2' \stackrel{\text{Set}}{=} h_1'$$

Fluid conditions upstream of the fluid conditioner are determined as follows:

$$\rho_1 = f(P_1, T_1) \quad (\text{hydrogen property tables})$$

$$V_1 = \frac{(144) \dot{W}}{\rho_1 A_1}$$

$$h_1 = f(P_1, T_1) \quad (\text{hydrogen property tables})$$

$$h_1' = h_1 + \frac{V_1^2}{2gJ}$$

If the fluid downstream of the fluid conditioner (pump inlet) is single phase, then

$$\rho_2 = f(P_2, T_2) \quad (\text{hydrogen property tables})$$

$$h_2 = f(P_2, T_2) \quad (\text{hydrogen property tables})$$

$$V_2 = \frac{144 \dot{W}}{\rho_2 A_2}$$

$$h_2' = h_2 + \frac{V_2^2}{2gJ}$$

For two phase pump inlet conditions, fluid properties are determined as follows:

$$h_2' \stackrel{\text{set}}{=} h_1' \quad (\text{or } h_{TK} \text{ depending on which option is selected})$$

Initially it is assumed that

$$h_2 = h_1$$

$$\text{Then } T_2 = f(P_2, h_2)$$

$$\rho_2 = f(P_2, h_2)$$

$$V_2 = \frac{144 \dot{W}}{\rho_2 A_2}$$

A new value for h_2 can now be computed

$$h_2 = h_2' - \frac{V_2^2}{2gJ}$$

Calculations are then repeated from the table look-up for T_2 until successive values of h_2 satisfy the following criteria:

$$\left| 1 - \frac{h_{2, \text{new}}}{h_{2, \text{old}}} \right| \leq 0.00001$$

The state point of the fluid at the pump inlet is now defined by P_2, h_2 .

Entropy of the fluid entering the pump is then found from the property tables

$$S_2 = f(P_2, H_2)$$

From saturation properties corresponding to P_2 , the following mixture properties are found:

$$\text{Quality} = X_2 = \frac{h_2 - h_L}{h - h_L}$$

$$\frac{\text{Vapor Volume}}{\text{Liquid Volume}} = \beta = \frac{\rho_L X_2}{\rho_2 (1 - X_2)}$$

$$\frac{\text{Vapor Volume}}{\text{Total Volume}} = \alpha = \frac{\beta}{\beta + 1}$$

Various methods of computing NPSP (net positive suction performance) have been used in the evaluation of pump suction performance. The method used for the LH_2 pump tests is described here.

It is assumed that the fluid initially is at the hypothetical tank condition shown on the T-S diagram of Figure 16. Also, it is assumed that the fluid undergoes an isentropic expansion from the hypothetical tank condition to P_2 , passing through the saturation state corresponding to S_2 . The logical definition for NPSP is then

$$\text{NPSP} \equiv P_2' - P_{\text{sat}}$$

where

P_2' is the total pressure corresponding to S_2 , h_2'

P_{sat} is the saturation pressure corresponding to S_2 .

It should be noted that negative values of NPSP result from this method for sufficiently high vapor content in the pump suction line.

Net positive suction head (NPSH) was computed by two methods. The first is based on constant density using saturation density corresponding to S_2 , i.e.


$$\text{NPSH} = \frac{144 \text{ NPSP}}{\rho_{\text{sat}}}$$

The second is based on the enthalpy difference

$$\text{NPSH} = 778.16 (h_2' - h_{\text{sat}})$$

The above calculated parameters establish pump suction conditions which provide the basis for suction performance and overall pump performance.

HYPOTHETICAL TANK CONDITION



2. Pump Performance

Overall performance is presented in normalized parameters $(H/N^2, Q_D/N)$ as well as in dimensionless form (ψ, ϕ_2) .

a. Isentropic Head

The isentropic head is defined by inlet conditions (pressure, temperature and entropy) and measured discharge pressure. The discharge velocity head is added to obtain the correct total head.

b. Impeller Discharge Flow Coefficient

The labyrinth leakage flow \dot{W}_{1b} was considered in the computation of the discharge flow coefficient ϕ_2 .

$$\phi_2 = 144 \frac{\dot{W}_s + \dot{W}_{1b}}{\rho A_2 U_2}$$

where:

A_2 = impeller discharge area blocked, (sq in)

U_2 = $D_2 N/229$ (ft/s)

\dot{W}_s = weight flow, inlet (lb/s)

ρ = fluid density in lb/ft³

The recirculating shroud labyrinth flow was estimated as follows:

$$\begin{aligned} \dot{W}_{1b} &= C_{1b} \frac{A_{1b}}{144} (2g (144) \rho \Delta P_{1b})^{1/2} \\ &= 0.66847 C_{1b} A_{1b} (\rho \Delta P_{1b})^{1/2} \end{aligned}$$

where:

A_{1b} = labyrinth flow area

ΔP_{1b} = pressure drop in lb/sq in across labyrinth

C_{1b} = labyrinth flow coefficient = 0.5

c. Stage Head Coefficient

$$\psi = \frac{g \Delta H_{is}}{U_2^2}$$

d. Impeller Discharge Total Head Coefficient (One-Dimensional)

This coefficient is based on an average static pressure determined from several wall static pressures measured around the impeller periphery between diffuser inlet and impeller discharge at radius R_M .

Since the static head (ψ_s) is based on measurements outside the impeller discharge the absolute velocity is reduced by the ratio of the impeller discharge radius R_2 to the radius of the pressure tap R_M . The velocity head therefore is multiplied by the radius ratio squared.

$$\psi_t = \psi_s + \left(\frac{R_2}{R_M}\right)^2 \frac{\phi_2^2 + \psi_2^2}{2}$$

The theoretical head coefficient ψ_i based on Stodola's slip correction is defined as:

$$\psi_i = 1 - \frac{\phi_2}{\tan \beta_2} - \frac{\pi \sin \beta_2}{Z}$$

where:

β_2 = discharge blade angle

Z = number of blades

e. Housing Losses

Diffusion housing losses are expressed

in head coefficient form as:

$$\Delta\psi_{\ell(\text{Housing})} = \psi_t(\text{Impeller}) - \psi_t(\text{Stage})$$


3. Radial Thrust

Radial thrust is determined from the wall static pressures measured around the impeller periphery. Each measured pressure multiplied by its effective area (circumferential increment x effective width) results in a force vector F shown below. The force components of F are:

$$F_y = F \sin \theta$$

and

$$F_x = F \cos \theta$$



The radial force \bar{F} then is the resultant of the algebraic sums of the force components F_y and F_x .

$$\bar{F} = \sqrt{\Sigma F_y + \Sigma F_x}$$

The direction of the resultant force is determined by the angle

$$\theta = \tan^{-1} \left(\frac{\Sigma F_y}{\Sigma F_x} \right)$$

θ is measured from the pressure tap nearest to the volute tongue in direction of impeller rotation.

The radial thrust parameter used in the data presentation is defined as the ratio of the resultant radial force \bar{F} to the average impeller static pressure rise.

$$RFP = \frac{\bar{F}}{P_{2m} - P_s}$$

B. HYDROGEN PROPERTIES

Hydrogen property routines were required for the data reduction program to evaluate pump performance. Early attempts to use the National Bureau of Standards (NBS) tab decks for parahydrogen proved unsatisfactory for the two phase suction performance calculations. This was due to an apparently ill-defined saturation line between the super-cooled liquid and two-phase regions. As a result of the problems associated with using the NBS tab decks, new hydrogen properties routines were developed.

The new parahydrogen routines are based on the hydrogen properties data of Reference 11. In the single phase region, linear interpolation of the tabulated data of Reference 11 is used. In the interpolation scheme pressure and one other property; temperature, enthalpy, etc; are used as the independent variables. Saturation data used to define the saturation line and to evaluate two-phase properties was the data on page 23 of Reference 11. Saturation properties are determined using spline fits of this data.

Use of these routines in the data reduction program to evaluate hydrogen properties, both in the single phase and two-phase regions yielded consistent results. The accuracy of hydrogen properties data derived from these routines is governed by the experimental accuracy of the data of Reference 11 and the limitations of linear interpolation of that data.

X. TEST PROGRAM

The NERVA LH₂ Pump Component Development tests were performed on the first stage pump rig at the NRDS test Cell "C" facility using the CEL test loop and the electric drive system. The tests were performed on six separate days utilizing the following test operating procedures:

<u>Test Designation</u>	<u>Date</u>	<u>TOP</u>
EP-1 First Day	8 December 1971	NRTO-TOP-0044 (Reference 12)
EP-1 Second Day	10 December 1971	NRTO-TOP-0044* (Reference 12)
EP-2 First Day	15 December 1971	NRTO-TOP-0045 (Reference 13)
EP-2 Second Day	16 December 1971	NRTO-TOP-0045* (Reference 13)
EP-2 Third Day	17 December 1971	NRTO-TOP-0045* (Reference 13)
EP-2A	22 December 1971	NRTO-TOP-0045* (Reference 13)

*Red-line revision with Test Requirement Engineer (TRE) approval.

All objectives of the planned tests were accomplished and several additional tests were performed.

The following sections (A through F) list the pertinent hardware configuration for a test or the changes made between successive tests as well as a brief statement of the tests performed each day.

A. EP-1, FIRST DAY

1. The test article and facility configuration were setup as follows for testing on 8 December 1971:

- a. The 47 hole fluid conditioner was installed.
- b. The pump inlet spool with displacement probes and the inducer spinner with calibration spotfaces were installed.

- c. The pump inlet bellows liner was installed.
- d. Electrical clamps were installed on valves C-8 and C-106 and were setup to limit their opening to 68% and 30% respectively.
- e. The controllers for C-8 (Q/N) and C-231 (PRES) were not setup; and RPM speed control was setup.

2. The following tests were completed on 8 December 1971:
(Wednesday)

a. The green run to 19K rpm was made in Manual speed control with C-8 and C-106 in Position control to a Q/N of .25. C-221 was left open and C-231 was left closed throughout the green run.

b. Before the coastdown test, two attempts were made to switch into RPM speed control but the system was unstable. The system coastdown time, with the drive motors off, was performed by opening the D.C. breakers when armature current reached approximately zero as the speed was manually decreased from a steady state 19K rpm. The pump and electric drive system coasted from 18K to 0 rpm in approximately 50 seconds. This compared with a coastdown time of approximately 200 seconds without the pump connected to the electric drive system as reported in Appendix A of Reference 2.

c. Frequency response measurements on the Manual (V_{GA}) speed control loop were performed at 19K rpm with C-8 in position control at a Q/N of .25. C-221 was closed and C-231 adjusted to maintain 45 psig at CP-220.

d. Frequency response measurements on C-231 in position control were performed at 19K rpm with speed in manual control, C-8 in position control at a Q/N of .25, C-221 closed, and C-231 set to establish 45 psig at CP-220. After the frequency response measurements were completed, CTO initiated a shutdown with the Emergency Shutdown (ESD) preset ramp rate at its slowest rate (approximately 2000 rpm/sec). The flow rate vs pump delta P trace on the X-Y plotter for the ESD was almost identical to the trace for the startup to 19K rpm.

e. Frequency response measurements on C-8 in position control were performed at 16K rpm with speed in manual control, C-8 set for a Q/N of .22 and C-231 set for 45 psig with C-221 closed. After the frequency responses were completed, an ESD was initiated with the preset ramp rate increased to approximately 4000 rpm/sec. This shutdown rate produced a maximum drive motor armature current of approximately 6000 amps and a flow rate vs pump delta P trace on the X-Y plotter which was almost identical to the startup trace.

f. C-8 and C-106 valve mapping tests were performed at 19K rpm with speed in manual control and C-231 manually adjusted to maintain 50 psig at CP-220 with C-221 closed. With C-106 closed and C-8 opened to the electrical clamp (68%) the maximum Q/N was .32. With C-8 closed and C-106 opened to the electrical clamp (30%) the maximum Q/N was .13. When using C-8 and then C-106 alone to decrease toward a Q/N of .1, the pump exhibited indications of stall around .10 to .11 Q/N at 19K rpm. A planned ESD was taken from 19K rpm while operating at a Q/N of .25 at a ramp rate \approx - 4000 rpm/sec. (700 pot divisions on the Shutdown Ramp Rate potentiometer). This ramp rate appeared to be quite satisfactory from the standpoint of both the Test Article and the Facility.

B. EP-1, SECOND DAY

1. The following test article and facility changes were made on 9 December 1971 in preparation for testing on 10 December 1971:

- a. Removed the 47 hole fluid conditioner and installed the open spacer in its place.
- b. Installed mechanical valve blocks on C-8 and C-106 to limit C-106 to 29% and C-8 to 68%. The electrical clamps on C-8 and C-106 were removed.
- c. Installed new compensation networks for the Q/N controller to permit C-8 to operate in Q/N control.
- d. Modified the RPM controller compensation to permit stable operation in RPM control.
- e. It was decided that a pressure controller for C-231 was not required; C-231 position control was acceptable.

2. The following tests were performed on 10 December 1971 (Friday):

- a. A green run to 26K rpm was performed in manual speed control and C-8 position control at a Q/N of .25. C-231 was manually opened at 10K rpm (before C-221 was closed) and adjusted to maintain 40 psig at CP-220 while increasing to 26K rpm. Because of questionable supply dewar LH₂ level instrumentation, an ESD was initiated at 26K. This shutdown demonstrated that an ESD was the most desirable way to terminate pump operation.
- b. Frequency response on the RPM speed control mode were performed at an indicated 19K rpm. Subsequent investigation determined that, based on pump delta P and flow rate, the true speed was more like 13K rpm. The higher speed indication was due to noise on speed channel UQ-1 and the design feature of the speed controller which utilizes the higher of the two speed channels. The frequency response measurements were made with C-8 in position

control at a Q/N of .25 and C-221 closed with C-231 adjusted for 60 psig at CP-220. A planned ESD was initiated by the CTO.

c. Frequency response measurements were made on the Q/N control system at 19K rpm with the speed controller in RPM control and C-221 closed with C-231 adjusted for 20 psig at CP-220. The test was terminated by a planned ESD.

d. Frequency response measurements were repeated on the RPM speed control loop at 19K rpm with C-8 in position control and C-221 closed with C-231 full open. The supply dewar was pressurized to 49 psig, and after completing the response measurements, C-8 was used in position control to map the 19K rpm speed line from Q/N of .25 out to .35 (the C-8 block) and to a minimum Q/N of .14 before returning to \sim .20/Q/N where a planned ESD was initiated. During the shutdown, C-8 opening was continued to the 60% position (\sim .25 Q/N).

e. Mapping of the 23K and 26K rpm speed lines with 40 psig supply dewar pressure was performed in the RPM speed control mode with C-8 in position control and C-221 closed with C-231 opened. The sequence which was used to get to 23K rpm was: C-221 open and C-231 closed with C-8 set to 60%; manual speed control from 0 to 10K rpm; switch C-106 to AUTO: Open C-231 to 4% and close C-221 then adjust C-231 for 20 psig at EP-220; Switch to RPM speed control; Switch to Hold and set Ramp Rate pot to 800 rpm/sec and RPM demand to 19K rpm; Switch to Run and open C-231 to 100% as speed increased to 19K rpm; at 19K switch to Hold and reset RPM demand to 23K; Switch to Run and monitor Q/N and rpm as it approached 23K rpm. At 23K rpm, the Q/N was first increased to .35 (C-8 Block) and then decreased to .14 before returning to .25. The speed then ramped to 26K rpm where the Q/N was decreased to .17 and increased to .35 before returning to .25 Q/N where a planned ESD was initiated.

f. Mapping of the 23K rpm speed line with 60 psig dewar pressure was performed in RPM speed control with C-8 in Q/N control and C-231 opened with C-221 closed. Mapping was limited to Q/N values of .33 and .17. After the Q/N was returned to .25, the supply dewar pressure was increased from 60 to 80 psig. The 80 psig dewar mapping of the 23K speed line was limited to Q/N value of .33 and .16 and the planned ESD was initiated at a Q/N of .20.

C. EP-2, FIRST DAY

1. The following test article and facility changes were made on Monday and Tuesday (13 and 14 December 1971) in preparation for testing on 15 December 1971:

a. The pump inlet spool with the displacement probes was replaced with a spool which had no obstructions.

b. The inducer spinner with the calibration spotfaces was replaced with the normal spinner.

c. The bellows liner was not removed.

d. The spacer was removed and the 21 hole fluid conditioner was installed.

e. Hot GHe pump purges and leak checks were completed.

f. The C-8 mechanical block was examined and determined that a brass collar had extruded from between the mechanical block and the actuator body allowing the valve to open to 84% - this was deemed acceptable.

2. The following 17 cavitation data points were obtained on 15 December 1971 (Wednesday):

<u>RUN NUMBER</u>	<u>SPEED, RPM</u>	<u>Q/N</u>	<u>DEWAR TEMP. °R</u>
1	19K	.17	39
1	19K	.24	39
2	19K	.30	41
3	22K	.17	41
3	19K	.17	41
4	24K	.24	37.5
5	19K	.24	41
5	22K	.24	41
6	24K	.24	41
6	24K	.17	41
7	24K	.17	39
7	22K	.17	39
8	19K	.30	37.5
8	19K	.24	37.5
8	19K	.17	37.5
9	19K	.30	39
9	22K	.24	39

D. EP-2, SECOND DAY

1. The following test article changes were made during the night of 15 December 1971 in preparation for testing on 16 December 1971:

a. The 21 hole fluid conditioner was removed and the 47 hole fluid conditioner was installed.

2. The data points listed below were performed on 16 December 1971 (Thursday); 13 cavitation points and two mapping tests.

a. Cavitation Points

<u>RUN NUMBER</u>	<u>SPEED, RPM</u>	<u>Q/N</u>	<u>DEWAR TEMP. °R</u>
10	22K	.30	37.5
10	24K	.30	37.5
11	22K	.30	41
11	24K	.30	41
11	26K	.30	41
12	22K	.30	39
12	24K	.30	39
12	26K	.30	39
13	22K	.30	43
13	24K	.30	43
14	26K	.30	37.5
15	26K	.30	43
15	24K	.24	43

b. A mapping test of the 23K rpm speed line was performed with 37.5°R LH₂ from Q/N values of .28 to .37 (where C-8 was open to the mechanical block) after cavitation run #14.

c. The low speed mapping tests were performed with 39°R LH₂ and a supply dewar pressure of 40 psig. The speed was increased to 12K rpm in rpm speed control with C-8 in Q/N control at .22. Q/N (using only C-8) was increased to .35 while at 12K rpm and then decreased to .14. The speed was then reduced to 9K rpm (in RPM control) and the Q/N increased from .14 (in Q/N control) toward .35, C-8 was switched to position control to reach the .35 value. At Q/N of .35, the speed was reduced to 6K rpm (in speed control)

and C-8 (in position control) was reduced to .14 Q/N with good control. At Q/N of .14, the speed was reduced to 3K (in speed control) and C-8 was opened (in position control) to increase toward Q/N of .35.

E. EP-2, THIRD DAY

1. The following test article changes were made during the night of 16 December 1971 in preparation for testing on 17 December 1971:

a. The 47 hole fluid conditioner was removed and the 21 hole fluid conditioner was installed.

2. The following 19 cavitation data points were obtained on 17 December 1971 (Friday):

<u>RUN NUMBER</u>	<u>SPEED, RPM</u>	<u>Q/N</u>	<u>DEWAR TEMP. °R</u>
16	24K	.17	37.5
16	22K	.17	37.5
16	22K	.24	37.5
17	24K	.17	43
17	22K	.17	43
17	22K	.24	43
17	19K	.24	43
17	19K	.17	43
18	26K	.17	41
18	26K	.21	41
19	26K	.17	43
19	26K	.21	43
20	26K	.17	37.5
20	26K	.21	37.5
21	26K	.17	39
21	26K	.21	39
21	24K	.21	39
22	19K	.30	43
23	24K	.24	39

F. EP-2A

1. The following test article changes were made on Monday and Tuesday (20 and 21 December) in preparation for testing on 22 December 1971:

- a. The 21 hole fluid conditioner was removed.
- b. The pump inlet bellows liner was removed.
- c. The 47 hole fluid conditioner was installed.

2. The final tests were completed on 22 December 1971 (Wednesday) and include 8 cavitation points, 2 mapping tests and a high speed test to determine the critical speed of the pump assembly.

a. Cavitation Points

<u>RUN NUMBER</u>	<u>SPEED, RPM</u>	<u>Q/N</u>	<u>DEWAR TEMP. °R</u>
24	26K	.26	37.5
25	27K	~.28 (73 pps)	39
26	26K	.26	39
26	24K	.30	39
26	22K	.30	39
27	26K	.26	41
28	26K	.26	43
29	27K	~.28 (73 pps)	37.5

b. A mapping test of the 23K rpm speed line was performed between cavitation runs #24 and #25 using 41°R LH₂ and a supply dewar pressure of 60 psig. The pump startup ramp to 23K rpm was made along the .14 Q/N line and then C-8 (in Q/N control) was used to move to the .34 Q/N point on the 23K rpm line where a planned ESD was initiated for a shutdown along the .34 Q/N line.

c. The high speed test was performed to locate the critical speed of the pump as indicated by a rapid increase in pump shaft displacement. This test was performed between cavitation runs #26 and #27 using 39°R LH₂ with a supply dewar pressure of 100 psig. The pump was started up in RPM speed control with C-8 in Q/N control to 26K rpm and a Q/N of .30. Then the speed demand was slowly increased while C-8 maintained a Q/N of .30 and the SCOPE operator monitored the shaft displacement instrumentation. The pump speed was reduced several hundred rpm after the displacement instruments showed a step increase; the maximum speed was approximately 29.2K rpm. The speed was slowly increased again and at approximately 29K, the shaft displacement began to increase and the speed was reduced before a planned ESD was initiated to terminate this test.


d. A low speed mapping test was performed between cavitation runs #28 and #29 using 37.5°R LH₂ with a supply dewar pressure of 50 psig. This test utilized pump inlet flow through K-130 (rather than the normal K-3) so that low flow rates could be measured by the turbine flowmeter KF-130 which had been re-ranged from 0-5 pps to 0-15 pps. The pump was operated at 3K and 6K rpm with K-130 open and C-8 used in position control to limit the KF-130 flow from dewar flow up to 15 pps. The pump discharge pressure for this test indicated very questionable data; it was suspected that the K-130 leg was offering too large a pressure drop creating a two-phase hydrogen condition at the pump inlet.

e. Another low speed mapping test was performed after cavitation run #29 using 39°R LH₂ and a supply dewar pressure of 40 psig. This test utilized pump inlet flow through K-3 rather than K-130. The 6K rpm speed line was mapped in RPM speed control from a Q/N of .20 to .1 with C-8 in position control. Then the 9K rpm speed line was mapped from a Q/N of .20 to .06 with RPM speed control and C-8 position control before a planned ESD was used to terminate the test.

The operating conditions are summarized in Figure 17.

The chronologies for the six experimental plans are included as Appendices B through G.

LH₂ PUMP COMPONENT DEVELOPMENT TEST OPERATING CONDITIONS



XI. RESULTS

The test program consisted of six run days as described in Section X. During the program a large amount of operational data was acquired. This section discusses the significant results of the tests conducted. The data acquired has been divided into three general categories: Non-cavitating Performance, Cavitating Performance, and High Speed Test results.

A. NON-CAVITATING PERFORMANCE


The following non-cavitating performance was evaluated:

1. Overall Performance
2. Inducer Performance
3. Impeller Performance
4. Housing Losses
5. Axial Thrust
6. Radial Thrust

1. Overall Performance

The overall head capacity curve is presented in Figure 18 in terms of normalized isentropic head rise ($\Delta H/N^2$) and normalized flow (Q_D/N). The discharge flow rate Q_D used in this presentation is 5 to 15% lower than the inlet flow Q_S because both the impeller rear labyrinth leakage and the bearing coolant flow were tapped off and directed to the burn stack. All data points plotted in Figure 18 were taken from mapping tests conducted at constant speeds and high suction pressure.

NERVA INDUCER TEST RIG
 OVERALL NORMALIZED ISENTROPIC HEAD RISE VS Q_D / IN



MADE IN U.S.A.
 ENGINE DIVISION
 GENERAL ELECTRIC COMPANY

Overall head rise was approximately four percent higher than predicted at the low Q_D/N value of 0.125. At higher capacity-speed ratios however the measured head agreed quite well with the predicted head curve.

Maximum head rise was measured at a Q_D/N value of approximately 0.125, which falls between that of the first stage and that of the second stage of the two-stage pump tested in air (Reference 1). This value was expected since the test rig consisted of a first stage rotor and a second stage housing.


The apparent discontinuity in the positive slope region of the head curve is primarily due to data scatter resulting from large differences in speed between the low flow test conducted at 9000 rpm and the regular mapping tests conducted at speeds above 18000 rpm. Stall as evidenced on the pump air test rig is not well defined in Figure 18 mainly because of data scatter and a lack of data at lower values of Q_D/N .

The high flow limit or the cut-off capacity at head breakdown due to cavitation ($Q_D/N = .345$) is well defined by data points taken at two operating speeds. This operating limit is also confirmed by the cavitation test results.

Figure 19 depicts the overall head coefficient plotted as a function of the discharge flow coefficient. Data points from cavitation tests at NPSP values greater than 20 psi agree well with data from mapping tests.

NERVA INDUCER TEST RES

OVERALL HEAD COEFFICIENT VS. DISCHARGE FLOW COEFFICIENT



10 X 10 PER HALL (INCH)
 NO. 510V-1017 DIELESEN CO.
 MADE IN U. S. A.
 ENGINE DIELESEN CO.

Pump efficiency presented in Figure 20 is expressed as the ratio of ideal enthalpy rise to actual enthalpy rise. The actual enthalpy rise was determined from measured temperature rise. Values of efficiency based on discharge flow (lower curve) account for impeller rear labyrinth and bearing coolant flow losses. These values were obtained by downgrading the upper values (based on inlet flow) in accordance to the ratio of discharge flow to inlet flow. Disc friction losses are not accounted for in the values presented because the frictional heat was dissipated by the labyrinth flow.

The peak efficiency of 82% based on inlet flow agrees with values measured on the air test rig when operated without flow recirculation.

2. Inducer Performance

The measured static head at the inducer discharge based on two wall static taps located between inducer exit and impeller inlet is presented in Figure 21 as a function of inlet flow. Measurements made on the air test rig at a similar location slightly inward of that of the inducer test rig are represented by the dashed line. The higher head obtained in liquid hydrogen was mainly attributed to differences in orientation and location of pressure taps between the two rigs rather than discrepancies in flow measurements. The slopes of the two characteristics are identical.


NERVA INDUCER TEST RIG

N8300R:72-101

May 1972

Page 79

EFFICIENCY VERSUS FLOW PARAMETER Q_D / N



SYMB	SPEED RPM	INLET TEMP °R	NEFP RANGE PSI
△	18800	38.0	39.1 - 44.8
◇	19300	37.0	28.0 - 35.75
○	23500	36.8	24.3 - 35.17
□	26500	36.8	20.75 - 32.16


Q_D / N (GPM/RPM)

(Q_D = DISCHARGE FLOW)

NERVA INDUCER TEST RIG
 INDUCER TIP STATIC HEAD RISE VS FLOW PARAMETER Q_s / N

SYMB.	SPEED RPM	INLET TEMP OR	NPSP RANGE PSI
△	18800	38.0	39.1 - 44.8
◇	19300	37.0	28. - 35.75
○	23500	36.8	24.3 - 35.17
□	26500	36.8	20.75 - 32.16

INDUCER TIP STATIC HEAD RISE $\Delta H_s / N^2$ (FT./RPM² x 10⁵)



Q_s / N (GPM/RPM)

Q_s = INLET FLOW

10 X
 ENGINEERING DIVISION
 GENERAL ELECTRIC CO.

12-29-72

3. Impeller Performance


The impeller head coefficient is plotted as a function of discharge flow coefficient in Figure 22. The data is compared with air test data and the predicted actual and ideal head coefficient at the design flow coefficient. The values presented were computed for axial inlet flow (no prewhirl) and thus include the inducer head. The velocity head, which is added to the measured static head, was calculated from the fluid tangential velocity component based on the Stodola correction for slip. The meridional component of velocity was obtained from continuity considerations. Equations used in the computation of the impeller head coefficient are presented in Section IX.

Air test and hydrogen test data agree quite well at flow coefficients above design. At low flow coefficients, however, the impeller head obtained in liquid hydrogen is somewhat less than that measured on the air test rig. The difference in performance at low flow could be related to the following causes:

- a. Changes in interaction effects resulting from different housings.
- b. Effect of backvanes with outward flow on air test impeller. Impeller of inducer test rig had smooth disc with inward flow through labyrinth.

NERVA INDUCER TEST RIG

IMPELLER HEAD COEFFICIENT VS. DISCHARGE FLOW COEFFICIENT



SYMB	SPEED	INLET TEMP °R	NPSP RANGE PSI
◇	23500	41.7	9.4 - 24.8
○	CAVITATION TESTS		NPSP > 20

DISCHARGE FLOW COEFFICIENT ϕ_2
 (BASED ON BLOCKED IMPELLER DISCHARGE
 AREA $A_2 = 19.13 \text{ IN}^2$)

3-7-72

10 / 10 PER HALF INCH
 NO. 2000-11.1 DIETZGEN GRAPH PAPER
 DIETZGEN CO.

4. Housing Losses

Housing losses are presented in Figure 23 in terms of head loss coefficient and discharge flow coefficient. The head loss coefficient is defined as the difference between the impeller head coefficient and the stage head coefficient and therefore, includes volute losses as well as diffuser vane losses. The static head used in the computation of the total head at the impeller discharge is based on an average circumferential pressure determined from equally spaced wall taps at identical locations with respect to the housing vanes. The average circumferential pressure thus does not necessarily represent an average value of pressure variations from vane to vane at the same radius.

The relatively large variation in housing loss coefficients results from general data scatter reflected on impeller head and overall pump head and the small difference in the magnitudes of these parameters. Minimum housing losses amounted to approximately 6% of the pump head rise and agree quite well with predictions based on air test data.


5. Axial Thrust

The net axial thrust was computed from the pressure forces acting upon the front face and the backface of the impeller. These pressure forces were determined through numerical integration of the respective pressure profiles. Axial thrust considered as positive in direction towards pump inlet, reached momentary peak magnitudes of approximately 3400 lbs at the highest speed, lowest Q/N value and lowest suction pressures tested. High negative thrust magnitudes of approximately 1000 lbs were obtained at high suction pressures, high values of Q/N and low speed. Thrust reversals were experienced during start and shutdown transients.

NERVA INDUCER TEST RIG
 HOUSING HEAD LOSS COEFFICIENT VS DISCHARGE FLOW
 COEFFICIENT

HOUSING HEAD LOSS COEFFICIENT $A_{H50} = \frac{W}{W_{TP}} - \frac{W}{W_{STAGE}}$

SYMB	SPEED RPM	INLET TEMP °R	NPSP RANGE PSI
◇	23500	41.7	9.4 - 24.8
○	CAVITATION TESTS		NPSP > 20



DISCHARGE FLOW COEFFICIENT ϕ_2
 (BASED ON BLOCKED IMPELLER
 DISCHARGE AREA $A_2 = 14.15$)

3-7-72 *ES*

10 X 10 REVISIONS INCH
 NO. 34-V-100 DIT. 11 REVISION PAPER
 MADE IN U.S.A.
 ENGINEER DIEITSEN CO.

6. Radial Thrust

The radial force acting upon the impeller shown in Figure 24 as a function of Q_D/N is expressed as the ratio of radial force to the average static pressure rise measured at the periphery of the impeller. The radial force was obtained by integrating the circumferential pressure profile based on 9 static pressure taps located between impeller tip and diffuser inlet. The effective impeller tip width was assumed to be one inch.

The radial force parameter of this single stage pump is about twice as high as that of the two stage air test pump (Reference 1) because the average impeller discharge pressure of the single stage pump would only be approximately half of that of the second stage of the air test pump under the same operating conditions.

Data points from mapping tests agree well with the minimum predicted value indicated by the dashed line in Figure 24 between the Q_D/N values of 0.2 and 0.3. The large scatter in data points taken from cavitation tests at high starting values of NPSP reflects instrumentation accuracy and non-steady state conditions.

B. CAVITATING PERFORMANCE

The following performance aspects were evaluated:


1. Suction Performance
2. Axial Thrust
3. Radial Thrust
4. High Frequency Pressure Measurements
5. Cavitation Data Correlation
6. Flow Limit

NERVA INDUCER TEST RIG

RADIAL FORCE PARAMETER VS Q_D / N

RADIAL FORCE PARAMETER = $\frac{\text{RADIAL FORCE (LN}^2\text{)}}{\text{INLET STAT. PRESSURE RISE}}$

SYMB	SPEED RPM	INLET TEMP OR	NPSP RANGE PSI
◇	23500	41.7	9.9 - 29.8
○	CAVITATION TESTS NPSP > 20		



Q_D / N (GPM/RPM)
 (Q_D = DISCHARGE FLOW)

MADE IN U.S.A. ENGINE DIETZ 100

1. Suction Performance

The reduced data for the cavitation tests are shown in Appendix H. These plots show the performance of the pump as the suction pressure was reduced to induce cavitation.

2. Axial Thrust

Axial thrust was very sensitive to suction pressure. During cavitation runs, the net thrust toward suction increased with decreasing suction pressure and reached a maximum value at the point where head breakdown occurred. At this limiting value of NPSF, thrust decreased as head dropped off. A typical axial thrust - NPSF characteristic is shown in Figure 25.

3. Radial Thrust

Radial thrust expressed in terms of the radial force parameter defined in Section IX is also plotted in Figure 25 as a function of NPSF. In contrast to axial thrust, radial thrust was only little affected by changes in suction pressure. A minor thrust peak occurred near the NPSF value at incipient cavitation. The drop off in radial thrust parameter in the region of head breakdown was minor.

4. High Frequency Pressure Measurements

Two Kistler high frequency (0-5000 Hz) pressure transducers were installed in the test facility system to monitor inlet and discharge pressure. The inlet pressure transducer, CP 511W (Range 0-100 psi) was located 1.5 inches upstream of the test article inlet and the discharge pressure transducer, CP-542W (Range 0-1000 psi) was located 3.5 inches downstream of the test article discharge flange. The signal conditioned transducer outputs were

recorded on wide band tape during all test runs. Playbacks of the data tape were recorded on oscillograph at a 1 inch per second rate for preliminary review. Selected portions of cavitation tests were recorded at 40 inches per second to permit observance of possible pressure wave forms.

Inspection of the high frequency pressure data showed the amplitude of pressure oscillation to be less than 1.0 psi and 50 psi for the inlet (CP 511W) and discharge (CP 542W) pressure measurements respectively and no discernable pressure wave form was observed.

5. Cavitation Data Correlation

Cavitation performance of the pump, in terms of net positive suction pressure (NPSP), is known to be a function of pump speed (N), pump volumetric flow rate (Q), and vapor pressure (P_V). An attempt was made to find an empirical relation for the NPSP at breakdown for the LH₂ pump. The derived relation was based on the cavitation data of Appendix H.

Preliminary plots of this data revealed the following trends regarding breakdown NPSP:

- a. NPSP is linear in speed (N) and vapor pressure (P_V)
- b. $\frac{\partial \text{NPSP}}{\partial N}$ is independent of flow coefficient (Q/N)
- c. NPSP is not linear in flow coefficient (Q/N)

The above information lead to the following form of the empirical relation

$$\text{NPSP} = \left[\frac{P_V}{a} + b \right] \left[\frac{N}{1000} + c + d \left(\frac{Q}{N} \right) + e \left(\frac{Q}{N} \right)^2 \right]$$

The coefficients a, b, c, d, and e were found using the data of Appendix H and least square techniques. The resulting values were

$$a = 130$$

$$b = -0.076$$

$$c = -153.1$$

$$d = 525$$

$$e = -450$$

Using this empirical relation, breakdown NPSP was computed for each cavitation test and compared with established test values. The results of this comparison are shown in Table III. The maximum difference was found to be 0.6 psi.

6. Flow Limit

Figure 26 presents maximum values of estimated vapor fractions (gas to liquid volume ratios) and flow to speed ratios (Q_S/N) for a series of 35 cavitation tests. It is interesting to note that the limiting Q_S/N values, which account for vapor in the suction line, fall within a rather narrow band of values from 0.33 to 0.38. The average value of Q_S/N agrees well with the cut-off capacity to speed ratio defined by mapping tests in Figure 18. The corresponding incidence to blade angle ratio at the inducer tip for the limiting Q_S/N value of 0.35 is approximately 0.21, when the fluid density at the inducer inlet is assumed to be the same as at the instrumentation location downstream of the vapor generator.

TABLE III
CAVITATION DATA CORRELATION

Q/N	N	PV	NPSP	CNPSP	DEV			
.190	19200.	20.2	-4.30	-4.00	.30			
.190	19300.	21.5	-4.50	-4.53	-.03			
.190	19000.	36.0	-10.40	-10.16	.24			
.190	18650.	46.8	-14.60	-14.41	.19			
.190	22200.	26.1	-3.40	-3.72	-.32			
.190	22200.	24.6	-5.60	-5.36	.24			
.190	22500.	35.5	-9.20	-9.28	-.08			
.190	22200.	45.5	-13.00	-12.98	.02			
.190	24300.	19.9	-3.20	-3.46	-.26			
.190	24400.	24.5	-5.30	-5.08	.22			
.190	24300.	34.0	-8.80	-8.40	.40			
.190	24400.	45.0	-12.30	-12.21	.09			
.190	26400.	19.0	-3.10	-3.03	.07			
.190	26500.	27.9	-5.70	-5.97	-.27			
.190	26500.	35.7	-8.40	-8.56	-.16			
.190	26500.	40.9	-10.30	-10.28	.02			
.260	19200.	19.7	-2.30	-2.10	.20			
.260	19300.	21.2	-2.40	-2.41	-.01			
.260	19200.	34.7	-5.10	-5.31	-.21			
.260	18300.	45.0	-7.40	-7.62	-.22			
.260	22500.	19.9	-1.80	-1.90	-.10			
.260	22500.	26.1	-3.20	-3.43	-.23			
.260	22400.	34.3	-4.50	-4.62	-.12			
.260	22200.	44.5	-6.30	-6.61	-.31			
.260	24400.	18.9	-1.80	-1.57	.33			
.260	24200.	27.5	-3.00	-3.09	-.09			
.260	24300.	32.9	-4.00	-4.02	-.02			
.260	24100.	42.4	-5.50	-5.73	-.23			
.240	26400.	19.2	-2.20	-1.91	.29			
.240	26400.	27.5	-3.40	-3.61	-.21			
.240	26500.	35.3	-5.20	-5.18	.02			
.240	26500.	40.2	-6.50	-6.18	.32			
.320	19200.	19.4	-1.40	-.88	.52			
.320	19200.	28.0	-1.70	-1.67	.03			
.320	19200.	33.1	-2.30	-2.12	.18			
.320	19100.	43.2	-3.40	-3.09	.31			
.320	22500.	21.6	-.60	-.78	-.18			
.320	22500.	25.7	-.90	-1.05	-.15			
.320	22100.	26.1	-1.00	-1.13	-.13			
.320	22500.	33.3	-1.70	-1.56	.14			
.320	24300.	21.8	-.40	-.63	-.23			
.320	24400.	25.8	-.80	-.83	-.03			
.320	24200.	26.0	-.80	-.86	-.06			
.320	24400.	33.4	-1.20	-1.22	-.02			
.320	26500.	18.3	-.30	-.30	-.60			
.320	26500.	26.8	-.50	-.61	-.11			
.320	26500.	33.7	-1.00	-.85	.15			
.320	26400.	41.6	-1.50	-1.16	.34			
A=	150.0	B=	-.076	C=	-153.1	D=	525.00E=	-450.000
MAX. DEVIATION =	.60	SUM DEV. SQ. =	2.51					

Morse-Balchert Form, Inc. 11

N8300R:72-101
May 1972
Page 91

$$NPSP = (P_v - 0.076) \sqrt{\frac{N}{T} - 153.1 + 525 \left(\frac{Q}{N}\right) - 450.0 \left(\frac{Q}{N}\right)^2}$$

LH₂ TEST RIG

N8300R:72-101

May 1972


Page 92

VAPOR FRACTION B VS. NORMALIZED INLET FLOW
AT HEAD BREAKDOWN

P_{vap} (PSIA)

- 20 - 21.9
- 25.2 - 26.7
- ◇ 33.5 - 35
- △ 40 - 46

VAPOR FRACTION B = V_{g05} / V_{in9}



NO. 3104-50 DIETZGEN GRAPH PAPER

MADE IN U.S.A. ENGINE DIETZGEN CO.

1-28-72 5/31
C2

C. HIGH SPEED TEST RESULTS

A high speed test of the test article was conducted during EP-2A to establish the critical speed experimentally.

1. Measurement and Data Display

Proximity measuring probes (Channels CD-702 through CD-708) radially located around the rotor at 90 degree intervals adjacent each rotor bearing, were used to detect both rotor rotation and radial rotor movement. A local step change in rotor shaft diameter (approximately .0003 in depth spotface) over an approximate arc of 12 degrees rotation provided a momentary proximeter to shaft distance step change. The resulting proximeter signal output step change for each revolution of the rotor shaft could be observed on oscilloscope monitor and subsequently on the oscillograph record. A pretest proximeter-to-rotor shaft distance calibration established the spotface depth in relation to signal output voltage value. The step change in proximeter signal output was a known distance based on the pretest calibration thereby allowing disregard for output sensitivity changes caused by temperature variation. The scale factor could likewise be used to measure, directly from the oscillograph record, the amplitude of rotor radial movement.

The signal conditioned proximeter output was tape recorded and patched on line to oscilloscope display during all tests. Off-line playback of the data through a CEC oscillograph recorder provided oscillograph data displayed at a paper speed of 1 inch per second with selected portions at 40 inches per second.

2. Test Results

A high speed run of the test article was conducted during the December 22nd EP-2A using inlet conditions of 100 psia inlet pressure and 39°R inlet fluid temperature. Discharge flow system impedance was controlled to maintain a Q/N of 0.30.


For the high speed test, rotational speed was adjusted to approximately 26,000 rpm and then slowly increased while observing the rotor dynamics displayed on the oscilloscopes. Figure 27 presents a plot of speed versus time at the maximum speed condition. The rotor radial displacement amplitude rapidly increased at approximately 29,200 rpm.


A maximum radial displacement of 6.0 mils double amplitude was measured at the 90 degree aft end bearing location at the time period of maximum speed. Corresponding forward rotor radial displacement (CD 703) was 3.6 mils double amplitude. The displacement amplitudes include shaft rotation eccentricity estimated at less than 0.05 mils double amplitude.

The peak speed achieved was 29,245 rpm based on the displacement probe shaft spotface frequency count.

Figure 28 presents a plot of shaft radial displacement (CD 703 and CD 706) and beat frequency versus speed. The beat frequency, characterized by sudden change in amplitude of the speed frequency, was observed at indefinite intervals in time at speeds in excess of 28,000 rpm. However a definite beat frequency between 90 and 100 Hz was noted between 28000 rpm and 29000 rpm. Additional speed increase reduced the beat frequency as noted on Figure 28.

The maximum radial displacements resulted when the beat frequency decreased to zero which was simultaneous with the maximum speed. Given the relationship $\omega_N = \omega_S \pm \omega_B$ (where ω_N = natural frequency, ω_S = speed frequency and ω_B = beat frequency) the data presented in Figure 28 shows the critical speed to occur at approximately 29,250 rpm which agrees well with the predicted critical speed of 30,000 rpm.





XII. REFERENCES

1. N8300R:71-090, "Performance of a Two-Stage Centrifugal NERVA Pump Tested with Air as the Working Fluid", dated 9 December 1971
2. NRTO-R-0213, "Test Description for NERVA LH₂ Pump Component Development Test at Test Cell "C", dated 11² November 1971
3. ANSC Drawing 1139300, "LH₂ Test Rig Assembly-First Stage"
4. ANSC Drawing 1138562, "Vaned Inlet Spool-LH₂ Test Rig"
5. ANSC Drawing 1138561, "Inlet Spool - LH₂ Test Rig"
6. ANSC Drawing 1138588, "Inducer - LH₂ Test Rig"
7. ANSC Drawing 1138550, "Impeller, First Stage LH₂ Rig"
8. ANSC Drawing 1138600, "Housing, LH₂ Test Rig"
9. NRTO Drawing 1440038, "Fluid Conditioner, FC-47, CEL Inducer Pump Testing"
10. NRTO Drawing 1440037, "Fluid Conditioner, FC-21, CEL Inducer Pump Testing"
11. NBS Monograph 94, Thermodynamic and Related Properties of Para-hydrogen from the Triple Point to 100°K at Pressures to 340 Atmospheres, dated 10 August 1965
12. NRTO-TOP-0044, Test Operating Procedure for NERVA Turbopump Inducer Tests (CEL), EP-I
13. NRTO-TOP-0045, Test Operating Procedure for NERVA Turbopump Inducer Tests (CEL), EP-II

APPENDIX A

LH₂ PUMP TEST DATA REDUCTION PROGRAM

EL. DATA.1.720405. 41895

000001	9	10	11	13	15	16	16	17	17	18	19	20	43	43	43	43	43	42	42	42	42	42	41	41	41
000002	40	40	39	39	38																				
000003	24.9029			25.2000				27.0000				28.8000			30.6000			32.4000			34.2000			36.0000	
000004	36.4823																								
000005	0.20788			0.20828				0.21058				0.21305			0.21575			0.21869			0.22187			0.22528	
000006	0.22632																								
000007	-132.27			-131.80				-128.88				-125.77			-122.46			-118.96			-115.25			-111.28	
000008	-110.18																								
000009	1.186			1.205				1.316				1.427			1.539			1.650			1.761			1.874	
000010	1.905																								
000011	24.9336			25.2000				27.0000				28.8000			30.6000			32.4000			34.2000			36.0000	
000012	37.8000			39.0995																					
000013	0.20780			0.20812				0.21042				0.21289			0.21559			0.21853			0.22163			0.22512	
000014	0.22894			0.23196																					
000015	-131.97			-131.55				-128.65				-125.53			-122.25			-118.75			-115.02			-111.07	
000016	-106.85			-103.63																					
000017	1.186			1.202				1.314				1.425			1.536			1.648			1.759			1.872	
000018	1.985			2.070																					
000019	24.9641			25.2000				27.0000				28.8000			30.6000			32.4000			34.2000			36.0000	
000020	37.8000			39.6000				41.1497																	
000021	0.20772			0.20804				0.21026				0.21281			0.21543			0.21829			0.22147			0.22489	
000022	0.22870			0.23291				0.23697																	
000023	-131.67			-131.31				-128.39				-125.30			-122.01			-118.51			-114.80			-110.86	
000024	-106.66			-102.16				-98.04																	
000025	1.186			1.201				1.312				1.424			1.534			1.645			1.757			1.869	
000026	1.983			2.099				2.201																	
000027	25.0254			25.2000				27.0000				28.8000			30.6000			32.4000			34.2000			36.0000	
000028	37.8000			39.6000				41.4000				43.2000			44.3376										
000029	0.20756			0.20780				0.21003				0.21249			0.21511			0.21797			0.22107			0.22449	
000030	0.22814			0.23236				0.23705				0.24237			0.24618										
000031	-131.10			-130.82				-127.92				-124.83			-121.54			-118.07			-114.38			-110.45	
000032	-106.27			-101.79				-96.99				-91.85			-88.38										
000033	1.187			1.197				1.309				1.420			1.530			1.641			1.752			1.863	
000034	1.977			2.092				2.211				2.333			2.412										
000035	25.0865			25.2000				27.0000				28.8000			30.6000			32.4000			34.2000			36.0000	
000036	37.8000			39.6000				41.4000				43.2000			45.0000			46.8000			46.8414				
000037	0.20740			0.20756				0.20979				0.21225			0.21479			0.21766			0.22067			0.22401	
000038	0.22767			0.23180				0.23641				0.24157			0.24769			0.25493			0.25508				
000039	-130.52			-130.35				-127.45				-124.36			-121.10			-117.62			-113.95			-110.03	
000040	-105.87			-101.43				-96.67				-91.56			-86.03			-79.95			-79.80				
000041	1.187			1.194				1.305				1.415			1.526			1.636			1.747			1.859	
000042	1.971			2.086				2.203				2.324			2.450			2.581			2.585				
000043	25.1459			25.2000				27.0000				28.8000			30.6000			32.4000			34.2000			36.0000	
000044	37.8000			39.6000				41.4000				43.2000			45.0000			46.8000			48.6000			48.9365	
000045	0.20724			0.20732				0.20955				0.21193			0.21456			0.21734			0.22036			0.22362	
000046	0.22719			0.23124				0.23577				0.24086			0.24674			0.25381			0.26232			0.26414	
000047	-129.95			-129.86				-126.96				-123.89			-120.63			-117.17			-113.50			-109.60	
000048	-105.46			-101.05				-96.33				-91.26			-85.80			-79.80			-73.17			-71.85	
000049	1.188			1.192				1.302				1.412			1.522			1.631			1.743			1.853	
000050	1.965			2.079				2.196				2.316			2.439			2.570			2.709			2.737	
000051	25.2071			27.0000				28.8000				30.6000			32.4000			34.2000			36.0000			37.8000	
000052	39.6000			41.4000				43.2000				45.0000			46.8000			48.6000			50.4000			50.7564	
000053	0.20709			0.20931				0.21162				0.21424			0.21694			0.21996			0.22322			0.22679	
000054	0.23069			0.23514				0.24014				0.24587			0.25262			0.26089			0.27130			0.27368	
000055	-129.37			-126.49				-123.44				-120.18			-116.72			-113.08			-109.19			-105.06	
000056	-100.68			-95.99				-90.96				-85.54			-79.65			-73.13			-65.75			-64.15	

100

000057	1,188	1,298	1,408	1,517	1,628	1,738	1,848	1,959
000058	2,073	2,189	2,308	2,430	2,559	2,695	2,844	2,876
000059	25.2665	27.0000	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000
000060	39.6000	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000
000061	52.3745							
000062	0.20693	0.20907	0.21138	0.21392	0.21662	0.21956	0.22282	0.22632
000063	0.23021	0.23450	0.23943	0.24507	0.25159	0.25945	0.26923	0.28242
000064	0.28401							
000065	-128.79	-126.02	-122.97	-119.71	-116.28	-112.63	-108.77	-104.65
000066	-100.30	-95.63	-90.66	-85.29	-79.48	-73.09	-65.90	-57.50
000067	-56.58							
000068	1,189	1,295	1,405	1,514	1,623	1,733	1,843	1,953
000069	2,067	2,182	2,299	2,421	2,547	2,682	2,827	2,990
000070	3,008							
000071	25.3278	27.0000	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000
000072	39.6000	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000
000073	53.8380							
000074	0.20677	0.20883	0.21114	0.21360	0.21630	0.21924	0.22242	0.22584
000075	0.22965	0.23395	0.23871	0.24420	0.25055	0.25810	0.26748	0.27964
000076	0.29561							
000077	-128.22	-125.53	-122.48	-119.26	-115.83	-112.18	-108.34	-104.25
000078	-99.92	-95.29	-90.34	-85.03	-79.29	-73.00	-65.98	-57.92
000079	-48.92							
000080	1,189	1,291	1,401	1,510	1,619	1,728	1,837	1,949
000081	2,060	2,175	2,291	2,412	2,538	2,669	2,810	2,968
000082	3,137							
000083	25.3871	27.0000	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000
000084	39.6000	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000
000085	54.0000	55.1717						
000086	0.20661	0.20860	0.21082	0.21336	0.21599	0.21893	0.22203	0.22544
000087	0.22918	0.23339	0.23808	0.24340	0.24960	0.25683	0.26573	0.27710
000088	0.29315	0.30896						
000089	-127.64	-125.06	-122.01	-118.79	-115.38	-111.75	-107.91	-103.84
000090	-99.53	-94.93	-90.02	-84.77	-79.10	-72.89	-66.05	-58.24
000091	-48.84	-41.01						
000092	1,189	1,289	1,407	1,506	1,615	1,724	1,833	1,943
000093	2,054	2,168	2,284	2,404	2,527	2,657	2,795	2,948
000094	3,124	3,267						
000095	25.4465	27.0000	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000
000096	39.6000	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000
000097	54.0000	55.8000	56.4029					
000098	0.20645	0.20836	0.21058	0.21305	0.21567	0.21853	0.22163	0.22505
000099	0.22870	0.23283	0.23744	0.24261	0.24865	0.25564	0.26414	0.27487
000100	0.23933	0.31238	0.32525					
000101	-127.07	-124.59	-121.54	-118.32	-114.91	-111.31	-107.49	-103.44
000102	-99.15	-94.56	-89.70	-84.50	-78.87	-72.79	-66.07	-58.48
000103	-49.56	-37.94	-32.54					
000104	1,190	1,285	1,394	1,502	1,611	1,719	1,828	1,938
000105	2,048	2,162	2,277	2,394	2,517	2,644	2,780	2,929
000106	3,096	3,308	3,404					
000107	25.5960	27.0000	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000
000108	39.6000	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000
000109	54.0000	55.8000	57.6000	59.1047				
000110	0.20613	0.20772	0.20995	0.21241	0.21495	0.21773	0.22075	0.22401
000111	0.22751	0.23148	0.23585	0.24078	0.24642	0.25294	0.26057	0.26994
000112	0.28186	0.29847	0.32597	0.41744				
000113	-125.62	-123.40	-120.37	-117.17	-113.78	-110.20	-106.42	-102.41
000114	-98.17	-93.65	-88.87	-83.77	-78.29	-72.40	-65.96	-58.86
000115	-50.78	-41.12	-28.19	-1.36				
000116	1,192	1,277	1,385	1,492	1,600	1,708	1,816	1,925

101

000117	2,034	2,145	2,259	2,374	2,491	2,617	2,747	2,886
000118	3,038	3,214	3,442	3,900				
000119	25,7435	27,0000	28,8000	30,6000	32,4000	34,2000	36,0000	37,8000
000120	39,6000	41,4000	43,2000	45,0000	46,8000	48,6000	50,4000	52,2000
000121	54,0000	55,8000	57,6000	59,4000	61,2000	63,0000	64,8000	66,6000
000122	68,4000	70,2000	72,0000	73,8000	75,6000	77,4000	79,2000	81,0000
000123	82,8000	84,6000	86,4000	88,2000	90,0000	91,8000	93,6000	95,4000
000124	97,2000	99,0000	100,8000					
000125	0.20574	0.20717	0.20939	0.21170	0.21424	0.21694	0.21980	0.22298
000126	0.22640	0.23021	0.23442	0.23911	0.24436	0.25040	0.25747	0.26581
000127	0.27614	0.28941	0.30825	0.34011	0.44994	0.75143	0.90298	1.01590
000128	1.11047	1.19573	1.27433	1.34799	1.41808	1.48531	1.55016	1.61310
000129	1.67436	1.73428	1.79301	1.85062	1.90728	1.96315	2.01830	2.07265
000130	2.12653	2.17978	2.23238					
000131	-124.19	-122.20	-119.20	-116.02	-112.65	-109.09	-105.33	-101.37
000132	-97.17	-92.73	-88.02	-83.00	-77.65	-71.91	-65.73	-58.97
000133	-51.44	-42.82	-32.46	-18.36	12.47	61.59	80.53	93.62
000134	104.16	113.40	121.76	129.52	136.84	143.81	150.53	157.01
000135	163.32	169.47	175.50	181.41	187.21	192.95	198.60	204.19
000136	209.73	1.94	7.40					
000137	1,193	1,269	1,376	1,483	1,591	1,697	1,804	1,912
000138	2,021	2,130	2,241	2,355	2,471	2,592	2,717	2,849
000139	2,990	3,147	3,330	3,571	4,080	4,874	5,172	5,371
000140	5,527	5,660	5,778	5,884	5,982	6,073	6,159	6,240
000141	6,317	6,391	6,461	6,528	6,595	6,658	6,718	6,777
000142	6,835	6,891	6,945					
000143	26,3369	27,0000	28,8000	30,6000	32,4000	34,2000	36,0000	37,8000
000144	39,6000	41,4000	43,2000	45,0000	46,8000	48,6000	50,4000	52,2000
000145	54,0000	55,8000	57,6000	59,4000	61,2000	63,0000	64,8000	66,6000
000146	68,4000	70,2000	72,0000	73,8000	75,6000	77,4000	79,2000	81,0000
000147	82,8000	84,6000	86,4000	88,2000	90,0000	91,8000	93,6000	95,4000
000148	97,2000	99,0000	100,8000					
000149	0.20502	0.20605	0.20820	0.21042	0.21281	0.21535	0.21813	0.22107
000150	0.22433	0.22783	0.23172	0.23601	0.24078	0.24610	0.25214	0.25914
000151	0.26732	0.27726	0.28957	0.30570	0.32851	0.36491	0.43071	0.53719
000152	0.64455	0.73618	0.81533	0.88589	0.95058	1.01082	1.06636	1.12072
000153	1.17293	1.22339	1.27234	1.31994	1.36651	1.41204	1.45670	1.50065
000154	1.54388	1.58647	1.62835					
000155	-121.33	-119.82	-116.83	-113.69	-110.37	-106.87	-103.16	-99.26
000156	-95.14	-90.81	-86.22	-81.38	-76.24	-70.76	-64.94	-58.67
000157	-51.86	-44.42	-36.06	-26.48	-14.92	0.00	20.68	45.94
000158	66.65	82.43	95.16	106.04	115.70	124.49	132.55	140.29
000159	147.67	154.75	161.60	168.23	174.69	181.03	187.21	193.29
000160	199.26	205.17	211.04					
000161	1,196	1,253	1,360	1,465	1,571	1,676	1,782	1,888
000162	1,994	2,102	2,209	2,320	2,431	2,546	2,664	2,786
000163	2,914	3,049	3,198	3,361	3,552	3,792	4,117	4,501
000164	4,808	5,037	5,215	5,365	5,494	5,609	5,712	5,808
000165	5,898	5,983	6,063	6,140	6,212	6,281	6,348	6,412
000166	6,474	6,534	6,594					
000167	26,3268	27,0000	28,8000	30,6000	32,4000	34,2000	36,0000	37,8000
000168	39,6000	41,4000	43,2000	45,0000	46,8000	48,6000	50,4000	52,2000
000169	54,0000	55,8000	57,6000	59,4000	61,2000	63,0000	64,8000	66,6000
000170	68,4000	70,2000	72,0000	73,8000	75,6000	77,4000	79,2000	81,0000
000171	82,8000	84,6000	86,4000	88,2000	90,0000	91,8000	93,6000	95,4000
000172	97,2000	99,0000	100,8000					
000173	0.20430	0.20502	0.20701	0.20915	0.21146	0.21392	0.21654	0.21940
000174	0.22242	0.22568	0.22934	0.23323	0.23760	0.24237	0.24777	0.25381
000175	0.26073	0.26875	0.27821	0.28965	0.30396	0.32239	0.34719	0.38160
000176	0.42943	0.48888	0.55324	0.61602	0.67499	0.73006	0.78163	0.83568

102

000177	0.08208	0.12651	0.16934	0.21074	0.25	0.29013	0.32843	0.36602
000178	0.40281	0.43897	0.47433					
000179	-118.47	-117.41	-114.46	-111.37	-108.06	-104.61	-100.96	-97.12
000180	-93.09	-88.83	-84.37	-79.66	-74.66	-69.42	-63.85	-57.92
000181	-51.59	-44.81	-37.40	-29.30	-20.24	-9.96	1.98	16.01
000182	32.24	49.35	65.54	79.83	92.37	103.48	113.55	122.80
000183	131.44	139.59	147.33	154.77	161.94	168.89	175.65	182.29
000184	188.75	195.10	201.42					
000185	1.199	1.238	1.343	1.449	1.553	1.657	1.761	1.865
000186	1.969	2.074	2.180	2.288	2.395	2.506	2.618	2.733
000187	2.853	2.976	3.106	3.246	3.395	3.561	3.749	3.962
000188	4.202	4.449	4.676	4.873	5.041	5.186	5.315	5.430
000189	5.535	5.634	5.724	5.809	5.890	5.966	6.039	6.109
000190	6.176	6.242	6.304					
000191	26.6130	27.0000	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000
000192	39.6000	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000
000193	54.0000	55.8000	57.6000	59.4000	61.2000	63.0000	64.8000	66.6000
000194	68.4000	70.2000	72.0000	73.8000	75.6000	77.4000	79.2000	81.0000
000195	82.8000	84.6000	86.4000	88.2000	90.0000	91.8000	93.6000	95.4000
000196	97.2000	99.0000	100.8000					
000197	0.20367	0.20407	0.20597	0.20804	0.21019	0.21257	0.21503	0.21773
000198	0.22060	0.22369	0.22711	0.23077	0.23474	0.23911	0.24396	0.24936
000199	0.25540	0.26224	0.27002	0.27916	0.28981	0.30268	0.31834	0.33789
000200	0.36236	0.39280	0.42936	0.47092	0.51518	0.55984	0.60379	0.64614
000201	0.68699	0.72624	0.76415	0.80611	0.84164	0.87620	0.90982	0.94272
000202	0.17490	0.20645	0.23744					
000203	-115.64	-115.02	-112.09	-109.02	-105.78	-102.35	-98.74	-94.97
000204	-90.98	-86.82	-82.45	-77.84	-73.00	-67.92	-62.55	-56.90
000205	-50.90	-44.53	-37.72	-30.41	-22.50	-13.86	-4.37	6.14
000206	17.78	30.52	44.02	57.71	70.95	83.37	94.82	105.42
000207	115.25	124.44	133.15	141.40	149.31	156.91	164.26	171.39
000208	178.32	185.10	191.86					
000209	1.201	1.224	1.329	1.432	1.535	1.638	1.741	1.843
000210	1.946	2.049	2.152	2.257	2.362	2.469	2.578	2.688
000211	2.801	2.917	3.036	3.162	3.292	3.432	3.580	3.740
000212	3.913	4.097	4.287	4.475	4.653	4.814	4.961	5.093
000213	5.213	5.323	5.425	5.519	5.608	5.692	5.771	5.847
000214	5.918	5.988	6.056					
000215	26.8955	27.0000	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000
000216	39.6000	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000
000217	54.0000	55.8000	57.6000	59.4000	61.2000	63.0000	64.8000	66.6000
000218	68.4000	70.2000	72.0000	73.8000	75.6000	77.4000	79.2000	81.0000
000219	82.8000	84.6000	86.4000	88.2000	90.0000	91.8000	93.6000	95.4000
000220	97.2000	99.0000	100.8000					
000221	0.20295	0.20311	0.20494	0.20693	0.20899	0.21130	0.21368	0.21622
000222	0.21893	0.22187	0.22505	0.22846	0.23220	0.23625	0.24070	0.24555
000223	0.25095	0.25691	0.26367	0.27122	0.27996	0.28997	0.30165	0.31548
000224	0.33177	0.35116	0.37397	0.40035	0.42983	0.46186	0.49539	0.52948
000225	0.56358	0.59703	0.62985	0.66196	0.69319	0.72370	0.75350	0.78267
000226	0.01652	0.04458	0.07199					
000227	-112.80	-112.63	-109.73	-106.68	-103.46	-100.09	-96.53	-92.79
000228	-88.87	-84.77	-80.47	-75.97	-71.25	-66.30	-61.10	-55.66
000229	-49.90	-43.87	-37.45	-30.66	-23.43	-15.69	-7.40	1.53
000230	11.17	21.51	32.54	44.06	55.85	67.63	79.08	90.08
000231	100.54	110.43	119.82	128.73	137.26	145.45	153.32	160.94
000232	168.34	175.55	182.67					
000233	1.205	1.210	1.314	1.417	1.519	1.620	1.722	1.823
000234	1.924	2.026	2.128	2.230	2.333	2.436	2.541	2.647
000235	2.756	2.866	2.978	3.094	3.214	3.339	3.469	3.605
000236	3.747	3.897	4.052	4.210	4.368	4.522	4.668	4.806

103

000237	4.933	5.052	5.161	5.264	5.449	5.534	5.615	
000238	5.692	5.765	5.836					
000239	27.1745	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000	39.6000
000240	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000	54.0000
000241	55.8000	57.6000	59.4000	61.2000	63.0000	64.8000	66.6000	68.4000
000242	70.2000	72.0000	73.8000	75.6000	77.4000	79.2000	81.0000	82.8000
000243	84.6000	86.4000	88.2000	90.0000	91.8000	93.6000	95.4000	97.2000
000244	99.0000	100.8000						
000245	0.20232	0.20399	0.20589	0.20788	0.21003	0.21233	0.21479	0.21742
000246	0.22020	0.22322	0.22640	0.22989	0.23363	0.23776	0.24221	0.24706
000247	0.25238	0.25834	0.26494	0.27233	0.28067	0.29013	0.30094	0.31325
000248	0.32740	0.34369	0.36213	0.38287	0.40575	0.43047	0.45653	0.48355
000249	0.51097	0.53846	0.56580	0.59290	0.61952	0.64574	0.67157	0.69692
000250	0.72179	0.74635						
000251	-109.96	-107.36	-104.33	-101.15	-97.81	-94.29	-90.60	-86.74
000252	-82.70	-78.46	-74.05	-69.44	-64.60	-59.54	-54.25	-48.73
000253	-42.91	-36.81	-30.39	-23.63	-16.46	-8.89	-0.85	7.67
000254	16.69	26.21	36.19	46.51	57.07	67.69	78.23	88.55
000255	98.53	108.17	117.43	126.34	134.92	143.19	151.21	158.97
000256	166.52	173.99						
000257	1.207	1.299	1.401	1.503	1.603	1.703	1.803	1.904
000258	2.003	2.103	2.203	2.304	2.405	2.507	2.610	2.714
000259	2.821	2.927	3.038	3.150	3.265	3.384	3.506	3.632
000260	3.763	3.897	4.033	4.172	4.309	4.445	4.577	4.704
000261	4.822	4.935	5.041	5.141	5.236	5.325	5.410	5.490
000262	5.567	5.642						
000263	27.4500	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000	39.6000
000264	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000	54.0000
000265	55.8000	57.6000	59.4000	61.2000	63.0000	64.8000	66.6000	68.4000
000266	70.2000	72.0000	73.8000	75.6000	77.4000	79.2000	81.0000	82.8000
000267	84.6000	86.4000	88.2000	90.0000	91.8000	93.6000	95.4000	97.2000
000268	99.0000	100.8000						
000269	0.20168	0.20303	0.20486	0.20677	0.20891	0.21106	0.21344	0.21591
000270	0.21861	0.22139	0.22449	0.22775	0.23124	0.23506	0.23919	0.24364
000271	0.24849	0.25381	0.25969	0.26613	0.27336	0.28131	0.29021	0.30022
000272	0.31151	0.32406	0.33821	0.35386	0.37103	0.38978	0.40981	0.43102
000273	0.45304	0.47561	0.49849	0.52154	0.54450	0.56731	0.58996	0.61237
000274	0.63454	0.65639						
000275	-107.13	-104.99	-101.99	-98.83	-95.52	-92.03	-88.40	-84.56
000276	-80.59	-76.43	-72.08	-67.56	-62.83	-57.90	-52.74	-47.36
000277	-41.76	-35.89	-29.75	-23.33	-16.59	-9.51	-2.06	5.73
000278	13.92	22.50	31.43	40.71	50.22	59.93	69.72	79.51
000279	89.17	98.68	107.94	116.96	125.70	134.19	142.44	150.46
000280	158.27	165.99						
000281	1.209	1.286	1.387	1.487	1.587	1.686	1.785	1.884
000282	1.982	2.080	2.179	2.277	2.376	2.476	2.577	2.677
000283	2.780	2.884	2.988	3.094	3.204	3.315	3.427	3.544
000284	3.661	3.782	3.905	4.028	4.153	4.277	4.399	4.519
000285	4.635	4.746	4.852	4.954	5.050	5.141	5.229	5.311
000286	5.391	5.469						
000287	27.7235	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000	39.6000
000288	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000	54.0000
000289	55.8000	57.6000	59.4000	61.2000	63.0000	64.8000	66.6000	68.4000
000290	70.2000	72.0000	73.8000	75.6000	77.4000	79.2000	81.0000	82.8000
000291	84.6000	86.4000	88.2000	90.0000	91.8000	93.6000	95.4000	97.2000
000292	99.0000	100.8000						
000293	0.20105	0.20208	0.20391	0.20574	0.20772	0.20987	0.21217	0.21456
000294	0.21710	0.21980	0.22266	0.22576	0.22910	0.23267	0.23649	0.24062
000295	0.24507	0.24992	0.25524	0.26096	0.26732	0.27424	0.28186	0.29037
000296	0.29967	0.31000	0.32136	0.33392	0.34758	0.36236	0.37834	0.39526

104

000297	0.41298	0.43150	0.45057	0.46996	0.48950	0.50938	0.52909	0.54879
000298	0.56834	0.58781						
000299	-104.33	-102.63	-99.64	-96.50	-93.22	-89.79	-86.18	-82.41
000300	-78.46	-74.37	-70.10	-65.64	-60.99	-56.17	-51.14	-45.89
000301	-40.45	-34.78	-28.87	-22.71	-16.27	-9.55	-2.55	4.75
000302	12.37	20.28	28.51	37.00	45.74	54.70	63.79	72.98
000303	82.17	91.30	100.34	109.24	117.96	126.49	134.83	142.96
000304	150.91	158.80						
000305	1.213	1.272	1.373	1.472	1.571	1.669	1.767	1.865
000306	1.962	2.059	2.155	2.252	2.349	2.448	2.546	2.644
000307	2.744	2.843	2.944	3.047	3.150	3.256	3.362	3.470
000308	3.580	3.692	3.804	3.918	4.033	4.147	4.260	4.373
000309	4.482	4.590	4.693	4.792	4.888	4.981	5.069	5.154
000310	5.234	5.314						
000311	28.2617	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000	39.6000
000312	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000	54.0000
000313	55.8000	57.6000	59.4000	61.2000	63.0000	64.8000	66.6000	68.4000
000314	70.2000	72.0000	73.8000	75.6000	77.4000	79.2000	81.0000	82.8000
000315	84.6000	86.4000	88.2000	90.0000	91.8000	93.6000	95.4000	97.2000
000316	99.0000	100.8000						
000317	0.19985	0.20033	0.20200	0.20383	0.20566	0.20764	0.20971	0.21193
000318	0.21432	0.21678	0.21940	0.22218	0.22520	0.22838	0.23172	0.23538
000319	0.23919	0.24332	0.24777	0.25262	0.25771	0.26335	0.26931	0.27582
000320	0.28290	0.29053	0.29879	0.30769	0.31731	0.32764	0.33860	0.35029
000321	0.36268	0.37564	0.38914	0.40313	0.41759	0.43230	0.44724	0.46241
000322	0.47767	0.49309						
000323	-98.72	-97.87	-94.95	-91.88	-88.63	-85.24	-81.70	-78.03
000324	-74.17	-70.19	-66.01	-61.70	-57.20	-52.55	-47.71	-42.69
000325	-37.51	-32.11	-26.55	-20.77	-14.71	-8.59	-2.17	4.45
000326	11.30	18.38	25.70	33.20	40.90	48.79	56.83	65.00
000327	73.28	81.60	89.96	98.32	106.63	114.91	123.08	131.14
000328	139.10	147.05						
000329	1.218	1.247	1.346	1.444	1.541	1.637	1.733	1.829
000330	1.924	2.019	2.112	2.207	2.301	2.395	2.489	2.584
000331	2.679	2.773	2.868	2.964	3.060	3.157	3.256	3.354
000332	3.452	3.552	3.653	3.752	3.853	3.954	4.054	4.155
000333	4.253	4.351	4.446	4.540	4.633	4.721	4.808	4.891
000334	4.973	5.052						
000335	28.7910	28.8000	30.6000	32.4000	34.2000	36.0000	37.8000	39.6000
000336	41.4000	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000	54.0000
000337	55.8000	57.6000	59.4000	61.2000	63.0000	64.8000	66.6000	68.4000
000338	70.2000	72.0000	73.8000	75.6000	77.4000	79.2000	81.0000	82.8000
000339	84.6000	86.4000	88.2000	90.0000	91.8000	93.6000	95.4000	97.2000
000340	99.0000	100.8000						
000341	0.19874	0.19874	0.20033	0.20200	0.20375	0.20558	0.20756	0.20963
000342	0.21177	0.21408	0.21646	0.21909	0.22179	0.22465	0.22767	0.23085
000343	0.23434	0.23792	0.24181	0.24595	0.25032	0.25500	0.26001	0.26534
000344	0.27106	0.27718	0.28369	0.29069	0.29808	0.30594	0.31429	0.32311
000345	0.33241	0.34218	0.35235	0.36292	0.37389	0.38517	0.39669	0.40853
000346	0.42061	0.43277						
000347	-93.13	-93.11	-90.26	-87.21	-84.03	-80.70	-77.22	-73.60
000348	-69.82	-65.92	-61.85	-57.64	-53.27	-48.75	-44.06	-39.24
000349	-34.23	-29.07	-23.73	-18.23	-12.58	-6.71	-0.70	5.50
000350	11.87	18.42	25.14	32.03	39.09	46.30	53.63	61.10
000351	68.69	76.35	84.09	91.88	99.70	107.53	115.34	123.12
000352	130.86	138.67						
000353	1.224	1.224	1.321	1.417	1.513	1.607	1.702	1.796
000354	1.888	1.981	2.073	2.166	2.257	2.348	2.439	2.530
000355	2.622	2.713	2.804	2.894	2.987	3.078	3.169	3.262
000356	3.353	3.445	3.538	3.630	3.722	3.814	3.906	3.997

105

000357	4.087	4.178	4.266	4.354	4.442	4.524	4.606	4.687
000358	4.766	4.845						
000359	29.3093	30.6000	32.4000	34.2000	36.0000	37.8000	39.6000	41.4000
000360	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000	54.0000	55.8000
000361	57.6000	59.4000	61.2000	63.0000	64.8000	66.6000	68.4000	70.2000
000362	72.0000	73.8000	75.6000	77.4000	79.2000	81.0000	82.8000	84.6000
000363	86.4000	88.2000	90.0000	91.8000	93.6000	95.4000	97.2000	99.0000
000364	100.8000							
000365	0.19763	0.19866	0.20025	0.20192	0.20367	0.20550	0.20748	0.20947
000366	0.21162	0.21384	0.21622	0.21869	0.22131	0.22409	0.22703	0.23013
000367	0.23339	0.23681	0.24046	0.24428	0.24833	0.25262	0.25723	0.26208
000368	0.26716	0.27257	0.27837	0.28441	0.29076	0.29752	0.30459	0.31198
000369	0.31969	0.32780	0.33614	0.34488	0.35386	0.36308	0.37254	0.38223
000370	0.39216							
000371	-87.59	-85.54	-82.56	-79.42	-76.14	-72.72	-69.16	-65.45
000372	-61.61	-57.62	-53.51	-49.24	-44.83	-40.09	-35.57	-30.73
000373	-25.74	-20.60	-15.31	-9.87	-4.28	1.45	7.33	13.37
000374	19.55	25.89	32.35	38.96	45.68	52.55	59.52	66.60
000375	73.77	81.02	88.34	95.72	103.12	110.56	118.00	125.45
000376	133.00							
000377	1.228	1.297	1.392	1.487	1.579	1.673	1.765	1.856
000378	1.946	2.038	2.126	2.216	2.305	2.394	2.483	2.571
000379	2.658	2.747	2.835	2.923	3.009	3.097	3.185	3.271
000380	3.359	3.445	3.532	3.618	3.704	3.790	3.875	3.959
000381	4.044	4.127	4.208	4.290	4.369	4.449	4.526	4.602
000382	4.678							
000383	29.8187	30.6000	32.4000	34.2000	36.0000	37.8000	39.6000	41.4000
000384	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000	54.0000	55.8000
000385	57.6000	59.4000	61.2000	63.0000	64.8000	66.6000	68.4000	70.2000
000386	72.0000	73.8000	75.6000	77.4000	79.2000	81.0000	82.8000	84.6000
000387	86.4000	88.2000	90.0000	91.8000	93.6000	95.4000	97.2000	99.0000
000388	100.8000							
000389	0.19660	0.19715	0.19866	0.20025	0.20192	0.20367	0.20542	0.20732
000390	0.20939	0.21146	0.21368	0.21599	0.21837	0.22091	0.22362	0.22640
000391	0.22934	0.23252	0.23577	0.23919	0.24277	0.24658	0.25055	0.25477
000392	0.25922	0.26390	0.26875	0.27392	0.27924	0.28488	0.29084	0.29696
000393	0.30340	0.31008	0.31699	0.32414	0.33153	0.33916	0.34695	0.35497
000394	0.36316							
000395	-82.09	-80.85	-77.91	-74.81	-71.57	-68.20	-64.68	-61.04
000396	-57.26	-53.36	-49.31	-45.15	-40.82	-36.38	-31.80	-27.06
000397	-22.22	-17.23	-12.11	-6.84	-1.47	4.05	9.70	15.48
000398	21.41	27.42	33.59	39.86	46.26	52.76	59.37	66.07
000399	72.85	79.74	86.67	93.69	100.75	107.85	114.97	122.14
000400	129.41							
000401	1.234	1.274	1.368	1.462	1.553	1.645	1.735	1.825
000402	1.914	2.003	2.092	2.180	2.266	2.353	2.439	2.526
000403	2.611	2.696	2.782	2.866	2.950	3.034	3.118	3.201
000404	3.284	3.367	3.450	3.532	3.613	3.694	3.776	3.855
000405	3.935	4.014	4.092	4.169	4.245	4.320	4.394	4.468
000406	4.540							
000407	30.3191	30.6000	32.4000	34.2000	36.0000	37.8000	39.6000	41.4000
000408	43.2000	45.0000	46.8000	48.6000	50.4000	52.2000	54.0000	55.8000
000409	57.6000	59.4000	61.2000	63.0000	64.8000	66.6000	68.4000	70.2000
000410	72.0000	73.8000	75.6000	77.4000	79.2000	81.0000	82.8000	84.6000
000411	86.4000	88.2000	90.0000	91.8000	93.6000	95.4000	97.2000	99.0000
000412	100.8000							
000413	0.19556	0.19580	0.19715	0.19866	0.20025	0.20192	0.20359	0.20542
000414	0.20732	0.20923	0.21130	0.21344	0.21575	0.21805	0.22060	0.22314
000415	0.22584	0.22870	0.23164	0.23474	0.23800	0.24142	0.24499	0.24873
000416	0.25262	0.25675	0.26104	0.26549	0.27018	0.27503	0.28004	0.28536

000417	0.29084	0.29649	0.30237	0.30841	0.3146	0.32112	0.32780	0.33455
000418	0.34146							
000419	-76.61	-76.16	-73.26	-70.21	-67.01	-63.68	-60.20	-56.62
000420	-52.91	-49.05	-45.08	-40.97	-36.74	-32.37	-27.89	-23.29
000421	-18.55	-13.69	-8.70	-3.58	1.64	6.99	12.45	18.04
000422	23.73	29.53	35.44	41.48	47.60	53.83	60.14	66.56
000423	73.06	79.63	86.29	92.99	99.77	106.59	113.46	120.35
000424	127.39							
000425	1.239	1.253	1.346	1.437	1.528	1.618	1.708	1.797
000426	1.885	1.972	2.059	2.144	2.231	2.315	2.400	2.484
000427	2.567	2.650	2.733	2.815	2.897	2.978	3.060	3.141
000428	3.220	3.299	3.379	3.458	3.536	3.613	3.692	3.768
000429	3.843	3.919	3.994	4.067	4.141	4.213	4.284	4.354
000430	4.425							
000431	31.2983	32.4000	34.2000	36.0000	37.8000	39.6000	41.4000	43.2000
000432	45.0000	46.8000	48.6000	50.4000	52.2000	54.0000	55.8000	57.6000
000433	59.4000	61.2000	63.0000	64.8000	66.6000	68.4000	70.2000	72.0000
000434	73.8000	75.6000	77.4000	79.2000	81.0000	82.8000	84.6000	86.4000
000435	88.2000	90.0000	91.8000	93.6000	95.4000	97.2000	99.0000	100.8000
000436	0.19366	0.19366	0.19580	0.19723	0.19866	0.20025	0.20184	0.20359
000437	0.20534	0.20717	0.20907	0.21106	0.21313	0.21527	0.21750	0.21988
000438	0.22226	0.22481	0.22743	0.23021	0.23299	0.23601	0.23903	0.24221
000439	0.24555	0.24897	0.25254	0.25628	0.26009	0.26406	0.26820	0.27241
000440	0.27678	0.28131	0.28600	0.29076	0.29569	0.30070	0.30586	0.31111
000441	-65.71	-63.96	-60.97	-57.86	-54.62	-51.22	-47.73	-44.10
000442	-40.37	-36.51	-32.52	-28.43	-24.22	-19.89	-15.46	-10.89
000443	-6.22	-1.45	3.41	8.40	13.50	18.68	23.97	29.34
000444	34.82	40.39	46.04	51.78	57.60	63.53	69.52	75.58
000445	81.72	87.93	94.20	100.54	106.91	113.35	119.84	126.47
000446	1.248	1.304	1.393	1.482	1.571	1.657	1.744	1.830
000447	1.914	1.998	2.083	2.164	2.247	2.329	2.410	2.490
000448	2.570	2.649	2.727	2.805	2.882	2.959	3.036	3.111
000449	3.187	3.262	3.335	3.408	3.481	3.554	3.625	3.696
000450	3.766	3.836	3.905	3.974	4.041	4.108	4.174	4.240
000451	32.2487	32.4000	34.2000	36.0000	37.8000	39.6000	41.4000	43.2000
000452	45.0000	46.8000	48.6000	50.4000	52.2000	54.0000	55.8000	57.6000
000453	59.4000	61.2000	63.0000	64.8000	66.6000	68.4000	70.2000	72.0000
000454	73.8000	75.6000	77.4000	79.2000	81.0000	82.8000	84.6000	86.4000
000455	88.2000	90.0000	91.8000	93.6000	95.4000	97.2000	99.0000	100.8000
000456	0.19183	0.19191	0.19318	0.19445	0.19588	0.19731	0.19874	0.20025
000457	0.20184	0.20351	0.20526	0.20701	0.20891	0.21082	0.21281	0.21487
000458	0.21702	0.21916	0.22147	0.22385	0.22632	0.22886	0.23148	0.23418
000459	0.23697	0.23991	0.24285	0.24595	0.24912	0.25246	0.25580	0.25930
000460	0.26287	0.26653	0.27026	0.27416	0.27813	0.28218	0.28631	0.29061
000461	-54.94	-54.70	-51.78	-48.73	-45.55	-42.22	-38.81	-35.27
000462	-31.60	-27.85	-23.97	-19.98	-15.88	-11.68	-7.37	-2.96
000463	1.55	6.16	10.87	15.67	20.58	25.57	30.64	35.78
000464	41.03	46.34	51.76	57.22	62.78	68.42	74.11	79.87
000465	85.69	91.60	97.55	103.59	109.64	115.78	121.95	128.28
000466	1.258	1.265	1.353	1.440	1.527	1.612	1.696	1.780
000467	1.863	1.945	2.027	2.107	2.187	2.266	2.344	2.423
000468	2.500	2.576	2.651	2.727	2.802	2.875	2.949	3.021
000469	3.093	3.164	3.236	3.305	3.374	3.443	3.512	3.579
000470	3.645	3.712	3.777	3.842	3.906	3.970	4.033	4.097
000471	33.1758	34.2000	36.0000	37.8000	39.6000	41.4000	43.2000	45.0000
000472	46.8000	48.6000	50.4000	52.2000	54.0000	55.8000	57.6000	59.4000
000473	61.2000	63.0000	64.8000	66.6000	68.4000	70.2000	72.0000	73.8000
000474	75.6000	77.4000	79.2000	81.0000	82.8000	84.6000	86.4000	88.2000
000475	90.0000	91.8000	93.6000	95.4000	97.2000	99.0000	100.8000	
000476	0.19016	0.19080	0.19199	0.19326	0.19461	0.19596	0.19739	0.19882

201

000477	0.20033	0.20192	0.20351	0.20518	0.20693	0.20875	0.21058	0.21249
000478	0.21448	0.21646	0.21861	0.22075	0.22298	0.22528	0.22767	0.23013
000479	0.23259	0.23522	0.23784	0.24062	0.24340	0.24626	0.24920	0.25222
000480	0.25532	0.25850	0.26176	0.26510	0.26851	0.27193	0.27551	
000481	-44.27	-42.61	-39.62	-36.49	-33.25	-29.88	-26.40	-22.84
000482	-19.15	-15.35	-11.45	-7.46	-3.34	0.85	5.14	9.53
000483	14.01	18.59	23.26	28.02	32.84	37.77	42.76	47.81
000484	52.95	58.16	63.42	68.78	74.20	79.68	85.22	90.83
000485	96.50	102.22	108.00	113.84	119.73	125.66	131.76	
000486	1.266	1.316	1.401	1.485	1.570	1.652	1.735	1.816
000487	1.897	1.976	2.054	2.132	2.209	2.286	2.362	2.437
000488	2.512	2.585	2.658	2.731	2.803	2.873	2.944	3.013
000489	3.081	3.150	3.218	3.284	3.350	3.416	3.481	3.545
000490	3.609	3.672	3.734	3.796	3.856	3.917	3.978	
000491	34.0793	34.2000	36.0000	37.8000	39.6000	41.4000	43.2000	45.0000
000492	46.8000	48.6000	50.4000	52.2000	54.0000	55.8000	57.6000	59.4000
000493	61.2000	63.0000	64.8000	66.6000	68.4000	70.2000	72.0000	73.8000
000494	75.6000	77.4000	79.2000	81.0000	82.8000	84.6000	86.4000	88.2000
000495	90.0000	91.8000	93.6000	95.4000	97.2000	99.0000	100.8000	
000496	0.18857	0.18865	0.18976	0.19095	0.19215	0.19342	0.19469	0.19604
000497	0.19747	0.19890	0.20041	0.20192	0.20351	0.20518	0.20685	0.20860
000498	0.21034	0.21217	0.21408	0.21599	0.21805	0.22012	0.22218	0.22433
000499	0.22656	0.22886	0.23124	0.23363	0.23609	0.23855	0.24118	0.24380
000500	0.24650	0.24920	0.25206	0.25493	0.25787	0.26081	0.26383	
000501	-33.69	-33.48	-30.54	-27.47	-24.27	-20.96	-17.55	-14.03
000502	-10.40	-6.69	-2.87	1.04	5.05	9.17	13.37	17.65
000503	22.05	26.51	31.07	35.70	40.41	45.19	50.05	54.98
000504	59.97	65.02	70.14	75.35	80.59	85.90	91.28	96.72
000505	102.20	107.74	113.35	118.98	124.70	130.44	136.34	
000506	1.276	1.280	1.365	1.449	1.530	1.612	1.693	1.773
000507	1.852	1.930	2.007	2.084	2.160	2.234	2.308	2.381
000508	2.455	2.526	2.597	2.668	2.738	2.807	2.875	2.943
000509	3.009	3.076	3.141	3.206	3.270	3.334	3.397	3.458
000510	3.520	3.581	3.642	3.701	3.760	3.820	3.879	
000511	34.9613	36.0000	37.8000	39.6000	41.4000	43.2000	45.0000	46.8000
000512	48.6000	50.4000	52.2000	54.0000	55.8000	57.6000	59.4000	61.2000
000513	63.0000	64.8000	66.6000	68.4000	70.2000	72.0000	73.8000	75.6000
000514	77.4000	79.2000	81.0000	82.8000	84.6000	86.4000	88.2000	90.0000
000515	91.8000	93.6000	95.4000	97.2000	99.0000	100.8000		
000516	0.18706	0.18770	0.18881	0.18992	0.19111	0.19231	0.19358	0.19485
000517	0.19620	0.19755	0.19898	0.20049	0.19405	0.20351	0.20510	0.20669
000518	0.20844	0.21011	0.21193	0.21368	0.21559	0.21750	0.21940	0.22147
000519	0.22346	0.22560	0.22775	0.22989	0.23212	0.23442	0.23681	0.23919
000520	0.24157	0.24404	0.24658	0.24920	0.25183	0.25445		
000521	-23.18	-21.49	-18.47	-15.31	-12.05	-8.70	-5.22	-1.66
000522	1.98	5.73	9.59	13.52	17.55	21.69	25.89	30.17
000523	34.57	39.03	43.55	48.15	52.85	57.58	62.40	67.28
000524	72.21	77.20	82.28	87.40	92.58	97.81	103.09	108.45
000525	113.84	119.30	124.81	130.35	135.94	141.70		
000526	1.284	1.331	1.413	1.495	1.575	1.655	1.733	1.811
000527	1.887	1.963	2.039	2.112	2.186	2.259	2.330	2.401
000528	2.472	2.542	2.611	2.680	2.747	2.814	2.880	2.945
000529	3.009	3.073	3.136	3.200	3.262	3.322	3.384	3.443
000530	3.502	3.561	3.619	3.677	3.734	3.792		
000531	-8.0377310E-07	1.2281445E-06	-2.1050322E-06	-3.8373024E-06	-8.7732374E-06			
000532	-1.5259414E-05	-2.6335328E-05	-4.1334596E-05	-6.5248416E-05	-9.56112215E-05			
000533	-1.3180607E-04	-1.7026696E-04	-2.1873437E-04	-2.5922335E-04	-3.1173105E-04			
000534	-3.6397233E-04	-4.2257714E-04	-4.5541749E-04	-5.0527305E-04	-5.48521585E-04			
000535	-5.8049584E-04	-6.1718419E-04	-6.4380987E-04	-6.5827104E-04	-6.5781804E-04			
000536	-6.4924148E-04	-6.2883272E-04	-5.9352177E-04	-5.5021366E-04	-4.9570493E-04			

108

000537	-4.3643903E-04	-3.7869989E-04	-3.2988888E-04	.9135311E-04	-2.7009731E-04
000538	-2.7696572E-04	-2.9812312E-04	-3.5004592E-04	+2.455082E-04	-5.2401202E-04
000539	-6.4125592E-04	-7.8212495E-04	-9.3448052E-04	-1.0934784E-03	-1.2559322E-03
000540	-1.3698538E-03	-1.5478358E-03	-1.7219023E-03	-1.8920438E-03	-2.0561721E-03
000541	-2.2143473E-03	-2.4177387E-03	-2.6272401E-03	-2.8407149E-03	-2.9235301E-03
000542	-3.2097408E-03	-3.4133869E-03	-3.4292715E-03	-4.0583221E-03	-4.0351868E-03
000543	-5.2023678E-03	-5.5757572E-03	-6.2069722E-03	-6.8678927E-03	-7.1803709E-03
000544	-7.6073285E-03	-7.9515444E-03	-9.1273819E-03	-9.5657506E-03	-1.0150509E-02
000545	-1.1959132E-02	-1.3886189E-02	-1.5505519E-02	-1.7400006E-02	-2.0124586E-02
000546	-2.2408441E-02	-2.3006439E-02	-2.3612257E-02	-2.1131850E-02	-1.5787078E-02
000547	-7.2297747E-03	-1.1157932E-02	2.0572108E-04	9.1201507E-03	-3.6886842E-02
000548	-2.5967306E-01	2.0399673E-02	4.1266163E-02	6.8570651E-02	1.4766631E-01
000549	4.1671141E-02	8.3815085E-02	1.2820967E-01	1.7331713E-01	2.2031547E-01
000550	2.6879575E-01	3.195518E-01	3.7255940E-01	4.2889084E-01	4.8814042E-01
000551	5.5015630E-01	6.1401927E-01	6.8175290E-01	7.4882307E-01	8.2030192E-01
000552	8.9316323E-01	9.6809537E-01	1.0395381E+00	1.1158471E+00	1.1918611E+00
000553	1.2680118E+00	1.3436317E+00	1.4195863E+00	1.4938576E+00	1.5657673E+00
000554	1.6369293E+00	1.7064442E+00	1.7737101E+00	1.8403582E+00	1.9056878E+00
000555	1.9713662E+00	2.0390411E+00	2.1107021E+00	2.1868961E+00	2.2692860E+00
000556	2.3605869E+00	2.4577571E+00	2.5647236E+00	2.6795942E+00	2.8029003E+00
000557	2.9331360E+00	3.0713863E+00	3.2149294E+00	3.3623746E+00	3.5129883E+00
000558	3.6532274E+00	3.8122308E+00	3.9723517E+00	4.1335542E+00	4.2953206E+00
000559	4.4572955E+00	4.6326102E+00	4.8109381E+00	4.9917539E+00	5.1482192E+00
000560	5.3505627E+00	5.5385032E+00	5.6917803E+00	5.9679756E+00	6.1196071E+00
000561	6.4955823E+00	6.7236159E+00	7.0008332E+00	7.2845818E+00	7.5091781E+00
000562	7.7573489E+00	7.9939722E+00	8.3571042E+00	8.6083924E+00	9.0096826E+00
000563	9.3389942E+00	9.8044979E+00	1.0229200E+01	1.0686035E+01	1.1241795E+01
000564	1.1740489E+01	1.2016333E+01	1.2275667E+01	1.2205924E+01	1.1833711E+01
000565	1.1143704E+01	1.1728386E+01	1.0774412E+01	1.0186019E+01	1.4999411E+01
000566	3.7406308E+01	1.0508182E+01	9.6191112E+00	8.3929369E+00	4.3831287E+00
000567	-5.7318471E-02	1.8093034E-01	-4.9784230E-01	-8.8737394E-01	-1.4439885E+00
000568	-2.1308185E+00	-3.0135132E+00	-4.0968010E+00	-5.4553331E+00	-7.0653434E+00
000569	-8.9079311E+00	-1.0891583E+01	-1.3194912E+01	-1.5409693E+01	-1.7982500E+01
000570	-2.0641264E+01	-2.3494803E+01	-2.5827529E+01	-2.8601520E+01	-3.1270310E+01
000571	-3.3868301E+01	-3.6312903E+01	-3.8676869E+01	-4.0770123E+01	-4.2521120E+01
000572	-4.4057432E+01	-4.5291856E+01	-4.6171278E+01	-4.6823811E+01	-4.7185354E+01
000573	-4.7400820E+01	-4.7608307E+01	-4.7991765E+01	-4.8607001E+01	-4.9585045E+01
000574	-5.1154888E+01	-5.3068125E+01	-5.5648849E+01	-5.8727770E+01	-6.2332962E+01
000575	-6.6339776E+01	-7.0798392E+01	-7.5474072E+01	-8.0216248E+01	-8.4945172E+01
000576	-8.8378554E+01	-9.3209590E+01	-9.775742E+01	-1.0205513E+02	-1.0598185E+02
000577	-1.0947043E+02	-1.1370972E+02	-1.1770864E+02	-1.2139729E+02	-1.2287832E+02
000578	-1.2737635E+02	-1.3032203E+02	-1.3031157E+02	-1.3843027E+02	-1.3730741E+02
000579	-1.5065102E+02	-1.5333181E+02	-1.5864047E+02	-1.6366492E+02	-1.6426362E+02
000580	-1.6578472E+02	-1.6593847E+02	-1.7221788E+02	-1.7159915E+02	-1.7825786E+02
000581	-1.8042763E+02	-1.8864278E+02	-1.9410328E+02	-2.0004923E+02	-2.0932852E+02
000582	-2.1504047E+02	-2.0928329E+02	-2.0118944E+02	-1.7942589E+02	-1.4498536E+02
000583	-9.8067031E+01	-9.7440413E+01	-3.8944428E+01	2.2018214E+00	-1.5324378E+02
000584	-9.6215597E+02	3.6778774E+01	7.2762252E+01	1.1458652E+02	1.9525322E+02
000585	-3.4852970E-01	-2.3328599E+00	-2.0682478E+00	-3.2165717E+00	-2.6094543E+00
000586	-1.2407244E+00	3.2160865E+00	1.1342612E+01	2.5378825E+01	4.4994254E+01
000587	6.9446852E+01	9.5141850E+01	1.2866170E+02	1.5495204E+02	1.9055501E+02
000588	2.2540166E+02	2.6281975E+02	2.7566446E+02	3.0073723E+02	3.1701581E+02
000589	3.2576079E+02	3.233676E+02	3.1249379E+02	2.8602308E+02	2.4109665E+02
000590	1.8228715E+02	1.0647765E+02	1.1968543E+01	-9.6472164E+01	-2.2083220E+02
000591	-3.5521484E+02	4.9429203E+02	-6.3011102E+02	-7.5967443E+02	-8.7793619E+02
000592	-9.7611348E+02	-1.0620580E+03	-1.1236298E+03	-1.1665448E+03	-1.1896026E+03
000593	-1.1965205E+03	-1.1861179E+03	-1.1663516E+03	-1.1427383E+03	-1.1180923E+03
000594	-1.1428658E+03	-1.1103218E+03	-1.0857529E+03	-1.0696396E+03	-1.0641185E+03
000595	-1.0733223E+03	-1.0504141E+03	-1.0340018E+03	-1.0264770E+03	-1.0823485E+03
000596	-1.0365624E+03	-1.0349302E+03	-1.1172453E+03	-9.5022563E+02	-1.0518802E+03

109

000597	-7.3317710E+02	-7.1729678E+02	-6.1916306E+02	5.2271128E+02	-5.3825987E+02
000598	-5.1531466E+02	-5.1639302E+02	-3.6579871E+02	5.6543501E+02	-1.8416297E+02
000599	-8.7846858E+01	1.5419294E+02	3.5588009E+02	5.7942490E+02	8.7722455E+02
000600	1.1212214E+03	1.1541824E+03	1.1518611E+03	9.4203092E+02	5.4030442E+02
000601	-3.5545003E+01	1.5041468E+02	-5.6987252E+02	-8.9772310E+02	1.9715175E+03
000602	1.5643871E+04	0.0E+00	0.0E+00	0.0E+00	0.0E+00
000603	1.0761355E+00	9.0125519E+00	-1.6858820E+01	-3.7102804E+01	-8.6642049E+01
000604	-1.5703564E+02	-2.7513041E+02	-4.5130837E+02	-7.0776183E+02	-1.0446450E+03
000605	-1.4487078E+03	-1.8692702E+03	-2.3880154E+03	-2.8067078E+03	-3.3410802E+03
000606	-3.8559030E+03	-4.3843916E+03	-4.5542515E+03	-4.8694049E+03	-5.0390446E+03
000607	-5.0769555E+03	-4.9279847E+03	-4.6275005E+03	-4.0775766E+03	-3.2393895E+03
000608	-2.1710548E+03	-8.3495872E+02	7.8810918E+02	2.6316170E+03	4.7142330E+03
000609	6.9491255E+03	9.2604127E+03	1.1524025E+04	1.3685515E+04	1.5672403E+04
000610	1.7362219E+04	1.8840761E+04	1.9943022E+04	2.0737451E+04	2.1205585E+04
000611	2.1388423E+04	2.1278368E+04	2.0977596E+04	2.0559050E+04	2.0065004E+04
000612	2.0212248E+04	1.9492025E+04	1.8829911E+04	1.8237987E+04	1.7749108E+04
000613	1.7442580E+04	1.6669838E+04	1.5978421E+04	1.5412988E+04	1.5529079E+04
000614	1.4476561E+04	1.3941732E+04	1.4340021E+04	1.2070660E+04	1.2720182E+04
000615	9.0641995E+03	8.6428251E+03	7.4271301E+03	6.3105084E+03	6.3673451E+03
000616	6.0708932E+03	6.0532802E+03	4.8294821E+03	4.9320575E+03	3.5624987E+03
000617	2.9059444E+03	1.1351017E+03	-3.1705787E+02	-1.8692257E+03	-3.8552011E+03
000618	-5.4197643E+03	-5.4462613E+03	-5.1573924E+03	-3.6215951E+03	-9.1656659E+02
000619	2.7670921E+03	2.0174573E+03	6.5948069E+03	8.2338889E+03	-9.3307466E+03
000620	-9.3572403E+04	0.0E+00	0.0E+00	0.0E+00	0.0E+00
000621	0.0005	0.0010	0.0015	0.0020	0.0025
000622	0.0055	0.0060	0.0065	0.0070	0.0075
000623	0.0105	0.0110	0.0115	0.0120	0.0125
000624	0.0155	0.0160	0.0165	0.0170	0.0175
000625	0.0205	0.0210	0.0215	0.0220	0.0225
000626	0.0255	0.0260	0.0265	0.0270	0.0275
000627	0.0305	0.0310	0.0315	0.0320	0.0325
000628	0.0355	0.0360	0.0365	0.0370	0.0375
000629	0.0405	0.0410	0.0415	0.0420	0.0425
000630	0.73234603E-02	-0.44074261E-03	0.66207946E-03	-0.29226363E-03	0.0035
000631	0.40084907E-04	0.0E+00	0.0E+00	0.0E+00	0.0040
000632	-0.27176666E+02	0.21129340E+03	0.13364318E+02	-0.19311670E+04	0.0045
000633	0.67461013E+04	0.0E+00	0.0E+00	0.0E+00	0.0050
000634	-0.71967724E-02	0.14495527E-02	0.32403130E-02	-0.44640177E-02	0.0055
000635	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0060
000636	0.17724540E+01	-0.44368880E+02	0.20554680E-01	0.0E+00	0.0065
000637	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0070
000638	0.20006200E+01	-0.50097080E+02	0.10044000E+01	0.17484950E-01	0.0075
000639	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0080
000640	-0.87239000E+03	0.26248000E+02	-0.09787200E+01	0.00271270E+01	0.0085
000641	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0090
000642	0.10111000E+04	-0.29485000E+02	0.25312000E+01	-0.00666590E+01	0.0095
000643	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0100
000644	-0.22172000E+02	0.52157000E+01	-0.02737800E+01	0.58282000E-02	0.0105
000645	0.04826500E+01	-0.29189000E-01	0.0E+00	0.0E+00	0.0110
000646	-0.06839500E+01	0.18552000E+01	-0.00378920E+01	0.40527000E+02	0.0115
000647	0.54573000E+01	-0.32436000E+01	-0.01769100E+01	0.00641000E+01	0.0120

110

* ELI, IST,1,720405, 41892

```

000001      COMPILER (DATA=SHORT)
000002      COMMON /TITLE/ TESTID(12),DAY(2),RUNTMF(2),IPAGE
000003      COMMON /TAPEIN/ CHAN1(100),CHAN2(100),CHAN3(100),CHAN4(100),
000004      1PARID(100),CHANID(200),UNITS(200),DEC(200),NPAR
000005      COMMON /TAPE/ TSTART,TSTOP,INT1,INT2,IAVE,NSETS,INPUT(100,50),
000006      1ATIME(50),TIME,IEND
000007      COMMON /CALC/ INPT(100),GEOM(50),OUT(120)
000008      INTEGER TESTID,DAY,PARID,CHAN1,CHAN2,CHAN3,CHAN4,CHANID,UNITS,DEC,
000009      1TAPEIN,TAPEOT
000010      REAL INPUT,INPT
000011      DIMENSION OUTPUT(120,50)
000012      DATA NSAT,NPAR,MPAR /22,33,95/
000013      CALL INPROP
000014      CALL SATUR(NSAT)
000015      CALL CHINPT(TAPEIN,TAPEOT)
000016      CALL GEOMT
000017      CALL OUTNOM(MPAR)
000018      NSETC=0
000019      IFILE=0
000020      10 READ (5,1000) TSTART,TSTOP,INT1,INT2,IAVE,IFLAG,NRTHR,IEND
000021      1000 FORMAT(F10.0,F10.0,6I5)
000022      GO TO 50
000023      20 CALL TAPE2
000024      GO TO 55
000025      50 CALL TAPE1
000026      55 IF (,NSETS.GE.50) GO TO 60
000027      IF (IEND.EQ.0) GO TO 10
000028      60 DO 540 I=1,NSETS
000029      DO 100 J=1,NPAR
000030      100 INPT(J)=INPUT(J,I)
000031      CALL FLOW(JFLG)
000032      IF (,JFLG.GT.1) GO TO 540
000033      CALL SUCTION (IFLAG,JFLG)
000034      IF (,JFLG.GT.1) GO TO 540
000035      CALL RADTHR (NRTHR)
000036      CALL AXFOR
000037      CALL PERFOR(JFLG)
000038      IF (,JFLG.GT.1) GO TO 540
000039      DO 500 J=1,36
000040      500 OUTPUT(J,I)=OUT(J)
000041      DO 510 J=40,75
000042      K=J-3
000043      510 OUTPUT(K,I)=OUT(J)
000044      DO 520 J=80,83
000045      K=J-7
000046      520 OUTPUT(K,I)=OUT(J)
000047      DO 530 J=85,103
000048      K=J-8
000049      530 OUTPUT(K,I)=OUT(J)
000050      540 CONTINUE
000051      CALL OUTPT (OUTPUT,ATIME,MPAR,NSETS,IFILE,TAPEIN,TAPEOT)
000052      NSETC=0
000053      IF (TIME.LT.TSTOP) GO TO 20
000054      IF (IEND.EQ.0) GO TO 10
000055      END FILE 2
000056      IFILE=0

```

```

000057 IF (IEND.EQ.1) GO TO 10
000058 STOP
000059 END
000060 SUBROUTINE CHINPT(TAPEIN,TAPEOT)
000061 COMPILER (DATA=SHORT)
000062 COMMON /TAPEIN/ CHAN1(100),CHAN2(100),CHAN3(100),CHAN4(100),
000063 1PARID(100),CHANID(200),UNITS(200),DEC(200),NPAR
000064 COMMON /TITLE/ TESTID(12),DAY(2),RUNTME(2),IPAGE
000065 INTEGER CHAN1,CHAN2,CHAN3,CHAN4,PARID,CHANID,UNITS,DEC,END,
000066 1PARCK(100),TAPEIN,TAPEOT
000067 DIMENSION DEF(100,10),ICHAN(4),IDN(4),DEFIN(10)
000068 DATA BLANK /' ' //
000069 DATA PARID /'PATM ','PSD ','TD ','PLFI ','PLFO ','PLRI ','
000070 1,PLRO ','WREF ','DPORF1','DPORF2','PORF ','PTK ','TTK '
000071 2,P1 ','T1 ','P2 ','T2 ','PID ','P708 ','P726 '
000072 3,PDIFI1','PDIFI2','PDIFI3','PDIFI4','PDIFI5','PDIFI6','PDIFI7'
000073 4,PDIFI8','PDIFI9','PDIFO ','N ','P707 ','P725 '
000074 DATA END/'END ' //
000075 LINE=0
000076 IPAGE=1
000077 READ (1) DAY,RUNTME,TESTID,TAPEIN,TAPEOT
000078 READ (1) MWORDS,(CHANID(I),I=1,MWORDS)
000079 READ (1) MWORDS,(UNITS(I),I=1,MWORDS)
000080 READ(1) MWORDS,(DEC(I),I=1,MWORDS)
000081 TAPEIN=TAPEOT
000082 DO 100 I=1,2
000083 DAY(I)=BLANK
000084 100 RUNTME(I)=BLANK
000085 CALL DATE (9,DAY)
000086 CALL TOD (8,RUNTME)
000087 IFLA=0
000088 DO 210 I=1,NPAR
000089 210 PARCK(I)=0
000090 READ (5,20) TAPEOT
000091 240 READ (5,20) IDENT,(DEFIN(J),J=1,10),(ICHAN(I),I=1,4)
000092 20 FORMAT (A6,1X,10A6,1X,4I3)
000093 K=0
000094 250 K=K+1
000095 IF (IDENT.EQ.END) GO TO 270
000096 IF (IPARID(K).EQ.IDENT) GO TO 260
000097 IF (K.GE.NPAR) GO TO 255
000098 GO TO 250
000099 255 WRITE (6,1000) IDENT
000100 1000 FORMAT (/10X,A6,' IS AN UNRECOGNIZABLE PARAMETER IDENTIFICATION')
000101 GO TO 240
000102 260 PARCK(K)=1
000103 CHAN1(K)=ICHAN(1)
000104 CHAN2(K)=ICHAN(2)
000105 CHAN3(K)=ICHAN(3)
000106 CHAN4(K)=ICHAN(4)
000107 N=1
000108 DO 265 I=2,4
000109 IF (ICHAN(I).EQ.0) GO TO 266
000110 265 N=I
000111 266 DO 267 I=1,N
000112 J=ICHAN(I)
000113 267 IDN(I)=CHANID(J)
000114 DO 268 I=1,10
000115 268 DEF(I,K)=DEFIN(I)
000116 IF (LINE.NE.0) GO TO 269

```

```

000117      WRITE (6,1100) IPAGE
000118      1100 FORMAT ('1',52X,'LH2 PUMP TEST',44X,'PAGE ',)
000119      1110 FORMAT (12A6,12X,'DATE ',2A6,'TIME ',2A6)
000120      WRITE (6,1110) TESTID,DAY,RUNTIME
000121      1130 FORMAT ('/ INPUT TAPE = ',A6,5X,'OUTPUT TAPE = ',A6/)
000122      WRITE (6,1130) TAPEIN,TAPEOT
000123      WRITE (6,1120)
000124      1120 FORMAT (1X,'PARAMETER',20X,'DEFINITION',38X,'CHANNELS USED'/)
000125      269 WRITE (6,1010) PARID(K),(DEF(K,L),L=1,10),(ICHAN(I),IDN(I),I=1,N)
000126      1010 FORMAT (1X,A6,2X,10A6,4(2X,I3,1X,A6))
000127      LINE=LINE+1
000128      IF (LINE.LT.50) GO TO 240
000129      LINE=0
000130      IPAGE=IPAGE+1
000131      GO TO 240
000132      270 DO 300 I=1,NPAR
000133      IF (PARCK(I).EQ.1) GO TO 300
000134      WRITE (6,1020) PARID(I)
000135      1020 FORMAT ('//10X,' NO CHANNEL IDENTIFICATION FOR ',A6)
000136      IFLAG=1
000137      300 CONTINUE
000138      IF (IFLAG.NE.0) STOP
000139      RETURN
000140      END
000141      SUBROUTINE OUTNOM(MPAR)
000142      COMMON /TITLE/ TESTID(12),DAY(2),RUNTIME(2),IPAGE
000143      COMMON /NOMEN/ HED(120),DEC(120),UN(120)
000144      DIMENSION DEF(10)
000145      INTEGER HED,DEC,UN,BLANK,TESTID,DAY,RUNTIME
000146      DATA BLANK /' '/
000147      LINE=0
000148      DO 100 I=1,MPAR
000149      100 UN(I)=BLANK
000150      DO 200 I=1,MPAR
000151      READ (5,1000) HED(I),DEF,UN(I),DEC(I)
000152      IF (LINE.GT.0) GO TO 150
000153      IPAGE=IPAGE+1
000154      WRITE (6,2000) IPAGE
000155      WRITE (6,2010) TESTID,DAY,RUNTIME
000156      150 LINE=LINE+1
000157      WRITE (6,1010) HED(I),DEF,UN(I)
000158      IF (LINE.LT.50) GO TO 200
000159      LINE=0
000160      200 CONTINUE
000161      1000 FORMAT (A6,1V,10A6,1X,A6,5X,A1)
000162      1010 FORMAT (1X,A6,1X,10A6,1X,A6)
000163      2000 FORMAT ('1',52X,'LH2 PUMP TEST',44X,'PAGE ',I4)
000164      2010 FORMAT (12A6,12X,'DATE ',2A6,'TIME ',2A6/)
000165      RETURN
000166      END
000167      SUBROUTINE OUTPT (OUTPUT,ATIME,MPAR,NSETS,IFILE,TAPEIN,TAPEOT)
000168      COMMON /TITLE/ TESTID(12),DAY(2),RUNTIME(2),IPAGE
000169      COMMON /NOMEN/ HED(120),DEC(120),UN(120)
000170      INTEGER HED,DEC,UN,TESTID,DAY,RUNTIME,F(22),G(22),V(14),BLANK,
000171      1TAPEIN,TAPEOT
000172      DIMENSION OUTPUT(120,50),ATIME(50),NUM(10)
000173      DATA F(1),F(2),F(4),F(6),F(8),F(10),F(12),F(14),F(16),F(18),F(20),
000174      1F(22) /'(F9.1,'10*'F11.),'/'
000175      DATA V(1),V(3),V(4),V(5),V(6),V(8),V(9),V(10),V(11),V(13),V(14)
000176      1/'(8X,' '(8X,I3', 6H)/3X,' 6HTIME',, '3X',, '(5X,A6',

```

143

```

000177      26H)/4X,1, 6HSEC,3, 'X,1, '(5X,A6, )//
000178      DATA G(22) /1)'/
000179      DATA NUM/1,2,3,4,5,6,7,8,9,10/'
000180      DATA BLANK /'
000181      IF (IFILE.GT.0) GO TO 100
000182      WRITE(2) DAY,RUNTIME,TESTID,TAPEIN,TAPEOT
000183      WRITE (2) MPAR,(HED(I),I=1,MPAR)
000184      WRITE (2) MPAR,(UN(I),I=1,MPAR)
000185      WRITE (2) MPAR,(DEC(I),I=1,MPAR)
000186      100 DO 200 K=1,MPAR,10
000187          IPAGE=IPAGE+1
000188          L=K+9
000189          NCOL=10
000190          IF (L.LE.MPAR) GO TO 150
000191          L=MPAR
000192          NCOL=MPAR-K+1
000193      150 V(2)=NUM(NCOL)
000194          V(7)=NUM(NCOL)
000195          V(12)=NUM(NCOL)
000196          WRITE (6,2000) IPAGE
000197          WRITE (6,2010) TESTID,DAY,RUNTIME
000198          WRITE (6,V) (I,I=K,L),(HED(I),I=K,L),(UN(I),I=K,L)
000199          M=1
000200          DO 180 I=K,L
000201          M=M+2
000202      180 F(M)=DEC(I)
000203          DO 182 I=1,M
000204      182 G(I)=F(I)
000205          IF (M.EQ.21) GO TO 200
000206          M1=M+1
000207          DO 185 I=M1,21
000208      185 G(I)=BLANK
000209          200 WRITE (6,G) (ATIME(M),(OUTPUT(I,M),I=K,L),M=1,NSETS)
000210          DO 300 J=1,NSETS
000211      300 WRITE (2) MPAR,ATIME(J),(OUTPUT(I,J),I=1,MPAR)
000212          DO 400 I=1,MPAR
000213          DO 400 J=1,50
000214      400 OUTPUT(I,J)=0.0
000215          IFILE=1
000216          2000 FORMAT ('1',52X,'LH2 PUMP TEST',44X,'PAGE ',I4)
000217          2010 FORMAT (12A6,12X,'DATE ',2A6,'TIME ',2A6//)
000218          RETURN
000219          END
000220          SUBROUTINE GEOMT
000221          COMMON /CALC/ INPT(100),GEOM(50),OUT(120)
000222          COMMON /TITLE/ TESTID(12),DAY(2),RUNTIME(2),IPAGE
000223          REAL INPT
000224          DATA NUM/30/
000225          EQUIVALENCE (GEOM(1),DSL1),(GEOM(2),DSL2),(GEOM(3),ALBF),
000226      1 (GEOM(4),CLABF),(GEOM(5),ALBR),(GEOM(6),CLABR),
000227      2 (GEOM(7),AI2),(GEOM(8),DI2),(GEOM(9),BET2),
000228      3 (GEOM(10),Z2),(GEOM(11),RPTAD),(GEOM(12),ADFD),
000229      4 (GEOM(13),DDL),(GEOM(14),RHOREF),(GEOM(15),ORFD),
000230      5 (GEOM(16),ORFCOE),(GEOM(17),RFBTA),(GEOM(18),W),
000231      6 (GEOM(19),R706),(GEOM(20),R707),(GEOM(21),R708),
000232      7 (GEOM(22),R724),(GEOM(23),R725),(GEOM(24),R726),
000233      8 (GEOM(25),RLF),(GEOM(26),RLM),(GEOM(27),RLI),
000234      9 (GEOM(28),RIN),(GEOM(29),RLD),(GEOM(30),RLS)
000235          IPAGE=IPAGE+1
000236          WRITE (6,1010) IPAGE

```

000237 1010 FORMAT('1',52X,'LH2 PUMP TEST',44X,'PAGE ',I
 000238 WRITE(6,1020) TESTID,DAY,RUNTIME
 000239 1020 FORMAT(12A6,12X,'DATE ',2A6,'TIME ',2A6)
 000240 READ(5,1000) (GEOM(I),I=1,NUM)
 000241 1000 FORMAT(8F10.0)
 000242 WRITE(6,2000) DSL1
 000243 2000 FORMAT (' DSL1 SUCTION LINE DIAMETER UPSTREAM FLOW COND.,,30X
 000244 1,F6.3,' IN')
 000245 WRITE(6,2010) DSL2
 000246 2010 FORMAT (' DSL2 SUCTION LINE DIAMETER DOWNSTREAM FLOW COND.,,
 000247 128X,F6.3,' IN')
 000248 WRITE(6,2020) ALBF
 000249 2020 FORMAT (' ALBF FRONT LABYRINTH FLOW AREA',46X,F6.3,' SQ-IN')
 000250 WRITE(6,2030) CLABF
 000251 2030 FORMAT (' CLABF FRONT LABYRINTH COEFFICIENT',44X,F6.4)
 000252 WRITE(6,2040) ALBR
 000253 2040 FORMAT (' ALBR REAR LABYRINTH FLOW AREA',47X,F6.3,' SQ-IN')
 000254 WRITE(6,2050) CLABR
 000255 2050 FORMAT (' CLABR REAR LABYRINTH COEFFICIENT',45X,F6.4)
 000256 WRITE(6,2060) AI2
 000257 2060 FORMAT (' AI2 IMPELLER DISCHARGE BLOCKED AREA',40X,F6.2
 000258 1,' SQ-IN')
 000259 WRITE(6,2070) DI2
 000260 2070 FORMAT (' DI2 IMPELLER DISCHARGE DIAMETER',44X,F6.3,' IN')
 000261 WRITE(6,2080) BET2
 000262 2080 FORMAT (' BET2 IMPELLER DISCHARGE BLADE ANGLE',41X,F6.2,
 000263 1,' DEG')
 000264 WRITE(6,2080) Z2
 000265 2090 FORMAT('Z2 NUMBER OF IMPELLER BLADES',50X,I2)
 000266 WRITE(6,3000) RPTAP
 000267
 000268 3000 FORMAT('RPTAP DIFFUSER INLET PRESSURE TAP RADIAL LOCATION',
 000269 127X,F6.3,' IN')
 000270 WRITE(6,3010) ADFD
 000271 3010 FORMAT(' ADFD DIFFUSER DISCHARGE FLOW AREA',42X,F6.2,
 000272 1,' SQ-IN')
 000273 WRITE(6,3020) DDL
 000274 3020 FORMAT(' DDL DISCHARGE LINE DIAMETER',48X,F6.3,' IN')
 000275 WRITE(6,3030) RHOREF
 000276 3030 FORMAT(' RHOREF REFERENCE DENSITY',54X,F6.4,' LB/CU-FT')
 000277 WRITE(6,3040) ORFD
 000278 3040 FORMAT (' ORFD BEARING COOLANT ORIFICE DIAMETER',39X,F6.4,
 000279 1,' IN')
 000280 WRITE(6,3050) ORFCOE
 000281 3050 FORMAT (' ORFCOE BEARING COOLANT ORIFICE COEFFICIENT',36X,
 000282 1F6.4)
 000283 WRITE(6,3060) ORFBTA
 000284 3060 FORMAT (' ORFBTA BEARING COOLANT ORIFICE BETA',43X,F6.4)
 000285 3070 FORMAT (' R707 RADIAL LOCATION OF PRESSURE TAP 707',35X,
 000286 1F6.4,' IN')
 000287 WRITE(6,3070) R707
 000288 3080 FORMAT (' W DIFFUSER VANE INLET WIDTH',45X,F6.4,' IN')
 000289 WRITE(6,3080) W
 000290 3090 FORMAT (' R706 RADIAL LOCATION OF PRESSURE TAP 706',35X,
 000291 1F6.4,' IN')
 000292 WRITE(6,3090) R706
 000293 4000 FORMAT (' R708 RADIAL LOCATION OF PRESSURE TAP 708',35X,
 000294 1F6.4,' IN')
 000295 WRITE(6,4000) R708
 000296 4010 FORMAT (' R724 RADIAL LOCATION OF PRESSURE TAP 724',35X,

115

```

000297      1F6.4,' IN')
000298      WRITE (6,4010) R724
000299      4020 FORMAT (' R725      RADIAL LOCATION OF PRESSURE TAP 725',35X,
000300      1F6.4,' IN')
000301      WRITE (6,4020) R725
000302      4030 FORMAT (' R726      RADIAL LOCATION OF PRESSURE TAP 726',35X,
000303      1F6.4,' IN')
000304      WRITE (6,4030) R726
000305      4040 FORMAT (' RLF      LABYRINTH LAND RADIUS',49X,F6.4,' IN')
000306      WRITE (6,4040) RLF
000307      4050 FORMAT (' RLM      LABYRINTH LAND RADIUS',49X,F6.4,' IN')
000308      WRITE (6,4050) RLM
000309      4060 FORMAT (' RLI      LABYRINTH LAND RADIUS',49X,F6.4,' IN')
000310      WRITE (6,4060) RLI
000311      4070 FORMAT (' RIN      INDUCER RADIUS',56X,F6.4,' IN')
000312      WRITE (6,4070) RIN
000313      4080 FORMAT (' RLD      LABYRINTH LAND RADIUS',49X,F6.4,' IN')
000314      WRITE (6,4080) RLD
000315      4090 FORMAT (' RLS      SHAFT RADIUS',58X,F6.4,' IN')
000316      WRITE (6,4090) RLS
000317      RETURN
000318      END
000319      SUBROUTINE SUCTION (IFLAG,JFLG)
000320      C-----SYMBOLS-----
000321      C A1=FLOW AREA UPSTREAM OF FLOW CONDITIONER---SQ-IN
000322      C A2=FLOW AREA DOWNSTREAM OF FLOW CONDITIONER---SQ-IN
000323      C ALPHA=VAPOR VOLUME/TOTAL VOLUME DOWNSTREAM OF FLOW CONDITIONER
000324      C B=VAPOR VOLUME/LIQUID VOLUME DOWNSTREAM OF FLOW CONDITIONER
000325      C H1=ENTHALPY UPSTREAM OF FLUID CONDITIONER---BTU/LB
000326      C H1T=STAGNATION ENTHALPY UPSTREAM OF FLUID CONDITIONER---BTU/LB
000327      C H2=ENTHALPY DOWNSTREAM OF FLUID CONDITIONER---BTU/LB
000328      C H2T=STAGNATION ENTHALPY DOWNSTREAM OF FLUID CONDITIONER---BTU/LB
000329      C HLIQ2=SATURATION ENTHALPY CORRESPONDING TO S2---BTU/LB
000330      C HTK=ENTHALPY IN TANK---BTU/LB
000331      C NPSHA=NET POSITIVE SUCTION HEAD USING NPSP AND RHOSAT---FT
000332      C NPSHB=NET POSITIVE SUCTION HEAD USING (H2-HLIQ2)---FT
000333      C NPSP=NET POSITIVE SUCTION PRESSURE=P2T-PVAP2---PSI
000334      C P1=PRESSURE UPSTREAM OF FLOW CONDITIONER---PSIA
000335      C P2=PRESSURE DOWNSTREAM OF FLOW CONDITIONER---PSIA
000336      C P2T=STAGNATION PRESSURE DOWNSTREAM OF FLOW CONDITIONER---PSIA
000337      C PTK=TANK PRESSURE ---PSIA
000338      C PVAP1=VAPOR PRESSURE UPSTREAM OF FLOW CONDITIONER---PSIA
000339      C PVAP2=VAPOR PRESSURE CORRESPONDING TO S2---PSIA
000340      C PVAPTK=VAPOR PRESSURE IN TANK---PSIA
000341      C RH01=FLUID DENSITY UPSTREAM OF FLOW CONDITIONER---LB/CU-FT
000342      C RH02=FLUID DENSITY DOWNSTREAM OF FLOW CONDITIONER---LB/CU-FT
000343      C RHOLIQ=LIQUID DENSITY DOWNSTREAM OF FLOW CONDITIONER---LB/CU-IN
000344      C RHOSAT=SATURATION DENSITY CORRESPONDING TO S2---LB/CU-FT
000345      C RHOVAP=VAPOR DENSITY DOWNSTREAM OF FLOW CONDITIONER---LB/CU-IN
000346      C S2=ENTROPY DOWNSTREAM OF FLUID CONDITIONER---BTU/LB-DEG R
000347      C T1=TEMPERATURE UPSTREAM OF FLOW CONDITIONER---DEG R
000348      C T2=MEASURED TEMPERATURE DOWNSTREAM OF FLOW CONDITIONER DEG R
000349      C T2CALC=VAPOR TEMPERATURE CORRESPONDING TO S2---DEG R
000350      C TTK=TANK TEMPERATURE---DEG R
000351      C V1=AVERAGE FLUID VELOCITY UPSTREAM OF FLUID CONDITIONER---FT/SEC
000352      C V2=AVERAGE FLUID VELOCITY DOWNSTREAM OF FLUID CONDITIONER---FT/SEC
000353      C WDOT=SUCTION WEIGHT FLOW RATE---LB/SEC
000354      C X2=QUALITY DOWNSTREAM OF FLUID CONDITIONER
000355      C-----
000356      REAL NPSP,NPSHA,NPSHB

```

146

```

000357 COMMON /SAT/ HSAT(25),PSAT(25),TSAT(25),SS(25),RHOSAT(25),
000358 1EMPT(25),EMPS(25),EMTS(25),EMHS(25),EMRHOS(25)
000359 COMMON /CALC/ INPT(100),GEOM(50),OUT(120)
000360 REAL INPT
000361 EQUIVALENCE (INPT(12),PTK),(INPT(13),TTK),(INPT(14),P1),
000362 1 (INPT(15),T1),(INPT(16),P2),(INPT(17),T2)
000363 EQUIVALENCE (OUT(11),WDOT),(OUT(12),QS),(OUT(13),PVAPTK),
000364 1 (OUT(14),HTK),(OUT(15),RH01),(OUT(16),V1),
000365 2 (OUT(17),H1),(OUT(18),H1T),(OUT(19),PVAP1),
000366 3 (OUT(20),RH02),(OUT(21),V2),(OUT(22),H2),
000367 4 (OUT(23),H2T),(OUT(24),PVAP2),(OUT(25),S2),
000368 5 (OUT(26),X2),(OUT(27),P2T),(OUT(28),NPSP),
000369 6 (OUT(29),NPSHA),(OUT(30),NPSHB),(OUT(31),B),
000370 7 (OUT(32),ALPHA),(OUT(33),T2CALC),(OUT(34),RHOLIQ),
000371 8 (OUT(35),RHOL2),(OUT(36),HLIq2)
000372 EQUIVALENCE (GEOM(1),DSL1),(GEOM(2),DSL2)
000373 A1=3.14159*DSL1**2/4.
000374 A2=3.14159*DSL2**2/4.
000375 N=22
000376 C*** COMPUTE TANK CONDITIONS
000377 CALL PTENTH(PTK,TTK,1,HTK,JFLG)
000378 IF (JFLG.GT.1) RETURN
000379 CALL SPLNT(N,TSAT,PSAT,EMPT,TTK,PVAPTK)
000380 C*** CHECK FOR VAPOR UPSTREAM OF FLOW CONDITIONER
000381 IF (P1.GT.PVAPTK) GO TO 90
000382 WRITE (6,1020)
000383 1020 FORMAT (' POSSIBLE VAPOR UPSTREAM OF FLOW CONDITIONER')
000384 90 CALL PTDENS(P1,T1,1,RH01,JFLG)
000385 IF (.JFLG.GT.1) RETURN
000386 V1=144.*WDOT/(RH01*A1)
000387 CALL PTENTH(P1,T1,2,H1,JFLG)
000388 IF (JFLG.GT.1) RETURN
000389 H1T=H1+V1**2/(2.*32.174*778.16)
000390 CALL SPLNT(N,TSAT,PSAT,EMPT,T1,PVAP1)
000391 IF (P2.LE.(PVAP1+3.)) GO TO 100
000392 C *** SINGLE PHASE DOWNSTREAM OF FLOW CONDITIONER
000393 CALL PTDENS(P2,T2,2,RH02,JFLG)
000394 IF (.JFLG.GT.1) RETURN
000395 CALL PTENTH(P2,T2,3,H2,JFLG)
000396 IF (.JFLG.GT.1) RETURN
000397 V2=144.*WDOT/(RH02*A2)
000398 H2T=H2+V2**2/(2.*32.174*778.16)
000399 CALL PTENTR(P2,T2,1,S2,JFLG)
000400 IF (JFLG.GT.1) RETURN
000401 RHOLIQ=RH02
000402 X2=0.0
000403 R=0.
000404 ALPHA=0.
000405 RHOVAP=0.
000406 GO TO 160
000407 C*** POSSIBLE TWO PHASE DOWNSTREAM OF FLOW CONDITIONER
000408 100 H2=H1
000409 IF (IFLAG.NE.0) GO TO 105
000410 HTOT=H1T
000411 GO TO 106
000412 105 HTOT=HTK
000413 106 ICOUNT=0
000414 110 ICOUNT=ICOUNT+1
000415 CALL PHTEMP(P2,H2,1,T2CALC,X2,JFLG)
000416 IF (.JFLG.GT.1) RETURN

```

```

000417 CALL PHDENS(P2,H2,1,RH02,RHOLIQ,X2,JFLG)
000418 IF (,JFLG.GT.1) RETURN
000419 IF (RHOLIQ.GT.0.0) GO TO 120
000420 RHOLIQ=RH02
000421 120 V2=144.*WDOT/(RH02*A2)
000422 H2NEW=HT0T-V2**2/(2.*32.174*778.16)
000423 IF (ABS(1.-H2/H2NEW).LE.0.00001) GO TO 150
000424 H2=H2NEW
000425 IF (ICOUNT.LE.20) GO TO 110
000426 WRITE (6,1000)
000427 1000 FORMAT (' SOLUTION FOR ENTHALPY DOWNSTREAM OF FLOW CONDITIONER DID
000428 1 NOT CONVERGE IN 20 ITERATIONS')
000429 150 CALL PHENTR(P2,H2,1,S2,JFLG)
000430 IF (,JFLG.GT.1) RETURN
000431 H2T=H2+V2**2/(2.*32.174*778.16)
000432 RHOVAP=X2*RHOLIQ/(RHOLIQ/RH02+X2-1.0)
000433 R=X2*RHOLIQ/((1.-X2)*RHOVAP)
000434 ALPHA=B/(B+1.)
000435 C *** FIND SATURATION PRESSURE CORRESPONDING TO S2
000436 160 CALL SPLNT (N,SSAT,TSAT,EMTS,S2,T2CALC)
000437 CALL SPLNT (N,SSAT,PSAT,EMPS,S2,PVAP2)
000438 CALL SPLNT (N,SSAT,HSAT,EMHS,S2,HLIQ2)
000439 CALL SPLNT (N,SSAT,RHOSAT,EMRHOS,S2,RHOL2)
000440 QS=4.8.86*WDOT/RH02
000441 300 P2T=P2+RH02*V2**2/(2.*32.174*144.)
000442 PTEST=P2T+0.5
000443 CALL PHENTR(PTEST,H2T,2,S11,JFLG)
000444 IF (,JFLG.GT.1) RETURN
000445 DP=PTEST-P2T
000446 ICOUNT=1
000447 315 CALL PHENTR(P2T,H2T,3,STEST,JFLG)
000448 IF (,JFLG.GT.1) RETURN
000449 DS=S11-STEST
000450 DPDS=DP/DS
000451 IF (ABS(1.-STEST/S2)-1.0E-05) 350,350,320
000452 320 IF (ICOUNT-30) 330,340,340
000453 330 ICOUNT=ICOUNT+1
000454 S11=STEST
000455 DP=DPDS*(STEST-S2)
000456 P2T=P2T-DP
000457 GO TO 315
000458 340 WRITE (6,1030)
000459 1030 FORMAT (' NO SOLUTION FOR P2T:')
000460 350 NPSP=P2T-PVAP2
000461 NPSHA=144.*NPSP/RHOL2
000462 450 NPSHB=778.16*(H2T-HLIQ2)
000463 500 RETURN
000464 END
000465 SUBROUTINE FLOW(JFLG)
000466 COMMON / CALC/ INPT(100),GEOM(50),OUT(120)
000467 REAL INPT
000468 EQUIVALENCE (GEOM(3),ALBF),(GEOM(4),CLABF),(GEOM(5),ALBR),
000469 1 (GEOM(6),CLABR),(GEOM(13),DDL),(GEOM(14),RHOREF),
000470 2 (GEOM(15),ORFD),(GEOM(16),ORFCOE),(GEOM(17),ORFBTA)
000471 EQUIVALENCE (INPT(2),PSD),(INPT(3),TD),(INPT(4),PLFI),
000472 1 (INPT(5),PLFO),(INPT(6),PLRI),(INPT(7),PLRO),
000473 2 (INPT(8),WREF),(INPT(9),DPORF1),(INPT(10),DPORF2),
000474 3 (INPT(11),PORF)
000475 EQUIVALENCE (OUT(1),RHOD),(OUT(2),WD),(OUT(3),QD),(OUT(4),HSDB),
000476 1 (OUT(5),RHOFLL),(OUT(6),WLBFL),(OUT(7),RECF),

```



```

000477      2      (OUT(8),RHORL),(OUT(9),WLBR),(OUT(10),BLDR),
000478      3      (OUT(11),WS),(OUT(103),WBRG)
000479      CALL PTDENS(PSD,TD,3,RHOD,JFLG)
000480      IF (JFLG.GT.1) RETURN
000481      WD=WREF*RHOD/RHOREF
000482      QD=448.86*WD/RHOD
000483      CALL PTENTH(PSD,TD,4,HSDB,JFLG)
000484      IF (JFLG.GT.1) RETURN
000485      CALL PHDENS(PORF,HSDB,2,RHOBRG,RHOLBG,QUAL,JFLG)
000485      IF (JFLG.GT.1) RETURN
000487      WB1=0.5252*ORFCOE*ORFBTA**2*ORFD**2*SQRT(RHOBRG*DPORF1)
000488      WB2=0.5252*ORFCOE*ORFBTA**2*ORFD**2*SQRT(RHOBRG*DPORF2)
000489      WBRG=WB1+WB2
000490      C      FRONT LABYRINTH FLOW
000491      CALL PHDENS(PLFO,HSDB,3,RHOFL,RHOLFL,QUAL,JFLG)
000492      IF (JFLG.GT.1) RETURN
000493      DPLBF=PLFI-PLFO
000494      WLBF=0.66847*CLABF*ALBF*SQRT(RHOFL*DPLRF)
000495      C      REAR LABYRINTH FLOW
000496      DPLBR=PLRI-PLRO
000497      CALL PHDENS(PLRO,HSDB,4,RHORL,RHOLRL,QUAL,JFLG)
000498      IF (JFLG.GT.1) RETURN
000499      WLBR=0.66847*CLABR*ALBR*SQRT(RHORL*DPLRR)
000500      C      REARING HOUSING FLOW
000501      C      SUCTION FLOW
000502      WS=WD+WBRG+WLBR
000503      RECF=WLBF/WS
000504      RLDR=WLBR/WS
000505      RETURN
000506      END
000507      SUBROUTINE AXFOR
000508      COMMON /CALC/ INPT(100),GEOM(50),OUT(120)
000509      REAL INPT
000510      EQUIVALENCE (GEOM(8),D2),(GEOM(19),R706),(GEOM(20),R707),
000511      1      (GEOM(21),R708),(GEOM(22),R724),(GEOM(23),R725),
000512      2      (GEOM(24),R726),(GEOM(25),RLF),(GEOM(26),RLM),
000513      3      (GEOM(27),RLI),(GEOM(28),RIN),(GEOM(29),RLD),
000514      4      (GEOM(30),RLS)
000515      EQUIVALENCE (INPT(16),PS),(INPT(19),P708),(INPT(20),P726),
000516      1      (INPT(4),P706),(INPT(5),P705),(INPT(6),P724),
000517      2      (INPT(7),P723),(INPT(32),P707),(INPT(33),P725),
000518      3      (INPT(31),SN)
000519      EQUIVALENCE (OUT(11),VWIN),(OUT(34),RHOSL),(OUT(85),P2F),
000520      1      (OUT(86),PLF),(OUT(87),XKSOU),(OUT(88),XKSOV),
000521      2      (OUT(89),FF),(OUT(90),FFLB),(OUT(91),FIN),
000522      3      (OUT(92),FFOV),(OUT(93),FMT),(OUT(94),P2R),
000523      4      (OUT(95),PLD),(OUT(96),XKDOU),(OUT(97),XKDOV),
000524      5      (OUT(98),FR),(OUT(99),F723),(OUT(100),FAS),
000525      6      (OUT(101),FROV),(OUT(102),FAX),(OUT(20),RHO2)
000526      PAMB=INPT(1)/2.036
000527      C-CONSTANTS
000528      R2 = D2/2.
000529      R708Q = R708**2
000530      R707Q = R707**2
000531      R706Q = R706**2
000532      R726Q = R726**2
000533      R725Q = R725**2
000534      R724Q = R724**2
000535      R2Q = R2**2
000536      RLFQ = RLF**2

```

119

```

000537 RLMQ = RLM**2
000538 RLIQ = RLI**2
000539 RINQ = RIN**2
000540 R726Q = R726**2
000541 R725Q = R725**2
000542 R724Q = R724**2
000543 RLDQ = RLD**2
000544 RLSQ=RLS**2
000545 C-PRESSURE EXTRAPOLATIONS SHROUD
000546 P2F = (R2Q-R707Q)*(P708-P707)/(R708Q-R707Q)+P707
000547 PLF = P706-(R706Q-RLFQ)*(P707-P706)/(R707Q-R706Q)
000548 C-K-VALUES SHROUD
000549 XKK = 11028./SN/SQRT(RH02)
000550 XKSOU = XKK * SQRT((P708-P707)/(R708Q-R707Q))
000551 XKSOV = XKK * SQRT((P708-P706)/(R708Q-R706Q))
000552 C-SHROUD PRESSURE FORCES
000553 FF27 = 1.5708*(R2Q-R707Q)*(P2F+P707)
000554 FF7L = 1.5708*(R707Q-RLFQ)*(P707+PLF)
000555 FF = FF27 + FF7L
000556 C-LABYRINTH PRESSURES
000557 PLFI = P705 + (PLF - P705)/3.
000558 PLFM = PLF - (PLF - P705)/3.
000559 C-PRESSURE FRONT LABYRINTH
000560 FLFM = 3.1417*(RLFQ - RLMQ)*PLFM
000561 FLFI = 3.1417*(RLMQ - RLIQ)*PLFI
000562 F705 = 3.1417*(RLIQ - RINQ)*P705
000563 FFLB = FLFM + FLFI + F705
000564 C-PRESSURE FORCE INDUCER
000565 FIN = 3.1417 * RINQ * PS
000566 C-MOMENTUM FORCE
000567 FMT = 0.145 * VWIN**2/RHOSL
000568 C-FRONT SIDE PRESSURE FORCE
000569 FFOV = FF + FFLB + FIN
000570 C-PRESSURE EXTRAPOLATIONS DISK
000571 P2R = (R2Q-R725Q)*(P726-P725)/(R726Q-R725Q)+P725
000572 PLD = P725 - (R725Q-RLDQ)*(P725-P724)/(R725Q-R724Q)
000573 C-K-VALUES DISK
000574 XKDOU = XKK * SQRT((P726-P725)/(R726Q-R725Q))
000575 XKDOV = XKK * SQRT((P726-P724)/(R726Q-R724Q))
000576 C-DISK PRESSURE FORCES
000577 FR25 = 1.5708*(R2Q - R725Q)*(P2R+P725)
000578 FR5L = 1.5708*(R725Q - RLDQ)*(P725+PLD)
000579 FR = FR25 + FR5L
000580 F723 = 3.1417*(RLDQ-RLSQ)*P723
000581 FAS = 3.1417* RLS**2* PAMB
000582 C-BACKSIDE PRESSURE FORCE
000583 FROV = FR + F723 + FAS
000584 C-AXIAL THROUST POSITIVE TOWARDS SUCTION
000585 FAX=FROV-FFOV-FMT
000586 RETURN
000587 END
000588 SUBROUTINE RADTHR(N)
000589 COMMON /CALC/ INPT(100),GEOM(50),OUT(120)
000590 DIMENSION P(9),THETA(10),FX(9),FY(9)
000591 EQUIVALENCE (INPT(21),P(1))
000592 EQUIVALENCE (GEOM(8),DI2),(GEOM(18),W)
000593 EQUIVALENCE (OUT(80),RUSL),(OUT(81),BETA),(OUT(82),RFP),
000594 1(OUT(83),PAVE)
000595 DTHETA=360./N
000596 THETA(1)=-DTHETA/2.

```

120

```

000597      DO 10 I=2,N
000598      10 THETA(I)=THETA(I-1)+DTHETA
000599      THETA(N+1)=THETA(1)+360.
000600      SUMFX=0.0
000601      SUMFY=0.0
000602      DO 110 I=1,N
000603      PHI = (THETA,I+1)-THETA(I)) / 2.+ THETA(I)
000604      IF (PHI.LT.0.0) GO TO 40
000605      IF (PHI.LE.90.0) GO TO 50
000606      IF (PHI.LE.180.0) GO TO 60
000607      IF (PHI.LE.270.0) GO TO 70
000608      IF (PHI.LE.360.0) GO TO 80
000609      40 WRITE (6,1000)
000610      1000 FORMAT (' ANGLE LESS THAN 0 OR GREATER THAN 360 DEG, RADIAL THRUST
000611      'CALCULATION TERMINATED')
000612      RETURN
000613      50 PSI=PHI
000614      SIGNY=-1.
000615      SIGNX=-1.
000616      GO TO 100
000617      60 PSI=180.-PHI
000618      SIGNY=-1.
000619      SIGNX=1.
000620      GO TO 100
000621      70 PSI=PHI-180.
000622      SIGNY=1.
000623      SIGNX=1.0
000624      GO TO 100
000625      80 PSI=360.-PHI
000626      SIGNY=1.
000627      SIGNX=-1.
000628      100 F=P(I)*W*DI2*ABS(SIN((THETA(I+1)-THETA(I))/(2.*57.296)))
000629      FX(I)=F*SIGNX*COS(PHI/57.296)
000630      FY(I)=F*SIGNY*SIN(PHI/57.296)
000631      SUMFX=SUMFX+FX(I)
000632      110 SUMFY=SUMFY+FY(I)
000633      IF (SUMFX.LE.0.0) GO TO 150
000634      IF (SUMFY.LE.0.0) GO TO 130
000635      BETA=57.296*ATAN(SUMFY/SUMFX)
000636      GO TO 200
000637      130 BETA=57.296*ATAN(SUMFY/SUMFX)+360.
000638      GO TO 200
000639      150 BETA=57.296*ATAN(SUMFY/SUMFX)+180.0
000640      200 RUSL=SQRT(SUMFX**2+SUMFY**2)
000641      SUMP=0.0
000642      DO 300 I=1,N
000643      300 SUMP=SUMP+P(I)
000644      PAVE=SUMP/N
000645      RFP=RUSL/PAVE
000646      RETURN
000647      END
000648      SUBROUTINE PERFOR(JFLG)
000649      COMMON /CALC/ INPT(100),GEOM(50),OUT(120)
000650      REAL INPT,N
000651      EQUIVALENCE (GEOM(9),BET2),(GEOM(10),Z2),(GEOM(13),DDL),
000652      1 (GEOM(8),DI2),(GEOM(7),AI2),(GEOM(11),RPTAP),
000653      2 (GEOM(12),ADFD)
000654      EQUIVALENCE (INPT(2),PSD),(INPT(3),TD),(INPT(18),PID),
000655      1 (INPT(19),PTIP),(INPT(20),PBTIP),(INPT(21),PDIFI1),
000656      2 (INPT(22),PDIFI2),(INPT(23),RDIFI3),(INPT(24),PDIFI4),

```

```

000657      3      (INPT(25),PDIF15),(INPT(26),PDIF16),(INPT(27),PDIF17),
000658      4      (INPT(28),PDIF18),(INPT(29),PDIF19),(INPT(30),PDIF0),
000659      5      (INPT(31),N),(INPT(16),PS)
000660      EQUIVALENCE (OUT(1),RHOD),(OUT(2),WD),(OUT(3),QD),(OUT(4),HSDB),
000661      1      (OUT(6),WLBFB),(OUT(9),WLBRA),(OUT(11),WS),(OUT(12),QS),
000662      2      (OUT(25),SS),(OUT(40),U2),(OUT(41),VDIS),
000663      3      (OUT(42),HTDB),(OUT(43),DPTD),(OUT(44),PTD),
000664      4      (OUT(45),DHISO),(OUT(46),HN20),(OUT(47),HCO),
000665      5      (OUT(48),QND),(OUT(49),DHTAB),(OUT(50),DHTI),
000666      6      (OUT(51),EFTD),(OUT(52),EFTD0),(OUT(53),DPSIN),
000667      7      (OUT(54),DHSIN),(OUT(55),HSIN2),(OUT(56),QNS),
000668      8      (OUT(57),PHI2),(OUT(58),PSITH),(OUT(59),HBIMP),
000669      9      (OUT(60),RHOD),(OUT(61),HISB),(OUT(62),DHISI),
000670      1      (OUT(63),HN2IS),(OUT(64),HCIS),(OUT(65),HCIT),
000671      2      (OUT(66),DHITI),(OUT(67),HN2IT),(OUT(68),EFIMP),
000672      3      (OUT(69),DHCHG),(OUT(70),DHIID),(OUT(71),HN2DS),
000673      4      (OUT(72),DHITD),(OUT(73),HCTD),(OUT(74),DHCDF),
000674      5      (OUT(75),DHCVO)
000675      EQUIVALENCE (OUT(83),PDIFIA)
000676      EQUIVALENCE (OUT(23),HTSB),(OUT(22),HSB),(OUT(27),PTS),
000677      1      (OUT(34),RHOSL)
000678      C      CONSTANTS
000679      BET2R=BET2/57.296
000680      TBE2=TAN(BET2R)
000681      SLP=3.14159*SIN(BET2R)/Z2
000682      ADL=3.14159/4.*DDL**2
000683      C      PUMP OVERALL PERFORMANCE
000684      U2=3.14159*D12*N/720.
000685      CALL PTENTR(PSD,TD,2,SD,JFLG)
000686      IF (.JFLG.GT.1) RETURN
000687      VDIS=QD*144./(ADL*448.86)
000688      HDVEL=VDIS**2/2./32.174
000689      PTD=PSD+RHOD*HDVEL/144.
000690      HTDB=HSDB+HDVEL/778.16
000691      DH=HTDB-HTSB
000692      DPTD=PTD-PTS
000693      CALL PSENTH(PTD,SS,1,HISOB,JFLG)
000694      IF (.JFLG.GT.1) RETURN
000695      DHISO=(HISOB-HTSB)*778.16
000696      HN20=DHISO/N**2
000697      HCO=DHISO*32.174/U2**2
000698      QND=QD/N
000699      DHTAB=(HTDB-HTSB)
000700      DHTI=(HISOB-HTSB)
000701      EFTD=DHTI/DHTAB
000702      EFTD0=EFTD*WD/WS
000703      C      INDUCER PERFORMANCE
000704      DPSIN=PID-PS
000705      DHSIN=144.*DPSIN/RHOSL
000706      HSIN2=DHSIN/N**2
000707      QNS=QS/N
000708      C      IMPELLER FLOW COEFFICIENT
000709      *SIMP=WS+WLBFB
000710      PIMP=(PTIP+PBTIP)/2.
000711      RHOIR=RHOD
000712      100 PHI2=144.*WSIMP/(RHOD*AI2*U2)
000713      PSITH=1.-PHI2/TBE2-SLP
000714      HVEL2=0.015547*U2**2*(PSITH**2+PHI2**2)
000715      HBIMP=HTDB-HVEL2/778.16
000716      RHOLD=RHOID

```

100

```

000717 CALL PHDENS(PIMP,HBIMP,2,RHOD,RHOL,QUAL,JFLG)
000718 IF (.FLG.GT.1) RETURN
000719 IF (ABS(1.-RHOLD/RHOD)-1.0E-05) 150,150,100
000720 C IMPELLER STATIC HEAD COEFFICIENT
000721 150 CALL PHTEMP(PDIFIA,HBIMP,2,TID,QI2,JFLG)
000722 IF (.FLG.GT.1) RETURN
000723 CALL PSENTH(PDIFIA,SS,2,HISIB,JFLG)
000724 IF (.FLG.GT.1) RETURN
000725 DHISI=(HISIB-HSB)*778.16
000726 HN2IS=DHISI/N**2
000727 HCIS=32.174*DHISI/U2**2
000728 C IMPELLER TOTAL HEAD COEFFICIENT
000729 HCIT=HCIS+(DI2/2./KPTAP)**2*(PSITH**2+PHI2**2)/2.
000730 DHITI=U2**2*HCIT/32.174
000731 HN2IT=DHITI/N**2
000732 EFIMP=HCIT/PSITH
000733 C HOUSING HEAD LOSS COEFFICIENT
000734 DHCHG=HCIT-HCO
000735 C DIFFUSER AND VOLUTE LOSSES
000736 CALL PSENTH(PDIFO,SS,3,HISDB,JFLG)
000737 IF (.FLG.GT.1) RETURN
000738 DHISD=(HISDB-HSB)*778.16
000739 HN2DS=DHISD/N**2
000740 C DIFFUSER DISCHARGE ANGLE BASED ON PFLEIDERS DEVIATION CRITERION
000741 CM52=144.*(WS-WLBR)/RHOD/ADF0
000742 CUTH2=U2*PSITH
000743 AL52R=ATAN(1./(2.01+0.245*CUTH2/CM52))
000744 HVDF=.975*(CM52/SIN(AL52R))**2/(2.*32.174)
000745 DHITD=DHISD+HVDF
000746 HCTD=32.174*DHITD/U2**2
000747 DHCDF=HCIT-HCTD
000748 DHCVO=HCTD-HCO
000749 RETURN
000750 END
000751 SUBROUTINE TAPE1
000752 COMMON / TITLE/ TESTID(12),DAY(2),RUNTME(2),IPAGE
000753 COMMON /TAPEIN/ CHAN1(100),CHAN2(100),CHAN3(100),CHAN4(100),
000754 1PARID(100),CHANID(200),UNITS(200),DEC(200),NPAR
000755 COMMON /TAPE/ TSTART,TSTOP,INT1,INT2,IAVE,NSETS,INPUT,ATIME,TIME,
000756 1IEND
000757 INTEGER CHAN1,CHAN2,CHAN3,CHAN4,PARID,CHANID,UNITS,UN(100),D(100)
000758 REAL INPUT
000759 DIMENSION INPUT(100,50),ATIME(50),DATA(200),NUM(10)
000760 INTEGER PGAGE
000761 INTEGER BLANK,F(22),G(22),V(14)
000762 INTEGER DEC,DAY,RUNTME,TESTID
000763 DATA BLANK /' /
000764 DATA PGAGE /'PSIG '/
000765 DATA F(1),F(2),F(4),F(6),F(8),F(10),F(12),F(14),F(16),F(18),F(20),
000766 1F(22) /'(F9.1,',10*'F11.',')'/
000767 DATA V(1),V(3),V(4),V(5),V(6),V(8),V(9),V(10),V(11),V(13),V(14)
000768 1/'(8X,', '(8X,'I3', 6H)/3X,', 6HTIME', '(3X,', '(5X,A6',
000769 26H)/4X,', 6HSEC',3, 'X', '(5X,A6', ')/'/
000770 DATA G(22) /' )'/
000771 DATA NUM/'1','2','3','4','5','6','7','8','9','10'/
000772 KENTR=1
000773 100 READ(1) NCHAN,TIME, (DATA(I),I=1,NCHAN)
000774 IF (TIME.LT.TSTART) GO TO 100
000775 BACKSPACE 1
000776 GO TO 250

```

123

```

000777 ENTRY TAPE2
000778 250 KENTR=2
000779 260 NSETS=NSETS+,
000780 DO 270 J=1,NPAR
000781 270 INPUT(J,NSETS)=0.0
000782 ATIME(NSETS)=0.0
000783 DO 300 I=1,INT1
000784 READ(1) NCHAN,TIME,(DATA(J),J=1,NCHAN)
000785 IF (KENTR.EQ.1) GO TO 310
000786 IF (TIME.GE.TSTOP) GO TO 310
000787 300 CONTINUE
000788 310 NAVE=1
000789 320 ATIME(NSETS)=ATIME(NSETS)+TIME
000790 DO 350 J=1,NPAR
000791 N=1
000792 K=CHAN1(J)
000793 PAR=DATA(K)
000794 UN(J)=UNITS(K)
000795 D(J)=DEC(K)
000796 IF (CHAN2(J).EQ.0) GO TO 350
000797 N=2
000798 K=CHAN2(J)
000799 PAR=PAR+DATA(K)
000800 IF (CHAN3(J).EQ.0) GO TO 350
000801 N=3
000802 K=CHAN3(J)
000803 PAR=PAR+DATA(K)
000804 IF (CHAN4(J).EQ.0) GO TO 350
000805 N=4
000806 K=CHAN4(J)
000807 PAR=PAR+DATA(K)
000808 350 INPUT(J,NSETS)=INPUT(J,NSETS)+PAR/N
000809 IF (NAVE.GE.IAVE.OR.TIME.GE.TSTOP) GO TO 450
000810 DO 400 I=1,INT2
000811 READ (1) NCHAN,TIME,(DATA(J),J=1,NCHAN)
000812 IF (TIME.GE.TSTOP) GO TO 410
000813 400 CONTINUE
000814 410 NAVE=NAVE+1
000815 GO TO 320
000816 450 DO 500 J=1,NPAR
000817 INPUT (J,NSETS)=INPUT(J,NSETS)/NAVE
000818 IF (UN(J).NE.PGAGE) GO TO 500
000819 INPUT(J,NSETS)=INPUT(J,NSETS)+INPUT(1,NSETS)/2.036
000820 UN(J)='PSIA'
000821 500 CONTINUE
000822 ATIME(NSETS)=ATIME(NSETS)/NAVE
000823 IF (NSETS.LT.50.AND.TIME.LT.TSTOP) GO TO 260
000824 IF (IEND.EQ.0) RETURN
000825 DO 600 K=1,NPAR,10
000826 IPAGE=IPAGE+1
000827 L=K+9
000828 NCOL=10
000829 IF (L.LE.NPAR) GO TO 550
000830 L=NPAR
000831 NCOL=NPAR-K+1
000832 550 V(2)=NUM(NCOL)
000833 V(7)=NUM(NCOL)
000834 V(12)=NUM(NCOL)
000835 WRITE (6,6050) IPAGE
000836 WRITE (6,6000) TESTID,DAY,RUNTIME

```

122

```

000837 WRITE (6,V) (I,I=K,L),(PARID(I),I=K,L),(U),I=K,L)
000838 M=1
000839 DO 580 I=K,L
000840 M=M+2
000841 580 F(M)=D(I)
000842 DO 582 I=1,M
000843 582 G(I)=F(I)
000844 IF (M.EQ.21) GO TO 600
000845 M1=M+1
000846 DO 585 I=M1,21
000847 585 G(I)=BLANK
000848 600 WRITE (6,G) (ATIME(M),(INPUT(I,M),I=K,L),M=1,NSETS)
000849 6000 FORMAT (12A6,12X,'DATE ',2A6,'TIME ',2A6)
000850 6050 FORMAT ('1',52X,'LH2 PUMP TEST',44X,'PAGE ',I4)
000851 RETURN
000852 END
000853 C
000854 C SPLINT CALCULATES INTERPOLATED POINTS AND DERIVATIVES
000855 C FOR A SPLINE CURVE
000856 SUBROUTINE SPLINT (N,X,Y,EM,XX,YINT)
000857 DIMENSION Z(10),X(25),Y(25),EM(25)
000858 1000 FORMAT (' SPLINT USED FOR EXTRAPOLATION',3E20.7/).
000859 MAX=1
000860 Z(1)=XX
000861 DO140 I=1,MAX
000862 K=2
000863 IF (Z(I)-X(1),70,60,90)
000864 60 YINT =Y(1)
000865 SK=X(K)-X(K-1)
000866 GO TO 130
000867 70 IF (Z(I)-(1.1*X(1)-0.1*X(2))) 75,120,120
000868 75 WRITE (6,1000) Z(I),X(1),X(2)
000869 SRW=16
000870 GO TO 120
000871 80 K=N
000872 IF (Z(I)-(1.1*X(N)-0.1*X(N-1))) 120,120,85
000873 85 WRITE (6,1000) Z(I),X(N-1),X(N)
000874 SRW=16
000875 GO TO 120
000876 90 IF (Z(I)-X(K)) 120,100,110
000877 100 YINT =Y(K)
000878 SK=X(K)-X(K-1)
000879 GO TO 130
000880 110 K=K+1
000881 IF (K-N) 90,90,80
000882 120 CONTINUE
000883 SK=X(K)-X(K-1)
000884 YINT =EM(K-1)*(X(K)-Z(I))**3/6. /SK+EM(K)*(Z(I)-X(K-1))**3/6.
000885 1/SK+(Y(K)/SK-EM(K)*SK/6.)*(Z(I)-X(K-1))+(Y(K-1)/SK-EM(K-1)*SK/6.
000886 2)*(X(K)-Z(I))
000887 130 DYDX =-EM(K-1)*(X(K)-Z(I))**2/2.0 /SK+EM(K)*(X(K-1)-Z(I))**2/2
000888 1 /SK+(Y(K)-Y(K-1))/SK-(EM(K)-EM(K-1))*SK/6.
000889 D2YDX=(X(K)-Z(I))*EM(K-1)/SK+(Z(I)-X(K-1))*EM(K)/SK
000890 RCURV=((1.+DYDX**2)**1.5)/ABS(D2YDX)
000891 140 CONTINUE
000892 500 RETURN
000893 END
000894 SUBROUTINE SPLINE (N,X,Y,EM)
000895 INTEGER SRW
000896

```

C

```

000897 C SPLINE CALCULATES FIRST AND SECOND DERIVATIVES SPLINE POINTS 3K
000898 C END CONDITION-SECOND DERIVATIVES ARE THE SAME, END POINT AND
000899 C ADJACENT POINT
000900 C
000901 DIMENSION X(25),Y(25),EM(25),G(25),SB(25),SLOPE(25),CURV(25)
000902 SRW=0
000903 SB(1)=-1.0
000904 G(1)=0.
000905 NO=N-1
000906 IF (NO-2) 20,7,7
000907 7 DO10I=2,NO
000908 A=(X(I)-X(I-1))/6.
000909 C=(X(I+1)-X(I))/6.
000910 W=2. *(A+C)-A*SB(I-1)
000911 SB(I)=C/W
000912 F=(Y(I+1)-Y(I))/(X(I+1)-X(I))-(Y(I)-Y(I-1))/(X(I)-X(I-1))
000913 10 G(I)=(F-A*G(I-1))/W
000914 20 EM(N)=G(N-1)/(1. +SB(N-1))
000915 DO30I=2,N
000916 K=N+1-I
000917 30 EM(K)=G(K)-SB(K)*EM(K+1)
000918 SLOPE(1)=(X(1)-X(2))/6. *(2. *EM(1)+EM(2))+(Y(2)-Y(1))/(X(2)-X(1)
000919 1))
000920 DO40I=2,N
000921 40 SLOPE(I)=(X(I)-X(I-1))/6. *(2. *EM(I)+EM(I-1))+(Y(I)-Y(I-1))/(X(
000922 I)-X(I-1))
000923 DO 45 I=1,N
000924 45 CURV(I)=((1.+SLOPE(I)**2)**1.5)/ABS(EM(I))
000925 IF (SRW) 50,100,50
000926 50 WRITE (6,1000) N, (X(I),Y(I),SLOPE(I),EM(I),CURV(I),I=1,N)
000927 100 RETURN
000928 1000 FORMAT (1,15HNO. OF POINTS =,I3/10X,1HX,19X,1HY,19X,5HSLOPE,15X,
000929 A2HEM,15X,4HCURV/(5E20.8))
000930 END
000931 SUBROUTINE SATUR(N)
000932 COMPILER (DATA=SHORT)
000933 COMMON /SAT/ HSAT(25),PSAT(25),TSAT(25),SSAT(25),RHOSAT(25),
000934 1EMPT(25),EMPS(25),EMTS(25),EMHS(25),EMRHO(25),EMTP(25),
000935 2HSATV(25),SSATV(25),RHOSTV(25),EMHLP(25),EMHVP(25),EMSLP(25),
000936 3EMSVP(25),EMROLP(25),EMROVP(25),EMPH(25)
000937 C*** SATURATION DATA
000938 DATA HSAT /-132.81,-132.25,-129.29,-126.13,-122.78,-119.2,-115.38,
000939 1-111.31,-110.18,-106.96,-102.31,-97.32,-91.966,-86.208,-79.959,
000940 2-73.176,-65.733,-57.436,-48.009,-36.876,-22.458,16.550/
000941 DATA PSAT /1.0214,1.1433,1.9546,3.1302,4.7762,6.9953,9.8904,13.564
000942 1,14.96,18.120,23.705,30.406,38.371,47.688,58.519,70.967,85.149,
000943 2101.21,119.30,139.63,162.40,187.51/
000944 DATA TSAT /24.845,25.2,27.0,28.8,30.6,32.4,34.2,36.0,36.482,37.8,
000945 139.6,41.4,43,2,45.0,46.8,48.6,50.4,52.2,54.0,55.8,57.6,59.3568/
000946 DATA SSAT /1.18491,1.20743,1.31999,1.43138,1.54157,1.65296,1.76315
000947 1,1.87572,1.90534,1.98828,2.10204,2.21816,2.33665,2.45751,2.58193,
000948 22.71227,2.84853,2.99428,3.15306,3.33553,3.56422,4.19696/
000949 DATA RHOSAT /4.8086,4.7975,4.7434,4.6884,4.6298,4.5693,4.5055,
000950 14.4371,4.4185,4.3664,4.2889,4.2086,4.1205,4.0256,3.9226,3.8086,
000951 23.6805,3.5358,3.3664,3.1578,2.8711,1.9619/
000952 DATA HSATV / 60.315,61.104,64.965,68.612,72.045,75.223,78.103,
000953 180.683,81.408,82.987,84.800,86.207,87.124,87.530,87.316,86.357,
000954 284.480,81.472,76.866,69.891,58.502,16.358 /
000955 DATA SSATV / 8.9615,8.8821,8.5147,8.1936,7.9093,7.6545,7.4223,
000956 17.2102,7.1581,7.0159,6.8298,6.6533,6.4850,6.3203,6.1592,5.9968,

```

126


```

000957      25.8310,5.6568,5.4672,5.2492,4.9707,4.1946/
000958      DATA RHOSTV /,007837, .008666, .07390, .021130, .000722, .043083,
000959      1.05864, .077866, .08351, .10105, .12927, .16304, .20317, .25074,
000960      2.3072, .3745, .4555, .5547, .6795, .8452, 1.0422, 1.9619 /
000961      CALL SPLNE(N,TSAT,PSAT,EMPT)
000962      CALL SPLNE(N,HSAT,PSAT,EMPH)
000963      CALL SPLNE(N,SSAT,PSAT,EMPS)
000964      CALL SPLNE(N,PSAT,TSAT,EMTP)
000965      CALL SPLNE(N,SSAT,TSAT,EMTS)
000966      CALL SPLNE(N,SSAT,HSAT,EMHS)
000967      CALL SPLNE(N,SSAT,RHOSAT,EMRHOS)
000968      CALL SPLNE(N,PSAT,HSAT,EMHLP)
000969      CALL SPLNE(N,PSAT,HSATV,EMHVP)
000970      CALL SPLNE(N,PSAT,SSAT,EMSLP)
000971      CALL SPLNE(N,PSAT,SSATV,EMSVP)
000972      CALL SPLNE(N,PSAT,RHOSAT,EMROLP)
000973      CALL SPLNE(N,PSAT,RHOSTV,EMROVP)
000974      RETU,N
000975      END
000976      SUBROUTINE PARAH
000977      COMMON /PROP/ T(30,50),SV(30,50),H(30,50),S(30,50),NUM(30),P(30),
000978      1AA(5,90),RHOX(90),B(9,8)
000979      COMMON /SAT/ HSAT(25),PSATUR(25),TSAT(25),SSAT(25),RHOSAT(25),
000980      1EMPT(25),EMPS(25),EMTS(25),EMHS(25),EMRHOS(25),EMTP(25),
000981      2HSATVP(25),SSATV(25),RHOSATV(25),EMHLP(25),EMHVP(25),EMSLP(25),
000982      3EMSVP(25),EMROLP(25),EMROVP(25),EMPH(25)
000983      DATA PCRIT /187.55/
000984      DATA N/22/
000985      C      ENTRY POINT FOR DENSITY(PP,TT)
000986      C
000987      ENTRY PTDENS(PP,TT,K,RHO,JFLG)
000988      ENTR=PTDENS,
000989      IF (PP.GT.PCRIT) GO TO 100
000990      CALL SPLNT(N,TSAT,PSATUR,EMPT,TT,PSAT)
000991      IF (PP.LT.PSAT) GO TO 160
000992      100 CALL HPROP(PP,TT,SV,T,1,2,C,JFLG,XMIN,XMAX)
000993      IF (JFLG.GT.1) GO TO 110
000994      RHO=1./C
000995      RETURN
000996      C      ENTRY FOR ENTHALPY(PP,TT)
000997      C
000998      ENTRY PTENTH(PP,TT,K,ENTH,JFLG)
000999      ENTR=PTENTH,
001000      IF (PP.GT.PCRIT) GO TO 101
001001      CALL SPLNT(N,TSAT,PSATUR,EMPT,TT,PSAT)
001002      IF (PP.LT.PSAT) GO TO 160
001003      101 CALL HPROP(PP,TT,H,T,1,3,ENTH,JFLG,XMIN,XMAX)
001004      IF (JFLG.GT.1) GO TO 110
001005      RETURN
001006      C      ENTRY FOR ENTROPY(PP,TT)
001007      C
001008      ENTRY PTENTR(PP,TT,K,ENTRO,JFLG)
001009      ENTR=PTENTR,
001010      IF (PP.GT.PCRIT) GO TO 102
001011      CALL SPLNT(N,TSAT,PSATUR,EMPT,TT,PSAT)
001012      IF (PP.LT.PSAT) GO TO 160
001013      102 CALL HPROP(PP,TT,S,T,1,4,ENTRO,JFLG,XMIN,XMAX)
001014      IF (JFLG.GT.1) GO TO 110
001015      105 RETURN
001016      110 GO TO (105,120,130,140,150),JFLG

```

LIST

```

001017 120 WRITE (6,2000) XMIN,XMAX,PP,ENTR,K
001018 2000 FORMAT (' MINIMUM TABULATED PRESSURE IS GREATER THAN P'/
001019 1: PMIN=',F10.2,5X,'PMAX=',F10.2,5X,'P=',F10.2,5X,A6,I2)
001020 RETURN
001021 130 WRITE (6,2010) XMIN,XMAX,PP,ENTR,K
001022 2010 FORMAT (' MAXIMUM TABULATED PRESSURE IS LESS THAN P'/
001023 1: PMIN=',F10.2,5X,'PMAX=',F10.2,5X,'P=',F10.2,5X,A6,I2)
001024 RETURN
001025 140 WRITE (6,2020) XMIN,XMAX,TT,ENTR,K
001026 2020 FORMAT (' MINIMUM TABULATED TEMPERATURE IS GREATER THAN T'/
001027 1: TMIN=',F10.2,5X,'TMAX=',F10.2,5X,'T=',F10.2,5X,A6,I2)
001028 RETURN
001029 150 WRITE (6,2030) XMIN,XMAX,TT,ENTR,K
001030 2030 FORMAT (' MAXIMUM TABULATED TEMPERATURE IS LESS THAN T'/
001031 1: TMIN=',F10.2,5X,'TMAX=',F10.2,5X,'T=',F10.2,5X,A6,I2)
001032 RETURN
001033 160 WRITE (6,2040) PSAT,PP,ENTR,K
001034 2040 FORMAT (' P IS LESS THAN SAT. PRESS. CORRESPONDING TO T'/
001035 1: PSAT=',F10.2,5X,'P=',F10.2,5X,A6,I2)
001036 JFLG=6
001037 RETURN
001038 C ENTRY FOR TEMPERATURE(PP,HH)
001039 C
001040 ENTRY PHTEMP(PP,HH,K,TEMP,X,JFLG)
001041 ENTR='PHTEMP'
001042 IF (PP.GT.PCRIT) GO TO 200
001043 CALL SPLNT(N,HSAT,PSATUR,EMPH,HH,PSAT)
001044 IF (PP.LT.PSAT) GO TO 260
001045 200 CALL HPROP(PP,HH,T,H,3,1,TEMP,JFLG,XMIN,XMAX)
001046 IF (JFLG.GT.1) GO TO 210
001047 X=0.0
001048 RETURN
001049 C ENTRY FOR DENSITY(PP,HH)
001050 C
001051 ENTRY PHDENS(PP,HH,K,RHO,RHOL,X,JFLG)
001052 ENTR='PHDENS'
001053 IF (PP.GT.PCRIT) GO TO 201
001054 CALL SPLNT(N,HSAT,PSATUR,EMPH,HH,PSAT)
001055 IF (PP.LT.PSAT) GO TO 280
001056 201 CALL HPROP(PP,HH,SV,H,3,2,C,JFLG,XMIN,XMAX)
001057 IF (JFLG.GT.1) GO TO 210
001058 RHO=1./C
001059 X=0.0
001060 RHOL=0.0
001061 RETURN
001062 C ENTRY FOR ENTROPY(PP,HH)
001063 C
001064 ENTRY PHENTR(PP,HH,K,ENTRO,JFLG)
001065 ENTR='PHENTR'
001066 IF (PP.GT.PCRIT) GO TO 202
001067 CALL SPLNT(N,HSAT,PSATUR,EMPH,HH,PSAT)
001068 IF (PP.LT.PSAT) GO TO 290
001069 202 CALL HPROP(PP,HH,S,H,3,4,ENTRO,JFLG,XMIN,XMAX)
001070 IF (JFLG.GT.1) GO TO 210
001071 RETURN
001072 210 GO TO (205,150,130,240,250),JFLG
001073 240 WRITE (6,3000) XMIN,XMAX,HH,ENTR,K
001074 3000 FORMAT (' MINIMUM TABULATED ENTHALPY IS GREATER THAN H'/
001075 1: HMIN=',F10.4,5X,'HMAX=',F10.4,5X,'H=',F10.4,5X,A6,I2)
001076 RETURN

```

```

001077 250 WRITE (6,3010) XMIN,XMAX,HH,ENTR,K
001078 3010 FORMAT (' MAXIMUM TABULATED ENTHALPY IS LESS THAN H'/
001079 1, HMIN=',F10.4,5X,'HMAX=',F10.4,5X,'H=',F10.4,5X,A6,I2)
001080 RETURN
001081 260 CALL SPLNT(N,PSATUR,HSAT,EMHLP,PP,HSATL)
001082 CALL SPLNT(N,PSATUR,HSATVP,EMHVP,PP,HSATV)
001083 CALL SPLNT(N,PSATUR,TSAT,EMTP,PP,TEMP)
001084 IF (,H.GT.HSATV) GO TO 270
001085 X=(HH-HSATL)/(HSATV-HSATL)
001086 RETURN
001087 270 WRITE (6,3020) PSAT,PP,HSATV,HH,ENTR,K
001088 3020 FORMAT (' P IS LESS THAN SAT. PRESS. CORRESPONDING TO H AND H IS G
001089 1,REATER THAN H SATURATED VAPOR',/ PSAT=',F10.2,5X,'P=',F10.2,5X,
001090 2,HSATV=',F10.4,5X,'H=',F10.4,5X,A6,I2)
001091 JFLG=6
001092 RETURN
001093 280 CALL SPLNT(N,PSATUR,RHOSAT,EMROL,PP,RHOL)
001094 CALL SPLNT(N,PSATUR,RHOSTV,EMROVP,PP,RHOV)
001095 CALL SPLNT(N,PSATUR,HSAT,EMHLP,PP,HSATL)
001096 CALL SPLNT(N,PSATUR,HSATVP,EMHVP,PP,HSATV)
001097 IF (HH.GT.HSATV) GO TO 270
001098 X=(HH-HSATL)/(HSATV-HSATL)
001099 RHO=RHOL*RHOV/(X*RHOL+(1.-X)*RHOV)
001100 RETURN
001101 290 CALL SPLNT(N,PSATUR,SSAT,EMSLP,PP,SL)
001102 CALL SPLNT(N,PSATUR,SSATV,EMSVP,PP,SVP)
001103 CALL SPLNT(N,PSATUR,HSAT,EMHLP,PP,HSATL)
001104 CALL SPLNT(N,PSATUR,HSATVP,EMHVP,PP,HSATV)
001105 IF (,H.GT.HSATV) GO TO 270
001106 XS=(HH-HSATL)/(HSATV-HSATL)
001107 ENTRO=XS*SVP+(1.-XS)*SL
001108 RETURN
001109 C ENTRY FOR ENTHALPY(PP,SS)
001110 C
001111 ENTRY PSENTH(PP,SS,K,ENTH,JFLG)
001112 ENTR=PSENTH
001113 IF IPP.GT.PCRIT) GO TO 300
001114 CALL SPLNT(N,SSAT,PSATUR,EMPS,SS,PSAT)
001115 IF IPP.LT.PSAT) GO TO 360
001116 300 CALL HPROP(PP,SS,H,S,4,3,ENTH,JFLG,XMIN,XMAX)
001117 IF (,JFLG.GT.1) GO TO 310
001118 305 RETURN
001119 310 GO TO (305,120,130,340,350), JFLG
001120 340 WRITE (6,4000) XMIN,XMAX,SS,ENTR,K
001121 4000 FORMAT (' MINIMUM TABULATED ENTROPY IS GREATER THAN S'/
001122 1, SMIN=',F10.5,5X,'SMAX=',F10.5,5X,'S=',F10.5,5X,A6,I2)
001123 RETURN
001124 350 WRITE (6,4010) XMIN,XMAX,SS,ENTR,K
001125 4010 FORMAT (' MAXIMUM TABULATED ENTROPY IS LESS THAN S'/
001126 1, SMIN=',F10.5,5X,'SMAX=',F10.5,5X,'S=',F10.5,5X,A6,I2)
001127 RETURN
001128 360 CALL SPLNT(N,PSATUR,HSAT,EMHLP,PP,HSATL)
001129 CALL SPLNT(N,PSATUR,HSATVP,EMHVP,PP,HSATV)
001130 CALL SPLNT(N,PSATUR,SSAT,EMSLP,PP,SL)
001131 CALL SPLNT(N,PSATUR,SSATV,EMSVP,PP,SVP)
001132 IF (SS.GT.SVP) GO TO 370
001133 XS=(SS-SL)/(SVP-SL)
001134 ENTH=XS*HSATV+(1.-XS)*HSATL
001135 RETURN
001136 370 WRITE (6,4020) PSAT,PP,SVP,SS,ENTR,K

```

129

```

001137 4020 FORMAT (1 P IS LESS THAN SAT. PRESS. CORRESPONDING TO S AND S IS G
001138 1REAT= R THAN S SATURATED VAPOR// PSAT=,F10.2, 'P',F10.2,5X'
001139 2,SV=,F10.5,5X,'S',F10.5,5X,A6,I2)
001140 JFLG=6
001141 RETURN
001142 END
001143 C**** THIS SUBROUTINE READS IN THE HYDROGEN PROPERTIES DATA TO BE USED FILE 001
001144 C**** IN SUBROUTINE HPROP FILE 002
001145 C FILE 003
001146 SUBROUTINE HPROP
001147 DIMENSION A(30)
001148 COMMON /PROP/ T(30,50),SV(30,50),H(30,50),S(30,50),NUM(30),P(30),
001149 1AA(5,90),RHOX(90),B(9,8)
001150 10 FORMAT (8F10.0) FILE 009
001151 20 FORMAT (25I3) FILE 010
001152 C FILE 011
001153 C**** READ NUMBER OF DATA POINTS FOR EACH ISOBAR FILE 012
001154 C FILE 013
001155 READ (5,20) (NUM(I),I=1,30)
001156 DO 50 I=1,30
001157 M=NUM(I) FILE 016
001158 C FILE 017
001159 C**** READ TEMPERATURES FOR ISOBAR I FILE 018
001160 C FILE 019
001161 READ (5,10) (T(I,J),J=1,M)
001162 C FILE 021
001163 C**** READ SPECIFIC VOLUMES FOR ISOBAR I FILE 022
001164 C FILE 023
001165 READ (5,10) (SV(I,J),J=1,M)
001166 C FILE 025
001167 C**** READ ENTHALPIES FOR ISOBAR I FILE 026
001168 C FILE 027
001169 READ (5,10) (H(I,J),J=1,M)
001170 C FILE 029
001171 C**** READ ENTROPIES FOR ISOBAR I FILE 030
001172 C FILE 031
001173 50 READ (5,10) (S(I,J),J=1,M)
001174 C FILE 037
001175 C**** CONVERT PRESSURES FROM ATMOSPHERES TO PSIA FILE 038
001176 C FILE 039
001177 A(1)=1. FILE 040
001178 A(2)=1.5 FILE 041
001179 DO 55 I=2,10 FILE 042
001180 55 A(I+1)=I FILE 043
001181 A(12)=12.5 FILE 044
001182 DO 60 I=1,8 FILE 045
001183 60 A(I+12)=10+5*I FILE 046
001184 DO 65 I=1,5 FILE 047
001185 65 A(I+20)=50+10*I FILE 048
001186 DO 70 I=1,5
001187 70 A(I+25)=100+20*I
001188 DO 80 I=1,30
001189 80 P(I)=14.696*A(I) FILE 050
001190 25 FORMAT (5E16.7) FILE 057
001191 30 FORMAT (10F8.4) FILE 058
001192 35 FORMAT (4E20.8) FILE 059
001193 C FILE 060
001194 C**** READ EMPIRICAL COEFFICIENTS FILE 061
001195 C FILE 062
001196 READ (5,25) ((AA(I,J),J=1,90),I=1,5)

```

130

001197	READ (5,30) (RHOX(I),I=1,90)	
001198	READ (5,35) ((B(I,J),J=1,8),I=1,9)	
001199	RETURN	FILE 066
001200	END	
001201	C**** SUBROUTINE HPROP ****	HPROP000
001202	C**** THIS SUBROUTINE PROVIDES THE FOLLOWING HYDROGEN PROPERTIES DATA TO	HPROP001
001203	C**** THE MAIN PROGRAM:	HPROP002
001204	C**** SUCTION LINE SPNIC VELOCITY AS A FUNCTION OF TEMPERATURE AND	HPROP003
001205	C**** PRESSURE	HPROP004
001206	C**** INDUCER INLET SPECIFIC VOLUME AS A FUNCTION OF TEMPERATURE AND	HPROP005
001207	C**** PRESSURE	HPROP006
001208	C**** PUMP INLET SPECIFIC VOLUME AS A FUNCTION OF TEMPERATURE AND	HPROP007
001209	C**** PRESSURE	HPROP008
001210	C	HPROP009
001211	SUBROUTINE HPROP(A,B,Y,X,KJ,K,C,JFLG,XMIN,XMAX)	
001212	DIMENSION X(30,50),Y(30,50),CP(2)	
001213	COMMON /PROP/ T(30,50),SV(30,50),H(30,50),S(30,50),N(30),P(30),	
001214	1AA(5,90),RHOX(90),D(9,8)	
001215	COMMON /SAT/ HSAT(25),PSAT(25),TSAT(25),SSAT(25),RHOSAT(25),	
001216	1EMPT(25),EMPS(25),EMTS(25),EMHS(25),EMRHS(25),EMTP(25),	
001217	2HSATV(25),SSATV(25),RHOSTV(25),EMHLP(25),EMHVP(25),EMSLP(25),	
001218	3EMSV(25),EMROL(25),EMROVP(25),EMPH(25)	
001219	C	HPROP012
001220	C**** P IS THE PRESSURE ARRAY	HPROP013
001221	C**** X IS THE INDEPENDENT PROPERTY ARRAY	HPROP014
001222	C**** Y IS THE DEPENDENT PROPERTY ARRAY	HPROP015
001223	C**** N IS THE OF DATA POINTS FOR EACH ISOBAR ARRAY	HPROP016
001224	C**** A IS PRESSURE	HPROP017
001225	C**** R IS THE SECOND INDEPENDENT VARIABLE	HPROP018
001226	C**** KJ DETERMINES THE INDEPENDENT PARAMETER USED	HPROP019
001227	C**** KJ=1,B IS TEMPERATURE	HPROP020
001228	C**** KJ NOT=1,B IS SPECIFIC VOLUME,ENTHALPY,ENTROPY OR SONIC VELOCITY	HPROP021
001229	C**** K DETERMINES THE DEPENDENT PARAMETER REQUESTED	HPROP022
001230	C**** K=1,C IS TEMPERATURE	HPROP023
001231	C**** K=2,C IS SPECIFIC VOLUME	HPROP024
001232	C**** K=3,C IS ENTHALPY	HPROP025
001233	C**** K=4,C IS ENTROPY	HPROP026
001234	C**** K=5,C IS SONIC VELOCITY	HPROP027
001235	C**** C IS THE REQUESTED DEPENDENT PROPERTY	HPROP028
001236	C**** D IS THE ARRAY OF EMPIRICAL CONSTANTS USED IN THE SATURATED	HPROP029
001237	C**** PRESSURE SUBPROGRAM SVSL	HPROP030
001238	C	HPROP031
001239	NSAT=22	
001240	JFLG=1	HPROP032
001241	I=0	HPROP033
001242	LIMIT=0	HPROP034
001243	C	HPROP035
001244	C**** SET XMIN=MINIMUM TABULATED PRESSURE	HPROP036
001245	C	HPROP037
001246	XMIN=P(1)	HPROP038
001247	C	HPROP039
001248	C**** SET XMAX=MAXIMUM TABULATED PRESSURE	HPROP040
001249	C	HPROP041
001250	XMAX=P(25)	HPROP042
001251	50 I=I+1	HPROP043
001252	C	HPROP044
001253	C**** SEARCH PRESSURE TABLE FOR VALUE CORRESPONDING TO A	HPROP045
001254	C	HPROP046
001255	IF(P(I)-A) 60,80,55	HPROP047
001256	C	HPROP048

001257	C**** TABULATED PRESSURE IS GREATER THAN A,TEST FOR MINIMUM TABLE VALUE	HPROP049
001258	C	HPROP050
001259	55 IF (I-1) 200,200,150	HPROP051
001260	C	HPROP052
001261	C**** TABULATED PRESSURE IS LESS THAN A,TEST FOR MAXIMUM TABLE VALUE	HPROP053
001262	C	HPROP054
001263	60 IF (I-25) 50,250,250	HPROP055
001264	C	HPROP056
001265	C**** TABULATED PRESSURE=A	HPROP057
001266	C	HPROP058
001267	80 M=N(I)	HPROP059
001268	C	HPROP060
001269	C**** SET XMIN=MINIMUM TABULATED INDEPENDENT PROP.	HPROP061
001270	C	HPROP062
001271	XMIN=X(I,1)	HPROP063
001272	C	HPROP064
001273	C**** SET XMAX=MAXIMUM TABULATED INDEPENDENT PROP.	HPROP065
001274	C	HPROP066
001275	XMAX=X(I,M)	HPROP067
001276	J=0	HPROP068
001277	85 J=J+1	HPROP069
001278	C	HPROP070
001279	C**** SEARCH INDEPENDENT PROPERTY TABLE FOR VALUE CORRESPONDING TO B	HPROP071
001280	C	HPROP072
001281	IF (X(I,J)-B) 95,100,90	HPROP073
001282	C	HPROP074
001283	C**** TABULATED PROP. IS GREATER THAN B,TEST FOR MINIMUM TABLE VALUE	HPROP075
001284	C	HPROP076
001285	90 IF (J-1) 300,300,110	HPROP077
001286	C	HPROP078
001287	C**** TABULATED PROP. IS LESS THAN B,TEST FOR MAXIMUM TABLE VALUE	HPROP079
001288	C	HPROP080
001289	95 IF (J-M) 85,350,350	
001290	C	HPROP082
001291	C**** TABULATED PROP=B,SET C=TABULATED VALUE	HPROP083
001292	C	HPROP084
001293	100 C=Y(I,J)	HPROP085
001294	GO TO 500	HPROP086
001295	C	HPROP087
001296	C**** INTERPOLATE ALONG ISOBAR I FOR C	HPROP088
001297	C	HPROP089
001298	110 C=Y(I,J-1)+(B-X(I,J-1))/(X(I,J)-X(I,J-1))*(Y(I,J)-Y(I,J-1))	HPROP090
001299	GO TO 500	HPROP091
001300	C	HPROP092
001301	C**** A LIES BETWEEN TWO TABULATED ISOBARS,INTERPOLATE ALONG EACH ISOBAR	HPROP093
001302	C**** FOR PROPER B	HPROP094
001303	C	HPROP095
001304	150 NM=I-1	HPROP096
001305	DO 180 IK=NM,I	HPROP097
001306	M=N(IK)	HPROP098
001307	JK=IK-I+2	HPROP099
001308	J=0	
001309	C	HPROP101
001310	C**** SET XMIN=MINIMUM TABULATED INDEPENDENT PROP.	HPROP102
001311	C	HPROP103
001312	XMIN=X(IK,1)	HPROP104
001313	C	HPROP105
001314	C**** SET XMAX=MAXIMUM TABULATED INDEPENDENT PROP.	HPROP106
001315	C	HPROP107
001316	XMAX=X(IK,M)	HPROP108

122

001317	155 J=J+1	HPROP109
001318	C	HPROP110
001319	C**** SEARCH INDEPENDENT PROPERTY TABLE FOR VALUE CORRESPONDING TO B	HPROP111
001320	C	HPROP112
001321	IF (X(IK,J)-B) 165,170,160	HPROP113
001322	C	HPROP114
001323	C**** TABULATED PROP. IS GREATER THAN B, TEST FOR MINIMUM TABLE VALUE	HPROP115
001324	C	HPROP116
001325	160 IF (J-1) 300,300,550	HPROP117
001326	C	HPROP118
001327	C**** TABULATED PROP. IS LESS THAN B, TEST FOR MAXIMUM TABLE VALUE	HPROP119
001328	C	HPROP120
001329	165 IF (J-N(IK)) 155,510,510	HPROP121
001330	C	HPROP122
001331	C**** TABULATED VALUE=B, SET CP=TABULATED VALUE	HPROP123
001332	C	HPROP124
001333	170 CP(JK)=Y(IK,J)	HPROP125
001334	GO TO 180	HPROP126
001335	C	HPROP127
001336	C**** MAXIMUM TABULATED VALUE IS LESS THAN B, IF ISOBAR LESS THAN A SET	HPROP128
001337	C**** LIMIT=1 AND CONTINUE, IF ISOBAR GREATER THAN A SET ERROR FLAG AND	HPROP129
001338	C**** RETURN	HPROP130
001339	C	HPROP131
001340	510 IF (JK-1) 520,520,350	HPROP132
001341	520 LIMIT = 1	HPROP133
001342	GO TO 180	
001343	C	HPROP135
001344	C**** CHECK LIMIT SET=1	HPROP136
001345	C	HPROP137
001346	550 IF (LIMIT) 175,175,600	HPROP138
001347	C	HPROP139
001348	C**** LIMIT=0, NORMAL INTERPOLATION SEQUENCE ON ISOBAR	HPROP140
001349	C	HPROP141
001350	175 CP(JK)=Y(IK,J-1)+(B-X(IK,J-1))/(X(IK,J)-Y(IK,J-1))*	HPROP142
001351	1(Y(IK,J)-Y(IK,J-1))	HPROP143
001352	180 CONTINUE	HPROP144
001353	C	HPROP145
001354	C**** NORMAL INTERPOLATION FOR C	HPROP146
001355	C	HPROP147
001356	C=CP(1)+(A-P(I-1))/(P(I)-P(I-1))*(CP(2)-CP(1))	HPROP148
001357	GO TO 500	HPROP149
001358	C	HPROP150
001359	C**** LIMIT=1, CHECK FOR TEMPERATURE AS INDEPENDENT PROPERTY	HPROP151
001360	C	HPROP152
001361	600 IF (KJ.EQ.1) GO TO 610	
001362	IF (KJ.EQ.3) GO TO 611	
001363	IF (KJ.EQ.4) GO TO 612	
001364	GO TO 350	
001365	C	HPROP154
001366	C**** TEMPERATURE ,S INDEPENDENT PROPERTY, FIND CORRESPONDING VAPOR	HPROP155
001367	C**** PRESSURE	HPROP156
001368	C	HPROP157
001369	610 CALL SPLNT(NSAT,TSAT,PSAT,EMPT,R,PSL)	
001370	GO TO 615	
001371	611 CALL SPLNT(NSAT,HSAT,PSAT,EMPH,R,PSL)	
001372	GO TO 615	
001373	612 CALL SPLNT(NSAT,SSAT,PSAT,EMPS,R,PSL)	
001374	615 GO TO (620,620,630,640,645),K	
001375	C	HPROP160
001376	C**** FIND STAURATED LIQUID SPEC. VOL. CORRESPONDING TO TEMPERATURE=B	HPROP161

133

001377	C		HPROP162
001378		620 CALL SPLNT(NSAT,PSAT,RHOSAT,EMROL,PSL,CP(2))	
001379		CP(2)=1./CP(2)	
001380		GO TO 650	HPROP164
001381	C		HPROP165
001382	C****	FIND SATURATED LIQUID ENTHALPY CORRESPONDING TO TEMPERATURE=B	HPROP166
001383	C		HPROP167
001384		630 CALL SPLNT(NSAT,PSAT,HSAT,EMHLP,PSL,CP(2))	
001385		GO TO 650	HPROP169
001386	C		HPROP170
001387	C****	FIND SATURATED LIQUID ENTROPY CORRESPONDING TO TEMPERATURE=B	HPROP171
001388	C		HPROP172
001389		640 CALL SPLNT(NSAT,PSAT,SSAT,EMSLP,PSL,CP(2))	
001390		GO TO 650	HPROP174
001391	C		HPROP175
001392	C****	SET SATURATED LIQUID SONIC VELOCITY	HPROP176
001393	C		HPROP177
001394		645 CP(2)=3940.	HPROP178
001395	C		HPROP179
001396	C****	INTEPOLATE FOR CP ON ISOBAR GREATER THAN A	HPROP180
001397	C		HPROP181
001398		650 CP(1)=Y(I,J-1)+(B-X(I,J-1))*(Y(I,J)-Y(I,J-1))/(X(I,J)-X(I,J-1))	HPROP182
001399	C		HPROP183
001400	C****	INTEPOLATE FOR C USING SATURATED CONDITIONS	HPROP184
001401	C		HPROP185
001402		C=CP(1)+(A-P(I))*(CP(2)-CP(1))/(PSL-P(I))	HPROP186
001403		GO TO 500	HPROP187
001404	C		HPROP188
001405	C****	MINIMUM TABULATED PRESSURE IS GREATER THAN A,SET ERROR FLAG	HPROP189
001406	C		HPROP190
001407		200 JFLG=2	HPROP191
001408		GO TO 500	HPROP192
001409	C		HPROP193
001410	C****	MAXIMUM TABULATED PRESSURE IS LESS THAN A,SET ERROR FLAG	HPROP194
001411	C		HPROP195
001412		250 JFLG=3	HPROP196
001413		GO TO 500	HPROP197
001414	C		HPROP198
001415	C****	MINIMUM TABULATED INDEPENDENT PROP. IS GREATER THAN B,SET ERROR	HPROP199
001416	C****	FLAG	HPROP200
001417	C		HPROP201
001418		300 JFLG=4	HPROP202
001419		GO TO 500	HPROP203
001420	C		HPROP204
001421	C****	MAXIMUM TABULATED INDEPENDENT PROP. IS LESS THAN B,SET ERROR FLAG	HPROP205
001422	C		HPROP206
001423		350 JFLG=5	HPROP207
001424		500 RETURN	HPROP208
001425		END	HPROP20
001426		NTABS 10	
001427		TAPE 1,'B' . KEN KIRK 'S TAPE	
001428		TAPE 2,'K' . OUTPUT TAPE FOR KIRK.	
001429		READ 5	
001430		PRINT 6	
001431		END	

CHRONOLOGY FOR CEL INDUCER TEST

EXPERIMENTAL PLAN I

08 DECEMBER 1971

135

I. PRE-OPERATIONAL PHASE

During this phase verification will be made of the Test Cell "C" readiness to conduct a test using the CEL and Electric Drive Systems. Facility setup checklists will be reviewed, personnel locations will be determined, the Operators communication net will be checked, and systems switched to LCR control. Valves and systems necessary for the test will then be operated, room inerting will be started, and a voltage calibration performed.

- A. SETUP CHECKLISTS HAVE BEEN REVIEWED AND APPROVED.
- B. REPORT ON STATUS OF PERSONNEL IN TEST CELL "C" AREA.
- C. CHECK THE OPERATORS NET.
- D. HAVE THE REQUIRED SYSTEMS SWITCHED TO LCR CONTROL.
- E. EXERCISE THE VALVES IN THE ELECTRIC PUMP ROOM, CEL AND HIGH PRESSURE ROOM.
- F. BEGIN INERTING THE TEST CELL.

12007 Turn off the HPR, EPR and MER fans.
12012 Close Q-113.
12022 Pressurize the room inerting header
(Bottles 13, 14, 15, and 16).

a. Open Q-213 CEL valve.

12140 Begin inerting the following areas:

HPR (G-451/452)
CEL (G-456)
EPR (G-455)

- a. Report when concentrations reach 3%.
- b. Maintain O₂ concentrations between 3 and 5%.

G. CHECK THE SHUTDOWN CHAIN.

12167 Bypass all the inputs to the Shutdown Chain.
12169 Reset the Shutdown Chain.
12172 Switch the following valves to Normal:

C-221
C-8

12176 Close C-221.
12210 C-8 switched to override.
12214 Push the Emergency Shutdown Button.

a. Report valve action.

12221 Reset the Shutdown Chain.
12228 Switch C-8 to POSITION Control and Close.
12232 Switch C-231 to POSITION Control and Close.
12240 Switch the shutdown outputs to Override.
12278 Close Q-213.

H. PERFORM A VOLTAGE CALIBRATION.

12681-12781 Calibration interval.
13201-13301 Recalibration interval.

II. PRESSURIZATION, CHILLDOWN, OVERSPEED TRIP CHECK

During this phase, the helium and hydrogen headers will be pressurized, Dewar 4/5 will be pressurized, the CEL flow loop will be chilled and soaked, and the overspeed inputs to the shutdown chain will be checked. K-3 and K-130 will be calibrated at a dewar pressure of 40 psig.

A. PROCEED WITH HEADER PRESSURIZATION

14676 Report on room inerting.
14679 Open K-50, K-153.
14686 Open L-50.
14691 Close Q-120, Q-150, Q-101 thru Q-112.

1.37

14718 Pressurize the helium header.

a. QP-20: 3050 psig.

14764 Pressurize the hydrogen header.

a. QP-30: 3050 psig.

B. PROCEED WITH THE CHILLDOWN

14927 Issue the ready order.

14930 Close K-153, K-262, K-403, C-221.

14983 Open K-2, K-62.

15003 Open C-214, K-3, C-8, C-231.

15050 Select Dewar 5 pressure feedback.

15055 In K-53 PRESSURE Control, establish
40 psig in Dewar 5.

15186 Use C-111 to chill CT-111.

a. Monitor CF-6.

15371 When CT-3 is chilled, close K-3.

15492 Open K-130.

15900 When CT-111 is chilled, set C-111 to
maintain CP-9 < 60 psig.

15907 Use C-106 to chill CT-106.

a. Vary KF-130 between 1 and 5 lbs/sec.

15978 When CT-106 is chilled, Open C-106.

16021 Close K-130.

16055 When CP-8 is less than 10 psig Close C-106,
C-214; Open C-4.

a. PMP: Report CP-8.

16122 Open K-130.

16170 Open C-111.

16178 Use C-8 to chill the pump.

a. Vary KF-130 between 1 and 5 lbs/sec.

178

- 16253 When CT-220 is chilled, open C-221.
- a. PMP: Report CT-220.
- 16347 Close C-231.
- 16418 At TD command, set C-111 to maintain CP-9 < 60 psig.
- 16527 Start 900 second timer.
- 16537 Switch K-53 to POSITION Control and Close.
- 16575 Close K-62.
- 16580 Open K-153.

C. PROCEED WITH STARTUP OF A.C. MOTOR.

- 16664 Report electric drive alarm status.
- 16667 Start synchronous motor.
- 16742 Start blowers.
- 16750 Establish and maintain unity power factor. (120 Amps)
- 16800 Increase D. C. motor field to 13 amps, then decrease to 5 amps.
- 16810 Raise and lower armature voltage.
- 16890 D. C. motor field reduced to 5 amps.

D. PROCEED WITH OVERSPEED TRIP CHECK.

- 17460 Set the overspeed trip pot to 105 divisions (4,000 rpm).
- 17472 Raise synchronous motor field to 120 amps.
- 17474 Raise D. C. motor field to 13 amps.
- 17492 Close K-153.
- 17498 Select Dewar 5 pressure feedback.
- 17510 Open K-62.
- 17514 In K-53 PRESSURE Control, establish 40 psig in Dewar 5.
- 17556 Switch the following shutdown output to NORMAL:

Speed Rate

- 17566 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
JP-101/201	CP-505

17583 Open K-3.
 17594 Close K-130.
 17607 Open C-11.
 17624 Close C-111.
 17637 Open K-161.
 17654 Open C-221.
 17656 Close C-231.
 17664 Use C-8 to chill the pump.
 17666 Set C-8 to 50%. (Q/N = .22)
 17673 Set C-106 to 30%.
 17690 When the pump is chilled, close the
 D.C. breakers.

a. PMP: Report pump chill.

17708 Activate CT-507 input to the shutdown chain.
 17716 Speed increased to 3,000 rpm.
 17785 Speed decreased to 0 rpm.
 17860 Dewar transfer.
 18000 Remove pressure off line.
 18900 Entry on MDB for oil lube temperature
 check and leak surveillance.
 19340 Re-entry crew returned to LCR.
 19504 Set the overspeed trip pot to 105 divisions
 (4,000 rpm).
 19508 Raise synchronous motor field to 120 amps.
 19510 Raise D.C. motor field to 13 amps.
 19516 Close K-153.
 19520 Select Dewar 4 pressure feedback.
 19525 Open K-61.
 19530 In K-53 PRESSURE Control, establish
 40 psig in Dewar 4.
 19540 Switch the following shutdown output to
 NORMAL:

Speed Rate

19550 Activate the following inputs to the shutdown
 chain:

UQ-2	CP-220
JP-101/201	CP-505

19556	Open K-3.
19560	Close K-130.
19563	Open C-12.
19578	Close C-111.
19580	Open K-162.
19586	Open C-221.
19590	Close C-231.
19597	Use C-8 to chill the pump.
19598	Set C-8 to 50%. (Q/N = .22)
19638	Set C-106 to 30%.
19684	When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

19690	Activate CT-507 input to the shutdown chain.
19699	Speed increased to 3,000 rpm.
19780	Reset the shutdown chain.
19781	Bypass UQ-2 shutdown input.
19782	Activate UQ-3 shutdown input.
19840	In MANUAL Control, increase speed to produce overspeed trip (5,500 rpm).
19848	When speed is zero, open the D. C. breakers.
19854	Bypass all the shutdown inputs.
19858	Reset the shutdown chain.
19861	Close C-106.
19867	Open K-130.
19892	Close K-3.
19907	When KF-130 is stable, close K-130 in 10% steps.
19960	60%
19970	50%
19980	40%
20000	30%
20010	20%
20030	10%
20045	5%
20055	0%

20058	Open and close K-3 in 10% steps.
20070	10%
20080	20%
20090	30%
20100	40%
20110	50%
20120	60%
20130	70%
20135	80%
20145	90%
20150	100%
20205	0%
20207	Open K-3.
20211	Use C-111 to maintain CP-9 between 60 and 100 psig.
20220	Close C-12.
20224	Close K-162.
20238	Switch K-53 to POSITION Control and close.
20250	Close K-61.
20255	Open K-153.
20262	Decrease D. C. motor field to less than 5 amps.
20267	Switch the shutdown outputs to OVERRIDE.

III.

GREEN RUN

During this phase, the pump will be operated along a Q/N of .22 to a maximum speed of 19,000 rpm.

A. PROCEED WITH THE GREEN RUN.

20960	Issue the ready order.
20966	Set the overspeed trip pot to 550 divisions (21,000 rpm).
20982	Raise the synchronous motor field to 120 amps.
20987	Raise the D. C. motor field to 13 amps.
20988	Close K-153.
21004	Select Dewar 4 pressure feedback.
21013	Open K-61.
21024	Switch the following shutdown outputs to NORMAL:
	Speed Rate
	C-221

21031 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-62

21040 In K-53 PRESSURE Control, establish 40 psig in Dewar 4.

21060 Use C-106 to chill CT-106.

21090 At CTO command, Open C-12; Close C-111.

21100 Open K-162.

21107 Open C-221.

21108 Close C-231.

21112 Set C-8 to 50% (Q/N = .22).

21176 When the pump is chilled, close the D. C. breakers.

 a. PMP: Report pump chill.

21182 Activate the following inputs to the shutdown chain:

 D. C. Breakers
 CT-507

21240 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

21280 Meter not indicating true Q/N.

21350 Decrease speed to 0 rpm.

21360 Open D. C. breakers.

21370 Outputs to shutdown chain bypassed.

21375 Shutdown chain reset.

21380 Use C-111 to maintain CP-9 between 60 and 100 psig.

21385 Close C-12.

21395 Switch K-53 to POSITION Control and close.

21400 Close K-61.

21410 Open K-153.

21415 Decrease D. C. motor field to less than 5 amps.

21420 Switch the shutdown outputs to OVERRIDE.

21470 Data hold (UQ-1 giving false reading).

B. PROCEED WITH THE GREEN RUN.

- 22234 Set the overspeed trip pot to 550 divisions (21,000 rpm).
22240 Raise the synchronous motor field to 120 amps.
22244 Raise the D. C. motor field to 13 amps.
22248 Close K-153.
22252 Select Dewar 4 pressure feedback.
22256 Open K-61.
22271 Switch the following shutdown outputs to NORMAL:

Speed Rate
C-221

- 22276 Activate the following inputs to the shutdown chain:

UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-62

- 22290 In K-53 PRESSURE Control, establish 40 psig in Dewar 4.
22310 Use C-106 to chill CT-106.
22328 At CTO command Open C-12; Close C-111.
22336 Open K-162.
22343 Open C-221.
22346 Close C-231.
22350 Set C-8 to 50% (Q/N = .22).
22434 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

- 22476 Activate the following inputs to the shutdown chain:

D. C. Breakers
CT-507

22540	In MANUAL Control, establish 10,000 rpm at a Q/N = .22.
22570	Use C-8 to decrease Q/N = .15.
22600	Use C-8 to increase Q/N = .25.
22604	Switch Speed Rate Control to HOLD.
22612	Set Speed Rate pot to 80 divisions (400 rpm/sec).
22710	Remain in Manual Control and demand 19,000 rpm.
22770	Bypass the following shutdown inputs: CT-507
22780	Decrease speed to zero.
22781	Open D. C. breakers.
22796	Bypass all the shutdown inputs.
22797	Reset the shutdown chain.
22800	Use C-111 to maintain CP-9 between 60 and 100 psig.
22804	Close C-12.
22810	Switch K-53 to POSITION Control and close.
22824	Close K-61.
22833	Open K-153.
22837	Decrease D. C. motor field to less than 5 amps.
22848	Switch the shutdown outputs to OVERRIDE.
22880	Data hold and lunch break.
23000	Liquid transfer.

IV.

BREAKER TRIP COASTDOWN

During this phase, a pump operating point of 19,000 rpm and Q/N of .22 will be established. Speed will be ramped to 17,000 rpm at various rates. When it is determined which rate gives a D. C. Motor Armature current close to 0 amps, 19,000 rpm will again be established, a down-ramp initiated, then the D. C. breakers opened to initiate an emergency shutdown. The breakers will be opened when the armature current is close to zero.

This phase will provide the non-powered coastdown time required for the D. C. Motors with the pump providing a load.

A. PROCEED WITH COASTDOWN

- 28570 Rechill system and bring Dewar 5
back on line.
- 28630 Close K-153.
- 28638 Select Dewar 5 pressure feedback.
- 28643 Open K-62.
- 28650 In K-53 PRESSURE Control, establish
70 psig in Dewar 5.
- 28710 Use C-111 to rechill system.
- 29002 Set the overspeed trip pot to 550 divisions
(21,000 rpm).
- 29004 Raise the synchronous motor field to 120 amps.
- 29010 Raise the D. C. motor field to 13 amps.
- 29020 In K-53 PRESSURE Control, establish
70 psig in Dewar 5.
- 29026 Switch the following shutdown outputs to
NORMAL:
- Speed Rate
- 29031 Activate the following inputs to the shutdown
chain:
- | | |
|------------|--------|
| UQ-2 | CP-505 |
| UQ-3 | CP-220 |
| JP-101/201 | KP-61 |
- 29050 Use C-106 to chill CT-106.
- 29076 At CTO command Open C-11; Close C-111.
- 29096 Open K-161.
- 29100 Open C-221.
- 29101 Close C-231.
- 29106 Set C-8 to 50% (Q/N = .22).
- 29116 When the pump is chilled, close the
D. C. breakers.
- a. PMP: Report pump chill.
- 29130 Breaker two opens on close command.
- 29135 Use C-111 to maintain CP-9 between
80 - 90 psig.

29140 Close C-11.
29250 Re-entry for checking breakers.
30984 Pressure reduced on lines to standby
condition.
33052 Set the overspeed trip pot to 550 divisions
(21,000 rpm).
33060 Raise the synchronous motor field to 120 amps.
33064 Raise the D. C. motor field to 13 amps.
33068 Close K-153.
33070 Select Dewar 5 pressure feedback.
33081 Open K-62.
33087 In K-53 PRESSURE Control, establish
50 psig in Dewar 5.
33091 Switch the following shutdown outputs to
NORMAL:

Speed Rate

33098 Activate the following inputs to the shutdown
chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-61

33135 Use C-106 to chill CT-106.
33155 At CTO command Open C-11; Close C-111.
33180 Open K-161.
33183 Open C-221.
33184 Close C-231.
33188 Set C-8 to 50% (Q/N = .22).
33438 When the pump is chilled, close the
D. C. breakers.

a. PMP: Report pump chill.

33452 Activate the following inputs to shutdown
chain:

D. C. Breakers
CT-507

147

33500	In MANUAL Control, establish 10,000 rpm at a Q/N = .22.
33510	Switch C-106 to AUTO.
33516	At CTO command, activate the following inputs to the shutdown chain:
	Q/N High
	Q/N Low
33528	Switch to SPEED Control.
33530	Oscillations in SPEED Control.
33630	Switch to SPEED Control (still have oscillations).
33700	Increase speed to 19,000 rpm in MANUAL Control.
33754	Demand 17,000 rpm in MANUAL Control.
33765	Increase speed to 19,000 rpm in MANUAL Control.
33789	When armature current is zero, open the D. C. breakers.
33806	Bypass all the shutdown inputs.
33808	Reset the shutdown chain.
33810	After reset, set MANUAL Speed Control pot to 50 divisions.
33818	When speed is zero, switch C-106 to RESET.
33834	Use C-111 to maintain CP-9 between 60 and 100 psig.
33836	Close C-11.
33843	Switch K-53 to POSITION Control and close.
33857	Close K-62.
33863	Open K-153.
33866	Decrease D. C. motor field to less than 5 amps.
33870	Switch the shutdown outputs to OVERRIDE.

V. K-3 MAPPING

During this phase, K-3 will be operated with dewar pressures of 60 and 80 psig. The D. C. Breakers will be open and flow will be to the flare through C-106 and C-111. This phase will investigate the ability of K-3 to provide the necessary ΔP 's for cavitation testing.

A. PROCEED WITH K-3 MAPPING.

33940	Close K-153.
33945	Select Dewar 5 pressure feedback.
33950	Open K-62.
33960	Close K-162.
33990	In K-53 PRESSURE Control, establish 60 psig in Dewar 5.
34030	Open C-11, Close C-111.
34138	Proceed with K-3 mapping.
34268	Increase KP-62 to 80 psig.
34272	Proceed with K-3 mapping.
34376	Use C-111 to maintain CP-9 between 80 and 100 psig.
34400	Close C-11.
34408	Switch K-53 to POSITION Control and close.
34418	Close K-62.
34427	Open K-153.
34433	Open K-161.

VI. FREQUENCY RESPONSE MEASUREMENTS

During this phase, the pump speed will be increased to 19,000 rpm at a Q/N of .25. C-231 will be set to maintain CP-220 at 45 psig and C-221 will be closed. Frequency response measurements will then be made on Manual VGA Control. C-8 will be set to maintain a Q/N of .25 and the pump speed decreased to zero.

A. PROCEED WITH THE FREQUENCY RESPONSE MEASUREMENTS.

34580	Dewar transfer.
35945	Patch the oscillator to Manual VGA loop.
35950	Set the oscillator amplitude to 2 volts.
35956	Set the overspeed trip pot to 550 divisions (21,000 rpm).
35959	Raise the synchronous motor field to 120 amps.
35968	Raise the D. C. motor field to 13 amps.
35986	Close K-153.
35990	Select Dewar 4 pressure feedback.
35994	Open K-61.

- 36009 Switch the following shutdown outputs to NORMAL:
- Speed Rate
C-221
- 36014 Activate the following inputs to the shutdown chain:
- UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-62
- 36030 In K-53 PRESSURE Control, establish 50 psig in Dewar 4.
- 36031 Use C-106 to chill CT-106.
- 36070 At CTO command Open C-12; Close C-11.
- 36073 Open K-162.
- 36077 Open C-221.
- 36080 Close C-231.
- 36087 Set C-8 to 55% (Q/N = .25).
- 36161 When the pump is chilled, close the D. C. breakers.
- a. PMP: Report pump chill.
- 36166 Activate the following inputs to the shutdown chain:
- D. C. Breakers
CT-507
- 36190 In MANUAL Control, establish 10,000 rpm at a Q/N = .25.
- 36196 Switch C-106 to AUTO.
- 36200 At CTO command, activate the following inputs to the shutdown chain:
- Q/N High
Q/N Low
- 36206 Open C-231.
- 36226 Close C-221.

36250	Use C-231 to establish and maintain 45 psig at CP-220.
36260	Establish 19,000 rpm in Manual Control.
36266	Use C-8 to maintain Q/N = .25.
36302	Proceed with frequency response measurements. (Manual VGA)
36474	Unpatch the oscillator from Manual VGA loop.
36504	Open C-221.
36506	Close C-231.
36511	Bypass the following shutdown inputs:
	CT-507
	Q/N High
	Q/N Low
36518	Switch C-106 to RESET.
36523	Decrease speed to zero.
36531	Open the D. C. breakers.
36543	Bypass all the shutdown inputs.
36547	Reset the shutdown chain.
36550	Use C-111 to maintain CP-9 between 60 and 100 psig.
36563	Close C-12.
36568	Switch K-53 to POSITION Control and close.
36572	Close K-61.
36576	Open K-153.
36580	Decrease D. C. motor field to below 5 amps.
36588	Switch the shutdown outputs to OVERRIDE.

VII. DEWAR 1 TO DEWAR 4/5 LH₂ TRANSFER

During this phase, Dewar 4/5 will be refilled by transferring LH₂ from Dewar 1.

A. PROCEED WITH THE LH₂ TRANSFER.

37120	Issue the ready order.
37122	Open L-251.
37130	Close L-261, L-153.
37136	Open L-61, L-301, L-330.
37158	Open L-331, X-301.
37191	Close K-401.

37210	Use K-161/162 to vent Dewar 4/5.
37235	Use L-53 in POSITION Control to establish and maintain 30 psig in Dewar 1.
37266	When LP-61 is greater than KP-61/62, Open K-301/302.
37301	When LH ₂ transfer is complete, Close K-301/302.
41814	Transfer complete.

VIII.

FREQUENCY RESPONSE MEASUREMENTS

During this phase, the pump speed will be increased to 19,000 rpm at a Q/N of .25. C-231 will be set to maintain CP-220 at 45 psig and C-221 will be closed. Frequency response measurements will then be made on C-231 POSITION. C-8 will be set to maintain a Q/N of .25 and the pump speed decreased to zero.

A. PROCEED WITH THE FREQUENCY RESPONSE MEASUREMENTS.

42330	Patch the oscillator to C-231 POSITION.
42336	Set the oscillator amplitude to 1 volt.
42350	Set the overspeed trip pot to 550 divisions (21,000 rpm).
42362	Raise the synchronous motor field to 120 amps.
42372	Raise the D. C. motor field to 13 amps.
42377	Close K-153.
42384	Select Dewar 5 pressure feedback.
42388	Open K-62.
42440	Switch the following shutdown outputs to NORMAL:

Speed Rate
C-221

42450 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-61

42480 In K-53 PRESSURE Control, establish
50 psig in Dewar 5.
42590 Use C-106 to chill CT-106.
42610 At CTO command, Open C-11, Close C-111.
42616 Open K-161.
42624 Open C-221.
42626 Close C-231.
42634 Set C-8 to 60% (Q/N = .25).
42770 When the pump is chilled, close the
D.C. breakers.

a. PMP: Report pump chill.

42774 Activate the following inputs to the shutdown
chain:

D.C. Breakers
CT-507

42818 In MANUAL Control, establish 10,000 rpm
at a Q/N = .25.

42820 Switch C-106 to AUTO.

42828 At CTO command, activate the following
inputs to the shutdown chain:

Q/N High
Q/N Low

42832 Open C-231 to 10%.

42846 Close C-221.

42858 Use C-231 to establish and maintain
45 psig at CP-220.

42920 In Manual Control, demand 19,000 rpm.

42925 Use C-8 to maintain Q/N = .25.

42978 Proceed with frequency response
measurements. (C-231 POSITION)

B. EMERGENCY SHUTDOWN CHECK

43143 Controlled shutdown CTO Manual from
19,000 rpm at approximately 2,000 rpm/sec.

IX. FREQUENCY RESPONSE MEASUREMENTS

During this phase, the pump speed will be increased to 16,000 rpm at a Q/N of .22. C-231 will be set to maintain CP-220 at 45 psig and C-221 will be closed. Frequency response measurements will then be made on C-8 POSITION. C-8 will be set to maintain a Q/N of .25 and the pump speed decreased to zero.

A. PROCEED WITH THE FREQUENCY RESPONSE MEASUREMENTS.

43550 Dewar transfer.
44293 Patch the oscillator to C-8 POSITION.
44303 Set the oscillator amplitude to 1 volt.
44312 Set the overspeed trip pot to 550 divisions (21,000 rpm).
44317 Raise the synchronous motor field to 120 amps.
44334 Raise the D. C. motor field to 13 amps.
44340 Close K-153.
44344 Select Dewar 4 pressure feedback.
44348 Open K-61.
44362 Switch the following shutdown outputs to NORMAL:

Speed Rate
C-221

44366 Activate the following inputs to the shutdown chain:

UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-62

44380 In K-53 PRESSURE Control, establish 50 psig in Dewar 4.
44395 Use C-106 to chill CT-106.
44410 At CTO command Open C-12, Close C-111.
44416 Open K-162.
44418 Open C-221.
44426 Close C-231.
44434 Set C-8 to 55% (Q/N = .22).

- 44510 When the pump is chilled, close the D.C. breakers.
- a. PMP: Report pump chill.
- 44514 Activate the following inputs to the shutdown chain:
- D.C. Breakers
CT-507
- 44555 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.
- 44559 Switch C-106 to AUTO.
- 44563 At CTO command, activate the following inputs to the shutdown chain:
- Q/N High
Q/N Low
- 44576 Open C-231 to 50 pot divisions.
- 44584 Close C-221.
- 44586 Use C-231 to establish and maintain 45 psig at CP-220.
- 44638 In Manual Control, demand 16,000 rpm.
- 44640 Use C-8 to maintain Q/N = .22.
- 44672 Proceed with frequency response measurements. (C-8 POSITION)

B. EMERGENCY SHUTDOWN CHECK

- 44941 Controlled shutdown CTO Manual from 21,000 rpm at approximately 4,000 rpm/sec.
- 44961 Switch C-106 to RESET.
- 44967 Open the D.C. breakers.
- 44972 Bypass all the shutdown inputs.
- 44975 Reset the shutdown chain.
- 44978 Use C-111 to maintain CP-9 between 60 and 100 psig.
- 44982 Close C-12.
- 44984 Switch K-53 to POSITION Control and close.

45000	Close K-61.
45006	Open K-153.
45012	Decrease D. C. motor field to below 5 amps.
45014	Switch the shutdown outputs to OVERRIDE.

X. C-8 AND C-106 MAPPING

During this phase, a pump operating condition of 19,000 rpm and .22 Q/N will be established. C-231 will be set to maintain 50 psig at CP-220 and C-221 will be closed. C-8 POSITION will be increased to increase the Q/N to .35 or to C-8 maximum position. C-8 will then be closed to provide a Q/N of .10 and opened to a Q/N of .22. C-8 will be closed and C-106 opened simultaneously. C-106 will be mapped between a Q/N of approximately .15 (electrical clamp) to .10. C-8 will then be opened to provide a Q/N of .25 while C-106 is being closed. Pump speed will then be decreased to zero.

A. PROCEED WITH VALVE MAPPING.

45400	Dewar transfer.
45983	Set the overspeed trip pot to 550 divisions (21,000 rpm).
45994	Raise the synchronous motor field to 120 amps.
45997	Raise the D. C. motor field to 13 amps.
45998	Close K-153.
46004	Select Dewar 5 pressure feedback.
46007	Open K-62.
46020	Switch the following shutdown outputs to NORMAL:
	Speed Rate
	C-221
46024	Activate the following inputs to the shutdown chain:
	UQ-2 CP-220
	UQ-3 CP-505
	JP-101/201 KP-61
46040	In K-53 PRESSURE Control, establish 60 psig in Dewar 5.

1.56

46050 Use C-106 to chill CT-106.
46062 At CTO command, Open C-11, Close C-111.
46072 Open K-161.
46075 Open C-221.
46080 Close C-231.
46082 Set C-8 to 55% (Q/N = .22).
46113 When the pump is chilled, close the
D. C. breakers.

a. PMP: Report pump chill.

46117 Activate the following inputs to the shutdown
chain:

D. C. Breakers
CT-507

46150 In MANUAL Control, establish 10,000 rpm
at a Q/N = .22.

46153 Switch C-106 to AUTO.

46157 At CTO command, activate the following
inputs to the shutdown chain:

Q/N High
Q/N Low

46160 Open C-231 to 52 pot divisions.

46168 Close C-221.

46190 Use C-231 to maintain 50 psig at CP-220.

46250 In Manual Control, demand 19,000 rpm.

46253 Use C-8 to maintain Q/N = .22.

46340 Use C-8 to increase Q/N to .35 or the C-8
clamp. (Clamp at .32)

a. Use .02 increments.

46400 Use C-8 to decrease Q/N to .20.

a. Use .03 increments.

46406 Switch C-106 to RESET.

46410 Bypass Q/N Low.

157

46455 Use C-8 to decrease Q/N to .10.
 a. Use .03 increments.

46490 Use C-106 to increase Q/N to .25.
 (Clamp at .22)

46540 Close C-8.

46580 Use C-106 to decrease Q/N to .10.
 a. Use .01 increments.

46590 Open C-106 (Q/N = .15).
 a. Use .02 increments.

46630 Use C-8 to increase Q/N to .25.

46640 Close C-106.

46699 Switch C-106 to AUTO.

46704 Activate Q/N Low.

B. CONTROLLED SHUTDOWN

46723 CTO Manual from 19,000 rpm at
 approximately 4,000 rpm/sec.

46726 Open C-221.

46737 Bypass the following shutdown inputs:

CT-507
 Q/N High
 Q/N Low

46745 Close C-231.

46746 Switch C-106 to RESET.

46748 Open the D. C. breakers.

46750 Bypass all the shutdown inputs.

46756 Reset the shutdown chain.

46757 Use C-111 to maintain CP-9 between
 60 and 100 psig.

46764 Close C-11.

46768 Switch K-53 in POSITION Control and close.

46786 Close K-62.
46790 Open K-153.
46795 Decrease D.C. motor field to below
 5 amps.
46798 Switch the shutdown outputs to
 OVERRIDE.

XI. MINIMUM SHUTDOWN PHASE

46910



A. POST VOLTAGE CALIBRATION

47681-47781 Calibration Interval



END

159

CHRONOLOGY FOR CEL INDUCER TEST

EXPERIMENTAL PLAN I

10 DECEMBER 1971

160

I.

PRE-OPERATIONAL PHASE

During this phase verification will be made of the Test Cell "C" readiness to conduct a test using the CEL and Electric Drive Systems. Facility setup checklists will be reviewed, personnel locations will be determined, the Operators communication net will be checked, and systems switched to LCR control. Valves and systems necessary for the test will then be operated, room inerting will be started, and a voltage calibration performed.

- A. SETUP CHECKLISTS HAVE BEEN REVIEWED AND APPROVED.
- B. REPORT ON STATUS OF PERSONNEL IN TEST CELL "C" AREA.
- C. CHECK THE OPERATORS NET.
- D. HAVE THE REQUIRED SYSTEMS SWITCHED TO LCR CONTROL.
- E. EXERCISE THE VALVES IN THE ELECTRIC PUMP ROOM, CEL AND HIGH PRESSURE ROOM.
- F. BEGIN INERTING THE TEST CELL.

04787 Turn off the HPR, EPR and MER fans.
 04930 Close Q-113.
 04940 Pressurize the room inerting header
 (Bottles 13, 14, 15, and 16).

- a. Report QP-50 1650 psig.
- b. Open CEL valve, use Q-213.

04994 Begin inerting the following areas:
 HPR (G-451/452)
 CEL (G-456) (G-457)
 EPR (G-455)

- a. Report when concentrations reach 3%.
- b. Maintain O₂ concentrations between 3 and 5%.

B. CHECK THE SHUTDOWN CHAIN.

05012 Bypass all the inputs to the Shutdown Chain.
 05018 Reset the Shutdown Chain.
 05021 Switch the following valves to Normal:

C-221
 C-8

05026 Close C-221.
 05031 Switch C-8 to Q/N Control.
 05057 Push the Emergency Shutdown Button.

- a. Report valve action.

05062 Reset the Shutdown Chain.
 05074 Switch C-8 to POSITION Control and CLOSE.
 05075 Switch the shutdown outputs to Override.
 05076 Close C-221.

H. PERFORM A VOLTAGE CALIBRATION.

05222-05322 Calibration Interval.

II. PRESSURIZATION, CHILLDOWN, OVERSPEED TRIP CHECK

During this phase, the helium and hydrogen headers will be pressurized, Dewar 4/5 will be pressurized, the CEL flow loop will be chilled and soaked, and the overspeed inputs to the shutdown chain will be checked. K-3 and K-130 will be calibrated at a dewar pressure of 60 psig.

A. PROCEED WITH HEADER PRESSURIZATION.

07739 Report on room inerting.
07746 Open K-50, K-153.
07754 Open L-50.
07760 Close Q-120, Q-150, Q-101 thru Q-112.
07783 Pressurize the helium header.

a. QP-20: 2900 psig.

08023 Pressurize the hydrogen header with
Bottle 4.

a. QP-30: 3000 psig.

B. PROCEED WITH THE CHILLDOWN.

08020 Close K-153, K-262, K-403, K-402, C-221.
08058 Open K-2, K-62.
08087 Open C-214, C-8.
08113 Select Dewar 5 pressure feedback.
08150 In K-53 PRESSURE Control, establish
60 psig in Dewar 5.
08158 Open C-111.
08217 Use K-130 to chill KT-130.

a. Monitor CF-6.

08610 When KT-130 is chilled, close K-130.
08613 Close K-130.
08630 Open K-3 to chill CT-3 to 100°R.
08920 Close K-3.
08931 Switch K-53 to POSITION Control and close.
08940 Close K-62.
08946 Open K-153.
08960 Standby for re-entry (Hydrogen decay check).
09211 Valves closed on helium, nitrogen and
hydrogen header.
10120 Pressurize the hydrogen header with
Bottle 5.

a. QP-30: 3100 psig.

163

10213 Repressure helium and nitrogen header.

 a. QP-20: 2900 psig.

10278 Close K-153.

10280 Open K-62.

10295 In K-53 PRESSURE Control, establish
60 psig in Dewar 5.

10420 Open K-3 to chill CT-3 to 100°R.

11050 Close K-3.

11060 Use K-130 to chill KT-130.

 a. Monitor CF-6.

11086 When KT-130 is chilled, close K-130.

11424 Close K-130.

11527 When CP-8 is less than 10 psig,
Open C-231, C-4; Close C-214.

 a. PMP: Report CP-8.

11564 Use K-130 to chill the pump.

 a. CTO monitor CF-6.

12168 When CT-220 is chilled, Open C-221 and
Close C-231.

12251 Open C-231, Close C-221.

12390 Pump reported chilled.

12610 Use C-106 to chill CT-106.

12621 Open K-130.

12660 Close K-130

12670 Slowly Open K-3.

12771 When CT-111 is chilled, set C-111 to
maintain CP-9 < 70-80 psig.

12784 Start 900 second timer.

12791 Switch K-53 to Postion Control and Close.

12806 Close K-62.

12811 Open K-153.

12820 Open C-221, Close C-231.

C. PROCEED WITH STARTUP OF A.C. MOTOR.

12889 Report electric drive alarm status.
12902 Start synchronous motor.
12986 Start blowers.
12994 Establish and maintain unity power
factor. (120 Amps)
13020 Increase D.C. motor field to 13 amps,
then decrease to 5 amps.
13060 Raise and lower armature voltage.
13153 5 Amps set on D.C. field.

D. PROCEED WITH OVERSPEED TRIP CHECK.

13867 Set the overspeed trip pot to 105 divisions
(4,000 rpm).
13872 Raise synchronous motor field to 120 amps.
13876 Raise D.C. motor field to 13 amps.
13886 Select Dewar 5 pressure feedback.
13888 Close K-153.
13891 Open K-62.
13896 In K-53 PRESSURE Control, establish
40 psig in Dewar 5.
13944 Switch the following shutdown output to
NORMAL:

Speed Rate

13948 Activate the following inputs to the shutdown
chain:

UQ-2 CP-220
JP-101/201 CP-505

13960 Open K-3.
13963 Close K-130.
13967 Open C-11.
13974 Close C-111.
13982 Open K-161.
14000 Open C-221.
14001 Close C-231.
14008 Use C-8 to chill the pump.

14020	Set C-8 to 55%. (Q/N = .22)
14068	Set C-106 to 20%.
14214	When the pump is chilled, close the D.C. breakers.
	a. PMP: Report pump chill.
14220	Activate CT-507 input to the shutdown chain.
14280	In MANUAL Control, increase speed to produce overspeed trip (4,000 rpm).
14292	Reset the shutdown chain.
14294	Bypass UQ-2 shutdown input.
14295	Activate UQ-3 shutdown input.
14303	In MANUAL Control, increase speed to produce overspeed trip (4,000 rpm). (No trip).
14444	When speed is zero, open the D.C. breakers.
14452	Bypass all the shutdown inputs.
14456	Reset the shutdown chain.
14460	Close C-106.
14477	Use C-111 to maintain CP-9 between 60 and 100 psig.
14481	Close C-11.
14494	Close K-161.
14508	Switch K-53 to POSITION Control and close.
14520	Close K-62.
14525	Open K-153.
14528	Decrease D. C. motor field to less than 5 amps.
14531	Switch the shutdown outputs to OVERRIDE.

III. SPEED CONTROL FREQUENCY RESPONSES

A. PROCEED WITH THE GREEN RUN

15424	Set the overspeed trip pot to 105 divisions (4,000 rpm).
15432	Raise the synchronous motor field to 120 amps.
15434	Raise the D.C. motor field to 13 amps.
15438	Close K-153.

15443 Select Dewar 5 pressure feedback.
15447 Open K-62.
15453 In K-53 PRESSURE Control, establish
40 psig in Dewar 5.
15458 Switch the following shutdown outputs to
NORMAL:

Speed Rate
C-221

15476 Activate the following inputs to the shutdown
chain:

UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-61

15500 Open C-111 to maintain CF-6 at 5 lb/sec.
15680 Use C-106 to chill CT-106.
15970 Dewar transfer.
16464 Patch the oscillator to the speed loop.
16488 Set the oscillator amplitude to 1 volt.
16493 Set the overspeed trip pot to 105 divisions
(4, 000 rpm).
16498 Raise the synchronous motor field to 120 amps.
16597 Raise the D. C. motor field to 13 amps.
16601 Close K-153.
16605 Select Dewar 4 pressure feedback.
16616 Open K-61.
16622 In K-53 PRESSURE Control, establish
40 psig in Dewar 4.
16640 Switch the following shutdown outputs to
NORMAL:

Speed Rate
C-221

16644 Activate the following inputs to the shutdown
chain:

JP-101/201 CP-505
CP-220 KP-62

167

16656 Use C-106 to chill CT-106.
 16681 At CTO command Open C-12, Close C-111.
 16704 Open K-162.
 16708 Open C-221.
 16710 Close C-231.
 16714 Set C-8 to 60% (Q/N = .25).
 16870 When the pump is chilled, close the
 D.C. breakers.

 a. PMP: Report pump chill.

 16876 Activate the following inputs to the shutdown
 chain:

 D.C. Breakers
 CT-507

 16939 Activate UQ-2 and UQ-3 inputs.
 16940 Set overspeed trip pot to 28,000 rpm
 (730 pot divisions).
 16945 In MANUAL Control, establish 10,000 rpm
 at a Q/N = .25.
 16947 At CTO command, activate the following
 inputs to the shutdown chain:

 Q/N High
 Q/N Low

 16950 Switch C-106 to AUTO.
 16951 Open C-231 to 60 pot divisions.
 16958 Close C-221.
 16963 Use C-231 to establish and maintain 60 psig
 at CP-220.
 17030 Increase speed to 19,000 rpm.
 17070 CP-220 reduced to 12 psig.
 17160 Increase speed to 23,000 rpm.
 17170 Use C-8 to maintain Q/N = .25.
 17235 Increase speed to 26,000 rpm.
 17255 Controlled CTO-ESD (Dewar level in
 Dewar 4 not indicating properly).

IV.

SPEED CONTROL FREQUENCY RESPONSE

A. PROCEED WITH THE GREEN RUN

- 19776 Set the overspeed trip pot to 550 divisions (21,000 rpm).
- 19786 Patch oscillator input to speed loop.
- 19796 Set oscillator amplitude to 1 volt.
- 19800 Raise the synchronous motor field to 120 amps.
- 19805 Raise the D. C. motor field to 13 amps.
- 19806 Close K-153.
- 19810 Select Dewar 5 pressure feedback.
- 19815 Open K-62.
- 19820 In K-53 PRESSURE Control, establish 40 psig in Dewar 5.
- 19824 Switch the following shutdown outputs to NORMAL:

Speed Rate
C-221
- 19830 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-61
- 19920 Use C-106 to chill CT-106.
- 19942 At CTO command Open C-11, Close C-111.
- 19961 Open K-161.
- 19968 Open C-221.
- 19969 Close C-231.
- 19976 Set C-8 to 60% (Q/N = .25).
- 20102 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

20108	Activate the following inputs to the shutdown chain: D. C. Breakers CT-507
20155	In MANUAL Control, establish 10,000 rpm at a Q/N = .25.
20158	Switch C-106 to AUTO.
20162	At CTO command, activate the following inputs to the shutdown chain: Q/N High Q/N Low
20166	Open C-231 to 60 pot divisions.
20174	Close C-221.
20180	Use C-231 to establish and maintain 60 psig at CP-220.
20245	Increase speed to 19,000 rpm.
20262	Use C-8 to maintain Q/N = .25.
20268	Switch speed rate control to RUN.
20270	Switch to speed control.
20280	Frequency response measurements.
20438	Push shutdown button.
20454	Open D. C. breakers.
20461	Bypass all the shutdown inputs.
20464	Reset the shutdown chain.
20473	Switch C-106 to RESET.
20478	Use C-111 to maintain CP-9 between 60 and 100 psig.
20480	Close C-11.
20482	Switch K-53 to POSITION Control and close.
20496	Close K-62.
20501	Open K-153.
20506	Decrease D. C. motor field to less than 5 amps.
20510	Switch the shutdown outputs to OVERRIDE.
20630	Liquid transfer.

V.

FREQUENCY RESPONSE MEASUREMENTS

During this phase, the pump speed will be increased to 19,000 rpm at a Q/N of .25. C-231 will be set to maintain CP-220 at 20 psig and C-221 will be closed. Frequency response measurements will then be made on C-8 Q/N Control. C-8 will be set to maintain a Q/N of .25 and the pump speed decreased to zero.

A. PROCEED WITH THE FREQUENCY RESPONSE MEASUREMENTS.

21632 Patch the oscillator to C-8 Q/N.
21638 Set the oscillator amplitude to 1 volt.
21644 Set the overspeed trip pot to 550 divisions
(21,000 rpm).
21648 Raise the synchronous motor field to 120 amps.
21651 Raise the D.C. motor field to 13 amps.
21662 Close K-153.
21667 Select Dewar 4 pressure feedback.
21673 Open K-61.
21677 In K-53 PRESSURE Control, establish
40 psig in Dewar 4.
21688 Switch the following shutdown outputs to
NORMAL:

Speed Rate
C-221
C-8

21704 Activate the following inputs to the shutdown
chain:

UQ-2 CP-505
UQ-3 KP-62
JP-101/201
CP-220

21750 Use C-106 to chill CT-106.
21757 At CTO command Open C-12, Close C-111.
21767 Open K-162.
21773 Open C-221.
21776 Close C-231.
21781 Set C-8 to 60% (Q/N = .25).

171

- 21865 When the pump is chilled, close the D. C. breakers.
- a. PMP: Report pump chill.
- 21876 Activate the following inputs to the shutdown chain:
- D. C. Breakers
CT-507
- 21920 In MANUAL Control, establish 10,000 rpm at Q/N = .25.
- 21923 Switch C-106 to AUTO.
- 21927 At CTO command, activate the following inputs to the shutdown chain:
- Q/N High
Q/N Low
- 21933 Open C-231 to 70 pot divisions.
- 21935 Close C-221.
- 21940 Use C-231 to establish and maintain 20 psig at CP-220.
- 22010 Increase speed to 19,000 rpm.
- 22030 Switch to Speed Control.
- 22069 Switch to Q/N Control.
- 22078 Proceed with frequency response measurements. (C-8 Q/N)
- 22098 Unpatch the oscillator.
- 22203 Shutdown.
- 22240 Liquid transfer.

B. PUMP MAPPING AND SPEED CONTROL FREQUENCY RESPONSE.

- 23380 Patch the oscillator to the speed loop.
- 23387 Set the oscillator amplitude to 1 volt.
- 23396 Set the overspeed trip pot to 550 divisions (21,000 rpm).
- 23400 Raise the synchronous motor field to 120 amps.
- 23405 Raise the D. C. motor field to 13 amps.
- 23412 Close K-153.
- 23420 Select Dewar 5 pressure feedback.
- 23424 Open K-62.

- 23430 In K-53 PRESSURE Control, establish
40 psig in Dewar 5.
- 23442 Switch the following shutdown outputs
to NORMAL:
- Speed Rate
C-221
- 23446 Activate the following inputs to the
shutdown chain:
- | | |
|------------|--------|
| UQ-2 | CP-220 |
| UQ-3 | CP-505 |
| JP-101/201 | KP-61 |
- 23468 Use C-106 to chill CT-106.
- 23471 At CTO command Open C-11, Close C-111.
- 23484 Open K-161.
- 23488 Open C-221.
- 23490 Close C-231.
- 23494 Set C-8 to 60% (Q/N = .25)
- 23566 When the pump is chilled, close the
D.C. breakers.
- a. PMP: Report pump chill.
- 23572 Activate the following inputs to the
shutdown chain:
- D.C. Breakers
CT-507
- 23610 In MANUAL Control, establish 10,000 rpm
at a Q/N = .25.
- 23616 Switch C-106 to AUTO.
- 23619 At CTO command, activate the following
inputs to the shutdown chain:
- Q/N High
Q/N Low

23626 Open C-231 to 70 pot divisions.
 23630 Close C-221.
 23632 Use C-231 to establish and maintain
 20 psig at CP-220.
 23646 Switch C-8 to Q/N.
 23666 Switch to Speed Control.
 23668 Switch to Hold.
 23670 Set Speed Rate pot to 80 divisions
 (400 rpm/sec).
 23690 Demand 19,000 rpm.
 23693 Switch to RUN.
 23732 Open C-231.
 23744 Q/N to POSITION Control.
 23774 Frequency response.
 23790 Unpatch oscillator.
 23843 Use C-8 to increase Q/N to .35.

a. Use .02 increments.

23870 Use C-8 to decrease Q/N to .25.
 23900 Bypass Q/N Low.
 23930 Use C-8 to decrease Q/N to .14.
 23934 Shutdown - Dewar transfer.

VI. DEWAR 1 TO DEWAR 4/5 LH₂ TRANSFER

During this phase, Dewar 4/5 will be refilled by transferring LH₂ from Dewar 1.

A. PROCEED WITH THE LH₂ TRANSFER.

23945 Issue the ready order.
 23978 Open L-251.
 24042 Close L-261, L-153.
 24095 Open L-61, L-301, L-330.
 24104 Open L-331, X-301.
 24116 Close K-401.
 24126 Use L-53 in POSITION Control to establish
 and maintain 65 psig in Dewar 1.
 24140 When LP-61 is greater than KP-61/62,
 Open K-301/302.

24146 When LH transfer is complete,
Close K-301/302.
28220 Transfer complete.

VII. PUMP MAPPING #1

During this phase, an initial pump operating condition of 19,000 rpm and .25 Q/N will be established. Using C-8 in Q/N Control to vary the system impedance, the pump will be mapped at the following:

<u>SPEED</u>	<u>Q/N</u>
23,000	.14 to .35
26,000	.17 to .35

At 26,000 rpm an emergency shutdown will be initiated. Dewar pressure will be maintained at 40 psig.

A. PROCEED WITH PUMP MAPPING.

28388 Bottle six on line.
28542 Issue the ready order.
28550 Set the overspeed trip pot to 730 divisions (28,000 rpm).
28554 Raise the synchronous motor field to 120 amps.
28557 Raise the D.C. motor field to 13 amps.
28588 Close K-153.
28594 Select Dewar 4 pressure feedback.
28600 Open K-61.
28604 In K-53 PRESSURE Control; establish 40 psig in Dewar 4.
28617 Switch the following shutdown outputs to NORMAL:

Speed Rate C-8
C-221

28619 Activate the following inputs to the shutdown chain:

UQ-2 CP-505
UQ-3 KP-62
JP-101/201
CP-220

175

G

29126	Use C-8 to decrease Q/N to .20.
29129	Bypass Q/N Low.
29160	Use C-8 to decrease Q/N to .14.
	a. Use .02 increments.
29185	Use C-8 to increase Q/N to .25.
29188	Activate Q/N Low.
29191	Switch Speed Rate Control to HOLD.
29196	Demand 26,000 rpm.
29200	Switch Speed Rate Control to RUN.
29240	Use C-8 to decrease Q/N to .17.
	a. Use .02 increments.
29290	Use C-8 to increase Q/N to .35.
	a. Use .02 increments.
29308	Close C-106 and decrease Q/N to .25.
29314	At TD command, push the shutdown button.
29334	Open D. C. Breakers.
29338	Bypass all the shutdown inputs.
29344	Switch C-231 to POSITION Control and close.
29348	Switch C-106 to RESET.
29350	Reset the shutdown chain.
29354	Use C-111 to maintain CP-9 between 60 and 100 psig.
29360	Close C-12.
29374	Switch K-53 to POSITION Control and close.
29380	Close K-61.
29384	Open K-153.
29388	Decrease D. C. motor field to less than 5 amps.
29393	Switch the shutdown outputs to OVERRIDE.

VIII. PUMP MAPPING #2

During this phase, an initial pump operating condition of 23,000 rpm and .25 Q/N will be established. Using C-8 in Q/N Control to vary the system impedance, the pump will be mapped at the following:

<u>SPEED</u>	<u>Q/N</u>
23,000	.14 to .35

A. PROCEED WITH PUMP MAPPING.

- 29567 Dewar 5 boil off.
30950 Set the overspeed trip pot to 660 divisions (25,000 rpm).
30956 Raise the synchronous motor field to 120 amps.
30958 Raise the D.C. motor field to 13 amps.
30960 Close K-153.
30969 Select Dewar 5 pressure feedback.
30970 Open K-62.
30977 In K-53 PRESSURE Control, establish 60 psig in Dewar 5.
30981 Switch the following shutdown outputs to NORMAL:

Speed Rate C-8
C-221

30986 Activate the following inputs to the shutdown chain:

UQ-2 CP-505
UQ-3 KP-61
JP-101/201
CP-220

31010 Use C-106 to chill CT-106.
31017 At CTO command Open C-11, Close C-111.
31032 Open K-161.
31036 Open C-221.
31038 Close C-231.
31040 Set C-8 to 60% (Q/N = .25).
31125 When the pump is chilled, close the D.C. Breakers.

a. PMP: Report pump chill.

31130 Activate the following inputs to the shutdown chain:

D.C. Breakers
CT-507

31165 In MANUAL Control, establish 10,000 rpm
at a Q/N = .25.

31167 Switch C-106 to AUTO.

31170 At CTO command, activate the following
inputs to the shutdown chain:

Q/N High
Q/N Low

31176 Open C-231 to 70 pot divisions.

31178 Close C-221.

31187 In C-231 POSITION Control, establish
20 psig at CP-220.

31197 Q/N Control switched.

31206 Switch to SPEED Control.

31210 Switch Speed Rate Control to HOLD.

31215 Set Speed Rate pot to 160 divisions
(800 rpm/sec).

31228 Demand 23,000 rpm.

31233 Switch Speed Rate Control to RUN.

31285 Use C-8 to increase Q/N to .33.

a. Use .02 increments.

31340 Use C-8 to decrease Q/N to .17.

31370 Use C-8 to increase Q/N to .25.

31383 80 psig set in Dewar 5.

31420 Use C-8 to increase Q/N to .33.

a. Use .02 increments.

31490 Use C-8 to decrease Q/N to .17.

31505 Use C-8 to increase Q/N to .20.

31510 Shutdown (CTO MANUAL).

31516 Switch C-231 to POSITION Control and close.

31526 Switch C-106 to RESET.

31530 Open D.C. Breakers.

31549 Use C-111 to maintain CP-9 between
60 and 100 psig.

31553 Close C-12.

31554 Bypass all the shutdown inputs.

31562	Reset the shutdown chain.
31566	Switch K-53 to POSITION Control and close.
31568	Close K-62.
31584	Open K-153
31586	Decrease D. C. motor field to less than 5 amps.
31590	Switch the shutdown outputs to OVERRIDE.
31800	Maximum Shutdown Phase.



END

CHRONOLOGY FOR CEL INDUCER TEST

EXPERIMENTAL PLAN II

15 DECEMBER 1971

180

I. PRE-OPERATIONAL PHASE

During this phase verification will be made of the Test Cell "C" readiness to conduct a test using the CEL and Electric Drive Systems. Facility setup checklists will be reviewed, personnel locations will be determined, the Operators communication net will be checked, and systems switched to LCR control. Valves and systems necessary for the test will then be operated, room inerting will be started, and a voltage calibration performed.

- A. SETUP CHECKLISTS HAVE BEEN REVIEWED AND APPROVED.
- B. REPORT ON STATUS OF PERSONNEL IN TEST CELL "C" AREA.
- C. CHECK THE OPERATORS NET.
- D. HAVE THE REQUIRED SYSTEMS SWITCHED TO LCR CONTROL.
- E. EXERCISE THE VALVES IN THE ELECTRIC PUMP ROOM, CEL AND HIGH PRESSURE ROOM.
- F. BEGIN INERTING THE TEST CELL.

01080 Turn off the HPR, EPR and MER fans.
01085 Close Q-113.
01095 Pressurize the room inerting header
(Bottles 13, 14, 15, and 16).
01158 Begin inerting the following areas:

HPR (G-451/452)
CEL (G-456)
EPR (G-455)

- a. Report when concentrations reach 3%.
- b. Maintain O₂ concentrations between 3 and 5%.

- G. CHECK THE SHUTDOWN CHAIN.
- H. PERFORM A VOLTAGE CALIBRATION.

04201-04301 Calibration interval.

II. PRESSURIZATION, CHILLDOWN, OVERSPEED TRIP CHECK

During this phase, the helium and hydrogen headers will be pressurized, Dewar 4/5 will be pressurized, the CEL flow loop will be chilled and soaked, and the overspeed inputs to the shutdown chain will be checked. K-3 and K-130 will be calibrated at a dewar pressure of 40 psig.

A. PROCEED WITH HEADER PRESSURIZATION.

- 04524 Report on room inerting.
- 04530 Open K-50, K-153.
- 04537 Open L-50.
- 04546 Close Q-120, Q-150, Q-101 thru Q-112.
- 04580 Pressurize the helium header.
 - a. QP-20: 1400 psig.

- 04713 Pressurize the hydrogen header with Bottle 2.
 - a. QP-30: 3000 psig.

B. PROCEED WITH THE CHILLDOWN.

- 04738 Close K-153, K-403, K-402, K-261, C-408.
- 04768 Close C-221.
- 04787 Open K-1, K-61.
- 04815 Open C-214, C-8.
- 04822 Select Dewar 4 pressure feedback.
- 04827 Open C-111.
- 04877 In K-53 PRESSURE Control, establish 60 psig in Dewar 4.
- 05647 Use K-3 to chill CT-3 to 100°R.
 - a. PMP: Report CT-3.

- 05947 Use K-130 to chill KT-130.
 - a. DSO: Report KT-130.

- 05962 Close K-130.
- 05990 When CP-8 is less than 10 psig, Open C-4, C-231; Close C-214.

06020 Close C-111.
 06583 Use C-106 to establish and maintain
 CP-505 between 10-20 psig.
 06584 Use K-130 to maintain 3 lbs/sec at KF-130.
 06590 When pump is chilled, slowly open K-3.
 06610 Close K-130.
 06654 Use C-111 to chill CT-111.
 06820 When CT-111 is chilled, set C-111 to
 maintain CP-9 between 80 and 100 psig.
 06821 Open C-221.
 06840 Close C-231.
 06841 Start 900 second timer.
 06845 Switch K-53 to POSITION Control and close.
 06854 Close K-61.
 06860 Open K-153.

C. PROCEED WITH STARTUP OF A.C. MOTOR.

06873 Report electric drive alarm status.
 06880 Start synchronous motor. (UI-2 not
 reading properly)
 06960 Start blowers.
 06987 Establish and maintain unity power
 factor. (120 amps)
 07026 Increase D.C. motor field to 13 amps,
 then decrease to 5 amps.
 07090 Raise and lower armature voltage.
 07130 5 Amps field set.

D. PROCEED WITH OVERSPEED TRIP CHECK.

07944 Set the overspeed trip pot to 105 divisions
 (4,000 rpm).
 07953 Raise synchronous motor field to 120 amps.
 07960 Close K-153.
 07964 Select Dewar 4 pressure feedback.
 07968 Open K-61.
 07986 Raise D.C. motor field to 13 amps.
 07990 In K-53 PRESSURE Control, establish
 45 psig in Dewar 4.
 07992 Switch the following shutdown output to
 NORMAL:

Speed Rate

07995 Activate the following inputs to the shutdown chain:

 UQ-2 JP-101/201
 CP-220 CP-505

08008 Open K-3.
08013 Close K-130.
08048 Open C-111.
08032 Open C-221.
08034 Close C-231.
08065 Use C-8 to chill the pump.
08082 Set C-8 to 55%. (Q/N = .22)
08090 Set C-106 to 15%.
08358 When the pump is chilled, close the D.C. breakers.

 a. PMP: Report pump chill.

08364 Activate CT-507 input to the shutdown chain.
08416 In MANUAL Control, increase speed to produce overspeed trip (4,000 rpm).
08420 Reset the shutdown chain.
08425 Bypass UQ-2 shutdown input.
08426 Activate UQ-3 shutdown input.
08460 In MANUAL Control, increase speed to produce overspeed trip (6,000 rpm -- 1 Trip).
08474 When speed is zero, open the D.C. breakers.
08475 Bypass all the shutdown inputs.
08480 Reset the shutdown chain.
08484 Close C-106.
08500 Use C-111 to maintain CP-9 between 60 and 100 psig.
08508 Switch K-53 to POSITION Control and close.
08516 Close K-61.
08520 Open K-153.
08528 Switch the shutdown outputs to OVERRIDE.
08570 Decrease D.C. motor field to less than 5 amps.

III.

CAVITATION TEST PHASE RUN #1A - 37.5°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
19,000	.07, .24

The supply dewar pressure will be maintained at 45 psig.

A. PROCEED WITH CAVITATION TEST.

- 09187 Set the overspeed trip pot to 550 divisions (21,000 rpm).
- 09203 Raise the synchronous motor field to 120 amps.
- 09217 Close K-153.
- 09218 Select Dewar 5 pressure feedback.
- 09224 Open K-62.
- 09230 In K-53 PRESSURE Control, establish 45 psig in Dewar 5
- 09236 Switch the following shutdown outputs to NORMAL:

Speed, Rate, C-8, C-221
- 09240 Raise the D. C. motor field to 13 amps.
- 09246 Activate the following inputs to the shutdown chain:

UQ-2	CP-505
UQ-3	CP-220
JP-101/201	KP-61
- 09272 Use C-106 to chill CT-106.
- 09322 At CTO command, Open C-11, Close C-111.
- 09342 Use K-161 to maintain KP-61 between 20 and 25 psig.
- 09361 Open C-221.
- 09374 Close C-231.
- 09430 Set C-8 to 55% (Q/N = .22).
- 09648 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

09654 Activate the following inputs to the shutdown chain:

D. C. Breakers, CT-507

09697 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

09701 Switch C-106 to AUTO.

09706 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

09713 Open C-231 to 70 pot divisions.

09716 Close C-221.

09730 Use C-231 to establish and maintain 20 psig at CP-220.

09739 Switch C-8 to Q/N control and establish Q/N = .22.

09767 Switch to SPEED Control.

09780 Switch Speed Rate Control to HOLD.

09781 Set Speed Rate pot to 160 divisions (800 rpm/sec).

09787 Demand 19,000 rpm.

09800 Switch Speed Rate Control to RUN.

09830 Open C-231.

09848 CTO Manual Shutdown (Speed not indicating properly).

09855 Open D. C. breakers.

09860 Bypass all the shutdown inputs.

09865 Switch C-106 to RESET.

09868 Switch C-231 to POSITION Control and close.

09870 Reset the shutdown chain.

09880 Use C-111 to maintain CP-9 between 60 and 100 psig.

09890 Close C-11.

09905 Switch K-53 to POSITION Control and close.

09912 Close K-62.

09915 Open K-153.

09918 Decrease D. C. motor field to less than 5 amps.

09922 Switch the shutdown outputs to OVERRIDE.

10452 Dewar transfer.

IV.

CAVITATION TEST PHASE RUN #1B - 39°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
19,000	.17, .24

The supply dewar pressure will be maintained at 75 psig.

A. PROCEED WITH CAVITATION TEST.

- | | |
|-------|---|
| 11296 | Set the overspeed trip pot to 550 divisions (21,000 rpm). |
| 00304 | Raise the synchronous motor field to 120 amps. |
| 11312 | Close K-153. |
| 11336 | Raise the D. C. motor field to 13 amps. |
| 11350 | Select Dewar 5 pressure feedback. |
| 11353 | Open K-62. |
| 11366 | Switch the following shutdown outputs to NORMAL: |
| | Speed Rate, C-8, C-221 |
| 11372 | Activate the following inputs to the shutdown chain: |
| | UQ-2 CP-220 |
| | UQ-3 CP-505 |
| | JP-101/201 KP-61 |
| 11390 | In K-53 PRESSURE Control, establish 75 psig in Dewar 5. |
| 11400 | Use C-106 to chill CT-106. |
| 11410 | At CTO command, Open C-11, Close C-111. |
| 11425 | Use K-161 to maintain KP-61 between 20 and 25 psig. |
| 11430 | Open C-221. |
| 11434 | Close C-231. |
| 11455 | Set C-8 to 530 pot divisions. |
| 11475 | When the pump is chilled, close the D. C. breakers. |

a. PMP: Report pump chill.

11480 Activate the following inputs to the shutdown chain:
D.C. Breakers, CT-507

11524 In MANUAL Control, establish 10,000 rpm
at a Q/N = .22.

11526 Switch C-106 to AUTO.

11530 At CTO command, activate the following inputs
to the shutdown chain:
Q/N High
Q/N Low

11537 Open C-231 to 70 pot divisions.

11540 Close C-221.

11550 Use C-231 to establish and maintain 20 psig
at CP-220.

11554 Switch C-8 to Q/N control and establish Q/N

11573 Switch to Speed Control.

11577 Switch Speed Rate Control to HOLD.

11581 Set Speed Rate pot to 160 divisions
(800 rpm/sec).

11590 Demand 19,000 rpm.

11609 Switch Speed Rate Control to RUN.

11646 Open C-231.

11680 Use C-8 in Q/N Control to establish a Q/N = .17.

11686 Report CP-700D. 475 psid.

11702 Slowly decrease K-3 position.

11745 CP-505 bypassed.

11856 Open K-3 (Q/N = .17 at 19,000 rpm --
K-3 minimum pot setting = 279 divisions).

11910 Use C-8 to increase Q/N to .24. (653 pot
divisions).

11920 Report CP-700D. 430 psid,

11924 Slowly decrease K-3 position.

12054 Open K-3 (Q/N = .24 at 19,000 rpm --
K-3 minimum pot setting = 386 divisions).

12096 Increase Dewar 5 pressure to 85 psig.

12134 Use C-8 to increase Q/N to .30. (Reached
approximately .29).

12143	At TD command, push the shutdown button.
12150	Open D. C. breakers.
12157	Bypass all the shutdown inputs.
12160	Switch C-231 to POSITION Control and close.
12162	Switch C-106 to RESET.
12165	Reset the shutdown chain.
12170	Use C-111 to maintain CP-9 between 60 and 100 psig.
12172	Close C-11.
12178	Switch K-53 to POSITION Control and close.
12190	Decrease D. C. motor field to less than 5 amps.
12194	Switch the shutdown outputs to OVERRIDE.
12198	Close K-62.
12200	Open K-153.
12520	Dewar 5 vented.

V. CAVITATION TEST PHASE RUN #2 - 41°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
19,000	.30

The supply dewar pressure will be maintained at 90 psig.

A. PROCEED WITH CAVITATION TEST.

13880	Set the overspeed trip pot to 630 divisions (24,000 rpm).
13896	Raise the synchronous motor field to 120 amps.
13902	Close K-153.
13906	Select Dewar 4 pressure feedback.
13910	Open K-61.
13923	Switch the following shutdown outputs to NORMAL:

Speed Rate, C-8, C-221

13936 Activate the following inputs to the shutdown
chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-62

13938 Raise the D. C. motor field to 13 amps.
13950 In K-53 PRESSURE Control, establish
85 psig in Dewar 4.
13964 Use C-106 to chill CT-106.
13973 At CTO command, Open C-12, Close C-111.
13984 Use K-162 to maintain KP-62 between
20 and 25 psig.
13997 Open C-221.
14000 Close C-231.
14008 Set C-8 to 530 pot divisions.
14115 When the pump is chilled, close the
D. C. breakers.

a. PMP: Report pump chill.

14118 Activate the following inputs to the shutdown
chain:

D. C. Breakers, CT-507

14158 In MANUAL Control, establish 10,000 rpm
at a Q/N = .22.
14159 Switch C-106 to AUTO.
14162 At CTO command, activate the following
inputs to the shutdown chain:

Q/N High
Q/N Low

14174 Open C-231 to 80 pot divisions.
14178 Close C-221.
14193 Use C-231 to establish and maintain
30 psig at CP-220.
14202 Switch to Q/N Control and establish Q/N = .20.
14219 Switch to SPEED Control.
14222 Switch Speed Rate Control to HOLD.
14228 Set Speed Rate pot to 160 divisions
(800 rpm/sec).
14232 Demand 19,000 rpm.
14238 Switch Speed Rate Control to RUN.
14254 Open C-231.

190

14340 Increase Dewar pressure to 90 psig.
 14384 Use C-8 in Q/N Control to establish a Q/N = .30.
 14392 Report CP-700D. 370 psid.
 14398 Slowly decrease K-3 position.
 14554 Open K-3 (Q/N = .30 at 19,000 rpm --
 K-3 minimum pot setting = 585 divisions).
 14567 At TD command, push the shutdown button.
 14575 Open D.C. breakers.
 14580 Switch C-231 to POSITION Control and close.
 14582 Switch C-106 to RESET.
 14584 Bypass all the shutdown inputs.
 14588 Reset the shutdown chain.
 14590 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 14600 Close C-12.
 14615 Switch K-53 to POSITION Control and close.
 14620 Close K-61.
 14626 Open K-153.
 14635 Decrease D.C. motor field to less than 5 amps.
 14638 Switch the shutdown outputs to OVERRIDE.
 15150 Bottle 3 brought on line.

a. QP-30 = 3100 psi.

VI. CAVITATION TEST PHASE RUN #3 - 41°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
19,000	.17
22,000	.17

The supply dewar pressure will be maintained at 85 psig.

A. PROCEED WITH CAVITATION TEST.

16090 Set the overspeed trip pot to 630 divisions
 (24,000 rpm).
 16094 Raise the synchronous motor field to 120 amps.
 16101 Close K-153.
 16108 Select Dewar 5 pressure feedback.

16111 Open K-62.

16127 Switch the following shutdown outputs to NORMAL:

Speed Rate, C-8, C-221

16130 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-61

16142 Raise the D. C. motor field to 13 amps.

16145 In K-53 PRESSURE Control, establish 85 psig in Dewar 5.

16158 Use C-106 to chill CT-106.

16169 At CTO command, Open C-11, Close C-111.

16184 Use K-161 to maintain KP-61 between 35 and 40 psig.

16186 Open C-221.

16188 Close C-231.

16192 Set C-8 to 530 pot divisions.

16262 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

16266 Activate the following inputs to the shutdown chain:

D. C. Breakers, CT-507

16303 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

16306 Switch C-106 to AUTO.

16310 At CTO command, activate the following inputs to the shutdown chain:

Q/N High

Q/N Low

192

16316	Open C-231 to 85 pot divisions.
16318	Close C-221.
16324	Use C-231 to establish and maintain 30 psig at CP-220.
16334	Switch to Q/N Control and establish Q/N = .20.
16342	Switch to SPEED Control.
16346	Switch Speed Rate Control to HOLD.
16352	Set Speed Rate pot to 160 divisions (800 rpm/sec).
16356	Demand 19,000 rpm.
16358	Switch Speed Rate Control to RUN.
16370	Open C-231.
16397	Use C-8 in Q/N Control to establish a Q/N = .17.
16427	Increase speed to 22,000.
16440	Slowly decrease K-3 position.
16544	Open K-3 (Q/N = .17 at 22,000 rpm -- K-3 minimum pot setting = 313 divisions).
16574	Decrease speed to 19,000 rpm.
16580	Report CP-700D. 450 psid.
16590	Slowly decrease K-3 position.
16667	Open K-3 (Q/N = .17 at 19,000 rpm -- K-3 minimum pot setting = 268 divisions).
16683	At TD command, push the shutdown button.
16692	Open D. C. breakers.
16694	Switch C-106 to RESET.
16697	Switch C-231 to POSITION Control and close.
16698	Bypass all the shutdown inputs.
16700	Reset the shutdown chain.
16706	Use C-111 to maintain CP-9 between 60 and 100 psig.
16725	Close C-11.
16728	Switch K-53 to POSITION Control and close.
16734	Close K-62.
16741	Open K-153.
16750	Decrease D. C. motor field to less than 5 amps.
16756	Switch the shutdown outputs to OVERRIDE.

VII. DEWAR 1 TO DEWAR 4/5 LH₂ TRANSFER

During this phase, Dewar 4/5 will be refilled by transferring LH₂ from Dewar 1.

A. PROCEED WITH THE LH₂ TRANSFER.

17322	Open L-251.
17330	Close L-261, L-153.
17360	Open L-61 (Won't open -- investigate valve).
18418	Open L-61, L-301, L-330.
18461	Open L-331, X-301.
18467	Close K-401.
18482	Use K-161/162 to vent Dewar 4/5.
18490	Use L-53 in POSITION Control to establish and maintain psig in Dewar 1.
18510	When LP-61 is greater than KP-61/62, Open K-301/302.
23448	When LH ₂ transfer is complete, Close K-301/302.

VIII. CAVITATION TEST PHASE RUN #4 - 37.5⁰R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
24,000	.24

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH CAVITATION TEST.

23626	Bottle 4 brought on line. a. QP-30 = 3000 psi.
24428	Set the overspeed trip pot to 680 divisions (26,000 rpm).
24436	Raise the synchronous motor field to 120 amps.
24441	Close K-153.
24446	Select Dewar 4 pressure feedback.
24450	Open K-61.
24500	Raise the D. C. motor field to 13 amps.
24514	50 psi established in Dewar 5.

- 24546 Switch the following shutdown outputs to NORMAL:
- Speed Rate, C-8, C-221
- 24550 Activate the following inputs to the shutdown chain:
- | | |
|------------|--------|
| UQ-2 | CP-220 |
| UQ-3 | CP-505 |
| JP-101/201 | KP-62 |
- 24586 In K-53 PRESSURE Control, establish 100 psig in Dewar 4.
- 24798 Use C-106 to chill CT-106.
- 24820 Dewar 5 pressure set at 60 psig.
- 24845 At CTO command, Open C-12, Close C-111.
- 24868 Use K-162 to maintain KP-62 between 50 and 60 psig.
- 24874 Open C-221.
- 24876 Close C-231.
- 24882 Set C-8 to 530 pot divisions.
- 25047 80 psig set in Dewar 4.
- 25051 When the pump is chilled, close the D. C. breakers.
- a. PMP: Report pump chill.
- 25060 Activate the following inputs to the shutdown chain:
- D. C. Breakers, CT-507
- 25081 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.
- 25086 Switch C-106 to AUTO.
- 25092 At CTO command, activate the following inputs to the shutdown chain:
- Q/N High
Q/N Low

25096	Open C-231 to 85 pot divisions
25098	Close C-221.
25113	Use C-231 to establish and maintain 30 psig at CP-220.
25116	Switch to Q/N Control and establish Q/N = .20.
25126	Switch to SPEED Control.
25129	Switch Speed Rate Control to HOLD.
25134	Set Speed Rate pot to 160 divisions (800 rpm/sec).
25140	Demand 19,000 rpm.
25164	Switch Speed Rate Control to RUN.
25180	Open C-231.
25216	Increase Dewar 4 pressure (85 psi).
25263	RPM increased to 24,000 rpm.
25266	90 psi in Dewar 4.
25310	95 psi in Dewar 4.
25340	100 psi in Dewar 4.
25344	Use C-8 in Q/N Control to establish a Q/N = .24.
25350	Slowly decrease K-3 position.
25468	Open K-3 (Q/N = .24 at 19,000 rpm -- K-3 minimum pot setting = 515 divisions).
25499	Use C-8 to decrease Q/N to .17.
25504	Slowly decrease K-3 position (Cavitation point not reached).
25540	At TD command, push the shutdown button.
25550	Open D.C. breakers.
25554	Switch C-231 to POSITION Control and close.
25558	Switch C-106 to RESET.
25560	Bypass all the shutdown inputs.
25562	Reset the shutdown chain.
25578	Use C-111 to maintain CP-9 between 60 and 100 psig.
25580	Close C-12.
25594	Switch K-53 to POSITION Control and close.
25598	Close K-61.
25605	Open K-153.
25611	Decrease D.C. motor field to less than 5 amps.
25615	Switch the shutdown outputs to OVERRIDE.
25830	Dewar transfer.

IX.

CAVITATION TEST PHASE RUN #5 - 41°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
19,000	.24
22,000	.24

The supply dewar pressure will be maintained at 85 psig.

A. PROCEED WITH CAVITATION TEST.

- 27386 Set the overspeed trip pot to 630 divisions (24,000 rpm).
- 27394 Raise the synchronous motor field to 120 amps.
- 27396 Close K-153.
- 27404 Select Dewar 5 pressure feedback.
- 27407 Open K-62.
- 27418 Switch the following shutdown outputs to NORMAL:
- Speed Rate, C-8, C-221
- 27426 Activate the following inputs to the shutdown chain:
- | | |
|------------|--------|
| UQ-2 | CP-220 |
| UQ-3 | CP-505 |
| JP-101/201 | KP-61 |
- 27434 Raise the D. C. motor field to 13 amps.
- 27444 In K-53 PRESSURE Control, establish 85 psig in Dewar 5.
- 27451 Use C-106 to chill CT-106.
- 27458 At CTO command, Open C-11, Close C-111.
- 27478 Use K-161 to maintain KP-61 between 40 and 50 psig.
- 27480 Open C-221.
- 27482 Close C-231.
- 27487 Set C-8 to 530 pot divisions.

27560 When the pump is chilled, close the D.C. breakers.

a. PMP: Report pump chill.

27564 Activate the following inputs to the shutdown chain:

D.C. Breakers, CT-507

27592 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

27594 Switch C-106 to AUTO.

27596 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

27600 Open C-231 to 85 pot divisions.

27603 Close C-221.

27610 Use C-231 to establish and maintain 30 psig at CP-220.

27620 Switch to Q/N Control and establish Q/N = .22.

27630 Switch to SPEED Control.

27633 Switch Speed Rate Control to HOLD.

27640 Set Speed Rate pot to 160 divisions (800 rpm/sec).

27643 Demand 19,000 rpm.

27647 Switch Speed Rate Control to RUN.

27659 Open C-231.

27676 Use C-8 in Q/N Control to establish a Q/N = .24.

27684 Report CP-700D. 420 psid.

27688 Slowly decrease K-3 position.

27700 100 psi set in Dewar 5.

27736 Open K-3 (Q/N = .24 at 19,000 rpm -- K-3 minimum pot setting = 338 divisions).

27756 Increase speed to 22,000 rpm.

27764 Report CP-700D. 560 psid.

27768 Slowly decrease K-3 position.

27816 Open K-3 (Q/N = .24 at 22,000 rpm -- K-3 minimum pot setting = 416 divisions).

27836	At TD command, push the shutdown button
27848	Open D.C. breakers.
27850	Switch C-231 to POSITION Control and close.
27856	Switch C-106 to RESET.
27859	Bypass all the shutdown inputs.
27860	Reset the shutdown chain.
27868	Use C-111 to maintain CP-9 between 60 and 100 psig.
27872	Close C-11.
27878	Switch K-53 to POSITION Control and close.
27884	Close K-62.
27888	Open K-153.
27900	Decrease D.C. motor field to less than 5 amps.
27904	Switch the shutdown outputs to OVERRIDE.
28320	Dewar transfer.

X.

CAVITATION TEST PHASE RUN #6 - 41^oR

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
24,000	.17, .24

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH CAVITATION TEST.

29204	Select Dewar 4 pressure feedback.
29210	Open K-61.
29233	Set the overspeed trip pot to 680 divisions (26,000 rpm).
29240	Raise the synchronous motor field to 120 amps.
29250	Switch the following shutdown outputs to NORMAL:

Speed Rate, C-8, C-221

29258 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-62

199

29272 Use C-106 to chill CT-106.
 29283 Raise the D.C. motor field to 13 amps.
 29290 At CTO command, Open C-12, Close C-111.
 29296 Use K-162 to maintain KP-62 between
 50 and 60 psig.
 29300 Open C-221.
 29304 Close C-231.
 29306 Set C-8 to 530 pot divisions.
 29348 When the pump is chilled, close the
 D.C. breakers.

 a. PMP: Report pump chill.

 29352 Activate the following inputs to the shutdown
 chain:

 D.C. Breakers, CT-507

 29372 In MANUAL Control, establish 10,000 rpm
 at a Q/N = .22.
 29374 Switch C-106 to AUTO.
 29378 At CTO command, activate the following
 inputs to the shutdown chain:

 Q/N High
 Q/N Low

 29381 Open C-231 to 85 pot divisions.
 29382 Close C-221.
 29384 Use C-231 to establish and maintain
 30 psig at CP-220.
 29400 Switch to Q/N Control and establish Q/N = .20.
 29406 Switch to SPEED Control.
 29408 Switch Speed Rate Control to HOLD.
 29416 Set Speed Rate pot to 160 divisions
 (800 rpm/sec).
 29418 Demand 24,000 rpm.
 29423 Switch Speed Rate Control to RUN.
 29444 Open C-231.
 29468 Use C-8 in Q/N Control to establish a Q/N = .24.
 29476 Report CP-700D. 650 psid.
 29480 Slowly decrease K-3 position.

29538 Open K-3 (Q/N = .24 at 24,000 rpm --
K-3 minimum pot setting = 540 divisions).
29576 Use C-8 to decrease Q/N to .17.
29581 Slowly decrease K-3 position.
29630 Open K-3 (Q/N = .17 at 24,000 rpm --
K-3 minimum pot setting = 312 divisions).
29640 At TD command, push the shutdown button.
29650 Open D.C. breakers.
29653 Switch C-231 to POSITION Control and close.
29656 Switch C-106 to RESET.
29659 Bypass all the shutdown inputs.
29660 Reset the shutdown chain.
29675 Use C-111 to maintain CP-9 between
60 and 100 psig.
29682 Close C-12.
29694 Switch K-53 to POSITION Control and close.
29698 Close K-61.
29704 Open K-153.
29708 Decrease D.C. motor field to less than 5 amps.
29714 Switch the shutdown outputs to OVERRIDE.
29830 Dewar transfer.

XI.

CAVITATION TEST PHASE RUN #7 - 39° R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
22,000	.17
24,000	.17

The supply dewar pressure will be maintained at 80 psig.

A. PROCEED WITH CAVITATION TEST.

31118 Set the overspeed trip pot to 680 divisions
(26,000 rpm).
31120 Raise the synchronous motor field to 120 amps.
31127 Close K-153.
31131 Select Dewar 5 pressure feedback.
31136 Open K-62.

201

- 31153 Switch the following shutdown outputs to NORMAL:
Speed Rate, C-8, C-221
- 31157 Raise the D. C. motor field to 13 amps.
31162 Activate the following inputs to the shutdown chain:
UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-61
- 31178 Use C-106 to chill CT-106.
31186 At CTO command, Open C-11, Close C-111.
31196 Use K-161 to maintain KP-61 between 30 and 40 psig.
- 31201 Open C-221.
31203 Close C-231.
31208 Set C-8 to 530 pot divisions.
31210 In K-53 PRESSURE Control, establish 80 psig in Dewar 5.
- 31317 When the pump is chilled, close the D. C. breakers.
a. PMP: Report pump chill.
- 31321 Activate the following inputs to the shutdown chain:
D. C. Breakers, CT-507
- 31340 In MANUAL Control, establish 10,000 rpm at a Q/N = .17.
31342 Switch C-106 to AUTO.
31348 At CTO command, activate the following inputs to the shutdown chain:
Q/N High
Q/N Low

202

31351	Open C-231 to 85 pot divisions
31354	Close C-221.
31358	Use C-231 to establish and maintain 30 psig at CP-220.
31365	Switch to Q/N Control and establish Q/N = .17.
31374	Switch to SPEED Control.
31376	Switch Speed Rate Control to HOLD.
31380	Set Speed Rate pot to 160 divisions (800 rpm/sec).
31387	Demand 24,000 rpm.
31390	Switch Speed Rate Control to RUN.
31394	Open C-231.
31419	Use C-8 in Q/N Control to establish a Q/N = .17.
31428	Report CP-700D. 750 psid.
31431	Slowly decrease K-3 position.
31505	Open K-3 (Q/N = .17 at 24,000 rpm -- K-3 minimum pot setting = 339 divisions).
31523	Decrease Speed to 22,000 rpm.
31530	Report CP-700D. 630 psid.
31538	Slowly decrease K-3 position.
31587	Open K-3 (Q/N = .17 at 22,000 rpm -- K-3 minimum pot setting = 307 divisions).
31597	At TD command, push the shutdown button.
31608	Open D. C. breakers.
31610	Switch C-231 to POSITION Control and close.
31612	Switch C-106 to RESET.
31614	Bypass all the shutdown inputs.
31618	Reset the shutdown chain.
31627	Use C-111 to maintain CP-9 between 60 and 100 psig.
31632	Close C-11.
31643	Switch K-53 to POSITION Control and close.
31648	Close K-62.
31651	Open K-153.
31656	Decrease D. C. motor field to less than 5 amps.
31659	Switch the shutdown outputs to OVERRIDE.

XII. DEWAR 1 TO DEWAR 4/5 LH₂ TRANSFER

During this phase, Dewar 4/5 will be refilled by transferring LH₂ from Dewar 1.

A. PROCEED WITH THE LH₂ TRANSFER.

31875 Open L-251.
31894 Close L-261, L-153.
31920 Open L-61, L-301, L-330.
31928 Open L-331, X-301.
31931 Close K-401.
31940 Use K-161/162 to vent Dewar 4/5.
31946 When LP-61 is greater than KP-61/62,
Open K-301/302.
36783 When LH₂ transfer is complete, Close
K-301/302.

XIII. CAVITATION TEST PHASE RUN #8 - 37.5°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
19,000	.17, .24, .30

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH CAVITATION TEST.

37270 Bottle 5 brought on line.
a. QP-30 = 3000 psi.
37456 Set the overspeed trip pot to 550 divisions
(21,000 rpm).
37468 Raise the synchronous motor field to 120 amps.
37473 Close K-153.
37476 Select Dewar 4 pressure feedback.
37478 Open K-61.
37500 Switch the following shutdown outputs to
NORMAL:

Speed Rate, C-8, C-221

37505 Activate the following inputs to the shutdown chain:

UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-62

37512 Raise the D. C. motor field to 13 amps.
37514 In K-53 PRESSURE Control, establish 90 psig in Dewar 4.

37527 Use C-106 to chill CT-106.
37540 At CTO command, Open C-12, Close C-111.
37568 Use K-162 to maintain KP-62 between 40 and 50 psig.

37571 Open C-221.
37577 Close C-231.
37581 Set C-8 to 530 pot divisions.
37754 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

37757 Activate the following inputs to the shutdown chain:

D. C. Breakers, CT-507

37774 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.
37776 Switch C-106 to AUTO.
37778 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

37782 Open C-231 to 85 pot divisions.
37786 Close C-221.
37791 Use C-231 to establish and maintain 30 psig at CP-220.
37801 Switch to Q/N Control and establish Q/N = .25.

37816 Switch to SPEED Control.
 37818 Switch Speed Rate Control to HOLD.
 37822 Set Speed Rate pot to 160 divisions
 (800 rpm/sec).
 37828 Demand 19,000 rpm.
 37832 Switch Speed Rate Control to RUN.
 37837 Open C-231.
 37874 Use C-8 in Q/N Control to establish a Q/N = .30.
 37892 Increase Dewar 4 pressure to 100 psig.
 37898 Report CP-700D. 390 psid.
 37903 Slowly decrease K-3 position.
 37974 Open K-3 (Q/N = .30 at 19,000 rpm --
 K-3 minimum pot setting = 465 divisions).
 38000 Use C-8 to decrease Q/N to .24.
 38008 Report CP-700D. 430 psid.
 38010 Slowly decrease K-3 position.
 38068 Open K-3 (Q/N = .24 at 19,000 rpm --
 K-3 minimum pot setting = 335 divisions).
 38096 Use C-8 to decrease Q/N to .17.
 38100 Report CP-700D. 480 psid.
 38110 Slowly decrease K-3 position.
 38156 Open K-3 (Q/N = .17 at 19,000 rpm --
 K-3 minimum pot setting = 245 divisions).
 38166 At TD command, push the shutdown button.
 38174 Open D.C. breakers.
 38178 Switch C-231 to POSITION Control and close.
 38181 Switch C-106 to RESET.
 38183 Bypass all the shutdown inputs.
 38187 Reset the shutdown chain.
 38193 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 38198 Close C-12.
 38210 Switch K-53 to POSITION Control and close.
 38214 Close K-61.
 38220 Open K-153.
 38227 Decrease D.C. motor field to less than 5 amps.
 38234 Switch the shutdown outputs to OVERRIDE.
 38544 Dewar transfer.

XIV.

CAVITATION TEST PHASE RUN #9 - 39°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
19,000	.30
22,000	.24

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH CAVITATION TEST.

- 39452 Set the overspeed trip pot to 630 divisions (24,000 rpm).
- 39460 Raise the synchronous motor field to 120 amps.
- 39470 Close K-153.
- 39474 Select Dewar 5 pressure feedback.
- 39478 Open K-62.
- 39486 Switch the following shutdown outputs to NORMAL:

Speed Rate, C-8, C-221
- 39490 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-61
- 39508 Use C-106 to chill CT-106.
- 39516 Raise the D. C. motor field to 13 amps.
- 39521 At CTO command, Open C-11, Close C-111.
- 39530 Use K-161 to maintain KP-61 between 50 and 60 psig.
- 39535 In K-53 PRESSURE Control, establish 100 psig in Dewar 5.
- 39538 Open C-221.
- 39540 Close C-231.
- 39544 Set C-8 to 530 pot divisions.
- 39574 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

207

39578 Activate the following inputs to the shutdown chain:

 D.C. Breakers, CT-507

39603 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

39606 Switch C-106 to AUTO.

39611 At CTO command, activate the following inputs to the shutdown chain:

 Q/N High

 Q/N Low

39612 Open C-231 to 85 pot divisions.

39613 Close C-221.

39618 Use C-231 to establish and maintain 30 psig at CP-220.

39624 Switch to Q/N Control and establish Q/N = .25.

39636 Switch to SPEED Control.

39638 Switch Speed Rate Control to HOLD.

39641 Set Speed Rate pot to 160 divisions (800 rpm/sec).

39647 Demand 19,000 rpm.

39651 Switch Speed Rate Control to RUN.

39654 Open C-231.

39690 Use C-8 in Q/N Control to establish a Q/N = .30.

39692 Report CP-700D. 370 psid.

39693 Slowly decrease K-3 position.

39757 Open K-3 (Q/N = .30 at 19,000 rpm -- K-3 minimum pot setting = 445 divisions).

39786 Use C-8 to decrease Q/N to .24.

39801 Increase speed to 22,000 rpm.

39805 Report CP-700D. 570 psid.

39806 Slowly decrease K-3 position.

39860 Open K-3 (Q/N = .24 at 22,000 rpm -- K-3 minimum pot setting = 406 divisions).

39870 At TD command, push the shutdown button.

39881 Open D.C. breakers.

39883 Switch C-231 to POSITION Control and close.

39884 Switch C-106 to RESET.

39890	Bypass all the shutdown inputs.
39893	Reset the shutdown chain.
39900	Use C-111 to maintain CP-9 between 60 and 100 psig.
39912	Close C-11.
39926	Switch K-53 to POSITION Control and close.
39930	Close K-62.
39937	Open K-153.
39941	Decrease D. C. motor field to less than 5 amps.
39947	Switch the shutdown outputs to OVERRIDE.
40464	Minimum shutdown phase.

↓
END

209

CHRONOLOGY FOR CEL INDUCER TEST

EXPERIMENTAL PLAN II

16 DECEMBER 1971

210

I. PRE-OPERATIONAL PHASE

During this phase verification will be made of the Test Cell "C" readiness to conduct a test using the CEL and Electric Drive Systems. Facility setup checklists will be reviewed, personnel locations will be determined, the Operators communication net will be checked, and systems switched to LCR control. Valves and systems necessary for the test will then be operated, room inerting will be started, and a voltage calibration performed.

- A. SETUP CHECKLISTS HAVE BEEN REVIEWED AND APPROVED.
- B. REPORT ON STATUS OF PERSONNEL IN TEST CELL "C" AREA.
- C. CHECK THE OPERATORS NET.
- D. HAVE THE REQUIRED SYSTEMS SWITCHED TO LCR CONTROL.
- E. EXERCISE THE VALVES IN THE ELECTRIC PUMP ROOM, CEL AND HIGH PRESSURE ROOM.
- F. BEGIN INERTING THE TEST CELL.
- G. CHECK THE SHUTDOWN CHAIN.
- H. PERFORM A VOLTAGE CALIBRATION.

06441-06541 Calibration interval.

II. PRESSURIZATION, CHILLDOWN, OVERSPEED TRIP CHECK

During this phase, the helium and hydrogen headers will be pressurized, Dewar 4/5 will be pressurized, the CEL flow loop will be chilled and soaked, and the overspeed inputs to the shutdown chain will be checked. K-3 and K-130 will be calibrated at a dewar pressure of 40 psig.

- A. PROCEED WITH HEADER PRESSURIZATION.

06968 Open K-50, K-153.
06981 Open L-50.
06983 Report on room inerting.

06988 Close Q-120, Q-150, Q-101 thru Q-112.
07137 Pressurize the helium header.
a. AP-20: 1250 psig.
07228 Pressurize the hydrogen header with Bottle 5.
a. QP-30: 2550 psig.

B. PROCEED WITH THE CHILLDOWN.

07271 Close K-153, K-403, K-402, K-261, C-408.
07272 Close C-221.
07308 Open K-1, K-61.
07334 Open C-214, C-8.
07356 Select Dewar 4 pressure feedback.
07391 In K-53 PRESSURE Control, establish
60 psig in Dewar 4.
07433 Open C-111.
07674 Use K-3 to chill CT-3 to 100^oR.
a. PMP: Report CT-3.
07900 Use K-130 to chill KT-130.
a. DSO: Report KT-130.
07956 When CP-8 is less than 10 psig, Open C-4,
C-231; Close C-214.
07976 Close C-111.
08017 Use C-106 to establish and maintain
CP-505 between 10 and 20 psig.
08604 Use K-130 to maintain 3 lbs/sec at KF-130.
a. CTO: Monitor CF-6.
08610 When pump is chilled, slowly open K-3.
08632 Close K-130.
08757 Use C-111 to chill CT-111.
08778 When CT-111 is chilled, set C-111 to
maintain CP-9 between 80 and 100 psig.
08781 Open C-221.
08804 Close C-231.
08810 Start 900 second timer.
08817 Switch K-53 to POSITION Control and close.
08824 Close K-61.
08831 Open K-153.

C. PROCEED WITH STARTUP OF A.C. MOTOR.

08852 Report electric drive alarm status.
08874 Start synchronous motor.
08928 Start blowers.
08958 Establish and maintain unity power factor. (120 Amps)
08994 Increase D.C. motor field to 13 amps, then decrease to 5 amps.
09042 Raise and lower armature voltage.
09065 Set field to 5 amps.

D. PROCEED WITH OVERSPEED TRIP CHECK.

10116 Set the overspeed trip pot to 105 divisions (4,000 rpm).
10120 Raise synchronous motor field to 120 amps.
10128 Close K-153.
10133 Select Dewar 4 pressure feedback.
10136 Open K-61.
10147 Raise D.C. motor field to 13 amps.
10152 In K-53 PRESSURE Control, establish 40 psig in Dewar 4.
10156 Switch the following shutdown output to NORMAL:

Speed Rate

10160 Activate the following inputs to the shutdown chain:

UQ-2, JP-101/201, CP-220, CP-505

10164 Open K-3.
10168 Close K-130.
10193 Open C-111.
10208 Set C-8 to 55%. (Q/N = .22).
10214 Open C-221.
10216 Close C-231.
10527 Use C-8 to chill the pump.
10533 When the pump is chilled, close the D.C. breakers.

a. PMP: Report pump chill.

10588 In MANUAL Control, increase speed to produce overspeed trip (4,000 rpm).
 10596 Reset the shutdown chain.
 10598 Bypass UQ-2 shutdown input.
 10600 Activate UQ-3 shutdown input.
 10632 In MANUAL Control, increase speed to produce overspeed trip (6,000 rpm).
 10655 When speed is zero, open the D. C. breakers.
 10664 Bypass all the shutdown inputs.
 10668 Reset the shutdown chain.
 10674 Close C-106.
 10678 Use C-111 to maintain CP-9 between 60 and 100 psig.
 10684 Switch K-53 to POSITION Control and close.
 10688 Close K-61.
 10697 Open K-153.
 10704 Decrease D. C. motor field to less than 5 amps.
 10710 Switch the shutdown outputs to OVERRIDE.

E. VOLTAGE CALIBRATION.

10951-11051 Recalibration interval.

III. CAVITATION TEST PHASE RUN #10 - 37.5°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
22,000	.30
24,000	.30

The supply dewar pressure will be maintained at 60 psig.

A. PROCEED WITH CAVITATION TEST.

12220 Set the overspeed trip pot to 680 divisions (26,000 rpm).
 12224 Raise the synchronous motor field to 120 amps.
 12257 Raise the D. C. motor field to 13 amps.
 12271 Close K-153.
 12273 Select Dewar 5 pressure feedback.
 12276 Open K-62.
 12287 In K-53 PRESSURE Control, establish 60 psig in Dewar 5.

- 12292 Switch the following shutdown outputs to NORMAL:
Speed Rate, C-8, C-221
- 12297 Activate the following inputs to the shutdown chain:
UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-61
- 12313 Use C-106 to chill CT-106.
12362 Pressure rise in Dewar 5.
12376 Close K-62.
12430 Use K-161 to vent the Dewar 5 to 60 psi.
12468 At CTO command, Open C-11, Close C-111.
12486 Use K-161 to maintain KP-61 between 10 and 20 psig.
12567 Open K-62.
12572 In K-53 PRESSURE Control, establish 60 psig in Dewar 5.
12588 Open C-221.
12590 Close C-231.
12596 Set C-8 to 530 pot divisions.
12660 When the pump is chilled, close the D.C. breakers.
a. PMP: Report pump chill.
- 12664 Activate the following inputs to the shutdown chain:
D.C. Breakers, CT-507
- 12681 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.
12684 Switch C-106 to AUTO.
12686 At CTO command, activate the following inputs to the shutdown chain:
Q/N High
Q/N Low

12692	Open C-231 to 85 pot divisions.
12696	Close C-221.
12708	Use C-231 to establish and maintain 30 psig at CP-220.
12710	Switch to Q/N Control and establish Q/N = .25.
12724	Switch to SPEED Control.
12728	Switch Speed Rate Control to HOLD.
12733	Set Speed Rate pot to 160 divisions (800 rpm/sec).
12744	Demand 22,000 rpm.
12747	Switch Speed Rate Control to RUN.
12751	On Ramp, open C-231.
12790	Use C-8 in Q/N Control to establish a Q/N = .30.
12794	Report CP-700D. 520 psid.
12797	Slowly decrease K-3 position.
12853	Open K-3 (Q/N = .30 at 22,000 rpm -- K-3 minimum pot setting = 434 divisions).
12878	Increase speed to 24,000 rpm.
12884	Report CP-700D. 610 psid
12892	Slowly decrease K-3 position.
12933	Open K-3 (Q/N = .30 at 24,000 rpm -- K-3 minimum pot setting = 458 divisions).
12941	At TD command, push the shutdown button.
12954	Open D.C. breakers.
12955	Switch C-231 to POSITION Control and close.
12956	Switch C-106 to RESET.
12957	Bypass all the shutdown inputs.
12960	Reset the shutdown chain.
12972	Use C-111 to maintain CP-9 between 60 and 100 psig.
12978	Close C-11.
12981	Switch K-53 to POSITION Control and close.
12986	Close K-62.
12998	Open K-153.
13004	Decrease D.C. motor field to less than 5 amps.
13008	Switch the shutdown outputs to OVERRIDE.
13140	Dewar transfer.

IV.

CAVITATION TEST PHASE RUN #11 - 41°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
22,000	.30
24,000	.30
26,000	.30

The supply dewar pressure will be maintained at 75 psig.

A. PROCEED WITH CAVITATION TEST.

- 14124 Set the overspeed trip pot to 730 divisions (28,000 rpm).
- 14128 Raise the synchronous motor field to 120 amps.
- 14130 Close K-153.
- 14136 Select Dewar 4 pressure feedback.
- 14138 Open K-61.
- 14150 Switch the following shutdown outputs to NORMAL:

Speed Rate, C-8, C-221
- 14156 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-62
- 14163 Raise the D. C. motor field to 13 amps.
- 14165 In K-53 PRESSURE Control, establish 75 psig in Dewar 4.
- 14170 Use C-106 to chill CT-106.
- 14174 At CTO command, Open C-12, Close C-111.
- 14181 Use K-162 to maintain KP-62 between 25 and 35 psig.
- 14184 Open C-221.
- 14186 Close C-231.

217

14193 Set C-8 to 530 pot divisions.
14247 When the pump is chilled, close the
D. C. breakers.

a. PMP: Report pump chill.

14252 Activate the following inputs to the shutdown
chain:

D. C. Breakers, CT-507

14267 In MANUAL Control, establish 10,000 rpm
at a Q/N = .22.

14269 Switch C-106 to AUTO.

14271 At CTO command, activate the following
inputs to the shutdown chain:

Q/N High
Q/N Low

14276 Open C-231 to 85 pot divisions
14278 Close C-221.
14286 Use C-231 to establish and maintain
30 psig at CP-220.

14291 Switch to Q/N Control and establish Q/N = .25.
14307 Switch to SPEED Control.
14310 Switch Speed Rate Control to HOLD.
14316 Set Speed Rate pot to 160 divisions
(800 rpm/sec).

14320 Demand 22,000 rpm.
14324 Switch Speed Rate Control to RUN.
14326 On Ramp, open C-231.
14362 Use C-8 in Q/N Control to establish a Q/N = .30.
14368 Report CP-700D. 300 psid.
14370 Slowly decrease K-3 position.
14421 Open K-3 (Q/N = .30 at 22,000 rpm --
K-3 minimum pot setting = 417 divisions).
14430 Increase Speed to 24,000 rpm.
14453 Report CP-700D. 300 psid.
14458 Slowly decrease K-3 position.
14503 Open K-3 (Q/N = .30 at 24,000 rpm --
K-3 minimum pot setting = 439 divisions).
14530 Increase Dewar 4 pressure to 80 psig.

14536 Increase speed to 26,000 rpm.
 14540 Use C-8 to increase Q/N to .30.
 14547 Report CP-700D. 710 psid.
 14548 Slowly decrease K-3 position.
 14597 Open K-3 (Q/N = .30 at 26,000 rpm --
 K-3 minimum pot setting = 451 divisions).
 14602 At TD command, push the shutdown button.
 14618 Open D.C. breakers.
 14622 Switch C-231 to POSITION Control and close.
 14623 Bypass all the shutdown inputs.
 14628 Switch C-106 to RESET.
 14631 Reset the shutdown chain.
 14636 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 14640 Close C-12.
 14650 Switch K-53 to POSITION Control and close.
 14656 Close K-61.
 14660 Open K-153.
 14663 Decrease D.C. motor field to less than 5 amps.
 14666 Switch the shutdown outputs to OVERRIDE.
 15600 Liquid boil-off and transfer.

V. CAVITATION TEST PHASE RUN #12 - 39°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
22,000	.30
24,000	.30
26,000	.30

The supply dewar pressure will be maintained at 65 psig.

A. PROCEED WITH CAVITATION TEST.

16060 Set the overspeed trip pot to 730 divisions
 (26,000 rpm).
 16062 Raise the synchronous motor field to 120 amps.
 16072 Close K-153.
 16074 Select Dewar 5 pressure feedback.
 16076 Open K-62.
 16091 Switch the following shutdown outputs to
 NORMAL:
 Speed Rate, C-8, C-221

16093 Raise the D. C. motor field to 13 amps.
16102 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-61

16110 In K-53 PRESSURE Control, establish 65 psig in Dewar 5.
16116 Use C-106 to chill CT-106.
16120 At CTO command, Open C-11, Close C-111.
16128 Use K-161 to maintain KP-61 between 20 and 30 psig.
16138 Open C-221.
16140 Close C-231.
16144 Set C-8 to 530 pot divisions.
161250 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

16253 Activate the following inputs to the shutdown chain:

D. C. Breakers, CT-507

16276 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.
16278 Switch C-106 to AUTO.
16280 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

16282 Open C-231 to 85 pot divisions.
16283 Close C-221.
16289 Use C-231 to establish and maintain 30 psig at CP-220.
16296 Switch to Q/N Control and establish Q/N - .25.
16313 Switch to SPEED Control.
16316 Switch Speed Rate Control to HOLD.

16320 Set Speed Rate pot to 160 divisions
(800 rpm/sec).

16327 Demand 22,000 rpm.

16329 Switch Speed Rate Control to RUN.

16334 On Ramp, Open C-231.

16369 Use C-8 in Q/N Control to establish a Q/N = .30.

16371 Report CP-700D. 500 psid.

16376 Slowly decrease K-3 position.

16450 Open K-3 (Q/N = .30 at 22,000 rpm --
K-3 minimum pot setting = 426 divisions).

16486 Increase speed to 24,000 rpm - maintain Q/N = .30.

16490 Report CP-700D. 600 psid.

16493 Slowly decrease K-3 position.

16546 Open K-3 (Q/N = .30 at 24,000 rpm --
K-3 minimum pot setting = 452 divisions).

16586 Increase speed to 26,000 rpm.

16588 Increase Dewar 5 pressure to 75 psig.

16591 Report CP-700D. 710 psid.

16597 Slowly decrease K-3 position.

16626 Open K-3 (Q/N = .30 at 26,000 rpm --
K-3 minimum pot setting = 460 divisions).

16628 At TD command, push the shutdown button.

16630 Switch C-231 to POSITION Control and close.

16640 Open D.C. breakers.

16645 Switch C-106 to RESET.

16646 Bypass all the shutdown inputs.

16647 Reset the shutdown chain.

16660 Use C-111 to maintain CP-9 between
60 and 100 psig.

16668 Close C-11.

16673 Switch K-53 to POSITION Control and close.

16678 Close K-62.

16682 Open K-153.

16686 Decrease D.C. motor field to less than 5 amps.

16690 Switch the shutdown outputs to OVERRIDE.

16800 Dewar transfer.

VI. CAVITATION TEST PHASE RUN #13 - 43^oR

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
22,000	.30
24,000	.30

The supply dewar pressure will be maintained at 70 psig.

A. PROCEED WITH CAVITATION TEST.

- 17750 Bottle 6 on line.
- a. QP-30: 3000 psig
- 17996 Set the overspeed trip pot to 730 divisions (28,000 rpm).
- 18010 Raise the synchronous motor field to 120 amps.
- 18015 Raise the D. C. motor field to 13 amps.
- 18016 Close K-153.
- 18023 Select Dewar 4 pressure feedback.
- 18027 Open K-61.
- 18041 Switch the following shutdown outputs to NORMAL:
- Speed Rate, C-8, C-221
- 18048 Activate the following inputs to the shutdown chain:
- | | |
|------------|--------|
| UQ-2 | CP-220 |
| UQ-3 | CP-505 |
| Jp-101/201 | KP-62 |
- 18051 In K-53 PRESSURE Control, establish 70 psig in Dewar 4.
- 18056 Use C-106 to chill CT-106.
- 18064 At CTO command Open C-12, Close C-111.
- 18071 Use K-162 to maintain KP-62 between 30 and 40 psig.
- 18076 Open C-221.
- 18078 Close C-231.
- 18080 Set C-8 to 530 pot divisions.
- 18207 When the pump is chilled, close the D. C. breakers.
- a. PMP: Report pump chill.
- 18214 Activate the following inputs to the shutdown chain:

D. C. Breakers

222

18228 In MANUAL Control, establish 10,000 rpm
at a Q/N = .22.

18230 Switch C-106 to AUTO.

18234 At CTO command, activate the following
inputs to the shutdown chain:

Q/N High
Q/N Low

18238 Open C-231 to 85 pot divisions.

18240 Close C-221.

18243 Use C-231 to establish and maintain
30 psig at CP-220.

18251 Switch to Q/N Control and establish Q/N = .25.

18266 Switch to SPEED Control.

18268 Switch Speed Rate Control to HOLD.

18274 Set Speed Rate pot to 160 divisions
(800 rpm/sec).

18278 Demand 22,000 rpm.

18282 Switch Speed Rate Control to RUN.

18287 On Ramp, Open C-231.

18316 Use C-8 in Q/N Control to establish a Q/N = .30.

18320 Report CP-700D. 480 psid.

18325 Slowly decrease K-3 position.

18362 Open K-3 (Q/N = .30 at 22,000 rpm --
K-3 minimum pot setting = 460 divisions).

18388 80 psig set in Dewar 4.

18396 Increase speed to 24,000 rpm and maintain
Q/N = .30.

18400 Report CP-700D. 580 psid.

18402 Slowly decrease K-3 position.

18454 Open K-3 (Q/N = .30 at 24,000 rpm --
K-3 minimum pot setting = 440 divisions).

18464 At TD command, push the shutdown button

18481 Open D.C. breakers.

18486 Switch C-231 to POSITION Control and close.

18487 Switch C-106 to RESET.

18489 Bypass all the shutdown inputs.

18490 Reset the shutdown chain.

18496 Use C-111 to maintain CP-9 between
60 and 100 psig.

18497 Close C-12.

18508	Switch K-53 to POSITION Control and close.
18513	Close K-61.
18516	Open K-153.
18520	Decrease D. C. motor field to less than 5 amps.
18522	Switch the shutdown outputs to OVERRIDE.

VII. DEWAR 1 TO DEWAR 4/5 LH₂ TRANSFER

During this phase, Dewar 4/5 will be refilled by transferring LH₂ from Dewar 1.

A. PROCEED WITH THE LH₂ TRANSFER.

18922	Open L-251.
18930	Close L-261, L-153.
18940	Open L-61, L-301, L-330.
18953	Open L-331, X-301.
18983	Close K-401.
19004	Use L-53 in POSITION Control to establish and maintain 65 psig in Dewar 1.
19012	When LP-61 is greater than KP-61/62, Open K-301/302.
19024	Use K-161/162 to vent Dewar 4/5.
25830	When LH ₂ transfer is complete, Close K-301/302.

VIII. CAVITATION TEST PHASE RUN #14 - 37.5°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
26,000	.30

The supply dewar pressure will be maintained at 80 psig.

A. PROCEED WITH CAVITATION TEST.

27850	Nevada Power loop closed.
28087	Set the overspeed trip pot to 730 divisions (28,000 rpm).
28097	Raise the synchronous motor field to 120 amps.

28100 Close K-153.
 28103 Select Dewar 5 pressure feedback.
 28108 Open K-62.
 28118 Switch the following shutdown outputs to
 NORMAL:

 Speed Rate, C-8, C-221

28127 Activate the following inputs to the shutdown
 chain:

 UQ-2 CP-220
 UQ-3 CP-505
 JP-101/201 KP-61

28130 Raise the D. C. motor field to 13 amps.
 28138 In K-53 PRESSURE Control, establish
 80 psig in Dewar 5.
 28202 Use C-106 to chill CT-106.
 28218 At CTO command Open C-11, Close C-111.
 28223 Use K-161 to maintain KP-61 between
 30 and 40 psig.
 28226 Open C-221
 28228 Close C-231.
 28232 Set C-8 to 530 pot divisions.
 28490 When the pump is chilled, close the
 D.C. breakers.

 a. PMP: Report pump chill.

28494 Activate the following inputs to the shutdown
 chain:

 D.C. Breakers, CT-507

28512 In MANUAL Control, establish 10,000 rpm
 at a Q/N = .22.
 28513 Switch C-106 to AUTO.
 28516 At CTO command, activate the following
 inputs to the shutdown chain:

 Q/N High
 Q/N Low

28520 Open C-231 to 85 pot divisions.
 28523 Close C-221.
 28528 Use C-231 to establish and maintain
 30 psig at CP-220.
 28540 Switch to Q/N Control and establish Q/N = .30.
 28556 Switch to SPEED Control.
 28558 Switch Speed Rate Control to HOLD.
 28564 Set Speed Rate pot to 160 divisions
 (800 rpm/sec).
 28568 Demand 24,000 rpm.
 28573 Switch Speed Rate Control to RUN.
 28580 On Ramp, Open C-231.
 28600 Use C-8 in Q/N Control to establish a Q/N = .30.
 28603 Increase speed to 26,000 rpm.
 28627 Report CP-700D. 740 psid.
 28634 Slowly decrease K-3 position.
 28710 Open K-3 (Q/N = .30 at 26,000 rpm --
 K-3 minimum pot setting = 433 divisions).
 28738 Increase KP-62 to 100 psig.
 28741 Decrease speed to 23,000 rpm.
 28744 Bypass Q/N High.
 28748 Decrease Q/N to .28.
 28810 Increase Q/N slowly (.36 maximum).
 28816 At PMP Command, decrease Q/N to .25.
 28831 At TD command, push the shutdown button.
 28842 Open D.C. breakers.
 28846 Bypass all the shutdown inputs.
 28848 Switch C-231 to POSITION Control and close.
 28850 Switch C-106 to RESET.
 28852 Reset the shutdown chain.
 28860 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 28868 Close C-11.
 28880 Switch K-53 to POSITION Control and close.
 28884 Close K-62.
 28888 Open K-153.
 28891 Decrease D.C. motor field to less than 5 amps.
 28892 Switch the shutdown outputs to OVERRIDE.
 28980 Dewar transfer.

IX.

CAVITATION TEST PHASE RUN #15 - 43°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
24,000	.24
26,000	.30

The supply dewar pressure will be maintained at 90 psig.

A. PROCEED WITH CAVITATION TEST

- 30080 Set the overspeed trip pot to 730 divisions (28,000 rpm).
- 30086 Raise the synchronous motor field to 120 amps.
- 30094 Close K-153.
- 30100 Select Dewar 4 pressure feedback.
- 30101 Open K-61.
- 30114 Switch the following shutdown outputs to NORMAL:
- Speed Rate, C-8, C-221
- 30123 Activate the following inputs to the shutdown chain:
- UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-62
- 30130 Raise the D. C. motor field to 13 amps.
- 30134 In K-53 PRESSURE Control, establish 90 psig in Dewar 4.
- 30136 Use C-106 to chill CT-106.
- 30149 Use K-162 to maintain KP-62 between 50 and 60 psig.
- 30152 At CTO command Open C-12, Close C-111.
- 30154 Open C-221.
- 30156 Close C-231.
- 30159 Set C-8 to 530 pot divisions.
- 30226 When the pump is chilled, close the D.C. breakers.
- a. PMP: Report pump chill.

227

30234 Activate the following inputs to the shutdown chain:

D. C. Breakers

30249 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

30250 Switch C-106 to AUTO.

30251 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

30253 Open C-231 to 85 pot divisions.

30256 Close C-221.

30262 Use C-231 to establish and maintain 30 psig at CP-220.

30271 Switch to Q/N Control and establish Q/N = .30.

30293 Switch to SPEED Control.

30296 Switch Speed Rate Control to HOLD.

30301 Set Speed Rate pot to 160 divisions (800 rpm/sec).

30306 Demand 26,000 rpm.

30308 Switch Speed Rate Control to RUN.

30313 On Ramp, Open C-231.

30338 Use C-8 in Q/N Control to establish a Q/N = .30.

30342 Report CP-700D. 680 psid.

30350 Slowly decrease K-3 position.

30426 Open K-3 (Q/N = .30 at 26,000 rpm -- K-3 minimum pot setting = 443 divisions).

30446 Decrease speed to 24,000 rpm.

30468 Use C-8 to decrease Q/N to .24.

30474 Report CP-700D. 650 psid.

30480 Slowly decrease K-3 position.

30540 Open K-3 (Q/N = .24 at 24,000 rpm -- K-3 minimum pot setting = 367 divisions).

30550 At TD command, push the shutdown button.

30562 Open D. C. breakers.

30564 Switch C-231 to POSITION Control and close.

30574 Switch C-106 to RESET.

- 30576 Bypass all the shutdown inputs.
- 30579 Reset the shutdown chain.
- 30586 Use C-111 to maintain CP-9 between 60 and 100 psig.
- 30596 Close C-12.
- 30600 Switch K-53 to POSITION Control and close.
- 30611 Close K-61.
- 30617 Open K-153.
- 30620 Decrease D. C. motor field to less than 5 amps.
- 30623 Switch the shutdown outputs to OVERRIDE.
- 30642 Dewar transfer.

X. LOW SPEED MAPPING

During this phase, pump mapping will be performed at speed of 3,000, 6,000, 9,000 and 12,000 rpm at Q/N's of .14 to .35. Supply fluid temperature will be 39°R. Dewar pressure will be maintained at 40 psig.

A. PROCEED WITH LOW SPEED MAPPING.

- 31968 Set the overspeed trip pot to 550 divisions (21,000 rpm).
- 31973 Raise the synchronous motor field to 120 amps.
- 31980 Close K-153.
- 31986 Select Dewar 5 pressure feedback.
- 31988 Open K-62.
- 32020 In K-53 PRESSURE Control, establish 40 psig in Dewar 5.
- 32023 Raise the D. C. motor field to 13 amps.
- 32046 Bottles 5 and 6 on line.
- 32056 Switch the following shutdown outputs to NORMAL:

Speed Rate, C-8, C-221
- 32064 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-61

32070 Use C-106 to chill CT-106.
 32081 At CTO command Open C-11, Close C-111.
 32100 Open K-161.
 32103 Open C-221.
 32106 Close C-231.
 32112 Set C-8 to 530 pot divisions.
 32274 When the pump is chilled, close the
 D. C. breakers.

 a. PMP: Report pump chill.

 32280 Activate the following inputs to the shutdown
 chain:

 D. C. Breakers, CT-507

 32307 In MANUAL Control, establish 10,000 rpm
 at a Q/N = .22.
 32308 Switch C-106 to AUTO.
 32316 At CTO command, activate the following
 inputs to the shutdown chain:

 Q/N High
 Q/N Low

 32322 Switch to Q/N Control.
 32328 Switch to SPEED Control.
 32386 Increase speed to 12,000 rpm.
 32394 Use C-8 to increase Q/N to .30.

 a. Use .02 increments.

 32433 Use C-8 to increase Q/N to .35.

 a. Use .02 increments.

 32476 Use C-8 to decrease Q/N to .25.
 32478 Bypass Q/N Low input.
 32480 Switch C-106 to RESET.
 32538 Use C-8 to decrease Q/N to .14.
 32567 Decrease speed to 9,000 rpm.

32630	Switch C-8 to POSITION Control.
32632	Use C-8 and C-106 to increase Q/N to .35.
32634	C-106 switched to RESET.
32636	Q/N High and Low bypassed.
32680	Decrease speed to 6,000 rpm.
32730	Use C-8 to decrease Q/N to .14. (40% on C-8)
32758	Decrease speed to 3,000 rpm.
32831	Use C-8 to increase Q/N to .35 (550 pot divisions).
32841	Bypass the following shutdown inputs: CT-507, Q/N High, Q/N Low
32853	Switch to MANUAL Control and decrease speed to zero.
32864	Open D. C. breakers.
32867	Bypass all the shutdown inputs.
32871	Reset the shutdown chain.
32876	Use C-111 to maintain CP-9 between 60 and 100 psig.
32888	Close C-11.
32904	Switch K-53 to POSITION Control and close.
32907	Close K-62.
32911	Open K-153.
32916	Decrease D. C. motor field to less than 5 amps.
32918	Switch the shutdown outputs to OVERRIDE.

XI. SHUTDOWN PHASE - MINIMUM

33800



A. POST CALIBRATION.

36551-36651 Calibration interval.



END

231

CHRONOLOGY FOR CEL INDUCER TEST

EXPERIMENTAL PLAN II

17 DECEMBER 1971

232

I. PRE-OPERATIONAL PHASE

During this phase, verification will be made of the Test Cell "C" readiness to conduct a test using the CEL and Electric Drive Systems. Facility setup checklists will be reviewed, personnel locations will be determined, the Operators communication net will be checked, and systems switch to LCR control. Valves and systems necessary for the test will then be operated, room inerting will be started, and a voltage calibration performed.

- A. SETUP CHECKLISTS HAVE BEEN REVIEWED AND APPROVED.
- B. REPORT ON STATUS OF PERSONNEL IN TEST CELL "C" AREA.
- C. CHECK THE OPERATORS NET.
- D. HAVE THE REQUIRED SYSTEMS SWITCHED TO LCR CONTROL.
- E. EXERCISE THE VALVES IN THE ELECTRIC PUMP ROOM, CEL AND HIGH PRESSURE ROOM.
- F. BEGIN INERTING THE TEST CELL.
- G. CHECK THE SHUTDOWN CHAIN.
- H. PERFORM A VOLTAGE CALIBRATION.

03401-03501 Calibration interval.

II. PRESSURIZATION, CHILLDOWN, OVERSPEED TRIP CHECK

During this phase, the helium and hydrogen headers will be pressurized, Dewar 4/5 will be pressurized, the CEL flow loop will be chilled and soaked, and the overspeed inputs to the shutdown chain will be checked. K-3 and K-130 will be calibrated at a dewar pressure of 40 psig.

- A. PROCEED WITH HEADER PRESSURIZATION.

03742	Report on room inerting.
03750	Open K-50, K-153
03754	Open L-50.
03766	Close Q-120, Q-150, Q-101 thru Q-112.

- 03812 Pressurize the helium header.
 - a. QP-20: 1000 psig
- 03893 Pressurize the hydrogen header with Bottle 6.
 - a. QP-30: 3100 psig

B. PROCEED WITH THE CHILLDOWN.

- 03916 Close K-153, K-403, K-402, K-261, C-408.
- 03924 Close C-221.
- 03941 Open K-1, K-61.
- 03951 Open C-214, C-8.
- 03956 Select Dewar 4 pressure feedback.
- 03974 Slowly Open K-3.
- 04026 In K-53 PRESSURE Control, establish
60 psig in Dewar 4.
- 04196 Use C-111 to chill CT-3 to 100°R.
 - a. PMP: Report CT-3.
- 04200 Slowly Close K-3.
- 04503 Use K-130 to chill KT-130.
 - a. DSO: Report KT-130.
- 04508 Close K-130.
- 04595 When CP-8 is less than 10 psig, Open C-4,
C-231; Close C-214.
- 04597 Use C-106 to establish and maintain CP-505
between 10 and 20 psig.
- 04600 Close C-111.
- 04908 Use K-130 to maintain 3 lbs/sec at KF-130.
 - a. CTO: Monitor CF-6.
- 04910 When pump is chilled, slowly open K-3.
- 04934 Close K-130.
- 04944 Use C-111 to chill CT-111.
- 04950 Close C-106.
- 05000 When CT-111 is chilled, set C-111 to
maintain CP-9 between 80 and 100 psig.
- 05003 Open C-221.
- 05006 Close C-231.

05017 Start 900 second timer.
05022 Switch K-53 to POSITION Control and close.
05031 Close K-61.
05034 Open K-153.

C. PROCEED WITH STARTUP OF A. C. MOTOR.

05056 Report electric drive alarm status.
05060 Start synchronous motor.
05131 Start blowers.
05146 Establish synchronous motor field at 120 amps.
05178 Increase D. C. motor field to 13 amps, then decrease to 5 amps.
05230 Raise and lower armature voltage.
05321 D. C. motor field amps will not reduce (Field remains at 13 amps).

D. PROCEED WITH OVERSPEED TRIP CHECK.

06192 Set the overspeed trip pot to 105 divisions (4,000 rpm).
06201 Raise synchronous motor field to 120 amps.
06205 Raise D. C. motor field to 13 amps.
06208 Close K-153.
06214 Select Dewar 4 pressure feedback.
06228 Open K-61.
06230 In K-53 PRESSURE Control, establish 55 psig in Dewar 4.
06234 Switch the following shutdown output to NORMAL:

Speed Rate.

06246 Activate the following inputs to the shutdown chain:

UQ-2 JP-101/201
CP-220 CP-505

06248 Open K-3.
06250 Close K-130.

06257 Open C-11.
 06261 Close C-111.
 06266 Open K-161.
 06268 Open C-221.
 06270 Close C-231.
 06272 Use C-8 to chill the pump.
 06274 Set C-8 to 55%. (Q/N = .22)
 06507 Set C-106 to 15%.
 06511 When the pump is chilled, close the
 D.C. breakers.

a. PMP: Report pump chill.

06514 Activate CT-507 input to the shutdown chain.
 06528 Establish 3,000 rpm.
 06559 In MANUAL Control, increase speed to
 produce overspeed trip (4,000 rpm).
 06567 Reset the shutdown chain.
 06569 Bypass UQ-2 shutdown input.
 06574 Activate UQ-3 shutdown input.
 06626 In MANUAL Control, increase speed to
 produce overspeed trip (6,000 rpm).
 06637 When speed is zero, open the D.C. breakers.
 06640 Bypass all the shutdown inputs.
 06643 Reset the shutdown chain.
 06646 Close C-106.
 06653 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 06656 Switch K-53 to POSITION Control and close.
 06660 Close K-61.
 06662 Open K-153.
 06672 Switch the shutdown outputs to OVERRIDE.

III. CAVITATION TEST PHASE RUN #16 - 37.5°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
22,000	.17, .24
24,000	.17

The supply dewar pressure will be maintained at 85 psig.

A. PROCEED WITH CAVITATION TEST.

- 06740 Set the overspeed trip pot to 680 divisions
(26,000 rpm).
- 06747 Raise the synchronous motor field to 120 amps.
- 06750 Raise the D. C. motor field to 13 amps.
- 06754 Close K-153.
- 06758 Select Dewar 5 pressure feedback.
- 06764 Open K-62.
- 06792 Switch the following shutdown outputs to
NORMAL:
- Speed Rate, C-8, C-221
- 06808 In K-53 PRESSURE Control, establish
55 psig in Dewar 5.
- 06810 Activate the following inputs to the shutdown
chain:
- | | |
|------------|--------|
| UQ-2 | CP-220 |
| UQ-3 | CP-505 |
| JP-101/201 | KP-61 |
- 06833 Use C-106 to chill CT-106.
- 06860 At CTO command Open C-11, Close C-111.
- 06877 Use K-161 to maintain KP-61 between
40 and 50 psig.
- 06881 Open C-221.
- 06884 Close C-231.
- 06886 Set C-8 to 530 pot divisions.
- 06958 Increase Dewar 5 pressure to 85 psig.
- 06964 When the pump is chilled, close the
D. C. breakers.
- a. PMP: Report pump chill.
- 06970 Activate the following inputs to the shutdown
chain:
- D. C. Breakers, CT-507

06982 In MANUAL Control, establish 10,000 rpm
at a Q/N = .22.

06984 Switch C-106 to AUTO.

06990 At CTO command, activate the following
inputs to the shutdown chain:

Q/N High
Q/N Low

06991 Open C-231 to 85 pot divisions.

06996 Close C-221.

06998 Use C-231 to establish and maintain
30 psig at CP-220.

07010 Switch to Q/N Control and establish Q/N = .20.

07020 Switch to SPEED Control.

07022 Switch Speed Rate Control to HOLD.

07025 Set Speed Rate pot to 160 divisions
(800 rpm/sec).

07032 Demand 24,000 rpm.

07034 Switch Speed Rate Control to RUN.

07037 On Ramp, Open C-231.

07073 Use C-8 to establish a Q/N = .17.

07076 Report CP-700D. 750 psid.

07080 Slowly decrease K-3 position.

07163 Open K-3 (Q/N = .17 at 24,000 rpm --
K-3 minimum pot setting = 329 divisions).

07188 Decrease speed to 22,000 rpm.

07196 Use C-8 to maintain Q/N at .17.

07198 Report CP-700D. 640 psid.

07201 Slowly decrease K-3 position.

07260 Open K-3 (Q/N = .17 at 22,000 rpm --
K-3 minimum pot setting = 300 divisions).

07304 Use C-8 to increase Q/N to .24.

07307 Report CP-700D. 580 psid.

07316 Slowly decrease K-3 position.

07377 Open K-3 (Q/N = .24 at 22,000 rpm --
K-3 minimum pot setting = 510 divisions).

07391 At TD command, push the shutdown button.

07403 Open D.C. breakers.

07404 Switch C-231 to POSITION Control and close.

07406 Switch C-106 to RESET.

07410 Bypass all the shutdown inputs.

07413 Reset the shutdown chain.

07420 Use C-111 to maintain CP-9 between
60 and 100 psig.
07426 Close C-11.
07436 Switch K-53 to POSITION Control and close.
07444 Close K-62.
07447 Open K-153.
07457 Switch the shutdown outputs to OVERRIDE.
07480 Dewar transfer.

IV. CAVITATION TEST PHASE RUN #17 - 43°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
19,000	.17, .24
22,000	.17, .24
24,000	.17

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH CAVITATION TEST.

08468 Set the overspeed trip pot to 680 divisions
(26,000 rpm).
08477 Raise the synchronous motor field to 120 amps.
08479 Raise the D.C. motor field to 13 amps.
08482 Close K-153.
08486 Select Dewar 4 pressure feedback.
08489 Open K-61.
08506 Switch the following shutdown outputs to NORMAL:

Speed Rate, C-8, C-221

08520 Activate the following inputs to the shutdown chain:

UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-62

08530 Use C-106 to chill CT-106.
08531 In K-53 PRESSURE Control, establish
100 psig in Dewar 4.
08542 At CTO command Open C-12, Close C-111.

239

08554 Use K-162 to maintain KP-62 between
50 and 60 psig.

08556 Open C-221.

08558 Close C-231.

08562 Set C-8 to 530 pot divisions.

08622 When the pump is chilled, close the
D.C. breakers.

a. PMP: Report pump chill.

08626 Activate the following inputs to the shutdown
chain:

D.C. Breakers, CT-507

08654 CT-507 high trip.

08680 CT-507 bypassed.

08706 Close Breaker.

08726 In MANUAL Control, establish 10,000 rpm
at a Q/N = .22.

08730 Switch C-106 to AUTO.

08734 At CTO command, activate the following
inputs to the shutdown chain:

Q/N High
Q/N Low

08736 Open C-231 to 85 pot divisions.

08740 Close C-221.

08746 Use C-231 to establish and maintain
30 psig at CP-220.

08750 Switch to Q/N Control and establish Q/N = .17.

08769 Switch to SPEED Control.

08771 Switch Speed Rate Control to HOLD.

08777 Set Speed Rate pot to 160 divisions
(800 rpm/sec).

08782 Demand 24,000 rpm.

08784 Switch Speed Rate Control to RUN.

08786 On Ramp, Open C-231.

08810 Use C-8 in Q/N Control to establish a Q/N = .17.

08813 Report CP-700D. 710 psid.
 08818 Slowly decrease K-3 position.
 08892 Open K-3 (Q/N = .17 at 24,000 rpm --
 K-3 minimum pot setting = 324 divisions).
 08914 Decrease speed to 22,000 rpm.
 08917 Use C-8 to maintain a Q/N of .17.
 08920 Report CP-700D. 590 psid.
 08927 Slowly decrease K-3 position.
 08973 Open K-3 (Q/N = .17 at 22,000 rpm --
 K-3 minimum pot setting = 298 divisions).
 09000 Use C-8 to increase Q/N to .24.
 09004 Report CP-700D. 540 psid.
 09008 Slowly decrease K-3 position.
 09056 Open K-3 (Q/N = .24 at 22,000 rpm --
 K-3 minimum pot setting = 436 divisions).
 09087 Decrease speed to 19,000 rpm.
 09088 Use C-8 to maintain a Q/N = .24.
 09091 Report CP-700D. 390 psid.
 09096 Slowly decrease K-3 position.
 09137 Open K-3 (Q/N = .24 at 19,000 rpm --
 K-3 minimum pot setting = 350 divisions).
 09170 Use C-8 to decrease Q/N to .17.
 09177 Report CP 700D. 430 psid.
 09180 Slowly decrease K-3 position.
 09237 Open K-3 (Q/N = .17 at 19,000 rpm --
 K-3 minimum pot setting = 253 divisions).
 09246 At TD command, push the shutdown button.
 09256 Open D.C. breakers.
 09261 Switch C-231 to POSITION Control and close.
 09263 Switch C-106 to RESET.
 09266 Bypass all the shutdown inputs.
 09268 Reset the shutdown chain.
 09270 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 09274 Close C-12.
 09287 Close K-61.
 09292 Switch K-53 to POSITION Control and close.
 09298 Open K-153.
 09306 Switch the shutdown outputs to OVERRIDE.
 09700 Dewar transfer and boil-off.

241

V.

CAVITATION TEST PHASE RUN #18 - 41°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
26,000	.17, .21

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH CAVITATION TEST.

10891	Set the overspeed trip pot to 730 divisions (28,000 rpm).
10900	Raise the synchronous motor field to 120 amps.
10905	Raise the D. C. motor field to 13 amps.
10906	Close K-153.
10908	Select Dewar 5 pressure feedback.
10913	Open K-62.
11004	Switch the following shutdown outputs to NORMAL: Speed Rate, C-8, C-221
11014	Activate the following inputs to the shutdown chain: UQ-2 CP-220 UQ-3 CP-505 JP-101/201 KP-61
11028	In K-53 PRESSURE Control, establish 100 psig in Dewar 5.
11036	Use C-106 to chill CT-106.
11048	At CTO command Open C-11, Close C-111.
11056	Use K-161 to maintain KP-61 between 60 and 70 psig.
11061	Open C-221.
11063	Close C-231.
11065	Set C-8 to 530 pot divisions.

11157 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

11164 Activate the following inputs to the shutdown chain:

D. C. Breakers, CT-507

11186 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

11196 Switch C-106 to AUTO.

11198 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

11202 Open C-231 to 85 pot divisions.

11204 Close C-221.

11206 Use C-231 to establish and maintain 30 psig at CP-220.

11216 Switch to Q/N Control and establish Q/N = .17.

11233 Switch to SPEED Control.

11236 Switch Speed Rate Control to HOLD.

11240 Set Speed Rate pot to 160 divisions (800 rpm/sec).

11246 Demand 26,000 rpm.

11251 Switch Speed Rate Control to RUN.

11259 On Ramp, Open C-231.

11280 Use C-8 in Q/N Control to establish a Q/N = .17.

11287 Report CP-700D. 860 psid.

11289 Slowly decrease K-3 position.

11381 Open K-3 (Q/N = .17 at 26,000 rpm -- K-3 minimum pot setting = 340 divisions).

11440 Use C-8 to increase Q/N to .24. (.21 max. reached)

11447 Report CP-700D. 810 psid.

11453 Slowly decrease K-3 position.

11516 Open K-3 (Q/N = .21 at 26,000 rpm -- K-3 minimum pot setting = 487 divisions).

11530 At TD command, push the shutdown button.
 11544 Open D. C. breakers.
 11546 Switch C-231 to POSITION Control and close.
 11547 Switch C-106 to RESET.
 11548 Bypass all the shutdown inputs.
 11550 Reset the shutdown chain.
 11558 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 11568 Close C-11.
 11578 Switch K-53 to POSITION Control and close.
 11581 Close K-62.
 11586 Open K-153.
 11590 Switch the shutdown outputs to OVERRIDE.
 11630 Dewar transfer.

VI. CAVITATION TEST PHASE RUN #19 - 43^oR

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
26,000	.17, .21

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH CAVITATION TEST.

12910 Bottle 7 on line.
 a. QP-30: 3200 psi
 13001 Set the overspeed trip pot to 730 divisions
 (28,000 rpm).
 13008 Raise the synchronous motor field to 120 amps.
 13011 Raise the D. C. motor field to 13 amps.
 13014 Close K-153.
 13019 Select Dewar 4 pressure feedback.
 13026 Open K-61.
 13035 Switch the following shutdown outputs to
 NORMAL:
 Speed Rate, C-8, C-221

244

13050 Activate the following inputs to the shutdown chain:

UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-62

13060 Use C-106 to chill CT-106.
13080 In K-53 PRESSURE Control, establish 100 psig in Dewar 4.
13083 At CTO command Open C-12, Close C-111.
13085 Use K-162 to maintain KP-62 between 60 and 70 psig.
13086 Open C-221.
13090 Close C-231.
13094 Set C-8 to 530 pot divisions.
13156 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

13163 Activate the following inputs to the shutdown chain:

D. C. Breakers

13183 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.
13187 Switch C-106 to AUTO.
13190 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

13192 Open C-231 to 85 pot divisions.
13194 Close C-221.
13201 Use C-231 to establish and maintain 30 psig at CP-220.
13208 Switch to Q/N Control and establish Q/N = .17.
13223 Switch to SPEED Control.
13225 Switch Speed Rate Control to HOLD.

13230	Set Speed Rate pot to 160 divisions (800 rpm/sec).
13232	Demand 26,000 rpm.
13238	Switch Speed Rate Control to RUN.
13243	On Ramp, Open C-231.
13273	Use C-8 in Q/N Control to establish a Q/N = .17.
13276	Report CP-700D. 840 psid.
13280	Slowly decrease K-3 position.
13353	Open K-3 (Q/N = .17 at 26,000 rpm -- K-3 minimum pot setting = 351 divisions).
13382	Use C-8 to increase Q/N to .21.
13388	Report CP-700D. 800 psid.
13389	Slowly decrease K-3 position.
13450	Open K-3 (Q/N = .21 at 26,000 rpm -- K-3 minimum pot setting = 520 divisions).
13456	At TD command, push the shutdown button.
13471	Open D. C. breakers.
13474	Switch C-231 to POSITION Control and close.
13475	Switch C-106 to RESET.
13477	Bypass all the shutdown inputs.
13478	Reset the shutdown chain.
13487	Use C-111 to maintain CP-9 between 60 and 100 psig.
13493	Close C-12.
13501	Switch K-53 to POSITION Control and close.
13507	Close K-61.
13510	Open K-153.
13516	Switch the shutdown outputs to OVERRIDE.
13594	D. C. motor field reduced less than 5 amps.

VII. DEWAR 1 TO DEWAR 4/5 LH₂ TRANSFER

During this phase, Dewar 4/5 will be refilled by transferring LH₂ from Dewar 1.

A. PROCEED WITH THE LH₂ TRANSFER.

13664	Open L-251.
13686	Close L-262, L-153.
13788	Open L-61/62, L-301, L-330; Close L-61.
13798	Open L-331, X-301.

13808	Close K-401.
13880	Use L-53 in POSITION Control to establish and maintain 65 psig in Dewar 2.
13863	When LP-61 is greater than KP-61/62, Open K-301/302.
20330	When LH ₂ transfer is complete, Close K-301/302.

VIII. CAVITATION TEST PHASE RUN #20 - 37.5°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
26,000	.17, .24

The supply dewar pressure will be maintained at 90 psig.

A. PROCEED WITH CAVITATION TEST.

20881	Set the overspeed trip pot to 730 divisions (26,000 rpm).						
20888	Raise the synchronous motor field to 120 amps.						
20890	Raise the D. C. motor field to 13 amps.						
20896	Close K-153.						
20898	Select Dewar 5 pressure feedback.						
20903	Open K-62.						
20914	Switch the following shutdown outputs to NORMAL: Speed Rate, C-8, C-221						
20924	Activate the following inputs to the shutdown chain: <table> <tr> <td>UQ-2</td> <td>CP-220</td> </tr> <tr> <td>UQ-3</td> <td>CP-505</td> </tr> <tr> <td>JP-101/201</td> <td>KP-61</td> </tr> </table>	UQ-2	CP-220	UQ-3	CP-505	JP-101/201	KP-61
UQ-2	CP-220						
UQ-3	CP-505						
JP-101/201	KP-61						
20951	In K-53 PRESSURE Control, establish 90 psig in Dewar 5.						
20961	Use C-106 to chill CT-106.						

20968 At CTO command Open C-11, Close C-111.
 20981 Use K-161 to maintain KP-61 between
 60 and 70 psig.
 20984 Open C-221.
 20986 Close C-231.
 20990 Set C-8 to 530 pot divisions.
 21186 When the pump is chilled, close the
 D.C. breakers.

 a. PMP: Report pump chill.

 21190 Activate the following inputs to the shutdown
 chain:

 D.C. Breakers, CT-507

 21207 In MANUAL Control, establish 10,000 rpm
 at a Q/N = .22.
 21208 Switch C-106 to AUTO.
 21212 At CTO command, activate the following
 inputs to the shutdown chain:

 Q/N High
 Q/N Low

 21216 Open C-231 to 85 pot divisions.
 21218 Close C-221.
 21223 Use C-231 to establish and maintain
 30 psig at CP-220.
 21230 Switch to Q/N Control and establish Q/N = .17.
 21246 Switch to SPEED Control.
 21248 Switch Speed Rate Control to HOLD.
 21254 Set Speed Rate pot to 160 divisions
 (800 rpm/sec).
 21258 Demand 26,000 rpm.
 21261 Switch Speed Rate Control to RUN.
 21267 On Ramp, Open C-231.
 21290 Use C-8 in Q/N Control to establish a Q/N = .17.
 21294 Report CP-700D. 890 psid.
 21298 Slowly decrease K-3 position.
 21379 Open K-3 (Q/N = .17 at 26,000 rpm --
 K-3 minimum pot setting = 355 divisions).

21438	Use C-8 to increase Q/N to .21.
21439	Increase dewar pressure to 100 psig.
21454	Slowly decrease K-3 position.
21541	Open K-3 (Q/N = .21 at 26,000 rpm -- K-3 minimum pot setting = 465 divisions).
21551	At TD command, push the shutdown button.
21566	Open D. C. breakers.
21575	Switch C-231 to POSITION Control and close.
21576	Switch C-106 to RESET.
21578	Bypass all the shutdown inputs.
21589	Reset the shutdown chain.
21581	Use C-111 to maintain CP-9 between 60 and 100 psig.
21586	Close C-11.
21596	Switch K-53 to POSITION Control and close.
21605	Close K-62.
21606	Open K-153.
21617	Switch the shutdown outputs to OVERRIDE.
21650	Dewar transfer.

IX. CAVITATION TEST PHASE RUN #21 - 39^oR

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
24,000	.21
26,000	.17, .21

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH CAVITATION TEST.

22794	Set the overspeed trip pot to 730 divisions (26,000 rpm).
22800	Raise the synchronous motor field to 120 amps.
22803	Raise the D. C. motor field to 13 amps.
22810	Close K-153.
22850	Bottle 8 on line.

a. QP-30: 3200 psi

22894 Open K-61.
 22896 Select Dewar 4 pressure feedback.
 22902 Switch the following shutdown outputs to
 NORMAL:

 Speed Rate, C-8, C-221

 22918 Activate the following inputs to the shutdown
 chain:

 UQ-2 CP-220
 UQ-3 CP-505
 JP-101/201 KP-62

 22922 Use C-106 to chill CT-106.
 22941 At CTO command Open C-12, Close C-111.
 22948 Use K-162 to maintain KP-62 between
 60 and 70 psig.
 22952 Open C-221.
 22953 Close C-231.
 22957 Set C-8 to 530 pot divisions.
 22963 In K-53 PRESSURE Control, establish
 100 psig in Dewar 4.
 23017 When the pump is chilled, close the
 D. C. breakers.

 a. PMP: Report pump chill.

 23020 Activate the following inputs to the shutdown
 chain:

 D. C. Breakers, CT-507

 23033 In MANUAL Control, establish 10,000 rpm
 at a Q/N = .22.
 23036 Switch C-106 to AUTO.
 23038 At CTO command, activate the following
 inputs to the shutdown chain:

 Q/N High
 Q/N Low

250

23041 Open C-231 to 85 pot divisions.
 23044 Close C-221.
 23051 Use C-231 to establish and maintain
 30 psig at CP-220.
 23056 Switch to Q/N Control and establish Q/N = .17.
 23066 Switch to SPEED Control.
 23068 Switch Speed Rate Control to HOLD.
 23073 Set Speed Rate pot to 160 divisions
 (800 rpm/sec).
 23082 Demand 26,000 rpm.
 23084 Switch Speed Rate Control to RUN.
 23086 On Ramp, Open C-231.
 23112 Use C-8 in Q/N Control to establish a Q/N = .17.
 23114 Report CP-700D. 880 psid.
 23119 Slowly decrease K-3 position.
 23177 Open K-3 (Q/N = .17 at 26,000 rpm --
 K-3 minimum pot setting = 337 divisions).
 23208 Use C-8 to increase Q/N to .21.
 23213 Report CP-700D. 830 psid.
 23216 Slowly decrease K-3 position.
 23304 Open K-3 (Q/N = .21 at 26,000 rpm --
 K-3 minimum pot setting = 468 divisions).
 23322 Decrease speed to 24,000 rpm.
 23330 Use C-8 to maintain a Q/N of .21.
 23333 Report CP-700D. 690 psid.
 23340 Slowly decrease K-3 position.
 23375 Open K-3 (Q/N = .21 at 24,000 rpm --
 K-3 minimum pot setting = 393 divisions).
 23384 At TD command, push the shutdown button.
 23397 Open D.C. breakers.
 23398 Switch C-231 to POSITION Control and close.
 23399 Switch C-106 to RESET.
 23404 Bypass all the shutdown inputs.
 23406 Reset the shutdown chain.
 23412 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 23426 Close C-12.
 23428 Switch K-53 to POSITION Control and close.
 23433 Close K-61.
 23436 Open K-153.
 23440 Switch the shutdown outputs to OVERRIDE.
 23610 Dewar transfer.

X. CAVITATION TEST PHASE RUN #22 - 43°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
19,000	.30

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH CAVITATION TEST.

24293	Set the overspeed trip pot to 550 divisions (21,000 rpm).
24300	Raise the synchronous motor field to 120 amps.
24305	Raise the D. C. motor field to 13 amps.
24307	Close K-153.
24310	Select Dewar 5 pressure feedback.
24314	Open K-62.
24324	Switch the following shutdown outputs to NORMAL: Speed Rate, C-8, C-221
24330	Activate the following inputs to the shutdown chain: UQ-2 CP-220 UQ-3 CP-505 JP-101/201 KP-61
24349	In K-53 PRESSURE Control, establish 100 psig in Dewar 5.
24352	Use C-106 to chill CT-106.
24362	At CTO command Open C-11, Close C-111.
24371	Use K-161 to maintain KP-61 between 60 and 70 psig.
24373	Open C-221.
24375	Close C-231.
24378	Set C-8 to 530 pot divisions.

252

24441 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

24447 Activate the following inputs to the shutdown chain:

D. C. Breakers

24460 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

24462 Switch C-106 to AUTO.

24468 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

24470 Open C-231 to 85 pot divisions.

24472 Close C-221.

24475 Use C-231 to establish and maintain 30 psig at CP-220.

24480 Switch to Q/N Control and establish Q/N = .30.

24502 Switch to SPEED Control.

24504 Switch Speed Rate Control to HOLD.

24507 Set Speed Rate pot to 160 divisions (800 rpm/sec).

24512 Demand 19,000 rpm.

24518 Switch Speed Rate Control to RUN.

24520 On Ramp, Open C-231.

24537 Use C-8 in Q/N Control to establish a Q/N = .30.

24542 Report CP-700D. 350 psid.

24546 Slowly decrease K-3 position.

24598 Open K-3 (Q/N = .30 at 19,000 rpm -- K-3 minimum pot setting = 482 divisions).

24614 At TD command, push the shutdown button.

24630 Open D. C. breakers.

24631 Switch C-231 to POSITION Control and close.

24632 Switch C-106 to RESET.

24633 Bypass all the shutdown inputs.

24636 Reset the shutdown chain.

24652 Use C-111 to maintain CP-9 between
60 and 100 psig.
24658 Close C-11.
24662 Switch K-53 to POSITION Control and close.
24664 Close K-62.
24666 Open K-153.
24668 Switch the shutdown outputs to OVERRIDE.
24720 Dewar transfer.

XI. CAVITATION TEST PHASE RUN #23 - 39°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
24,000	.24

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH CAVITATION TEST.

25616 Set the overspeed trip pot to 680 divisions
(26,000 rpm).
25622 Raise the synchronous motor field to 120 amps.
25627 Raise the D.C. motor field to 13 amps.
25630 Close K-153.
25634 Select Dewar 5 pressure feedback.
25640 Open K-62.
25647 Switch the following shutdown outputs to
NORMAL:

Speed Rate, C-8, C-221

25640 Activate the following inputs to the shutdown
chain:

UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-61

25665 Use C-106 to chill CT-106.

254

25668 In K-53 PRESSURE Control, establish
100 psig in Dewar 5.

25671 At CTO command Open C-11, Close C-111.

25682 Use K-161 to maintain KP-61 between
60 and 70 psig.

25690 Open C-221.

25692 Close C-231.

25694 Set C-8 to 530 pot divisions.

25762 When the pump is chilled, close the
D.C. breakers.

a. PMP: Report pump chill.

25764 Activate the following inputs to the shutdown
chain:

D.C. Breakers, CT-507

25780 In MANUAL Control, establish 10,000 rpm
at a Q/N = .22.

25782 Switch C-106 to AUTO.

25786 At CTO command, activate the following
inputs to the shutdown chain:

Q/N High
Q/N Low

25788 Open C-231 to 85 pot divisions.

25790 Close C-221.

25796 Use C-231 to establish and maintain
30 psig at CP-220.

25800 Switch to Q/N Control and establish Q/N = .24.

25816 Switch to SPEED Control.

25818 Switch Speed Rate Control to HOLD

25832 Set Speed Rate pot to 160 divisions
(800 rpm/sec).

25841 Demand 24,000 rpm.

25846 Switch Speed Rate Control to RUN.

25852 On Ramp, Open C-231.

25868 Use C-8 in Q/N Control to establish a Q/N = .24.

25874 Report CP-700D. 660 psid.

25878 Slowly decrease K-3 position.

25964 Open K-3 (Q/N = .24 at 24,000 rpm --
K-3 minimum pot setting = 512 divisions).
25984 At TD command, push the shutdown button.
25988 Switch C-231 to POSITION Control and close.
25997 Open D.C. breakers.
26001 Bypass all the shutdown inputs.
26004 Reset the shutdown chain.
26008 Switch C-106 to RESET.
26013 Use C-111 to maintain CP-9 between
60 and 100 psig.
26028 Close C-11.
26029 Switch K-53 to POSITION Control and close.
26034 Close K-62.
26038 Open K-153.
26050 Switch the shutdown outputs to OVERRIDE.
26096 Decrease D.C. motor field to less than 5 amps.

POST VOLTAGE CALIBRATION

26541-26641 Calibration interval.



MAXIMUM SHUTDOWN SECURE

26850



END

256

CHRONOLOGY FOR CEL INDUCER TEST

EXPERIMENTAL PLAN II A

22 DECEMBER 1971

257.

I. PRE-OPERATIONAL PHASE

During this phase, verification will be made of the Test Cell "C" readiness to conduct a test using the CEL and Electric Drive Systems. Facility setup checklists will be reviewed, personnel locations will be determined, the Operators communication net will be checked, and systems switched to LCR control. Valves and systems necessary for the test will then be operated, room inerting will be started, and a voltage calibration performed.

- A. SETUP CHECKLISTS HAVE BEEN REVIEWED AND APPROVED.
- B. REPORT ON STATUS OF PERSONNEL IN TEST CELL "C" AREA.
- C. CHECK THE OPERATORS NET.
- D. HAVE THE REQUIRED SYSTEMS SWITCHED TO LCR CONTROL.
- E. EXERCISE THE VALVES IN THE ELECTRIC PUMP ROOM, CEL AND HIGH PRESSURE ROOM.
- F. BEGIN INERTING THE TEST CELL.
- G. CHECK THE SHUTDOWN CHAIN.
- H. PERFORM A VOLTAGE CALIBRATION.

03361-03461 Calibration interval.

II. PRESSURIZATION, CHILLDOWN, OVERSPEED TRIP CHECK

During this phase, the helium and hydrogen headers will be pressurized, Dewar 4 will be pressurized, the CEL flow loop will be chilled and soaked, and the overspeed inputs to the shutdown chain will be checked. K-3 and K-130 will be calibrated at a dewar pressure of 40 psig.

- A. PROCEED WITH HEADER PRESSURIZATION.

03700 Report on room inerting.
03710 Open K-50, K-153.

03713 Open L-50.
 03725 Close Q-120, Q-150, Q-101 thru Q-112.
 03764 Pressurize the helium header.

a. QP-20: 2700 psig

03841 Pressurize the hydrogen header with Bottle 7.

a. QP-30: 1700 psig

B. PROCEED WITH THE CHILLDOWN.

03878 Close K-153, K-262, K-403, K-402, C-408.
 03887 Close C-221.
 03895 Open K-1, K-61.
 03907 Open C-214, C-8.
 03926 Select Dewar 4 pressure feedback.
 03933 Open C-111.
 03959 In K-53 PRESSURE Control, establish
 60 psig in Dewar 4.
 04667 Use K-3 to chill CT-3 for 100°R.
 04680 Close K-3.
 04914 Use K-130 to chill KT-130.
 04919 Close K-130.
 05030 When CP-8 is less than 10 psig Open C-4,
 C-231; Close C-214.

a. PMP: Report CP-8.

05048 Close C-111.
 05053 Use C-106 to establish and maintain CP-505
 between 10 and 20 psig.
 05063 Use K-130 to maintain 3 lbs/sec at KF-130.
 05341 When pump is chilled, slowly open K-3.
 05355 Close K-130.
 05370 Use C-111 to chill CT-111.
 05410 When CT-111 is chilled, set C-111 to
 maintain CP-9 between 80 and 100 psig.
 05412 Open C-221.
 05419 Close C-231.
 05423 Start 900 second timer.

05435 Switch K-53 to POSITION Control and close.
05448 Close K-61.
05451 Open K-153.

C. PROCEED WITH STARTUP OF A.C. MOTOR.

05457 Report electric drive alarm status.
05460 Start synchronous motor.
05535 Start blowers.
05568 Establish and maintain unity power
factor. (120 Amps)
05578 Increase D.C. motor field to 13 amps,
then decrease to 5 amps.
05617 Raise and lower armature voltage.
05631 5 Amps set on D.C. motor field.

D. PROCEED WITH OVERSPEED TRIP CHECK.

06550 Set the overspeed trip pot to 105 divisions
(4,000 rpm).
06556 Close K-153.
06561 Select Dewar 4 pressure feedback.
06569 Raise synchronous motor field to 120 amps.
06572 Raise D.C. motor field to 13 amps.
06580 Open K-61.
06582 In K-53 PRESSURE Control, establish
60 psig in Dewar 4.
06585 Switch the following shutdown output to
NORMAL:

Speed Rate

06590 Activate the following inputs to the shutdown
chain:

UQ-2	CP-220
JP-101/201	CP-505

06600 Open K-3.
06605 Close K-130.
06611 Open C-111.
06616 Open C-221.
06620 Close C-231.

06628 Use C-8 to chill the pump.
06858 Set C-8 to 55%. (Q/N = .22)
06860 Set C-106 to 15%.
06864 When the pump is chilled, close the
D. C. breakers.

a. PMP: Report pump chill.

06868 Activate CT-507 input to the shutdown chain.
06907 In MANUAL Control, increase speed to
produce overspeed trip (4,000 rpm).
06910 Reset the shutdown chain.
06915 Bypass UQ-2 shutdown input.
06918 Activate UQ-3 shutdown input.
06955 In MANUAL Control, increase speed to
produce overspeed trip (4,000 rpm).
06957 When speed is zero, open the D. C. breakers.
06960 Bypass all the shutdown inputs.
06962 Reset the shutdown chain.
06964 Close C-106.
06984 Use C-111 to maintain CP-9 between
60 and 100 psig.
06990 Switch K-53 to POSITION Control and close.
06996 Close K-61.
06999 Open K-153.
07007 Switch the shutdown outputs to OVERRIDE.
07015 Decrease D. C. motor field to less than 5 amps.

III. CAVITATION TEST PHASE RUN #24 - 37.5°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
26,000	.26

The supply dewar pressure will be maintained at 50 psig.

A. PROCEED WITH CAVITATION TEST.

07286 Set the overspeed trip pot to 730 divisions
(28,000 rpm).

07292 Raise the synchronous motor field to 120 amps.
07304 Close K-153.
07307 Select Dewar 5 pressure feedback.
07310 Open K-62.
07315 Raise the D. C. motor field to 13 amps.
07349 Switch the following shutdown outputs to
NORMAL:

Speed Rate, C-8, C-221

07356 Activate the following inputs to the shutdown
chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-61

07371 In K-53 PRESSURE Control, establish
50 psig in Dewar 5.
07384 Use C-106 to chill CT-106.
07410 At CTO command Open C-11, Close C-111.
07424 Use K-161 to maintain KP-61 between
30 and 40 psig.
07429 Open C-221.
07430 Close C-231.
07432 Set C-8 to 530 pot divisions.
07590 Critical power breaker tripped (Data hold).
07982 When the pump is chilled, close the
D. C. breakers.

a. PMP: Report pump chill.

07989 Activate the following inputs to the shutdown
chain:

D. C. Breakers, CT-507

08010 In MANUAL Control, establish 10,000 rpm
at a Q/N = .22.
08013 Switch C-106 to AUTO.

08015 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

08018 Open C-231 to 85 pot divisions.
08020 Close C-221.
08023 Use C-231 to establish and maintain 30 psig at CP-220.
08032 Switch to Q/N Control and establish Q/N = .26.
08051 Switch to SPEED Control.
08054 Switch Speed Rate Control to HOLD.
08058 Set Speed Rate pot to 160 divisions (800 rpm/sec).
08067 Demand 26,000 rpm.
08071 Switch Speed Rate Control to RUN.
08074 On Ramp, Open C-231.
08097 Use C-8 in Q/N Control to establish a Q/N = .26.
08103 Report CP-700D. 760 psid.
08106 Slowly decrease K-3 position.
08152 Close K-3 (Q/N = .26 at 26,000 rpm -- K-3 minimum pot setting = 484 divisions).
08162 At TD command, push the shutdown button.
08177 Open D.C. breakers.
08179 Bypass all the shutdown inputs.
08180 Switch C-231 to POSITION Control and close.
08182 Switch C-106 to RESET.
08184 Reset the shutdown chain.
08194 Use C-111 to maintain CP-9 between 60 and 100 psig.
08198 Close C-11.
08207 Switch K-53 to POSITION Control and close.
08211 Close K-62.
08213 Open K-153.
08219 Decrease D.C. motor field to less than 5 amps.
08225 Switch the shutdown outputs to OVERRIDE.
08240 Dewar transfer.

IV. PUMP MAPPING

During this phase, pump mapping will be performed at a speed of 23,000 rpm at Q/N's of .14 to .34. Supply fluid temperature will be 37.5°R. Dewar pressure will be maintained at 50 psig.

A. PROCEED WITH PUMP MAPPING.

- 08757 Set the overspeed trip pot to 680 divisions (26,000 rpm).
- 08762 Raise the synchronous motor field to 120 amps.
- 08770 Raise the D. C. motor field to 13 amps.
- 08793 Close K-153.
- 08800 Select Dewar 4 pressure feedback.
- 08808 Open K-61.
- 08818 Switch the following shutdown outputs to NORMAL:
- Speed Rate, C-8, C-221
- 08029 Activate the following inputs to the shutdown chain:
- | | |
|------------|--------|
| UQ-2 | CP-220 |
| UQ-3 | CP-505 |
| JP-101/201 | KP-62 |
- 08835 In K-53 PRESSURE Control, establish 50 psig in Dewar 4.
- 08841 Use C-106 to chill CT-106.
- 08848 At CTO command Open C-12, Close C-111.
- 08854 Use K-162 to maintain KP-62 between 30 and 40 psig.
- 08860 Open C-221.
- 08863 Close C-231.
- 08868 Set C-8 to 530 pot divisions.
- 08949 When the pump is chilled, close the D. C. breakers.

a. PMP: Report pump chill.

264

08954 Activate the following inputs to the shutdown chain:

 D.C. Breakers, CT-507

08973 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

09012 At CTO command, activate the following inputs to the shutdown chain:

 Q/N High

09018 Open C-231 to 85 pot divisions.

09020 Close C-221.

09026 Use C-231 to establish and maintain 30 psig at CP-220.

09032 Switch to Q/N Control and establish Q/N = .14.

09054 Switch to SPEED Control.

09057 Switch Speed Rate Control to HOLD.

09062 Set Speed Rate pot to 160 divisions (800 rpm/sec).

09069 Demand 23,000 rpm.

09073 Switch Speed Rate Control to RUN.

09078 On Ramp, Open C-231.

09101 Use C-8 to establish Q/N = .14.

09136 Switch C-106 to AUTO.

09139 Q/N Low activated.

09205 Dewar 4 pressure increased to 60 psig.

09218 Use C-8 to increase Q/N to .34 in Q/N Control.

09221 At TD command, push the shutdown button.

09243 Open D.C. breakers.

09246 Switch C-231 to POSITION Control and close.

09249 Switch C-106 to RESET.

09250 Bypass all the shutdown inputs.

09252 Reset the shutdown chain.

09254 Use C-111 to maintain CP-9 between 60 and 100 psig.

09262 Close C-12.

09274 Switch K-53 to POSITION Control and close.

09276 Close K-61.

09280 Open K-153.
 09288 Decrease D. C. motor field to less than 5 amps.
 09290 Switch the shutdown outputs to OVERRIDE.
 09360 Dewar transfer.

B. VOLTAGE CALIBRATION.

09831-09931 Calibration interval.

V. CAVITATION TEST PHASE RUN #25 - 39° R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
27,000	.28

The supply dewar pressure will be maintained at 80 psig.

A. PROCEED WITH CAVITATION TEST.

10397 Set the overspeed trip pot to 760 divisions
 (28,000 rpm).
 10404 Raise the synchronous motor field to 120 amps.
 10406 Raise the D. C. motor field to 13 amps.
 10408 Close K-153.
 10410 Select Dewar 5 pressure feedback.
 10415 Open K-62.
 10426 Switch the following shutdown outputs to
 NORMAL:

Speed Rate, C-8, C-221

10434 Activate the following inputs to the shutdown
 chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-61

266

10450 In K-53 PRESSURE Control, establish
80 psig in Dewar 5.

10457 Use C-106 to chill CT-106.

10465 At CTO command Open C-11, Close C-111.

10480 Use K-161 to maintain KP-61 between
30 and 40 psig.

10484 Open C-221.

10486 Close C-231.

10490 Set C-8 to 530 pot divisions.

10621 When the pump is chilled, close the
D.C. breakers.

a. PMP: Report pump chill.

10626 Activate the following inputs to the shutdown
chain:

D.C. Breakers, CT-507

10647 In MANUAL Control, establish 10,000 rpm
at a Q/N = .22.

10650 Switch C-106 to AUTO.

10656 At CTO command, activate the following
inputs to the shutdown chain:

Q/N High
Q/N Low

10661 Open C-231 to 85 pot divisions.

10663 Close C-221.

10668 Use C-231 to establish and maintain
30 psig at CP-220.

10672 Switch to Q/N Control and establish Q/N = .28.

10699 Switch to SPEED Control.

10700 Switch Speed Rate Control to HOLD.

10705 Set Speed Rate pot to 160 divisions
(800 rpm/sec).

10720 Demand 27,000 rpm.

10723 Switch Speed Rate Control to RUN

10725 On Ramp, Open C-231.

10761 Use C-8 in Q/N Control to establish a
Q/N = .17. (73 lbs/sec).

267

10769 Report CP-700D. 800 psid.
 10774 Slowly decrease K-3 position.
 10832 Open K-3 (Q/N = .28 at 27,000 rpm --
 K-3 minimum pot setting = 430 divisions).
 10840 At TD command, push the shutdown button.
 10854 Open D.C. breakers.
 10855 Switch C-231 to POSITION Control and close.
 10856 Switch C-106 to RESET.
 10868 Bypass all the shutdown inputs.
 10870 Reset the shutdown chain.
 10873 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 10878 Close C-11.
 10891 Switch K-53 to POSITION Control and close.
 10895 Close K-62.
 10900 Open K-153.
 10910 Switch the shutdown outputs to OVERRIDE.
 11105 Dewar transfer.

VI.

CAVITATION TEST PHASE RUN #26 - 39°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
24,000	.30
26,000	.26

The supply dewar pressure will be maintained at 75 psig.

A. PROCEED WITH CAVITATION TEST.

12261 Set the overspeed trip pot to 730 divisions
 (28,000 rpm).
 12267 Raise the synchronous motor field to 120 amps.
 12268 Raise the D.C. motor field to 13 amps.
 12270 Close K-153.
 12272 Select Dewar 4 pressure feedback.
 12274 Open K-61.
 12293 Switch the following shutdown outputs to
 NORMAL:

Speed Rate, C-8, C-221

268

12294 Activate the following inputs to the shutdown chain:

UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-62

12314 Use C-106 to chill CT-106.
12316 In K-53 PRESSURE Control, establish 75 psig in Dewar 4.
12329 At CTO command Open C-12, Close C-111.
12334 Use K-162 to maintain KP-62 between 30 and 40 psig.
12338 Open C-221.
12340 Close C-231.
12343 Set C-8 to 530 pot divisions.
12449 When the pump is chilled, close the D.C. breakers.

a. PMP: Report pump chill.

12452 Activate the following inputs to the shutdown chain:

D.C. Breakers, CT-507

12470 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.
12471 Switch C-106 to AUTO.
12472 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

12476 Open C-231 to 85 pot divisions.
12479 Close C-221.
12484 Use C-231 to establish and maintain 30 psig at CP-220.
12488 Switch to Q/N Control and establish Q/N = .25.
12504 Switch to SPEED Control.
12506 Switch Speed Rate Control to HOLD.

12512 Set Speed Rate pot to 160 divisions
 (800 rpm/sec).
 12518 Demand 26,000 rpm.
 12521 Switch Speed Rate Control to RUN.
 12525 On Ramp, Open C-231.
 12555 Use C-8 in Q/N Control to establish a Q/N = .26.
 12559 Report CP-700D. 770 psid.
 12562 Slowly decrease K-3 position.
 12625 Open K-3 (Q/N = .26 at 26,000 rpm --
 K-3 minimum pot setting = 415 divisions).
 12647 Decrease speed to 24,000 rpm.
 12661 Use C-8 to increase Q/N to .30.
 12665 Report CP-700D. 610 psid.
 12668 Slowly decrease K-3 position.
 12707 Open K-3 (Q/N = .30 at 24,000 rpm --
 K-3 minimum pot setting = 428 divisions).
 12731 Decrease speed to 22,000 rpm.
 12735 Use C-8 to increase Q/N to .30.
 12739 Report CP-700D. 510 psid.
 12740 Slowly decrease K-3 position.
 12789 Open K-3 (Q/N = .30 at 22,000 rpm --
 K-3 minimum pot setting = 403 divisions).
 12798 At TD command, push the shutdown button.
 12809 Open D. C. breakers.
 12810 Switch C-231 to POSITION Control and close.
 12812 Switch C-106 to RESET.
 12817 Bypass all the shutdown inputs.
 12819 Reset the shutdown chain.
 12824 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 12828 Close C-12.
 12841 Switch K-53 to POSITION Control and close.
 12849 Close K-61.
 12850 Open K-153.
 12860 Decrease D. C. motor field to less than 5 amps.
 12862 Switch the shutdown outputs to OVERRIDE.
 12900 Dewar transfer.

270

VII. PUMP OVERSPEED TEST PHASE - 39⁰R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
26,000 to 28,500	.30

The supply dewar pressure will be maintained at 100 psig.

A. PROCEED WITH OVERSPEED.

14164	Set the overspeed trip pot to 830 divisions (32,000 rpm).
14173	Raise the synchronous motor field to 120 amps.
14176	Raise the D. C. motor field to 13 amps.
14180	Close K-153.
14183	Select Dewar 5 pressure feedback.
14186	Open K-62.
14196	Switch the following shutdown outputs to NORMAL: Speed Rate, C-3, C-221
14198	Activate the following inputs to the shutdown chain: UQ-2 CP-220 UQ-3 CP-505 JP-101/201 KP-61
14214	Use C-106 to chill CT-106.
14221	In K-53 PRESSURE Control, establish 100 psig in Dewar 5.
14228	At CTO command Open C-11, Close C-111.
14239	Use K-161 to maintain KP-61 between 30 and 40 psig.
14244	Open C-221.
14248	Close C-231.
14250	Set C-8 to 530 pot divisions.

14347 When the pump is chilled, close the D.C. breakers.

a. PMP: Report pump chill.

14350 Activate the following inputs to the shutdown chain:

D.C. Breakers, CT-507

14366 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

14370 Switch C-106 to AUTO.

14373 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

14376 Open C-231 to 85 pot divisions.

14379 Close C-221.

14384 Use C-231 to establish and maintain 30 psig at CP-220.

14389 Switch to Q/N Control and establish Q/N = .29.

14417 Switch to SPEED Control.

14420 Switch Speed Rate Control to HOLD.

14423 Set Speed Rate pot to 160 divisions (800 rpm/sec).

14428 Demand 26,000 rpm.

14434 Switch Speed Rate Control to RUN.

14438 On Ramp, Open C-231.

14461 Use C-8 in Q/N Control to establish a Q/N = .30.

14475 Increase speed.

14496 Speed at 27,000 rpm.

14511 Speed at 28,000 rpm.

14521 Speed at 28,500 rpm.

14522 Decrease speed to 27,000 rpm.

14532 Slowly increase pump speed.

14540 Speed at 28,500 rpm.

14542 Decrease to 27,000 rpm.

14551 At TD command, push the shutdown button.

14566 Open D. C. breakers.
 14567 Switch C-231 to POSITION Control and close.
 14568 Switch C-106 to RESET.
 14570 Bypass all the shutdown inputs.
 14572 Reset the shutdown chain.
 14582 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 14585 Close C-11.
 14590 Switch K-53 to POSITION Control and close.
 14595 Close K-62.
 14604 Open K-153.
 14610 Decrease D. C. motor field to less than 5 amps.
 14615 Switch the shutdown outputs to OVERRIDE.
 14650 Dewar transfer.

VIII.

CAVITATION TEST PHASE RUN # 27 - 41⁰R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
26,000	.26

The supply dewar pressure will be maintained at 75 psig.

A. PROCEED WITH CAVITATION TEST.

15333 Set the overspeed trip pot to 730 divisions
 (28,000 rpm).
 15340 Raise the synchronous motor field to 120 amps.
 15344 Raise the D. C. motor field to 13 amps.
 15346 Close K-153.
 15350 Select Dewar 4 pressure feedback.
 15356 Open K-61.
 15362 Switch the following shutdown outputs to
 NORMAL:

Speed Rate, C-8, C-221

15371 Activate the following inputs to the shutdown
 chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-62

15379 Use C-106 to chill CT-106.
 15386 In K-53 PRESSURE Control, establish
 75 psig in Dewar 4.
 15388 At CTO command Open C-12, Close C-111.
 15396 Use K-161 to maintain KP-61 between
 30 and 40 psig.
 15400 Open C-221.
 15402 Close C-231.
 15406 Set C-8 to 530 pot divisions.
 15517 When the pump is chilled, close the
 D.C. breakers.

 a. PMP: Report pump chill.

 15520 Activate the following inputs to the shutdown
 chain:

 D.C. Breakers, CT-507

 15534 In MANUAL Control, establish 10,000 rpm
 at a Q/N = .22.
 15540 Switch C-106 to AUTO.
 15543 At CTO command, activate the following
 inputs to the shutdown chain:

 Q/N High
 Q/N Low

 15547 Open C-231 to 85 pot divisions.
 15549 Close C-221.
 15553 Use C-231 to establish and maintain
 30 psig at CP-220.
 15558 Switch to Q/N Control and establish Q/N = .25.
 15577 Switch to SPEED Control.
 15580 Switch Speed Rate Control to HOLD.
 15584 Set Speed Rate pot to 160 divisions
 (800 rpm/sec).
 15588 Demand 26,000 rpm.
 15593 Switch Speed Rate Control to RUN.
 15599 On Ramp, Open C-231.
 15617 Use C-8 in Q/N Control to establish a Q/N = .26.

15623 Report CP-700D. 760 psid.
 15626 Slowly decrease K-3 position.
 15679 Open K-3 (Q/N = .26 at 26,000 rpm --
 K-3 minimum pot setting = 426 divisions).
 15697 At TD command, push the shutdown button.
 15711 Open D. C. breakers.
 15714 Switch C-231 to POSITION Control and close.
 15719 Switch C-106 to RESET.
 15721 Bypass all the shutdown inputs.
 15722 Reset the shutdown chain.
 15726 Use C-111 to maintain CP-9 between
 60 and 100 psig.
 15729 Close C-11.
 15741 Switch K-53 to POSITION Control and close.
 15746 Close K-62.
 15749 Open K-153.
 15760 Decrease D. C. motor field to less than 5 amps.
 15736 Switch the shutdown outputs to OVERRIDE.
 15820 Dewar transfer.

IX. CAVITATION TEST PHASE RUN #28 - 43°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
26,000	.26

The supply dewar pressure will be maintained at 80 psig.

A. PROCEED WITH CAVITATION TEST.

16340 Set the overspeed trip pot to 730 divisions
 (28,000 rpm).
 16350 Raise the synchronous motor field to 120 amps.
 16354 Close K-153.
 16356 Select Dewar 5 pressure feedback.
 16359 Open K-62.
 16364 Raise the D. C. motor field to 13 amps.
 16366 Switch the following shutdown outputs to
 NORMAL:

 Speed Rate, C-8, C-221

16378 Activate the following inputs to the shutdown chain:

UQ-2 CP-220
UQ-3 CP-505
JP-101/201 KP-61

16383 In K-53 PRESSURE Control, establish 80 psig in Dewar 5.

16386 Use C-106 to chill CT-106.

16397 At CTO command Open C-11, Close C-111.

16402 Use K-161 to maintain KP-61 between 30 and 40 psig.

16406 Open C-221.

16408 Close C-231.

16412 Set C-8 to 530 pot divisions.

16477 When the pump is chilled, close the D.C. breakers.

a. PMP: Report pump chill.

16480 Activate the following inputs to the shutdown chain:

D.C. Breakers, CT-507

16500 CT-507 tripped shutdown chain.

16543 CT-507 bypassed.

16549 When the pump is chilled, close the D.C. breakers.

a. PMP: Report pump chill.

16551 Activate the following inputs to the shutdown chain:

D.C. Breakers

16565 In MANUAL Control, establish 10,000 rpm at a Q/N = .22.

16567 Switch C-106 to AUTO.

16573 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
Q/N Low

16576 Open C-231 to 85 pot divisions.
16578 Close C-221.
16582 Use C-231 to establish and maintain 30 psig at CP-220.
16587 Switch to Q/N Control and establish Q/N = .26.
16604 Switch to SPEED Control.
16606 Switch Speed Rate Control to HOLD.
16612 Set Speed Rate pot to 160 divisions (800 rpm/sec).
16615 Demand 26,000 rpm.
16622 Switch Speed Rate Control to RUN.
16625 On Ramp, Open C-231.
16648 Use C-8 in Q/N Control to establish a Q/N = .26.
16652 Report CP-700D. 730 psid.
16654 Slowly decrease K-3 position.
16699 Open K-3 (Q/N = .26 at 26,000 rpm -- K-3 minimum pot setting = 427 divisions).
16709 At TD command, push the shutdown button.
16724 Open D.C. breakers.
16729 Switch C-231 to POSITION Control and close.
16730 Switch C-106 to RESET.
16734 Bypass all the shutdown inputs.
16736 Reset the shutdown chain.
16737 Use C-111 to maintain CP-9 between 60 and 100 psig.
16746 Close C-11.
16751 Switch K-53 to POSITION Control and close.
16756 Close K-62.
16758 Open K-153.
16760 Decrease D.C. motor field to less than 5 amps.
16762 Switch the shutdown outputs to OVERRIDE.

277

X. DEWAR 2 TO DEWAR 4/5 LH₂ TRANSFER

During this phase, Dewar 4/5 will be refilled by transferring LH₂ from Dewar 2.

A. PROCEED WITH THE LH₂ TRANSFER.

16850	Open L-251.
16856	Close L-261, L-153.
16864	Open L-62, L-302, L-330.
16885	Open L-331, X-301.
16892	Close K-401.
16899	Use K-161/162 to vent Dewar 4/5.
16913	Use L-53 in POSITION Control to establish and maintain 65 psig in Dewar 2.
16993	When LP-61 is greater than KP-61/62, Open K-301/302.
22810	When LH ₂ transfer is complete, Close K-301/302.

XI. LOW SPEED MAPPING AND CAVITATION RUN #29 - 37.5°R

The following points will be investigated:

<u>Speed</u>	<u>Q/N</u>
27,000	.28

The supply dewar pressure will be maintained at 50 psig.

A. PROCEED WITH CAVITATION TEST.

22822	Set the overspeed trip pot to 315 divisions (12,000 rpm).
22837	Raise the synchronous motor field to 120 amps.
22839	Raise the D. C. motor field to 13 amps.
22905	Close K-153.
22915	Select Dewar 4 pressure feedback.
22926	Open K-61.
22928	Switch the following shutdown outputs to NORMAL: Speed Rate, C-8, C-221

22930 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101/201	KP-62

22936 In K-53 PRESSURE Control, establish 50 psig in Dewar 4.

23002 Use C-106 to chill CT-106..

23015 At CTO command Open C-12, Close C-111.

23016 Open C-221.

23021 Close C-231.

23026 Set C-8 to 530 pot divisions.

23217 Open K-130.

23290 Slowly close K-3 (3-1/2 lbs/sec flow for dewar pressure alone).

23345 When the pump is chilled, close the D. C. breakers.

 a. PMP: Report pump chill.

23351 Activate the following inputs to the shutdown chain:

 D. C. Breakers, CT-507

23362 In MANUAL Control, establish 3,000 rpm with maximum KF-130 of 15 lbs/sec.

23424 Vary KF-130 between 4 and 15 lbs/sec with C-8 and C-106.

23450 Close C-106.

23469 Increase speed to 6,000 rpm.

23520 Use C-8 to decrease KF-130 to 4 lbs/sec (40% on C-8).

23556 Use C-8 to increase KF-130 to 6 lbs/sec.

23577 Demand 0 speed (plotters not reading correctly).

23590 Breakers open.

23610 Data hold.

23934 Set C-8 to 55% (Q/N = .22).

23937 When the pump is chilled, close the D.C. breakers.

a. PMP: Report pump chill.

23945 Activate the following inputs to the shutdown chain:

D.C. Breakers

23966 In MANUAL Control, establish 9,000 rpm.
 23981 Demand 0 speed (pump inlet pressure falling).
 24001 Reset the overspeed trip pot to 760 divisions (28,000 rpm).

24015 Open K-3.
 24026 Close K-130.
 24047 Increase Dewar 4 pressure to 80 psig.
 24082 In MANUAL Control, demand 10,000 rpm.
 24084 Switch C-106 to AUTO.
 24088 At CTO command, activate the following inputs to the shutdown chain:

Q/N High
 Q/N Low

24096 Open C-231 to 85 pot divisions.
 24100 Close C-221.
 24104 Use C-231 to establish and maintain 30 psig at CP-220.
 24116 Switch to Q/N Control and establish Q/N = .27.
 24140 Switch to SPEED Control.
 24144 Switch Speed Rate Control to HOLD.
 24150 Set Speed Rate pot to 160 divisions (800 rpm/sec).
 24152 Demand 27,000 rpm.
 24157 Switch Speed Rate Control to RUN.
 24168 On Ramp, Open C-231.
 24195 Use C-8 in Q/N Control to establish 73 lbs/sec.
 24200 Report CP-700D. 820 psid.
 24206 Slowly decrease K-3 position.
 24269 Open K-3 (Q/N = .28 at 27,000 rpm -- K-3 minimum pot setting = 428 divisions).

24298	Switch Speed Rate Control to HOLD.
24300	Demand 9,000 rpm.
24311	Switch Speed Rate Control to RUN.
24348	At TD command, push the shutdown button.
24355	Open D.C. breakers.
24358	Bypass all the shutdown inputs.
24360	Reset the shutdown chain.
24368	Switch C-231 to POSITION Control and close.
24370	Switch C-106 to RESET.
24372	Use C-111 to maintain CP-9 between 60 and 100 psig.
24378	Close C-12.
24388	Switch K-53 to POSITION Control and close.
24395	Close K-61.
24398	Open K-153.
24400	Decrease D.C. motor field to less than 5 amps.
24402	Switch the shutdown outputs to OVERRIDE.
24470	Dewar transfer.

XII. LOW SPEED MAPPING

During this phase, pump mapping will be performed at speeds of 6,000, 9,000 rpm at Q/N's of .14 to .35. Supply fluid temperature will be 39°R. Dewar pressure will be maintained at 40 psig.

A. PROCEED WITH LOW SPEED MAPPING.

25288	Set the overspeed trip pot to 395 divisions (15,000 rpm).
25295	Raise the synchronous motor field to 120 amps.
25300	Raise the D.C. motor field to 13 amps.
25310	Close K-153.
25316	Select Dewar 5 pressure feedback.
25319	Open K-62.
25329	Switch the following shutdown outputs to NORMAL:
	Speed Rate, C-8, C-221

25339 Activate the following inputs to the shutdown chain:

UQ-2	CP-220
UQ-3	CP-505
JP-101-201	KP-61

25340 In K-53 PRESSURE Control, establish 40 psig in Dewar 5.

25352 Use C-106 to chill CT-106.

25364 At CTO command Open C-11, Close C-111.

25366 Open K-161.

25368 Open C-221.

25370 Close C-231.

25373 Set C-8 to 530 pot divisions.

25390 Incoming line breaker tripped.

25465 When the pump is chilled, close the D.C. breakers.

 a. PMP: Report pump chill.

25470 Activate the following inputs to the shutdown chain:

 D.C. Breakers, CT-507

25496 In MANUAL Control, establish 6,000 rpm at a Q/N = .22.

25545 Switch to SPEED Control.

25606 Use C-8 to maintain Q/N = .10 (30% minimum on C-8).

25631 Bypass CP-507.

25646 Use C-8 to increase Q/N to .20.

 a. Use .02 increments.

25667 Increase speed to 9,000 rpm.

25714 Use C-8 to decrease Q/N to .10 at 9 lbs/sec.

25739 Q/N = .06 (22% on C-8 minimum point).

25762 Use C-8 to increase Q/N to .20.

25766 Shutdown CTO Manual.
25772 Open D. C. breakers.
25775 Bypass all the shutdown inputs.
25779 Reset the shutdown chain.
25788 Use C-111 to maintain CP-9 between
60 and 100 psig.
25792 Close C-11.
25806 Switch K-53 to POSITION Control and close.
25809 Close K-62.
25813 Open K-153.
25816 Decrease D. C. motor field to less than 5 amps.
25819 Switch the shutdown outputs to OVERRIDE.

POST VOLTAGE CALIBRATION

26091-26191 Calibration interval.



MAXIMUM SHUTDOWN SECURE

26300



END

283


LH₂ PUMP COMPONENT DEVELOPMENT PROGRAM

INDUCER NO. 1

CAVITATION TEST DATA

284

LH₂ PUMP COMPONENT DEVELOPMENT TEST OPERATING CONDITIONS



INDUCER I-LH₂ PUMP TEST - CAVITATION TEST SUMMARY

TARGET				ACTUAL					COND. AT SCHEMATIC	
SPEED	Q/N (DISCH.)	TEMP. (DEWAR)	CAV. RUN	SPEED	Q/N (SUPT.)	W (SUPT.)	TEMP. (DISVAC)	VAP. PRESS (EQUIV. TANK)	NPSP (EQUIV. TANK)	VAP. B/W L ₂ (SUPT. LINE)
19K	.17	37.5	8C	19.2K	.19	35.4	36.6	20.2	-4.3	.50
		39	1A	19.3K	.19	35.5	37.5	21.6	-4.5	.48
		41	3B	19.0K	.19	33.5	41.5	36.0	-10.4	.54
		43	17E	18.85K	.19	32.4	43.4	46.8	-14.6	.55
	.24	37.5	8B	19.2K	.26	48.4	36.5	19.7	-2.3	.35
		39	1B	19.3K	.26	48.5	37.5	21.2	-2.4	.32
		41	5A	19.2K	.26	47	41.2	34.7	-5.1	.34
		43	17D	18.8K	.26	45	43.4	45.0	-7.4	.34
	.30	37.5	8A	19.2K	.32	60	36.5	19.4	-1.5	.28
		39	9A	19.2K	.32	58	39.5	28.0	-1.7	.19
		41	2	19.3K	.31	56.6	41.0	33.1	-2.3	.20
		43	22	19.1K	.32	56.3	43.4	43.2	-3.4	.19
22K	.17	37.5	16B	22.2K	.19	41.5	36.9	20.1	-3.4	.44
		39	7D	22.2K	.19	40.5	38.5	24.6	-5.6	.49
		41	3A	22.5K	.19	40	41.5	35.5	-9.2	.50
		43	17B	22.2K	.19	38	43.4	45.5	-13.0	.52
	.24	37.5	16C	22.3K	.26	57.5	36.9	19.9	-1.8	.29
		39	9B	22.5K	.26	55.8	39.5	28.1	-3.2	.30
		41	5B	22.4K	.26	54.9	41.2	34.3	-4.5	.30
		43	17C	22.2K	.26	53.2	43.4	44.5	-6.3	.31
	.30	37.5	10A	22.5K	.32	70	38.1	21.6	-.6	.14
		39	12A	22.5K	.32	69	39.3	25.7	-.9	.14
		39 [ⓐ]	26C	22.1K	.32	68	39.3	26.1	-1.0	.15
		41	11A	22.5K	.32	68	41.3	33.3	-1.7	.16
		43	13A	22.5K	.32	67	42.8	39.8	-2.4	.16


ⓐ WITHOUT INLET LINE BELLOWS LINER

INDUCER I-LH₂ PUMP TEST - CAVITATION TEST SUMMARY (Cont'd)

TARGET			ACTUAL								COND. AT BREAKDOWN	
SPEED	Q/N (DISCH)	TEMP. (DISCH)	CAV. RUN	SPEED	Q/N (SUCT)	W (SUCT)	TEMP. (DISCH)	VAP. PRESS (COND. TANK)	NPSP (COND. TANK)	VAP. EVAC (SUCT. LINE)		
24K	.17	37.5	16A	24.3K	.19	45.5	36.9	19.8	-3.2	.42		
		39	7A	24.4K	.19	45	38.5	24.5	-5.3	.48		
		41	6B	24.3K	.19	43.2	40.9	34.0	-8.8	.50		
		43	17A	24.4K	.19	42.2	43.4	45.0	-12.3	.50		
	.21	39	21C	24.1K	.23	53.5	39.4	27.7	-3.9	.35		
	.24	37.5	4	24.4K	.26	62	36.3	18.9	-2.2	.36		
		39	23	24.2K	.26	60.5	39.4	27.5	-3.0	.30		
		41	6A	24.3K	.26	59.8	40.8	32.9	-4.0	.30		
		43	15B	24.1K	.26	58	43.1	42.4	-5.5	.30		
	.30	37.5	10B	24.3K	.32	75.2	38.1	21.8	-.4	.11		
		39	12B	24.4K	.32	75	39.3	25.8	-.8	.13		
		39 ^①	26B	24.2K	.32	72	39.3	26.0	-.8	.12		
		41	11B	24.4K	.32	73	41.3	33.4	-1.2	.13		
		43	13B	24.4K	.32	72	42.9	40.5	-2.0	.14		
	26K	.17	37.5	20A	26.4K	.19	49	36.4	19.0	-3.1	.44	
			39	21A	26.5K	.19	48	39.3	27.9	-5.7	.45	
41			18A	26.5K	.19	47.2	41.4	35.7	-8.4	.48		
43			19A	26.5K	.19	47	42.6	40.9	-10.3	.48		
.21		37.5	20B	26.4K	.23	60	36.5	19.2	-2.4	.37		
		39	21B	26.4K	.23	59	39.3	27.5	-3.4	.32		
		41	18B	26.5K	.24	58	41.4	35.3	-5.2	.34		
		43	19B	26.5K	.24	57.5	42.6	40.2	-6.5	.35		
.26		37.5 ^①	24	26.3K	.28	72	38.6	22.6	-.8	.14		
		39 ^①	26A	26.5K	.28	72	39.3	26.0	-1.4	.18		
		41 ^①	27	26.5K	.29	71	41.4	33.8	-2.4	.20		
		43 ^①	28	26.5K	.29	69.5	42.2	42.0	-3.8	.22		
.30		37.5	14	26.5K	.32	83	36.5	18.3	+.4	0		
		39	12C	26.5K	.32	81.3	39.6	26.8	-.5	.10		
		41	11C	26.5K	.32	80	41.3	33.7	-1.0	.12		
		43	15A	26.4K	.32	78.3	43.1	41.6	-1.5	.11		
27K	73 ⁴⁵ / ₁₀₀	37.5 ^①	29	27.2K	.30	81.1	36.5	18.2	0	.10		
		39 ^①	25	②	②	②	②	②	②	②		

① WITHOUT INLET LINE BELLOW LINER
 ② PERFORMANCE CALCULATIONS NOT COMPLETED DUE TO DATA STORAGE FORMAT

INDUCER 1 LH2 PUMP TEST




CAV. TEST 1A, DEC 15, 1971
 Q/N SUCTION = 0.19
 N = 19300 RPM
 WDOT SUCTION = 35.5 LB/SEC
 TANK TEMP. = 37.5 DEG R

683


262

INDUCER 1 LH2 PUMP TEST




CAV. TEST 18. DEC 15. 1971
 Q/N SUCTION = 0.26
 N = 19300 RPM
 WDST SUCTION = 48.5 LB/SEC
 TANK TEMP. = 37.5 DEG R

262




862

INDUCER 1 LH2 PUMP TEST



202

INDJCR 1 LH2 PUMP TEST



CRV. TEST 3A, DEC 15, 1971
 Q/N SUCTION = 0.19
 N = 22500 RPM
 WGT SUCTION = 40 LB/SEC
 TANK TEMP. = 41.5 DEG R


562

INDUCER 1 LH2 PUMP TEST

◊ ISENTROPIC EFFICIENCY
 0.10 0.20 0.30 0.40 0.50 0.60 0.70 0.80 0.90 1.00


○ ISN. IND. DEL-H/N2 (TIMES 10⁴FT)
 0.00 1.00 2.00 3.00 4.00 5.00 6.00 7.00 8.00 9.00

□ ISN. IMP. DEL-H/N2 (TIMES 10⁴FT)
 2.60 2.80 3.00 3.20 3.40 3.60 3.80 4.00 4.20 4.40



902

INDJCR 1 LH2 PUMP TEST




CRV. TEST 38. DEC 15, 1971
 G/W SUCTION = 0.19
 N = 19000 RPM
 MDPT SUCTION = 33.5 LB/SEC
 TANK TEMP. = 41.5 DEG R

202

INDUCER 1 LH2 PUMP TEST


○ ISENTROPIC EFFICIENCY
○ ISN. IND. DEL-H/N2 (TIMES 10⁰⁰⁰G)
○ ISN. IMP. DEL-H/N2 (TIMES 10⁰⁰⁰G)



CRV. TEST 38, DEC 15, 1971
A/W SUCTION = 0.19
N = 19000 RPM
WDBT SUCTION = 33.5 LB/SEC
TANK TEMP. = 41.5 DEG R

INDUCER 1 LH2 PUMP TEST


862



CRV. TEST 4, DEC 15, 1971
 Q/N SUCTION = 0.26
 N = 24400 RPM
 WGBT SUCTION = 62 LB/SEC
 TANK TEMP. = 36.3 DEG R

209


INDUCER 1 LH2 PUMP TEST



CRV. TEST 4, DEC 15, 1971
Q/N SUCTION = 0.26
N = 24400 RPM
WGHT SUCTION = 62 LB/SEC
TANK TEMP. = 36.3 DEG R

002


INDUCER 1 LH2 PUMP TEST



CAV. TEST 5A, DEC 15, 1971
 Q/N SUCTION = 0.26
 N = 19200 RPM
 MD8T SUCTION = 47 LB/SEC
 TANK TEMP. = 41.2 DEG R


301

INDUCER 1 LH2 PUMP TEST




CAV. TEST 5A, DEC 15, 1971
 Q/N SUCTION = 0.26
 N = 19200 RPM
 MDOT SUCTION = 47 LB/SEC
 TANK TEMP. = 41.2 DEG R

202




8108

INDUCER 1 LH2 PUMP TEST




CRV. TEST 58, DEC 15, 1971
 Q/N SUCTION = 0.26
 N = 22400 RPM
 MDOT SUCTION = 54.9 LB/SEC
 TANK TEMP. = 41.2 DEG R

304




302

INDUCER 1 LH2 PUMP TEST




CAV. TEST 6A, DEC 15, 1971
 Q/N SUCTION = 0.26
 N = 24300 RPM
 HOBT SUCTION = 59.8 LB/SEC
 TANK TEMP. = 40.8 DEG R

306




208




808

INDUCER 1 LH2 PUMP TEST




CAV. TEST 7A, DEC 15, 1971
 Q/N SUCTION = 0.19
 N = 24400 RPM
 HDOT SUCTION = 45.0 LB/SEC
 TANK TEMP. = 38.5 DEG R

602



310


INDUCER 1 LH2 PUMP TEST



CAV. TEST 78, DEC 15, 1971
 Q/N SUCTION = 0.19
 N = 22200 RPM
 HGT SUCTION = 40.5 LB/SEC
 TANK TEMP. = 38.5 DEG R

78

INDUCER 1 LH2 PUMP TEST



CRV. TEST 7B, DEC 15, 1971
 Q/N SUCTION = 0.19
 N = 22200 RPM
 WGT SUCTION = 40.5 LB/SEC
 TANK TEMP. = 38.5 DEG R

546

ISENTROPIC EFFICIENCY


0.10 0.20 0.30 0.40 0.50 0.60 0.70 0.80 0.90 1.00

0.00 1.00 2.00 3.00 4.00 5.00 6.00 7.00 8.00 9.00

○ ISN. IND. DEL-H/N2 (TIMES 10^{mm6})

2.20 2.40 2.60 2.80 3.00 3.20 3.40 3.60 3.80 4.00


□ ISN. IMP. DEL-H/N2 (TIMES 10^{mm5})



CAV. TEST 8A, DEC 15, 1971
 Q/N SUCTION = 0.32
 N = 19200 RPM
 WGT SUCTION = 60 LB/SEC
 TANK TEMP. = 36.5 DEG R

NPSP PSI (EQUIV. TANK)


INDUCER 1 LH2 PUMP TEST



7182

58


INDUCER 1 LH2 PUMP TEST



CAV. TEST 88. DEC 15. 1971
 Q/N SUCTION = 0.25
 N = 19200 RPM
 WDOT SUCTION = 48.4 LB/SEC
 TANK TEMP. = 36.5 DEG R

INDUCER 1 LH2 PUMP TEST


988



CAV. TEST 8C, DEC 15, 1971
 Q/N SUCTION = 0.19
 N = 19200 RPM
 WDOT SUCTION = 35.4 LB/SEC
 TANK TEMP. = 36.6 DEG R


218

INDUCER 1 LH2 PUMP TEST




812

INDUCER 1 LH2 PUMP TEST




648




320

INDUCER 1 LH2 PUMP TEST



328


INDUCER 1 LH2 PUMP TEST




CAV. TEST 98, DEC 15, 1971
Q/N SUCTION = 0.26
N = 22500 RPM
WDOT SUCTION = 55.8 LB/SEC
TANK TEMP. = 39.5 DEG R

INDUCER 1 LH2 PUMP TEST

228




INDUCER 1 LH2 PUMP TEST



328

INDUCER 1 LH2 PUMP TEST

◊ VAPOR PRESSURE (EQUIV. TANK)
 12.0 14.0 16.0 18.0 20.0 22.0 24.0 26.0 28.0 30.0
 ○ SUCTION LINE VAPOR BY VOLUME
 -0.100 0.000 0.100 0.200 0.300 0.400 0.500 0.600 0.700 0.800
 □ ISN. (VOL. DEL-H/N2 (TIMES 10¹⁰))
 2.20 2.40 2.60 2.80 3.00 3.20 3.40 3.60 3.80 4.00




CAV. TEST 108, DEC 16, 1971
 Q/N SUCTION = 0.32
 N = 24300 RPM
 WGT SUCTION = 75.2 LB/SEC
 TANK TEMP. = 30.1 DEG R

NPSP PSI (EQUIV. TANK)

INDUCER 1 LH2 PUMP TEST


928



CAV. TEST 108, DEC 16, 1971
 Q/W SUCTION = 0.32
 N = 24300 RPM
 WDOT SUCTION = 75.2 LB/SEC
 TANK TEMP. = 38.1 DEG R


928

INDUCER 1 LH2 PUMP TEST



INDUCER 1 LH2 PUMP TEST


228



CAV. TEST 11A, DEC 16, 1971
 Q/N SUCTION = 0.32
 N = 22500 RPM
 WDOT SUCTION = 68 LB/SEC
 TANK TEMP. = 41.3 DEG R

828


INDUCER 1 LH2 PUMP TEST



CRV. TEST 118. DEC 16. 1971
 Q/N SUCTION = 0.32
 N = 24400 RPM
 WGT SUCTION = 73 LB/SEC
 TANK TEMP. = 41.3 DEG R


602

INDUCER 1 LH2 PUMP TEST




CAV. TEST 118, DEC 16, 1971
 Q/N SUCTION = 0.32
 N = 24400 RPM
 WGT SUCTION = 73 LB/SEC
 TANK TEMP. = 41.3 DEG R

INDUCER 1 LH2 PUMP TEST




788

INDUCER 1 LH2 PUMP TEST




CAV. TEST 11C, DEC 16, 1971
 Q/N SUCTION = 0.32
 N = 26500 RPM
 WDOT SUCTION = 80 LB/SEC
 TANK TEMP. = 41.3 DEG R

828




324




INDUCER 1 LH2 PUMP TEST

522




922

INDUCER 1 LH2 PUMP TEST



222


INDUCER 1 LH2 PUMP TEST



CRV. TEST 12C. DEC 16, 1971
 Q/N SUCTION = 0.32
 N = 26500 RPM
 HDQT SUCTION = 81.3 LB/SEC
 TANK TEMP. = 39.6 DEG R


328

INDUCER 1 LH2 PUMP TEST




628

INDUCER 1 LH2 PUMP TEST




CAV. TEST 13A, DEC 16, 1971
 Q/N SUCTION = 0.32
 N = 22500 RPM
 WDOT SUCTION = 67 LB/SEC
 TANK TEMP. = 42.9 DEG R

340



341


INDUCER 1 LH2 PUMP TEST



E

222


INDUCER 1 LH2 PUMP TEST



CAV. TEST 14. DEC 16, 1971
 Q/N SUCTION = 0.32
 N = 26500 RPM
 WDOT SUCTION = 83 LB/SEC
 TANK TEMP. = -36.5 DEG R


343

INDUCER 1 LH2 PUMP TEST




INDUCER-1 LH2 PUMP TEST

314




3A5



CAV. TEST 15A, DEC 16, 1971
Q/N SUCTION = 0.32
N = 26400 RPM
WDOT SUCTION = 78.3 LB/SEC
TANK TEMP. = 43.1 DEG R


9V2

INDUCER 1 LH2 PUMP TEST




INDUCER 1 LH2 PUMP TEST

AVE




CAV. TEST 158, DEC 16, 1971
 Q/N SUCTION = 0.26
 N = 24100 RPM
 WDG T SUCTION = 58 LB/SEC
 TANK TEMP. = 43.1 DEG R

INDUCER 1 LH2 PUMP TEST




CAV. TEST 16A, DEC 17, 1971
 Q/N SUCTION = 0.19
 N = 24300 RPM
 WGT SUCTION = 45.5 LB/SEC
 TANK TEMP. = 36.9 DEG R

349




058

INDUCER 1 LH2 PUMP TEST




CRV. TEST 166, DEC 17, 1971
Q/N SUCTION = 0.19
N = 22200 RPM
WGT SUCTION = 41.5 LB/SEC
TANK TEMP. = 36.9 DEG R

254




258



358


INDUCER 1 LH2 PUMP TEST



CAV. TEST 16C, DEC 17, 1971
 Q/N SUCTION = 0.26
 N = 22300 RPM
 HGHT SUCTION = 57.5 LB/SEC
 TANK TEMP. = 36.9 DEG R


NPSP: PSI (EQUIV. TANK)

INDUCER 1 LH2 PUMP TEST



354


INDUCER 1 LH2 PUMP TEST




CAV. TEST 17A, DEC 17, 1971
 Q/N SUCTION = 0.19
 N = 24400 RPM
 HOOT SUCTION = 42.2 LB/SEC
 TANK TEMP. = 43.4 DEG R

358
 358

INDUCER 1 LH2 PUMP TEST




INDUCER 1 LH2 PUMP TEST




CAV. TEST 178, DEC 17, 1971
 Q/N SUCTION = 0.19
 N = 22200 RPM
 WDOT SUCTION = 38 LB/SEC
 TANK TEMP. = 43.4 DEG R

458


INDUCER 1 LH2 PUMP TEST






358

INDUCER 1 LH2 PUMP TEST




CAV. TEST 170, DEC 17, 1971
Q/N SUCTION = 0.26
N = 16800 RPM
KDOT SUCTION = 45 LB/SEC
TANK TEMP. = 43.4 DEG R

INDUCER 1 LH2 PUMP TEST




298

INDUCER 1 LH2 PUMP TEST




398

INDUCER 1-LH2 PUMP TEST



CAV. TEST 18A. DEC 17, 1971
 Q/N SUCTION = 0.19
 N = 26500 RPM
 W08T SUCTION = 47.2 LB/SEC
 TANK TEMP. = 41.4 DEG R


INDUCER 1 LH2 PUMP TEST



598


99c

INDUCER 1 LH2 PUMP TEST




CAV. TEST 188, DEC 17, 1971
Q/N SUCTION = 0.24
N = 26500 RPM
WDOT SUCTION = 58 LB/SEC
TANK TEMP. = 41.4 DEG R

498




892

INDUCER 1 LH2 PUMP TEST



369
P


INDUCER 1 LH2 PUMP TEST



CAV. TEST 19A, DEC. 17, 1971
Q/N SUCTION = 0.19
N = 26500 RPM
WDOT SUCTION = 47 LB/SEC
TANK TEMP. = 42.6 DEG R

028


INDUCER 1 LH2 PUMP TEST



cut

148


INDUCER 1 LH2 PUMP TEST



CAV. TEST 198, DEC 17, 1971
 Q/N SUCTION = 0.24
 N = 26500 RPM
 WDOT SUCTION = 57.5 LB/SEC
 TANK TEMP. = 42.6 DEG R

242


INDUCER 1 LH2 PUMP TEST



CAV. TEST 20A, DEC 17, 1971
Q/N SUCTION = 0.19
N = 26400 RPM
MDOT SUCTION = 49 LB/SEC
TANK TEMP. = 36.4 DEG R

822


INDUCER 1 LH2 PUMP TEST



CAV. TEST 20A, DEC 17, 1971
Q/N SUCTION = 0.19
N = 25400 RPM
HDST SUCTION = 49 LB/SEC
TANK TEMP. = 36.4 DEG R

374


INDUCER 1 LH2 PUMP TEST



CAV. TEST 209, DEC. 17, 1971
G/N SUCTION = 0.23
N = 26400 RPM
ROOT SUCTION = 60 LB/SEC
TANK TEMP. = 35.5 DEG R


S&C

INDUCER 1 LH2 PUMP TEST




CAV. TEST 209, DEC. 17, 1971
 Q/N SUCTION = 0.23
 N = 26400 RPM
 WGBT SUCTION = 60 LB/SEC
 TANK TEMP. = 36.5 DEG R

948




248

INDUCER 1 LH2 PUMP TEST




CAV. TEST 21A. DEC 17, 1971
Q/N SUCTION = 0.19
N = 26500 RPM
HOCT SUCTION = 48 LB/SEC
TANK TEMP. = 39.3 DEG R


848



648




088C




384

INDUCER 1 LH2 PUMP TEST




CAV. TEST 21C, DEC 17, 1971
 Q/N SUCTION = 0.23
 N = 24100 RPM
 WDOT SUCTION = 53.5 LB/SEC
 TANK TEMP. = 39.4 DEG R

288



388

INDUCER 1 LH2 PUMP TEST




CAV. TEST 22, DEC 17, 1971
 Q/N SUCTION = 0.32
 N = 19100 RPM
 HOBT SUCTION = 56.3 LB/SEC
 TANK TEMP. = 43.4 DEG R

05


384

INDUCER 1 LH2 PUMP TEST




CAV. TEST 28, DEC 17, 1971
Q/N SUCTION = 0.26
N = 24200 RPM
WGHT SUCTION = 60.5 LB/SEC
TANK TEMP. = 39.4 DEG R

582




386

INDUCER 1 LH2 PUMP TEST




48E

INDUCER 1 LH2 PUMP TEST




CAV. TEST 24, DEC 22, 1971
 Q/N SUCTION = 0-28
 N = 26300 RPM
 HOOT SUCTION = 72 LB/SEC
 TANK TEMP. = 38.6 DEG R

388




688

INDUCER I LH2 PUMP TEST




390

INDUCER 1 LH2 PUMP TEST




391




26C

INDUCER 1 LH2 PUMP TEST




CAV. TEST 26C, DEC 22, 1971
 Q/N SUCTION = 0.32
 N = 22100 RPM
 WDOT SUCTION = 68 LB/SEC
 TANK TEMP. = 39.3 DEG R

868




INDUCER 1 LH2 PUMP TEST

700




INDUCER 1 LH2 PUMP TEST

202



961




CRV. TEST 28. DEC 22. 1971
Q/M SUCTION = 0.29
N = 26500 RPM
ROBT SUCTION = 69.5 LB/SEC
TANK TEMP. = 42.2 DEG R

3

26E

INDUCER 1 LH2 PUMP TEST



CRV. TEST 28. DEC 22. 1971
Q/R SUCTION = 0.29
N = 26500 RPM
WDOT SUCTION = 69.5 LB/SEC
TANK TEMP. = 42.2 DEG R

862

INDUCER 1 LH2 PUMP TEST

