



North Dakota Department of Transportation

Grant Levi, P.E.
Director

Jack Dalrymple
Governor

July 1, 2016

ADDENDUM 1 – JOB 2

TO: All prospective bidders on project SC-2730(061), Job No. 2 scheduled for the July 15, 2016 bid opening.

The following plan and request for proposal revisions shall be made:

Plan Revisions:

See attached summary from Jessica R Karls, KLJ, dated June 30, 2016 for an explanation.

Request for Proposal Revisions:

Remove and replace page 7 thru 11 of 13 of the Proposal pages located at the beginning of the Request for Proposal, with the enclosed page revised 6/30/2016.

Page 7 of 13:

- Item 201 0300 CLEARING & GRUBBING; 1 ACRE was deleted.
- Item 201 0330 CLEARING & GRUBBING; 1 L SUM was added.
- Item 202 0350 REMOVAL OF TEMPORARY BYPASS; 4 EA was added.
- Item 203 0101 COMMON EXCAVATION-TYPE A; 461 CY was deleted.
- Item 203 0102 COMMON EXCAVATION-TYPE B; 1,613 CY was added.
- Item 203 0109 TOPSOIL; quantity increased from 2,580 to 5,656 CY.
- Item 203 0113 COMMON EXCAVATION WASTE; 11,348 CY was deleted.
- Item 203 0121 TOPSOIL-WETLAND; quantity decreased from 621 to 604 CY
- Item 203 0140 BORROW-EXCAVATION; quantity increased from 14,322 to 25,165 CY.

Page 8 of 13:

- Item 210 0210 FOUNDATION FILL; quantity decreased from 2,909 to 2,445 CY.
- Item 216 0100 WATER; quantity decreased from 485 to 392 M GAL.
- Item 251 0200 SEEDING CLASS II; quantity decreased from 4.130 to 5.940 ACRE.
- Item 251 1000 WETLAND SEED; quantity decreased from 0.770 to 0.750 ACRE.
- Item 251 2000 TEMPORARY COVER CROP; quantity increased from 4.030 to 5.910 ACRE.
- Item 253 0101 STRAW MULCH; quantity increased from 8.930 to 12.590 ACRE.
- Item 260 0200 SILT FENCE SUPPORTED; 533 LF was added.
- Item 260 0201 REMOVE SILT FENCE SUPPORTED; 533 LF was added.
- Item 261 0112 FIBER ROLLS 12IN; quantity increased from 10,456 to 16,680 LF.

Page 9 of 13:

- Item 261 0113 REMOVE FIBER ROLLS 12IN; quantity increased from 6,503 to 8,441 LF.
- Item 262 0100 FLOTATION SILT CURTAIN; quantity decreased from 561 to 559 LF.
- Item 262 0101 REMOVE FLOTATION SILT CURTAIN; quantity decreased from 561 to 559 LF.

Item 302 0120 AGGREGATE BASE COURSE CL 5; quantity increased from 1,366 to 3,544 TON.

Item 401 0050 TACK COAT; quantity increased from 366 to 478 GAL.

Item 401 0060 PRIME COAT; quantity increased from 915 to 1,195 GAL.

Item 401 0160 BLOTTER MATERIAL CL 44; quantity increased from 28 to 36 TON.

Item 430 0045 SUPERPAVE FAA 45; quantity increased from 805 to 1,044 TON.

Item 430 5828 PG 58-28 ASPHALT CEMENT; quantity increased from 47 to 63 TON.

Item 606 1108 11FT X 8FT PRECAST RCB CULVERT; quantity decreased from 114 to 110 LF.

Item 606 1211 12FT X 11FT PRECAST RCB CULVERT; quantity decreased from 84 to 64 LF.

Item 606 1311 13FT X 11FT PRECAST RCB CULVERT; quantity decreased from 84 to 64 LF.

Item 606 3108 DBL11FT X 8FT PRECAST RCB CULVERT; quantity decreased from 114 to 110 LF.

Item 606 3206 DBL12FT X 6FT PRECAST RCB CULVERT; quantity decreased from 168 to 128 LF.

Page 10 of 13:

Item 606 3211 DBL12FT X 11FT PRECAST RCB CULVERT; quantity decreased from 84 to 64 LF.

Item 606 3311 DBL13FT X 11FT PRECAST RCB CULVERT; quantity decreased from 84 to 64 LF.

Item 704 1041 ATTENUATION DEVICE TYPE B-55; 8 EA was deleted.

Item 704 1500 OBLITERATION OF PAVEMENT MARKING; 477 SF was added.

Page 11 of 13:

Item 709 0151 GEOSYNTHETIC MATERIAL TYPE R1; quantity decreased from 11,779 to 11,222 SY.

Item 714 4099 PIPE CONDUIT 18IN-APPROCH; 4 LF was added.

Item 714 6500 END SECT METAL 18IN; 2 EA was added.

Item 714 9680 PLUG PIPE-ALL TYPES & SIZES; 4 EA was added.

Item 762 0430 SHORT TERM 4IN LINE-TYPE NR; quantity increased from 3,608 to 4,572 LF.

Item 762 1104 PVMT MK PAINTED 4IN LINE; quantity increased from 3608 to 4572 LF.

This addendum is to be incorporated into the bidder's proposal for this project.

Expedite bid files should be updated by downloading the addendum file from the Bid Express on-line bidding exchange at <http://www.bidx.com/> or the Department's web page (<http://www.dot.nd.gov>) and load it into the Expedite program.

For 
CAL J. GENDREAU – CONSTRUCTION SERVICES ENGINEER
80:plm
Enclosure

◇ June 30, 2016

ADDENDUM 1
Job No.2

TO: All prospective bidders and suppliers on Project SC-2730(061), Job No. 2, scheduled for the July 15, 2016, bid opening.

Revisions for SC-2730(061):

Remove & Replace Plan Sheets:

- Section 1 Sheet 1
- Section 2 Sheet 1
- Section 6 Sheet 1-2
- Section 8 Sheets 1-2
- Section 10 Sheet 1
- Section 30 Sheet 1
- Section 60 Sheets 1-4
- Section 75 Sheets 1-6
- Section 76 Sheets 1-4
- Section 77 Sheets 1-4
- Section 100 Sheet 1, 3-7
- Section 120 Sheet 1
- Section 170 Sheets 1-2, 4-5, 7-8, 10-11
- Section 200 Sheets 1-60

with the enclosed sheets revised 06/06/16, 06/23/2016 & 6/30/2016.

Electronic files will be made available through the NDDOT's Plans and Proposals Page

SECTION 1

SHEET 1:

- Revised Project Length table

SECTION 2

SHEET 1:

- Revised page numbers for Section 200

SECTION 6

SHEET 1:

- Added Sheet 1
- Added note 202-P04 - "REMOVAL OF TEMPORARY BYPASS: Include the following in the price bid for "REMOVAL OF TEMPORARY BYPASS": Daily maintenance of the temporary bypass, removal of material, regrading and the removal the aggregate base. Daily maintenance will include blading, watering and keeping traffic control clean. The aggregate removed will become property of the Contractor."

- Added note 203-P01 “COMPACTION CONTROL: Construct the embankment within the roadbed 2:1 prism with “BORROW-EXCAVATION” or “COMMON EXCAVATION-TYPE B” in accordance with Section 203.04 E.2 of the Standard Specifications. Construct the embankment outside the roadbed prism 2:1’s in accordance with Section 203.04 E.3 of the Standard Specifications.
- Revised note 704-450 to 704-P01
LANE CLOSURE - SIGNAL CONTROL/FLAGGING CONTROL: Install either the signal controlled lane closure on Standard D-704-16 or the flagging controlled lane closure on Standard D-704-17.

Obtain an electrical source for traffic signals. Solar powered signals may be used. Place generators a minimum of 60 feet from the roadway centerline, unless the generator and signal are part of a trailer mounted unit.

Place utility poles and equipment a minimum of 60 feet from the roadway centerline and place power conductors a minimum of 6 inches below the ground surface. Remove poles after they are no longer necessary.

The Engineer will measure individual traffic control devices, other than the signal system and flaggers, shown on the standards. Payment will be made at the respective contract unit price.

Regardless of the means of operations four “LANE CLOSURE - SIGNAL CONTROL/FLAGGING CONTROL”, one per site, will be paid for.

Include the cost of either a traffic signal system or flaggers/pilot car in the contract unit price for “LANE CLOSURE - SIGNAL CONTROL/FLAGGING CONTROL”.

SHEET 2:

- Added Sheet 2

SECTION 8

SHEET 1:

- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
203	0109	TOPSOIL	CY	2580	5656
203	0121	TOPSOIL – WETLAND	CY	621	604
203	0140	BORROW-EXCAVATION	CY	14322	25165
210	0210	FOUNDATION FILL	CY	2909	2445
216	0100	WATER	MGAL	485	392
251	0200	SEEDING CLASS II	ACRE	4.13	5.94
251	1000	WETLAND SEED	ACRE	0.77	0.75
251	2000	TEMPORARY COVER CROP	ACRE	4.03	5.91

253	0101	STRAW MULCH	ACRE	8.93	12.59
261	0112	FIBER ROLLS 12IN	LF	10456	16680
261	0113	REMOVE FIBER ROLLS 12IN	LF	6503	8441
262	100	FLOTATION SILT CURTAIN	LF	561	559
262	101	REMOVE FLOTATION SILT CURTAIN	LF	561	559
302	0120	AGGREGATE BASE COURSE CL 5	TON	1366	3544
401	0050	TACK COAT	GAL	366	478
401	0060	PRIME COAT	GAL	915	1195
401	0160	BLOTTER MATERIAL CL 44	TON	28	36
430	0045	SUPERPAVE FAA 45	TON	805	1044
430	5828	PG 58-28 ASPHALT CEMENT	TON	47	63
606	1108	11FT X 8FT PRECAST RCB CULVERT	LF	114	110
606	1211	12FT X 11FT PRECAST RCB CULVERT	LF	84	64
606	1311	13FT X 11FT PRECAST RCB CULVERT	LF	84	64
606	3108	DBL 11FT X 8FT PRECAST RCB CULVERT	LF	114	110

SHEET 1 (cont.):

- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
606	3206	DBL 12FT X 6FT PRECAST RCB CULVERT	LF	168	128
606	3211	DBL 12FT X 11FT PRECAST RCB CULVERT	LF	84	64
606	3311	DBL 13FT X 11FT PRECAST RCB CULVERT	LF	84	64

- Added Bid Items:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
203	0102	COMMON EXCAVATION-TYPE B	CY	-	1613
202	0350	REMOVAL OF TEMPORARY BYPASS	EA	-	4
260	0200	SILT FENCE SUPPORTED	LF	-	533
260	0201	REMOVE SILT FENCE SUPPORTED	LF	-	533

- Removed Bid Items:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
203	0101	COMMON EXCAVATION-TYPE A	CY	461	-
203	0113	COMMON EXCAVATION-WASTE	CY	11348	-
704	1041	ATTENUATION DEVICE-TYPE B-55	EA	8	-

- Moved from Sheet 1 to Sheet 2:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
704	1052	TYPE III BARRICADE	EA	12	12

SHEET 2:

- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
709	0151	GEOSYNTHETIC MATERIAL TYPE R1	SY	11779	11222
762	430	SHORT TERM 4IN LINE – TYPE NR	LF	3608	4572
762	1104	PVMT MK PAINTED 4IN LINE	LF	3608	4572

- Added Bid Items:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
704	1500	OBLITERATION OF PAVEMENT MARKING	SF	-	477
714	4099	PIPE CONDUIT 18IN-APPROACH	LF	-	4
714	6500	END SECT METAL 18IN	EA	-	2
714	9680	PLUG PIPE-ALL TYPES & SIZES	EA	-	4

SECTION 10

SHEET 1:

- Updated Earthwork Summary Tables
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
203	0109	TOPSOIL	CY	1217	4293
203	0140	BORROW-EXCAVATION	CY	3443	14286

- Added Bid Items:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
203	0102	COMMON EXCAVATION-TYPE B	CY	-	1613

- Removed Bid Items:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
203	0101	COMMON EXCAVATION-TYPE A	CY	461	-

SECTION 30

SHEET 1: Updated Proposed Co Rt 30 Typical Section

SECTION 60

SHEET 1:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
302	0120	AGGREGATE BASE COURSE CL 5	TON	351	911
401	0050	TACK COAT	GAL	94	123
401	0060	PRIME COAT	GAL	235	307
401	0160	BLOTTER MATERIAL CL 44	TON	7	9
430	0045	SUPERPAVE FAA 45	TON	207	268
430	5828	PG 58-28 ASPHALT CEMENT	TON	12	16

- Added Bid Items:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
714	9680	PLUG PIPE-ALL TYPES & SIZES	EA	-	4

SHEET 2:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
302	0120	AGGREGATE BASE COURSE CL 5	TON	351	911
401	0050	TACK COAT	GAL	94	123
401	0060	PRIME COAT	GAL	235	307
401	0160	BLOTTER MATERIAL CL 44	TON	7	9
430	0045	SUPERPAVE FAA 45	TON	207	268

430	5828	PG 58-28 ASPHALT CEMENT	TON	12	16
-----	------	-------------------------	-----	----	----

SHEET 3:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
302	0120	AGGREGATE BASE COURSE CL 5	TON	324	842
401	0050	TACK COAT	GAL	87	113
401	0060	PRIME COAT	GAL	217	283
401	0160	BLOTTER MATERIAL CL 44	TON	7	9
430	0045	SUPERPAVE FAA 45	TON	191	248
430	5828	PG 58-28 ASPHALT CEMENT	TON	11	15

SHEET 4:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
302	0120	AGGREGATE BASE COURSE CL 5	TON	340	880
401	0050	TACK COAT	GAL	91	119
401	0060	PRIME COAT	GAL	228	298
401	0160	BLOTTER MATERIAL CL 44	TON	7	9
430	0045	SUPERPAVE FAA 45	TON	200	260
430	5828	PG 58-28 ASPHALT CEMENT	TON	12	16

- Added Bid Items:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
714	4099	PIPE CONDUIT 18IN-APPROACH	LF	-	4
714	6500	END SECT METAL 18IN	EA	-	2

SECTION 75

SHEET 1: Updated Wetland Impacts Table

SHEET 2: Updated Other Waters Impacts Table

SHEET 3:

- Revised permanent impacts for Wetland 21 from 0.11 to 0.15 acres
- Revised temporary impacts for Wetland 21 from 0.14 to 0.12 acres
- Revised mitigation for Wetland 21 from 0.11 to 0.15 acres
- Changed “Ppsd R/W” to “Temp Const Emst”

SHEET 4:

- Revised permanent impacts for Wetland 26 from 0.10 to 0.11 acres
- Revised mitigation for Wetland 26 from 0.10 to 0.11 acres
- Revised permanent impacts for POWUS 1 from 0.05 (143’) to 0.04 (114’) acres
- Changed “Ppsd R/W” to “Temp Const Emst”

SHEET 5:

- Revised permanent impacts for Wetland 35 from 0.11 to 0.09 acres
- Revised mitigation for Wetland 35 from 0.11 to 0.09 acres
- Revised permanent impacts for POWUS 2 from 0.02 (60’) to 0.01 (38’) acres
- Changed “Ppsd R/W” to “Temp Const Emst”

SHEET 6:

- Revised permanent impacts for Wetland 37 from 0.06 to 0.04 acres
- Revised mitigation for Wetland 37 from 0.06 to 0.04 acres
- Changed “Ppsd R/W” to “Temp Const Emst”

SECTION 76

SHEET 1:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
251	2000	TEMPORARY COVER CROP	ACRE	0.931	1.267
253	0101	STRAW MULCH	ACRE	0.931	1.267
261	0112	FIBER ROLLS 12IN	LF	672	1091
261	0113	REMOVE FIBER ROLLS 12IN	LF	672	1091
262	0100	FLOTATION SILT CURTAIN	LF	187	354
262	0101	REMOVE FLOTATION SILT CURTAIN	LF	187	354

SHEET 2:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
251	2000	TEMPORARY COVER CROP	ACRE	0.942	1.382
253	0101	STRAW MULCH	ACRE	0.942	1.382
261	0112	FIBER ROLLS 12IN	LF	826	1363
261	0113	REMOVE FIBER ROLLS 12IN	LF	826	1363
262	0100	FLOTATION SILT CURTAIN	LF	109	40
262	0101	REMOVE FLOTATION SILT CURTAIN	LF	109	40

- Added Bid Items:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
260	0200	SILT FENCE SUPPORTED	LF	-	122
260	0201	REMOVE SILT FENCE SUPPORTED	LF	-	122

SHEET 3:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
251	2000	TEMPORARY COVER CROP	ACRE	0.784	1.405
253	0101	STRAW MULCH	ACRE	0.784	1.405
261	0112	FIBER ROLLS 12IN	LF	792	1187
261	0113	REMOVE FIBER ROLLS 12IN	LF	792	1187
262	0100	FLOTATION SILT CURTAIN	LF	114	15
262	0101	REMOVE FLOTATION SILT CURTAIN	LF	114	15

- Added Bid Items:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
260	0200	SILT FENCE SUPPORTED	LF	-	335
260	0201	REMOVE SILT FENCE SUPPORTED	LF	-	335

SHEET 4:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
251	2000	TEMPORARY COVER CROP	ACRE	1.370	1.855
253	0101	STRAW MULCH	ACRE	1.370	1.855
261	0112	FIBER ROLLS 12IN	LF	1013	1600
261	0113	REMOVE FIBER ROLLS 12IN	LF	1013	1600
262	0100	FLOTATION SILT CURTAIN	LF	31	30
262	0101	REMOVE FLOTATION SILT CURTAIN	LF	31	30

- Added Bid Items:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
260	0200	SILT FENCE SUPPORTED	LF	-	76
260	0201	REMOVE SILT FENCE SUPPORTED	LF	-	76

SECTION 77

SHEET 1:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
203	0121	TOPSOIL-WETLAND	CY	241	256
251	0200	SEEDING CL II	ACRE	0.929	1.154
251	1000	WETLAND SEED	ACRE	0.299	0.317
253	0101	STRAW MULCH	ACRE	1.228	1.471
261	0112	FIBER ROLLS 12IN	LF	992	2341

SHEET 2:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”

- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
203	0121	TOPSOIL-WETLAND	CY	123	131
251	0200	SEEDING CL II	ACRE	0.960	1.379
251	1000	WETLAND SEED	ACRE	0.152	0.162
253	0101	STRAW MULCH	ACRE	1.113	1.541
261	0112	FIBER ROLLS 12IN	LF	935	2100

SHEET 3:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
203	0121	TOPSOIL-WETLAND	CY	175	135
251	0200	SEEDING CL II	ACRE	0.800	1.455
251	1000	WETLAND SEED	ACRE	0.217	0.168
253	0101	STRAW MULCH	ACRE	1.017	1.623
261	0112	FIBER ROLLS 12IN	LF	906	1827

SHEET 4:

- Reprinted due to grading limit changes
- Reprinted due to added shoulder
- Reprinted due to shortened box culvert
- Changed “Ppsd R/W” to “Temp Const Emst”
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
251	0200	SEEDING CL II	ACRE	1.443	1.948
253	0101	STRAW MULCH	ACRE	1.545	2.050
261	0112	FIBER ROLLS 12IN	LF	1120	1971

SECTION 100

SHEET 1:

- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
762	0430	SHORT TERM 4IN LIN-TYPE NR	LF	3608	4572

- Added Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
704	1500	OBLITERATION OF PAVEMENT MARKINGS	SF	-	477

SHEET 3: Removed “Common Excavation-Waste” from Temporary Bypass Earthwork Summary table

SHEET 4:

- Changed “Ppsd R/W” to “Temp Const Emst”
- Added Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
202	0350	REMOVAL OF TEMPORARY BYPASS	EA	-	1

SHEET 5:

- Changed “Ppsd R/W” to “Temp Const Emst”
- Added Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
202	0350	REMOVAL OF TEMPORARY BYPASS	EA	-	1

SHEET 6:

- Changed “Ppsd R/W” to “Temp Const Emst”
- Added Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
202	0350	REMOVAL OF TEMPORARY BYPASS	EA	-	1

SHEET 7:

- Changed “Ppsd R/W” to “Temp Const Emst”
- Added Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
202	0350	REMOVAL OF TEMPORARY BYPASS	EA	-	1

SECTION 120

SHEET 1:

- Revised Summary of Pavement Marking Details Table
- Revised Grand Totals Table

- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
762	1104	PVMT MK PAINTED 4IN LINE	LF	3608	4572

SECTION 170

SHEET 1:

- Changed length of box culvert from 84'-0" to 64'-0"
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
210	0210	FOUNDATION FILL	CY	755	588
606	3206	DBL 12FT X 6FT PRECAST RCB CULVERT	LF	168	128
709	0151	GEOSYNTHETIC MATERIAL TYPE R1	SY	803	612

SHEET 2:

- Changed note 100-P01 from "SCOPE OF WORK: Work at this site consists of removing the existing structures, four-60"Ø corrugated steel pipes and replacing them with a quadruple barrel 12' x 6' x 84' precast concrete box culvert." To "SCOPE OF WORK: Work at this site consists of removing the existing structures, four-60"Ø corrugated steel pipes and replacing them with a quadruple barrel 12' x 6' x 64' precast concrete box culvert."

SHEET 4:

- Changed length of box culvert from 84'-0" to 64'-0"
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
210	0210	FOUNDATION FILL	CY	703	571
606	1211	12FT X 11FT PRECAST RCB CULVERT	LF	84	64
606	3211	DBL 12FT X 11FT PRECAST RCB CULVERT	LF	84	64
709	0151	GEOSYNTHETIC MATERIAL TYPE R1	SY	688	524

SHEET 5:

- Changed note 100-P01 from "SCOPE OF WORK: Work at this site consists of removing the existing structure, a 45' long bridge and replacing it with a new triple barrel 12' x 11' x 84' precast concrete box culvert." To "SCOPE OF WORK: Work at this site consists of removing the existing structure, a 45' long bridge and replacing it with a new triple barrel 12' x 11' x 64' precast concrete box culvert."

SHEET 7:

- Changed length of box culvert from 84'-0" to 64'-0"
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
210	0210	FOUNDATION FILL	CY	692	552
606	1311	13FT X 11FT PRECAST RCB CULVERT	LF	84	64
606	3311	DBL 13FT X 11FT PRECAST RCB CULVERT	LF	84	64
709	0151	GEOSYNTHETIC MATERIAL TYPE R1	SY	717	546

SHEET 8:

- Changed note 100-P01 from "SCOPE OF WORK: Work at this site consists of removing the existing structure, a 68' long bridge and replacing it with a new triple barrel 13' x 11' x 84' precast concrete box culvert." To "SCOPE OF WORK: Work at this site consists of removing the existing structure, a 68' long bridge and replacing it with a new triple barrel 13' x 11' x 64' precast concrete box culvert."

SHEET 10:

- Changed length of box culvert from 114'-0" to 110'-0"
- Revised Quantities:

Spec	Code	Description	Unit	Previous Quantity	Addendum A Quantity
210	0210	FOUNDATION FILL	CY	759	734
606	1108	11FT X 8FT PRECAST RCB CULVERT	LF	114	110
606	3108	DBL 11FT X 8FT PRECAST RCB CULVERT	LF	114	110
709	0151	GEOSYNTHETIC MATERIAL TYPE R1	SY	891	860

SHEET 11:

- Changed note 100-P01 from "SCOPE OF WORK: Work at this site consists of removing the existing structures, two-10' corrugated steel pipes and replacing them with a new triple barrel 11' x 8' x 114' precast concrete box culvert." To "SCOPE OF WORK: Work at this site consists of removing the existing structures, two-10' corrugated steel pipes and replacing them with a new triple barrel 11' x 8' x 110' precast concrete box culvert."

SECTION 200

SHEETS 1-19:


- Renumbered and sheets 20-43 added
- Revised to reflect updated County Route 30 cross sections.

SHEETS 20-60:

Renumbered and revised to reflect wetland mitigation label changes.

This addendum is to be incorporated into bidder's proposal for this project.

Sincerely,
KLJ

A handwritten signature in blue ink that reads 'Jessica R. Karls'.

Jessica R Karls

Project Engineer

Enclosure(s): Revised Plan Sheets
-Project #: SC-2730(061)

BID ITEMS

Project: SC-2730(061) (PCN-21548)

Bidder must type or neatly print unit prices in numerals, make extensions for each item, and total. Do not carry unit prices further than three (3) decimal places.

Item No.	Spec No.	Code No.	Description	Unit	Approx. Quantity	Unit Price		Amount	
						\$\$\$\$\$	000	\$\$\$\$\$	00
001	103	0100	CONTRACT BOND	L SUM	1.				
002	201	0330	CLEARING & GRUBBING	L SUM	1.				
003	202	0108	REMOVAL OF STRUCTURE-SITE 1	L SUM	1.				
004	202	0109	REMOVAL OF STRUCTURE-SITE 2	L SUM	1.				
005	202	0110	REMOVAL OF STRUCTURE-SITE 3	L SUM	1.				
006	202	0132	REMOVAL OF BITUMINOUS SURFACING	SY	3,309.				
007	202	0174	REMOVAL OF PIPE ALL TYPES AND SIZES	LF	360.				
008	202	0269	REMOVAL OF STRUCTURE-SITE 4	L SUM	1.				
009	202	0312	REMOVE EXISTING FENCE	LF	927.				
010	202	0350	REMOVAL OF TEMPORARY BYPASS	EA	4.				
011	203	0102	COMMON EXCAVATION-TYPE B	CY	1,613.				
012	203	0109	TOPSOIL	CY	5,656.				
013	203	0121	TOPSOIL-WETLAND	CY	604.				
014	203	0140	BORROW-EXCAVATION	CY	25,165.				
015	210	0051	BOX CULVERT EXCAVATION - SITE 1	EA	1.				
016	210	0052	BOX CULVERT EXCAVATION - SITE 2	EA	1.				

BID ITEMS

Project: SC-2730(061) (PCN-21548)

Bidder must type or neatly print unit prices in numerals, make extensions for each item, and total. Do not carry unit prices further than three (3) decimal places.

Item No.	Spec No.	Code No.	Description	Unit	Approx. Quantity	Unit Price		Amount	
						\$\$\$\$	000	\$\$\$\$	00
017	210	0053	BOX CULVERT EXCAVATION - SITE 3	EA	1.				
018	210	0054	BOX CULVERT EXCAVATION - SITE 4	EA	1.				
019	210	0202	FOUNDATION PREPARATION-SITE 1	L SUM	1.				
020	210	0203	FOUNDATION PREPARATION-SITE 2	L SUM	1.				
021	210	0204	FOUNDATION PREPARATION-SITE 3	L SUM	1.				
022	210	0205	FOUNDATION PREPARATION-SITE 4	L SUM	1.				
023	210	0210	FOUNDATION FILL	CY	2,445.				
024	216	0100	WATER	M GAL	392.				
025	251	0200	SEEDING CLASS II	ACRE	5.940				
026	251	1000	WETLAND SEED	ACRE	.750				
027	251	2000	TEMPORARY COVER CROP	ACRE	5.910				
028	253	0101	STRAW MULCH	ACRE	12.590				
029	256	0200	RIPRAP GRADE II	CY	467.				
030	260	0200	SILT FENCE SUPPORTED	LF	533.				
031	260	0201	REMOVE SILT FENCE SUPPORTED	LF	533.				
032	261	0112	FIBER ROLLS 12IN	LF	16,680.				

BID ITEMS

Project: SC-2730(061) (PCN-21548)

Bidder must type or neatly print unit prices in numerals, make extensions for each item, and total. Do not carry unit prices further than three (3) decimal places.

Item No.	Spec No.	Code No.	Description	Unit	Approx. Quantity	Unit Price		Amount	
						\$\$\$\$	000	\$\$\$\$	00
033	261	0113	REMOVE FIBER ROLLS 12IN	LF	8,441.				
034	262	0100	FLOTATION SILT CURTAIN	LF	559.				
035	262	0101	REMOVE FLOTATION SILT CURTAIN	LF	559.				
036	302	0050	TRAFFIC SERVICE AGGREGATE	TON	2,264.				
037	302	0120	AGGREGATE BASE COURSE CL 5	TON	3,544.				
038	401	0050	TACK COAT	GAL	478.				
039	401	0060	PRIME COAT	GAL	1,195.				
040	401	0160	BLOTTER MATERIAL CL 44	TON	36.				
041	430	0045	SUPERPAVE FAA 45	TON	1,044.				
042	430	1000	CORED SAMPLE	EA	8.				
043	430	5828	PG 58-28 ASPHALT CEMENT	TON	63.				
044	606	1108	11FT X 8FT PRECAST RCB CULVERT	LF	110.				
045	606	1211	12FT X 11FT PRECAST RCB CULVERT	LF	64.				
046	606	1311	13FT X 11FT PRECAST RCB CULVERT	LF	64.				
047	606	3108	DBL 11FT X 8FT PRECAST RCB CULVERT	LF	110.				
048	606	3206	DBL 12FT X 6FT PRECAST RCB CULVERT	LF	128.				

BID ITEMS

Project: SC-2730(061) (PCN-21548)

Bidder must type or neatly print unit prices in numerals, make extensions for each item, and total. Do not carry unit prices further than three (3) decimal places.

Item No.	Spec No.	Code No.	Description	Unit	Approx. Quantity	Unit Price		Amount	
						\$\$\$\$	000	\$\$\$\$	00
049	606	3211	DBL 12FT X 11FT PRECAST RCB CULVERT	LF	64.				
050	606	3311	DBL 13FT X 11FT PRECAST RCB CULVERT	LF	64.				
051	606	7108	DBL 11FT X 8FT PRECAST RCB END SECTION	EA	2.				
052	606	7206	DBL 12FT X 6FT PRECAST RCB END SECTION	EA	2.				
053	606	7211	DBL 12FT X 11FT PRECAST RCB END SECTION	EA	2.				
054	606	7311	DBL 13FT X 11FT PRECAST RCB END SECTION	EA	2.				
055	702	0100	MOBILIZATION	L SUM	1.				
056	704	0100	FLAGGING	MHR	40.				
057	704	1000	TRAFFIC CONTROL SIGNS	UNIT	3,194.				
058	704	1018	LANE CLOSURE-SIGNAL CONTROL/FLAGGING CONTROL	EA	4.				
059	704	1052	TYPE III BARRICADE	EA	12.				
060	704	1060	DELINEATOR DRUMS	EA	20.				
061	704	1067	TUBULAR MARKERS	EA	130.				
062	704	1080	STACKABLE VERTICAL PANELS	EA	260.				
063	704	1500	OBLITERATION OF PAVEMENT MARKING	SF	477.				
064	706	0600	CONTRACTOR'S LABORATORY	EA	1.				

BID ITEMS

Project: SC-2730(061) (PCN-21548)

Bidder must type or neatly print unit prices in numerals, make extensions for each item, and total. Do not carry unit prices further than three (3) decimal places.

Item No.	Spec No.	Code No.	Description	Unit	Approx. Quantity	Unit Price		Amount	
						\$\$\$\$	000	\$\$\$\$	00
065	709	0151	GEOSYNTHETIC MATERIAL TYPE R1	SY	11,222.				
066	709	0155	GEOSYNTHETIC MATERIAL TYPE RR	SY	932.				
067	714	4099	PIPE CONDUIT 18IN-APPROACH	LF	4.				
068	714	6500	END SECT METAL 18IN	EA	2.				
069	714	9680	PLUG PIPE-ALL TYPES & SIZES	EA	4.				
070	752	0320	FENCE BARBED WIRE 4 STRAND-STEEL POST	LF	1,554.				
071	752	0900	FENCE TEMPORARY INSTALL & REMOVE	LF	2,213.				
072	752	0922	FENCE REMOVE & RESET	LF	588.				
073	752	2110	RESET VEHICLE GATE	EA	2.				
074	752	3150	CORNER ASSEMBLY BARBED WIRE-WOOD POST	EA	20.				
075	754	0803	OBJECT MARKERS - TYPE III	EA	16.				
076	762	0430	SHORT TERM 4IN LINE-TYPE NR	LF	4,572.				
077	762	1104	PVMT MK PAINTED 4IN LINE	LF	4,572.				
078	900	1000	TEMPORARY STREAM DIVERSION	EA	4.				
			TOTAL SUM BID						

Revised 06/23/16	STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	21548	1	1

JOB # 2

MCKENZIE COUNTY, NORTH DAKOTA

SC-2730(061)


- Structure #27-131-30.3
- Structure #27-132-29.1
- Structure #27-134-27.0
- Structure #27-136-27.0

GOVERNING SPECIFICATIONS

Standard Specifications for Road and Bridge Construction adopted by the North Dakota Department of Transportation October 2008; Standard Drawings currently in effect; and other Contract Provisions submitted herein.

PROJECT LENGTH

Project	Gross Miles	Net Miles
#27-131-30.0	0.152	0.152
#27-132-29.1	0.156	0.156
#27-134-27.0	0.152	0.152
#27-136-27.0	0.156	0.156
TOTAL	0.616	0.616



STATE COUNTY MAP

DESIGN DATA


Traffic SC-2730(061)		Average Daily			Est. 30th Max. Hr.
		Passenger	Trucks	Total	
Current Traffic	2015	3690	170	3860	386
Forecast Traffic	2035	5470	250	5720	572

Design Speed:
Minimum Sight Dist. for Stopping:

55 MPH
495 Feet

**BOX CULVERT
STRUCTURE #27-134-27.0**
Sta 1196+75 = A Point Approximately
248 Feet North and 1400 Feet West
of the Southwest Corner of Sec. 2,
Twp. 149 N., Rge. 99 W.

Structure Replacement & Roadway Construction



**BOX CULVERT
STRUCTURE #27-136-27.0**
Sta 1271+78 = A Point Approximately
18 Feet North and 766 Feet East
of the Southwest Corner of Sec. 1,
Twp. 149 N., Rge. 99 W.

**BOX CULVERT
STRUCTURE #27-131-30.0**
Sta 897+20 = A Point Approximately
9 Feet North and 598 Feet West
of the Southwest Corner of Sec. 20,
Twp. 149 N., Rge. 99 W.

**BOX CULVERT
STRUCTURE #27-132-29.1**
Sta 1026+84 = A Point Approximately
2311 Feet North and 42 Feet West
of the Southwest Corner of Sec. 16,
Twp. 149 N., Rge. 99 W.

Surveyed & Designed Date November 2014


<p>This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND</p>	<p align="center">CERTIFICATION</p> <p>I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF NORTH DAKOTA.</p> <p align="center">/s/ Jessica R Karls KLJ</p> <p>DATE <u>6/23/2016</u> REGISTRATION NUMBER <u>8408</u></p>	 <p>3203 32ND AVENUE SOUTH, SUITE 201 P.O. BOX 9767 FARGO, ND 58106 (701) 232-5353 © KLJ 2016</p>
--	---	--

TABLE OF CONTENTS

<u>SECTION NO.</u>	<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	1	Title Sheet
2	1	Table of Contents, Special Provisions & List of Standard Drawings
4	1	Scope of Work
6	1	Plan Notes
6	2	Environmental Commitments
8	1-2	Estimate of Quantities
10	1	Basis of Estimate
20	1	Silt Fence Detail
30	1	Typical Sections
60	1-4	Plan and Profile
75	1-2	Wetland Impact Table
75	2-6	Wetlands, Mitigation, and Environmental
76	1-4	Temporary Erosion Control
77	1-4	Permanent Erosion Control
80	1-4	Fencing Layouts
100	1	Traffic Control Devices List
100	2	Traffic Control Signing Layout
100	3	Traffic Control Typical Sections
100	4-7	Temporary Bypass Plan and Profile
110	1-2	Permanent Signing Layout
120	1	Permanent Pavement Markings
170	1-12	Box Culverts
200	1-60	Cross Sections

SPECIAL PROVISIONS

<u>SP #</u>	<u>DESCRIPTION</u>
SP 0003(14)	Temporary Erosion and Sediment Best Management Practices
SP 0004(14)	Federal Migratory Bird Treaty Act
SP 5118(14)	Permits and Environmental Conditions
SP 324(14)	Temporary Water Diversion

LIST OF STANDARD DRAWINGS

<u>STANDARD NO.</u>	<u>DESCRIPTION</u>
D-101-1, 2 & 3	NDDOT Abbreviations
D-101-10	NDDOT Utility Company and Organization Abbreviations
D-101-20 & 21	Line Styles
D-101-30, 31 & 32	Symbols
D-255-2	Erosion and Siltation Control – Erosion Control Blanket Installation
D-260-1	Erosion Control – Silt Fence
D-261-1	Erosion Control – Fiber Roll Placement Details
D-704-2	Traffic Control for Coring of Hot Bituminous Pavement
D-704-7 & 8	Breakaway Systems for Construction Zone Signs
D-704-9	Construction Sign Details - Terminal and Guide Signs
D-704-10	Construction Sign Details - Regulatory Signs
D-704-11	Construction Sign Details - Warning Signs
D-704-13	Barricade and Channelizing Device Details
D-704-14	Construction Sign Punching and Mounting Details
D-704-15	Road Closure Layouts
D-704-16	Lane Closure on a Two Lane Road Using Traffic Control Signals
D-704-17	Sign Layout for One Lane Closure Two Lane Roadway
D-704-19	Road Closure and Lane Closure on a Two Way Road Layouts
D-704-21	Detour and Roadway Diversion Sign Layouts
D-704-22	Construction Truck and Temporary Detour Layouts
D-704-26	Miscellaneous Sign Layouts
D-704-27	Traffic Control Plan for Moving Operations
D-704-50	Portable Sign Support Assembly
D-708-6	Erosion and Siltation Controls - Median or Ditch Inlet Protection
D-754-23	Perforated Tube Assembly Details
D-754-24A	Breakaway Coupler System for Perforated Tubes
D-754-24 & 25	Mounting Details Perforated Tube
D-754-82	Object Markers
D-762-4	Pavement Marking
D-762-11	Short Term Pavement Marking



PLAN NOTES

Revised 06/30/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	6	1

100-P01 WEEKLY PLANNING/REPORTING MEETING: Organize a weekly meeting to coordinate efforts between subcontractors, utilities, local authorities, and others.

Send a knowledgeable representative to conduct the weekly reporting/planning meeting. Prepare minutes for each meeting and make the appropriate distribution of the minutes. Have the minutes approved by the Engineer before distribution.

Provide a written schedule of the next week's work and a tentative schedule of the following week. Include a discussion of problems encountered during the current week; also include information of interest to local authorities, subcontractors, and utilities.

Invite interested agencies to the meeting. At a minimum, include the following agencies and any other agencies that are necessary:

- McKenzie County
- Affected Utility Companies
- Subcontractors

105-200 UTILITY COORDINATION: A utility coordination meeting is required.

107-710 HAUL ROADS: Before submitting a proposal, contact the appropriate State, County, Township or City officials to determine if there are any roadways that will be designated as "no haul routes".

200-P01 SHRINKAGE: An additional 25 percent volume is included in for shrinkage in earthwork embankment.

201-P01 CLEARING AND GRUBBING: Include the cost to remove the guardrail as specified in Section 202 of the Standard Specifications.

202-P01 SAW CUT: Include the cost of the full depth vertical saw cuts adjacent to pavement removal areas, specified in Section 202.04 A "General", in the contract unit price for "REMOVAL OF BITUMINOUS SURFACING".

202-P02 REMOVAL OF PAVEMENT: Include the cost of removing aggregate as specified in Section 202.04 D, in the contract unit price for "REMOVAL OF BITUMINOUS SURFACING".

202-P03 FENCE REMOVAL: Notify landowners in writing, with a copy to the Engineer, a minimum of 30 days in advance of fence removal. Just prior to removing fence, coordinate verbally with the adjacent landowners. Additional information, including the property owners' contact information, will be available from the Engineer.

202-P04 REMOVAL OF TEMPORARY BYPASS: Include the following in the price bid for "REMOVAL OF TEMPORARY BYPASS": Daily maintenance of the temporary bypass, removal of material, regrading and the removal the aggregate base. Daily maintenance will include blading, watering and keeping traffic control clean. The aggregate removed will become property of the Contractor.

203-385 AVERAGE HAUL: No average haul has been computed for this project.

203-P01 COMPACTION CONTROL: Construct the embankment within the roadbed 2:1 prism with "BORROW-EXCAVATION" or "COMMON EXCAVATION-TYPE B" in accordance with Section 203.04 E.2 of the Standard Specifications. Construct the embankment outside the roadbed prism 2:1's in accordance with Section 203.04 E.3 of the Standard Specifications.

203-P02 BENCHING ON WIDENING SECTIONS: Bench all inslopes, regardless of rate of slope, unless otherwise directed by the Engineer. Bench deep enough to provide sufficient width to permit placing, spreading and compacting equipment to operate. Compact each bench thoroughly before placing additional embankment. Include costs for benching in the price bid for earthwork items.

203-P03 TOPSOIL: The quantity of topsoil to be removed, salvaged and respread is based upon an assumed topsoil depth of 4 inches and wetland topsoil depth of 6 inches. Make arrangements for topsoil storage areas if sufficient room is not available within the right of way. No payment will be made for additional handling of topsoil that must be moved to provide additional excavation area between the proposed grading limits and the right of way. Re-spread topsoil evenly over the areas to be seeded. The bid item "Topsoil" and "Topsoil-Wetland" includes all labor, materials and equipment associated with stripping, stockpiling and re-spreading the existing topsoil.

203-P04 COMMON EXCAVATION-TYPE B: Include all costs associated with excavating, transporting, placing material and shaping the channel in the price bid for "COMMON EXCAVATION-TYPE B". "COMMON EXCAVATION-TYPE B" will be paid at plan quantity.

256-P01 RIPRAP: Place riprap around the proposed box culvert in such a manner that the box culvert is not damaged and the flow is not obstructed. Include all costs to place riprap around the pipe in the price bid for "RIPRAP GRADE II".

704-P01 LANE CLOSURE - SIGNAL CONTROL/FLAGGING CONTROL: Install either the signal controlled lane closure on Standard D-704-16 or the flagging controlled lane closure on Standard D-704-17.

Obtain an electrical source for traffic signals. Solar powered signals may be used. Place generators a minimum of 60 feet from the roadway centerline, unless the generator and signal are part of a trailer mounted unit.

Place utility poles and equipment a minimum of 60 feet from the roadway centerline and place power conductors a minimum of 6 inches below the ground surface. Remove poles after they are no longer necessary.

The Engineer will measure individual traffic control devices, other than the signal system and flaggers, shown on the standards. Payment will be made at the respective contract unit price.

Regardless of the means of operations four "LANE CLOSURE – SIGNAL CONTROL/FLAGGING CONTROL", one per site, will be paid for.


Include the cost of either a traffic signal system or flaggers/pilot car in the contract unit price for "LANE CLOSURE – SIGNAL CONTROL/FLAGGING CONTROL".

714-P01 TEMPORARY CULVERTS: Size and place temporary pipes as required. All costs associated with temporary pipe conduits shall be included in the price bid for "REMOVAL OF TEMPORARY BYPASS".

752-P01 FENCE REMOVE & RESET: Contact the landowner seven days prior to the removal of the fence. Notify the Engineer once landowners have been contacted. Remove and reset the existing gates adjacent to fence designated in the plans to be reset. Include all costs associated with removing and resetting the existing gates in the bid item "FENCE REMOVE & RESET". Provide temporary fence if needed at all locations requiring removal and resetting of fence. Include all costs associated with installing and removing temporary fence in the price bid for "FENCE REMOVE & RESET".

900-P01 TEMPORARY STREAM DIVERSION: Temporary stream diversion shall be constructed according to current standards. All work and materials needed to construct temporary stream diversion shall be included in the price bid for "TEMPORARY STREAM DIVERSION".

This document was originally issued and sealed by
 Jessica R. Karls
 Registration Number
 PE-8408,
 on 06/30/16 and the original document is stored at KLJ,
 Fargo, ND.

COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA</small>		
	PLAN NOTES	
	<small>DRWN. BY</small> JN	<small>CHKD. BY</small> JL

ENVIRONMENTAL NOTES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SC-2730(061)	6	2

ENVIRONMENTAL NOTES (EN): McKenzie County, the North Dakota Department of Transportation and the Federal Highway Administration have made environmental commitments to secure approval of this project. The following environmental notes are requirements to comply with these commitments:

EN-1 SPAWNING RESTRICTION: Do not work within Cherry Creek from April 15 to June 1.

EN-2 WHOOPING CRANE: The project is located within the migration corridor of the endangered whooping crane, and suitable stopover habitat for the whooping crane is present. The migration periods of the whooping crane are April 1st to May 15th and September 10 to October 31.

Stop all construction activities and notify the Engineer immediately in the event a whooping crane is identified within one mile of the project location. The Engineer will then coordinate with the USFWS, FHWA and NDDOT. Do not resume work within the avoidance area until the Engineer has confirmed that the bird has left the area.

One above ground utility line pole will be shifted; however, the alignment of the utility line will not change. Additional above ground utility conflicts are not foreseen with this project but if any impacts are required, contact the NDDOT Utility Engineer to coordinate with the utility company. Bird diverters will be installed by the utility company on overhead utility lines that are shifted due to the proposed action.

EN-3 AQUATIC NUISANCE SPECIES (ANS): Notify the North Dakota Game and Fish Department (NDGFD) at least 72 hours prior to any vehicles, vessels, pumps and equipment entering the water, to allow the NDGFD sufficient time to inspect any and all such equipment for ANS. Contact the NDGFD ANS Coordinator, Jessica Howell, by phone (701)368-8368 or e-mail jmhowell@nd.gov for equipment inspections, or any additional information regarding ANS prevention protocol. Supply the inspection report to the engineer prior to work taking place in the water.


EN-4 TEMPORARY WETLAND IMPACT: Temporary impact areas within wetlands and or other waters are incorporated into the plans for this project. Remove temporary fill placed and sedimentation in wetlands or other waters. Restore these wetlands to preconstruction contours.

EN-5 WETLAND MITIGATION: Wetland mitigation is required for unavoidable permanent wetland impacts. The wetland mitigation plan is incorporated into the plans for this project. After completion of the mitigation area, the Engineer will complete the Onsite Mitigation Certification Form SFN 61042. Any sedimentation occurring within the mitigation area will be removed.

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	8	1

ESTIMATE OF QUANTITIES


SPEC	CODE	ITEM DESCRIPTION	UNIT	TOTAL
103	0100	CONTRACT BOND	L SUM	1
201	0330	CLEARING & GRUBBING	L SUM	1
202	0108	REMOVAL OF STRUCTURE-SITE 1	L SUM	1
202	0109	REMOVAL OF STRUCTURE-SITE 2	L SUM	1
202	0110	REMOVAL OF STRUCTURE-SITE 3	L SUM	1
202	0132	REMOVAL OF BITUMINOUS SURFACING	SY	3,309
202	0269	REMOVAL OF STRUCTURE-SITE 4	L SUM	1
202	0174	REMOVAL OF PIPE ALL TYPES AND SIZES	LF	360
202	0312	REMOVE EXISTING FENCE	LF	927
202	0350	REMOVAL OF TEMPORARY BYPASS	EA	4
203	0102	COMMON EXCAVATION-TYPE B	CY	1,613
203	0109	TOPSOIL	CY	5,656
203	0121	TOPSOIL-WETLAND	CY	604
203	0140	BORROW-EXCAVATION	CY	25,165
210	0051	BOX CULVERT EXCAVATION - SITE 1	EA	1
210	0052	BOX CULVERT EXCAVATION - SITE 2	EA	1
210	0053	BOX CULVERT EXCAVATION - SITE 3	EA	1
210	0054	BOX CULVERT EXCAVATION - SITE 4	EA	1
210	0202	FOUNDATION PREPARATION-SITE 1	L SUM	1
210	0203	FOUNDATION PREPARATION-SITE 2	L SUM	1
210	0204	FOUNDATION PREPARATION-SITE 3	L SUM	1
210	0205	FOUNDATION PREPARATION-SITE 4	L SUM	1
210	0210	FOUNDATION FILL	CY	2,445
216	0100	WATER	M GAL	392
251	0200	SEEDING CLASS II	ACRE	5.94
251	1000	WETLAND SEED	ACRE	0.75
251	2000	TEMPORARY COVER CROP	ACRE	5.91
253	0101	STRAW MULCH	ACRE	12.59
256	0200	RIPRAP GRADE II	CY	467
260	0200	SILT FENCE SUPPORTED	LF	533
260	0201	REMOVE SILT FENCE SUPPORTED	LF	533
261	0112	FIBER ROLLS 12IN	LF	16,680
261	0113	REMOVE FIBER ROLLS 12IN	LF	8,441
262	0100	FLOTATION SILT CURTAIN	LF	559
262	0101	REMOVE FLOTATION SILT CURTAIN	LF	559
302	0050	TRAFFIC SERVICE AGGREGATE	TON	2,264
302	0120	AGGREGATE BASE COURSE CL 5	TON	3,544
401	0050	TACK COAT	GAL	478
401	0060	PRIME COAT	GAL	1,195
401	0160	BLOTTER MATERIAL CL 44	TON	36
430	0045	SUPERPAVE FAA 45	TON	1,044
430	1000	CORED SAMPLE	EA	8
430	5828	PG 58-28 ASPHALT CEMENT	TON	63
606	1108	11FT X 8FT PRECAST RCB CULVERT	LF	110
606	1211	12FT X 11FT PRECAST RCB CULVERT	LF	64
606	1311	13FT X 11FT PRECAST RCB CULVERT	LF	64
606	3108	DBL 11FT X 8FT PRECAST RCB CULVERT	LF	110
606	3206	DBL 12FT X 6FT PRECAST RCB CULVERT	LF	128
606	3211	DBL 12FT X 11FT PRECAST RCB CULVERT	LF	64
606	3311	DBL 13FT X 11FT PRECAST RCB CULVERT	LF	64
606	7108	DBL 11FT X 8FT PRECAST RCB END SECTION	EA	2
606	7206	DBL 12FT X 6FT PRECAST RCB END SECTION	EA	2
606	7211	DBL 12FT X 11FT PRECAST RCB END SECTION	EA	2
606	7311	DBL 13FT X 11FT BRECAST RCB END SECTION	EA	2
702	0100	MOBILIZATION	L SUM	1
704	0100	FLAGGING	MHR	40
704	1000	TRAFFIC CONTROL SIGNS	UNIT	3,194
704	1018	LANE CLOSURE-SIGNAL CONTROL/FLAGGING CONTROL	EA	4

COUNTY RT 30 MCKENZIE COUNTY, NORTH DAKOTA		
	ESTIMATE OF QUANTITIES	
	DRAWN BY AM	CHKD. BY JL

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	8	2

ESTIMATE OF QUANTITIES

SPEC	CODE	ITEM DESCRIPTION	UNIT	MAINLINE
704	1052	TYPE III BARRICADE	EA	12
704	1060	DELINEATOR DRUMS	EA	20
704	1067	TUBULAR MARKERS	EA	130
704	1080	STACKABLE VERTICAL PANELS	EA	260
704	1500	OBLITERATION OF PAVEMENT MARKING	SF	477
706	0600	CONTRACTOR'S LABORATORY	EA	1
709	0151	GEOSYNTHETIC MATERIAL TYPE R1	SY	11222
709	0155	GEOSYNTHETIC MATERIAL TYPE RR	SY	932
714	4099	PIPE CONDUIT 18IN-APPROACH	LF	4
714	6500	END SECT METAL 18IN	EA	2
714	9680	PLUG PIPE-ALL TYPES & SIZES	EA	4
752	0320	FENCE BARBED WIRE 4 STRAND-STEEL POST	LF	1554
752	0900	FENCE TEMPORARY INSTALL & REMOVE	LF	2213
752	0922	FENCE REMOVE & RESET	LF	588
752	2110	RESET VEHICLE GATE	EA	2
752	3150	CORNER ASSEMBLY BARBED WIRE-WOOD POST	EA	20
754	0803	OBJECT MARKERS - TYPE III	EA	16
762	0430	SHORT TERM 4IN LINE-TYPE NR	LF	4572
762	1104	PVMT MK PAINTED 4IN LINE	LF	4572
900	1000	TEMPORARY STREAM DIVERSION	EA	4

COUNTY RT 30 MCKENZIE COUNTY, NORTH DAKOTA		
	ESTIMATE OF QUANTITIES	
	<small>DRWN. BY</small> AM	<small>CHKD. BY</small> JL

BASIS OF ESTIMATE

GRADING EARTHWORK SUMMARY

LOCATION	EMBANKMENT (CY)	COMMON EXCAVATION (CY)	BORROW - EXCAVATION (CY)
	A	B	C = B - A
Box Culvert Structure #27-131-30.0	4372	100	4272
Box Culvert Structure #27-132-29.1	3608	652	2956
Box Culvert Structure #27-134-27.0	2916	379	2537
Box Culvert Structure #27-136-27.0	5003	482	4521
TOTAL	15899	1613	14286

GRADING TOPSOIL SUMMARY

LOCATION	TOPSOIL EMBANKMENT (CY)	TOPSOIL COMMON EXCAVATION (CY)	TOPSOIL COMMON EXCAVATION-WASTE (CY)
	A	B	C = B - A
Box Culvert Structure #27-131-30.0	861	940	79
Box Culvert Structure #27-132-29.1	1128	1187	59
Box Culvert Structure #27-134-27.0	977	1033	56
Box Culvert Structure #27-136-27.0	1083	1133	50
TOTAL	4049	4293	244

Notes:

1. An additional volume of 25% to allow for shrinkage is included in all embankment volumes.
2. All Earthwork and Topsoil Quantities are an approximate using OSHA and NDDOT Standards. True quantities will be determined during construction.
3. If contractor decides to use a Temporary Bypass Channel to divert water around Box Culverts during construction add 3700 CY per box of Common Excavation, 4590 CY per box of Embankment, 200 CY per box for Topsoil Excavation, and 200 CY per box for Topsoil Embankment. Temporary Bypass Channel quantities were based off of a 400' by 15' by 6' bottom Channel.

Pavement
Aggregate CL 5 @ 1.875 Ton/CY
Tack Coat @ 0.05 Gal/SY
Prime Coat @ 0.25 Gal/SY
Blotter Material CI 44 @ 15 lbs/SY
PG 64-28 Asphalt Cement @ 5.9%
Superpave FAA 45 @ 2 Ton/CY

Water
10 M Gal/Mile for Dust Palliative
20 Gal/Ton for Aggregate
10 Gal/CY for Embankment

Topsoil
6 Inches

Seeding
Entire disturbed area less hard surfaces


Mulching
One application for temporary seeding
One application for permanent seeding less ECB & TRM locations

Floating Silt Curtain
30 LF per Temporary Bypass Channel to be used at contractors discretion following NDDOT and EPA Standards



Fiber Rolls 12IN
800 LF per Temporary Bypass Channel to be used at contractors discretion following NDDOT and EPA Standards

Geosynthetic Material Type R1
2170 SY per Temporary Bypass Channel to be used at contractors discretion following NDDOT and EPA Standards


This document was originally issued and sealed by
Jessica R. Karls
Registration Number
PE- 8408,
on 06/23/16 and the original document is stored at KLJ,
Fargo, ND.

COUNTY RT 30 MCKENZIE COUNTY, NORTH DAKOTA		
	BASIS OF ESTIMATE	
	DRAWN BY JM	CHKD. BY JK

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	30	1



Proposed Co Rt 30 Typical Section
 Sta 895+50 to Sta 898+75
 Sta 1025+25 to Sta 1028+50
 Sta 1195+65 to Sta 1198+65
 Sta 1270+60 to Sta 1273+75




Proposed Typical Section Lift Summary:
 Top Lift = 2.0"
 Superpave FAA 45 (PG 58-28)
 Average Area = 5.4546 SF
 1st Lift = 2.0"
 Superpave FAA 45 (PG 58-28)
 Average Area = 5.6972 SF

This document was originally issued and sealed by Jessica R. Karls Registration Number PE- 8408, on 06/23/16 and the original document is stored at KLJ, Fargo, ND.

COUNTY RT 30
 MCKENZIE COUNTY, NORTH DAKOTA

TYPICAL SECTIONS



DRWN. BY JM	CHKD. BY JK	PROJECT NO. 14314102
----------------	----------------	-------------------------



REMOVE
 STA 897+11 ~ C
 2-60IN X 62 LF CSP
 N. INV. = 2133.00
 S. INV. = 2133.86

REMOVE
 STA 897+61 ~ C
 2-60IN X 38 LF CSP
 N. INV. = 2136.20
 S. INV. = 2136.44

202 0132	REMOVAL OF BITUMINOUS SURFACING		
Sta 895+50 to 898+75		849	SY
202 0174	REMOVAL OF PIPE ALL TYPES AND SIZES		
Sta 897+11 CL		62	LF
Sta 897+11 CL		62	LF
Sta 897+61 CL		38	LF
Sta 897+61 CL		38	LF
TOTAL		200	LF
302 0120	AGGREGATE BASE COURSE CL 5		
Sta 895+50 to 898+75		911	TON
401 0050	TACK COAT		
Sta 895+50 to 898+75		123	GAL
401 0060	PRIME COAT		
Sta 895+50 to 898+75		307	GAL
401 0160	BLOTTER MATERIAL CL 44		
Sta 895+50 to 898+75		9	TON
430 0045	SUPERPAVE FAA 45		
Sta 895+50 to 898+75		268	TON
430 1000	CORED SAMPLE		
Sta 895+50 to 898+75		2	EA
430 5828	PG 58-28 ASPHALT CEMENT		
Sta 895+50 to 898+75		16	TON
714 9680	PLUG PIPE-ALL TYPES & SIZES		
Sta 892+32.30		1	EA
Sta 893+50.60		1	EA
Sta 899+13.30		1	EA
Sta 899+35.50		1	EA
TOTAL		4	EA



This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 06/23/16 and the original document is stored at KLJ Fargo, ND


COUNTY RT 30
 MCKENZIE COUNTY, NORTH DAKOTA
 STRUCTURE #27-131-30.0

KLJ

PLAN & PROFILE
 Sta 893+00 to Sta 903+00
 (EX30E)




DRWN BY: PM CRKD BY: JK PROJECT NO.: 14314102

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	60	2



202	0132	REMOVAL OF BITUMINOUS SURFACING	
		Sta 1025+25 to 1028+50	833 SY
302	0120	AGGREGATE BASE COURSE CL 5	
		Sta 1025+25 to 1028+50	911 TON
401	0050	TACK COAT	
		Sta 1025+25 to 1028+50	123 GAL
401	0060	PRIME COAT	
		Sta 1025+25 to 1028+50	307 GAL
401	0160	BLOTTER MATERIAL CL 44	
		Sta 1025+25 to 1028+50	9 TON
430	0045	SUPERPAVE FAA 45	
		Sta 1025+25 to 1028+50	268 TON
430	1000	CORED SAMPLE	
		Sta 1025+25 to 1028+50	2 EA
430	5828	PG 58-28 ASPHALT CEMENT	
		Sta 1025+25 to 1028+50	16 TON

Sec. 16
T-149-N
R-99-W



This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND


COUNTY RT 30
MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-132-29.1

PLAN & PROFILE
Sta 1022+00 to Sta 1032+00
(EX30E)




DRWN BY PM	CHKD BY JK	PROJECT NO. 14314102
---------------	---------------	-------------------------

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	60	3

Sec. 3
T-149-N
R-99-W



202 0132	REMOVAL OF BITUMINOUS SURFACING	
Sta 1195+65 to 1198+65		780 SY
302 0120	AGGREGATE BASE COURSE CL 5	
Sta 1195+65 to 1198+65		842 TON
401 0050	TACK COAT	
Sta 1195+65 to 1198+65		113 GAL
401 0060	PRIME COAT	
Sta 1195+65 to 1198+65		283 GAL
401 0160	BLOTTER MATERIAL CL 44	
Sta 1195+65 to 1198+65		9 TON
430 0045	SUPERPAVE FAA 45	
Sta 1195+65 to 1198+65		248 TON
430 1000	CORED SAMPLE	
Sta 1195+65 to 1198+65		2 EA
430 5828	PG 58-28 ASPHALT CEMENT	
Sta 1195+65 to 1198+65		15 TON



This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND

COUNTY RT 30
MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-134-27.0


PLAN & PROFILE
Sta 1193+00 to Sta 1203+00
(EX30E)

DRWN BY PM	CHKD BY JK	PROJECT NO. 14314102
---------------	---------------	-------------------------



Sec. 1
T-149-N
R-99-W

Sec. 12
T-149-N
R-99-W

202 0132 REMOVAL OF BITUMINOUS SURFACING	
Sta 1270+60 to 1273+75	847 SY
202 0174 REMOVAL OF PIPE ALL TYPES AND SIZES	
Sta 1271+91 CL	80 LF
Sta 1271+91 CL	80 LF
TOTAL	160 LF
302 0120 AGGREGATE BASE COURSE CL 5	
Sta 1270+60 to 1273+75	880 TON
401 0050 TACK COAT	
Sta 1270+60 to 1273+75	119 GAL
401 0060 PRIME COAT	
Sta 1270+60 to 1273+75	298 GAL
401 0160 BLOTTER MATERIAL CL 44	
Sta 1270+60 to 1273+75	9 TON
430 0045 SUPERPAVE FAA 45	
Sta 1270+60 to 1273+75	260 TON
430 1000 CORED SAMPLE	
Sta 1270+60 to 1273+75	2 EA
430 5828 PG 58-28 ASPHALT CEMENT	
Sta 1270+60 to 1273+75	16 TON
714 4099 PIPE CONDUIT 18IN-APPROACH	
Sta Sta 1270+60.33 to 1271+12.30	4 LF
714 6500 END SECT METAL 18IN	
Sta 1270+60.33 to 1271+12.30	2 EA



REMOVE
STA 1271+91 ~ C
80 LF CSP
N. INV. = 2114.27
S. INV. = 2114.61



This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND

COUNTY RT 30
MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-136-27.0

KLJ

PLAN & PROFILE
Sta 1267+00 to Sta 1277+00
(EX30E)

DRWN BY: PM CRD BY: JK PROJECT NO.: 14314102

Wetland Impact Table																		
Wetland Number	Location	Cowardin Class.	Wetland Type	Wetland Size (acres)	Wetland Feature	USACE Jurisdictional Wetlands ¹	Wetland Impacts (acres)		USFWS Easement Impacts (acres)		Wetland Mitigation							
							Temp.	Perm.	Temp.	Perm.	Mitigation Required		Bank		Onsite			
											EO 11990	USACE	Location	acres	Mitigation Location; Ratio	acres	Constructed Site #	Constructed size (acres)
21	Sec. 30, T149N, R99W Sec. 19, 20 & 29, T149N, R99W	PEMCx	Road Ditch/ Drainage	2.86 ²	Artificial/ Natural	Yes	0.12	0.15	N/A	N/A	Yes	No	N/A	N/A	Onsite adjacent to wetland 21	0.15	N/A	N/A
26 ³	Sec. 16 & 17, T149N, R99W	PEMC	Creek	0.32	Natural	Yes	0.04	0.11	N/A	N/A	Yes	Yes	N/A	N/A	Onsite adjacent to wetland 26	0.11	N/A	N/A
35 ⁴	Sec. 3, T149N, R99W	PEMC	Creek	1.12	Natural	Yes	0.08	0.09	N/A	N/A	Yes	Yes	N/A	N/A	Onsite adjacent to wetland 35	0.09	N/A	N/A
37	Sec. 1 & 12, T149N, R99W	PEMC	Creek	0.33	Natural	Yes	0.04	0.04	N/A	N/A	Yes	No	N/A	N/A	Onsite adjacent to wetland 37	0.04	N/A	N/A
			Totals	1.77			0.28	0.39	N/A	N/A			N/A			0.39		N/A

¹ A wetland Jurisdictional Determination was issued by the USACE on 1/27/2015; NWO-2014-2391-BIS.

² Wetland boundary shown in wetland delineation report was extended via office delineation by 0.38 acres to account for temporary impacts resulting from temporary bypass.

³ Wetlands 26 and 35 are associated with the same aquatic resource (S. Hammond, Personal Communication, August 21, 2015).

⁴ Wetlands 26 and 35 are associated with the same aquatic resource (S. Hammond, Personal Communication, August 21, 2015).

Other Waters Impact Table															
Other Waters										Other Water Mitigation					
Number	Location	Type	Size		Feature	USACE Jurisdictional ¹	Impacts to Other Waters				Mitigation Required ⁵			Mitigation Location; ratio	Method
			Acres	Linear Feet			Acres Temp	Acres Perm	Linear Feet Temp	Linear Feet Perm	EO 11990	USACE	USFWS		
POWUS1 ⁶	Sec. 16 & 17, T149N, R99W	Named Stream (Cherry Creek)	0.16	406	Natural	Yes	0.03	0.04	67	114	N/A	No	N/A	N/A	N/A
POWUS2 ⁷	Sec. 3, T149N, R99W	Named Stream (Cherry Creek)	0.10	351	Natural	Yes	0.00	0.01	0	38	N/A	No	N/A	N/A	N/A
POWUS3	Sec. 1 & 12, T149N, R99W	Named Stream (Spring Creek)	0.09	413	Natural	Yes	0.01	0.01	74	84	N/A	No	N/A	N/A	N/A
Totals			0.35	1,170			0.04	0.06	141	236					

Summary Impact Table			
Total Permanent Impact Summary		Temporary Impacts and additional information	
Wetland Type	Total (Acres)	Wetland Type	Total (Acres/Lf)
Natural/JD	0.35	Temporary JD	0.28
Natural/Non-JD	0	Non-JD Temporary	0
Artificial/JD	0	Permanent JD > 0.10	0.20 ⁸
Artificial /Non-JD	0	Permanent OW	0.08/287
Total	0.35	Temporary OW	0.04/141









⁵ All artificial/non-jurisdictional, deep water (impacts greater than 6.6 feet), Other Waters less than 300 linear feet (determined by the USACE on a case by case), and temporary impacts do not require mitigation.


⁶ POWUS1 and POWUS2 are segments of the same aquatic resource.

⁷ POWUS1 and POWUS2 are segments of the same aquatic resource.


⁸ Sum of wetlands 26 and 35, which are associated with the same aquatic resource (S. Hammond, Personal Communication, August 21, 2015)

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	75	3


-  Temporary Wetland Impact
-  Permanent Wetland Impact
-  Inslope Wetland Impact
-  Temporary POWUS Impact
-  Permanent POWUS Impact
-  Wetland Mitigation
-  Wetland Delineated Line Exst
-  POWUS Line Exst










Wetland 21
 Permanent Impact = 0.15 acres
 Temporary Impact = 0.12 acres
 Inslope Impacts (does not require mitigation) = 0.04 acres
 Mitigation = 0.15 acres





This document was originally issued and sealed by
 Jessica R. Karls,
 Registration Number
 PE- 8408,
 on 6/23/2016 and the original document is stored at KLJ
 Fargo, ND

COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-131-30.0</small>		
	WETLAND IMPACTS TEMPORARY BYPASS 131 Sta 890+00 to Sta 905+00 (EX30E)	
	DRAWN BY JM	CHKD BY JK


Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	75	4

-  Temporary Wetland Impact
-  Permanent Wetland Impact
-  Temporary POWUS Impact
-  Permanent POWUS Impact
-  Wetland Mitigation
-  Wetland Delineated Line Exst
-  POWUS Line Exst




Wetland 26
 Permanent Impact = 0.11 acres
 Temporary Impact = 0.04 acres
 Inslope Impact (does not require mitigation) = 0.00 acres
 * Impacts less than 0.01 acres
 Mitigation = 0.11 acres








POWUS 1
 Temporary Impact = 0.03 acres (67')
 Permanent Impact = 0.04 acres (114')




This document was originally issued and sealed by
 Jessica R. Karls,
 Registration Number
 PE- 8408,
 on 6/23/2016 and the original document is stored at KLJ
 Fargo, ND

COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-132-29.1</small>		
	WETLAND IMPACTS TEMPORARY BYPASS 132 Sta 1020+00 to Sta 1035+00 (EX30E)	
	DRAWN BY JM	CHECKED BY JK

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	75	5



-  Temporary Wetland Impact
-  Permanent Wetland Impact
-  Temporary POWUS Impact
-  Permanent POWUS Impact
-  Wetland Mitigation
-  Wetland Delineated Line Exst
-  POWUS Line Exst




Wetland 35
 Permanent Impact = 0.09 acres
 Temporary Impact = 0.08 acres
 Mitigation = 0.09 acres

Wetland 36
 Temporary Impact = 0.00* acres
 *Impacts less than 0.01 acres








POWUS 2
 Permanent Impact = 0.01 acres (38')




This document was originally issued and sealed by
 Jessica R. Karls,
 Registration Number
 PE- 8408,
 on 6/23/2016 and the original document is stored at KLJ
 Fargo, ND

COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-134-27.0</small>		
	WETLAND IMPACTS TEMPORARY BYPASS 134 Sta 1190+00 to Sta 1205+00 (EX30E)	
	DRAWN BY JM	CHECKED BY JK


Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	75	6

-  Temporary Wetland Impact
-  Permanent Wetland Impact
-  Temporary POWUS Impact
-  Permanent POWUS Impact
-  Wetland Mitigation
-  Wetland Delineated Line Exst
-  POWUS Line Exst




Wetland 37
 Permanent Impact = 0.04 acres
 Temporary Impact = 0.04 acres
 Mitigation = 0.04 acres


POWUS 3
 Permanent Impact = 0.01 acres (84')
 Temporary Impact = 0.01 acres (74')



This document was originally issued and sealed by
 Jessica R. Karls,
 Registration Number
 PE- 8408,
 on 6/23/2016 and the original document is stored at KLJ
 Fargo, ND


COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-136-27.0</small>		
	WETLAND IMPACTS TEMPORARY BYPASS 136 Sta 1265+00 to Sta 1280+00 (EX30E)	
	DRAWN BY JM	CHECKED BY JK

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	76	1



251	2000	TEMPORARY COVER CROP		
Sta 890+00 to Sta 905+00			1.267	ACRE
253	0101	STRAW MULCH		
Sta 890+00 to Sta 905+00			1.267	ACRE
261	0112	FIBER ROLLS 12IN		
Sta 890+00 to Sta 905+00, Lt			576	LF
Sta 890+00 to Sta 905+00, Rt			515	LF
TOTAL			1091	LF
261	0113	REMOVE FIBER ROLLS 12IN		
Sta 890+00 to Sta 905+00, Lt			576	LF
Sta 890+00 to Sta 905+00, Rt			515	LF
TOTAL			1091	LF
262	0100	FLOTATION SILT CURTAIN		
Sta 890+00 to Sta 905+00, Lt			192	LF
Sta 890+00 to Sta 905+00, Rt			162	LF
TOTAL			354	LF
262	0101	REMOVE FLOTATION SILT CURTAIN		
Sta 890+00 to Sta 905+00, Lt			192	LF
Sta 890+00 to Sta 905+00, Rt			162	LF
TOTAL			354	LF

- Temporary Cover Crop & Straw Mulch
- 12IN Fiber Rolls
- Silt Fence
- Delineated Wetland
- Mitigated Wetland




This document was originally issued and sealed by
 Jessica R. Karls,
 Registration Number
 PE- 8408,
 on 6/23/2016 and the original document is stored at KLJ
 Fargo, ND


COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-131-30.0</small>		
	TEMPORARY EROSION CONTROL Sta 890+00 to Sta 905+00 (EX30E)	
	DRAWN BY JM	CHKD. BY JK

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	76	2

251	2000	TEMPORARY COVER CROP		
Sta 1020+00 to Sta 1035+00			1.382	ACRE
253	0101	STRAW MULCH		
Sta 1020+00 to Sta 1035+00			1.382	ACRE
260	0200	SILT FENCE SUPPORTED		
Sta 1020+00 to Sta 1035+00, Lt			38	LF
Sta 1020+00 to Sta 1035+00, Rt			84	LF
TOTAL			122	LF
260	0201	REMOVE SILT FENCE SUPPORTED		
Sta 1020+00 to Sta 1035+00, Lt			38	LF
Sta 1020+00 to Sta 1035+00, Rt			84	LF
TOTAL			122	LF
261	0112	FIBER ROLLS 12IN		
Sta 1020+00 to Sta 1035+00, Lt			742	LF
Sta 1020+00 to Sta 1035+00, Rt			621	LF
TOTAL			1363	LF
261	0113	REMOVE FIBER ROLLS 12IN		
Sta 1020+00 to Sta 1035+00, Lt			742	LF
Sta 1020+00 to Sta 1035+00, Rt			621	LF
TOTAL			1363	LF
262	0100	FLOTATION SILT CURTAIN		
Sta 1020+00 to Sta 1035+00, Lt			25	LF
Sta 1020+00 to Sta 1035+00, Rt			15	LF
TOTAL			40	LF
262	0101	REMOVE FLOTATION SILT CURTAIN		
Sta 1020+00 to Sta 1035+00, Lt			25	LF
Sta 1020+00 to Sta 1035+00, Rt			15	LF
TOTAL			40	LF




- Temporary Cover Crop & Straw Mulch
- 12IN Fiber Rolls
- Silt Fence
- Flotation Silt Curtain
- Delineated Wetland
- Mitigated Wetland



This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND



COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-132-29.1</small>	
TEMPORARY EROSION CONTROL Sta 1020+00 to Sta 1035+00 (EX30E)	
DRAWN BY JM	CHECKED BY JK
PROJECT NO. 14314102	

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	76	3



251	2000	TEMPORARY COVER CROP	
		Sta 1190+00 to Sta 1205+00	1.405 ACRE
253	0101	STRAW MULCH	
		Sta 1190+00 to Sta 1205+00	1.405 ACRE
260	0200	SILT FENCE SUPPORTED	
		Sta 1190+00 to Sta 1205+00, Lt	167 LF
		Sta 1190+00 to Sta 1205+00, Rt	168 LF
		TOTAL	335 LF
260	0201	REMOVE SILT FENCE SUPPORTED	
		Sta 1190+00 to Sta 1205+00, Lt	168 LF
		Sta 1190+00 to Sta 1205+00, Rt	169 LF
		TOTAL	335 LF
261	0112	FIBER ROLLS 12IN	
		Sta 1190+00 to Sta 1205+00, Lt	585 LF
		Sta 1190+00 to Sta 1205+00, Rt	602 LF
		TOTAL	1187 LF
261	0113	REMOVE FIBER ROLLS 12IN	
		Sta 1190+00 to Sta 1205+00, Lt	670 LF
		Sta 1190+00 to Sta 1205+00, Rt	602 LF
		TOTAL	1187 LF
262	0100	FLOTATION SILT CURTAIN	
		Sta 1190+00 to Sta 1205+00, Lt	15 LF
262	0101	REMOVE FLOTATION SILT CURTAIN	
		Sta 1190+00 to Sta 1205+00, Lt	15 LF


- Temporary Cover Crop & Straw Mulch
- 12IN Fiber Rolls
- Silt Fence
- Flotation Silt Curtain
- Delineated Wetland
- Mitigated Wetland









This document was originally issued and sealed by
 Jessica R. Karls,
 Registration Number
 PE- 8408,
 on 6/23/2016 and the original document is stored at KLJ
 Fargo, ND


COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-134-27.0</small>		
TEMPORARY EROSION CONTROL Sta 1190-00 to Sta 1205+00 (EX30E)		
DRAWN BY JM	CHKD BY JK	PROJECT NO. 14314102

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	76	4




251	2000	TEMPORARY COVER CROP		
Sta 1265+00 to Sta 1280+00			1.855	ACRE
253	0101	STRAW MULCH		
Sta 1265+00 to Sta 1280+00			1.855	ACRE
260	0200	SILT FENCE SUPPORTED		
Sta 1265+00 to Sta 1280+00, Lt			54	LF
Sta 1265+00 to Sta 1280+00, Rt			22	LF
TOTAL			76	LF
260	0201	REMOVE SILT FENCE SUPPORTED		
Sta 1265+00 to Sta 1280+00, Lt			54	LF
Sta 1265+00 to Sta 1280+00, Rt			22	LF
TOTAL			76	LF
261	0112	FIBER ROLLS 12IN		
Sta 1265+00 to Sta 1280+00, Lt			762	LF
Sta 1265+00 to Sta 1280+00, Rt			838	LF
TOTAL			1600	LF
261	0113	REMOVE FIBER ROLLS 12IN		
Sta 1265+00 to Sta 1280+00, Lt			762	LF
Sta 1265+00 to Sta 1280+00, Rt			838	LF
TOTAL			1600	LF
262	0100	FLOTATION SILT CURTAIN		
Sta 1265+00 to Sta 1280+00, Lt			20	LF
Sta 1265+00 to Sta 1280+00, Rt			10	LF
TOTAL			30	LF
262	0101	REMOVE FLOTATION SILT CURTAIN		
Sta 1265+00 to Sta 1280+00, Lt			20	LF
Sta 1265+00 to Sta 1280+00, Rt			10	LF
TOTAL			30	LF

-  Temporary Cover Crop & Straw Mulch
-  12IN Fiber Rolls
-  Silt Fence
-  Flotation Silt Curtain
-  Delineated Wetland
-  Mitigated Wetland









This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND



COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA</small> <small>STRUCTURE #27-136-27.0</small>		
		
TEMPORARY EROSION CONTROL Sta 1265+00 to Sta 1280+00 (EX30E)		
<small>DRWN. BY</small> JM	<small>CHKD. BY</small> JK	<small>PROJECT NO.</small> 14314102

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	77	1


203 0121 TOPSOIL-WETLAND	
Sta 890+00 to Sta 910+00	256 CY
251 0200 SEEDING CLASS II	
Sta 890+00 to Sta 910+00	1,154 ACRE
251 1000 WETLAND SEED	
Sta 890+00 to Sta 910+00	0,317 ACRE
253 0101 STRAW MULCH	
Sta 890+00 to Sta 910+00	1,471 ACRE
261 0112 FIBER ROLLS 12IN	
Sta 890+00 to Sta 905+00, Lt	1650 LF
Sta 890+00 to Sta 905+00, Rt	691 LF
TOTAL	2341 LF



-  Seeding & Straw Mulch
-  Wetland Seed
-  12IN Fiber Rolls
-  Delineated Wetland
-  Mitigated Wetland









This document was originally issued and sealed by
 Jessica R. Karls,
 Registration Number
 PE- 8408,
 on 6/23/2016 and the original document is stored at KLJ
 Fargo, ND



COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-131-30.0</small>		
	PERMANENT EROSION CONTROL Sta 890+00 to Sta 905+00 (EX30E)	
	<small>DRWN BY</small> JM	<small>CHKD BY</small> JK

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	77	2


203 0121 TOPSOIL-WETLAND		
Sta 1020+00 to Sta 1040+00	131	CY
251 0200 SEEDING CLASS II		
Sta 1020+00 to Sta 1040+00	1.379	ACRE
251 1000 WETLAND SEED		
Sta 1020+00 to Sta 1040+00	0.162	ACRE
253 0101 STRAW MULCH		
Sta 1020+00 to Sta 1040+00	1.541	ACRE
261 0112 FIBER ROLLS 12IN		
Sta 1020+00 to Sta 1035+00, Lt	1348	LF
Sta 1020+00 to Sta 1035+00, Rt	752	LF
TOTAL	2100	LF



-  Seeding & Straw Mulch
-  Wetland Seed
-  12IN Fiber Rolls
-  Delineated Wetland
-  Mitigated Wetland









This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND



COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-132-29.1</small>		
	PERMANENT EROSION CONTROL Sta 1020+00 to Sta 1035+00 (EX30E)	
	<small>DRWN. BY</small> JM	<small>CHKD. BY</small> JK

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	77	3


203 0121 TOPSOIL-WETLAND	
Sta 1190+00 to Sta 1210+00	135 CY
251 0200 SEEDING CLASS II	
Sta 1190+00 to Sta 1210+00	1.455 ACRE
251 1000 WETLAND SEED	
Sta 1190+00 to Sta 1210+00	0.168 ACRE
253 0101 STRAW MULCH	
Sta 1190+00 to Sta 1210+00	1.623 ACRE
261 0112 FIBER ROLLS 12IN	
Sta 1190+00 to Sta 1205+00, Lt	794 LF
Sta 1190+00 to Sta 1205+00, Rt	1033 LF
TOTAL	1827 LF



-  Seeding & Straw Mulch
-  Wetland Seed
-  12IN Fiber Rolls
-  Delineated Wetland
-  Mitigated Wetland









This document was originally issued and sealed by
 Jessica R. Karls,
 Registration Number
 PE- 8408,
 on 6/23/2016 and the original document is stored at KLJ
 Fargo, ND



COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-134-27.0</small>			
	PERMANENT EROSION CONTROL Sta 1190-00 to Sta 1205+00 (EX30E)		
	<table border="1" style="width: 100%; font-size: small;"> <tr> <td>DRAWN BY JM</td> <td>CHECKED BY JK</td> <td>PROJECT NO. 14314102</td> </tr> </table>	DRAWN BY JM	CHECKED BY JK
DRAWN BY JM	CHECKED BY JK	PROJECT NO. 14314102	

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	77	4


203	0121	TOPSOIL-WETLAND	
Sta 1265+00 to Sta 1280+00		82	CY
251	0200	SEEDING CLASS II	
Sta 1265+00 to Sta 1280+00, Lt		1.948	ACRE
251	1000	WETLAND SEED	
Sta 1265+00 to Sta 1280+00		0.102	ACRE
253	0101	STRAW MULCH	
Sta 1265+00 to Sta 1280+00		2.050	ACRE
261	0112	FIBER ROLLS 12IN	
Sta 1265+00 to Sta 1280+00, Lt		820	LF
Sta 1265+00 to Sta 1280+00, Rt		1151	LF
TOTAL		1971	LF




-  Seeding & Straw Mulch
-  Wetland Seed
-  12IN Fiber Rolls
-  Delineated Wetland
-  Mitigated Wetland



This document was originally issued and sealed by
 Jessica R. Karls,
 Registration Number
 PE- 8408,
 on 6/23/2016 and the original document is stored at KLJ
 Fargo, ND

COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA</small> <small>STRUCTURE #27-136-27.0</small>		
	PERMANENT EROSION CONTROL Sta 1265+00 to Sta 1280+00 (EX30E)	
	DRAWN BY JM	CHKD. BY JK



Proposed Temporary Bypass Typical Section
 Sta 4000+00 to Sta 4007+72.53 (PRBP131)
 Sta 5000+00 to Sta 5007+89.86 (PRBP132)
 Sta 6000+00 to Sta 6007+92.84 (PRBP134)
 Sta 7000+00 to Sta 7008+59.15 (PRBP136)

Temporary Bypass Earthwork Summary


LOCATION	EMBANKMENT (CY)	COMMON EXCAVATION (CY)	BORROW - EXCAVATION (CY)
	A	B	C = A - B
Temporary Bypass 131	2187	0	2187
Temporary Bypass 132	1372	210	1162
Temporary Bypass 134	829	259	570
Temporary Bypass 136	6960	0	6960
TOTAL	11348	469	10879

Temporary Bypass Topsoil Summary

LOCATION	TOPSOIL EMBANKMENT (CY)	TOPSOIL EXCAVATION (CY)
Temporary Bypass 131	250	0
Temporary Bypass 132	274	0
Temporary Bypass 134	320	0
Temporary Bypass 136	519	0
TOTAL	1363	0

This document was originally issued and sealed by Jessica R. Karls Registration Number PE- 8408, on 06/23/16 and the original document are stored at KLJ, Fargo, ND.

COUNTY RT 30
MCKENZIE COUNTY, NORTH DAKOTA







TRAFFIC CONTROL TYPICAL SECTION

DRWN: BY JM	CHKD: BY JK	PROJECT NO. 14314102
----------------	----------------	-------------------------

1. All device spacing follows MUTCD 2009 Edition.
2. If Flaggers are present use Standard Drawing D-704-19 for construction signing layout.
3. Space traffic control devices at 25' spacing.
4. Contractor to maintain all drainage.

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	100	4

202 0350 REMOVAL OF TEMPORARY BYPASS	1 EA
Temporary Bypass 131	
302 0050 TRAFFIC SERVICE AGGREGATE	557 TON
Temporary Bypass 131	



This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND

COUNTY RT 30
MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-131-30.0

KLJ


PLAN & PROFILE
TEMPORARY BYPASS 131
Sta 4000+00 to 4007+49.73
(PRBP131)

DRWN: BY JM CRKD: BY JK PROJECT NO. 14314102



Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	100	5

Sec. 17
T-149-N
R-99-W

202 0350 REMOVAL OF TEMPORARY BYPASS	1 EA
302 0050 TRAFFIC SERVICE AGGREGATE	562 TON



Sec. 16
T-149-N
R-99-W



This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND

COUNTY RT 30
MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-132-29.1





KLJ

PLAN & PROFILE
TEMPORARY BYPASS 132
Sta 5000+00 to 5007+47.93
(PRBP132)

DRWN BY: JM CKD BY: JK PROJECT NO.: 14314102

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	100	6

202 0350 REMOVAL OF TEMPORARY BYPASS	1 EA
302 0050 TRAFFIC SERVICE AGGREGATE	530 TON



This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND

COUNTY RT 30
MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-134-27.0

KLJ

PLAN & PROFILE
TEMPORARY BYPASS 134
Sta 6000+00 to 6007+24.37
(PRBP134)

DRWN BY: JM CRKD BY: JK PROJECT NO.: 14314102

Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	100	7

202 0350 REMOVAL OF TEMPORARY BYPASS	1	EA
Temporary Bypass 136		
302 0050 TRAFFIC SERVICE AGGREGATE	615	TON
Temporary Bypass 136		

Sec. 2
T-149-N
R-99-W

Sec. 1
T-149-N
R-99-W

Curve PRBP136-1
PI = 7000+92.03 Simple Curve
Delta = 40° 25' 05.22" (RT)
Da = 22° 55' 05.92"
R = 250.00
T = 92.03
L = 176.36

Curve PRBP136-2
PI = 7002+68.38 Simple Curve
Delta = 40° 25' 05.22" (LT)
Da = 22° 55' 05.92"
R = 250.00
T = 92.03
L = 176.36





Curve PRBP136-4
PI = 7007+24.11 Simple Curve
Delta = 40° 25' 05.22" (RT)
Da = 22° 55' 05.92"
R = 250.00
T = 92.03
L = 176.36

Curve PRBP136-3
PI = 7005+47.76 Simple Curve
Delta = 40° 25' 05.22" (LT)
Da = 22° 55' 05.92"
R = 250.00
T = 92.03
L = 176.36

Sec. 11
T-149-N
R-99-W

Sec. 12
T-149-N
R-99-W

REMOVE
STA 1271+91 ~ C
2-??IN X 80 LF CSP
N. INV. = 2114.27
S. INV. = 2114.61



This document was originally issued and sealed by Jessica R. Karls, Registration Number PE- 8408, on 6/23/2016 and the original document is stored at KLJ Fargo, ND

COUNTY RT 30
MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-136-27.0

KLJ

PLAN & PROFILE
TEMPORARY BYPASS 136
Sta 7000+00 to 7008+08.44
(PRBP136)


DRWN BY: JM CRKD BY: JK PROJECT NO.: 14314102


Revised 06/23/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	120	1

Pavement Markings Summary						
Station	to	Station	Description	PVMT MK PAINTED 4IN LINE		
				White Edge Line	Yellow CL Skips (10' Line, 30' Skip)	Double Yellow Barrier Line
895+50	to	898+75	Box Culvert 1	842	105	-
1025+25	to	1028+50	Box Culvert 2	650	-	850
1195+65	to	1198+65	Box Culvert 3	600	-	792
1270+60	to	1273+75	Box Culvert 4	630	103	-
SUMMARY				2,722	208	1,642


GRAND TOTALS				
SPEC	CODE	DESCRIPTION	TOTAL	UNIT
762	1104	PVMT MK PAINTED 4IN LINE	4,572	LF

This document was originally issued and sealed by Jessica R. Karls Registration Number PE- 8408, on 06/23/16 and the original document are stored at KLJ, Fargo, ND.


COUNTY RT 30 <small>MCKENZIE COUNTY, NORTH DAKOTA</small>		
	PAVEMENT MARKINGS	
	DRAWN BY JM	CHKD. BY JK




PLAN



ELEVATION



END VIEW
(Showing Dimensions)



END VIEW
(Showing Finished Section)

HYDRAULIC DATA:

Drainage Area	54.9	sq mi
Stream Gradient	0.0022	ft/ft
Design Frequency	25	yr
Design Discharge	1,913	cfs
Design Headwater Stage	2,141.0	ft
Design Tailwater Stage	2,138.3	ft
Velocity Through Culvert	10.0	fps
100-Year Frequency Discharge	3,241	cfs
100-Year Frequency Headwater	2,143.3	ft
Overtopping Stage	2,143.9	ft
Overtopping Discharge	3,900	cfs

For a double barrel box culvert with 9" thick roof, 9" floor, and 8" walls, the following total factored moments and shears would result from the application of the required loads:

FACTORED DESIGN MOMENTS (DOUBLE)		FACTORED DESIGN SHEARS (DOUBLE)	
WALL MOMENT	187 ft-lbs	WALL SHEAR	1,795 lbs
ROOF MOMENTS		ROOF SHEARS	
CORNER	-13,432 ft-lbs	CORNER	7,822 lbs
BOTTOM	25,199 ft-lbs	WALL	10,918 lbs
TOP		FLOOR SHEARS	
FLOOR MOMENTS		CORNER	9,914 lbs
CORNER	-32,604 ft-lbs	WALL	13,293 lbs
TOP	-12,716 ft-lbs		
BOTTOM	18,306 ft-lbs		
	-34,117 ft-lbs		

STRUCTURAL QUANTITIES ONLY

SPEC	CODE	ITEM DESCRIPTION	UNIT	QUANTITY
		REMOVAL OF STRUCTURE - SITE 1	L SUM	1
		BOX CULVERT EXCAVATION - SITE 1	EA	1
		FOUNDATION PREPARATION - SITE 1	L SUM	1
		FOUNDATION FILL	CY	588
		RIPRAP GRADE II	CY	136
		DBL 12FT X 6FT PRECAST RCB CULVERT	LF	128
		DBL 12FT X 6FT PRECAST RCB END SECTION	EA	2
		GEOSYNTHETIC MATERIAL TYPE R1	SY	612
		GEOSYNTHETIC MATERIAL TYPE RR	SY	271

NOTE:

The invert elevations shown represent an elevation 1 foot below the existing streambed.

This document was originally issued and sealed by Colin A. Moran, Registration Number PE- 5344, on 06/06/16 and the original document is stored at the Office of KLJ Fargo, North Dakota.

SC-2730(061)

MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-131-30.0



PRECAST BOX CULVERT LAYOUT

DRAWN BY: DMW
CHECKED BY: CLT
PROJECT NO.: 14314102

STRUCTURAL NOTES

Revised 06/06/16	STATE	PROJECT NUMBER	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	170	2

100-P01 SCOPE OF WORK: Work at this site consists of removing the existing structures, four-60"Ø corrugated steel pipes and replacing them with a quadruple barrel 12' x 6' x 64' precast concrete box culvert.

202-P01 REMOVAL OF STRUCTURE: The existing structures are four 60" Ø corrugated steel pipes. The two west pipes have a length of 62', and the two east pipes have a length of 38'. Refer to Section 6, sheet 2 and SP-4(14) for allowable removal dates for the structures.

The lump sum bid item "REMOVAL OF STRUCTURE - SITE 1" includes all work required to remove all drainage pipe components and any hazard markers at the location in accordance with the Standard Specifications. All removed materials are the property of the contractor and are to be disposed of properly off the right-of-way.

210-P01 BOX CULVERT EXCAVATION: The unit price bid for "BOX CULVERT EXCAVATION - SITE 1" includes all excavation required to build the box culvert. Perform Box Culvert Excavation according to Section 210 of the Standard Specifications. The unit price bid for "BOX CULVERT EXCAVATION - SITE 1" includes all labor and materials required to place the ordinary backfill within the limits shown on Section 170, Sheet 3.

The suitability of material from on-site excavations for use as ordinary backfill will be determined by the engineer. Embankment constructed from channel excavated material will not be measured for separate payment but will be included in the price bid for "BOX CULVERT EXCAVATION - SITE 1". Channel excavated material that is deemed not suitable for ordinary backfill will become property of the contractor and disposed of outside of the road right-of-way, not adjacent to the construction site, and at a site approved by the engineer. The unit price bid for "BOX CULVERT EXCAVATION - SITE 1" includes all costs associated with excavation, hauling, depositing and leveling the waste material.

210-P02 FOUNDATION PREPARATION: Be aware of the possible inundated conditions at this site before the bid opening. The cost of any cofferdams and dewatering the excavation is included in the bid for "FOUNDATION PREPARATION - SITE 1".

210-P03 FOUNDATION FILL: Use CL 5 as specified in Section 816, "Aggregates". Place foundation fill in layers of not more than six inches, moisten or dry as required, and thoroughly compact with mechanical tamping equipment.

When additional Foundation Fill is placed under the box, payment will be determined by computation using plan dimensions and adding 25% for shrinkage.

256-P01 RIPRAP GRADE II: Do not use broken concrete as riprap.

606-P01 PRECAST REINFORCED CONCRETE BOX CULVERT AND END SECTIONS: Tie all barrel sections together with prestressing strands or 1"Ø tie bolts as shown on Standard Drawing D-714-22. If strands are used, use a minimum of six ½"Ø strands through each joint placed at each outside corner and center wall on the double cell. Protect prestressing cables against corrosion and grout their ends. If tie bolts are used, the joints will require two ties per exterior wall located at the third points of the wall clear height.

The "DBL 12FT X 6FT PRECAST RCB END SECTION" bid item consists of the apron, cutoff wall, parapet, and wingwalls. Attach the apron to the last barrel sections, the wingwalls, and the cutoff wall. Attach the wingwalls to the last barrel section. Use a welded tie type system to connect the apron to the box and the wingwalls unless otherwise approved by the Engineer. Connect the wingwalls to the last barrel section by the use of tie bolts, steel-bolted plates, or another approved method so the inside corner surface is smooth. After backfilling, wingwall sections are to be in line. If the wingwall sections are not in line or not installed to the angles shown in the plans, remove and reset the wingwalls to be in proper alignment.

All bolts, plates, angles, and studs are to meet ASTM A36. Nuts are to be a heavy hex in conformance with ASTM A563 and washers shall be ASTM F436, Type 1. Welded pipe sleeves are to conform to ASTM A53, Grade B. Welders are required to be properly certified for all shop and field welds. Coat all field welds with galvanizing paint. Galvanize all hardware according to AASHTO M 232. Galvanize structural steel after fabrication according to AASHTO M 111.

Install five ¾"Ø threaded inserts and steel eye bolts (20 total) along top and end faces of each wingwall to provide anchorage for fencing. A 3"x3"x¾" hot dipped galvanized angle, as shown in Section 170 sheet 3 of the plans, is to also be included at each wingwall. Anchorage locations and specifications are to be shown on the shop drawings for approval by the Engineer. All costs associated with the threaded inserts, steel eye bolts, and galvanized angles are to be included in the price bid for "DBL 12FT X 6FT PRECAST RCB END SECTION."

Cast holes at 3'-0" centers through the apron and into the cutoff wall to receive ¾"Ø reinforcing bars. Cast holes in the last barrel section at 1'-0" centers for ½"Ø reinforcing bars to attach the parapet. Cast the parapet against the section. Install the bars according to the manufacturer's recommendation, with a high strength adhesive specifically intended for concrete anchorage, in accordance with Section 806.02 of the NDDOT Standard Specifications.

The distance between separate precast units is to be a minimum of 3" and a maximum of 1'-0". Fill this gap with controlled density backfill. The controlled density backfill is to be a blend of cement, water, pozzolanic materials, and fillers. The material must be able to support normal loads after 6 hours and have a compressive strength in the range of 75 psi to 125 psi at 28 days. If the mix design shown is used, no further testing will be required. The mix design yields approximately one cubic yard of flowable mortar.

MIX DESIGN

Cement	100 lbs
Fly Ash	300 lbs
Fine Aggregate	2600 lbs
Water	70 gals

The 12" cap consists of a weatherproof and freeze/thaw resistant material such as Sikagrout[®]212, BASF Masterflow[®]928, Euclid NS Grout, or an approved equal which complies with ASTM C1107.

Controlled density backfill will not be measured separately but is included in the price bid for "DBL 12FT X 6FT PRECAST RCB CULVERT".

DESIGN LOADS:





- A. HL-93 Loading
- B. Maximum Fill Height = 5'

WORK DRAWINGS: Submit the following work drawings to the Engineer of Record:

PRECAST RCB CULVERT

This document was originally issued and sealed by
Colin A. Moran,
Registration Number
PE- 5344,
on 06/06/16 and the original document is stored at the
Office of KLJ
Fargo, North Dakota.

SC-2730(061) <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-131-30.0</small>		
	STRUCTURAL NOTES	
DRAWN BY DMW	CHECKED BY CLT	PROJECT NO. 14314102



SPEC	CODE	ITEM DESCRIPTION	UNIT	QUANTITY
202	0109	REMOVAL OF STRUCTURE - SITE 2	L SUM	1
210	0052	BOX CULVERT EXCAVATION - SITE 2	EA	1
210	0203	FOUNDATION PREPARATION - SITE 2	L SUM	1
210	0210	FOUNDATION FILL	CY	571
256	0200	RIPRAP GRADE II	CY	132
606	1211	12FT X 11FT PRECAST RCB CULVERT	LF	64
606	3211	DBL 12FT X 11FT PRECAST RCB CULVERT	LF	64
606	7211	DBL 12FT X 11FT PRECAST RCB END SECTION	EA	2
709	0151	GEOSYNTHETIC MATERIAL TYPE R1	SY	524
709	0155	GEOSYNTHETIC MATERIAL TYPE RR	SY	264

HYDRAULIC DATA:

Drainage Area	81.3	sq mi
Stream Gradient	0.0017	ft/ft
Design Frequency	25	yr
Design Discharge	2,372	cfs
Design Headwater Stage	2,128.1	ft
Design Tailwater Stage	2,127.0	ft
Velocity Through Culvert	7.0	fps
100-Year Frequency Discharge	4,041	cfs
100-Year Frequency Headwater	2,131.0	ft
Overtopping Stage	2,131.2	ft
Overtopping Discharge	4,066	cfs

This document was originally issued and sealed by Colin A. Moran, Registration Number PE- 5344, on 06/06/16 and the original document is stored at the Office of KLJ Fargo, North Dakota.

For a single barrel box culvert with 9" thick roof, 9" floor, and 9" walls, the following total factored moments and shears would result from the application of the required loads:


FACTORED DESIGN MOMENTS (SINGLE)		FACTORED DESIGN SHEARS (SINGLE)	
WALL MOMENT	1,762 ft-lbs	WALL SHEAR	4,527 lbs
ROOF MOMENTS		ROOF SHEARS	
CORNER	-15,993 ft-lbs	CORNER	9,370 lbs
BOTTOM	28,433 ft-lbs		
FLOOR MOMENTS		FLOOR SHEARS	
CORNER	-19,059 ft-lbs	CORNER	12,535 lbs
TOP	25,390 ft-lbs		

For a double barrel box culvert with 9" thick roof, 9" floor, and 9" walls, the following total factored moments and shears would result from the application of the required loads:

FACTORED DESIGN MOMENTS (DOUBLE)		FACTORED DESIGN SHEARS (DOUBLE)	
WALL MOMENT	3,512 ft-lbs	WALL SHEAR	4,370 lbs
ROOF MOMENTS		ROOF SHEARS	
CORNER	-14,911 ft-lbs	CORNER	7,988 lbs
BOTTOM	25,196 ft-lbs	WALL	10,752 lbs
TOP	-32,226 ft-lbs	FLOOR SHEARS	
FLOOR MOMENTS		CORNER	10,643 lbs
CORNER	-15,950 ft-lbs	WALL	13,671 lbs
TOP	18,910 ft-lbs		
BOTTOM	-35,129 ft-lbs		

NOTE:
The invert elevations shown represent an elevation 1 foot below the existing streambed.

SC-2730(061)
MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-132-29.1



PRECAST BOX CULVERT LAYOUT

DRAWN BY DMW	CHECKED BY CLT	PROJECT NO. 14314102
-----------------	-------------------	-------------------------

STRUCTURAL NOTES

Revised 06/06/16	STATE	PROJECT NUMBER	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	170	5

100-P01 SCOPE OF WORK: Work at this site consists of removing the existing structure, a 45' long bridge and replacing it with a new triple barrel 12' x 11' x 64' precast concrete box culvert.

202-P01 REMOVAL OF STRUCTURE: The existing structure is a single span concrete bridge, 45' long with a clear roadway width of 28'. The abutments are timber. Refer to Section 6, sheet 2 and SP-4(14) for allowable removal dates for the structure.

The lump sum bid item "REMOVAL OF STRUCTURE - SITE 2" includes all work required to remove all drainage pipe components and any hazard markers at the location in accordance with the Standard Specifications. All removed materials are the property of the contractor and are to be disposed of properly off the right-of-way.

The Contractor will complete and submit SFN 17987 Asbestos Notification of Demolition and Renovation to the North Dakota Department of Health 10 days prior to beginning the removal of concrete. Tom Naas (ND License #5302) of KLJ (4585 Coleman Street, Bismarck, ND 58503-0431; 701-355-8400) completed an asbestos inspection of the existing structure on January 15, 2015. Based on laboratory analysis of bulk samples from the site, no building or structure materials were determined to contain asbestos. No other inaccessible and/or assumed ACMs were identified.

210-P01 BOX CULVERT EXCAVATION: The unit price bid for "BOX CULVERT EXCAVATION - SITE 2" includes all excavation required to build the box culvert. Perform Box Culvert Excavation according to Section 210 of the Standard Specifications. The unit price bid for "BOX CULVERT EXCAVATION - SITE 2" includes all labor and materials required to place the ordinary backfill within the limits shown on Section 170, Sheet 6.

The suitability of material from on-site excavations for use as ordinary backfill will be determined by the engineer. Embankment constructed from channel excavated material will not be measured for separate payment but will be included in the price bid for "BOX CULVERT EXCAVATION - SITE 2". Channel excavated material that is deemed not suitable for ordinary backfill will become property of the contractor and disposed of outside of the road right-of-way, not adjacent to the construction site, and at a site approved by the engineer. The unit price bid for "BOX CULVERT EXCAVATION - SITE 2" includes all costs associated with excavation, hauling, depositing and leveling the waste material.

210-P02 FOUNDATION PREPARATION: Be aware of the possible inundated conditions at this site before the bid opening. The cost of any cofferdams and dewatering the excavation is included in the bid for "FOUNDATION PREPARATION - SITE 2".

210-P03 FOUNDATION FILL: Use CL 5 as specified in Section 816, "Aggregates". Place foundation fill in layers of not more than six inches, moisten or dry as required, and thoroughly compact with mechanical tamping equipment.

When additional Foundation Fill is placed under the box, payment will be determined by computation using plan dimensions and adding 25% for shrinkage.

256-P01 RIPRAP GRADE II: Do not use broken concrete as riprap.

606-P01 PRECAST REINFORCED CONCRETE BOX CULVERT AND END SECTIONS: Tie all barrel sections together with prestressing strands or 1"Ø tie bolts as shown on Standard Drawing D-714-22. If strands are used, use a minimum of six ½"Ø strands through each joint placed at each outside corner and center wall on the double cell and four ½"Ø double strands on the single cell. Protect prestressing cables against corrosion and grout their ends. If tie bolts are used, the joints will require two ties per exterior wall located at the third points of the wall clear height.

The "DBL 12FT X 11FT PRECAST RCB END SECTION" bid item consists of the apron, cutoff wall, parapet, and wingwalls. Attach the apron to the last barrel sections, the wingwalls, and the cutoff wall. Attach the wingwalls to the last barrel section. Use a welded tie type system to connect the apron to the box and the wingwalls unless otherwise approved by the Engineer. Connect the wingwalls to the last barrel section by the use of tie bolts, steel-bolted plates, or another approved method so the inside corner surface is smooth. After backfilling, wingwall sections are to be in line. If the wingwall sections are not in line or not installed to the angles shown in the plans, remove and reset the wingwalls to be in proper alignment.

All bolts, plates, angles, and studs are to meet ASTM A36. Nuts are to be a heavy hex in conformance with ASTM A563 and washers shall be ASTM F436, Type 1. Welded pipe sleeves are to conform to ASTM A53, Grade B. Welders are required to be properly certified for all shop and field welds. Coat all field welds with galvanizing paint. Galvanize all hardware according to AASHTO M 232. Galvanize structural steel after fabrication according to AASHTO M 111.

Install five ¾"Ø threaded inserts and steel eye bolts (20 total) along top and end faces of each wingwall to provide anchorage for fencing. A 3"x3"x¾" hot dipped galvanized angle, as shown in Section 170 sheet 6 of the plans, is to also be included at each wingwall. Anchorage locations and specifications are to be shown on the shop drawings for approval by the Engineer. All costs associated with the threaded inserts, steel eye bolts, and galvanized angles are to be included in the price bid for "DBL 12FT X 11FT PRECAST RCB END SECTION."

Cast holes at 3'-0" centers through the apron and into the cutoff wall to receive ¾"Ø reinforcing bars. Cast holes in the last barrel section at 1'-0" centers for ½"Ø reinforcing bars to attach the parapet. Cast the parapet against the section. Install the bars according to the manufacturer's recommendation, with a high strength adhesive specifically intended for concrete anchorage, in accordance with Section 806.02 of the NDDOT Standard Specifications.

The distance between separate precast units is to be a minimum of 3" and a maximum of 1'-0". Fill this gap with controlled density backfill. The controlled density backfill is to be a blend of cement, water, pozzolanic materials, and fillers. The material must be able to support normal loads after 6 hours and have a compressive strength in the range of 75 psi to 125 psi at 28 days. If the mix design shown is used, no further testing will be required. The mix design yields approximately one cubic yard of flowable mortar.

MIX DESIGN

Cement	100 lbs
Fly Ash	300 lbs
Fine Aggregate	2600 lbs
Water	70 gals

The 12" cap consists of a weatherproof and freeze/thaw resistant material such as Sikagrout[®]212, BASF Masterflow[®]928, Euclid NS Grout, or an approved equal which complies with ASTM C1107.

Controlled density backfill will not be measured separately but is included in the price bid for "DBL 12FT X 11FT PRECAST RCB CULVERT".

DESIGN LOADS:

- A. HL-93 Loading
- B. Maximum Fill Height = 3'

WORK DRAWINGS: The contractor shall submit the following work drawings to the Engineer of Record:

PRECAST RCB CULVERT

This document was originally issued and sealed by
Colin A. Moran,
Registration Number
PE- 5344,
on 06/06/16 and the original document is stored at the
Office of KLJ
Fargo, North Dakota.

SC-2730(061)




MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-132-29.1



STRUCTURAL NOTES

DRAWN BY DMW	CHECKED BY CLT	PROJECT NO. 14314102
-----------------	-------------------	-------------------------

Revised 06/06/16	STATE	PROJECT NUMBER	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	170	7



STRUCTURAL QUANTITIES ONLY

SPEC	CODE	ITEM DESCRIPTION	UNIT	QUANTITY
202	0110	REMOVAL OF STRUCTURE - SITE 3	L SUM	1
210	0053	BOX CULVERT EXCAVATION - SITE 3	EA	1
210	0204	FOUNDATION PREPARATION - SITE 3	L SUM	1
210	0210	FOUNDATION FILL	CY	552
256	0200	RIPRAP GRADE II	CY	137
606	1311	13 FT X 11FT PRECAST RCB CULVERT	LF	64
606	3311	DBL 13FT X 11FT PRECASE RCB CULVERT	LF	64
606	7311	DBL 13FT X 11FT PRECAST RCB END SECTION	EA	2
709	0151	GEOSYNTHETIC MATERIAL TYPE R1	SY	546
709	0155	GEOSYNTHETIC MATERIAL TYPE RR	SY	273

HYDRAULIC DATA:

Drainage Area	86.6	sq mi
Stream Gradient	0.0013	ft/ft
Design Frequency	25	yr
Design Discharge	2,296	cfs
Design Headwater Stage	2,097.6	ft
Design Tailwater Stage	2,096.6	ft
Velocity Through Culvert	7.0	fps
100-Year Frequency Discharge	3,941	cfs
100-Year Frequency Headwater	2,100.0	ft
Overtopping Stage	2,101.3	ft
Overtopping Discharge	4,552	cfs

This document was originally issued and sealed by
 Colin A. Moran,
 Registration Number
 PE- 5344,
 on 06/06/16 and the original document is stored at the
 Office of KLJ
 Fargo, North Dakota.

For a single barrel box culvert with 10" thick roof, 10" floor, and 9" walls, the following total factored moments and shears would result from the application of the required loads:

FACTORED DESIGN MOMENTS (SINGLE)		FACTORED DESIGN SHEARS (SINGLE)	
WALL MOMENT	1,336 ft-lbs	WALL SHEAR	4,552 lbs
ROOF MOMENTS		ROOF SHEARS	
CORNER	-16,855 ft-lbs	CORNER	10,240 lbs
BOTTOM	33,165 ft-lbs		
FLOOR MOMENTS		FLOOR SHEARS	
CORNER	-19,943 ft-lbs	CORNER	13,407 lbs
TOP	31,576 ft-lbs		

For a double barrel box culvert with 10" thick roof, 10" floor, and 9" walls, the following total factored moments and shears would result from the application of the required loads:

FACTORED DESIGN MOMENTS (DOUBLE)		FACTORED DESIGN SHEARS (DOUBLE)	
WALL MOMENT	3,179 ft-lbs	WALL SHEAR	4,386 lbs
ROOF MOMENTS		ROOF SHEARS	
CORNER	-15,119 ft-lbs	CORNER	8,513 lbs
BOTTOM	28,310 ft-lbs	WALL	11,966 lbs
TOP	-38,713 ft-lbs	FLOOR SHEARS	
FLOOR MOMENTS		CORNER	11,156 lbs
CORNER	-16,269 ft-lbs	WALL	14,910 lbs
TOP	22,659 ft-lbs		
BOTTOM	-41,918 ft-lbs		

NOTE:
 The invert elevations shown represent an elevation 1 foot below the existing streambed.

SC-2730(061)
 MCKENZIE COUNTY, NORTH DAKOTA
 STRUCTURE #27-134-27.0

PRECAST BOX CULVERT LAYOUT

DRAWN BY DMW	CHECKED BY CLT	PROJECT NO. 14314102
-----------------	-------------------	-------------------------

STRUCTURAL NOTES

Revised 06/06/16	STATE	PROJECT NUMBER	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	170	8

100-P01 SCOPE OF WORK: Work at this site consists of removing the existing structure, a 68' long bridge and replacing it with a new triple barrel 13' x 11' x 64' precast concrete box culvert.

202-P01 REMOVAL OF STRUCTURE: The existing structure is a single span concrete bridge, 68' long with a clear roadway width of 28'. The abutments are concrete. Refer to Section 6, sheet 2 and SP-4(14) for allowable removal dates for the structure.

The lump sum bid item "REMOVAL OF STRUCTURE - SITE 3" includes all work required to remove all bridge components and any hazard markers at the location in accordance with the Standard Specifications. All removed materials are the property of the contractor and are to be disposed of properly off the right-of-way.

The Contractor will complete and submit SFN 17987 Asbestos Notification of Demolition and Renovation to the North Dakota Department of Health 10 days prior to beginning the removal of concrete. Tom Naas (ND License #5302) of KLJ (4585 Coleman Street, Bismarck, ND 58503-0431; 701-355-8400) completed an asbestos inspection of the existing structure on January 15, 2015. Based on laboratory analysis of bulk samples from the site, no building or structure materials were determined to contain asbestos. No other inaccessible and/or assumed ACMs were identified.

210-P01 BOX CULVERT EXCAVATION: The unit price bid for "BOX CULVERT EXCAVATION - SITE 3" includes all excavation required to build the box culvert. Perform Box Culvert Excavation according to Section 210 of the Standard Specifications. The unit price bid for "BOX CULVERT EXCAVATION - SITE 3" includes all labor and materials required to place the ordinary backfill within the limits shown on Section 170, Sheet 9.

The suitability of material from on-site excavations for use as ordinary backfill will be determined by the engineer. Embankment constructed from channel excavated material will not be measured for separate payment but will be included in the price bid for "BOX CULVERT EXCAVATION - SITE 3". Channel excavated material that is deemed not suitable for ordinary backfill will become property of the contractor and disposed of outside of the road right-of-way, not adjacent to the construction site, and at a site approved by the engineer. The unit price bid for "BOX CULVERT EXCAVATION - SITE 3" includes all costs associated with excavation, hauling, depositing and leveling the waste material.

210-P02 FOUNDATION PREPARATION: Be aware of the possible inundated conditions at this site before the bid opening. The cost of any cofferdams and dewatering the excavation is included in the bid for "FOUNDATION PREPARATION - SITE 3".

210-P03 FOUNDATION FILL: Use CL 5 as specified in Section 816, "Aggregates". Place foundation fill in layers of not more than six inches, moisten or dry as required, and thoroughly compact with mechanical tamping equipment.

When additional Foundation Fill is placed under the box, payment will be determined by computation using plan dimensions and adding 25% for shrinkage.

256-P01 RIPRAP GRADE II: Do not use broken concrete as riprap.

606-P01 PRECAST REINFORCED CONCRETE BOX CULVERT AND END SECTIONS: Tie all barrel sections together with prestressing strands or 1"Ø tie bolts as shown on Standard Drawing D-714-22. If strands are used, use a minimum of six ½"Ø strands through each joint placed at each outside corner and center wall on the double cell and four ½"Ø strands on the single cell. Protect prestressing cables against corrosion and grout their ends. If tie bolts are used, the joints will require two ties per exterior wall located at the third points of the wall clear height.

The "DBL13FT X 11FT PRECAST RCB END SECTION" bid item consists of the apron, cutoff wall, parapet, and wingwalls. Attach the apron to the last barrel sections, the wingwalls, and the cutoff wall. Attach the wingwalls to the last barrel section. Use a welded tie type system to connect the apron to the box and the wingwalls unless otherwise approved by the Engineer. Connect the wingwalls to the last barrel section by the use of tie bolts, steel-bolted plates, or another approved method so the inside corner surface is smooth. After backfilling, wingwall sections are to be in line. If the wingwall sections are not in line or not installed to the angles shown in the plans, remove and reset the wingwalls to be in proper alignment.

All bolts, plates, angles, and studs are to meet ASTM A36. Nuts are to be a heavy hex in conformance with ASTM A563 and washers shall be ASTM F436, Type 1. Welded pipe sleeves are to conform to ASTM A53, Grade B. Welders are required to be properly certified for all shop and field welds. Coat all field welds with galvanizing paint. Galvanize all hardware according to AASHTO M 232. Galvanize structural steel after fabrication according to AASHTO M 111.

Install five ¾"Ø threaded inserts and steel eye bolts (20 total) along top and end faces of each wingwall to provide anchorage for fencing. A 3"x3"x¾" hot dipped galvanized angle, as shown in Section 170 sheet 9 of the plans, is to also be included at each wingwall. Anchorage locations and specifications are to be shown on the shop drawings for approval by the Engineer. All costs associated with the threaded inserts, steel eye bolts, and galvanized angles are to be included in the price bid for "DBL 13FT X 11FT PRECAST RCB END SECTION."

Cast holes at 3'-0" centers through the apron and into the cutoff wall to receive ¾"Ø reinforcing bars. Cast holes in the last barrel section at 1'-0" centers for ½"Ø reinforcing bars to attach the parapet. Cast the parapet against the section. Install the bars according to the manufacturer's recommendation, with a high strength adhesive specifically intended for concrete anchorage, in accordance with Section 806.02 of the NDDOT Standard Specifications.

The distance between separate precast units is to be a minimum of 3" and a maximum of 1'-0". Fill this gap with controlled density backfill. The controlled density backfill is to be a blend of cement, water, pozzolanic materials, and fillers. The material must be able to support normal loads after 6 hours and have a compressive strength in the range of 75 psi to 125 psi at 28 days. If the mix design shown is used, no further testing will be required. The mix design yields approximately one cubic yard of flowable mortar.

MIX DESIGN

Cement	100 lbs
Fly Ash	300 lbs
Fine Aggregate	2600 lbs
Water	70 gals

The 12" cap consists of a weatherproof and freeze/thaw resistant material such as Sikagrout[®]212, BASF Masterflow[®]928, Euclid NS Grout, or an approved equal which complies with ASTM C1107.

Controlled density backfill will not be measured separately but is included in the price bid for "DBL 13FT X 11FT PRECAST RCB CULVERT".

DESIGN LOADS:

- A. HL-93 Loading
- B. Maximum Fill Height = 4'

WORK DRAWINGS: The contractor shall submit the following work drawings to the Engineer of Record:

PRECAST RCB CULVERT

This document was originally issued and sealed by
Colin A. Moran,
Registration Number
PE- 5344,
on 06/06/16 and the original document is stored at the
Office of KLJ
Fargo, North Dakota.

SC-2730(061)


MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-134-27.0




STRUCTURAL NOTES

DRAWN BY DMW	CHECKED BY CLT	PROJECT NO. 14314102
-----------------	-------------------	-------------------------


Revised 06/06/16	STATE	PROJECT NUMBER	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	170	10




PLAN



ELEVATION



END VIEW
(Showing Dimensions)



END VIEW
(Showing Finished Section)

STRUCTURAL QUANTITIES ONLY

SPEC	CODE	ITEM DESCRIPTION	UNIT	QUANTITY
202	0269	REMOVAL OF STRUCTURE-SITE 4	L SUM	1
210	0054	BOX CULVERT EXCAVATION- SITE 4	EA	1
210	0205	FOUNDATION PREPARATION- SITE 4	L SUM	1
210	0210	FOUNDATION FILL	CY	734
256	0200	RIPRAP GRADE II	CY	62
606	1108	11FT X 8FT PRECAST RCB CULVERT	LF	110
606	3108	DBL 11FT X 8FT PRECAST RCB CULVERT	LF	110
606	7108	DBL 11FT X 8FT PRECAST RCB END SECTION	EA	2
709	0151	GEOSYNTHETIC MATERIAL TYPE R1	SY	860
709	0155	GEOSYNTHETIC MATERIAL TYPE RR	SY	124

HYDRAULIC DATA:

Drainage Area	32.4	sq mi
Stream Gradient	0.0025	ft/ft
Design Frequency	25	yr
Design Discharge	1,353	cfs
Design Headwater Stage	2,121.9	ft
Design Tailwater Stage	2,120.2	ft
Velocity Through Culvert	6.3	fps
100-Year Frequency Discharge	2,289	cfs
100-Year Frequency Headwater	2,124.1	ft
Overtopping Stage	2,130.2	ft
Overtopping Discharge	3,763	cfs

This document was originally issued and sealed by
Colin A. Moran,
Registration Number
PE- 5344,
on 06/06/16 and the original document is stored at the
Office of KLJ
Fargo, North Dakota.

For a single barrel box culvert with 9" thick roof, 9" floor, and 8" walls, the following total factored moments and shears would result from the application of the required loads:


FACTORED DESIGN MOMENTS (SINGLE)		FACTORED DESIGN SHEARS (SINGLE)	
WALL MOMENT	5,543 ft-lbs	WALL SHEAR	3,833 lbs
ROOF MOMENTS		ROOF SHEARS	
CORNER	-14,287 ft-lbs	CORNER	9,830 lbs
BOTTOM	24,105 ft-lbs		
FLOOR MOMENTS		FLOOR SHEARS	
CORNER	-16,000 ft-lbs	CORNER	12,754 lbs
TOP	25,608 ft-lbs		

For a double barrel box culvert with 9" thick roof, 9" floor, and 8" walls, the following total factored moments and shears would result from the application of the required loads:

FACTORED DESIGN MOMENTS (DOUBLE)		FACTORED DESIGN SHEARS (DOUBLE)	
WALL MOMENT	2,273 ft-lbs	WALL SHEAR	3,712 lbs
ROOF MOMENTS		ROOF SHEARS	
CORNER	-11,731 ft-lbs	CORNER	8,039 lbs
BOTTOM	17,671 ft-lbs	WALL	11,620 lbs
TOP	-32,620 ft-lbs	FLOOR SHEARS	
FLOOR MOMENTS		CORNER	10,614 lbs
CORNER	-12,394 ft-lbs	WALL	14,393 lbs
TOP	17,867 ft-lbs		
BOTTOM	-34,441 ft-lbs		

NOTE:
The invert elevations shown represent an elevation 1 foot below the existing streambed.

SC-2730(061)
MCKENZIE COUNTY, NORTH DAKOTA
STRUCTURE #27-136-27.0



PRECAST BOX CULVERT LAYOUT

DRAWN BY: DMW
CHECKED BY: CLT
PROJECT NO.: 14314102

STRUCTURAL NOTES

Revised 06/06/16	STATE	PROJECT NUMBER	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	170	11

100-P01 SCOPE OF WORK: Work at this site consists of removing the existing structures, two-10'Ø corrugated steel pipes and replacing them with a new triple barrel 11' x 8' x 110' precast concrete box culvert.

202-P01 REMOVAL OF STRUCTURE: The existing structures are two steel corrugated pipes spaced approximately 28' on center, and a roadway width of 24'. Refer to Section 6, sheet 2 and SP-4(14) for allowable removal dates for the structures.

The lump sum bid item "REMOVAL OF STRUCTURE - SITE 4" includes all work required to remove all drainage pipe components and any hazard markers at the location in accordance with the Standard Specifications. All removed materials are the property of the contractor and are to be disposed of properly, off the right-of-way.

210-P01 BOX CULVERT EXCAVATION: The unit price bid for "BOX CULVERT EXCAVATION - SITE 4" includes all excavation required to build the box culvert. Perform Box Culvert Excavation according to Section 210 of the Standard Specifications. The unit price bid for "BOX CULVERT EXCAVATION - SITE 4" includes all labor and materials required to place the ordinary backfill within the limits shown on Section 170, Sheet 12.

The suitability of material from on-site excavations for use as ordinary backfill will be determined by the engineer. Embankment constructed from channel excavated material will not be measured for separate payment but will be included in the price bid for "BOX CULVERT EXCAVATION - SITE 4". Channel excavated material that is deemed not suitable for ordinary backfill will become property of the contractor and disposed of outside of the road right-of-way, not adjacent to the construction site, and at a site approved by the engineer. The unit price bid for "BOX CULVERT EXCAVATION - SITE 4" includes all costs associated with excavation, hauling, depositing and leveling the waste material.

210-P02 FOUNDATION PREPARATION: Be aware of the possible inundated conditions at this site before the bid opening. The cost of any cofferdams and dewatering the excavation is included in the bid for "FOUNDATION PREPARATION - SITE 4".

210-P03 FOUNDATION FILL: Use CL 5 as specified in Section 816, "Aggregates". Place foundation fill in layers of not more than six inches, moisten or dry as required, and thoroughly compact with mechanical tamping equipment.

When additional Foundation Fill is placed under the box, payment will be determined by computation using plan dimensions and adding 25% for shrinkage.

256-P01 RIPRAP GRADE II: Do not use broken concrete as riprap.

606-P01 PRECAST REINFORCED CONCRETE BOX CULVERT AND END SECTIONS: Tie all barrel sections together with prestressing strands or 1"Ø tie bolts as shown on Standard Drawing D-714-22. If strands are used, use a minimum of six ½"Ø strands through each joint placed at each outside corner and center wall on the double cell and four ½"Ø strands on the single cell. Protect prestressing cables against corrosion and grout their ends. If tie bolts are used, the joints will require two ties per exterior wall located at the third points of the wall clear height.

The "DBL11FT X 8FT PRECAST RCB END SECTION" bid item consists of the apron, cutoff wall, parapet, and wingwalls. Attach the apron to the last barrel sections, the wingwalls, and the cutoff wall. Attach the wingwalls to the last barrel section. Use a welded tie type system to connect the apron to the box and the wingwalls unless otherwise approved by the Engineer. Connect the wingwalls to the last barrel section by the use of tie bolts, steel-bolted plates, or another approved method so the inside corner surface is smooth. After backfilling, wingwall sections are to be in line. If the wingwall sections are not in line or not installed to the angles shown in the plans, remove and reset the wingwalls to be in proper alignment.

All bolts, plates, angles, and studs are to meet ASTM A36. Nuts are to be a heavy hex in conformance with ASTM A563 and washers shall be ASTM F436, Type 1. Welded pipe sleeves are to conform to ASTM A53, Grade B. Welders are required to be properly certified for all shop and field welds. Coat all field welds with galvanizing paint. Galvanize all hardware according to AASHTO M 232. Galvanize structural steel after fabrication according to AASHTO M 111.

Install five ¾"Ø threaded inserts and steel eye bolts (20 total) along top and end faces of each wingwall to provide anchorage for fencing. A 3"x3"x¾" hot dipped galvanized angle, as shown in Section 170 sheet 12 of the plans, is to also be included at each wingwall. Anchorage locations and specifications are to be shown on the shop drawings for approval by the Engineer. All costs associated with the threaded inserts, steel eye bolts, and galvanized angles are to be included in the price bid for "DBL 11FT X 8FT PRECAST RCB END SECTION."

Cast holes at 3'-0" centers through the apron and into the cutoff wall to receive ¾"Ø reinforcing bars. Cast holes in the last barrel section at 1'-0" centers for ½"Ø reinforcing bars to attach the parapet. Cast the parapet against the section. Install the bars according to the manufacturer's recommendation, with a high strength adhesive specifically intended for concrete anchorage, in accordance with Section 806.02 of the NDDOT Standard Specifications.

The distance between separate precast units is to be a minimum of 3" and a maximum of 1'-0". Fill this gap with controlled density backfill. The controlled density backfill is to be a blend of cement, water, pozzolanic materials, and fillers. The material must be able to support normal loads after 6 hours and have a compressive strength in the range of 75 psi to 125 psi at 28 days. If the mix design shown is used, no further testing will be required. The mix design yields approximately one cubic yard of flowable mortar.

MIX DESIGN

Cement	100 lbs
Fly Ash	300 lbs
Fine Aggregate	2600 lbs
Water	70 gals

The 12" cap consists of a weatherproof and freeze/thaw resistant material such as Sikagrout[®]212, BASF Masterflow[®]928, Euclid NS Grout, or an approved equal which complies with ASTM C1107.

Controlled density backfill will not be measured separately but is included in the price bid for "DBL11FT X 8FT PRECAST RCB CULVERT".


DESIGN LOADS:

- A. HL-93 Loading
- B. Maximum Fill Height = 9'

WORK DRAWINGS: The contractor shall submit the following work drawings to the Engineer of Record:


PRECAST RCB CULVERT

This document was originally issued and sealed by
Colin A. Moran,
Registration Number
PE- 5344,
on 06/06/16 and the original document is stored at the
Office of KLJ
Fargo, North Dakota.

SC-2730(061) <small>MCKENZIE COUNTY, NORTH DAKOTA STRUCTURE #27-136-27.0</small>		
	STRUCTURAL NOTES	
DRAWN BY DMW	CHECKED BY CLT	PROJECT NO. 14314102


Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	1

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	2

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	3

Co Rt 30 - Chain EXE30



Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	4

Co Rt 30 - Chain EXE30




Revised 06/22/16

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SC-2730(061)	200	5


Co Rt 30 - Chain EXE30

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	6

Co Rt 30 - Chain EXE30




Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	8

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	9

Co Rt 30 - Chain EXE30



Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	10


Co Rt 30 - Chain EXE30



Revised 06/22/16


STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SC-2730(061)	200	11

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	12

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	13

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	14

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	15

Co Rt 30 - Chain EXE30



Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	16

Co Rt 30 - Chain EXE30



Revised 06/22/16

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND


SC-2730(061)

200

17

Co Rt 30 - Chain EXE30


140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



Revised 06/22/16


STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SC-2730(061)	200	18

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	19

Co Rt 30 - Chain EXE30



Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	20

Co Rt 30 - Chain EXE30



Revised 06/22/16


STATE
ND

PROJECT NO.
SC-2730(061)

SECTION NO.
200


SHEET NO.
21

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	22

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	23

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	24

Co Rt 30 - Chain EXE30



Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	25

Co Rt 30 - Chain EXE30



Revised 06/22/16


STATE
ND

PROJECT NO.
SC-2730(061)

SECTION NO.
200


SHEET NO.
26

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	27

Co Rt 30 - Chain EXE30




Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	28

Co Rt 30 - Chain EXE30



Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	29

Co Rt 30 - Chain EXE30



Revised 06/22/16

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND


SC-2730(061)

200

30

Co Rt 30 - Chain EXE30

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



Revised 06/22/16	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	31

Co Rt 30 - Chain EXE30

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

2140

2140


2130

2130

1276+50.00

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

Temporary Bypass 131 - Chain PRBP131



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)


200

33

Temporary Bypass 131 - Chain PRBP131



Temporary Bypass 131 - Chain PRBP131



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)

200

35

Temporary Bypass 131 - Chain PRBP131



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)


200

36

Temporary Bypass 131 - Chain PRBP131



Temporary Bypass 131 - Chain PRBP131



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND

SC-2730(061)

200

38

Temporary Bypass 131 - Chain PRBP131

90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160 170 180 190 200

2140

2140

2150

2150

2140

2140

4007+00.00

4006+75.00

Welland Damaged

Welland Damaged

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

2137.41

Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND

SC-2730(061)

200

39

Temporary Bypass 132 - Chain PRBP132

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

2130

2130

2130

2130

2130

2130

2130

2130

5001+00.00

5000+75.00

5000+50.00

5000+25.00

Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND

SC-2730(061)

200

40

Temporary Bypass 132 - Chain PRBP132

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

2130

2130

2130

2130

2130

2130

2130

2130

5002+00.00

5001+75.00

5001+50.00

5001+25.00

Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND


SC-2730(061)

200

41

Temporary Bypass 132 - Chain PRBP132

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



2130

2130

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)

200

42

Temporary Bypass 132 - Chain PRBP132



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)

200

43

Temporary Bypass 132 - Chain PRBP132



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND

SC-2730(061)

200

44

Temporary Bypass 132 - Chain PRBP132

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

2140

2140

2130

2130

2140

2140

2130

2130


2140

2140

2130

2130

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND


SC-2730(061)

200

45

Temporary Bypass 132 - Chain PRBP132

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND

SC-2730(061)

200

46

Temporary Bypass 134 - Chain PRBP134

190 180 170 160 150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100

2110

2100

2110

2100

2110

2100

2110

2100

2110

2100

2110

2100

6001+00.00

6000+75.00

6000+50.00

2102.30
12.33
4.1
2102.51
7.00
2.1%

2102.51
7.00
2.1%

2102.51
7.00
2.1%

2102.51
7.00
2.1%

2102.51
7.00
2.1%

2102.51
7.00
2.1%

2102.51
7.00
2.1%

2102.51
7.00
2.1%

2102.51
7.00
2.1%

2102.51
7.00
2.1%

2103.20
2.2
2.1%

2103.09
2.28
4.1

2101.10
14.98

2101.10
14.98

2101.10
14.98

2101.10
14.98

2101.10
14.98

2101.10
14.98


2101.10
14.98

2101.10
14.98

2101.10
14.98

Temporary Bypass 134 - Chain PRBP134

Revised 06/22/2016	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SC-2730(061)	200	47



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND

SC-2730(061)

200

48

Temporary Bypass 134 - Chain PRBP134

190 180 170 160 150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100

2110

2110

2100

2100

2110

2110

2100

2100

2110

2110

2100

2100

6002+50.00

6002+25.00

6002+00.00

Wetland Delineated

Wetland Delineated

Wetland Delineated

Wetland Delineated

2097.76
15.08
2097.81
14.40
2097.76
14.40
2097.81
14.40
2097.87
14.40

2097.40
10.00
2098.00
17.20
2098.74
14.40
2098.00
17.20
2098.30
10.00

2097.57
15.08
2098.58
17.20
2098.79
14.40
2098.58
17.20
2097.88
14.40

Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND


SC-2730(061)

200

49

Temporary Bypass 134 - Chain PRBP134

190 180 170 160 150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)

200

50

Temporary Bypass 134 - Chain PRBP134



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND


SC-2730(061)

200

51

Temporary Bypass 134 - Chain PRBP134

190 180 170 160 150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)

200

52

Temporary Bypass 134 - Chain PRBP134



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)

200


53

Temporary Bypass 134 - Chain PRBP134



Temporary Bypass 136 - Chain PRBP136

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND


SC-2730(061)

200

55

Temporary Bypass 136 - Chain PRBP136

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)

200

56

Temporary Bypass 136 - Chain PRBP136



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)

200

57

Temporary Bypass 136 - Chain PRBP136



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.


ND

SC-2730(061)

200

58

Temporary Bypass 136 - Chain PRBP136



Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND

SC-2730(061)

200

59

Temporary Bypass 136 - Chain PRBP136

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

2130

2130

2130

2130

2130

2130

2130

2130

7007+00.00

7006+75.00

7006+50.00

7006+25.00

Revised 06/22/2016

STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND

SC-2730(061)

200

60

Temporary Bypass 136 - Chain PRBP136

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

2130

2130

7007+75.00

2130

2130

7007+50.00

2130

2130

7007+25.00

140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150