

NEDO-21159-2  
77NED140  
CLASS I  
OCTOBER 1978

**AIRBORNE RELEASES  
FROM BWR'S FOR  
ENVIRONMENTAL IMPACT  
EVALUATIONS  
AMENDMENT 2 (IODINE-131)**

T. R. MARRERO

ALL  
THIS DOCUMENT CONTAINS  
POOR QUALITY PAGES

7812290172

GENERAL  ELECTRIC

NEDO-21159-2  
77NED140  
Class I  
October 1978

AIRBORNE RELEASES FROM BWR'S  
FOR ENVIRONMENTAL IMPACT EVALUATIONS  
AMENDMENT 2 (IODINE-131)

T. R. Marrero

Reviewed. *N. R. Horton*  
N. R. Horton, Manager  
Radiological Analysis

Approved *C. D. Wilkinson*  
C. D. Wilkinson, Manager  
Chemical & Radiological Engineering

NUCLEAR ENERGY ENGINEERING DIVISION • GENERAL ELECTRIC COMPANY  
SAN JOSE, CALIFORNIA 95125

GENERAL  ELECTRIC

### DISCLAIMER OF RESPONSIBILITY

*This document was prepared by or for the General Electric Company. Neither the General Electric Company nor any of the contributors to this document*

- A. Makes any warranty or representation, express or implied, with respect to the accuracy, completeness or usefulness of the information contained in this document, or that the use of any information disclosed in this document may not infringe privately owned rights; or*
- B. Assumes any responsibility for liability or damage of any kind which may result from the use of any information disclosed in this document.*

## TABLE OF CONTENTS

	Page
ABSTRACT .....	xvii
1. INTRODUCTION .....	1-1
1.1 References .....	1-2
2. SUMMARY OF RESULTS .....	2-1
2.1 References .....	2-2
3. AIRBORNE IODINE-131 RELEASE DATA .....	3-1
3.1 Measurements by Utilities .....	3-1
3.1.1 Boston Edison Company (Pilgrim 1) .....	3-1
3.1.2 Commonwealth Edison Company (Dresden 2/3, Quad Cities 1/2) .....	3-1
3.1.2.1 Dresden 2/3 .....	3-1
3.1.2.2 Quad Cities 1/2 .....	3-1
3.1.3 Northern States Power Company (Monticello) .....	3-2
3.1.4 Philadelphia Electric Company (Peach Bottom 2/3) .....	3-2
3.2 Measurements by Electric Power Research Institute .....	3-2
3.3 Measurements by Nuclear Regulatory Commission .....	3-3
3.4 Measurements by General Electric .....	3-3
3.5 References .....	3-3
4. CHEMICAL FORM OF IODINE 131 RELEASES .....	4-1
4.1 References .....	4-3
5. IODINE 131 IN MILK .....	5-1
5.1 References .....	5-1
6. NORMALIZATION OF IODINE 131 RELEASES .....	6-1
6.1 Iodine 131 Carryover .....	6-1
6.2 Iodine 131 Reactor Water Concentrations .....	6-2
6.3 Fuel Performance .....	6-3
6.4 Normalized Release Rates of Iodine 131 .....	6-4
6.5 References .....	6-6
7. RESULTS .....	7-1
8. RECOMMENDATIONS .....	8-1
9. ACKNOWLEDGEMENTS .....	9-1

TABLE OF CONTENTS (Continued)

	Page
APPENDICES	
2A NRC COMMISSIONERS' OPINION ON 10CFR50 APPENDIX 1 (APRIL 30, 1975) SELECTED QUOTATIONS	2A 1
2B IODINE 131 SPECIES MEASUREMENTS OF IN PLANT EQUIPMENT COMPARTMENTS AND SJAЕ DELAY PIPE EXHAUST	2B 1
2C SUMMARY OF IODINE 131 REACTOR WATER CONCENTRATIONS IN BWRS (1975 TO 1977), AVERAGE ANNUAL VALUES	2C 1
2D SUMMARY OF DATA AVAILABLE FOR IODINE 131 VENTILATION RELEASES AT BROWNS FERRY DURING 1977	2D 1

## LIST OF ILLUSTRATIONS

Figure	Title	Page
2 1	Long-Term Trend Analysis of Cumulative Iodine-131 Airborne Releases from BWR Ventilation Exhausts. . . . .	2-7
3-1	Calendar Quarterly Total Plant Ventilation Releases of I-131 versus Time, Pilgrim 1 (Reactor, Turbine and Radwaste Buildings). . . . .	3-33
3 2	Accumulative Probability Distribution of Calendar Quarter I-131 Ventilation Releases, Pilgrim 1 (Reactor, Turbine and Radwaste Buildings, October 1974 to December 1976). . . . .	3-34
3-3	Calendar Quarter Reactor Building Ventilation Release of I-131 Versus Time, Dresden 2/3 . . . . .	3-35
3-4	Accumulative Normal Probability Distribution of Calendar Quarter Reactor Building Ventilation Releases of I-131, Dresden 2/3 (January 1973 to December 1976). . . . .	3-36
3-5	Calendar Quarter Reactor Building Ventilation Release of I-131 versus Time, Quad Cities 1/2. . . . .	3-37
3-6	Accumulative Normal Probability Distribution of Calendar Quarter Reactor Ventilation Releases of I-131, Quad Cities 1/2 (July 1973 to June 1977). . . . .	3-38
3-7	Calendar Quarter Total Plant Ventilation Release of I-131 Versus Time, Monticello (Reactor, Turbine and Radwaste Buildings). . . . .	3-39
3 8	Accumulative Lognormal Probability Distribution of Calendar Quarter I 131 Total Plant Ventilation Releases, Monticello (Reactor, Turbine and Radwaste Buildings, January 1974 to December 1976). . . . .	3-40
5 1	Empirical Correlation of I-131 Acitivity in Milk as Produced in Environs of BWR's. . . . .	5-7
6 1	Normal Probability Distribution of Iodine-131 Carryover in BWR's. . . . .	6-25
6 2	Iodine-131 Reactor Water Concentration at Browns Ferry 1, 1977 . . . . .	6-26
6-3	Iodine-131 Reactor Water Concentration at Browns Ferry 2, 1977 . . . . .	6-27
6-4	Iodine-131 Reactor Water Concentration at Browns Ferry 3, 1977 . . . . .	6-28
6-5	Iodine-131 Reactor Water Concentration at Brunswick 1, 1977 . . . . .	6-29
6-6	Reactor Water Concentration at Brunswick 2, 1977. . . . .	6-30
6-7	Iodine-131 Reactor Water Concentration at Cooper, 1975. . . . .	6-31
6-7a	Iodine-131 Reactor Water Concentration at Cooper, 1976. . . . .	6-32

## LIST OF ILLUSTRATIONS (Continued)

Figure	Title	Page
6 7b	Iodine 131 Reactor Water Concentration at Cooper, 1977	6 33
6 8	Iodine 131 Reactor Water Concentration at Dresden 2, 1975	6 34
6 8a	Iodine 131 Reactor Water Concentration at Dresden 2, 1976	6 35
6 8b	Iodine 131 Reactor Water Concentration at Dresden 2, 1977	6 36
6 9	Iodine 131 Reactor Water Concentration at Dresden 3, 1975	6 37
6 9a	Iodine 131 Reactor Water Concentration at Dresden 3, 1976	6 38
6 9b	Iodine 131 Reactor Water Concentration at Dresden 3, 1977	6 39
6 10	Iodine 131 Reactor Water Concentration at Duane Arnold, 1975	6 40
6 10a	Iodine 131 Reactor Water Concentration at Duane Arnold, 1976	6 41
6 10b	Iodine 131 Reactor Water Concentration at Duane Arnold, 1977	6 42
6 11	Iodine 131 Reactor Water Concentration at Fitzpatrick, 1977	6 43
6 12	Iodine 131 Reactor Water Concentration at Hatch 1, 1975	6 44
6 12a	Iodine 131 Reactor Water Concentration at Hatch 1, 1976	6 45
6 12b	Iodine 131 Reactor Water Concentration at Hatch 1, 1977	6 46
6 13	Iodine 131 Reactor Water Concentration at Millstone Point 1, 1975	6 47
6 14	Iodine 131 Reactor Water Concentration at Millstone Point 1, 1976	6 48
6 14a	Iodine 131 Reactor Water Concentration at Millstone Point 1, 1977	6 49
6 15	Iodine 131 Reactor Water Concentration at Monticello, 1974	6 50
6 16	Iodine 131 Reactor Water Concentration at Monticello, 1975	6 51
6 17	Iodine 131 Reactor Water Concentration at Monticello, 1976	6 52
6 17a	Iodine 131 Reactor Water Concentration at Monticello, 1977	6 53
6 18	Iodine 131 Reactor Water Concentration at Nine Mile Point 1, 1975	6 54
6 19	Iodine 131 Reactor Water Concentration at Nine Mile Point 1, 1976	6 55
6 19a	Iodine 131 Reactor Water Concentration at Nine Mile Point 1, 1977	6 56

## LIST OF ILLUSTRATIONS (Continued)

Figure	Title	Page
6-20	Iodine-131 Reactor Water Concentration at Oyster Creek, 1975. . . . .	6-57
6-21	Iodine-131 Reactor Water Concentration at Oyster Creek, 1976. . . . .	6-58
6-21a	Iodine-131 Reactor Water Concentration at Oyster Creek, 1977. . . . .	6-59
6-22	Iodine-131 Reactor Water Concentration at Peach Bottom 2, 1975. . . . .	6-60
6-23	Iodine-131 Reactor Water Concentration at Peach Bottom 2, 1976. . . . .	6-61
6-23a	Iodine-131 Reactor Water Concentration at Peach Bottom 2, 1977. . . . .	6-62
6-24	Iodine-131 Reactor Water Concentration at Peach Bottom 3, 1975. . . . .	6-63
6-25	Iodine-131 Reactor Water Concentration at Peach Bottom 3, 1976. . . . .	6-64
6-25a	Iodine-131 Reactor Water Concentration at Peach Bottom 3, 1977. . . . .	6-65
6-26	Iodine-131 Reactor Water Concentration at Pilgrim 1, 1975. . . . .	6-66
6-27	Iodine-131 Reactor Water Concentration at Pilgrim 1, 1976. . . . .	6-67
6-27a	Iodine-131 Reactor Water Concentration at Pilgrim 1, 1977. . . . .	6-68
6-28	Iodine-131 Reactor Water Concentration at Quad Cities 1, 1975. . . . .	6-69
6-29	Iodine-131 Reactor Water Concentration at Quad Cities 1, 1976. . . . .	6-70
6-29a	Iodine-131 Reactor Water Concentration at Quad Cities 1, 1977. . . . .	6-71
6-30	Iodine-131 Reactor Water Concentration at Quad Cities 2, 1975. . . . .	6-72
6-31	Iodine-131 Reactor Water Concentration at Quad Cities 2, 1976. . . . .	6-73
6-31a	Iodine-131 Reactor Water Concentration at Quad Cities 2, 1977. . . . .	6-74
6-32	Iodine-131 Reactor Water Concentration at Vermont Yankee, 1974. . . . .	6-75
6-33	Iodine-131 Reactor Water Concentration at Vermont Yankee, 1975. . . . .	6-76
6-34	Iodine-131 Reactor Water Concentration at Vermont Yankee, 1976. . . . .	6-77
6-34a	Iodine-131 Reactor Water Concentration at Vermont Yankee, 1977. . . . .	6-78
6-35	Normal Probability Distribution of Medians of Maximum Monthly I-131 Reactor Water Concentrations During 1975 and 1976 for 15 Domestic BWR's . . . . .	6-79
6-36	Variation of Median I-131 Reactor Water Concentration in Domestic BWR's for 1975 and 1976. . . . .	6-79
6-37	(Deleted) . . . . .	6-80



LIST OF ILLUSTRATIONS (Continued)

Figure	Title	Page
6-38	Normalized I-131 Release Rates, Reactor Building Ventilation Exhaust at Vermont Yankee (1974 and 1976) . . . . .	6-81
6-39	Normalized I-131 Release Rates, Reactor Building Ventilation Exhaust at Monticello (1974 and 1975) . . . . .	6-82
6-40	Normalized I-131 Release Rates, Reactor Building Ventilation Exhaust at Oyster Creek (1975 and 1976) . . . . .	6-83
6-41	Normalized I-131 Release Rates, Turbine Building Ventilation Exhaust at Vermont Yankee (1974 and 1975) . . . . .	6-84
6-42	Normalized I-131 Release Rates, Turbine Building Ventilation Exhaust at Monticello (1974 and 1975) . . . . .	6-85
6-43	Normalized I-131 Release Rates, Turbine Building Ventilation Exhaust at Oyster Creek (1975 and 1976) . . . . .	6-86
6-44	Normalized I-131 Release Rates, Radwaste Building Ventilation Exhaust at Vermont Yankee (1974 and 1975) . . . . .	6-87
6-45	Normalized I-131 Release Rates, Radwaste Building Ventilation Exhaust at Monticello (1974 and 1975) . . . . .	6-88
6-46	Normalized I-131 Release Rates, Radwaste Building Ventilation Exhaust at Oyster Creek (1975 and 1976) . . . . .	6-89
6-47	Bar Graph of Normalized I-131 Airborne Releases at Three BWRs for all Plant Operations . . . . .	6-90
6-48	Bar Graph of Normalized I-131 Airborne Releases at Three BWRs for Power Generation Operations . . . . .	6-91
6-49	Bar Graph of Normalized I-131 Airborne Releases at Three BWRs for One Refueling/Maintenance Outage . . . . .	6-92
6-50	Frequency Polygons of Normalized I-131 Airborne Release Rates From Reactor, Turbine and Radwaste Buildings at Vermont Yankee . . . . .	6-93
6-51	Frequency Polygons of Normalized I-131 Airborne Release Rates From Reactor, Turbine and Radwaste Buildings at Monticello . . . . .	6-94
6-52	Frequency Polygons of Normalized I-131 Airborne Release Rates From Reactor, Turbine and Radwaste Buildings at Oyster Creek . . . . .	6-95
6-53	Frequency Polygons of Normalized I-131 Turbine Building Airborne Release Rates Adjusted to I-131 Carryover of 1 Percent . . . . .	6-96

LIST OF ILLUSTRATIONS (Continued)

Figure	Title	Page
6-54	Normalized I-131 Turbine Building Airborne Release Rates and Reactor Power at Oyster Creek . . . . .	6-97
6-55	Cumulative Normalized I-131 Radwaste Building Airborne Release at Vermont Yankee . . . . .	6-98
6-56	Cumulative Normalized I-131 Turbine Building Airborne Release at Vermont Yankee . . . . .	6-99
6-57	Cumulative Normalized I-131 Radwaste Building Airborne Release at Vermont Yankee . . . . .	6-100
6-58	Cumulative Normalized I-131 Reactor Building Airborne Release at Monticello . . . . .	6-101
6-59	Cumulative Normalized I-131 Turbine Building Airborne Release at Monticello . . . . .	6-102
6-60	Cumulative Normalized I-131 Radwaste Building Airborne Release at Monticello . . . . .	6-103
6-61	Cumulative Normalized I-131 Reactor Building Airborne Release at Oyster Creek (1975 - 1976) . . . . .	6-104
6-62	Cumulative Normalized I-131 Reactor Building Airborne Release at Oyster Creek (1976) . . . . .	6-105
6-63	Cumulative Normalized I-131 Turbine Building Airborne Release at Oyster Creek (1975 - 1976) . . . . .	6-106
6-64	Cumulative Normalized I-131 Turbine Building Airborne Release at Oyster Creek (1976) . . . . .	6-107
6-65	Cumulative Normalized I-131 Radwaste Building Airborne Release at Oyster Creek (1976) . . . . .	6-108
6-66	Cumulative Normalized I-131 Radwaste Building Airborne Release at Oyster Creek (1976) . . . . .	6-109
6-67	Trend Analysis of Dresden 2/3 Iodine-131 Airborne Releases from Reactor Building Ventilation Exhaust . . . . .	6-110
6-68	Trend Analysis of Quad Cities 1/2 Iodine-131 Airborne Releases of Reactor Building Ventilation Exhaust . . . . .	6-111
6-69	Trend Analysis of Monticello Iodine-131 Airborne Releases from Reactor, Turbine and Radwaste Buildings . . . . .	6-112
6-70	Trend Analysis of Pilgrim 1 Iodine-131 Airborne Releases from Reactor, Turbine and Radwaste Buildings . . . . .	6-113

LIST OF ILLUSTRATIONS (Continued)

Figure	Title	Page
7-1	Correlation of I-131 Concentration in Reactor Water with Amount of Improved Fuel .....	7-7
7-2	Frequency Polygon of I-131 Reactor Water Concentrations in BWR's with 100% Improved Fuel .....	7-7
7-3	Cumulative Frequency Polygon and Ogive Curve of I-131 Reactor Water Concentrations in BWR's with 100% Improved Fuel. ....	7-8

## LIST OF TABLES

Table	Title	Page
2-1	Normalized Annual Airborne Releases of Elemental Iodine-131 for Environmental Impact Evaluations of BWR's . . . . .	2-3
2-2	Normalized Annual Airborne Releases of Elemental Iodine-131 According to Plant Operating Mode for Environmental Impact Evaluations of BWR's . . . . .	2-3
2-3	Normalized Annual Airborne Releases of Non-Elemental Iodine-131 Species for Power Generation Operations (300 Days), for Environmental Impact Evaluations of BWR's. . . . .	2-4
2-4	Normalized Annual Airborne Releases of Non-Elemental Iodine-131 Species for a Refueling/Maintenance Outage for Environmental Impact Evaluations of BWR's. . . . .	2-5
2-5	Correlation of Long-Term Trends in Actual I-131 Airborne Releases from BWR Ventilation Exhausts. . . . .	2-6
3-1	Iodine-131 Airborne Release Plant -- Pilgrim 1, Buildings -- Reactor, Turbine, and Radwaste. . . . .	3-7
3-2	Iodine-131 Airborne Release, Plants -- Dresden 2/3, Building -- Reactor . . . . .	3-8
3-3	Iodine-131 Airborne Release, Plants -- Quad Cities 1/2, Building -- Reactor . . . . .	3-9
3-4	Iodine-131 Airborne Release, Plant: Monticello, Buildings, Reactor, Turbine, and Radwaste. . . . .	3-10
3-5	Iodine-131 Airborne Release, Plant -- Peach Bottom 2, Buildings -- Reactor, Turbine and Radwaste. . . . .	3-10
3-6	Iodine-131 Airborne Release, Plant -- Peach Bottom 3, Buildings -- Reactor, Turbine. . . . .	3-10
3-7	Average I-131 Ventilation Release Rates, Plant -- Vermont Yankee, Data Source -- EPRI/NES. . . . .	3-11
3-8	Actual I-131 Ventilation Releases, Plant -- Vermont Yankee, Data Source -- EPRI/NES . . . . .	3-12
3-9	Iodine-131 Reactor Water Concentrations and Power Levels at Vermont Yankee, Data Source -- EPRI/NES. . . . .	3-13
3-10	Average I-131 Ventilation Release Rates, Plant -- Monticello, Data Source -- EPRI/NES. . . . .	3-14
3-11	Actual I-131 Ventilation Releases, Plant -- Monticello, Data Source -- EPRI/NES . . . . .	3-15

LIST OF TABLES (Continued)

Table	Title	Page
3-12	Iodine-131 Reactor Water Concentrations and Power Levels at Monticello, Data Source - EPRI/NES . . . . .	3-16
3-12a	Iodine-131 Reactor Water Concentrations at Monticello During Refueling/Maintenance Outages . . . . .	3-17
3-13	Average I-131 Ventilation Release Rates, Plant -- Oyster Creek (2/75 - 2/76), Data Source - EPRI/NES . . . . .	3-18
3-13a	Average I-131 Ventilation Release Rates, Plant -- Oyster Creek (6/76 - 11/76), Data Source - EPRI/NES . . . . .	3-19
3-14	Actual I-131 Ventilation Release, Plant -- Oyster Creek (2/75 - 2/76), Data Source - EPRI/NES . . . . .	3-20
3-14a	Actual I-131 Ventilation Releases, Plant -- Oyster Creek (6/76 - 11/76), Data Source - EPRI/NES . . . . .	3-21
3-15	Iodine-131 Reactor Water Concentrations and Power Levels at Oyster Creek (2/75 - 2/76), Data Source - EPRI/NES . . . . .	3-22
3-15a	Iodine-131 Reactor Water Concentrations and Power Levels at Oyster Creek (6/76 - 11/76), Data Source - EPRI/NES . . . . .	3-23
3-15b	Iodine-131 Reactor Water Concentrations at Oyster Creek During Refueling/Maintenance Outages . . . . .	3-24
3-16	Iodine-131 Reactor Water Concentration, Power Levels and Steam Flow Rates During Startup (After 75 Day Shutdown) at Oyster Creek Station, Data Source - EPRI/NES . . . . .	3-25
3-17	Iodine-131 Airborne Concentrations in Building Exhausts and Gland Seal Steam Exhaust During Startup (After 75 Day Shutdown) at Oyster Creek, Data Source - EPRI/NES . . . . .	3-28
3-18	Summary of Actual I-131 Ventilation Measurements by EPRI/NES at Vermont Yankee, Monticello and Oyster Creek . . . . .	3-29
3-19	Summary of Actual I-131 Ventilation Measurements by EPRI/NES at Vermont Yankee, Monticello and Oyster Creek Adjusted to 300 Days of Power Operations and 1% I-131 Carryover . . . . .	3-30
3-20	Summary of NRC Measurements of I-131 Releases at Six BWR's . . . . .	3-31
3-21	Summary of Airborne I-131 Releases, Measurements by General Electric Company . . . . .	3-32
4-1	Summary of Measurements of Iodine-131 Species in BWR Reactor Building Ventilation Exhausts . . . . .	4-4

LIST OF TABLES (Continued)

Table	Title	Page
4-2	Summary of Measurements of Iodine-131 Species in BWR Turbine Building Ventilation Exhausts . . . . .	4-7
4-3	Summary of Measurements of Iodine-131 Species in BWR Feedwater and Condensate Pump Room Exhausts at Oyster Creek . . . . .	4-9
4-4	Summary of Measurements of Iodine-131 Species in BWR Reheater Protection System and Lube Oil Storage Area Exhausts at Oyster Creek . . . . .	4-10
4-5	Summary of Measurements of Iodine-131 Species in BWR Radwaste Building Ventilation Exhausts . . . . .	4-11
4-6	Summary of Measurements of Iodine-131 Species in BWR Gland Seal Steam and Mechanical Vacuum Pump Exhausts . . . . .	4-13
4-7	Summary of Iodine-131 Species Measurements in BWR Ventilation Exhausts . . . . .	4-15
4-8	Recommended Relative Concentrations of Iodine-131 Species in BWR Ventilation Exhausts During Normal Power Generation Operations and Refueling/Maintenance Outages for Environmental Impact Evaluations . . . . .	4-16
4-9	Summary of Number of Iodine-131 Species Measurements . . . . .	4-17
5-1	Iodine-131 Activity in Milk in Environs of Monticello (During 1976) . . . . .	5-3
5-2	Iodine-131 Activity in Milk in Environs of Peach Bottom 2/3 (During 1976) . . . . .	5-4
5-3	Iodine-131 Activity in Milk in Environs of Quad Cities 1/2 (During 1975 and First Half of 1976) . . . . .	5-5
6-1	Summary of BWR Iodine-131 Carryover Values . . . . .	6-7
6-2	Arithmetic Mean of I-131 Reactor Water Concentrations for Domestic BWR's During 1975 . . . . .	6-8
6-2a	Arithmetic Mean of I-131 Reactor Water Concentrations for Domestic BWR's During 1976 . . . . .	6-9
6-2b	Arithmetic Mean of I-131 Reactor Water Concentrations for Domestic BWR's During 1977 . . . . .	6-10
6-3	Summary of Medians of Maximum Monthly I-131 Reactor Water Concentration at 15 Domestic BWR's . . . . .	6-11
6-4	Iodine-131 Reactor Water Concentrations at BWR's with High Amounts of Improved Fuel in the Reactors . . . . .	6-11
6-5	Iodine-131 Reactor Water Concentration Data for BWR's with 100% Improved Fuel . . . . .	6-12

LIST OF TABLES (Continued)

Table	Title	Page
6 6	Comparison of I-131 Reactor Water Concentrations and Fuel Burnups	6 15
6 7	Summary of BWR Fuel Types by Plant and Related Parameters	6 15
6 8	Normalized I-131 Airborne Release Rates at Vermont Yankee	6 16
6 9	Normalized I-131 Airborne Releases at Vermont Yankee	6 17
6 10	Normalized I-131 Airborne Release Rates at Monticello	6 18
6 11	Normalized I-131 Airborne Releases at Monticello	6 19
6 12	Normalized I-131 Airborne Release Rates at Oyster Creek (1976-1976)	6 20
6 12a	Normalized I-131 Airborne Release Rates at Oyster Creek (1976)	6 21
6 13	Normalized I-131 Airborne Release Rates at Oyster Creek (1974-1976)	6 22
6 13a	Normalized I-131 Airborne Release Rates at Oyster Creek (1976)	6 23
6 14	Summary by Plant of Normalized I-131 Releases at Vermont Yankee, Monticello and Oyster Creek for Power Generation Operations (300 Days) and One Refueling/Maintenance Outage	6 24
6 15	Normalized I-131 Turbine Building Release Adjusted to One Percent I-131 Carryover	6 24
7 1	Amounts of Iodine-131 Species in Airborne Releases of BWRs	7 3
7 2	Summary of Utility Measurements on I-131 Airborne Releases	7 3
7 3	Summary by Building of Normalized I-131 Releases at Vermont Yankee, Monticello and Oyster Creek for Power Generation Operations (300 Days) and One Refueling/Maintenance Outage	7 4
7 4	Comparison of Normalized I-131 Releases with EPRI/NES Results	7 5
7 5	Comparison of Normalized I-131 Releases with the Current NRC "Source Term"	7 5
7 6	Summary of Iodine-131 Ventilation Releases at Browns Ferry Site During 1977 - Normalized Results	7 6
B 1	I-131 Species - In-Plant Compartments/Reactor Building	2B 1
B 2	I-131 Species - In-Plant Compartments/Turbine Building (all Measurements Sponsored by EPRI, Conducted by NES)	2B 3
B 3	Summary of Measurements of Iodine-131 Chemical Form in BWR Steam Jet Air Ejector Delay Line	2B 5

LIST OF TABLES (Continued)

Table	Title	Page
C-1	Summary of Iodine 131 Reactor Water Concentration in BWR's (1975-1977). Average Annual Values . . . . .	2C-1
D-1	Summary of Actual Iodine 131 Ventilation Releases at Browns Ferry During 1977. . . . .	2D-1
D-2	Iodine-131 Vent Monitor Measurements at Browns Ferry 1 During 1977, Monitor 1 250 . . . . .	2D-2
D-3	Iodine-131 Vent Monitor Measurements at Browns Ferry 1 During 1977, Monitor 1 249 . . . . .	2D-3
D-4	Iodine-131 Vent Monitor Measurements at Browns Ferry 1 During 1977, Monitor 1 251 . . . . .	2D-4
D-5	Iodine-131 Vent Monitor Measurements at Browns Ferry 2 During 1977, Monitor 2 250 . . . . .	2D-5
D-6	Iodine-131 Vent Monitor Measurements at Browns Ferry 2 During 1977, Monitor 2 249 . . . . .	2D-6
D-7	Iodine-131 Vent Monitor Measurements at Browns Ferry 2 During 1977, Monitor 2 251 . . . . .	2D-7
D-8	Iodine-131 Vent Monitor Measurements at Browns Ferry 3 During 1977, Monitor 3 250 . . . . .	2D-8
D-9	Iodine-131 Vent Monitor Measurements at Browns Ferry 3 During 1977, Monitor 3 249 . . . . .	2D-9
D-10	Iodine-131 Vent Monitor Measurements at Browns Ferry 3 During 1977, Monitor 3 251 . . . . .	2D-10
D-11	Iodine-131 Vent Monitor Measurements at Browns Ferry 1, 2, and 3 During 1977, Monitor 0 252 . . . . .	2D-11



ABSTRACT

*Airborne iodine-131 releases from BWRs are decreasing based on an evaluation of 31 reactor-years of operating plant data. An independent analysis of extensive I-131 measurements sponsored by the Electric Power Research Institute indicate an annual normalized release of elemental iodine (I<sub>2</sub>) to be 25 millicuries per reactor. The basis for normalization is a calendar year consisting of 300 days of power operations and one refueling maintenance shutdown period, a concentration of I-131 in reactor water of 1  $\mu\text{Ci/kg}$ , a carryover of I-131 from reactor water to reactor steam of 1%, and full-flow condensate treatment. Adjustment factors would be applied to plants with parameters varying from this normalization basis to determine the annual I-131 airborne release rate for future BWR environmental impact assessments.*

*Actual measurements of I-131 activity in milk produced on farms near BWRs indicate that if an infant consumed this milk at a rate of 300 liters per year, conservative assumptions, then the thyroid dose due to I-131 ingestion would amount to much less than one millirem. This dose estimate is a decade less than the United States Nuclear Regulatory Commission dose objective. Iodine-131 airborne releases from operating BWRs have not been significant causes of dose via the plant airborne release-grass-cow-milk-infant pathway, nor are they anticipated to be in the foreseeable future.*

## 1. INTRODUCTION

This amendment to NEDO-21159, March 1976, "Airborne Releases from BWR's for Environmental Impact Evaluations," updates the original report with new information on iodine-131 (I-131) releases from ventilation systems. New information includes I-131 release measurements from July 1975 to about December 1976, I-131 reactor water concentrations in domestic BWRs and improved-fuel exposures to December 1977, plus an evaluation of I-131 release measurements that allows for the projection of current results to future BWRs.

No new information is included in this amendment about noble radiogas or particulate releases.

For environmental impact assessments of BWRs results are summarized in Section 2. These results for I-131 airborne releases are presented on a "normalized" basis. The reader may recall that the original version of NEDO-21159 (March 1976) treated the release data on an "as is" basis. In NEDO-21159 a limited evaluation indicated that the I-131 releases could be correlated to I-131 reactor water concentrations. This amendment includes the results of a more extensive evaluation of I-131 release data normalized to reactor water concentration and other plant performance parameters. The normalization basis is defined as follows:

1. a calendar year consists of 300 days of power operations and one refueling/maintenance shutdown period,
2. a concentration of I-131 in reactor water of 1  $\mu\text{Ci}/\text{kg}$ ,
3. a carryover of I-131 from reactor water to reactor steam of 1%, and
4. full-flow condensate treatment.

For a plant with parameters varying from any of these values adjustment factors would be applied to the normalized release rates to determine the I-131 airborne releases from BWRs. Furthermore, for proper environmental impact evaluations the I-131 releases must include percentages of each species of I-131 from BWR reactor, turbine and radiowaste building ventilation exhausts and the gland seal steam/mechanical vacuum pump discharges. The results for I-131 are based on measurements in ventilation exhausts without charcoal treatment.

The results reported in Section 2 establish a quantitative relationship between I-131 airborne releases to the environs of BWRs and plant parameters, including I-131 reactor water concentration. In addition Section 2 presents the results of a significant analysis that indicates a general downward trend in actual I-131 release rates at four BWR plants.

The airborne I-131 releases from currently designed BWR process off-gas treatment systems have been estimated to be essentially zero (Reference 1-1).

In NEDO-21159 (March, 1976) reference was made to 10CFR50 Appendix I in order to establish realistic estimates of off-site doses from nuclear power plant airborne effluents. In this amendment, Appendix 2A presents selected quotations from the Nuclear Regulatory Commissioner's opinion on Appendix I, for the reader's convenience (Reference 1-2). The quotations from the Commissioner's are included in this amendment to re-emphasize the importance of realistic dose assessments and the end to objections in already conservative dose objectives. The dose objectives stipulated in 10CFR50 Appendix I are understood to be firm values which are not expected to be reduced in the future due to superior performance by BWRs (Reference 1-3).

Section 3 of this amendment presents I-131 release measurements on an "as is" basis. These measurements include routine operating plant data for about 31 reactor-years, data for about 3.8 reactor-years from special measurements sponsored by the Electric Power Research Institute (EPRI), and other short-term measurements by the Nuclear Regulatory Commission (NRC) and the General Electric Company (GE). The measurements of I-131 species--particulates, elemental iodine, hypoiodous acid and organic iodine--are presented in Section 4. The following section presents data for the I-131 concentrations in milk produced on farms near BWRs; this is new information that was not included in NEDO 21159 (March, 1976). An empirical correlation has been developed between I-131 concentrations in milk and distance from the plant.

Section 6 presents background information relative to I-131 carryover from reactor water to steam, I-131 concentrations in reactor water, and data on improved fuel performance. The final part of Section 6 presents the EPRI measurements on a normalized basis including statistical and trend analysis.

The results for I-131 airborne measurements are presented in Section 7. These results include average values for the I-131 species, summaries of the utility and EPRI data. In addition an empirical relationship is shown that indicates the overall effect of improved fuel performance on I-131 reactor water concentrations in BWRs. The results of this study for the generic determination of annual I-131 releases from BWRs are verified by test against an independent data set, 3 reactor years of measurements from the Browns Ferry site during 1977. The results of this verification are presented in Section 7.

## 1.1 REFERENCES

- 1-1 Gutierrez, R. J. and C. W. Miller, February 1977, "N66 SJA6 Off-Gas Treatment System," *General Electric Company, Licensing Topical Report, Class 1*, NEDO-21056, Section 6.6.
- 1-2 United States Nuclear Regulatory Commission, April 30, 1975, "Opinion of the Commission, In the Matter of Rulemaking Hearing: Numerical Guides for Design Objectives and Limiting Conditions for Operation to Meet the Criterion 'As Low As Practicable' for Radioactive Material in Light-Water-Cooled Nuclear Power Reactor Effluents," Docket No. RM-50-2
- 1-3 Kahan, R. S., and Y. Feige, 1977, "The Wide Margin of Implicit Built-in Safety Factors in Current Radiation Protection Standards," *Health Physics* 32, 509.

## 2. SUMMARY OF RESULTS

This section summarizes the results for normalized iodine-131 release rates as well as a trend analysis of actual airborne I-131 release rates. The data base and methods used to develop these results are described in the following sections of this report. With regard to the concentration levels of I-131 in milk produced in BWR environs all the information is presented in Section 5.

On the basis of extensive special studies of iodine-131 (I-131) airborne releases the normalized annual airborne release of I-131 in elemental form is 25 millicuries per year per reactor, see Tables 2-1 and 2-2. Relative to elemental I-131, the results indicate that about 75% of the iodine is released from the turbine building with the reactor building being the next largest source, 15%. The other sources of elemental I-131 release are nominal, see Table 2-1. Elemental I-131 is the primary form of iodine for environmental impact evaluations of agricultural pathways because its relatively high deposition velocity compared to other identified species in BWR airborne releases.

Airborne release results for non-elemental I-131 species are presented in Tables 2-3 and 2-4.

Iodine-131 normalized releases presented in this amendment are based on measurements sponsored by the Electric Power Research Institute, and conducted by Nuclear Environmental Services at three BWRs, namely, Vermont Yankee, Monticello, and Oyster Creek. There are about 4 reactor years of special measurements at these different types of BWR's. Oyster Creek is the oldest plant, commissioned in 1969 and Vermont Yankee, which began commercial power generation in 1972, is the newest of the three.

The cumulative calendar quarterly I-131 releases were correlated by least-squares regression analysis. This analysis considers reactors for which I-131 ventilation release data are available for at least 2 years. For correlation purposes data from the first year, or so, of reactor operations were eliminated to discount any start-up effects that would have biased the results downwards. The correlation is of the form

where  $y = a x^b$

$y$  = cumulative I-131 release, millicuries

$x$  = cumulative plant operating time, months

$a, b$  = constants determined by regression analysis

For the evaluation of trends in I-131 release rates, the important term is the exponent,  $b$ , because the exponent is an index of whether releases are increasing ( $b > 1$ ), decreasing ( $b < 1$ ), or constant ( $b = 1$ ). The correlation results are summarized in Table 2-5. The  $b$  results listed in the right-hand column of Table 2-5 indicate that the I-131 ventilation releases from BWR's are on the decrease.

Trend analysis results are also graphically summarized in Figure 2-1. The ordinate of Figure 2-1 is a "normalized" index of I-131 releases useful to monitor trends. The ordinate is the ratio of the calculated deviation between the observed and correlated values at each period to the standard error of estimate\* of the correlation. Negative deviations indicate decreasing I-131 release rates, and conversely. This parameter is analogous to the number of standard deviations that a sample point is from the sample mean. In Figure 2-1 the tail-ends of the curves are below the mean by more than two "standard deviations" for three of the four BWR plants; namely, Pilgrim 1, Monticello and Quad Cities 1/2. There has been only a slight decrease in release rates from Dresden 2/3 over the last few years; its I-131 releases have been relatively small.

\* The standard error of estimate,  $S_E$  is defined as follows,<sup>1</sup>

$$S_E^2 = \sum_{i=1}^n (Y_i - \hat{Y}_i)^2 / (n-2),$$

where  $n$  = number of sample pair

$Y_i$  = observed value of dependent variable,

$\hat{Y}_i$  = estimated value of  $Y_i$  by regression equation.

<sup>1</sup>Ostle, B., and R. W. Mesing, 1975, *Statistics in Research*, 3rd ed., Ames The Iowa State University Press, p. 170

2.1 REFERENCES

- 2.1 American Nuclear Society Standards Committee Working Group ANS-18.1, "American National Standard Source Term Specification," American Nuclear Society, ANS-18.1, ANSI N237-1976 (Approved May 11, 1976), Table 5.
- 2.2 Lin, C. C. and H. L. Kenitzer, July 1977, "Fission Product Transport Measurements at Brunswick-2," General Electric Company, Internal Document (Draft), Figure 5.

**Table 2-1**  
**NORMALIZED \* ANNUAL AIRBORNE RELEASES OF ELEMENTAL IODINE-131 FOR ENVIRONMENTAL IMPACT EVALUATIONS OF BWR's**

Source Building or Exhaust	Elemental I-131 Release <sup>d, e</sup>	
	Millicuries Per Year Per Reactor	Percent
Reactor <sup>d</sup>	.8	15
Turbine <sup>e, f, g</sup>	19.0	76
Radwaste	1.3	5
Gland Seal Steam and Mechanical Vacuum Pump <sup>h, i</sup>	1.1	4
<b>Total<sup>j</sup></b>	<b>25.0 millicuries</b>	<b>100%</b>

Notes

- (a) Results are normalized to the following conditions: (1) a calendar year consisting of 300 days of power operations and one refueling/maintenance shutdown period; (2) a concentration of I-131 in reactor water of 1 µCi/kg; (3) a carryover of I-131 from reactor water to reactor steam of 1%; and (4) full flow condensate treatment.
- (b) The elemental iodine (I<sub>2</sub>) form of I-131 is identified as that portion of the airborne release trapped by cadmium iodide adsorbent in the iodine species sampler, see Section 4.
- (c) Normalized releases are based on an I-131 reactor water concentration of 1.0 µCi/kg. For BWR's with other than this concentration, adjust releases in direct proportion to the expected I-131 reactor water concentration. On the basis of selected measurements in 1972 at several BWR's an I-131 reactor water concentration of 5 µCi/kg has been used for environmental impact assessments (Reference 2-1). On the basis of this evaluation's analysis of 1975 and 1976 operating data from 15 domestic BWR's the expected I-131 reactor water concentration for future BWR's with 100% improved fuel and full flow condensate treatment is 0.5 µCi/kg. However, this concentration should still be conservative because it is based in part on the performance of old-type fuel (see Section 7).
- (d) Reactor building releases are based on BWR Mark I containments. For BWR Mark III containments use 50% of the Mark I reactor building result for to the auxiliary and fuel buildings and 50% for the Mark III containment building.
- (e) For BWR's with deep-bed condensate treatment systems or powder plants with stainless steel condenser tubing multiply above results by 1.5 and for plants with powder systems multiply results by 0.4 (see Table E-1).
- (f) For BWR's with forward pumped flow multiply above results by 0.25. Increase reactor and radwaste building releases by 1.75 (Reference 2-2).
- (g) Gland seal steam release is based on BWR's without the use of an auxiliary boiler for clean steam; for BWR's with a separate steam supply, the gland seal release should be divided by 1000.
- (h) Normalized releases assume one refueling/maintenance outage per year and 300 days of power generation operations; for BWR's with longer fuel cycles the annual releases should be adjusted to the cycle period; see Table 2-2.

**Table 2-2**  
**NORMALIZED ANNUAL AIRBORNE RELEASES OF ELEMENTAL IODINE-131 ACCORDING TO PLANT OPERATING MODE FOR ENVIRONMENTAL IMPACT EVALUATIONS OF BWR's \***

Source Building or Exhaust	Elemental I-131 Release Millicuries per Year per Reactor	
	Power Generation	Refueling/Maintenance
Reactor Building	3.4	0.40
Turbine Building	18.0	0.97
Radwaste Building	1.3	0.039
Gland Seal Steam	1.1	--
Mechanical Vacuum Pump	--	0.006
<b>Total</b>	<b>23.8</b>	<b>1.42</b>

Notes: (a) See Notes listed in Table 2-1

**Table 2-3**  
**NORMALIZED ANNUAL AIRBORNE RELEASES OF NON-ELEMENTAL IODINE-131 SPECIES**  
**FOR POWER GENERATION OPERATIONS (300 DAYS), FOR**  
**ENVIRONMENTAL IMPACT EVALUATIONS OF BWR's**

Source	Species I-131 Release, Millicuries per Year per Reactor		
	Particulate	HOI	CH <sub>3</sub> I
Reactor Building	1.0	1.5	3.2
Turbine Building	6.4	4.9	3.0
Radwaste Building	0.18	0.48	3.4
Gland Seal Steam and Mechanical Vacuum Pump	<u>0.88</u>	<u>3.9</u>	<u>13.1</u>
Totals	8.5	10.8	22.7

Notes: (a) See Notes listed in Table 2-1.

(b) I-131 species are discussed in Section 4; particulates correspond to I-131 trapped on sampler filter paper; HOI means hypiodous acid and trapped on p-iodophenol adsorbent, and CH<sub>3</sub>I means methyl iodide or I-131 species which penetrates the following adsorbents: filter paper, cadmium iodide and p-iodophenol. The CH<sub>3</sub>I is trapped by charcoal impregnated with TE(DA) (or silver zeolite). Actual chemical analyses may indicate relatively small amounts of other organic compounds.

(c) Iodine-131 species are summarized on a percentage basis for the various sources and plant operating modes in Table 4-B.

**Table 2-4**  
**NORMALIZED ANNUAL AIRBORNE RELEASES OF NON-ELEMENTAL IODINE-131 SPECIES**  
**FOR A REFUELING/MAINTENANCE OUTAGE FOR ENVIRONMENTAL**  
**IMPACT EVALUATIONS OF BWR's<sup>a, b</sup>**

Source	Species I-131 Release, Millicuries per Year per Reactor		
	Particulate	HOI	CH <sub>3</sub> I
Reactor Building	0.079	0.65	0.46
Turbine Building	0.17	1.4	0.99
Radwaste Building	0.005	0.066	0.69
Mechanical Vacuum Pump	<u>0.012</u>	<u>0.006</u>	<u>6.0</u>
Totals	0.266	2.122	8.14

Notes: (a) See Notes listed in Table 2-1

(b) Iodine-131 species are summarized on a percentage basis for the various sources and plant operating modes in Table 4-8



**Table 2-5  
CORRELATION OF LONG-TERM TRENDS IN ACTUAL  
I-131 AIRBORNE RELEASES FROM BWR VENTILATION EXHAUSTS**

Plant	Exhaust	Operation Period Month/Year	Elapsed Time Months	Correlation Exponent, b Operational Period	
				Overall	Recent
Dresden 2/3	Reactor Bldg.	startup <sup>a</sup> (7/71 and 11/71) to 12/72	12	not calculated	
Dresden 2/3	Reactor Bldg	1/73 to 12/76	48	1.15	—
Dresden 2/3	Reactor Bldg	1/75 to 12/76	24	—	0.95
Quad Cities 1/2	Reactor Bldg	startup <sup>a</sup> (8/72) to 6/73	10	not calculated	
Quad Cities 1/2	Reactor Bldg	7/73 to 6/77	48	1.19	—
Quad Cities 1/2	Reactor Bldg	1/76 to 6/77	18	—	0.71
Monticello	Reactor, Turbine and Radwaste Bldgs	startup <sup>a</sup> (7/71) to 12/73	30	not calculated	
Monticello	Reactor, Turbine and Radwaste Bldgs.	1/74 to 12/76	36	1.00	—
Monticello	Reactor, Turbine and Radwaste Bldgs	1/75 to 12/76	12	—	0.04
Pilgrim 1	Reactor, Turbine and Radwaste Bldgs	startup <sup>a</sup> (12/72) to 9/74	22	not calculated	
Pilgrim 1	Reactor, Turbine and Radwaste Bldgs.	10/74 to 6/76	21	1.29	—
Pilgrim 1	Reactor, Turbine and Radwaste Bldgs	7/75 to 6/76	12	—	0.44

Notes: (a) Startup is defined here as first month of commercial service.

(b) Correlation is of form  $y = ax^b$  where b is called the correlation exponent, y is the cumulative I-131 release, and x is the cumulative time.

0 7 7 0




Figure 2-1. Long-Term Trend Analysis of Cumulative Iodine 131 Airborne Releases from BWR Ventilation Exhausts

NEDO-21159-2

### 3. AIRBORNE IODINE-131 RELEASE DATA

This section presents airborne I-131 release data from measurements routinely performed at operating BWR plants and from special studies. The special measurements have been sponsored primarily by the Electric Power Research Institute and conducted by Nuclear Environmental Services, a division of Science Applications, Inc.

A few special measurements have been performed by the General Electric Company and the Atomic Energy Commission (now the Nuclear Regulatory Commission). These results were previously reported in the original version of NEDO-21159 (March 1976), but are included here for completeness.

#### 3.1 MEASUREMENTS BY UTILITIES

The following data were reported in semi-annual operating reports by several utilities, and in some instances, data were obtained from plant records. These data are obtained by routine procedures of health physics/chemistry personnel. The results provide long-term histories of actual BWR airborne releases of iodine-131 via ventilation exhausts.

##### 3.1.1 Boston Edison Company (Pilgrim 1)

For Pilgrim 1 data are available for total plant ventilation exhaust releases from January 1973 to June 1976 (References 3-1 to 3-7). These data are presented in Figure 3-1 and listed in Table 3-1.

Figure 3-2 presents the distribution of quarterly releases of I-131 for the total plant ventilation release, including the total of the reactor, turbine and radwaste building exhausts. The plant operational period is from October 1974 to December 1976, inclusive. This period discounts the data during the first 22 months of commercial operations.

##### 3.1.2 Commonwealth Edison Company (Dresden 2/3, Quad Cities 1/2)

###### 3.1.2.1 Dresden 2/3

For the Dresden 2/3 reactors data are available for the reactor building ventilation release up to December 1976 (References 3-8 to 3-22). Figure 3-3 illustrates the chronology of I-131 ventilation releases from the Dresden 2/3 reactors from 1972 to 1976, inclusive. Table 3-2 lists the data.

The reactor building ventilation releases of I-131 are normally distributed as shown by Figure 3-4. For all the data, 16 calendar quarters the arithmetic mean is 0.026 curies/quarter per 2 reactors, and the standard deviation is large at 0.013 Ci/quarter. The large variance is partially due to one outlier because of an unusually high I-131 release that occurred during the fourth quarter of 1974, as shown by Figure 3-3. Rejection of this value, leads to a slightly lower mean, 0.023 Ci/quarter with a standard deviation of 0.0076. This corresponds to a coefficient of variation of 33% instead of 50% when the outlier is included. The coefficient of variation is defined as the ratio of the sample standard deviation to the sample mean, expressed in percent. This release is about one-half the reactor building release recommended in the original version of NEDO-21159 (March 1976).

During 1975 and 1976 the I-131 reactor water concentrations at Dresden 2 and Dresden 3 ranged from about 0.2 to 5  $\mu\text{Ci}/\text{kg}$ . Dresden 3 had consistently higher I-131 concentrations than Dresden 2.

###### 3.1.2.2 Quad Cities 1/2

For the Quad Cities 1/2 plants data are presented from July 1972 to December 1977 (References 3-23 to 3-35). Figure 3-5 illustrates the chronology of I-131 releases from the Quad Cities 1/2 reactors, and Table 3-3 lists the data on a quarterly basis.

The Quad Cities 1/2 reactor building ventilation releases of I-131 are normally distributed, as at Dresden 2/3, see Figure 3-6. For the last 8 reactor-years of operations the mean I-131 release is 0.0394 curies per quarter for 2 reactors. The standard deviation is 0.015 Ci/quarter which yields a 36% coefficient of variation. This degree of variation is almost the same as for Dresden 2/3.

The average annual I-131 release for the reactor building ventilation release is 79 millicuries/reactor. This value is about 10% less than the reactor building release recommended in the original version of NEDO-21159 (March 1976).

During 1975 and 1976 the I-131 reactor water concentrations at Quad Cities 1 and Quad Cities 2 range from about 0.3 to 40  $\mu\text{Ci}/\text{kg}$ . During 1975 the I-131 concentrations were greater at Quad Cities 2, however, during the latter-half of 1976 both reactors were operating with I-131 concentrations of about 2 to 3  $\mu\text{Ci}/\text{kg}$ . This is a general decrease in concentration with time which is reflected in lower I-131 reactor building ventilation releases, see Figure 3-5.

### 3.1.3 Northern States Power Company (Monticello)

Iodine-131 ventilation release data are presented from January 1974 to December 1977 for the Monticello plant (References 3-36 to 3-42). Figure 3-7 presents the chronology of total plant ventilation releases, plant ventilation releases are the sum of the reactor, turbine and radwaste building exhausts. These data are listed in Table 3-4.

The Monticello total plant I-131 releases are lognormally distributed prior to 1976; data for 1976 are normally distributed, see Figure 3-8. Note Figure 3-8 plots the 1976 data on lognormal probability paper for convenience only. The change in distribution type occurred after the refueling/maintenance outage in late 1975. After this outage the fuel was primarily of the improved type (GE fuel type, "8x8") and variations in I-131 reactor water concentrations were small. Prior to 1976 I-131 reactor water concentrations ranged from about 10 to 200  $\mu\text{Ci}/\text{kg}$ , in 1976 concentrations were generally between 4 and 10  $\mu\text{Ci}/\text{kg}$  with a decreasing trend.

The actual average (geometric mean since data are lognormally distributed) I-131 release from the reactor, turbine and radwaste buildings at Monticello is 0.31 Ci/quarter with a geometric standard deviation of 2.9. This release extends over 2 reactor years of operation. For the one reactor year of operation (1976) after complete incorporation of improved fuel, the total plant ventilation I-131 release is an average of 0.015 Ci/quarter with a coefficient of variation of 24%.

The change from old-type fuel to improved fuel has decreased the average I-131 plant ventilation release by approximately a factor of 20. Further decrease in plant I-131 release would be expected as residual tramp uranium in the reactor vessel is "burned up."

### 3.1.4 Philadelphia Electric Company (Peach Bottom 2/3)

There is a limited amount of data for I-131 releases via a total plant ventilation exhaust at Peach Bottom 2/3 (Reference 3-43). For these two reactors, the I-131 release data are available for the first 9 months of 1976, see Tables 3-5 and 3-6. Since the data base is only for 1.5 reactor years it is of limited use in establishing long term trends. However, it is presented here because the data are useful when combined with the analysis of I-131 in milk produced on farms in the environs of the plant (see Section 5).

## 3.2 MEASUREMENTS BY ELECTRIC POWER RESEARCH INSTITUTE

The Electric Power Research Institute sponsored Nuclear Environmental Services (NES) to perform measurements of airborne releases at three BWR's. This report summarizes I-131 release data available in the various studies in the period of June 1974 through December 1976 for Oyster Creek, Monticello and Vermont Yankee (References 3-44 to 3-47). The first phase of studies at Vermont Yankee were sponsored by the Yankee Atomic Electric Company (Reference 3-48).

In this section the data are simply tabulated. In Section 6.4 graphs are presented of the I-131 releases as a function of time. These graphs present the I-131 release information on a normalized basis, that is, the actual I-131 releases for each sample period are divided by the actual average I-131 reactor water concentration during the same period. Normalized releases allow a comparison of I-131 airborne releases from each building ventilation exhaust at each BWR studied on a common basis. Tables 3-7 to 3-19 tabulate the EPRI sponsored data; Tables 3-7 to 3-9 are for Vermont Yankee, Tables 3-10 to 3-12 are for Monticello, and Tables 3-13 to 3-16 are for Oyster Creek. For each plant these tables present information in the following sequence: average I-131 release rate ( $\mu\text{Ci}/\text{s}$ ), total I-131 release (millicuries), and average I-131 reactor water concentration ( $\mu\text{Ci}/\text{kg}$ ) and power level (% of rated). The results are in chronological order by plant. Table 3-17 presents some miscellaneous data obtained at Oyster Creek. The total I-131 releases are summarized for each plant in Tables 3-18 and 3-19. However, for practical purposes these latter results are not directly

useful because of differences in sample time, plant operation and fuel performance. These variables are accounted for in Section 6.4. Thus the results presented in Tables 3-18 and 3-19 are listed only for possible information needs of the reader and the results are not applicable as I-131 "source terms" for environmental impact evaluations of BWR's.

### 3.3 MEASUREMENTS BY NUCLEAR REGULATORY COMMISSION

Table 3-20 is a summary of NRC measurements conducted during 1972 and 1973 (References 3-49 and 3-50). This table appeared as Table 3-28 in the original version of NEDO-21159 (March 1976). References 3-51 and 3-52 contain information by the AEC that confirms the measurements at Dresden by Commonwealth Edison personnel.

### 3.4 MEASUREMENTS BY GENERAL ELECTRIC

Table 3-21 is a summary of GE measurements conducted during 1971 to 1974 (References 3-53 to 3-60). This table appeared as Table 3-29 in the original version of NEDO-21159 (March 1976). One data point has been added, namely for a mechanical vacuum pump I-131 release at Millstone Point 1 during a brief shutdown on September 1, 1972.

### 3.5 REFERENCES

- 3-1 Pilgrim Nuclear Power Station, January through June 1973, "Semiannual Operating and Maintenance Report," Docket 50-293-151.
- 3-2 Pilgrim Nuclear Power Station, July through December 1973, "Semiannual Operating and Maintenance Report," Docket 50-293-663.
- 3-3 Pilgrim Nuclear Power Station, January through June 1974, "Semiannual Operating and Maintenance Report," Docket 50-293-334.
- 3-4 Pilgrim Nuclear Power Station, July through December 1974, "Semiannual Report No. 5, Environmental Radiation Monitoring Program, Supplement," Docket 50-293-411.
- 3-5 Pilgrim Nuclear Power Station, January 1, to June 30, 1975, "Semiannual Operating and Maintenance Report."
- 3-6 Pilgrim Nuclear Power Station, July through December 1975, "Radioactive Effluent Release Report."
- 3-7 Pilgrim Nuclear Power Station, "Radioactive Effluent Release Report, April - June 1976," (Boston Edison Company, Mass.), 30 August 1976, Docket 50-293-717 and
- 3-7a Pilgrim Nuclear Power Station, "Radioactive Effluent Release Report," July through December, 1976, Docket 50-293-826, February 28, 1977.
- 3-8 Dresden Nuclear Power Station, January 1 - June 30, 1972, "Radioactive Waste and Environmental Monitoring Semiannual Report Docket," 50-101-119.
- 3-9 Dresden Nuclear Power Station, July 1, 1972, "Semiannual Report Section IV: Radioactive Waste and Environmental Monitoring," Dockets 50-010-135, 50-237-299, 50-249-190.
- 3-10 Dresden Nuclear Power Station, January through June 1973, "Radioactive Waste and Environmental Monitoring, Semiannual Report."
- 3-11 Dresden Nuclear Power Station, July through December 1973, "Radioactive Waste and Environmental Monitoring, Semiannual Report," Docket 50-010-221.
- 3-12 Appendix A to Operating License DPR-25, "Technical Specifications and Basis for Dresden Nuclear Power Station Unit 3," Grundy County, Illinois, Commonwealth Edison Company Docket 50-249, July 16, 1974, section 3.8, p. 134B (Note: The Dresden Unit 2 has the same values.)

NEDO-21159-2

- 3-13 Dresden Nuclear Power Station, January through June 1974, "Radioactive Waste and Environmental Monitoring, Semiannual Report."
- 3-14 Dresden Nuclear Power Station, July through December 1974, "Radioactive Waste and Environmental Monitoring Semiannual Report."
- 3-15 Dresden Nuclear Power Station, January through April 1975, "Units 2 and 3 Vent Stack Release."
- 3-16 Dresden Nuclear Power Station, July through December 1973, "Unit 2 Rx Vent (CAM) "
- 3-17 Dresden Nuclear Power Station, July through December 1973, "Unit 3 Rx Vent (CAM)."
- 3-18 Dresden Nuclear Power Station, January through June 1975, "Radioactive Waste, Environmental Monitoring and Occupational Personnel Radiation Exposure."
- 3-19 Dresden Nuclear Power Station, January 1974 to June 1975, "Units 2 and 3, Fuel Warrant Report, Form A-8" (Commonwealth Edison Company Transmittal to the General Electric Company).
- 3-20 Dresden Nuclear Power Station, "Radioactive Waste, Environmental Monitoring and Occupational Personnel Radiation Exposure, July through December 1976," Table 1.1-2.
- 3-21 Dresden Nuclear Power Station, August 1976, "Radioactive Waste, Environmental Personnel Radiation Exposure, January through June 1976," Table 1.1-2.
- 3-22 Iodine-133 Vent Stack Releases (Dresden), July through December 1976, as reported in letter D. L. Butcher to R. H. Thomas, April 15, 1977
- 3-23 Quad Cities Nuclear Power Station, January through June 1973, "Radioactive Waste and Environmental Monitoring, Semiannual Report," (Submitted by Eberline Instrument Corporation, Midwest Laboratory)
- 3-24 Quad Cities Nuclear Power Station, July through December 1973, "Radioactive Waste and Environmental Monitoring," Docket 50-254-326.
- 3-25 Quad Cities Nuclear Power Station, January through June 1974, "Radioactive Waste and Environmental Monitoring "
- 3-26 Quad Cities Nuclear Power Station, July through December 1974, "Semiannual Report, Radioactive Waste, Environmental Monitoring and Occupational Personnel Radiation Exposure."
- 3-27 Quad Cities Power Station, January through June 1975, "Radioactive Waste, Environmental Monitoring and Occupational Personnel Radiation Exposure."
- 3-28 Quad Cities, Plant Startup through June 1975, "Rx Vent Particulates, Isotopic Analyses."
- 3-29 Quad Cities, Plant Startup through June 1975, "Rx Vent Iodine Release."
- 3-30 Quad Cities, Plant Startup through June 1975, "Reactor Vent Stack Particulate Release."
- 3-31 Appendix A to Operating License No. DPR-29 and Operating License No. DPR-30, "Technical Specifications and Bases for Quad-Cities Station Units 1 and 2," Rock Island County, Illinois, Commonwealth Edison Company and Iowa-Illinois Gas and Electric Company, Dockets Nos. 50-254 and 50-265. Change No 4 Date of Issuance: December 14, 1972, Section 3.8 page 181.
- 3-32 Quad Cities Nuclear Power Station, July through December 1975, "Radioactive Effluent Discharges, Environmental Monitoring, Solid Radioactive Waste, and Personnel Exposures."

- 3-33 Quad Cities Nuclear Power Station, January through June 1976, "Radioactive Effluent Discharges, Environmental Monitoring, Solid Radioactive Waste, and Personnel Exposures."
- 3-34 Quad Cities Nuclear Power Station, July through December 1976, "Effluent and Waste Disposal Semi-annual Report 1976, Gaseous Effluents-Ground Level Release," as reported in letter D. L. Butcher to R. H. Thomas, April 1, 1977.
- 3-35 Quad Cities Nuclear Power Station, First and Second Calendar Quarter of 1977, Unit 1 and Unit 2 Ground Level Releases, to be published in semi-annual report.
- 3-36 Monticello Nuclear Power Station, December 31, 1973, to July 1, 1974, "Chemistry Log-Reactor Building Vent, Weekly Values."
- 3-37 Monticello Nuclear Power Station, July 1, 1974, to June 30, 1975, "Chemistry Report-Reactor Building Vent and Stack Releases, Weekly Average Values."
- 3-38 Monticello Nuclear Generating Plant, January 1, 1974, to June 30, 1974, "Semiannual Operating Report No. 7, Northern States Power Company, Minneapolis, Minn.
- 3-39 Monticello Nuclear Generating Plant, July 1, 1974, through December 31, 1974, "Semiannual Operating Report No. 8"
- 3-40 Monticello Nuclear Generating Plant, January 1, 1975, through June 30, 1975, "Semiannual Operating Report No. 9," Northern States Power Company, Minneapolis, Minn.
- 3-41 Monticello Nuclear Generating Plant, June 3, 1977, "Appendix I Filing, Supplement 2-Revised," (includes releases July, 1975 to June 1976), as reported in letter L. D. Mayer to D. K. Davis.
- 3-42 Monticello Nuclear Generating Plant, June 3, 1977, "Revision to Effluent and Waste Disposal Semiannual Reports for January 1 - June 30, 1976 and July 1 - December 31, 1976," reported in letter L. O. Mayer to J. G. Keppler.
- 3-43 Peach Bottom 2/3, 1976, Stack & Vent Release Data, (December 29, 1975 to October 4, 1976), as reported to T. R. Marrero, November 1976.
- 3-44 Nuclear Environmental Services, February 1978, "Sources of Radioiodine at Boiling Water Reactors," Report to Electric Power Research Institute. NP-495.
- 3-45 Nuclear Environmental Services, 1977, "Environmental Radioiodine Chemical Form Study," Interim Report to Electric Power Research Institute, Phase I-Oyster Creek, 1976, II. Measurements of I-131 in Gaseous Effluents.
- 3-46 Nuclear Environmental Services, August 12, 1975, letter regarding mechanical vacuum pump discharges in BWR's, W. A. Emel to T. R. Marrero.
- 3-47 J. E. Cline and W. A. Emel, October 29, 1975, "Use and Testing of the Species Sampler, A Status Report," Nuclear Environmental Services.
- 3-48 Nuclear Environmental Services, October 15, 1974, "Iodine-131 Releases from the Vermont Yankee Nuclear Power Station, June-July 1974," Report to Yankee Atomic Electric Company.
- 3-49 C. A. Pelletier, Compiler, 1973, "Results of Independent Measurements of Radioactivity in Process Streams and Effluents at Boiling Water Reactor," Exhibit No. 22, Public Hearing Docket RM-50-2, USAEC.
- 3-50 F. E. Kruesi, May 22, 1973, "Results of Measurements at Quad Cities Station," letter from Director, Regulatory Operations, AEC, to B. B. Stephenson, Superintendent, Quad Cities Station, Commonwealth Edison Company.

- 3-51 United States Atomic Energy Commission, October, 1973, "Results of Measurements of Iodine-131 in Air, Vegetation, and Milk at Three Operating Reactor Sites," Interim Report, Directorate of Regulatory Operations, Exhibit No. 24, Public Hearing Docket RM 50-2 (See also NUREG-75-021)
- 3-52 United States Nuclear Regulatory Commission, March 1975, "Detailed Measurement of <sup>131</sup>I in Air, Vegetation, and Milk Around Three Operating Reactor Sites," NUREG-75-021, Contributors: B. H. Weiss, P. G. Volleque, J. H. Keller, B. Kahn, H. L. Krueger, A. Martin, C. R. Philips.
- 3-53 R. S. Gilbert, "Release Rate of Halogen Activity to Ventilation Exhaust, A Review of Data from Operating Plants," NEDM-12286, Rev. A, Class I (1973). [Includes data for KRB (1967-1970), Dresden 2 (January-February, 1971), Nine Mile Point, 1971 ]
- 3-54 R. S. Gilbert, "Release Rate of Halogen Activity to Ventilation Exhaust, A Review of Data from Operating Plants," NEDM 12286, Rev. A, Class I (1973).
- 3-55 R. S. Gilbert to V. Benaroya and J. Collins, "Information Disclosure of Progress on Ventilation Studies, Meeting at VNC on 5-23-74," letter dated May 23, 1974. [The enclosed tables (15 pages) represent the preliminary results of a study of the Nine Mile Point-1 ventilation systems ]
- 3-56 J. C. Golden and R. A. Pavlick, and contributors, "Measurements of Radioactivity in Process Systems of the Dresden Nuclear Power Station and in the Environment - January-February, 1971," Commonwealth Edison Company, Report No. 21, (1973)
- 3-57 C. Lin, Subject: 1. Activity Discharge by Mechanical Vacuum Pump (9/1/72), 2. Iodine-131 Activity in Reactor R. S. Gilbert, letter to H. L. Log, dated January 16, 1974 (Millstone Point 1 data on MVP, recalculation)
- 3-58 R. S. Gilbert, letter to H. L. Log, dated January 16, 1974 (Millstone Point 1 data on MVP, recalculation)
- 3-59 H. R. Helmholtz, R. S. Gilbert, and M. E. Meek, "Noble Gas and Iodine Activity in the Oyster Creek Ventilation and Off-Gas Systems During Power Operation," NEDE-11215, Class I (1973)
- 3-60 H. R. Helmholtz with contributions by J. H. Holloway, C. Lin, and M. E. Meek, "Millstone Nuclear Power Station Ventilation Sampling Program, July 13, 1972 - August 5, 1972," draft, see also Docket RM050-2, November 9, 1973, ALAP GE Exhibit No. 5, p. 16a.



**Table 3-1**  
**IODINE-131 AIRBORNE RELEASE**  
**PLANT — PILGRIM 1**  
**BUILDINGS — REACTOR, TURBINE, AND RADWASTE**

Year	Quarter	Iodine-131 Release curies/quarter
1973	1st	0 00429
	2nd	0 05952
	3rd	0 01606
	4th	0 01024
1974	1st	0 00283
	2nd	ND <sup>a</sup>
	3rd	0 00831
	4th	0 1449
1975	1st	0 2306
	2nd	0 4020
	3rd	0 492
	4th	0 0735
1976 <sup>b</sup>	1st	0.189
	2nd	0.0609
	3rd	0 0325
	4th	0 0507

arithmetic mean<sup>c</sup> = 0.14 Ci/quarter (October 1974 to December 1976)  
 standard deviation = 0.16 Ci/quarter

Notes: (a) Non-Detectable Activity  
 (b) Data for latter half 1976 not available  
 (c) Discounts initial period of commercial power generation operations

**Table 3-2  
IODINE-131 AIRBORNE RELEASE  
PLANTS — DRESDEN 2/3  
BUILDING — REACTOR**

Year	Quarter	I-131 Release curies per calendar quarter
1972	1st	0 019
	2nd	0 011
	3rd	0 013
	4th	0 006
1973	1st	0 0230
	2nd	0 0100
	3rd	0 0124
	4th	0 0320
1974	1st	0 0259
	2nd	0 0189
	3rd	0 0317
	4th	0 0664
1975	1st	0 0200
	2nd	0 0196
	3rd	0 0170
	4th	0 0181
1976	1st	0 0257
	2nd	0 0288
	3rd	0 0371
	4th	0 0271

Arithmetic mean release (1973 to 1976) 0 024  
Ci/quarter

Standard Deviation 0 013 Ci/quarter

Note (a) This period eliminates release data during first year  
(approximately) of commercial operation

**Table 3-3**  
**IODINE-131 AIRBORNE RELEASE**  
**PLANTS — QUAD CITIES 1/2**  
**BUILDING — REACTOR**

Year	Quarter	I-131
		Total curies released per calendar quarter
1972	3rd	0.00620
	4th	0.00303
1973	1st	0.0015
	2nd	0.0135
	3rd	0.0253
	4th	0.0370
1974	1st	0.0257
	2nd	0.0389
	3rd	0.0498
	4th	0.0586
1975	1st	0.0327
	2nd	0.0376
	3rd	0.0737
	4th	0.0534
1976	1st	0.0498
	2nd	0.0302
	3rd	0.0307
	4th	0.0243
1977	1st	0.028
	2nd	0.037
	3rd	0.042
	4th	0.053

Arithmetic mean \* 0.040 = I-131 curies/quarter  
 Standard deviation = 0.013 Ci/quarter

Note (a) Average calculated for period of 1973 3rd quarter to 1977 4th quarter, inclusive (the last 4½ years). average release excludes data during first year (approximately) of commercial operation

**Table 3-4**  
**IODINE-131 AIRBORNE RELEASE**  
**PLANT — MONTICELLO**  
**BUILDINGS — REACTOR, TURBINE, AND RADWASTE**

Year	Quarter	Iodine-131 Release	
		curies/quarter	
1974	1st	0.4658	} geometric mean 0.312 Ci/quarter
	2nd	0.1531	
	3rd	0.4638	
	4th	0.2931	
1975	1st	0.2049	} geometric standard deviation 2.93
	2nd	0.7052	
	3rd	1.5005	
	4th	0.0426	
1976	1st	0.0193	} Arithmetic mean 0.015 Ci/quarter
	2nd	0.0126	
	3rd	0.0116	} standard deviation 0.004 Ci/quarter
	4th	0.0170	
1977	1st	0.00731	
	2nd	0.00563	
	3rd	0.00421	
	4th	0.00135	

Note: The dramatic decrease (See Figure 3-8) in I-131 release which occurred in the 4th quarter of 1975 and thereafter is primarily due to a change in fuel. The entire core has been almost completely changed to improved type General Electric fuel.

**Table 3-5**  
**IODINE-131 AIRBORNE RELEASE**  
**PLANT — PEACH BOTTOM 2**  
**BUILDINGS — REACTOR, TURBINE AND RADWASTE**

Year	Quarter	I-131 Release, curies/quarter	
		gaseous	particulate
1976	1st	0.06	0.0072
	2nd	0.13	0.00365
	3rd	0.17	0.0098

**Table 3-6**  
**IODINE-131 AIRBORNE RELEASE**  
**PLANT — PEACH BOTTOM 3**  
**BUILDINGS — REACTOR, TURBINE AND RECOMBINER**

Year	Quarter	I-131 Release, curies/quarter	
		gaseous	particulate
1976	1st	0.00239	0.00187
	2nd	0.232	0.00496
	3rd	0.080	0.014

**Table 3-7**  
**AVERAGE I-131 VENTILATION RELEASE RATES**  
**PLANT — VERMONT YANKEE**  
**DATA SOURCE\* — EPRI/NES**  
**Average I-131 Release Rate,  $\mu\text{Ci/s}$**

Nominal Sample Period Month/Day/Year	Reactor (0.001)	Turbine (0.001)	Radwaste (0.001)	Gland Seal and MVP (0.001)	Stack (0.001)
6 20-7 2 74	3.5 <sup>a</sup>	1.4	1.5	0.5	NS <sup>1</sup>
7 2-7 9 74	24.0	2.2	4.0	50.0	NS
7 9-7 23 74	4.2	1.1	2.4	0.37	NS
7 23-7 30 74	2.6	1.5	1.7	0.49	NS
7 30-8 13 74	1.9	1.5	1.1	0.44	NS
8 13-8 27 74	1.8	1.6	1.4	0.40	NS
8 27-9 12 74	4.2	2.6	1.5	0.32	NS
9 14-9 27 74	3.9	1.5	3.0	NS	9.2
9 27-10 10 74	1.1	0.75	1.4	0.36	5.5
10/11- 10/13/74 <sup>b</sup>	18.0	} 4.7	NS	42.0	NS
10.13-10 14 74	23.0		NS	110.0	NS
10 14-10 31 74	45.0		8.2	NS	160
10 31-11 1 74	16.0	5.6	1.6	13.0	NS
11 1-11 18 74	17.0	0.86	0.65	0.62	NS
11 18-12 2 74	12.0	0.032	0.38	0.17	NS
12 2-12 6 74	1.2	0.040	0.27	0.18	NS
12 6-12 27 74	0.064	0.023	NS	NS	NS
12 27-1 28 75	0.016	0.025	0.016	0.030 <sup>a</sup>	NS
1 28-2 14 75	0.009	0.016	0.012	0.020	NS
2 14-3 5 75	0.064	0.018	0.014	0.037	NS
3 5-3 8 75	0.005	0.008	0.030	0.021	NS
3 8-3 26 75	0.34	0.032	0.035	0.087	NS
3 26-4 10 75	0.034	0.047	0.012	0.025	NS
4 10-4 26 75	0.034	0.027	0.0088	0.0190	NS
4 26-5 8 75	0.029	0.060	0.017	0.0131	NS
5 8-5 29 75	0.020	0.075	0.016	0.0696	NS
5 29-6 13 75	0.042	0.0142	0.0086	0.00736	NS
6 13-6 26 75	0.0223	0.037	0.021	0.0155	NS
6 26-7 10 75	0.048	0.057	0.028	0.0306	NS
7 10-7 29 75	0.026	0.031	0.042	0.0258	0.130 <sup>a</sup>
7 29-8 13 75	0.19	0.030	0.010	0.017	0.37
8 13-8 28 75	0.10	0.0077	0.0020	0.020	0.13
8 28-9 19 75	0.021	0.039	0.0060	NS	0.068
9 19-10 7 75	0.031	0.032	0.014	0.050	0.094
10 7-10 21 75	0.069	0.024	0.039	0.014	0.25
10 21-11 7 75	0.022	0.0081	0.050	0.024	0.77

Notes (1) NS means no sample taken

(2) Notation example Reactor Building release rate 6/20-7/2 74 is 0.0035  $\mu\text{Ci/s}$

(3) Refueling maintenance outage transpired 10/11 to 12/13/74

a. Collected 1/7 to 1/28/75

b. Collected 6/26 to 7/29/75

\*Measurements from 6/20/74 to 7/30/74 were sponsored by Yankee Atomic Electric Company

NEDO-21159-2

Table 3-8

ACTUAL I-131 VENTILATION RELEASES  
PLANT—VERMONT YANKEE  
DATA SOURCE — EPRI/NES

Total I-131 Release, millicuries

Nominal Sample Period Month/Day/Year	Sample Period Days	Reactor	Turbine	Radwaste	Gland Seal & MVP
6 20-7 2 74	12	3 629	1 452	1 555	0 518
7 2-7 9 74	7	14 515	1 331	2 419	30 240
7 9-7 23 74	14	5 080	1 331	2 903	0 448
7 23-7 30 74	7	1 572	0 907	1 028	0 296
7 30-8 13 74	14	2 298	1 814	1 331	0 532
8 13-8 27 74	14	2 177	1 935	1 693	0 484
8 27-9 12 74	16	5 806	3 594	2 074	0 442
9 14-9 27 74	13	1 123	4 380	3 370	NS*
9 27-10 10 74	13	1 236	0 842	1 572	0 404
10 11-10 13 74	2	3 110		NS	NS
10 13-10 14 74	1	1 987	6 903	NS	9 504
10 14-10 31 74	17	66 10		12 04	7 258
10 31-11 1 74	1	1 382	0 493	0 138	1 123
11 1-11 18 74	17	24 970	1 263	8 955	0 911
11 18-12 2 74	14	14 515	0 039	0 460	0 206
12 2-12 6 74	4	0 415	0 014	0 093	0 062
12 6-12 27 74	21	0 116	0 042	NS	NS
12 27-1 28 75	32	0 044	0 069	0 044	0 054
1 28-2 14 75	17	0 013	0 024	0 018	0 029
2 14-3 5 75	19	0 105	0 030	0 023	0 061
3 5-3 8 75	3	0 0013	0 0021	0 0078	0 0054
3 8-3 26 75	18	0 5288	0 049	0 0544	0 1353
3 26-4 10 75	15	0 0441	0 0609	0 0156	0 0324
4 10-4 26 75	16	0 0470	0 0373	0 0122	0 0263
4 26-5 8 75	12	0 0301	0 0622	0 0176	0 0136
5 8-5 29 75	21	0 0363	0 1361	0 0290	0 1263
5 29-6 13 75	15	0 0544	0 0184	0 0115	0 0954
6 13-6 26 75	13	0 0250	0 0416	0 0236	0 0174
6 26-7 10 75	14	0 0581	0 0689	0 0339	0 0370
7 10-7 29 75	19	0 0427	0 0509	0 0689	0 0424
7 29-8 13 75	15	0 2462	0 0389	0 0130	0 0220
8 13-8 28 75	15	0 1296	0 0100	0 0026	0 0259
8 28-9 19 75	22	0 0399	0 0741	0 0114	NS
9 19-10 17 75	18	0 0482	0 0498	0 0218	0 0778
10 7-10 21 75	14	0 0835	0 0290	0 0472	0 0169
10 21-11 7 75	17	0 0323	0 0119	0 0734	0 0353
Total I-131 Release, millicuries		151.641	27.205	32.160	53.281
Total sample time, days		502	502	478	418

- Notes (1) NS means no sample taken  
 (2) Release rates reported as less than (-) Table 3-7, were treated as equal to (=)  
 (3) Sample period for gland seal & MVP release was taken to be 21 days corresponding to collection period of 1/7 to 1/28/75  
 (4) Stack release not tabulated because release includes process off gas  
 (5) Actual I-131 Release Data are summarized in Tables 3-18 and 3-19

Table 3-10  
**AVERAGE I-131 VENTILATION RELEASE RATES**  
**PLANT—MONTICELLO**  
**DATA SOURCE — EPRI/NES**

Average Release Rate,  $\mu\text{Ci/s}$

Nominal Sample Period Month:Day/Year	Reactor (0.001)	Turbine (0.001)	Radwaste (0.001)	Roof-Vent (0.001)
11-15-11-17-74	210	37	53	30
11-20-12-3-74	22	19	26	44
12-5-12-18-74	16	94	14	27
12-18-1-6-75	91	70	18	18
1-8-1-9-75	61	4.1	12	11
1-13-1-15-75	27	34	14	65
1-9-1-13 and 1-15-1-22-75	18	39	0.64	58
1-22-2-7-75	68	68	0.28	14
2-7-2-22-75	31	28	0.45	31
2-22-3-10-75	81	18	0.26	26
3-10-3-25-75	22	20	NS	42
3-25-4-7-75	14	44	11	59
4-7-4-21-75	21	37	0.84	59
4-21-5-5-75	NS	51	1	NS
5-5-5-17-75	77	52	1.4	130
5-19-6-5-75	36	41	3.5	81
6-5-6-23-75	58	29	5.3	93
6-23-7-8-75	77	34	7.5	120
7-8-7-22-75	210	54	9.6	250
7-11-7-30-75	54	41	8.5	93
8-5-8-21-75	83	56	3.7	140
8-21-9-3-75	100	110	6.4	210
9-3-9-11-75	53	57	3.3	110
9-11-9-25-75	48	5.3	2.9	56
9-25-10-15-75	NS	1.4	0.25	NS
10-15-10-27-75	20	0.2	0.029	2.2
10-27-11-14-75	0.18	0.065	0.0096	0.25
11-14-11-17-75	0.0149	0.0188 <sup>a</sup>	NS	NS
11-17-11-18-75	0.0425	0.0538	0.0107	NS
11-18-11-18-75	NS	0.1076	0.0213	NS
11-18-11-19-75	0.1296	0.0807	0.0160	NS
11-19-11-19-75	0.0141	0.0829	0.0160	NS
11-19-11-20-75	0.1508	0.0798	0.0304	NS
11-20-11-21-75	0.3398	0.1067	0.0533	NS
11-21-11-21-75	0.3611	0.1573	0.0693	NS
11-21-11-22-75	0.4248	0.4490	0.0405	NS
11-22-11-22-75	0.4885	0.2634	0.0533	NS
11-22-11-23-75	0.4248	0.3725	0.0587	NS
11-23-11-23-75	0.4885	0.3488	0.0491	NS
11-23-11-24-75	0.7646	0.3634	NS	NS

Notes a Sampling period 5-5-5:12-75  
 b This data point and subsequent turbine building rates excludes MVP equipment compartment exhaust because no samples were taken  
 (1) Refueling maintenance outages transpired 1-8-27/75 and 9-11-11:17-75  
 (2) NS means no sample taken.

**Table 3-9**  
**IODINE-131 REACTOR WATER CONCENTRATIONS AND POWER**  
**LEVELS AT VERMONT YANKEE**  
**DATA SOURCE—EPR/INES**

Nominal Sample Period Month/Day/Year	Average I-131 Reactor Water Concentration $\mu\text{Ci/kg}$	Thermal Power % of Rated
6 20-7 2 74	25 0	79
7 2-7 9 74	25 0	35
7 9-7 23 74	25 0	79
7 23-7 30 74	25 0	79
7 30-8 13 74	30 0	79
8 13-8 27 74	35 0	79
8 27-9 12 74	38 0	79
9 14-9 27 74	37 0	73
9 27-10 10 74	35 0	79
10 11-10 13 74	a	0
10 13-10 14 74	a	0
10 14-10 31 74	a	0
10 31-11 1 74	a	0
11 1-11 18 74	a	0
11 18-12 2 74	a	0
12 2-12 6 74	a	0
12 6-12 27 74	1.0	41
12 27-1 28 75	0.81	91
1 28-2 14 75	0.78	99
2 14-3 5 75	0.89	55
3 5-3 8 75	—	—
3 8-3 26 75	0.80	78
3 26-4 10 75	0.63	93
4 10-4 26 75	0.90	99
4 26-5 8 75	0.61	99
5 8-5 29 75	0.71	84
5 29-6 13 75	0.53	36
6 13-6 26 75	0.62	67
6 26-7 10 75	0.62	82
7 10-7 29 75	0.61	82
7 29-8 13 75	0.67	45
8 13-8 28 75	0.64	0
8 28-9 19 75	0.61	79
9 19-10 17 75	0.85	96
10 7-10 21 75	0.77	97
10 21-11 7 75	0.89	99

a Plant down for refueling maintenance 10 11 to 12 13 74. I-131 reactor water concentration data are not available.



**Table 3-11**  
**ACTUAL I-131 VENTILATION RELEASES**  
**PLANT—MONTICELLO**  
**DATA SOURCE—EPRI/NES**

Total I-131 Release, millicuries

Nominal Sample Period Month/Day/Year	Nominal Sample Time Days	Reactor	Turbine	Radwaste	Roof-Vent
11 15-11 17 74	2	3 629	0 639	0 916	5 184
11 20-12 5 74	15	28 51	24 62	3 370	57 02
12 5-12 18 74	13	17 97	10 56	1 572	30 33
12 18-1 6 75	19	14 94	11 49	2 955	29 55
1 8 1 9 75	1	0 527	0 354	0 104	0 950
1 13-1 15 75	2	4 666	5 875	0 242	11 23
1 9-1 13 75 and 1 15-1 22 75	11	17 11	37 07	0 608	55 12
1 22-2 7 75	16	9 400	9 400	0 387	19 35
2 7-2 22 75	15	4 018	36 29	0 583	40 18
2 22-3 10 75	16	11 20	24 88	0 359	35 94
3 10-3 25 75	15	28 51	25 92	NS	54 43
3 25-4 7 75	13	15 72	49 42	1 236	66 27
4 7-4 21 75	14	25 40	44 76	1 016	71 37
4 21-5 5 75	14	NS	61 69	1 210	NS
5 5-5 17 75	12	79 83	53 91	0 847	134 8
5 19-6 5 75	17	52 88	60 22	5 141	119 0
6 5-6 23 75	18	90 20	45 10	8 243	144 6
6 23-7 8 75	15	99 79	44 06	9 720	155 5
7 8-7 22 75	14	254 0	65 32	11 61	302 4
7 11-7 30 75	8	37 32	28 34	5 875	64 28
8 5-8 21 75	16	114 7	77 41	5 115	193 5
8 21-9 3 75	13	112 3	123 6	7 188	235 9
9 3-9 11 75	8	36 63	39 40	2 281	76 03
9 11-9 25 75	14	58 06	6 411	3 508	67 74
9 25-10 15 75	20	NS	2 419	0 432	NS
10 15-10 27 75	12	2 074	0 207	0 030	2 281
10 27-11 14 75	18	0 280	0 101	0 015	0 389
11 14-11 17 75	2 90	0 00	0 005	NS	NS
11 17-11 18 75	1 01	0 002	0 005	0 009	NS
11 18-11 18 75	0 43	NS	0 004	0 008	NS
11 18-11 19 75	0 52	0 006	0 004	0 007	NS
11 19-11 19 75	0 49	0 004	0 004	0 007	NS
11 19-11 20 75	0 68	0 009	0 005	0 002	NS
11 20-11 21 75	0 47	0 0014	0 004	0 002	NS
11 21-11 21 75	0 68	0 02	0 009	0 004	NS
11 21-11 22 75	0 65	0 24	0 025	0 002	NS
11 22-11 22 75	0 43	0 18	0 010	0 002	NS
11 22-11 23 75	0 63	0 23	0 020	0 003	NS
11 23-11 23 75	0 38	0 016	0 011	0 002	NS
11 23-11 24 75	0 61	0 040	0 019	NS	NS
<b>Totals</b>	<b>360.88</b>	<b>1119.847</b>	<b>889.591</b>	<b>74.583</b>	<b>1973.344</b>
sample time, days		326.5	360.9	337.4	317.0

Notes: a Sample period is 7 days  
 (1) Actual I-131 release data are summarized in Tables 3-18 and 3-19  
 (2) NS means no sample taken

**Table 3-12**  
**IODINE-131 REACTOR WATER CONCENTRATIONS AND POWER**  
**LEVELS AT MONTICELLO**  
**DATA SOURCE-EPR/NES**

Nominal Sample Period Month/Day/Year	Average I-131 Reactor Water Concentration $\mu\text{Ci/kg}$	Thermal Power % of Rated
11:15-11/17/74	-	-
1:20-12/5/74	72.	80
12:5-12/18/74	83.	78
12/18-1/6/75	67.	75
1/8-1/9/75	55	63
1/13-1/15/75	a	0
1/9-1/13 and 1:15-1/22/75	a	0
1/22-2/7/75	a	0
2/7-2/22/75	10.	0-100
2/22-3/10/75	34.	100
3/10-3/25/75	35.	100
3/25-4/7/75	39	100
4/7-4/21/75	52.	100
4/21-5/5/75	67.	100
5/5-5/15/75	73	97
5/19-6/5/75	160.	87
6/5-6/23/75	140.	87
6/23-7/8/75	150.	82
7/8-7/22/75	240.	77
7/22-7/30/75	230.	69
8/5-8/21/75	150.	64
8/21-9/3/75	210.	60
9/3-9/11/75	170.	56
9/11-9/25/75	b	0
9/25-10/15/75	b	0
10/15-10/27/75	b	0
10/27-11/14/75	b	0
11/14-11/17/75	b	0
11/17-11/18/75	0.013	Critical
11/18-11/18/75	0.029	Critical
11/18-11/19/75	0.0783	1.2
11/19-11/19/75	0.433	15.0
11/19-11/20/75	1.43	21.1
11/20-11/21/75	1.83	51.4
11/21-11/21/75	2.09	49.4
11/21-11/22/75	2.83	58.0
11/22-11/22/75	3.56	61.0
11/22-11/23/75	2.75	63.0
11/23-11/23/75	2.72	64.0
11/23-11/24/75	3.21	66.0

Notes a Refueling/maintenance outage transpired 1/9 to 2/7/75.  
b Refueling/maintenance outage transpired 9/11 to 11/17/75.

**Table 3-12a**  
**IODINE-131 REACTOR WATER CONCENTRATIONS AT MONTICELLO**  
**DURING REFUELING/MAINTENANCE OUTAGES**  
**DATA SOURCE — EPRI/NES**

**Outage of January/February 1975**

<b>Sample Date</b> <b>Month/Day</b>	<b>Average I-131</b> <b>Reactor Water</b> <b>Concentration</b> <b>μCi/Kg</b>
1 9	54.
1 13	42
1 15	5.1
1 16	4.2
1 17	3.3
2 5	0.57
2 6	1.2
2 7	4.0

**Outage of September/November 1975**

9 11	190
9 15	14.
9 18	5.5
9 22	0.64
9 25	2.1

**Table 3-13**  
**AVERAGE I-131 VENTILATION RELEASE RATES**  
**PLANT — OYSTER CREEK (2/75-2/76)**  
**DATA SOURCE — EPRI/NES**

Average I-131 Release Rate,  $\mu\text{Ci/s}$

Nominal Sample Period Month/Day/Year	Reactor (0.001)	Turbine (0.001)	Radwaste (0.001)	Gland Seal and MVP (0.001)	Total Vent (0.001)
2 22-2:26:75	0.75	25.	0.46	NS	26
2 26-3 12:75	0.53	28.	0.68	NS	29
3 12-3:28:75	2.2	28.	0.49	NS	31.
3 29 -4:15:75	5.3	80.	NS	NS	91.
4 15-5 1:75	1.3	53.	3.4	NS	58.
5 1-5 15:75	0.50	4.6	NS	NS	5.1
5 15-5 29:75	0.20	0.42	0.048	NS	0.67
5 29-6 16:75	0.75	2.9	0.16	NS	3.9
6 16-6 30:75	1.1	4.6	0.15	1.4	5.9
6 30-7 17:75	1.1	2.7	0.46	1.22	4.3
7 17-8 5:75	0.42	5.6	1.01	6.6	7.1
8 5-8 21:75	0.33	7.5	0.72	2.2	8.6
8 21-9 8:75	0.10	3.3	1.9	5.5	5.5
9 8-9 29:75	0.18	4.7	1.9	NS	6.8
9 29-10 14:75	0.19	0.95	1.1	NS	2.2
10 14-10 31:75	0.086	NS	0.56	NS	-
10 31-11 14:75	0.096	7.7	0.24	0.55	8.0
11 14-12 4:75	0.94	4.3	1.0	5.6	6.3
12 4-12:18:75	0.19	7.0	0.19	2.0	7.5
12:18-1:5:76	1.2	4.5	NS	8.2	-
1 5-1:22:76	0.18	10.5	0.109	0.18	10.8
1 22-2:9:76	0.031	1.4	0.081	0.0052	1.5

Notes (1) Refueling maintenance outage transpired 3:29 to 5:29:75  
 (2) Refueling maintenance outage transpired 1:5:76 to 2:9:76 and continued to 3 14:76  
 (3) NS means no sample taken

**Table 3-13a**  
**AVERAGE I-131 VENTILATION RELEASE RATES**  
**PLANT — OYSTER CREEK (6/76-11/76)**  
**DATA SOURCE — EPRI/NES**

Average I-131 Release Rate,  $\mu\text{Ci/s}$

Nominal Sample Period Month/Day/Year	Reactor (0.001)	Turbine (0.001)	Radwaste (0.001)	Gland Seal and MVP (0.001)	Feedwater Pump/ Condensate Pump Room Exhaust (0.001)	Reheater Protection System Exhaust (0.001)
6:16-6:23:76	0.2388	11.49	0.4632	NS	NS	NS
6:23-6:30:76	0.2095	11.80	0.2714	0.4321	0.1425	NS
6:30-7:7:76	0.2168	21.79	0.5554	0.4887		NS
7:7-7:13:76	0.1049	14.19	0.6074	0.3397	0.1196	NS
7:13-7:20:76	0.1595	12.89	0.1463	0.6198		NS
7:20-7:27:76	0.1875	13.99	0.0930	0.4440	0.09894	0.691
7:27-8:3:76	8.258	6.464	1.0918	27.803		0.691
8:3-8:10:76	0.9990	13.71	0.5491	0.5602	0.2884	1.053
8:10-8:17:76	0.8125	21.20	0.2003	0.1118		1.053
8:17-8:24:76	0.7093	19.19	1.0176	0.6616	0.09512	1.683
8:24-8:30:76	1.029	11.22	0.9084	1.9281		1.683
8:30-9:7:76	0.3363	11.46	0.4060	1.3619	0.1776	1.690
9:7-9:16:76	0.3563	9.063	0.7462	1.6420		1.690
9:16-9:23:76	0.4762	16.72	1.3462	1.9936	0.1776	0.9508
9:23-9:30:76	0.0406	13.10	4.4096	2.4436		0.9508
9:30-10:7:76	0.2831	14.43	0.9657	1.5496	0.1438	1.006
10:7-10:14:76	0.2801	14.33	0.5554	1.5794		1.006
10:14-10:21:76	0.2641	13.51	0.4357	1.4095	0.1158	0.6566
10:21-10:28:76	0.2298	12.00	1.1554	1.2844		0.6566
10:28-11:4:76	0.2165	12.83	0.6646	1.2754	0.2292	0.7524
11:4-11:11:76	0.2244	12.11	0.5194	1.3470		0.7524
11:11-11:18:76	0.2288	11.39	0.7538	0.9476	0.2178	NS
11:18-11:30:76	0.1765	10.53	0.6169	1.2278		0.3783

Note: Plant shutdown for five days between 7.26 and 8.1.76

**Table 3-14**  
**ACTUAL I-131 VENTILATION RELEASES**  
**PLANT — OYSTER CREEK (2/75-2/76)**  
**DATA SOURCE — EPRI/NES**

Total I-131 Release, millicuries

Nominal Sample Period Month/Day/Year	Nominal Sample Time Days	Reactor	Turbine	Radwaste	Gland Seal & MVP	Total Vent
2 22-2 26 75	4	0.259	8.640	0.159	NS	8.986
2 26-3 12 75	14	0.641	33.87	0.823	NS	35.08
3 12-3 28 75	16	3.041	38.71	0.677	NS	42.85
3 29-4 15 75	17	7.785	117.5	NS	NS	133.7
4 15-5 1 75	16	1.797	73.27	4.700	NS	80.18
5 1-5 15 75	14	0.605	5.564	NS	NS	6.169
5 15-5 29 75	14	0.242	0.508	0.058	NS	0.810
5 19-6 16	18	1.166	4.510	0.249	NS	6.065
6 16-6 30 75	14	1.331	5.564	0.181	1.693	7.137
6 30-7 17 75	17	1.616	3.966	0.676	1.792	6.316
7 17-8 5 75	19	0.689	9.193	1.658	10.83	11.66
8 5-8 21 75	16	0.456	10.37	0.995	3.041	11.89
8 21-9 8 75	18	0.156	5.132	2.955	8.554	8.554
9 8-9 29 75	21	0.327	8.528	3.447	NS	12.34
9 29-10 14 75	15	0.246	1.231	1.426	NS	2.851
10 14-10 31 75	17	0.126	NS	1.823	NS	-
10 31-11 14 75	14	0.116	9.314	0.290	0.665	9.677
1 14-12 4 75	20	1.624	7.430	1.728	9.677	10.89
12 4-12 18 75	14	0.230	8.467	0.230	2.419	9.072
12 18-1 5 76	18	1.866	6.998	NS	12.75	-
1 5-1 22 76	17	0.264	15.42	0.160	0.264	15.86
1 22-2 9 76	18	0.048	2.177	0.126	0.008	2.333
Total I-131 Release millicuries		24.631	376.362	21.361	51.693	422.420
Total sample time, days		351	334	302	185	316

Notes: (1) Refueling maintenance outage transpired 3 29 to 5 29 75  
 (2) Refueling maintenance outage transpired 1 5 to 2 9 76 and continued to 3 14 76  
 (3) NS means no sample taken

**Table 3-14a**  
**ACTUAL I-131 VENTILATION RELEASES**  
**PLANT — OYSTER CREEK (6/76-11/76)**  
**DATA SOURCE — EPRI/NES**

Total I-131 Release, millicuries

Nominal Sample Period Month:Day:Year	Sample Period Days	Reactor	Turbine	Radwaste	Gland Seal & MVP	Feedwater Pump Condensate Pump Room Exhaust	Reheater Protection System Exhaust
6 16-6 23 76	7	0 1444	6 950	0 2802	NS	NS	NS
6 23-6 30 76	7	0 1267	7 136	0 1641	0 2613		NS
6 30-7 7 76	7	0 1311	13 176	0 3359	0 2956	0 1724	NS
7 7-7 13 76	6	0 05438	7 358	0 3149	0 1761		NS
7 13-7 20 76	7	0 09647	7 798	0 08847	0 3749	0 1343	NS
7 20-7 27 76	7	0 1134	8 460	0 05622	0 2685		
7 27-8 3 76	7	4 9947	3 909	0 6603	16 815	0 1197	0 8356
8 3-8 10 76	7	0 6042	8 294	0 3321	0 3388		
8 10-8 17 76	7	0 4914	12 824	0 1212	0 06759	0 5233	1 274
8 17-8 24 76	7	0 4290	11 604	0 6154	0 4001		1 890
8 24-8 30 76	6	0 5334	5 815	0 4709	0 9995		
8 30-9 7 76	8	0 2325	7 919	0 2806	0 9413	0 1151	
9 7-9 16 76	9	0 2771	7 047	0 5803	1 2768		2 482
9 16-9 23 76	7	0 2880	10 115	0 8142	1 2057		
9 23-9 30 76	7	0 02457	7 922	2 6669	1 4779	0 4604	1 150
9 30-10 7 76	7	0 1712	8 729	0 5840	0 9372		
10 7-10 14 76	7	0 1634	8 667	0 3359	0 9552		1 216
10 14-10 21 76	7	0 1597	8 170	0 2635	0 8525	0 1740	
10 21-10 28 76	7	0 1390	7 260	0 6988	0 7768		0 7943
10 28-11 4 76	7	0 1309	7 757	0 4020	0 7714	0 1400	
11 4-11 11 76	7	0 1357	7 322	0 3141	0 8146		0 9101
11 11-11 18 76	7	0 1384	6 888	0 4558	0 5731	0 2722	NS
11 18-11 30 76	12	0 1830	10 921	0 6396	1 2729	0 2258	0 3922
Total I-131 Release (millicuries)		9 7685	192 041	11 4574	31 8535	2 3421	10 9440
Total sample time (days)		167	167	167	167	160	126

Notes (1) Plant shutdown for five days between 7 26 and 8 3 76  
 (2) NS means no sample taken

**Summary of all Data:**

Total I-131 Release (millicuries)	344	568	328	835	234	109
Total sample time (days)	518	501	469	352	160	126

**Table 3-15**  
**IODINE-131 REACTOR WATER CONCENTRATIONS AND POWER**  
**LEVELS AT OYSTER CREEK (2/75-2/76)**  
**DATA SOURCE — EPRI/NES**

Nominal Sample Period Month/Day/Year	Average I-131 Reactor Water Concentration $\mu\text{Ci}/\text{kg}$	Thermal Power % of Rated
2-22-2-26 75	6.5	88
2-26-3-12 75	6.5	94
3-12-3-28 75	6.5	95
3-29-4-15-75	a	0
4-15-5-1-75	a	0
5-1-5-15-75	a	0
5-15-5-29-75	a	0
5-29-6-16-75	1.7	62
6-16-6-30-75	3.0	80
6-30-7-17-75	1.7	80
7-17-8-5-75	1.8	75
8-5-8-21-75	1.6	82
8-21-9-8-75	1.4	37
9-8-9-29-75	1.3	60
9-29-10-14-75	1.0	27
10-14-10-31-75	1.6	47
10-31-11-14-75	1.7	76
11-14-12-4-75	1.4	47
12-4-12-18-75	1.7	76
12-18-1-5-76	1.6	26
1-5-1-22-76	b	0
1-22-2-9-76	b	0

Notes a Refueling maintenance outage transpired 3-29 to 5-29 75

b Refueling maintenance outage transpired 1/5 to 2/9 76, outage continued to 3-14 76



**Table 3-15a**  
**IODINE-131 REACTOR WATER CONCENTRATIONS AND POWER**  
**LEVELS AT OYSTER CREEK (6/76-11/76)**  
**DATA SOURCE — EPRI/NES**

Nominal Sample Period Month Day:Year	Average I-131 Reactor Water Concentration $\mu\text{Ci/kg}$	Thermal Power % of Rated
6 16-6 23 76	1.43	90.3
6 23-6 30 76	1.47	91.3
6 30-7 7 76	1.29	89.8
7 7-7 13 76	1.36	92.2
7 13-7 20 76	1.49	91.4
7 20-7 27 76	1.52	80.6
7 27-8 3 76	0.45	33.0
8 3-8 10 76	1.53	91.9
8 10-8 17 76	1.71	95.9
8 17-8 24 76	2.17	96.3
8 24-8 30 76	1.47	96.7
8 30-9 7 76	1.35	95.8
9 7-9 23 76	1.14	83.4
9 23-9 30 76	1.19	97.0
9 30-10 7 76	1.93	93.3
10 7-10 14 76	1.81	96.4
10 14-10 21 76	2.18	94.4
10 21-10 28 76	2.05	99.4
10 28-11 4 76	3.10	96.7
11 4-11 11 76	2.36	99.8
11 11-11 18 76	2.36	97.5
11 18-11 30 76	2.05	95.6

Table 3-15b  
 IODINE-131 REACTOR WATER CONCENTRATIONS AT OYSTER CREEK  
 DURING REFUELING/MAINTENANCE OUTAGES  
 DATA SOURCE — EPRI/NES

Outage of March/May 1975	
Nominal Sample Period Month/Day	Average I-131 Reactor Water Concentration $\mu\text{Ci/Kg}$
4:2 -4:8	3.9
4:9 -4:15	0.70
4:16-4:22	0.44
4:23-4:29	0.053
4:30-5:6	0.016
5:7 -5:13	0.020
5:14-5:20	0.022
5:21-5:27	0.64
Outage of January/March 1976	
12:29-1:5	0.13*
1:5 -1:12	0.11
1:12-1:19	0.095
1:19-1:26	0.080

\*Plant down for refueling and condenser maintenance 12:26:75;  
 thermal power (percent of rated) was 26% during period from  
 12:18:75 to 1:5:76.

**Table 3-16**  
**IODINE-131 REACTOR WATER CONCENTRATION, POWER LEVELS AND STEAM FLOW RATES**  
**DURING STARTUP (AFTER 75 DAY SHUTDOWN) AT OYSTER CREEK STATION**  
**DATA SOURCE—EPRI/NES**

Date		I-131 Concentration	Power Level	Steam Flow
Month/Day/	Hour	In Reactor Water,	% of Rated	LB/hr x 10 <sup>4</sup>
1976		$\mu\text{Ci/Kg}$		
3 14	0254	—	41.9	2.89
	0820	0.81	—	—
	1054	—	41.8	2.89
	1314	—	45.0	3.13
	1404	—	46.2	3.21
	1755	0.85	—	—
	1959	—	45.2	3.14
3 15	0115	0.86	—	—
	1259	—	44.5	3.09
	1020	0.83	—	—
	1059	—	45.9	3.16
	1559	—	47.7	3.28
	1714	—	45.8	3.19
	1732	0.78	—	—
1914	—	45.8	3.18	
3 16	0127	0.77	—	—
	0214	—	45.0	3.12
	0714	—	46.4	3.20
	0835	0.82	—	—
	1544	—	45.0	3.13
	1604	—	49.4	3.40
	1713	0.88	—	—
2004	—	49.1	3.39	

Table 3-16 (Continued)  
 IODINE-131 REACTOR WATER CONCENTRATION, POWER LEVELS AND STEAM FLOW RATES  
 DURING STARTUP (AFTER 75 DAY SHUTDOWN) AT OYSTER CREEK STATION  
 DATA SOURCE—EPRI/NES

Date Month/Day/Hour 1976	I-131 Concentration in Reactor Water, $\mu\text{Ci/Kg}$	Power Level % of Rated	Steam Flow $\text{LB/hr} \times 10^4$
3 17	0112	—	—
	0304	—	—
	0830	0.86	49.1
	1204	—	—
	1304	—	49.1
	1404	—	50.5
	1504	—	54.6
	2004	—	57.2
3 18	0304	—	—
	1000	0.92	58.3
	1104	—	—
	1910	0.96	57.7
	2024	—	—
3 19	0324	—	—
	0820	0.95	56.0
	1049	—	—
	1909	—	55.9
3 20	0309	—	—
	1109	—	55.8
	2009	—	55.8
3 21	0309	—	—
	1109	—	55.8
	2009	—	55.8
	2209	—	55.4
	2309	—	55.6
		70.3	3.94

Table 3-16 (Continued)  
 IODINE-131 REACTOR WATER CONCENTRATION, POWER LEVELS AND STEAM FLOW RATES  
 DURING STARTUP (AFTER 75 DAY SHUTDOWN) AT OYSTER CREEK STATION  
 DATA SOURCE—EPRI/NES

Date Month/Day/Hour 1976	I-131 Concentration in Reactor Water, $\mu\text{Ci/KG}$	Power Level % of Rated	Steam Flow $\text{LB/hr} \times 10^4$
3 22	0009	—	5 15
	0109	—	5 22
	0959	—	5 08
	1959	—	4 95
3 23	0259	—	4 95
	1059	—	4 94
	1909	—	4 94
3 24	0309	—	4 85
	0829	1 5	—
	1209	—	4 87

**Table 3-17**  
**IODINE-131 AIRBORNE CONCENTRATIONS IN BUILDING EXHAUSTS AND GLAND SEAL STEAM**  
**EXHAUST DURING STARTUP (AFTER 75 DAY SHUTDOWN) AT OYSTER CREEK**  
**DATA SOURCE—EPRI/NES**

**I-131 CONCENTRATION,  $\mu\text{Ci/cc}$**

Sample Time Month/Day/Hour 1976		Reactor	Turbine	Radwaste	Gland Seal Steam
3 15	0030	—	8.8 (-12)	—	—
	0823	—	—	—	2.6 ( 10)
	1624	—	7.7 ( 12)	—	—
3 16	0027	—	4.2 (-12)	—	—
	0043	—	—	3.2 ( 12)	—
	0852	—	3.2 ( 12)	—	—
	0910	—	—	—	4.6 ( 10)
	1700	—	1.6 ( .11)	—	4.9 ( 10)
	3 17	0100	—	1.4 ( 11)	4.4 ( 12)
	0900	—	1.2 (-11)	—	4.3 ( 10)
	1110	—	—	5.4 ( 12)	—
	1745	—	—	—	6.3 ( 10)
	1750	—	6.5 (-11)	—	—
	1800	3.0 (-12)	—	—	—
	1819	—	—	4.8 (-12)	—
3 18	0029	—	—	—	5.4 ( 10)
	0041	—	7.8 (-11)	—	—
	0047	2 ( 12)	—	—	—
	0056	—	—	5.2 ( 12)	—
	0900	—	1.2 (-10)	—	6.7 ( 10)
	0930	2 ( 12)	—	—	—
	1645	—	—	—	6.8 ( 10)
	1650	—	1.5 ( 10)	—	—
	1700	2 ( 12)	—	—	—
	1800	—	—	4.0 (-12)	—
3 19	0940	—	—	—	6.9 ( 10)
	0941	—	1.4 (-10)	—	—
	0948	3.5 ( 12)	—	—	—
	0956	—	—	3.6 (-12)	—
3 24	1326	—	—	—	7.8 ( 10)
	1345	—	3.0 (-10)	—	—
	1355	3.5 ( 12)	—	—	—
	1425	—	—	1.0 (-11)	—
	2003	—	—	—	1.2 (-9)
	2100	—	2.7 (-10)	—	—
	2200	—	—	1.2 (-11)	—

cbm

**Table 3-18**  
**SUMMARY OF ACTUAL I-131 VENTILATION MEASUREMENTS BY EPR/NES**  
**AT VERMONT YANKEE, MONTICELLO AND OYSTER CREEK**

	PLANT					
	Vermont Yankee		Monticello		Oyster Creek	
<b>Total I-131 Release, millicuries (sample time, days)</b>						
<b>Power Generation Operations</b>						
<b>Release From:</b>						
Reactor Building	39.	(446)	1028.3	(253.5)	13.89	(255)
					9.77	(167)
Turbine Building	18.	(446)	828.0	(267.0)	161.9 <sup>a</sup>	(238)
					192.0	(167)
Radwaste Building	18.	(425)	69.4	(264.4)	16.32	(237)
					11.5	(167)
Gland Seal Steam Exhaust	34.	(379)	No Data		31.9	(167)
<b>Refueling/Maintenance Outage</b>						
Reactor Building	113.	(56)	31.2	(29)	10.43	(61)
			60.4	(44)	0.312	(35)
Turbine Building	9.	(56)	52.3	(29)	196.8	(61)
			9.1	(64)	17.6	(35)
Radwaste Building	14.	(53)	1.24	(29)	4.76	(30)
			3.99	(64)	0.286	(35)
Mechanical Vacuum Pump	19.	(39)	No Data		No Data	
					0.272	(35)

Notes a Total includes all chemical species of I-131  
 b Excludes I-131 releases from feedwater pump/condensate pump room exhaust and reheater protection system exhaust because no samples were taken.  
 c Excludes I-131 releases from feedwater pump/condensate pump room exhaust and reheater protection system exhaust, these releases are small, namely 2.34 mCi (160 days) and 10.9 mCi (126 days), respectively

**Table 3-19**  
**SUMMARY OF ACTUAL I-131 VENTILATION MEASUREMENTS BY**  
**EPRI/NES AT VERMONT YANKEE, MONTICELLO AND OYSTER CREEK**  
**ADJUSTED TO 300 DAYS OF POWER OPERATIONS AND 1% I-131 CARRYOVER**

Release From	PLANT		
	Vermont Yankee	Monticello	Oyster Creek
	Total I-131 Release, millicuries		
	Power Generation Operations		
Reactor	26.3	1217	16.8
Turbine	31.1	2061	127.0 <sup>a</sup>
Radwaste	13.0	78.7	20.6
Gland Seal Steam	27.1	No Data	78.8
Sub-total	97.5	3357	243.2
	Refueling Maintenance Outages		
Reactor	112.5	49.5	5.37
Turbine	21.8	68.3	46.6
Radwaste	14.3	2.6	13.4
Mechanical Vacuum Pump	215	No Data	0.12
Sub-total	364	120	65.5
Total Annual Release	462	3477	309

a. Total includes all chemical forms of I-131

b. Includes releases from reheater protection system and feedwater condensate pump equipment compartment

c. Annual includes 300 days of power operations plus one R M outage



Table 3-20  
SUMMARY OF NRC MEASUREMENTS OF I-131 RELEASES AT SIX BWR'S

I-131 Release Rate,  $\mu\text{Ci/s}$ 

Plant	Operating Mode	Reactor	Turbine	Radwaste	Sample Time (Days)
Oyster Creek	Normal	0 0016	0.018	0 00067	14
	Normal	0 0014	0 043	0 00053	14
	Normal	0 0025	NM	NM	14
	Normal	0 0081	0 007	0 0019	14
	Containment Purge	0 14	0 087	0 0011	2
	Refueling	0 011	0 080	0 0025 <sup>d</sup>	45
Monticello	Normal <sup>a</sup>	0 0070	0 0050	0 0064	29 hours
	Normal		0.0017 <sup>c</sup>		42 <sup>a</sup>
Dresden 2	Normal <sup>a</sup>	0 0019	NM	NM	24 hours
	Normal	NM	0 00028	NM	15
	Normal	NM	0 00027	NM	14
Dresden 3	Normal <sup>a</sup>	0 0061	NM	NM	24 hours
	Normal	NM	0.00065	NM	13
	Normal	NM	0.0008	NM	14
Dresden 2 & 3	Normal	NM	0 0006	NM	42 <sup>a</sup>
Quad Cities 1	Normal	0 0038	NM	NM	1
	Normal	NM	0 00047	—	14
Quad Cities 2	Normal	0 00023	NM	NM	1

Notes a. First 31 days only

b. In conjunction with iodine species measurement, assume normal operations

c. Includes all buildings

d. Approximate value (NEDO 21159 March 1976 Figure 3-20)

(1) Measurements made during 1972 except for Quad Cities 1, 2 plants which were investigated in 1973

(2) NM means no measurement

**Table 3-21**  
**SUMMARY OF AIRBORNE I-131 RELEASES; MEASUREMENTS BY GENERAL ELECTRIC COMPANY**

**I-131 RELEASE RATE,  $\mu\text{Ci/s}$**

Plant	Mode of Operation	Reactor	Turbine	Radwaste	Gland Seal Exhaust	Sample Period (hrs)	Sample Time Month Year	I-131 Coolant Concentration ( $\mu\text{Ci/cc}$ )
Dresden 2	Normal	0.005	—	—	NM	2	Jan 1971	0.0023
	Normal	NM	0.006	—	NM	15	Feb 1971	0.0023
Nine Mile Point 1	Normal	NM	0.0016	NM	NM	NA	Dec 1971	0.0017
	Normal	5.57 E-4 (29.7)	5.57 E-3 (42.4)	1.00 E-3 <sup>b</sup> (50.9)	—	a	March-April 74	0.002
	Normal	6.64 E-4 (44.9)	7.3 E-3 (6.7)	4.04 E-4 (44.1)	—	a		
	Normal	4.6 E-4 (66.2)	4.54 E-3 (64.2)	4.2 E-5 (48.5)	—	a		
	Normal	7.97 E-4 (5.3)	7.02 E-3 (65.3)	1.0 E-5 (43.2)	—	a		
	Normal	7.1 E-4 (15.8)	—	—	—	a		
	Shutdown	4.48 E-3 (126.3)	1.38 E-3 (47.7)	5.2 E-5 (75.1)	—	a		
	Shutdown	1.79 E-3 (16.2)	7.81 E-3 (71.8)	1.6 E-4 (43.2)	—			
Oyster Creek	Normal	0.00144	0.0009	0.00030	0.006	1	April 1972	0.0075
			0.0029			1		
Millstone Point 1	Normal	0.00165	NM	0.00105	0.000192	1	July 1972	0.0034
	Normal	0.00146	NM	—	—	1		
	Normal	—	0.0026	—	—	9		
	Normal	0.00323	—	NM	—	1		
	Normal	0.0058	—	NM	—	1		
	Shutdown				c		Sept 1972	0.030 to 0.232

Notes: a. Sample period (hrs) in parenthesis  
 b. Concentrator steam leak at about this time  
 c. Approximately 2.1 millicuries of I-131 released during 70 minutes of mechanical vacuum pump operation on September 1, 1972. The plant was shut down on August 29, 1972  
 (1) NM - Not Measured  
 (2) NA - Not Available




Figure 3-1. Calendar Quarterly Total Plant Ventilation Releases of I-131 versus Time, Pilgrim 1 (Reactor, Turbine and Radwaste Buildings)




Figure 3-2 Accumulative Probability Distribution of Calendar Quarter I-131 Ventilation Releases, Pilgrim 1 (Reactor, Turbine and Radwaste Buildings, October 1974 to December 1976)





Figure 3-3. Calendar Quarter Reactor Building Ventilation Release of I-131 Versus Time, Dresden 2/3



NEDO-21159-2

Figure 3-4. Accumulative Normal Probability Distribution of Calendar Quarter Reactor Building Ventilation Releases of I-131 Dresden 2,3 (January 1973 to December 1976)




Figure 35 Calendar Quarter Reactor Building Ventilation Release of I-131 versus Time, Quad Cities 1 2




Figure 36. Accumulative Normal Probability Distribution of Calendar Quarter Reactor Ventilation Releases of I-131, Quad Cities 1-2 (July 1973 to June 1977)






Figure 3-7. Calendar Quarter Total Plant Ventilation Release of I-131 versus Time, Monticello (Reactor, Turbine and Radwaste Buildings)




Figure 3-8. Accumulative Lognormal Probability Distribution of Calendar Quarter 1-131 Total Plant Ventilation Releases, Monticello (Reactor, Turbine and Radwaste Buildings, January 1974 to December 1976)

#### 4. CHEMICAL FORM OF IODINE-131 RELEASES

The following material on iodine-131 chemical form updates data previously reported in NEDO-21159, March 1976, Chapter 4.

The chemical form of radioiodine releases is an important factor in a realistic and proper environs dose impact assessment. The specification of I-131 species is in accord with Appendix I of 10CFR50 which requires realistic dose evaluations (see Appendix 2A). From BWR operating plant experience, I-131 exists in several forms, both inorganic and organic. Inorganic iodine forms of interest are particulate, elemental ( $I_2$ ), and hypoiodous acid (HOI). For ingestion dose evaluations, the amount of elemental I-131 release is needed (Reference 4-1). Organic iodine (methyl iodide) is not a significant contributor to the milk pathway dose. However,  $CH_3I$  would contribute to an inhalation dose. Methyl iodide is known to have a much smaller deposition velocity than elemental iodine, thus it does not readily deposit on vegetation which could be eaten by cows and found in milk (References 4-2, 4-3, 4-4, and 4-5). The deposition velocity for  $I_2$  is more than 1000 times greater than for  $CH_3I$ , and more than 10 times greater than for iodine in particulate form. The deposition velocity for HOI is unknown.

The importance of iodine chemical form in BWR releases has been recognized by the NRC. In 1972, the NRC (then AEC) conducted measurements of BWR releases which included measurements of radioiodine species. Similar species measurements with improved techniques were conducted in 1973. In addition to the NRC measurements, GE has independently conducted species measurements at a few BWR plants. The most extensive measurements of radioiodine species have been sponsored by EPRI. This chapter includes EPRI results through December, 1976.

The chemical forms of iodine-131, or species thereof, are defined on the basis of samplers previously described (References 4-6 through 4-11). All the samplers consist of a series of adsorbents which selectively identify the iodine species in the direction of air flow as follows:

<i>I-131 species</i>	<i>adsorbent</i>
particulate	filter paper, Flanders F-700
elemental ( $I_2$ )	cadmium iodide on chromasorb - p
hypoiodous acid (HOI)	4-iodophenol on alumina
organic ( $CH_3I$ )	KI or TEDA impregnated charcoal (or silver zeolite)

Thus the iodine species are defined in terms of the adsorbents.

At this time there is some question about the actual presence of HOI. The chemical nature of the HOI has not been positively determined and is so-called on the basis of circumstantial evidence. In this document the iodine species collected on the third adsorbent is called HOI, but with serious reservations as to its existence. Also, in this document  $CH_3I$  is used as a synonym for organic iodine. However, organic iodine species other than  $CH_3I$  have not been fully determined in operating plant atmospheres.

The chemical form of I-131 varies significantly between BWR operating modes. The relative amounts of elemental and organic iodine change from normal power generation operations to refueling/maintenance outages. Furthermore, the I-131 species concentrations are different for each of the principal building ventilation exhausts and the gland seal/mechanical vacuum pump exhausts. The available measurements on I-131 species are listed in Tables 4-1, 4-2, 4-5, and 4-6 are for the reactor, turbine, radwaste, and gland seal/MVP exhausts, respectively. Tables 4-3 and 4-4 list results, unique to Oyster Creek, for I-131 species of the Feedwater Pump and Condensate Pump room exhaust and the Reheater Protection System and Lube Oil Storage Area exhaust. The total I-131 release from both these exhausts is less than 10% of the turbine building release.

Appendix 2B summarizes I-131 species data for in-plant compartments of the BWR reactor and turbine buildings. In addition I-131 species measurements at the end of the SJAE delay line are listed in Appendix 2B. This appendix

contains data for the reader's convenience; the information was not used to calculate I-131 species concentrations in ventilation exhausts.

Table 4-7 summarizes the I-131 chemical form data according to plant. The data for normal power generation operations are separate from data for refueling/maintenance outages.

The concentrations of particulate, elemental, HOI and  $\text{CH}_3\text{I}$  recommended for environmental impact evaluations are listed in Table 4-8.

The species measurements were evaluated to obtain the best single estimate of the I-131 chemical form in each building ventilation exhaust during both power generation operations (including brief plant shutdowns) and refueling/maintenance outages. Inspection of the data indicated that species concentrations were relatively similar for a given plant, but significant differences existed between plants. For example, the average  $\text{CH}_3\text{I}$  concentration during power generation operations in the reactor building ventilation exhaust at Quad Cities 1 is approximately a factor of 1.5 greater than at Quad Cities 2. The assumption was made that the available measurements constitute a random selection of operating BWR's. For each plant, the relative I-131 concentrations (percentages of I-131 released in each ventilation exhaust) were determined by weighting the reported results according to sample time. This assumes that a sample of long-duration yields more characteristic information than a short-time sample (Reference 4-12). The weighting of data according to sample time is analogous to taking samples for a constant sample period but weighting the mean results according to the number of samples. The greater the number of samples (equivalent to longer sample times), the more certain one becomes that the sample mean will be close to the (unknown) population mean. This effect is based on the central limit theorem of statistics (Reference 4-13). After a set of weighted mean concentrations were determined for each plant and exhaust, these results were simply averaged (the arithmetic mean calculated) in order to establish the best single estimate of the average I-131 species concentrations.

The above data reduction procedure gives equal weight to results from each BWR in spite of the number of samples at each BWR. This may be considered a shortcoming to the results reported here. However, the data reduction method favors a best-estimate on the basis of measurements from many different BWR's rather than a large number of measurements from a few BWR plants.

A summary of the number of data points and plants is presented in Table 4-9. There are a total of 14 domestic BWR's that have commenced commercial operations since 1969 (starting with Oyster Creek) and with more than one year of commercial operation, but excluding the Browns Ferry plants. The iodine-131 species measurements have been made at more than half of the domestic BWR reactor buildings, and at about one-fifth of the turbine and radwaste building exhausts.

The I-131 species data were also evaluated to determine the sensitivity of the reported concentrations to the various variables. The I-131 species concentrations were found to be independent of the following variables:

1. total I-131 release rate,
2. total I-131 activity collected on sampler,
3. sample time,
4. sampling by different organizations,
5. sampling at different times after the plant has commenced commercial operation.

Furthermore, a consistent set of ratios between the species for a given plant, ventilation exhaust, operating condition was not apparent. The I-131 species data were found to be relatively consistent for each plant, ventilation exhaust, and plant mode of operation.

It is beyond the scope of this document to present analyses of variance or estimates of confidence intervals for I-131 species.

## 4.1 REFERENCES

- 4-1 U.S. Nuclear Regulatory Commission, March 1976, "Calculation of Annual Average Doses to Man from Routine Releases of Reactor Effluents for the Purpose of Evaluating Compliance with 10CFR50, Appendix I," Regulatory Guide 1.109 p. 54.
- 4-2 Bunch, D. F., editor, 1966, "Controlled Environmental Radioiodine Tests Progress Report No. 2," U.S. Atomic Energy Commission, Idaho Operations Office, IDO-12053.
- 4-3 Hoffman, F. O., 1973, "Environmental Variables Involved with the Estimation of the Amount of  $^{131}\text{I}$  in Milk and the Subsequent Dose to the Thyroid," Institut für Reaktorsicherheit der Technischen Überwachungs-Vereine e.V., IRS-W-6.
- 4-4 Hoffman, F. O., 1975, "A Reassessment of the Parameters Used to Predict the Environmental Transport of  $^{131}\text{I}$  from Air to Milk," Institut für Reaktorsicherheit der Technischen Überwachungs-Vereine e.V., IRS-W-13.
- 4-5 Hoffman, F. O., 1977 "A Reassessment of the Deposition Velocity in the Prediction of the Environmental Transport of Radioiodine from Air to Milk," Health Physics 32, 437.
- 4-6 Cartan, F. O., H. R. Beard, F. A. Duce, J. H. Keller, 1968, "Evidence for the Existence of Hypoiodous Acid as a Volatile Iodine Species Produced in Water-Air Mixtures," 10th Air Cleaning Conference (CONF-680821), p. 342.
- 4-7 Nuclear Environmental Services, 1975, "Plans and Procedures Evaluation of Radioiodine Sources and Other Radionuclide Effluents at Nuclear Power Stations," Report to the Electric Power Research Institute (under Contract RP-274-1).
- 4-8 Marrero, T. R., 1976, "Airborne Releases from BWR's for Environmental Impact Evaluations," General Electric Company, Licensing Topical Report, NEDO-21159, Appendix A.
- 4-9 Emel, W. A., 1976, "A Program for Determining the Chemical Species of Radioiodine in Atmospheric Effluents from LWR Power Plants and Their Persistence in the Nearby Environment," A Final Report by Nuclear Environmental Services to the Atomic Industrial Forum.
- 4-10 Emel, W. A., D. Hetzer, C. A. Pelletier, E. D. Barefoot, J. E. Cline, 1976, "An Airborne Radioiodine Species Sampler and Its Application for Measuring Removal Efficiencies of Large Charcoal Adsorbers for Ventilation Exhaust Air," 14th ERDA Air Cleaning Conference, Sun Valley, Idaho.
- 4-11 Nuclear Environmental Services, 1977, "Sources of Radioiodine at Boiling Water Reactors," Appendix D, Draft report to the Electric Power Research Institute (under Contract RP-274-1).
- 4-12 Healy, J. W., 1970, *Los Alamos Handbook of Radiation Monitoring*, (Los Alamos Scientific Laboratory of the University of California, Los Alamos, New Mexico, LA-4400), pp. 83-86.
- 4-13 Ostle, B. and R. W. Mensing, 1975, *Statistics in Research*, (The Iowa State University Press, Ames, Iowa), p. 76.
- 4-14 Voilleque, P., (NES-SAI), 8 April 1977, Speed Message to M. Bell (NRC).

Table 4-1  
 SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN  
 BWR REACTOR BUILDING VENTILATION EXHAUSTS

Plant	Sample Period Month/Day/Year	Particulate	Species, % of I-131 Release			Measurements By	Sample Time Days	Reference
			I <sub>2</sub>	HOI	CH <sub>3</sub> I			
Plant Mode: Power Generation Operations								
Nine Mile Point 1	3-24-74	11.0	44.0	3.0	42.0	GE	187	3-55
Nine Mile Point 1	3-29-74	25.0	41.0	1.0	34.0	GE	022	3-55
Oyster Creek	2-22 — 2-27-75	49.0	17.0	2.0	34.0	EPRI(NES)	5	3-44
Oyster Creek	9-29 — 10-14-75	2.6	9.7	19.4	68.2	EPRI(NES)	15	3-44
Oyster Creek	12-4 — 12-18-75	20.5	26.0	21.9	31.5	EPRI(NES)	14	3-44
Oyster Creek	6-16 — 6-23-76	1.0	24.0	12.0	64.0	EPRI(NES)	7	3-45
Oyster Creek	6-23 — 6-30-76	10.0		69	21.0	EPRI(NES)	7	3-45
Oyster Creek	6-30 — 7-7-76	17.0		62	21.0	EPRI(NES)	7	3-45
Oyster Creek	7-7 — 7-13-76	7.0	27.0	40.0	25.0	EPRI(NES)	6	3-45
Oyster Creek	7-13 — 7-20-76	17.0	24.0	35.0	24.0	EPRI(NES)	7	3-45
Oyster Creek	7-20 — 7-27-76	13.0	30.0	33.0	24.0	EPRI(NES)	7	3-45
Oyster Creek	7-27 — 8-3-76	8.0	26.0	35.0	31.0	EPRI(NES)	7	3-45
Oyster Creek	8-3 — 8-10-76	2.0	25.0	46.0	27.0	EPRI(NES)	7	3-45
Oyster Creek	8-10 — 8-17-76	5.0	24.0	39.0	32.0	EPRI(NES)	7	3-45
Oyster Creek	8-17 — 8-24-76	6.0	19.0	38.0	37.0	EPRI(NES)	7	3-45
Oyster Creek	8-24 — 8-30-76	5.0	11.0	17.0	67.0	EPRI(NES)	6	3-45
Oyster Creek	8-30 — 9-7-76	11.0	24.0	41.0	24.0	EPRI(NES)	8	3-45
Oyster Creek	9-7 — 9-16-76	7.0	26.0	46.0	21.0	EPRI(NES)	9	3-45
Oyster Creek	9-16 — 9-23-76	9.0	26.0	39.0	25.0	EPRI(NES)	7	3-45
Oyster Creek	9-23 — 9-30-76	4.0	28.0	37.0	31.0	EPRI(NES)	7	3-45
Oyster Creek	9-30 — 10-7-76	6.0	35.0	34.0	25.0	EPRI(NES)	7	3-45
Oyster Creek	10-7 — 10-14-76	10.0	27.0	41.0	22.0	EPRI(NES)	7	3-45
Oyster Creek	10-14 — 10-21-76	11.0	33.0	29.0	27.0	EPRI(NES)	7	3-45
Oyster Creek	10-21 — 10-28-76	10.0	34.0	31.0	25.0	EPRI(NES)	7	3-45
Oyster Creek	10-28 — 11-4-76	13.0	35.0	27.0	25.0	EPRI(NES)	7	3-45
Oyster Creek	11-4 — 11-11-76	16.0	33.0	26.0	25.0	EPRI(NES)	7	3-45
Oyster Creek	11-11 — 11-18-76	15.0	40.0	21.0	24.0	EPRI(NES)	7	3-45
Oyster Creek	11-18 — 11-30-76	5.0	37.0	30.0	29.0	EPRI(NES)	12	3-45
Dresden 2	1973	8.0	45.0	15.0	32.0	AEC	1	3-49
Dresden 2	:973	24.0	56.0	7.0	13.0	EPA-NRC	NA	3-52

Table 4-1  
 SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN  
 BWR REACTOR BUILDING VENTILATION EXHAUSTS (Continued)

Plant	Sample Period Month/Day/Year	Particulate	Species, % of I-131 Release			Measurements By	Sample Time Days	Reference
			I <sub>2</sub>	HOI	CH <sub>3</sub> I			
Dresden 3	1973	0.0	71.0	18.0	11.0	AEC	1	3-49
Dresden 3	1973	4.0	54-58	14.0	38-42	EPA-NRC	NA	3-52
Monticello	1973	10.3	29.3	21.7	38.7	EPA-NRC	NA	3-52
Monticello	11-18 — 11-19-74	27.3	45.1	10.6	17.0	EPRI(NES)	1	3-44
Monticello	1-8 — 1-9-75	25.4	53.6	13.3	7.7	EPRI(NES)	1	3-44
Monticello	7-31 — 8-3-75	22.3	34.4	30.6	11.6	EPRI(NES)	3	3-44
Monticello	9-3 — 9-5-75	27.8	41.5	22.2	8.0	EPRI(NES)	2	3-44
Quad Cities 1	6-27 — 7-9-74	7.8	15.1	19.4	57.7	EPA-NRC	12	4-14
Quad Cities 1	7-9 — 7-17-74	8.6	25.8	15.3	50.4	EPA-NRC	8	4-14
Quad Cities 1	7-17 — 7-25-74	10.1	24.0	19.4	46.6	EPA-NRC	8	4-14
Quad Cities 1	7-25 — 8-6-74	20.0	22.9	15.9	41.1	EPA-NRC	12	4-14
Quad Cities 1	8-6 — 8-20-74	19.0	36.6	26.7	17.7	EPA-NRC	14	4-14
Quad Cities 1	8-28 — 9-12-74	3.6	15.6	25.6	55.2	EPA-NRC	15	4-14
Quad Cities 1	9-12 — 9-19-74	2.6	25.7	25.3	46.3	EPA-NRC	7	4-14
Quad Cities 1	9-19 — 9-26-76	1.4	9.3	9.9	79.4	EPA-NRC	7	4-14
Quad Cities 1	9-26 — 10-1-74	13.4	13.6	14.8	58.2	EPA-NRC	5	4-14
Quad Cities 1	10-1 — 10-10-74	7.0	17.4	18.9	56.7	EPA-NRC	9	4-14
Quad Cities 1	10-10 — 10-17-74	12.9	21.2	18.6	47.4	EPA-NRC	7	4-14
Quad Cities 1	10-17 — 10-24-74	8.0	33.2	17.8	40.9	EPA-NRC	7	4-14
Quad Cities 2	6-27 — 7-9-74	12.6	39.4	16.7	31.2	EPA-NRC	12	4-14
Quad Cities 2	7-9 — 7-17-74	12.9	33.0	21.4	32.7	EPA-NRC	8	4-14
Quad Cities 2	7-17 — 7-25-74	13.4	34.3	21.2	31.1	EPA-NRC	8	4-14
Quad Cities 2	7-25 — 8-6-74	14.8	37.8	24.8	22.7	EPA-NRC	12	4-14
Quad Cities 2	8-6 — 8-20-74	18.0	41.8	26.1	14.1	EPA-NRC	14	4-14
Quad Cities 2	8-23 — 9-12-74	5.5	25.7	31.3	37.5	EPA-NRC	15	4-14
Quad Cities 2	9-12 — 9-19-74	3.7	23.5	28.0	44.8	EPA-NRC	7	4-14
Quad Cities 2	9-19 — 9-26-74	2.0	16.0	20.5	61.6	EPA-NRC	7	4-14
Quad Cities 2	9-26 — 10-1-74	10.1	23.5	22.2	44.2	EPA-NRC	5	4-14
Quad Cities 2	10-1 — 10-10-74	13.4	17.9	18.3	50.4	EPA-NRC	9	4-14
Quad Cities 2	10-10 — 10-17-74	16.5	22.9	16.8	43.8	EPA-NRC	7	4-14
Quad Cities 2	10-17 — 10-24-74	5.7	39.4	20.4	34.4	EPA-NRC	7	4-14
Quad Cities 2	10-24 — 10-31-74	7.7	44.4	25.4	22.6	EPA-NRC	7	4-14
Vermont Yankee	6-19 — 6-22-74	3.7	23.5	14.5	59.4	YAEC(NES)	3	3-44

A.R.

NEDO-21159-2

Table 4-1  
**SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN  
 BWR REACTOR BUILDING VENTILATION EXHAUSTS (Continued)**

Plant	Sample Period Month/Day/Year	Particulate	Species, % of I-131 Release			Measurements By	Sample Time Days	Reference
			I <sub>2</sub>	HOI	CH <sub>3</sub> I			
Vermont Yankee	9-12 — 9-13-74	7.4	24.7	17.7	50.0	EPRI(NES)	1	3-44
Vermont Yankee	10-10 — 10-11-74	6.6	6.2	6.8	80.4	EPRI(NES)	1	3-44
Vermont Yankee	9-19 — 9-22-75	4.8	34.6	(18.5)	(42.1)	EPRI(NES)	3	3-44
Vermont Yankee	9-22 — 10-7-75	16.1	26.2	(15.0)	(57.7)	EPRI(NES)	15	3-44
Vermont Yankee	10-7 — 10-21-75	<15.0	<15.0	(15.0)	(100.0)	EPRI(NES)	14	3-44
Vermont Yankee	11-7 — 11-8-75	<7.0	25.3	(18.0)	(74.7)	EPRI(NES)	1	3-44
<b>Plant Mode: Refueling/Maintenance Outage</b>								
Oyster Creek	12-18 — 1-5-76	7.1	11.1	27.3	54.5	EPRI(NES)	18	3-44
Oyster Creek	1-5 — 1-22-76	5.1	13.7	52.7	28.5	EPRI(NES)	17	3-44
Oyster Creek	1-22 — 2-9-76	<6.0	11.8	32.8	55.4	EPRI(NES)	18	3-44
Monticello	1-13 — 1-15-75	6.9	61.0	12.6	19.6	EPRI(NES)	2	3-44
Monticello	9-11 — 9-25-75	6.8	33.8	41.7	17.6	EPRI(NES)	14	3-44
Monticello	10-15 — 10-27	9.7	23.3	(16.5)	(64.9)	EPRI(NES)	12	3-44
Monticello	10-27 — 11-14	31.2	9.1	(18.8)	(59.6)	EPRI(NES)	18	3-44
Vermont Yankee	10-31 — 11-1-74	2.0	16.0	59.0	23.0	EPRI(NES)	1	3-44

NOTES (1) NA - Data Not Available

(2) Numbers in parenthesis indicate questionable quality of sample adsorbent media. IPH

NEDO-21159-2

4-6



Table 4-2  
 SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN  
 BWR TURBINE BUILDING VENTILATION EXHAUSTS

Plant	Sample Period Month/Day/Year	Particulate	Species, % of I-131 Release			Measurements By	Sample Time Days	Reference
			I <sub>2</sub>	HOI	CH <sub>3</sub> I			
Plant Mode: Power Generation Operations								
Nine Mile Point 1	3-24-74	18.0	68.0	2.0	12.0	GE	028	3-55
Oyster Creek	2-22 — 2-27-75	27.0	47.0	19.0	7.0	EPRI(NES)	5	3-44
Oyster Creek	9-8 — 9-29-75	13.5	46.1	(17.4)	(23.0)	EPRI(NES)	21	3-44
Oyster Creek	9-29 — 10-14-75	11.8	44.1	(14.7)	(29.4)	EPRI(NES)	15	3-44
Oyster Creek	10-31 — 11-14-75	22.5	46.8	(1.2)	(29.5)	EPRI(NES)	14	3-44
Oyster Creek	12-4 — 12-18-75	22.4	45.4	24.4	7.8	EPRI(NES)	14	3-44
Oyster Creek	12-18 — 1-5-76	20.3	39.1	27.3	13.3	EPRI(NES)	18	3-44
Oyster Creek	6-16 — 6-23-76	18.0	49.0	28.0	5.0	EPRI(NES)	7	3-45
Oyster Creek	6-23 — 6-30-76	22.0	49.0	45.0	4.0	EPRI(NES)	7	3-45
Oyster Creek	6-30 — 7-7-76	11.0	—	84 —	5.0	EPRI(NES)	7	3-45
Oyster Creek	7-7 — 7-13-76	20.0	37.0	38.0	5.0	EPRI(NES)	6	3-45
Oyster Creek	7-13 — 7-20-76	23.0	29.0	43.0	5.0	EPRI(NES)	7	3-45
Oyster Creek	7-20 — 7-27-76	21.0	43.0	31.0	5.0	EPRI(NES)	7	3-45
Oyster Creek	7-27 — 8-3-76	18.0	31.0	39.0	13.0	EPRI(NES)	7	3-45
Oyster Creek	8-3 — 8-10-76	25.0	45.0	25.0	5.0	EPRI(NES)	7	3-45
Oyster Creek	8-10 — 8-17-76	25.0	39.0	30.0	6.0	EPRI(NES)	7	3-45
Oyster Creek	8-17 — 8-24-76	22.0	29.0	40.0	9.0	EPRI(NES)	7	3-45
Oyster Creek	8-24 — 8-30-76	9.0	39.0	41.0	11.0	EPRI(NES)	6	3-45
Oyster Creek	8-30 — 9-7-76	12.0	40.0	38.0	10.0	EPRI(NES)	8	3-45
Oyster Creek	9-7 — 9-16-76	15.0	30.0	46.0	9.0	EPRI(NES)	9	3-45
Oyster Creek	9-16 — 9-23-76	21.0	41.0	29.0	9.0	EPRI(NES)	7	3-45
Oyster Creek	9-23 — 9-30-76	18.0	52.0	23.0	7.0	EPRI(NES)	7	3-45
Oyster Creek	9-30 — 10-7-76	15.0	52.0	27.0	6.0	EPRI(NES)	7	3-45
Oyster Creek	10-7 — 10-14-76	18.0	45.0	31.0	6.0	EPRI(NES)	7	3-45
Oyster Creek	10-14 — 10-21-76	16.0	51.0	25.0	8.0	EPRI(NES)	7	3-45
Oyster Creek	10-21 — 10-28-76	12.0	54.0	26.0	8.0	EPRI(NES)	7	3-45
Oyster Creek	10-28 — 11-4-76	22.0	44.0	25.0	9.0	EPRI(NES)	7	3-45
Oyster Creek	11-4 — 11-11-76	3.0	65.0	24.0	8.0	EPRI(NES)	7	3-45
Oyster Creek	11-11 — 11-18-76	14.0	57.0	19.0	10.0	EPRI(NES)	7	3-45
Oyster Creek	11-18 — 11-30-76	6.0	56.0	30.0	8.0	EPRI(NES)	12	3-45
Monticello	11-18 — 11-19-74	15.1	47.9	14.8	22.3	EPRI(NES)	1	3-44

4-7

NEDO-21159-2

Table 4-2  
 SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN  
 BWR TURBINE BUILDING VENTILATION EXHAUSTS (Continued)

Plant	Sample Period Month/Day/Year	Particulate	Species. % of I-131 Release			Measurements By	Sample Time Days	Reference
			I	HOI	CHI			
Monticello	1-8 — 1-9-75	13.4	64.0	12.3	10.3	EPRI(NES)	1	3-44
Monticello	5-12 — 5-15-75	26.5	51.5	15.4	6.6	EPRI(NES)	3	3-44
Vermont Yankee	6-23 — 6-24-74	24.9	63.8	4.0	11.3	EPRI(NES)	1	3-44
Vermont Yankee	9-12 — 9-14-74	17.1	55.0	20.9	7.0	EPRI(NES)	2	3-44
Vermont Yankee	10-10 — 10-11-74	33.7	57.1	9.2	3.0	EPRI(NES)	1	3-44
Vermont Yankee	9-22 — 10-7-75	8.0	48.6	(26.4)	(25.0)	EPRI(NES)	15	3-44
Vermont Yankee	10-7 — 10-21-75	21.0	48.6	(18.0)	(30.3)	EPRI(NES)	14	3-44
Vermont Yankee	10-21 — 11-6-75	50.0	100.0	(50.0)	(50.0)	EPRI(NES)	16	3-44
Vermont Yankee	7-5 — 7-8-74	— 89.5	—	0.0	10.5	EPRI(NES)	3	3-44
<b>Plant Mode: Refueling/Maintenance Outage</b>								
Oyster Creek	3-30 — 3-31-75	12.3	28.6	19.0	40.1	EPRI(NES)	1	3-44
Oyster Creek	3-31 — 4-1-75	2.0	53.7	19.3	27.1	EPRI(NES)	1	3-44
Oyster Creek	1-5 — 1-22-76	5.7	18.4	50.3	25.6	EPRI(NES)	17	3-44
Oyster Creek	1-22 — 2-9	3.2	14.3	56.8	25.7	EPRI(NES)	18	3-44
Monticello	1-13 — 1-15-75	2.4	55.5	16.3	25.8	EPRI(NES)	2	3-44
Monticello	9-11 — 9-25-75	8.1	31.3	40.0	20.6	EPRI(NES)	14	3-44
Monticello	9-25 — 10-15	2.3	9.4	(0.4)	(88.0)	EPRI(NES)	20	3-44
Monticello	10-15 — 10-27	2.4	17.6	(3.2)	(82.4)	EPRI(NES)	12	3-44
Monticello	10-27 — 11-14	7.1	11.9	(11.9)	(100.0)	EPRI(NES)	17	3-44
Vermont Yankee	10-31 — 11-1-74	2.0	10.0	57.0	31.0	EPRI(NES)	1	3-44

NOTE: Numbers in parentheses indicate questionable quality of adsorbent media. IPH

Table 4-3  
 SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN  
 BWR FEEDWATER AND CONDENSATE PUMP ROOM EXHAUSTS AT OYSTER CREEK

Plant	Sample Period Month/Day/Year	Particulate	Species. % of I-131 Release			Measurements By	Sample Time Days	Reference
			I <sub>2</sub>	HOI	CH <sub>3</sub> I			
Plant Mode: Power Generation Operations								
Oyster Creek	6-16 — 6-23-76		No Sample			EPRI(NES)	7	3-45
Oyster Creek	6-23 — 7-7-76	1	35	62	3	EPRI(NES)	14	3-45
Oyster Creek	7-7 — 7-20-76	5	— 95	—	11	EPRI(NES)	13	3-45
Oyster Creek	7-20 — 8-3-76	10	— 83	—	7	EPRI(NES)	14	3-45
Oyster Creek	8-3 — 8-24-76	8	— 87	—	4	EPRI(NES)	21	3-45
Oyster Creek	8-24 — 9-7-76	12	44	15	29	EPRI(NES)	14	3-45
Oyster Creek	9-7 — 10-7-76	6	41	49	4	EPRI(NES)	30	3-45
Oyster Creek	10-7 — 10-21-76	6	50	43	1	EPRI(NES)	14	3-45
Oyster Creek	10-21 — 11-4-76	7	82	8	3	EPRI(NES)	14	3-45
Oyster Creek	11-4 — 11-18-76	17	77	6	1	EPRI(NES)	12	3-45
Oyster Creek	11-18 — 11-30-76	12	69	15	4	EPRI(NES)	12	3-45

4-9

NEDO-21159-2

**Table 4-4**  
**SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN**  
**BWR REHEATER PROTECTION SYSTEM AND LUBE OIL STORAGE AREA EXHAUSTS AT OYSTER CREEK**

Plant	Sample Period Month/Day/Year	Particulate	Species, % of I-131 Release I <sub>2</sub>	HOI	CH <sub>3</sub> I	Measurements By	Sample Time Days	Reference
<b>Plant Mode: Power Generation Operations</b>								
Oyster Creek	7-20 — 8-3	3.0	9.0	19.0	69.0	EPRI(NES)	14	3-45
Oyster Creek	8-3 — 8-17	1.0	6.0	7.0	86.0	EPRI(NES)	14	3-45
Oyster Creek	8-17 — 8-30	1.0	2.0	5.0	92.0	EPRI(NES)	13	3-45
Oyster Creek	8-30 — 9-16	6.0	12.0	14.0	68.0	EPRI(NES)	17	3-45
Oyster Creek	9-16 — 9-30	0.3	17.0	12.0	71.0	EPRI(NES)	14	3-45
Oyster Creek	9-30 — 10-14	10.0	28.0	15.0	47.0	EPRI(NES)	14	3-45
Oyster Creek	10-14 — 10-28	9.0	21.0	14.0	56.0	EPRI(NES)	14	3-45
Oyster Creek	10-28 — 11-11	9.0	20.0	13.0	58.0	EPRI(NES)	14	3-45
Oyster Creek	11-18 — 11-30	7.0	20.0	23.0	50.0	EPRI(NES)	12	3-45

NOTE: No results available for periods of 6-16 to 7-20-76 and 11-11 to 11-18-76

Table 4-5  
 SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN  
 BWR RADWASTE BUILDING VENTILATION EXHAUSTS

Plant	Sample Period Month/Day/Year	Particulate	Species, % of I-131 Release			Measurements By	Sample Time Days	Reference
			I <sub>2</sub>	HOI	CH <sub>3</sub> I			
Plant Mode: Power Generation Operations								
Nine Mile Point 1	3-24-74	9.0	56.0	1.0	34.0	GE	184	3-55
Oyster Creek	2-22 — 2-27-75	2.0	20.0	30.0	50.0	EPRI(NES)	5	3-44
Oyster Creek	9-29 — 10-14-75	2.5	18.2	(9.5)	(69.9)	EPRI(NES)	15	3-44
Oyster Creek	10-14 — 10-31-75	1.0	15.1	(5.5)	(79.4)	EPRI(NES)	17	3-44
Oyster Creek	10-31 — 11-14-75	1.0	12.8	(2.3)	(87.0)	EPRI(NES)	14	3-44
Oyster Creek	12-4 — 12-18-75	2.0	9.0	28.8	62.2	EPRI(NES)	14	3-44
Oyster Creek	6-16 — 6-23-76	0.2	9.0	18.0	73.0	EPRI(NES)	7	3-45
Oyster Creek	6-23 — 6-30	6.0		49	45.0	EPRI(NES)	7	3-45
Oyster Creek	6-30 — 7-7	0.2		47	53.0	EPRI(NES)	7	3-45
Oyster Creek	7-7 — 7-13	<0.1	15.0	28.0	57.0	EPRI(NES)	6	3-45
Oyster Creek	7-13 — 7-20	0.5	13.0	26.0	61.0	EPRI(NES)	7	3-45
Oyster Creek	7-20 — 7-27	0.7	13.0	20.0	66.0	EPRI(NES)	7	3-45
Oyster Creek	7-27 — 8-3	<0.1	5.0	17.0	78.0	EPRI(NES)	7	3-45
Oyster Creek	8-3 — 8-10	0.2	9.0	14.0	77.0	EPRI(NES)	7	3-45
Oyster Creek	8-10 — 8-17	0.3	41.0	43.0	16.0	EPRI(NES)	7	3-45
Oyster Creek	8-17 — 8-24	0.1	7.0	21.0	72.0	EPRI(NES)	7	3-45
Oyster Creek	8-24 — 8-30	0.3	8.0	17.0	75.0	EPRI(NES)	6	3-45
Oyster Creek	8-30 — 9-7	0.2	14.0	23.0	63.0	EPRI(NES)	8	3-45
Oyster Creek	9-7 — 9-16	0.1	9.0	23.0	68.0	EPRI(NES)	9	3-45
Oyster Creek	9-16 — 9-23	0.1	10.0	14.0	76.0	EPRI(NES)	7	3-45
Oyster Creek	9-23 — 9-30	0.1	2.0	3.0	95.0	EPRI(NES)	7	3-45
Oyster Creek	9-30 — 10-7	0.5	41.0	17.0	41.0	EPRI(NES)	7	3-45
Oyster Creek	10-7 — 10-14	0.2	29.0	20.0	51.0	EPRI(NES)	7	3-45
Oyster Creek	10-14 — 10-21	0.2	15.0	30.0	55.0	EPRI(NES)	7	3-45
Oyster Creek	10-21 — 10-28	0.1	27.0	33.0	40.0	EPRI(NES)	7	3-45
Oyster Creek	10-28 — 11-4	0.6	27.0	18.0	55.0	EPRI(NES)	7	3-45
Oyster Creek	11-4 — 11-11	0.2	17.0	32.0	51.0	EPRI(NES)	7	3-45
Oyster Creek	11-11 — 11-18	0.1	8.0	23.0	69.0	EPRI(NES)	7	3-45
Oyster Creek	11-18 — 11-30	0.1	19.0	22.0	59.0	EPRI(NES)	12	3-45
Monticello	11-18 — 11-19-74	0.2	1.5	1.6	96.7	EPRI(NES)	1	3-44
Monticello	1-8 — 1-9-75	1.0	1.0	1.0	100.0	EPRI(NES)	1	3-44

4-11

NEDO-21159-2

Table 4-5  
**SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN  
 BWR RADWASTE BUILDING VENTILATION EXHAUSTS (Continued)**

Plant	Sample Period Month/Day/Year	Particulate	Species, % of I-131 Release			Measurements By	Sample Time Days	Reference
			I <sub>2</sub>	HOI	CH <sub>3</sub> I			
Vermont Yankee	6-19 — 6-20-74	0.6	14.5	10.8	74.9	EPRI(NES)	1	3-44
Vermont Yankee	9-12 — 9-13-74	<0.1	11.7	9.2	79.1	EPRI(NES)	1	3-44
Vermont Yankee	9-26 — 9-27-74	0.5	8.2	8.7	82.4	EPRI(NES)	1	3-44
Vermont Yankee	10-10 — 10-11-74	0.9	16.0	5.4	77.7	EPRI(NES)	1	3-44
Vermont Yankee	3-5 — 3-8-75	<1.0	<1.0	<1.0	100.0	EPRI(NES)	3	3-44
Vermont Yankee	9-22 — 10-7-75	<3.0	25.7	(7.3)	(67.0)	EPRI(NES)	15	3-44
Vermont Yankee	10-7 — 10-21-75	<1.0	35.2	(2.1)	(62.7)	EPRI(NES)	14	3-44
Vermont Yankee	10-21 — 11-8-75	<1.0	37.0	(2.0)	(63.0)	EPRI(NES)	18	3-44
<b>Plant Mode: Refueling/Maintenance Outage</b>								
Oyster Creek	1-5 — 1-22-76	6.0	9.7	17.6	72.7	EPRI(NES)	17	3-44
Oyster Creek	1-22 — 2-9-76	9.0	13.0	27.6	72.4	EPRI(NES)	18	3-44
Monticello	1-13 — 1-15-75	0.3	3.9	3.9	91.9	EPRI(NES)	2	3-44
Monticello	9-11 — 9-25-75	0.2	5.5	14.7	79.6	EPRI(NES)	14	3-44
Monticello	9-25 — 10-15-75	0.2	6.7	(0.4)	(93.3)	EPRI(NES)	20	3-44
Monticello	10-15 — 10-27-75	1.8	11.9	(3.7)	(88.1)	EPRI(NES)	12	3-44
Monticello	10-27 — 11-14-75	8.4	33.0	(11.0)	(67.0)	EPRI(NES)	18	3-44
Vermont Yankee	10-31 — 11-1-74	1.0	5.0	7.0	87.0	EPRI(NES)	1	3-44

NOTE: Numbers in parentheses indicate questionable quality of adsorbent media. IPH

Table 4-6  
 SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN  
 BWR GLAND SEAL STEAM AND MECHANICAL VACUUM PUMP EXHAUSTS

Plant	Sample Period Month/Day/Year	Particulate	Species, % of I-131 Release			Measurements By	Sample Time Days	Reference
			I <sub>2</sub>	HOI	Organic			
Plant Mode: Power Generation Operations (Gland Seal Steam Exhaust)								
Oyster Creek	7-16-75	28.0	15.0	8.0	49.0	EPRI(NES)	1	3-44
Oyster Creek	3-24-76	38.0	6.5	7.6	48.0	EPRI(NES)	1	3-44
Oyster Creek	3-24-76	.	(10.4)	(12.2)	(77.4)	EPRI(NES)		3-44
Oyster Creek	6-16 — 6-23-76		No Sample			EPRI(NES)	7	3-45
Oyster Creek	6-23 — 6-30	0.1	9.0	12.0	79.0	EPRI(NES)	7	3-45
Oyster Creek	6-30 — 7-7	1.0	18.0	26.0	55.0	EPRI(NES)	7	3-45
Oyster Creek	7-7 — 7-13	1.0	15.0	19.0	65.0	EPRI(NES)	6	3-45
Oyster Creek	7-13 — 7-20	1.0	36		63.0	EPRI(NES)	7	3-45
Oyster Creek	7-20 — 7-27	1.0		7.0	33.0	59.0	EPRI(NES)	7
Oyster Creek	7-27 — 8-3	<0.1	6.0	15.0	79.0	EPRI(NES)	7	3-45
Oyster Creek	8-3 — 8-10	1.0	22.0	38.0	39.0	EPRI(NES)	7	3-45
Oyster Creek	8-10 — 8-17	1.0	1.0	28.0	70.0	EPRI(NES)	7	3-45
Oyster Creek	8-17 — 8-24	3.0	9.0	42.0	46.0	EPRI(NES)	7	3-45
Oyster Creek	8-24 — 8-30	0.2	8.0	55.0	37.0	EPRI(NES)	6	3-45
Oyster Creek	8-30 — 9-7	0.4	5.0	55.0	40.0	EPRI(NES)	8	3-45
Oyster Creek	9-7 — 9-16	0.3	6.0	57.0	37.0	EPRI(NES)	9	3-45
Oyster Creek	9-16 — 9-23	0.1	8.0	50.0	42.0	EPRI(NES)	7	3-45
Oyster Creek	9-23 — 9-30	0.3	5.0	50.0	44.0	EPRI(NES)	7	3-45
Oyster Creek	9-30 — 10-7	1.0	6.0	43.0	50.0	EPRI(NES)	7	3-45
Oyster Creek	10-7 — 10-14	0.2	7.0	49.0	44.0	EPRI(NES)	7	3-45
Oyster Creek	10-14 — 10-21	0.3	6.0	43.0	51.0	EPRI(NES)	7	3-45
Oyster Creek	10-21 — 10-28	0.4	6.0	47.0	47.0	EPRI(NES)	7	3-45
Oyster Creek	10-28 — 11-4	0.3	5.0	44.0	51.0	EPRI(NES)	7	3-45
Oyster Creek	11-4 — 11-11	1.0	6.0	45.0	48.0	EPRI(NES)	7	3-45
Oyster Creek	11-11 — 11-18	0.4	10.0	6.0	83.0	EPRI(NES)	7	3-45
Oyster Creek	11-18 — 11-30	1.0	6.0	42.0	51.0	EPRI(NES)	12	3-45
Vermont Yankee	6-18 — 6-19-74	6.5	0.4	0.8	92.3	EPRI(NES)	1	3-44
Vermont Yankee	6-20 — 6-21-74	3.6	1.0	3.9	91.5	EPRI(NES)	1	3-44
Vermont Yankee	9-13 — 9-14-74	12.0	1.0	1.6	85.6	EPRI(NES)	1	3-44
Vermont Yankee	10-10 — 10-11-74	1.5	2.9	2.7	93.0	EPRI(NES)	1	3-44
Vermont Yankee	3-5 — 3-8-75	12.0	6.0	4.0	78.0	EPRI(NES)	3	3-44

4-13

NEDO-21159-2

Table 4-6  
**SUMMARY OF MEASUREMENTS OF IODINE-131 SPECIES IN  
 BWR GLAND SEAL STEAM AND MECHANICAL VACUUM PUMP EXHAUSTS (Continued)**

Plant	Sample Period Month/Day/Year	Particulate	Species, % of I-131 Release			Measurements By	Sample Time Days	Reference
			I,	HOI	Organic			
Vermont Yankee	10-7 — 10-21-75	<0.1	5.0	8.8	86.2	EPRI(NES)	14	3-44
Vermont Yankee	11-18-75	<0.3	2.1	(3.0)	(94.8)	EPRI(NES)	0.42	3-44
<b>Plant Mode: Refueling/Maintenance Outage (Mechanical Vacuum Pump Exhaust)</b>								
Monticello *	1-9-75	0.4	0.9	1.8	97.0	EPRI(NES)	0.542	3-44
Monticello *	1-10-75	0.8	2.8	6.9	98.5	EPRI(NES)	0.583	3-44
Monticello *	1-14-75	1.5	9.8	41.0	47.7	EPRI(NES)	0.917	3-44
Vermont Yankee	10-11 — 10-12-74	0.3	0.1	0.1	99.5	EPRI(NES)	0.67	3-44
Vermont Yankee	10-12 — 10-14-74	0.2	0.2	0.2	99.4	EPRI(NES)	1.92	3-44
Vermont Yankee	10-31-74	<1.0	<1.0	<1.0	<99.0	EPRI(NES)	1	3-44

NOTES (a) Monticello MVP results are actually stack releases which may include I-131 releases other than from use of MVP.  
 (1) Numbers in parentheses indicate questionable quality of adsorbent media, IPH



Table 4-7  
SUMMARY OF IODINE-131 SPECIES MEASUREMENTS  
IN BWR VENTILATION EXHAUSTS

Ventilation Exhaust	Plant	Particulate	Species, % of I-131 Release						
			Normal Operations			Refueling Operations			
			I <sub>2</sub>	HOI	CH <sub>3</sub> I	Particulate	I <sub>2</sub>	HOI	CH <sub>3</sub> I
Reactor Building	Nine Mile Point 1	18.0	42.5	1.5	38.0	—	—	—	—
	Oyster Creek	10.3	26.4	30.5	32.3	6.1	12.2	37.6	46.1
	Dresden 2	16.0	50.5	11.0	22.5	—	—	—	—
	Dresden 3	2.0	63.5	11.0	25.5	—	—	—	—
	Monticello	23.2	42.8	17.6	16.2	6.9	47.4	27.2	18.6
	Quad Cities 1	10.0	22.1	19.9	48.1	—	—	—	—
	Quad Cities 2	11.0	31.7	23.1	34.3	—	—	—	—
	Vermont Yankee	5.9	18.1	13.0	63.3	2.0	16.0	59.0	23.0
Turbine Building	Nine Mile Point 1	18.0	68.0	2.0	2.0	—	—	—	—
	Oyster Creek <sup>a</sup>	17.1	44.5	30.7	8.3	6.7	28.7	36.4	29.6
	Monticello	18.3	54.5	14.2	13.1	5.3	43.4	28.2	23.2
	Vermont Yankee	25.2	58.6	11.4	7.1	2.0	10.0	57.0	31.0
Radwaste Building	Nine Mile Point 1	9.0	56.0	1.0	34.0	—	—	—	—
	Oyster Creek	0.80	15.6	22.8	60.5	7.5	11.4	22.6	72.6
	Monticello	2.4	15.2	6.2	73.9	0.3	4.7	9.3	85.8
	Vermont Yankee	0.62	10.3	7.0	82.8	1.0	5.0	7.0	87.0
Gland Seal Steam	Oyster Creek	0.85	8.0	38.2	54.4	—	—	—	—
	Vermont Yankee	7.1	2.3	2.6	88.1	—	—	—	—
Mechanical Vacuum Pump <sup>b</sup>	Vermont Yankee	—	—	—	—	0.2	0.13	0.13	99.3

NOTES: (a) Turbine Building results for Oyster Creek exclude contributions from the feedwater pump and condensate pump compartment exhaust and the reheater protection system and lube oil storage area exhaust.  
(b) Mechanical Vacuum Pump release reported for Monticello (Table 4-8) are not included here because of uncertainties in obtaining a representative sample.

**Table 4-8**  
**RECOMMENDED RELATIVE CONCENTRATIONS OF IODINE-131 SPECIES IN**  
**BWR VENTILATION EXHAUSTS DURING NORMAL POWER GENERATION OPERATIONS AND**  
**REFUELING/MAINTENANCE OUTAGES FOR ENVIRONMENTAL IMPACT EVALUATIONS\***

I-131 Species	Plant Mode	
	Power Generation	Refueling/Maintenance
Species, % of I-131 Release		
<b>Reactor Building Exhaust</b>		
Particulate	11.3	5.0
Elemental	37.4	25.2
Hypoiodous Acid	16.6	41.3
Organic	35.0	29.2
	<u>100.3</u>	<u>100.7</u>
<b>Turbine Building Exhaust</b>		
Particulate	20.0	4.7
Elemental	55.8	27.4
Hypoiodous Acid	15.3	40.5
Organic	9.5	27.9
	<u>100.6</u>	<u>100.5</u>
<b>Radwaste Building Exhaust</b>		
Particulate	3.3	0.6
Elemental	24.1	4.9
Hypoiodous Acid	9.0	8.2
Organic	64.2	86.4
	<u>100.6</u>	<u>100.1</u>
<b>Gland Seal Steam and Mechanical Vacuum Pump<sup>b</sup></b>		
Particulate	4.7	0.2
Elemental	5.7	0.1
Hypoiodous Acid	20.6	0.1
Organic	69.8	99.3
	<u>100.8</u>	<u>99.7</u>

NOTES (a) Data weighted by sample time to obtain a weighted average value for each plant studied, recommended values are the arithmetic means of the sample-time weighted plant averages  
 (b) Mechanical Vacuum Pump corresponds to refueling/maintenance outages, only.

Table 4-9  
 SUMMARY OF NUMBER OF IODINE-131 SPECIES MEASUREMENTS

Ventilation Exhaust	Plant Mode			
	Power Generation Plants	Operations Samples	Refueling/Maintenance Plants	Outage Samples
Reactor Building	8	69	3	8
Turbine Building	4	40	3	10
Radwaste Building	4	39	3	8
Gland seal steam	2	32	—	—
Mechanical Vacuum Pump	—	—	2	6

## 5. IODINE-131 IN MILK

The purpose of this section is to update I-131 in milk data previously presented in NEDO-21159 (March 1976). Additional data have been obtained for the Monticello and Peach Bottom 2/3 plants for the 1976 grazing season.

At Monticello the 1976 annual release of I-131 (all species) was 0.12 curies from the stack and the plant ventilation exhaust. Most of the release was from the ventilation exhaust. The amount of I-131 which was observed in the milk at farms as close as 2.4 miles to the plant corresponded to activities less than 0.25 pCi/liter (Reference 5-1). The Monticello data are summarized in Table 5-1.

At the Peach Bottom station with two 1000 MWe reactors operating the I-131 activity in milk was very carefully monitored at farms from about 1. miles from the plant site to 11 miles from the plant site (Reference 5-2). During the grazing season (April 1 to November 30) the I-131 release the environs amounted to 0.78 Ci (all species). At the closest farm the arithmetic mean I-131 activity was 0.7 pCi/liter. The mean I-131 activity in milk decreased with distance from the plant, and the results were correlated by least-squares regression analysis.

The regression analysis considered correlations of both arithmetic and geometric means of the milk sample data. Normally arithmetic means are used for environmental dose assessments. However, in this instance, geometric means yield more conservative results as the milk samples are taken from farms further away from the plant. This effect arises because a majority of the samples taken during the entire sampling period have activities less than or equal to the minimum detection limit. On the other hand, samples from the closest farm result in an arithmetic mean which is 13% greater than the geometric mean. Calculation of geometric mean discounts samples with activities reported as less than the minimum detection limit, and calculation of the arithmetic mean assumes those samples to be at the minimum detection limit, 0.07 pCi/liter. Both of these calculation procedures are conservative. At a distance of 2.4 miles from the plant, the correlated results have a crossover point, that is, for distances less than 2.4 miles the arithmetic mean is greater than the geometric mean, and conversely. For overall correlation purposes an equation based on the geometric means of the data is recommended. This equation is shown in Figure 5-1. The Peach Bottom 2/3 data are summarized in Table 5-2. The Peach Bottom 2/3 I-131 activity levels are consistent with the Monticello data when compared on the basis of similar I-131 airborne releases from the plant, see Figure 5-1.

Iodine-131 concentrations in milk in environs of Quad Cities 1/2 site are listed in Table 5-3. Concentrations were not above background during 1975 and the first-half of 1976. These results have a detection limit of 0.5 pCi/liter.

The observations of I-131 activity in milk at Monticello can be used to estimate a maximum annual ingestion thyroid dose. Assume an infant drinks 300 liters of milk per year, which is a conservative assumption by a factor of about 50%, and a dose conversion factor of 0.013 mrem/picocurie ingested (References 5-3, 5-4 and 5-5). During 1976 the I-131 activity was always less than 0.25 picocuries/liter in milk collected at farms as close as 2.3 miles to the plant. (This excludes radioactive fallout effects due to the Chinese weapons test of September 1976.) The maximum dose is  $0.25 \text{ picocuries/liter} \times 300 \text{ liter} \times 0.013 \text{ mrem/picocurie} = < 1.0 \text{ mrems}$ . This dose estimate corresponds to an annual I-131 airborne release of 0.12 curies. The calculated dose is more than a decade below the NRC dose objective of 15 mrem stipulated in 10CFR50 Appendix I.

Calculations similar to the above can be made on the basis of the Peach Bottom data. At the farm within 1 mile of the plant the maximum potential dose due to milk ingestion is 2.6 mrems. This is a factor of 6 less than the NRC dose objective. The calculated dose corresponds to a I-131 release during the grazing season of 0.75 curies.

### 5.1 REFERENCES

- 5-1 Clark, B. W., March 30, 1977, letter to T. R. Marrero, "Monticello Nuclear Generating Plant Radiation Environmental Monitoring Program. Annual Report - 1976."
- 5-2 Peach Bottom Atomic Power Station, Radiological Regional Environmental Monitoring Program Report Number 12 (1976), Table XXXI.
- 5-3 Thompson, J. C., 1976, "Comments on the Paper, 'Radiation Doses from Iodine-129 in the Environment,' by J. K. Soldat," Health Physics 31, 287.

- 5-4 Soldat, J. K., 1976, "Reply to J. C. Thompson, Jr.'s Comments on the Paper, ' Radiation Doses from Iodine-129 in the Environment, ' " by J. K. Soldat, *Health Physics* 31, 288.
- 5-5 U. S. Nuclear Regulatory Commission, March 1976, "Calculation of Annual Average Doses to Man from Routine Releases of Reactor Effluents for the Purpose of Implementing Appendix I," *Regulatory Guide 1.109*, p. 27.
- 5-6 Commonwealth Edison Company, "Quad Cities Power Station Radioactive Waste, Environmental Monitoring and Occupational Personnel Radiation Exposure," Semi-annual reports for January through June 1975, July through December 1975, January through June 1976.

Table 5-1  
IODINE-131 ACTIVITY IN MILK IN ENVIRONS OF MONTICELLO (DURING 1976)

FARM					
Peterson 2.3 mi at 111°/ESE	Nelson 2.4 mi at 269°/W	Olson 2.5 mi at 24°/NWE	Shovelain 3.0 mi at 250°/WSW	Kotilinek 5.6 mi at 230°/SW	Hopkins 7.6 mi at 193°/SSW
<0.25(1-13)	<0.25(1-13)	<0.25(1-13)	<0.25(1-13)	<0.25(3-8)	<0.25(3-8)
<0.25(2-9)	<0.25(2-9)	<0.25(2-9)	<0.25(2-9)	<0.25(5-11)	<0.25(5-11)
<0.25(3-8)	<0.25(3-8)	<0.25(3-8)	<0.25(3-8)		
<0.25(4-12)	<0.25(4-12)	<0.25(4-12)	<0.25(4-12)		
<0.25(5-11)	<0.25(5-11)	—	<0.25(5-11)		
<0.25(6-2)	<0.25(6-2)	<0.25(6-2)	<0.25(6-2)		
<0.25(6-8)	<0.25(6-8)	<0.25(6-8)	<0.25(6-8)		
<0.25(6-15)	<0.25(6-15)	<0.25(6-15)	<0.25(6-15)		
<0.25(6-22)	<0.25(6-22)	<0.25(6-22)	<0.25(6-22)		
<0.25(6-29)	<0.25(6-29)	<0.25(6-29)	<0.25(6-29)		
<0.25(7-13)	<0.25(7-13)	<0.25(7-13)	<0.25(7-13)		
<0.25(8-10)	<0.25(8-10)	<0.25(8-25)	<0.25(8-10)		
<0.25(9-8)	<0.25(9-7)	<0.25(9-7)	<0.25(9-7)		
<0.25(10-19)	0.76(10-19) <sup>a</sup>	<0.25(10-19)	0.96(10-19) <sup>a</sup>		
<0.25(11-9)	<0.25(11-9)	<0.25(11-9)	<0.25(11-9)		
<0.25(12-7)	<0.25(12-7)	<0.25(12-7)	<0.25(12-15)		
Holland 8.1 mi at 199°/SSW	Vandergon 8.3 mi at 247°/WSW	Vetsch 9.4 mi at 128°/SE	Becker 10.0 mi at 130°/SE	Kirchenbauer 11.5 mi at 323°/NW	Dwinger 13.0 mi at 335°/NNW
<0.25(3-16)	<0.25(3-8)	<0.25(3-8)	<0.25(3-8)	<0.25(3-8)	<0.25(3-8)
<0.25(5-11)	<0.25(5-11)	<0.25(5-11)	<0.25(5-11)	<0.25(5-11)	<0.25(5-11)
				<0.25(7-13)	
				<0.25(8-25)	
				<0.25(9-7)	
				2.23(10-19) <sup>a</sup>	
				<0.25(11-9)	
				<0.25(12-7)	

NOTES. a Higher activity due to fallout from nuclear test conducted by People's Republic of China on September 26, 1976.  
b. The nominal lower limit of detection based on 3 sigma error for background sample is 0.25 picocuries/liter.  
c. The milk sample collection date is indicated parenthetically next to the I-131 activity.

Table 5-2  
 IODINE-131 ACTIVITY IN MILK IN ENVIRONS OF PEACH BOTTOM 2/3 (DURING 1976)

Farm Distance Sector (miles)	I-131 Activity, picocuries/liter										
	J	G	H	M	L	D	N	A	C	E	B
	0-1 W	1-2 SSW	1-2 S&SSW	2-3 ENE	2-3 NE	3-4 NE	3-4 ESE	5-10 WSW	5-10 NW	5-10 N	10-20 S
1	1.9 E-1	5.5 E-1	3.2 E-1	5.7 E-1	5.2 E-1	0.4 E-1	1.5 E-1	1.3 E-1	0.5 E-1	1.5 E-1	0.9 E-1
2	7.4 E-1	3.8 E-1	2.3 E-1	1.2 E-1	1.3 E-1	2.0 E-1	11.0 E-1	10.0 E-1	2.1 E-1	1.9 E-1	0.4 E-1
3	13.0 E-1	3.2 E-1	7.7 E-1	2.1 E-1	0.9 E-1	2.0 E-1	9.2 E-1	3.2 E-1	2.2 E-1	1.1 E-1	1.0 E-1
4	2.4 E-1	0.6 E-1	4.5 E-1	0.5 E-1	1.8 E-1	7.5 E-1	9.0 E-1	1.2 E-1	1.9 E-1	1.0 E-1	2.7 E-1
5	1.5 E-1	7.4 E-1	1.2 E-1	0.9 E-1	4.9 E-1	4.4 E-1	5.1 E-1	0.7 E-1	0.5 E-1	0.9 E-1	0.7 E-1
6	43.0 E-1	22.0 E-1	2.3 E-1	9.2 E-1	1.3 E-1	2.1 E-1	2.2 E-1	0.5 E-1	1.0 E-1	1.4 E-1	0.5 E-1
7	20.0 E-1	32.0 E-1	9.0 E-1	1.0 E-1	1.0 E-1	0.8 E-1	3.3 E-1		0.5 E-1	1.6 E-1	
8	12.0 E-1	17.0 E-1	13.0 E-1	0.7 E-1	1.6 E-1	3.6 E-1	2.6 E-1		4.0 E-1	4.0 E-1	
9	6.1 E-1	10.0 E-1	10.0 E-1	3.2 E-1	0.9 E-1	1.0 E-1	2.0 E-1			4.1 E-1	
10	3.6 E-1	5.2 E-1	2.8 E-1	3.0 E-1	3.9 E-1	4.0 E-1	1.9 E-1			2.3 E-1	
11	2.5 E-1	1.7 E-1	0.7 E-1	0.7 E-1	7.2 E-1	0.8 E-1	10.0 E-1				
12	2.3 E-1	0.7 E-1	3.2 E-1	0.8 E-1	4.4 E-1	2.5 E-1	6.3 E-1				
13	14.0 E-1	1.1 E-1	3.0 E-1		3.4 E-1	1.8 E-1	1.1 E-1				
14	9.0 E-1	1.4 E-1	1.6 E-1		8.2 E-1	1.3 E-1	2.3 E-1				
15	3.7 E-1	12.0 E-1	6.8 E-1			2.4 E-1	4.6 E-1				
16	8.0 E-1	1.1 E-1	4.2 E-1			2.3 E-1	2.0 E-1				
17	4.1 E-1	3.3 E-1	10.0 E-1				1.4 E-1				
18	3.0 E-1	6.0 E-1	1.5 E-1				8.5 E-1				
19	11.0 E-1	2.8 E-1	9.4 E-1				9.0 E-1				
20	4.7 E-1	2.0 E-1	5.3 E-1				7.2 E-1				
21		0.4 E-1	1.6 E-1				3.4 E-1				
22		13.0 E-1	4.0 E-1				2.2 E-1				
							6.0 E-1				
Geometric Mean	0.58	0.37	0.37	0.16	0.25	0.19	0.38	0.16	0.12	0.17	0.084
Arithmetic Mean	0.66	0.58	0.41	0.15	0.20	0.17	0.42	0.12	0.096	0.12	0.077

NOTE: Samples were collected from 3-29-76 to 9-26-76 on a weekly basis. The sample numbers are in sequence, however many samples had activity levels less than the lower limit of detection (0.07 pCi/liter) and these results are omitted from this tabulation. Prior to 3-29-76 I-131 concentrations in milk were less than 0.07 pCi/liter. After 9-27-76 the I-131 activities increased significantly due to the nuclear weapons test conducted by the People's Republic of China.

5-4

NEDO-21159-2

**Table 5-3**  
**IODINE-131 ACTIVITY IN MILK IN**  
**ENVIRONS OF QUAD CITIES 1/2**  
**(DURING 1975 AND FIRST-HALF OF 1976)**

Collection Date Month/Day 1975	Dairy	
	Background <sup>a</sup> I-131 Concentration, pCi/liter	Indicator <sup>b</sup>
1/4	<4	<4
2/1	<4	<4
3/2	<4	<4
4/5	<0.5	<0.5
4/12	<0.5	<0.5
4/19	<0.5	<0.5
4/26	<0.5	<0.5
5/3	<0.5	<0.5
5/10	<0.5	<0.5
5/18	<0.5	<0.5
5/24	<0.5	<0.5
5/31	<0.5	<0.5
6/7	<0.5	<0.5
6/14	<0.5	<0.5
6/21	<0.5	<0.5
6/28	<0.5	<0.5
7/5	<0.5	<0.5
7/12	<0.5	<0.5
7/19	<0.5	<0.5
7/26	<1.0	<0.5
8/2	<0.5	<0.5
8/9	0.6 ± 0.2	<0.5
8/16	<0.5	<0.5
8/22	<0.5	<0.5
8/30	<0.5	<0.5
9/6	<0.5	<0.5
9/14	<0.5	<0.5
9/20	<0.5	<0.5
9/27	<0.5	<0.5
10/4	<4	<4
11/1	<4	<4
12/7	<4	<4



Table 5-3 (Continued)  
 IODINE-131 ACTIVITY IN MILK IN ENVIRONS OF QUAD CITIES ½  
 (DURING 1975 AND FIRST-HALF OF 1976)

Collection Date Month/Day 1976	Dairy	
	Background <sup>a</sup> I-131 Concentration, pCi/liter	Indicator <sup>b</sup>
1:3	<4	<4
2:7	<4	<4
3:6	<4	<4
	<0.5	<0.5
4:10		<0.5
4:17	<0.5	<0.5
4:24	<0.5	<0.5
5:1	<0.5	<0.5
5:8	<0.5	<0.5
5:15	<0.5	<0.5
5:22	<0.5	<0.5
5:26	<0.5	<0.5
6:4	<0.79	0.69
6:11	<0.5	0.5
6:18	<0.5	<0.7
6:25	<0.5	0.5

Notes: Data reported as < are at the 99% confidence level  
 a. Hansen Dairy Farm, about 5.5 miles from site.  
 b. Saddle Club Dairy, less than 1 mile from site.




Figure 5-1. Empirical Correlation of I-131 Activity in Milk as Produced in Environs of BWR's

## 6. NORMALIZATION OF IODINE-131 RELEASES

The following information on iodine-131 updates data previously reported in NEDO-21159, March 1976, Chapter 6. This information is divided into four major subjects; namely,

1. iodine-131 carryover,
2. iodine-131 reactor water concentrations,
3. fuel performance of current BWR's,
4. normalization of iodine-131 ventilation releases to its reactor water concentration.

### 6.1 IODINE-131 CARRYOVER

Iodine-131 carryover is significant because it affects the amount of I-131 release from the turbine building ventilation exhaust, the gland seal steam exhaust and the mechanical vacuum pump. A first-order approximation is that the higher the carryover the higher will be the I-131 release from the above exhausts. Measurements of I-131 carryover at operating BWR's indicate that carryover may range from 0.2 to 2.5 percent, depending on the plant. Thus in order to compare I-131 releases from the turbine building ventilation exhaust, etc., it is necessary to account for differences in I-131 carryover.

Iodine-131 carryover is defined as the ratio of the I-131 concentration in the condenser hotwell to its concentration in the reactor vessel. This definition is directly applicable to BWR's in which 100% of the steam is condensed in the hotwell. At this time there is only one exception to this flow pattern. The Brunswick plants have forward pumped flow, and for this type of flow the I-131 that is recycled to the reactor without passing through the hotwell must be taken into account in order to estimate I-131 carryover, as defined above. This is an important consideration because many future BWR's will have forward pumped flow and the distribution of I-131 sources within the turbine building will depend on the steam/condensate flow pattern.

A brief outline of the principal methods used to determine I-131 carryover is as follows. The most frequent method is based on sampling I-131 activity in the water of the reactor vessel and the hotwell. Carryover is the simple ratio of I-131 activities per unit volume, hotwell to reactor, and reported as a percentage. Less frequently "no-cleanup" tests are conducted. This method compares the rate-of-loss of iodine from the reactor vessel by all processes with and without the cleanup system in service. These processes include radioactive decay, leakage of primary water, and carryover. A third method, infrequently performed, determines carryover based on analyses of the turbine moisture separator and heater drains. Further information on I-131 carryover measurement methods can be found in References 6-1 and 6-2. Iodine-131 activities are based on analyses of the sample by gamma spectra usually with Ge (Li) detectors. Liquid samples are concentrated by use of ion-exchange membranes.

The I-131 carryover data are summarized in Table 6-1. These results are based on various internal General Electric Company documents, including Chemical and Radiochemical Startup Reports, and personal communications for some unpublished results. The data has been approved for release by the utilities involved. The summary includes data available to this author through January 1977 (References 6-1, 6-3 and 6-4). The carryover results exclude data from BWR's which commenced commercial operations prior to 1969, or plants of pre-Oyster Creek vintage. For some BWR's several I-131 carryover values have been reported, however this summary presents only one value per plant.

A discussion of the effects of power, water level, steam flow, and other variables on I-131 carryover is beyond the scope of this report.

The results in Table 6-1 indicate that I-131 carryover is related to the type of condensate treatment system. This empirical result is illustrated in Figure 6-1. Apparently BWR's with "Powdex" condensate treatment systems have lower carryover values than plants with "Deep Bed" condensate systems. The only exception to this grouping is "Powdex" plants with stainless steel condenser tubing, the other "Powdex" plants have condenser tubing made of a copper bearing alloy. This exception implies circumstantially that the amount of copper in the reactor water has a significant effect on I-131 carryover (see also, Reference 6-5).

For "Deep Bed" plants the arithmetic mean I-131 carryover is 1.5% with a sample standard deviation of 0.65%; for "Powdex" plants the mean and standard deviation are 0.40% and 0.1%, respectively.

The above results suggest a mean I-131 carryover value of about 1.0%. A one percent I-131 carryover is used in later sections of this document to normalize BWR I-131 airborne release data from the turbine building ventilation exhaust, gland seal steam exhaust, and mechanical vacuum pump.

## 6.2 IODINE-131 REACTOR WATER CONCENTRATIONS

Iodine-131 reactor water concentration data are presented in this section. The data have been obtained under Operational Information Exchange Provisions between the General Electric Company and utilities with commercially operating BWR's and are reported here with the concurrence of the utilities. The reported I-131 reactor water concentrations are for 15 domestic BWR's operating during 1975 and 1976. The time period was chosen to provide more recent data, to determine a I-131 concentration trend with time, if any, and for two plants data from 1974 were included to show the effect of improved fuel performance. These numerous data are here provided by a series of graphs, Figures 6-2 to 6-34a. In these figures improved-fuel denotes both General Electric Company fuel types (7x7R) and (8x8).

Table 6-2 lists the maximum monthly value of the available I-131 reactor water concentrations by plant. The medians of the monthly maximum concentrations were plotted on normal probability paper, Figure 6-35. This figure shows that the range of I-131 reactor water concentrations decreased significantly from 1975 to 1976. Figure 6-36 is a trend analysis over the two year period. This figure was developed from the deviations on a monthly basis of the arithmetic mean of the 24 medians of the maximum monthly concentrations. The results indicate a decreasing concentration with time. The above analyses are like "snapshots" of I-131 concentrations for all BWR's sampled.

On a plant basis over the two year period, Table 6-3 summarizes the median maximum monthly I-131 reactor water concentrations. Data are excluded when a plant is undergoing refueling/maintenance outage or there are not data available for a given month. Thus the I-131 concentrations conservatively apply only to plants in the power generation mode of operations. Table 6-3 also indicates the fractional I-131 fuel release resulting from old type fuel defects, namely, from GE type "7x7" fuel. These values are estimates from a survey of 1975 and 1976 fuel performance data and account for the increase in I-131 reactor water concentration from the beginning of a fuel cycle.

An analysis was also performed to determine an empirical relationship between the percentage of improved fuel in the reactors and the I-131 reactor water concentration. The purpose of this analysis was to see if the current BWR fuel performance and plant operations indicate any differences from the previous source-term (Reference 2-1). The data presented in Figures 6-2 to 6-34a were evaluated according to fuel cycle number and fraction of core loading that consisted of improved fuel.

The 15 domestic BWR's studied contain large differences in the amount of improved fuel loaded into the core, and in most cores there is a mixture of old-type fuel and improved fuel. Reactors with a relatively large amount of old-type fuel would not be representative of current fuel design. Thus, the following criteria were selected in an attempt to correlate I-131 reactor water concentration with the percentage of improved-fuel in BWR's:

1. Fuel cycle numbers must be greater than 1.
2. The amount of old-type fuel (7x7) must be less than or equal to 67%.

The first criterion eliminates data from reactors that are still in their first fuel cycle. The fuel exposures would be low relative to the total exposure to be experienced by the fuel. The observed I-131 reactor water concentrations during the first fuel cycle are probably less than in later cycles. The second criterion, eliminates data from reactors that have a preponderance of old-type fuel; core loadings which would be atypical for future BWR's.

On the basis of these criteria, twelve data points were available for consideration. Each point corresponded to the arithmetic mean of the monthly I-131 reactor water concentration data available for a reactor and fuel cycle. These results are summarized in Table 6-4.

The mean I-131 concentrations were then plotted against percent improved fuel, and a definite correlation was apparent. However, there were two outliers, namely Dresden 2 (fuel cycle 5) and Monticello (fuel cycle 5). The Dresden 2 point fell way below the other data points. This is probably due to the fact that in 1972, at the end of cycle 2, almost the entire core loading was changed, which removed the defective fuel and tramp uranium. Thus, subsequent cycles would not be so affected by the previous fuel performance due to the "core flush." The Monticello point was above the other points because of residual tramp uranium. At Monticello, in 1975, with old-type fuel the I-131 reactor water concentration had been up to about 200  $\mu\text{Ci}/\text{kg}$ . These two outliers were rejected for correlation purposes. Furthermore, the data from Nine Mile Point 1 (cycles 3 and 4) seemed slightly out-of-line. A review of its history indicated that Nine Mile Point 1 has been operating at "stretch power levels," not at design levels. This kind of plant operation essentially increased the number of defects. To adjust the Nine Mile Point 1 data to the same design bases as the other plants the average I-131 reactor water concentrations were multiplied by 0.7.

The 10 data points for I-131 concentration were correlated with percent improved fuel by least squares regression analysis. The correlation was found to be linear,

$$y = a + bx$$

where:

$y$  = concentration of I-131 in reactor water,  $\mu\text{Ci}/\text{kg}$

$x$  = percentage of improved fuel,

$a, b$  = constants determined by regression analysis

The  $a$  coefficient was found to be 4.46 and the  $b$  coefficient was  $-0.0393$ . The latter indicates that increasing the amount of improved fuel decreases the I-131 concentration in the reactor water, as would be expected. The correlation coefficient was fairly good, equal to 0.86.

Additional analyses were performed of the data at 100% improved fuel conditions. These data are listed in Table 6-5. The results are graphically presented in Section 7.

The data provided in this report are more comprehensive and recent than the input to the currently accepted value for I-131 reactor water concentration. Both the American Nuclear Society 18.1 Standards Committee and the U.S. Nuclear Regulatory Commission, Office of Standards Development, use a value of 5  $\mu\text{Ci}/\text{kg}$ , I-131 in the reactor water (References 6-6 and 6-7). This value has recently been reduced to 1.7  $\mu\text{Ci}/\text{kg}$  (Reference 6-8).

### 6.3 FUEL PERFORMANCE

As previously reported (NEDO-21159, March 1976) BWR cores containing all or significant quantities of improved fuel (the 7x7R and/or the 8x8 fuel design) demonstrate much lower iodine reactor water concentrations than BWR cores containing old 7x7 fuel. This is the result of a factor of 100 fewer fuel defects in early life ( $<5$  GWD/T) and a factor of  $>10$  fewer fuel defects in mid-life (5-15 GWD/T) burnups. Additionally, the fuel defects that have been inspected in the 7x7R fuel design show very small tight cracks in the active fuel region with no exposed fuel. In comparison the old 7x7 fuel was frequently exposed directly to the coolant resulting in a rapid increase in the core "recoil" level. Defects in the improved fuel are consequently degrading at a much slower rate and at lower release levels than previously observed (lower by greater than a factor of ten). The net effect is reactor water iodine-131 concentrations of 0.006 to 0.5 ( $\mu\text{Ci}/\text{kg}$ ) in cores that contain only improved fuel (plants B, C, D & E in Table 6-6). In cores that contain reload improved fuel the old 7x7 effects are still being seen with higher iodine concentrations of

2 to 5  $\mu\text{Ci}/\text{kg}$  (plants A & K in Table 6-6). The old 7x7 fuel "recoil" is *continually decreasing* due to fissioning during plant operation and core component replacement (fuel, channels, etc.) during refueling. This is dramatically seen at Vermont Yankee end-of-cycle 2 (10/74) and throughout cycles 3 and 4 (Figures 6-32 and 6-33). A similar reduction in iodine concentrations occurred at Monticello end-of-cycle 4 (9/75) (Figures 6-16 and 6-17).

The increased experience with improved fuel and the extremely low offgas and reactor water iodine release rates, a number of reactor operators with improved fuel cores have elected to dispense with leak detection and defective fuel removal at end of fuel cycles. As a result of this practice a number of improved fuel bundles containing defects have seen extensive core residence time with only modest increases in core "recoil", offgas, and reactor water iodine concentrations being observed. The reactor water iodine concentrations remained 1 to 2 decades lower than levels typically observed in old 7x7 cores.

Table 6-7 summarizes information related to fuel loadings, plant capacity, and reactor water cleanup system capacity.

#### 6.4 NORMALIZED RELEASE RATES OF IODINE-131

Measurements of I-131 airborne releases have been made at BWR's operating under different conditions. In order to provide expected annual I-131 releases, the actual release rates (see Section 3) have been normalized. The basis for normalization is a concentration of I-131 in reactor water of 1  $\mu\text{Ci}/\text{kg}$ , a carryover of I-131 from reactor water to reactor steam of 1%, full-flow condensate treatment, and a calendar year consisting of 300 days of power operations and one refueling/maintenance shutdown period. The next discussion deals with normalization of actual I-131 release data to its reactor water concentration, only.

The I-131 release rate normalized to concentration is the rate of the actual release divided by the average I-131 reactor water concentration in  $\mu\text{Ci}/\text{kg}$  during the same operating period. Thus, the units for normalized I-131 release rates may be expressed as  $[\mu\text{Ci}/\text{s}]$ , corresponding to an I-131 reactor water concentration of 1.0  $\mu\text{Ci}/\text{kg}$ . Similarly, the normalized I-131 release (millicuries) is the product of the normalized release rate times the normal sample time in seconds times  $1.0 \times 10^{-3}$ . The latter factor converts microcuries to millicuries. Normalized I-131 release rates significantly reduce the variations in release rates for both intra-plant and inter-plant results. For a given plant the normalized release rates over about one calendar year of operation will usually vary by less than a factor of 10. Generally, the inter-plant results also have less than a factor of 20 difference on a normalized basis.

A normalized airborne I-131 release is determined for both power generation operations and refueling/maintenance (R/M) outages. For (R/M) outages the average I-131 reactor water concentration for about three to four weeks, equivalent to about 3 half-lives, prior to the shutdown is used for normalization purposes. This assumes that the R/M outage I-131 release is proportional to the previous plant I-131 inventory and allows a reasonable time to account for its radioactive decay. Note that normalized I-131 release rates do not account for its chemical form; normalized rates are based on all I-131 species.

The normalization of I-131 ventilation releases to its reactor water concentration is admittedly a first approximation. Other plant design features or operating conditions will also affect I-131 ventilation releases. However, as previously indicated in NEDO-21159 (March 1976) there appears to be a strong correlation between I-131 release and its reactor water concentration. On the other hand the analysis of I-131 normalized release rates can help determine the effect of plant operations or system conditions. In this report only a very limited discussion is presented of plant operation effects; such as equipment testing, process changes, process leaks that are identified and repaired.

This amendment to NEDO-21159 presents data obtained by the Electric Power Research Institute from mid-1974 through December 1976.

The available results of the EPRI sponsored measurements are presented in Tables 6-8 and 6-9 for Vermont Yankee (BWR/4), Tables 6-10 and 6-11 for Monticello (BWR/3), and Tables 6-12 and 6-13 for Oyster Creek (BWR/2). These results are illustrated in Figures (6-38 to 6-46) for the three plants as a function of time and ventilation release point (building).

The normalized I-131 release results are presented in Tables 6-8 to 6-13. For each plant - Vermont Yankee, Monticello and Oyster Creek normalized I-131 release rates and releases (millicuries) are tabulated. The results for second listing for measurements of June through November, 1976. Table 6-14 is a summary of the normalized I-131 releases for the three BWR's and indicates the release activities for power generation operations and refueling/maintenance outages. For purposes of normalization, the power generation operation period is assumed to be 300 days and the refueling/maintenance outage is assumed to be an annual event.

Table 6-15 compares normalized I-131 releases from the turbine building of all three BWR's (above) at the same I-131 carryover. For normalization purposes a 1.0 percent carryover was assumed.

The tabulated normalized I-131 releases are presented in a series of bar graphs, Figures 6-47 to 6-49, which compare the building releases at the three BWRs for different plant operations. These results are a marked contrast to the results on an "as is" basis, discussed in Section 3.2. For all plant operations, assuming one R/M outage per year, the reactor building normalized I-131 average airborne release for the three BWR's is approximately 10 millicuries/year plus-or-minus 50%. For the turbine building the I-131 annual release ranges from 3 to 70 millicuries. Two of the three BWR's have normalized I-131 annual releases from the radwaste building of only millicurie/year, the third is more than a factor of 10 greater.

Figures 6-50 to 6-53 are frequency polygons of the normalized I-131 airborne release rates. The I-131 release rates that are not normally distributed, but are lognormal. The results were calculated by means of a General Electric Company data analysis program STATPAC (Reference 6-9). These graphs are helpful in determining causes of abnormal I-131 releases. For example, at Vermont Yankee the reactor building normalized I-131 release rates appear to be bimodal. The relatively high values occurred during the refueling/maintenance outage. The low peak occurred after the R/M outage. Presumably some leaks from the power-generation and process equipment were repaired during the outage. The turbine building is distinctly unimodal with a mean of about the same magnitude as the reactor building normalized I-131 release rate after the R/M outage. There are two low outliers and these correspond to the final days of the R/M outage. Apparently all the I-131 is released from the turbine building during the first-phase of a R/M outage at Vermont Yankee. Similar evaluations of frequency polygons are possible for all the other BWR's. However, further detailed discussions are outside the scope of this report.

Figure 6-53 compares the frequencies of turbine building airborne normalized I-131 release rates at the three plants at 1% I-131 carryover. It is readily apparent from Figure 6-53 that the normalized I-131 release rates increase in the order, Vermont Yankee, Monticello and Oyster Creek. On an "as is" basis the frequency of I-131 rates would show greater differences between Oyster Creek and the other two plants because the sample I-131 carryover at Oyster Creek is 2.3%, whereas at Vermont Yankee and Monticello the carryover is 0.40 and 0.45%, respectively.

Figure 6-54 shows that the turbine building, normalized I-131 release rate correlates with plant power level. This effect was not evident at Vermont Yankee and Monticello. Presumably, at Oyster Creek there is relatively large fluid leakage-probably steam. This conclusion is made because turbine steam pressures at intermediate and low-pressure stages are proportional to power level. Estimates were made of turbine intermediate pressures as a function of power from sample BWR heat balances. These results indicate that the normalized I-131 release rate can be correlated to the square root of pressure. It is generally true that fluid leakage from orifices is proportional to the square-root of pressure.

Another evaluation of the normalized I-131 release results was made by integrating the releases as a function of time. These cumulative amounts were plotted on log-log graph paper, Figure 6-55 to 6-66. The slope of these data indicate whether or not leakage is increasing, decreasing or remains the same during plant operations. If the slope is greater than 1 the release rate is increasing, if the slope is 1 then the release rate is constant; and if the slope is less than 1 then the rate is decreasing with time. Since the above graphs plot normalized I-131 release rates the results are estimates of the effective fluid leakage from the nuclear steam supply system and auxiliaries. Only a few comments follow regarding the interpretation of the cumulative I-131 release results. A refueling/maintenance outage causes a sharp rise in normalized I-131 release. The system is opened and more fluid leakage is inevitable. However, the actual I-131 releases are off-set by decreasing I-131 inventories due to clean-up and radioactive decay. At Monticello the reactor building leakage increased rapidly during mid-1975, between the R/M outages. This increase may be due to the continued deterioration of the seals on the reactor water cleanup pumps. At Oyster Creek the radwaste building

leakage increased significantly with time presumably due to changes in processing methods. At Vermont Yankee leakage was constant or decreasing with time presumably due to the implementation of an effective maintenance program.

Trend analyses were made of actual I-131 airborne emissions from several BWR's on the basis of routine operating plant data. The purpose of these analyses was to determine the long-term trend in airborne release rates. The numerical results have already been presented in Table 2-5. In this section the results are presented in graphical form, Figures 6-67 to 6-70. Trend analysis are based on the cumulative releases as a function of plant operating time. The cumulative I-131 airborne release for Dresden 2/3, Quad Cities 1/2, Monticello and Pilgrim 1 show a decreasing trend. This is apparent from Figures 6-67 to 6-70 which are log-log plots of the data. Increases in rates correspond to slopes greater than one, and decreases in rates correspond to slopes less than 1. For these trend analyses data from the first year, or so, of commercial operations were deleted to eliminate any startup effects. Such effects were apparent for the plants considered, see Figures 3-1, 3-3, and 3-5.

## 6.5 REFERENCES

- 6-1 Helmholtz, H. R., 1973 "Carryover Measurements at Commercial BWR's from Dresden-1 through May, 1973," General Electric Company, NEDM-12439 (unpublished).
- 6-2 Pelletier, C. A. compiler, 1973, "Results of Independent Measurements of Radioactivity in Process Systems and Effluents at Boiling Water Reactors," U.S. Atomic Energy Commission, Docket RM-50-2, ALAP Exhibit No. 22.
- 6-3 Helmholtz, H. R., letter to J. M. Skarpetos, September 2, 1975, "I-131 Carryover Values," General Electric Company, internal correspondence.
- 6-4 Pelletier, C. A., E. A. Barefoot, J. E. Cline, R. N. Hemphill, W. A. Emel, P. G. Volleque, October 1976, "Sources of Radioiodine at Boiling Water Reactors," page III-5, Nuclear Environmental Services Division, An Interim Report on Research Project 274-1 prepared for Electric Power Research Institute.
- 6-5 Lin, C. C., October 15, 1976, letter to M. E. Meek, "Iodine Carryover vs. Cu Content in Feedwater," General Electric Company, internal document.
- 6-6 NAS 18-1, ANSI N237-1976, American National Standard, "Source Term Specification," Table 5.
- 6-7 U.S. Nuclear Regulatory Commission, 1976, "Calculation of Releases of Radioactive Materials in Gaseous and Liquid Effluents from Boiling Water Reactors (BWR - GALE CODE), NUREG-0016, Office of Standards Development, NUREG-0016, pg. 2-3.
- 6-8 U.S. Nuclear Regulatory Commission, 1978, "Calculation of Releases of Radioactive Materials in Gaseous and Liquid Effluents from Boiling Water Reactors (BWR - GALE CODE), NUREG-0016 (Draft).
- 6-9 Nelson, W. B., R. Hendrickson, M. C. Phillips, and L. Thumhart, 1973, "STATPAC Simplified--A Short Introduction to How to Run STATPAC, A General Statistical Package for Data Analysis," General Electric Company, Report No. 73 CRD 046 (Class II).



Table 6-1  
SUMMARY OF BWR IODINE-131 CARRYOVER VALUES

A. BWRs with Deep Bed Condensate Treatment Systems or Powdex Systems with Stainless Steel Condenser Tubing

Plant	Carryover %
Cooper <sup>a</sup>	1.2
Dresden 2	1.8
Dresden 3	2.0
Fukushima 1 <sup>c</sup>	1.1
Fukushima 2	1.4
Fitzpatrick	1.8
Millstone Point 1	1.2
Pilgrim 1	0.82
Quad Cities 1 <sup>c</sup>	1.09
Nine Mile Point 1	2.0
Oyster Creek	2.4
Tsuruga	2.5
Nuclenor	0.21

a. Powdex with stainless steel condenser tubing

Arithmetic mean 1.5%  
STD 0.65%

c. Reported values are sample cases

B. BWRs with Powdex Condensate Treatment Systems<sup>b</sup>

Plant	Carryover %
Browns Ferry 1	0.5
Browns Ferry 2	0.23
Browns Ferry 3	0.3
Duane Arnold <sup>d</sup>	0.4
Hatch 1	0.35
KKM	0.6
Monticello	0.4
Peach Bottom 2	0.4
Peach Bottom 3	0.44
Vermont Yankee	0.4

b. Plants have condensers with admiralty brass tubing or other copper bearing material  
Arithmetic mean 0.4%  
STD 0.10%

d. Based on measurements of I-132, I-133 and I-135

Table 6-2  
 ARITHMETIC MEAN OF I-131 REACTOR  
 WATER CONCENTRATIONS FOR DOMESTIC BWR's DURING 1975

Year — 1975

Plant/Month	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.
I-131 Concentration, $\mu$ Ci/kg												
Cooper	0.000724	0.00145	0.00177	0.00228	0.00157	0.00188	0.00328	0.0044	0.00206	—	0.0137	0.0352
Dresden 2	—	—	—	—	—	0.22	0.34	0.24	0.23	0.16	0.21	0.27
Dresden 3	4.2	5.7	5.9	5.8	—	—	—	—	1.5	2.8	2.9	2.4
Duane Arnold	0.00172	0.00169	0.00188	0.00153	0.00182	0.00194	0.00195	0.00224	0.00200	0.00220	0.00258	0.00243
Hatch 1	—	—	0.00196	0.00240	0.00181	0.00402	0.00250	0.00425	0.00549	0.00512	0.00280	0.00330
Millstone Point 1	5.05	6.35	9.35	9.88	9.19	8.48	9.15	19.5	14.4	1.61	3.21	2.45
Monticello	56.0	23.5	31.1	49.8	77	138	203.	175	171	—	—	—
Nine Mile Point 1	1.20	2.54	3.21	4.72	4.71	4.05	4.61	8.33	12.9	—	—	—
Oyster Creek	3.56	4.86	9.96	—	—	1.66	1.96	1.78	1.21	1.30	1.69	1.63
Peach Bottom 2	0.0083	0.0261	0.0200	0.0185	0.0147	—	0.0600	0.0243	0.0215	0.0374	—	0.0277
Peach Bottom 3	0.00292	0.0525	0.0384	0.0826	0.0699	0.0580	0.0202	0.0308	—	0.0294	0.0274	0.0307
Pilgrim 1	14.0	5.70	13.1	15.3	18.0	13.1	18.7	20.9	20.3	—	13.0	17.6
Quad Cities 1	0.041	0.306	0.328	0.921	0.559	0.868	2.48	1.36	0.521	0.650	0.365	0.344
Quad Cities 2	—	—	—	—	2.79	8.25	40.	23.3	9.02	43	0.982	1.97
Vermont Yankee	0.86	0.663	0.738	0.82	0.75	0.85	0.77	0.66	0.79	0.84	0.843	0.725
Browns Ferry 1	0.121	0.933	0.413	—	—	—	—	—	—	—	—	—
Browns Ferry 2	0.0034	0.0083	0.124	—	—	—	—	—	—	—	—	—
Brunswick 2	—	—	—	—	—	—	—	—	—	0.0059	0.0033	0.012

68

NEDO-211592

Table 6-2a  
 ARITHMETIC MEAN OF I-131 REACTOR  
 WATER CONCENTRATIONS FOR DOMESTIC BWR's DURING 1976

Year — 1976

Plant/Month	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.
	I-131 Concentration, $\mu\text{Ci/kg}$											
Cooper	0.0612	0.0382	0.0756	0.0168	0.279	0.0820	0.0250	0.0361	0.0524	—	Cycle 2 0.0103	0.0036
Dresden 2	0.27	0.35	0.28	—	—	0.35	0.21	0.26	0.33	0.26	0.29	0.32
Dresden 3	2.9	2.7	2.5	2.5	4.0	2.6	3.6	3.6	6.8	—	3.5	4.0
Duane Arnold	0.00278	0.00267	—	Cycle 2 0.00739	0.00717	0.00501	0.00519	0.0147	0.0480	0.348	0.238	0.0108
Fitzpatrick	—	—	—	—	—	—	—	0.144	0.112	—	0.179	0.195
Hatch 1	0.00619	0.00693	0.0108	0.0111	0.0952	0.0672	0.0296	0.0188	0.0437	0.179	0.297	0.413
Millstone Point 1	2.24	2.10	0.895	1.73	2.34	2.29	2.65	2.70	—	—	—	1.14
Monticello	7.09	7.91	7.42	9.07	8.40	7.91	7.03	4.95	8.20	6.97	6.04	4.69
Nine Mile Point 1	1.46	1.41	1.14	0.857	1.23	1.50	0.835	1.34	1.99	1.41	1.67	5.63
Oyster Creek	—	—	1.12	1.40	1.23	1.55	1.37	1.95	1.95	2.33	2.75	1.90
Peach Bottom 2	8.43	19.9	79.3	—	—	Cycle 2 0.253	0.522	4.79	0.809	0.786	0.680	1.12
Peach Bottom 3	—	0.0446	0.504	0.257	0.396	0.221	0.591	0.636	1.91	0.767	0.40	0.556
Pilgrim 1	—	—	—	—	—	11.2	12.4	15.5	35.6	11.4	11.6	18.3
Quad Cities 1	—	—	—	1.37	1.31	1.17	3.77	3.15	2.47	7.94	2.40	1.34
Quad Cities 2	2.53	28.8	6.37	8.30	2.38	2.59	1.59	1.87	1.60	—	1.90	13.1
Vermont Yankee	0.538	0.680	0.700	0.603	0.686	0.470	—	0.410	0.483	0.328	0.487	0.328
Browns Ferry 1	—	—	—	—	—	—	—	—	—	—	0.238	0.781
Browns Ferry 2	—	—	—	—	—	—	—	—	—	—	0.030	0.345
Brunswick 2	—	0.0082	—	—	—	0.0055	0.290	1.00	0.441	—	6.15	0.070

Table 6-2b  
 ARITHMETIC MEAN OF I-131 REACTOR  
 WATER CONCENTRATIONS FOR DOMESTIC BWR's DURING 1977

Year — 1977

Plant/Month	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	
	I-131 Concentration, $\mu\text{Ci}/\text{kg}$												
Cooper	0.00828	0.00531	0.00437	0.00369	0.00681	0.00802	0.0364	0.278	0.243	0.00416	0.00459	0.00442	
Dresden 2	0.536	0.55	0.30	0.643	0.593	0.392	0.345	0.303	R.M.	R.M.	R.M.	0.220	
Dresden 3	4.10	4.30	4.90	3.50	2.18	5.14	2.58	2.45	2.90	2.48	7.94	13.6	
Duane Arnold	0.770	0.0950	R.M.	R.M.	0.109	0.00931	0.00919	0.0172	0.0237	0.0244	0.0155	0.0107	
	Cycle 2												
Hatch 1	1.20	1.47	12.7	R.M.	R.M.	0.00968	0.0128	0.0108	0.0832	0.230	0.0170	0.186	
Millstone Point 1	1.19	0.936	1.52	2.88	1.78	1.26	2.65	4.05	2.62	5.91	6.29	6.92	
Monticello	4.95	5.38	4.45	4.71	5.25	5.23	4.95	4.87	5.45	R.M.	3.13	3.10	
Nine Mile Point 1	6.38	8.26	R.M.	R.M.	R.M.	R.M.	R.M.	1.34	1.20	1.44	1.38	1.44	
Oyster Creek	1.97	2.33	2.75	1.71	R.M.	R.M.	R.M.	1.77	2.62	2.60	3.59	4.11	
Peach Bottom 2	1.58	0.728	0.569	2.33	R.M.	R.M.	R.M.	R.M.	R.M.	0.210	0.273	0.344	
	Cycle 2												
Peach Bottom 3	R/M	R.M.	R.M.	R/M	0.697	NA	1.54	0.747	0.610	1.17	1.16	NA	
Pilgrim 1	9.9	16.6	11.6	28.0	17.2	15.7	17.	16.	R.M.	R/M	R/M	0.92	
Quad Cities 1	3.41	2.39	2.15	R/M	R.M.	<LLD	0.312	0.19	5.55	6.98	NA	1.18	
Quad Cities 2	1.95	<LLD	2.61	2.72	7.59	4.49	1.45	7.66	1.72	2.04	<LLD	11.5	
Vermont Yankee	0.391	0.431	0.394	0.383	0.333	0.470	0.554	0.318	R.M.	0.394	0.246	0.287	
Cycle 1	Browns Ferry 1	0.483	0.195	0.0911	2.13	1.04	0.728	0.958	1.53	0.131	R.M.	R.M.	R.M.
	Browns Ferry 2	0.0369	0.0135	0.0220	0.142	10.0	0.800	0.260	0.334	0.0213	0.0207	M	0.00450
	Browns Ferry 3	0.0349	0.0532	0.0605	0.0520	0.165	0.0848	0.787	0.0539	0.0500	0.0450	0.0440	0.0374
	Brunswick 1	NA	0.0139	0.00940	0.0258	M	M	0.0514	0.0213	0.0129	0.00954	0.00997	0.0179
	Brunswick 2	0.402	10.8	0.442	1.04	0.770	1.67	0.923	1.39	4.16	R.M.	R.M.	R.M.
	Cycle 2												
Fitzpatrick	0.198	0.212	0.152	0.122	0.127	0.150	R.M.	R.M.	R.M.	0.0104	0.120	0.0555	

<LLD = less than lower limit of detection

M = maintenance outage

NA = not available

R.M. = refueling/maintenance outage

6-10

NEDO-21159-2

Table 6-3  
SUMMARY OF MEDIANS OF MAXIMUM MONTHLY I-131 REACTOR WATER  
CONCENTRATION AT 15 DOMESTIC BWR'S\*

Plant	Concentration I-131 Ci/Kg	Fractional I-131 Release Resulting From Old Fuel Defects
Copper (from July 1975)	0.039	0.0
Dresden 2	0.27	0.95
Dresden 3	3.5	0.95
Duane Arnold (1975 only)	0.011	0.0
Hatch 1 (1976 only)	0.070	0.0
Millstone Point 1	2.9	0.9
Monticello (from Dec., 1975)	9.0	1.0
Nine Mile Point	2.0	0.8
Oyster Creek	2.0	0.95
Peach Bottom 2	0.88	1.0
Peach Bottom 3	0.76	1.0
Pilgrim 1	19.7	0.95
Quad Cities 1	1.9	0.9
Quad Cities 2	5.4	0.95
Vermont Yankee	0.76	1.0

Notes: a Data for 1975 and 1976 unless otherwise specified

Table 6-4  
IODINE-131 REACTOR WATER CONCENTRATIONS AT BWR'S  
WITH HIGH AMOUNTS OF IMPROVED FUEL IN THE REACTORS\*

Plant	Date Year	Cycle Number	Amount of Improved Fuel %	Mean Monthly I-131 Concentration $\mu\text{Ci/kg}$
Dresden 2	1976	5	44	0.289 $\pm$ 0.0487(7)
Dresden 3	1975-76	4	33	3.138 $\pm$ 1.269(13)
Duane Arnold	1976	2	100	0.0847 $\pm$ 0.1328(8)
Millstone Point 1	1975-76	4	51	2.202 $\pm$ 0.620(11)
Monticello	1975-76	5	100	7.149 $\pm$ 1.282(13)
Nine Mile Point 1	1975	3	38	5.140 $\pm$ 3.505(9)
Nine Mile Point 1	1976	4	76	1.705 $\pm$ 1.275(12)
Oyster Creek	1975	5	c	1.597 $\pm$ 0.307(7)
Oyster Creek	1976	6	c	1.768 $\pm$ 0.542(10)
Peach Bottom 2	1976	2	100	1.281 $\pm$ 1.570(7)
Vermont Yankee	1975-76	3	100	0.727 $\pm$ 0.102(8)
Vermont Yankee	1976	4	100	0.407 $\pm$ 0.078(5)

Notes: (a) Selection of plants excludes reactor in their first fuel cycle

(b) Notation is arithmetic mean  $\pm$  one standard deviation, months of continuous power generation are listed in parentheses

(c) Old-type fuel (7x7) amounts to 40% for cycle 5, and 30% for cycle 6

Table 6-5  
 IODINE-131 REACTOR WATER CONCENTRATION DATA  
 FOR BWR's WITH 100% IMPROVED FUEL

Plant (fuel cycle)	sample date month/day/year	I-131 concentration $\mu\text{Ci/kg}$
Duane Arnold (2)	4/27/76	0.00739
	5/4/76	0.00795
	5/11/76	0.00458
	5/18/76	0.00897
	6/8/76	0.0106
	6/15/76	0.00235
	6/22/76	0.00229
	6/29/76	0.00481
	7/6/76	0.00417
	7/13/76	0.00246
	7/27/76	0.00895
	8/3/76	0.0169
	8/10/76	0.0121
	8/17/76	0.0203
	8/24/76	0.00949
	9/7/76	0.0170
	9/14/76	0.114
	9/21/76	0.0147
	9/28/76	0.0461
	10/5/76	0.0317
	10/12/76	0.0292
	10/19/76	0.0128
	10/26/76	1.32
	11/2/76	0.484
11/9/76	0.0561	
11/18/76	0.105	
11/23/76	0.382	
11/30/76	0.165	
12/7/76	0.0185	
12/14/76	0.00822	
12/28/76	0.00556	
Peach Bottom 2 (2)	6/28/76	0.253
	7/6/76	0.231
	7/12/76	0.861
	7/13/76	0.877
	7/14/76	0.86
	7/20/76	0.499
	7/27/76	0.143
	8/3/76	0.257
	8/17/76	9.32
	9/2/76	0.449
	9/7/76	0.551
	9/14/76	0.555
	9/21/76	0.709
9/30/76	1.78	
10/5/76	0.905	
10/15/76	0.691	

Table 6-5 (Cont.)  
 IODINE-131 REACTOR WATER CONCENTRATION DATA  
 FOR BWR's WITH 100% IMPROVED FUEL

Plant (fuel cycle)	sample date month/day/year	I-131 concentration $\mu\text{Ci/kg}$
Peach Bottom 2 (2)	10/26/76	0.763
	11/2/76	0.645
	11/9/76	0.715
	12/3/76	1.28
	12/7/76	1.15
	12/16/76	0.944
Vermont Yankee (3)	1/9/75	1.03
	1/21/75	0.77
	1/30/75	0.78
	2/4/75	0.738
	2/25/76	0.588
	3/4/75	0.935
	3/12/75	0.880
	3/18/75	0.400
	4/4/75	0.700
	4/8/75	0.670
	4/15/75	1.10
	4/22/75	1.00
	4/29/75	0.64
	5/8/75	0.58
	5/15/75	0.56
	5/22/75	0.96
	5/29/75	0.88
	6/4/75	0.90
	6/20/75	0.73
	6/26/75	0.93
	7/3/75	0.50
	7/11/75	0.69
	7/15/75	1.10
	7/22/75	0.851
	7/29/75	0.703
	8/6/75	0.66
	9/5/75	0.569
	9/11/75	0.770
	9/18/75	0.809
	9/25/75	1.01
10/2/75	0.78	
10/8/75	0.798	
10/14/75	0.824	
10/23/75	0.760	
10/30/75	1.00	
11/4/75	0.863	
11/7/75	0.798	
11/18/75	0.934	
11/26/75	0.778	
12/2/75	0.748	
12/8/75	0.744	

Table 6-5 (Cont.)  
 IODINE-131 REACTOR WATER CONCENTRATION DATA  
 FOR BWR's WITH 100% IMPROVED FUEL

Plant (fuel cycle)	sample date month/day/year	I-131 concentration $\mu\text{Ci/kg}$
Vermont Yankee (3)	12/15/75	0 682
	1/8/76	0 675
	1/13/76	0 670
	1/20/76	0 568
	2/20/76	0 598
	2/24/76	0 761
	3/2/76	0 862
	3/9/76	0 709
	3/30/76	0 519
	4/6/76	0 559
	4/15/76	0 531
	4/20/76	0 588
	4/29/76	0 735
	5/4/76	0 614
	5/11/76	0 832
	5/20/76	0 612
	6/4/76	0 427
6/8/76	0 524	
6/15/76	0 459	
Vermont Yankee (4)	8/19/76	0 475
	8/24/76	0 352
	8/31/76	0 404
	9/7/76	0 559
	9/24/76	0 407
	10/1/76	0 443
	10/8/76	0 271
	10/15/76	0 451
	10/22/76	0 348
	10/28/76	0 128
	11/5/76	0 520
	11/9/76	0 483
	11/16/76	0 458
	12/3/76	0 348
12/7/76	0 225	
12/14/76	0 411	

Note: Data base includes information available from January 1975 to December 1976, excluding experience data for first fuel cycle of BWRs with 100% improved fuel; excludes Monticello data for cycle 5 which has 100% improved fuel but relatively high amounts of tramp uranium due to previous defects in unimproved fuel.



Table 6-6  
COMPARISON OF I-131 REACTOR WATER CONCENTRATIONS AND FUEL BURNUPS.

Plant	BWR Name	I-131 Coolant Concentration and Burnup			
		NEDO-21159 <sup>a</sup>		Present <sup>b</sup>	
		Conc. μCi/Kg	Burnup GWD/t	Conc. μCi/Kg	Burnup GWD/t
A	c	0.08	6.6	2.1	15
B	c	0.2	3.2	0.5	10
C	Cooper	0.005	5.7	0.006	11
D	Duane Arnold	0.005	4.4	0.13	10
E	Vermont Yankee	1.0	5.0	0.43	15
K	c	99.	d	5.4	10

NOTES a Data as of about 12/31/75, concentration values are maximum values reported during fuel cycle to indicated burnup  
 b Data as of about 1/26/77, concentration values correspond to this date.  
 c No permission received from utility to identify plant by name  
 d Unimproved fuel, fuel performance not like improved fuel in other listed plants.

Table 6-7  
SUMMARY OF BWR FUEL TYPES BY PLANT AND RELATED PARAMETERS.

Plant	Rated Power MWR	Fuel Type <sup>b</sup> %			Reactor Water Cleanup Flow % of Feedwater Flow
		7x7	7x7R	8x8	
Cooper	801	2	76	22	1
Dresden 2	810	56	4	39	8
Dresden 3	810	47	7	46	8
Duane Arnold	566	—	77	23	1
Fitzpatrick	850	24	76	—	1
Hatch 1	809	—	—	100	1
Millstone Point 1	650	28	26	46	7
Monticello	543	—	4	96	1
Nine Mile Point 1	620	24	20	56	5
Oyster Creek	641	30	—	—	1
Peach Bottom 2	1098	—	75	25	1
Peach Bottom 3	1098	—	100	—	1
Pilgrim 1	655	74	—	26	2
Quad Cities 1	810	70	4	27	1
Quad Cities 2	810	57	—	43	1
Vermont Yankee	537	—	11	89	1

Notes a Nominal turbine plate rating  
 b Date as of 1/1/77  
 c Nominal capacity is 6% however system always operated at 3% of feedwater flow

Table 6-8  
 NORMALIZED I-131 AIRBORNE RELEASE RATES AT VERMONT YANKEE

Normalized I-131 Release Rate, [ $\mu\text{Ci/s}$ ]

Nominal Sample Period Month/Day/Year	Reactor (0.001)	Turbine (0.001)	Radwaste (0.001)	GS & MVP (0.001)
6:20-7:2:74	0.1400	0.0560	0.0600	0.0120
7:2-7:9:74	0.9600	0.0880	0.1601	2.0001
7:9-7:23:74	0.1680	0.0440	0.0960	0.0148
7:23-7:30:74	0.1040	0.0600	0.0680	0.0195
7:30-8:13:74	0.0633	0.0500	0.0367	0.0146
8:13-8:27:74	0.0514	0.0457	0.0400	0.0114
8:27-9:12:74	0.1105	0.0684	0.0395	0.0084
9:14-9:27:74	0.0271	0.1054	0.0811	NS
9:27-10:10:74	0.0314	0.0215	0.0400	0.0102
10:11-10:13:74	0.5000	} 0.1110	} (0.0694) <sup>d</sup>	1.1667
10:13-10:14:74	0.6389			3.0556
10:14-10:31:74	1.250			(1.16) <sup>d</sup>
10:31-11:1:74	0.444	0.1551	0.0440	0.3611
11:1-11:18:74	0.4722	0.0239	0.0180	0.0172
11:18-12:2:74	0.3333	0.0009	0.0106	0.0047
12:2-12:6:74	0.0333	0.0012	0.0075	0.0049
12:6-12:27:74	0.0639	0.0231	NS	NS
12:27-1:28:75	0.0196	0.0308	0.0196	0.0241
1:28-2:14:75	0.0114	0.0210	0.0157	0.0253
2:14-3:5:75	0.0719	0.0205	0.0157	0.0417
3:5-3:8:75	—	—	—	—
3:8-3:26:75	0.4250	0.0400	0.0437	0.1087
3:26-4:10:75	0.0540	0.0746	0.0191	0.0397
4:10-4:26:75	0.0378	0.0299	0.0098	0.0211
4:26-5:8:75	0.0476	0.0984	0.0279	0.0215
5:8-5:29:75	0.0282	0.1057	0.0225	0.0980
5:29-6:13:75	0.0792	0.0268	0.0167	0.1389
6:13-6:26:75	0.0359	0.0597	0.0339	0.0250
6:26-7:10:75	0.0775	0.0918	0.0452	0.0494
7:10-7:29:75	0.0426	0.0508	0.0688	0.0423
7:29-8:13:75	0.2836	0.0448	0.0150	0.0253
8:13-8:28:75	0.1562	0.0120	0.0032	0.0312
8:28-9:19:75	0.0344	0.0639	0.0098	NS
9:19-10:7:75	0.0365	0.0377	0.0165	0.0588
10:7-10:21:75	0.0896	0.0312	0.0507	0.0181
10:21-11:7:75	0.0247	0.0091	0.0562	0.0270

Notes: (a) Normalized I-131 release rates are based on EPRI/NES measurements  
 (b) Data are normalized to an I-131 Reactor water concentration of  $1\mu\text{Ci/Kg}$   
 (c) Refueling maintenance outage transpired 10:11 to 12:13:74.  
 (d) Numbers in parenthesis are estimated values

Table 6-9  
 NORMALIZED I-131 AIRBORNE RELEASES AT VERMONT YANKEE

Nominal Sample Period Month/Day/Year	Normalized I-131 Release, millicuries			
	Reactor	Turbine	Radwaste	Gland Seal & MVP
6/20-7/2/74	0.1452	0.0581	0.0622	0.0207
7/2-7/9/74	0.5806	0.0532	0.0968	1.210
7/9-7/23/74	0.2032	0.0532	0.1161	0.0179
7/23-7/30/74	0.0629	0.0363	0.0411	0.0118
7/30-8/13/74	0.0766	0.0605	0.0444	0.0177
8/13-8/27/74	0.0622	0.0553	0.0484	0.0138
8/27-9/12/74	0.1528	0.0946	0.0546	0.0116
9/14-9/27/74	0.0304	0.1184	0.0911	NS
9/27-10/10/74	0.0353	0.0241	0.0449	0.0115
10/11-10/13/74	0.0864	} 0.1918	} (0.018) <sup>d</sup>	0.2016
10/13-10/14/74	0.0552			0.2640
10/14-10/31/74	1.836			(0.1) <sup>d</sup>
10/31-11/1/74	0.0384	0.0134	0.0038	0.0312
11/1-11/18/74	0.6936	0.0351	0.0265	0.0253
11/18-12/2/74	0.4032	0.0011	0.0128	0.0057
12/2-12/6/74	0.0115	0.0004	0.0026	0.0017
12/6-12/27/74	0.116	0.042	NS	NS
12/27-1/28/75	0.0543	0.0852	0.0543	0.0667
1/28-2/14/75	0.0167	0.0308	0.0231	0.0372
2/14-3/5/75	0.1180	0.0337	0.0258	0.0685
3/5-3/8/75	—	—	—	—
3/8-3/26/75	0.6610	0.0622	0.0680	0.1691
3/26-4/10/75	0.0070	0.0967	0.0248	0.0514
4/10-4/26/75	0.0522	0.0414	0.0136	0.0292
4/26-5/8/75	0.0493	0.1020	0.0289	0.0223
5/8-5/29/75	0.0511	0.1917	0.0408	0.1779
5/29-6/13/75	0.1026	0.0347	0.0217	0.1800
6/13-6/26/75	0.0403	0.0671	0.0381	0.0281
6/26-7/10/75	0.0937	0.1111	0.0547	0.0597
7/10-7/29/75	0.0700	0.0834	0.1130	0.0695
7/29-8/13/75	0.3675	0.0581	0.0194	0.0328
8/13-8/28/75	0.2025	0.0156	0.0041	0.0405
8/28-9/19/75	0.0654	0.1215	0.0187	NS
9/19-10/7/75	0.0567	0.0586	0.0256	0.0915
10/7-10/21/75	0.1084	0.0377	0.0613	0.0219
10/21-11/7/75	0.0363	0.0134	0.0825	0.0397

Notes (a) Normalized I-131 releases are based on EPRI/NES measurements  
 (b) Data are normalized to an I-131 reactor water concentration of 1.0 μCi/kg for each sample period  
 (c) Refueling/maintenance outage transpired 10/11 to 12/13/74.  
 (d) See Table 6-12 for summary of total I-131 releases  
 (e) Numbers in parentheses are estimated values  
 (f) Sample I-131 carryover is 0.40%

Table 6-10  
 NORMALIZED I-131 AIRBORNE RELEASE RATES AT MONTICELLO

Nominal Sample Period Month:Day:Year	Normalized I-131 Release Rate, [ $\mu\text{Ci/s}$ ]			
	Reactor (0.001)	Turbine (0.001)	Radwaste (0.001)	Roof-Vent (0.001)
11/15-11/17/74	—	—	—	—
11/20-12/5/74	0.3056	0.2639	0.0361	0.6111
12/5-12/18/74	0.1927	0.1133	0.0169	0.3253
12/18-1/6/75	0.1358	0.1045	0.0269	0.2687
1/8-1/9/75	0.1109	0.0745	0.0218	0.2000
1/13-1/15/75	0.4426	0.5574	0.0230	1.0656
1/9-1/13 and 1/15-1/22/75	0.2951	0.6393	0.0105	0.9508
1/22-2/7/75	0.1115	0.1115	0.0046	0.2295
2/7-2/22/75	0.3100	2.8000	0.0450	3.1000
2/22-3/10/75	0.2382	0.5294	0.0076	0.7647
3/10-3/25/75	0.6286	0.5714	NS <sup>a</sup>	1.2000
3/25-4/7/75	0.3589	1.1282	0.0282	1.5128
4/7-4/21/75	0.4038	0.7115	0.0161	1.1346
4/21-5/5/75	NS	0.7611	0.0149	NS <sup>d</sup>
5/5-5/17/75	1.0548	0.7123	0.0191	1.7808
5/19-6/5/75	0.2250	0.2562	0.0218	0.5062
6/5-6/23/75	0.4142	0.2071	0.0378	0.6642
6/23-7/8/75	0.5133	0.2266	0.0500	0.8000
7/8-7/22/75	0.8750	0.2250	0.0400	1.0416
7/11-7/30/75	0.2347	0.1782	0.0369	0.4043
8/5-8/21/75	0.5533	0.3733	0.0246	0.9333
8/21-9/3/75	0.4761	0.5238	0.0304	1.0000
9/3-9/11/75	0.3118	0.3353	0.0194	0.6471
9/11-9/25/75	0.2526	0.0279	0.0153	0.2947
9/25-10/15/75	NS	0.0074	0.0013	NS <sup>d</sup>
10/15-10/27/75	0.0105	0.0011	0.0002	0.0116
10/27-11/14/75	0.0009	0.0003	0.0001	0.0013
11/14-11/17/75	—	—	NS <sup>d</sup>	NS
11/17-11/18/75	3.269	4.14	0.823	NS
11/18-11/18/75	NS	3.71	0.734	NS
11/18-11/19/75	1.655	1.03	0.204	NS
11/19-11/19/75	0.240	0.191	0.037	NS
11/19-11/20/75	0.105	0.056	0.201	NS
11/20-11/21/75	0.186	0.0583	0.0291	NS
11/21-11/21/75	0.173	0.0753	0.0332	NS
11/21-11/22/75	0.150	0.159	0.0143	NS
11/22-11/22/75	0.137	0.0740	0.0150	NS
11/22-11/23/75	0.155	0.136	0.0213	NS
11/23-11/23/75	0.180	0.128	0.0181	NS
11/23-11/24/75	0.238	0.113	NS	NS

Notes (a) Normalized I-131 release rates are based on EPRI/NES measurements.  
 (b) Data are normalized to an I-131 reactor water concentration of 1.0  $\mu\text{Ci/kg}$  for each sample period.  
 (c) Refueling maintenance outages transpired 1/9 to 2/7/75 and 9/11 to 11/17/75.  
 (d) NS indicates that no sample measurement is available.

Table 6-11  
 NORMALIZED I-131 AIRBORNE RELEASES AT MONTICELLO<sup>a, b, c, d</sup>

Nominal Sample Period Month/Day/Year	Normalized I-131 Release, millicuries			
	Reactor	Turbine	Radwaste	Roof-Vent
11/15-11/17/74	—	—	—	—
11/20-12/5/74	0.3960	0.3419	0.0468	0.7919
12/5-12/18/74	0.2165	0.1272	0.0189	0.3654
12/18-1/6/75	0.1715	0.2230	0.0441	0.4410
1/8-1/9/75	0.0096	0.0064	0.0019	0.0173
1/13-1/15/75	0.0765	0.0963	0.0040	0.1841
1/9-1/13 and 1/15-1/22/75	0.2805	0.6077	0.0100	0.9036
1/22-2/7/75	0.1541	0.1541	0.0063	0.3172
2/7-2/22/75	0.0402	3.629	0.0583	4.0180
2/22-3/10/75	0.3294	0.7318	0.0106	1.0571
3/10-3/25/75	0.8145	0.7405	NS <sup>e</sup>	1.5551
3/25-4/7/75	0.4030	1.2671	0.0316	1.6992
4/7-4/21/75	0.4884	0.8607	0.0195	1.3725
4/21-5/5/75	NS	0.9207	0.0181	NS
5/5-5/17/75	1.0935	0.7384	0.0116	1.8465
5/19-6/5/75	0.3305	0.3763	0.0321	0.7437
6/5-6/23/75	0.6442	0.3221	0.0588	1.0328
6/23-7/8/75	0.6652	0.2937	0.0648	1.0366
7/8-7/22/75	1.0583	0.2721	0.0483	1.2600
7/11-7/30/75	0.1622	0.1232	0.0255	0.2794
8/5-8/21/75	0.7646	0.5160	0.0341	1.2900
8/21-9/3/75	0.5347	0.5885	0.0342	1.1230
9/3-9/11/75	0.2155	0.2318	0.0134	0.4472
9/11-9/25/75	0.3056	0.0337	0.0185	0.3565
9/25-10/15/75	NS	0.0127	0.0023	NS
10/15-10/27/75	0.0109	0.0011	0.0002	0.0120
10/27-11/14/75	0.0015	0.0005	0.0001	0.0020
11/14-11/17/75	—	—	NS	NS
11/17-11/18/75	0.2860	0.3620	0.0720	NS
11/18-11/18/75	NS	0.1362	0.0270	NS
11/18-11/19/75	0.0745	0.0464	0.0092	NS
11/19-11/19/75	0.0102	0.0081	0.0016	NS
11/19-11/20/75	0.0062	0.0033	0.0013	NS
11/20-11/21/75	0.0076	0.0024	0.0012	NS
11/21-11/21/75	0.0101	0.0044	0.0019	NS
11/21-11/22/75	0.0085	0.0090	0.0008	NS
11/22-11/22/75	0.0051	0.0028	0.0006	NS
11/22-11/23/75	0.0084	0.0074	0.0012	NS
11/23-11/23/75	0.0059	0.0042	0.0006	NS
11/23-11/24/75	0.0125	0.0060	NS	NS

Notes: (a) Normalized I-131 release rates are based on EPRI-NES measurements  
 (b) Data are normalized to an I-131 reactor water concentration of 1.0  $\mu\text{Ci/kg}$  for each sample period.  
 (c) Refueling/maintenance outages transpired 1/9 to 2/7/75 and 9/11 to 11/17/75.  
 (d) NS indicates that no sample measurement is available.  
 (e) Sample I-131 carryover is 0.45%.  
 (f) See Table 6-12 for a summary of total I-131 releases.

Table 6-12  
 NORMALIZED I-131 AIRBORNE RELEASE RATES AT OYSTER CREEK (1975-1976)

Nominal Sample Period Month/Day/Year	Normalized I-131 Release Rate, ( $\mu\text{Ci/s}$ )			
	Reactor (0.001)	Turbine (0.001)	Radwaste (0.001)	Gland Seal & MVP (0.001)
2/22-2/26/75	0.1154	3.8462	0.0708	NS
2/26-3/12/75	0.0815	4.3077	0.1046	NS
3/12-3/28/75	0.3385	4.3077	0.0754	NS
3/29-4/15/75	0.8154	12.3077	NS	NS
4/15-5/1/75	0.200	8.1538	0.5231	NS
5/1-5/15/75	0.0769	0.7077	NS	NS
5/15-5/29/75	0.0308	0.0646	0.0074	NS
5/29-6/16/75	0.4412	1.7059	0.0941	NS
6/16-6/30/75	0.3667	1.5333	0.0500	0.4667
6/30-7/17/75	0.6471	1.5882	0.2706	0.7176
7/17-8/5/75	0.2333	3.1111	0.5611	3.6667
8/5-8/21/75	0.2063	4.6875	0.4500	1.3750
8/21-9/8/75	0.0714	2.3571	1.3571	3.9286
9/8-9/29/75	0.1385	3.6154	1.4615	NS
9/29-10/14/75	0.1900	0.9500	1.1000	NS
10/14-10/31/75	0.0538	NS	0.3500	NS
10/31-11/14/75	0.0565	4.5294	0.1412	0.3235
11/14-12/4/75	0.6714	3.0714	0.7143	4.0000
12/4-12/18/75	0.1117	4.1176	0.1118	1.1765
12/18-1/5/76	0.7500	2.8125	NS	5.1250
1/5-1/22/76	0.1125	6.5625	0.0681	0.1125
1/22-2/9/76	0.0194	0.8750	0.0506	0.0033

Note: See end of Table 6-12a

Table 6-12a  
 NORMALIZED I-131 AIRBORNE RELEASE RATES AT OYSTER CREEK (1976)<sup>a, b, c</sup>

Normalized I-131 Release Rate, [ $\mu\text{Ci/s}$ ]

Nominal Sample Period Month/Day/Year	Reactor (0.001)	Turbine (0.001)	Radwaste (0.001)	Gland Seal & MVP (0.001)	Feedwater Pump/ Condensate Pump Room Exhaust (0.001)	Reheater Protection System Exhaust (0.001)
6/16-6/23/76	0.167	8.04	0.324	NS <sup>d</sup>	NS	NS
6/23-6/30/76	0.142	8.03	0.185	0.294		NS
6/30-7/7/76	0.168	16.9	0.431	0.379	0.103	NS
7/7-7/13/76	0.0771	10.4	0.447	0.250		NS
7/13-7/20/76	0.107	8.65	0.982	0.416	0.0836	NS
7/20-7/27/76	0.123	9.20	0.0612	0.292		
7/27-8/3/76	18.4	14.4	2.43	61.8	0.0846	0.698
8/3-8/10/76	0.653	8.96	0.359	0.366		
8/10-8/17/76	0.475	12.4	0.117	0.0654	0.149	0.650
8/17-8/24/76	0.327	8.84	0.469	0.305		
8/24-8/30/76	0.700	7.63	0.618	1.31	0.0684	0.924
8/30-9/7/76	0.249	8.49	0.301	1.01		
9/7-9/16/76	0.221	5.63	0.464	1.02		1.14
9/16-9/23/76	0.418	14.7	1.18	1.75		
9/23-9/30/76	0.0341	11.0	3.71	2.05	0.114	0.813
9/30-10/7/76	0.147	7.48	0.500	0.803		
10/7-10/14/76	0.155	7.92	0.307	0.873		0.538
10/14-10/21/76	0.121	6.20	0.200	0.647	0.0719	
10/21-10/28/76	0.112	5.86	0.564	0.627		0.310
10/28-11/4/76	0.0698	4.14	0.214	0.411	0.449	
11/4-11/11/76	0.0951	5.13	0.220	0.571		0.276
11/11-11/18/76	0.0969	4.83	0.319	0.402	0.0971	NS
11/18-11/30/76	0.0861	5.14	0.301	0.599	0.106	0.185

Notes (a) Normalized I-131 release rates are based on EPRINES measurements.

(b) Data are normalized to an I-131 reactor water concentration of 1.0  $\mu\text{Ci/kg}$  for each sample period.

(c) Refueling maintenance outages transpired 3/29 to 5/29/75 and 1/5 to 3/14/76.

(d) NS indicates that no sample measurement is available.

**Table 6-13**  
**NORMALIZED I-131 AIRBORNE RELEASE RATES AT OYSTER CREEK (1975-1976)**

**Normalized I-131 Release, Millicuries**

<b>Nominal Sample Period Month/Day/Year</b>	<b>Reactor</b>	<b>Turbine</b>	<b>Radwaste</b>	<b>Gland Seal &amp; MVP</b>
2-22-2/26/75	0.0398	1.3292	0.0245	NS
2/26-3/12/75	0.0986	5.2108	0.1266	NS
3/12-3/28/75	0.4678	5.9954	0.1042	NS
3/29-4/15/75	1.1977	18.0769	NS	NS
4/15-5/1/75	0.2765	11.2723	0.7231	NS
5/1-5/15/75	0.0931	0.8560	NS	NS
5/15-5/29/75	0.0372	0.0782	0.0089	NS
5/29-6/16/75	0.6859	2.6529	0.1465	NS
6/16-6/30/75	0.4437	1.8547	0.0603	0.5643
6/30-7/17/75	0.9506	2.3329	0.3976	1.0541
7/17-8/5/75	0.3828	5.1072	0.9211	6.0167
8/5-8/21/75	0.2850	6.4813	0.6219	1.9006
8/21-9/8/75	0.1114	3.6657	2.1107	6.1100
9/8-9/29/75	0.2515	6.5600	2.6515	NS
9/29-10/14/75	0.2460	1.231	1.4260	NS
10/14-10/31/75	0.0788	NS	0.5144	NS
10/31-11/14/75	0.0682	5.4788	0.1706	0.3912
11/14-12/4/75	1.1600	5.3071	1.2343	6.9121
12/4-12/18/75	0.1353	4.9806	0.1353	1.4229
12/18-1/5/76	1.1663	4.3738	NS	7.9688
1/5-1/22/76	0.1650	9.6375	0.1000	0.1650
1/22-2/9/76	0.0300	1.3606	0.0788	0.0050

Note: See notes at end of Table 6-13a



Table 6-13a  
 NORMALIZED I-131 AIRBORNE RELEASE RATES AT OYSTER CREEK (1976)<sup>a, b, c, e, f</sup>

## Normalized I-131 Release, Millicuries

Nominal Sample Period Month/Day/Year	Reactor	Turbine	Radwaste	Gland Seal & MVP	Feedwater Pump/ Condensate Pump Room Exhaust	Reheater Protection System Exhaust
6/16-6/23/76	0.10098	4.8601	0.1959	NS <sup>d</sup>	NS	NS
6/23-6/30/76	0.08618	4.8544	0.1117	0.1778		NS
6/30-7/7/76	0.10164	10.214	0.2604	0.2291	0.1249	NS
7/7-7/13/76	0.03998	5.4100	0.2315	0.1295		NS
7/13-7/20/76	0.06475	5.2335	0.05938	0.2516	0.0939	NS
7/20-7/27/76	0.07460	5.5657	0.03699	0.1767		
7/27-8/3/76	11.099	8.6873	1.4674	37.368	0.1023	0.844
8/3-8/10/76	0.39490	5.4211	0.2171	0.2215		
8/10-8/17/76	0.28738	7.4995	0.07086	0.0395	0.2697	0.787
8/17-8/24/76	0.19769	5.3474	0.2836	0.1844		
8/24-8/30/76	0.36287	3.9559	0.3204	0.6799		1.04
8/30-9/7/76	0.17220	5.8660	0.2079	0.6973	0.0828	
9/7-9/16/76	0.17209	4.3773	0.3604	0.7931		1.68
9/16-9/23/76	0.25263	8.8724	0.7142	1.0577		
9/23-9/30/76	0.02065	6.6572	2.2411	1.2419	0.2951	0.983
9/30-10/7/76	0.08870	4.5227	0.3026	0.4856		
10/7-10/14/76	0.09358	4.7882	0.1856	0.5278		0.650
10/14-10/21/76	0.07326	3.7478	0.1209	0.3911	0.0870	
10/21-10/28/76	0.06779	3.5415	0.3409	0.3789		0.375
10/28-11/4/76	0.04223	2.5021	0.1297	0.2488	0.0543	
11/4-11/11/76	0.05752	3.1026	0.1331	0.3452		0.333
11/11-11/18/76	0.05863	2.9186	0.1931	0.2429	0.1175	NS
11/18-11/30/76	0.08926	5.3274	0.3120	0.6210	0.1101	0.191

- Notes: (a) Normalized I-131 releases are based in EPRI/NEES measurements.  
 (b) Data are normalized to an I-131 reactor water concentration of 1.0  $\mu\text{Ci/kg}$  for each sample period.  
 (c) Refueling/maintenance outages transpired 3/29 to 5/29/75 and 1/5 to 3/14/76  
 (d) NS indicates that no sample measurement is available  
 (e) Sample I-131 carryover is 2.3%.  
 (f) See Table 6-12 for a summary of total I-131 releases.

**Table 6-14**  
**SUMMARY BY PLANT OF NORMALIZED I-131 RELEASES AT**  
**VERMONT YANKEE, MONTICELLO AND OYSTER CREEK FOR POWER GENERATION OPERATIONS (300 DAYS)**  
**AND ONE REFUELING/MAINTENANCE OUTAGE <sup>a, b, c</sup>**

Building/Plant	Power Generation Operations (300 Days)		
	I-131 Release, millicuries		
	Vermont Yankee	Monticello <sup>d</sup>	Oyster Creek
	I-131 Release, millicuries		
Reactor	2.49 (53)	10.50 (40)	14.62 (9)
Turbine	1.25 (27)	14.72 (57)	137.65 (83)
Radwaste	<u>0.94 (20)</u>	<u>0.80 (3)</u>	<u>14.21 (9)</u>
Total Building Release =	4.68 mCi	26.03 mCi	166.48 mCi
Gland Seal Steam =	2.00 mCi	—	74.60 mCi
	Refueling/Maintenance Outage <sup>e</sup>		
Reactor	3.12 (83)	0.69 (59)	0.90 (4)
Turbine	0.24 (6)	0.45 (39)	20.64 (88)
Radwaste	<u>0.40 (11)</u>	<u>0.03 (3)</u>	<u>1.96 (8)</u>
Total Building Release =	3.76 mCi	1.17 mCi	23.50 mCi
MVP =	2.4 mCi	—	—

Notes: (a) Normalized I-131 releases are based on EPRINES measurements  
 (b) Data are normalized to an I-131 reactor water concentration of 1.0  $\mu$ Ci/kg.  
 (c) Numbers in parentheses are percentages of total building ventilation release per plant per operation  
 (d) Monticello radwaste release includes input from reactor water cleanup demineralizer which is an input source to reactor building at the other two plants  
 (e) At plants with two R/M outages, the I-131 releases were determined by the arithmetic mean.

**Table 6-15**  
**NORMALIZED I-131 TURBINE**  
**BUILDING RELEASE ADJUSTED TO ONE PERCENT I-131 CARRYOVER <sup>a, b</sup>**

I-131 RELEASE, MILLICURIES	
Power Generation Operations (300 days)	
Vermont Yankee	3.12
Monticello	32.71
Oyster Creek	59.85
Refueling/Maintenance Outage	
Vermont Yankee	0.60
Monticello	1.01
Oyster Creek	8.97

NOTES: (a) At Vermont Yankee gland seal release is 5.0 millicuries and the MVP I-131 release is 6.0 millicuries.  
 (b) At Oyster Creek gland seal I-131 release is 32.4 millicuries.




Figure 6-1. Normal Probability Distribution of Iodine-131 Carryover in BWR's




Figure 6-2. Iodine-131 Reactor Water Concentration at Browns Ferry 1, 1977




Figure 6-3. Iodine-131 Reactor Water Concentration at Browns Ferry 2, 1977




Figure 6-4. Iodine-131 Reactor Water Concentration at Browns Ferry 3, 1977




Figure 6-5. Iodine-131 Reactor Water Concentration at Brunswick 1, 1977




Figure 6-6. Iodine-131 Reactor Water Concentration at Brunswick 2, 1977






Figure 6-7. Iodine-131 Reactor Water Concentration at Cooper, 1975




Figure 6-7a. Iodine-131 Reactor Water Concentration at Cooper, 1976




Figure 6-7b. Iodine-131 Reactor Water Concentration at Cooper, 1977




Figure 6-8. Iodine-131 Reactor Water Concentration at Dresden 2, 1975




Figure 6-8a. Iodine-131 Reactor Water Concentration at Dresden 2, 1976




Figure 6-8b. Iodine-131 Reactor Water Concentration at Dresden 2, 1977




Figure 6-9. Iodine-131 Reactor Water Concentration at Dresden 3, 1975




Figure 6-9a. Iodine-131 Reactor Water Concentration at Dresden 3, 1976






Figure 6-9b. Iodine-131 Reactor Water Concentration at Dresden 3, 1977




Figure 6-10. Iodine-131 Reactor Water Concentration at Duane Arnold, 1975





Figure 6-10a. Iodine-131 Reactor Water Concentration at Duane Arnold, 1976



NEDO-21159-2

Figure 6-10b. Iodine-131 Reactor Water Concentration at Duane Arnold, 1977




Figure 6-11. Iodine-131 Reactor Water Concentration at Fitzpatrick, 1977




Figure 6-12. Iodine-131 Reactor Water Concentration at Hatch 1, 1975




Figure 6-12a. Iodine-131 Reactor Water Concentration at Hatch 1, 1976




Figure 6-12b. Iodine-131 Reactor Water Concentration at Hatch 1, 1977






Figure 6-13. Iodine-131 Reactor Water Concentration at Millstone Point 1, 1975




Figure 6-14. Iodine-131 Reactor Water Concentration at Millstone Point 1, 1976





Figure 6-14a. Iodine-131 Reactor Water Concentration at Millstone Point 1, 1977



NEDO-21159-2

Figure 6-15. Iodine-131 Reactor Water Concentration at Monticello, 1974




Figure 6-16. Iodine-131 Reactor Water Concentration at Monticello, 1975





Figure 6-17. Iodine-131 Reactor Water Concentration at Monticello, 1976

6-53



NEDO 21159-2

Figure 6-17a. Iodine-131 Reactor Water Concentration at Monticello, 1977




Figure 6-18. Iodine-131 Reactor Water Concentration at Nine Mile Point 1, 1975






Figure 6-19. Iodine-131 Reactor Water Concentration at Nine Mile Point 1, 1976




Figure 6-19a. Iodine-131 Reactor Water Concentration at Nine Mile Point 1, 1977




Figure 6-20. Iodine-131 Reactor Water Concentration at Oyster Creek, 1975




Figure 6-21. Iodine-131 Reactor Water Concentration at Oyster Creek, 1976




Figure 6-21a. Iodine-131 Reactor Water Concentration at Oyster Creek, 1977




Figure 6-22. Iodine-131 Reactor Water Concentration at Peach Bottom 2, 1975




Figure 6-23. Iodine-131 Reactor Water Concentration at Peach Bottom 2, 1976




Figure 6-23a. Iodine-131 Reactor Water Concentration at Peach Bottom 2, 1977






Figure 6-24. Iodine-131 Reactor Water Concentration at Peach Bottom 3, 1975




Figure 6-25. Iodine-131 Reactor Water Concentration at Peach Bottom 3, 1976

NEDO-21159-2

6-54




Figure 6-25a. Iodine-131 Reactor Water Concentration at Peach Bottom 3, 1977





Figure 6-26. Iodine-131 Reactor Water Concentration at Pilgrim 1, 1975



NEDO-21159-2

Figure 6-27. Iodine-131 Reactor Water Concentration at Pilgrim 1, 1976




Figure 6-27a. Iodine-131 Reactor Water Concentration at Pilgrim 1, 1977




Figure 6-28. Iodine-131 Reactor Water Concentration at Quad Cities 1, 1975




Figure 6-29. Iodine-131 Reactor Water Concentration at Quad Cities 1, 1976






Figure 6-29a. Iodine-131 Reactor Water Concentration at Quad Cities 1, 1977




Figure 6-30. Iodine-131 Reactor Water Concentration at Quad Cities 2, 1975




Figure 6-31. Iodine-131 Reactor Water Concentration at Quad Cities 2, 1976




Figure 6-31a. Iodine-131 Reactor Water Concentration at Quad Cities 2, 1977




Figure 6-32. Iodine-131 Reactor Water Concentration at Vermont Yankee, 1974




Figure 6-33. Iodine-131 Reactor Water Concentration at Vermont Yankee, 1975




Figure 6-34. Iodine-131 Reactor Water Concentration at Vermont Yankee, 1976




Figure 6-34a. Iodine-131 Reactor Water Concentration at Vermont Yankee, 1977






Figure 6-35. Normal Probability Distribution of Medians of Maximum Monthly I-131 Reactor Water Concentrations During 1975 and 1976 for 15 Domestic BWR's





Figure 6-36. Variation of Median I-131 Reactor Water Concentration in Domestic BWR's for 1975 and 1976

NEDO-21159-2

*Figure 6-37. Deleted*



3.27 (NOT TO SCALE)

1.66 (NOT TO SCALE)

1.05 (NOT TO SCALE)






Figure 6-39. Normalized I-131 Release Rates, Reactor Building Ventilation Exhaust at Monticello (1974 and 1975)

REFUELING/  
MAINTENANCE  
OUTAGE









Figure 6-38. Normalized I-131 Release Rates, Reactor Building Ventilation Exhaust at Vermont Yankee (1974 and 1975)



REFUELING/  
 MAINTENANCE  
 OUTAGE

10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31  
 AUGUST SEPTEMBER OCTOBER NOVEMBER DECEMBER JANUARY FEBRUARY MARCH








Figure G-41. Normalized I-131 Release Rates, Turbine Building Ventilation Exhaust at Vermont Yankee (1974 and 1975)



REFUELING/  
MAINTENANCE  
OUTAGE

31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20  
SEPTEMBER OCTOBER NOVEMBER DECEMBER JANUARY FEBRUARY MARCH APRIL











Figure 6-40. Normalized I-131 Release Rates, Reactor Building Ventilation Exhaust at Oyster Creek (1975 and 1976)





$10^{-3}$  (NOT TO SCALE)

$4.14 \times 10^{-3}$  (NOT TO SCALE)   
 $3.7 \times 10^{-3}$  (NOT TO SCALE)   
 $1.03 \times 10^{-3}$  (NOT TO SCALE) 






Figure 6-42. Normalized I-131 Release Rates, Turbine Building Ventilation Exhaust at Monticello (1974 and 1975)



REFUELING/  
MAINTENANCE  
OUTAGE

10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31  
AUGUST SEPTEMBER OCTOBER NOVEMBER DECEMBER JANUARY FEBRUARY MARCH





(NOT TO SCALE)


$16.9 \times 10^{-3}$

$14.4 \times 10^{-3}$

$14.7 \times 10^{-3}$

$12.4 \times 10^{-3}$

$11.0 \times 10^{-3}$




10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31

APRIL MAY JUNE JULY AUGUST SEPTEMBER OCTOBER NOVEMBER

SAMPLE PERIOD 1975

Figure 6-43 Normalized I-131 Release Rates, Turbine Building Ventilation Exhaust at Oyster Creek (1975 and 1976)








Figure 6-45. Normalized I-131 Release Rates, Radwaste Building Ventilation Exhaust at Monticello (1974 and 1975)










Figure 6-44. Normalized I-131 Release Rates, Radwaste Building Ventilation Exhaust at Vermont Yankee (1974 and 1975)







REFUELING/  
MAINTENANCE  
OUTAGE

31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20 31 10 20  
SEPTEMBER      OCTOBER      NOVEMBER      DECEMBER      JANUARY      FEBRUARY      MARCH      APRIL




Figure 6-46. Normalized I-131 Release Rates, Radwaste Building Ventilation Exhaust at Oyster Creek (1975 and 1976)




Figure 6-47. Bar Graph of Normalized I-131 Airborne Releases at Three BWRs for All Plant Operations




Figure 6-48. Bar Graph of Normalized I-131 Airborne Releases at Three BWRs for Power Generation Operations





Figure 6-49. Bar Graph of Normalized I-131 Airborne Releases at Three BWRs for One Refueling/Maintenance Outage

6-93



NEDO-21159-2

Figure 6-50. Frequency Polygons of Normalized I-131 Airborne Release Rates From Reactor, Turbine and Radwaste Buildings at Vermont Yankee




Figure 6-51. Frequency Polygons of Normalized I-131 Airborne Release Rates from Reactor, Turbine and Radwaste Buildings at Monticello




Figure 6-52. Frequency Polygons of Normalized I-131 Airborne Release Rates From Reactor, Turbine and Radwaste Buildings at Oyster Creek






Figure 6-53. Frequency Polygons of Normalized I-131 Turbine Building Airborne Release Rates Adjusted to I-131 Carryover of 1 Percent




Figure 6-54. Normalized I-131 Turbine Building Airborne Release Rates and Reactor Power at Oyster Creek




Figure 6-55. Cumulative Normalized I-131 Radwaste Building Airborne Release at Vermont Yankee




Figure 6-56. Cumulative Normalized I-131 Turbine Building Airborne Release at Vermont Yankee




Figure 6-57. Cumulative Normalized I-131 Radwaste Building Airborne Release at Vermont Yankee




Figure 6-58. Cumulative Normalized I-131 Reactor Building Airborne Release at Monticello




Figure 6-59. Cumulative Normalized I-131 Turbine Building Airborne Release at Monticello




Figure 6-60. Cumulative Normalized I-131 Radwaste Building Airborne Release at Monticello






Figure 6-61. Cumulative Normalized I-131 Reactor Building Airborne Release at Oyster Creek (1975 - 1976)




Figure 6-62. Cumulative Normalized I-131 Reactor Building Airborne Release at Oyster Creek (1976)




Figure 6-63. Cumulative Normalized I-131 Turbine Building Airborne Release at Oyster Creek (1975 - 1976)




Figure 6-64. Cumulative Normalized I-131 Turbine Building Airborne Release at Oyster Creek (1976)




Figure 6-65. Cumulative Normalized I-131 Radwaste Building Airborne Release at Oyster Creek (1975 - 1976)




Figure 6-66. Cumulative Normalized I-131 Radwaste Building Airborne Release at Oyster Creek (1976)

8-110





Figure 6-67. Trend Analysis of Dresden 2/3 Iodine-131 Airborne Releases from Reactor Building Ventilation Exhaust

NEDO-21159-2

6-111




NEDO-21159-2

Figure 6.68. Trend Analysis of Quad Cities 1,2 Iodine-131 Airborne Releases of Reactor Building Ventilation Exhaust




6-112



NED-21159-2

Figure 6-69. Trend Analysis of Monticello Iodine-131 Airborne Releases from Reactor, Turbine and Radwaste Buildings



NEDO-21159-2

Figure 6.70. Trend Analysis of Pilgrim 1 Iodine-131 Airborne Releases from Reactor, Turbine and Radwaste Buildings

## 7. RESULTS

The additional measurements of airborne I-131 releases since the issuance of the NEDO-21159, March 1976, provides corroborative evidence regarding I-131 species, fuel performance, building ventilation release rates, and gland seal steam/mechanical vacuum pump exhausts.

The percentages of the various I-131 species released from BWRs are summarized in Table 7-1. Most of the elemental I-131 arises from the turbine building ventilation exhaust. A majority of organic I-131 (methyl iodide) is released from the mechanical vacuum pump (MVP). The I-131 species appears to be dependent on its hold-up time in processes and/or plate-out on building or process equipment surfaces. In areas where the I-131 would be delayed the most the relative amount of organic I-131 increases. Additional summaries of I-131 species have been presented in Tables 4-8 and Tables 2-1 to 2-4.

Table 7-2 summarizes the utility data and includes a rough indication of the I-131 reactor water concentrations. Precise estimates are not available for the 24 reactor years of operation, but if the average total annual I-131 release, as measured by the utility, is divided by the approximate mean reactor water concentration to obtain normalized release rates, it is apparent that the annual normalized releases are in most cases in the 10 to 100 millicurie range. This range is comparable to the results calculated from the extensive EPRI/NES measurements, see Table 7-3.

Table 7-3 is a summary of normalized I-131 airborne releases for the three BWR's according to building and plant. The arithmetic mean building I-131 release is indicated for both power generation operations (on 300 days) and a refueling/maintenance outage. The results are conservative because one of the plants (Oyster Creek) can operate with relatively high I-131 releases and cause no significant environmental impact, because the airborne activity is discharged from a tall stack. Thus by use of the simple arithmetic mean these results are skewed in favor of Oyster Creek.

The EPRI/NES study also included an independent method for the determination of normalized I-131 release rates. The results reported by EPRI/NES are compared to the results of this study in Table 7-4. In many instances the results are the same, differences are generally small. Both analyses have the same magnitude for I-131 releases and this confirms the general validity of the results reported here.

A comparison of the current NRC source-term and the results reported here is presented in Table 7-5. The NRC source term for elemental I-131 based on the earlier 1972-1974 measurements can now be reduced by about an order of magnitude.

With regard to the reactor building releases from Mark I/BWR plants relative to Mark III/BWRs it is difficult to assess the division of releases between the containment and the auxiliary/fuel buildings. The reactor building releases were due primarily to problems with the reactor water cleanup pump at Monticello and the sample hood at Oyster Creek, according to the EPRI/NES study. However other plants have different leakage sources in the reactor building. Thus even though the reactor water cleanup is located in the Mark III auxiliary building the releases from it may not be greater than the containment building. The type of sample hood at Oyster Creek is not used in any new BWR's designs and sample hoods are not expected to be a significant in-plant source of I-131. Thus, it is probably best at this time to assume a 50/50 split for releases between the containment and auxiliary buildings.

Figure 7-1 shows the correlation of I-131 concentration in reactor water with percent improved fuel discussed in Section 6.2. At the reactors with 100% improved fuel each reported concentration was considered, Table 6-5, and plotted to determine a frequency distribution, Figure 7-2. Recall that these data include results from Vermont Yankee which still has some tramp uranium in the reactor from the exposure of old-type fuel. This uranium is slowly "burning-off" as indicated by continuing decreases in the I-131 reactor water concentrations, see Figures 6-32, 6-33, and 6-34. From Figure 7-2 a bimodal frequency distribution is apparent, the low value corresponds to fuel performance at Duane Arnold (fuel cycle 2) and the upper from Peach Bottom 2 (fuel cycle 2) and Vermont Yankee (fuel cycle 3 and 4). These data are conveniently presented in the form of a *cumulative* frequency distribution showing the number of observations less than or equal to a specified value, see Figure 7-3.

A summary of iodine-131 reactor water concentrations in domestic BWRs is presented in Appendix C. This summary includes the experience of 21 plants during 1975, 1976 and 1977. The results are the arithmetic mean of data available. Individual utilities have been contacted to verify the data base appropriate to their plant(s). The majority of the plants have verified or modified the data base as appropriate. The values in this document reflect the verified and modified utility input. The plants with mostly improved type fuel (7x7R and 8x8) are the BWR/4s which have experienced fewer defects than other BWRs; accordingly, these plants have lower levels of I-131 in the reactor water in comparison to the other BWRs which have used old-type (7x7) fuel. Two BWRs (Browns Ferry 3 and Brunswick 1) have had an initial core loading of all 8x8 type fuel, the only type of fuel now manufactured by General Electric. These plants exhibit much lower I-131 concentrations,  $<0.2 \mu\text{Ci}/\text{kg}$ . Although this upper limit value is limited to 1 year of data at each plant, it agrees with the above analysis (see Figure 7-1). Due to this limited operating experience, the 8x8 data from these two plants was not used in the determination of the normalized release rates.

A verification of the normalization method for the determination of I-131 release rates was completed. Release rate data were obtained from three BWRs, not included in any of the original studies. The data are from Browns Ferry 1/2/3 during all of 1977. A comparison of the normalized release values of this report and those from the three Browns Ferry reactors is presented in Table 7-6. The available data are presented in Appendix D. These results show that I-131 airborne effluent rates from the reactor and turbine buildings as calculated by the values listed in Chapter 2 (of this report) are always conservative by factors of 1.3, 4.9 and 1.7, for Browns Ferry 1, Browns Ferry 2, and Browns Ferry 3, respectively. Apparently, Unit 2 has extremely little leakage. For the radwaste building, a factor 2.6 was calculated, again indicating that the results of this report lead to conservative values for I-131 airborne releases. This conservatism is quite reasonable because the reference plants Monticello, Oyster Creek and Vermont Yankee all have tall stacks which allow operations with greater leakage due to more favorable atmospheric diffusion conditions.

The above results are on a normalized basis, namely, the same I-131 reactor water concentration, carryover, and an annual fuel cycle. The actual average total I-131 from the Browns Ferry plants indicates an annual release of  $\approx 10$  millicuries per reactor-year (see Appendix D, Table D-1). This total includes all chemical forms of I-131. Thus, the Browns Ferry plants are operating with effluent rates (and no charcoal treatment on the ventilation exhausts) a factor of approximately 10 less than would be calculated by NRC procedures in NUREG 0016, Rev. 1 Draft, June 1978.

**Table 7-1**  
**AMOUNTS OF IODINE-131 SPECIES IN AIRBORNE RELEASES OF BWRs.<sup>a,b</sup>**  
**PROPORTION OF PLANT, %**

Source	I-131 Species		HOI	CH <sub>3</sub> I
	Elemental	Particulate		
Reactor building	15	13	17	12
Turbine building	76	75	49	13
Radwaste building	5	2	4	13
Gland seal steam and MVP	4	10	30	62
Total annual release, millicuries	25.0	8.7	13.0	31.0
Grand total all I-131 species - 78 millicuries				

NOTES (a) Source release is taken to be 300 days of power operations and one refueling maintenance outage  
 (b) The total annual release including all I-131 species for the sources are as follows:  
 reactor - 11 mCi, turbine - 36 mCi, radwaste - 6.2 and gland seal and MVP - 15 mCi

**Table 7-2**  
**SUMMARY OF UTILITY MEASUREMENTS ON I-131 AIRBORNE RELEASES.**

Plant	Sample Period Month/Year	Operating Period Reactor-Years	Approximate Index of I-131 Reactor Water Concentration $\mu\text{Ci/Kg}$	Average Total I-131 Release (all plant operations) Millicuries/Year/Reactor
<u>Reactor Building Release (only)</u>				
Dresden 2/3	1/73-12/76	8	0.3 to 4	46
Quad Cities 1/2	7/73- 6/77	8	2 to 5	80
<u>Reactor, Turbine and Radwaste Buildings</u>				
Monticello	1/74-12/75	2	10-200	1240
	1/76-12/76	1	9	60
Pilgrim 1	1/73- 6/76	3.5	20	480
Peach Bottom 2/3	1/76- 9/76	1.5	0.5-100	440

( effect of improved fuel )

Total Length of Operations = 24. Reactor-Years

**Table 7-3**  
**SUMMARY BY BUILDING OF NORMALIZED I-131 RELEASES AT VERMONT YANKEE,**  
**MONTICELLO AND OYSTER CREEK FOR POWER GENERATION OPERATIONS (300 DAYS)**  
**AND ONE REFUELING/MAINTENANCE OUTAGE. a, b, c, d**

	Power generation	Plant Operation Refueling/maintenance		Annual total
	I-131 release, millicuries			
<b>Reactor Building</b>				
Vermont Yankee	2.49	3.12	=	5.61
Monticello	10.50	0.69	=	11.19
Oyster Creek	14.62	0.90	=	15.52
Arithmetic mean	= 9.20	1.57		
<b>Turbine Building (I-131 Carryover at 1%)</b>				
Vermont Yankee	3.12	0.61	=	3.73
Monticello	32.71	1.01	=	33.72
Oyster Creek	59.85	8.97	=	68.82
Arithmetic mean	= 31.89	3.53		
<b>Radwaste Building</b>				
Vermont Yankee	0.94	0.40	=	1.34
Monticello	0.80	0.03	=	0.83
Oyster Creek	14.21	1.96	=	16.17
Arithmetic mean	= 5.32	0.80		

- NOTES: (1) Data are normalized to an I-131 reactor water concentration of 1.0  $\mu\text{Ci/Kg}$ .  
 (2) Gland seal steam I-131 release (I-131 carryover at 1%) is 5.0 millicuries at Oyster Creek.  
 (3) Mechanical Vacuum Pump (MVP) I-131 release (I-131 carryover at 1%) is 6.0 millicuries at Vermont Yankee.  
 (4) At plants with two R/M outages the I-131 releases were determined by the arithmetic mean.

**Table 7-4**  
**COMPARISON OF NORMALIZED I-131 RELEASES WITH EPRI/NES RESULTS. <sup>a, b</sup>**

Source	Plant Operating Mode			
	Power generation (300 days)		Refueling/maintenance	
	I-131 release, millicuries			
	This report	EPRI/NES	This report	EPRI/NES
Reactor building at:				
Vermont Yankee	2.5	1.5	3.1	3.2
Monticello	11.	11.	0.81	0.93
Oyster Creek	7.7	5.7	1.8	2.5
Turbine building at:				
Vermont Yankee	1.3	2.0	0.24	0.25
Monticello	15.	17.	0.91	0.78
Oyster Creek	79.	98.	41.	48
Radwaste building at:				
Vermont Yankee	0.94	1.0	0.40	0.40
Monticello	0.80	0.73	0.06	0.04
Oyster Creek	13.	13.	2.0	1.4

NOTES: (a) EPRI/NES results evaluated at 1  $\mu$ Ci/kg  
 (b) Oyster Creek results exclude June-November 1976 data

**Table 7-5**  
**COMPARISON OF NORMALIZED I-131 RELEASES WITH THE**  
**CURRENT NRC "SOURCE TERM" <sup>a, b, c</sup>**

**ALL I-131 SPECIES**

Source	(NRC NUREG-0016)	This Report I-131 Reactor Water Concentration	
		at 5 $\mu$ Ci/kg	at 1 $\mu$ Ci/kg
Reactor Building	340	55	11
Turbine Building	190	180	36
Radwaste Building	46	31	6.2
Mechanical Vacuum Pump	<u>30</u>	<u>30</u>	<u>6</u>
	606	296	59

Notes: (a) In dose evaluations the NRC assumes 50% of the total I-131 release is in elemental form or 303 millicuries according to this study the recommended results is 25 millicuries year reactor of I-131 in elemental form  
 (b) Annual releases were calculated at two I-131 reactor water concentrations to illustrate differences between old (1972) values ( 5  $\mu$ Ci/kg) and expected values concentrations based on data to 1976  
 (c) NRC "source term" is NUREG-0016 April 1976 "Calculation of Releases of Radioactive Materials in Gaseous and Liquid Effluents from Boiling Water Reactors (BWR-Gale Code), PP. 1-6 and 2-27.

**Table 7-6  
SUMMARY OF IODINE-131 VENTILATION RELEASES AT BROWNS FERRY SITE  
DURING 1977-NORMALIZED RESULTS<sup>a</sup>**

Reactor and Turbine Building Releases:	PLANT OPERATION				
	Power Operations	Refuel/Maint.	Power Operations	Refuel/Maint.	Power Operations
Reactor Unit	1		2		3
Vent Location (NO.)	Normalized I-131 Release, mCi/Reactor Year				
Reactor Bldg. & Turbine Equip. Rooms (-250)	12.5	5.53	4.422	0.213	10.38
Turbine Operating Floor (4 vents) (-249)	0.094	0.102	0.087	0.013	1.01
Turbine Operating Floor (5 vents) (-251)	0.265	0.073	0.034	0.013	1.68
Annual Normalized Release	18.6		5.1		13.1
Calculated Normalized Release (This Report)	25.0		25.0		22.0
Release Ratio. (This Report/Browns Ferry Plant)	1.3		4.9		1.7
<b>Radwaste Building Release (Unit 1/2/3 Combined):</b>					
Average Normalized Release of the Three Plants			2.41 mCi/reactor-year		
Calculated Normalized Release (This Report)			6.16 mCi/reactor-year		
Release Ratio. (This Report/Browns Ferry Plants)			2.6		

<sup>a</sup> Normalized results calculated from annual (300 days power operations plus one refueling/maintenance outage) releases presented in Appendix D, Table D-1, divided by the appropriate I-131 reactor water concentration. The average annual I-131 concentrations at each plant were as follows: Browns Ferry 1, 0.889  $\mu\text{Ci/kg}$ ; Browns Ferry 2, 1.35  $\mu\text{Ci/kg}$ ; Browns Ferry 3, 0.132  $\mu\text{Ci/kg}$ ; average of three plants, 0.79  $\mu\text{Ci/kg}$ .






Figure 7-1. Correlation of I-131 Concentration in Reactor Water with Amount of Improved Fuel




Figure 7-2. Frequency Polygon of I-131 Reactor Water Concentrations in BWR's with 100% Improved Fuel\*




Figure 7-3. Cumulative Frequency Polygon and Ogive Curve of I-131 Reactor Water Concentrations in BWR's with 100% Improved Fuel\*

## 8. RECOMMENDATIONS

For the purposes of iodine-131 "source terms" for environmental impact evaluations of future BWRs the results of this study are recommended. For each chemical form of I-131, the annual airborne effluent releases are to be determined by the product of normalized release rates from the various release points in a BWR plant and the I-131 reactor water concentration. Iodine-131 reactor water concentrations of  $1\mu\text{Ci}/\text{kg}$  for full-flow condensate treatment and  $2\mu\text{Ci}/\text{kg}$  for pumped-forward heater drain plants are realistic, yet conservative, average values for BWRs.

To date, the extensive BWR operating experience indicates that no charcoal treatment is required on any ventilation exhausts to meet Nuclear Regulatory Commission Appendix I dose objectives.

The measurements of I-131 activities in milk are the most reliable index of potential dose. From operating BWRs, which have released more than 10 times as much I-131 to the environs as expected from future plants, the measured I-131 activities in milk were still sufficiently low such that doses (if the milk were continuously ingested) would equal a fraction of the NRC dose objectives. Thus, it is suggested that the costly monitoring of milk, as currently performed by BWR owners, could be reduced in terms of sample frequency and precision requirements. It is recommended that more simple programs for milk monitoring be developed and implemented.

## 9. ACKNOWLEDGMENTS

The preparation of this amendment required the continued cooperation of many personnel and organizations. The author appreciates the assistance from all who helped make this report possible. Especial thanks are due to Dr. Henry A. Till of the Electric Power Research Institute, who allowed the release of data prior to its formal publication, and to operating-BWR owners who permitted the release of proprietary information on I-131 concentrations in reactor water, I-131 carryover, and I-131 activities in milk. Particularly helpful in the transmittal of utility data were the following personnel: M. Whitmore with the Commonwealth Edison Company, B. Clark with Northern States Power Company, and A. Clements with the Tennessee Valley Authority. Many personnel at the General Electric Company have expended a great deal of effort towards this report, namely, B. J. Dalton, C. G. Ellis, W. J. Michaels, R. H. Thomas and the following Units: Product Services, Reactor Chemistry, Fuel Projects, Safety and Licensing, and Installation and Service Engineering. The author again thanks J. M. Smith for his continuing encouragement and kindly assistance.

**APPENDIX 2A**

**NRC Commissioners' Opinion on 10CFR50  
Appendix I (April 30, 1975): Selected Quotations**

**Quotations From**

**NRC Commissioners' Opinion on**

**10CFR50 Appendix I, dated April 30, 1975**

The following are quotes from the Commissioners' opinion at the time of issuance of Appendix I for ALARA on reactor effluents, on the question of use of environs monitoring data to improve dose calculational models and to change technical specification. This is of particular practical importance on the relationship between radiiodine emissions and actual dose from milk consumption.

The page numbers indicated are from the original typewritten 149 page issue of April 30, 1975. Other publications of the opinion may have other page numbering systems.

**Chapter I: Summary and Statement of Considerations**

**Background**

**Page 4-5**

"The numerical guides of Appendix I which we announce today are a quantitative expression of the meaning of the requirement that radioactive material in effluents released to unrestricted areas from light-water-cooled nuclear power reactors be kept 'as low as practicable.'"

**Page 6**

"The commission believes that the record clearly indicates that any biological effects that might occur at the low levels of these standards have such low probability of occurrence that they would escape detection by present-day methods of observation and measurement."

**Chapter II: Appendix I**

**Section I. Introduction**

**Page 25**

"Design objectives and limiting conditions for operation conforming to the guidelines of this appendix shall be deemed a conclusive showing of compliance with the 'as low as practicable' requirements of 10 CFR sections 50.34a and 50.36a."

**Chapter IV, Guides on Technical Specifications for Limiting Conditions of Operation**

**A. The Rule**

**Page 101**

"If, for any individual light-water-cooled nuclear power reactor, the quantity of radioactive material actually released in effluents to unrestricted areas during any calendar quarter is such as to cause radiation exposure, calculated on the same basis as the design-objective exposure, which would exceed one-half the annual design-objective exposure, the licensee shall make an investigation to identify the causes of these high release rates." . . .

**Page 102**

"The licensee is also required. . . to provide data on measurable levels of radiation and radioactive materials in the environment so that the relationship between quantities of radioactive materials released and radiation dosages to individuals can be evaluated". . .

**Page 103**

"It is further provided that, if the data developed in the surveillance and monitoring program described above show the relationship between quantities of radioactive materials released in effluents and the dose to individuals in unrestricted areas is significantly different from that assumed in the calculations used to determine design-objective limits, the Commission may modify the quantities in the technical specifications defining the limiting conditions for operation in the license that authorized operation of the light-water-cooled nuclear power reactor."

**B. Discussion of Section IV of Appendix I**

**2. Surveillance and Measurement in Operating Plants**

**Page 106-107**

"Quantitative measurement of radioactive materials released in effluents has always been required of persons licensed to operate nuclear power plants."

**Page 107-108**

"This preference for measured confirmation of estimates was shared by other participants. As discussed in Chapter V, the incentives for improving calculational models, which must necessarily be used in establishing design objectives for each reactor, are strong. Measurements at operating reactors are a means for making improvements. We are in sympathy with those who cite the virtues of designing and operating effluent-control systems with the enlightenment of real experience rather than with arbitrarily conservative calculational models. Measured levels of environmental radioactivity are generally small in comparison with values calculated from known or presumed release rates."

**Page 109-110**

"The pathway of greatest concern is the radioiodine course from air to grass to cow to milk to child. The Commission and the Environment Protection Agency made a study of this pathway, including a program of independent measurements in the vicinity of three operating light-water-cooled nuclear power plants. This study and further evidence in the record show the practicability of making useful measurements pertaining to the radioiodine pathway in situations in which radioiodine releases are substantial. We have required, by Appendix I, special surveillance measures for such situations and have adopted an implementation policy that should encourage applicants to use the best data available in any case."

**Chapter V Implementation**

**A. Applicability**

**2. Discussion of Applicability**

**Page 119**

"... We agree that it would be preferable to base evaluations of design objectives on actual operating experience with the reactor in question in cases where substantial relevant information has been accumulated during plant operations."

**B. Implementation of Numerical Guidelines**

**2. Discussion**

**Page 126-127**

"... The necessity of explicit guidance is suggested in the argument that the procedures used by the Regulatory Staff for calculating doses show a predisposition to make unnecessarily conservative assumptions. The draft

Regulatory Guides circulated by the Directorate of Regulatory Standards with the Staff's concluding statement reflect a tendency toward the use of unnecessarily conservative calculational assumptions. The calculational methods described in the Final Environmental Statement and in draft Regulatory Guides are opposed in some particulars; furthermore it was argued that the Staff has, in the course of reactor licensing actions, generally been quite conservative in its quantitative assessment of effluent controls.

Particular areas of controversy shifted as the hearing progressed. It was not clear to participants whether or not models and assumptions used in the Final Environmental Statement were also intended by the Regulatory Staff to be applicable to the analysis of individual applications for licenses in the implementation of Appendix I. Examples of allegedly unnecessarily conservative implementation methods as they have been used in current licensing, include: excessive source-term assumptions with regard to radiiodine emissions; neglect, with regard to such emissions, of their chemical form, actual release points and modes, and expected plume behavior; overestimation of disposition rates and retention factors for radiiodine on forages, and postulation of nonexistent dairy cows and unrealistic milk-consumption patterns."

**Page 130**

"...Our resolution strongly favors the suggestions that calculational methods be realistic, which in turn has influenced our adoption of particular numerical guideline values for dose objectives..."

**Page 131-133**

"The essence of our conclusions on how calculational procedures should be used in determining design objectives is given in the five following points.

- (1) *An applicant should be free to use as realistic a model for characterizing natural phenomena, including plant performance, as he considers useful. An applicant may take into account situations not adequately characterized by such standardized models as may be available with respect to specific features of plant design, proposed modes of plant operation, or local natural environmental features which are not likely to change significantly during the term of plant operation.*

...several effects that should be recognized, and we restate some of them here to illustrate natural phenomena that might be partially or entirely neglected in standard models but could be properly considered:

- (a) radioisotopic composition of effluents;
- (b) radioactive decay of released nuclides prior to exposure of the receptor;
- (c) waterway flow and the associated diffusion and dilution;
- (d) removal of radioactive material from solution or suspension in the water by sedimentation or other naturally occurring mechanisms or by water-treatment processes;
- (e) exposure modes and occupancy or use factors;
- (f) release conditions (to the atmosphere) including elevation of release point, effluent stream buoyancy and momentum, and building geometry;
- (g) local meteorological and aerodynamic conditions influencing airborne effluent plume dispersion;
- (h) beta and gamma radiation energies for the radioisotopes released and the associated dose effects;
- (i) chemical form and physical behavior of the effluent constituents;
- (j) plume elevation, size, and depletion;



- (k) shielding effects;
- (l) partitioning, filtration, and other retention and depletion effects;
- (m) deposition rates and velocities for the various chemical forms of released radioiodine on offsite vegetation, ground, and other surfaces, with appropriate apportionment to the vegetation of its capture fraction; and
- (n) weathering and other loss factors for radioiodine on grass and other vegetation.

Clearly other natural phenomena must also be adequately taken into account in models used for determining design objectives, but these are sufficiently established in practice that they need not be repeated here."

**Page 134**

"The models last proposed by the Regulatory Staff are different from the highly criticized versions used in the evaluations presented in the Final Environmental Statement. Testimony of the Staff indicates that the models used by the Staff and described in Regulatory Guides will continue to change. We believe Regulatory Guides to be useful; however, Regulatory Guide models should not be applied as a norm to be abandoned at the peril of the applicant. We believe the testimony of Staff witnesses in this hearing might, by some reasonable persons, indeed be construed as indicating that the Staff has been excessively zealous in applying Regulatory Guide models. We particularly expect all parties to licensing actions to which Appendix I applies to note both the potential utility of Regulatory Guides and their subordinate status relative to Commission regulations and opinions."

**Page 135-136**

"... We believe that the opportunity to modify models and data as new experimental information comes to light could have substantial advantages over a rigid rule, which is a persuasive argument for permitting this matter to be dealt with by the preparation of Regulatory Guides and be case-by-case evaluations."

**Page 138**

"The models described in the hearing record and the evidence and arguments advanced with regard to numerical estimation of dose lead us to the conclusion that one should try to attain realistic estimates; but, where uncertainties exist, one should choose calculational procedures that are unlikely to produce substantial underestimates. We believe, furthermore, that it is in the best interest of the public to make realistic estimates, even with uncertain data, and to depend upon the programs for improving models and data, particularly programs of in-plant measurements, to determine whether proper case-by-case design decisions were made. . . ."

**Page 148**

"Furthermore the evidence shows that with additional experience and data from operating plants the most likely result will be that estimates based upon present-day models and assumptions are unrealistically high. . . ."

**APPENDIX 2B**

**Iodine-131 Species Measurements  
of In-Plant Equipment Compartments  
and SJAE Delay Pipe Exhaust**

Table B-1  
I-131 SPECIES — IN-PLANT COMPARTMENTS/REACTOR BUILDING

Plant	Compartment	Sample Date Month/Day/Year	Species, % of I-131 Release				I-131 Release Rate, μCi/s (0.001)	Plant Operating Condition	Sample Time Days
			Particulate	I <sub>2</sub>	HOI	CH <sub>3</sub> I			
Monticello	Fuel Pool Skimmer	11-5 — 11-7-74	24.1	22.7	20.8	32.4	0.16	O	2
		1-8 — 1-9-75	40.8	59.2	27.0	27.0	0.10	O	1
		1-13 — 1-15-75	2.8	52.6	37.4	7.3	22.0	R	2
		9-11 — 9-25-75	3.5	30.2	37.4	28.9	20.0	R	14
		9-25 — 10-15-75	2.0	20.0	(0.3)	(77.5)	7.8	R	20
		10-15 — 10-27-75	3.4	21.3	(2.6)	(75.6)	1.7	R	12
		10-27 — 11-14	2.4	31.0	(2.7)	(69.0)	0.12	R	18
Monticello	Sampling Hood	11-5 — 11-7-74	6.4	19.0	9.3	65.3	0.49	O	2
		1-8 — 1-9-75	16.1	75.0	4.0	8.5	0.078	O	1
		1-12 — 1-15-75	2.4	44.7	15.1	37.3	0.22	R	2
Monticello	Containment purge to Standby Gas Treatment System	11-17 — 11-18-74	0.3	6.2	16.1	77.4	2.4	O	1
		1-9 — 1-10-75	7.9	8.0	25.4	58.7	1.9	R	1
		1-10 — 1-12-75	0.2	2.9	14.6	82.3	1.1	R	2
		1-12 — 1-14-75	0.3	5.6	28.1	66.0	0.32	R	2
Monticello	Standby Gas Treatment System	5-16 — 5-17-75 (1700 hrs — 1555 hrs)	Inlet				3.6	O	0.96
			2.3	19.2	50.4	28.1			
			Outlet				0.21	O	0.96
			2.8	14.8	17.9	65.5			
Monticello	Clean-up pump room exhaust	0015, 5-19 to 1020, 5-19-75	19.1	45.4	29.1	6.4	36.0	O	0.42
		1920, 7-30 to 0832, 7-31-75	23.0	42.8	26.5	7.7	110.0	O	0.55
		0856, 7-31 to 2007, 7-31-75	26.9	35.9	29.1	8.1	96.0	O	0.47

28-1

NEDO-21159-2

Table B-1  
I-131 SPECIES — IN-PLANT COMPARTMENTS/REACTOR BUILDING (Continued)

Plant	Compartment	Sample Date Month/Day/Year	Species. % of I-131 Release			I-131 Release Rate, μCi/s (0.001)	Plant Operating Condition	Sample Time Days	
			Particulate	I <sub>2</sub>	HOI				CH <sub>3</sub> I
		2010, 7-31 to 0917, 8-1-75	27.9	34.9	27.9	92	95.0	O	0.55
		0920, 8-1 to 2232, 8-1-75	29.9	39.5	22.5	8.1	95.0	O	0.55
		1920, 7-30 to 2232, 8-1-75	23.7	36.2	30.9	9.2	100.0	O	2.1
Nine Mile Point 1	Drywell Purge	3-29-74	21.8	10.9	0.0	67.3	1.47	R	0.11
Nine Mile Point 1	Steam Dome	4-1-74	1.1	35.9	27.5	35.4	NA	R	0.18

2B-2

NEDO-21159-2

NOTE (1) All measurements sponsored by EPRI (conducted by NES) except those at Nine Mile Point 1 which were done by GE.  
 (2) Plant mode notation: O — Power Generation Operations (which may include brief plant shutdowns); R — Refueling maintenance outage.  
 (3) I-131 Release rate notation: 0.16 (0.001) = 0.00016 microcuries/second.

Table B-2  
**I-131 SPECIES — IN PLANT COMPARTMENTS/TURBINE BUILDING**  
 (ALL MEASUREMENTS SPONSORED BY EPRI, CONDUCTED BY NES)

Plant	Compartment	Sample Date Month/Day/Year	Species. % of I-131 Release				I-131 Release Rate, μCi/s (0.001)	Plant Operating Condition	Sample Time Days
			Particulate	I <sub>2</sub>	HOI	CH <sub>3</sub> I			
Monticello	Condenser area	11-15 — 11-17-74	18.4	53.1	12.2	16.3	2.9	D	2
		1-8 — 1-9-75	13.8	68.6	9.2	8.4	3.4	O	1
		1-13 — 1-15-75	1.4	50.7	16.9	32.4	22.0	R	2
		5-12 — 5-15-75	26.5	51.5	15.4	6.6	31.0	O	3
		9-11 — 9-25-75	8.1	31.3	40.0	20.6	4.7	R	14
		9-25 — 10-15	2.3	9.4	(0.4)	(88.0)	1.3	R	20
		10-15 — 10-27	<2.4	17.6	(<3.2)	(82.4)	0.17	R	12
		10-27 — 11-14-75	<7.1	<11.9	(<11.9)	(100.0)	0.058	R	18
Oyster Creek	Condenser area (top)	3-27 — 3-28-75	38.0	48.0	10.0	4.0		O	1
	(bottom)	3-27 — 3-28-75	51.0	40.0	9.0	<1.0		O	1
Vermont Yankee	Condenser area	9-12 — 9-14-74	30.4	60.6	6.7	1.6	4.1	O	2
		10-31 — 11-1-74	1.0	9.0	47.0	43.0	5.6	R	1
Monticello	SJAE Room	11-15 — 11-17-74	3.4	30.4	16.3	50.0	0.5	O	2
		1-8 — 1-9-75	12.6	43.3	28.8	15.3	0.62	O	1
		1-13 — 1-15-75	4.0	71.6	13.8	10.5	2.8	R	2
Monticello	MVP Room	11-18 — 11-19-74	2.2	26.5	37.0	34.0	0.3	O	1
		1-8 — 1-9-75	<6.8	40.8	15.0	44.8	0.1	O	1
		1-13 — 1-15-75	3.0	30.6	24.2	42.2	2.8	R	2
Monticello	Operating floor	1-8 — 1-9-75	<12.7	63.3	36.7	<19.0	0.11	O	1
		1-12 — 1-15-75	2.9	26.0	23.0	48.0	7.8	R	2
Oyster Creek	Operating floor	2-22 — 2-27-75	32.0	43.0	21.0	4.0	4.0	O	5

28-3

NEDO-21159-2

Table B-2  
**I-131 SPECIES — IN PLANT COMPARTMENTS/TURBINE BUILDING**  
 (ALL MEASUREMENTS SPONSORED BY EPRI, CONDUCTED BY NES) (Continued)

Plant	Compartment	Sample Date Month/Day/Year	Species, % of I-131 Release				I-131 Release Rate, μCi/s (0.001)	Plant Operating Condition	Sample Time Days
			Particulate	I <sub>2</sub>	HOI	CH <sub>3</sub> I			
Oyster Creek	Heater Bay 1	2-22 — 2-27-75	17.0	60.0	20.0	3.0	NA	O	5
	2	2-22 — 2-27-75	16.0	56.0	23.0	5.0		O	5
	2	3-30 — 3-31-75	6.4	18.2	14.5	60.9		R	1
	3	2-22 — 2-27-75	17.0	55.0	23.0	5.0		O	5
	4	2-22 — 2-27-75	17.0	55.0	23.0	5.0		O	5
	5	2-22 — 2-27-75	27.0	47.0	20.0	6.0		O	5
	5	3-30 — 3-31-75	<2.0	42.9	20.2	36.9		R	1
	6	2-22 — 2-27-75	25.0	50.0	19.0	6.0		O	5
Oyster Creek	Climate	2-22 — 2-27-75	25.0	50.0	20.0	5.0	NA		5
		3-30 — 3-31-75	5.7	33.5	13.6	47.3	NA	R	1
Oyster Creek	Reheater area (top)	3-27 — 3-28-75	17.0	67.0	13.0	3.0	NA	O	1
	(middle)	3-27 — 3-28-75	1.0	79.0	12.0	8.0		O	1
	(bottom)	3-27 — 3-28-75	21.0	68.0	7.0	4.0		O	1
	exhaust	4-1 — 4-2-75	0.2	11.0	58.8	30.0		R	1

NOTES (1) Plant Mode notation: O - Power Generation Operations (which may include brief plant shutdowns), R - refueling, maintenance outages  
 (2) I-131 Release Rate notation: 2.9 (0.001) = 0.0029 microcuries/second  
 (3) NA - Data not available

2B-4

NEDO-21159-2

Table B-3  
 SUMMARY OF MEASUREMENTS OF IODINE-131 CHEMICAL FORM IN  
 BWR STEAM-JET AIR-EJECTOR DELAY LINE

Plant	Sample Period Month/Day/Year	Species. % of I-131 Release				Measurements By	Sample Time Days
		Particulate	I <sub>2</sub>	HOI	CH <sub>3</sub> I		
Oyster Creek	6-16 — 6-23-76		No Sample			EPRI(NES)	7
Oyster Creek	6-23 — 6-30-76	<0.1	1.0	18.0	81	EPRI(NES)	7
Oyster Creek	6-30 — 7-7-76	<0.1	0.1	19.0	81	EPRI(NES)	7
Oyster Creek	7-7 — 7-13-76		Sample Lost			EPRI(NES)	6
Oyster Creek	7-13 — 7-20-76	0.1	<0.1	18.0	82	EPRI(NES)	7
Oyster Creek	7-20 — 7-27-76	0.1	3.0	16.0	81	EPRI(NES)	7
Oyster Creek	7-27 — 8-3-76	<0.1	1.0	10.0	89	EPRI(NES)	7
Oyster Creek	8-3 — 8-10-76	<0.1	1.0	24.0	75	EPRI(NES)	7
Oyster Creek	8-10 — 8-17-76	<0.1	0.4	19.0	80	EPRI(NES)	7
Oyster Creek	8-17 — 8-24-76	<0.1	1.0	17.0	82	EPRI(NES)	7
Oyster Creek	8-24 — 8-30-76	<0.1	3.0	18.0	79	EPRI(NES)	6
Oyster Creek	8-30 — 9-7-76	<0.1	1.0	25.0	74	EPRI(NES)	8
Oyster Creek	9-7 — 9-16-76	<0.1	0.4	33.0	67	EPRI(NES)	9
Oyster Creek	9-16 — 9-23-76	<0.1	0.4	12.0	88	EPRI(NES)	7
Oyster Creek	9-23 — 9-30-76	<0.1	<0.1	13.0	87	EPRI(NES)	7
Oyster Creek	9-30 — 10-7-76	<0.1	0.2	6.0	94	EPRI(NES)	7
Oyster Creek	10-7 — 10-14-76	<0.1	0.1	<0.1	100	EPRI(NES)	7
Oyster Creek	10-14 — 10-21-76	<0.1	0.2	6.0	94	EPRI(NES)	7
Oyster Creek	10-21 — 10-28-76	<0.1	0.1	3.0	97	EPRI(NES)	7
Oyster Creek	10-28 — 11-4-76	<0.1	0.1	1.0	99	EPRI(NES)	7
Oyster Creek	11-4 — 11-11-76	<0.1	0.1	2.0	98	EPRI(NES)	7
Oyster Creek	11-11 — 11-18-76	<0.1	0.1	1.0	99	EPRI(NES)	7
Oyster Creek	11-18 — 11-30-76	<0.1	0.1	1.0	99	EPRI(NES)	12

NEDO-21159-2

**APPENDIX 2C**

**Summary of Iodine-131 Reactor Water Concentrations  
in BWRs (1975 to 1977), Average Annual Values**



Table C-1  
 SUMMARY OF IODINE-131 REACTOR WATER CONCENTRATIONS  
 IN BWRs (1975-1977), AVERAGE ANNUAL VALUES

Type	Condensate Treatment	Plant	Year		
			1975	1976	1977
			I-131 Concentration, $\mu\text{Ci/Kg}$		
2	Full-Flow	Nine Mile Point 1	4.5	1.9	3.0
		Oyster Creek	<u>3.2</u>	<u>1.7</u>	<u>2.7</u>
		Average	3.9	1.8	2.9
3	Full-Flow	Dresden 2	0.24	0.29	0.64
		Dresden 3	3.9	3.5	4.9
		Millstone Point 1	8.0	2.0	3.2
		Monticello	101.	7.3	4.7
		Pilgrim 1	16.	16.	17.
		Quad Cities 1	0.83	2.7	6.5
		Quad Cities 2	<u>16</u>	<u>6.1</u>	<u>3.6</u>
Average	21	5.4	5.9		
4	Full-Flow	Browns Ferry 1	0.46	0.55	0.89
		Browns Ferry 2	0.046	0.17	1.4
		Browns Ferry 3	—	—	0.13
		Cooper	0.0061	0.054	0.044
		Duane Arnold	0.0020	0.082	0.036
		Fitzpatrick	—	0.14	0.12
		Hatch 1	0.0034	0.11	0.89
		Peach Bottom 2	0.028	12.	5.2
		Peach Bottom 3	0.043	0.59	1.0
		Vermont Yankee	<u>0.79</u>	<u>0.52</u>	<u>0.38</u>
		Average	0.17	1.6	1.0
4	Pump-Forward	Brunswick 1	—	—	0.017
		Brunswick 2	<u>0.0070</u>	<u>0.89</u>	<u>3.0</u>
		Average	0.0070	0.89	1.5

**APPENDIX 2D**

**Summary of Data Available for Iodine-131  
Ventilation Releases at Browns Ferry During 1977**

**Table D-1**  
**SUMMARY OF ACTUAL IODINE-131 VENTILATION RELEASES AT BROWNS FERRY DURING 1977**

Plant	Vent No. <sup>a</sup>	Vent Flow		I-131 Conc.		I-131 Release		Sample Period		I-131 Release		Total Plant I-131 Release mCi/Reactor Yr.
		Rate cc/s		(avg.) μCi/cc		Rate (avg.) μCi/s		Power Oper.	Refuel/Maint.	Power Oper.	Refuel/Maint.	
Browns Ferry 1	1-250	11.9	E-7	36.2	E-13	43.0	E-5	257	—	11.1	—	= 16.5
	1-250	11.9	E-7	45.1	E-13	53.7	E-5	—	106	—	4.92	
	1-249	2.98	E-7	3.00	E-13	0.322	E-5	(108-00S) <sup>c</sup>	—	0.0834	—	
	1-249	2.98	E-7	12.6	E-13	1.62	E-5	—	(28-00S)	—	0.0910	
	1-251	3.27	E-7	7.61	E-13	0.912	E-5	(110-00S)	—	0.236	—	
	1-251	3.27	E-7	4.19	E-13	1.16	E-5	—	(55-00S)	—	0.0650	
<b>Totals</b>										11.4	5.07	
Browns Ferry 2	2-250	12.6	E-7	18.3	E-13	23.0	E-5	296	—	5.97	—	= 6.45
	2-250	12.6	E-7	3.56	E-13	4.49	E-5	—	74	—	0.287	
	2-249	3.03	E-7	4.89	E-13	0.450	E-5	(91-00S)	—	0.117	—	
	2-249	3.03	E-7	3.36	E-13	0.313	E-5	—	(20-00S)	—	0.0176	
	2-251	3.79	E-7	1.53	E-13	0.176	E-5	(91-00S)	—	0.0455	—	
	2-251	3.79	E-7	2.67	E-13	0.312	E-5	—	(20-00S)	—	0.0175	
<b>Totals</b>										6.13	0.322	
Browns Ferry 3	3-250	12.1	E-7	4.37	E-13	5.29	E-5	365	—	1.37	No Outage	= 1.73
	3-249	2.58	E-7	2.86	E-13	0.514	E-5	(209-00S)	—	0.133	During	
	3-251	3.23	E-7	4.55	E-13	0.857	E-5	(175-00S)	—	0.222	Year	
<b>Totals</b>										1.73		
Browns Ferry 1/2/3	0-252	1.61	E-7	112.	E-13	18.0		365		5.69	(three plants)	= 1.90 <sup>d</sup>

**NOTES**

- a Vent-250 releases are from reactor building and certain equipment rooms in turbine building. Vent-249 are releases from four fans over operating floor of turbine building. Vent-251 releases are from 5 fans over operating floor of turbine building.
- b Releases adjusted to 300 days of power operation per year plus one RM outage.
- c Notations: 11.9 E-7 = 11.9 × 10<sup>-7</sup>; 00S = Out of Service.
- d Radwaste building processes wastes from all three reactors. Annual release taken as total release divided by three.
- 1 Average I-131 reactor water concentration (μCi/kg) during power operation is as follows: Unit 1: 0.890; Unit 2: 1.35; Unit 3: 0.131.
- 2 Average I-131 release per plant (total of reactor, turbine and radwaste building ventilation releases): (16.5 + 6.45 + 1.73) ÷ 3 = 10.1 mCi reactor year.

Table D-2  
 IODINE-131 VENT MONITOR MEASUREMENTS AT BROWNS FERRY 1  
 DURING 1977, MONITOR 1-250 (REACTOR BUILDING AND EQUIPMENT  
 ROOMS IN TURBINE BUILDING, FLOW RATE =  $11.9 \times 10^6$  cc/s).

Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{12}$	Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{12}$
12/31-1/7	0.505	5/26-5/27	4.42
1/6-1/7	7.95	5/27-6/4	3.73
1/7-1/15	0.116	6/4-6/11	43.5
1/15-1/21	<0.0161	6/11-6/17	5.17
1/21-1/25	<0.126	6/17-6/20	0.334
1/25-1/26	<0.399	6/20-6/21	1.61
1/26-1/27	1.51	6/21-6/24	2.31
1/27-1/27	<3.50	6/24-7/1	0.590
1/27-1/29	1.00	7/1-7/7	2.31
1/29-2/4	0.352	7/7-7/8	0.880
2/4-2/11	0.152	7/8-7/9	0.723
2/11-2/13	9.80	7/9-7/11	2.16
2/13-2/13	2.90	7/11-7/11	5.52
2/13-2/14	4.79	7/11-7/15	2.44
2/14-2/16	2.17	7/15-7/21	2.28
2/16-2/17	2.67	7/21-7/22	2.73
2/17-2/18	1.15	7/22-7/27	1.66
2/18-2/21	0.342	7/27-7/28	1.14
2/21-2/22	<0.435	7/28-7/29	5.67
2/22-2/26	0.327	7/29-8/5	12.9
2/26-3/5	0.119	8/5-8/13	3.82
3/5-3/11	0.234	8/13-8/19	2.26
3/11-3/12	<0.834	8/19-8/22	2.30
3/12-3/12	<4.10	8/22-8/23	2.29
3/12-3/13	<0.544	8/23-8/26	1.36
3/13-3/14	<0.480	8/26-8/30	1.18
3/14-3/18	0.391	9/2-9/9	0.691
3/18-3/21	<0.215	9/9-9/16	0.806
3/21-3/22	<0.631	9/16-9/20	12.2
3/22-3/24	0.651	9/20-9/21	12.7
3/24-3/24	0.843	9/21-9/23	4.77
3/24-3/25	<2.17	9/23-9/30	2.50
3/25-3/25	1.37	9/30-10/8	40.4
3/25-4/2	0.864	10/8-10/14	6.85
4/1-4/9	0.447	10/14-10/22	3.86
4/9-4/15	0.490	10/22-10/24	0.335
4/15-4/22	1.49	10/24-10/25	1.25
4/22-4/25	15.7	10/25-10/29	13.6
4/25-4/26	9.15	10/29-11/4	0.512
4/26-4/30	37.3	11/4-11/12	0.563
4/30-5/6	<2.54	11/12-11/19	<0.137
5/6-5/13	2.88	11/19-11/21	<0.318
5/13-5/20	1.32	11/21-11/22	<1.11
5/20-5/23	5.55	11/22-11/26	0.812
5/23-5/23	7.95	11/26-12/3	0.269
5/23-5/23	9.96	12/3-12/9	0.158
5/23-5/24	<5.56	12/9-12/16	<0.162
5/24-5/24	4.51	12/16-12/19	<0.266
5/24-5/26	<2.56	12/19-12/20	<0.629
5/26-5/28	<4.78	12/20-12/23	<0.183
5/26-5/26	4.21	12/23-12/31	<0.115

**Table D-3**  
**IODINE-131 VENT MONITOR MEASUREMENTS AT BROWNS FERRY 1**  
**DURING 1977, MONITOR 1-249 (FOUR VENTS OVER OPERATING FLOOR**  
**OF TURBINE BUILDING, FLOW RATE =  $2.98 \times 10^7$  cc/s).**

Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^7$
1/1 -5/27	Out of Service
5/27-5/27	<0.993
5/27-6/4	<0.108
6/4 -6/10	0.657
6/10-6/17	0.332
6/17-6/20	<0.253
6/20-6/21	<0.510
6/21-6/24	0.210
6/24-7/1	0.157
7/1 -7/9	0.135
7/9 -7/10	<0.104
7/15-7/22	<0.0823
7/22-7/27	<0.159
7/27-7/28	<0.456
7/28-7/29	<0.195
7/29-8/5	0.984
8/5 -8/13	0.307
8/13-8/19	0.279
8/19-8/22	0.208
8/22-8/23	<0.417
8/23-8/26	<0.158
8/26-8/30	<0.175
8/30-9/2	<0.153
9/2 -9/9	<0.0824
9/9 -9/16	<0.0855
9/16-9/20	<0.248
9/20-9/21	<0.538
9/21-9/23	1.26
9/23-9/30	1.07
9/30-10/8	3.79
10/8-10/14	<0.672
10/14-12/31	Out of Service

**Table D-4**  
**IODINE-131 VENT MONITOR MEASUREMENTS AT BROWNS FERRY 1**  
**DURING 1977, MONITOR 1-251 (FIVE VENTS OVER OPERATING FLOOR**  
**OF TURBINE BUILDING, FLOW RATE =  $3.72 \times 10^7$  cc/s).**

Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^7$
1/1 -5/27	Out of Service
5/27-5/27	<1.14
5/27-6/4	0.344
6/4 -6/10	0.751
6/10-6/17	0.491
6/17-6/20	<0.299
6/20-6/21	<0.706
6/21-6/24	<0.294
6/24-7/1	<0.184
7/1-7/7	<0.184
7/8-7/9	<0.139
7/15-7/21	0.165
7/21-7/22	<6.57
7/22-7/23	4.03
7/22-7/27	<0.225
7/27-7/28	<0.677
7/28-7/29	<0.289
7/29-8/5	1.26
8/5-8/13	0.250
8/13-8/19	0.360
8/19-8/22	<0.228
8/22-8/23	<0.361
8/23-8/26	<0.182
8/26-8/30	<0.292
8/30-9/2	<0.140
9/2-9/9	<0.116
9/9-9/16	<0.104
9/16-9/20	<0.260
9/20-9/21	<0.441
9/21-9/23	1.31
9/23-9/30	0.374
9/30-10/8	0.551
10/8-10/14	<0.185
10/14-10/22	<0.0502
10/22-10/24	<0.306
10/24-10/25	<0.610
10/25-10/29	<0.208
10/29-11/4	<0.0956
11/4-11/13	<0.179
11/2-12/13	Out of service

Table D-5  
 IODINE-131 VENT MONITOR MEASUREMENTS AT BROWNS FERRY 2  
 DURING 1977, MONITOR 2-250 (REACTOR BUILDING AND EQUIPMENT  
 ROOMS IN TURBINE BUILDING, FLOW RATE =  $12.6 \times 10^7$  cc/s),

Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{12}$	Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{12}$
12/31-1/7	0.151	5/20-5/23	3.28
1/7-1/15	0.232	5/23-5/24	0.695
1/15-1/21	0.0902	5/24-5/27	3.73
1/21-1/25	3.30	5/27-6/4	2.55
1/25-1/26	29.9	6/4-6/11	9.87
1/26-1/29	8.17	6/11-6/17	0.573
1/29-2/3	2.35	6/17-6/20	0.419
2/3-2/4	1.47	6/20-6/21	0.405
2/4-2/11	1.72	6/21-6/24	0.293
2/11-2/18	1.10	6/24-7/1	0.337
2/18-2/19	1.03	7/1-7/9	0.854
2/19-2/21	0.279	7/9-7/15	0.673
2/21-2/22	0.699	7/15-7/23	0.537
2/22-2/22	5.75	7/22-7/27	0.218
2/22-2/26	0.481	7/27-7/28	0.40
2/26-3/5	0.185	7/28-7/29	0.285
3/5-3/11	0.0989	7/29-8/5	0.0833
3/11-3/14	0.408	8/5-8/13	0.331
3/14-3/14	1.67	8/13-8/20	0.212
3/14-3/18	0.130	8/20-8/22	0.189
3/18-3/21	0.263	8/22-8/23	0.444
3/21-3/22	0.444	8/23-8/26	0.133
3/22-3/24	0.850	8/26-9/2	0.0891
3/24-3/25	0.757	9/2-9/9	0.0836
3/25-3/25	1.83	9/9-9/16	0.502
3/25-3/25	3.01	9/16-9/19	12.1
3/25-3/26	0.693	9/19-9/21	2.71
3/26-3/28	0.239	9/21-9/23	1.65
3/28-3/28	7.25	9/23-9/30	0.928
3/28-3/31	0.174	9/30-10/8	7.53
3/31-4/1	0.544	10/8-10/14	2.03
4/1-4/1	0.512	10/14-10/22	2.16
4/1-4/8	0.0868	10/22-10/24	0.307
4/8-4/9	0.937	10/24-10/25	1.05
4/9-4/11	0.172	10/25-10/29	0.379
4/11-4/23	0.638	10/29-11/4	0.385
4/12-4/12	4.28	11/4-11/11	0.420
4/12-4/13	0.857	11/11-11/18	0.213
4/13-4/15	0.187	11/18-11/21	0.252
4/15-4/22	0.823	11/21-11/22	0.750
4/22-4/25	0.788	11/22-11/26	0.268
4/25-4/26	0.934	11/26-12/3	0.237
4/26-4/30	1.30	12/3-12/9	0.175
4/30-5/6	0.258	12/9-12/16	0.139
4/5-5/13	0.456	12/16-12/19	0.213
5/13-5/21	0.264	12/19-12/20	0.570
		12/20-12/23	0.220
		12/23-12/31	0.124

Table D-6  
 IODINE-131 VENT MONITOR MEASUREMENTS AT BROWNS FERRY 2  
 DURING 1977, MONITOR 2-249 (FOUR VENTS OVER OPERATING FLOOR  
 OF TURBINE BUILDING, FLOW RATE =  $3.03 \times 10^7$  cc/s).

Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{12}$
1/1 -7/19	Out of Service
7/19-7/20	<1.83
7/25-7/26	0.130
7/26-7/27	<0.621
7/27-7/29	0.217
7/29-8/5	0.676
8/5-8/6	0.139
8/13-8/19	0.143
8/19-8/22	<0.215
8/22-8/23	<0.623
8/23-8/26	<0.229
8/26-9/2	<0.411
9/2-9/9	<0.110
9/9-9/16	<0.155
9/16-9/19	<0.300
9/19-9/20	<0.716
9/20-9/23	1.42
9/23-9/30	0.552
9/30-10/7	0.466
10/7-10/14	<0.556
10/14-10/21	0.277
10/21-10/24	<0.324
10/24-10/25	<0.796
10/25-10/29	<0.260
10/29-11/5	<0.182
11/5-11/10	<0.117
11/10-12/31	Out of Service



**Table D-7**  
**IODINE-131 VENT MONITOR MEASUREMENTS AT BROWNS FERRY 2**  
**DURING 1977, MONITOR 2-251 (FIVE VENTS OVER OPERATING FLOOR**  
**OF TURBINE BUILDING, FLOW RATE =  $3.79 \times 10^7$  cc/s).**

Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{12}$
1/1 -7/19	Out of Service
7/19-7/20	<0.0710
7/25-7/26	<0.0944
7/26-7/27	<0.194
7/27-7/29	<0.0852
7/29-8/5	0.0685
8/5-8/13	<0.363
8/13-8/19	0.0409
8/19-8/22	<0.0943
8/22-8/23	<0.192
8/23-8/26	<0.0882
8/26-9/2	<0.0546
9/2-9/9	<0.0492
9/9-9/16	<0.044
9/16-9/19	<0.114
9/19-9/20	<0.252
9/20-9/23	1.01
9/23-9/30	0.0869
9/30-10/7	0.0543
10/7-10/14	0.0456
10/14 - 10/21	<0.0538
10/21 - 10/24	<0.306
10/24-10/25	<0.194
10/25-10/29	<0.725
10/29-11/5	<0.0741
11/5-11/10	<0.0375
11/10-12/31	Out of Service

Table D-8  
 IODINE-131 VENT MONITOR MEASUREMENTS AT BROWNS FERRY 3  
 DURING 1977, MONITOR 3-250 (REACTOR BUILDING AND EQUIPMENT  
 ROOMS IN TURBINE BUILDING, FLOW RATE =  $12.1 \times 10^7$  cc/s).

Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{12}$	Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{12}$
12/31-1/7	1.23	7/1-7/9	<0.0727
1/7-1/15	0.145	7/9-7/15	<0.0814
1/15-1/21	<0.0651	7/15-7/22	<0.0791
1/21-1/25	0.198	7/22-7/27	<0.103
1/25-1/26	<0.396	7/27-7/28	<0.399
1/26-1/29	1.59	7/28-7/29	<0.255
1/29-2/3	0.376	7/29-8/5	<0.0802
2/4-2/11	<0.932	8/5-8/13	<0.0659
2/11-2/18	0.0977	8/13-8/20	<0.0744
2/18-2/19	<0.193	8/20-8/22	<0.18
2/21-2/21	<0.522	8/22-8/23	<0.386
2/22-2/26	<0.169	8/23-8/26	<0.129
2/26-3/5	0.115	8/26-9/2	<0.0841
3/5-3/11	<0.104	9/2-9/9	<0.0848
3/11-3/18	0.103	9/9-9/16	0.346
3/18-3/21	0.206	9/16-9/19	5.33
3/21-3/22	<0.531	9/19-9/21	0.668
3/22-3/25	<0.144	9/21-9/23	0.653
3/25-4/1	<0.858	9/23-9/30	0.499
4/1-4/8	<0.0884	9/30-10/8	2.34
4/9-4/15	<0.107	10/8-10/14	0.450
4/15-4/22	0.274	10/14-10/22	0.323
4/22-4/25	0.338	10/22-10/24	0.715
4/25-4/26	<0.447	10/24-10/25	<0.381
4/26-4/30	0.239	10/25-10/29	<0.194
4/30-5/6	1.33	10/29-11/4	0.228
5/6-5/13	1.45	11/4-11/11	<0.0905
5/13-5/20	<0.0748	11/11-11/18	0.114
5/20-5/23	<0.179	11/18-11/21	<0.215
5/23-5/24	<0.412	11/21-11/22	<0.586
5/24-5/27	<0.133	11/22-11/26	0.339
5/27-6/4	<0.0746	11/26-12/3	<0.132
6/4-6/11	0.120	12/3-12/9	<0.146
6/11-6/17	<0.0837	12/9-12/16	<0.110
6/17-6/20	<0.145	12/16-12/19	<0.227
6/20-6/21	<0.372	12/19-12/20	<0.485
6/21-6/24	<0.123	12/20-12/23	<0.172
6/24-7/1	0.177	12/23-12/31	<0.120

**Table D-9**  
**IODINE-131 VENT MONITOR MEASUREMENTS AT BROWNS FERRY 3**  
**DURING 1977, MONITOR 3-249 (FOUR VENTS OVER OPERATING FLOOR**  
**OF TURBINE BUILDING, FLOW RATE =  $2.58 \times 10^7$  cc/s).**

Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{17}$
1/1 -4/18	Out of Service
4/18-4/22	<0.335
4/22-4/24	1.01
4/24-4/26	0.646
4/26-4/27	<0.455
4/27-4/30	2.04
4/30-5/6	0.19
5/6-5/13	<0.0938
5/13-5/21	<0.123
5/21-5/23	0.430
5/23-5/24	0.918
4/25-5/27	0.269
5/27-6/4	<0.180
6/4-6/11	0.300
6/11-6/17	0.194
6/17-6/20	<0.242
6/20-6/21	<0.451
6/21-6/24	<0.136
6/24-7/1	<0.0815
7/1-7/9	<0.0776
7/9-7/15	<0.0825
7/15-7/22	<0.0773
7/22-7/27	<0.125
7/27-7/28	<0.397
7/28-7/29	<0.178
7/29-8/5	0.0939
8/5-8/13	<0.0775
8/13-8/20	<0.149
8/20-8/23	<0.970
8/23-8/26	<0.220
8/26-9/2	<0.118
9/2-9/9	<0.367
9/9-9/15	<0.112
9/15-9/16	<0.312
9/16-9/19	<0.237
9/19-9/21	<0.482
9/21-9/23	<0.198
9/23-9/30	0.104
9/30-10/8	0.0704
10/8-10/14	<0.0390
10/4-10/22	<0.0459
10/22-10/24	<0.0898
10/24-10/25	<0.180
10/25-10/29	<0.655
10/29-11/4	<0.0373
11/4-11/11	<0.0805
11/11-12/31	Out of Service

Table D-11  
 IODINE-131 VENT MONITOR MEASUREMENTS AT BROWNS FERRY 1, 2, and 3  
 DURING 1977, MONITOR 0-252 (RADWASTE BUILDING,  
 FLOW RATE =  $1.61 \times 10^7$  cc/s).

Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{12}$	Sample Period Month/Day	I-131 Concentration ( $\mu\text{Ci/cc}$ ) $\times 10^{12}$
12/31-1/7	23.2	7/9-7/10	0.375
1/7-1/15	22.0	7/10-7/15	0.954
1/15-1/21	3.08	7/15-7/22	0.855
1/21-1/25	118.	7/22-7/27	1.41
1/25-1/26	104.	7/27-7/28	0.316
1/26-1/29	272.	7/28-7/29	0.847
1/29-2/4	<0.215	7/29-8/5	10.4
2/4-2/11	15.3	8/5-8/13	3.33
2/11-2/18	<0.156	8/13-8/19	1.55
2/18-2/21	32.6	8/19-8/22	1.33
2/21-2/21	26.2	8/22-8/23	0.928
2/21-2/22	<2.62	8/23-8/26	0.646
2/22-2/26	9.85	8/26-9/2	0.978
2/26-3/5	13.7	9/2-9/9	0.291
3/5-3/11	4.11	9/9-9/16	0.558
3/11-3/18	1.34	9/16-9/20	13.8
3/18-3/21	0.363	9/20-9/21	4.00
3/21-3/22	0.239	9/21-9/23	1.47
3/22-3/25	0.486	9/23-9/30	0.887
3/25-4/2	1.57	9/30-10/8	17.9
4/1-4/9	0.400	10/8-10/14	4.51
4/9-4/9	<0.446	10/14-10/22	2.09
4/9-4/15	0.336	10/22-10/24	<0.150
4/15-4/22	2.47	10/24-10/25	0.657
4/22-4/25	14.2	10/25-10/29	0.395
4/25-4/26	28.3	10/29-11/5	1.63
4/26-4/30	9.53	11/4-11/23	0.617
4/30-5/6	5.69	11/12-11/19	0.347
5/6-5/13	2.42	11/19-11/21	1.18
5/13-5/20	1.08	11/21-11/22	1.09
5/20-5/23	8.89	11/22-11/26	1.53
5/23-5/24	30.1	11/26-12/3	0.300
5/24-5/27	30.0	12/3-12/9	<0.221
5/27-6/4	1.84	12/9-12/16	<0.102
6/4-6/11	8.32	12/16-12/19	<0.260
6/11-6/17	4.83	12/19-12/20	<0.605
6/17-6/20	1.12	12/20-12/24	<0.183
6/20-6/21	1.83	12/24-12/31	<0.102
6/21-6/24	0.640		
6/24-7/1	1.30		
7/1-7/9	0.976		

NUCLEAR ENERGY DIVISIONS • GENERAL ELECTRIC COMPANY  
SAN JOSE, CALIFORNIA 95125

GENERAL  ELECTRIC

TECHNICAL INFORMATION EXCHANGE

TITLE PAGE

AUTHOR	SUBJECT	TIE NUMBER
T. R. Marrero	Reactor Technology	77NED140
		DATE
		October 1978
TITLE	GE CLASS	
Airborne Releases from BWRs for Environmental Impact Evaluations Amendment 2 (Iodine 131)	I	
	GOVERNMENT CLASS	
REPRODUCIBLE COPY FILED AT TECHNICAL SUPPORT SERVICES, R&UD, SAN JOSE, CALIFORNIA 95125 (Mail Code 211)	NUMBER OF PAGES	
SUMMARY		
Airborne iodine-131 releases from BWRs are decreasing based on an evaluation of 31 reactor-years of operating plant data. An independent analysis of extensive I-131 measurements sponsored by the Electric Power Research Institute indicate an annual normalized release of elemental iodine (I <sub>2</sub> ) to be 25 millicuries per reactor. The basis for normalization is a calendar year consisting of 300 days of power operations and one refueling/maintenance shutdown period, a concentration of I-131 in reactor water of 1 μCi/kg, a carryover of I-131 from reactor water to reactor steam of 1%, and full-flow condensate treatment. Adjustment factors would be applied to plants with parameters varying from this normalization basis to determine the annual I-131 airborne release rate for future BWR environmental impact assessments.		

By cutting out this rectangle and folding in half, the above information can be fitted into a standard card file.

DOCUMENT NUMBER NEDO-21159-2

INFORMATION PREPARED FOR Nuclear Energy Engineering Division

SECTION Chemical & Radiological Engineering

BUILDING AND ROOM NUMBER K-2625 MAIL CODE 682