


Approval <i>W F Kitchens</i> <i>W F Kitchens</i>	Vogtle Electric Generating Plant NUCLEAR OPERATIONS	 <b>Georgia Power</b>	Procedure No. 93240-C
Date 3/8/90 3/20/90	Unit <u>COMMON</u>		Revision No. <i>787</i> <i>JFC</i>
			Page No. 1 of 98

*Procedure for* 05-316-90

REACTOR VESSEL ASSEMBLY/DISASSEMBLY INSTRUCTIONS

1.0 PURPOSE

This procedure provides instruction for the assembly and disassembly of the reactor vessel including requirements for vessel preparation for and recovery from a refueling or fueling exercise.

2.0 PRECAUTIONS AND LIMITATIONS

2.1 GENERAL

- 2.1.1 Exercise care when handling equipment above the reactor.
- 2.1.2 Comply with instructions identified on the RWP for this job and be aware of the potential for high radiation levels.
- 2.1.3 Spotters and guide ropes should be used while lifting and moving large components.
- 2.1.4 A radiation survey must be completed prior to any work being conducted in a contaminated or potentially contaminated area for possible issuance of a Radiation Work Permit.
- 2.1.5 Personnel and material accountability shall be in accordance with Procedure 00254-C, "Plant Housekeeping/Material Condition Program". Small items such as pens, badges, binoculars, etc., shall be taped or secured to the person by lanyards and tools shall be tethered. Tools and equipment used in one operation should be cleared from the immediate area before proceeding to the next operation.
- 2.1.6 Steps involving cleaning operations or tool setup/breakdown may be accomplished at any time as long as it is completed prior to time needed.

FOR INFORMATION ONLY

9202210477 920116  
PDR ADDCK 05000424  
S PDR

2.2 INSTRUMENT PORT CONOSEALS

- 2.2.1 During disassembly some parts may have high quantities of loose surface contamination and should be treated as directed by the Health Physics Technician.
- 2.2.2 Handle all parts with particular care to prevent damage which would affect seal integrity.
- 2.2.3 Cleanliness is of the utmost importance in the conoseal joint. Assemble the joint using clean white lint free cloth and/or rubber gloves.
- 2.2.4 Ensure Health Physics monitoring of the immediate area for increases in airborne activity during this operation.

2.3 REACTOR VESSEL STUDS

- 2.3.1 Care should be exercised when taking elongation measurements during the stud tensioning process to eliminate time consuming corrections.
- 2.3.2 Do not detension studs until the vessel water and metal temperature is below 140°F and the pressure is reduced to 0 psig. The metal temperature must be equal to or greater than RT<sub>NDT</sub> as calculated per Procedure 55023-C, "Incore Irradiation Specimens", but less than 140°F when studs are tensioned or detensioned.
- 2.3.3 Do not pressurize the stud tensioners unless the stud tensioner puller bar is completely engaged on the assembled stud.
- 2.3.4 All studs, nuts, and washers should be kept in matched numbered sets and shall be installed in the appropriate stud hole in the pressure vessel.
- 2.3.5 After setting of the reactor vessel head, the water level in the vessel should not be raised closer than 48 inches (ELEV. 190') to the vessel flange prior to tensioning the first six studs.
- 2.3.6 Measuring rods shall not be interchanged or replaced after the original depth readings have been recorded.



- 2.3.7 Maximum Stud Tensioner Hydraulic Pump Pressure shall not exceed 9500 psi unless approved by the cognizant Maintenance Foreman.
- 2.3.8 Constantly exercise care throughout all steps of this procedure to prevent damage to threads and surfaces of all parts and components and to ensure cleanliness at all times.
- 2.4 REACTOR VESSEL HEAD

## CAUTION

Inadvertent containment ventilation isolation may occur during the movement of the Reactor Vessel head from the Reactor cavity to the head stand or from the head stand to the Reactor cavity. Ensure Health Physics and operations initiate compensatory actions to prevent inadvertent actuation.

- 2.4.1 Whenever raising or lowering the head, constantly monitor the load cell for changes which would indicate binding or interference.
- 2.4.2 All personnel should avoid exposure to the underside of the Reactor Vessel Head as much as possible.
- 2.4.3 All tools and equipment used in the cavity during the time the vessel head is removed must have lanyards attached and inventoried in and out of the cavity as per Procedure 00254-C, "Plant Housekeeping/Material Condition Program".
- 2.4.4 The O-rings shall be replaced with the head on the storage pedestal. The O-rings should be replaced before the head is lifted from the pedestal for installation. This will eliminate possible O-ring contamination from dust or foreign materials.
- 2.4.5 All personnel shall wear clean, white, lint-free cotton/rubber gloves for all cleaning and handling of the O-rings.
- 2.4.6 During movement of the reactor vessel head, the safe load path as outlined in Figure 5 shall be followed. Within the defined safe load path the specified load shall not be lifted greater than five feet above the operating deck (220 foot elevation).
- 2.4.7 The reactor vessel head and associated equipment shall be handled with care, to prevent inadvertent contact with other components.

- 2.4.8 Whenever the reactor vessel head is being raised or lowered the first and last foot onto the reactor vessel, the polar crane should be controlled at slow speed to preclude damage to closely mating components. Crane speed during other phases of handling shall be consistent with safe moving practices of critical components.
- 2.4.9 The reactor vessel head shall be maintained no closer than one foot to the refueling cavity water level.
- 2.4.10 A direct method of voice communications shall be provided between the polar crane operator and the person on the refueling floor directing the vessel head lift. A backup method of voice communications during reactor vessel head lifts is highly recommended.
- 2.4.11 Do not twist the knurled incore thermocouple connectors during disassembly or reassembly.
- 2.5 INTERNALS/LIFT RIG
- 2.5.1 Do not submerge the load cell at any time. If it is accidentally submerged; thoroughly dry, check, and re-zero if necessary.
- 2.5.2 During movement of the reactor vessel upper internals, the safe load path as outlined in Figure 6 shall be followed. Within the defined safe load path the specified load shall not be lifted greater than 24.5 feet from its original position.
- 2.5.3 A direct method of voice communications shall be provided between the polar crane operator and the person on the refueling floor directing the internals lift. A backup method of voice communications during internals lifts is highly recommended.

3.0 PREREQUISITES AND INITIAL CONDITIONS

NOTE

Unless otherwise noted Section 3.1 applies to all instructions.

3.1 GENERAL PLANT CONDITIONS FOR PERFORMING VESSEL  
\*/\* ASSEMBLY/DISASSEMBLY

- 3.1.1 Health Physics has issued the appropriate RWPs per Procedure 43007-C, "Issuance, Use, And Control Of Radiation Work Permits".

- 3.1.2 Verify that a Quality Control (QC) representative has signed the "Data Sheet" indicating QC review of procedure for HOLD POINTS. If HOLD POINTS are indicated, QC should be notified 4 hours prior to starting work.
- 3.2  
\*/\* The Polar Crane has been checked out in accordance with Procedure 27305-C, "Reactor Polar Crane Service Check".
- 3.3  
\*/\* All applicable equipment has been checked out in accordance with Procedure 93100-C, "Refueling Tools And Equipment Preservice Inspection/Checkout".
- 3.4  
\*/\* All sling, straps, and shackles to be used are in accordance with Procedure 20425-C, "Control Of Refueling Lifting And Rigging Equipment."
- 3.5 HEAD VENT PIPING
- 3.5.1 The reactor vessel water level is 6 inches (minimum) below the reactor vessel flange.
- 3.5.2 The reactor vessel head has been vented, per Procedure 13005-1 or 13005-2, "Reactor Coolant System Draining".
- 3.5.3 The reactor vessel head venting has been sampled per Procedure 43002-C, "Airborne Radioactivity Sampling And Evaluation".
- 3.6 REACTOR VESSEL STUD TENSIONING/DETENSIONING
- 3.6.1 The On-Shift Operations Supervisor (OSOS) has confirmed that plant conditions are in order for a mode change and has given approval for stud detensioning/tensioning.
- 3.6.2 The reactor vessel, vessel head, studs, nuts, and washers temperature is greater than RT<sub>NDT</sub>, but less than or equal to 140°F.
- 3.6.3 The reactor vessel water level is 48 inches (minimum)/(Elev. 190') below the vessel flange prior to any tensioning and 24 inches (minimum)/(Elev. 192) prior To detensioning operations.
- 3.6.4 Plant air (260 to 400 scfm at 100 psi recommended) for the stud tensioners is available.
- 3.6.5 The source range and audio count in Containment is on and operational.



3.7  
\*/\*

### REACTOR VESSEL O-RING INSTALLATION

New O-Rings have been stored in their container around the reactor vessel head storage stand.

4.0  
\*/\*

### INSTRUCTIONS

4.1

Assemble an access platform from the operating floor (Elevation 220 feet) to the missile shield.

4.2  
\*/\*

### SEISMIC TIE RODS

#### NOTE

With proper care, seismic tie rods may be disconnected and stored without the aid of the polar crane.

4.2.1

Attach a nylon strap to the seismic tie rod at a point close to the cavity wall.

4.2.2

With the appropriate rigging taking the weight off the tie rod, remove the cotter pin from the tie rod connecting pin and the connecting pin from the tie rod clevis-cavity wall lug.

#### NOTE

These rods may have to be pivoted downward and horizontally to clear the cavity walls prior to pivoting upward to engage with the supports on the missile shield.

4.2.3

Pivot the tie rod up into the tie rod support on the missile shield. Lock in place.

4.2.4

Replace the previously removed connecting pin and cotter pin into the uprighted tie rod clevis.

4.2.5  
\*/\*

Repeat Steps 4.2.1 through 4.2.4 for each of the 6 seismic tie rods.

4.3 CABLE DISCONNECTS

NOTE

Subsection 4.3 may be accomplished now or any time prior to Step 4.15. If accomplished now, however, a 480V power cable will have to be connected to the receptacle at the bottom of the shroud to provide power to the radial arm hoists.

- 4.3.1 Ensure identification tags are on the cable connections for ease in reassembly.
- 4.3.2 Disconnect all cables at the outside of the connector plate. Document on Data Sheet 4.
- 4.3.3 Store all cables in the racks on the tray.
- 4.3.4 Unlatch the tray restraints at the shroud.

CAUTION

Carefully monitor the flexing of the cabling so that no excessive binding occurs.

- 4.3.5 Using the reactor head electric cable tray winches, pivot the cable tray upward into the supports on the Steam Generator wall.

NOTE

Should the cable tray winches become disabled, other means to lift the cable trays may be used.

- 4.3.6 Lock the cable tray in the stored position.
- 4.3.7 \*/\* Repeat Steps 4.3.1 through 4.3.6 for the other cable tray.
- 4.3.8 \*/\* Connect 480V power cable for the radial arm hoist if required.

## 4.6 REMOVAL OF REACTOR HEAD INSULATION

## NOTE

Subsection 4.4 may be accomplished now or at any time prior to Subsection 4.10.

- 4.4.1 Loosen and store attaching fasteners.
- 4.4.2 Using proper lifting equipment, carefully hand maneuver the section of insulation clear of the reactor vessel head.
- 4.4.3 Remove the section to a designated lay-down area.
- 4.4.4 Repeat Steps 4.4.1 through 4.4.3 for each of the 9  
\*/\* insulation sections.
- 4.5 Before proceeding with any further work in this  
\*/\* procedure the Vessel (Reactor Coolant System) water level must be brought to a minimum of 24" (Elev. 192') inches below the reactor vessel (RV) flange and the RV head must have been vented and sampled to assure safe working conditions.

## 4.6 HEAD VENT PIPING

Prerequisites 3.1 and 3.5 apply to this section.

## NOTE

Subsection 4.6 may be accomplished at any time after venting and sampling occur but must be completed prior to Subsection 4.10.

- 4.6.1 Using proper rigging equipment, attach nylon straps to the head vent removable spool piece located between the RV Head and the cavity floor.
- 4.6.2 Disconnect flanges and cover the pipe ends to keep interiors clean.
- 4.6.3 Move the spool piece to a designated lay-down area.  
\*/\*



## NOTE

The following work must be completed prior to Step 4.16.6.

- 4.6.4 Clean and coat each of the flange 1/2 inch nut and bolt threads and bolt head undersides with Never-Seez Pure Nickel Special.
- 4.6.5 Install the blind flange over the vent flange through the cavity floor at approximately the 328° azimuth for Unit 1 or the 211° azimuth for Unit 2. Use the old spiral wound gasket if possible.
- 4.6.6 Torque the 1/2 inch bolts in a three-step method cross pattern to 300 foot pounds.  
\*/\*
- 4.7 REACTOR VESSEL LEVEL INSTRUMENTATION SYSTEM (RVLIS)

## NOTE

Subsection 4.7 may be accomplished any time after venting and sampling occur but must be completed prior to Step 4.10.15.

- 4.7.1 Disconnect Swagelok fittings which attach the tube sections from the RV Head to the sensors. Cover all four ends of the tubing to keep their interiors clean.
- 4.7.2 Remove tubing to a designated lay-down area.  
\*/\*
- 4.8 SEAL TABLE PREPARATION

## NOTE

Subsection 4.8 may be accomplished any time after Step 4.5 has occurred but must be completed prior to Step 4.16.6.

- 4.8.1 The seal table system will be prepared for refueling in accordance with Procedure 93280-C, "Flux Thimble Withdrawal And Reinsertion For Refueling".  
\*/\*

4.9  
\*/\*

## INSTRUMENT PORT-CONOSEAL DISASSEMBLY

## NOTE

Subsection 4.9 may be accomplished any time after venting and sampling occur, but must be completed prior to Subsection 4.10.

- 4.9.1 Lower the thermocouple protective sleeves and all other necessary tools and equipment to the reactor flange elevation using proper rigging equipment.
- 4.9.2 Unlatch and open the appropriate doors on the surround (approximate azimuth 23°, 67°, 147°, 247°).

## CAUTION

Do NOT twist the knurled thermocouple connectors during assembly.

- 4.9.3 Disconnect the thermocouple wiring making sure it is labeled for ease in later reconnections. Document on Data Sheet 4.

## NOTE

Refer to Figures 3 and 4 for item numbers.

- 4.9.4 Remove lock wire (Item 13).
- 4.9.5 Loosen all six jack screws and remove at least two of the jack screws. (Item 5).
- 4.9.6 Remove the split ring (Item 4) and the jack screw plate (Item 3). Remove the remaining jack screws from the jack screw plate.
- 4.9.7 Remove the coupling assembly (Item 8) by completely removing one bolt and loosening the rest. Reinstall the bolt in the coupling assembly after removing the assembly from the flange.
- 4.9.8 Carefully remove male flange (Item 1).
- 4.9.9 Remove and discard upper conoseal gasket (Item 8).

PROCEDURE NO. VEGP	93240-C	REVISION <i>7 ST JPC 1/10</i>	PAGE NO. 11 of 98
-----------------------	---------	----------------------------------	----------------------

4.9.10 Remove and discard lower conoseal gasket (Item 7) using the removal tool (Item 16) if required.

4.9.11 Place approved tape over top and bottom of the male flange to keep interior clear and protect sealing surface.

NOTE

Conoseals must be labeled for their original location or azimuth.

4.9.12 Package, protect, label and store, in a designated lay-down area, all components removed in Steps 4.9.4 through 4.9.8.

4.9.13 Install O-ring at the top of thermocouple column assembly.

NOTE

Neolube # 1 or # 2 or GE Versilube 392 may be used on the O-rings to enhance sealing capabilities.

4.9.14 Install the thermocouple protective sleeve.

CAUTION

In Step 4.9.13 it is possible to install the spring incorrectly, 180° from its proper position. When properly installed no part of the spring will protrude outside the diameter of the protective sleeve.

4.9.15 Install the protective sleeve holding spring.

4.9.16 Repeat Steps 4.9.1 through 4.9.15 for each of the \*/\* four instrument ports.

4.9.17 Clean job area and remove all tools and equipment.



4.10  
\*/\*

## STUD TENSIONING

Prerequisites 3.1, 3.2, 3.3, 3.4 and 3.6 apply to this section.

### NOTE

When setting and hooking up the stud tensioners, pay particular attention that tensioner Number 1 is hooked to the hydraulic pump for use in the #46 to #54 stud area. The remaining five tensioners are interchangeable in position. (See Figure 1.)

Sections 4.6 and 4.7 should be completed prior to proceeding with this section.

- 4.10.1 Lower the stud tensioners into the reactor cavity using the polar crane auxiliary hoist and transfer each to its associated radial arm hoist assembly.
- 4.10.2 Station each tensioner near its first setup position, i.e., tensioner #1 to stud #46, #2 to stud #37, #3 to stud #28, #4 to stud #19, #5 to stud #10, and #6 to stud #1.
- 4.10.3 Lower the hydraulic pump assembly into the reactor cavity using the polar crane auxiliary hoist, and station it in the southwest (northeast for Unit 2) corner of the 194 elevation area.
- 4.10.4 Lower the tensioner hose sets into the cavity and hook up as follows:

### NOTE

Figures 1 and 2 may be used as an aid in hose hookup.

- 4.10.4.1 Connect the two, 12-foot long, 3/8-inch diameter, high pressure hydraulic hoses between the tensioners to couplings on either side of the cylinder. To connect the coupling, remove the dust cap which protects the body half and push the male tip into the body. Then screw on the collar until it bottoms. The collar is a free fit and should almost spin on, however, it must be bottomed for the hydraulic fluid to flow freely.

- 4.10.4.2 Connect the 12-foot long, 1/4-inch diameter, low pressure hydraulic hose (bypass valve signal) between the tensioners to the union adapters located just above the high pressure couplings.
- 4.10.4.3 Connect the black, 12-foot long, 1/4-inch diameter, air hose (piston return) between the tensioners to the couplings located on the front portion of the top plate.
- 4.10.4.4 Connect the red, 12-foot long, 1/4-inch diameter, air hose (air signal) between the tensioners to the couplings located on the top left and right hand side of the top plate.
- 4.10.4.5 Connect the single 12-foot long, 1/4-inch diameter, air hose (air signal) between tensioner #6 and tensioner #1.
- 4.10.4.6 Repeat Steps 4.10.4.1 through 4.10.4.4 for each of the five 12-foot long hose sets.
- 4.10.4.7 Connect each of the hoses in the 35-foot long set between tensioner #1 and the pumping assembly in the same manner as the interconnecting hoses in Steps 4.10.4.1 through 4.10.4.4.
- 4.10.5 Connect the plant air supply to the pumping assembly through the two 1-inch female pipe connections located on the upper left hand side of the pump. One or both connections may be used to provide an adequate supply however, if only one connector is used, the other must be plugged.

**WARNING**

DO NOT CLOSE THE PUMP RELEASE VALVE OR PUSH THE AIR VALVE UNLESS ALL TENSIONER HOSES ARE CONNECTED AND THE TENSIONERS ARE FULLY SEATED ON THE VESSEL FLANGE WITH THE WEIGHT OFF THE HOIST ENOUGH TO LOCK THE PULL SYSTEM TO THE STUD THERE-BY ACTIVATING THE LIMIT SWITCH.

## NOTES

- a. When lowering a tensioner onto a stud, it is best to use the buddy system, i.e., one man operating the hoist while the other man guides the tensioner over the stud by use of the two handles provided on the front of the tensioner.
  - b. Table 2 may be cut apart and taped securely to its respective tensioner to be used as a sequence guide in the detensioning operation.
- 4.10.6 Using the individual radial arm hoist assemblies, lower each tensioner over its first stud as seen on the sequence guide (Table 2).
- 4.10.7 Ensure that each tensioner is seated flush on the head flange and the tensioner pull system is locked to the stud.

## NOTE

If adjustments to the tensioners are needed to cause the tensioner to latch, these adjustments may be made without generating a Maintenance Work Order.

## NOTE

Detensioning is done in two passes with an intermediate pressure of 4700 psi for the first pass and 0 psi for the second pass. A pass consists of nine set-ups or nine sets of six studs each.

- 4.10.8 Notify the OSOS for approval to begin detensioning in accordance with Procedure 12007-C, "Refueling Entry".
- 4.10.9 Close the release valve on the pumping assembly, then depress and hold the air valve.



## CAUTION

Maximum hydraulic pump pressure shall not exceed 9500 psi.

- 4.10.10 Continue pumping operation until all six spherical nuts can be moved. This can be accomplished by inserting the torque handle into one of the holes in the upper portion of the spherical nut and holding a slight pressure in the counter clockwise direction while pumping is in progress.
- 4.10.11 When all six nuts are loose, release the air valve, then back off at least one full turn (18 holes) on each nut.
- 4.10.12 Slowly open the release valve and allow the hydraulic pressure to be reduced to the intermediate pressure. Close the release valve.

## NOTE

The torque handle is preset to deliver the required torque. It must be used in a vertical position with the marked pivot pin.

- 4.10.13 When the intermediate pressure has been obtained, insert the torque handle into each nut and turn clockwise until the nut bottoms, then apply force to the handle until an audible click is heard. This will seat the nut at the lower elongation value.
- 4.10.14 After all six nuts have been resealed, open the release valve and allow the hydraulic pressure to drop to zero.
- 4.10.15 Carefully raise the tensioners clear of the studs using the individual radial arm hoists attached.

## NOTE

Section 4.7 must be completed before proceeding.

- 4.10.16 When all six tensioners are clear of their respective studs, move them to their next set-up.

4.10.17 Repeat Steps 4.10.7 through 4.10.16 for each of the nine set-ups of this pass.

4.10.18 If detensioning from a normal operating condition (two pass process), the intermediate pressure will be 4700 psi for the first pass. On the second pass, after the nuts have been backed off one full turn, do not reseal, but reduce pressure to zero leaving the nuts free for removal.  
\*/\*

NOTE

It is sometimes necessary to go back and release a stuck or locked nut on a stud after the detensioning process is complete. Remember that all tensioners must be locked to a stud before raising the hydraulic pressure. This can be accomplished by locking on to an already detensioned stud or by hooking up the hoses to only as many tensioners as are required.

4.10.19 When all 54 spherical nuts are free to turn, the detensioning process is complete. Unhook and remove all tensioning equipment from the reactor cavity prior to starting the next operation.

4.11 STUD REMOVAL

NOTE

Any number (1-6) of tools can be used, (space and personnel dependent) or hand removal is allowed.

CAUTION

No stud should be threaded into or out of the vessel without the use of a weight compensating device, crane scale, etc., capable of a preload of at least 1/2 of the stud weight, to protect the stud and vessel threads.

NOTE

A chalk match mark on the vessel flange and stud may be used to detect stud rotation.

- 4.11.1 Move the stud turnout tools into the reactor cavity and hook them to their individual radial arm hoist.
- 4.11.2 Hook up a regulated air supply to the air compensator and adjust to approximately 55 psi.
- 4.11.3 Have available 51 stud hole plugs with handling fixture, 3 RV guide studs with sleeves, and the sleeve handling fixture.

NOTE

When ISI Vessel Inspection is required, 50 STUD Hole plugs and 4 RV guide studs with sleeves are needed.

- 4.11.4 If the studs are to be removed from the cavity separately from the head, then 6 stud storage racks should be available.
- 4.11.5 If the studs are to be removed from the cavity with the head, then one storage rack and 51 stud collars should be available.
- 4.11.6 Lower the individual spin out tools over their respective studs.
- 4.11.7 Remove the top stud plug and thread the lubricated (N5000) eyebolt into the top of the stud until the lower nut bottoms.
- 4.11.8 Align the eyebolt locking cap with the stud and lower the cap over the top of the stud.
- 4.11.9 Using the radial arm hoist, raise the weight compensator until its cylinder arm is extended approximately 9 inches.

## CAUTION

Do not allow the cylinder arm to extend more than 10 inches. To maintain proper preload on the stud during removal, maintain cylinder arm between 8 to 10 inches by use of the radial arm hoist during stud removal.

- 4.11.10 Place the motor control switch on the tool to the REVERSE direction and, using the Variac to control the speed, unthread the stud.
- 4.11.11 When the scu is fully unthreaded from the vessel it should slowly rise automatically. If it does not, adjust the air compensator regulator to increase pressure. If it moves upward too quickly reduce pressure.
- 4.11.12 If studs are to be removed separately from the head, then move each stud, nut and washer away from the flange and place them into a storage rack (6 stud storage racks should be available).
- 4.11.13 If studs are to be lifted with the head, then temporarily move the stud, nut, and washer away from the flange hole (one stud storage rack and 51 stud collars should be available).
- 4.11.14 After the stud hole has been cleared, attach a stud hole plug onto the stud hole plug fixture using the installation adapter and insert the plug into the vessel flange through the head for all stud holes except 12, 28, 44.

## NOTES

- a. When ISI for Vessel Inspection is being performed, hole 30 will be utilized for mini guide stud.
- b. Neolube #1 or #2 or GE Versilube 392 may be used on the stud hole plug O-rings to enhance sealing capabilities.



- 4.11.15 Remove the installation adapter.
- 4.11.16 When holding the stud hole plug fixture upper "T" handle, turn the lower "T" handle to the right, thereby compressing the two plates together and the O-ring out. This will lock the plug against the hole. When tight, lift the fixture by the lower "T" handle off of the now installed plug.
- 4.11.17 If studs are to be lifted with head, move the stud, nut, and washer back over the flange (except 12, 28, 44 and when ISI Vessel Inspection is being performed, Hole 3). Install into the head flange hole with a stud collar placed between the flange and the stud nut and washer. This will keep the stud bottom threads up inside the head for protection.
- 4.11.18 The stud spinout tool can now be disconnected from the stud by lifting the eyebolt locking cap above the top of the stud and unthreading the eyebolt.
- 4.11.19 Continue this process until all studs have been unthreaded from the vessel, all stud hole plugs (except 12, 28, 44 and when ISI Vessel Inspection is required 30) have been installed, and all studs, nuts, and washers have been stored in their respective places.  
\*/\*
- 4.11.20 Stud holes 12, 28, 44 and when ISI Vessel Inspection is performed Hole 30, are used for the RV guide studs so the studs, nuts, and washers removed from the holes must now be stored in a stud rack.
- 4.11.21 To install the three guide studs, ensure that the guide stud sleeves have been cleaned and lightly lubricated with Fel Pro N5000 or approved lubricant.
- 4.11.22 Using the guide stud sleeve tool insert the sleeve through the head and carefully thread the sleeve into the vessel. When seated, back off 1/2 turn.

**CAUTION**

Use a chain fall between the polar crane and guide stud when threading the guide studs to prevent sleeve or guide stud thread damage.

4.11.23 \*/\* After the sleeve is installed, the guide stud may be threaded into the sleeve using the polar crane auxiliary hook. Carefully lower the guide stud through the opening provided in the upper portion of the Integrated Head package for each of the three guide studs.

4.11.24 Remove stud racks (as applicable) and all tools used in Subsection 4.11 from the reactor cavity.

#### 4.12 REACTOR VESSEL STUD CLEANING AND LUBRICATION

##### NOTE

This section may be performed on a needed basis anytime after 4.11 but before Section 4.24.

The studs may either be cleaned by hand using a nylon brush or the Baron and Associates Stud Cleaning Machine may be used. For the manual method, use Section 4.12.1, and for the machine method, use Section 4.12.2.

##### 4.12.1 Manual Method

4.12.1.1 Remove a stud, nut and washer from the storage rack and/or head and move to the cleaning area.

4.12.1.2 Remove the bottom closing screw from the bottom of the stud and the stud lifting eyebolt from the top of the stud.

##### NOTE

Handle with extreme care to prevent thread damage.

4.12.1.3 Use a nylon brush to remove all significant rust or foreign matter from the stud, nut, washer, closing screw, and eyebolt. Stainless steel wire brushes may be used at the discretion of the cognizant Maintenance Foreman.

4.12.1.4 Using a nylon brush or lint-free rags and ethyl alcohol or acetone, thoroughly bathe and clean the threads on the stud, nut, and washer.

- 4.12.1.5 Check for cleanliness. Repeat Steps 4.12.2 and 4.12.3 as necessary in order to ensure cleanliness.
- 4.12.1.6 Lubricate the stud and nut threads very lightly with Fel-Pro N5000. Apply by brushing and then wiping off visible excess.

NOTE

A properly lubricated thread should be slippery but no lube should be visible to the naked eye. Over lubrication will cause binding.

- 4.12.1.7 Install the bottom closing screw in the bottom of the stud and the stud lifting eye bolt in the top of each stud (54 total). Lubricate threads with N5000.
- 4.12.1.8 Return the clean, lubricated stud and nut to the storage rack and/or head. Thread the nut then place the washer on the stud.
- 4.12.1.9 Cover the stud assemblies as required to maintain cleanliness.
- 4.12.2 Machine Method
  - 4.12.2.1 Verify that the machine is connected to a HEPA vacuum cleaner of at least 100 cfm capacity to avoid the spread of airborne contamination from the machine and to prevent accumulation of brushing debris in the machine.
  - 4.12.2.2 Thread the ball bearing swivel hook into the stud to be cleaned and position the stud over the machine.

CAUTION

The machine rotates the reactor vessel stud under power. Use caution to avoid entangling loose clothing in the rotating stud.

This machine contains high speed wire brushes. Do not operate the machine without the top cover in place. Do not reach into, or work on the interior of the machine without disconnecting the power lead.

- 4.12.2.3 Using the ROTATE motor starter, start the power rollers. Verify that the red indicator lamp is lit.
- 4.12.2.4 Adjust the gear motor adjusting lever to grip and rotate the suspended stud and lock the lever with the lock knob.
- 4.12.2.5 Using the BRUSH motor starter, start the power brush. Verify that the red indicator lamp is lit.

#### NOTE

Use the minimum brush pressure necessary to clean the stud.

- 4.12.2.6 Adjust the brush motor adjusting lever to bring the power brush against the stud surface and lock the lever with the lock knob.
- 4.12.2.7 Using the slow speed of the crane (approximately 2.5 fpm), slowly lower the stud into the machine until all the threads have been cleaned. Then slowly raise the stud out of the machine. The brush motor position may have to be adjusted to clean all of the stud.
- 4.12.2.8 Stop the brush motor and the roller motor.
- 4.12.2.9 Clean the inside of the stud using the guidelines in Steps 4.12.1.3 and 4.12.1.4.
- 4.12.2.10 Return the stud to the appropriate storage location.
- 4.12.2.11 Complete Steps 4.12.2.2 through 4.12.2.10 for each stud to be cleaned.

#### 4.13 REACTOR CAVITY SEALING

#### NOTES

- a. This subsection may be completed in any order any time prior to Subsection 4.15.



- b. After each opening is mechanically sealed, 732 RTV or equivalent may be applied as a backup seal.

4.13.1 Emergency Containment Spray Drain Lines

4.13.1.1 Remove the strainers from the two Emergency Containment Spray Drain lines located in the refueling cavity upender pit. Store the strainers for future operational use.

4.13.1.2 Clean and coat the threads and head underside of the 7/8 inch bolts with Never-Seez Pure Nickel Special.

4.13.1.3 Install two 3/16 inch thick full face EPDM gaskets, and blind flanges over the drains.

4.13.1.4 \*\* Torque the 7/8 inch bolts in a multi-step method cross pattern until gasket compression is achieved. Maximum allowable torque will be 400 ft-lbs.

4.13.2 Reactor Cavity Ventilation Openings

4.13.2.1 Install the 8 manufactured plates (solid plate down) with new 3/16 inch thick full face EPDM gaskets on the reactor cavity ventilation openings located circumferentially around the vessel.

4.13.2.2 Clean and coat the 1/2 inch bolt (16 each per plate) thread and head underside with Never-Seez Pure Nickel Special.

4.13.2.3 \*\* Torque the 1/2 inch bolts in a two-step method cross pattern with 50 to 60 percent of the final torque applied on the first step. Final torque will be 60 ft-lbs minimum.

4.13.3 ISI Ports

4.13.3.1 Unbolt the 8 ISI ports located circumferentially around the reactor vessel and remove the old gaskets.

4.13.3.2 Replace the old gasket material with new 3/16 inch thick EPDM gasket material. A full face gasket between the cover and the junction box, and a 2 3/8 inch wide gasket between the junction box and the cavity floor is required for each port.

4.13.3.3 Clean the 3/4 inch studs and nuts, then coat the threads and nut undersides with Never-Seez Pure Nickel Special.

4.13.3.4 \*/\* Reinstall and torque the 3/4 inch-nuts in a two-step method cross pattern with 50 to 60 percent of the final torque applied on the first step. Final torque will be 120 ft-lbs minimum.

4.13.4 Permanent Cavity Seal Ring

4.13.4.1 \*/\* Visually check the permanent cavity seal for nicks, cuts or other damage which could affect cavity sealing ability.

4.13.5 \*/\* Remove all tools and equipment from the refueling cavity.

4.14 TRANSFER TUBE BLIND FLANGE

NOTE

The transfer tube blind flange may be removed at any time prior to Subsection 4.15.

4.14.1 \*/\* Perform an "as found" Seal Integrity Check in accordance with Procedure 24960-1 for Unit 1 or 24960-2 for Unit 2, "Containment Penetration No. 89 - Local Leak Rate Test", prior to removing the blind flange.

CAUTION

Care must be exercised in removing the blind flange as water may have leaked into the tube from the spent fuel pit.

4.14.2 Remove and store the 20 blind flange bolts in a designated storage area.

4.14.3 Using the cavity arm, swing the blind flange up and away from the transfer tube tracks.

4.14.4 Remove and discard the two quad ring seals on the blind flange.

4.14.5 \*/\* Install the two 1/16-inch brass plugs on the face of the bolted flange.

4.15 PREPARATION FOR FLOODING

## CAUTION

Ensure that all previous steps have been completed and appropriate sign offs made.

- 4.15.1 Disconnect the temporary 480V power cable (if used) from the Integrated Head Package.
- 4.15.2 Close and latch all shroud doors except 4 adjacent to the conoseals, on the Integrated Head.
- 4.15.3 Remove all tools, equipment and material from the cavity to ensure that it is ready for flooding.

\*/\*

4.16

\*/\*

## HEAD REMOVAL AND CAVITY FLOODING

## CAUTION

Inadvertent containment ventilation isolation may occur during the movement of the Reactor Vessel head from the Reactor cavity to the head stand or from the head stand to the Reactor cavity. Ensure Health Physics and operations initiate compensatory actions to prevent inadvertent actuation.

## NOTE

Prior to lifting the head ensure that a new set of head O-rings are in position around the head storage pad.





- 4.16.1 Attach the load cell to the polar crane main hook. The connecting pin should be a snug fit, however, no excessive force or metal to metal pounding is allowed.
- 4.16.2 Connect the load cell leads from the cell to the readout and place the readout at a convenient location for monitoring throughout the lift.

## NOTE

Do not use feet or excessive force to crank the load cell connecting pin in or out.

# 1





## IMAGE EVALUATION TEST TARGET (MT-3)










# 1

## IMAGE EVALUATION TEST TARGET (MT-3)



# 1

## IMAGE EVALUATION TEST TARGET (MT-3)



- 4.16.3 Align the polar crane and load cell to the head lift rig and attach by hand cranking the connecting pin in. This pin is turned in by cranking left (counterclockwise).
- 4.16.4 Ensure that the head lift rig leg turnbuckles are disconnected after polar crane is attached to the lift rig.

## CAUTION

No movement of the head shall be attempted without continuous voice communication between the crane operator and signal man. Hand signals are not allowed. If voice communications are lost, suspend movement of the head until the situation can be corrected.

- 4.16.5 Securely attach at least three levels to the top of the vessel head flange, approximately 120° apart.

## CAUTION

Sections 4.2 through 4.11 must be completed before proceeding.

## WARNING

DURING STEPS 4.15.6 AND 4.16.13  
ONGOING RADIATION MEASUREMENTS  
MUST BE TAKEN TO ENSURE SAFE  
WORKING CONDITIONS.

- 4.16.6 Lift the head approximately 1 inch and check for levelness. If head is not level, slowly set it back on the vessel and adjust. Small adjustments should be made by movement of the radial arm hoists around the head circumference prior to any major adjustments involving the lift rig.
- 4.16.7 \*/\* When the head is level, hold at the 1-inch position for ten minutes while visually checking the accessible welded and bolted lift rig and load cell connections.
- 4.16.8 Remove the levels from the vessel head.

- 4.16.9 Open applicable shroud doors and lift the head approximately 24 inches. Check with a flashlight to ensure that the instrument port column moves freely through the head and the head does not raise any RCCA drive shafts during the lift.
- 4.16.10 When it is apparent that the head is not binding on the thermocouple protective sleeves or RCCA drive shafts, evacuate all personnel from the reactor cavity and note the weight reading on the load cell monitor.

## NOTE

The head may be lifted from a dry cavity or Operations may start flooding as desired.

## CAUTION

Do not allow water to come in contact with the exterior surface of the head.

- 4.16.11 Continue lifting the head and if flooding the cavity maintain at least of 12 inches between head and water level. Constantly monitor the load cell readout for any sudden  $\pm 5\%$  change in the previously noted load cell readout which would indicate binding or interference.
- 4.16.12 Lift the head out of the cavity and place it on the head storage pad.
- 4.16.13 Request Operations to start or continue filling the cavity to the normal refueling level (elevation 218 feet 6 inches).
- 4.16.14 \*/\* When the head is sitting on the head storage pads in a no load condition, reconnect the lift rig leg turnbuckles.

## NOTE

Do not use feet or excessive force to crank the load cell connecting pin out.

- 4.16.15 Disconnect the load cell from the head lift rig by using the load cell and readout for determining the null load point for removing the connecting pin. Turn the crank by hand to the right (clockwise) to remove.



- 4.16.16 Attach the underwater light fixtures to their respective holders on the walls of the cavity liner.

CAUTION

Do not energize underwater lights until they are submerged in water for cooling purposes.

- 4.17  
\*/\* UNLATCHING OF RCCA DRIVE SHAFTS

NOTE

At any time the reactor cavity is flooded, water purity and clarity should be controlled by the Spent Fuel Cooling and Cleaning System and/or the Reactor Cavity Filtration System.

The unlatching of the RCCA drive shafts shall be accomplished in accordance with Procedure 93140-C, "Control Rod Drive Shaft Unlatching Tool Operating Instructions".

- 4.18  
\*/\* UPPER INTERNALS REMOVAL

- 4.18.1  
\*/\* At the discretion of the Outage Area Supervisor, and using a weighted tape measure, measure the distance from the top of the hand rail on the SIGMA refueling machine to the top of the internals flange. Measurements should be taken in at least 3 places and recorded on Data Sheet 2.

NOTES

- a. Prior to removing the upper internals, the SIGMA Refueling machine must be moved to its eastern for Unit 1 or western for Unit 2 most position in order to have access to both the vessel and the upper internals storage stand.
- b. Do not use feet or excessive force to crank the load cell connecting pin in.

- 4.18.2 Align the polar crane main hook and load cell to the lift rig. Insert the connecting pin by hand cranking to the left (counterclockwise).
- 4.18.3 While monitoring the load cell readout, slowly raise the lift rig until it is at the elevation to clear the guide studs on the reactor vessel. Note the weight reading on the load cell monitor.
- 4.18.4 Move the lift rig over the reactor vessel and align it with respect to the vessel guide studs.
- 4.18.5 While monitoring the load cell readout for any sudden  $\pm 5$  percent change in the previously noted load readout which would indicate binding or interferences, slowly lower the lift rig down until it is seated on the upper internals.
- 4.18.6 To engage the roto-locks into the internals; depress the foot pedal, rotate the "T" handle 60° clockwise from the lock position. Push the handle down to the bottom of the slot in the assembly housing and rotate it back 60° counterclockwise to the lock position. Release the "T" handle, then release the foot pedal.
- 4.18.7 Repeat Step 4.18.6 for the other two roto-lock operator assemblies.

#### NOTES

- a. No movement of the upper internals shall be attempted without continuous voice communication between the crane operator and the signal man. Hand signals are not allowed. If voice communications are lost, suspend all internals movement until the situation can be corrected.
- b. Refueling cavity water level must be raised to at least 218'6" elevation in accordance with Procedure 12007-C before lifting upper internals.

## CAUTION

Visually monitor control rod drive shafts as upper internals are lifted. The drive shaft should drop slightly, indicating the shaft is no longer resting on the control rod spider.

- 4.18.8 While monitoring the load cell readout, slowly take a strain on the polar crane so that the entire weight of the upper internals and lift rig is on the crane.
- 4.18.9 \*/\* Hold this condition for 10 minutes while visually checking all accessible lift rig bolted and welded connections. Note the weight reading on the load cell monitor.

## CAUTION

As the upper internals clear the vessel flange, visually monitor beneath the internals for any unusual shadows indicating a lifted fuel bundle or RCCA.

- 4.18.10 Slowly lift the upper internals up out of the reactor until they clear the vessel and the guide bushing is clear of the guide studs. At all times monitor the load cell readout for any sudden  $\pm 5$  percent change in the previously noted load readout which would indicate binding or interference.
- 4.18.11 Move the lift rig and internals over the upper internals storage stand and align them with respect to the storage stand guide studs.
- 4.18.12 \*/\* While monitoring the load cell readout, slowly lower the upper internals and lift rig until they are seated on the storage stand.

## NOTE

Do not use feet or excessive force to crank the connecting pin out.

- 4.18.13 Disconnect the polar crane and load cell from the internals lift rig. Use the load cell readout to determine null load point to remove the connecting pin. Turn the crank by hand to the right (clockwise) to remove.

4.18.14 Move the polar crane and load cell clear for refueling operations. If the main hook is to be used for other lifts then the load cell should be disconnected. When removing the load cell lift pin, use the polar crane weight indicator to determine null load point. No excessive force or metal to metal pounding is allowed.

4.19 \*/\* UPPER INTERNALS INSTALLATION

NOTES

- a. Prior to installing the upper internals, the SIGMA refueling machine must be moved to its eastern for Unit 1 or western for Unit 2 most position in order to have access to both the vessel and internals storage stands.
- b. Do not use feet or excessive force to crank the connecting pin in.

4.19.1 Align the polar crane main hook with the load cell attached to the internals lift rig. Insert the connecting pin by hand cranking to the left (counterclockwise).

CAUTION

No movement of the upper internals shall be attempted without continuous voice communication between the crane operator and the signal man. Hand signals are not allowed. If voice communications are lost, suspend all internals movement until the situation can be corrected.

4.19.2 While monitoring the load readout, slowly take a strain on the polar crane so that the entire weight of the internals and lift rig is on the crane.

4.19.3 \*/\* Hold this condition for 10 minutes while visually checking all accessible lift rig bolted and welded connections. Note the weight reading on the load cell monitor.

- 4.19.4 Slowly lift the upper internals to an elevation that will clear the guide studs on the vessel. At all times monitor the load cell for any sudden  $\pm 5$  percent change in the previously noted load readout which would indicate binding or interference.
- 4.19.5 Move the internals over the vessel and align them with respect to the vessel guide studs.
- 4.19.6 While monitoring the load cell readout for any sudden  $\pm 5$  percent change in the previously noted load readout which would indicate binding or interference, slowly lower the internals down over the guide studs until they are seated in the vessel.

NOTE

At the discretion of the Outer Area Supervisor, Step 4.19.1 may be performed at this time. This may require performance of Step 4.19.11. When the measurements are complete, the polar crane will be reconnected to the lift rig in accordance with Steps 4.19.1 and 4.19.2.

- 4.19.7 To disengage the roto-locks from the internals, depress the foot pedal, hold down on the "T" handle, and rotate it 60° clockwise from the lock position. Slowly release the pressure on the "T" handle and allow it to move to the top of the slot in the assembly housing, then rotate it back 60° counterclockwise to the lock position. Release the "T" handle, then release the foot pedal.
- 4.19.8 Repeat Step 4.19.7 for the other two roto-lock operating assemblies.
- 4.19.9 While monitoring the load cell readout, slowly raise the lift rig and protective ring out of the vessel and clear of the vessel guide studs.
- 4.19.10 Orient the lift rig with respect to the storage stand guide studs and lower it until it is seated on the storage stand.

NOTE

Do not use feet or excessive force to crank the connecting pin out.



- 4.19.11 Disconnect the polar crane and load cell from the lift rig. Use the load cell readout to determine null load point to remove the connecting pin. Turn the crank by hand to the right (clockwise) to remove the pin.
- 4.19.12 \*/\* At the discretion of the Outage Area Supervisor, and using a weighted tape measure, measure the distance from the top of the hand rail on the SIGMA refueling machine to the top of the internals flange. Try to use the same locations as were used in Step 4.18.1, if applicable. Measurements should be taken in at least 3 places and recorded on Data Sheet 3.
- 4.19.13 \*/\* If measurements were taken in Step 4.19.14, the Outage Area Supervisor shall evaluate the measurements and signify his concurrence with the proper installation of the internals on Data Sheet 3.
- 4.20 \*/\* **RCCA DRIVE SHAFT LATCHING**
- The RCCA drive shafts will be latched in accordance with Procedure 93140-C, "Control Rod Drive Shaft Unlatching Tool Operating Instructions".
- 4.21 \*/\* **HEAD AND O-RING INSTALLATION**
- 4.21.1 Coordinate with Operations to begin cavity dewatering.

**WARNING**

AS THE WATER LEVEL GOES DOWN,  
ENSURE THAT THE UNDERWATER  
LIGHTS ARE DE-ENERGIZED BEFORE  
THE WATER LEVEL IS BELOW THE  
LIGHTS.

- 4.21.2 **Cleaning The Vessel Flange**

**NOTE**

Proper cleaning of the vessel and O-ring mating surfaces is a very important factor in making a leak free seal. All cleaning and rubbing upon the sealing surfaces shall be circumferential, not radial, with respect to the vessel centerline to prevent radial scratches.

- 4.21.2.1 When the water level reaches a minimum of 24 inches (Elev. 192') below the vessel flange, cleaning of the vessel O-ring mating surface can start.
- 4.21.2.2 The flange may be cleaned manually by polishing with Scotch brite #7447 and wiping using lint-free rags and either isopropyl alcohol or acetone, followed by demineralized water.
- 4.21.2.3 The flange may also be cleaned using the Reactor Vessel Flange O-Ring Seat Cleaning Machine.
  - 4.21.2.3.1 For cleaning purposes, verify that the machine has the light cleaning and buffing disks (3M grade A-VFN) installed.
  - 4.21.2.3.2 Connect a portable HEPA vacuum cleaner to the 1-1/2 inch tube on the front of the machine. Verify that there is sufficient hose to allow convenient travel of the machine around the reactor vessel flange O-ring seating groove.
  - 4.21.2.3.3 Using the handles, place the machine on the reactor vessel flange, approximately centered over a capped stud hole. Place a clean pad under the machine to avoid picking up foreign material in the brush disks or rollers.
  - 4.21.2.3.4 Engage the installation dolly in the slot in the front of the machine, and tilt the dolly handle down to pick up the unit.
  - 4.21.2.3.5 Roll the dolly forward until the machine is over the reactor vessel flange O-ring seating groove, and gently lower the unit into the groove.
  - 4.12.2.3.6 Verify the correct fit of the bumpers and brush hoods along the sides of the groove.

NOTE

LEFT and RIGHT directions are given on the control panel facing the machine, with the machine installed in the reactor vessel flange O-ring seating groove.

The travel direction toggle switch has a detent in the STOP position, which prevents changing direction without pausing at STOP, to protect the gear motor.

- 4.21.2.3.7 Operate the travel drive using the LEFT - STOP - RIGHT toggle switch and the TRAVEL SPEED knob on the remote control box. Guide the control cable and vacuum cleaner hose as the machine moves to prevent snags.
- 4.21.2.3.8 Operate the brush disks with the BRUSH MOTOR toggle switch on the remote control box.

CAUTION

Approach the guide studs slowly to avoid damage to the machine.

- 4.21.2.3.9 Using the above controls, move the machine around the vessel flange as required to clean the flange. Adjust the brushing pressure and/or replace the brush disk assemblies as required.
- 4.21.2.3.10 After cleaning a section of the vessel flange O-ring seating groove between the guide studs, position the machine for convenient removal using the installation dolly. Move the machine to the next section of the flange, and repeat the above process.
- 4.21.2.3.11 The machine will not clean O-ring flange behind the guide studs. This area must be cleaned manually using the methods outline in Step 4.21.2.2.
- 4.21.3 Visually check the vessel flange mating surface for cleanliness, nicks, scratches, or other undesirable conditions and visually check the vessel head flange mating surface for traces of raised metal. Small scratches or blemishes may be removed by hand rubbing with Scotch brite #7447 and/or an Arkansas hard stone followed by cleaning with acetone and a demineralized water rinse. No other cleaning or polishing is allowed.
- 4.21.4 Concurrently with dewatering and/or vessel flange cleaning, head O-ring replacement may begin.

NOTES

- a. Retainer bolts require a 5/32 Allen type wrench for loosening and removal.
- b. The retainer bolts and clips may be totally removed from the head to ease O-ring removal, but care must be used so that they are not lost.

c. All personnel in contact with the O-rings shall wear lint free cotton and/or rubber gloves.

- 4.21.5 Supporting the old O-rings one at-a-time by hand, loosen the sixteen (16) O-ring retainer bolts and turn the associated retainer clips away from each O-ring.
- 4.21.6 Lower the old O-ring away from the head and cut it into several pieces. Place the pieces into approved containers and have Health Physics dispose.
- 4.21.7 Thoroughly clean the head flange sealing surfaces and O-ring grooves using lint-free rags and either isopropyl alcohol or acetone. Rinse with demineralized water.
- 4.21.8 Visually check the head flange mating surface as per 4.21.3.
- 4.21.9 Replace the inner O-ring as follows:
- 4.21.9.1 Pick up the O-ring using a minimum of four people equally spaced around the ring to prevent kinking or bending. Each person should hold his arms as far apart as is convenient so that in effect there are 8 support points.

## NOTE

Any unwrapping or cleaning of the O-rings should be done by workmen other than those holding the O-rings. All personnel shall wear clean, white, lint-free cotton and/or rubber gloves for all cleaning and handling of the O-rings.

- 4.21.9.2 Carefully unwrap and clean the new O-ring with acetone or approved cleaning solvent and rinse thoroughly with demineralized water.
- 4.21.9.3 Visually check the O-ring for cleanliness, nicks, scratches, or other undesirable conditions.
- 4.21.9.4 Lift the O-ring to within one inch of the O-ring groove and line up the O-ring slots with the retainer clip slots in the vessel head.

- 4.21.9.5 Insert the O-ring into its groove and insert the stem of the retainer clips into the O-ring slots. Retighten or reinstall the retainer bolts through the eyes of the retainer clips. Tighten snugly with the Allen wrench.

## NOTE

The O-ring retainer bolts shall be bottomed tightly on their shoulders to eliminate the possibility of the heads extending out beyond the mating surface and damaging the vessel mating surface upon contact.

- 4.21.10 Repeat Steps 4.21.9.1 through 4.21.9.5 for the outer O-ring.
- 4.21.11 \*/\* Visually check the O-rings to ensure that they are properly fitted in their grooves and that the surfaces are clean.
- 4.21.12 Check the retainer bolts with a straight edge to ensure that they will not interfere with the mating surfaces.
- 4.21.13 Clean the job area and remove all tools.

## NOTE

Do not use feet or excessive force to insert the connecting pin.

- 4.21.14 Align the polar crane and load cell to the head lift rig and attach by hand cranking the connecting pin in. The pin is inserted by cranking left (counterclockwise).
- 4.21.15 Ensure that the head lift rig leg turnbuckles are disconnected after the polar crane is attached to the lift rig.



## CAUTION

No movement of the head shall be attempted without continuous voice communication between the crane operator and signal man. Hand signals are not allowed. If voice communications are lost, suspend movement of the head until the situation can be corrected.

- 4.21.16 Securely attach at least three levels to the top of the vessel head flange approximately 120° apart.
- 4.21.17 Take a strain with the polar crane and lift the head approximately one inch off the storage pad. Check for levelness. If not level, set it back on the storage pads and adjust. Small adjustment should be made by movement of the radial arm hoists around the head circumference prior to any major adjustments involving the lift rig.
- 4.21.18 \*/\* Once the head is level hold it at the one inch position for ten minutes while visually checking the accessible welded and bolted lift rig and load cell connections. Note the weight reading on the load cell monitor.
- 4.21.19 Remove the levels from the head.
- 4.21.20 While monitoring the load cell readout for any sudden  $\pm 5$  percent change in the previously noted load cell readout, slowly lift the head to an elevation that will clear all obstructions between the storage pad and reactor cavity.
- 4.21.21 Align the head over the vessel (guide studs in holes 12, 28, 44 and mini guide stud 30 when ISI Vessel Inspection is performed) and lower to within one foot of the water level, if the level is to be lowered with the head, or to the top of the guide studs.

## CAUTION

Do not allow the head to come into contact with the water.

- 4.21.22 While constantly monitoring the load cell readout for any sudden  $\pm 5$  percent change in the previously noted load cell readout which would indicate binding or interference, continue to lower the head.

- 4.21.23 Visually check to ensure proper drive shaft and thermocouple alignment as they enter the head guide funnels.

## NOTE

Coordination with Operations will be required as the water level must be approximately 48" (Elev. 190') below the vessel flange before seating the head.

- 4.21.24 \*/\* Lower the vessel head until it is seated on the vessel.
- 4.21.25 Assemble the access platform from the operating floor (elevation 220 feet) to the missile shield if necessary.
- 4.21.26 Reconnect the lift rig leg turnbuckles.

## NOTE

Do not use feet or excessive force to crank the connecting pin out.

- 4.21.27 Using the load cell readout to determine null load point, disconnect the polar crane load cell from the head lift rig. Turn the crank to the right (clockwise) to remove the connecting pin.
- 4.21.28 The load cell may now be de-energized, disconnected, and stored.
- 4.21.29 Remove and store the underwater lights if not already completed during dewatering of the cavity.

## 4.22 REFUELING CAVITY DECONTAMINATION

Allow Health Physics to decontaminate the refueling cavity per Procedure 43301-C, "Decontamination Of Areas, Tools And Equipment".

#### 4.23 INSTALLATION OF TRANSFER TUBE BLIND FLANGE

##### NOTE

This work may be accomplished at any time between Step 4.22 and completion of this procedure.

- 4.23.1 Remove the two 1/16-inch brass plugs from the face of the bolted flange. Store them for future use.
- 4.23.2 \*/\* Clean and visually check the mating surfaces.
- 4.23.3 Install two new quad ring seals. These seal gaskets should be coated with GE Versilube 392.
- 4.23.4 Using the davit arm, swing the blind flange over the fuel transfer tracks and down into position.
- 4.23.5 Clean the 20 flange bolts. Lightly lubricate the bolt threads and head underside with Never-Seez Pure Nickel Special.
- 4.23.6 \*/\* Install the bolts and hand tighten. Torque the bolts in a two-step method cross pattern to a value of 45 ft-lbs in the first pass and then to a final torque value of 80 ft-lbs  $\pm$  2 ft-lbs.

##### NOTE

Seal integrity will be checked during the maintenance surveillance testing in accordance with Procedure 24960-1 for Unit 1 or 24960-2 for Unit 2, "Containment Penetration No. 39 - Local Leak Rate Test".

#### 4.24 \*/\* STUD INSTALLATION

##### CAUTION

Studs, nuts, washers, and stud holes are match-marked by number and must always be used together.

## NOTE

At the discretion of the Outage Area Supervisor, a second head lift may be added at this time to ensure that cavity decontamination or stud hole cleaning did not force particles into the vessel O-ring sealing area. Section 4.24.1 governs activities to perform the second lift. If no second head lift is required, skip to Section 4.24.2.

- 4.24.1 Second Head Lift Prior To Stud Installation
- 4.24.1.1 Remove the stud hole plugs as follows:
  - 4.24.1.1.1 Using the stud hole plug removal tool's lower "T" handle, insert the tool into the plug.
  - 4.24.1.1.2 While holding the upper "T" handle in a fixed position, turn the lower "T" handle to the left. The two plates will be decompressed to unlock the plug from the hole.
  - 4.24.1.1.3 Attach the installation-removal adapter by screwing the adapter onto the plug.
  - 4.24.1.1.4 Lift the lower "T" handle and remove the plug from the hole.
  - 4.24.1.1.5 Repeat Steps 4.24.1.1.1 through 4.24.1.1.4 until all stud hole plugs have been removed.
- 4.24.1.2 After each stud hole plug is removed, the stud hole must be inspected and dewatered and/or cleaned as necessary. The accessible holes may be cleaned manually, using Section 4.24.1.2.1, or may be power cleaned using Section 4.24.1.2.2.
  - 4.24.1.2.1 Manual Cleaning Method
    - 4.24.1.2.1.1 A power nylon brush may be used provided a protective sleeve is slipped through the head hole down to rest on the top threads. A stainless steel brush may be used at the discretion of the cognizant Maintenance Foreman. This will prevent the power brush from slinging debris onto the already cleaned O-ring and mating surfaces.

4.24.1.2.1.2 Ethyl alcohol or acetone may be used as a cleaning agent but do not attempt to lubricate threads through the head as excess lubrication will occur.

4.24.1.2.2 Power Cleaning Method

#### CAUTION

Do not attempt to operate the power brush or the vacuum cleaner unless the machine is firmly in place in a stud hole because:

- a. The power brush is not supported for unrestrained operation and damage to the drive may result.
- b. The power brush is not equipped with a guard, and may endanger the operator.
- c. The vacuum cleaner may discharge partially filtered radioactive particles, creating an airborne contamination hazard.

#### NOTE

The brush drive and vacuum cleaner power are interlocked with a limit switch, so that they are de-energized if the machine is not firmly seated in a stud hole.

The cleaning machine should have nylon brushes installed. Use of the stainless steel brushes shall be approved by the cognizant Maintenance Foreman.



- 4.24.1.2.2.1 Verify that at least 3/4 inch of bristle remains on the strip brushes and that the setscrews holding the strip brushes are tight.

#### CAUTION

The stud hole to be cleaned must be free of water to avoid damage to the paper vacuum filter.

- 4.24.1.2.2.2 Remove the storage cap from the end of the machine.
- 4.24.1.2.2.3 Place the machine in a stud hole in the reactor head flange. Verify that the gasket sleeve is seated firmly in the reactor vessel head stud hole. Adjust the 3/8 inch hex head bolt support feet as required.
- 4.24.1.2.2.4 Verify that the junction box is positioned such that the limit switch on the bottom of the box opens when the machine is lifted 1/8 inch. Adjust the position of the box on the mounting bracket as required.
- 4.24.1.2.2.5 Using the control switches, verify operation of the vacuum cleaner and the power brush.

#### NOTE

The brush drive motor power is interlocked with the vacuum cleaner pushbutton switch (RUN), so that the vacuum cleaner and the brush drive operate together.

- 4.24.1.2.2.6 Press down on the T-handle swivel joint to extend the brush assembly down into the stud hole.
- 4.24.1.2.2.7 Using the UP/DOWN switch and the RUN switch, run the brush up and down the stud hole threads as required to clean the stud hole.
- 4.24.1.2.2.8 After cleaning the stud hole, pull up on the T-handle swivel joint to fully withdraw the brush assembly up into the brush tube.
- 4.24.1.2.2.9 The machine may then be moved to the next hole to be cleaned, and the cleaning performed per Steps 4.24.1.2.2.6 through 4.24.1.2.2.9.

- 4.24.1.2.2.10 After completion of cleaning operations, firmly replace the storage cap.
- 4.24.1.3 If desired, set the stud hole plugs back into the cleaned holes, but do not lock the plug in.
- 4.24.1.4 Lift the head by performing Steps 4.16.1 through 4.16.9.  
\*/\*
- 4.24.1.5 When it is apparent that the head is not binding on the thermocouple protective sleeves or RCCA drive shafts, note the weight reading on the load cell monitor.
- 4.24.1.6 Continue to lift the head to a height determined by the Outage Area Supervisor. Constantly monitor the load cell readout for any sudden +/-5% change in the previously noted load cell readout which would indicate binding or interference.
- 4.24.1.7 Hold the head at the height determined above. Inspect the vessel flange and O-ring seating surface for cleanliness or any foreign objects or debris. Clean the flange, if necessary, in accordance with Section 4.21.2.

## NOTE

Coordination with Operations will be required as the water level must be approximately 48" (Elev. 190') below the vessel flange before seating the head.

- 4.24.1.8 If the head was lifted above the top of the guide studs, align the head over the vessel (guide studs in holes 12, 28, 44 and mini guide stud 30 when ISI Vessel Inspections are being performed), and begin lowering the head. Constantly monitor the load cell readout for any sudden +/-5% change in the previously noted load cell readout which would indicate binding or interference.
- 4.24.1.9 Visually check to ensure that proper drive shaft and thermocouple alignment as they enter the head guide funnels.
- 4.24.1.10 Lower the vessel head until it is seated on the vessel.

4.24.1.11 Assemble the access platform from the operating floor (elevation 220 feet) to the missile shield.

4.24.1.12 Reconnect the lift rig turnbuckles.

## NOTE

Do not use feet or excessive force to crank the connecting pin out.

4.24.1.13 Using the load cell readout to determine the null load point, disconnect the polar crane load cell from the head lift rig. Turn the crank to the right (clockwise) to remove the connecting pin.

4.24.1.14 The load cell may now be de-energized, disconnected, and stored.

## NOTE

Use a chain fall between the polar crane and the guide studs.

4.24.1.15 Using the polar crane auxiliary hoist hook and a sling through the access hole in the upper portion of the integrated head, remove the three guide studs.

4.24.1.16 \*/\* Using the guide stud sleeve tool, remove the three guide stud sleeves.

4.24.1.17 Clean the stud holes that the guide studs were removed from using one of the cleaning methods in Sections 4.24.1.2.1 or 4.24.1.2.2.

4.24.1.18 \*/\* Remove all remaining stud hole plugs.

## NOTE

Section 4.24.1 includes the requirements of 4.24.2. Proceed to 4.24.3.

4.24.2 Preparation For Stud Installation

## NOTE

Use a chainfall between the polar crane and the guide studs.

- 4.24.2.1 Using the polar crane auxiliary hoist hook and a sling through the access hole in the upper portion of the integrated head, remove the guide studs.
- 4.24.2.2 Using the guide stud sleeve tool remove the guide stud sleeves.

\*/\*

## NOTE

If the studs, nuts, and washers were stored in their storage racks, then all stud hole plugs should be removed at this time. If they were stored on the vessel head, then each stud hole plug must be removed individually after the stud has been lifted for stud collar removal.

- 4.24.2.3 Remove all stud hole plugs in accordance with Steps 4.24.1.1.1 through 4.24.1.1.5.
- \*/\*
- 4.24.2.4 Clean the stud holes in accordance with Section 4.24.1.2.
- 4.24.3 Installation Of The Studs
- 4.24.3.1 Move the fast stud turnout tools, stud racks (if applicable), and necessary accessories into the cavity.
- 4.24.3.2 If the integrated head cable trays have not been lowered and the connector plate cables reconnected, connect a temporary 480V power source to the bottom of the shroud for the radial arm hoists.
- 4.24.3.3 Electric Tool Operation

## NOTE

Any number (1-6) of tools can be used, (space and personnel dependent) or hand installation is allowed.

## CAUTION

No stud should be threaded into or out of the vessel without the use of a weight compensator, crane scale or other device capable of a preload of at least 1/2 the stud weight. This will protect the stud and vessel threads.

- 4.24.3.3.1 Move the stud turnout tools into the reactor cavity and hook them to their individual radial arm hoists.
- 4.24.3.3.2 Hook up a regulated air supply to the air compensator and adjust to approximately 55 psi.
- 4.24.3.3.3 If the studs were stored on the head, attach the radial hoist with the turnout tool and weight compensator to a stud and lift the stud out of the head hole. Remove and store the stud collar and then remove the stud hole plug as instructed in Steps 4.24.1.1.1 through 4.24.1.1.4 above.
- 4.24.3.3.4 If the studs were stored in their storage racks then there will be no stud collar or stud hole plug to remove at this time. A stud, nut and washer can now be picked up out of the stud rack.

## NOTE

The convex side of stud washers point up.

- 4.24.3.3.5 Position the individual stud in its match marked hole. Ensure the washer is placed between the head flange and the nut. The nut, if left on the stud, is positioned so as to not interfere with the threading operation.
- 4.24.3.3.6 Hand thread the stud into the vessel flange a minimum of three complete turns.
- 4.24.3.3.7 By use of the radial arm hoist control, adjust the height until the compensator cylinder arm is extended approximately one inch.
- 4.24.3.3.8 Verify that the eyebolt locking cap is properly aligned and seated on the top of the stud.



## NOTE

While threading the stud into the vessel maintain the cylinder arm extension between 2 to 8 inches.

## CAUTION

Use slow speed or a joggling motion as the stud almost bottoms. This will preclude locking the stud to the vessel or damaging the threads.

- 4.24.3.3.9 Place the motor control switch on the tool in the forward direction and, using the Variac to control the speed, thread the stud into the vessel flange.
- 4.24.3.3.10 When the stud has bottomed, back it off approximately 1/2 turn. This will help to preclude jammed studs after tensioning and heat cycling.
- 4.24.3.3.11 Disconnect the stud spinout tool by lifting the eyebolt locking cap above the top of the stud and unthreading the eyebolt.
- 4.24.3.3.12 When all studs have been installed, remove all tools, racks, etc., from the cavity prior to proceeding to the next subsection.

## 4.25

## STUD TENSIONING

\*/\*

- 4.25.1 Remove and store the 54 stud eye bolts. Make sure that there is no foreign material on top of the stud which could fall into the measuring hole.
- 4.25.2 Install an elongation measuring rod in each stud. Do not allow rods to drop into the hole as rod damage and inaccurate measurements could result.

## NOTE

The acceptance criteria for stud tensioning is based on stud elongation; 0.051 inch  $\pm$ .002. QC must verify each reading taken for the initial and final (after adjustment) condition as recorded in columns 1 and 4 of Data Sheet 1. All other intermediate elongation data and/or tensioner pump pressures are for information to get to the required final elongation point.

4.25.3  
\*\*

After the temperature of the vessel, head, studs, and rods have stabilized and are approximately equal, take and record in column 1 of Data Sheet 1 the initial condition readings for all 54 studs.

## NOTE

When setting and hooking up the stud tensioners, pay particular attention that tensioner #1 is hooked to the hydraulic pump and used in the #46 to #54 stud area. The remaining five tensioners are interchangeable in position (see Figure 1.).

4.25.4

Lower the stud tensioners into the reactor cavity using the polar crane auxiliary hoist and transfer each to its associated radial arm hoist assembly.

4.25.5

Station each tensioner near its first setup position, i.e., Tensioner #1 to stud #46, #2 to #37, #3 to #28, #4 to #19, #5 to #10, and #6 to #1.

4.25.6

Lower the hydraulic pump assembly into the reactor cavity using the polar crane auxiliary hoist and station it in the southwest corner for Unit 1 or northeast corner for Unit 2 of the elevation 194 floor area.

4.25.7

Lower the tensioner hoses into the cavity and hook up as follows:

## NOTE

Figures 1 and 2 may be used as an aid to hose hook up.

- 4.25.7.1 Connect the two, 12-foot long, 3/8-inch diameter, high pressure hydraulic hoses between the tensioners to the couplings on both sides of the cylinder. To connect the coupling, remove the dust cap which protects the body half and push the male tip into the body. Then screw on the collar until it bottoms. The collar is a free fit and should almost spin on, however, it must be bottomed for the hydraulic fluid to flow freely.
- 4.25.7.2 Connect the 12-foot long, 1/4-inch diameter, low pressure hydraulic hose (bypass valve signal) between the tensioners to the union adapters located just above the high pressure couplings.
- 4.25.7.3 Connect the black, 12-foot long, 1/4-inch diameter, air hose (piston return) between the tensioners to the couplings located on the front portion of the top plate.
- 4.25.7.4 Connect the red, 12-foot long, 1/4-inch diameter, air hose (air signal) between the tensioners to the couplings located on the top left and right hand side of the top plate.
- 4.25.7.5 Connect the single, 12-foot long, 1/4-inch diameter, air hose (air signal) between tensioner #6 and tensioner #1.
- 4.25.7.6 Repeat Steps 4.25.7.1 through 4.25.7.4 for each of the five 12-foot long hose sets.
- 4.25.7.7 Connect each one of the hoses in the 35-foot long set between tensioner #1 and the pumping assembly in the same manner as the interconnecting hoses in Steps 4.25.7.1 through 4.25.7.4.
- 4.25.8 Connect an air supply to the pumping assembly through the two 1-inch female pipe connections located on the upper left hand side of the pump. One or both connections may be used to provide an adequate supply however, if only one connector is used, the other one must be plugged.

## WARNING

DO NOT CLOSE THE PUMP RELEASE VALVE OR PUSH THE AIR VALVE UNLESS ALL TENSIONER HOSES ARE CONNECTED AND THE TENSIONERS ARE FULLY SEATED ON THE VESSEL FLANGE WITH THE WEIGHT OFF THE HOIST ENOUGH TO LOCK THE PULL SYSTEM TO THE STUD, THERE-BY ACTIVATING THE LIMIT SWITCH.

## NOTES

- a. When lowering a tensioner onto a stud, it is best to use the buddy system, i.e., one man operating the hoist while the other man guides the tensioner over the stud by use of the two handles provided on the front of the tensioner.
- b. Table 2 may be cut apart and taped securely to its respective tensioner to be used as a sequence guide in the tensioning operation.

- 4.25.9 Using the individual radial arm hoist assemblies, lower each tensioner over its first stud as seen on the sequence guide (Table 2).
- 4.25.10 Ensure that each tensioner is seated flush on the head flange and that the tensioner pull system is locked to the stud.

## NOTE

If adjustment of stud tensioners is required, adjustment may be performed without the need for a Maintenance Work Order.

- 4.25.11 Close the release valve on the pumping assembly then depress and hold the air valve.

## CAUTION

Maximum hydraulic pump pressure shall not exceed 9500 psi.



- 4.25.12 Continue pumping operation until the pressure (Table 1) for that particular set and pass has been reached.
- 4.25.13 When the appropriate pump pressure has been reached, insert the torque handle into one of the holes in the upper portion of the spherical nut and rotate in the clockwise direction until the nut bottoms.
- NOTE
- To torque, the pivot pin on the torque handle must be in a vertical position. The torque handle is marked to indicate this proper position.
- 4.25.14 When the nut bottoms, apply force to the torque handle until an audible click is heard. This will seat the nut at a preset torque.
- 4.25.15 Open the release valve and allow the pressure to reduce to zero.

CAUTION

- Pull system release of a stud is activated by taking up slack in the tensioner lift mechanism. Make sure pull system is released before continuing lift of tensioner.
- 4.25.16 Carefully raise the tensioners clear of the studs using the individually attached radial arm hoists.
- 4.25.17 When all tensioners are clear of their respective studs move all tensioners in unison to the next set-up.
- 4.25.18 Continue Steps 4.25.9 through 4.25.17 until all sets and all passes (Table 1) are completed.  
\*/\*
- 4.25.19 When the two passes have been completed, move the six tensioners clear. Take and record elongation data in column 2 of Data Sheet 1.
- 4.25.20 Calculate the amount of residual elongation (column 3) for each stud.



## NOTES

- a. Studs and nuts not requiring adjustment but used for locking down tensioners during adjustment passes may be marked with a chalk line to allow detection of inadvertent movement.
- b. If an adjustment pass is required, then a set sequence need not apply; however, all tensioners hydraulically connected must be locked to a stud before pressurization may start. If a tensioner is locked to a stud which does not need readjustment, pumping up and down without moving the spherical nut should leave its elongation within tolerance.
- c. Steps 4.25.21 and 4.25.22 are to be used as a basic adjustment guide. Variation in pump pressure or nut position may be required to bring stud elongation into tolerance.

- 4.25.21 To adjust studs which are below required elongation, pump up to 7000 psi and set the nut with the torque handle.
- 4.25.22 To adjust studs which are above the required elongation; pump up until nuts are free. Back the nut off one full turn (18 holes), then return to 7000 psi and reset the nut using the torque handle.

## NOTE

When adjustments are made to a particular stud it may affect the elongation of the adjacent studs.

- 4.25.23  
\*/\* After all out-of-tolerance studs have been adjusted and all 54 studs are within limits, contact QC. Take and record the final elongation readings in column 4 of Data Sheet 1.

- 4.25.24 When all studs have been tensioned within the specified limits, disconnect and remove all tensioning equipment from the cavity.
- 4.25.25 Remove and store the elongation measuring rods.
- 4.25.26 Lightly lubricate the 54 stud top screw inserts with N5000 and install.

4.26  
\*/\* SEAL TABLE PREPARATION

NOTE

Subsection 4.26 may be accomplished any time after 4.19 but must be completed prior to Subsection 4.32.

- 4.26.1 The seal table will be prepared for operation in accordance with Procedure 93280-C, "Flux Thimble Withdrawal And Reinsertion For Refueling".

4.27  
\*/\* INSTRUMENT PORT - CONOSEAL ASSEMBLY

NOTE

Step 4.27 may be accomplished any time after Step 4.25 but must be completed prior to Step 4.32.

CAUTION

In the assembly of the conoseal, cleanliness is of the utmost importance in the seal joint; therefore, QC should continuously monitor this operation for cleanliness and verify torquing requirements. Use clean lint-free cotton and/or rubber gloves for this installation.

- 4.27.1 Open the applicable shroud door. Remove and store the thermocouple protective sleeve spring, protective sleeve, and O-ring.
- 4.27.2 Clean the female flange and new lower conoseal gasket with acetone or isopropyl alcohol followed by demineralized water.

- 4.27.3 Ensure that the gasket and flange, especially the mating areas are clean and free of nicks or scratches.
- 4.27.4 Install the lower gasket on the female flange. Make sure that the apex of the cone formed by the gasket points toward the top of the containment building.
- 4.27.5 Clean the upper sealing surface of the thermocouple support column and the new upper console gasket with acetone or isopropyl alcohol followed by demineralized water.
- 4.27.6 Ensure that the gasket and sealing surface are clean and free of nicks or scratches.
- 4.27.7 Install the upper gasket on the support column. Make sure that the apex of the cone formed by the gasket points toward the bottom of the Containment Building.
- 4.27.8 Clean the male flange and weld ring (if used) with acetone or isopropyl alcohol followed by rinsing with demineralized water.
- 4.27.9 Ensure that the male flange, especially the mating areas are clean and free from nicks or scratches.
- 4.27.10 Place the weld ring (if used) on the female flange, and place the male flange on the female flange until the male flange rests on the lower gasket.
- 4.27.11 Assemble the loading device and slip it down over the flanges. *SEE ATTACHMENT PER 7.4.10* The loading device may be assembled before or after setting on the conoseal. Engage the locking flange of the loading device by rotating it approximately 15° such that the protrusions are inside the notches in the female flange.
- 4.27.12 Clean the coupling assembly and apply a thin coat of Neolube #1 or #2 to the bolt threads, the interior contact points of the clamp and the exterior contact points of the male and female flanges.

Add note between 4.27.10 and 4.27.11

NOTE

THE OLD STYLE HOLLOW LOADING RAM OR  
NEW STYLE LIGHTWEIGHT LOADING RAM MAY  
BE USED TO ASSEMBLE CONSEALS.

## NOTES

- a. When installing the coupling assembly be sure the bolts are in their proper location with respect to the loading device. About 1 inch between bolt and loading device should allow the loading device to be rotated to the unlocked position.
- b. When hand tightening the three coupling bolts, keep them approximately even so that all three will protrude far enough for future cotter pin installation.

4.27.13 Install the coupling assembly and hand tighten the three bolts. *SEE ATTACHMENT CAM 3.6.7.1*

~~4.27.14 Gradually apply pressure to the hydraulic cylinder using the hand pump. A pressure between 1275 to 1375 psi is required for proper sealing. This pressure can be read on the hand pump gage.~~

~~4.27.15 While maintaining the 1275 to 1375 psi on the loading device, torque the three bolts uniformly in increments of approximately 25 to 30 ft-lbs until a final torque of 50 to 60 ft-lbs is obtained.~~

4.27.16 When torquing is complete, release the hydraulic pressure. Rotate the loading device to the unlocked position and remove.

## NOTE

The loading device may be disassembled in order to remove it.

4.27.17 Install cotter pins through the bolts and bend against the body of the clamp to prevent bolt rotation.

4.27.18 Clean and install the jack screw plate to the thermocouple column. Up to 4 jackscrews may be pre-installed prior to attachment to the thermocouple column.



- 4.27.14 SLOWLY PRESSURIZE THE HOLLOW CYLINDER LOADING RAM TO BETWEEN 1275 PSI AND 1375 PSI OR THE LIGHTWEIGHT LOADING RAM TO BETWEEN 5650 PSI AND 6100 PSI.
- 4.27.15 WHILE MAINTAINING THE CORRECT PRESSURE ON THE LOADING RAM, TORQUE THE THREE BOLTS UNIFORMLY IN INCREMENTS OF APPROXIMATELY 25 TO 30 FT-LBS UNTIL A FINAL TORQUE OF 50 TO 60 FT-LBS IS OBTAINED.

- 4.27.19 Clean and install the split ring to the thermocouple support ring.
- .27.20 Clean and apply a thin coat of Neolube #1 or #2 to the jack screw, then install it through the jackscrew plate.
- 4.27.21 Tighten the jack screws uniformly in a cross pattern in approximately 30 in-lbs increments until a final torque of 95 to 105 in-lbs is obtained.
- 4.27.22 Install locking wire to prevent screw rotation.
- 4.27.23 Repeat Steps 4.27.1 through 4.27.22 until all four instrument port conoseals have been completed.  
\*/\*

CAUTION

Do NOT twist the knurled thermocouple connectors during reassembly.

- 4.27.24 For thermocouples equipped with Conax-Style connectors, torque the 1/2-inch compression cap to 144-180 inches-pounds while holding the connector body with a wrench to prevent rotation.
- 4.27.25 Connect all thermocouple connectors. Close the shroud doors. Document on Data Sheet 4.
- 4.28 CAVITY PREPARATION

NOTE

Step 4.28 may be accomplished any time after Step 4.22 or any time prior to procedure completion.

- 4.28.1 Remove and store the two blind flanges on the emergency containment spray returns. Replace the drain screens by cleaning and coating threads on studs and nuts and underside of the nut with Never-Seez Pure Nickel Special. Torque nuts in a two-step cross pattern method with 50-60% of final torque applied on the first step. Final torque will be 60 ft-lbs minimum.  
\*/\*

4.28.2

\*/\*

Invert and reinstall the eight refueling cavity ventilation opening cover plates (slotted plate down) using the same EPDM gasket which was previously installed. Coat threads with Never-Seez Pure Nickel Special. Tighten the 1/2" bolts to a snug tight fit.

4.29

## HEAD VENT PIPING

4.29.1

Remove and store the blank flange on the cavity floor penetration for the RV head vent line.

4.29.2

\*/\*

Install the head vent lines using new 25001b. spiral wound gaskets. Coat threads with Never-Seez Pure Nickel Special. The flange bolts, shall be torqued in a 3 pass cross pattern to a 300 ft-lbs.

4.30

\*/\*

## REACTOR VESSEL LEVEL INSTRUMENTATION SYSTEM (RVLIS)

4.30.1

Install the RVLIS tubing. Swagelok fittings are tightened hand tight plus 1/4 turn.

4.31

## INSTALLATION OF THE REACTOR HEAD INSULATION

## NOTE

Head insulation may be installed anytime after Step 4.25.26.

4.31.1

Using appropriate rigging, hand maneuver each section of the Reactor Vessel Head insulation into place. Start with the section designated for azimuth 0°.

4.31.2

\*/\*

Continue placing sections around the head until all sections have been installed. Insert section fastener devices and tighten to a snug tight fit.

4.32

## RV FILL AND VENT

## NOTE

Reactor vessel filling can start at any time after Step 4.30.

4.32.1

RV filling and venting are accomplished in accordance with Procedure 13001-1 or 13001-2, "Reactor Coolant System Filling and Venting", as applicable.

### 4.33 CABLE RECONNECTION

#### NOTE

Lowering of cable trays and connection of all cables may occur any time after Step 4.22; however, due to interference around the head it is best to wait until late in this procedure to start this work.

- 4.33.1 Disconnect temporary 480V power cable (if used) from the integrated head shroud.
- 4.33.2 Unlatch the cable tray from its stored position.
- 4.33.3 Using the Reactor Head Electric cable tray winches, pivot the cable tray downward to the tray restraints at the shroud. Alternate lifting devices may be used to lower cable trays should the winches fail.
- 4.33.4 Latch the shroud cable tray restraints.
- 4.33.5 Repeat Steps 4.33.2 through 4.33.4 for the other cable tray.
- 4.33.6 \*/\* Reconnect all cables from the cable tray to the outside of the connector plate. Document cable reconnection on Data Sheet 4.
- 4.34 \*/\* SEISMIC TIE RODS
- 4.34.1 Unlock the tie rod from its stored position and lower it to its cavity wall lug.
- 4.34.2 Remove the cotter pin and connecting pin from the tie rod clevis and maneuver the clevis to the lug.
- 4.34.3 Install the connecting and cotter pins.
- 4.34.4 \*/\* Repeat Steps 4.34.1 through 4.34.4 for each of the six tie rods.
- 4.35 Remove the access platform from the operating floor to the missile shield and all tools and materials used in this procedure.

4.36 \*/\*      Notifv the Shift Supervisor tHe reactor has been re-assembled for operation.

5.0      REFERENCES

- 5.1      1X6AB02-70 (2X6AB02-145), Instruction Manual, Reactor Vessel Unit 1/2)
- 5.2      X6AB02-231, Technical Manual, Four-Loop Integrated Head Package
- 5.3      X6AB02-143, Operating and Maintenance Manual, Quick Acting Stud Tensioners Unit 1/2
- 5.4      X6AB02-207, Instruction Manual, Reactor Vessel Stud Removal Tool Unit 1/2
- 5.5      X6AN09-63, Technical Manual, Fuel Transfer System Unit 1/2
- 5.6      X6AQ02-19, Westinghouse F Specification F-2 Preoperation for Refueling Unit 1/2
- 5.7      X6AB06-86, Westinghouse Assembly Specification, Instrumentation Port Column Assembly Unit 1/2
- 5.8      X6AB02-171, 190, Drawing, Reactor Tophead Insulation Field Erection
- 5.9      X6AB02-153, 222, Technical Manual, 450A Load Cell System

5.10      PROCEDURES

- 5.10.1      00254-C,      "Plant Housekeeping/Material Condition Program"
- 5.10.2      12007-C,      "Refueling Entry"
- 5.10.3      13001-1,      "Reactor Coolant System Filling And Venting"
- 5.10.4      13001-2,      "Reactor Coolant System Filling And Venting"
- 5.10.5      13005-1,      "Reactor Coolant System Draining"
- 5.10.6      13005-2,      "Reactor Coolant System Draining"



PROCEDURE NO. VEGP	93240-C	REVISION <i>3 of 3/2/90</i>	PAGE NO. 61 of 98
-----------------------	---------	--------------------------------	----------------------

- 5.10.7 20425-C, "Control Of Refueling Lifting And Rigging Equipment"
- 5.10.8 27305-C, "Reactor Polar Crane Service Check"
- 5.10.9 27315-C, "Spent Fuel Cask Monthly And Annual Check Out"
- 5.10.10 24960-1, "Containment Penetration No. 89 - Local Leak Rate Test"
- 5.10.11 24960-2, "Containment Penetration No. 89 - Local Leak Rate Test"
- 5.10.12 43002-C, "Airborne Radioactive Sampling And Evaluation"
- 5.10.13 43007-C, "Issuance, Use, And Control Of Radiation Work Permits"
- 5.10.14 43301-C, "Decontamination Of Areas, Tools, And Equipment"
- 5.10.15 55023-C, "Incore Irradiation Specimens"
- 5.10.16 93100-C, "Refueling Tools And Equipment Preservice Inspection/Checkout"
- 5.10.17 93140-C, "Control Rod Drive Shaft Unlatching Tool Operating Instructions"
- 5.10.18 93280-C, "Flux Thimble Withdrawal And Reinsertion For Refueling"

END OF PROCEDURE TEXT

TABLE 1  
OPERATIONAL BOLT-UP

	2	3	4	5	6
	Stud Numbers	First Pass Pump Pressure (psi)	Second Pass Pump Pressure (psi)	Adjustment Pass Pump Pressure (psi)	Desired Residual Elongation (inches)
1	1, 19, 37, 10, 28, 46, 4, 22, 40	5200	7800	7000	0.051 ± .002
2	13, 31, 49, 7, 25, 43				
3	16, 34, 52, 2, 20, 38	4950	7400		
4	11, 29, 47, 5, 23, 41				
5	14, 32, 50, 8, 26, 44				
6	17, 35, 53, 3, 21, 39	4700	7000		
7	12, 30, 48, 6, 24, 42				
8	15, 33, 51, 9, 27, 45				
9	18, 36, 54				

TABLE 2

STUD TENSIONING-DETENSIONING SEQUENCE  
Cut Apart and Tape to Individual Tensioners

TENSIONER 1		TENSIONER 2		TENSIONER 3	
SEQUENCE	STUD	SEQUENCE	STUD	SEQUENCE	STUD
SET-UP		SET-UP		SET-UP	
1	46	1	37	1	28
2	49	2	40	2	31
3	52	3	43	3	34
4	47	4	38	4	29
5	50	5	41	5	32
6	53	6	44	6	35
7	48	7	39	7	30
8	51	8	42	8	33
9	54	9	45	9	36

TENSIONER 4		TENSIONER 5		TENSIONER 6	
SEQUENCE	STUD	SEQUENCE	STUD	SEQUENCE	STUD
SET-UP		SET-UP		SET-UP	
1	19	1	10	1	1
2	22	2	13	2	4
3	25	3	16	3	7
4	20	4	11	4	2
5	23	5	14	5	5
6	26	6	17	6	8
7	21	7	12	7	3
8	24	8	15	8	6
9	27	9	18	9	9





FIGURE 1



SECTION

--- SEE DRAWING 93240-1 FOR  
 --- IDENTIFICATION OF THE  
 --- ELECTRICAL CONNECTIONS  
 --- TO THE SENSORS






FIGURE 2




Tol 183  
2/6/90



**DETAIL-F**  
SEE FIG. 11  
STRENGTHENED BORE AS SHOWN IN SECTION E-F FOR CLOSURE OF PORT AFTER REMOVAL OF SPEC. A INSTRUMENTATION COL. A SEE NOTE R.





⑪ TORQUE TO BE 20-405 IN. LB. (22-45 kg)  
FOR HYDROSTATIC TEST - SEE NOTE L. DIMENSIONAL SAMPLE AS SHOWN IN DETAIL-G.



TORQUE TO BE 20-405 IN. LB. (22-45 kg)  
ONLY APPLIED TO THIS CONTACT SURFACE.

**DETAIL-S**



⑫ SEE FIG. 11 (b) FOR THE PLACES WHERE THE (b) PLUG IS HELD IN POSITION BY THE (b) PLUG.

⑬ SEE NOTE 1

⑭ SEE NOTE 1

FIGURE 3




FIGURE 4




FIGURE 5 - Head Lift Safe Load Path



DATA SHEET 1

ELONGATION DATA SHEET FOR OPERATIONAL LOAD					
	1	2	3	4	5
Stud No.	Initial Dial Indicator Reading	Dial Indicator Reading After 2nd Pass	Amount of Residual Elongation After 2nd Pass (Column 2-1)	Dial Indicator Reading After Adj. Pass	Amount of Res. Elong. After Adjustment (4-1)
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					



781 JPS  
3/6/90

DATA SHEET 1

ELONGATION DATA SHEET FOR OPERATIONAL LOAD					
	1	2	3	4	5
Stud No.	Initial Dial Indicator Reading	Dial Indicator Reading After 2nd Pass	Amount of Residual Elongation After 2nd Pass (Column 2-1)	Dial Indicator Reading After Adj. Pass	Amount of Res. Elong. After Adjustment (4-1)
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					

Dial Indicator used \_\_\_\_\_ Sum = \_\_\_\_\_  
 Calibration good until \_\_\_\_\_

Average Residual Elongation =  $\frac{\text{Sum Col. 5}}{54}$

## DATA SHEET 2

## VESSEL DISASSEMBLY COMPLETION SHEET

## NOTE

Place N/A in the SIGN-OFF space for those sections not applicable and note in the remarks section the reason for the N/A.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>SIGN-OFF</u>	<u>Q.C. VERIFICATION</u>
4.0	Prerequisites and Initial Conditions for the procedure (3.1. and 3.4) have been completed (see Attachment 1, Item 5)	____/____	____/____
4.2	Equipment for this section (3.2) has been checked out and is available for use (see Attachment 1, Item 1)	____/____	
4.2.5	Seismic tie rod disconnected and locked in the upright position 45° azimuth 135° azimuth 225° azimuth 262° azimuth 278° azimuth 315° azimuth	____/____ ____/____ ____/____ ____/____ ____/____ ____/____	
4.3.7	Cables disconnected and cable tray locked in stored position 0° azimuth 180° azimuth	____/____ ____/____	
4.3.8	Temporary radial arm hoist power cable connected if required	____/____	
4.4.4	RV head insulation removed and stored	____/____	
4.5	RV water level 24 inches minimum below flange, vented and sampled	____/____	
4.6.3	Head vent spool piece removed and stored	____/____	
4.6.6	Head vent seal flange installed	____/____	

## DATA SHEET 2

## VESSEL DISASSEMBLY COMPLETION SHEET

<u>STEP</u>	<u>DESCRIPTION</u>	<u>SIGN-OFF</u>	<u>Q.C. VERIFICATION</u>
4.7.2	RVLIS interconnect tubing removed and stored	<u>  /  </u>	
4.8.1	Seal table has been prepared for refueling and the thimbles have been withdrawn 13 feet 8 inches or 22 feet 3 inches minimum (line out one)	<u>  /  </u>	
4.9	Applicable tools and equipment for this section have been checked out and are available for use (see Attachment 1, Item 2)	<u>  /  </u>	
4.9.16	Conoseal components removed, protected and stored. Protective sleeves installed		
	Core Location	Approximate Azimuth	
	A-5	247°	<u>  /  </u>
	L-1	147°	<u>  /  </u>
	L-15	23°	<u>  /  </u>
	R-11	67°	<u>  /  </u>
4.10	Prerequisites and Initial Conditions (3.6) for this subsection have been completed. (see Attachment 1, Item 2)	<u>  /  </u>	
4.10.18	Operational Pass 1	<u>  /  </u>	
	2	<u>  /  </u>	

TST JAS  
7/6/40

DATA SHEET 2  
VESSEL DISASSEMBLY COMPLETION SHEET

<u>STEP</u>	<u>DESCRIPTION</u>	<u>SIGN-OFF</u>	<u>Q.C. VERIFICATION</u>
4.11.19	All 54 studs removed from the vessel in racks with the head and all stud hole plugs installed except 12, 28, 44 and 30 if applicable.	_____ / _____	
4.11.23	Guide studs installed in holes 12, 28, 44 and 30 if applicable.	_____ / _____	
4.13.1.4	Emergency Containment Spray drains installed,		
	North	_____ / _____	
	South	_____ / _____	
4.13.2.3	Reactor cavity ventilation opening cover plates installed		
	Approximate Azimuth		
	22°	_____ / _____	
	67°	_____ / _____	
	112°	_____ / _____	
	157°	_____ / _____	
	202°	_____ / _____	
	247°	_____ / _____	
	292°	_____ / _____	
	337°	_____ / _____	
4.13.3.4	IEI Ports installed		
	Approximate Azimuth		
	0°	_____ / _____	
	45°	_____ / _____	
	90°	_____ / _____	
	135°	_____ / _____	
	180°	_____ / _____	
	225°	_____ / _____	
	270°	_____ / _____	
	315°	_____ / _____	
4.13.4.1	Reactor Vessel permanent cavity seal has been visually checked	_____ / _____	
4.13.5	Reactor cavity sealing complete	_____ / _____	

## DATA SHEET 2

## VESSEL DISASSEMBLY COMPLETION SHEET

<u>STEP</u>	<u>DESCRIPTION</u>	<u>SIGN-OFF</u>	<u>Q.C. VERIFICATION</u>
4.14.1	An "as found" Seal Integrity Test has been performed.	/	
4.14.5	Transfer tube blind flange prepared for refueling	/	
4.15.3	Preparation for cavity flooding complete	/	
4.16	Equipment (3.3) for this section have been checked out and are available for use (see Attachment 1, Item 4)	/	
4.16.7	Ten minute hold for visual checks of rigging completed	/	
4.16.14	Reactor Vessel Head is removed and stored	/	
4.17	RCCA drive shafts unlatched	/	
4.18	Equipment (3.3) for this section have been checked out and are available for use	/	
4.18.1	Optional internals measurements.		
	Location _____ Value _____	/	
	Location _____ Value _____	/	
	Location _____ Value _____	/	
4.18.9	Ten minute hold for visual check of rigging completed	/	
4.18.12	Upper Internals removed and stored	/	



Remarks:

---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---

The Reactor Vessel is ready for refueling operations to begin.

MAINTENANCE FOREMAN \_\_\_\_\_ / DATE

REVIEWED BY: \_\_\_\_\_ OUTAGE AREA SUPERVISOR \_\_\_\_\_ / DATE

DATA SHEET 3  
VESSEL ASSEMBLY COMPLETION SHEET

NOTE

Place an N/A in the SIGN-OFF space for those sections not applicable and note in the remarks section the reason for the N/A.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>SIGN-OFF</u>	<u>Q.C. VERIFICATION</u>
4.19	The vessel is ready for reassembly and work is ready to commence, (3.1, 3.2, 3.3 3.4) complete (see Attachment 1, Item 5)	/	/
4.19.3	Ten minute hold for visual check of rigging completed	/	
4.19.6	Upper Internals installed in the RV	/	
4.19.10	The lift rig is stored on stand	/	
4.19.12	Optional internals measurements:  Location _____ value _____ Location _____ value _____ Location _____ value _____	/	
4.19.13	Outage Area Supervisor Evaluation:  Acceptable/Not Acceptable	/	
4.20	RCCA drive shafts latched	/	
4.21	Equipment (3.7) for this section have been checked out and are available for use (see Attachment 1, Item 4)	/	

DATA SHEET 3

VESSEL ASSEMBLY COMPLETION SHEET

<u>STEP</u>	<u>DESCRIPTION</u>	<u>SIGN-OFF</u>	<u>Q.C. VERIFICATION</u>
4.21.11	Vessel O-rings are installed in head	/	
4.21.18	Ten minute hold for visual check of rigging completed	/	
4.21.24	Head is seated on vessel	/	
4.23.2	Transfer tube mating surfaces checked for cleanliness.	/	/
4.23.6	Transfer tube blind flange installed	/	/
	Torque Wrench M&TE No. _____		
	Calibration good until _____		
4.24	Applicable tools and equipment (4.1 <sup>2</sup> ) for this section have been checked out and are available for use (see Attachment 1, Item 3)	/	
4.24.1.4	From Step 4.16.7: Ten minute hold for visual checks of rigging completed	/	
4.24.1.16 or 4.24.2.2	Guide studs and sleeves removed	/	
4.24.1.18 or 4.24.2.3	All stud hole plugs have been removed	/	
4.24.3.4.12	All studs have been installed in the vessel	/	

DATA SHEET 3

VESSEL ASSEMBLY COMPLETION SHEET

<u>STEP</u>	<u>DESCRIPTION</u>	<u>SIGN-OFF</u>	<u>Q.C. VERIFICATION</u>
4.25	All applicable tools and equipment for this section (3.6) have been checked out and are available for use (see Attachment 1, Item 3)  Temperature conditions have been met.	____/____	____/____
4.25.3	Initial stud elongation measurements have been recorded	____/____	____/____
4.25.18	Stud Tensioning passes complete 1st pass 2nd pass 3rd pass (hydro only)	____/____ ____/____ ____/____	____/____
4.25.23	All studs have been tensioned to the required elongations	____/____	____/____
4.26	The seal table is ready for system filling	____/____	____/____
4.27	All applicable conditions, tools, and equipment for this section (3.8) have been checked out and are available for use (see Attachment 1, Item 2)	____/____	____/____

## DATA SHEET 3

## VESSEL ASSEMBLY COMPLETION SHEET

<u>STEP</u>	<u>DESCRIPTION</u>	<u>SIGN-OFF</u>	<u>Q.C. VERIFICATION</u>
4.27.23	Instrument port conoseals assembled		
	Core Location	Approximate Azimuth	
	A-5	247°	<u>          /          </u>
	L-1	147°	<u>          /          </u>
	L-15	23°	<u>          /          </u>
	R-11	67°	<u>          /          </u>
	Torque wrench		
	ft-lbs M&TE No. _____	Calib. good until _____	
	in-lbs M&TE No. _____	Calib. good until _____	
	Pump Gauge M&TE No. _____	Calib. good until _____	
4.28.1	Emergency containment spray drain blank flanges removed and stored. Screen replaced in drain		
	North	<u>          /          </u>	<u>          /          </u>
	South	<u>          /          </u>	<u>          /          </u>
4.28.2	All eight reactor vessel vent plates installed in the vent position.	<u>          /          </u>	
4.29.2	RV head vent spool piece installed	<u>          /          </u>	
4.30	RVLIS interconnect installed	<u>          /          </u>	
4.31.2	Reactor Head insulation installed	<u>          /          </u>	
4.33.6	Cable tray latch down and all cable reconnected	<u>          /          </u>	
4.34	Applicable tools and equipment for this section have been checked out and are available for use (See Attachment 1 Item 1).	<u>          /          </u>	





DATA SHEET 4

POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

NOTES

- a. Ensure that each cable/wire is marked so it can be uniquely identified with its termination point.
- b. Original Data Sheet 5 should be included with the vessel disassembly package. A copy of the original will be used to sign off reconnects and be included in the assembly package.
- c. Independent Verification is only required on Safety-Related equipment. Place N/A in that column for Non-Safety related equipment.
- d. Panel Azimuth are as follows:  
 Unit 1: A-0°      B-180°  
 Unit 2: A-180°    B-0°

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	VERIFICATION INDEPENDENT
A	CRDM	C-K6			N/A
		C-K10			N/A
		D-M12			N/A
		D-M4			N/A
		C-P8			N/A
		Unit 1    Unit 2			
		C-H2      C-H14			N/A
		SB-N9			N/A
		SB-N7			N/A
		B-K14			N/A
		B-K2			N/A
		Unit 1    Unit 2			
		SB-J3      SB-J13			N/A

DATA SHEET 4

POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION		
A	CRDM	Unit 1	Unit 2				
		SB-G3	SB-G13		N/A		
			SE-M8			N/A	
			Unit 1	Unit 2			
			SE-H4	SE-H12		N/A	
			B-F10			N/A	
			B-P6			N/A	
			SA-M14			N/A	
			SA-M2			N/A	
			SD-N11			N/A	
			SD-L3			N/A	
			A-K8			N/A	
			Unit 1	Unit 2			
			A-H6	A-H10		N/A	
			SA-P12			N/A	
			SA-P4			N/A	
			SC-L13			N/A	
			SC-N5			N/A	
			DPRI	D-H8-B			N/A
			DMIMS	Unit 1	Unit 2		
	MIM-1	MIM-3			N/A		
	DPRI	SE-D8-B			N/A		
		SE-M8-B			N/A		
		SE-H12-B			N/A		
		SE-H4-B			N/A		
		D-D12-B			N/A		

## DATA SHEET 4

## POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
A	DPRI	D-D4-B			N/A
		C-F10-B			N/A
		C-F6-B			N/A
		C-K10-B			N/A
		C-K6-B			N/A
		SD-E13-B			N/A
		SD-N11-B			N/A
		SB-G13-B			N/A
		SB-G3-B			N/A
		SB-N9-B			N/A
		SB-N7-B			N/A
		D-M12-B			N/A
		D-M4-B			N/A
		C-H14-B			N/A
		C-H2-B			N/A
		C-P8-B			N/A
		C-B8-B			N/A
		SD-L3-B			N/A
		SD-C5-B			N/A
		SB-J13-B			N/A
		SB-J3-B			N/A

## DATA SHEET 4

## POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
A	DPRI	SB-C9-B			N/A
		SB-C7-B			N/A
		A-H10-B			N/A
		A-H6-B			N/A
		B-F14-B			N/A
		B-F2-B			N/A
		B-P10-B			N/A
		B-P6-B			N/A
		SC-L13-B			N/A
		SC-C11-B			N/A
		SA-D14-B			N/A
		SA-D2-B			N/A
		SA-P12-B			N/A
		SA-P4-B			N/A
		A-K8-B			N/A
		A-F8-B			N/A
		B-K14-B			N/A
		B-K2-B			N/A
		B-B6-B			N/A
		B-B10-B			N/A
		SC-E3-B			N/A
		SC-N5-B			N/A



## DATA SHEET 4

## POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
A	DPRI	SA-M14-B			N/A
		SA-M2-B			N/A
		SA-B12-B			N/A
		SA-B4-B			N/A
	CRDM	C-F6			N/A
		C-F10			N/A
		D-D12			N/A
		D-D4			N/A
		C-B8			N/A
		Unit 1 Unit 2			N/A
		C-H14 C-H2			N/A
		SB-C9			N/A
		SB-C7			N/A
		D-H8			N/A
		B-F14			N/A
		B-F2			N/A
		Unit 1 Unit 2			N/A
		SB-J13 SB-J3			N/A
		Unit 1 Unit 2			N/A
		SB-G13 SB-G3			N/A
		Unit 1 Unit 2			N/A
		SE-H12 SE-H4			N/A
		SE-D8			N/A
		B-B10			N/A
		B-B6			N/A

DATA SHEET 4 -

POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
A	CRDM	SA-D14			N/A
		SA-D2			N/A
		SD-E13			N/A
		SD-C5			N/A
		Unit 1    Unit 2			
		A-H10    A-H6			N/A
		A-F8			N/A
		SA-B12			N/A
		SA-B4			N/A
		SC-C11			N/A
		SC-E3			N/A
	Aux Pwr	Aux Pwr			N/A
	Cooling Fan Pwr	CF-4			N/A
		CF-3			N/A
		CF-2			N/A
		CF-1			N/A
	Thermo Couples	T-1-78A			
		T-27-78A			
		T-4-78A			
		T-29-78A			
		T-31-78A			
		T-32-78A			
		T-41-75A			

## DATA SHEET 4

## POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
A	Thermo Couples	T-45-75A			
		T-20-76A			
		T-44-76A			
		T-43-76A			
		T-47-76A			
		T-48-76A			
		T-49-76A			
		T-5-75A			
		T-33-75A			
		T-30-75A			
		T-38-75A			
		T-7-77A			
		T-15-77A			
		T-13-77A			
		T-35-77A			
		T-39-77A			
		T-42-77A			
		T-46-77A			

## DATA SHEET 4

## POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

## NOTES

- a. Ensure that each cable/wire is marked so it can be uniquely identified with its termination point.
- b. Original Data Sheet 4 should be included with the vessel disassembly package. A copy of the original will be used to sign off reconnects and be included in the assembly package.
- c. Independent Verification is only required on Safety-Related equipment. Place N/A in that column for Non-Safety related equipment.
- d. Panel Azimuth are as follows:  
 Unit 1: A-0° B-180°  
 Unit 2: A-180° B-0°

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
B	DMIMS	MIM-1 (Unit 2 ONLY)			N/A
		MIM-2			N/A
		MIM-3 (Unit 2 ONLY)			N/A
		Ground			N/A
	Thermo couples	T-2-78B			
		T-6-78B			
		T-3-78B			
		T-8-78B			
		T-26-78B			
		T-28-78B			
		T-34-77B			
		T-40-77B			

787 1/2  
2/6/90

Sheet 9 of 14

## DATA SHEET 4 -

## POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
B	Thermo Couples	T-18-76B			
		T-22-76B			
		T-19-76B			
		T-23-76B			
		T-24-76B			
		T-25-76B			
		T-50-76B			
		T-10-77B			
		T-16-77B			
		T-14-77B			
		T-21-77B			
		T-9-75B			
		T-12-75B			
		T-11-75B			
		T-17-75B			
		T-36-75B			
		T-37-75B			
	Cooling Fans	CFH-1			N/A
		CFH-2			N/A
		CFH-3			N/A
		CFH-4			N/A
		CFI-1 (Unit 2 ONLY)			N/A
		CFI-2 (Unit 2 ONLY)			N/A
		CFI-3 (Unit 2 ONLY)			N/A



## DATA SHEET 4 -

## POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
B	COOLING FANS	CFI-4 (Unit 2 ONLY)			N/A
	DPRI	D-H8-A			N/A
		SE-D8-A			N/A
		SE-M8-A			N/A
		SE-H12-A			N/A
		SE-H4-A			N/A
		D-D12-A			N/A
		D-D4-A			N/A
		C-F10-A			N/A
		C-F6-A			N/A
		C-K10-A			N/A
		C-K6-A			N/A
		SD-E13-A			N/A
		SD-N11-A			N/A
		SB-G13-A			N/A
		SB-G3-A			N/A
		SB-N9-A			N/A
		SB-N7-A			N/A

## DATA SHEET 4

## POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
B	DPRI	D-M12-A			N/A
		D-M4-A			N/A
		C-H14-A			N/A
		C-H2-A			N/A
		C-P8-A			N/A
		C-B8-A			N/A
		SD-L3-A			N/A
		SD-C5-A			N/A
		SB-J13-A			N/A
		SB-J3-A			N/A
		SB-C9-A			N/A
		SB-C7-A			N/A
		A-H10-A			N/A
		A-H6-A			N/A
		B-F14-A			N/A
		B-F2-A			N/A
		B-P10-A			N/A
		B-P6-A			N/A
		SC-L13-A			N/A
		SC-C11-A			N/A
		SA-D14-A			N/A

DATA SHEET 4

POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
B	DPRI	SA-D2-A			N/A
		SA-P12-A			N/A
		SA-P4-A			N/A
		A-K8-A			N/A
		A-F8-A			N/A
		B-K14-A			N/A
		B-K2-A			N/A
		B-B6-A			N/A
		B-B10-A			N/A
		SC-E3-A			N/A
		SC-N5-A			N/A
		SA-M14-A			N/A
		SA-M2-A			N/A
		SA-B12-A			N/A
		SA-B4-A			N/A
<b>Thermocouple</b>					
Column	Thermo				
L-15	Couple	T-5-75A	(C-12)		
		T-9-75B	(E-14)		
		T-11-75B	(G-8)		
		T-12-75B	(G-12)		
		T-17-75B	(J-14)		

## DATA SHEET 4 -

## POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
Thermocouple Column L-15	Thermo Couple	T-30-75A (C-14)			
		T-33-75A (E-12)			
		T-36-75B (G-10)			
		T-37-75B (G-14)			
		T-38-75A (H-15)			
		T-41-75A (J-12)			
		T-45-75A (L-14)			
R-11		T-18-76B (L-4)			
		T-19-76B (L-8)			
		T-20-76A (L-12)			
		T-22-76B (N-6)			
		T-23-76B (N-10)			
		T-24-76B (N-14)			
		T-25-76B (R-8)			
		T-43-76A (L-6)			
		T-44-76A (L-10)			
		T-47-76A (N-8)			
		T-48-76A (N-12)			
		T-49-76A (R-6)			
		T-50-76B (R-10)			
L-1		T-7-77A (E-6)			
		T-10-77B (G-4)			

TEST DPZ  
3/6/90

Sheet 14 of 14

## DATA SHEET 4

## POWER AND SIGNAL CABLE REMOVAL/REPLACEMENT

PANEL	TYPE	IDENTIFICATION	REMOVED	RECONNECT	INDEPENDENT VERIFICATION
Thermocouple Column L-1	Thermo Couple	T-13-77A (H-1)			
		T-14-77B (J-2)			
		T-15-77A (J-6)			
		T-16-77B (J-10)			
		T-21-77B (N-2)			
		T-34-77B (G-2)			
		T-35-77A (G-6)			
		T-39-77A (J-4)			
		T-40-77B (J-8)			
		T-42-77A (L-2)			
		T-46-77A (N-4)			
A-5		T-1-78A (A-6)			
		T-2-78B (A-10)			
		T-3-78B (C-4)			
		T-4-78A (C-8)			
		T-6-78B (E-2)			
		T-8-78B (E-10)			
		T-26-78B (A-8)			
		T-27-78A (C-2)			
		T-28-78B (C-5)			
		T-29-78A (C-10)			
		T-31-78A (E-4)			
		T-32-78A (E-8)			



## ATTACHMENT 1

## TOOLS AND EQUIPMENT LIST

The following tools and equipment should be available, properly functioning, clean and ready to use.

1. SEISMIC TIE RODS, HEAT VENT PIPING, AND UPPER INTERNALS
  - a. Nylon Straps, one-ton capacity
  - b. Polar Crane or appropriate Lifting Device
  - c. Approved Duct Tape
2. INSTRUMENT PORT-CONOSEAL
  - a. Instrument Column Protective Sleeves (4)
  - b. Instrument Column Protective Sleeve O-rings (4)
  - c. Protective Sleeve Holding Springs (4)
  - d. Instrument Column Upper Conoseal Gaskets (4)
  - e. Instrument Column Lower Conoseal Gaskets (4)
  - f. Conoseal Gasket Removal Tool
  - g. 0-150 Inch-Pound Torque Wrench (3/8" Drive)
  - h. 5/8" Allen - Socket Wrench
  - i. 0-150 Foot-Pounds Torque Wrench (1/2" Drive)
  - j. 5/16" Allen - Socket Wrench
  - k. Supply of Neolube (Nuclear Grade)
  - l. Axial Loading Ram Assembly
  - m. Hydraulic Pump with Cylinder
  - n. 0-2,000 psi (minimum) calibrated gauge
  - o. Cotter Pins
  - p. Safety Wire

## ATTACHMENT 1 (CONT'D.)

3. REACTOR VESSEL STUD
- a. Alignment Guide Pins (3)
  - b. Eye-bolts (3)
  - c. Guide Stud Turning Bar
  - d. Stud Lifting Eyes (54)
  - e. Measuring Rods (54)
  - f. Depth Dial Indicator (Starrett #644J or equivalent)
  - g. Nut Wrench Assembly
  - h. Stud Wrench
  - i. Stud Hole Plugs (51)
  - j. Protective Sleeves (12)
  - k. Chalk
  - l. Stud Tensioners (6)
  - m. Five sets of 12' Tensioner Hose (5 hoses per set)
  - n. One set of 35' Tensioner Hose (5 hoses per set)
  - o. One - six foot Air Signal Hose
  - p. Pyrometer (IMC type or equivalent)
  - q. Polar Crane
  - r. Stud Racks (6)
  - s. 50' sections of 1" Air Hose (3 minimum)
  - t. RV Stud Removal Tools (6)
  - u. Chain Fall, 1 ton capacity minimum.
4. Reactor Vessel Head
- a. Load Cell
  - b. Polar Crane

## ATTACHMENT 1 (CONT'D.)

- c. Bubble Levels (3)
  - d. Metal O-Ring (outer)
  - e. Metal O-Ring (inner)
  - f. Allen type wrench set
  - g. Bolt Cutters
5. GENERAL USAGE
- a. Lint-free rags
  - b. Isopropyl Alcohol (stainless steel surfaces)
  - c. Ethyl Alcohol (carbon steel surfaces)
  - d. Acetone (carbon and stainless surfaces)
  - e. Approved Bags for material collection and disposal
  - f. Nuclear grade Neolube, #1 or # 2
  - g. Fel-Pro N5000
  - h. GE Versilube 392.
  - i. Never-Seez pure nickel special

ORIGINAL

05-317-90

SECTION XI REPAIR / REPLACEMENT TRAVELER

Traveler: 90117 Rev. 0	Repair <input type="checkbox"/> Replacement <input checked="" type="checkbox"/>
Associated Documents	Component
MWO: 18905286	Code Class: ASME I
DC: _____	Tag. No: H208-U6-036
DCP: _____	Description: check valve
Other: _____	Serial No: _____

Work Description: Replace eight studs and nuts.

Examination / Test Requirements

VT-1  VT-2  VT-3  VT-4  Other

Nominal Operating Pressure  Pneumatic  Hydrostatic  
none other than

Pressure \_\_\_\_\_ Temperature: \_\_\_\_\_ Hold Time: UTNUP + NOT

Evaluation of Suitability (IWA 7220) \_\_\_\_\_

Design/Construction Code Reconciliation \_\_\_\_\_

Repair / Replacement Organization GPC Maintenance

INITIAL REVIEW

	Signature	Date	Hold Points
Maintenance Engineering	<i>[Signature]</i>	3-20-90	Yes <input type="checkbox"/> None <input checked="" type="checkbox"/>
Quality Control	<i>[Signature]</i>	3/20/90	Yes <input checked="" type="checkbox"/> None <input type="checkbox"/>
ANII	<i>[Signature]</i>	3-20-90	Yes <input type="checkbox"/> None <input checked="" type="checkbox"/>

*[Signature]* 3-20-90

FINAL REVIEW

	Signature	Date
Maintenance Engineering	_____	_____
ISI	_____	_____
Quality Control	_____	_____
ANII	_____	_____

Remarks: \_\_\_\_\_







**ORIGINAL**

ASME TEST VERIFICATION FORM

TVF No. 90017 MWD No. 18905285 Traveler No. N/A

Tag/ Weld No. 1-1208-46-036

Item Description: 3" check valve with seal cap

Description of Work: Dissassemble and reassemble class one valve. Weld on seal cap.

QC Initial Review Edward A. Szymon 3/19/90 ANII Initial Review 2/2 Valladares 3/19/90

Required NDE/Testing		Q.C.		ANII	
TEST	ENTRY/ACCEPTABLE CRITERIA	A/R	REPORT #	W/H	A/R
ASME VT-1, 2, 3, 4	VT-2	A	N/A #40		
SURFACE EXAM. VT, PT, MT	VT, PT N/A 3-19-90	A	* #34/7/90		
VOLUMETRIC EXAM. UT, RT	N/A				
OTHER	N/A				

REMARKS: \* SEE TRAVELER # 90-49 FOR THIS INSPECTION 3/17/90

Maintenance Engineering James Woods Date 4/18/90

ANII \_\_\_\_\_ Date 1/1

SECTION XI REPAIR / REPLACEMENT TRAVELER

ORIGINAL

Traveler: 12102 Rev. \_\_\_\_\_

Repair  Replacement

----- Associated Documents -----

----- Component -----

MWO: 12102

Code Class: Hand

DC: \_\_\_\_\_

Tag. No: 12102

DCP: N/A

Description: Hand

Other: N/A

Serial No: 02000000000000000000

Work Description: Adjust alignment during overhaul

----- Examination / Test Requirements -----

N/A

\_\_\_ VT-1 \_\_\_ VT-2 \_\_\_ VT-3 \_\_\_ VT-4 Other \_\_\_\_\_

\_\_\_ Nominal Operating Pressure \_\_\_ Pneumatic \_\_\_ Hydrostatic

Pressure \_\_\_\_\_ Temperature: \_\_\_\_\_ Hold Time: \_\_\_\_\_

Evaluation of Suitability (IWA 7220) N/A

Design/Construction Code Reconciliation N/A

Repair / Replacement Organization Aviation Maintenance Corp

----- INITIAL REVIEW -----

	Signature	Date	Hold Points
Maintenance Engineering	<u>[Signature]</u>	<u>02/22/90</u>	Yes <input type="checkbox"/> None <input checked="" type="checkbox"/>
Quality Control	<u>[Signature]</u>	<u>3/01/90</u>	Yes <input checked="" type="checkbox"/> None <input type="checkbox"/>
ANII	<u>[Signature]</u>	<u>3-22-90</u>	Yes <input type="checkbox"/> None <input checked="" type="checkbox"/>

----- FINAL REVIEW -----

	Signature	Date
Maintenance Engineering	<u>[Signature]</u>	<u>4-18-90</u>
ISI	_____	_____
Quality Control	<u>[Signature]</u>	<u>4/12/90</u>
ANII	_____	_____

Remarks: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_







DEFICIENCY CARD

CARD #	1-90-209		UNIT 1 (x)	UNIT 2 ( )	COMMON ( )	
1:	DESCRIPTION OF DEFICIENCY	(ADDITIONAL SHEETS ATTACHED? YES NO)				
COMPLETED BY INITIATOR	Refer to MW0 18905286 Value 1-1208-46-036					
	Tracability of Material is subterfuge due to					
	MEX 90-5017 calls out studs for P.O 89-7001508 issued,					
	yet all of the studs per P.O 89-7001508 are still in the warehouse location D-69-M					
	LOCATION OF THE DEFICIENCY?	Material Tracability				
	WHAT IS AFFECTED BY THE DEFICIENCY?	Material				
	HOW WAS THE DEFICIENCY DISCOVERED?	During QC Review of MW0				
	EVENT TIME	10:51 <sup>CS</sup>	DATE	4/6/90	DISCOVERY TIME	
					10:51 <sup>CT</sup>	
	DISCOVERED BY?	ALAN A SIMMONS		WORK #	3349	
				DEPT.	D. C	
COMPLETED BY SS WITHIN 2 HOURS	2:	SHIFT SUPERVISOR REVIEW				
		NAME OF SS REPORTED TO?	TIME	DATE		
		PLANT MODE/CONDITION:				
		IS IMMEDIATE NOTIFICATION REQUIRED?	YES	NO		
		IF YES, 1 HOUR, 2 HOUR, OR 24 HOUR	REPORTED DATE		TIME	
		TECH SPEC REQUIRED ACTION TAKEN?	YES	NO	NA	
		LIST APPLICABLE TECH SPEC SECTION(S)				
		SUMMARIZE COMPENSATORY ACTION TAKEN:				
		LCO INITIATED: NO	YES #	TYPE: INFO	LCO	FIRE
		WRT INITIATED: NO	YES #			
	SIGNATURE OF SS	TIME	DATE			

MWO/OTHER # <i>18905286</i>	INSP PROCEDURE # 85060-C	REV # <i>3</i>	DRAWING # <i>1X4A3111</i>	REV # <i>17</i>
--------------------------------	-----------------------------	-------------------	------------------------------	--------------------

LINE/EQUIP # <i>1-1208-06-036</i>	TEST CODE: ASME Section XI <input checked="" type="checkbox"/> ANSI B31.1 <input type="checkbox"/> OTHER _____
--------------------------------------	---

TYPE OF TEST:

System Leakage       System Inservice       System Pneumatic   
 System Functional       System Hydrostatic       Other \_\_\_\_\_

COMPONENT OR SYSTEM:

Insulated       Non-Insulated

TEST CONDITIONS: (Complete as applicable)

Required NOP  NOT       Verified NOP  NOT   
 Required \_\_\_\_\_ PSIG      Verified \_\_\_\_\_ PSIG  
 Required \_\_\_\_\_ F      Verified \_\_\_\_\_ F

TEST CONDITION VERIFIED BY:

Examiner   
 Other  Name *GEORGE CUNN* Time *1505 CD*  
*7:05*

TEST INSTRUMENTATION:

INSTRUMENT # <u><i>N/A</i></u>	Cal. Due Date <u>  /  /  </u>
INSTRUMENT # <u><i>N/A</i></u>	Cal. Due Date <u>  /  /  </u>
INSTRUMENT # <u><i>N/A</i></u>	Cal. Due Date <u>  /  /  </u>

\* Cal. Data Not Required Except For hydrostatic & Pneumatic Tests

TEST RESULTS:

SAT.       UNSAT.       DC # \_\_\_\_\_

DESCRIPTION OF DEFICIENCY IF UNSAT: *NOVC*

---



---



---

VISUAL EQUIPMENT USED: *FLUORESCENT INSPECTION MIRROR*

---



---

REMARKS:

---



---



---

EXAMINER: <u><i>Rob E. [Signature]</i></u>	LEVEL: <u><i>II</i></u>	DATE: <u><i>4/16/90</i></u>
EVALUATOR:	N/A <input checked="" type="checkbox"/>	LEVEL:      DATE:
ANII REVIEW:	N/A <input type="checkbox"/>	DATE:

## ANTI/ISI TEST VERIFICATION FORM

MWO NO. 1990-5286 <sup>REV. 1st</sup> 8/21/89      Traveler No. NH      Rev. \_\_\_\_\_      Date 8-7-89

Description of Test/work performed: DISASSEMBLY AND INSPECTION OF VALVES 1-1208-V-6-035 AND C36-VT-3 INSPECTION REQD. AFTER REASSEMBLY (CLASS 1)

ANTI-REVIEW

*[Signature]*  
8-7-89

Prepared by: Z. N. CALDWAY      Date 8-7-89      Maint. Eng. Review [Signature]      Date 8-27-89      ISI Review [Signature]      Date 8-17-89

Results of Test      Accept       Reject       Date \_\_\_\_\_

IF Rejected:

Proposed Retest: NI

Supporting Document: \_\_\_\_\_

Review of Test Results

Maint. Eng. [Signature]      Date 4-23-90

ARI \_\_\_\_\_      Date \_\_\_\_\_


ISI \_\_\_\_\_      Date \_\_\_\_\_

Remarks: \* VALVE 1-1208-V-6-035 WAS NOT DISASSEMBLED IN 4-23-90

Quality Control Inspection Report

VOGTLE GENERATING PLANT—UNITS 1 & 2

34083

Georgia Power 

Page 1 of 2


MWO/ODR/DR No. <u>18905286</u>	Building <u>CTMT</u>	Procedure/Spec. No./Rev. <u>26621-C R/1</u>
Room No./Level No. <u>C</u>	Sys./Start-Up Designator <u>1208</u>	Tag No. <u>1-1208-46-036</u>
Drawing No./Rev. <u>N/A</u>	Vendor Manual Log No. <u>N/A</u>	Other <u>N/A</u>

- Inspector will use separate form for each completed inspection function(s) and insert original with work package, use continuation sheets when needed.
- Use simple narrative type report procedure. Reference all applicable drawing numbers, specifications, special instructions, etc., connected with your inspection. Use sketches, when applicable, showing dimensions checked, alignment, physical location of defects found, etc. N/A all blocks not used.
- Upon completion of the inspection activity, enter results below and sign and date.

Remarks

VISUALLY VERIFY PROCEDURE STEPS 4.3.1, 4.3.2, 4.3.3, 4.4.1, 4.4.2F, 4.4.3, 4.4.12 - INTERNAL VALVE INSPECTIONS & STUD AND BONNET TORQUE. VERIFIED & REPLACEMENT STUDS & GASKET MATERIAL BOTH ON MER# 5017. THESE ITEMS ARE ACCEPTABLE.

VISUAL EXAM ON BODY EXTERNAL SURFACE @ SEAL WELD REMOVAL AREA REVEALED A GRINDING GROOVE APPROX. 3/32" TO 1/8" IN DEPTH APPROX 200° AROUND BODY, WIDTH OF GROOVE APPROX 1/8"



Inspection Results

SAT  UNSAT—ODR/DR NO.(S): 18905286

Inspector Andrew K. P... Date 3/22/90




IR# 34083

Page 2 of 2

MWD/ORD No./Other  
MWO 18905286

Remarks #2  
CONTINUOUS GROOVE ON BACKSIDE  
FOR 20' APPROX SAME DIMENSIONS AS #1

#1  
CONTINUOUS GROOVE  
150' APPROX 1/2 TO  
3/32" IN WIDTH & DEPTH



VIEW FACING WALL

Inspector *And K Pen*

Date 3/22/90



Liquid Penetrant Inspection Report

MWO 18965286

Plant/Site/Project <i>VOGTLE / UNIT 1</i>			
Procedure No. <i>85062-C</i>	Rev. <i>0</i>	Drawing No. <i>N/A</i>	Rev. <i>N/A</i>
Part No. <i>1-1208-46-036 CHECK VALV</i>		Surface Condition <i>AS GROUND</i>	
Pre-Clean (Method): <i>SOLVENT WIPE</i>			
Penetrant (Brand): <i>MAGNAFLUX SKL-HF/S</i>		Batch No. <i>81A045</i>	
Penetrant Removal (Brand): <i>MAGNAFLUX SKL-S</i>		Batch No. <i>89F04K</i>	
Emulsifier (Brand): <i>N/A</i>		Batch No. <i>N/A</i>	
Developer (Brand): <i>MAGNAFLUX S1.0-NF/ZP-913</i>		Batch No. <i>8814043</i>	
Interpretation	Accept <input checked="" type="checkbox"/>	Reject <input type="checkbox"/>	Repairs
	<i>N/A</i>	<i>N/A</i>	<i>N/A</i>
			See Report No. <i>L.P. 1682</i>
Remarks <i>PERFORMED LIQUID PENETRANT TEST ON SEAL WELD REMOVAL AREAS ON BONNET AND BODY NOT COVERED ON PREVIOUS L.P.T. OF WELD REPAIR. REF. L.P. INSPECTION REPORT # 1682 DATED 3/22/90</i>			
Sketch: <i>N/A</i>			
NDE Signature <i>Andrew K. Poon</i>		Level <i>II</i>	Date <i>3/22/90</i>
Inspection Supervisor		Section	Date
Document Control			Date

Liquid Penetrant Inspection Report

M.W.O. 18905286


Plant/Site/Project VOGTLE / UNIT 1			
Procedure No. 85062-C	Rev. 0	Drawing No. N/A	Rev. N/A
Part No. 1-1208-126-036 CHECK VALVE		Surface Condition AS GROUND ; AS WELDED	
Pre-Clean (Method): SOLVENT WIPE			
Penetrant (Brand): MAGNAFLUX SKL-HF/S		Batch No. 87A045	
Penetrant Removal (Brand): MAGNAFLUX SKC-S		Batch No. 89F04K	
Emulsifier (Brand): N/A		Batch No. N/A	
Developer (Brand): MAGNAFLUX SKD-NF/ZP-9B		Batch No. 88H043	
Interpretation Accept		Repairs See ② Below ✓ CCG Reject 3-22-90	See Report No. N/A

Remarks

① PERFORMED L.P.T. OF THE GROOVE AREA PRIOR TO WELDING NO DISCREPANCIES NOTED.

② PERFORMED L.P.T. OF THE REPAIR AFTER WELDING & GRINDING. 3/8" LINEAR INDICATION NOTED.

③ RE-PERFORMED L.P.T. AFTER LIGHT GRINDING AND BUFFING. NO DISCREPANCIES NOTED.



NDE Signature <i>Christopher C. [Signature]</i>	Level II	Date 3-22-90
Inspection Supervisor	Section	Date
Document Control		Date

Nuclear Plant Maintenance Work Order Continuation Sheet

MPL No. 1120846036 MWO No. 18905286

Work Description Block 27 CONTINUED

VALVE 1-1208-46-036 FORGED. WAITED ONE  
HOUR AND RE-FORGED AT 170 FT. LBS.

TORQUE WRENCH UP 3-2075 CAL. DUE DATE  
7/3/90. Q.C. INSPECTED

JH 3/22/90

REMOVED SEAL CAP TO WAREHOUSE FROM MER 90-05016.

ME 3/26/90

Vogtle Electric Generating Plant  
Nuclear Plant Maintenance Work Order Continuation Sheet

MPL No. 1-1208-06-056

MWO No. 18906286

Work Description Block # 27 Can't

Blended out area on valve 1-1208-06-056 for  
P.T. After surface P.T. was sold, weld was made on  
body of valve using ER 308L  $\frac{1}{8}$ " HT. # P0443  
and welded area was prepared for final P.T.  
Mentioned some III housekeeping. MPP 3/22/90

## Nuclear Plant Maintenance Work Order Continuation Sheet

MPL No. 1120846036

MWO No. 18905286

Work Description Block 27 CONTINUED

ALL tools needed to disassemble valve 1-1208-46-036 ARE ON PLATFORM DIRECTLY IN FRONT OF VALVE. THE BACKSIDE OF VALVE NEXT TO CONCRETE WALL HAS BEEN ground out on bottom side. The front side bottom half AND CENTER WELD ARE LEFT TO GRIND. Scaffold in front needed to be modified and CARPENTERS HAVE COMPLETED THIS. FIRE EXTINGUISHER IS ALSO ON PLATFORM. GEORGE BROWN IS THERE FOR A HANDS ON TURN OVER. CLASS III CLEANLINESS. ZONE TO HOUSEKEEPING

Tommy Titani

JH 3/19/90

Block 27 continued

GRIND OUT FRONT OF VALVE 1-1208-46-036 ALSO INSIDE CAP ON VALVE. REMOVED CAP BEGGED AND TOOK TO DEACON. TOOK <sup>measurement of 5.10-90</sup> measurement of bonnett nut 1 1/16". HAD ABOUT A QUART OF WATER OVER CAP. LEFT ALL TOOL & FIRE EXTINGUISHER AND WORK AREA ON PLATFORM. CLASS III CLEANLINESS. ZONE III - HOUSEKEEPING.

Peter Ciccio 3/20/90



MWO No. 1890328C

MPL No. 1-1208-46-036

Work Description: Block 27 Gasket, Replaced Cap and Patents

DATE: 3/20/90

BY: J. J. ...

FROM: 1208-46-036, 1208-46-036, 1208-46-036

REMOVED FROM 110 FT. TO 135 FT. TB, THERE'S A DRAWING

AT THE BOTTOM PATTERN WITH THE SPECS FOR EACH PART IN A

PLASTIC BAG ON THE PLATFORM, FLANGE AND OTHER PARTS

ARE IN BAGS ON THE VALUE, THE VALUE HAS BEEN CLEANED

AND THE THERMOS CHANGED WITH ATRD, HEIGHT OF THE OLD

STUDS WERE MEASURED BEFORE REMOVAL, LENGTH WAS 2 1/2"

USED SCREW WRENCH U.P. 3 2328-9-2-90, USED DIAL CALIPER

U.P. 3-2129-10-3-90, LEFT IN DECOR.

Langley, J. Williams, Sr.


3-19+20-90

Block 27 3/21/90 had measurements taken on gasket

surface on value Body with depth gauge, U.P. 3-2211

11-50

measurements are:



Transported Block to decor, Block is tagged

with Red tape with valve ID on it, machining

of Block will take place at hot machine stop

Block has been decored but still is non-smearable (untransported)

Have to get that Ball out later 3/21/90

Nuclear Plant Maintenance Work Order Continuation Sheet

MPL No. 6117

MWO No. 19905116

Work Description Block #11 Jeff & John 3/21/90

When VALVE WAS DISASSEMBLED, WE RAN A FIBERSCOPE IN  
THRU VALVE #036 & TO SEE THE INTERNALS OF VALVE #035  
DISC WAS INTACT & INTERNALS LOOKED GOOD. 3-20-90

Verified Disc was intact only 1. Wayne R Jones 3-20-90

2. Michael W. Spier 3-20-90

3. (Jim) Cucci 3-20-90

Nuclear Plant Maintenance Work Order Continuation Sheet

MPL No. 11208-06-036

MWO No. 18905286

Work Description Block 27 measured valve Bonnet cap, before  
machining 1.500. set up cap in lathe machined  
to .250 cms finish thickness After machining 1.498  
O.D. mic 1-2" VP3-2456 Cal Due Date 8-290 <sup>Cal 3-22-90</sup>  
Maintained zone III Housekeeping

Carl Lew

CFM

3-22-90

CFM used <sup>SNE 311140</sup> dial indicator (0-100) <sup>Cal Due Date VP-3-2874</sup> VP-3-2874 to  
setup bonnet cap in lathe prior to machining. <sup>SNE 312100</sup>

WCC No: 5286 11/1/91  
1890-595 01

PROCEDURE & REV NO: 26621-C 1/1

VALVE:

NOTIFY QUALITY CONTROL PRIOR TO PERFORMING THE WORK ACTIVITY OR STEP ASSOCIATED WITH THE HOLD (H) OR WITNESS (W) POINT

1120806030

DO NOT BYPASS QC HOLD OR WITNESS POINTS

STEP NO.	H/W	HOLD POINT / WITNESS POINT DESCRIPTION	ASSIGNED BY		NOTIFIED		QC ACTION	
			INIT	DATE	INIT	DATE	INIT	I-W-N/A
4.3.1	H	NOTIFY Q.C. TO PERFORM VISUAL INSPECTION OF DESC ASSEMBLY FOR CORROSION, CRACKS, EXCESSIVE WEAR, OR OTHER ABNORMALITIES	Dad	7-21-89	AKR	3/22/90	AKR	I
4.3.2	H	NOTIFY Q.C. TO INSPECT BODY FOR CORROSION, CRACKS, EXCESSIVE WEAR, OR OTHER ABNORMALITIES	Dad	7-21-89	AKR	3/22/90	AKR	I
4.3.3	H	NOTIFY Q.C. TO INSPECT BONNET FOR CORROSION, CRACKS, EXCESSIVE WEAR, OR OTHER ABNORMALITIES	Dad	7-21-89	AKR	3/22/90	AKR	I
4.4.1	H	NOTIFY Q.C. TO VISUALLY CHECK VALVE BODY AND ACCESSIBLE PIPE FOR CLEANLINESS	Dad	7-21-89	AKR	3/22/90	AKR	I
4.4.2	H	NOTIFY Q.C. TO OBSERVE REASSEMBLY OF VALVE INTERNALS AND TO ENSURE THE DISC IS FREE TO OPEN AND CLOSE, AND THE DISC SEATS COMPLETELY AGAINST SEAT RING IN THE BODY	Dad	7-21-89	AKR	3/22/90	AKR	I
4.4.3	H	NOTIFY Q.C. TO OBSERVE TORQUING OF ANY STUDS REMOVED FROM VALVE BODY	Dad	7-21-89	AKR	3/22/90	AKR	I
4.4.12	H	NOTIFY Q.C. TO OBSERVE TORQUING OF FINAL PASS BY REMOVING 3 NUT AT A TIME ON MAIN FLANGE	Dad	7-21-89	AKR	3/22/90	AKR	I

COMMENTS & IR NUMBERS: (initial and date entries)

Blank lines for comments and IR numbers.

MWO No: 18905286 <sup>A</sup>/<sub>2</sub>

PROCEDURE & REV No: N/A

NOTIFY QUALITY CONTROL PRIOR TO PERFORMING THE WORK ACTIVITY  
OR STEP ASSOCIATED WITH THE HOLD (H) OR WITNESS (W) POINT

DO NOT BYPASS QC HOLD OR WITNESS POINTS

1-1208-UG-036

STEP No.	H/W	HOLD POINT / WITNESS POINT DESCRIPTION	ASSIGNED BY		NOTIFIED		QC ACTION	
			INIT	DATE	INIT	DATE	INIT	I-W-N/A
①	H	NOTIFY Q.C. PER THE AS-SIGNED HOLD POINTS IN SECT. 2 TRAVELER 90119						
		a) PT BLENDED AREAS	JE	3/22/90	CCG	3-22-90	CCG	I
		b) VISUALLY INSPECT REPAIR WELD	JE	3/22/90	CCG	3-22-90	CCG	I
		c) PT WELD AREA	JE	3/22/90	CCG	3-22-90	CCG	I
		NOTE:						
		REF. WKS# 900868						

COMMENTS & IR NUMBERS: (initial and date entries)

Blank area for handwritten comments and IR numbers.



## Nuclear Plant Maintenance Work Order Continuation Sheet

REASSEMBLY

MPL No. 1-1208-46-036

MWO No.

DPA 3-22-90

129

18905286

Work Description Block 27 COXD Reassembled a valve 1-1208-46-036  
 installed 8 new studs and nuts and gasket. FORGING  
 for studs was done per procedure 26621-C, FORGING for  
 nuts was done per Westinghouse letter GP-14763.  
 GASKET was measured with dial caliper VP-3-2179 -  
 cal date 10-3-90. All measurements were within Westinghouse  
 tolerances per procedure <sup>GP 14763 DPA 3-22-90</sup> 26621-C. Stud height ranged  
 from 2 1/8" to 2 1/4" with 6" scale torque wrench V-P-3-2866  
 cal date 5-1-90 was used for first torque - 25 FT LBS.  
<sup>1-3-90</sup> VP-3-2075 was used for remainder <sup>DPA 3-22-90</sup> of the steps including  
 final slip after a 2 hour wait. MER # 3-16-90-005017  
 for studs nuts & gasket maintained ZONE III Housekeeping

Darryl J. Williams Sr.

3-22-90

1. MWO/OTHER # 18905286	2. INSP PROCEDURE # 85050-C	REV # 2	3. DRAWING # N/A	REV #
4. TAG/EQUIP # 1120806 036	5. SYS. DESIGNATOR 1208	6. BUILDING CTMT	ROOM/LEVEL C	
7. WELD # 900868	8. MATERIAL TYPE/HEAT # P8 to P8			
9. TIME OF EXAMINATION: FIT UP INSP <input checked="" type="checkbox"/> IN PROCESS <input type="checkbox"/> FINAL INSP <input checked="" type="checkbox"/> INSERVICE <input type="checkbox"/>				

Note: Enter weld inspection attributes accepted or rejected with reasons for rejection.

10. REMARKS:

VISUALLY INSPECTED THE BLENDED OUT GRINDING GROOVE PRIOR TO WELD OUT. NO DISCREPANCIES NOTED.  
VISUALLY INSPECTED THE WELD REPAIR AREA PER CATEGORY 'D' REQUIREMENTS OF 85050-C R/2. NO DISCREPANCIES NOTED.

11. SKETCH:

12. DC/ODR #

13. INSPECTOR

*Christopher C. [Signature]*

LEVEL II

DATE 3-22-90

ACCEPT  REJECT

14. EVALUATOR

N/A

LEVEL

DATE

COMPLETION SHEET

Procedure No. 26621-C	Revision 1	Sheet 1 of 2
Tag No. 1-1208-46-036	Description Check Valves 3"-12"	
Serial No. 4A	Manufacturer Westinghouse	Model 30-43 Style B
Test Equipment Used	M&TE No.	Safety Related/QC Hold Points
Torque wrench	VP-3 2586 cal 210 5-1-80	( ) Safety Related
Dial Caliper	VP-3 2015 cal 800 2-2-90	( ) Non-Safety Related
D.H.I. Caliper	VP-3-2174 Caliper 10-2-90	

PROCEDURE STEP	DESCRIPTION	MAINT. INIT/DATE	HOLD POINT (Yes/No)	QC INIT/DATE
4.1	Verify Prerequisites	4/28/80 12-22-80	No	Sub 4/31/89
4.2.1	Notify Shift Supervisor	4/28/80 12-22-80	I	I I I
4.2.2	Clearance and Tagging	4/28/80 12-22-80	I	I I I
4.3.1	Check Disc Assembly	4/28/80 12-22-80	Q.C. HOLD POINT	AKR 12/2/80
4.3.2	Check Body	4/28/80 12-22-80	Q.C. HOLD POINT	AKR 12/2/80
4.3.3	Check Bonnet	4/28/80 12-22-80	Q.C. HOLD POINT	AKR 12/2/80
4.4.1	Check Cleanliness	4/28/80 12-22-80	Q.C. HOLD POINT	AKR 12/2/80
4.4.2f	Disc Free	4/28/80 12-22-80	Q.C. HOLD POINT	AKR 12/2/80
4.4.3	Studs Torqued to 100 ft.lbs.	4/28/80 12-22-80	Q.C. HOLD POINT	AKR 12/2/80
4.4.7	Nuts Torqued to 25 ft.lbs (Level 1)	4/28/80 12-22-80	No	Sub 4/31/89
4.4.8	Nuts Torqued to 60 ft.lbs (Level 2)	4/28/80 12-22-80	I	I I I

\* INTERNAL USE ONLY

PROCEDURE  
STEP

DESCRIPTION

MAINT.  
INIT/DATE

HOLD  
POINT  
(Yes/No)

QC  
INIT/DATE

4.4.9

Nuts Torqued to  
150 ft.lbs (Level 3)

4/28/82-90

No

4/19/91/91

4.4.12

Final Torque on flange  
Nuts 170 ft.lbs

4/28/82-90

20 HOLD POINT

4/19/91/91

4.4.13

Notify Shift Supervisor

4/28/82-90

No

4/19/91/91

Comments/additional hold points: \_\_\_\_\_

QC has reviewed this procedure for hold points

4/21/89  
Signature

APPROVED (✓)	DISAPPROVED ( )
FOREMAN	DATE
<u>Wayne K. Jones</u>	<u>3-22-90</u>

COMPLETED BY	DATE
<u>Henry Anderson</u>	<u>3-22-90</u>

DATA SHEET 1

MAINTENANCE CLEANLINESS AND HOUSEKEEPING

Maintenance Work Order No. 15905286 Date 3-22-90

Maintenance Cleanliness and Housekeeping Standard Required

B C D (Circle one)

Name of system or component requiring cleaning

CLEANLINESS STANDARDS

<u>B</u>	C	D	INIT/DATE
Metal clean surface.	Thin rust on carbon steel OK.	Tight mill scale Carbon steel OK.	<u>KWB/3-22-90</u>
Rust allowable 2 sq/in per 1 sq/ft.	Rust allowable 15 sq/in per 1 sq/ft.	Rust which resists brushing.	<u>KWB/3-22-90</u>
*** No particulates/particles removable by brushing.			<u>KWB/3-22-90</u>
*** No oil, grease, or other organic films removable by brushing.			<u>KWB/3-22-90</u>
*** Perform closeout Step 4.3.5.b.6.			<u>KWB/3-22-90</u>
*** No contaminants removable in large amounts by wiping.			<u>KWB/3-22-90</u>
*** Decon tools and equipment.			<u>KWB/3-22-90</u>
*** Finish maintenance cleaning and housekeeping using Figure 1, "Maintenance Cleanliness and Housekeeping Handout".			<u>KWB/3-22-90</u>

COMMENTS: \_\_\_\_\_

[Signature]

MAINTENANCE PERSON SIGNATURE/DATE

KWB 3-22-90

MAINTENANCE FOREMAN SIGNATURE/DATE

3-22-90  
DATE RESULTS REVIEWED

(  ) Approved

(  ) Disapproved

\*\*\* (for all cleanliness standards)



TASK 4 RECOMMENDATIONS

4.1 Disassembly and Inspection

Disassemble the check valves in accordance with the requirements covered in the Maintenance and Instruction Book 5710-99. *PROCEDURE 26621-C IHB 3.5-98*

Record the breakout torque values of the nuts.

Remove the cap.

Measure the height of the studs above the body flange.

If the stud height above the flange is less than 2.32 inches, the studs are fully engaged in the valve body.

If the stud height above the valve body flange is more than 2.32 inches, the stud is not fully engaged in the valve body.

Since the valve has been leaking, it is necessary to clean the studs before reassembly. To do so, it is recommended that all studs be removed from the body and cleaned to remove any boron deposits.

O.C.  
HOLD POINT

If the stud height is more than 2.32 inches, remove the stud and use a bottoming tap (5/8 -11) to tap the stud holes to .96 to 1.00 inch. The holes are predrilled to 1.10 inches (see attached sketch). Clean the the tapped holes and the studs, and lubricate the studs in accordance instructions in the Instruction Book using Fel-Pro N-5000 or equivalent.

O.C.  
HOLD POINT

Dimensionally inspect the valve bonnet/cap to make sure there is no dishing or warping of the cap. If the cap is dished or warped, it must be evaluated before it is reused.

2.3. HOLD POINT  
Inspect the seating surface of the cap to make sure there is no scratch marks or wear marks at the gasket seating area. If it is scratched or worn, take a skin cu of the surface (.001 inch to .003 inch) with a surface finish of 125-250 RMS.

Clean the gasket groove with acetone or suitable cleaning fluid making sure not to scratch the surface.

#### 4.2 Installation

2.3. HOLD POINT  
Install the studs in the valve body in accordance with Instruction Book <sup>4115 3-9 34</sup> paragraph 6.2.9. *2664-C*

Q.C. HOLD POINT  
Measure the stud heights above the badge flange and confirm that the heights are less than 2.32 inches above the body flange face.

Q.C. HOLD POINT  
Obtain a new gasket from the warehouse and measure the gasket dimensions before installation. The gasket dimensions shall be:

O.D	$4.49 + .000/- .047$ inches
I.D	$3.78 + .016/- .016$ inches
Thickness	$.125 + .010/- .000$ inch

Install the cap and tighten the stud nuts in accordance with <sup>2002</sup> ~~Instruction~~ 20021 ~~Book~~ paragraph 6.2.11 (Table 6-2B) as modified below. The torquing sequence shall be:

Torque Level 1 25 ft -lb

Torque Level 2 60 ft -lb

Torque Level 3 150 ft -lb

Torque Level 4 170 ft -lb


G.C.  
HOLD POINT

After completing the torquing sequence, repeat the sequence one more time at 170 ft-lb to assure that all the studs are well torqued.


\*\*\*\*\* NOTE \*\*\*\*\*

G.C.  
HOLD POINT

WAIT FOR 1 HOUR AFTER TORQUING ALL NUTS TO LEVEL 4 (SECOND TIME) TO ALLOW THE TORQUES TO STABILIZE. RECHECK TORQUE LEVEL 4 FOR ALL STUD NUTS AND RETORQUE AS NECESSARY TO 170 FT-LBS. THIS WILL BE THE THIRD CYCLE AT 170 FT-LBS.



Attachment 1: Check Valve Body



Attachment 2: Check Valve Bonnet/Cap



CONTROL NO. 18905286 02

MPL/TAG NO.	SYSTEM	EQP	CLS	DESCRIPTION	LOCATION
11208U6035	1208	111		CHECK VALVE 3.0,C88,1500	1RB184-SG1-4N3E21
11208U6036	1208	111		CHECK VALVE 3.0,C88,1500	1RB184-SG1-4N3E19

Block 26 E.M. J. ~~Reuter~~ 3/19/90

MWO #: 18905286 RCN #: MEPM TAG #: 11208U6G36

PACKAGING INSTRUCTIONS

ZZZ:TOOLS. N/A

QQ: CAUTION: MID-LOOP AND NO RHR FLOW IS REQUIRED.

ERECT SCAFFOLDING.

REMOVE SHEETMETAL COVER AND INSULATION.

GRIND OUT WELD ON SEAL CAPS.

DISASSEMBLE VALVE.

INSPECT INTERNALS FOR ABNORMAL WEAR AND FULL SWING ON

DISC ARM. IF ANY DEFECTS ARE FOUND NOTIFY SYSTEM

ENG./MAINT. ENG. FOR INSPECT !. \*\*

DO NOT REPLACE ANY PRESSURE BOUNDARY PARTS THAT'S NOT

ON A SECTION XI TRAVELER. SECT. XI TRAVELER # 90117.

REASSEMBLE VALVE PER 26621-C.

MAINTAIN CLEANLINESS CLASS - B.

→ WELD ON NEW SEAL CAP PER WPCS (SEE MWO)

( PT BODY &amp; BONNET WHERE SEAL CAP WELD WAS REMOVED.)

QC/ANII TO PERFORM A VT-II AT N.O.P./T.

REINSTALL INSULATION/SHEETMETAL LAGGING.

↓ \*\* WHEN VALVE IS DISASSEMBLED, INSERT A BOROSCOPE INTO THE

LINE AND INSPECT THE INTERNALS OF THE OTHER CHECK VALVE

Document FINDINGS in sheet 27

MWO #: 18905286 RCN #: MEPM TAG #: 11208U6036

PACKAGING INSTRUCTIONS

TO THE EXTEND POSSIBLE. THE OTHER VALVE NOT TO BE  
DISASSEMBLE WITHOUT A SEPERATE MWO AND SYSTEM  
ENGINEERING APPROVAL.

E:EST MAN/HRS. 60 MEOP

D:DUR. 30 HRS.

DATA SHEETS PAGES 1-12 & 116-115 REMOVED AND PM  
CHECKLISTS <sup>IN</sup> 31111 5660497 REMOVED AS THEY ARE NOT  
APPLICABLE LAC 3/15/90

## EQUIPMENT MAINTENANCE CHECKLIST

MWO-NUMBER	CHECKLIST	CLASS	FREQUENCY	PAGE
18905286	SCL00497	C	N/A	1 OF 1
TAG NUMBER	REFERENCE MATERIAL			
1-1208-U6-036	26621-C			
MAINTENANCE REQUIREMENTS AND SPECIAL INSTRUCTIONS				SKILL AND INITIALS
WESTINGHOUSE STYLE B CHECK VALVE INSPECTION				
(COMMITMENT # 16052) (RER 89-0278)				
1. DISASSEMBLE AND INSPECT CHECK VALVE PER PROCEDURE 26621-C.				<u>CJA 1208</u>
2. INSPECT FOR INDICATIONS OF WEAR, LEAKAGE, EROSION, CORROSION, DEFORMATIONS, MISSING PARTS OR OTHER ABNORMALITIES. PAY PARTICULAR ATTENTION TO INTERNAL VALVE COMPONENTS SUCH AS DISCS, DISC ARMS, HINGE PINS, ANTI-ROTATION LUGS, PISTONS, SPRINGS, LOCKING DEVICES, SEATING/SEALING SURFACES, ETC., AS APPLICABLE. DOCUMENT ANY FINDINGS.				<u>CJA 1208</u>
MAINTENANCE ENGINEER/SUPV. APPROVAL H R VAUGHT LAST MINOR CHANGE DATE 00/00/00				REV. 01 01/09/90


MAINTENANCE WORK ORDER REVISION SHEET

1 CONTROL NO. <i>18905886</i>	2 REVISION NO. <i>2</i>	3 MPL TAG NO. <i>1-1208-UE 136</i>	4 DATE <i>3/22/90</i>
5 REASON FOR REVISION			
<p>The body requires weld repair where the seat cap was welded on.</p>			
<p>Block 23 job: Work per Sect II Traveler 90119</p>			
<ul style="list-style-type: none"> <li>- Blend out area, prepare surface for P.T.</li> </ul>			
<ul style="list-style-type: none"> <li>- P.T. Area</li> </ul>			
<ul style="list-style-type: none"> <li>- Repair area by welding WPLS # 900868</li> </ul>			
<ul style="list-style-type: none"> <li>- Blend weld surface</li> </ul>			
<ul style="list-style-type: none"> <li>- P.T. weld repair</li> </ul>			
			6 INITIATOR <i>L. J. ...</i>
REVIEW SIGNATURES			
7 MAINTENANCE ENG <i>Kirkston 3-22-90</i>	8 OPERATIONS <i>[Signature] 3-22-90</i>	9 CLEARANCE REQUIRED <i>P.O.</i>	
10 QP REVIEW <i>[Signature] Check 3/22/90</i>	11 HOLD POINTS <b>HOLD POINT ATTACHED</b>		
12 HP REVIEW <i>[Signature] 3-22-90</i>	13 NEW RWP REQUIRED <i>90-6604</i>		
14 ANI REVIEW <i>N/A see Sect II Traveler</i>	15 HOLD POINTS <i>N/A see sect II Traveler 3/22/90</i>		
16 WORK PLANNER <i>[Signature] 3/22/90</i>	17 PROCEDURES		
18 FIRE PROTECTION REVIEW <i>[Signature]</i>	19 SHIFT SUPERVISOR <i>[Signature]</i>		3/22/90
20 REMARKS			



GEORGIA POWER CO.

GENERATING PLANT  
MAINTENANCE WORK ORDER REVISION SHEET  
CONTROL NO. 18905286



2 REVISION NO. 1  
3 MPL TAG NO. 1120846036

4 DATE 3-15-90

5 REASON FOR REVISION  
ADDITIONAL WORK INSTRUCTIONS TO BE PERFORMED  
GP-1473

Block 23: PERFORM SPECIAL INSTRUCTIONS  
PER ATTACHED CONTINUATIONS  
SHEETS, PERFORM REV 0 ON  
1120846036 I.F. REQUIRED

7 MAINTENANCE ENG	8 INITIATOR	9 CLEARANCE REQUIRED
10 AS REVIEW M. O. C. 3-19-90	10 OPERATIONS J. B. BROWN	11 HOLD POINTS 3-19-90
12 HP REVIEW M. O. C. 3-19-90	11 HOLD POINTS 3-19-90	13 NEW RWP REQUIRED NONE
14 ANI REVIEW M. O. C. 3-19-90	12 HOLD POINTS 3-19-90	15 HOLD POINTS NONE
16 WORK PLANNER M. O. C. 3-19-90	13 PROCEDURES NONE	17 SHIFT SUPERVISOR J. B. BROWN 3-19-90
18 FIRE PROTECTION REVIEW M. O. C. 3-19-90	14 PROCEDURES NONE	18 HOLD POINTS NONE
20 REMARKS 3-19-90	15 PROCEDURES NONE	19 HOLD POINTS NONE

3-19-90  
3-19-90  
3-19-90

MAINTENANCE WORK ORDER REVISION SHEET

1 CONTROL NO. 18905286	2 REVISION NO. 1	3 MPL TAG NO. 1120846036	4 DATE 3-19-90
5 REASON FOR REVISION ADDITIONAL WORK INSTRUCTIONS TO BE PERFORMED ON 1120846036 ONLY PER WESTINGHOUSE LETTER GP-14763.			
Block 23: PERFORM SPECIAL INSTRUCTIONS PER ATTACHED CONTINUATION SHEETS. PERFORM REV. O. ON 1120846036 IF REQUIRED			
			6 INITIATOR Don Baggett 3/19/90
REVIEW SIGNATURES			
7 MAINTENANCE ENG K. Heaton 3-19-90	8 OPERATIONS Michael 3/19/90	9 CLEARANCE REQUIRED 7 ECP 01	
10 ASST. SUPERVISOR O. C. Chew 3/19/90	11 HOLD POINTS <b>HOLD POINT ATTACHED</b>		
12 H. W. SUPERVISOR L. B. 3-19-90	13 NEW RWP REQUIRED 90-6604	15 HOLD POINTS UJA 003 3-19-90	
16 W. P. SUPERVISOR UJA 3-19-90	17 PROCEDURES UJA 3-19-90	19 SHIFT SUPERVISOR J. C. 3-19-90	
18 FINAL ENGINEER REVIEW UJA 3/19/90	20 REMARKS CONTACT WEBB - 3-20-90		

MAINTENANCE WORK ORDER REVISION SHEET

1 CONTROL NO. 18905286	2 REVISION NO. 1	3 MPL TAG NO.. 1120806036	4 DATE 3 19 90
5 REASON FOR REVISION ADDITIONAL WORK INSTRUCTIONS TO BE PERFORMED ON 1120806036 ONLY PER WESTINGHOUSE LETTER GP-14763.			
Block 23 PERFORM SPECIAL INSTRUCTIONS PER ATTACHED CONTINUATION SHEETS. PERFORM REV. 0 ON 1120806036 IF REQUIRED.			
			6 INITIATOR Don EASSETT 3/19/90
REVIEW SIGNATURES			
7 MAINTENANCE ENG K. Katicton 3-19-90	8 OPERATIONS Vital Powell 3-19-90	9 CLEARANCE/REQUIRED JERRY	
10 QC REVIEW Chris O. Clark 3/19/90	11 HOLD POINTS		
12 HP REVIEW Mike Rott 3-19-90	13 NEW RWP REQUIRED 30 6604		
14 ANI REVIEW M. Callender 3-19-90	15 HOLD POINTS VJ 05 3-19-90		
16 WORK PLANNER VJ 05 3-19-90	17 PROCEDURES VJ 05 3-19-90		
18 FIRE PROTECTION REVIEW VJ 05 3/19/90	19 SH. A SUPERVISOR VJ 05 3-19-90	30 HART 3-20-90	
20 REMARKS			

MAINTENANCE WORK ORDER REVISION SHEET

1 CONTROL NO. 18905286	2 REVISION NO. 1	3 MPL TAG NO. 1120506 036	4 DATE 3 19 90
5 REASON FOR REVISION ADDITIONAL WORK INSULTIONS TO BE PERFORMED ON 1120506 ONLY PER HEADHOUSE LETTER GP-14763			
6 INITIATOR J. E. ... 3/19/90			
7 MAINTENANCE ENG K. ... 3-19-90			
8 OPERATIONS J. ... 3-19-90			
9 CLEARANCE REQUIRED 700 REV			
10 QC REVIEW M. O. ... 3/19/90			
11 HOLD POINTS			
12 HP REVIEW J. ... 3-19-90			
13 NEW RWP REQUIRED			
14 ANI REVIEW J. ... 3-19-90			
15 HOLD POINTS			
16 WORK PLANNER J. ... 3-19-90			
17 PROCEDURES J. ... 3-19-90			
18 FIRE PROTECTION REVIEW J. ... 3-19-90			
19 SHIFT SUPERVISOR J. ... 3-19-90			
20 REMARKS CHART 3-20-90			



May 2, 1990

Reference No. 17133B-006

Georgia Power Company  
40 Inverness Center Parkway  
P. O. Box 1295  
Birmingham, Alabama 35201

Attention: Kenneth S. Burr

Subject: Reliability Evaluation Testing of Calcon Model A3500-W3  
Temperature Sensors

References: 1) Georgia Power Company Purchase Order No. 60031-1  
2) Wyle Laboratories' Test Procedure 17133

Dear Mr. Burr:

Two new Calcon Model A3500-W3 Temperature Sensors (Serial Nos. OC3011 and OC3002 designated as Temperature Sensor 0 and 1, respectively) were subjected to the Reliability Evaluation Test Program described in Wyle Laboratories' Test Procedure 17133 with the following exceptions: 1) The As-Received Setpoint Determination Test was performed prior to removal of the sensors from their thermowells and inspection of their spacer-tubes, and 2) due to temperature sensor performance during Test Series 1 when the sensors were removed from their thermowells and inserted directly in the water bath, no tests were performed with loose spacer-tubes with the sensors removed from their thermowells and inserted directly in the water bath (tests originally specified for Test Series 3). In addition, it was determined prior to the test that the model number specified in the test procedure (A3501-W3) was taken from an incorrect manufacturer's document which has been corrected in a more recent release of the document, and A3500-W3 is the correct model number.

The test program was performed in the following sequence:

- o Specimen identification and external visual inspection.
- o As-Received Setpoint Determination Test
- o Sensor removal from thermowells and inspection of and marking location of spacer-tubes.
- o Calibration of specimens.
- o Setpoint Repeatability Tests to determine the effects of varying rates of temperature change, varying input air pressure, vibration, varying ambient air temperature, thermowell setscrew tightness, spacer-tube looseness, etc.



X

The attached table contains a list of all tests performed including test conditions and results. The tests demonstrated that input air pressure variations of 5 psi or less, a rapid water temperature decrease (approximately 10°F/minute) from just below the setpoint, vibration typical of in-service vibration (excluding long-term effects), ambient air temperature variations of 20°F or less, and slightly noticeable bowing of the Viton O-ring/disk assembly have no significant effect on Temperature Sensor operation and calibration. The following paragraphs describe parameters that were shown to have a significant effect on the operation and/or calibration of the Temperature Sensors.

#### Insufficient Temperature Stabilization Period Prior to Calibration

Consecutive calibration checks indicated a slight upward shift in the setpoint apparently due to the failure to completely stabilize the temperature of all components of the specimens prior to the initial calibration. It was concluded that a minimum two-hour soak period at approximately 200°F prior to calibration (180°F for setpoint checks) is necessary to ensure consistent performance.

#### Contaminants on the Temperature Sensor

Tests performed with the Sensors removed from their thermowells and inserted directly in the water bath caused a downward shift of approximately 10°F in the setpoint of both specimens apparently due to mineral residue on the Viton O-ring/disk assembly (standard facility water and not demineralized water was used in the water bath). The Viton O-ring/disk assemblies were cleaned with Dow Corning 200 Fluid (silicone oil) and allowed to dry overnight. The specimens were then recalibrated and remained in calibration for the remainder of the tests prior to the intentional loosening of the spacer-tubes. It was concluded that the Sensors should not be immersed directly in water. All calibrations and tests should be performed with the Sensors installed in their thermowells.

#### Setpoint Reference Temperature

All tests were performed with a thermocouple used to monitor the internal temperature of a reference thermowell in the water bath along with the specimens. The temperature of the water was also monitored with a thermocouple. It was determined that due to the temperature indication lag of the thermowell thermocouple caused by the thermocouple not displacing as much air as the Sensors, the thermocouple not being as close to the thermowell wall as the Sensors, and the time constant of the thermocouple in still air, the water bath temperature is a more realistic reference for calibration and testing. The lag time for the thermocouple in the circulating water bath was insignificant.

#### Water Bath Heatup Rate

A slow water bath heatup rate (approximately 1°F per minute) was shown to allow the thermowell internal temperature to more closely follow the water bath temperature. A slow heatup rate causes the specimens to trip at a higher temperature (as measured in the thermowell) than a fast heatup rate. It should be noted that a slow heatup rate causes the specimens to trip at a lower water temperature than a fast heatup rate.

7

Thermowell Setscrew Tightness

The tests with the thermowell setscrews loose demonstrated that a loose setscrew causes an increase of approximately 2°F in the setpoint when measured with a heatup rate of 1°F per minute. This setpoint shift is apparently due to the loss of contact between the Sensor and the wall of the thermowell. All calibrations and testing should be performed with the thermowell setscrew tight.

Spacer-Tube Position

The tests performed with the spacer-tube loose demonstrated that the setpoint decreases approximately 80°F for each full turn. A thread-locking compound is recommended to ensure that the spacer-tube remains in its tightened position for all calibrations, tests, and in-service use.

A test report to be issued at a later date shall contain details of the inspections and tests, test results, photographs, equipment calibration data, etc.


Should you have any questions or require additional information, please contact the undersigned.

Sincerely,

WYLE LABORATORIES  
Eastern Operations




Don Smith  
Senior Engineer  
Nuclear Environmental Qualification



Dawn K. Bates  
Senior Contracts Administrator



Flavous R. Johnson, P.E.  
Department Manager  
Nuclear Environmental Qualification



G. W. Hight  
Manager, Quality Assurance

DS/DKB/grd

Attachment

ATTACHMENT

AS-RECEIVED TEST,  
CALIBRATION,  
AND  
RELIABILITY EVALUATION TEST  
SUMMARY

STOPPED

DATE	SERIES	RUN	RATE	LOC.	TEMPERATURE SENSOR 0 SERIAL NO. GC3011				TEMPERATURE SENSOR 1 SERIAL NO. GC3002							
					TRIP		40 PSIG RESET		4/-1 PSIG RESET		TRIP		40 PSIG RESET		4/-1 PSIG RESET	
					TW	W	TW	W	TW	W	TW	W	TW	W	TW	W
4/23/90	AR	1	1	IN	204.1	208.1	200.2	200.1	200.2	200.1	206.0	210.8	199.3	199.4	199.3	199.4
	AR	2	1	IN	205.7	209.3	201.4	201.7	201.4	201.7	207.2	210.9	208.7	201.8	200.7	201.8
	AR	3	*	IN	209.9	211.7	204.8	204.6	204.9	204.6	210.1	211.9	202.9	203.7	202.9	203.7

VISUAL INSPECTION/TS-1 SPACER-TUBE SLIGHTLY LOOSE, TIGHTENED BEFORE CONTINUING

CALIBRATION AT 200°F

	CC	1	1	IN	198.6	202.2	196.3	196.1	193.3	195.0	199.9	203.2	193.3	193.0	193.3	193.0
	CC	2	1	IN	198.7	202.1	196.5	196.5	193.6	192.6	200.3	203.5	193.6	192.6	193.6	192.6
4/24/90	1	1	1	IN	198.2	201.7	195.8	195.6	194.9	194.7	198.9	201.9	192.4	191.7	192.4	191.7
	1	2	1	OUT	186.4	190.2	180.6	180.3	180.6	180.3	187.6	191.3	181.7	181.3	181.7	181.3
	1	3	1	IN	186.3	190.1	181.6	181.6	181.4	181.2	185.2	188.7	179.7	179.5	179.7	179.3

SEE NOTE 2.

---	3A	1	1	IN	187.1	190.7	182.5	182.3	182.3	182.1	192.6	196.7	187.2	187.2	187.2	187.2
-----	----	---	---	----	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

VISUAL INSPECTION/TS-0 SPACER-TUBE SLIGHTLY LOOSE, TIGHTENED BEFORE CONTINUING

	1	4	1	OUT	186.6	190.4	182.5	182.3	182.4	182.2	186.6	190.4	181.1	181.3	181.1	181.3
	1	5	1	IN	187.4	191.3	184.2	184.0	183.8	183.6	184.7	198.4	177.7	177.5	177.7	177.5
	1	6	1	OUT	181.9	185.5	178.6	178.2	177.5	177.2	182.1	185.9	177.5	177.1	177.5	177.1

RECALIBRATION AT 200°F

DURING RAMP																
	TO 200°F	1	IN	184.5	188.3	N/A	N/A	N/A	N/A	N/A	181.2	184.7	N/A	N/A	N/A	N/A
	CC	1	1	IN	196.9	200.6	N/A	N/A	N/A	N/A	197.6	201.5	N/A	N/A	N/A	N/A

RECALIBRATION AT 200°F

4/25/90	CC	1	1	IN	196.9	200.9	193.7	193.7	192.2	192.4	197.1	200.8	189.6	189.6	189.6	189.6
	1	7	2	IN	194.0	199.8	195.0	195.9	193.0	190.9	197.2	203.2	191.8	190.7	191.8	190.7
	1	8	4	IN	189.3	197.6	194.2	189.2	193.5	188.5	196.3	205.8	194.0	189.4	194.0	189.4
	1	9	6	IN	186.6	196.8	193.9	186.3	195.9	186.3	196.3	208.3	194.4	187.3	194.4	187.3
	1	10	10	IN	184.1	199.5	195.8	184.7	195.6	184.7	196.9	211.4	198.8	186.6	195.6	184.7
	1	11	15	IN	183.8	201.1	196.3	179.2	196.3	179.2	196.7	210.9	199.7	188.5	199.5	187.7
	1	12	20	IN	181.8	202.1	197.2	175.7	197.2	175.7	197.5	211.2	200.8	185.8	200.8	185.8
	---	12A	1	IN	191.2	194.5	N/A	N/A	N/A	N/A	DID NOT TRIP AT 209.4°F TW/211.4°F W					

THERMOWELLS AND EXTERNAL SURFACE OF SENSOR PROBES CLEANED WITH SILICONE OIL AND BRUSH.



TEMPERATURE SENSOR 0  
SERIAL NO. 0530:1

TEMPERATURE SENSOR 1  
SERIAL NO. 023002

DATE	SERIES	RUN RATE	LOC.	40 PSIG		+/-1 PSIG		40 PSIG		+/-1 PSIG					
				TRIP	RESET	TRIP	RESET	TRIP	RESET	TRIP	RESET				
4/26/90	1	128	1 IN	199.7	202.3	192.5	192.4	192.3	192.4	205.5	209.2	198.9	199.2	198.9	199.2

RECALIBRATION AT 200°F (NOTE: TS-0 AND TS-1 RING POSITIONS WERE APPROX. 6/32 AND 8/32 INCHES COUNTERCLOCKWISE FROM THEIR PREVIOUS POSITION AFTER THIS CALIBRATION.)

CC	1	1	1 IN	199.8	203.8	197.1	197.8	195.0	195.8	200.8	204.5	192.3	192.8	192.3	192.8
CC	2	1	1 IN	200.8	203.9	197.8	198.2	195.5	196.7	200.8	204.6	192.3	193.3	192.8	193.3

MOVED THERMOCOUPLE IN THERMOWELL FROM ITS ORIGINAL POSITION 1/2-INCH FROM THE BOTTOM TO TOUCHING THE BOTTOM OF THE THERMOWELL.

CC	3	1	1 IN	201.1	204.6	198.7	199.2	196.3	196.8	201.9	205.2	193.5	193.8	193.5	193.8
----	---	---	------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

RETURNED THERMOWELL THERMOCOUPLE TO ITS ORIGINAL POSITION.

SEE NOTE 1.

1	13	1	1 IN	199.8	204.1	197.0	198.4	195.0	196.1	198.8	203.0	192.0	192.9	192.0	192.9
1	14	1	1 IN	203.3	207.6	199.6	201.3	199.6	201.3	203.5	207.9	194.0	194.2	194.0	194.2

THE MOTOR USED TO TURN THE PROPELLER WHICH CIRCULATED THE WATER IN THE BATH AND WHICH CAUSED SOME SPECIMEN VIBRATION WAS TURNED OFF FOR THE FOLLOWING TEST AND THE SPECIMENS WERE TAPPED CONTINUOUSLY WITH SCREWDRIVERS AT THE RATE OF 2 TO 3 PER SECOND.

1	15	1	1 IN	202.6	207.5	200.0	180.8	199.4	169.6	200.6	204.7	194.6	170.6	194.6	170.6
---	----	---	------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

SEE NOTE 3.



60

		TEMPERATURE SENSOR 0 SERIAL NO. 0C3011				TEMPERATURE SENSOR 1 SERIAL NO. 0C3002			
DATE	SERIES RUN RATE LOC.	TRIP	40 PSIG RESET	TRIP	+/- 1 PSIG RESET	TRIP	40 PSIG RESET	TRIP	+/- 1 PSIG RESET
4/27/90	SEE NOTE 4.								
		TW	M	TW	M	TW	M	TW	M

1	16	1	IN	200.3	203.9	196.5	196.6	196.5	196.6	201.8	205.8	193.0	193.1	193.0	193.1
1	17	1	IN	202.1	206.8	197.1	197.7	197.1	197.7	202.6	207.2	193.3	193.8	193.3	193.8
1	18	**	IN	NO TRIP OCCURRED											

SEE NOTE 5.

---	18A	20	IN	188.8	210.2	195.7	190.4	195.7	190.4	187.7	210.2	195.1	188.5	195.1	188.5
---	18B	1	IN	201.1	206.8	198.2	199.0	198.2	199.0	202.2	206.6	194.1	194.2	194.1	194.2

LOOSEMED THERMOWELL SET SCREW

2	1	1	IN	203.7	207.8	201.9	202.5	201.9	202.5	203.9	208.1	199.8	200.3	199.8	200.3
---	---	---	----	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

RETTIGHTENED THERMOWELL SET SCREW

2	2	1	IN	201.2	205.4	198.3	199.2	198.3	199.2	203.0	207.2	195.9	196.1	195.9	196.1
---	---	---	----	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

4/30/90 THE FOLLOWING TESTS WERE PERFORMED TO DETERMINE THE EFFECTS OF VIBRATION ON THE SETPOINTS OF THE SPECIMENS. TEST RUNS 1 AND 2 WERE PERFORMED WITH \*THE ONLY VIBRATION PROVIDED BY THE MOTOR USED TO CIRCULATE THE WATER IN THE BATH. TEST RUN 3 WAS PERFORMED WITH ADDITIONAL VIBRATION AT 15 HZ AND TEST RUN 4 WAS PERFORMED WITH ADDITIONAL VIBRATION AT 30 HZ. THE ADDITIONAL VIBRATION SIMULATED IN-SERVICE VIBRATION CONDITIONS AT THE FREQUENCIES IN EACH AXIS WHERE THE HIGHEST VIBRATION LEVELS WERE MEASURED.

4	1	1	IN	197.5	201.2	193.7	193.8	193.7	193.8	198.2	202.3	189.3	188.1	189.3	188.1
4	2	1	IN	198.3	202.1	194.6	194.9	194.5	194.7	198.5	202.1	189.5	189.4	189.5	189.4
4	3	1	IN	198.0	202.5	195.8	195.7	195.8	195.7	198.7	202.4	190.3	190.3	190.3	190.3
4	4	1	IN	198.3	202.3	196.4	196.8	196.4	196.8	198.9	202.6	190.8	190.7	190.8	190.7

5/01/90 SPACER-TUBES WERE LOOSEMED 1/4-TURN/TURNING WATER HEATUP TO 180°F (AT THE RATE OF APPROX. 20°F PER MINUTE), TS-0 TRIPPED AT 165.3°F TW/187.7°F M AND TS-1 TRIPPED AT 149.5°F TW/186.0°F M. THE TEMPERATURE WAS DECREASED TO RESET THE THE SPECIMENS AND WAS HELD AT 165°F FOR APPROXIMATELY 2 HOURS.

3	1	1	IN	179.1	182.9	175.9	177.3	175.9	177.3	178.4	182.4	168.8	168.1	168.8	168.1
3	2	1	IN	179.0	182.8	176.5	176.6	176.5	176.6	179.1	182.9	168.7	168.9	168.7	168.9

SPACER-TUBES WERE LOOSEMED 1/2-TURN/TEMPERATURE WAS HELD AT 150°F FOR APPROXIMATELY 15 MINUTES.

3	3	1	IN	160.9	165.1	158.0	158.2	158.0	158.2	159.4	163.1	155.7	155.4	155.7	155.4
---	---	---	----	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------

TEMPERATURE SENSOR 6  
SERIAL NO. 0C3011

DATE	TEST	TV	W	40 PSIG		TV	W	+/-1 PSIG	
				TRIP	RESET			TRIP	RESET
5/02/90	AR	198.0	202.4	194.4	195.4	194.4	195.4	194.4	195.4
	AR	198.5	204.0	194.8	196.2	194.5	196.2	194.5	196.2

TEMPERATURE SENSOR 2  
115M19111

DATE	TEST	TV	W	40 PSIG		TV	W	+/-1 PSIG	
				TRIP	RESET			TRIP	RESET
5/02/90	AR	188.7	192.8	178.7	178.7	178.7	178.7	178.7	178.7
	AR	189.1	194.7	179.6	180.6	179.9	180.6	179.9	180.6

TEMPERATURE SENSOR 4  
115M19146

DATE	TEST	TV	W	40 PSIG		TV	W	+/-1 PSIG	
				TRIP	RESET			TRIP	RESET
5/02/90	AR	194.6	199.7	192.4	193.8	192.4	193.8	192.4	193.8
	AR	195.1	199.6	192.4	193.5	192.4	193.5	192.4	193.5

TEMPERATURE SENSOR 7  
115M19117

DATE	TEST	TV	W	40 PSIG		TV	W	+/-1 PSIG	
				TRIP	RESET			TRIP	RESET
5/02/90	AR	185.7	190.1	183.6	183.7	182.7	183.0	182.7	183.0
	AR	186.5	191.0	186.5	186.7	182.0	184.2	182.0	184.2

NOTES: 1. ALL TESTS WERE PERFORMED WITH SUPPLY AIR PRESSURE AT APPROX. 60 PSIG, WITH TEMPERATURE SENSORS INSTALLED IN THERMOWELLS, AND WITH WATER TEMPERATURE INCREASED AND DECREASED AT THE RATE OF 1°F PER MINUTE.

LEGEND: AR = AS-RECEIVED  
CC = CALIBRATION CHECK  
TV = THERMOWELL TEMPERATURE (°F)  
W = WATER BATH TEMPERATURE (°F)







05-319-1-90

SFINS No. 6835  
IW 52-20

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, D.C. 20555

June 28, 1982

IE INFORMATION NOTICE NO. 82-20: CHECK VALVE PROBLEMS

Addressees:

All nuclear power reactor facilities holding an operating license (OL) or construction permit (CP).

Purpose:

This information notice is provided as a notification of potentially significant problems pertaining to check valves. It is expected that recipients will review the information for applicability to their facilities. No specific action or response is required at this time.

Description of Circumstances:

A number of problems were recently reported involving swing check valves supplied by two manufacturers. Palisades Nuclear Plant, which is an operating plant, reported severe damage to the internals of 6-inch Alloy Steel Products Company (ALOYCO) swing check valves used in the low-pressure safety injection system (LPSI).

Susquehanna Steam Electric Station, which is under construction, reported three separate problems with Pacific Company swing check valves that range in size from 6 inches to 20 inches installed in the residual heat removal (RHR), reactor core isolation cooling (RCIC), and core spray systems.

The valves are similar in design and service to numerous other swing check valves, manufactured by other companies, that have had similar problems in the past. (Ref. LER 50-298/77-18, 50-255/81-37; AO 50-331/75-23; IE Information Notices 80-41, 81-30 and 81-35)

Internal Damage to ALOYCO Valves:

During required modifications of the LPSI system at the Palisades Nuclear Plant, Consumers Power Co. of Michigan reported that two of the four LPSI swing check valves were found to have internal damage. In both valves the disc nut washer and the disc nut pin were missing and the valve body, clapper arm, disc clapper arm shaft, and clapper arm support were severely worn. The discs were still attached to their clapper arms; however, valve seat and disc sealing surfaces were damaged and leaks from the valves could have been excessive.

8204210389 488



It was subsequently discovered that the remaining two LPSI check valves had similar internal damage. The four LPSI check valves at Palisades were manufactured by ALOYCO about 1968. They are 6-inch swing-type check valves with weld ends for attachment to Schedule 120 piping. All four valves were mounted vertically with the flow direction upward.

The swing check valves have an inline configuration with a ballooned or expanding area in the valve body for movement of the flapper-type disc. The disc is substantially larger than the nominal inside diameter of the pipe or valve. If the disc should become separated from the clapper arm, it would be trapped within the expanded portion of the valve body. This could lead to reduced LPSI flow or (with some small probability) the complete blockage of the line.

Operation of the swing check valve in the direction of flow (normal operation) causes the threaded shaft on the back of the valve disc to strike the valve body as it opens to the full-flow position. (The valve body is the ultimate limiter of disc opening.) During full-flow operation, there apparently is sufficient turbulence to cause the disc to chatter against the valve body. The valves at Palisades, which are used for extended periods during shutdown cooling, exhibited about 1/2 inch of wear of the threaded portion of the disc shaft (greater than the height of the disc nut). Although the disc nuts had been worn away, none of the discs had separated from its clapper arm because of the peening of the shafts to a larger diameter.

The ALOYCO check valves form the boundary between the LPSI and high-pressure safety injection (HPSI) systems at Palisades. The abnormal wear of the check valves was discovered during modifications of the LPSI piping to add leak-testing capability as required by NRC order, dated April 20, 1981, for Event V valve configurations. This order required the licensee to perform periodic leak-testing of check valves that form the interface between a high-pressure system connected to the reactor coolant system (RCS) and a low pressure system whose piping leads outside containment. Event V is defined as the failure of two in-series check valves to function as a pressure isolation barrier between a high-pressure system connected to the RCS and a lower pressure system extending beyond containment. This failure could cause an overpressurization and rupture of the low-pressure system, which would result in a LOCA that bypasses containment and simultaneously render inoperable some of the equipment needed to mitigate a LOCA.

#### Problems With Pacific Valves :

During start-up testing at the Susquehanna Steam Electric Station Unit 1, Pennsylvania Power and Light reported three problems with Pacific check valves: (1) disc assembly to body interference and excessive packing friction, (2) excessive wear at hinge arm/disc stud interface, and (3) disc stud breakage. The Pacific check valves are used in many non-safety systems as well as the residual heat removal, reactor core isolation cooling, and core spray systems.

1. Disc Assembly to Body Interference and Excessive Packing Friction

The interference problem was attributed to tolerance buildup by the valve manufacturer. Undetected, a deficiency of this type could render the valve unable to perform its safety function. The valves were subsequently reworked at Susquehanna. The packing friction problem was solved by changing packing type.


2. Excessive Wear at Hinge Arm/Disc Stud Interface

The excessive wear at the hinge arm/disc stud interface was identified on non-safety related valves. The hinges and discs involved in the excessive wear problem have been replaced in the safety related valves. The licensee will re-inspect the safety related valves to confirm that the modifications have been effective in reducing wear. These inspections will be performed after the valves have operated for a sufficient time period that wear might be expected.

3. Disc Stud Breakage

The problem with the fractured stud, which is an integral part of the disc/stud casting, appears to be similar to a earlier failure of an Anchor/Darling valve (50-298/77-18). Although these failures were similar, the cause of the Susquehanna failures appears to be a metallurgical problem that is limited to the specific valves in this case. In the safety related valves, the licensee is replacing the CA15 discs with discs manufactured from A516 Grade 70 plate with a stud fabricated from the same material threaded and welded to the disc. In the RCIC and HPCI exhaust systems, the swing check valve is being replaced by a lift check valve. The inherent damping action of this type valve is believed by the licensee to make it more able to withstand the erratic steam flow conditions.

If you have any questions regarding this matter, please contact the Regional Administrator of the appropriate NRC Regional Office, or this office.

  
E. L. Jordan, Director  
Division of Engineering  
and Quality Assurance

Technical Contact: M. S. Wegner  
301-492-4511

Attachment:  
List of Recently Issued IE Information Notices

Attachment  
IN 82-20  
June 28, 1982

LIST OF RECENTLY ISSUED  
IE INFORMATION NOTICES

Information Notice No.	Subject	Date of Issue	Issued to
82-19	Loss of High Head Safety Injection Emergency Boration and Reactor Coolant Makeup Capability	6/18/82	All power reactor facilities holding an OL or CP
82-18	Assessment of Intakes of Radioactive Material by Workers	6/11/82	All power reactor facilities holding an OL or CP, other specified licenses
82-17	Overpressurization of Reactor Coolant System	6/10/82	All power reactor facilities holding an OL or CP
82-16	HPCI/RCIC High Steam Flow Setpoints	5/28/82	All power reactor facilities holding an OL or CP
82-15	Notification of the Nuclear Regulatory Commission (NRC)	5/28/82	All NRC licensees and all power reactor facilities holding a CP
82-14	TMI-1 Steam Generator/Reactor Coolant System Chemistry/Corrosion Problem	5/12/82	All power reactor facilities holding an OL or CP
82-13	Failures of General Electric Type HFA Relays	5/10/82	All power reactor facilities holding an OL or CP
82-12	Surveillance of Hydraulic Snubbers	4/21/82	All power reactor facilities holding an OL or CP
82-11	Potential Inaccuracies in Wide Range Pressure Instruments used in Westinghouse Designed Plants	04/09/82	All power reactor facilities holding an OL or CP

OL = Operating License  
CP = Construction Permit

05-319-2-90

SSINS No.: 6835  
IN 86-09

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, D.C. 20555

February 3, 1986

IE INFORMATION NOTICE NO. 86-09: FAILURE OF CHECK AND STOP CHECK VALVES  
SUBJECTED TO LOW FLOW CONDITIONS

Addressees:

All nuclear power reactor facilities holding an operating license (OL) or a construction permit (CP).

Purpose:

This notice is provided to alert recipients of a potentially significant safety problem pertaining to check and stop check valves failing under low flow conditions. It is expected that recipients will review the information for applicability to their facilities and consider actions, if appropriate, to preclude a similar problem occurring at their facilities. However, suggestions contained in this notice do not constitute NRC requirements; therefore, no specific action or written response is required.

Description of Circumstances:

Between late November 1985 and early January 1986, Florida Power and Light's Turkey Point facility experienced numerous failures of the 12 stop check valves in the steam supply system to the auxiliary feedwater pumps. The stop check valves are located upstream and downstream of a motor-operated valve (MOV) that opens when required to initiate auxiliary feedwater flow. The stop check valves are normally open and thus allow steam flow to the pumps while at the same time preventing backflow through the steam line in the event of a steam line break.


The mode of failure of the valve was degradation of the disc and disc nut assembly (see attached sketch) due to low steam flow conditions caused by slight leakage past the normally closed MOV. The low steam flow rate was not sufficient to keep the disc open and the disc assembly then vibrated and chattered causing excessive wear and damage to the valve internals, in particular, the disc assembly. In many cases (three in November and four in January), the disc guide stud had broken off from the disc. This allowed the disc to become cocked in the valve and prevented full closure (thus defeating both the check and stop features of the valve) and full opening (thus restricting steam flow). In addition, the broken disc guide stud was free to travel downstream with steam flow and could have caused damage to equipment and components in the flow path.

The licensee performed a failure analysis of the disc assembly to verify the acceptability of a higher strength material being used in a redesigned disc guide. In addition, the licensee committed to a program of regular radiographic examination of the valves on Unit 3 for the remainder of the refueling cycle. However, the licensee considers this to be an interim repair pending the completion of the study underway by its AFW Enhancement Task Force.

A related series of events was discussed in IE Information Notice 82-26, "RCIC and HPCI Turbine Exhaust Check Valve Failures." In this case the low steam flow rates were the result of testing the RCIC and HPCI turbines at less than rated load. The corrective actions consisted of changes to test procedures, changes to the exhaust system design, and changing to a different check valve style.

The information herein is being provided as an early notification of a possibly significant matter that is still under review by the NRC staff. Recipients should review the information for possible applicability to their facilities. If NRC evaluation so indicates, further licensee actions may be requested.

No specific action or written response is required by this information notice. If you have any questions about this matter, please contact the Regional Administrator of the appropriate regional office or this office.

  
Edward V. Jordan, Director  
Division of Emergency Preparedness  
and Engineering Response  
Office of Inspection and Enforcement


Technical Contacts: George A. Schnebli, RII  
(404)331-4875

Richard J. Kiessel, IE  
(301)492-8119

Attachments:

1. Sketch of Stop Check Globe Valve
2. List of Recently Issued IE Information Notices





LIST OF RECENTLY ISSUED  
 IE INFORMATION NOTICES

Information Notice No.	Subject	Date of Issue	Issued to
86-08	Licensee Event Report (LER) Format Modification	2/3/86	All power reactor facilities holding an OL or CP
86-07	Lack Of Detailed Instruction And Inadequate Observance Of Precautions During Maintenance And Testing Of Diesel Generator Woodward Governors	2/3/86	All power reactor facilities holding an OL or CP
86-06	Failure Of Lifting Rig Attachment While Lifting The Upper Guide Structure At St. Lucie Unit 1	2/3/86	1 power reactor facilities holding an OL or CP
86-05	Main Steam Safety Valve Test Failures And Ring Setting Adjustments	1/31/86	All PWR facilities holding an OL or CP
86-04	Transient Due To Loss Of Power To Integrated Control System At A Pressurized Water Reactor Designed By Babcock & Wilcox	1/31/86	All power reactor facilities holding an OL or CP
86-03	Potential Deficiencies In Environmental Qualification Of Limitorque Motor Valve Operator Wiring	1/14/86	All power reactor facilities holding an OL or CP
86-02	Failure Of Valve Operator Motor During Environmental Qualification Testing	1/6/86	All power reactor facilities holding an OL or CP
86-01	Failure Of Main Feedwater Check Valve Causes Loss Of Feedwater Sy. Integrity And Water-Hamm. Damage	1/6/86	All power reactor facilities holding an OL or CP

OL = Operating License  
 CP = Construction Permit

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, DC 20555

March 31, 1983

INFORMATION NOTICE NO. 83-17: ELECTRICAL CONTROL LOGIC PROBLEM RESULTING  
IN INOPERABLE AUTO-START OF EMERGENCY DIESEL  
GENERATOR UNITSAddressees:

All nuclear power reactor facilities holding an operating licensee (OL) or construction permit (CP).

Purpose:

This information notice is provided as a notification of a potential problem in the control logic circuitry which could adversely affect the auto-start feature provided for diesel generators at nuclear facilities. It is expected that recipients will review the information for applicability to their facilities. No specific action or reference is required.

Description of Circumstances:

Recently the licensee performed a loss of offsite power test at the North Anna Unit 2 Station. The test is conducted periodically and is a technical specification requirement. Specifically, this test is performed to verify the capability of the emergency diesel generators (EMDs) to load-shed and reload the essential emergency busses following loss of an EMD when offsite power is unavailable.

Briefly, the selected emergency bus was "set up" to simultaneously receive electrical power from the offsite power source and the associated EMD. A safety injection test signal was then initiated and the diesel generator unit was manually shut down. These actions were followed by opening the offsite power supply feeder breaker to the selected emergency bus. Given these conditions, the associated EMD did not respond to an auto-start call upon resetting its shutdown relay.

When the licensee investigated the event, he found that the periodic test procedure used to conduct this test did not specifically address a 60-second time delay feature in the diesel generator's restart circuitry. The purpose of this time delay is to allow the diesel generator to come to a complete stop before attempting a restart. This time delay prevents fuel from being supplied to the diesel generator for 60 seconds after the shutdown relay has been manually reset by a remote pushbutton located in the control room.

Further review of this event determined that when the shutdown relay was manually reset (because of the presence of the safety injection signal mentioned above), the compressed starting air was admitted to start the diesel even though no fuel was admitted during the 60-second delay period. At the end of this delay,

fuel was admitted but the supply of compressed air used to rotate the engine for a restart attempt had been consumed. Thus, the diesel unit effectively became inoperable until the air storage tanks were repressurized.

This licensee's action taken to preclude this event from recurring included modifying the test procedures so as to require the control selector switch for the diesel generator being tested to be placed in the "local" position before the shutdown relay is reset. This action, in effect, blocks the auto-start diesel signal from activating the air start solenoid for the diesel generator being tested. Following this action, the shutdown relay may be manually reset and the time delay permitted to run out. Subsequently, the control selector switch may be returned to its normal "remote" position at which time the diesel generator unit being tested should auto-start and reload its associated emergency busses in accordance with design requirements.

During an in-depth study of the control logic circuitry for the diesel generator units at Hatch Unit 1 Station, a potential control logic problem was identified which is identical to the problem at North Anna Unit 2 Station. Subsequently, the licensee implemented a design change which now allows fuel to be supplied into the diesel unit concurrent with the logic signal calling for diesel generator "re-start."

Since North Anna Unit 2 is a pressurized water reactor power plant and Hatch Unit 1 is a boiling water reactor power plant, the control logic problem, as discussed, has strong generic implications and may affect many of the addressees of this information notice. Licensees should be aware that since the local/remote control switch is located in the control room and is placed in the "remote" position during normal plant operation, it will require direct immediate operator corrective action to preclude failure of the diesel generator to re-start under the set of conditions discussed above. On this basis, we suggest these addressees review this information for applicability to the control logic circuitry of diesel generator units in use at their plant.

No written response to this notice is required. If you have questions regarding this matter, please contact the Regional Administrator of the appropriate NRC Regional Office, or this office.

*William P. Mills* <sup>for</sup>  
Edward L. Jordan, Director  
Division of Emergency Preparedness  
and Engineering Response  
Office of Inspection and Enforcement

CONTACT: V. D. Thomas  
301-492-4755

Attachment:  
List of Recently Issued Information Notices

Attachment  
IN 83-17  
March 31, 1983

LIST OF RECENTLY ISSUED  
IE INFORMATION NOTICES

Information Notice No.	Subject	Date of Issue	Issued to
83-16	Contamination of the Auburn Steel Property with Cobalt-60	03/30/83	All Material licensees
83-15	Falsified Pre-Employment Screening Records	03/25/83	All power reactor facilities holding an OL or CP
83-14	Dewatered Spent Ion Exchange Resin Susceptibility to Exothermal Chemical Reaction	03/21/83	All power reactor facilities holding an OL or CP
83-13	Design Misapplication of Bergen-Paterson Standard Strut Restraint Clamp	03/21/83	All power reactor facilities holding an OL or CP
83-12	Incorrect Boron Standards	03/18/83	All power reactor facilities holding an OL or CP
83-11	Possible Seismic Vulnerability of Old Lead Storage Batteries	03/14/83	All power reactor facilities holding an OL or CP
83-10	Clarification of Several Aspects Relating to Use of NRC-Certified Transport Packages	03/11/83	All NRC-licensed facilities and registered users of NRC-Certified transport packages
83-09	Safety and Security of Irradiators	03/09/83	All power reactor facilities holding an OL or CP
83-08	Component Failures Caused by Elevated DC Control Voltage	03/09/83	All power reactor facilities holding an OL or CP
83-07	Nonconformities with Materials Supplied by Tube Line Corporation	03/07/83	All power reactor facilities holding an OL or CP

OL = Operating License  
CP = Construction Permit



UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D. C. 20555

OFFICIAL BUSINESS  
PENALTY FOR PRIVATE USE \$300

FIRST CLASS MAIL  
POSTAGE & FEES PAID  
USNRC  
WASH D C  
PERMIT No. 587

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, D.C. 20555

August 5, 1983

IE INFORMATION NOTICE NO. 83-51: DIESEL GENERATOR EVENTS

Addressees:

All nuclear power facilities holding an operating license (OL) or a construction permit (CP).

Purpose:

This information notice is provided to bring to the attention of licensees and construction permit holders some events and experience of generic diesel generator problems and corrective action taken. It is expected that recipients will review the information for applicability to their facilities. No other action or response is required.


Description of Circumstances:

In its continuing review of licensee event reports (LERs), NRC has identified during the past five months more than 100 LERs pertaining to diesel generator problems. Most of these appear to be material, equipment, or component failures. No single common trend can be identified.

NRC is concerned about the large number of diesel generator events. During discussions with diesel manufacturers and licensees, it appears that many of these events could have been eliminated or prevented by implementation of a conscientious maintenance and inspection program as well as monitoring equipment through a plant's trend program. Some licensees have instituted such a program to determine the underlying cause of the failures (see IE Information Notice 82-10) and to prevent their recurrence. Components or materials that have experienced failures are monitored or inspected more frequently. Many affected items are repaired or replaced before actual breakdown. For example, cooling water heat exchangers that were found to be ineffective after a certain period of time because of tube fouling were replaced. Cooling jacket circulating water pump bearings are inspected for wear and replaced in certain intervals. Pressure switches and timers have been found with drifting setpoints and were recalibrated or replaced frequently.

Because of the large number of diesel generator events it is not feasible to describe all the events reported. However, Attachment 1 to this information notice gives several representative examples and corrective actions taken.

If there are any questions regarding this matter, please contact the Regional Administrator of the appropriate NRC Regional Office, or this office.



Edward L. Jordan, Director  
Division of Emergency Preparedness  
and Engineering Response  
Office of Inspection and Enforcement

Technical Contact: Wolfgang Laudan, IE  
301-492-9759

Attachments:

1. Selected Examples of Licensee Event Reports  
Related to Emergency Diesel Generators
2. List of Recently Issued IE Information Notices

SELECTED EXAMPLES OF LICENSEE EVENT REPORTS AND VENDOR REPORTS  
RELATED TO EMERGENCY DIESEL GENERATORS

QUAD-CITIES 2, OCTOBER 6, 1982

During the monthly preventive maintenance testing of Unit 2 diesel generator, the diesel tripped on high temperature 10 minutes after loading. The cause was determined to be fouling in the cooling water heat exchanger. The heat exchanger was replaced and the diesel testing was satisfactorily completed. The licensee placed the heat exchanger on a preventive maintenance schedule for cleaning.

SEQUOYAH 2, OCTOBER 20, 1982

During a performance test of diesel generator 2B-B, the cooling jacket circulating water pump on the diesel generator was found to be inoperable as a result of a ball bearing failure in the pump. The bearing was replaced and the diesel generator was returned to service.

SUSQUEHANNA, OCTOBER 27, 1982

During a performance test of a diesel generator, the diesel generator tripped on high vibration. It was postulated that a vibration switch and a pressure regulator were both involved in the trip. Both were repaired and the diesel generator was returned to service. The equipment will be monitored through the plant's trend program.

BRUNSWICK 1, NOVEMBER 5, 1982

During a quick start testing program of diesel generator No. 4, the diesel generator tripped on "low lube oil pressure." The same problem occurred 2 days later on the same unit. Both events resulted from intermittent failures of the "low lube oil pressure start time relay" (STR). The relay timed out before actual pressure was above the low trip setpoint. The relay was replaced and the diesel testing was satisfactorily completed.

DRESDEN 3, NOVEMBER 9, 1982

During a Unit 3 diesel generator surveillance test, the diesel generator tripped on low cooling water pressure. A defective low cooling water pressure switch caused this event. The switch was replaced and the testing was satisfactorily completed.

RANCHO SECO, MAY 25, 1983

During startup testing, the diesel generator would not reach full operating speed. The Woodward governor speed adjustment on the unit stopped at about 650 rpm. It was found that the pointer disk was hanging up behind the dial plate. The manufacturer recommended filing about 1/16-inch off the pointer disk to allow free movement. After that the diesel achieved proper speed.

CALVERT CLIFFS, APRIL 7, 1983

During a routine inspection of the intake air check valve of No. 11 diesel generator, the licensee found a check valve holding pin sheared and the check valve loose. The same valve on two other diesel generators at Calvert Cliffs had been found to be cracked when inspected during 1982. The disk of one of these valves was found broken in two pieces. The engines in question are Fairbanks Morse Model 38TD81/8.

Because these failures did not render the diesel generators inoperable, as evidenced by successful completion of weekly operational tests, no LER was issued. The licensee pointed out that there were internal baffles between the check valves and the diesel turbocharger which made it unlikely to have a piece of the check valve enter the diesel's turbocharger. The check valve in question diverts air between the diesel turbocharger and integral air-blower. Failure of the check valve would result in air being available through the turbocharger at low loads and would affect the load control.

SHOREHAM, OCTOBER 15, 1982; APRIL 15, 1983; APRIL 20, 1983; MAY 4, 1983

During preoperational testing of Shoreham's three Transamerica Delaval, Inc. emergency diesel generators, the following mechanical problems were identified in the past 9 months and reported by the licensee under 10 CFR 50.55 (e):

October 15, 1982 - The jacket waterpump shaft failed.  
April 15, 1983 - The engine head cracked.  
April 20, 1983 - The fuel injection line failed.  
May 4, 1983 - The rocker arm bolt failed.

Approximately 2 years before these problems occurred, the licensee discovered the following:

1. Loose hardware in cam gears during initial onsite inspection.
2. Multiple broken cylinder head exhaust bolts resulting from insufficient pipe guide clearances in the exhaust manifold.
3. Cracks in the fuel oil ejector that connects to the fuel oil drip line.
4. Absence of a drilled passageway for the relief valve on one lube oil pump line as required by design.
5. Leaky lube oil cooler tubes resulting from improper rolling in the tube sheet.
6. Cracks in rocker arm push rod socket (or cup).
7. Cam gear fitted bolts not installed at the factory as required.

The problems were corrected under the surveillance of vendor representatives. Nuclear sites with Transamerica Delaval diesel generators are listed on page 4 of this attachment.



LOUIS ALLIS REPORTED TWO DIFFERENT POTENTIAL PROBLEMS, MAY 20, 1983

(Louis Allis is the successor to Belouit Power Systems, Inc., and to Colt-Fairbanks Engine Division)

1. At the diesel generator in the Clinton Nuclear Plant, a three-phase rectifier assembly in the exciter was not connected in parallel, which could cause field winding insulation to deteriorate. Louis Allis field service took corrective action by making the necessary connections.
2. Detroit Edison experienced high vibration on its diesel generator. The cause was loose pole wedges. Louis Allis performed a detailed engineering evaluation of this problem and found that in 1976 a material change from HRS 1020 steel to 1045 steel was made. This means that diesel generators manufactured before this change may experience the same loose pole wedge problem. The affected plants are Fermi, Millstone Unit 2, and Hatch. These plants were notified by copy of the Part 21 report dated May 20, 1983.

TRANSAMERICA DELAVAL - 1981 TO 1983

The manufacturer reported the following turbocharger thrust bearing lubrication problem:

The design of the lubricating oil system permits the oil flow to the turbocharger bearing only when the diesel generator is running. When the diesel generator is in the standby mode, the turbocharger bearing lube oil system is bypassed to prevent a possible fire hazard should pressurized oil leak around the bearing seals onto hot impellers. Therefore, during startup, a sufficient amount of oil would not be available to adequately lubricate the turbocharger bearing. Because diesels are started once a month and run for a short length of time, premature bearing wear was experienced because of insufficient lubrication.

At San Onofre, the wear rate for this condition after 100 hours of operation was equivalent to 15,000 to 20,000 hours of continuous operation.

To ensure proper lubrication during startup, a design modification in the form of a lubrication oil drip system causing the lubricating oil to drip on the bearings through an orifice at a given rate was proposed, installed, and tested. An alternate method to this design modification is a change in the operating procedure. Before a monthly start, an operator would manually run the auxiliary lube oil pump for 30 to 60 seconds and confirm lube oil pressure. In the event of an emergency start, the bearings will function until oil pressure is developed.

Transamerica Delaval reported that the following nuclear sites were affected:

Shoreham	Perry	WPPSS 4
Grand Gulf	Bellefonte	Midland 1 & 2
Catawba	WPPSS 1	Hartsville
San Onofre	Comanche Peak 1 & 2	Phipps Bend

The licensees of the above plants were notified by copy of Transamerica Delaval Part 21 report dated September 19, 1980.

LIST OF RECENTLY ISSUED  
IE INFORMATION NOTICES

Information Notice No.	Subject	Date of Issue	Issued to
83-50	Failure of Class 1E Safety-Related Switchgear Circuit Breakers to Close on Demand	8/1/83	All power reactor facilities holding an OL or CP
83-49	Sampling and Prevention of Intrusion of Organic Chemicals into Reactor Coolant Systems	07/25/83	All power reactor facilities holding an OL or CP
83-48	Gaseous Effluent Releases of Radioactive Iodine-125 and Iodine-131 in Excess of NRC Limits	07/14/83	NRC licensed byproduct material licensees, including medical and academic institutions, radiopharmaceutical suppliers, and industrial research
83-47	Failure of Hydraulic Snubbers as a Result of Contaminated Hydraulic Fluid	07/12/83	All power reactor facilities holding an OL or CP
83-46	Common-Mode Valve Failures Degrade Surry's Recirculation Spray Subsystem	07/11/83	All power reactor facilities holding an OL or CP
83-45	Environmental Qualification Test Of General Electric Company "CR-2940" Position Selector Control Switch	07/01/83	All power reactor facilities holding an OL or CP
83-44	Potential Damage to Redundant Safety Equipment as a Result of Backflow Through the Equipment	07/01/83	All power reactor facilities holding an OL or CP
83-43	Improper Settings of Intermediate Range (IR) High Flux Trip Setpoints	06/24/83	All power reactor facilities holding an OL or CP
83-42	Reactor Mode Switch Modifications	06/23/83	All BWR facilities holding an OL or CP

OL = Operating License  
CP = Construction Permit

120555063633 1 00000  
US NRC  
IE-DIV EMER PREP & ENR RESPON  
DIVISION DIRECTOR  
EWS-305A  
WASHINGTON DC 20555

05-319-5-90

SSINS No.: 6835  
IN 85-28

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, DC 20555

April 9, 1985

IE INFORMATION NOTICE NO. 85-28: PARTIAL LOSS OF AC POWER AND DIESEL  
GENERATOR DEGRADATION

Addressees:

All nuclear power reactor facilities holding an operating license (OL) or a construction permit (CP).

Purpose:

This notice is provided to inform recipients of a potential problem with diesel generator voltage regulation that might prevent the diesel generators from loading on to their safety buses. It is expected that recipients will review the information for applicability to their facilities and consider actions, if appropriate, to preclude a similar problem occurring at their facilities. However, suggestions contained in this information notice do not constitute NRC requirements; therefore, no specific action or written response is required.

Description of Circumstances:

On January 31, 1985, WNP 2 was at 100 percent power when a lockout relay, used in the offsite power supply fast transfer logic, spuriously tripped. This was an abnormal partial actuation that caused the 500 kV generator output breaker to open and the circuit breakers from the startup transformer to close on the plant buses even though the normal auxiliary transformers were not disconnected from the same plant buses. The opening of the 500 kV output breaker initiated the digital-electrohydraulic control system overspeed protection circuit which closed the turbine control valves. The turbine control valve fast closure caused a reactor scram as designed.

As a result of this abnormal condition, the generator remained connected to the 230 kV grid via the auxiliary and startup transformers. (See attached simplified diagram illustrating abnormal breaker alignment during the first seconds of this transient.) After 4 seconds, a breaker in the 230 kV line to the startup transformer opened, leaving the plant without non-safety-related power. Two of the buses without power, SM-1 and SM-3, ordinarily feed safety-related buses SM-7 and SM-8. As a result of losing power to two safety-related buses, the backup transformer, which is powered by a 115 kV line, was automatically connected to the safety-related buses and the diesel generators for these buses started, but were not required to assume load.

~~8504050047~~

SIP



In the control room, there were false indications such as high containment pressure and valid indications of vessel low level (level 2, -50 inches). The high pressure core spray (HPCS) and reactor core isolation cooling system (RCIC) started on the low level signal.

Eventually, the main generator's protective circuits actuated the balance of the fast transfer logic, causing the auxiliary transformer to separate from the plant buses.


Discussion:

After the event, it was found that the output voltage had been set incorrectly on diesel generators DG-1 and DG-2. If the backup transformer or its supply had failed, the diesel generators would not have loaded on the safety buses because the voltage regulators were set at their lowest voltage set point. The safety buses have protective relaying that prevents the diesel generators from loading on the safety-related buses if their output voltage deviates too much from nominal. There was no control room alarm indicating the diesel generator output voltage was too low to permit loading diesel generators on their safety-related buses.

The condition was caused during troubleshooting of the voltage regulators for DG-1 and DG-2. These voltage regulators have a manual "raise/lower" handle in the control room which permitted their output voltage to be adjusted even though the diesel was not running. If the diesels were not running, as was the case during the troubleshooting, there was no indication of the generator output voltage and, thus, no indication of the voltage setting of the voltage regulator. The type of voltage regulator used on DG-1 and DG-2 allowed for inadvertent degradation without indication or alarm in the control room. This situation did not exist on DG-3, which is dedicated solely for the HPCS and has an automatic voltage set point reset upon start of the diesel generator.

A number of corrective measures have been or will be taken as a result of this event. The licensee has modified the voltage regulators for DG-1 and DG-2 so that the output voltage of the diesel generators can be adjusted only while the diesels are running. The licensee is pursuing an automatic voltage set point reset feature for these diesel generators. The licensee will evaluate the efficacy of control room annunciation for high/low diesel generator output voltage. The licensee also has modified the offsite power supply fast transfer logic so that if a partial spurious actuation occurs again, then the balance of the logic will actuate. The licensee has modified procedures and training to reflect the lessons learned from this event.

No specific action or written response is required by this information notice. If you have any questions about this matter, please contact the Regional Administrator of the appropriate NRC regional office or this office.

  
Edward L. Jordan, Director  
Division of Emergency Preparedness  
and Engineering Response  
Office of Inspection and Enforcement


Technical Contact: Eric W. Weiss, IE  
(301) 492-9005

Attachments:

1. Simplified Diagram Illustrating Abnormal Breaker Alignment
2. List of Recently Issued IE Information Notices

# WNP-2\*

(SIMPLIFIED ONE LINE DIAGRAM)



\* Abnormal breaker alignment caused by partial spurious actuation of the Offsite Power Supply Fast Transfer Logic

LEGEND :

■ = CLOSED  
□ = OPEN

Attachment 1  
IN 85-28  
Apr 11 9, 1985

LIST OF RECENTLY ISSUED  
 IE INFORMATION NOTICES

Information Notice No.	Subject	Date of Issue	Issued to
85-27	Notifications To The NRC Operations Center And Reporting Events In Licensee Event Reports	4/3/85	All power reactor facilities holding an OL or CP
85-26	Vacuum Relief System For Boiling Water Reactor Mark I And Mark II Containments	4/2/85	All BWR facilities having a Mark I or Mark II containment and holding an OL or CP
85-25	Consideration Of Thermal Conditions In The Design And Installation Of Supports For Diesel Generator Exhaust Silencers	4/2/85	All power reactor facilities holding an OL or CP
85-24	Failures Of Protective Coatings In Pipes And Heat Exchangers	3/26/85	All power reactor facilities holding an OL or CP
85-23	Inadequate Surveillance And Postmaintenance And Post-modification System Testing	3/22/85	All power reactor facilities holding an OL or CP
85-22	Failure Of Limitorque Motor-Operated Valves Resulting From Incorrect Installation Of Pinon Gear	3/21/85	All power reactor facilities holding an OL or CP
85-21	Main Steam Isolation Valve Closure Logic	3/18/85	All PWR facilities holding an OL or CP
85-20	Motor-Operated Valve Failures Due To Hammering Effect	3/12/85	All power reactor facilities holding an OL or CP
85-19	Alleged Falsification Of Certifications And Alteration Of Markings On Piping, Valves And Fittings	3/11/85	All power reactor facilities holding an OL or CP

OL = Operating License  
 CP = Construction Permit

05-319-6-90

SSINS No.: 6835  
IN 85-73

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, D.C. 20555

August 23, 1985

IE INFORMATION NOTICE NO. 85-73: EMERGENCY DIESEL GENERATOR CONTROL CIRCUIT  
LOGIC DESIGN ERROR

Addressees:

All nuclear power reactor facilities holding an operating license (OL) or a construction permit (CP).

Purpose:

This information notice is to alert recipients of a potentially significant emergency diesel generator (EDG) control logic error that could prevent transfer to the emergency bus while the EDG is in the "maintenance shutdown" mode. It is expected that recipients will review the information for applicability to their facilities and consider actions, if appropriate, to preclude a similar problem occurring at their facilities. However, suggestions contained in this information notice do not constitute NRC requirements; therefore, no specific action or written response is required.

Description Of Circumstances:

According to the design, the EDGs at Rancho Seco Nuclear Power Generating Station enter the maintenance shutdown control mode whenever they are normally shut down from the control room or the remote EDG control panel. On June 1, 1985, the plant was shut down for refueling, an EDG was in the maintenance shutdown control mode after being secured from an operational condition (idling at 600 rpm with the output breaker open), when an emergency bus was de-energized for planned work on a parallel bus. This created an undervoltage condition equivalent to a loss of offsite power (LOOP) on the emergency bus. The diesel generator sped up to the design speed but the EDG output breaker continuously cycled open and closed, thereby rendering the EDG set inoperable.

Investigation by the licensee indicates that the cycling of the EDG output breaker was the result of a design error in the EDG control circuit logic. According to the licensee, the design deficiency affects proper response of the EDG set when it is operating in the maintenance shutdown control mode. Normal surveillance testing would not discover the control circuit design error because surveillance is not done in the maintenance shutdown control mode. The June 1, 1985 event at Rancho Seco represents the first time in the life of the plant that an undervoltage signal occurred with an EDG in the maintenance shutdown control mode.

8508210321

3pp




When an EDG is secured from operation, the control circuit logic places it in the maintenance shutdown control mode. In this mode, the control logic opens its output breaker and reduces its speed from 900 to 600 rpm. The EDG then idles at 600 rpm for 15 minutes before coasting down to rest.

If a LOOP should occur while an EDG is in the maintenance shutdown control mode, the undervoltage signal causes it to speed back up to 900 rpm and to close its output breaker. This would cause the undervoltage signal to drop out. However, the maintenance shutdown control mode does not drop out for 30 seconds after the receipt of the undervoltage signal because of the control circuit design error. Thus, the maintenance shutdown control logic senses that the EDG output breaker is closed, opens the breaker, and resets the 15-minute timer for the maintenance shutdown control mode. As soon as the EDG output breaker opens, the undervoltage signal recurs and the EDG output breaker closes in response to the LOOP. The EDG output breaker continues to cycle open and closed as this process repeats itself. At Rancho Seco, this control circuit logic design error has been corrected by installing a relay to de-energize the maintenance shutdown control logic immediately upon receipt of an undervoltage signal.

The Rancho Seco plant utilizes General Motors (GM) Model 20-465-E4 diesel generators with a 2750 kw nameplate rating. According to the licensee, the design error was in the interface provided by the Architect-Engineer (Bechtel) to the shutdown control logic provided by GM. Bechtel has advised the NRC that the Rancho Seco diesel generator control logic is unique and other plants designed by them are not affected.

No specific action or written response is required by this information notice. If you have any questions about this matter, please contact the Regional Administrator of the appropriate regional office or this office.

  
Edward L. Jordan, Director  
Division of Emergency Preparedness  
and Engineering Response  
Office of Inspection and Enforcement

Technical Contact: W. Swenson, NRR  
(301) 492-7876

R. Singh, IE  
(301) 492-8985

Attachment: List of Recently Issued Information Notices

Attachment 1  
IN 85-73  
August 23, 1985

LIST OF RECENTLY ISSUED  
IE INFORMATION NOTICES

Information Notice No.	Subject	Date of Issue	Issued to
85-72	Uncontrolled leakage Of Reactor Coolant Outside Containment	8/22/85	All power reactor facilities holding an OL or CP
85-71	Containment Integrated Leak Rate Tests	8/22/85	All power reactor facilities holding an OL or CP
85-70	Teletherapy Unit Full Calibration And Qualified Expert Requirements (10 CFR 35.23 And 10 CFR 35.24)	8/15/85	All material licensees
85-69	Recent Felony Conviction For Cheating On Reactor Operator Requalification Tests	8/15/85	All power reactor facilities holding an OL or CP
85-68	Diesel Generator Failure At Calvert Cliffs Nuclear Station Unit 1	8/14/85	All power reactor facilities holding an OL or CP
85-42 Rev. 1	Loose Phosphor In Panasonic 800 Series Badge Thermo-luminescent Dosimeter (TLD) Elements	8/12/85	Materials and fuel cycle licensees
85-67	Valve-Shaft-To-Actuator Key May Fall Out Of Place When Mounted Below Horizontal Axis	8/8/85	All power reactor facilities holding an OL or CP
85-66	Discrepancies Between As-Built Construction Drawings And Equipment Installations	8/7/85	All power reactor facilities holding an OL or CP
85-65	Crack Growth In Steam Generator Girth Welds	7/31/85	All PWR facilities holding an OL or CP

OL = Operating License  
CP = Construction Permit

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D.C. 20545

OFFICIAL BUSINESS  
PENALTY FOR PRIVATE USE \$300

FIRST CLASS MAIL  
POSTAGE & FEES PAID  
USNRC  
WASH D C  
PERMIT No. 567

05-319-7-90

SSINS No.: 6835  
IN 85-91

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, D.C. 20555

November 27, 1985

IE INFORMATION NOTICE NO. 85-91: LOAD SEQUENCERS FOR EMERGENCY DIESEL GENERATORS

Addressees:

All nuclear power reactor facilities holding an operating license (OL) or a construction permit (CP).

Purpose:

This information notice is provided to advise licensees and applicants of potential design deficiencies that could bypass load sequencers, thereby causing loss of redundant emergency diesel generators (EDGs). Recipients are expected to review the information for applicability to their facilities and consider actions, if appropriate, to preclude similar problems occurring at their facilities. However, suggestions contained in this information notice do not constitute NRC requirements; therefore, no specific action or written response is required.

Description of Circumstances:

On August 22, 1985, the licensee for the Duane Arnold nuclear plant discovered that an accident signal and the loss of the standby transformer (a source of offsite electric power) would cause engineered safety feature (ESF) loads to be applied as a single block load onto the EDGs (the sources of onsite electric power), which would likely cause loss of both EDGs.

Pending replacement of the unit auxiliary transformer (lost in a transformer fire in October 1984), the licensee was operating the plant with the non-safety-related loads on the station startup transformer and the safety-related loads on the station standby transformer. The plant design objective was to sequence the ESF loads onto the EDGs if offsite power to the ESF buses should be lost and an accident signal was present. The licensee's training staff realized that the logic and sensors used to determine the availability of off-site power were such that the offsite power feeder breakers to the ESF buses could be tripped, but offsite power would be indicated as being still available. Under these conditions the design would cause the ESF diesel generator load sequencers to be bypassed.

To justify continued safe operation, the licensee has temporarily placed certain sequencer test switches in the test position, which forces the sequencers to function even though offsite power is sensed as being available.


For the longer term, the licensee is developing a permanent design change which is to be reviewed by the NRC.

Discussion:

The design of the electric power system at the Duane Arnold nuclear plant includes features to sequence ESF loads onto the EDGs, but not to sequence loads onto offsite power. In a sense, these design objectives are in conflict; that is, one is for sequencing and the other is for not sequencing. When design objectives are potentially conflicting, careful analysis is necessary to ensure that failures of various types do not result in implementation of the improper objective. In this case, the logic was designed so that if any source of offsite power is "available" (such as at either the standby transformer or the startup transformer) the ESF load sequencers would be bypassed. Thus, if the standby transformer were lost, causing a loss of power to the safety-related loads, the logic would still indicate offsite power as available. This design was provided by Bechtel Corporation.

The result was the potential for an interaction between the offsite electric power system and the onsite electric power system that could have caused the loss of redundant sources of onsite power. Such an interaction is incompatible with the requirements of 10 CFR 50, Appendix A, General Design Criterion No. 17, "Electric Power Systems." The Duane Arnold original design was such that the availability of offsite electric power was determined indirectly; that is, by an upstream measurement rather than directly at the ESF buses. This deficiency existed in the original plant design and was not discovered when the design was reviewed again by the licensee after the loss of the unit auxiliary transformer in October 1984.

No specific action or written response is required by this information notice. If you have questions about this matter, please contact the Regional Administrator of the appropriate NRC regional office or this office.



Edward L. Jordan, Director  
Division of Emergency Preparedness  
and Engineering Response  
Office of Inspection and Enforcement

Technical Contacts: J. T. Beard, NRR  
(301) 492-7465

Eric Weiss, IE  
(301) 492-9005

Attachment: List of Recently Issued IE Information Notices



LIST OF RECENTLY ISSUED  
 IE INFORMATION NOTICES

Information Notice No.	Subject	Date of Issue	Issued to
85-58 Sup. 1	Failue Of A General Electric Type AK-2-25 Reactor Trip Breaker	11/19/85	All power reactor facilities designed by B&W and CE holding an OL or CP
85-90	Use Of Sealing Compounds In An Operating System	11/19/85	All power reactor facilities holding an OL or CP
85-89	Potential Loss Of Solid-State Instrumentation Following Failure Of Control Room Cooling	11/19/85	All power reactor facilities holding an OL or CP
85-88	Licensee Control Of Contracted Services Providing Training	11/18/85	All power reactor facilities holding an OL or CP
85-87	Hazards Of Inerting Atmospheres	11/18/85	All power reactor facilities holding an OL or CP; and fuel facilities
85-86	Lightning Strikes At Nuclear Power Generating Stations	11/5/85	All power reactor facilities holding an OL or CP
85-85	Systems Interaction Event Resulting In Reactor System Safety Relief Valve Opening Following A Fire-Protection Deluge System Malfunction	10/31/85	All power reactor facilities holding an OL or CP
85-84	Inadequate Inservice Testing Of Main Steam Isolation Valves	10/30/85	All power reactor facilities holding an OL or CP
85-83	Potential Failures Of General Electric PK-2 Test Blocks	10/30/85	All power reactor facilities holding an OL or CP

OL = Operating License  
 CP = Construction Permit

*facture*

SSINS No.: 6835  
IN 84-69

*05-319-8-90*

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, D.C. 20555

August 29, 1984

IE INFORMATION NOTICE NO. 84-69: OPERATION OF EMERGENCY DIESEL GENERATORS

Addressees:

All nuclear power reactor facilities holding an operating license (OL) or construction permit (CP).

Purpose:

This notice is provided to alert recipients of potentially significant safety problems that can arise when one or more emergency diesel generators (EDGs) are operated in modes (such as in parallel with the offsite power sources) other than the prescribed standby service mode. Experience has shown that such a practice can lead to a complete loss of ac power to safety buses. It is expected that recipients will review this information for applicability to their facilities and consider actions, if appropriate, to preclude similar problems occurring at their facilities. However, suggestions contained in this notice do not constitute NRC requirements; therefore, no specific action or written response is required.

Description of Circumstances:

On May 17, 1983, at Fort St. Vrain Unit 1, with the reactor in a shutdown condition and one of the two EDGs out of service for maintenance, the offsite power system started experiencing problems as a result of high winds and snow. As a precautionary measure, the available EDG was started and tied to the associated safety bus in parallel with the offsite power source. Approximately half an hour later, all offsite power to the plant was lost and the output breaker of the operating EDG tripped, apparently on overload. As a result, the plant was without all ac power, except for the inverter ac power off the dc power system, for approximately half an hour until the EDG was restored. The offsite power was restored after another hour.

Grand Gulf Nuclear Station Unit 1 was in a startup mode on May 7, 1984, when a partial loss of offsite power occurred as a result of heavy winds and rain. This caused automatic starting and loading of the Division III EDG. While paralleling the EDG with the offsite power grid in order to restore normal power lineup, the EDG tripped on reverse power. Later, the site entered a tornado watch and all three EDGs were started and loaded on their respective buses in parallel with the offsite power grid. An hour and a half later, the Division II EDG tripped on reverse power, apparently as a result of the grid voltage fluctuations during the storm and a low reverse power trip set point.

8408270459 *4pp*

## Discussion

The EDGs are provided as sources of standby onsite electric power in the event that offsite power is lost. Regulatory requirements have long been to minimize the probability of losing the onsite sources when power from the offsite transmission network (grid) is disturbed or lost. More specifically, the NRC Standard Review Plan prohibits the use of EDGs for purposes other than supplying standby power, when needed, and permits interconnection of the onsite and offsite sources only for short periods of time for the purpose of EDG load testing. During such testing, only one of the redundant EDGs is to be paralleled at any one time, leaving the other EDG(s) available in standby service.

Although operators may be tempted to start the EDGs when offsite power is threatened or undergoing disturbances, running the EDGs is likely to be more of a hindrance than a help. If an EDG is paralleled with the offsite power system, it is vulnerable to loss from any of the normal protective features such as overload or reverse power, especially at the moment that offsite power is interrupted. Such a practice is contrary to the intent of General Design Criterion 17. To serve as a dependable backup power source, the EDGs must be kept separate from the offsite source.


One scheme suggested was to start the EDGs in anticipation of the loss of offsite power. If dummy loads are not included in the plant design, the operator is forced either to load the EDG or leave it at no-load idle. Operating experience reported some years ago in NUREG/CR-0660, "Enhancement of Onsite Diesel Generator Reliability," indicates that running an EDG at no-load or light loads may cause other EDG problems.

Another scheme suggested was to run the EDGs on the safety buses but to isolate these buses from the offsite power system. While this appears, on the surface, to achieve the desired independence, licensees need to consider other aspects of the situation. In most plant designs, safety loads (needed for either an accident situation or safe shutdown without an accident) will not be automatically sequenced onto the EDG if the bus is isolated and the EDG is providing power to the bus.

Applicants and licensees are expected to review this information for applicability to the onsite power system at their facilities and to initiate appropriate actions such as management directives and training to preclude similar problems from occurring at their facilities.

IN 84-69  
August 29, 1984  
Page 3 of 3

If you have any questions regarding this matter, please contact the Regional Administrator of the appropriate regional office, or this office.



Edward L. Jordan, Director  
Division of Emergency Preparedness  
and Engineering Response  
Office of Inspection and Enforcement

Technical Contacts: J. T. Beard, NRR  
(301) 492-7465

R. N. Singh, IE  
(301) 492-0868

Attachment: List of Recently Issued IE Information Notices

LIST OF RECENTLY ISSUED  
IE INFORMATION NOTICES

Information Notice No.	Subject	Date of Issue	Issued to
84-68	Potential Deficiency in Improperly Rated Field Wiring to Solenoid Valves	08/21/84	All power reactor facilities holding an OL or CP.
84-67	Recent Snubber Inservice Testing with High Failure Rates	08/17/84	All power reactor facilities holding an OL or CP.
84-66	Undetected Unavailability of the Turbine-Driven Auxiliary Feedwater Train	08/17/84	All power reactor facilities holding an OL or CP.
84-65	Underrated Fuses Which May Adversely Affect Operation of Essential Electrical Equipment	08/16/84	All power reactor facilities holding an OL or CP.
84-64	BWR High-Pressure Coolant Injection (HPCI) Initiation Seal-In and Indication	08/15/84	All BWR licensees and applicants for an OL.
84-63	Defective RHR Replacement Piping	08/13/84	All power reactor facilities holding an OL or CP.
84-62	Therapy Misadministrations To Patients Undergoing Cobalt-60 Teletherapy Treatments	08/10/84	All NRC licensees authorized to possess and use sealed sources in teletherapy units.
84-61	Overexposure of Diver in Pressurized Water Reactor (PWR) Refueling Cavity	08/08/84	All power reactor facilities holding and OL or CP.
84-60	Failure of Air-Purifying Respirator Filters To Meet Efficiency Requirement	08/06/84	All power reactor facilities holding an OL or CP.
84-59	Deliberate Circumventing of Station Health Physics Procedures	08/06/84	All power reactor facilities holding an OL or CP.

OL = Operating License  
CP = Construction Permit



UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D.C. 20555

FIRST CLASS MAIL  
POSTAGE & FEES PAID  
USNRC  
WASH D C  
PERMIT NO. 582

OFFICIAL BUSINESS  
PENALTY FOR PRIVATE USE \$300

120555063533 1 99999  
US NRC  
IE-DIV EMER PREP & ENGR RESPON  
DIVISION DIRECTOR  
EW-359  
WASHINGTON DC 20555

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, DC 20555

05-319-9-90

February 24, 1986

IE INFORMATION NOTICE NO. 84-69, SUPPLEMENT 1: OPERATION OF EMERGENCY DIESEL GENERATORS

Addressees:

All nuclear power reactor facilities holding an operating license (OL) or a construction permit (CP).

Purpose:

Information Notice 84-69, issued on August 29, 1984, was provided to alert recipients of potentially significant safety problems that can arise when one or more emergency diesel generators (EDGs) are operated in modes other than the prescribed standby service mode, such as loaded on non-emergency buses parallel with offsite power sources. The purpose of this supplement is to reemphasize the need for licensees to review the information provided in IN 84-69, in addition to the information contained herein, for applicability to their facilities and consider actions, if appropriate, to preclude similar problems at their facilities. However, suggestions contained in this supplement do not constitute NRC requirements; therefore, no specific action or written response is required.

Description of Circumstances:

Following a 10 CFR 50.72 report made to the NRC Headquarters Operations Center on August 12, 1985, it was discovered that Crystal River Unit 3 was continuously running the one operable EDG loaded in parallel with the grid while the other EDG was declared inoperable. Crystal River Technical Specifications require fast starting of the operable EDG (i.e., verifying that the diesel starts from ambient conditions and accelerates to the required speed within a required period of time) within 1 hour after the declaration of an inoperable EDG and every 8 hours thereafter. Because of a concern about increased EDG wear and reduced overall EDG reliability, the licensee chose to keep the EDG running loaded parallel to the offsite grid rather than fast starting the EDG every 8 hours.

The licensee believed that continuous running was an acceptable alternative to the test starts required by the Technical Specifications and that the EDG was operable per Technical Specifications while running in parallel with the offsite power system. The licensee indicated also that it was aware of IN 84-69 and had implemented procedures that prohibited operating the EDG parallel to the grid during inclement weather (e.g., lightning, heavy winds).

Discussion:

When an EDG is operated connected to offsite or nonvital loads, the emergency power system is not independent of disturbances on the nonvital and offsite power systems that can adversely affect emergency power availability. The situation is of particular concern when the onsite emergency power system is already in a degraded condition due to an EDG being inoperable and the operable EDG is loaded on non-emergency loads. In this condition, a disturbance in the non-emergency power system could result in both a loss of offsite power and a disabling of the remaining emergency power source. Although the events described in IN 84-69 occurred due to weather conditions, the concerns of the IN apply to parallel operation of EDGs with non-emergency loads at all times.


If a fault develops while the EDG is connected to non-emergency buses, EDG availability for subsequent emergency demands may be affected. In some design configurations, the EDG would trip as a result of overcurrent or reverse power, actuate a lockout device, and require local operator action to reset the lockout. In such cases, the EDG is recoverable, but the timeliness of its availability is not comparable to that of having the EDG in its normal standby service.

In other design configurations the EDG may not trip, but the operation of the load sequencer may be adversely affected. The load sequencer timers are often linked with the closing of the EDG output breaker or with detection of loss of voltage on the bus. If the EDG does not trip, conditions are not proper for the designed operation of the load sequencers. Consequently, the EDG cannot perform automatically in a manner comparable to that of having the EDG in its normal standby mode.

Another potential concern deals with the vulnerability of the EDG to trip signals which are bypassed for emergency demands but are operable for manual starts and during running for test purposes. The EDG would be more vulnerable to such trips.

The licensee's concern regarding excessive test starts is valid. In this particular case, the licensee was encouraged to address that concern more directly by submitting changes to the plant Technical Specifications. Such changes were approved for North Anna Unit 2 on April 25, 1985.

No specific action or written response is required by this information notice. If you have any questions about this matter, please contact the Regional Administrator of the appropriate regional office or this office.



Edward L. Jordan, Director  
Division of Emergency Preparedness  
and Engineering Response  
Office of Inspection and Enforcement

Technical Contacts: Joseph G. Gitter, IE  
(301) 492-9001

J. T. Beard, NRR  
(301) 492-7465

Attachment: List of Recently Issued Information Notices

LIST OF RECENTLY ISSUED  
 IE INFORMATION NOTICES

Information Notice No.	Subject	Date of Issue	Issued to
86-10	Safety Parameter Display System Malfunctions	2/13/86	All power reactor facilities holding an OL or CP
86-09	Failure Of Check And Stop Check Valves Subjected To Low Flow Conditions	2/3/86	All power reactor facilities holding an OL or CP
86-08	Licensee Event Report (LER) Format Modification	2/3/86	All power reactor facilities holding an OL or CP
86-07	Lack Of Detailed Instruction And Inadequate Observance Of Precautions During Maintenance And Testing Of Diesel Generator Woodward Governors	2/3/86	All power reactor facilities holding an OL or CP
86-06	Failure Of Lifting Rig Attachment While Lifting The Upper Guide Structure At St. Lucie Unit 1	2/3/86	All power reactor facilities holding an OL or CP
86-05	Main Steam Safety Valve Test Failures And Ring Setting Adjustments	1/31/86	All PWR facilities holding an OL or CP
86-04	Transient Due To Loss Of Power To Integrated Control System At A Pressurized Water Reactor Designed By Babcock & Wilcox	1/31/86	All power reactor facilities holding an OL or CP
86-03	Potential Deficiencies In Environmental Qualification Of Limitorque Motor Valve Operator Wiring	1/14/86	All power reactor facilities holding an OL or CP
86-02	Failure Of Valve Operator Motor During Environmental Qualification Testing	1/6/86	All power reactor facilities holding an OL or CP

OL = Operating License  
 CP = Construction Permit





UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D. C. 20545

OFFICIAL BUSINESS  
PENALTY FOR PRIVATE USE \$300

FIRST CLASS MAIL  
POSTAGE & FEES PAID  
USNRC  
WASH D C  
PERMIT No. 657

05-319-10-90

SSINS No.: 6835  
IN 86-73

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, D.C. 20555

August 20, 1986

IE INFORMATION NOTICE NO. 86-73: RECENT EMERGENCY DIESEL GENERATOR PROBLEMS

Addressees:

All nuclear power reactor facilities holding an operating license or a construction permit.

Purpose:

This notice is to alert addressees to vibration-induced fuel line wear and of a deficiency in the design of the field flash circuitry on nuclear plant emergency diesel generators. Recipients are expected to review the information for applicability to their facilities and consider actions, if appropriate, to preclude similar problems occurring at their facilities. However, suggestions contained in this information notice do not constitute NRC requirements; therefore, no specific action or written response is required.

Description of Circumstances:

Nine Mile Point Unit 2

While conducting diesel generator testing in early May 1986, it was discovered that diesel fuel lines had experienced extensive wear and fuel leaks in the area of the clamps that mount the fuel lines to the diesel engine. The diesels are Cooper-Bessemer model KSV-16-T, 600 rpm, 4 stroke, 16 cylinder units with low total operating hours.

Fuel line damage was caused by vibration from the diesel engine and fuel system pulsation induced by rapid, repeated cycling of a fuel system relief valve. This valve relieves from the low pressure fuel system via a cooler to the fuel day tank to control low pressure fuel system pressure. The manufacturer proposes to correct the problem by inserting plastic sleeves between the fuel line and its hold down clamps and installing a dashpot on the relief valve to dampen its operation.

Watts Bar Units 1 and 2

In April 1986 a deficiency was identified which affects all five standby diesel generators (DGs) at Watts Bar Nuclear Plant and could prevent the DGs from developing a voltage output when required in an emergency. The affected DGs are tandem 16-645 E4 units supplied by Morrison-Knudson Co. The normal shutdown cycle of the DG includes a 10-minute cooldown run at about 450 rpm. If during


this idle period an emergency start signal were received, the DG would accelerate to the normal 900 rpm operating speed, but the generator field would not be flashed and an output voltage therefore would not be developed.

This problem has also been determined to exist on the HPCS DG at Grand Gulf Nuclear Station. This unit was supplied by General Motors Corporation.

The root cause of this deficiency has been found to be a design error by the manufacturer. During a normal or emergency start, as the DG accelerates past 475 rpm, logic is completed to flash the generator field. When output voltage has built up, the field flash circuitry is automatically disabled. The logic design is such that engine speed must go below 200 rpm to re-enable the field flash circuitry, thus no field flash will occur if an emergency start signal is received during the 450 rpm cooldown period. Field flash would be needed under these circumstances because the self-excitation path is interrupted early in the shutdown sequence.

The corrective action proposed by the DG manufacturer is to modify the control circuitry to eliminate the speed dependence of field flash reset.

No specific action or written response is required by this information notice. If you have any questions about this matter, please contact the Regional Administrator of the appropriate regional office or this office.



Edward L. Jordan, Director  
Division of Emergency Preparedness  
and Engineering Response  
Office of Inspection and Enforcement

Technical Contact: Kevin Wolley, IE  
(301) 492-8373

Attachment: List of Recently Issued IE Information Notices

LIST OF RECENTLY ISSUED  
 IE INFORMATION NOTICES

Information Notice No.	Subject	Date of Issue	Issued to
86-72	Failure 17-7 PH Stainless Steel Springs In Valcor Valves Due to Hydrogen Embrittlement	8/19/86	All power reactor facilities holding an OL or CP
86-71	Recent Identified Problems With Limitorque Motor Operators	8/19/86	All power reactor facilities holding an OL or CP
86-70	Spurious System Isolation Caused By The Panalarm Model 86 Thermocouple Monitor	8/18/86	All GE BWR facilities holding an OL or CP
86-69	Scram Solenoid Pilot Valve (SSPV) Rebuild Kit Problems	8/18/86	All BWR facilities holding an OL or CP
86-68	Stuck Control Rod	8/15/86	All BWR facilities holding an OL or CP
86-67	Portable Moisture/Density Gauges: Recent Incidents And Common Violations Of Requirements For Use, Transportation, And Storage	8/15/86	All NRC licensees authorized to possess, use, transport, and store sealed sources
86-66	Potential For Failure Of Replacement AC Coils Supplied By The Westinghouse Electric Corporation For Use In Class 1E Motor Starters And Contractors	8/15/86	All power reactor facilities holding an OL or CP
86-65	Malfunctions Of ITT Barton Model 580 Series Switches During Requalification Testing	8/14/86	All power reactor facilities holding an OL or CP
86-64	Deficiencies In Upgrade Programs For Plant Emergency Operating Procedures	8/14/86	All power reactor facilities holding an OL or CP

OL = Operating License  
 CP = Construction Permit



05-319-11-90

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF NUCLEAR REACTOR REGULATION  
WASHINGTON, D.C. 20555

September 16, 1988

NRC INFORMATION NOTICE NO. 88-75: DISABLING OF DIESEL GENERATOR OUTPUT  
CIRCUIT BREAKERS BY ANTI-PUMP CIRCUITRY

Addressees:

All holders of operating licenses or construction permits for nuclear power reactors.

Purpose:

This information notice is being provided to alert addressees to potential problems where the capability to either automatically or manually close diesel generator circuit breakers from the control room may be lost. It is expected that recipients will review the information for applicability to their facilities and consider actions, as appropriate, to avoid similar problems. However, suggestions contained in this information notice do not constitute NRC requirements; therefore, no specific action or written response is required.

Description of Circumstances:

On June 5, 1988, operators at Browns Ferry Unit 3 were unable to reclose the diesel generator output breakers to the 4-kV shutdown boards from the control room during a loss-of-power/loss-of-coolant-accident (LOP/LOCA) test. During the test, the output breakers connected the diesel generators to their respective 4-kV shutdown boards after the LOP signal was generated; however, the breakers tripped and remained open after receiving the LOCA signal. Operators diagnosed the output breaker lockout problem using system electrical configuration drawings. An operator was sent to the 4-kV shutdown board to manually transfer output breaker control power to its alternate source. This momentarily removed power, enabling the breaker to close when the power was restored.

On October 14, 1987, an operator at Wolf Creek Generating Station manually tripped the output circuit breaker of the emergency diesel generator (EDG) from the control room. At the time, the EDG was supplying a vital bus. When the operators tried to reenergize the vital bus from the still-operating EDG, they found that they could not close the EDG output breaker from the control room. The vital bus was finally reenergized from the offsite power supply. Through examination of the breaker control schematics the licensee later found that the EDG circuit breaker could be closed by cycling the EDG mode switch at the EDG local control station.

Discussion:

The anti-pump circuit configuration will protect large breakers from rapid cycling and, under certain circumstances, will prevent breaker closure. At Browns Ferry Unit 3, a unique sequence of events, a LOP signal followed within 6 seconds by a LOCA signal, led to the discovery of a design deficiency of this circuit configuration. Contacts from the undervoltage relay will seal in the breaker anti-pump relay until the undervoltage condition on the 4-kV boards clears.

The circuit is designed such that following a LOP, the undervoltage condition must exist for at least 5 seconds and the diesel must reach rated speed before the diesel generator output breaker will close on the bus. Once the breaker has closed, the closure spring recharge motor and the breaker anti-pump relay will be energized. A fully discharged closure spring requires 2 seconds for the spring to be fully recharged. During this 2 second window the anti-pump coil will remain energized via contacts sensing spring position, and if an undervoltage condition exists on the 4-kV bus it will seal in and lock open the breaker.

During the Browns Ferry event, the EDG output breaker closed 5 seconds after the LOP signal, the undervoltage condition was eliminated, and the undervoltage relay began its 5 second cycle to reset from the undervoltage condition. About 1.5 seconds later, the LOCA signal retripped the breaker and created another undervoltage condition on the 4-kV bus. At this point, because the undervoltage relay had not completed its reset cycle, the undervoltage relay remained in its undervoltage state. Therefore, the undervoltage relay sealed in the still-energized anti-pump relay because the undervoltage condition occurred before the breaker charging spring was fully charged. Thus, the breaker could not be closed from the control room either manually or automatically until control power was removed, which deenergized the anti-pump relay.

The Browns Ferry licensee modified the breaker control logic to prevent the anti-pump relay from sealing in during a LOCA condition by adding a time-delay relay in the breaker trip coil circuitry. This relay will be energized by a LOCA signal and its contact in the anti-pump coil seal-in path will open after a 2-to 5-second delay to prevent anti-pump coil seal-in and breaker lockout.

The Wolf Creek EDG output circuit breaker has automatic closing logic to close the circuit breaker when the following five permissives are satisfied:

- (1) Both offsite circuit breakers are open.
- (2) The EDG mode switch is in the automatic mode.
- (3) Lockout relays are deenergized.
- (4) A 3-second time delay has elapsed.
- (5) The EDG has reached operating speed and voltage.

This logic sends a constant close signal to the circuit breaker that keeps the breaker's internal anti-pump relay energized as long as the logic permissives are satisfied. The anti-pump relay prevents the circuit breaker from cycling if attempts are made to hold the breaker closed against a valid trip signal.


When the Wolf Creek operator manually tripped the EDG output breaker, the automatic closing logic permissives remained satisfied. Therefore, the anti-pump relay remained energized, preventing reclosure of the circuit breaker. Cycling the EDG mode control switch at the local control station allowed the circuit breaker to reclose by momentarily interrupting the automatic close signal, thereby resetting the anti-pump logic. When the mode switch contact was reclosed by returning the switch to the "auto" position, the circuit breaker's automatic closing logic closed the breaker.

The Wolf Creek licensee modified the EDG breaker control switch located in the control room to enable the operator to reclose the EDG circuit breaker from the control room. This switch was originally intended only as a means of paralleling the EDG with the offsite power supply. With the current modification, the switch can be used to reset the anti-pump logic and allow the automatic circuit to reclose the breaker. The modification added a contact that is closed in the "normal" position and open in the "trip" and "pull to lock" positions of the control switch. When operators manually trip the EDG circuit breaker from this control switch, the contacts open to interrupt the close circuit and reset the circuit breaker anti-pump relay. If the operator wishes to keep the breaker open, he must put the switch in the "pull to lock" position. Returning the switch to the "normal" position completes the automatic close circuit and the breaker recloses.

It should be noted that although the above discussion has dealt only with EDG output circuit breakers, anti-pump circuit problems could also apply to other breakers that use automatic closing logic, such as load-sequencing breakers and offsite supply breakers to the emergency buses.

The information herein is being provided as an early notification of a potentially significant matter that is still under consideration by the NRC staff. If NRC evaluation so indicates, specific licensee actions may be requested.

No specific action or written response is required by this information notice. If you have any questions about this matter, please contact one of the technical contacts listed below or the Regional Administrator of the appropriate regional office.

  
Charles E. Rossi, Director  
Division of Operational Events Assessment  
Office of Nuclear Reactor Regulation

Technical Contacts: James Lazevnick, NRR  
(301) 492-0814

Carl Schulten, NRR  
(301) 492-1192

Fred Burrows, NRR  
(301) 492-0783

Attachment: List of Recently Issued NRC Information Notices



LIST OF RECENTLY ISSUED  
 NRC INFORMATION NOTICES

Information Notice No.	Subject	Date of Issuance	Issued to
88-74	Potentially Inadequate Performance of ECCS in PMPs During Recirculation Operation Following a LOCA	9/14/88	All holders of DLs or CPs for W and B&W-designed nuclear power reactors.
88-73	Direction-Dependent Leak Characteristics of Containment Purge Valves	9/8/88	All holders of DLs or CPs for nuclear power reactors.
88-72	Inadequacies in the Design of dc Motor-Operated Valves	9/2/88	All holders of DLs or CPs for nuclear power reactors.
88-71	Possible Environmental Effect of the Reentry of COSMOS 1900 and Request for Collection of Licensee Radioactivity Measurements Attributed to That Event	6/1/88	All holders of DLs or CPs for nuclear power reactors, fuel cycle licensees, and Priority 1 material licensees.
88-70	Check Valve Inservice Testing Program Deficiencies	6/29/88	All holders of DLs or CPs for nuclear power reactors.
88-69	Movable Contact Finger Binding in HFA Relays Manufactured by General Electric (GE)	6/19/88	All holders of DLs or CPs for nuclear power reactors.
88-68, Supplement 1	Licensee Report of Defective Refurbished Valves	6/24/88	All holders of DLs or CPs for nuclear power reactors.
88-68	Setpoint Testing of Pressurizer Safety Valves with Filled Loop Seals Using Hydraulic Assist Devices	8/22/88	All holders of DLs or CPs for nuclear power reactors.
88-67	PWR Auxiliary Feedwater Pump Turbine Overspeed Trip Failure	8/22/88	All holders of DLs or CPs for nuclear power reactors.

DL = Operating License  
 CP = Construction Permit

UNITED STATES  
 NUCLEAR REGULATORY COMMISSION  
 WASHINGTON, D.C. 20555

OFFICIAL BUSINESS  
 PENALTY FOR PRIVATE USE, \$300

FIRST CLASS MAIL  
 POSTAGE & FEES PAID  
 USNRC  
 PERMIT No. G-67

120555031515 - 1 1001CY1FB11A1  
 US NRC-AEOD  
 DIRECTOR  
 MNBB-3302  
 WASHINGTON DC 20555

05-319-12-90

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
OFFICE OF NUCLEAR REACTOR REGULATION  
WASHINGTON, D.C. 20555

December 19, 1989

NRC INFORMATION NOTICE NO. 89-87: DISABLING OF EMERGENCY DIESEL GENERATORS  
BY THEIR NEUTRAL GROUND-FAULT PROTECTION  
CIRCUITRY

Addressees:

All holders of operating licenses or construction permits for nuclear power reactors.

Purpose:

This information notice is intended to alert addressees to possible unconsidered failure modes in which emergency diesel generators could be rendered inoperable as a result of their neutral ground-fault protection circuitry. It is expected that recipients will review the information for applicability to their facilities and consider actions, as appropriate, to avoid similar problems. However, suggestions contained in this information notice do not constitute NRC requirements; therefore, no specific action or written response is required.

Description of Circumstances:

On May 25, 1989, a plant engineering design review at Perry Unit 1 revealed a design anomaly whereby ground faults on emergency diesel generator loads coincident with loss of offsite power during a seismic event or fire could lead to the inoperability of more than one emergency diesel generator. As a result, the Perry staff declared several of the emergency diesel generators inoperable until temporary modifications could be made to disable the neutral ground-fault relay contacts that were designed to trip the emergency diesel generators.

Discussion:

At Perry Unit 1, each emergency diesel generator was designed with a neutral ground circuit consisting of a high impedance path from the neutral to ground, which limits ground-fault current to no more than 2 amperes (see typical network in Figure 1). The purpose of providing this grounding path (in lieu of an ungrounded system) is to limit the buildup of high voltage stress during certain ground-fault conditions that could ultimately result in the breakdown of the insulation of such components as motors and cables. It also provides a convenient means of detecting a ground in the system so that a search can be made to eliminate the ground before a second ground occurs and causes a phase-to-phase fault.

8912130473


4PP



Ground faults are detected by sensing the voltage that is developed in the emergency diesel generator grounding circuit whenever a ground fault exists in the electrical distribution system supplied by the emergency diesel generator. In the Perry design, a voltage sensing relay would initiate a trip of the corresponding emergency diesel generator whenever this voltage exceeded the relay's pickup value. This relay's contacts are bypassed by the automatic response to a loss-of-coolant accident. For non-LOCA events, however, a ground fault in any component, including non-Class 1E components, would have the undesirable result of shutting down the emergency diesel generator. This raises the concern that a seismic event or fire could have resulted in simultaneous ground faults in non-safety components supplied by all of the redundant emergency diesel generators. Action by the protection circuitry at Perry could then have shut down all of the emergency diesel generators, preventing them from performing their intended safety functions.

The Perry staff has temporarily disabled the neutral ground-fault relays to prevent them from shutting down the emergency diesel generators. Permanent modifications are planned to replace the ground-fault emergency diesel generator trip function with ground-fault alarms in the control room. These modifications will be supported by alarm response procedures requiring that the operators determine the location and safety significance of ground faults and take appropriate action.

This information notice requires no specific action or written response. If you have any questions about the information in this notice, please contact the technical contact listed below or the appropriate NRR project manager.



Charles E. Rossi, Director  
Division of Operational Events Assessment  
Office of Nuclear Reactor Regulation

Technical Contact: F. Burrows, NRR  
(301) 492-0833

Attachments:

1. Figure 1
2. List of Recently Issued NRC Information Notices

### TYPICAL HIGH RESISTANCE NEUTRAL GROUNDING SYSTEM




FIGURE 1

LEGEND

- 64 - Voltage sensing relay, provides alarm actuation or trip.
- 64X - Provides overvoltage protection for the 64 relay.

LIST OF RECENTLY ISSUED  
NRC INFORMATION NOTICES

Information Notice No.	Subject	Date of Issuance	Issued to
89-85, Supp. 2	Metalclad, Low-Voltage Power Circuit Breakers Refurbished with Substandard Parts	12/15/89	All holders of OLS or CPs for nuclear power reactors.
89-86	Type HK Circuit Breakers Missing Close Latch Anti-Shock Springs.	12/15/89	All holders of OLS or CPs for nuclear power reactors.
89-85	EPA's Interim Final Rule on Medical Waste Tracking and Management	12/15/89	All medical, academic, industrial, waste broker, and waste disposal site licensees.
89-84	Failure of Impersoll Rand Air Start Motors as a Result of Pinion Gear Assembly Fitting Problems	12/12/89	All holders of OLS or CPs for nuclear power reactors.
89-83	Sustained Degraded Voltage on the Offsite Electrical Grid and Loss of Other Generating Stations as a Result of a Plant Trip	12/11/89	All holders of OLS or CPs for nuclear power reactors.
89-82	Recent Safety-Related Incidents at Large Irradiators	12/7/89	All NRC licensees authorized to possess and use sealed sources at large irradiators.
89-59, Supp. 1	Suppliers of Potentially Misrepresented Fasteners	12/6/89	All holders of OLS or CPs for nuclear power reactors.
89-81	Inadequate Control of Temporary Modifications to Safety-Related Systems	12/6/89	All holders of OLS or CPs for nuclear power reactors.

OL = Operating License  
CP = Construction Permit

UNITED STATES  
NUCLEAR REGULATORY COMMISSION  
WASHINGTON, D.C. 20555

OFFICIAL BUSINESS  
PENALTY FOR PRIVATE USE, \$300

FIRST CLASS MAIL  
POSTAGE & FEES PAID  
USNRC  
PERMIT No. G-87

120555051515  
US NRC-AEOD  
DIRECTOR  
MNBB-3701  
WASHINGTON

1 1141181001CY1

DC 20555

05-320-90

NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, D. C. 20555

IE BULLETIN 77-01  
Date: April 29, 1977  
Page 1 of 3

PNEUMATIC TIME DELAY RELAY SETPOINT DRIFT

DESCRIPTION OF CIRCUMSTANCES:

Millstone Unit 2 and North Anna Unit 1 facilities experienced repeated diesel-generator starting failures several of which investigation revealed were caused by setpoint drift on the pneumatic time delay relays used in the control circuitry for the diesel-generator. The relays involved are identified as ITE Imperial, Catalog Nos. J20T3/J13P20 and J20T3/J13P30. The affected diesel-generators are Fairbanks Morse Units by Colt Industries.

These types of time delay relays are used in several different applications in the control circuitry for the diesel-generator. One of these relays is used to bypass the normal low oil pressure shutdown functions during diesel-generator startup. At Millstone Unit 2 the relay had drifted approximately 10 seconds from the required 20 second delay which allowed the low oil pressure trip circuit to shut down the diesel-generator before the oil pressure had time to build up. At North Anna Unit 1, excessive drift of similar ITE time delay relays was also observed during preoperational testing of the diesel-generators.

ITE Imperial has identified the time delay relays involved at Millstone Unit 2 as coming from the 1972 and 1973 production runs. The catalog specification for this vintage of relays requires a trip-point setting repeat accuracy of  $\pm 15$  percent. Units manufactured in 1974 or later have demonstrated a repeat accuracy of  $\pm 3$  to 4 percent, well within the catalog specification of  $\pm 15$  percent.

7909050210 3pp



Month and year of production for the time delay relays in question can be determined by the six or seven digit bold white number on the timer head. The first two or three digits indicate the month and year of production. (The last four digits provide other coded information.) For example: 124056 indicates a production date of January 1972; 1234056 indicates a production date of December 1973.

According to the time delay relay manufacturers, the potential for setpoint drift is a common characteristic of most pneumatic relays, irrespective of manufacturer. The magnitude of setpoint drift is related to the repeat accuracy specified for the device and the mode in which it will operate, that is, energized or de-energized. In most cases energized units tend to be susceptible to greater deviations from setpoint because of the temperature effects on the internal parts of the unit.

**ACTION TO BE TAKEN BY LICENSEES AND PERMIT HOLDERS:**

For all power reactor facilities with an operating license or construction permit:

1. If you have been notified of the potential problem, describe the actions taken regarding corrective measures to identify and resolve any setpoint drift problems with the ITE time delay relays.
2. In addition to Item 1 above, pneumatic time delay relays intended for use in safety related systems and specifying a repeat accuracy range of  $\pm 15$  percent or greater should be demonstrated to provide satisfactory operation. You are requested to provide your basis for concluding that existing pneumatic time delay relays are functioning as required, or provide your plans to assure satisfactory operation.

Reports for facilities with operating licenses should be submitted within 30 days after receipt of this Bulletin, and reports for facilities with construction permits should be submitted within 60 days after receipt of this Bulletin. Your report should include the date when the above actions were or will be completed.



IE Bulletin 77- 01  
Date: April 29, 1977  
Page 3 of 3

Reports should be submitted to the Director of the NRC Regional Office and a copy should be forwarded to the NRC Office of Inspection and Enforcement, Division of Reactor Inspection Programs, Washington, D. C. 20555.

Approval of NRC requirements for reports concerning possible generic problems has been obtained under 44 U.S.C 3152 from the U. S. General Accounting Office. (GAO Approval B-180255 (R0072), expires 7/31/77)

05-327-90

NUCLEAR REGULATORY COMMISSION  
OFFICE OF INSPECTION AND ENFORCEMENT  
WASHINGTON, D.C. 20555

December 9, 1977

IE Circular 77-16

EMERGENCY DIESEL GENERATOR ELECTRICAL TRIP LOCK-OUT FEATURES

Description of Circumstances:

On June 15, 1977, Duquesne Light Company (Beaver Valley 1) reported that during the performance of a test of the diesel-generator (D/G) trip lock-out features in the emergency mode of operation, the D/G output circuit breaker opened when the field voltage trip interlock was tested. This is contrary to a requirement for this facility that, in the emergency mode, all D/G output breaker trips except generator differential and overcurrent be automatically disabled. The engine overspeed trip, which shuts down the diesel engine (but does not affect breaker operation) is also expected to be operable during the emergency mode of operation.

An investigation conducted by the licensee disclosed that the unexpected opening of the output breaker was due to deenergizing a field voltage sensing relay which was supplied by the vendor but had not been disconnected during the on-site acceptance testing of the D/G nor disabled by the protection circuitry logic. A redundant field voltage relay which was supplied by the licensee is correctly by-passed during fast start conditions and emergency operation.

791130450-5 pp

A design change was initiated by the licensee which removed the field voltage trip feature. This was accomplished by disconnecting the set of relay contacts to the trip circuitry of the D/G output breaker. Subsequent testing of the D/G was performed by the licensee which demonstrated satisfactory operation.

This is an example of an event which resulted from inadequate test procedure performance. The procedures as performed had not previously identified the type of deficiency described in this circular.

The safety significance of this situation is that the premodified protection circuitry would have opened the circuit breaker if a loss of field voltage occurred while running in the emergency mode of operation.

The D/G Units for the above facility were supplied by the Electro Motive Division (EMD) of General Motors. The model numbers for the D/G Units are:

Engine Model No. 20-345-E4

Generator Model No. A-20-C7

Control Panel Model No. 999-20

All holders of operating licenses or construction permits should assure that the appropriate D/G protection trip circuits are provided with automatic by-pass features that prevent them from negating automatic starting or tripping of D/Gs during fast start or emergency operations. It is recommended that the following be considered in your reviews of this matter:

1. Facility procedures should specifically determine whether the protection circuitry that trips the D/G set or the associated output breaker is in accordance with the facility Technical Specifications.
2. Test procedures for your D/G sets (e.g. acceptance preoperational and surveillance tests) should be reviewed to assure that D/G system performance is demonstrated by these tests to be in accordance with related operational requirements specified in the facility Technical Specifications.
3. Strengthening of management controls should be reviewed as necessary to assure adherence to D/G test procedures by plant personnel.

No written response to this circular is required. If you require additional information regarding this matter, contact the Director of the appropriate NRC Regional Office.

## LISTING OF IE CIRCULARS ISSUED IN 1977

CIRCULAR NO.	SUBJECT	FIRST DATE OF ISSUE	ISSUED TO
77-01	Malfunctions of Limitorque Valve Operators	1-4-77	All holders of OLs or CPs
77-02	Potential Heavy Spring Flooding	2-15-77	All affected holders of OLs
77-02A	Potential Heavy Spring Flooding	2-16-77	All affected holders of CPs
77-03	Fire Inside a Motor Control Center	2-28-77	All holders of OLs and CPs
77-04	Inadequate Lock Assemblies	3-17-77	Safeguard Group I, II, IV, V, Licensees
77-05	Liquid Entrapment in Valve Bonnets	3-24-77	All holders of OLs and CPs
77-06	Effects of Hydraulic Fluid on Electrical Cable	4-1-77	All holders of OL's and CPs
77-07	Short Period During Reactor Startup	4-12-77	Holders of BWR OLs
77-08	Failure of Feedwater Sample Probe	4-13-77	All holders of OLs
77-09	Improper Fuse Coordination In BWR Standby Liquid Control System Control Circuits	5-25-77	All holders of BWR OLs or CPs
77-10	Vacuum Conditions Resulting in Damage to Liquid Process Tanks	7-15-77	All holders of OLs



## LISTING OF IE CIRCULARS ISSUED IN 1977 (Continued)

CIRCULAR NO.	SUBJECT	FIRST DATE OF ISSUE	ISSUED TO
77-11	Leakage of Containment Isolation Valves with Resilient Seats	9-6-77	All holders of OLs and CPs
77-12	Dropped Fuel Assemblies at BWR Facilities	9-15-77	All holders of BWR OLs or CPs
77-13	Reactor Safety Signals Negated During Testing	9-22-77	All holders of OLs and CPs
77-14	Separation of Contaminated Water Systems From Noncontaminated Plant Systems	11-22-77	All Power and Test Reactor, Fuel Cycle, and major By-product material processor facilities with OLs or CPs
77-15	Degradation of Fuel Oil Flow to the Emergency Diesel Generators	12/1/77	All holders of OLs and CPs

1 05-322-90

1. Control No. <b>18808316</b>		2. Date <b>11/17/88</b>		3. Unit	
4. System/Component <b>1204/MOY</b>			5. MPL/Tag No. <b>1HV8808D</b>		
6. Problem/Work Requested <b>SUBJECT VALVE HAS BEEN REPORTED AS LEAKING BY THE SEAT. MOVATS TEST DATA OBTAINED UNDER MWO 18808314 INDICATES A DEFORMATION DURING VALVE SEATING AND CONFIRMS REPORTED SEATING CONCERNS.</b>					
7. Initiator <b>ROBERT L. GLENNON X-4160</b> <b>11/17/88</b>					
9. Classification (Safety) <b>III</b>		10. Unit Status Required <b>Any Mode</b>		11. Fire Protection System <b>NO</b>	
12. DCR <input type="checkbox"/> No. <b>NA</b>		13. NCR/DRA <input type="checkbox"/> No. <b>NA</b>		14. Type Maintenance Plant <input checked="" type="checkbox"/> Facility <input type="checkbox"/>	
14. Type Maintenance Plant <input checked="" type="checkbox"/> Facility <input type="checkbox"/>		15. Duration of Maintenance <b>20</b>		17. Clearance Required <input checked="" type="checkbox"/> ETD <b>19015-18</b>	
16. Est/Act Man Hours Summary		18. Permits Required <b>None</b>		19. Q.C. Hold Pts. <b>None</b>	
Hrs. <b>24</b> Mech. <b>16</b> Elect. <b>NA</b> I&C <b>NA</b> Other <b>NA</b>		20. Procedure No. <b>26610C/2659C/2656C</b>		21. Priority <b>E3</b>	
23. Work Instruction <b>SEE 4/1/24</b>		22. LCO <input type="checkbox"/>		22. LCO <input type="checkbox"/> <b>T.S. 3.8.4.2</b>	
23. Work Instruction <b>REWORK VALVE AS NECESSARY TO ENSURE PROPER VALVE SEATING - LOCK</b>					
24. Initiation Review					
25. Special Review Required <input checked="" type="checkbox"/>		25. Special Review Required <input checked="" type="checkbox"/> <b>SEE CONT 1</b>			
27. Actual Work Performed		27. Actual Work Performed			
27. Actual Work Performed <b>Block #27 determined wires at valve # 1HV-8808D could not remove flex fittings on valve. See the lifted lead data sheet Proc 250.96-c data sheet Work stopped and Maintained ZONE-IV Cleanliness 2-25-90</b>					
History Summary					
28. Material Required <input type="checkbox"/>					
29. Person Performing Work (Name)		30. Maintenance Program		31. Inspection Performed By	
32. Method of Functional Test		34. Performed By		35. Date	
33. Procedure No.		36. Proves Operability Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		37. Method Used To Prove Operability	
38. Satisfactory <input type="checkbox"/> Unsatisfactory <input checked="" type="checkbox"/>		39. If Unsatisfactory, Corrective Action Taken		40. Unit Status At Time of Failure	
40. Unit Status At Time of Failure		41. Type of Failure		42. Mode of Failure	
43. Cause of Failure		44. Detection By		46. Effect on System	
48. Effect on Plant		47. MWO # & Code		48. Cause Description	
49. Next MWO No.		50. Operation Accepted By		51. Meeting Number	
52. OSOS Approval		53. Special Review Completed		54. Meeting Number	
55. Close-out Approval By QC		55. Close-out Approval By QC		55. Close-out Approval By QC	

**B-TRAIN**

Nuclear Plant Maintenance Work Order Continuation Sheet

MPL No. JHV8808D

MWO No.

18808316

Work Description \_\_\_\_\_

BLOCK 23 CONTINUED:

NUMBER # 4 DRAINED. IF A Freeze seal required in lieu of draining system  
Initiate a separate MWO/PO For a Vendor to Freeze seal line OR  
initiate a Temp. procedure with MWO to provide instructions for Freeze sealing a  
10 inch pipe.

MEOP

- Coordinate with H.P.
- Disassemble valve per procedure 26610-C (VALVE 10GM88)
- Maintain Cleanliness Class -B.
- Verify that operator and bonnet can be removed together from body. All details to be document in 26610-C.

(ISI HOLD POINT)

- Inspect Disc., seat ring, internals. Contact I.S.I Group for Inspect
- IF ANY pressure boundary parts require replacement and/or rework, except for minor leakage, RETURN MWO to WPG for Section XI Traveler.

- Reassemble valve per 26610-C, including Reterm. & Repair 25036-C \*\*\*
- Reset valve per ~~26834-C~~ <sup>26834-C</sup> & Re-MOVAT per 26859-C \*\*\*
- ~~Reset valve~~ No 5 min STROKE TIME, Valve not LLRT valve.

- No Leakage to be performed by QC/ANII (VT-2) at NOP/T under F/T Block 32.

\*\*\* Notify QC Prior to Reterm For Holdpoints <sup>11/23/88</sup>

\* Pressure Boundary Parts: Body, Bonnet, Disc., STEEL MAIN Flange STUDS / NUTS. <sup>11/29/88</sup>

\*\*\* Ref mwo 18902972 for movets ~~26834-C~~ Also for electrical <sup>11/29/88</sup>



NUCLEAR PLANT MAINTENANCE WORK ORDER CONTINUATION SHEET

MPL NO. 1 HV 8808D

MWO NO. 18808316

WORK DESCRIPTION BLOCK 23 - MAINTAIN CLASS 'B' CLEANLINESS, AND ZONE III HOUSEKEEPING. SAC 2-22-90

Block 27) Disconnected flexible conduit of control cable and motor leads Maintained Containment Cleanliness F22530

Block 26 E.m. ~~Started~~ for 3/19/90

Block 27

Disassembled VALVE A per procedure 26610-C

cleaned disc + body to bonnet surface + seat MAINTAINED CLASS B Cleanliness and ZONE III Housekeeping

Mark D Langston 3/19/90

Block 27 - BLUE checked valve, tested seat, installed new gasket, called QC for check and ~~and~~ lowered Bonnet on valve, installed nuts

Mark D Langston

Block 27 - Torqued main flange bolts with torque wrench VP-3-2272 due 6-11-90 and multiplier VTR-42-006 called QC to witness final torque, maintained Class <sup>H<sub>2</sub>O</sup> Cleanliness and Zone <sup>H<sub>2</sub>O</sup> IV Housekeeping SAC 3-22-90

Mark D Langston 3-22-90

VALVE WAS DISASSEMBLED AT MAIN FLANGE ONLY, REPACK NOT REQUIRED. SAC 3-21-90

Nuclear Plant Maintenance Work Order Continuation Sheet

MPL No. 1 HV 8808D

MWO No. 18808316

Work Description BLK 26: JCHART 3-20-90

Block 27) Completed the determination of all external cables of 1HV8808D per 250360 P/S date sheet. MAINT TESTING TO BE PERFORMED UNDER MWO 18902972 (Mandated Cont dealines) F3-21-90

Block 29) FAIRB 3-21-90

Block 30: James Benky 3-21-90

Block 50: WRT 1050 generated for seat leakage. M. Chance 4/11/90

Block 27: THE LEAKAGE IDENTIFIED ON VT-2 INSPECTION BY D.C. LEWIS ON 4-14-90 WAS FOUND TO HAVE BEEN COMING FROM VALVE 1-1204-44-025. THIS VALVE TO BE REPAIRED UNDER MWO 19000543. THE VT-2 INSPECTION FOR 1HV-8808D HAS BEEN REPERFORMED ON 4-15-90 BY RALPH WABB (RC) AND FOUND TO BE SATISFACTORY. INSPECTION REPORT ATTACHED.  
Ralph Wabb 4-15-90

Block 32<sup>4/15/90</sup> 34: Ralph A Check (BASED ON VT-2 REPORT DATED 4-15-90) W/ST

Block 32: VT-2 is complete and satisfactory at WOP/NOT.

Seat leakage still exist according to M. Chance MWO 19001895 was written to correct this problem. W. Stevenson 4/15/90

Block 50: 19001895 - W. Stevenson 4/15/90  
EST



MWO/OTHER # 18808316 IWSF PROCEDURE # 85060-C REV # 3 DRAWING # 1869A06-656 REV # R11

LINE/EQUIP # 1-HV380015 TEST CODE: ASME Section XI  ANSI B31.1  OTHER \_\_\_\_\_

TYPE OF TEST:  
System Leakage  System Inservice  System Pneumatic   
System Functional  System Hydrostatic  Other \_\_\_\_\_

COMPONENT OR SYSTEM:  
Insulated  Non-Insulated

TEST CONDITIONS: (Complete as applicable)  
Required NOP  NOT  Verified NOP  NOT   
Required N/A PSIG Verified N/A PSIG  
Required N/A F Verified N/A F

TEST CONDITION VERIFIED BY:  
Examiner  4/15/90  
Other  Name FRED HOWARD Time 15:30

TEST INSTRUMENTATION:  
INSTRUMENT # N/A Cal. Due Date 1/1  
INSTRUMENT # N/A Cal. Due Date 1/1  
INSTRUMENT # N/A Cal. Due Date 1/1  
\* Cal. Data Not Required Except For Hydrostatic & Pneumatic Tests

TEST RESULTS:  
SAT.  UNSAT.  DC # \_\_\_\_\_

DESCRIPTION OF DEFICIENCY IF UNSAT: NONE

VISUAL EQUIPMENT USED: FLASH LIGHT

REMARKS: 557°F 2235 PSIG PER FRED HOWARD

VT 2 PERFORMED BASED ON DC-190-267

EXAMINER: [Signature] LEVEL II DATE 4-15-90

EVALUATOR: N/A  LEVEL DATE

AMII REVIEW: N/A  LEVEL DATE

Procedure No. VEGP 25036-C	Revision 3	Page No. 21 of 26
-------------------------------	---------------	----------------------

POWER AND SIGNAL REMOVAL/REPLACEMENT DATA SHEET

Sheet 1 of 1

Safety Related/QC Holdpoints

Non-Safety Related

NOTES

- a. To install jumpers and/or lift wires, other than those directly associated with the equipment tag(s)/scheme number(s) listed on the Work Order, notify the Shift Supervisor and comply with his instructions.
- b. Ensure that each lead (wire) is marked so it can be uniquely identified with its termination point.
- c. Independent verification is only required on safety related equipment. Place N/A in independent verification block for non-safety related equipment.
- d. If the worker leaves the immediate proximity of the work or the work is interrupted, complete and install a "Jumper and Lifted Wire" tag per 00306-C, "Temporary Jumper And Lifted Wire Control". Instead of Control Number use the Procedure number on the tag.
- e. If holdpoints do not apply, NA QC Verification block.

**QC  
HOLD POINT**

IDENTIFY LEADS LIFTED, JUMPERS INSTALLED, LINES OPEN, ETC.	LOCATION PANEL OR JUNCTION BOX	REMOVAL			RECONNECTION		
		PERFORMED BY/DATE	INDEPENDENT VERIFICATION BY/DATE	QC VERIF. BY/DATE	PERFORMED BY/DATE	INDEPENDENT VERIFICATION BY/DATE	QC VERIF. BY/DATE
LBRE 19 LA	1-HV-8808D	DAE 2-25-90	ADW 3/25/90				
Main Lead BLK TO TB 1	↓				F 3-21-90	RB 3-21-90	RCY 3/21/90
" " Red To TB 2					F 3-21-90	RB 3-21-90	RCY 3/21/90
" " WHT To TB 3					F 3-21-90	RB 3-21-90	RCY 3/21/90
LBRE 19 SC							
Red To RB #2 (Control SW 30)					F 3-21-90	RB 3-21-90	RCY 3/21/90
Blk To RB #3 (Control SW 28)					F 3-21-90	RB 3-21-90	RCY 3/21/90
Grn To Term. Strip Pt. 21					F 3-21-90	RB 3-21-90	RCY 3/21/90
Grn/Blk To RB #1 (Control SW 10) (10)					F 3-21-90	RB 3-21-90	RCY 3/21/90
Blk/Blk To Term Strip A B	1-HV-8808D	DAE 2-25-90	ADW 3/25/90		F 3-21-90	RB 3-21-90	RCY 3/21/90

Procedure No. <b>VEGP 25036-C</b>	Revision <b>8</b>	Page No. <b>21 of 26</b>
--------------------------------------	----------------------	-----------------------------

Sheet 1 of 1

**POWER AND SIGNAL REMOVAL/REPLACEMENT DATA SHEET**

Safety Related/QC Holdpoints

Non-Safety Related

**NOTES**

- a. To install jumpers and/or lift wires, other than those directly associated with the equipment tag(s)/scheme number(s) listed on the Work Order, notify the Shift Supervisor and comply with his instructions.
- b. Ensure that each lead (wire) is marked so it can be uniquely identified with its termination point.
- c. Independent verification is only required on safety related equipment. Place N/A in independent verification block for non-safety related equipment.
- d. If the worker leaves the immediate proximity of the work or the work is interrupted, complete and install a "Jumper and Lifted Wire" tag per 00306-C, "Temporary Jumper And Lifted Wire Control". Instead of Control Number use the Procedure number on the tag.
- e. If holdpoints do not apply, NA QC Verification block.

**QC HOLD POINT**

IDENTIFY LEADS LIFTED, JUMPERS INSTALLED, LINES OPEN, ETC.	LOCATION PANEL OR JUNCTION BOX	REMOVAL			RECONNECTION		
		PERFORMED BY/DATE	INDEPENDENT VERIFICATION BY/DATE	QC VERIF. BY/DATE	PERFORMED BY/DATE	INDEPENDENT VERIFICATION BY/DATE	QC VERIF. BY/DATE
188EM95C	1-HV-8808D	ABE 2-25-90	RAHE 2/21/90				
W/L to Pwr #4 (contact 13) (17) ✓	↑	↓	↓	↓	F 3-21-90	RB 3-21-90	RAHE 3/21/90
Orig to Pwr #4 (contact 13) (16) ✓					F	RB 3-21-90	RAHE 3/21/90
Orig/W/L to Term Strip pt. 36 ✓					F	RB 3-21-90	RAHE 3/21/90
W/L to Pwr #4 (contact 13) (18) ✓					F	RB 3-21-90	RAHE 3/21/90
W/L/W/L. Pwr #3 (contact 11) (19)					F	RB 3-21-90	RAHE 3/21/90
W/L to Pwr #3 (contact 11) (20)					F ↓	RB 3-21-90	RAHE 3/21/90
W/L/W/L. Pwr #4 (contact 15) (49) ✓					F 3-21-90	RB 3-21-90	RAHE 3/21/90
188EM95D					1-HV-8808D	ABE 2-25-90	RAHE 2/21/90
Pwr Pwr #3 (contact 12) (30) ✓				F 3-21-90	RB 3-21-90	RAHE 3/21/90	





COMPLETION SHEET

PROCEDURE NO. 25036-C	REVISION 8	SHEET 1 of 5
TAG NO. 1HV-8808D	DESCRIPTION	
SERIAL NO.	MANUFACTURE	MODEL
TEST EQUIPMENT USED	M&TE [ ] Safety Related/QC hold points [ ] Non-Safety Related	

PROCEDURE STEP	DESCRIPTION	MAINT. INIT/DATE	HOLD POINT (Yes/No)	QC INIT/DATE
3.5	Special indicator MOV/MAC [ ] Applies (Post test assigned) [ ] Does not apply	N/A	NO	RA 17/2/89
4.1.1	Prerequisites and Initial Conditions verified	/		/
4.1.2	Shift Supervisor Notified	/		/
4.1.3	Clearance and Tagging Verified	/		/
4.1.5	Normal Overload Protection effect With any Jumpers Lifted/Document on "Power and Signal Removal/Replacement Data" Sheet or Temp. Mod. as Required.	/		/
4.1.6	Record MWO NO. _____ VALVE TAG NO. _____	/		/
4.2.1	Visual Check of Stuffing Box Complete with any Abnormalities recorded as Comments. [ ] SATISFACTORY [ ] UNSATISFACTORY	/	NO	RA 17/2/89





COMPLETION SHEET (cont'd)

PROCEDURE STEP	DESCRIPTION	MAINT. INIT/DATE	HOLD POINT (Yes/No)	QC INIT/DATE
-------------------	-------------	---------------------	---------------------------	-----------------

4.3.8 NAME OF PERSON CONTACTED FOR DECONTAMINATION.

DECON FOREMAN \_\_\_\_\_ DATE \_\_\_\_\_ TIME \_\_\_\_\_

5.1.1 Verify operations concurrence

N/A NO 12/2/89

5.1.2 Check valve operation

\_\_\_\_\_ NO \_\_\_\_\_

5.3 If Running Current Can Not Be Reduced Below Threshold Limits Of 130% of Rated Nameplate Current, Name of Maint. Engineer Contacted

(Name Of Person Notified) (Date) (Time)

\_\_\_\_\_ 1 NO \_\_\_\_\_

5.4 Phase to Phase Line Voltage

\_\_\_\_\_ Volts A to B

\_\_\_\_\_ Volts B to C

\_\_\_\_\_ Volts A to C

Lowest Steady State Running Current

\_\_\_\_\_ Amps Opening at \_\_\_\_\_ Location

\_\_\_\_\_ Amps Closing at \_\_\_\_\_ Location

Measured Valve Stroke Times

Actual Stroke Times

Open \_\_\_\_\_ seconds

Close \_\_\_\_\_ seconds

Satisfactory

Unsatisfactory

\_\_\_\_\_ NO 12/2/89

COMPLETION SHEET (cont'd)

PROCEDURE STEP	DESCRIPTION	MAINT. INIT/DATE	HOLD POINT (Yes/No)	QC INIT/DATE
5.5	Stroke Air Operated valves several times to assure valve operate properly	N/A	NO	17/12/89
5.5.1	AOV STROKE TIME			
	REQUIRED ACTUAL			
	OPEN			
	CLOSE	/		/
5.7	Slide Wire Potentiometer Reconnected/Recalibrated As Required.	/		/
5.8	Any Required Thermal Overload Jumpers Verified Reinstalled or Temp. Mod. In Force To Ensure Replacement.			
	[ ] Jumper Removal N/A			
	[ ] Jumpers Reinstalled as Required			
	[ ] Temp. Mod. No. _____ in force to ensure Reinstallation of Jumpers.			
5.9	Shift Supervisor Notified that required Maintenance is complete.	/	NO	17/12/89
	(Name of Person Notified)	(Date)	(Time)	

COMPLETION SHEET (cont'd)

Comments/Additional Holdpoints: None

Used for lifted lead sheet only - F3-21-90

SEE IR # 34061 REM 3/21/90

Q.C. has reviewed this procedure for holdpoints [Signature]  
Signature

APPROVED  DISAPPROVED

FOREMAN [Signature] DATE 3/21/90

COMPLETED BY: DATE

FAIRS 3-21-90





COMPLETION SHEET

Procedure No. 26610-C	Revision 3	Sheet 1 of 2
Tag No. 1 HV 8303D	Description Westinghouse Gate Valves	
Serial No.	Manufacturer Westinghouse	Model
Test Equipment Used Torque Wk VP-3-2276 DUE 6-11-90	MATE / <input checked="" type="checkbox"/> Safety Related/OC Hold Points <input type="checkbox"/> Non-Safety Related	

PROCEDURE STEP	DESCRIPTION	MAINT. INIT/DATE	HOLD POINT (Yes/No)	QC INIT/DATE
4.1.1	Verify Prerequisites	<u>RB 13-19-90</u>	<u>NO</u>	<u>RAF 2/12/90</u>
4.1.2	Notify Shift Supervisor	<u>RB 13-19-90</u>	<u>NO</u>	<u>RAF 4/17/90</u>
4.1.3	Verify Clearance and Tagging	<u>RB 13-19-90</u>	<u>NO</u>	<u>RAF 7/7/90</u>
4.2.1	Visually Check Sealing Surfaces	<u>RB 13-19-90</u>	<u>QC HOLD POINT</u>	<u>WRP 13/20/90</u>
4.2.2	Check Sealing Surface of Disc	<u>RB 13-19-90</u>	<u>QC HOLD POINT</u>	<u>WRP 13/20/90</u>
4.2.3	Check Sealing Surface of Seat	<u>RB 13-19-90</u>	<u>QC HOLD POINT</u>	<u>WRP 13/20/90</u>
4.2.4	Check Stem Pin	<u>NA RB 13/20/90</u>	<u>QC N/A WRP HOLD POINT 13/20/90</u>	<u>1</u>
4.2.5	Check Stem Head and Bearing Blocks	<u>NA RB 13/20/90</u>	<u>QC N/A WRP HOLD POINT 13/20/90</u>	<u>1</u>
4.3.4	Lock Pins Welded	<u>NA RB 13/20/90</u>	<u>QC HOLD POINT 13/20/90</u>	<u>1</u>
4.3.10	Check Cleanliness	<u>RB 13-19-90</u>	<u>QC HOLD POINT</u>	<u>WRP 13/20/90</u>
4.3.12	Torqued Yoke-Bonnet Nuts To <u>969.0</u> ft. lbs	<u>NA RB 13/20/90</u>	<u>QC HOLD POINT</u>	<u>1</u>
4.3.11	Torqued Operator Capscrews To _____ ft. lbs.	<u>NA RB 13/20/90</u>	<u>QC HOLD POINT</u>	<u>1</u>

See Comments \*

Sheet 2 of 2

PROCEDURE STEP	DESCRIPTION	MAINT. INIT/DATE	HOLD POINT (Yes/No)	QC INIT/DATE
4.3.37	Locating pins and guide slots aligned	<u>WBP 1/20/90</u>	<u>HOLD POINT</u>	<u>1</u>
4.3.42	Torqued Main Flange Bolts To <u>2100</u> ft.lbs	<u>WBP 3/20/90</u>	<u>HOLD POINT</u>	<u>AKRB/21/90</u>
4.3.44	Torqued Packing Nuts To _____ ft.lbs	<u>WBP 3/20/90</u>	<u>NO</u>	<u>RAH 4/12/90</u>
4.3.46	Notify Shift Supervisor	<u>WBP 1/20/90</u>	<u>NO</u> <u>KAF</u>	<u>RAH 1/21/90</u>

Comments/additional hold points: IR<sup>#</sup> 33273, WBP, 3/20/90

SEE 25036-C FOR LIFTED LEADS JEA 3/21/90  
\* ONLY MAIN FLANGE REQUIRES TORQUE, VALVE  
WAS DISASSEMBLED AT MAIN FLANGE NO  
REPACK REQUIRED. JAC 3-21-90

QC has reviewed this procedure for hold points RAE 2/10/90  
 Signature

APPROVED ( <input checked="" type="checkbox"/> ) DISAPPROVED ( )
FOREMAN DATE
<u>William H. Allen</u> <u>3-20-90</u>

COMPLETED BY	DATE
<u>William H. Allen</u>	<u>3/20/90</u>

**DATA SHEET 1**  
**MAINTENANCE CLEANLINESS AND HOUSEKEEPING**

Maintenance Work Order No. 18808316 Date 3-17-90

Maintenance Cleanliness and Housekeeping Standard Required  
 B                      C                      D                      (Circle one)

Name of system or component requiring cleaning  
1 HV 8808D

**CLEANLINESS STANDARDS**

<input checked="" type="radio"/> B	C	D	INIT/DATE
Metal clean surface.	Thin rust on carbon steel OK.	Tight mill scale Carbon steel OK.	<u>RSB 13-19-90</u>
Rust allowable 2 sq/in per 1 sq/ft.	Rust allowable 15 sq/in per 1 sq/ft.	Rust which resists brushing.	<u>RSB 13-19-90</u>
*** No particulates/particles removable by brushing.			<u>RSB 13-19-90</u>
*** No oil, grease, or other organic films removable by brushing.			<u>RSB 13-19-90</u>
*** Perform closeout Step 4.3.5.b.6.			<u>1</u>
*** No contaminants removable in large amounts by wiping.			<u>RSB 13-19-90</u>
*** Decon tools and equipment.			<u>RSB 13-19-90</u>
*** Finish maintenance cleaning and housekeeping using Figure 1, "Maintenance Cleanliness and Housekeeping Handout".			<u>RSB 13-19-90</u>

COMMENTS: \_\_\_\_\_

*[Signature]* MAINTENANCE PERSON SIGNATURE/DATE 3-20-90 DATE RESULTS REVIEWED  
 Approved  
 Disapproved

MAINTENANCE FOREMAN SIGNATURE/DATE

\*\*\* (for all cleanliness standards)

\* *supvn initials*

Sheet 1 of 1

DATA SHEET 1  
MAINTENANCE CLEANLINESS AND HOUSEKEEPING

Maintenance Work Order No. 18808316 Date 2-22-90

Maintenance Cleanliness and Housekeeping Standard Required

B                                      C                                      D                                      (Circle one)

Name of system or component requiring cleaning

1204 - 1 HV 8808D

**CLEANLINESS STANDARDS**

<input checked="" type="radio"/> B	C	D	INIT/DATE
Metal clean surface.	Thin rust on carbon steel OK.	Tight mill scale Carbon steel OK.	<u>BGC 2-22-90</u>
Rust allowable 2 sq/in per 1 sq/ft.	Rust allowable 15 sq/in per 1 sq/ft.	Rust which resists brushing.	<u>n/a 2-22-90</u>
*** No particulates/particles removable by brushing.			<u>KCB 13/2/90</u>
*** No oil, grease, or other organic films removable by brushing.			<u>KCB 13/2/90</u>
*** Perform closeout Step 4.3.5.b.6.			<u>DM 3-20-90</u>
*** No contaminants removable in large amounts by wiping.			<u>DM 3-20-90</u>
*** Decon tools and equipment.			<u>KCB 13/2/90</u>
*** Finish maintenance cleaning and housekeeping using Figure 1, "Maintenance Cleanliness and Housekeeping Handout".			<u>KCB 13/2/90</u>

COMMENTS:

\* [Signature] 3/20/90  
MAINTENANCE PERSON SIGNATURE/DATE

DATE RESULTS REVIEWED

[Signature] 3-20-90  
MAINTENANCE FOREMAN SIGNATURE/DATE

(  ) Approved

(  ) Disapproved

\*\*\* (for all cleanliness standards)



ISNO/OTHER # 18808316 INSP PROCEDURE # 85060-C REV # 3 DRAWING # 1X4AA 04-654-1 REV #

LINE/EQUIP # 1HV8888D TEST CODE: ASME Section XI  ANSI B31.1  OTHER \_\_\_\_\_

TYPE OF TEST:  
System Leakage  System Inservice  System Pneumatic   
System Functional  System Hydrostatic  Other \_\_\_\_\_

COMPONENT OR SYSTEM:  
Insulated  Non-Insulated

TEST CONDITIONS: (Complete as applicable)  
Required NOP  NOT  Verified NOP  NOT   
Required \_\_\_\_\_ PSIG Verified \_\_\_\_\_ PSIG  
Required \_\_\_\_\_ F Verified \_\_\_\_\_ F

TEST CONDITION VERIFIED BY:  
Examiner   
Other  Name JEFF GASSER Time 9:30 EDT

TEST INSTRUMENTATION:  
INSTRUMENT # \_\_\_\_\_ Cal. Due Date \_\_\_/\_\_\_/\_\_\_  
INSTRUMENT # \_\_\_\_\_ Cal. Due Date \_\_\_/\_\_\_/\_\_\_  
INSTRUMENT # \_\_\_\_\_ Cal. Due Date \_\_\_/\_\_\_/\_\_\_  
\* Cal. Data Not Required Except For Hydrostatic & Pneumatic Tests

TEST RESULTS:  
SAT.  UNSAT.  DC # 1-90-207

DESCRIPTION OF DEFICIENCY IF UNSAT: Water On Top of Bonnet,  
Water Under Valve On Floor, Valve Body insulated

VISUAL EQUIPMENT ~~GOOD~~: Faded light.

REMARKS:

EXAMINER: D C Lewis LEVEL II DATE 4.14.90

EVALUATOR: N/A  LEVEL DATE

AMII REVIEW: N/A  DATE



# NUCLEAR OPERATIONS QUALITY CONTROL HOLD POINT SHEET

MWO NO: 188 08 316

WHEN THE WORK HAS REACHED THE INDICATED HOLD POINT(S) NOTIFY NUCLEAR OPERATIONS QUALITY CONTROL FOR VERIFICATION OF THE HOLD POINT ACTIVITY  
DO NOT WORK PAST THE HOLD POINT WITHOUT QC APPROVAL

NO:	HOLD POINTS	ASSIGNED		NOTIFIED			WAIVER	
		BY	DATE	INITIAL	TIME	DATE	BY	DATE
①	Notify QC For Hold Points on procedure 26410-C completion sheet.	AP	11/20/80	144500				
②	Notify QC to perform VT-2	DP	11/20/80	144500	10:00	11/20/80		


QUALITY CONTROL INFORMATION/COMMENTS  
(INITIAL AND DATE EACH ENTRY)


TO BE FILLED OUT BY AUTHORIZED PERSONNEL ONLY

Quality Control Inspection Report

VOGTLE GENERATING PLANT—UNITS 1 & 2

34061

Georgia Power 

Page 1 of 1

MWO/ODR/DR No. <b>18808310</b>	Building <b>CONTAINMENT</b>	Procedure/Spec. No./Rev. <b>25036C<sup>2</sup>/B</b>
Room No./Level No. <b>LEVEL "C"</b>	Sys./Start-Up Designator <b>1204</b>	Tag No. <b>14V8308D</b>
Drawing No./Rev. <b>NA</b>	Vendor Manual Log No. <b>NA</b>	Other <b>NA</b>

1. Inspector will use separate form for each completed inspection function(s) and insert original with work package, use continuation sheets when needed.
2. Use simple narrative type report procedure. Reference all applicable drawing numbers, specifications, special instructions, etc., connected with your inspection. Use sketches, when applicable, showing dimensions checked, alignment, physical location of defects found, etc. N/A all blocks not used.
3. Upon completion of the inspection activity, enter results below and sign and date.

Remarks **METHOD OF INSPECTION - VISUAL**  
**VERIFIED CABLES / WIRES RELANDED PER UPTIME**  
**LEAD DATA SHEET ON 25036C<sup>2</sup>/B**

---

Sketch

**NA**

Inspection Results

SAT.       UNSAT—ODR/DR NO.(S):

Inspector **Robert R. McCarty**      Date **3/21/90**

706516A MCS161

Quality Control Inspection Report

VOGTLE GENERATING PLANT--UNITS 1 & 2

33273

Georgia Power

Page 1 of 1


MWO/ODR/DR No. 18808316	Building UNIT 1 CATMT	Procedure/Spec. No./Rev. 26610-C, R/3
Room No./Level No. level C	Sys./Start-Up Designator 1204	Tag No. 1HV8808D
Drawing No./Rev. N/A	Vendor Manual Log No. N/A	Other N/A

- Inspector will use separate form for each completed inspection function(s) and insert original with work package, use continuation sheets when needed.
- Use simple narrative type report procedure. Reference all applicable drawing numbers, specifications, special instructions, etc., connected with your inspection. Use sketches, when applicable, showing dimensions checked, alignment, physical location of defects found, etc. N/A all blocks not used.
- Upon completion of the inspection activity, enter results below and sign and date.

Remarks Performed a visual examination for the following procedure steps. 4.2.1 verified seating surfaces of body and bonnet are clean, smooth and not damaged. 4.2.2 checked disc seating surfaces for nicks, scratches or other abnormalities. 4.2.3 visually checked seating surface of seat ring for nicks, scratches or other abnormalities. 4.3.10 Visually checked valve body and accessible piping for cleanliness.

Sketch

MER # 90-5199, 10" flex gasket



Inspection Results

SAT.

UNSAT—ODR/DR NO.(#):

705016A M03191

Inspector

W. R. Podhowsky Jr

Date

3/20/90


WHITE—Work Package

CANARY—Q.C. Supv.

PINK—Inspector

Quality Control Inspection Report

VOGTLE GENERATING PLANT—UNITS 1 & 2

Georgia Power 

33274

Page 1 of 1


MWO/ODR/DR No. <i>18909316</i>	Building <i>Maint</i>	Procedure/Spec. No./Rev. <i>N/A</i>
Room No./Level No. <i>Cal Room</i>	Sys./Start-Up Designator <i>1204</i>	Tag No. <i>1-HV-5508D</i>
Drawing No./Rev. <i>N/A</i>	Vendor Manual Log No. <i>N/A</i>	Other <i>N/A</i>

1. Inspector will use separate form for each completed inspection function(s) and insert original with work package, use continuation sheets when needed.
2. Use simple narrative type report procedure. Reference all applicable drawing numbers, specifications, special instructions, etc., connected with your inspection. Use sketches, when applicable, showing dimensions checked, alignment, physical location of defects found, etc. N/A all blocks not used.
3. Upon completion of the inspection activity, enter results below and sign and date.

Remarks *Using the visual method, verified torque using VP-3-2656 Torque Wrench (Cal Due Date 3/1/90) with Multiplier VTR-42-01B  
275 ft/lbs = 969.0 ft/lbs*

*inox on torque wrench calibrator VP-3-2774, Cal Due Date 3/1/90*

Sketch



*N/A*

Inspection Results

SAT.     UNSAT—CDR/DR NO.(S):

7055-6A MC5191

Inspector *W.R. Podhachsky Jr*    Date *3/20/90*

Quality Control Inspection Report

VOGTLE GENERATING PLANT—UNITS 1 & 2

33823

Page \_\_\_\_\_ of \_\_\_\_\_

MWO/ODR/DR No. 18808316	Building MAINT.	Procedure/Spec. No./Rev. N/A
Room No./Level No. CAL ROOM	Sys./Start-Up Designator 1204	Tag No. 1-HV-880815
Drawing No./Rev. N/A	Vendor Manual Log No. N/A	Other


- Inspector will use separate form for each completed inspection function(s) and insert original with work package, use continuation sheets when needed.
- Use simple narrative type report procedure. Reference all applicable drawing numbers, specifications, special instructions, etc., connected with your inspection. Use sketches, when applicable, showing dimensions checked, alignment, physical location of defects found, etc. N/A all blocks not used.
- Upon completion of the inspection activity, enter results below and sign and date.

Remarks

VISUALLY VERIFY TORQUE VALUES USING TORQUE WRENCH  
 VP-3-2272 ONE 6-11-90 WITH MULTIPLIER VTR-42-006  
 SET 140 FT/LBS = 2,584 FT/LBS.  
 SET 109 FT/LBS = 2,125 FT/LBS.

Sketch

N/A



Inspection Results

SAT.     UNSAT—ODR/DR NO.(S):


Inspector Andrew R. Row    Date 3/20/10



Quality Control Inspection Report

VOGTLE GENERATING PLANT—UNITS 1 & 2

33827

Georgia Power 


Page \_\_\_\_\_ of \_\_\_\_\_

MWO/ODR/DR No. 188083110	Building CTAT	Procedure/Spec. No./Rev. 26610-C R.3
Room No./Level No. C 171	Sys./Start-Up Designator 1204	Tag No. 1HV-8808D
Drawing No./Rev. N/A	Vendor Manual Log No. N/A	Other N/A

- Inspector will use separate form for each completed inspection function(s) and insert original with work package, use continuation sheets when needed.
- Use simple narrative type report procedure. Reference all applicable drawing numbers, specifications, special instructions, etc., connected with your inspection. Use sketches, when applicable, showing dimensions checked, alignment, physical location of defects found, etc. N/A all blocks not used.
- Upon completion of the inspection activity, enter results below and sign and date.

Remarks DATE 3/21/90  
 VISUALLY VERIFIED TORQUE PER STEP 4.3.32.42  
 2100 FT/03. REF. I.R. # 33823 3/20/90  
 VALVE # 1-HV-8808D

Sketch  
 MITE  
 T.W. # VP-3-2272  
 MULT. VTR-42-006



Inspection Results  
 SAT.     UNSAT—ODR/DR NO.(s):

Inspector Andrew K. Poon    Date 3/21/90

MWO No: 18808316

PROCEDURE & REV No:

26610-C Revision 3

NOTIFY QUALITY CONTROL PRIOR TO PERFORMING THE WORK ACTIVITY  
OR STEP ASSOCIATED WITH THE HOLD (H) OR WITNESS (W) POINT

DO NOT BYPASS QC HOLD OR WITNESS POINTS

STEP No.	H/W	HOLD POINT / WITNESS POINT DESCRIPTION	ASSIGNED BY		NOTIFIED		QC ACTION	
			INIT	DATE	INIT	DATE	INIT	I-W-N/A
	H	Prior to reassembly notify QC to inspect the following:						
4.2.1	H	Sealing surfaces of body to bonnet	AWP	2-8-90	WRP	3/20/90	WRP	I
4.2.2	H	Sealing surfaces of disc					WRP	I
4.2.3	H	Sealing surfaces of seat rings					WRP	I
4.2.4	H	Stem and disc pin for smoothness					WRP	N/A
4.2.5	H	Stem head and bearing blocks for smoothness					WRP	N/A
4.3.4	H	Weld on lock pins at both ends (308 ss wire)					WRP	N/A
4.3.10	H	Valve body and accessible piping for cleanliness				WRP 3/20/90	WRP	I
4.3.12	H	Witness torque of yoke-bonnet nuts on final pass					N/A	
4.3.15	H	Witness torque of operator cap screws on final pass					N/A	
4.3.37	H	Locating pin to ensure it is inserted into its hold and the disc is properly positioned with the guide slots					N/A	
4.3.42	H	Witness torque of mainflange bolts on final pass					AKR 3/20/90	AKR I

COMMENTS & IR NUMBERS: (initial and date entries)

Steps 4.2.1 thru 4.3.10 IR# 33273 WRP 3/20/90



WORK ORDER NO: 188083/6

NOTIFY QUALITY CONTROL PRIOR TO PERFORMING THE WORK ACTIVITY  
ON STEPS ASSOCIATED WITH THE HOLD (H) OR WITNESS (W) POINT

DO NOT BYPASS QC HOLD OR WITNESS POINTS

STEP NO.	H W	HOLD POINT / WITNESS POINT DESCRIPTION	ASSIGNED BY		NOTIFIED DATE		QC ACTION	
			INIT	DATE	INIT	DATE	INIT	I-W-N
4.3.7	H	Notify QC prior to relanding any safety related conductors	DJD	8-3-89				

COMMENTS & IR NUMBERS: (initial and date entries)



MWO/OTHER # 18808316 INSP PROCEDURE # 85051-C REV # R10 DRAWING # 1K4-1204-123-02 REV # R17

TAG # 1-MV-8808 D INSPECTION METHOD: VT-1  VT-3

TYPE OF COMPONENT:  
 BOLTS  STUDS  WASHERS  NUTS  FLANGES   
 PUMP  VALVE   
 FLANGES: ASSEMBLED  DISASSEMBLED   
 ATTACHMENT WELDS: INTERNAL  EXTERNAL   
 REACTOR INTERNALS: WELDS  COMPONENTS

COMPONENT CONDITION:	SAT	UNSAT	N/A
a. Cracks	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
b. Thread damage	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c. Pitting	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
d. Corrosion	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
e. Erosion	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
f. Gouges	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
g. Bending, twisting, or deformed	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
h. Fractured	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
i. Evidence of leakage	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
j. Missing or loose fasteners	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
k. Displacement/alignment of components	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
l. Wear of mating surfaces	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
m. Foreign material	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

EXAMINATION RESULTS: Sat  Unsat  DC # \_\_\_\_\_

DESCRIPTION OF DEFICIENCY IF UNSAT/REMARKS: NONE

METHOD OF EXAMINATION:  
 Direct Examination  Remote Examination

EQUIPMENT USED: Flashlight

NOTE: REFER TO IR # 33273 FOR ORIGINAL DOCUMENTED INSPECTION OF VALVE, THIS IR ISSUED FOR ISI REQUIREMENTS

INSPECTOR <u>W.R. Podhradsky</u>	LEVEL <u>III</u>	DATE <u>4/17/90</u>
EVALUATOR <u>David R. Quatt</u>	N/A <input type="checkbox"/> LEVEL <u>II</u>	DATE <u>4-17-90</u>
ANII REVIEW	N/A <input type="checkbox"/>	DATE





10/2

EQ EVALUATION CHECKLIST

FOR USE ON PROJECT CLASSES Q111, Q212,  
Q313, Q013, Q015, Q11E, Q11J, Q12E, 61J

MWO NO. 1850836

SECTION I

PART A ORIGINAL PART

- 1. DESCRIPTION MCV 10"
- 2. TAG NO. 1-HV-5363D
- 3. PROJECT CLASS 11
- 4. SPECIFICATION (EQDP) NO. 212A66
- 5. MANUFACTURER (W)
- 6. MODEL NO. NA
- 7. PART NO. 1

PART B REPLACEMENT PART

- 1. DESCRIPTION \_\_\_\_\_
- 2. MFR NO. \_\_\_\_\_
- 3. STOCK NO. \_\_\_\_\_
- 4. SPECIFICATION (EQDP) NO. \_\_\_\_\_
- 5. MANUFACTURER \_\_\_\_\_
- 6. MODEL NO. \_\_\_\_\_
- 7. PART NO. \_\_\_\_\_
- 8. PO NO. \_\_\_\_\_

COMMENTS SEE SHEET 2

SECTION II WORK PLANNING

1. ARE PROCEDURES, VENDOR MANUALS, DRAWINGS OR INSTRUCTIONS AVAILABLE TO DISASSEMBLE/REWORK COMPONENT?

YES  NO  
W 12/17/90  
(Init. Date)

2. ARE SPECIFICATION NUMBERS FOR ORIGINAL AND REPLACEMENT ITEMS THE SAME?

YES  NO

3. ARE MANUFACTURER MODEL/PART NUMBERS OF THE ORIGINAL AND REPLACEMENT PARTS THE SAME?

YES  NO

4. IS BULK MATERIAL LISTED ON ATTACHMENT ACCEPTABLE? LIST ITEM NO. FROM ATTACHMENT IF "NO" IS CHECKED.

NA  
(Item No.)

YES  NO  
W 13-22-90  
(Init. Date)

NOTE

If items 2, 3, or 4 are checked No, the Checklist must be reviewed by the EQ Group.

- PART(S) ARE ACCEPTABLE FOR USE
- SEND TO EQ GROUP

W 13-22-90  
WFG DATE

SECTION III EQ GROUP EVALUATION

PART IS ACCEPTABLE FOR USE  PART IS UNACCEPTABLE FOR USE

JUSTIFICATION FOR ACCEPTANCE:

\_\_\_\_\_  
EQ ENGINEER DATE

FIGURE 3

EQ EVALUATION CHECKLIST  
FOR BULK MATERIAL

MWO NO 18409316

1. DESCRIPTION OF ITEM 10" GATE VALVE BONNET GASKET

MER 5199 PO 10387

2. DESCRIPTION OF ITEM \_\_\_\_\_

MER \_\_\_\_\_ PO \_\_\_\_\_

3. DESCRIPTION OF ITEM \_\_\_\_\_

MER \_\_\_\_\_ PO \_\_\_\_\_

4. DESCRIPTION OF ITEM \_\_\_\_\_

MER \_\_\_\_\_ PO \_\_\_\_\_

5. DESCRIPTION OF ITEM \_\_\_\_\_

MER \_\_\_\_\_ PO \_\_\_\_\_

6. DESCRIPTION OF ITEM \_\_\_\_\_

MER \_\_\_\_\_ PO \_\_\_\_\_

7. DESCRIPTION OF ITEM \_\_\_\_\_

MER \_\_\_\_\_ PO \_\_\_\_\_

8. DESCRIPTION OF ITEM \_\_\_\_\_

MER \_\_\_\_\_ PO \_\_\_\_\_

*75H 3-22-90*

REMARKS:

FIGURE 3 (CONT'D.)



## VEGP FIRE PROTECTION CHECKLIST

1. MWO NO. 95-576 2. MPL/TAG NO. 171-5857  
 3. LOCATION CORRIDOR

4. WILL THE WORK INSTALL, IMPAIR, MODIFY, ISOLATE, DEFEAT, OR REMOVE ANY OF THE FOLLOWING? IF THE ANSWER IS "YES" CHECK THE BOX, AND INDICATE APPROPRIATE DETAILS.

- SPRINKLER SYSTEM \_\_\_\_\_  
 INTERIOR HOSE STATION \_\_\_\_\_  
 HALON SYSTEM \_\_\_\_\_  
 DETECTION SYSTEM \_\_\_\_\_  
 EMERGENCY LIGHTING SYSTEM \_\_\_\_\_  
 PERMANENT COMBUSTIBLES (CABLE, WOOD, PLASTIC, ETC.) \_\_\_\_\_  
 STRUCTURAL STEEL, OR RACEWAY FIREPROOFING \_\_\_\_\_  
 FIRE SUPPRESSION SUPPLY SYSTEM (PUMPS, TANKS, ETC.) \_\_\_\_\_  
 CONDUIT SEALS OR EQUIPMENT ENCLOSURE (CABINET HOUSING) \_\_\_\_\_  
 FIRE EXTINGUISHER \_\_\_\_\_  
 COMMUNICATIONS SYSTEM \_\_\_\_\_  
 RCP OIL COLLECTION SYSTEM \_\_\_\_\_  
 SEISMIC STANDPIPE SYSTEM \_\_\_\_\_

5. WILL THE WORK DEFEAT, MODIFY OR IMPAIR ANY OF THE FOLLOWING FIRE SEPARATION FEATURES? IF THE ANSWER IS "YES" CHECK THE BOX, AND INDICATE APPROPRIATE DETAILS.

- A. FIRE AREA BOUNDARY (WALL, ETC.) \_\_\_\_\_  
 B. PASSIVE AREA BOUNDARY PENETRATION SEAL ASSEMBLY.  
 PENETRATION SEAL \_\_\_\_\_  
 WALL BLOCKOUT \_\_\_\_\_  
 FLOOR PLUG OR HATCH \_\_\_\_\_  
 CABLE TRAY OR CONDUIT WRAP \_\_\_\_\_  
 RADIANT ENERGY SHIELD \_\_\_\_\_  
 C. ACTIVE FIRE AREA BOUNDARY PENETRATION SEAL.  
 FIRE DOOR \_\_\_\_\_  
 FIRE DAMPER \_\_\_\_\_

6. IF ALL THE ANSWERS IN BLOCKS 4 and 5 ARE "NO", STOP THE EVALUATION HERE, AND ENTER "NO" IN BLOCK 11 OF THE MWO FORM. IF ANY QUESTIONS WERE ANSWERED "YES", ENTER "YES" IN BLOCK 11 OF THE MWO FORM.

EVALUATOR [Signature] DATE 2/17/90

POST WORK REVIEW (COMPLETE "A, B, OR C" BELOW)

- (A) THE CONDITION IMPACTING THE FIRE PROTECTION COMPONENTS LISTED ABOVE HAS BEEN REMOVED. FPE \_\_\_\_\_ DATE \_\_\_\_\_  
 (B) THE FIRE PROTECTION COMPONENT IS STILL IMPAIRED. FPE \_\_\_\_\_ DATE \_\_\_\_\_  
 (C) RESTORATION OF THE IMPAIRMENT HAS BEEN TRANSFERRED (Ref: \_\_\_\_\_) AND THE FIRE PROTECTION LCO LOG HAS BEEN CHANGED TO REFERENCE THE NEW MWO FOR THIS IMPAIRMENT. FPE \_\_\_\_\_ DATE \_\_\_\_\_