

ESBWR Design Control Document

Tier 2

Chapter 3

Design of Structures,

Components,

Equipment, and

Systems

Appendices 3G - 3L



Contents

| | |
|---|-------|
| 3G. DESIGN DETAILS AND EVALUATION RESULTS OF SEISMIC CATEGORY I STRUCTURES | 3G-1 |
| 3G.1 Reactor Building | 3G-1 |
| 3G.1.1 Objective and Scope..... | 3G-1 |
| 3G.1.2 Conclusions | 3G-1 |
| 3G.1.3 Structural Description | 3G-1 |
| 3G.1.3.1 Description of the Reactor Building | 3G-1 |
| 3G.1.3.1.1 Reactor Building Structure..... | 3G-1 |
| 3G.1.3.1.2 Containment and Containment Structure | 3G-2 |
| 3G.1.3.1.3 Reactor Building Structure/Containment Structure Connections | 3G-2 |
| 3G.1.3.1.4 Containment Internal Structures | 3G-2 |
| 3G.1.4 Analytical Models | 3G-3 |
| 3G.1.4.1 Structural Models | 3G-3 |
| 3G.1.4.2 Foundation Models | 3G-4 |
| 3G.1.5 Structural Analysis and Design | 3G-4 |
| 3G.1.5.1 Site Design Parameters | 3G-4 |
| 3G.1.5.2 Design Loads, Load Combinations, and Material Properties | 3G-5 |
| 3G.1.5.2.1 Design Loads..... | 3G-5 |
| 3G.1.5.2.1.1 Dead Load (D) and Live Load (L and Lo)..... | 3G-5 |
| 3G.1.5.2.1.2 Snow Load | 3G-5 |
| 3G.1.5.2.1.3 Lateral Soil Pressure at Rest | 3G-5 |
| 3G.1.5.2.1.4 Wind Load (W) | 3G-5 |
| 3G.1.5.2.1.5 Tornado Load (W_t) | 3G-5 |
| 3G.1.5.2.1.6 Thermal Loads | 3G-6 |
| 3G.1.5.2.1.7 Pressure Loads | 3G-6 |
| 3G.1.5.2.1.8 Condensation Oscillation (CO) and Chugging (CHUG) Loads..... | 3G-6 |
| 3G.1.5.2.1.9 SRV Loads | 3G-6 |
| 3G.1.5.2.1.10 Steam Tunnel Subcompartment Pressure | 3G-6 |
| 3G.1.5.2.1.11 Subcompartment Pressure in Other Compartments | 3G-6 |
| 3G.1.5.2.1.12 Annulus Pressurization (AP) Loads..... | 3G-7 |
| 3G.1.5.2.1.13 Design Seismic Loads | 3G-7 |
| 3G.1.5.2.2 Load Combinations and Acceptance Criteria | 3G-7 |
| 3G.1.5.2.2.1 Reinforced Concrete Containment Vessel (RCCV)..... | 3G-7 |
| 3G.1.5.2.2.2 Steel Containment Components..... | 3G-7 |
| 3G.1.5.2.2.3 Containment Internal Structures | 3G-7 |
| 3G.1.5.2.2.4 Reactor Building (RB) Concrete Structures Including Pool Girders... | 3G-8 |
| 3G.1.5.2.3 Material Properties | 3G-8 |
| 3G.1.5.2.3.1 Concrete | 3G-8 |
| 3G.1.5.2.3.2 Reinforcing Steel..... | 3G-8 |
| 3G.1.5.2.3.3 Structural Steel..... | 3G-9 |
| 3G.1.5.3 Stability Requirements | 3G-9 |
| 3G.1.5.4 Structural Design Evaluation | 3G-9 |
| 3G.1.5.4.1 Containment Structure | 3G-9 |
| 3G.1.5.4.1.1 Containment Wall Including RPV Pedestal..... | 3G-10 |
| 3G.1.5.4.1.2 Containment Top Slab and Suppression Pool Slab..... | 3G-10 |

| | |
|---|--------|
| 3G.1.5.4.1.3 Containment Foundation Mat | 3G-11 |
| 3G.1.5.4.1.4 Drywell Head | 3G-11 |
| 3G.1.5.4.2 Containment Internal Structures | 3G-12 |
| 3G.1.5.4.2.1 Diaphragm Floor | 3G-13 |
| 3G.1.5.4.2.2 Vent Wall Structure | 3G-13 |
| 3G.1.5.4.2.3 Reactor Shield Wall (RSW) | 3G-14 |
| 3G.1.5.4.2.4 RPV Support Bracket | 3G-14 |
| 3G.1.5.4.2.5 Gravity Driven Cooling System (GDCCS) Pool | 3G-14 |
| 3G.1.5.4.3 Reactor Building | 3G-14 |
| 3G.1.5.4.3.1 RB Shear Walls | 3G-15 |
| 3G.1.5.4.3.2 RB Foundation Mat Outside Containment | 3G-15 |
| 3G.1.5.4.3.3 RB Floor Slabs | 3G-15 |
| 3G.1.5.4.3.4 Pool Girders | 3G-15 |
| 3G.1.5.4.3.5 Main Steam Tunnel Floors and Walls | 3G-15 |
| 3G.1.5.5 Foundation Stability | 3G-15 |
| 3G.1.5.6 Tornado Missile Evaluation | 3G-16 |
| 3G.1.6 References | 3G-16 |
| 3G.2 Control Building | 3G-180 |
| 3G.2.1 Objective and Scope | 3G-180 |
| 3G.2.2 Conclusions | 3G-180 |
| 3G.2.3 Structural Description | 3G-180 |
| 3G.2.4 Analytical Models | 3G-180 |
| 3G.2.4.1 Structural Model | 3G-180 |
| 3G.2.4.2 Foundation Models | 3G-181 |
| 3G.2.5 Structural Analysis and Design | 3G-181 |
| 3G.2.5.1 Site Design Parameters | 3G-181 |
| 3G.2.5.2 Design Loads, Load Combinations, and Material Properties | 3G-181 |
| 3G.2.5.2.1 Design Loads | 3G-181 |
| 3G.2.5.2.1.1 Dead Load (D) and Live Load (L and Lo) | 3G-181 |
| 3G.2.5.2.1.2 Snow Load | 3G-182 |
| 3G.2.5.2.1.3 Lateral Soil Pressure at Rest | 3G-182 |
| 3G.2.5.2.1.4 Wind Load (W) | 3G-182 |
| 3G.2.5.2.1.5 Tornado Load (W_t) | 3G-182 |
| 3G.2.5.2.1.6 Thermal Load (T_o and T_a) | 3G-182 |
| 3G.2.5.2.1.7 Design Seismic Loads | 3G-182 |
| 3G.2.5.2.2 Load Combinations and Acceptance Criteria | 3G-182 |
| 3G.2.5.2.3 Material Properties | 3G-183 |
| 3G.2.5.3 Stability Requirements | 3G-183 |
| 3G.2.5.4 Structural Design Evaluation | 3G-183 |
| 3G.2.5.4.1 Shear Walls | 3G-183 |
| 3G.2.5.4.2 Floor Slabs | 3G-183 |
| 3G.2.5.4.3 Foundation Mat | 3G-183 |
| 3G.2.5.5 Foundation Stability | 3G-184 |
| 3G.2.5.6 Tornado Missile Evaluation | 3G-184 |
| 3G.3 Fuel Building | 3G-218 |
| 3G.3.1 Objective and Scope | 3G-218 |

| | |
|---|--------|
| 3G.3.2 Conclusions | 3G-218 |
| 3G.3.3 Structural Description | 3G-218 |
| 3G.3.4 Analytical Models | 3G-218 |
| 3G.3.5 Structural Analysis and Design | 3G-219 |
| 3G.3.5.1 Site Design Parameters | 3G-219 |
| 3G.3.5.2 Design Loads, Load Combinations, and Material Properties | 3G-219 |
| 3G.3.5.2.1 Design Loads | 3G-219 |
| 3G.3.5.2.1.1 Dead Load (D) and Live Load (L and Lo) | 3G-219 |
| 3G.3.5.2.1.2 Snow Load | 3G-219 |
| 3G.3.5.2.1.3 Lateral Soil Pressure at Rest | 3G-219 |
| 3G.3.5.2.1.4 Wind Load (W) | 3G-219 |
| 3G.3.5.2.1.5 Tornado Load (W_t) | 3G-219 |
| 3G.3.5.2.1.6 Thermal Load (T_o) | 3G-219 |
| 3G.3.5.2.1.7 Design Seismic Loads | 3G-220 |
| 3G.3.5.2.2 Load Combinations and Acceptance Criteria | 3G-220 |
| 3G.3.5.2.3 Material Properties | 3G-220 |
| 3G.3.5.3 Stability Requirements | 3G-220 |
| 3G.3.5.4 Structural Design Evaluation | 3G-220 |
| 3G.3.5.4.1 Shear Walls and Spent Fuel Pool Walls | 3G-220 |
| 3G.3.5.4.2 Floor Slabs | 3G-221 |
| 3G.3.5.4.3 Foundation Mat | 3G-221 |
| 3G.3.5.5 Foundation Stability | 3G-221 |
| 3G.3.5.6 Tornado Missile Evaluation | 3G-221 |
| 3H. EQUIPMENT QUALIFICATION DESIGN ENVIRONMENTAL CONDITIONS | 3H-1 |
| 3H.1 Introduction | 3H-1 |
| 3H.2 Plant Zones | 3H-1 |
| 3H.2.1 Containment Vessel | 3H-1 |
| 3H.2.2 Outside Containment Vessel | 3H-1 |
| 3H.3 Environmental Conditions | 3H-2 |
| 3H.3.1 Plant Normal Operating Conditions | 3H-2 |
| 3H.3.2 Accident Conditions | 3H-2 |
| 3H.3.3 Water Quality | 3H-2 |
| 3H.4 References | 3H-3 |
| 3I. DESIGNATED NEDE-24326-1-P MATERIAL WHICH MAY NOT CHANGE WITHOUT PRIOR NRC APPROVAL | 3I-1 |
| 3I.1 General Requirements for Dynamic Testing | 3I-1 |
| 3I.2 Product and Assembly Testing | 3I-2 |
| 3I.3 Multiple-Frequency Tests | 3I-3 |
| 3I.4 Single- and Multi-axis Tests | 3I-3 |
| 3I.5 Single Frequency Tests | 3I-3 |
| 3I.6 Damping | 3I-3 |
| 3I.7 Qualification Determination | 3I-4 |
| 3I.8 Dynamic Qualification by Analysis | 3I-4 |

| | |
|---|------|
| 3I.9 Required Response Spectra | 3I-4 |
| 3I.10 Time History Analysis..... | 3I-5 |
| 3I.11 References | 3I-5 |
| 3J. EVALUATION OF POSTULATED RUPTURES IN HIGH ENERGY PIPES | 3J-1 |
| 3J.1 Background and Scope | 3J-1 |
| 3J.2 Identification of Rupture Locations and Rupture Geometry..... | 3J-2 |
| 3J.2.1 Ruptures in Containment Penetration Area..... | 3J-2 |
| 3J.2.2 Ruptures in Areas other than Containment Penetration..... | 3J-2 |
| 3J.2.3 Determine the Type of Pipe Break..... | 3J-2 |
| 3J.3 Design and Selection of Pipe Whip Restraints..... | 3J-2 |
| 3J.3.1 Make Preliminary Selection of Pipe Whip Restraint | 3J-2 |
| 3J.3.2 Prepare Simplified Computer Model of Piping-Pipe Whip Restraint System..... | 3J-2 |
| 3J.3.3 Run Pipe Dynamic Analysis..... | 3J-3 |
| 3J.3.4 Select Pipe Whip Restraint for Pipe Whip Restraint Analysis..... | 3J-3 |
| 3J.4 Pipe Rupture Evaluation..... | 3J-3 |
| 3J.4.1 General Approach..... | 3J-3 |
| 3J.4.2 Procedure For Dynamic Time-History Analysis With Simplified Model | 3J-4 |
| 3J.4.2.1 Modeling of Piping System..... | 3J-4 |
| 3J.4.2.2 Dynamic Analysis of Simplified Piping Model | 3J-5 |
| 3J.4.3 Procedure For Dynamic Time-History Analysis Using Detailed Piping Model..... | 3J-5 |
| 3J.4.3.1 Modeling of Piping System..... | 3J-5 |
| 3J.4.3.2 Dynamic Analysis using Detail Piping Model | 3J-5 |
| 3J.5 Jet Impingement on Essential Piping | 3J-6 |
| 3K. RESOLUTION OF INTERSYSTEM LOSS OF COOLANT ACCIDENT..... | 3K-1 |
| 3K.1 Introduction..... | 3K-1 |
| 3K.2 Regulatory Positions | 3K-1 |
| 3K.3 Boundary Limits of Ultimate Rupture Strength..... | 3K-2 |
| 3K.4 Evaluation Procedure | 3K-2 |
| 3K.5 Systems Evaluated | 3K-2 |
| 3K.6 Piping Design Pressure for Ultimate Rupture Strength Compliance..... | 3K-3 |
| 3K.7 Applicability of Ultimate Rupture Strength Non-piping Components | 3K-3 |
| 3K.8 Results..... | 3K-3 |
| 3K.9 Valve Misalignment Due To Operator Error | 3K-3 |
| 3K.10 Summary | 3K-4 |
| 3K.11 References..... | 3K-4 |
| ATTACHMENT 3KA. ULTIMATE RUPTURE STRENGTH SYSTEM BOUNDARY EVALUATION..... | 3K-5 |
| 3KA.1 Control Rod Drive System..... | 3K-5 |
| 3KA.1.1 System URS Boundary Description..... | 3K-5 |
| 3KA.1.2 Downstream Interfaces..... | 3K-5 |
| 3KA.1.3 Low-Pressure Piping Systems and Components Designed to URS Pressure | 3K-6 |
| 3KA.2 Standby Liquid Control System..... | 3K-7 |

| | |
|--|-------|
| 3KA.2.1 System URS Boundary Description..... | 3K-7 |
| 3KA.2.2 Downstream interfaces..... | 3K-7 |
| 3KA.2.3 Low Pressure Piping Systems and Components Designed to URS Pressure.... | 3K-7 |
| 3KA.3 Reactor Water Cleanup/Shutdown Cooling System | 3K-8 |
| 3KA.3.1 System URS Boundary Description..... | 3K-8 |
| 3KA.3.2 Downstream Interfaces..... | 3K-8 |
| 3KA.3.3 Low-Pressure Piping Systems and Components Designed to URS Pressure | 3K-8 |
| 3KA.4 Fuel And Auxiliary Pools Cooling System..... | 3K-9 |
| 3KA.4.1 System URS Boundary Description..... | 3K-9 |
| 3KA.4.2 Downstream Interfaces..... | 3K-9 |
| 3KA.4.3 Low-Pressure Piping Systems and Components Designed to URS Pressure | 3K-9 |
| 3KA.5 Nuclear Boiler System | 3K-10 |
| 3KA.5.1 System URS Boundary Description..... | 3K-10 |
| 3KA.5.2 Downstream Interfaces..... | 3K-10 |
| 3KA.5.3 Low-Pressure Piping Systems and Components Designed to URS Pressure .. | 3K-10 |
| 3KA.6 Condensate And Feedwater System..... | 3K-11 |
| 3KA.6.1 System URS Boundary Description..... | 3K-11 |
| 3KA.6.2 Downstream Interfaces..... | 3K-11 |
| 3KA.6.3 Low-Pressure Piping Systems and Components Designed to URS Pressure .. | 3K-11 |
| 3L. REACTOR INTERNALS FLOW INDUCED VIBRATION PROGRAM..... | 3L-1 |
| 3L.1 Introduction | 3L-1 |
| 3L.2 Reactor Internal Components FIV Evaluation..... | 3L-2 |
| 3L.2.1 Evaluation Process – Part 1 | 3L-2 |
| 3L.2.2 Evaluation Process – Part 2 | 3L-4 |
| 3L.3 Chimney Partition Assembly Evaluation | 3L-5 |
| 3L.3.1 Design and Materials..... | 3L-5 |
| 3L.3.2 Prior Operating Experience | 3L-5 |
| 3L.3.3 Testing and Two-phase Flow Analysis | 3L-5 |
| 3L.4 Steam Dryer Evaluation Program..... | 3L-7 |
| 3L.4.1 Steam Dryer Design and Performance | 3L-7 |
| 3L.4.2 Materials and Fabrication | 3L-7 |
| 3L.4.3 Load Combinations | 3L-7 |
| 3L.4.4 Fluid Loads on the Dryer..... | 3L-8 |
| 3L.4.5 Structural Evaluation..... | 3L-9 |
| 3L.4.6 Instrumentation and Startup Testing | 3L-9 |
| 3L.5 Startup Test Program..... | 3L-12 |
| 3L.5.1 Component Selections..... | 3L-12 |
| 3L.5.2 Sensor Locations | 3L-12 |
| 3L.5.3 Test Conditions..... | 3L-12 |
| 3L.5.4 Data Reduction Methods | 3L-13 |
| 3L.5.4.1 Time History Analysis..... | 3L-13 |
| 3L.5.4.2 Frequency Analysis | 3L-14 |
| 3L.5.5 Data Evaluation Methods | 3L-14 |
| 3L.5.5.1 Finite Element Models | 3L-15 |
| 3L.5.5.1.1 Chimney Head and Steam Separators | 3L-15 |

3L.5.5.1.2 Shroud and Chimney3L-15
3L.5.5.1.3 Steam Dryer3L-16
3L.5.5.1.4 Standby Liquid Control Lines3L-17
3L.5.5.2 Stress Evaluation3L-17
3L.5.5.2.1 Methods I and II3L-19
3L.5.5.2.2 Method III.....3L-22
3L.6 References3L-24

List of Tables

Global Abbreviations And Acronyms List

| | |
|---------------|--|
| Table 3G.1-1 | Soil Spring Constants for the RB Analysis Model |
| Table 3G.1-2 | Site Design Parameters |
| Table 3G.1-3 | Equipment and Hydrostatic Loads inside RCCV |
| Table 3G.1-4 | Equipment and Hydrostatic Loads in RB Pools |
| Table 3G.1-5 | Miscellaneous Structures, Piping, and Commodity Loads on RB Floor |
| Table 3G.1-6 | Equivalent Linear Temperature Distributions at Various Sections |
| Table 3G.1-7 | Pressure Loads Inside RCCV |
| Table 3G.1-8 | Pressure Loads Inside IC/PCCS Pools |
| Table 3G.1-9 | Maximum Vertical Acceleration |
| Table 3G.1-10 | Selected Load Combinations for the RCCV |
| Table 3G.1-11 | Selected Load Combinations for the RB |
| Table 3G.1-12 | Material Constants for Design Calculations |
| Table 3G.1-13 | Results of NASTRAN Analysis, Dead Load |
| Table 3G.1-14 | Results of NASTRAN Analysis, Drywell Unit Pressure (1 MPa) |
| Table 3G.1-15 | Results of NASTRAN Analysis, Wetwell Unit Pressure (1 MPa) |
| Table 3G.1-16 | Results of NASTRAN Analysis, Temperature Load (Normal Operation: Winter) |
| Table 3G.1-17 | Results of NASTRAN Analysis, Temperature Load (LOCA After 6 minutes: Winter) |
| Table 3G.1-18 | Results of NASTRAN Analysis, Temperature Load (LOCA After 72 hours: Winter) |
| Table 3G.1-19 | Results of NASTRAN Analysis, Seismic Load (Horizontal: North to South Direction) |
| Table 3G.1-20 | Results of NASTRAN Analysis, Seismic Load (Horizontal: East to West Direction) |
| Table 3G.1-21 | Results of NASTRAN Analysis, Seismic Load (Vertical: Upward Direction) |
| Table 3G.1-22 | Combined Forces and Moments: RCCV, Selected Load Combination CV-1 |
| Table 3G.1-23 | Combined Forces and Moments: RCCV, Selected Load Combination CV-7a |
| Table 3G.1-24 | Combined Forces and Moments: RCCV, Selected Load Combination CV-7b |
| Table 3G.1-25 | Combined Forces and Moments: RCCV, Selected Load Combination CV-11a |
| Table 3G.1-26 | Combined Forces and Moments: RCCV, Selected Load Combination CV-11b |
| Table 3G.1-27 | Sectional Thicknesses and Rebar Ratios of RCCV Used in the Evaluation |
| Table 3G.1-28 | Rebar and Concrete Stresses of RCCV: Selected Load Combination CV-1 |
| Table 3G.1-29 | Rebar and Concrete Stresses of RCCV: Selected Load Combination CV-7a |
| Table 3G.1-30 | Rebar and Concrete Stresses of RCCV: Selected Load Combination CV-7b |
| Table 3G.1-31 | Rebar and Concrete Stresses of RCCV: Selected Load Combination CV-11a |
| Table 3G.1-32 | Rebar and Concrete Stresses of RCCV: Selected Load Combination CV-11b |
| Table 3G.1-33 | Transverse Shear of RCCV |
| Table 3G.1-34 | Tangential Shear of RCCV |
| Table 3G.1-35 | Containment Liner Plate Strains (Max) |
| Table 3G.1-36 | Drywell Head Elements Stress Summary |
| Table 3G.1-37 | Diaphragm Floor (D/F) Slab Elements Stress Summary |
| Table 3G.1-38 | Diaphragm Floor (D/F) Slab Anchorage Structural Capacity |
| Table 3G.1-39 | Vent Wall Structural Elements Stress Summary |

| | |
|---------------|--|
| Table 3G.1-40 | Reactor Shield Wall (RSW) Structural Element Stress Summary |
| Table 3G.1-41 | RPV Support Bracket Structural Elements Stress Summary |
| Table 3G.1-42 | Vent Wall and RPV Support Bracket Anchorage Structural Capacity |
| Table 3G.1-43 | Gravity Driven Cooling System (GDCS) Pool Structural Elements Stress Summary |
| Table 3G.1-44 | Gravity Driven Cooling System (GDCS) Pool Anchorage Structural Capacity |
| Table 3G.1-45 | Combined Forces and Moments: RB, Selected Load Combination RB-4 |
| Table 3G.1-46 | Combined Forces and Moments: RB, Selected Load Combination RB-8a |
| Table 3G.1-47 | Combined Forces and Moments: RB, Selected Load Combination RB-8b |
| Table 3G.1-48 | Combined Forces and Moments: RB, Selected Load Combination RB-9a |
| Table 3G.1-49 | Combined Forces and Moments: RB, Selected Load Combination RB-9b |
| Table 3G.1-50 | Sectional Thicknesses and Rebar Ratios of RB Used in the Evaluation |
| Table 3G.1-51 | Rebar and Concrete Stresses of RB: Selected Load Combination RB-4 |
| Table 3G.1-52 | Rebar and Concrete Stresses of RB: Selected Load Combination RB-8a |
| Table 3G.1-53 | Rebar and Concrete Stresses of RB: Selected Load Combination RB-8b |
| Table 3G.1-54 | Rebar and Concrete Stresses of RB: Selected Load Combination RB-9a |
| Table 3G.1-55 | Rebar and Concrete Stresses of RB: Selected Load Combination RB-9b |
| Table 3G.1-56 | Transverse Shear of RB |
| Table 3G.1-57 | Factors of Safety for Foundation Stability |
| Table 3G.1-58 | Maximum Soil Bearing Stress Involving SSE |
| Table 3G.2-1 | Soil Spring Constants for the CB Analysis Model |
| Table 3G.2-2 | Equipment Load of CB |
| Table 3G.2-3 | Miscellaneous Structures, Piping, and Commodity Load of CB |
| Table 3G.2-4 | Equivalent Liner Temperature Distributions at Various Sections |
| Table 3G.2-5 | Maximum Vertical Acceleration |
| Table 3G.2-6 | Selected Load Combinations for the CB |
| Table 3G.2-7 | Results of NASTRAN Analysis: Dead Load |
| Table 3G.2-8 | Results of NASTRAN Analysis: Temperature Load (LOCA: Winter) |
| Table 3G.2-9 | Results of NASTRAN Analysis: Seismic Load (Horizontal: North to South Direction) |
| Table 3G.2-10 | Results of NASTRAN Analysis: Seismic Load (Horizontal: East to West Direction) |
| Table 3G.2-11 | Results of NASTRAN Analysis: Seismic Load (Vertical: Downward Direction) |
| Table 3G.2-12 | Combined Forces and Moments: Selected Load Combination CB-3 |
| Table 3G.2-13 | Combined Forces and Moments: Selected Load Combination CB-7 |
| Table 3G.2-14 | Combined Forces and Moments: Selected Load Combination CB-9 |
| Table 3G.2-15 | Sectional Thicknesses and Rebar Ratios Used in the Evaluation |
| Table 3G.2-16 | Rebar and Concrete Stresses (Basemat and Slabs): Selected Load Combination CB-3 |
| Table 3G.2-17 | Rebar and Concrete Stresses (Walls): Selected Load Combination CB-3 |
| Table 3G.2-18 | Rebar and Concrete Stresses (Basemat and Slabs): Selected Load Combination CB-7 |
| Table 3G.2-19 | Rebar and Concrete Stresses (Walls): Selected Load Combination CB-7 |
| Table 3G.2-20 | Rebar and Concrete Stresses (Basemat and Slabs): Selected Load Combination CB-9 |
| Table 3G.2-21 | Rebar and Concrete Stresses (Walls): Selected Load Combination CB-9 |

| | |
|---------------|--|
| Table 3G.2-22 | Calculation Results for Transverse Shear |
| Table 3G.2-23 | Factors of Safety for Foundation Stability |
| Table 3G.2-24 | Maximum Soil Bearing Stress Involving SSE |
| Table 3G.3-1 | Miscellaneous Structures and Commodity in Spent Fuel Pool |
| Table 3G.3-2 | Miscellaneous Structures, Piping, and Commodity Load on FB Floor |
| Table 3G.3-3 | Equivalent Liner Temperature Distributions at Various Sections* |
| Table 3G.3-4 | Selected Load Combinations for the FB |
| Table 3G.3-5 | Results of NASTRAN Analysis: Dead Load |
| Table 3G.3-6 | Results of NASTRAN Analysis: Temperature Load (Winter) |
| Table 3G.3-7 | Results of NASTRAN Analysis: Seismic Load (Horizontal: North to South Direction) |
| Table 3G.3-8 | Results of NASTRAN Analysis: Seismic Load (Horizontal: East to West Direction) |
| Table 3G.3-9 | Results of NASTRAN Analysis: Seismic Load (Vertical: Upward Direction) |
| Table 3G.3-10 | Combined Forces and Moments: Selected Load Combination FB-4 |
| Table 3G.3-11 | Combined Forces and Moments: Selected Load Combination FB-8 |
| Table 3G.3-12 | Combined Forces and Moments: Selected Load Combination FB-9 |
| Table 3G.3-13 | Sectional Thicknesses and Rebar Ratios Used in the Evaluation |
| Table 3G.3-14 | Rebar and Concrete Stresses: Selected Load Combination FB-4 |
| Table 3G.3-15 | Rebar and Concrete Stresses: Selected Load Combination FB-8 |
| Table 3G.3-16 | Rebar and Concrete Stresses: Selected Load Combination FB-9 |
| Table 3G.3-17 | Transverse Shear of FB |
| Table 3H-1 | Cross Reference of Plant Environmental Data and Location |
| Table 3H-2 | Thermodynamic Environment Conditions Inside Containment Vessel for Normal Operating Conditions |
| Table 3H-3 | Thermodynamic Environment Conditions Inside Reactor Building for Normal Operating Conditions |
| Table 3H-4 | Thermodynamic Environment Conditions Inside Control Building for Normal Operating Conditions |
| Table 3H-5 | Radiation Environment Conditions Inside Containment Vessel for Normal Operating Conditions |
| Table 3H-6 | Radiation Environment Conditions Inside Reactor Building for Normal Operating Conditions |
| Table 3H-7 | Radiation Environment Conditions Inside Control Building for Normal Operating Conditions |
| Table 3H-8 | Thermodynamic Environment Conditions Inside Containment Vessel for Accident Conditions |
| Table 3H-9 | Thermodynamic Environment Conditions Inside Reactor Building for Accident Conditions |
| Table 3H-10 | Thermodynamic Environment Conditions Inside Control Room Zone for Accident Conditions |
| Table 3H-11 | Radiation Environment Conditions Inside Containment Vessel for Accident Conditions |
| Table 3H-12 | Radiation Environment Inside Reactor Building for Accident Conditions |
| Table 3H-13 | Radiation Environment Conditions Inside Control Room Zone for Accident Conditions |

- Table 3L-1 Comparison of Major Steam Dryer Configuration Parameters
- Table 3L-2 Specific Steam Dryer Load Definition Legend
- Table 3L-3 Typical Vibration Sensors
- Table 3L-4 Typical Sensor Locations and Types
- Table 3L-5 Applicable Data Reduction Method for Comparison to Criteria
- Table 3L-6 Parameters Used in Spectrum Generation
- Table 3L-7 Data Evaluation Methods to be Used for Each Component

List of Illustrations

- Figure 3G.1-1. RB and FB Concrete Outline Plan at EL -11500
- Figure 3G.1-2. RB and FB Concrete Outline Plan at EL 4650
- Figure 3G.1-3. RB and FB Concrete Outline Plan at EL 17500
- Figure 3G.1-4. RB and FB Concrete Outline Plan at EL 27000
- Figure 3G.1-5. RB Concrete Outline Plan at EL 34000
- Figure 3G.1-6. RB and FB Concrete Outline N-S Section
- Figure 3G.1-7. RB and FB Concrete Outline E-W Section
- Figure 3G.1-8. FE Model of RB/FB (Isometric View)
- Figure 3G.1-9. FE Model of RB/FB (Foundation Mat)
- Figure 3G.1-10. FE Model of RB/FB (RCCV Wall)
- Figure 3G.1-11. FE Model of RB/FB (RPV Pedestal)
- Figure 3G.1-12. FE Model of RB/FB (Top Slab)
- Figure 3G.1-13. FE Model of RB/FB (Suppression Pool Slab)
- Figure 3G.1-14. FE Model of RB/FB (External Wall: North Side)
- Figure 3G.1-15. FE Model of RB/FB (External Wall: East Side)
- Figure 3G.1-16. FE Model of RB/FB (Internal Wall on R7/F1 Column Line)
- Figure 3G.1-17. FE Model of RB/FB (RCCV Internals)
- Figure 3G.1-18. FE Model of RB/FB (RCCV Liner)
- Figure 3G.1-19. Soil Pressure at Rest
- Figure 3G.1-20. Sections Where Temperature Loads Are Defined
- Figure 3G.1-21. Condensation Oscillation (CO) Pressure Loads
- Figure 3G.1-22. Chugging (CHUG) Pressure Loads
- Figure 3G.1-23. Safety Relief Valve (SRV) Pressure Loads
- Figure 3G.1-24. Design Seismic Shears and Moments for RB and FB Walls
- Figure 3G.1-25. Design Seismic Shears and Moments for RCCV
- Figure 3G.1-26. Design Seismic Shears and Moments for RPV Pedestal and Vent Wall
- Figure 3G.1-27. Seismic Lateral Soil Pressure
- Figure 3G.1-28. Section Considered for Analysis
- Figure 3G.1-29. Force and Moment in Shell Element
- Figure 3G.1-30. Section Deformation for Dead Load
- Figure 3G.1-31. Section Deformation for Drywell Unit Pressure (1 MPa)
- Figure 3G.1-32. Section Deformation for Wetwell Unit Pressure (1 MPa)
- Figure 3G.1-33. Section Deformation for Temperature Load (Normal Operation: Winter)
- Figure 3G.1-34. Section Deformation for Temperature Load (LOCA After 6 min.: Winter)
- Figure 3G.1-35. Section Deformation for Temperature Load (LOCA After 72 hr.: Winter)
- Figure 3G.1-36. Section Deformation for Seismic Load (Horizontal: North to South)
- Figure 3G.1-37. Section Deformation for Seismic Load (Horizontal: East to West)
- Figure 3G.1-38. Section Deformation for Seismic Load (Vertical: Upward)
- Figure 3G.1-39. Flow Chart for Structural Analysis and Design
- Figure 3G.1-40. Reinforcing Steel of Foundation Mat: Plan
- Figure 3G.1-41. Reinforcing Steel of Foundation Mat: Section A-A
- Figure 3G.1-42. Reinforcing Steel of RCCV Wall
- Figure 3G.1-43. Reinforcing Steel of Suppression Pool Slab
- Figure 3G.1-44. Reinforcing Steel of Top Slab

Figure 3G.1-45. Reinforcing Steel of RPV Pedestal
Figure 3G.1-46. Reinforcing Steel of IC/PCCS Pool Girder
Figure 3G.1-47. List of RB Wall and Slab Reinforcement
Figure 3G.1-48. Liner Anchor
Figure 3G.1-49. Liner Plate Plans
Figure 3G.1-50. Liner Plate Development Elevation
Figure 3G.1-51. Drywell Head
Figure 3G.1-52. Equipment Hatch
Figure 3G.1-53. Wetwell Hatch
Figure 3G.1-54. Personnel Airlock
Figure 3G.1-55. Diaphragm Floor
Figure 3G.1-56. Diaphragm Floor Slab Anchor
Figure 3G.1-57. RPV Support Bracket & Vent Wall
Figure 3G.1-58. Reactor Shield Wall
Figure 3G.1-59. GDCS Pool
Figure 3G.2-1. CB Concrete Outline Plan at EL -7400 and Foundation Reinforcement
Figure 3G.2-2. CB Concrete Outline Plan at EL -2000/4850 and Section Details
Figure 3G.2-3. CB Concrete Outline Plan at EL 9060, Section and Section Detail
Figure 3G.2-4. FE Model of CB (Isometric View)
Figure 3G.2-5. FE Model of CB (Foundation Mat)
Figure 3G.2-6. FE Model of CB (External Wall: South Side)
Figure 3G.2-7. FE Model of CB (External Wall: East Side)
Figure 3G.2-8. FE Model of CB (Floor Slab: EL -2000)
Figure 3G.2-9. FE Model of CB (Floor Slab: EL 4650)
Figure 3G.2-10. Soil Pressure at Rest
Figure 3G.2-11. Sections Where Temperature Loads Are Defined
Figure 3G.2-12. Design Seismic Shears and Moments for CB
Figure 3G.2-13. Seismic Lateral Soil Pressure
Figure 3G.2-14. Force and Moment in Shell Element
Figure 3G.3-1. Sections Where Temperature Loads Are Defined
Figure 3G.3-2. Section Considered for Analysis
Figure 3G.3-3. Force and Moment in Shell Element
Figure 3G.3-4. Reinforcing Steel of Spent Fuel Pool Walls
Figure 3G.3-5. List of FB Wall and Slab Reinforcement
Figure 3H-1. Environmental Zones in the Containment Vessel
Figure 3H-2. Reactor Building Arrangements
Figure 3H-3. HCU Rooms
Figure 3H-4. CRD Pump Room
Figure 3H-5. SLC System Room
Figure 3H-6. Battery Rooms
Figure 3H-7. Electrical Division Rooms
Figure 3H-8. RPS Arrangement
Figure 3H-9. SPTMS Arrangement
Figure 3H-10. Sensors & Electrical Modules Arrangements For LD&IS, PRMS, CMS
Figure 3H-11. Electrical Modules Arrangements For NMS, E-DCIS
Figure 3H-12. Isolation & Shutoff Valves Arrangements For RWCU/SDC

- Figure 3H-13. MS and FW Tunnel Isolation Valve Arrangements
- Figure 3H-14. ICS Condenser and Piping Arrangement Outside Containment
- Figure 3H-15. Main Control Room Panel Arrangement
- Figure 3H-16. Emergency Breathing Air System Arrangement
- Figure 3H-17. 1E DCIS Rooms Arrangement
- Figure 3J-1. Simplified Piping Models
- Figure 3J-2. Representation of Pipe With Both Ends Supported With a Longitudinal Break
- Figure 3L-1. Chimney and Partition Assembly
- Figure 3L-2. ESBWR Steam Dryer Assembly

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|--------------------|--|
| 10 CFR | Title 10, Code of Federal Regulations |
| A/D | Analog-to-Digital |
| AASHTO | American Association of Highway and Transportation Officials |
| AB | Auxiliary Boiler |
| ABS | Auxiliary Boiler System |
| ABWR | Advanced Boiling Water Reactor |
| ac / AC | Alternating Current |
| AC | Air Conditioning |
| ACF | Automatic Control Function |
| ACI | American Concrete Institute |
| ACS | Atmospheric Control System |
| AD | Administration Building |
| ADS | Automatic Depressurization System |
| AEC | Atomic Energy Commission |
| AFIP | Automated Fixed In-Core Probe |
| AGMA | American Gear Manufacturer's Association |
| AHS | Auxiliary Heat Sink |
| AISC | American Institute of Steel Construction |
| AISI | American Iron and Steel Institute |
| AL | Analytical Limit |
| ALARA | As Low As Reasonably Achievable |
| ALWR | Advanced Light Water Reactor |
| ANS | American Nuclear Society |
| ANSI | American National Standards Institute |
| AOO | Anticipated Operational Occurrence |
| AOV | Air Operated Valve |
| API | American Petroleum Institute |
| APLHGR | Average Planar Linear Head Generation Rate |
| APRM | Average Power Range Monitor |
| APR | Automatic Power Regulator |
| APRS | Automatic Power Regulator System |
| ARI | Alternate Rod Insertion |
| ARMS | Area Radiation Monitoring System |
| ASA | American Standards Association |
| ASD | Adjustable Speed Drive |
| ASHRAE | American Society of Heating, Refrigerating, and Air Conditioning Engineers |
| ASME | American Society of Mechanical Engineers |
| AST | Alternate Source Term |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|--------------------|--|
| ASTM | American Society of Testing Methods |
| AT | Unit Auxiliary Transformer |
| ATLM | Automated Thermal Limit Monitor |
| ATWS | Anticipated Transients Without Scram |
| AV | Allowable Value |
| AWS | American Welding Society |
| AWWA | American Water Works Association |
| B&PV | Boiler and Pressure Vessel |
| BAF | Bottom of Active Fuel |
| BHP | Brake Horse Power |
| BOP | Balance of Plant |
| BPU | Bypass Unit |
| BPWS | Banked Position Withdrawal Sequence |
| BRE | Battery Room Exhaust |
| BRL | Background Radiation Level |
| BTP | NRC Branch Technical Position |
| BTU | British Thermal Unit |
| BWR | Boiling Water Reactor |
| BWROG | Boiling Water Reactor Owners Group |
| CAV | Cumulative absolute velocity |
| C&FS | Condensate and Feedwater System |
| C&I | Control and Instrumentation |
| C/C | Cooling and Cleanup |
| CB | Control Building |
| CBHVAC | Control Building HVAC |
| CCI | Core-Concrete Interaction |
| CDF | Core Damage Frequency |
| CFR | Code of Federal Regulations |
| CIRC | Circulating Water System |
| CIS | Containment Inerting System |
| CIV | Combined Intermediate Valve |
| CLAVS | Clean Area Ventilation Subsystem of Reactor Building HVAC |
| CM | Cold Machine Shop |
| CMS | Containment Monitoring System |
| CMU | Control Room Multiplexing Unit |
| COL | Combined Operating License |
| COLR | Core Operating Limits Report |
| CONAVS | Controlled Area Ventilation Subsystem of Reactor Building HVAC |
| CPR | Critical Power Ratio |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|-------------|--|
| CPS | Condensate Purification System |
| CPU | Central Processing Unit |
| CR | Control Rod |
| CRD | Control Rod Drive |
| CRDA | Control Rod Drop Accident |
| CRDH | Control Rod Drive Housing |
| CRDHS | Control Rod Drive Hydraulic System |
| CRGT | Control Rod Guide Tube |
| CRHA | Control Room Habitability Area |
| CRT | Cathode Ray Tube |
| CS&TS | Condensate Storage and Transfer System |
| CSDM | Cold Shutdown Margin |
| CS / CST | Condensate Storage Tank |
| CT | Main Cooling Tower |
| CTVCF | Constant Voltage Constant Frequency |
| CUF | Cumulative usage factor |
| CWS | Chilled Water System |
| D-RAP | Design Reliability Assurance Program |
| DAC | Design Acceptance Criteria |
| DAW | Dry Active Waste |
| DBA | Design Basis Accident |
| dc / DC | Direct Current |
| DCS | Drywell Cooling System |
| DCIS | Distributed Control and Information System |
| DEPSS | Drywell Equipment and Pipe Support Structure |
| DF | Decontamination Factor |
| D/F | Diaphragm Floor |
| DG | Diesel-Generator |
| DHR | Decay Heat Removal |
| DM&C | Digital Measurement and Control |
| DOF | Degree of freedom |
| DOI | Dedicated Operators Interface |
| DOT | Department of Transportation |
| dPT | Differential Pressure Transmitter |
| DPS | Diverse Protection System |
| DPV | Depressurization Valve |
| DR&T | Design Review and Testing |
| DS | Independent Spent Fuel Storage Installation |
| DTM | Digital Trip Module |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|--------------------|---|
| DW | Drywell |
| EB | Electrical Building |
| EBAS | Emergency Breathing Air System |
| EBHV | Electrical Building HVAC |
| ECCS | Emergency Core Cooling System |
| E-DCIS | Essential DCIS (Distributed Control and Information System) |
| EDO | Environmental Qualification Document |
| EFDS | Equipment and Floor Drainage System |
| EFPY | Effective full power years |
| EHC | Electrohydraulic Control (Pressure Regulator) |
| ENS | Emergency Notification System |
| EOC | Emergency Operations Center |
| EOC | End of Cycle |
| EOF | Emergency Operations Facility |
| EOP | Emergency Operating Procedures |
| EPDS | Electric Power Distribution System |
| EPG | Emergency Procedure Guidelines |
| EPRI | Electric Power Research Institute |
| EQ | Environmental Qualification |
| ERICP | Emergency Rod Insertion Control Panel |
| ERIP | Emergency Rod Insertion Panel |
| ESF | Engineered Safety Feature |
| ETS | Emergency Trip System |
| FAC | Flow-Accelerated Corrosion |
| FAPCS | Fuel and Auxiliary Pools Cooling System |
| FATT | Fracture Appearance Transition Temperature |
| FB | Fuel Building |
| FBHV | Fuel Building HVAC |
| FCI | Fuel-Coolant Interaction |
| FCM | File Control Module |
| FCS | Flammability Control System |
| FCU | Fan Cooling Unit |
| FDDI | Fiber Distributed Data Interface |
| FFT | Fast Fourier Transform |
| FFWTR | Final Feedwater Temperature Reduction |
| FHA | Fire Hazards Analysis |
| FIV | Flow-Induced Vibration |
| FMCRD | Fine Motion Control Rod Drive |
| FMEA | Failure Modes and Effects Analysis |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|--------------------|--|
| FPS | Fire Protection System |
| FO | Diesel Fuel Oil Storage Tank |
| FOAKE | First-of-a-Kind Engineering |
| FPE | Fire Pump Enclosure |
| FTDC | Fault-Tolerant Digital Controller |
| FTS | Fuel Transfer System |
| FW | Feedwater |
| FWCS | Feedwater Control System |
| FWS | Fire Water Storage Tank |
| GCS | Generator Cooling System |
| GDC | General Design Criteria |
| GDCS | Gravity-Driven Cooling System |
| GE | General Electric Company |
| GE-NE | GE Nuclear Energy |
| GEN | Main Generator System |
| GETAB | General Electric Thermal Analysis Basis |
| GL | Generic Letter |
| GM | Geiger-Mueller Counter |
| GM-B | Beta-Sensitive GM Detector |
| GSIC | Gamma-Sensitive Ion Chamber |
| GSOS | Generator Sealing Oil System |
| GWSR | Ganged Withdrawal Sequence Restriction |
| HAZ | Heat-Affected Zone |
| HCU | Hydraulic Control Unit |
| HCW | High Conductivity Waste |
| HDVS | Heater Drain and Vent System |
| HEI | Heat Exchange Institute |
| HELB | High Energy Line Break |
| HEP | Human error probability |
| HEPA | High Efficiency Particulate Air/Absolute |
| HFE | Human Factors Engineering |
| HFF | Hollow Fiber Filter |
| HGCS | Hydrogen Gas Cooling System |
| HIC | High Integrity Container |
| HID | High Intensity Discharge |
| HIS | Hydraulic Institute Standards |
| HM | Hot Machine Shop & Storage |
| HP | High Pressure |
| HPNSS | High Pressure Nitrogen Supply System |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|-------------|---|
| HPT | High-pressure turbine |
| HRA | Human Reliability Assessment |
| HSI | Human-System Interface |
| HSSS | Hardware/Software System Specification |
| HVAC | Heating, Ventilation and Air Conditioning |
| HVS | High Velocity Separator |
| HWCS | Hydrogen Water Chemistry System |
| HWS | Hot Water System |
| HX | Heat Exchanger |
| I&C | Instrumentation and Control |
| I/O | Input/Output |
| IAS | Instrument Air System |
| IASCC | Irradiation Assisted Stress Corrosion Cracking |
| IBC | International Building Code |
| IC | Isolation Condenser |
| ICD | Interface Control Diagram |
| ICS | Isolation Condenser System |
| IE | Inspection and Enforcement |
| IEB | Inspection and Enforcement Bulletin |
| IED | Instrument and Electrical Diagram |
| IEEE | Institute of Electrical and Electronic Engineers |
| IGSCC | Intergranular Stress Corrosion Cracking |
| IIS | Iron Injection System |
| ILRT | Integrated Leak Rate Test |
| IOP | Integrated Operating Procedure |
| IMC | Induction Motor Controller |
| IMCC | Induction Motor Controller Cabinet |
| IRM | Intermediate Range Monitor |
| ISA | Instrument Society of America |
| ISI | In-Service Inspection |
| ISLOCA | Intersystem Loss of Coolant Accident |
| ISLT | In-Service Leak Test |
| ISM | Independent Support Motion |
| ISMA | Independent Support Motion Response Spectrum Analysis |
| ISO | International Standards Organization |
| ITA | Inspections, Tests or Analyses |
| ITAAC | Inspections, Tests, Analyses and Acceptance Criteria |
| ITA | Initial Test Program |
| LAPP | Loss of Alternate Preferred Power |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|--------------------|--|
| LCO | Limiting Conditions for Operation |
| LCW | Low Conductivity Waste |
| LD | Logic Diagram |
| LDA | Lay down Area |
| LD&IS | Leak Detection and Isolation System |
| LERF | Large early release frequency |
| LFCV | Low Flow Control Valve |
| LHGR | Linear Heat Generation Rate |
| LLRT | Local Leak Rate Test |
| LMU | Local Multiplexer Unit |
| LO | Dirty/Clean Lube Oil Storage Tank |
| LOCA | Loss-of-Coolant-Accident |
| LOFW | Loss-of-feedwater |
| LOOP | Loss of Offsite Power |
| LOPP | Loss of Preferred Power |
| LP | Low Pressure |
| LPCI | Low Pressure Coolant Injection |
| LPCRD | Locking Piston Control Rod Drive |
| LPMS | Loose Parts Monitoring System |
| LPRM | Local Power Range Monitor |
| LPSP | Low Power Setpoint |
| LWMS | Liquid Waste Management System |
| MAAP | Modular Accident Analysis Program |
| MAPLHGR | Maximum Average Planar Linear Head Generation Rate |
| MAPRAT | Maximum Average Planar Ratio |
| MBB | Motor Built-In Brake |
| MCC | Motor Control Center |
| MCES | Main Condenser Evacuation System |
| MCPR | Minimum Critical Power Ratio |
| MCR | Main Control Room |
| MCRP | Main Control Room Panel |
| MELB | Moderate Energy Line Break |
| MLHGR | Maximum Linear Heat Generation Rate |
| MMI | Man-Machine Interface |
| MMIS | Man-Machine Interface Systems |
| MOV | Motor-Operated Valve |
| MPC | Maximum Permissible Concentration |
| MPL | Master Parts List |
| MS | Main Steam |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|--------------------|--|
| MSIV | Main Steam Isolation Valve |
| MSL | Main Steamline |
| MSLB | Main Steamline Break |
| MSLBA | Main Steamline Break Accident |
| MSR | Moisture Separator Reheater |
| MSV | Mean Square Voltage |
| MT | Main Transformer |
| MTTR | Mean Time To Repair |
| MWS | Makeup Water System |
| NBR | Nuclear Boiler Rated |
| NBS | Nuclear Boiler System |
| NCIG | Nuclear Construction Issues Group |
| NDE | Nondestructive Examination |
| NE-DCIS | Non-Essential Distributed Control and Information System |
| NDRC | National Defense Research Committee |
| NDT | Nil Ductility Temperature |
| NFPA | National Fire Protection Association |
| NIST | National Institute of Standard Technology |
| NMS | Neutron Monitoring System |
| NOV | Nitrogen Operated Valve |
| NPHS | Normal Power Heat Sink |
| NPSH | Net Positive Suction Head |
| NRC | Nuclear Regulatory Commission |
| NRHX | Non-Regenerative Heat Exchanger |
| NS | Non-seismic |
| NSSS | Nuclear Steam Supply System |
| NT | Nitrogen Storage Tank |
| NTSP | Nominal Trip Setpoint |
| O&M | Operation and Maintenance |
| O-RAP | Operational Reliability Assurance Program |
| OBCV | Overboard Control Valve |
| OBE | Operating Basis Earthquake |
| OGS | Offgas System |
| OHLHS | Overhead Heavy Load Handling System |
| OIS | Oxygen Injection System |
| OLMCPR | Operating Limit Minimum Critical Power Ratio |
| OLU | Output Logic Unit |
| OOS | Out-of-service |
| ORNL | Oak Ridge National Laboratory |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|-------------|---|
| OSC | Operational Support Center |
| OSHA | Occupational Safety and Health Administration |
| OSI | Open Systems Interconnect |
| P&ID | Piping and Instrumentation Diagram |
| PA/PL | Page/Party-Line |
| PABX | Private Automatic Branch (Telephone) Exchange |
| PAM | Post Accident Monitoring |
| PAR | Passive Autocatalytic Recombiner |
| PAS | Plant Automation System |
| PASS | Post Accident Sampling Subsystem of Containment Monitoring System |
| PCC | Passive Containment Cooling |
| PCCS | Passive Containment Cooling System |
| PCT | Peak cladding temperature |
| PCV | Primary Containment Vessel |
| PFD | Process Flow Diagram |
| PGA | Peak Ground Acceleration |
| PGCS | Power Generation and Control Subsystem of Plant Automation System |
| PH | Pump House |
| PL | Parking Lot |
| PM | Preventive Maintenance |
| PMCS | Performance Monitoring and Control Subsystem of NE-DCIS |
| PMF | Probable Maximum Flood |
| PMP | Probable Maximum Precipitation |
| PPQS | Product Performance Qualification Specification |
| PQCL | Product Quality Check List |
| PRA | Probabilistic Risk Assessment |
| PRMS | Process Radiation Monitoring System |
| PRNM | Power Range Neutron Monitoring |
| PS | Plant Stack |
| PSD | Power Spectra Density |
| PSS | Process Sampling System |
| PSWS | Plant Service Water System |
| PT | Pressure Transmitter |
| PWR | Pressurized Water Reactor |
| QA | Quality Assurance |
| RACS | Rod Action Control Subsystem |
| RAM | Reliability, Availability and Maintainability |
| RAPI | Rod Action and Position Information |
| RAT | Reserve Auxiliary Transformer |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|-------------------|---|
| RB | Reactor Building |
| RBC | Rod Brake Controller |
| RBCC | Rod Brake Controller Cabinet |
| RBCWS | Reactor Building Chilled Water Subsystem |
| RBHV | Reactor Building HVAC |
| RBS | Rod Block Setpoint |
| RBV | Reactor Building Vibration |
| RC&IS | Rod Control and Information System |
| RCC | Remote Communication Cabinet |
| RCCV | Reinforced Concrete Containment Vessel |
| RCCWS | Reactor Component Cooling Water System |
| RCPB | Reactor Coolant Pressure Boundary |
| RCS | Reactor Coolant System |
| RDA | Rod Drop Accident |
| RDC | Resolver-to-Digital Converter |
| REPAVS | Refueling and Pool Area Ventilation Subsystem of Fuel Building HVAC |
| RFP | Reactor Feed Pump |
| RG | Regulatory Guide |
| RHR | Residual Heat Removal (function) |
| RHX | Regenerative Heat Exchanger |
| RMS | Root Mean Square |
| RMS | Radiation Monitoring Subsystem |
| RMU | Remote Multiplexer Unit |
| RO | Reverse Osmosis |
| ROM | Read-only Memory |
| RPS | Reactor Protection System |
| RPV | Reactor Pressure Vessel |
| RRPS | Reference Rod Pull Sequence |
| RSM | Rod Server Module |
| RSPC | Rod Server Processing Channel |
| RSS | Remote Shutdown System |
| RSSM | Reed Switch Sensor Module |
| RSW | Reactor Shield Wall |
| RTIF | Reactor Trip and Isolation Function(s) |
| RT _{NDT} | Reference Temperature of Nil-Ductility Transition |
| RTP | Reactor Thermal Power |
| RW | Radwaste Building |
| RWCU/SDC | Reactor Water Cleanup/Shutdown Cooling |
| RWE | Rod Withdrawal Error |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|--------------------|--|
| RWM | Rod Worth Minimizer |
| SA | Severe Accident |
| SAR | Safety Analysis Report |
| SB | Service Building |
| S/C | Digital Gamma-Sensitive GM Detector |
| S/D | Scintillation Detector |
| S/DRSRO | Single/Dual Rod Sequence Restriction Override |
| S/N | Signal-to-Noise |
| S/P | Suppression Pool |
| SAS | Service Air System |
| SB&PC | Steam Bypass and Pressure Control System |
| SBO | Station Blackout |
| SBWR | Simplified Boiling Water Reactor |
| SCEW | System Component Evaluation Work |
| SCRRI | Selected Control Rod Run-in |
| SDC | Shutdown Cooling |
| SDM | Shutdown Margin |
| SDS | System Design Specification |
| SEOA | Sealed Emergency Operating Area |
| SER | Safety Evaluation Report |
| SF | Service Water Building |
| SFP | Spent fuel pool |
| SIL | Service Information Letter |
| SIT | Structural Integrity Test |
| SIU | Signal Interface Unit |
| SJAE | Steam Jet Air Ejector |
| SLC | Standby Liquid Control |
| SLCS | Standby Liquid Control System |
| SLMCPR | Safety Limit Minimum Critical Power Ratio |
| SMU | SSLC Multiplexing Unit |
| SOV | Solenoid Operated Valve |
| SP | Setpoint |
| SPC | Suppression Pool Cooling |
| SPDS | Safety Parameter Display System |
| SPTMS | Suppression Pool Temperature Monitoring Subsystem of Containment Monitoring System |
| SR | Surveillance Requirement |
| SRM | Source Range Monitor |
| SRNM | Startup Range Neutron Monitor |
| SRO | Senior Reactor Operator |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|--------------------|--|
| SRP | Standard Review Plan |
| SRS | Software Requirements Specification |
| SRSRO | Single Rod Sequence Restriction Override |
| SRSS | Square Root of the Sum of the Squares |
| SRV | Safety Relief Valve |
| SRVDL | Safety relief valve discharge line |
| SSAR | Standard Safety Analysis Report |
| SSC(s) | Structure, System and Component(s) |
| SSE | Safe Shutdown Earthquake |
| SSLC | Safety System Logic and Control |
| SSPC | Steel Structures Painting Council |
| ST | Spare Transformer |
| STP | Sewage Treatment Plant |
| STRAP | Scram Time Recording and Analysis Panel |
| STRP | Scram Time Recording Panel |
| SV | Safety Valve |
| SWH | Static water head |
| SWMS | Solid Waste Management System |
| SY | Switch Yard |
| TAF | Top of Active Fuel |
| TASS | Turbine Auxiliary Steam System |
| TB | Turbine Building |
| TBCE | Turbine Building Compartment Exhaust |
| TBE | Turbine Building Exhaust |
| TBLOE | Turbine Building Lube Oil Area Exhaust |
| TBS | Turbine Bypass System |
| TBHV | Turbine Building HVAC |
| TBV | Turbine Bypass Valve |
| TC | Training Center |
| TCCWS | Turbine Component Cooling Water System |
| TCS | Turbine Control System |
| TCV | Turbine Control Valve |
| TDH | Total Developed Head |
| TEMA | Tubular Exchanger Manufacturers' Association |
| TFSP | Turbine first stage pressure |
| TG | Turbine Generator |
| TGSS | Turbine Gland Seal System |
| THA | Time-history accelerograph |
| TLOS | Turbine Lubricating Oil System |

Global Abbreviations And Acronyms List

| <u>Term</u> | <u>Definition</u> |
|--------------------|---|
| TLU | Trip Logic Unit |
| TMI | Three Mile Island |
| TMSS | Turbine Main Steam System |
| TRM | Technical Requirements Manual |
| TS | Technical Specification(s) |
| TSC | Technical Support Center |
| TSI | Turbine Supervisory Instrument |
| TSV | Turbine Stop Valve |
| UBC | Uniform Building Code |
| UHS | Ultimate Heat Sink |
| UL | Underwriter's Laboratories Inc. |
| UPS | Uninterruptible Power Supply |
| URS | Ultimate Rupture Strength |
| USE | Upper Shelf Energy |
| USM | Uniform Support Motion |
| USMA | Uniform support motion response spectrum analysis |
| USNRC | United States Nuclear Regulatory Commission |
| USS | United States Standard |
| UV | Ultraviolet |
| V&V | Verification and Validation |
| Vac / VAC | Volts Alternating Current |
| Vdc / VDC | Volts Direct Current |
| VDU | Video Display Unit |
| VW | Vent Wall |
| VWO | Valves Wide Open |
| WD | Wash Down Bays |
| WH | Warehouse |
| WS | Water Storage |
| WT | Water Treatment |
| WW | Wetwell |
| XMFR | Transformer |
| ZPA | Zero Period Acceleration |

3G. DESIGN DETAILS AND EVALUATION RESULTS OF SEISMIC CATEGORY I STRUCTURES

This appendix presents the structural design and analysis for the Reactor Building, Control Building and Fuel Building of the ESBWR standard plant. It addresses all applicable items included in Appendix C to USNRC Standard Review Plan, NUREG-0800, Section 3.8.4.

3G.1 REACTOR BUILDING

The Reactor Building (RB) encloses the concrete containment and its internal systems, structures, and components. In addition, the RB contains the Isolation Condenser/Passive Containment Cooling (IC/PCC) pools and the services pools for storage of Dryer/Separator on the top of the concrete containment.

3G.1.1 Objective and Scope

The objective of this subsection is to document the structural design details, inputs and analytical results from the analysis of the ESBWR main building structures encased in the Reactor Building. The scope includes the design and analysis of the structure for normal, severe environmental, extreme environmental, and abnormal loads.

3G.1.2 Conclusions

The following are the major summary conclusions on the design and analysis of the Reactor Building, the concrete containment and the containment internal structures.

- Based on the results of finite element analyses performed in accordance with the design conditions identified in Subsections 3G.1.3 and 3G.1.5, stresses and/or strains in concrete, reinforcement, liner and containment internal structures are less than the allowable stresses and/or strains per the applicable regulations, codes or standards listed in Section 3.8.
- The factors of safety against floatation, sliding, and overturning of the structure under various loading combinations are higher than the required minimum.
- The thickness of the roof slabs and exterior walls are more than the minimum required to preclude penetration, perforation or spalling resulting from impact of design basis tornado missiles.

3G.1.3 Structural Description

3G.1.3.1 Description of the Reactor Building

3G.1.3.1.1 Reactor Building Structure

The RB structure and the containment structure share the same wall structure which encloses the Gravity-Driven Cooling System (GDCS) pools and the Suppression pool. The RB structure consists of the following areas that are not part of the containment structure.

- RB super structure at and above the refueling floor, up to the support for the bridge crane, including the roof, is made of reinforced concrete floors and walls (floor slabs can also be

composite structure). Roof trusses and their supporting columns are made of structural steel.

- Passive Containment Cooling System (PCCS) and Isolation Condenser (IC) heat exchanger pools, the separator/dryer storage pool, the reactor cavity and the buffer pool.
- Rooms at several elevation levels outside the containment but attaching to the containment structure.
- The main steam tunnel that consists of reinforced concrete walls and floor.

The key dimensions of the RB are summarized in Table 3.8-8. Figures 3G.1-1 through 3G.1-7 show the configurations of the RB.

The Fuel Building (FB) is integrated with the RB in the ESBWR standard plant. The RB and FB share a common wall between them and a large common basemat. The summary of the FB design is described in Section 3G.3.

3G.1.3.1.2 Containment and Containment Structure

The containment is a reinforced concrete containment vessel (RCCV), which encloses the reactor pressure vessel (RPV) and its related systems and components. The containment is divided into a drywell region and a wetwell region with an interconnecting vent system.

The key dimensions of the RCCV are summarized in Table 3.8-1. Figure 3.8-1 shows the configuration of the RCCV.

The containment structure boundary consists of the containment top slab with removable drywell head, the containment cylindrical wall that is also the outer wall of the suppression pool, the suppression pool floor slab, the RPV pedestal that encloses the volume under the RPV, and the basemat. The concrete containment is lined with a steel liner for leak-tightness. The containment cylindrical outer wall extends below the suppression pool floor slab to the basemat. This extension is not part of the containment pressure boundary, however, it supports the upper containment cylinder. The reinforced concrete basemat foundation supports the entire containment system, which includes the RPV pedestal, and extends to support the reactor building surrounding the containment. The outline drawings are shown in Figures 3G.1-1 through 3G.1-7.

3G.1.3.1.3 Reactor Building Structure/Containment Structure Connections

The RCCV and the RB structure are integrated by the IC/PCCS pool girders at the top of the containment and by floor slabs at elevations that are defined as part of the RB structure and the basemat. The IC/PCCS pool girders are deep reinforced concrete girders, and they are integrated with the containment top slab and with RB walls.

3G.1.3.1.4 Containment Internal Structures

The containment internal structures consist of the diaphragm floor slab, vent wall, Gravity-Driven Cooling System (GDCS) pool walls, reactor shield wall, and the RPV support bracket. These structures are shown in the general arrangement drawings in this appendix.

The diaphragm floor slab acts as a barrier between the drywell and the wetwell. The diaphragm floor slab is supported on the reinforced concrete containment wall at its outer periphery and on

the vent wall at its inner periphery. The diaphragm floor slab is a concrete-filled steel structure. The space between the floor slab top and bottom plates is filled with concrete. The slab is supported by a system of radial beams spaced evenly all around and spanning between the vent wall structure and the reinforced concrete containment wall.

The vent wall structure is also a concrete-filled steel design consisting of two concentric carbon steel cylinders connected together by vertical web plates evenly spaced all around. The vent wall structure is anchored at the bottom into the RPV pedestal and is restrained at the top by the diaphragm floor slab. The cylindrical annulus carries 12 vent pipes and 12 safety relief valve downcomer pipes with sleeves, from the drywell into the suppression pool. The space in the cylindrical annulus is filled with concrete.

There are three GDCS pools supported on top of the diaphragm floor slab. The pools on one side are contained by the reinforced concrete containment wall and on the other side by structural steel walls.

The reactor shield wall is a thick steel cylindrical structure that surrounds the RPV. It is supported by the RPV support brackets and the reactor pedestal. The function of the reactor shield wall is to attenuate radiation emanating from the RPV. In addition, the reactor shield wall provides structural support for the RPV stabilizer, the RPV insulation and miscellaneous equipment, piping and commodities. Openings are provided in the reactor shield wall to permit the routing of necessary piping to the RPV and to permit inservice inspection of the RPV and piping.

3G.1.4 Analytical Models

3G.1.4.1 Structural Models

The RB and the RCCV including its internal structures are analyzed as one integrated structure utilizing the finite element computer program NASTRAN. The finite element model consists of quadrilateral, triangular, and beam elements. The quadrilateral and triangular elements are used to represent the slabs and walls. Beam elements are used to represent columns and beams. The model is shown in Figures 3G.1-8 to 3G.1-18.

As shown in Figure 3G.1-8, the Fuel Building (FB) is also included in the model, because the FB is integrated with the RB. The model includes the whole (360°) portion of the RB including the RCCV and FB taking the application of nonaxisymmetrical loads and the asymmetric layout of the FB structure into consideration.

Liner plates of various thicknesses as shown in Figure 3G.1-48 are included in the model at locations of the pressure boundary of the containment. The liner plate nodal points are connected to the containment nodal points by rigid beams. The liner plate elements are shown in Figure 3G.1-18. Pressure loads in the containment are applied on the liner plate.

The vent wall and the diaphragm floor are concrete-filled structures consisting of steel plates and concrete. The infill concrete is neglected in analysis model conservatively. Steel plates including connecting rib plates and girders are modeled by shell elements. The GDCS pool, the reactor shield wall and the RPV support brackets are also included in the analysis model. These structures are modeled by shell elements, except the GDCS pool beams which are modeled by

beam elements. The analysis model of these structures is shown in Figure 3G.1-17. For the GDCCS pool, the detail stress evaluation is performed using a local model.

The following major penetrations in the concrete containment are included in the model in order to take local reduction of the wall stiffness into consideration. The penetrations in the model are shown in Figures 3G.1-10 and 3G.1-11.

- upper drywell equipment and personnel hatches
- lower drywell equipment and personnel hatches
- wetwell access hatch
- main steam and feedwater pipe penetrations.

Small penetrations in the containment are not modeled because their effects on the wall stiffness are negligible.

The nodal points are defined by a right hand Cartesian coordinate system X, Y, Z. This system, called the global coordinate system, has its origin located at the center of the containment at the bottom of the RPV, i.e., EL 0. The positive X axis is parallel with the IC/PCCS pool girder in the 180° direction of the containment; the Y axis is perpendicular to the IC/PCCS pool girder in the 90° direction of the containment; the Z axis is vertical upward. This coordinate system is shown in Figure 3G.1-8.

3G.1.4.2 Foundation Models

The foundation soil is represented by soil springs. The spring constants for rocking and translations are determined based on the following soil parameters which correspond to the Soft Site conditions described in Appendix 3A.

- Shear wave velocity: 300 m/s
- Unit weight: 0.0196 MN/m³ (2.00 t/m³)
- Shear modulus: 180 MN/m² (1.835×10⁴ t/m²)
- Poisson's Ratio: 0.478

Soil springs are attached to the bottom of the foundation mat, and the constraints by side soil are not included in the model. The values of the soil springs used in the analysis are shown in Table 3G.1-1. The springs have perfectly elastic stiffness.

These spring values are multiplied by the foundation mat nodal point tributary areas to compute the spring constants assigned to the base slab nodal points.

3G.1.5 Structural Analysis and Design

3G.1.5.1 Site Design Parameters

The key site design parameters are located in Table 3G.1-2.

3G.1.5.2 Design Loads, Load Combinations, and Material Properties**3G.1.5.2.1 Design Loads****3G.1.5.2.1.1 Dead Load (D) and Live Load (L and Lo)**

The weights of structures are evaluated using the following unit weights.

- reinforced concrete: 23.5 kN/m³
- plain concrete: 22.5 kN/m³
- steel: 77.0 kN/m³

Weights of major equipment, miscellaneous structures, piping, and commodities are summarized in Tables 3G.1-3 through 3G.1-5.

Live loads on the RB floor slabs are described in Subsection 3.8.4.3.1.1.

For the computation of global seismic loads, the value of floor live load is limited to the expected live load, L_o , during normal plant operation. The values of L_o are 25% of the above full floor live loads, L , when used in combination with seismic and dead loads as described in Subsection 3.8.4.3.1.1.

3G.1.5.2.1.2 Snow Load

The snow load is applied to the roof slabs and is taken as shown in Table 3G.1-2. Snow load is reduced to 75% when snow load is combined with seismic loads.

3G.1.5.2.1.3 Lateral Soil Pressure at Rest

The lateral soil pressure at rest is applied to external walls below grade and is based on soil properties given in Table 3G.1-2. Pressures to be applied to the walls are provided in Figure 3G.1-19.

3G.1.5.2.1.4 Wind Load (W)

The wind load is applied to the roof slabs and external walls above grade and is based on basic wind speed given in Table 3G.1-2.

3G.1.5.2.1.5 Tornado Load (W_t)

The tornado load is applied to the roof slabs and external walls above grade and its characteristics are given in Table 3G.1-2. The tornado load, W_t , is further defined by the following combinations:

$$W_t = W_w$$

$$W_t = W_p$$

$$W_t = W_m$$

$$W_t = W_w + 0.5W_p$$

$$W_t = W_w + W_m$$

$$W_t = W_w + 0.5W_p + W_m$$

where,

W_t = Total Tornado Load

W_w = Tornado Wind Load

W_p = Tornado Differential Pressure Load

W_m = Tornado Missile Load

3G.1.5.2.1.6 Thermal Loads

Thermal loads are evaluated for the normal operating conditions and abnormal (LOCA) conditions. Figure 3G.1-20 shows the section location for temperature distributions for various structural elements, and Table 3G.1-6 shows the magnitude of equivalent linear temperature distribution.

The evaluation method of temperature effect on the concrete design is based on ACI 349-01 Commentary Figure RA.1.

The two cases, winter and summer, are considered in the analysis.

Stress-free temperature is 15.5°C.

3G.1.5.2.1.7 Pressure Loads

Table 3G.1-7 shows the pressure loads applied to the RCCV during normal operation, structural integrity test, and the LOCA. Pressure loads in the IC/PCCS pools are provided in Table 3G.1-8.

3G.1.5.2.1.8 Condensation Oscillation (CO) and Chugging (CHUG) Loads

The condensation oscillation (CO) and chugging (CHUG) pressure loads along with Dynamic Load Factors (DLF) are provided in Figures 3G.1-21 and 3G.1-22.

3G.1.5.2.1.9 SRV Loads

The SRV loads along with DLF are provided in Figure 3G.1-23.

3G.1.5.2.1.10 Steam Tunnel Subcompartment Pressure

The design pressure in the RB main steam tunnel due to main steam line break is 76.0 kPag. Thermal loads need not be included due to short duration of the tunnel pressurization.

3G.1.5.2.1.11 Subcompartment Pressure in Other Compartments

For ESBWR, the Reactor Water Cleanup/Shutdown Cooling (RWCU/SDC) system is considered high energy during normal operation. The maximum design pressure inside the affected subcompartments from the high energy line break (HELB) of the system is 34.5 kPag. Thermal loads need not be included due to short duration of subcompartment pressurization.

3G.1.5.2.1.12 Annulus Pressurization (AP) Loads

The annulus pressurization (AP) loads due to FW and RWCU breaks are considered. AP loads contain pressure load and associated jet forces and pipe whip restraint loads.

3G.1.5.2.1.13 Design Seismic Loads

The design seismic loads are obtained by soil – structure interaction analyses, which are described in Appendix 3A. The seismic loads used for design are as follows:

- Figure 3G.1-24: design seismic shears and moments for RB and FB walls
- Figure 3G.1-25: design seismic shears and moments for RCCV
- Figure 3G.1-26: design seismic shears and moments for RPV Pedestal and Vent Wall
- Table 3G.1-9: maximum vertical acceleration

The seismic loads are composed of one vertical and two perpendicular horizontal components. The effects of the three components are combined based on the 100/40/40 method as described in Subsection 3.8.1.3.6.

Seismic lateral soil pressure for wall design is provided in Figure 3G.1-27 using the elastic procedure described in ASCE 4-98 Section 3.5.3.2.

Seismic member forces for each section are obtained directly from the NASTRAN analysis using these seismic input loads.

3G.1.5.2.2 Load Combinations and Acceptance Criteria

Load combinations and acceptance criteria for the various elements of the RB complex are discussed on the following subsections.

3G.1.5.2.2.1 Reinforced Concrete Containment Vessel (RCCV)

Table 3.8-2 gives a detailed list of various Service and Factored load combinations with acceptance criteria per ASME Section III Division 2. Based on previous experience, critical load combinations are selected for the RCCV design. They are mainly combinations including LOCA loads and seismic loads as shown in Table 3G.1-10. The acceptance criteria for the selected combinations are also included in Table 3G.1-10.

3G.1.5.2.2.2 Steel Containment Components

Table 3.8-4 gives a detailed list of various load combinations with acceptance criteria per ASME Section III Division 1, Subsection NE. For the drywell head, the loads of W, W', Ro, Ra, Y, SRV and LOCA are not direct loads and their indirect effects through the supporting RCCV top slab are negligibly small.

3G.1.5.2.2.3 Containment Internal Structures

Table 3.8-7 gives a detailed list of various load combinations with acceptance criteria per ANSI/AISC N690.

3G.1.5.2.2.4 Reactor Building (RB) Concrete Structures Including Pool Girders

Table 3.8-15 gives load combinations for the safety-related reinforced concrete structure. Based on previous experience, critical load combinations are selected for the RB design. They are mainly combinations including LOCA loads and seismic loads as shown in Table 3G.1-11. The acceptance criteria for the selected combinations are also included in Table 3G.1-11.

3G.1.5.2.3 Material Properties

3G.1.5.2.3.1 Concrete

Properties of concrete used for the design analyses are shown in Table 3G.1-12.

Concrete has a tendency to change properties when subjected to elevated temperatures. For the ESBWR design, reduction of concrete strength due to high temperature is determined based upon the average value of the following upper bound and lower bound equations excerpted from Reference 3G.1-1.

- Lower bound reduction factor
 - $\phi = 1.0 - 0.0030 (T-21.1)$ $21.1^{\circ}\text{C} (70^{\circ}\text{F}) \leq T \leq 121.1^{\circ}\text{C} (250^{\circ}\text{F})$
 - $\phi = 0.70 - 0.00083 (T-121.1)$ $121.1^{\circ}\text{C} (250^{\circ}\text{F}) \leq T$
- Upper bound reduction factor
 - $\phi = 1.0$ $T \leq 260.0^{\circ}\text{C} (500^{\circ}\text{F})$
 - $\phi = 1.0 - 0.00081 (T-260.0)$ $260.0^{\circ}\text{C} (500^{\circ}\text{F}) \leq T$

Young's modulus for concrete is also determined based upon the average value of the following upper bound and lower bound equations excerpted from Reference 3G.1-1.

- Lower bound reduction factor
 - $\phi = 1.0 - 0.0069 (T-21.1)$ $21.1^{\circ}\text{C} (70^{\circ}\text{F}) \leq T \leq 93.3^{\circ}\text{C} (200^{\circ}\text{F})$
 - $\phi = 0.50 - 0.0009 (T-93.3)$ $93.3^{\circ}\text{C} (200^{\circ}\text{F}) \leq T$
- Upper bound reduction factor
 - $\phi = 1.0 - 0.00056 (T-21.1)$ $21.1^{\circ}\text{C} (70^{\circ}\text{F}) \leq T \leq 204.4^{\circ}\text{C} (400^{\circ}\text{F})$
 - $\phi = 0.90 - 0.0015 (T-204.4)$ $204.4^{\circ}\text{C} (400^{\circ}\text{F}) \leq T$

The design temperature of the drywell is $171^{\circ}\text{C} (340^{\circ}\text{F})$ as shown in Table 1.3-3, and it satisfies the concrete temperature limit, 350°F , for accident or short term period specified in ASME Section III, Subsection CC-3440.

3G.1.5.2.3.2 Reinforcing Steel

Reinforcing steel is deformed billet steel conforming to ASTM A-615 grade 60. Minimum yield strength, F_y , is 413.6 MPa.

Reinforcing steel also has tendency to decrease in strength at elevated temperatures. The reduction of reinforcing steel strength is based upon the following equation excerpted from Reference 3G.1-1.

- Reduction Factor
 - $\phi = 1.0 - 0.000873 (T-21.1) \quad 21.1^{\circ}\text{C} (70^{\circ}\text{F}) \leq T \leq 204.4^{\circ}\text{C} (400^{\circ}\text{F})$

3G.1.5.2.3.3 Structural Steel

Properties of structural steel used for the design analyses are included in Table 3G.1-12.

3G.1.5.3 Stability Requirements

The RB foundations shall have the following safety factors against overturning and sliding. Because the impact on the stability by seismic load is larger than wind and tornado, the load combinations for W and Wt, which are shown in Table 3.8-14, are excluded.

| Load Combination | Overturning | Sliding | Floatation |
|------------------|-------------|---------|------------|
| D + H + E' | 1.1 | 1.1 | |
| D + F' | | | 1.1 |

Where

D = Dead Load, F' = Buoyant forces of design basis flood

H = Lateral soil pressure, E' = Safe Shutdown Earthquake

3G.1.5.4 Structural Design Evaluation

The evaluation of the containment structure, the containment internal structures, and the RB structures is based on the results from the load combinations indicated in Subsection 3G.1.5.2.2.

Figure 3G.1-28 shows the location of the sections that are selected for evaluation of reinforced concrete structures. They are selected, in principle, from the center and both ends of walls and slabs, where it is reasonably expected that the critical stresses appear based on engineering experience and judgment. The computer program SSDP-2D is used for the evaluation of stresses in rebar and concrete. The input to SSDP-2D consists of rebar ratios, material properties, and element geometry at the section under consideration together with the forces and moments from the NASTRAN analysis, which are shown in Tables 3G.1-13 through 3G.1-21. Element forces and moments listed in the tables are defined with relation to the element coordinate system shown in Figure 3G.1-29. Figures 3G.1-30 through 3G.1-38 indicate deformations of structures obtained by NASTRAN analyses for the loads corresponding to Table 3G.1-13 through 3G.1-21.

Figure 3G.1-39 shows a flow chart for the structural analysis and design. Figures 3G.1-40 through 3G.1-47 present the design drawings used for the evaluation of the containment and the Reactor Building structural design. Figures 3G.1-48 through 3G.1-50 show the design details of containment liner plate. Figures 3G.1-51 through 3G.1-54 show the design details of containment major penetrations. Figures 3G.1-55 through 3G.1-59 show the details of containment internal structures.

3G.1.5.4.1 Containment Structure

Tables 3G.1-22 through 3G.1-26 show the resultant combined forces and moments in accordance with the selected load combinations listed in Table 3G.1-10. Table 3G.1-27 lists the sectional

thicknesses and rebar ratios used in the evaluation. At each section, in general, three elements are analyzed at azimuth 0° , 90° and 135° .

Tables 3G.1-28 through 3G.1-32 show the rebar and concrete stresses at these sections for the representative elements. Tables 3G.1-33 and 3G.1-34 summarize evaluation results for transverse shear and tangential shear in accordance with ASME Section III, Division 2, Article CC-3520.

Table 3G.1-35 shows the maximum strains of containment liner plate. Table 3G.1-36 shows the stress summary of drywell head.

3G.1.5.4.1.1 Containment Wall Including RPV Pedestal

Sections 1 through 9 shown in Figure 3G.1-28 are considered critical sections for the containment wall including the RPV pedestal. Maximum stress in the meridional rebar is found to be 292.5 MPa at Section 4 near the bottom of the RCCV Wetwell due to load combination CV-11a, as shown in Table 3G.1-31. The maximum stress in the circumferential rebar is found to be 363.0 MPa, which occurs also at Section 4, the bottom of the RCCV Wetwell due to load combination CV-11a, as shown in Table 3G.1-31. The maximum concrete stress is found to be 22.1 MPa, which occurs at Section 6 due to load combination CV-11a.

The maximum transverse shear stress is found to be 3.88 MPa at Section 1 for the load combination CV-11b. The amounts of shear ties provided satisfy the required values at all sections, as indicated in Table 3G.1-33.

As for tangential shear, the maximum stress of 4.18 MPa is found at Section 4, the bottom of the Wetwell, due to the combination CV-11b. The value is less than the allowable tangential shear stress provided by orthogonal reinforcement, which is described in Table 3.8-3. The amounts of reinforcement provided satisfy the required values at all sections, as indicated in Table 3G.1-34.

Table 3G.1-35 shows liner plate strains. The liner maximum strain is found to be 0.0040 at Section 6, which is within allowable limits given in Table CC-3720-1, ASME Code Section III, Division 2.

3G.1.5.4.1.2 Containment Top Slab and Suppression Pool Slab

Sections 12 through 17 are examined for the Containment Top Slab and Suppression Pool Slab. The locations of these sections are shown in Figure 3G.1-28. The maximum rebar stresses are found to be 256.0 MPa at Section 16 due to the load combination CV-11b in the Top Slab, and 264.0 MPa at Section 13 due to the combination CV-7a in the Suppression Pool Slab. The maximum concrete stresses are 10.6 MPa and 20.4 MPa in the Top Slab and the Suppression Pool Slab, respectively.

The maximum transverse shear stresses are found to be 0.93 MPa at Section 17 for the load combination CV-7b in the Top Slab, and 4.22 MPa at Section 12 for the combination CV-11a in the Suppression Pool Slab. The amounts of shear ties provided satisfy the required values at all sections, as indicated in Table 3G.1-33.

Maximum Liner strain is found to be 0.0025 at Section 12 as shown in Table 3G.1-35 and is within ASME Code allowable.

3G.1.5.4.1.3 Containment Foundation Mat

Sections 10 and 11 are evaluated for the part of the concrete containment in the foundation mat. The sections are shown in Figure 3G.1-28. The maximum rebar stress is calculated as 271.3 MPa at Section 11 just inside the RPV Pedestal and is shown in Table 3G.1-32. The maximum transverse shear stress of 1.58 MPa is found also at the Section 11 for the load combination CV-11a.

The liner plate maximum strain is found to be 0.0006 at Section 11 as shown in Table 3G.1-35.

3G.1.5.4.1.4 Drywell Head

Figure 3G.1-51 shows the design details. The highest stresses are summarized in Table 3G.1-36. The stresses except PL+Pb+Q at service Level A and B are well within the allowable stress limits. PL+Pb+Q at service Level A and B exceeds allowable, however, it meets all requirements for simplified elastic-plastic analysis stipulated in NE-3228.3 of ASME B & PV Code, Sec.III.

Simplified Elastic-Plastic Analysis

The range of primary plus secondary stress intensity S_n is 794 MPa and the allowable of $3S_{m1}$ is 456 MPa from Table 3G.1-36. S_n exceeds $3S_{m1}$, so simplified elastic-plastic analysis is required. The results of comparison against each requirement of NE-3228.3 are as follows.

(1) NE-3228.3 (a)

The range of primary plus secondary membrane plus bending stress intensity, excluding thermal bending stress is 390 MPa from the result of FEM analysis.

(2) NE-3228.3 (b)

The values of S_a used for entering the design fatigue curve is multiplied by the factor K_e . The values of m and n are decided as 3 and 0.2 respectively from Table NE-3228.3(b)-1 of ASME B & PV Code, Sec. III. Because S_{m1} is 156 MPa from Table 5-2, $3 \cdot m \cdot S_{m1}$ is calculated as 1368 MPa. $S_n = 794$ MPa is between $3 \cdot S_{m1} = 456$ MPa and $3 \cdot m \cdot S_{m1} = 1368$ MPa, so K_e is calculated by the following Formula:

$$K_e = 1.0 + \left[\frac{(1-n)}{n} \cdot (m-1) \right] \cdot \left[\left(\frac{S_n}{3 \cdot S_{m1}} \right) - 1 \right] = 2.49$$

(3) NE-3228.3 (c)

Fatigue evaluation is conducted as follows:

$$S_a = K_e \cdot S_n = 1978 \text{ MPa (287 ksi)}$$

$$E_1 = 30000 \text{ ksi}$$

$$E_2 = 28100 \text{ ksi}$$

Where

E_1 : Modulus of elasticity given on the design fatigue curve from Figure I-9.1 of Appendix I of Sec. III.

E_2 : Modulus of elasticity at 340°F (170°C) from Table TM-1 of Sec. II, Part D

$$S_a' = S_a \cdot (E_1/E_2) = 2117 \text{ MPa (307 ksi)}$$

S_a for 10 cycles is 3999 MPa (580 ksi) from Table I-9.1 ($UTS \leq 80$ ksi) and N for $S_a' = 307$ ksi is obtained as 38 from Table I-9.1, General Note (b). So the requirement of NE-3228.3 (c) is satisfied.

(4) NE-3228.3 (d)

Because an accident temperature T_a is not a cyclic load, the thermal ratcheting can be neglected.

(5) NE-3228.3 (e)

From Table NE-3228.3(b)-1, the maximum temperature T_{max} is 700°F (370°C) for carbon steel. T_a is 171°C, so it satisfies this requirement.

(6) NE-3228.3 (f)

Specified minimum yield strength S_y and specified minimum tensile strength S_u of SA-516 Gr. 70 are 38 ksi and 70 ksi respectively. The ratio of S_y to S_u is calculated as 0.543. This value is below 0.80. So it satisfies this requirement.

3G.1.5.4.2 Containment Internal Structures

Tables 3G.1-37 through 3G.1-44 show the summary of stress analysis results for containment internal structures.

The type of analyses for various loads considered for the containment internal structures, such as diaphragm floor, vent wall, RPV support bracket (RPVSB), reactor shield wall and GDCS pool are:

(1) Dead load

(2) Static analysis is performed for the dead load to all containment internal structures. Hydrostatic loads of pool water are also applied statically to vent wall and GDCS pool.

(3) Pressure load

(4) Static analysis is performed for the pressure load (P_o and P_a) applied to diaphragm floor and vent wall.

(5) Thermal load

(6) Static analysis is performed for the thermal load (T_o and T_a) to all internal structures. All steel temperature is the same as atmospheric temperature. The temperature of the intermediate node of VW rib plate is the average value of outer and inner plate ones.

(7) Seismic load

(8) Static analysis is performed for the seismic load on diaphragm floor, vent wall, RPV support bracket and reactor shield wall in the integral NASTRAN model, while response spectra analysis is performed for GDCS pool local model.

(9) In this response spectra analysis, it is assumed that all pool water mass is distributed uniformly on the GDCD pool wall and RCCV wall. This is considered as a conservative assumption, therefore sloshing is not considered in GDCS pool local model. For integral NASTRAN model, however, sloshing load is considered as the static pressure load on DF upper surface and static reaction load from GDCS pool wall. The results from integral

NASTRAN model due to these loads are used for the structural integrity evaluation of the structures other than GDCS pool, while the results from GDCS pool local model are used for evaluation of GDCS pool itself.

- (10) Hydrodynamic load
- (11) Static analysis is performed for the hydrodynamic load (CO, CH and SRV) on vent wall taking $DLF = 2$ into account.
- (12) Pipe Break loads consist of Annulus Pressurization (AP) load, jet impingement and pipe-whip restraint loads
- (13) These loads acting on the RSW are first analyzed for dynamic response using the NASTRAN beam model. The resulting maximum values of bending moment and shear force are then applied to the integral NASTRAN static analysis model.

3G.1.5.4.2.1 Diaphragm Floor

Design of Structural Components

The design of the diaphragm floor is based on the elastic analysis results obtained from model described in Section 3G.1.4. Figure 3G.1-55 shows design details. Table 3G.1-37 summarizes the highest stresses in various structural elements of the D/F slab. All stresses are within allowable stress limits.

Design of Anchorage

Figure 3G.1-56 shows diaphragm floor anchorage into the RCCV wall. Rebars have been used for anchoring the steel plates. Threaded couplers have been used so that the anchor bars can be connected after installation of the reinforcing steel of the RCCV wall. The anchorage is designed so as to avoid interference with the RCCV reinforcing steel. Anchorage requirements for various loading combinations and the capacity of anchorage provided is shown in Table 3G.1-38.

3G.1.5.4.2.2 Vent Wall Structure

Design of Structural Components

Figure 3G.1-57 shows the design details. Highest stresses in inner cylinder, outer cylinder and the web plates are summarized in Table 3G.1-39. The stresses are shown to be within allowable stress limits.

Design of Anchorage

Figure 3G.1-57 shows vent wall anchorage into the RCCV wall. Rebars have been used for anchoring the steel plates. Threaded couplers have been used so that the anchor bars can be connected after installation of the reinforcing steel of the RCCV wall. The anchorage is designed so as to avoid interference with the RCCV reinforcing steel. Anchorage requirements for various loading combinations and the capacity of anchorage provided is shown in Table 3G.1-42.

3G.1.5.4.2.3 Reactor Shield Wall (RSW)

The reactor shield wall is designed to resist the loads and loading combinations discussed in Subsections 3G.1.5.2. Annulus pressurization (AP) loads are also considered.

Figure 3G.1-58 shows the design details. The highest stresses are summarized in Table 3G.1-40. The stresses are well within the allowable stress limits.

3G.1.5.4.2.4 RPV Support Bracket

Design of Structural Components

Figure 3G.1-57 shows the design details. The calculated stresses in various elements of the support bracket are shown in Table 3G.1-41 and are within allowable stress limits.

Design of Anchorage

Figure 3G.1-57 shows RPV support bracket anchorage into the RCCV wall. Rebars have been used for anchoring the steel plates. Threaded couplers have been used so that the anchor bars can be connected after installation of the reinforcing steel of the RCCV wall. The anchorage is designed so as to avoid interference with the RCCV reinforcing steel. Anchorage requirements for various loading combinations and the capacity of anchorage provided is shown in Table 3G.1-42.

3G.1.5.4.2.5 Gravity Driven Cooling System (GDCCS) Pool

Design of Structural Components

Figure 3G.1-59 shows the design details. Highest stresses are summarized in Table 3G.1-43. The stresses are within allowable stress limits.

Design of Anchorage

Threaded mechanical coupler with anchor bars have been used as shown in Figure 3G.1-59. Table 3G.1-44 shows the anchorage requirements and capacity of anchorage provided.

3G.1.5.4.3 Reactor Building

Tables 3G.1-45 through 3G.1-49 show the resultant combined forces and moments in accordance with the selected load combinations listed in Table 3G.1-11. Table 3G.1-50 lists the sectional thicknesses and rebar ratios used in the evaluation. At each section, in general, three elements are analyzed at azimuth 0°, 90° and 135° (or 45°).

Tables 3G.1-51 through 3G.1-55 show the rebar and concrete stresses at these sections for the representative elements. Table 3G.1-56 summarizes evaluation results for transverse shear in accordance with ACI 349, Chapter 11.

Sections 18 through 31 shown in Figure 3G.1-28 are analyzed for the RB outside the containment. Sections 18 to 23 are selected for the RB shear walls, Section 24 for the basemat outside the containment, Sections 25 to 27 for the RB slabs, Sections 28 to 30 for the IC/PCCS pool girders and Section 31 for the Main Steam tunnel wall and slab.

3G.1.5.4.3.1 RB Shear Walls

The maximum rebar stress of 364.6 MPa is found in the horizontal rebar at Section 23 due to the load combination RB-9b as shown in Table 3G.1-55. The maximum vertical rebar stress is found to be 351.8 MPa also at Section 23 due to the load combination RB-9a as shown in Table 3G.1-54. The maximum transverse shear force is found to be 4.70 MN/m against the shear strength of 5.07 MN/m at Section 20, the top of the cylindrical wall below the RCCV wall.

3G.1.5.4.3.2 RB Foundation Mat Outside Containment

Section 24 is selected for the foundation mat outside the containment at the junction with the cylindrical wall below the RCCV wall. The maximum rebar stress of 196.6 MPa is found in the top rebar as shown in Table 3G.1-54. The maximum bottom rebar stress is found to be 139.6 MPa also as shown in Table 3G.1-54. The maximum transverse shear force is found to be 12.03 MN/m against the shear strength of 14.79 MN/m.

3G.1.5.4.3.3 RB Floor Slabs

Sections 25 to 27 are selected for the floor slabs at elevations EL 4650, EL 17500 and EL 27000 (see Figure 3G.1- 28) at their junction with the RCCV. Floor slabs are composite structures, which are reinforced by rebars at their top surfaces and by steel plates at the bottom surfaces, as described in Subsection 3.8.4.1.1. However, the slabs surrounding the Main Steam (MS) tunnel are constructed of conventional reinforced concrete. Among the elements at Sections 26 and 27, Element #96113 and 98424 are included in the MS tunnel slabs.

The maximum rebar stress of 338.1 MPa is found at Section 26 as shown in Table 3G.1-53, whereas the maximum stress of steel plate is found to be 136.8 MPa at Section 26 as shown in Table 3G.1-55. The maximum transverse shear force is found to be 6.24 MN/m against the shear strength of 7.53 MN/m.

3G.1.5.4.3.4 Pool Girders

The maximum rebar stress of 263.9 MPa is found in the vertical rebar at Section 28 as shown in Table 3G.1-55, whereas the maximum horizontal rebar stress is found to be 249.2 MPa also at Section 28 as shown in Table 3G.1-53. The maximum transverse shear force is found to be 3.36 MN/m against the shear strength of 6.47 MN/m.

3G.1.5.4.3.5 Main Steam Tunnel Floors and Walls

Section 31 is selected for the MS tunnel wall (Element #150122) and slabs (Elements #96611 and #98614). The MS tunnel is composed of the reinforced concrete structures as described in Subsection 3G.1.5.4.3.3.

The maximum rebar stress is found to be 230.6 MPa in Table 3G.1-54, and the maximum transverse shear force is found to be 1.91 MN/m against the shear strength of 4.95 MN/m.

3G.1.5.5 Foundation Stability

The Reactor Building, the concrete containment and the Fuel Building share a common foundation. The stabilities of the foundation against overturning, sliding and floatation are evaluated. The energy approach is used in calculating the factor of safety against overturning.

The factors of safety against overturning, sliding and floatation are given in Table 3G.1-57. All of these meet the acceptance criteria.

Maximum soil bearing stress is found to be 699 kPa due to dead plus live loads. Maximum bearing stresses for load combinations involving SSE are shown in Table 3G.1-58 for various site conditions.

3G.1.5.6 Tornado Missile Evaluation

The minimum thickness required to prevent penetration and concrete spalling is evaluated. The methods and procedures are shown in Section 3.5.3.1.1. The minimum thickness required is less than the minimum 1000 and 700 mm thickness provided for the RB external walls and roof, respectively.

3G.1.6 References

- 3G.1-1 Burns & Roe, "State-of-the-Art Report on High Temperature Concrete Design," prepared for US. Department of Energy, Document No. DOE/CH/94000-1, November 1985.

**Table 3G.1-1
Soil Spring Constants for the RB Analysis Model**

| Direction of Spring | | Loads | Stiffness (MN/m/m ²) |
|---------------------|-------------|--------------------------|-------------------------------------|
| Horizontal | X-direction | All | 9.107 |
| | Y-direction | All | 9.654 |
| Vertical | | Horizontal Seismic Loads | 38.35 |
| | | Other Loads | 13.66 |

**Table 3G.1-2
Site Design Parameters**

| Parameter | Value(s) |
|---|---------------------------|
| Soil: | |
| Minimum shear wave velocity, m/s (ft/s) | 300 (984) |
| Poisson's Ratio | 0.35 to 0.478 |
| Unit Weight, kN/m ³ (t/m ³) | 19.6 to 24.5 (2.0 to 2.5) |
| Maximum Ground Water Level, m (ft) | 0.61 (2.0) below grade |
| Maximum Flood Level, m (ft) | 0.30 (1.0) below grade |
| Maximum Snow Load, kPa (lbf/ft ²) | 2.394 (50) |
| Design Temperatures | |
| Summer, °C (°F) | 46.1 (115) |
| Winter, °C (°F) | -40.0 (-40) |
| Seismology: For seismic design parameters, refer to Subsection 3.7.1. | |
| Extreme Wind | |
| Basic wind speed (50 year recurrence interval), m/s (mi/hr) | 62.6 (140) |
| Importance Factors (Safety-related structures)* | 1.15 |
| Exposure Category | Exposure D |
| Tornado | |
| Maximum Tornado wind speed, m/s (mi/hr) | 147.5 (330) |
| Maximum Rotational Speed, m/s (mi/hr) | 116.2 (260) |
| Maximum Translational Speed, m/s (mi/hr) | 31.3 (70) |
| Radius, m (ft) | 45.7 (150) |
| Maximum Pressure Drop, kPa (psi) | 16.6 (2.4) |
| Maximum Rate of Pressure Drop, kPa/s (psi/s) | 11.7 (1.7) |
| Missile Spectrum | See Section 3.5.1.4. |
| Maximum Rainfall | |
| Design rainfall, cm/hr (in/hr) | 49.3 (19.4) |
| Note *: Per ASCE 7-02. | |

**Table 3G.1-3
Equipment and Hydrostatic Loads inside RCCV**

| Description | Weight |
|--|-----------------------|
| Reactor Pressure Vessel (normal operating condition) | 21600 kN |
| Drywell Top Head (including refueling facilities bulkhead plate) | 1100 kN |
| Top Slab | |
| a. Liner below slab | 2.5 kN/m ² |
| b. Miscellaneous attachments below slab | 2.4 kN/m ² |
| Upper Drywell | |
| a. Wall Liner | 2.7 kN/m ² |
| b. Personal Airlock (EL17500) | 200 kN |
| c. Equipment Hatch (EL17500) | 110 kN |
| d. Miscellaneous attachments to wall | 2.4 kN/m ² |
| GDCS Pool | |
| a. Water (H=6.8 m) | 67 kN/m ² |
| Wetwell | |
| a. Water (H=5.5 m) HWL | 54 kN/m ² |
| b. Wall Liner | 1.6 kN/m ² |
| c. Floor Liner | 2.4 kN/m ² |
| d. Access Hatch (EL13570) | 90 kN |
| e. Quenchers (12 units) | 510 kN |
| f. Miscellaneous attachments to wall | 2.4 kN/m ² |
| Lower Drywell | |
| a. Wall Liner | 3.1 kN/m ² |
| b. Floor Liner | 0.6 kN/m ² |
| c. Sacrificial (basaltic) concrete (H=1.6 m) | 36 kN/m ² |
| d. Personal Airlock (EL-6400) | 200 kN |
| e. Equipment Hatch (EL-6400) | 110 kN |
| f. Miscellaneous attachments to wall | 2.4 kN/m ² |
| RCCV Internal Structures except Diaphragm Floor | |
| a. Equipment and piping on the slab | 2.4 kN/m ² |
| Diaphragm Floor (excluding GDCS pool areas) | |
| a. Equipment and piping on the slab | 9.8 kN/m ² |

Table 3G.1-4
Equipment and Hydrostatic Loads in RB Pools

| Description | Weight | Remarks |
|-----------------------------------|-----------------------|------------------|
| Reactor Cavity Pool | | |
| a. Water (H=6.7m) | 66 kN/m ² | |
| b. Wall Liner | 1.0 kN/m ² | |
| c. Floor Liner | 1.6 kN/m ² | |
| Dryer / Separator Pool | | |
| a. Water (H=6.7m) | 66 kN/m ² | |
| b. Wall Liner | 1.0 kN/m ² | |
| c. Floor Liner | 1.6 kN/m ² | |
| d. Steam Dryer, Steam Separator | 66 kN/m ² | During refueling |
| Fuel Buffer Pool | | |
| a. Water (H=6.7m) | 66 kN/m ² | |
| b. Wall Liner | 1.0 kN/m ² | |
| c. Floor Liner | 1.6 kN/m ² | |
| d. Fuel Storage Racks | 153 kN/m ² | During refueling |
| IC / PCCS Pool | | |
| a. Water (H=4.8m) | 47 kN/m ² | |
| b. Wall Liner | 1.0 kN/m ² | |
| c. Floor Liner | 1.6 kN/m ² | |
| d. IC heat exchanger | 333 kN/unit | |
| e. PCCS heat exchanger | 233 kN/unit | |
| Fuel Transfer Tube Pool | | |
| a. Water (H=11.64m) | 114 kN/m ² | |
| b. Wall Liner | 1.0 kN/m ² | |
| c. Floor Liner | 1.6 kN/m ² | |
| IC / PCCS Expansion Pools | | |
| a. Water (H=4.8m) | 47 kN/m ² | |
| b. Wall Liner | 1.0 kN/m ² | |
| c. Floor Liner | 1.6 kN/m ² | |
| Dryer/Separator Storage Pool Gate | 300 kN | |
| Reactor Well Gate | 50 kN | |
| Fuel Transfer Channel Pool Gate | 50 kN | |

Table 3G.1-5**Miscellaneous Structures, Piping, and Commodity Loads on RB Floor**

| Elevation (mm) | Weights | Remarks |
|-----------------------|--|-------------------|
| 52,400 | 2.4 kN/m ² (50psf) | |
| 34,000 | 2.4 kN/m ² (50psf) | |
| 27,000 | 2.4 kN/m ² (50psf) | |
| 17,500 | 2.4 kN/m ² (50psf) 20.0 kN/m ² (415psf) | Main Steam Tunnel |
| 13,570 | 2.4 kN/m ² (50psf) | |
| 9,060 | 2.4 kN/m ² (50psf) | |
| 4,650 | 2.4 kN/m ² (50psf) | |
| -1,000 | 2.4 kN/m ² (50psf) | |
| -6,400 | 2.4 kN/m ² (50psf) | |
| -11,500 | 2.4 kN/m ² (50psf) | |

Table 3G.1-6

Equivalent Linear Temperature Distributions at Various Sections

| Section [*] 1 | Side ^{*2} | | Equivalent Linear Temperature ^{*3} (°C) | | | | | |
|---------------------------|--------------------|----|--|------|-----------------------|------|-----------------------|-------|
| | | | Normal Operation Winter | | DBA (6 min) Winter | | DBA (72 hr) Winter | |
| | 1 | 2 | Td | Tg | Td | Tg | Td | Tg |
| C1 | DW | RM | 33.5 | 38.1 | 34.7 | 45.2 | 58.2 | 127.3 |
| C2 | WW | RM | 26.5 | 26.7 | 27.4 | 32.0 | 47.0 | 101.0 |
| C3 | SP | RM | 28.2 | 29.5 | 28.8 | 32.7 | 45.2 | 90.8 |
| C4 | SP | RM | 28.2 | 29.5 | 28.7 | 32.4 | 45.2 | 90.8 |
| C5 | DW | IP | 49.4 | 12.8 | 50.6 | 17.6 | 83.4 | 36.0 |
| C6 | DW | XP | 49.4 | 12.8 | 50.6 | 17.7 | 83.4 | 36.0 |
| C7 | DW | RM | 33.5 | 39.3 | 34.5 | 45.5 | 53.9 | 121.2 |
| M1 | DW | GR | 27.5 | 23.9 | 27.5 | 23.9 | 27.5 | 23.9 |
| M2 | RM | GR | 12.9 | -5.2 | 12.9 | -5.2 | 12.9 | -5.2 |
| P1 | IP | DP | 43.0 | 0.0 | 43.3 | 1.5 | 64.0 | 65.1 |
| P2 | IP | XP | 43.0 | 0.0 | 44.2 | 0.3 | 109.8 | 0.0 |
| W1 | RM | RM | 10.0 | 0.0 | 10.0 | 0.0 | 10.0 | 0.0 |
| W2 | RM | GR | 13.0 | -4.9 | 13.0 | -4.9 | 13.0 | -4.9 |
| W3 | RM | AT | -17.7 | 42.3 | -17.7 | 42.3 | -17.7 | 42.3 |
| S1 | RM | RM | 10.0 | 0.0 | 10.0 | 0.0 | 10.0 | 0.0 |
| S2 | RM | AT | -20.0 | 36.0 | -20.0 | 36.0 | -20.0 | 36.0 |

Note *1: See Figure 3G.1-20 for the location of sections.

Note *2: DW: Drywell, WW: Wetwell Air Space, SP: Suppression Pool, IP: IC/PCCS Pool, XP: Expansion Pool, RM: RB Room outside Containment, GR: Ground, AT: Air

Note *3: Td: Average Temperature

Tg: Surface Temperature Difference (positive when temperature at Side 1 is higher)

Table 3G.1-7
Pressure Loads Inside RCCV

| Event | Drywell pressure in kPag (psig) | Wetwell pressure in kPag (psig) | Note |
|------------------|--|--|-------------------------------|
| Normal operation | 5.2 (0.75) | 5.2 (0.75) | |
| SIT 1 | 356.8 (51.8) | 356.8 (51.8) | Maximum pressure |
| SIT 2 | 310 (45) | 32.5 (4.75) | Maximum differential pressure |
| LOCA (6 minutes) | 257 (37.3) | 241 (35.0) | |
| LOCA (72 hours) | 310 (45.0) | 310 (45.0) | |

Table 3G.1-8
Pressure Loads Inside IC/PCCS Pools

| Event | IC/PCCS pool pressure in kPag (psig) |
|------------------|---|
| Normal operation | 34.5 (5) |
| LOCA | 48.3 (7) |

**Table 3G.1-9
Maximum Vertical Acceleration**

| RB/FB Walls | | | RB/FB Slabs | | |
|------------------------|----------|--------------------------------|-------------|----------|--------------------------------|
| Elev. (m) | Node No. | Max. Vertical Acceleration (g) | Elev. (m) | Node No. | Max. Vertical Acceleration (g) |
| 52.40 | 110 | 0.76 | 52.40 | 9101 | 1.20 |
| 34.00 | 109 | 0.65 | | 9102 | 1.83 |
| 27.00 | 108 | 0.61 | | 9103 | 1.63 |
| 22.50 | 107 | 0.50 | | 9104 | 1.72 |
| 17.50 | 106 | 0.51 | | 9105 | 1.69 |
| 13.57 | 105 | 0.50 | | 9106 | 1.88 |
| 9.06 | 104 | 0.47 | 27.00 | 9081 | 0.94 |
| 4.65 | 103 | 0.44 | 22.50 | 9071 | 1.57 |
| -1.00 | 102 | 0.43 | | 9072 | 1.26 |
| -6.40 | 101 | 0.41 | | 9073 | 1.39 |
| -11.50 | 2 | 0.38 | | 9074 | 0.97 |
| -15.50 | 1 | 0.34 | | 9075 | 0.76 |
| RCCV Wall | | | 17.50 | 9061 | 1.08 |
| 34.00 | 209 | 0.84 | | 9062 | 0.92 |
| 27.00 | 208 | 0.84 | | 9063 | 0.59 |
| 17.50 | 206 | 0.71 | | 9064 | 1.17 |
| 13.57 | 205 | 0.66 | 13.57 | 9051 | 0.55 |
| 9.06 | 204 | 0.57 | 9.06 | 9041 | 0.52 |
| 4.65 | 203 | 0.52 | 4.65 | 9031 | 0.87 |
| -1.00 | 202 | 0.44 | | 9032 | 0.54 |
| -6.40 | 201 | 0.38 | | 9033 | 0.52 |
| RPV Pedestal/Vent Wall | | | -1.00 | 9021 | 0.73 |
| 17.50 | 701 | 0.59 | | 9022 | 1.05 |
| 14.50 | 702 | 0.57 | | 9023 | 0.67 |
| 11.50 | 703 | 0.53 | | 9024 | 0.53 |
| 8.50 | 704 | 0.49 | -6.40 | 9011 | 0.57 |
| 7.4625 | 705 | 0.50 | | 9012 | 0.66 |
| 4.65 | 303 | 0.47 | | | |
| 2.42 | 377 | 0.44 | | | |
| -1.00 | 302 | 0.46 | | | |
| -2.75 | 376 | 0.43 | | | |
| -6.40 | 301 | 0.43 | | | |

Note : See Figure 3A.7-4 for the node numbers.

Table 3G.1-10
Selected Load Combinations for the RCCV

| Category | Load Combination | | | | | | | | | | | Acceptance Criteria* ¹ |
|------------------------|--------------------|-----|-----|----------------|----------------|----------------|-----|----------------|-----|-----|------|-----------------------------------|
| | No. * ² | D | L | P _t | P _a | T _a | E' | R _a | SRV | CO | CHUG | |
| SIT (maximum pressure) | CV-1 | 1.0 | 1.0 | 1.0 | | | | | | | | S |
| LOCA (1.5Pa) 6 minutes | CV-7a | 1.0 | 1.0 | | 1.5 | 1.0 | | 1.0 | 1.0 | 1.5 | | U |
| LOCA (1.5Pa) 72 hours | CV-7b | 1.0 | 1.0 | | 1.5 | 1.0 | | 1.0 | 1.0 | | 1.5 | U |
| LOCA + SSE 6 minutes | CV-11a | 1.0 | 1.0 | | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | | U |
| LOCA + SSE 72 hours | CV-11b | 1.0 | 1.0 | | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | | 1.0 | U |

Note:

*1: S = Allowable Stress as in ASME Section III, Div. 2, Subsection CC-3430 for Service Load Combination.

U = Allowable Stress as in ASME Section III, Div. 2, Subsection CC-3420 for Factored Load Combination.

*2: Based on Table 3.8-2

Table 3G.1-11
Selected Load Combinations for the RB

| Category | Load Combination | | | | | | | | | Acceptance Criteria* ¹ |
|-------------------------------------|--------------------|------|-----|-------------------------------|----------------|-------------------------------|-----|-----|---|-----------------------------------|
| | No. * ² | D | L | P _a * ³ | T _o | T _a * ³ | E' | W | | |
| Severe Environmental | RB-4 | 1.05 | 1.3 | | 1.3 | | | 1.3 | U | |
| LOCA (1.5P _a) 6 minutes | RB-8a | 1.0 | 1.0 | 1.5 | | 1.0 | | | U | |
| LOCA (1.5P _a) 72 hours | RB-8b | 1.0 | 1.0 | 1.5 | | 1.0 | | | U | |
| LOCA + SSE 6 minutes | RB-9a | 1.0 | 1.0 | 1.0 | | 1.0 | 1.0 | | U | |
| LOCA + SSE 72 hours | RB-9b | 1.0 | 1.0 | 1.0 | | 1.0 | 1.0 | | U | |

Note:

*1: U = Required section strength based on the strength design method per ACI 349.

*2: Based on Table 3.8-15

*3: P_a and T_a are accident pressure load within the containment and thermal load generated by LOCA, respectively.

P_a and T_a are indirect loads, but their effects are considered in the RB design.

Table 3G.1-12
Material Constants for Design Calculations

| | | | Reinforced Concrete | | Steel | | |
|-------------------------------------|-------------|---------------------|---|--|--------------------------|-----------------------------|-----------------------|
| | | | Basemat f _c =4000psi 27.6MPa | Others f _c =5000psi 34.5MPa | Carbon Steel Liner | Stainless Steel Liner | Structural Steel |
| | | Temperature (°C) | | | | | |
| Young's Modulus (MPa) | Temperature | <21 | 2.49×10 ⁴ | 2.78×10 ⁴ | 2.00×10 ⁵ | | |
| | Loads | 93 | 1.81×10 ⁴ | 2.03×10 ⁴ | | | |
| | | 204 | 1.62×10 ⁴ | 1.81×10 ⁴ | | | |
| | Other Loads | | | 2.49×10 ⁴ | 2.78×10 ⁴ | 2.00×10 ¹ | 2.00×10 ⁵ |
| Poisson's Ratio | | | 0.17 | | 0.3 | | |
| Thermal Expansion (m/m°C) | | | 9.90×10 ⁻⁶ | | 1.17×10 ⁻⁵ | 1.52×10 ⁻⁵ | 1.17×10 ⁻⁵ |
| Weight Density (MN/m ³) | | | 0.0235 | | 0.0770 | | |

Table 3G.1-13
Results of NASTRAN Analysis, Dead Load

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 RPV Pedestal Bottom | 5006 | 1.152 | -4.311 | 0.163 | -0.352 | -2.073 | 0.012 | -0.019 | -0.856 |
| | 5013 | 0.739 | -5.029 | 0.259 | -0.297 | -1.732 | 0.000 | -0.017 | -0.667 |
| | 5024 | 0.352 | -5.153 | 0.013 | -0.271 | -1.568 | 0.005 | 0.010 | -0.596 |
| 2 RPV Pedestal Mid-Height | 6006 | -0.082 | -4.184 | 0.271 | 0.023 | 0.060 | 0.032 | 0.035 | -0.027 |
| | 6013 | -0.115 | -4.357 | 0.392 | -0.038 | -0.008 | 0.009 | -0.016 | 0.031 |
| | 6024 | 0.025 | -3.246 | -0.362 | -0.001 | -0.089 | 0.011 | 0.021 | 0.089 |
| 3 RPV Pedestal Top | 6606 | -0.123 | -3.190 | 0.620 | 0.358 | 2.389 | 0.117 | 0.051 | -0.888 |
| | 6613 | -0.157 | -3.287 | 0.100 | 0.298 | 2.327 | -0.143 | -0.014 | -0.864 |
| | 6624 | -0.029 | -3.152 | 0.154 | 0.333 | 2.335 | 0.147 | 0.012 | -0.853 |
| 4 RCCV Wetwell Bottom | 1806 | -0.360 | -4.620 | 0.097 | -0.050 | -0.369 | 0.006 | -0.003 | -0.055 |
| | 1813 | -0.553 | -4.690 | 0.161 | -0.050 | -0.247 | 0.006 | -0.001 | 0.004 |
| | 1824 | -0.408 | -5.291 | -0.106 | -0.058 | -0.375 | 0.000 | -0.003 | -0.049 |
| 5 RCCV Wetwell Mid-Height | 2606 | -0.052 | -4.139 | 0.137 | 0.009 | -0.025 | 0.005 | 0.000 | -0.092 |
| | 2613 | -0.214 | -4.257 | 0.187 | -0.034 | -0.066 | 0.003 | 0.000 | -0.060 |
| | 2624 | -0.233 | -4.868 | -0.071 | 0.026 | 0.000 | 0.000 | -0.003 | -0.132 |
| 6 RCCV Wetwell Top | 3406 | -0.056 | -3.591 | 0.240 | 0.055 | 0.307 | -0.009 | 0.041 | -0.123 |
| | 3413 | -0.059 | -3.975 | 0.179 | -0.021 | -0.025 | -0.061 | 0.015 | -0.026 |
| | 3424 | -0.233 | -4.262 | -0.021 | 0.067 | 0.327 | -0.022 | 0.050 | -0.090 |
| 7 RCCV Drywell Bottom | 3606 | 0.076 | -3.285 | 0.151 | -0.011 | 0.008 | -0.015 | 0.035 | 0.076 |
| | 3613 | 0.093 | -3.570 | 0.223 | 0.020 | 0.178 | -0.040 | -0.014 | 0.203 |
| | 3624 | -0.180 | -4.276 | 0.038 | 0.070 | 0.360 | -0.020 | 0.037 | 0.150 |
| 8 RCCV Drywell Mid-Height | 4006 | 0.506 | -3.094 | 0.044 | -0.119 | -0.360 | -0.031 | 0.000 | 0.160 |
| | 4013 | 0.432 | -3.724 | 0.331 | -0.047 | -0.366 | 0.005 | -0.006 | 0.105 |
| | 4976 | 0.029 | -3.502 | 0.188 | -0.003 | -0.169 | -0.004 | -0.006 | 0.116 |
| 9 RCCV Drywell Top | 4406 | 0.048 | -3.381 | -0.797 | -0.206 | -1.125 | -0.016 | 0.002 | 0.242 |
| | 4413 | -0.490 | -3.850 | 0.188 | -0.164 | -0.828 | 0.000 | -0.013 | 0.165 |
| | 4424 | 0.148 | -2.696 | 0.151 | -0.056 | -0.509 | 0.006 | 0.002 | 0.117 |
| 10 Basemat @ Center | 80003 | -1.314 | -1.549 | 0.093 | 4.630 | 4.830 | -0.010 | 0.280 | -0.216 |
| | 80007 | -1.330 | -1.562 | 0.086 | 4.649 | 4.834 | -0.006 | -0.032 | -0.347 |
| | 80012 | -1.326 | -1.589 | 0.086 | 4.649 | 4.837 | -0.008 | -0.328 | -0.048 |
| 11 Basemat Inside RPV Pedestal | 80206 | -1.270 | -1.479 | 0.127 | 1.102 | 1.524 | 1.179 | 1.351 | -1.229 |
| | 80213 | -1.322 | -1.581 | 0.144 | 2.324 | 0.060 | -0.100 | -0.055 | -1.868 |
| | 80224 | -1.385 | -1.751 | 0.082 | 0.200 | 2.392 | -0.172 | -1.766 | -0.148 |
| 12 S/P Slab @ RPV | 83306 | 0.148 | 0.584 | -0.237 | 1.653 | 1.214 | -0.035 | 1.077 | -0.024 |
| | 83313 | 0.357 | 0.453 | -0.122 | 1.686 | 1.225 | 0.019 | 1.091 | 0.029 |
| | 83324 | 0.303 | 0.621 | 0.025 | 1.695 | 1.227 | -0.030 | 1.097 | -0.026 |
| 13 S/P Slab @ Center | 83406 | 0.205 | 0.507 | -0.186 | -0.975 | 0.477 | -0.011 | 0.415 | 0.000 |
| | 83413 | 0.465 | 0.321 | -0.039 | -0.966 | 0.464 | -0.004 | 0.424 | 0.002 |
| | 83424 | 0.372 | 0.521 | 0.005 | -0.985 | 0.463 | -0.003 | 0.431 | -0.001 |
| 14 S/P Slab @ RCCV | 83506 | 0.228 | 0.432 | -0.170 | -1.220 | -0.013 | -0.010 | -0.069 | 0.002 |
| | 83513 | 0.504 | 0.275 | -0.005 | -1.247 | -0.033 | -0.004 | -0.058 | 0.004 |
| | 83524 | 0.383 | 0.496 | 0.007 | -1.293 | -0.041 | -0.001 | -0.051 | -0.002 |
| 15 Top slab @ Drywell Head Opening | 98120 | 0.971 | 0.265 | 0.361 | -0.447 | -0.258 | -0.329 | 0.045 | 0.276 |
| | 98135 | 2.709 | 0.254 | -0.282 | -0.611 | 0.277 | 0.078 | -0.096 | 0.348 |
| | 98104 | 0.122 | 0.721 | -0.140 | -0.207 | -1.216 | 0.261 | -0.003 | 0.283 |
| 16 Top slab @ Center | 98149 | 1.409 | -0.206 | 0.425 | -0.616 | -0.435 | 0.029 | -0.047 | -0.229 |
| | 98170 | 1.201 | 0.025 | -0.054 | -0.758 | -1.020 | 0.003 | -0.013 | -0.023 |
| | 98109 | 0.301 | 0.591 | -0.046 | -0.754 | -0.807 | 0.153 | 0.076 | 0.046 |
| 17 Top slab @ RCCV | 98174 | 0.636 | -0.114 | 0.055 | -0.338 | -0.628 | -0.284 | -0.182 | 0.105 |
| | 98197 | 0.153 | 0.132 | -0.225 | -0.393 | 1.027 | 0.079 | 0.052 | 0.685 |
| | 98103 | 0.079 | 0.532 | 0.041 | 1.964 | 0.374 | 0.208 | 0.985 | 0.109 |

Table 3G.1-13
Results of NASTRAN Analysis, Dead Load (Continued)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 18 Wall Below RCCV Bottom | 6 | 0.318 | -7.057 | 0.469 | -0.279 | -1.953 | 0.015 | -0.041 | -0.571 |
| | 13 | 0.474 | -5.576 | 0.416 | -0.572 | -3.046 | 0.011 | -0.015 | -0.883 |
| | 24 | 0.497 | -6.141 | -0.200 | -0.613 | -3.202 | 0.007 | -0.002 | -0.897 |
| 19 Wall Below Below RCCV Mid-Height | 806 | 0.072 | -5.889 | 0.072 | 0.032 | 0.032 | -0.028 | 0.009 | -0.115 |
| | 813 | -0.050 | -5.434 | 0.324 | -0.029 | -0.030 | -0.032 | 0.005 | -0.244 |
| | 824 | 0.081 | -6.028 | -0.204 | -0.056 | -0.035 | -0.010 | 0.003 | -0.309 |
| 20 Wall Below RCCV Top | 1606 | -0.539 | -5.095 | 0.007 | 0.130 | 0.675 | 0.003 | -0.007 | -0.242 |
| | 1613 | -0.742 | -5.136 | 0.208 | 0.140 | 0.860 | 0.006 | -0.002 | -0.320 |
| | 1624 | -0.607 | -5.737 | -0.151 | 0.144 | 0.840 | -0.001 | -0.006 | -0.299 |
| 21 Exterior Wall @ EL-11.50 ~10.50m | 20011 | -0.689 | -3.815 | -0.467 | 0.006 | 0.210 | 0.009 | 0.055 | 0.107 |
| | 20023 | -0.017 | -1.287 | -0.541 | 0.072 | -0.324 | 0.005 | -0.109 | -0.198 |
| | 30010 | -0.184 | -2.157 | 0.044 | -0.375 | -2.012 | 0.018 | 0.006 | 0.463 |
| | 30020 | -0.054 | -1.126 | -0.240 | 0.213 | -0.634 | -0.066 | 0.144 | 0.217 |
| | 40001 | -0.049 | -1.167 | 0.197 | 0.217 | -0.647 | 0.065 | -0.146 | 0.212 |
| | 40011 | -0.225 | -2.632 | -0.013 | -0.435 | -2.249 | -0.013 | -0.003 | 0.502 |
| 22 Exterior Wall @ EL4.65 ~6.60m | 22011 | 0.234 | -2.897 | 0.603 | -0.016 | 0.035 | 0.004 | -0.017 | 0.032 |
| | 22023 | 0.057 | -1.428 | -0.518 | -0.143 | -0.016 | -0.022 | 0.105 | 0.014 |
| | 32010 | 0.019 | -1.750 | 0.039 | 0.001 | 0.044 | 0.003 | 0.000 | -0.014 |
| | 32020 | -0.047 | -2.007 | -0.093 | -0.063 | -0.001 | -0.010 | -0.058 | -0.008 |
| | 42001 | -0.062 | -2.089 | -0.072 | -0.080 | -0.003 | 0.000 | 0.042 | -0.004 |
| | 42011 | -0.330 | -2.307 | -0.121 | 0.000 | 0.023 | -0.001 | 0.002 | 0.002 |
| 23 Exterior Wall @ EL22.50 ~24.60m | 24211 | -0.108 | -1.460 | 0.038 | -0.054 | -0.369 | 0.007 | -0.003 | -0.086 |
| | 24224 | -0.025 | -0.839 | 0.213 | 0.003 | -0.067 | -0.034 | -0.055 | -0.058 |
| | 34210 | 0.018 | -0.723 | 0.118 | 0.001 | -0.023 | -0.001 | 0.003 | 0.009 |
| | 34220 | 0.055 | -0.953 | -0.148 | 0.048 | -0.024 | -0.010 | 0.040 | 0.003 |
| | 44201 | 0.013 | -1.089 | -0.322 | 0.044 | -0.012 | 0.017 | -0.045 | 0.000 |
| 24 Basemat @ Wall Below RCCV | 90140 | 0.040 | -0.822 | -0.247 | -1.717 | -1.183 | 2.874 | -1.685 | 1.913 |
| | 90182 | -0.448 | -0.362 | -0.067 | 0.860 | -1.481 | -0.332 | 0.223 | 0.599 |
| | 90111 | -0.399 | -0.620 | 0.033 | -1.284 | 1.044 | -0.462 | 0.643 | 0.129 |
| 25 Slab EL4.65m @ RCCV | 93140 | -0.031 | 0.144 | 0.065 | 0.088 | 0.103 | -0.070 | 0.123 | -0.101 |
| | 93182 | 0.142 | 0.101 | 0.031 | 0.036 | 0.138 | 0.009 | -0.010 | -0.179 |
| | 93111 | 0.058 | 0.173 | -0.030 | 0.189 | 0.041 | 0.007 | -0.188 | -0.004 |
| 26 Slab EL17.5m @ RCCV | 96144 | -0.094 | 0.199 | 0.167 | 0.065 | 0.073 | -0.054 | 0.107 | -0.084 |
| | 96186 | 0.265 | -0.077 | -0.013 | 0.008 | 0.044 | 0.002 | -0.006 | -0.075 |
| | 96113 | -0.202 | 0.401 | -0.073 | -0.074 | 0.039 | 0.009 | 0.168 | 0.023 |
| 27 Slab EL27.0m @ RCCV | 98472 | 0.190 | 0.037 | 0.046 | 0.141 | 0.199 | -0.161 | 0.269 | -0.200 |
| | 98514 | -0.012 | 0.163 | 0.039 | 0.028 | 0.074 | 0.010 | 0.003 | -0.123 |
| | 98424 | 0.158 | 0.648 | -0.024 | 2.007 | 0.536 | 0.005 | -1.222 | -0.095 |
| 28 Pool Girder @ Storage Pool | 123004 | -0.610 | -4.746 | -1.459 | 0.054 | -0.031 | 0.030 | -0.003 | -0.006 |
| | 123104 | 0.941 | -1.732 | -0.725 | 0.032 | -0.001 | 0.028 | 0.027 | -0.008 |
| 29 Pool Girder @ Cavity | 123012 | 1.097 | 0.682 | 0.395 | -0.036 | -0.297 | 0.002 | -0.017 | -0.171 |
| | 123112 | -0.103 | 0.394 | 0.479 | -0.010 | -0.039 | 0.028 | 0.014 | -0.009 |
| 30 Pool Girder @ Fuel Pool | 123017 | -0.492 | -4.038 | 1.604 | 0.069 | -0.017 | -0.098 | -0.009 | -0.069 |
| | 123117 | 0.500 | -1.278 | 0.853 | 0.047 | 0.040 | -0.019 | -0.025 | 0.009 |
| 31 MS Tunnel Wall and Slab | 150122 | -0.250 | -0.101 | 0.876 | -0.017 | 0.020 | 0.016 | -0.023 | -0.054 |
| | 96611 | -0.068 | 0.293 | -0.045 | 0.000 | -0.212 | -0.094 | -0.179 | 0.011 |
| | 98614 | 0.014 | -0.086 | 0.035 | 0.009 | -0.460 | -0.055 | -0.159 | 0.014 |

Table 3G.1-14

Results of NASTRAN Analysis, Drywell Unit Pressure (1 MPa)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 RPV Pedestal Bottom | 5006 | -4.911 | -4.633 | -0.085 | 1.470 | 8.804 | 0.041 | -0.004 | 4.002 |
| | 5013 | -5.056 | -4.286 | -0.229 | 1.429 | 8.711 | -0.007 | -0.004 | 4.046 |
| | 5024 | -4.885 | -3.567 | 0.050 | 1.531 | 8.273 | -0.037 | 0.035 | 3.699 |
| 2 RPV Pedestal Mid-Height | 6006 | 4.568 | -4.411 | -0.437 | -0.183 | -0.665 | -0.015 | 0.046 | -0.519 |
| | 6013 | 4.479 | -4.272 | -0.230 | -0.185 | -0.711 | -0.012 | 0.017 | -0.522 |
| | 6024 | 5.177 | -2.835 | -0.349 | 0.185 | -0.369 | -0.004 | -0.053 | -0.231 |
| 3 RPV Pedestal Top | 6606 | 2.487 | -4.322 | 0.035 | -0.249 | -1.712 | -0.284 | 0.194 | 1.008 |
| | 6613 | 2.001 | -4.803 | -0.355 | -0.254 | -1.244 | 0.271 | -0.177 | 0.794 |
| | 6624 | 2.398 | -4.701 | 0.056 | -0.264 | -1.866 | -0.224 | 0.153 | 1.067 |
| 4 RCCV Wetwell Bottom | 1806 | 0.467 | 3.073 | -0.471 | 0.279 | 1.669 | 0.000 | -0.001 | 0.228 |
| | 1813 | 0.467 | 2.342 | -0.083 | 0.277 | 1.716 | -0.002 | -0.001 | 0.307 |
| | 1824 | 0.516 | 3.402 | 0.041 | 0.287 | 1.590 | -0.003 | 0.001 | 0.271 |
| 5 RCCV Wetwell Mid-Height | 2606 | 1.442 | 3.057 | -0.528 | 0.014 | 0.541 | 0.031 | 0.000 | 0.190 |
| | 2613 | 1.261 | 2.085 | -0.071 | 0.041 | 0.400 | -0.007 | -0.002 | 0.219 |
| | 2624 | 1.452 | 3.374 | 0.010 | 0.105 | 0.292 | -0.006 | 0.006 | 0.177 |
| 6 RCCV Wetwell Top | 3406 | 4.373 | 3.292 | 0.030 | -1.025 | -5.552 | 1.328 | -1.007 | 1.947 |
| | 3413 | 3.381 | 1.775 | -0.486 | -0.691 | -4.100 | -1.220 | 0.767 | 1.526 |
| | 3424 | 2.992 | 3.358 | 0.837 | -0.697 | -4.401 | 1.466 | -0.902 | 1.545 |
| 7 RCCV Drywell Bottom | 3606 | 4.519 | 7.067 | 0.080 | 0.160 | 1.320 | 1.429 | -0.404 | 1.817 |
| | 3613 | 3.612 | 5.452 | -0.440 | 0.405 | 2.421 | -1.285 | 0.152 | 2.199 |
| | 3624 | 3.429 | 8.536 | 0.813 | 0.598 | 3.087 | 1.532 | -0.158 | 2.090 |
| 8 RCCV Drywell Mid-Height | 4006 | 1.512 | 8.081 | 0.081 | -0.094 | 0.433 | 0.154 | 0.301 | -1.151 |
| | 4013 | 2.041 | 5.445 | 0.360 | -0.215 | -0.236 | 0.068 | -0.042 | -0.692 |
| | 4976 | 2.687 | 7.934 | -0.378 | -0.011 | 0.007 | 0.013 | 0.003 | -0.902 |
| 9 RCCV Drywell Top | 4406 | 0.639 | 10.388 | 2.430 | 1.025 | 7.639 | -0.144 | -0.109 | -1.919 |
| | 4413 | 0.677 | 5.201 | 0.493 | 1.036 | 7.332 | 0.145 | 0.092 | -2.540 |
| | 4424 | 2.055 | 6.903 | -0.370 | 1.014 | 6.316 | 0.048 | 0.004 | -2.036 |
| 10 Basemat @ Center | 80003 | 3.974 | 4.223 | -0.013 | -10.747 | -10.393 | -0.003 | -0.425 | 0.323 |
| | 80007 | 3.993 | 4.234 | -0.007 | -10.743 | -10.390 | -0.001 | 0.064 | 0.526 |
| | 80012 | 3.985 | 4.246 | -0.002 | -10.752 | -10.386 | -0.001 | 0.520 | 0.070 |
| 11 Basemat Inside RPV Pedestal | 80206 | 4.060 | 4.100 | 0.023 | -5.849 | -6.023 | -1.469 | -1.117 | 0.840 |
| | 80213 | 4.083 | 4.279 | -0.062 | -7.508 | -4.325 | 0.068 | -0.007 | 1.467 |
| | 80224 | 4.090 | 4.051 | -0.010 | -4.585 | -7.254 | 0.121 | 1.545 | 0.049 |
| 12 S/P Slab @ RPV | 83306 | -1.228 | 1.040 | -0.116 | -3.691 | -2.125 | -0.042 | -1.301 | 0.013 |
| | 83313 | -1.422 | 0.908 | 0.003 | -3.697 | -2.145 | 0.025 | -1.315 | 0.002 |
| | 83324 | -1.131 | 1.079 | -0.010 | -3.727 | -2.183 | -0.002 | -1.337 | -0.008 |
| 13 S/P Slab @ Center | 83406 | -0.651 | 0.391 | -0.058 | 0.519 | -1.299 | -0.033 | -0.902 | -0.001 |
| | 83413 | -0.706 | 0.395 | -0.022 | 0.516 | -1.309 | 0.009 | -0.900 | -0.002 |
| | 83424 | -0.610 | 0.408 | 0.018 | 0.514 | -1.290 | 0.005 | -0.916 | 0.001 |
| 14 S/P Slab @ RCCV | 83506 | -0.429 | 0.149 | -0.015 | 2.997 | -0.103 | -0.010 | -0.686 | -0.012 |
| | 83513 | -0.437 | 0.236 | -0.024 | 2.987 | -0.106 | 0.004 | -0.689 | -0.001 |
| | 83524 | -0.452 | 0.143 | 0.018 | 3.031 | -0.062 | 0.003 | -0.704 | 0.001 |
| 15 Top slab @ Drywell Head Opening | 98120 | -2.469 | 1.190 | -0.018 | 1.790 | 1.051 | 1.170 | -0.230 | -1.136 |
| | 98135 | -9.521 | -0.243 | 0.273 | 2.553 | -1.580 | 0.021 | 0.662 | -1.608 |
| | 98104 | 0.502 | 2.365 | -0.641 | 1.123 | 7.240 | -1.038 | 0.435 | -1.748 |
| 16 Top slab @ Center | 98149 | -4.573 | 3.370 | -1.802 | 2.560 | 1.444 | -0.399 | 0.452 | 1.641 |
| | 98170 | -3.641 | 2.251 | -0.696 | 3.552 | 5.282 | -0.099 | -0.108 | -0.215 |
| | 98109 | 0.576 | 1.443 | -0.192 | 5.270 | 6.281 | -0.557 | -0.044 | -0.722 |
| 17 Top slab @ RCCV | 98174 | -1.093 | 2.651 | -0.266 | 0.837 | 2.100 | 1.656 | 1.224 | -0.967 |
| | 98197 | -0.047 | 2.768 | -0.076 | 0.724 | -6.567 | -0.422 | -0.330 | -4.964 |
| | 98103 | 2.025 | 2.126 | -0.437 | -6.783 | 0.343 | -1.315 | -4.883 | -0.879 |

Table 3G.1-14
Results of NASTRAN Analysis, Drywell Unit Pressure (1 MPa) (Continued)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 18 Wall Below RCCV Bottom | 6 | -0.974 | 2.625 | -0.442 | 0.543 | 3.146 | -0.009 | 0.023 | 0.979 |
| | 13 | -0.841 | 2.333 | -0.144 | 0.570 | 3.263 | -0.005 | 0.006 | 0.979 |
| | 24 | -1.138 | 2.559 | 0.061 | 0.594 | 3.346 | -0.006 | 0.005 | 1.003 |
| 19 Wall Below Below RCCV Mid-Height | 806 | 0.068 | 2.574 | -0.358 | -0.027 | -0.090 | 0.015 | -0.008 | 0.070 |
| | 813 | 0.053 | 2.050 | -0.128 | -0.014 | -0.034 | 0.017 | 0.005 | 0.205 |
| | 824 | -0.117 | 2.584 | 0.090 | 0.027 | -0.050 | 0.006 | -0.003 | 0.216 |
| 20 Wall Below RCCV Top | 1606 | 0.740 | 2.463 | -0.399 | -0.309 | -1.768 | 0.000 | 0.000 | 0.488 |
| | 1613 | 0.750 | 1.792 | -0.090 | -0.322 | -1.816 | -0.004 | 0.000 | 0.541 |
| | 1624 | 0.771 | 2.759 | 0.067 | -0.318 | -1.963 | -0.001 | 0.002 | 0.577 |
| 21 Exterior Wall @ EL-11.50 ~10.50m | 20011 | 0.083 | 0.589 | 0.047 | 0.233 | 0.862 | 0.016 | -0.018 | 0.268 |
| | 20023 | 0.008 | -0.130 | -0.088 | -0.071 | 0.043 | -0.002 | 0.000 | 0.030 |
| | 30010 | 0.234 | -0.091 | -0.029 | 0.301 | 1.468 | -0.016 | -0.006 | -0.313 |
| | 30020 | 0.089 | -0.385 | -0.063 | -0.110 | 0.017 | 0.032 | 0.034 | 0.002 |
| | 40001 | 0.052 | -0.342 | 0.172 | -0.109 | 0.087 | -0.018 | -0.012 | -0.017 |
| 22 Exterior Wall @ EL4.65 ~6.60m | 40011 | -0.160 | 0.053 | -0.011 | 0.331 | 1.576 | 0.012 | 0.001 | -0.329 |
| | 22011 | 0.076 | 0.484 | -0.065 | 0.011 | 0.030 | 0.007 | 0.004 | -0.104 |
| | 22023 | -0.005 | -0.242 | -0.020 | 0.002 | 0.028 | -0.006 | 0.018 | -0.005 |
| | 32010 | 0.223 | 0.082 | 0.024 | 0.010 | 0.089 | 0.002 | 0.000 | 0.029 |
| | 32020 | 0.014 | -0.351 | 0.330 | 0.017 | 0.034 | -0.004 | -0.003 | 0.024 |
| 23 Exterior Wall @ EL22.50 ~24.60m | 42001 | -0.012 | -0.289 | 0.321 | 0.017 | 0.028 | -0.006 | -0.001 | 0.002 |
| | 42011 | 0.089 | 0.681 | -0.011 | 0.015 | 0.034 | 0.005 | -0.003 | 0.050 |
| | 24211 | 0.833 | 0.393 | -0.053 | 0.143 | 0.819 | 0.024 | 0.022 | -0.478 |
| | 24224 | 0.044 | -1.059 | -0.252 | 0.033 | 0.143 | 0.056 | 0.069 | 0.088 |
| | 34210 | 0.902 | 0.116 | 0.068 | -0.042 | 0.077 | 0.014 | -0.010 | 0.063 |
| 24 Basemat @ Wall Below RCCV | 34220 | 0.008 | -0.767 | 0.201 | 0.021 | 0.089 | 0.058 | 0.002 | -0.024 |
| | 44201 | 0.064 | -0.661 | 0.375 | 0.035 | 0.061 | -0.014 | 0.006 | -0.010 |
| | 90140 | -0.080 | 0.388 | 0.713 | 2.798 | 2.185 | -3.294 | 0.247 | -0.521 |
| | 90182 | 1.495 | 0.130 | -0.055 | -0.942 | 4.136 | 0.435 | -0.079 | -0.412 |
| 25 Slab EL4.65m @ RCCV | 90111 | 0.164 | 0.784 | -0.082 | 4.086 | -0.843 | 0.482 | -0.425 | -0.045 |
| | 93140 | -0.060 | 0.051 | 0.049 | 0.064 | 0.043 | -0.051 | 0.009 | -0.011 |
| | 93182 | 0.113 | -0.078 | 0.012 | -0.017 | 0.025 | 0.002 | 0.002 | 0.055 |
| 26 Slab EL17.5m @ RCCV | 93111 | -0.068 | 0.032 | 0.005 | 0.044 | -0.010 | 0.001 | 0.028 | -0.001 |
| | 96144 | 0.352 | 0.353 | 1.213 | 0.160 | 0.247 | -0.170 | 0.035 | -0.080 |
| | 96186 | 1.165 | -0.550 | 0.116 | 0.015 | 0.278 | -0.064 | 0.019 | -0.087 |
| 27 Slab EL27.0m @ RCCV | 96113 | -0.852 | 1.280 | 0.344 | 1.849 | 0.141 | -0.364 | -0.705 | -0.078 |
| | 98472 | 0.203 | 0.751 | -0.714 | -0.258 | -0.277 | 0.313 | -0.368 | 0.122 |
| | 98514 | 0.234 | -0.054 | -0.039 | -0.067 | -0.525 | -0.048 | 0.011 | 0.179 |
| 28 Pool Girder @ Storage Pool | 98424 | -0.456 | 1.390 | -0.179 | -4.819 | -0.756 | -0.338 | 1.587 | 0.131 |
| | 123004 | 3.198 | 12.783 | 7.501 | -0.047 | 0.310 | -0.287 | 0.157 | 0.025 |
| 29 Pool Girder @ Cavity | 123104 | -1.441 | 4.080 | 6.225 | 0.040 | 0.124 | -0.105 | -0.161 | 0.093 |
| | 123012 | -4.030 | -4.444 | -2.369 | 0.107 | 1.186 | -0.019 | 0.124 | 0.668 |
| 30 Pool Girder @ Fuel Pool | 123112 | 1.638 | -2.746 | -2.509 | 0.034 | 0.180 | -0.136 | -0.033 | 0.025 |
| | 123017 | 2.600 | 12.320 | -6.968 | -0.345 | -0.205 | 0.493 | -0.014 | -0.200 |
| 31 MS Tunnel Wall and Slab | 123117 | -1.287 | 3.605 | -5.253 | -0.058 | 0.031 | 0.124 | 0.138 | 0.040 |
| | 150122 | 0.158 | -0.206 | 0.196 | -0.024 | 0.025 | -0.007 | 0.007 | -0.029 |
| | 96611 | -0.118 | 0.252 | -0.053 | -0.090 | -0.090 | -0.009 | 0.032 | 0.003 |
| | 98614 | 0.055 | 0.072 | 0.016 | -0.772 | -0.463 | -0.034 | 0.172 | 0.007 |

Table 3G.1-15

Results of NASTRAN Analysis, Wetwell Unit Pressure (1 MPa)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 RPV Pedestal Bottom | 5006 | -0.799 | -1.047 | 0.031 | 0.172 | 1.017 | 0.002 | 0.002 | 0.487 |
| | 5013 | -0.812 | -0.913 | 0.112 | 0.166 | 1.001 | 0.001 | -0.002 | 0.492 |
| | 5024 | -0.849 | -0.771 | 0.023 | 0.177 | 1.026 | -0.006 | 0.003 | 0.507 |
| 2 RPV Pedestal Mid-Height | 6006 | -0.416 | -1.191 | 0.054 | -0.016 | -0.137 | 0.004 | 0.004 | -0.082 |
| | 6013 | -0.472 | -0.945 | 0.113 | -0.022 | -0.128 | 0.001 | -0.013 | -0.090 |
| | 6024 | -0.552 | -0.464 | -0.006 | -0.060 | -0.125 | -0.004 | 0.005 | -0.059 |
| 3 RPV Pedestal Top | 6606 | 0.613 | -1.807 | 0.124 | 0.768 | 4.820 | 0.066 | 0.168 | -1.287 |
| | 6613 | 0.759 | -1.543 | 0.116 | 0.721 | 4.595 | -0.081 | -0.136 | -1.199 |
| | 6624 | 0.699 | -1.104 | -0.016 | 0.784 | 4.812 | 0.055 | 0.136 | -1.282 |
| 4 RCCV Wetwell Bottom | 1806 | 2.243 | 4.362 | 0.004 | 0.853 | 5.136 | 0.000 | 0.001 | 1.939 |
| | 1813 | 2.160 | 4.039 | -0.016 | 0.849 | 5.146 | -0.006 | -0.003 | 1.972 |
| | 1824 | 2.411 | 4.006 | 0.029 | 0.823 | 5.082 | 0.013 | -0.001 | 1.965 |
| 5 RCCV Wetwell Mid-Height | 2606 | 6.324 | 4.407 | -0.075 | -0.455 | -2.270 | -0.020 | 0.011 | -0.091 |
| | 2613 | 5.863 | 3.899 | -0.004 | -0.474 | -2.063 | -0.002 | -0.011 | -0.060 |
| | 2624 | 6.120 | 3.818 | -0.014 | -0.443 | -2.079 | -0.006 | 0.005 | -0.187 |
| 6 RCCV Wetwell Top | 3406 | 2.787 | 4.390 | -0.479 | 0.798 | 4.654 | -1.228 | 0.928 | -1.768 |
| | 3413 | 2.768 | 3.985 | 0.492 | 0.473 | 3.725 | 1.171 | -0.714 | -1.507 |
| | 3424 | 2.841 | 3.992 | -0.757 | 0.798 | 4.963 | -1.376 | 0.826 | -1.854 |
| 7 RCCV Drywell Bottom | 3606 | 2.198 | 0.823 | -0.618 | -0.212 | -1.310 | -1.245 | 0.371 | -0.665 |
| | 3613 | 2.232 | 0.441 | 0.672 | -0.555 | -2.304 | 1.255 | -0.117 | -0.877 |
| | 3624 | 2.326 | -0.322 | -0.867 | -0.492 | -2.542 | -1.437 | 0.133 | -0.797 |
| 8 RCCV Drywell Mid-Height | 4006 | 2.047 | 0.219 | -0.203 | 0.136 | -0.562 | -0.035 | -0.227 | 0.007 |
| | 4013 | 1.577 | 0.039 | -0.034 | -0.069 | -0.171 | -0.062 | 0.028 | -0.367 |
| | 4976 | 1.561 | -0.264 | 0.001 | -0.038 | -0.042 | 0.007 | -0.007 | -0.365 |
| 9 RCCV Drywell Top | 4406 | 0.842 | -0.620 | -0.273 | 0.464 | 0.376 | 0.116 | -0.001 | -0.557 |
| | 4413 | 0.233 | -0.203 | -0.114 | 0.147 | 0.687 | -0.026 | -0.035 | -0.137 |
| | 4424 | 0.475 | -0.201 | 0.020 | 0.132 | 0.781 | -0.005 | -0.010 | -0.206 |
| 10 Basemat @ Center | 80003 | 0.601 | 0.620 | 0.002 | -1.111 | -1.070 | 0.004 | 0.027 | -0.004 |
| | 80007 | 0.602 | 0.616 | 0.000 | -1.093 | -1.065 | 0.007 | 0.019 | -0.009 |
| | 80012 | 0.601 | 0.610 | 0.001 | -1.083 | -1.062 | 0.004 | 0.009 | 0.000 |
| 11 Basemat Inside RPV Pedestal | 80206 | 0.623 | 0.624 | 0.023 | -1.293 | -1.178 | 0.065 | 0.081 | -0.035 |
| | 80213 | 0.614 | 0.625 | 0.007 | -1.132 | -1.213 | 0.080 | 0.076 | -0.055 |
| | 80224 | 0.614 | 0.556 | -0.006 | -1.082 | -1.114 | -0.004 | -0.006 | -0.012 |
| 12 S/P Slab @ RPV | 83306 | 1.680 | 1.903 | -0.069 | -0.821 | 1.216 | -0.001 | 4.158 | -0.052 |
| | 83313 | 1.855 | 1.882 | 0.068 | -0.745 | 1.241 | -0.018 | 4.183 | 0.056 |
| | 83324 | 1.592 | 1.940 | -0.005 | -0.772 | 1.258 | 0.002 | 4.180 | -0.048 |
| 13 S/P Slab @ Center | 83406 | 1.809 | 1.848 | -0.036 | -6.236 | -1.496 | -0.011 | -0.339 | 0.000 |
| | 83413 | 1.971 | 1.795 | 0.039 | -6.211 | -1.486 | -0.013 | -0.332 | 0.001 |
| | 83424 | 1.776 | 1.935 | -0.005 | -6.224 | -1.479 | 0.001 | -0.331 | 0.001 |
| 14 S/P Slab @ RCCV | 83506 | 1.850 | 1.797 | -0.010 | 2.798 | -0.380 | -0.008 | -3.784 | -0.003 |
| | 83513 | 2.007 | 1.784 | 0.035 | 2.811 | -0.378 | -0.002 | -3.782 | -0.002 |
| | 83524 | 1.886 | 1.954 | -0.022 | 2.794 | -0.373 | -0.001 | -3.781 | 0.003 |
| 15 Top slab @ Drywell Head Opening | 98120 | 0.417 | 0.564 | 0.328 | -0.007 | -0.031 | -0.005 | -0.003 | -0.016 |
| | 98135 | 0.803 | 0.171 | -0.201 | -0.048 | -0.008 | 0.008 | -0.002 | -0.001 |
| | 98104 | 0.177 | 1.082 | -0.199 | -0.003 | -0.025 | 0.001 | -0.001 | 0.005 |
| 16 Top slab @ Center | 98149 | 0.486 | 0.730 | -0.001 | -0.039 | -0.064 | 0.022 | 0.013 | -0.057 |
| | 98170 | 0.694 | 0.264 | 0.034 | -0.083 | -0.130 | -0.019 | -0.012 | -0.027 |
| | 98109 | 0.394 | 0.729 | -0.006 | -0.060 | -0.047 | -0.004 | -0.021 | 0.002 |
| 17 Top slab @ RCCV | 98174 | 0.483 | 0.831 | 0.084 | -0.206 | -0.360 | 0.120 | 0.075 | -0.088 |
| | 98197 | 0.323 | 0.266 | -0.021 | -0.202 | -0.227 | -0.054 | -0.033 | -0.013 |
| | 98103 | 0.366 | 0.572 | 0.035 | -0.217 | -0.064 | 0.000 | -0.022 | -0.003 |

Table 3G.1-15
Results of NASTRAN Analysis, Wetwell Unit Pressure (1 MPa) (Continued)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 18 Wall Below RCCV Bottom | 6 | -0.264 | 0.194 | -0.080 | 0.106 | 0.634 | -0.004 | 0.007 | 0.178 |
| | 13 | -0.246 | -0.018 | -0.046 | 0.133 | 0.735 | 0.000 | 0.001 | 0.212 |
| | 24 | -0.299 | -0.056 | 0.034 | 0.135 | 0.749 | -0.002 | 0.001 | 0.214 |
| 19 Wall Below Below RCCV Mid-Height | 806 | 0.151 | 0.123 | 0.021 | 0.043 | 0.226 | 0.012 | 0.002 | -0.025 |
| | 813 | 0.188 | -0.073 | -0.020 | 0.068 | 0.249 | 0.005 | 0.001 | 0.015 |
| | 824 | 0.156 | -0.096 | 0.038 | 0.051 | 0.258 | 0.001 | -0.001 | 0.031 |
| 20 Wall Below RCCV Top | 1606 | 1.633 | 0.065 | 0.003 | -0.464 | -2.668 | -0.001 | 0.001 | 0.866 |
| | 1613 | 1.594 | -0.194 | -0.016 | -0.475 | -2.726 | -0.006 | -0.002 | 0.926 |
| | 1624 | 1.796 | -0.226 | 0.023 | -0.500 | -2.778 | 0.009 | -0.001 | 0.957 |
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | 0.133 | 0.533 | 0.026 | 0.085 | 0.324 | 0.007 | -0.020 | 0.106 |
| | 20023 | 0.002 | -0.005 | -0.007 | -0.030 | 0.040 | 0.000 | 0.012 | 0.023 |
| | 30010 | 0.171 | 0.305 | 0.000 | 0.103 | 0.543 | -0.004 | -0.002 | -0.113 |
| | 30020 | 0.027 | -0.148 | -0.023 | -0.047 | 0.042 | 0.013 | 0.003 | -0.008 |
| | 40001 | 0.016 | -0.135 | 0.058 | -0.047 | 0.059 | -0.010 | 0.002 | -0.013 |
| | 40011 | 0.104 | 0.343 | 0.021 | 0.110 | 0.578 | 0.003 | 0.002 | -0.118 |
| 22 Exterior Wall @ EL4.65 ~6.60m | 22011 | 0.997 | 0.293 | -0.099 | -0.002 | 0.131 | 0.004 | -0.015 | 0.307 |
| | 22023 | 0.116 | 0.353 | 0.195 | 0.302 | 0.060 | -0.062 | -0.097 | -0.011 |
| | 32010 | 1.131 | 0.164 | -0.064 | -0.016 | 0.100 | 0.016 | -0.001 | -0.301 |
| | 32020 | 0.108 | 0.617 | 0.252 | 0.222 | 0.041 | -0.106 | 0.157 | 0.014 |
| | 42001 | 0.148 | 0.661 | -0.054 | 0.292 | 0.041 | 0.041 | -0.108 | 0.021 |
| | 42011 | 1.037 | 0.239 | 0.146 | -0.056 | 0.063 | -0.025 | 0.003 | -0.291 |
| 23 Exterior Wall @ EL22.50 ~24.60m | 24211 | 0.419 | 0.475 | 0.007 | 0.031 | 0.211 | -0.003 | -0.004 | -0.010 |
| | 24224 | 0.021 | 0.315 | -0.168 | -0.042 | -0.052 | 0.014 | 0.001 | -0.066 |
| | 34210 | 0.478 | 0.176 | -0.004 | 0.014 | 0.165 | -0.019 | 0.002 | 0.031 |
| | 34220 | -0.018 | 0.129 | 0.002 | -0.013 | 0.029 | 0.017 | -0.029 | -0.015 |
| | 44201 | -0.014 | 0.148 | 0.114 | -0.008 | 0.022 | -0.012 | 0.030 | -0.009 |
| 24 Basemat @ Wall Below RCCV | 90140 | 0.079 | 0.126 | 0.130 | 0.077 | 0.039 | -0.452 | -0.075 | 0.005 |
| | 90182 | 0.311 | 0.107 | 0.009 | -0.308 | 0.020 | 0.063 | -0.003 | 0.270 |
| | 90111 | 0.096 | 0.220 | -0.013 | -0.057 | -0.322 | 0.077 | 0.305 | 0.007 |
| 25 Slab EL4.65m @ RCCV | 93140 | 0.337 | 0.402 | 0.355 | 0.057 | 0.043 | -0.051 | 0.002 | -0.002 |
| | 93182 | 0.704 | 0.216 | -0.057 | -0.007 | 0.087 | 0.005 | 0.002 | 0.068 |
| | 93111 | 0.224 | 0.691 | -0.132 | 0.062 | -0.014 | -0.001 | 0.060 | -0.001 |
| 26 Slab EL17.5m @ RCCV | 96144 | -0.054 | 0.908 | 0.409 | 0.036 | -0.089 | 0.044 | 0.007 | 0.024 |
| | 96186 | 0.852 | -0.302 | -0.428 | 0.019 | -0.020 | 0.075 | -0.023 | -0.105 |
| | 96113 | -0.526 | 1.389 | -0.701 | -0.865 | -0.012 | 0.377 | 0.043 | 0.028 |
| 27 Slab EL27.0m @ RCCV | 98472 | -0.169 | 0.033 | 0.273 | 0.094 | 0.112 | -0.068 | 0.098 | -0.057 |
| | 98514 | 0.094 | 0.102 | 0.004 | 0.026 | 0.171 | 0.004 | 0.000 | -0.127 |
| | 98424 | 0.150 | 0.439 | 0.004 | 0.429 | 0.070 | 0.026 | -0.193 | -0.013 |
| 28 Pool Girder @ Storage Pool | 123004 | 0.254 | -0.030 | -0.051 | 0.005 | -0.060 | 0.007 | 0.025 | -0.032 |
| | 123104 | 0.105 | 0.010 | -0.036 | 0.005 | 0.002 | -0.002 | 0.012 | -0.005 |
| 29 Pool Girder @ Cavity | 123012 | 0.292 | 0.029 | 0.039 | -0.009 | 0.006 | 0.002 | 0.013 | 0.021 |
| | 123112 | 0.215 | 0.029 | 0.085 | -0.011 | -0.006 | -0.003 | 0.015 | -0.006 |
| 30 Pool Girder @ Fuel Pool | 123017 | -0.071 | -0.917 | 0.129 | 0.043 | -0.174 | -0.078 | -0.022 | -0.120 |
| | 123117 | 0.206 | -0.292 | -0.024 | 0.002 | 0.005 | -0.003 | -0.024 | -0.014 |
| 31 MS Tunnel Wall and Slab | 150122 | 0.047 | 0.010 | -0.004 | -0.023 | 0.020 | 0.008 | -0.001 | 0.000 |
| | 96611 | -0.098 | 0.361 | -0.055 | 0.017 | -0.022 | 0.006 | 0.003 | 0.000 |
| | 98614 | 0.057 | -0.001 | 0.016 | -0.134 | -0.055 | -0.010 | 0.022 | 0.000 |

Table 3G.1-16

Results of NASTRAN Analysis, Temperature Load (Normal Operation: Winter)

| Location | Element ID | Nx(MN/m) | Ny(MN/m) | Nxy (MN/m) | Mx (MNm/m) | My(MNm/m) | Mxy(MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|----------|----------|------------|------------|-----------|------------|-----------|-----------|
| 1 RPV Pedestal Bottom | 5006 | -4.824 | -0.465 | -0.214 | -5.642 | -4.446 | -0.033 | 0.062 | 1.557 |
| | 5013 | -4.495 | -0.249 | -0.163 | -5.751 | -4.784 | -0.004 | 0.030 | 1.450 |
| | 5024 | -4.603 | -0.081 | -0.019 | -5.814 | -4.514 | -0.025 | -0.019 | 1.428 |
| 2 RPV Pedestal Mid-Height | 6006 | -1.897 | -0.133 | 0.043 | -5.774 | -5.565 | 0.151 | 0.044 | -0.691 |
| | 6013 | -1.963 | -0.214 | -0.250 | -5.876 | -5.494 | -0.030 | -0.016 | -0.801 |
| | 6024 | -2.065 | -0.151 | 0.004 | -6.554 | -4.209 | -0.240 | 0.011 | -0.694 |
| 3 RPV Pedestal Top | 6606 | -2.691 | -0.086 | 0.128 | -5.695 | -3.487 | 0.023 | -0.192 | -1.695 |
| | 6613 | -2.310 | -0.102 | -0.247 | -5.619 | -3.447 | 0.025 | 0.210 | -1.762 |
| | 6624 | -2.362 | -0.303 | 0.053 | -5.603 | -3.222 | 0.027 | -0.357 | -1.734 |
| 4 RCCV Wetwell Bottom | 1806 | -2.563 | -1.526 | -0.505 | -3.715 | -5.464 | 0.050 | 0.048 | -0.398 |
| | 1813 | -3.004 | -3.488 | -0.335 | -3.549 | -5.455 | -0.016 | -0.006 | -0.390 |
| | 1824 | -2.581 | -4.244 | 0.028 | -3.620 | -5.153 | 0.015 | -0.056 | -0.275 |
| 5 RCCV Wetwell Mid-Height | 2606 | -2.955 | -1.840 | -0.507 | -3.057 | -2.370 | -0.005 | 0.048 | -0.129 |
| | 2613 | -4.074 | -4.373 | -0.070 | -2.625 | -1.960 | 0.002 | -0.054 | 0.080 |
| | 2624 | -3.188 | -4.876 | -0.052 | -3.030 | -2.118 | -0.017 | 0.054 | 0.214 |
| 6 RCCV Wetwell Top | 3406 | 0.382 | -2.431 | -0.111 | -3.082 | -3.463 | -0.092 | 0.172 | 0.532 |
| | 3413 | -1.604 | -5.332 | 0.135 | -2.805 | -3.149 | 0.010 | -0.014 | 0.529 |
| | 3424 | 0.907 | -6.367 | 0.149 | -2.773 | -2.141 | -0.017 | -0.048 | 0.171 |
| 7 RCCV Drywell Bottom | 3606 | -2.497 | -2.662 | -0.413 | -4.073 | -3.963 | 0.046 | 0.167 | 0.167 |
| | 3613 | -1.903 | -6.161 | 0.665 | -2.949 | -2.526 | -0.097 | -0.043 | 0.275 |
| | 3624 | -12.907 | -7.430 | 0.040 | 0.091 | 0.481 | 0.011 | -0.022 | 1.578 |
| 8 RCCV Drywell Mid-Height | 4006 | 0.313 | -2.683 | 0.093 | -4.069 | -4.432 | 0.067 | -0.027 | 0.133 |
| | 4013 | 0.832 | -7.035 | 0.527 | -3.169 | -3.074 | 0.018 | -0.108 | 0.187 |
| | 4976 | -8.880 | -6.829 | 0.607 | -0.328 | -1.435 | -0.003 | 0.003 | -0.469 |
| 9 RCCV Drywell Top | 4406 | 1.744 | -2.456 | -0.925 | -3.912 | -5.591 | 0.278 | 0.007 | 0.353 |
| | 4413 | 0.546 | -7.448 | -0.281 | -3.488 | -4.568 | 0.281 | -0.048 | 0.715 |
| | 4424 | -9.747 | -5.630 | 0.792 | 0.400 | 2.176 | -0.012 | -0.012 | -2.081 |
| 10 Basemat @ Center | 80003 | -4.346 | -4.862 | 0.010 | -4.059 | -4.050 | -0.018 | 0.025 | -0.012 |
| | 80007 | -4.363 | -4.828 | 0.040 | -4.040 | -4.047 | -0.016 | 0.016 | -0.017 |
| | 80012 | -4.366 | -4.767 | 0.027 | -4.032 | -4.048 | -0.016 | 0.005 | -0.003 |
| 11 Basemat Inside RPV Pedestal | 80206 | -4.334 | -5.160 | 0.103 | -4.405 | -4.434 | 0.054 | 0.023 | -0.084 |
| | 80213 | -4.492 | -4.818 | 0.094 | -4.252 | -4.521 | -0.088 | -0.037 | -0.110 |
| | 80224 | -4.397 | -4.671 | 0.051 | -4.294 | -4.192 | -0.016 | -0.060 | 0.011 |
| 12 S/P Slab @ RPV | 83306 | -4.837 | -1.899 | -0.110 | -2.916 | -2.725 | -0.008 | 0.141 | -0.002 |
| | 83313 | -5.355 | -1.357 | 0.193 | -2.863 | -2.724 | -0.020 | 0.199 | 0.009 |
| | 83324 | -5.143 | -1.343 | 0.220 | -2.826 | -2.670 | -0.007 | 0.216 | 0.007 |
| 13 S/P Slab @ Center | 83406 | -3.519 | -2.900 | -0.209 | -3.073 | -2.828 | -0.013 | 0.071 | 0.002 |
| | 83413 | -4.453 | -2.246 | 0.288 | -3.200 | -2.880 | -0.007 | 0.137 | 0.000 |
| | 83424 | -3.977 | -2.228 | 0.023 | -3.178 | -2.834 | 0.001 | 0.136 | -0.001 |
| 14 S/P Slab @ RCCV | 83506 | -2.891 | -3.113 | -0.123 | -3.239 | -2.978 | -0.023 | 0.022 | 0.003 |
| | 83513 | -4.017 | -2.908 | 0.302 | -3.630 | -3.043 | -0.004 | 0.140 | 0.003 |
| | 83524 | -3.373 | -2.594 | -0.018 | -3.551 | -3.013 | 0.013 | 0.106 | -0.004 |
| 15 Top slab @ Drywell Head Opening | 98120 | -8.852 | -6.611 | -4.769 | 0.970 | 0.989 | 0.841 | 0.011 | 0.184 |
| | 98135 | -14.175 | -4.059 | 2.686 | 2.010 | 0.110 | -0.430 | 0.087 | -0.026 |
| | 98104 | -3.705 | -8.366 | 2.799 | 0.113 | 1.464 | -0.357 | 0.027 | -0.112 |
| 16 Top slab @ Center | 98149 | -8.419 | -6.116 | -1.244 | 1.346 | 1.748 | 0.241 | 0.182 | 0.293 |
| | 98170 | -9.287 | -5.378 | 0.041 | 1.797 | 3.119 | 0.000 | 0.112 | 0.365 |
| | 98109 | -7.378 | -6.392 | 1.097 | 1.035 | 1.619 | 0.159 | 0.284 | -0.128 |
| 17 Top slab @ RCCV | 98174 | -7.209 | -7.073 | 1.684 | 2.362 | 2.616 | 0.242 | -0.386 | 0.208 |
| | 98197 | -10.683 | -5.431 | -0.510 | 1.513 | 2.339 | 0.337 | 0.150 | -0.713 |
| | 98103 | -8.340 | -7.216 | 0.229 | 4.178 | 3.159 | 0.208 | 1.069 | -0.002 |

Table 3G.1-16
Results of NASTRAN Analysis, Temperature Load (Normal Operation: Winter),
(Continued)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 18 Wall Below RCCV Bottom | 6 | 1.023 | -0.886 | -0.654 | 0.212 | 1.426 | -0.036 | 0.036 | 0.224 |
| | 13 | 0.507 | -2.542 | -0.586 | 0.379 | 2.154 | 0.000 | 0.013 | 0.472 |
| | 24 | 0.532 | -2.869 | 0.118 | 0.411 | 2.277 | -0.006 | 0.001 | 0.518 |
| 19 Wall Below Below RCCV Mid-Height | 806 | 1.000 | -1.482 | 0.007 | 0.116 | 0.725 | 0.064 | -0.045 | 0.006 |
| | 813 | 0.593 | -2.519 | -0.497 | 0.074 | 0.726 | -0.026 | 0.010 | 0.464 |
| | 824 | 0.409 | -2.995 | 0.111 | 0.101 | 0.757 | 0.016 | 0.007 | 0.458 |
| 20 Wall Below RCCV Top | 1606 | 6.731 | -2.008 | -0.088 | -0.441 | -1.840 | 0.064 | 0.047 | 1.352 |
| | 1613 | 6.528 | -2.928 | -0.407 | -0.479 | -2.808 | -0.006 | -0.011 | 1.675 |
| | 1624 | 6.913 | -3.793 | -0.068 | -0.544 | -2.721 | -0.001 | -0.051 | 1.709 |
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | 2.540 | 2.455 | 0.310 | 0.308 | 1.144 | 0.043 | -0.128 | 0.398 |
| | 20023 | -3.248 | -2.017 | 0.860 | -2.274 | -2.960 | 0.035 | -0.815 | -0.643 |
| | 30010 | 0.453 | 2.322 | -0.053 | 1.022 | 3.264 | -0.016 | -0.021 | -0.581 |
| | 30020 | -0.102 | -1.058 | -0.196 | 0.121 | 1.096 | 0.111 | -0.026 | -0.279 |
| | 40001 | -0.159 | -0.692 | -0.029 | 0.170 | 1.214 | -0.073 | 0.118 | -0.312 |
| 22 Exterior Wall @ EL4.65 ~-6.60m | 40011 | 0.823 | 2.622 | 0.053 | 1.046 | 3.500 | 0.007 | 0.012 | -0.650 |
| | 22011 | 1.843 | 2.253 | -0.169 | -0.064 | -0.019 | 0.029 | 0.016 | 0.166 |
| | 22023 | 1.142 | -3.655 | 0.414 | 0.195 | -0.119 | -0.152 | 0.111 | 0.023 |
| | 32010 | 12.203 | 5.953 | -0.005 | -2.691 | -2.510 | -0.004 | -0.002 | -0.189 |
| | 32020 | 0.286 | 4.009 | 2.271 | -0.586 | -1.816 | -0.384 | 0.707 | 0.105 |
| 23 Exterior Wall @ EL22.50 ~-24.60m | 42001 | 2.259 | 2.832 | 2.345 | -0.754 | -1.648 | -0.038 | -0.653 | -0.264 |
| | 42011 | 10.948 | 4.426 | 0.096 | -2.788 | -2.373 | 0.071 | 0.067 | -0.152 |
| | 24211 | 2.522 | 2.258 | -0.280 | -0.128 | -0.437 | -0.036 | -0.040 | 1.851 |
| | 24224 | 0.174 | 4.366 | -3.359 | 0.618 | -0.270 | -0.552 | -0.582 | -0.214 |
| | 34210 | 13.072 | 4.591 | -0.448 | -2.803 | -2.690 | 0.029 | -0.011 | -0.164 |
| 24 Basemat @ Wall Below RCCV | 34220 | 1.415 | 4.367 | 1.792 | 0.568 | -1.677 | -0.355 | 1.406 | 0.095 |
| | 44201 | 0.851 | 4.776 | -0.637 | 0.172 | -1.845 | 0.435 | -1.737 | 0.113 |
| | 90140 | 0.776 | 0.878 | 1.441 | 0.099 | -0.105 | -0.496 | -0.936 | 0.209 |
| | 90182 | 2.003 | 0.465 | 0.485 | -0.217 | -3.036 | 0.138 | -0.119 | 2.399 |
| | 90111 | 0.557 | 2.512 | -0.038 | -3.682 | -0.570 | 0.051 | 2.681 | 0.125 |
| 25 Slab EL4.65m @ RCCV | 93140 | -0.023 | 1.556 | 2.383 | -0.396 | -0.318 | 0.219 | -0.107 | 0.086 |
| | 93182 | 2.267 | -2.651 | -0.772 | -0.297 | -1.495 | -0.065 | 0.061 | 1.107 |
| | 93111 | -2.303 | 2.913 | -0.078 | -1.569 | -0.289 | -0.039 | 1.040 | 0.002 |
| 26 Slab EL17.5m @ RCCV | 96144 | 0.027 | 2.598 | 3.033 | -0.175 | -0.152 | 0.114 | -0.034 | 0.046 |
| | 96186 | 2.655 | -1.900 | -1.096 | -0.113 | -0.543 | -0.035 | 0.019 | 0.434 |
| | 96113 | -3.979 | -2.962 | -0.545 | -3.812 | -2.712 | -0.133 | 0.521 | -0.025 |
| 27 Slab EL27.0m @ RCCV | 98472 | -1.527 | -0.418 | 4.539 | -0.490 | -0.061 | -0.191 | 0.307 | -0.457 |
| | 98514 | -0.760 | -2.401 | -0.907 | -0.504 | -0.232 | -0.059 | 0.048 | -0.160 |
| | 98424 | -10.129 | -10.794 | -0.971 | 6.001 | 3.682 | 0.035 | -4.073 | -0.189 |
| 28 Pool Girder @ Storage Pool | 123004 | -4.442 | -10.462 | -0.306 | 0.444 | 1.780 | -0.275 | -0.295 | 1.487 |
| | 123104 | -1.614 | -3.341 | 1.911 | -0.140 | -0.494 | 0.091 | -0.445 | 0.305 |
| 29 Pool Girder @ Cavity | 123012 | -3.312 | -0.105 | 0.192 | 0.090 | 0.340 | 0.003 | -0.048 | 0.152 |
| | 123112 | -3.485 | -0.116 | -0.081 | 0.051 | -0.023 | -0.038 | -0.145 | 0.104 |
| 30 Pool Girder @ Fuel Pool | 123017 | 0.207 | -4.788 | -0.951 | 2.325 | 2.914 | -0.165 | 0.309 | 0.477 |
| | 123117 | -1.651 | -2.038 | -0.603 | 2.235 | 1.798 | -0.075 | -0.157 | 0.287 |
| 31 MS Tunnel Wall and Slab | 150122 | 2.242 | -0.256 | -0.859 | 3.735 | 3.890 | 0.060 | -0.257 | -0.296 |
| | 96611 | 0.077 | 1.898 | -0.095 | -3.385 | -6.331 | -0.225 | 0.617 | 0.053 |
| | 98614 | 0.356 | 2.473 | -0.324 | 9.730 | 13.818 | 0.063 | -1.834 | -0.158 |

Table 3G.1-17

Results of NASTRAN Analysis, Temperature Load (LOCA After 6 minutes: Winter)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy(MN/m) | Mx(MNm/m) | My(MNm/m) | Mxy(MNm/m) | Qx(MN/m) | Qy(MN/m) |
|--|------------|-----------|-----------|-----------|-----------|-----------|------------|----------|----------|
| 1 RPV Pedestal Bottom | 5006 | -4.914 | 1.511 | -0.308 | -6.365 | -4.559 | -0.052 | 0.107 | 1.915 |
| | 5013 | -4.492 | 1.682 | -0.086 | -6.538 | -4.972 | -0.006 | 0.026 | 1.799 |
| | 5024 | -4.788 | 1.835 | -0.003 | -6.598 | -4.346 | -0.034 | -0.030 | 1.882 |
| 2 RPV Pedestal Mid-Height | 6006 | 0.032 | 1.753 | 0.169 | -6.298 | -4.819 | 0.250 | 0.076 | -1.338 |
| | 6013 | -0.090 | 1.491 | -0.205 | -6.540 | -4.716 | -0.049 | -0.028 | -1.484 |
| | 6024 | -0.282 | 2.013 | 0.068 | -7.565 | -2.982 | -0.333 | 0.009 | -1.347 |
| 3 RPV Pedestal Top | 6606 | 13.800 | 1.993 | 0.458 | -6.972 | -5.243 | 0.061 | -1.094 | 0.930 |
| | 6613 | 14.040 | 1.756 | -0.439 | -6.980 | -5.204 | 0.051 | 1.161 | 0.871 |
| | 6624 | 14.663 | 2.298 | 0.204 | -6.952 | -5.291 | 0.078 | -1.430 | 1.061 |
| 4 RCCV Wetwell Bottom | 1806 | 1.751 | -0.007 | -0.297 | -4.421 | -7.805 | 0.062 | 0.058 | -1.566 |
| | 1813 | 1.093 | -2.329 | -0.367 | -4.202 | -7.396 | -0.025 | -0.007 | -1.331 |
| | 1824 | 1.981 | -2.824 | 0.082 | -4.322 | -7.438 | 0.022 | -0.082 | -1.354 |
| 5 RCCV Wetwell Mid-Height | 2606 | 1.184 | -0.011 | -0.269 | -3.357 | -1.133 | 0.021 | 0.034 | 0.033 |
| | 2613 | -0.038 | -2.791 | -0.063 | -3.081 | -1.119 | 0.008 | -0.077 | 0.390 |
| | 2624 | 1.079 | -3.158 | -0.043 | -3.384 | -1.119 | -0.022 | 0.071 | 0.377 |
| 6 RCCV Wetwell Top | 3406 | 11.624 | 0.596 | 0.226 | -4.154 | -8.398 | -0.221 | 0.439 | 3.322 |
| | 3413 | 7.954 | -3.660 | -0.047 | -4.357 | -9.124 | -0.396 | 0.519 | 3.323 |
| | 3424 | 11.052 | -4.630 | 0.371 | -3.786 | -5.604 | -0.046 | -0.058 | 2.298 |
| 7 RCCV Drywell Bottom | 3606 | 8.432 | 0.427 | 0.558 | -5.339 | -8.935 | 0.587 | 0.513 | -1.847 |
| | 3613 | 4.514 | -4.417 | 0.816 | -4.914 | -6.085 | -0.394 | 0.296 | -0.734 |
| | 3624 | -3.703 | -6.328 | 0.263 | -1.033 | -3.093 | 0.041 | -0.049 | 0.123 |
| 8 RCCV Drywell Mid-Height | 4006 | 5.852 | 0.754 | -0.011 | -5.144 | -5.509 | 0.007 | -0.183 | -0.528 |
| | 4013 | 4.218 | -5.936 | 0.807 | -4.699 | -4.400 | 0.008 | -0.150 | -0.234 |
| | 4976 | -3.420 | -5.654 | 0.772 | -0.840 | -1.477 | -0.001 | 0.007 | -0.863 |
| 9 RCCV Drywell Top | 4406 | 3.417 | -0.742 | -1.786 | -4.287 | -4.604 | 0.344 | -0.208 | -0.354 |
| | 4413 | 0.498 | -6.550 | -0.446 | -4.823 | -4.853 | 0.289 | -0.224 | 0.725 |
| | 4424 | -7.055 | -4.082 | 0.940 | -0.023 | 2.580 | -0.017 | -0.012 | -1.978 |
| 10 Basemat @ Center | 80003 | -3.832 | -4.440 | 0.007 | -4.240 | -4.238 | -0.016 | 0.032 | -0.015 |
| | 80007 | -3.849 | -4.408 | 0.035 | -4.214 | -4.234 | -0.013 | 0.025 | -0.019 |
| | 80012 | -3.854 | -4.352 | 0.023 | -4.202 | -4.237 | -0.013 | 0.012 | -0.004 |
| 11 Basemat Inside RPV Pedestal | 80206 | -3.801 | -4.758 | 0.111 | -4.600 | -4.678 | 0.083 | 0.016 | -0.101 |
| | 80213 | -3.948 | -4.381 | 0.095 | -4.421 | -4.762 | -0.050 | 0.006 | -0.146 |
| | 80224 | -3.874 | -4.291 | 0.046 | -4.364 | -4.386 | -0.020 | -0.043 | 0.010 |
| 12 S/P Slab @ RPV | 83306 | -8.430 | 8.012 | 0.027 | -4.417 | -2.896 | 0.015 | -0.248 | 0.001 |
| | 83313 | -8.845 | 8.448 | -0.275 | -4.426 | -2.958 | -0.032 | -0.239 | -0.022 |
| | 83324 | -8.617 | 8.870 | 0.723 | -4.216 | -2.783 | 0.001 | -0.123 | 0.042 |
| 13 S/P Slab @ Center | 83406 | -4.716 | 3.300 | -0.435 | -3.598 | -3.189 | -0.006 | -0.274 | 0.009 |
| | 83413 | -5.529 | 3.887 | 0.330 | -3.708 | -3.266 | -0.014 | -0.232 | -0.007 |
| | 83424 | -5.039 | 4.216 | 0.041 | -3.677 | -3.155 | -0.002 | -0.184 | 0.007 |
| 14 S/P Slab @ RCCV | 83506 | -2.707 | 1.467 | -0.274 | -2.852 | -3.128 | -0.032 | -0.252 | 0.010 |
| | 83513 | -3.724 | 1.595 | 0.393 | -3.192 | -3.182 | -0.007 | -0.152 | 0.000 |
| | 83524 | -3.075 | 2.237 | -0.023 | -3.204 | -3.140 | 0.013 | -0.148 | -0.004 |
| 15 Top slab @ Drywell Head Opening | 98120 | -7.704 | -4.732 | -1.166 | 0.747 | 0.629 | 2.583 | -0.150 | 0.074 |
| | 98135 | -10.062 | -5.610 | 0.556 | 3.094 | -2.008 | -1.221 | 0.306 | -0.222 |
| | 98104 | -5.268 | -2.661 | 0.786 | -1.577 | 3.078 | -1.390 | 0.146 | -0.201 |
| 16 Top slab @ Center | 98149 | -6.420 | -3.274 | -0.448 | 1.814 | 2.130 | 0.346 | 0.136 | 0.106 |
| | 98170 | -6.246 | -3.905 | -0.324 | 2.174 | 3.114 | -0.038 | 0.113 | 0.455 |
| | 98109 | -6.252 | -2.427 | 0.725 | 1.007 | 2.226 | 0.038 | 0.380 | -0.086 |
| 17 Top slab @ RCCV | 98174 | -5.257 | -4.725 | 1.957 | 2.429 | 2.294 | 0.439 | -0.175 | -0.031 |
| | 98197 | -7.993 | -3.381 | -0.911 | 1.891 | 2.951 | 0.273 | 0.139 | -0.592 |
| | 98103 | -6.656 | -4.117 | 0.218 | 4.494 | 3.771 | 0.226 | 1.080 | 0.001 |

Table 3G.1-17
Results of NASTRAN Analysis, Temperature Load (LOCA After 6 minutes: Winter),
(Continued)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 18 Wall Below RCCV Bottom | 6 | 0.931 | -1.125 | -0.748 | 0.244 | 1.608 | -0.041 | 0.046 | 0.242 |
| | 13 | 0.411 | -3.022 | -0.610 | 0.437 | 2.455 | 0.002 | 0.013 | 0.528 |
| | 24 | 0.330 | -3.256 | 0.152 | 0.473 | 2.598 | -0.007 | 0.001 | 0.588 |
| 19 Wall Below Below RCCV Mid-Height | 806 | 1.402 | -1.854 | 0.083 | 0.220 | 1.176 | 0.076 | -0.051 | -0.079 |
| | 813 | 0.936 | -3.009 | -0.507 | 0.150 | 1.159 | -0.032 | 0.010 | 0.460 |
| | 824 | 0.749 | -3.304 | 0.158 | 0.167 | 1.199 | 0.020 | 0.009 | 0.452 |
| 20 Wall Below RCCV Top | 1606 | 10.806 | -2.486 | 0.050 | -0.665 | -3.012 | 0.083 | 0.059 | 2.184 |
| | 1613 | 10.443 | -3.560 | -0.419 | -0.713 | -3.998 | -0.010 | -0.013 | 2.514 |
| | 1624 | 11.250 | -4.196 | -0.083 | -0.794 | -4.030 | 0.001 | -0.077 | 2.602 |
| 21 Exterior Wall @ EL-11.50 --10.50m | 20011 | 2.705 | 3.066 | 0.389 | 0.368 | 1.368 | 0.053 | -0.156 | 0.466 |
| | 20023 | -3.251 | -1.996 | 0.825 | -2.301 | -2.914 | 0.034 | -0.800 | -0.621 |
| | 30010 | 0.724 | 2.695 | -0.073 | 1.092 | 3.667 | -0.017 | -0.022 | -0.637 |
| | 30020 | -0.071 | -1.233 | -0.217 | 0.074 | 1.116 | 0.124 | -0.017 | -0.276 |
| | 40001 | -0.153 | -0.846 | 0.059 | 0.127 | 1.264 | -0.082 | 0.120 | -0.316 |
| 22 Exterior Wall @ EL4.65 -6.60m | 40011 | 0.891 | 3.003 | 0.054 | 1.119 | 3.906 | 0.009 | 0.013 | -0.707 |
| | 22011 | 3.318 | 2.710 | -0.171 | -0.103 | -0.066 | 0.048 | 0.030 | 0.058 |
| | 22023 | 1.285 | -3.170 | 0.477 | 0.534 | -0.054 | -0.170 | 0.006 | 0.009 |
| | 32010 | 14.112 | 6.168 | -0.023 | -2.775 | -2.672 | 0.003 | -0.007 | -0.020 |
| | 32020 | 0.400 | 4.604 | 2.519 | -0.338 | -1.807 | -0.378 | 0.875 | 0.157 |
| 23 Exterior Wall @ EL22.50 -24.60m | 42001 | 2.426 | 3.483 | 2.473 | -0.440 | -1.604 | -0.045 | -0.762 | -0.249 |
| | 42011 | 12.516 | 4.854 | 0.184 | -2.941 | -2.613 | 0.072 | 0.080 | 0.063 |
| | 24211 | 3.814 | 3.230 | -0.215 | -0.028 | 0.139 | -0.034 | -0.045 | 1.652 |
| | 24224 | 0.397 | 5.311 | -3.629 | 0.850 | -0.366 | -0.448 | -0.780 | -0.397 |
| | 34210 | 14.993 | 4.941 | -0.346 | -2.787 | -2.419 | 0.017 | -0.013 | 0.093 |
| 24 Basemat @ Wall Below RCCV | 34220 | 1.556 | 5.056 | 1.786 | 0.885 | -1.523 | -0.164 | 1.522 | -0.010 |
| | 44201 | 0.989 | 5.532 | -0.249 | 0.541 | -1.740 | 0.350 | -1.832 | 0.050 |
| | 90140 | 0.810 | 0.937 | 1.518 | -0.219 | -0.337 | -0.492 | -1.096 | 0.272 |
| | 90182 | 2.214 | 0.531 | 0.485 | -0.413 | -3.760 | 0.157 | -0.103 | 2.795 |
| | 90111 | 0.599 | 2.396 | -0.039 | -4.358 | -0.699 | 0.073 | 3.051 | 0.135 |
| 25 Slab EL4.65m @ RCCV | 93140 | 0.135 | 2.185 | 3.808 | -0.512 | -0.404 | 0.288 | -0.137 | 0.113 |
| | 93182 | 3.924 | -3.797 | -1.043 | -0.359 | -1.846 | -0.083 | 0.076 | 1.380 |
| | 93111 | -3.346 | 4.625 | -0.234 | -1.884 | -0.337 | -0.050 | 1.257 | 0.001 |
| 26 Slab EL17.5m @ RCCV | 96144 | -0.275 | 4.650 | 7.008 | -0.256 | -0.148 | 0.178 | -0.080 | 0.026 |
| | 96186 | 6.634 | -4.133 | -1.423 | -0.104 | -0.384 | -0.051 | 0.018 | 0.398 |
| | 96113 | -8.012 | 3.448 | -1.490 | -4.673 | -2.833 | -0.192 | 1.013 | -0.053 |
| 27 Slab EL27.0m @ RCCV | 98472 | -1.982 | -0.328 | 5.374 | -0.389 | 0.081 | -0.331 | 0.462 | -0.565 |
| | 98514 | 0.251 | -2.349 | -1.148 | -0.511 | 0.076 | -0.048 | 0.047 | -0.499 |
| | 98424 | -10.347 | -8.098 | -1.199 | 6.883 | 3.766 | 0.096 | -4.484 | -0.220 |
| 28 Pool Girder @ Storage Pool | 123004 | -3.222 | -10.345 | 0.042 | 0.420 | 1.524 | -0.253 | -0.188 | 1.420 |
| | 123104 | -1.162 | -3.219 | 1.957 | -0.186 | -0.569 | 0.085 | -0.399 | 0.291 |
| 29 Pool Girder @ Cavity | 123012 | -1.584 | -0.088 | -0.190 | -0.062 | 0.579 | 0.047 | 0.057 | 0.427 |
| | 123112 | -2.306 | -0.056 | -0.066 | -0.143 | -0.117 | -0.095 | -0.039 | 0.096 |
| 30 Pool Girder @ Fuel Pool | 123017 | 0.774 | -6.893 | -0.910 | 2.469 | 2.741 | -0.228 | 0.208 | 0.414 |
| | 123117 | -0.984 | -2.677 | -0.716 | 2.293 | 1.832 | -0.079 | -0.209 | 0.279 |
| 31 MS Tunnel Wall and Slab | 150122 | 2.226 | -0.111 | -0.753 | 3.639 | 3.907 | 0.083 | -0.262 | -0.322 |
| | 96611 | -0.174 | 3.068 | -0.248 | -3.645 | -6.606 | -0.247 | 0.700 | 0.064 |
| | 98614 | 0.527 | 2.703 | -0.288 | 9.377 | 13.644 | 0.044 | -1.769 | -0.155 |

Table 3G.1-18

Results of NASTRAN Analysis, Temperature Load (LOCA After 72 hours: Winter)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 RPV Pedestal Bottom | 5006 | -13.947 | 0.161 | -0.486 | -15.740 | -11.087 | -0.102 | 0.226 | 4.880 |
| | 5013 | -13.372 | 0.271 | -0.086 | -16.029 | -11.713 | -0.007 | 0.019 | 4.752 |
| | 5024 | -13.919 | 0.215 | 0.002 | -16.061 | -10.406 | -0.078 | -0.046 | 4.926 |
| 2 RPV Pedestal Mid-Height | 6006 | -2.483 | 0.613 | 0.460 | -16.186 | -15.497 | 0.425 | 0.153 | -1.652 |
| | 6013 | -2.675 | 0.292 | -0.222 | -16.668 | -15.409 | -0.043 | -0.034 | -1.882 |
| | 6024 | -2.798 | 0.648 | 0.087 | -18.667 | -11.882 | -0.682 | 0.031 | -1.562 |
| 3 RPV Pedestal Top | 6606 | 3.459 | 0.568 | 0.467 | -16.412 | -12.055 | 0.121 | -0.772 | -1.957 |
| | 6613 | 4.014 | 0.624 | -0.376 | -16.392 | -12.231 | -0.024 | 0.838 | -1.943 |
| | 6624 | 4.131 | 0.639 | 0.234 | -16.379 | -12.033 | 0.102 | -1.077 | -1.799 |
| 4 RCCV Wetwell Bottom | 1806 | -2.089 | -1.627 | -0.394 | -10.252 | -14.421 | 0.073 | 0.070 | -1.432 |
| | 1813 | -2.608 | -4.438 | -0.288 | -9.980 | -13.822 | -0.044 | -0.007 | -1.104 |
| | 1824 | -1.725 | -4.483 | 0.172 | -10.129 | -13.767 | 0.031 | -0.103 | -1.054 |
| 5 RCCV Wetwell Mid-Height | 2606 | -4.378 | -2.154 | -0.405 | -9.998 | -7.615 | 0.005 | 0.039 | 0.073 |
| | 2613 | -5.309 | -5.586 | 0.063 | -9.714 | -7.480 | -0.018 | -0.096 | 0.442 |
| | 2624 | -4.767 | -5.072 | -0.072 | -10.108 | -7.790 | -0.038 | 0.082 | 0.381 |
| 6 RCCV Wetwell Top | 3406 | 5.146 | -1.793 | 0.374 | -10.845 | -13.921 | 0.028 | 0.122 | 2.434 |
| | 3413 | 3.360 | -7.377 | 0.327 | -10.754 | -14.083 | -0.105 | 0.111 | 2.634 |
| | 3424 | 3.550 | -6.962 | 0.378 | -10.104 | -10.258 | 0.043 | -0.160 | 1.032 |
| 7 RCCV Drywell Bottom | 3606 | 0.855 | -1.873 | -0.034 | -12.684 | -14.715 | 0.245 | 0.161 | -0.543 |
| | 3613 | -1.019 | -8.771 | 1.274 | -12.290 | -13.057 | -0.280 | 0.001 | -0.234 |
| | 3624 | -10.073 | -8.472 | 0.316 | -7.314 | -7.358 | 0.070 | -0.111 | 1.306 |
| 8 RCCV Drywell Mid-Height | 4006 | 1.877 | -1.562 | -0.442 | -12.483 | -13.207 | 0.139 | -0.296 | -0.380 |
| | 4013 | 1.214 | -10.590 | 1.149 | -12.238 | -11.748 | 0.051 | -0.198 | -0.348 |
| | 4976 | -8.101 | -7.344 | 0.924 | -7.622 | -8.430 | 0.004 | 0.035 | -0.545 |
| 9 RCCV Drywell Top | 4406 | 0.823 | -3.764 | -3.737 | -11.621 | -12.462 | 0.691 | -0.182 | -0.529 |
| | 4413 | -1.109 | -11.745 | -0.412 | -12.243 | -11.597 | 0.480 | -0.143 | 0.316 |
| | 4424 | -11.976 | -5.333 | 1.168 | -6.791 | -4.544 | -0.050 | -0.027 | -2.329 |
| 10 Basemat @ Center | 80003 | -1.458 | -2.035 | -0.010 | -4.165 | -4.332 | -0.019 | 0.027 | -0.018 |
| | 80007 | -1.464 | -1.996 | 0.023 | -4.146 | -4.331 | -0.018 | 0.015 | -0.025 |
| | 80012 | -1.469 | -1.929 | 0.013 | -4.141 | -4.341 | -0.014 | -0.003 | -0.003 |
| 11 Basemat Inside RPV Pedestal | 80206 | -1.451 | -2.440 | 0.102 | -4.566 | -4.901 | 0.112 | -0.003 | -0.132 |
| | 80213 | -1.559 | -1.931 | 0.037 | -4.414 | -4.996 | -0.075 | -0.008 | -0.208 |
| | 80224 | -1.413 | -1.846 | 0.033 | -4.392 | -4.556 | -0.029 | -0.087 | 0.015 |
| 12 S/P Slab @ RPV | 83306 | -9.972 | 1.598 | -0.064 | -9.481 | -8.299 | 0.020 | -0.052 | -0.031 |
| | 83313 | -10.412 | 2.279 | 0.020 | -9.487 | -8.358 | -0.018 | -0.032 | 0.009 |
| | 83324 | -10.086 | 2.442 | 0.535 | -9.395 | -8.241 | -0.004 | 0.012 | 0.009 |
| 13 S/P Slab @ Center | 83406 | -6.718 | -1.759 | -0.385 | -8.944 | -8.523 | -0.007 | -0.094 | 0.009 |
| | 83413 | -7.659 | -0.903 | 0.493 | -9.069 | -8.607 | -0.009 | -0.043 | -0.004 |
| | 83424 | -6.972 | -0.779 | -0.021 | -9.008 | -8.518 | 0.002 | -0.039 | 0.004 |
| 14 S/P Slab @ RCCV | 83506 | -5.228 | -3.030 | -0.183 | -8.795 | -8.644 | -0.044 | -0.124 | 0.014 |
| | 83513 | -6.407 | -2.664 | 0.563 | -9.202 | -8.697 | -0.010 | 0.002 | 0.004 |
| | 83524 | -5.481 | -2.152 | -0.087 | -9.085 | -8.636 | 0.017 | -0.037 | -0.005 |
| 15 Top slab @ Drywell Head Opening | 98120 | -12.118 | -11.183 | -5.512 | 6.841 | 6.030 | 5.411 | -0.811 | -0.398 |
| | 98135 | -17.422 | -7.219 | 2.697 | 11.169 | 0.342 | -2.394 | 0.848 | -0.819 |
| | 98104 | -6.925 | -12.999 | 2.994 | 2.265 | 12.026 | -3.290 | 0.606 | -0.472 |
| 16 Top slab @ Center | 98149 | -11.284 | -4.069 | -0.857 | 4.361 | 5.925 | 0.936 | 0.661 | -1.018 |
| | 98170 | -10.473 | -4.943 | 0.330 | 4.246 | 5.164 | -0.051 | 0.133 | 0.663 |
| | 98109 | -6.965 | -3.863 | 0.571 | 8.864 | 11.344 | -0.270 | 0.605 | -0.017 |
| 17 Top slab @ RCCV | 98174 | -8.731 | -7.669 | 2.634 | 5.537 | 4.434 | 0.957 | -0.904 | -0.184 |
| | 98197 | -12.156 | -5.258 | -1.159 | 4.205 | 6.099 | 0.531 | 0.320 | -0.561 |
| | 98103 | -6.757 | -8.103 | 0.104 | 13.587 | 13.101 | 0.388 | 1.276 | 0.008 |

Table 3G.1-18
Results of NASTRAN Analysis, Temperature Load (LOCA After 72 hours: Winter),
(Continued)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 18 Wall Below RCCV Bottom | 6 | 0.500 | -1.654 | -0.972 | 0.379 | 2.437 | -0.053 | 0.065 | 0.459 |
| | 13 | -0.085 | -4.092 | -0.679 | 0.635 | 3.539 | 0.001 | 0.019 | 0.830 |
| | 24 | 0.018 | -3.987 | 0.219 | 0.642 | 3.557 | -0.009 | 0.000 | 0.840 |
| 19 Wall Below Below RCCV Mid-Height | 806 | 1.715 | -2.757 | 0.110 | 0.305 | 1.594 | 0.082 | -0.064 | -0.104 |
| | 813 | 1.263 | -4.045 | -0.535 | 0.199 | 1.585 | -0.036 | 0.005 | 0.613 |
| | 824 | 1.020 | -4.014 | 0.229 | 0.220 | 1.644 | 0.029 | 0.013 | 0.560 |
| 20 Wall Below RCCV Top | 1606 | 15.255 | -3.697 | 0.077 | -0.865 | -3.917 | 0.106 | 0.072 | 2.988 |
| | 1613 | 15.098 | -4.773 | -0.377 | -0.955 | -5.278 | -0.012 | -0.016 | 3.467 |
| | 1624 | 15.945 | -5.116 | -0.071 | -1.065 | -5.223 | 0.003 | -0.102 | 3.539 |
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | 3.015 | 4.539 | 0.539 | 0.546 | 2.096 | 0.065 | -0.209 | 0.722 |
| | 20023 | -3.247 | -1.943 | 0.806 | -2.359 | -2.817 | 0.031 | -0.795 | -0.575 |
| | 30010 | 1.001 | 3.822 | -0.190 | 1.305 | 4.878 | -0.022 | -0.029 | -0.906 |
| | 30020 | -0.043 | -1.519 | -0.380 | 0.011 | 1.225 | 0.146 | -0.023 | -0.288 |
| | 40001 | -0.085 | -1.165 | 0.093 | 0.037 | 1.359 | -0.099 | 0.110 | -0.329 |
| 22 Exterior Wall @ EL4.65 ~-6.60m | 40011 | 1.348 | 3.854 | 0.063 | 1.290 | 4.897 | 0.012 | 0.016 | -0.910 |
| | 22011 | 4.828 | 4.398 | -0.287 | -0.154 | -0.139 | 0.067 | 0.044 | 0.162 |
| | 22023 | 1.518 | -2.692 | 0.328 | 0.990 | 0.017 | -0.183 | -0.173 | 0.000 |
| | 32010 | 16.476 | 7.814 | -0.100 | -2.875 | -2.936 | -0.003 | -0.013 | -0.029 |
| | 32020 | 0.610 | 4.810 | 2.460 | 0.061 | -1.837 | -0.391 | 1.189 | 0.188 |
| 23 Exterior Wall @ EL22.50 ~-24.60m | 42001 | 2.708 | 3.726 | 2.529 | 0.074 | -1.559 | -0.037 | -0.972 | -0.233 |
| | 42011 | 14.259 | 5.931 | 0.283 | -3.138 | -2.902 | 0.064 | 0.089 | 0.069 |
| | 24211 | 5.628 | 6.168 | -0.121 | 0.036 | 0.461 | -0.032 | -0.057 | 1.532 |
| | 24224 | 1.066 | 6.059 | -3.947 | 1.882 | 0.047 | -0.627 | -1.457 | -0.289 |
| | 34210 | 21.500 | 5.814 | -0.637 | -2.922 | -2.837 | 0.043 | -0.005 | -0.143 |
| 24 Basemat @ Wall Below RCCV | 34220 | 2.573 | 6.295 | 3.703 | 2.522 | -1.254 | -0.604 | 2.464 | 0.060 |
| | 44201 | 1.787 | 7.067 | -0.242 | 2.081 | -1.543 | 0.575 | -2.867 | 0.058 |
| | 90140 | 0.656 | 1.200 | 1.911 | -1.180 | -1.211 | -0.619 | -1.550 | 0.481 |
| | 90182 | 2.514 | 0.741 | 0.349 | -1.063 | -5.492 | 0.225 | -0.057 | 3.883 |
| | 90111 | 0.765 | 3.129 | -0.047 | -5.573 | -1.339 | 0.131 | 3.888 | 0.160 |
| 25 Slab EL4.65m @ RCCV | 93140 | 0.490 | 2.920 | 5.382 | -0.742 | -0.577 | 0.416 | -0.195 | 0.167 |
| | 93182 | 5.916 | -4.973 | -1.484 | -0.488 | -2.535 | -0.114 | 0.107 | 1.922 |
| | 93111 | -4.283 | 6.565 | -0.433 | -2.488 | -0.436 | -0.068 | 1.677 | 0.002 |
| 26 Slab EL17.5m @ RCCV | 96144 | 0.694 | 5.742 | 8.267 | -0.286 | -0.226 | 0.196 | -0.057 | 0.076 |
| | 96186 | 9.941 | -4.575 | -2.193 | -0.167 | -0.769 | -0.060 | 0.027 | 0.707 |
| | 96113 | -8.874 | 6.068 | -1.617 | -4.618 | -2.819 | -0.231 | 0.824 | -0.088 |
| 27 Slab EL27.0m @ RCCV | 98472 | -4.967 | -2.594 | 6.298 | -1.805 | -1.111 | -0.360 | 0.517 | -0.794 |
| | 98514 | -3.009 | -2.822 | -1.263 | -1.884 | -1.446 | -0.081 | 0.071 | -0.380 |
| | 98424 | -9.362 | -3.812 | -1.884 | 8.865 | 4.514 | 0.244 | -4.534 | -0.244 |
| 28 Pool Girder @ Storage Pool | 123004 | -3.773 | -8.909 | 2.443 | -3.191 | -1.408 | -0.451 | -0.296 | 2.590 |
| | 123104 | -0.908 | -1.329 | 2.320 | -4.096 | -4.643 | 0.160 | -1.017 | 0.189 |
| 29 Pool Girder @ Cavity | 123012 | -1.053 | -0.015 | -0.253 | -3.807 | -2.087 | 0.177 | 0.085 | 1.518 |
| | 123112 | 0.271 | 0.204 | -0.468 | -4.115 | -3.707 | -0.173 | -0.004 | -0.028 |
| 30 Pool Girder @ Fuel Pool | 123017 | 5.174 | -7.676 | -2.219 | 2.826 | 2.658 | -0.300 | 0.268 | 0.239 |
| | 123117 | 1.810 | -2.768 | -0.560 | 2.974 | 1.894 | -0.159 | -0.541 | 0.254 |
| 31 MS Tunnel Wall and Slab | 150122 | 2.279 | -0.182 | -0.887 | 3.448 | 3.933 | 0.118 | -0.222 | -0.262 |
| | 96611 | -0.295 | 3.728 | -0.322 | -3.550 | -6.604 | -0.232 | 0.690 | 0.063 |
| | 98614 | 1.306 | 2.277 | -0.049 | 9.353 | 14.160 | -0.019 | -1.882 | -0.168 |

Table 3G.1-19

Results of NASTRAN Analysis, Seismic Load (Horizontal: North to South Direction)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 RPV Pedestal Bottom | 5006 | -3.659 | -4.291 | -0.463 | 0.933 | 5.377 | 0.046 | 0.061 | 2.277 |
| | 5013 | -0.845 | 1.502 | -0.434 | 0.377 | 2.323 | -0.013 | 0.130 | 0.940 |
| | 5024 | 2.083 | 7.762 | -0.043 | -0.392 | -1.472 | -0.004 | 0.013 | -0.778 |
| 2 RPV Pedestal Mid-Height | 6006 | 0.421 | -2.493 | -1.016 | -0.148 | -0.141 | 0.015 | 0.118 | 0.098 |
| | 6013 | -0.364 | 1.437 | -1.767 | -0.345 | -0.186 | -0.111 | -0.049 | 0.004 |
| | 6024 | -0.380 | 3.898 | 0.316 | 0.367 | 0.224 | -0.039 | -0.049 | -0.258 |
| 3 RPV Pedestal Top | 6606 | -0.120 | -1.156 | -0.164 | -0.406 | -3.016 | -0.196 | 0.727 | 0.863 |
| | 6613 | -1.375 | 1.345 | -1.301 | -0.577 | -1.769 | 0.318 | -0.089 | 0.297 |
| | 6624 | 0.293 | 3.518 | -0.102 | 0.328 | -0.109 | 0.011 | -0.062 | 0.073 |
| 4 RCCV Wetwell Bottom | 1806 | -1.663 | -1.606 | -3.784 | 0.241 | 1.992 | -0.076 | 0.018 | 0.733 |
| | 1813 | -0.371 | 3.027 | -4.441 | 0.119 | 0.882 | -0.034 | 0.019 | 0.352 |
| | 1824 | 0.906 | 6.607 | -0.267 | -0.034 | -0.345 | -0.011 | 0.003 | -0.240 |
| 5 RCCV Wetwell Mid-Height | 2606 | -0.421 | -1.104 | -3.924 | -0.087 | -0.098 | -0.120 | -0.018 | 0.181 |
| | 2613 | -0.798 | 2.750 | -4.413 | -0.053 | -0.089 | -0.036 | -0.024 | 0.163 |
| | 2624 | -0.044 | 5.027 | -0.262 | 0.099 | 0.205 | -0.005 | -0.005 | -0.062 |
| 6 RCCV Wetwell Top | 3406 | -0.091 | -0.510 | -3.585 | -0.105 | -0.299 | -0.018 | -0.047 | 0.142 |
| | 3413 | -0.662 | 2.398 | -4.252 | -0.039 | -0.196 | -0.071 | 0.067 | 0.077 |
| | 3424 | -0.518 | 3.811 | -0.168 | 0.065 | 0.270 | 0.045 | -0.033 | -0.081 |
| 7 RCCV Drywell Bottom | 3606 | -0.031 | -0.141 | -3.512 | 0.074 | 0.711 | 0.047 | -0.003 | 0.201 |
| | 3613 | -0.698 | 2.066 | -3.945 | 0.081 | 0.502 | -0.070 | 0.057 | 0.204 |
| | 3624 | -0.550 | 3.914 | -0.186 | -0.048 | -0.303 | 0.055 | -0.007 | -0.021 |
| 8 RCCV Drywell Mid-Height | 4006 | 0.790 | 0.233 | -3.141 | -0.077 | -0.071 | -0.062 | 0.029 | 0.261 |
| | 4013 | -0.292 | 2.306 | -3.780 | -0.012 | -0.067 | -0.088 | 0.014 | 0.108 |
| | 4976 | -0.454 | 3.036 | -0.266 | -0.063 | -0.168 | -0.016 | 0.009 | -0.046 |
| 9 RCCV Drywell Top | 4406 | 1.184 | 1.012 | -2.125 | -0.314 | -1.191 | 0.022 | 0.092 | 0.455 |
| | 4413 | 0.714 | 2.598 | -3.377 | -0.009 | -0.368 | -0.034 | -0.042 | 0.072 |
| | 4424 | -0.865 | 2.281 | -0.226 | -0.048 | -0.330 | -0.020 | -0.004 | -0.009 |
| 10 Basemat @ Center | 80003 | 3.586 | 2.842 | -0.331 | -4.691 | -4.176 | 0.064 | 0.477 | 0.092 |
| | 80007 | 3.503 | 2.916 | -0.316 | -4.254 | -4.033 | 0.165 | 0.614 | 0.111 |
| | 80012 | 3.205 | 3.049 | -0.151 | -3.908 | -3.829 | 0.022 | 0.680 | -0.001 |
| 11 Basemat Inside RPV Pedestal | 80206 | 4.320 | 2.471 | -1.054 | -6.305 | -4.299 | 0.491 | 0.742 | 0.202 |
| | 80213 | 3.499 | 2.910 | -1.544 | -3.171 | -2.170 | 1.378 | 1.189 | 0.724 |
| | 80224 | 2.510 | 3.600 | -0.146 | 1.629 | -1.229 | 0.129 | 1.970 | 0.063 |
| 12 S/P Slab @ RPV | 83306 | -0.024 | -1.056 | -1.566 | -2.820 | -1.643 | -0.313 | -1.032 | 0.123 |
| | 83313 | -0.431 | -1.505 | 0.783 | -1.652 | -1.076 | -0.449 | -0.591 | 0.167 |
| | 83324 | -0.623 | -0.113 | 0.101 | -0.297 | -0.317 | -0.028 | -0.051 | 0.017 |
| 13 S/P Slab @ Center | 83406 | 0.042 | -1.356 | -1.365 | 0.433 | -0.909 | -0.224 | -0.712 | -0.011 |
| | 83413 | -0.317 | -1.137 | 0.740 | 0.244 | -0.656 | -0.297 | -0.419 | 0.010 |
| | 83424 | -0.869 | -0.164 | 0.069 | 0.039 | -0.327 | -0.018 | -0.075 | 0.000 |
| 14 S/P Slab @ RCCV | 83506 | 0.316 | -1.405 | -1.038 | 2.407 | 0.020 | -0.029 | -0.546 | -0.048 |
| | 83513 | -0.282 | -0.902 | 0.686 | 1.379 | -0.078 | -0.051 | -0.322 | -0.055 |
| | 83524 | -0.923 | -0.264 | 0.036 | 0.211 | -0.213 | 0.002 | -0.048 | -0.004 |
| 15 Top slab @ Drywell Head Opening | 98120 | 0.071 | 0.072 | 0.030 | -0.046 | -0.076 | -0.034 | -0.040 | -0.019 |
| | 98135 | 0.622 | 0.061 | -0.118 | -0.162 | -0.016 | 0.026 | 0.008 | 0.000 |
| | 98104 | -0.057 | -1.401 | 0.071 | -0.034 | -0.263 | 0.004 | -0.035 | 0.028 |
| 16 Top slab @ Center | 98149 | 0.296 | 0.658 | 0.077 | -0.091 | 0.043 | -0.048 | -0.055 | 0.067 |
| | 98170 | 0.114 | -0.309 | 0.242 | -0.109 | -0.114 | -0.002 | -0.025 | -0.023 |
| | 98109 | 0.015 | -1.309 | -0.036 | -0.221 | -0.377 | -0.030 | -0.060 | 0.070 |
| 17 Top slab @ RCCV | 98174 | 0.306 | 1.159 | 0.053 | 0.252 | 0.417 | -0.212 | -0.180 | 0.149 |
| | 98197 | 0.116 | -0.499 | 0.542 | 0.094 | -0.045 | -0.123 | 0.028 | 0.104 |
| | 98103 | -0.349 | -1.493 | 0.077 | -1.238 | -0.628 | 0.001 | -0.319 | 0.019 |

Table 3G.1-19
Results of NASTRAN Analysis, Seismic Load (Horizontal: North to South Direction),
(Continued)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 18 Wall Below RCCV Bottom | 6 | -4.226 | -2.828 | -3.149 | 0.950 | 5.629 | 0.027 | 0.006 | 2.014 |
| | 13 | -0.092 | 2.940 | -3.947 | 0.616 | 3.308 | -0.083 | 0.135 | 0.998 |
| | 24 | 2.743 | 8.464 | -0.014 | 0.216 | 1.126 | -0.009 | 0.003 | -0.018 |
| 19 Wall Below Below RCCV Mid-Height | 806 | -2.173 | -2.516 | -3.422 | -0.138 | -0.431 | -0.021 | 0.024 | 0.198 |
| | 813 | -0.413 | 3.201 | -4.445 | -0.018 | -0.076 | 0.039 | -0.051 | 0.288 |
| | 824 | 0.979 | 7.859 | -0.125 | 0.047 | 0.231 | 0.002 | -0.001 | 0.236 |
| 20 Wall Below RCCV Top | 1606 | -1.483 | -1.946 | -3.743 | -0.333 | -1.320 | -0.069 | -0.002 | 0.183 |
| | 1613 | -0.138 | 3.051 | -4.514 | -0.243 | -1.271 | -0.022 | 0.009 | 0.366 |
| | 1624 | 0.985 | 6.565 | -0.214 | -0.062 | -0.477 | -0.009 | 0.004 | 0.204 |
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | -0.662 | -1.083 | 0.877 | 1.978 | 8.162 | 0.050 | -0.088 | 3.032 |
| | 20023 | -0.008 | -1.289 | -0.936 | -0.832 | 1.337 | 0.170 | 1.299 | 0.909 |
| | 30010 | 1.283 | 2.225 | -3.374 | 0.481 | 2.677 | -0.053 | -0.091 | -0.745 |
| | 30020 | 0.109 | 2.149 | -0.455 | 0.024 | 1.101 | 0.025 | -0.285 | -0.252 |
| | 40001 | 0.366 | 1.950 | -0.726 | -0.198 | 0.593 | -0.080 | 0.012 | -0.170 |
| | 40011 | 3.276 | 3.698 | -0.076 | 0.140 | 1.121 | 0.012 | 0.005 | -0.164 |
| 22 Exterior Wall @ EL4.65 ~-6.60m | 22011 | -0.441 | -7.125 | 2.468 | 0.116 | 0.966 | 0.154 | -0.038 | 0.853 |
| | 22023 | 0.104 | -4.679 | -0.933 | -0.214 | 0.171 | -0.153 | 0.394 | 0.153 |
| | 32010 | -0.867 | 1.234 | -3.866 | -0.010 | -0.012 | 0.000 | -0.002 | -0.103 |
| | 32020 | -0.041 | 3.265 | -1.524 | 0.147 | 0.024 | 0.003 | 0.129 | -0.002 |
| | 42001 | 0.127 | 3.461 | -1.547 | 0.200 | -0.027 | -0.023 | -0.077 | -0.010 |
| | 42011 | 0.749 | 3.196 | 0.267 | 0.003 | -0.098 | 0.009 | 0.000 | 0.092 |
| 23 Exterior Wall @ EL22.50 ~-24.60m | 24211 | -1.174 | -5.369 | 0.191 | -0.170 | -0.660 | -0.042 | -0.003 | 0.840 |
| | 24224 | -0.282 | -7.465 | 0.532 | 0.695 | 1.033 | -0.289 | 0.178 | 1.126 |
| | 34210 | -1.211 | 0.237 | -3.509 | -0.031 | -0.189 | -0.011 | 0.011 | -0.088 |
| | 34220 | -0.048 | 1.855 | -1.261 | 0.007 | 0.010 | -0.003 | 0.014 | -0.006 |
| | 44201 | -0.107 | 2.171 | -1.075 | 0.032 | 0.040 | -0.008 | 0.012 | -0.013 |
| 24 Basemat @ Wall Below RCCV | 90140 | 0.034 | 1.460 | -2.130 | -6.707 | -0.901 | -0.370 | -2.810 | 1.163 |
| | 90182 | 3.163 | 0.701 | -1.456 | -1.619 | -0.476 | 1.390 | -1.659 | 0.675 |
| | 90111 | 1.027 | 5.920 | -0.258 | 0.380 | -1.228 | 0.393 | -2.033 | -0.131 |
| 25 Slab EL4.65m @ RCCV | 93140 | -1.560 | 0.330 | -0.338 | -0.361 | -0.226 | 0.156 | -0.082 | 0.108 |
| | 93182 | -0.546 | -0.147 | -0.448 | -0.089 | -0.343 | -0.012 | 0.018 | 0.317 |
| | 93111 | -0.088 | -0.093 | 0.017 | 0.067 | -0.003 | 0.007 | -0.042 | 0.002 |
| 26 Slab EL17.5m @ RCCV | 96144 | -0.551 | 0.162 | 0.116 | -0.295 | -0.230 | 0.156 | -0.061 | 0.070 |
| | 96186 | -0.608 | -0.144 | 0.033 | -0.075 | -0.342 | -0.012 | 0.027 | 0.274 |
| | 96113 | 0.211 | -1.036 | 0.004 | 0.468 | -0.036 | -0.012 | -0.448 | -0.066 |
| 27 Slab EL27.0m @ RCCV | 98472 | 1.119 | -0.227 | 0.006 | -0.157 | -0.188 | 0.097 | -0.125 | 0.084 |
| | 98514 | -0.245 | -0.158 | -0.052 | -0.073 | -0.266 | 0.014 | 0.005 | 0.210 |
| | 98424 | 1.140 | -1.230 | 0.150 | -1.103 | -0.494 | 0.076 | 1.187 | 0.079 |
| 28 Pool Girder @ Storage Pool | 123004 | 0.507 | 2.822 | -0.383 | -0.070 | -0.008 | 0.034 | -0.041 | -0.012 |
| | 123104 | -0.578 | 1.180 | -0.739 | -0.090 | -0.008 | -0.001 | -0.034 | 0.011 |
| 29 Pool Girder @ Cavity | 123012 | 0.042 | -0.086 | 0.277 | -0.025 | 0.009 | -0.004 | 0.026 | 0.045 |
| | 123112 | -0.554 | -0.088 | 0.245 | -0.113 | -0.026 | -0.013 | 0.039 | 0.003 |
| 30 Pool Girder @ Fuel Pool | 123017 | 0.301 | 2.991 | 0.076 | 0.072 | 0.236 | 0.043 | 0.022 | 0.221 |
| | 123117 | -1.053 | 0.840 | 1.010 | 0.040 | 0.016 | -0.022 | 0.023 | 0.011 |
| 31 MS Tunnel Wall and Slab | 150122 | 0.144 | 0.403 | -0.048 | -0.062 | -0.103 | -0.009 | 0.015 | -0.033 |
| | 96611 | 0.026 | -0.379 | 0.030 | -0.117 | -0.342 | 0.005 | 0.077 | 0.012 |
| | 98614 | 0.080 | -0.246 | 0.036 | 0.176 | 0.303 | 0.009 | -0.069 | -0.009 |

Table 3G.1-20

Results of NASTRAN Analysis, Seismic Load (Horizontal: East to West Direction)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 RPV Pedestal Bottom | 5006 | 3.824 | 6.562 | -1.902 | -0.846 | -4.326 | -0.053 | 0.250 | -1.867 |
| | 5013 | 5.429 | 10.427 | 0.215 | -1.323 | -6.638 | -0.002 | 0.012 | -2.984 |
| | 5024 | 0.453 | 0.627 | 3.241 | -0.093 | -0.436 | 0.007 | -0.264 | -0.196 |
| 2 RPV Pedestal Mid-Height | 6006 | -0.307 | 2.620 | -3.688 | 0.070 | 0.312 | -0.267 | 0.010 | -0.094 |
| | 6013 | -0.916 | 4.064 | 0.457 | 0.189 | 0.314 | -0.026 | 0.009 | -0.303 |
| | 6024 | -0.203 | 1.547 | 6.461 | 0.032 | 0.048 | 0.415 | 0.220 | 0.041 |
| 3 RPV Pedestal Top | 6606 | -1.238 | 0.118 | -2.973 | 0.335 | 1.594 | 0.093 | -0.028 | -0.657 |
| | 6613 | -1.347 | 0.069 | 0.314 | 0.642 | 2.502 | 0.025 | -0.155 | -0.972 |
| | 6624 | -0.190 | 0.065 | 4.374 | -0.010 | 0.231 | -0.176 | 0.137 | -0.087 |
| 4 RCCV Wetwell Bottom | 1806 | 0.729 | 4.585 | -4.703 | -0.176 | -0.955 | -0.027 | 0.011 | -0.377 |
| | 1813 | 1.114 | 5.859 | 0.928 | -0.274 | -1.581 | -0.011 | 0.006 | -0.664 |
| | 1824 | 0.071 | 0.451 | 7.426 | -0.033 | -0.119 | 0.094 | -0.059 | -0.064 |
| 5 RCCV Wetwell Mid-Height | 2606 | 0.042 | 3.102 | -4.217 | 0.030 | 0.120 | -0.061 | -0.007 | -0.089 |
| | 2613 | -0.005 | 4.069 | 0.921 | 0.044 | 0.171 | -0.017 | -0.010 | -0.249 |
| | 2624 | 0.046 | 0.198 | 6.829 | 0.008 | 0.044 | 0.103 | 0.036 | -0.013 |
| 6 RCCV Wetwell Top | 3406 | -0.398 | 1.932 | -3.913 | 0.030 | 0.165 | -0.110 | 0.074 | -0.089 |
| | 3413 | -0.289 | 2.645 | 0.971 | 0.054 | 0.321 | 0.036 | -0.062 | -0.227 |
| | 3424 | -0.187 | 0.123 | 5.910 | 0.017 | 0.013 | 0.010 | 0.005 | 0.006 |
| 7 RCCV Drywell Bottom | 3606 | -0.452 | 1.766 | -3.473 | -0.041 | -0.248 | -0.085 | 0.065 | -0.016 |
| | 3613 | -0.265 | 2.846 | 1.125 | -0.134 | -0.780 | -0.006 | -0.052 | -0.296 |
| | 3624 | -0.126 | 0.166 | 5.784 | -0.041 | -0.106 | 0.041 | 0.024 | -0.050 |
| 8 RCCV Drywell Mid-Height | 4006 | -0.910 | 0.987 | -3.270 | 0.020 | 0.052 | -0.092 | -0.017 | -0.156 |
| | 4013 | -1.066 | 1.762 | 0.993 | 0.076 | 0.313 | 0.008 | -0.022 | -0.324 |
| | 4976 | 0.115 | 0.026 | 5.969 | 0.045 | 0.045 | 0.059 | 0.041 | -0.021 |
| 9 RCCV Drywell Top | 4406 | -1.432 | 0.273 | -2.870 | 0.144 | 0.700 | -0.008 | 0.016 | -0.292 |
| | 4413 | -1.216 | 0.860 | 0.828 | 0.183 | 1.145 | 0.044 | 0.052 | -0.240 |
| | 4424 | 0.212 | -0.022 | 6.191 | 0.053 | 0.031 | 0.004 | 0.056 | 0.017 |
| 10 Basemat @ Center | 80003 | 0.003 | 0.113 | 0.970 | 0.137 | 0.241 | -0.184 | 0.020 | 0.540 |
| | 80007 | 0.363 | -0.256 | 0.505 | 0.315 | 0.349 | -0.067 | -0.002 | 0.512 |
| | 80012 | -0.098 | 0.116 | 0.355 | 0.055 | 0.059 | 0.106 | -0.005 | 0.558 |
| 11 Basemat Inside RPV Pedestal | 80206 | 1.123 | -0.469 | 2.151 | 2.151 | 2.565 | -1.023 | -0.541 | 1.016 |
| | 80213 | 1.929 | -0.848 | 0.482 | 2.692 | 4.698 | 0.061 | 0.096 | 1.708 |
| | 80224 | 0.076 | 0.039 | -1.798 | 0.300 | 0.206 | 0.366 | 0.075 | 0.061 |
| 12 S/P Slab @ RPV | 83306 | -0.804 | -0.320 | 1.004 | 1.133 | 0.470 | -0.277 | 0.459 | 0.135 |
| | 83313 | -1.336 | -0.260 | 0.171 | 1.627 | 0.736 | 0.021 | 0.659 | -0.015 |
| | 83324 | -0.175 | -0.020 | -1.709 | 0.074 | 0.043 | 0.410 | 0.039 | -0.175 |
| 13 S/P Slab @ Center | 83406 | -0.707 | 0.030 | 0.424 | -0.259 | 0.175 | -0.189 | 0.290 | 0.000 |
| | 83413 | -1.249 | -0.033 | 0.148 | -0.337 | 0.283 | 0.028 | 0.418 | 0.001 |
| | 83424 | -0.106 | -0.009 | -0.929 | -0.033 | 0.010 | 0.268 | 0.026 | 0.015 |
| 14 S/P Slab @ RCCV | 83506 | -0.506 | -0.030 | 0.101 | -1.095 | -0.198 | -0.003 | 0.234 | -0.050 |
| | 83513 | -1.070 | -0.066 | 0.138 | -1.520 | -0.265 | 0.009 | 0.331 | 0.005 |
| | 83524 | -0.061 | -0.032 | -0.577 | -0.110 | -0.025 | -0.026 | 0.023 | 0.083 |
| 15 Top slab @ Drywell Head Opening | 98120 | -1.292 | -1.085 | -0.943 | -0.055 | -0.435 | -0.121 | -0.057 | -0.066 |
| | 98135 | 0.125 | 0.340 | -0.586 | -0.132 | -0.167 | 0.070 | 0.008 | -0.065 |
| | 98104 | 0.417 | 0.603 | -0.632 | -0.056 | -0.513 | 0.012 | 0.016 | -0.418 |
| 16 Top slab @ Center | 98149 | -1.003 | -0.296 | -0.570 | 0.004 | -0.119 | -0.001 | 0.055 | -0.012 |
| | 98170 | -1.062 | 0.055 | -0.748 | -0.033 | 0.008 | -0.035 | 0.007 | -0.003 |
| | 98109 | 0.121 | -0.022 | -0.733 | -0.018 | -0.235 | -0.142 | 0.014 | -0.139 |
| 17 Top slab @ RCCV | 98174 | -1.274 | -0.317 | -0.731 | -0.157 | -0.150 | 0.128 | 0.060 | -0.052 |
| | 98197 | -1.529 | -0.094 | -0.596 | -0.157 | -0.512 | -0.060 | -0.039 | -0.104 |
| | 98103 | -0.222 | 0.168 | -1.093 | -0.035 | -0.048 | -0.197 | 0.040 | -0.043 |

Table 3G.1-20
Results of NASTRAN Analysis, Seismic Load (Horizontal: East to West Direction),
(Continued)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 18 Wall Below RCCV Bottom | 6 | 4.080 | 9.611 | -4.318 | -0.696 | -3.389 | -0.046 | 0.140 | -1.392 |
| | 13 | 4.939 | 9.278 | 0.447 | -0.384 | -2.349 | -0.019 | 0.036 | -1.176 |
| | 24 | 0.630 | 0.657 | 6.609 | 0.010 | -0.204 | 0.106 | -0.160 | -0.129 |
| 19 Wall Below Below RCCV Mid-Height | 806 | 0.690 | 7.399 | -5.103 | -0.009 | 0.249 | -0.132 | -0.022 | 0.020 |
| | 813 | 1.979 | 8.078 | 0.751 | 0.012 | 0.364 | -0.002 | -0.016 | -0.087 |
| | 824 | 0.194 | 0.650 | 7.276 | 0.037 | 0.064 | 0.059 | 0.069 | 0.036 |
| 20 Wall Below RCCV Top | 1606 | 0.628 | 5.038 | -5.272 | 0.082 | 0.563 | -0.019 | -0.005 | -0.110 |
| | 1613 | 1.016 | 6.058 | 0.909 | 0.148 | 0.962 | -0.001 | 0.010 | -0.200 |
| | 1624 | 0.076 | 0.521 | 7.447 | -0.016 | -0.009 | 0.052 | -0.049 | 0.027 |
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | -0.657 | -0.961 | -9.354 | -0.082 | 0.416 | 0.025 | 0.100 | 0.091 |
| | 20023 | 0.059 | 4.728 | -0.475 | 0.320 | 0.224 | -0.093 | -0.079 | 0.031 |
| | 30010 | 3.694 | 3.409 | 0.982 | -0.320 | -1.172 | -0.031 | -0.026 | 0.395 |
| | 30020 | 0.512 | 2.678 | 1.213 | -0.065 | 0.349 | 0.031 | 0.086 | -0.091 |
| | 40001 | 0.005 | 3.037 | 0.977 | 0.369 | 1.132 | 0.016 | 0.362 | -0.176 |
| | 40011 | -0.252 | -0.361 | 4.538 | 0.015 | -0.047 | 0.085 | 0.124 | -0.029 |
| 22 Exterior Wall @ EL4.65 ~-6.60m | 22011 | 0.466 | 3.318 | -6.436 | 0.034 | -0.023 | -0.021 | 0.029 | -0.002 |
| | 22023 | 0.069 | 4.568 | -3.234 | 0.055 | -0.073 | 0.086 | -0.202 | -0.079 |
| | 32010 | 0.643 | 3.408 | 0.932 | -0.019 | -0.097 | -0.012 | -0.001 | 0.219 |
| | 32020 | 0.047 | 2.920 | 2.784 | 0.125 | -0.060 | 0.015 | 0.091 | 0.016 |
| | 42001 | -0.017 | 2.714 | 2.956 | 0.166 | 0.064 | -0.012 | -0.063 | -0.031 |
| | 42011 | 0.214 | -0.581 | 5.945 | 0.045 | 0.003 | 0.018 | 0.040 | -0.015 |
| 23 Exterior Wall @ EL22.50 ~-24.60m | 24211 | -0.114 | 0.162 | -5.394 | -0.003 | 0.026 | 0.015 | 0.004 | 0.008 |
| | 24224 | 0.259 | 3.913 | -3.713 | -0.231 | -0.100 | -0.022 | 0.227 | -0.045 |
| | 34210 | -0.199 | 1.096 | 0.772 | 0.064 | 0.354 | -0.010 | -0.002 | 0.139 |
| | 34220 | -0.162 | 0.839 | 2.354 | 0.119 | 0.142 | 0.026 | 0.026 | -0.022 |
| | 44201 | 0.145 | 0.808 | 2.848 | 0.066 | 0.009 | 0.059 | -0.076 | 0.024 |
| 24 Basemat @ Wall Below RCCV | 90140 | 0.415 | 4.638 | 2.888 | 0.033 | 3.216 | -2.595 | 2.865 | -5.032 |
| | 90182 | 6.054 | 0.571 | 0.309 | 0.153 | -0.445 | -0.242 | -0.046 | -3.502 |
| | 90111 | -0.250 | 0.765 | -0.889 | -0.470 | 0.409 | 1.439 | -0.060 | -2.916 |
| 25 Slab EL4.65m @ RCCV | 93140 | 0.376 | -0.215 | -0.049 | 0.156 | 0.126 | -0.093 | 0.047 | -0.033 |
| | 93182 | 0.013 | -0.083 | -0.165 | 0.085 | 0.479 | 0.017 | -0.023 | -0.425 |
| | 93111 | 0.148 | 0.059 | -0.226 | 0.001 | -0.009 | -0.026 | 0.012 | 0.006 |
| 26 Slab EL17.5m @ RCCV | 96144 | -0.105 | -0.246 | -0.165 | 0.139 | 0.119 | -0.090 | 0.046 | -0.017 |
| | 96186 | -0.330 | 0.169 | -0.231 | 0.108 | 0.616 | 0.023 | -0.031 | -0.490 |
| | 96113 | 0.093 | -0.157 | 0.672 | 0.081 | 0.033 | -0.003 | -0.018 | 0.044 |
| 27 Slab EL27.0m @ RCCV | 98472 | 0.368 | -1.005 | -0.324 | 0.038 | 0.037 | -0.017 | 0.011 | -0.012 |
| | 98514 | -0.432 | 0.208 | -0.345 | 0.063 | 0.441 | -0.003 | -0.008 | -0.368 |
| | 98424 | 0.352 | -0.350 | -5.666 | 0.038 | 0.037 | -0.205 | 0.024 | 0.046 |
| 28 Pool Girder @ Storage Pool | 123004 | -0.043 | -0.854 | -0.200 | 0.285 | 0.713 | -0.142 | 0.099 | 0.614 |
| | 123104 | 0.031 | -0.354 | 0.429 | 0.149 | -0.068 | -0.025 | 0.014 | 0.077 |
| 29 Pool Girder @ Cavity | 123012 | -0.584 | -0.011 | 0.262 | 0.082 | 0.217 | -0.021 | 0.002 | 0.186 |
| | 123112 | -0.677 | -0.004 | 0.368 | 0.091 | -0.015 | -0.016 | -0.088 | -0.009 |
| 30 Pool Girder @ Fuel Pool | 123017 | -0.134 | -0.858 | 0.754 | 0.327 | 0.638 | 0.095 | -0.251 | 0.577 |
| | 123117 | -0.187 | -0.380 | -0.012 | 0.094 | -0.070 | 0.027 | 0.019 | 0.053 |
| 31 MS Tunnel Wall and Slab | 150122 | 0.113 | 0.172 | -0.176 | 0.072 | -0.158 | -0.012 | 0.018 | 0.202 |
| | 96611 | 0.019 | -0.093 | -0.266 | -0.036 | -0.076 | 0.083 | -0.011 | -0.060 |
| | 98614 | -0.025 | -0.005 | 0.172 | -0.022 | 0.063 | 0.203 | -0.041 | 0.048 |

Table 3G.1-21

Results of NASTRAN Analysis, Seismic Load (Vertical: Upward Direction)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 RPV Pedestal Bottom | 5006 | -1.459 | 1.504 | -0.109 | 0.369 | 2.146 | -0.005 | 0.011 | 0.951 |
| | 5013 | -1.245 | 1.957 | -0.167 | 0.325 | 1.935 | -0.001 | 0.012 | 0.845 |
| | 5024 | -0.986 | 2.190 | -0.014 | 0.309 | 1.777 | -0.007 | -0.003 | 0.773 |
| 2 RPV Pedestal Mid-Height | 6006 | 0.062 | 1.529 | -0.161 | -0.022 | -0.079 | -0.020 | -0.017 | -0.006 |
| | 6013 | 0.066 | 1.672 | -0.252 | 0.007 | -0.047 | -0.008 | 0.010 | -0.040 |
| | 6024 | -0.043 | 1.267 | 0.131 | -0.001 | 0.014 | -0.008 | -0.011 | -0.062 |
| 3 RPV Pedestal Top | 6606 | 0.166 | 1.067 | -0.306 | -0.247 | -1.746 | -0.099 | -0.047 | 0.631 |
| | 6613 | 0.176 | 1.114 | -0.128 | -0.210 | -1.696 | 0.113 | 0.019 | 0.609 |
| | 6624 | 0.091 | 1.069 | -0.073 | -0.227 | -1.697 | -0.114 | -0.019 | 0.598 |
| 4 RCCV Wetwell Bottom | 1806 | 0.276 | 3.169 | -0.099 | 0.073 | 0.469 | -0.006 | 0.001 | 0.100 |
| | 1813 | 0.403 | 3.198 | -0.126 | 0.071 | 0.390 | -0.005 | 0.001 | 0.066 |
| | 1824 | 0.327 | 3.634 | 0.042 | 0.074 | 0.449 | 0.000 | 0.002 | 0.092 |
| 5 RCCV Wetwell Mid-Height | 2606 | 0.129 | 2.896 | -0.130 | -0.004 | 0.020 | -0.007 | 0.001 | 0.061 |
| | 2613 | 0.199 | 2.967 | -0.138 | 0.020 | 0.040 | -0.003 | 0.000 | 0.040 |
| | 2624 | 0.193 | 3.390 | 0.018 | -0.013 | -0.002 | 0.000 | 0.002 | 0.080 |
| 6 RCCV Wetwell Top | 3406 | 0.195 | 2.546 | -0.179 | -0.076 | -0.463 | 0.034 | -0.071 | 0.157 |
| | 3413 | 0.063 | 2.823 | -0.097 | -0.025 | -0.210 | 0.004 | 0.016 | 0.076 |
| | 3424 | 0.120 | 3.010 | -0.010 | -0.059 | -0.305 | 0.045 | -0.058 | 0.079 |
| 7 RCCV Drywell Bottom | 3606 | 0.062 | 2.442 | -0.034 | 0.009 | -0.005 | 0.039 | -0.062 | -0.045 |
| | 3613 | -0.070 | 2.782 | -0.112 | 0.007 | 0.010 | -0.009 | 0.017 | -0.131 |
| | 3624 | 0.078 | 3.186 | -0.058 | -0.032 | -0.159 | 0.047 | -0.033 | -0.095 |
| 8 RCCV Drywell Mid-Height | 4006 | -0.449 | 2.407 | 0.073 | 0.095 | 0.356 | 0.041 | 0.003 | -0.161 |
| | 4013 | -0.429 | 2.930 | -0.188 | 0.043 | 0.368 | 0.001 | 0.006 | -0.071 |
| | 4976 | -0.086 | 2.647 | -0.162 | 0.018 | 0.189 | 0.003 | 0.005 | -0.084 |
| 9 RCCV Drywell Top | 4406 | -0.124 | 2.743 | 0.734 | 0.154 | 1.012 | 0.008 | -0.003 | -0.180 |
| | 4413 | 0.349 | 3.050 | -0.086 | 0.139 | 0.731 | -0.005 | 0.010 | -0.144 |
| | 4424 | -0.042 | 2.067 | -0.135 | 0.054 | 0.448 | -0.003 | 0.000 | -0.085 |
| 10 Basemat @ Center | 80003 | 1.176 | 1.338 | -0.029 | -3.648 | -3.734 | 0.003 | -0.174 | 0.134 |
| | 80007 | 1.185 | 1.348 | -0.024 | -3.657 | -3.736 | 0.001 | 0.023 | 0.216 |
| | 80012 | 1.185 | 1.364 | -0.024 | -3.656 | -3.737 | 0.002 | 0.208 | 0.029 |
| 11 Basemat Inside RPV Pedestal | 80206 | 1.149 | 1.282 | -0.043 | -1.685 | -1.928 | -0.649 | -0.747 | 0.658 |
| | 80213 | 1.179 | 1.367 | -0.064 | -2.356 | -1.102 | 0.052 | 0.028 | 1.027 |
| | 80224 | 1.233 | 1.441 | -0.024 | -1.139 | -2.368 | 0.090 | 0.999 | 0.079 |
| 12 S/P Slab @ RPV | 83306 | -0.124 | -0.267 | 0.146 | -1.455 | -0.965 | 0.018 | -0.734 | 0.021 |
| | 83313 | -0.247 | -0.187 | 0.074 | -1.467 | -0.967 | -0.012 | -0.738 | -0.021 |
| | 83324 | -0.232 | -0.288 | -0.002 | -1.473 | -0.971 | 0.018 | -0.742 | 0.020 |
| 13 S/P Slab @ Center | 83406 | -0.143 | -0.260 | 0.105 | 0.552 | -0.468 | 0.003 | -0.366 | 0.000 |
| | 83413 | -0.294 | -0.142 | 0.032 | 0.545 | -0.458 | 0.002 | -0.369 | -0.002 |
| | 83424 | -0.256 | -0.261 | -0.004 | 0.553 | -0.457 | 0.001 | -0.373 | 0.001 |
| 14 S/P Slab @ RCCV | 83506 | -0.144 | -0.236 | 0.096 | 1.146 | -0.010 | 0.006 | -0.102 | -0.002 |
| | 83513 | -0.304 | -0.128 | 0.012 | 1.156 | 0.003 | 0.003 | -0.108 | -0.003 |
| | 83524 | -0.248 | -0.264 | -0.007 | 1.178 | 0.007 | 0.001 | -0.111 | 0.001 |
| 15 Top slab @ Drywell Head Opening | 98120 | -0.808 | -0.210 | -0.293 | 0.379 | 0.220 | 0.278 | -0.038 | -0.236 |
| | 98135 | -2.236 | -0.182 | 0.197 | 0.527 | -0.240 | -0.066 | 0.082 | -0.299 |
| | 98104 | -0.066 | -0.456 | 0.069 | 0.172 | 1.050 | -0.219 | 0.002 | -0.239 |
| 16 Top slab @ Center | 98149 | -1.174 | 0.156 | -0.372 | 0.527 | 0.371 | -0.031 | 0.043 | 0.191 |
| | 98170 | -1.023 | 0.029 | -0.024 | 0.653 | 0.874 | -0.004 | 0.011 | 0.023 |
| | 98109 | -0.194 | -0.382 | 0.000 | 0.646 | 0.724 | -0.119 | -0.054 | -0.048 |
| 17 Top slab @ RCCV | 98174 | -0.519 | 0.046 | -0.052 | 0.277 | 0.532 | 0.234 | 0.161 | -0.084 |
| | 98197 | -0.155 | -0.016 | 0.113 | 0.343 | -0.833 | -0.060 | -0.048 | -0.581 |
| | 98103 | 0.009 | -0.287 | -0.065 | -1.481 | -0.221 | -0.171 | -0.781 | -0.095 |

Table 3G.1-21
Results of NASTRAN Analysis, Seismic Load (Vertical: Upward Direction) (Continued)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 18 Wall Below RCCV Bottom | 6 | -0.321 | 4.250 | -0.279 | 0.231 | 1.518 | -0.009 | 0.024 | 0.450 |
| | 13 | -0.421 | 3.452 | -0.258 | 0.399 | 2.157 | -0.007 | 0.010 | 0.633 |
| | 24 | -0.417 | 3.860 | 0.100 | 0.425 | 2.253 | -0.005 | 0.002 | 0.637 |
| 19 Wall Below Below RCCV Mid-Height | 806 | -0.054 | 3.702 | -0.048 | -0.019 | -0.024 | 0.019 | -0.004 | 0.065 |
| | 813 | 0.021 | 3.433 | -0.210 | 0.018 | 0.014 | 0.021 | -0.002 | 0.157 |
| | 824 | -0.053 | 3.860 | 0.103 | 0.036 | 0.019 | 0.007 | -0.003 | 0.199 |
| 20 Wall Below RCCV Top | 1606 | 0.407 | 3.300 | -0.034 | -0.123 | -0.670 | -0.005 | 0.004 | 0.219 |
| | 1613 | 0.540 | 3.308 | -0.149 | -0.128 | -0.778 | -0.005 | 0.002 | 0.270 |
| | 1624 | 0.471 | 3.747 | 0.069 | -0.133 | -0.780 | 0.001 | 0.004 | 0.262 |
| 21 Exterior Wall @ EL-11.50 ~10.50m | 20011 | 0.399 | 2.223 | 0.230 | 0.022 | -0.013 | -0.003 | -0.031 | -0.030 |
| | 20023 | 0.013 | 0.711 | 0.290 | -0.077 | 0.136 | 0.003 | 0.048 | 0.091 |
| | 30010 | 0.086 | 1.161 | -0.023 | 0.250 | 1.318 | -0.013 | -0.005 | -0.300 |
| | 30020 | 0.037 | 0.598 | 0.129 | -0.136 | 0.364 | 0.042 | -0.080 | -0.124 |
| | 40001 | 0.033 | 0.628 | -0.099 | -0.139 | 0.376 | -0.039 | 0.082 | -0.123 |
| | 40011 | 0.128 | 1.494 | -0.001 | 0.288 | 1.476 | 0.009 | 0.002 | -0.326 |
| 22 Exterior Wall @ EL4.65 ~6.60m | 22011 | -0.121 | 1.929 | -0.415 | 0.007 | -0.026 | -0.001 | 0.012 | -0.024 |
| | 22023 | -0.017 | 0.997 | 0.206 | 0.074 | 0.002 | 0.011 | -0.052 | -0.011 |
| | 32010 | 0.012 | 1.087 | -0.027 | -0.001 | -0.028 | -0.002 | 0.000 | 0.013 |
| | 32020 | 0.032 | 1.252 | 0.072 | 0.042 | 0.001 | 0.007 | 0.038 | 0.006 |
| | 42001 | 0.039 | 1.311 | 0.061 | 0.053 | 0.002 | -0.001 | -0.027 | 0.002 |
| | 42011 | 0.214 | 1.479 | 0.058 | -0.001 | -0.021 | 0.002 | -0.002 | 0.005 |
| 23 Exterior Wall @ EL22.50 ~24.60m | 24211 | 0.087 | 0.973 | -0.055 | 0.074 | 0.507 | -0.011 | 0.000 | 0.135 |
| | 24224 | 0.039 | 0.762 | -0.252 | -0.010 | 0.046 | 0.050 | 0.040 | 0.028 |
| | 34210 | 0.013 | 0.514 | -0.045 | -0.006 | -0.005 | 0.001 | -0.003 | -0.011 |
| | 34220 | -0.042 | 0.660 | 0.115 | -0.034 | 0.017 | 0.007 | -0.029 | -0.002 |
| | 44201 | -0.013 | 0.763 | 0.232 | -0.031 | 0.008 | -0.010 | 0.033 | 0.001 |
| 24 Basemat @ Wall Below RCCV | 90140 | -0.060 | 0.480 | 0.263 | 1.419 | 0.971 | -2.078 | 0.964 | -1.107 |
| | 90182 | 0.369 | 0.221 | 0.046 | -0.592 | 1.442 | 0.238 | -0.137 | -0.399 |
| | 90111 | 0.246 | 0.490 | -0.027 | 1.301 | -0.708 | 0.327 | -0.439 | -0.071 |
| 25 Slab EL4.65m @ RCCV | 93140 | -0.001 | -0.080 | -0.032 | -0.041 | -0.051 | 0.031 | -0.067 | 0.055 |
| | 93182 | -0.073 | -0.068 | -0.025 | -0.020 | -0.060 | -0.004 | 0.005 | 0.099 |
| | 93111 | -0.045 | -0.094 | 0.017 | -0.092 | -0.023 | -0.003 | 0.105 | 0.002 |
| 26 Slab EL17.5m @ RCCV | 96144 | 0.200 | -0.155 | -0.096 | -0.036 | -0.037 | 0.029 | -0.072 | 0.054 |
| | 96186 | -0.178 | 0.088 | 0.017 | 0.003 | 0.021 | -0.001 | 0.006 | 0.023 |
| | 96113 | 0.138 | -0.325 | 0.062 | 0.169 | -0.011 | -0.009 | -0.171 | -0.016 |
| 27 Slab EL27.0m @ RCCV | 98472 | -0.147 | 0.039 | -0.075 | -0.116 | -0.166 | 0.128 | -0.206 | 0.148 |
| | 98514 | 0.011 | -0.065 | -0.042 | -0.018 | -0.046 | -0.008 | -0.004 | 0.058 |
| | 98424 | -0.031 | -0.369 | 0.013 | -1.555 | -0.380 | -0.015 | 0.872 | 0.069 |
| 28 Pool Girder @ Storage Pool | 123004 | 0.536 | 3.574 | 1.280 | -0.034 | 0.052 | -0.025 | 0.001 | 0.018 |
| | 123104 | -0.664 | 1.245 | 0.734 | -0.024 | -0.002 | -0.018 | -0.017 | 0.015 |
| 29 Pool Girder @ Cavity | 123012 | -0.913 | -0.581 | -0.368 | 0.034 | 0.265 | -0.003 | 0.016 | 0.151 |
| | 123112 | 0.119 | -0.337 | -0.426 | 0.010 | 0.031 | -0.027 | -0.013 | 0.012 |
| 30 Pool Girder @ Fuel Pool | 123017 | 0.443 | 3.312 | -1.363 | -0.060 | 0.040 | 0.080 | 0.011 | 0.084 |
| | 123117 | -0.434 | 0.996 | -0.736 | -0.052 | -0.054 | 0.013 | 0.005 | -0.002 |
| 31 MS Tunnel Wall and Slab | 150122 | 0.174 | 0.081 | -0.517 | 0.007 | -0.016 | -0.011 | 0.016 | 0.034 |
| | 96611 | 0.036 | -0.192 | 0.026 | 0.028 | 0.132 | 0.058 | 0.115 | -0.007 |
| | 98614 | -0.008 | 0.058 | -0.023 | 0.013 | 0.311 | 0.032 | 0.089 | -0.010 |

Table 3G.1-22

Combined Forces and Moments: RCCV, Selected Load Combination CV-1

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---------------------------------|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 1 RPV Pedestal Bottom | 5006 | OTHR | -1.727 | -6.401 | -0.058 | 0.275 | 1.551 | 0.035 | -0.001 | 0.986 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 5013 | OTHR | -2.322 | -6.785 | 0.057 | 0.163 | 1.662 | -0.003 | -0.007 | 1.141 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 5024 | OTHR | -2.066 | -6.398 | 0.055 | 0.394 | 1.508 | -0.008 | 0.011 | 0.957 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 2 RPV Pedestal Mid-Height | 6006 | OTHR | 1.042 | -6.118 | 0.013 | -0.049 | -0.183 | 0.017 | 0.069 | -0.354 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 6013 | OTHR | 0.749 | -6.140 | 0.197 | -0.208 | -0.225 | 0.003 | -0.002 | -0.347 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 6024 | OTHR | 1.103 | -4.503 | -0.422 | 0.311 | 0.115 | 0.014 | -0.013 | -0.289 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 3 RPV Pedestal Top | 6606 | OTHR | 0.537 | -5.344 | 0.648 | 0.562 | 3.555 | -0.005 | 0.263 | -1.124 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 6613 | OTHR | 0.219 | -5.533 | 0.019 | 0.423 | 3.594 | -0.061 | -0.118 | -1.182 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 6624 | OTHR | 0.839 | -5.202 | 0.214 | 0.574 | 3.301 | 0.099 | 0.093 | -0.952 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 4 RCCV Wetwell Bottom | 1806 | OTHR | 0.376 | -1.977 | -0.056 | 0.321 | 1.958 | 0.019 | 0.008 | 0.712 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 1813 | OTHR | 0.091 | -2.467 | 0.175 | 0.326 | 2.120 | 0.000 | -0.005 | 0.840 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 1824 | OTHR | 0.586 | -2.541 | -0.008 | 0.318 | 1.823 | 0.007 | -0.005 | 0.743 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 5 RCCV Wetwell Mid-Height | 2606 | OTHR | 2.671 | -1.526 | -0.123 | -0.160 | -0.650 | 0.001 | 0.006 | -0.068 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 2613 | OTHR | 2.262 | -2.175 | 0.186 | -0.201 | -0.685 | 0.001 | -0.004 | -0.005 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 2624 | OTHR | 2.588 | -2.151 | -0.029 | -0.101 | -0.679 | -0.005 | 0.002 | -0.130 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 6 RCCV Wetwell Top | 3406 | OTHR | 2.479 | -0.900 | 0.042 | -0.024 | 0.015 | 0.020 | 0.015 | -0.073 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 3413 | OTHR | 2.098 | -1.977 | 0.166 | -0.100 | -0.158 | -0.079 | 0.034 | -0.017 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 3424 | OTHR | 1.934 | -1.509 | 0.034 | 0.093 | 0.438 | 0.009 | 0.021 | -0.162 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 7 RCCV Drywell Bottom | 3606 | OTHR | 2.464 | -0.495 | -0.076 | -0.032 | 0.012 | 0.048 | 0.026 | 0.488 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 3613 | OTHR | 2.145 | -1.537 | 0.273 | -0.029 | 0.252 | -0.050 | 0.000 | 0.686 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 3624 | OTHR | 1.927 | -1.314 | 0.050 | 0.126 | 0.621 | 0.007 | 0.024 | 0.627 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 8 RCCV Drywell Mid-Height | 4006 | OTHR | 1.797 | -0.169 | -0.028 | -0.107 | -0.416 | 0.010 | 0.026 | -0.244 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 4013 | OTHR | 1.725 | -1.830 | 0.414 | -0.148 | -0.514 | 0.004 | -0.011 | -0.266 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 4976 | OTHR | 1.561 | -0.735 | 0.079 | -0.013 | -0.177 | 0.006 | -0.009 | -0.323 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 9 RCCV Drywell Top | 4406 | OTHR | 0.600 | 0.050 | -0.062 | 0.320 | 1.699 | -0.026 | -0.037 | -0.632 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 4413 | OTHR | -0.150 | -2.122 | 0.294 | 0.254 | 2.000 | 0.041 | 0.006 | -0.780 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 4424 | OTHR | 1.057 | -0.281 | 0.049 | 0.350 | 1.987 | 0.022 | 0.001 | -0.669 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |

OTHR: Loads other than thermal loads

TEMP: Thermal loads

Table 3G.1-22
Combined Forces and Moments: RCCV, Selected Load Combination CV-1 (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 10 Basemat @ Center | 80003 | OTHR | -2.942 | -1.742 | 0.128 | 1.035 | 1.317 | -0.019 | 0.176 | -0.095 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 80007 | OTHR | -2.979 | -1.751 | 0.113 | 1.083 | 1.332 | -0.007 | 0.021 | -0.161 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 80012 | OTHR | -3.025 | -1.740 | 0.113 | 1.096 | 1.348 | -0.013 | -0.128 | -0.014 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 11 Basemat Inside RPV Pedestal | 80206 | OTHR | -2.658 | -1.873 | 0.186 | -0.915 | -0.674 | 0.704 | 0.992 | -1.016 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 80213 | OTHR | -2.772 | -1.755 | 0.088 | -0.043 | -1.330 | -0.070 | -0.054 | -1.384 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 80224 | OTHR | -3.233 | -2.037 | 0.057 | -1.239 | -0.088 | -0.116 | -1.256 | -0.120 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 12 S/P Slab @ RPV | 83306 | OTHR | -0.016 | 1.200 | -0.428 | 0.057 | 0.890 | -0.052 | 2.089 | -0.033 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 83313 | OTHR | 0.148 | 0.948 | -0.076 | 0.127 | 0.914 | 0.019 | 2.107 | 0.049 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 83324 | OTHR | 0.177 | 1.482 | 0.033 | 0.072 | 0.887 | -0.024 | 2.071 | -0.049 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 13 S/P Slab @ Center | 83406 | OTHR | 0.297 | 0.897 | -0.292 | -2.978 | -0.510 | -0.031 | -0.034 | 0.002 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 83413 | OTHR | 0.580 | 0.677 | -0.037 | -2.948 | -0.511 | -0.009 | -0.023 | 0.003 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 83424 | OTHR | 0.397 | 1.156 | 0.029 | -2.923 | -0.498 | 0.004 | -0.042 | 0.000 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 14 S/P Slab @ RCCV | 83506 | OTHR | 0.446 | 0.768 | -0.202 | 0.896 | -0.166 | -0.025 | -1.667 | 0.000 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 83513 | OTHR | 0.760 | 0.603 | -0.030 | 0.881 | -0.171 | -0.006 | -1.656 | 0.002 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 83524 | OTHR | 0.457 | 1.054 | 0.035 | 0.965 | -0.129 | -0.001 | -1.675 | 0.001 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 15 Top slab @ Drywell Head Opening | 98120 | OTHR | 0.289 | 0.934 | 0.507 | 0.182 | 0.098 | 0.082 | -0.038 | -0.136 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 98135 | OTHR | -0.376 | 0.222 | -0.244 | 0.270 | -0.292 | 0.091 | 0.140 | -0.226 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 98104 | OTHR | 0.355 | 1.944 | -0.425 | 0.191 | 1.348 | -0.108 | 0.152 | -0.343 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 16 Top slab @ Center | 98149 | OTHR | -0.016 | 1.283 | -0.200 | 0.274 | 0.041 | -0.105 | 0.118 | 0.334 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 98170 | OTHR | 0.182 | 0.921 | -0.259 | 0.464 | 0.782 | -0.039 | -0.057 | -0.116 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 98109 | OTHR | 0.646 | 1.371 | -0.090 | 1.101 | 1.409 | -0.049 | 0.053 | -0.212 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 17 Top slab @ RCCV | 98174 | OTHR | 0.444 | 1.149 | 0.002 | -0.116 | -0.028 | 0.344 | 0.276 | -0.270 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 98197 | OTHR | 0.282 | 1.209 | -0.228 | -0.210 | -1.380 | -0.091 | -0.076 | -1.076 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 98103 | OTHR | 0.929 | 1.495 | -0.078 | -0.537 | 0.462 | -0.264 | -0.766 | -0.207 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |

Table 3G.1-23

Combined Forces and Moments: RCCV, Selected Load Combination CV-7a

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---------------------------------|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 1 RPV Pedestal Bottom | 5006 | OTHR | -4.644 | -13.519 | 0.055 | 0.866 | 5.159 | 0.055 | -0.018 | 2.677 |
| | | TEMP | -4.914 | 1.511 | -0.308 | -6.365 | -4.559 | -0.052 | 0.107 | 1.915 |
| | 5013 | OTHR | -5.508 | -13.646 | 1.078 | 0.797 | 5.431 | 0.006 | -0.034 | 2.978 |
| | | TEMP | -4.492 | 1.682 | -0.086 | -6.538 | -4.972 | -0.006 | 0.026 | 1.799 |
| | 5024 | OTHR | -5.325 | -11.447 | 0.743 | 0.997 | 4.947 | -0.016 | 0.019 | 2.697 |
| | | TEMP | -4.788 | 1.835 | -0.003 | -6.598 | -4.346 | -0.034 | -0.030 | 1.882 |
| 2 RPV Pedestal Mid-Height | 6006 | OTHR | 1.057 | -14.746 | 0.283 | -0.129 | -0.301 | 0.048 | 0.125 | -0.487 |
| | | TEMP | 0.032 | 1.753 | 0.169 | -6.298 | -4.819 | 0.250 | 0.076 | -1.338 |
| | 6013 | OTHR | 0.521 | -13.532 | 1.230 | -0.331 | -0.501 | 0.002 | -0.019 | -0.465 |
| | | TEMP | -0.090 | 1.491 | -0.205 | -6.540 | -4.716 | -0.049 | -0.028 | -1.484 |
| | 6024 | OTHR | 0.643 | -7.415 | -0.030 | 0.246 | -0.397 | -0.005 | 0.020 | -0.290 |
| | | TEMP | -0.282 | 2.013 | 0.068 | -7.565 | -2.982 | -0.333 | 0.009 | -1.347 |
| 3 RPV Pedestal Top | 6606 | OTHR | 1.004 | -13.022 | 1.940 | 0.743 | 6.083 | 0.207 | 0.083 | -2.376 |
| | | TEMP | 13.800 | 1.993 | 0.458 | -6.972 | -5.243 | 0.061 | -1.094 | 0.930 |
| | 6613 | OTHR | 0.429 | -12.394 | 0.600 | 0.641 | 6.784 | -0.027 | 0.366 | -2.409 |
| | | TEMP | 14.040 | 1.756 | -0.439 | -6.980 | -5.204 | 0.051 | 1.161 | 0.871 |
| | 6624 | OTHR | 0.527 | -9.224 | 0.930 | 1.564 | 8.165 | 0.063 | 1.046 | -2.265 |
| | | TEMP | 14.663 | 2.298 | 0.204 | -6.952 | -5.291 | 0.078 | -1.430 | 1.061 |
| 4 RCCV Wetwell Bottom | 1806 | OTHR | 2.031 | -0.569 | -0.124 | 0.954 | 5.932 | 0.015 | 0.013 | 2.319 |
| | | TEMP | 1.751 | -0.007 | -0.297 | -4.421 | -7.805 | 0.062 | 0.058 | -1.566 |
| | 1813 | OTHR | 1.512 | -1.230 | 0.373 | 1.002 | 6.222 | 0.010 | -0.016 | 2.564 |
| | | TEMP | 1.093 | -2.329 | -0.367 | -4.202 | -7.396 | -0.025 | -0.007 | -1.331 |
| | 1824 | OTHR | 1.342 | -1.731 | 0.026 | 1.068 | 6.299 | 0.023 | -0.019 | 2.639 |
| | | TEMP | 1.981 | -2.824 | 0.082 | -4.322 | -7.438 | 0.022 | -0.082 | -1.354 |
| 5 RCCV Wetwell Mid-Height | 2606 | OTHR | 4.286 | -0.391 | -0.287 | -0.244 | -0.896 | -0.015 | 0.010 | -0.343 |
| | | TEMP | 1.184 | -0.011 | -0.269 | -3.358 | -1.133 | 0.021 | 0.034 | 0.033 |
| | 2613 | OTHR | 3.744 | -1.115 | 0.371 | -0.279 | -0.981 | 0.017 | -0.006 | -0.210 |
| | | TEMP | -0.038 | -2.791 | -0.063 | -3.081 | -1.119 | 0.008 | -0.077 | 0.390 |
| | 2624 | OTHR | 4.162 | -1.263 | 0.052 | -0.203 | -1.088 | -0.002 | 0.009 | -0.344 |
| | | TEMP | 1.079 | -3.158 | -0.043 | -3.384 | -1.119 | -0.022 | 0.071 | 0.377 |
| 6 RCCV Wetwell Top | 3406 | OTHR | 2.930 | 0.064 | -0.093 | -0.055 | -0.101 | 0.081 | -0.071 | 0.095 |
| | | TEMP | 11.624 | 0.596 | 0.226 | -4.154 | -8.398 | -0.221 | 0.439 | 3.322 |
| | 3413 | OTHR | 2.419 | -1.009 | 0.237 | -0.097 | -0.186 | -0.116 | 0.080 | 0.132 |
| | | TEMP | 7.954 | -3.660 | -0.047 | -4.357 | -9.124 | -0.396 | 0.519 | 3.323 |
| | 3424 | OTHR | 2.524 | -0.633 | 0.084 | 0.051 | 0.054 | 0.049 | -0.025 | 0.061 |
| | | TEMP | 11.052 | -4.630 | 0.371 | -3.786 | -5.604 | -0.046 | -0.058 | 2.298 |
| 7 RCCV Drywell Bottom | 3606 | OTHR | 2.808 | 0.553 | -0.221 | 0.025 | 0.372 | 0.106 | -0.029 | 0.585 |
| | | TEMP | 8.432 | 0.427 | 0.558 | -5.339 | -8.935 | 0.587 | 0.513 | -1.847 |
| | 3613 | OTHR | 2.328 | -0.650 | 0.245 | 0.077 | 0.812 | -0.089 | 0.026 | 0.859 |
| | | TEMP | 4.514 | -4.417 | 0.816 | -4.914 | -6.085 | -0.394 | 0.296 | -0.734 |
| | 3624 | OTHR | 2.331 | -0.626 | 0.115 | 0.259 | 1.214 | 0.060 | 0.005 | 0.804 |
| | | TEMP | -3.703 | -6.328 | 0.263 | -1.033 | -3.093 | 0.041 | -0.049 | 0.123 |
| 8 RCCV Drywell Mid-Height | 4006 | OTHR | 1.952 | 0.830 | -0.142 | -0.086 | -0.272 | 0.018 | 0.039 | -0.224 |
| | | TEMP | 5.852 | 0.754 | -0.011 | -5.144 | -5.509 | 0.007 | -0.183 | -0.528 |
| | 4013 | OTHR | 1.881 | -0.739 | 0.380 | -0.134 | -0.437 | 0.006 | -0.009 | -0.177 |
| | | TEMP | 4.218 | -5.936 | 0.807 | -4.699 | -4.400 | 0.008 | -0.150 | -0.234 |
| | 4976 | OTHR | 1.786 | -0.082 | 0.086 | 0.021 | -0.162 | 0.014 | -0.014 | -0.236 |
| | | TEMP | -3.420 | -5.654 | 0.772 | -0.840 | -1.477 | -0.001 | 0.007 | -0.863 |
| 9 RCCV Drywell Top | 4406 | OTHR | 0.752 | 1.281 | 0.157 | 0.294 | 1.729 | -0.015 | -0.015 | -0.555 |
| | | TEMP | 3.417 | -0.742 | -1.786 | -4.287 | -4.604 | 0.344 | -0.208 | -0.354 |
| | 4413 | OTHR | 0.391 | -0.865 | 0.386 | 0.227 | 1.835 | 0.053 | 0.017 | -0.701 |
| | | TEMP | 0.498 | -6.550 | -0.446 | -4.823 | -4.853 | 0.289 | -0.224 | 0.725 |
| | 4424 | OTHR | 1.218 | 0.280 | 0.064 | 0.330 | 1.809 | 0.025 | 0.004 | -0.594 |
| | | TEMP | -7.055 | -4.082 | 0.940 | -0.023 | 2.580 | -0.017 | -0.012 | -1.978 |

Table 3G.1-23
Combined Forces and Moments: RCCV, Selected Load Combination CV-7a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 10 Basemat @ Center | 80003 | OTHR | -0.773 | 0.281 | 0.108 | -1.804 | -1.242 | 0.027 | 0.518 | -0.397 |
| | | TEMP | -3.832 | -4.439 | 0.007 | -4.240 | -4.238 | -0.016 | 0.032 | -0.015 |
| | 80007 | OTHR | -0.806 | 0.221 | 0.061 | -1.623 | -1.205 | 0.054 | 0.227 | -0.530 |
| | | TEMP | -3.849 | -4.408 | 0.035 | -4.214 | -4.235 | -0.013 | 0.025 | -0.019 |
| | 80012 | OTHR | -0.905 | 0.143 | 0.083 | -1.419 | -1.004 | -0.052 | -0.087 | -0.244 |
| | | TEMP | -3.854 | -4.352 | 0.023 | -4.203 | -4.237 | -0.013 | 0.012 | -0.004 |
| 11 Basemat Inside RPV Pedestal | 80206 | OTHR | -0.178 | 0.420 | 0.284 | -6.537 | -5.863 | 1.949 | 2.035 | -2.023 |
| | | TEMP | -3.802 | -4.758 | 0.110 | -4.600 | -4.678 | 0.084 | 0.016 | -0.101 |
| | 80213 | OTHR | -0.406 | 0.319 | 0.136 | -4.092 | -7.447 | 0.618 | 0.611 | -2.696 |
| | | TEMP | -3.949 | -4.381 | 0.094 | -4.421 | -4.763 | -0.049 | 0.006 | -0.146 |
| | 80224 | OTHR | -1.192 | -0.577 | -0.012 | -4.808 | -3.505 | -0.805 | -1.804 | -0.791 |
| | | TEMP | -3.875 | -4.291 | 0.046 | -4.364 | -4.386 | -0.020 | -0.043 | 0.010 |
| 12 S/P Slab @ RPV | 83306 | OTHR | -0.141 | 2.867 | -0.564 | -1.806 | 1.160 | -0.137 | 5.281 | -0.079 |
| | | TEMP | -8.430 | 8.012 | 0.027 | -4.417 | -2.896 | 0.015 | -0.248 | 0.001 |
| | 83313 | OTHR | 0.530 | 2.519 | -0.868 | -1.716 | 1.267 | -0.150 | 5.316 | 0.073 |
| | | TEMP | -8.845 | 8.448 | -0.275 | -4.426 | -2.958 | -0.032 | -0.239 | -0.022 |
| | 83324 | OTHR | 2.400 | 2.791 | -0.695 | -1.441 | 1.649 | -0.199 | 5.500 | -0.096 |
| | | TEMP | -8.617 | 8.870 | 0.723 | -4.216 | -2.783 | 0.001 | -0.123 | 0.042 |
| 13 S/P Slab @ Center | 83406 | OTHR | 0.512 | 2.595 | -0.494 | -8.310 | -2.323 | -0.048 | -0.584 | -0.001 |
| | | TEMP | -4.716 | 3.300 | -0.435 | -3.598 | -3.189 | -0.006 | -0.274 | 0.009 |
| | 83413 | OTHR | 1.326 | 2.246 | -0.358 | -8.313 | -2.272 | -0.109 | -0.555 | 0.004 |
| | | TEMP | -5.529 | 3.887 | 0.330 | -3.708 | -3.266 | -0.014 | -0.232 | -0.007 |
| | 83424 | OTHR | 2.466 | 2.307 | -0.300 | -8.353 | -2.065 | -0.091 | -0.493 | 0.004 |
| | | TEMP | -5.039 | 4.216 | 0.041 | -3.677 | -3.155 | -0.002 | -0.184 | 0.007 |
| 14 S/P Slab @ RCCV | 83506 | OTHR | 1.040 | 2.443 | -0.329 | 4.067 | -0.651 | -0.038 | -5.138 | -0.006 |
| | | TEMP | -2.707 | 1.467 | -0.274 | -2.852 | -3.128 | -0.032 | -0.252 | 0.010 |
| | 83513 | OTHR | 1.721 | 2.169 | -0.246 | 3.982 | -0.624 | -0.044 | -5.120 | -0.007 |
| | | TEMP | -3.724 | 1.594 | 0.393 | -3.192 | -3.182 | -0.007 | -0.152 | 0.000 |
| | 83524 | OTHR | 2.395 | 2.144 | -0.248 | 3.825 | -0.543 | -0.033 | -5.076 | -0.007 |
| | | TEMP | -3.075 | 2.237 | -0.023 | -3.204 | -3.140 | 0.013 | -0.148 | -0.004 |
| 15 Top slab @ Drywell Head Opening | 98120 | OTHR | 0.486 | 1.002 | 0.633 | 0.180 | 0.107 | 0.087 | -0.035 | -0.141 |
| | | TEMP | -7.704 | -4.732 | -1.166 | 0.747 | 0.629 | 2.583 | -0.150 | 0.074 |
| | 98135 | OTHR | -0.280 | 0.222 | -0.209 | 0.278 | -0.345 | 0.107 | 0.166 | -0.268 |
| | | TEMP | -10.062 | -5.610 | 0.556 | 3.094 | -2.008 | -1.221 | 0.306 | -0.222 |
| | 98104 | OTHR | 0.348 | 1.803 | -0.413 | 0.201 | 1.422 | -0.112 | 0.163 | -0.402 |
| | | TEMP | -5.268 | -2.661 | 0.786 | -1.577 | 3.078 | -1.390 | 0.146 | -0.201 |
| 16 Top slab @ Center | 98149 | OTHR | 0.254 | 1.491 | -0.297 | 0.327 | 0.180 | -0.114 | 0.114 | 0.297 |
| | | TEMP | -6.420 | -3.274 | -0.448 | 1.814 | 2.130 | 0.346 | 0.136 | 0.106 |
| | 98170 | OTHR | 0.374 | 1.219 | -0.207 | 0.546 | 0.948 | -0.015 | -0.019 | -0.052 |
| | | TEMP | -6.246 | -3.905 | -0.324 | 2.174 | 3.114 | -0.038 | 0.113 | 0.455 |
| | 98109 | OTHR | 0.643 | 1.367 | -0.077 | 1.239 | 1.482 | -0.069 | 0.054 | -0.223 |
| | | TEMP | -6.252 | -2.427 | 0.725 | 1.007 | 2.226 | 0.038 | 0.380 | -0.086 |
| 17 Top slab @ RCCV | 98174 | OTHR | 0.854 | 1.359 | -0.046 | -0.023 | 0.173 | 0.346 | 0.250 | -0.221 |
| | | TEMP | -5.257 | -4.725 | 1.957 | 2.429 | 2.294 | 0.439 | -0.175 | -0.031 |
| | 98197 | OTHR | 0.732 | 1.442 | -0.094 | -0.151 | -1.669 | -0.070 | -0.078 | -1.093 |
| | | TEMP | -7.993 | -3.381 | -0.911 | 1.891 | 2.951 | 0.273 | 0.139 | -0.592 |
| | 98103 | OTHR | 0.936 | 1.552 | -0.065 | -0.896 | 0.331 | -0.306 | -0.957 | -0.234 |
| | | TEMP | -6.656 | -4.117 | 0.218 | 4.494 | 3.771 | 0.226 | 1.080 | 0.001 |

Table 3G.1-24

Combined Forces and Moments: RCCV, Selected Load Combination CV-7b

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---------------------------------|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 1 RPV Pedestal Bottom | 5006 | OTHR | -4.379 | -12.330 | 0.043 | 0.860 | 5.118 | 0.053 | -0.014 | 2.626 |
| | | TEMP | -13.947 | 0.161 | -0.486 | -15.740 | -11.087 | -0.102 | 0.226 | 4.880 |
| | 5013 | OTHR | -5.160 | -12.289 | 1.016 | 0.774 | 5.297 | 0.006 | -0.029 | 2.880 |
| | | TEMP | -13.372 | 0.271 | -0.086 | -16.029 | -11.713 | -0.007 | 0.019 | 4.752 |
| | 5024 | OTHR | -4.841 | -10.006 | 0.735 | 0.966 | 4.729 | -0.015 | 0.018 | 2.553 |
| | | TEMP | -13.919 | 0.215 | 0.002 | -16.061 | -10.406 | -0.078 | -0.046 | 4.926 |
| 2 RPV Pedestal Mid-Height | 6006 | OTHR | 1.513 | -13.440 | 0.200 | -0.125 | -0.259 | 0.041 | 0.117 | -0.498 |
| | | TEMP | -2.483 | 0.613 | 0.460 | -16.186 | -15.497 | 0.425 | 0.153 | -1.652 |
| | 6013 | OTHR | 0.987 | -12.192 | 1.138 | -0.318 | -0.450 | -0.001 | -0.012 | -0.480 |
| | | TEMP | -2.675 | 0.292 | -0.222 | -16.668 | -15.409 | -0.043 | -0.034 | -1.882 |
| | 6024 | OTHR | 1.163 | -6.325 | 0.046 | 0.280 | -0.321 | -0.006 | 0.008 | -0.313 |
| | | TEMP | -2.798 | 0.648 | 0.087 | -18.667 | -11.882 | -0.682 | 0.031 | -1.562 |
| 3 RPV Pedestal Top | 6606 | OTHR | 1.298 | -11.837 | 1.781 | 0.583 | 5.020 | 0.171 | 0.064 | -1.986 |
| | | TEMP | 3.459 | 0.568 | 0.467 | -16.412 | -12.055 | 0.121 | -0.772 | -1.957 |
| | 6613 | OTHR | 0.687 | -11.202 | 0.597 | 0.490 | 5.759 | 0.013 | 0.383 | -2.036 |
| | | TEMP | 4.014 | 0.624 | -0.376 | -16.392 | -12.231 | -0.024 | 0.838 | -1.943 |
| | 6624 | OTHR | 0.792 | -8.006 | 0.864 | 1.422 | 7.146 | 0.022 | 1.031 | -1.894 |
| | | TEMP | 4.131 | 0.639 | 0.234 | -16.379 | -12.033 | 0.102 | -1.077 | -1.799 |
| 4 RCCV Wetwell Bottom | 1806 | OTHR | 1.953 | -0.245 | -0.155 | 0.846 | 5.275 | 0.015 | 0.013 | 1.980 |
| | | TEMP | -2.089 | -1.627 | -0.394 | -10.252 | -14.421 | 0.073 | 0.070 | -1.432 |
| | 1813 | OTHR | 1.415 | -0.964 | 0.297 | 0.889 | 5.565 | 0.010 | -0.016 | 2.222 |
| | | TEMP | -2.608 | -4.438 | -0.288 | -9.980 | -13.822 | -0.044 | -0.007 | -1.104 |
| | 1824 | OTHR | 1.258 | -1.275 | 0.011 | 0.951 | 5.584 | 0.023 | -0.017 | 2.282 |
| | | TEMP | -1.725 | -4.483 | 0.172 | -10.129 | -13.767 | 0.031 | -0.103 | -1.054 |
| 5 RCCV Wetwell Mid-Height | 2606 | OTHR | 4.605 | 0.008 | -0.310 | -0.263 | -0.990 | -0.011 | 0.010 | -0.248 |
| | | TEMP | -4.378 | -2.154 | -0.405 | -9.998 | -7.615 | 0.005 | 0.039 | 0.073 |
| | 2613 | OTHR | 4.013 | -0.833 | 0.315 | -0.304 | -1.067 | 0.014 | -0.005 | -0.133 |
| | | TEMP | -5.309 | -5.586 | 0.063 | -9.714 | -7.480 | -0.018 | -0.096 | 0.442 |
| | 2624 | OTHR | 4.409 | -0.850 | 0.039 | -0.208 | -1.172 | -0.001 | 0.009 | -0.281 |
| | | TEMP | -4.767 | -5.072 | -0.072 | -10.108 | -7.790 | -0.038 | 0.082 | 0.381 |
| 6 RCCV Wetwell Top | 3406 | OTHR | 3.492 | 0.530 | -0.117 | -0.055 | -0.085 | 0.053 | -0.040 | 0.041 |
| | | TEMP | 5.146 | -1.793 | 0.374 | -10.845 | -13.921 | 0.028 | 0.122 | 2.434 |
| | 3413 | OTHR | 2.903 | -0.723 | 0.224 | -0.110 | -0.145 | -0.094 | 0.064 | 0.062 |
| | | TEMP | 3.360 | -7.377 | 0.327 | -10.754 | -14.083 | -0.105 | 0.111 | 2.634 |
| | 3424 | OTHR | 2.884 | -0.187 | 0.074 | 0.088 | 0.313 | 0.019 | 0.001 | -0.073 |
| | | TEMP | 3.550 | -6.962 | 0.378 | -10.104 | -10.258 | 0.043 | -0.160 | 1.032 |
| 7 RCCV Drywell Bottom | 3606 | OTHR | 3.353 | 0.954 | -0.249 | -0.001 | 0.241 | 0.086 | -0.012 | 0.643 |
| | | TEMP | 0.855 | -1.873 | -0.034 | -12.684 | -14.715 | 0.245 | 0.161 | -0.543 |
| | 3613 | OTHR | 2.819 | -0.386 | 0.280 | 0.022 | 0.625 | -0.058 | 0.024 | 0.912 |
| | | TEMP | -1.019 | -8.771 | 1.274 | -12.290 | -13.057 | -0.280 | 0.001 | -0.234 |
| | 3624 | OTHR | 2.736 | -0.116 | 0.086 | 0.221 | 1.041 | 0.029 | 0.015 | 0.853 |
| | | TEMP | -10.073 | -8.472 | 0.316 | -7.314 | -7.358 | 0.070 | -0.111 | 1.306 |
| 8 RCCV Drywell Mid-Height | 4006 | OTHR | 2.267 | 1.274 | -0.137 | -0.084 | -0.330 | 0.026 | 0.037 | -0.332 |
| | | TEMP | 1.877 | -1.562 | -0.442 | -12.483 | -13.207 | 0.139 | -0.296 | -0.380 |
| | 4013 | OTHR | 2.186 | -0.572 | 0.418 | -0.168 | -0.500 | 0.005 | -0.010 | -0.300 |
| | | TEMP | 1.214 | -10.590 | 1.149 | -12.238 | -11.748 | 0.051 | -0.198 | -0.348 |
| | 4976 | OTHR | 2.118 | 0.395 | 0.064 | 0.006 | -0.173 | 0.013 | -0.013 | -0.380 |
| | | TEMP | -8.101 | -7.344 | 0.924 | -7.622 | -8.430 | 0.004 | 0.035 | -0.545 |
| 9 RCCV Drywell Top | 4406 | OTHR | 0.871 | 1.786 | 0.269 | 0.443 | 2.438 | -0.018 | -0.031 | -0.802 |
| | | TEMP | 0.823 | -3.764 | -3.737 | -11.621 | -12.462 | 0.691 | -0.182 | -0.529 |
| | 4413 | OTHR | 0.343 | -0.786 | 0.398 | 0.336 | 2.583 | 0.059 | 0.019 | -0.956 |
| | | TEMP | -1.109 | -11.745 | -0.412 | -12.243 | -11.597 | 0.480 | -0.143 | 0.316 |
| | 4424 | OTHR | 1.407 | 0.702 | 0.042 | 0.439 | 2.498 | 0.028 | 0.002 | -0.817 |
| | | TEMP | -11.976 | -5.333 | 1.168 | -6.791 | -4.544 | -0.050 | -0.027 | -2.329 |

Table 3G.1-24
Combined Forces and Moments: RCCV, Selected Load Combination CV-7b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 10 Basemat @ Center | 80003 | OTHR | -0.964 | 0.150 | 0.109 | -2.152 | -1.630 | 0.027 | 0.441 | -0.333 |
| | | TEMP | -1.459 | -2.034 | -0.010 | -4.165 | -4.332 | -0.019 | 0.027 | -0.018 |
| | 80007 | OTHR | -0.996 | 0.094 | 0.064 | -1.971 | -1.593 | 0.054 | 0.243 | -0.428 |
| | | TEMP | -1.464 | -1.995 | 0.022 | -4.146 | -4.332 | -0.017 | 0.015 | -0.025 |
| | 80012 | OTHR | -1.094 | 0.024 | 0.085 | -1.764 | -1.390 | -0.053 | 0.018 | -0.231 |
| | | TEMP | -1.470 | -1.929 | 0.013 | -4.141 | -4.342 | -0.014 | -0.003 | -0.003 |
| 11 Basemat Inside RPV Pedestal | 80206 | OTHR | -0.385 | 0.271 | 0.271 | -5.936 | -5.329 | 1.634 | 1.735 | -1.730 |
| | | TEMP | -1.452 | -2.440 | 0.102 | -4.566 | -4.902 | 0.112 | -0.003 | -0.132 |
| | 80213 | OTHR | -0.598 | 0.190 | 0.128 | -3.790 | -6.506 | 0.653 | 0.633 | -2.255 |
| | | TEMP | -1.560 | -1.931 | 0.037 | -4.415 | -4.996 | -0.075 | -0.008 | -0.208 |
| | 80224 | OTHR | -1.382 | -0.647 | -0.009 | -3.875 | -3.196 | -0.766 | -1.377 | -0.757 |
| | | TEMP | -1.413 | -1.845 | 0.033 | -4.392 | -4.556 | -0.029 | -0.087 | 0.015 |
| 12 S/P Slab @ RPV | 83306 | OTHR | -0.423 | 2.679 | -0.507 | -1.751 | 0.861 | -0.136 | 4.470 | -0.071 |
| | | TEMP | -9.972 | 1.598 | -0.064 | -9.481 | -8.299 | 0.020 | -0.052 | -0.031 |
| | 83313 | OTHR | 0.214 | 2.311 | -0.858 | -1.645 | 0.976 | -0.160 | 4.511 | 0.068 |
| | | TEMP | -10.412 | 2.279 | 0.020 | -9.487 | -8.358 | -0.018 | -0.032 | 0.009 |
| | 83324 | OTHR | 2.069 | 2.575 | -0.690 | -1.346 | 1.374 | -0.194 | 4.707 | -0.088 |
| | | TEMP | -10.086 | 2.442 | 0.535 | -9.394 | -8.241 | -0.004 | 0.012 | 0.009 |
| 13 S/P Slab @ Center | 83406 | OTHR | 0.234 | 2.390 | -0.451 | -7.113 | -2.072 | -0.046 | -0.561 | -0.001 |
| | | TEMP | -6.718 | -1.759 | -0.385 | -8.944 | -8.523 | -0.007 | -0.094 | 0.009 |
| | 83413 | OTHR | 1.030 | 2.018 | -0.369 | -7.117 | -2.019 | -0.112 | -0.528 | 0.004 |
| | | TEMP | -7.659 | -0.903 | 0.493 | -9.069 | -8.607 | -0.009 | -0.043 | -0.004 |
| | 83424 | OTHR | 2.142 | 2.067 | -0.296 | -7.168 | -1.806 | -0.091 | -0.458 | 0.004 |
| | | TEMP | -6.972 | -0.779 | -0.021 | -9.008 | -8.518 | 0.002 | -0.039 | 0.004 |
| 14 S/P Slab @ RCCV | 83506 | OTHR | 0.755 | 2.233 | -0.297 | 3.728 | -0.545 | -0.035 | -4.482 | -0.006 |
| | | TEMP | -5.228 | -3.030 | -0.183 | -8.795 | -8.644 | -0.044 | -0.124 | 0.014 |
| | 83513 | OTHR | 1.437 | 1.939 | -0.269 | 3.635 | -0.526 | -0.043 | -4.460 | -0.008 |
| | | TEMP | -6.407 | -2.664 | 0.563 | -9.202 | -8.697 | -0.010 | 0.002 | 0.004 |
| | 83524 | OTHR | 2.073 | 1.895 | -0.242 | 3.442 | -0.449 | -0.034 | -4.410 | -0.007 |
| | | TEMP | -5.481 | -2.152 | -0.087 | -9.085 | -8.636 | 0.017 | -0.037 | -0.005 |
| 15 Top slab @ Drywell Head Opening | 98120 | OTHR | 0.279 | 1.159 | 0.645 | 0.338 | 0.195 | 0.188 | -0.057 | -0.238 |
| | | TEMP | -12.118 | -11.183 | -5.512 | 6.841 | 6.030 | 5.411 | -0.811 | -0.398 |
| | 98135 | OTHR | -1.032 | 0.220 | -0.215 | 0.497 | -0.469 | 0.105 | 0.217 | -0.398 |
| | | TEMP | -17.422 | -7.219 | 2.697 | 11.170 | 0.342 | -2.394 | 0.848 | -0.819 |
| | 98104 | OTHR | 0.413 | 2.149 | -0.492 | 0.297 | 2.026 | -0.202 | 0.198 | -0.541 |
| | | TEMP | -6.925 | -12.999 | 2.994 | 2.265 | 12.026 | -3.290 | 0.606 | -0.472 |
| 16 Top slab @ Center | 98149 | OTHR | -0.144 | 1.862 | -0.422 | 0.541 | 0.283 | -0.139 | 0.156 | 0.416 |
| | | TEMP | -11.284 | -4.069 | -0.857 | 4.361 | 5.925 | 0.936 | 0.661 | -1.018 |
| | 98170 | OTHR | 0.103 | 1.440 | -0.279 | 0.828 | 1.367 | -0.031 | -0.030 | -0.071 |
| | | TEMP | -10.473 | -4.943 | 0.330 | 4.246 | 5.164 | -0.051 | 0.133 | 0.663 |
| | 98109 | OTHR | 0.742 | 1.574 | -0.094 | 1.661 | 2.003 | -0.112 | 0.048 | -0.283 |
| | | TEMP | -6.965 | -3.863 | 0.571 | 8.864 | 11.344 | -0.270 | 0.605 | -0.017 |
| 17 Top slab @ RCCV | 98174 | OTHR | 0.724 | 1.682 | -0.035 | 0.014 | 0.277 | 0.506 | 0.369 | -0.313 |
| | | TEMP | -8.731 | -7.669 | 2.634 | 5.537 | 4.434 | 0.957 | -0.904 | -0.184 |
| | 98197 | OTHR | 0.673 | 1.737 | -0.135 | -0.131 | -2.224 | -0.116 | -0.109 | -1.502 |
| | | TEMP | -12.156 | -5.258 | -1.159 | 4.205 | 6.099 | 0.531 | 0.320 | -0.561 |
| | 98103 | OTHR | 1.158 | 1.791 | -0.098 | -1.409 | 0.394 | -0.409 | -1.333 | -0.304 |
| | | TEMP | -6.757 | -8.103 | 0.104 | 13.587 | 13.101 | 0.388 | 1.276 | 0.008 |

Table 3G.1-25

Combined Forces and Moments: RCCV, Selected Load Combination CV-11a

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|-----------------------------|---------------------------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 1 RPV Pedestal Bottom | 5006 | OTHR | -3.434 | -11.709 | 0.057 | 0.564 | 3.351 | 0.046 | -0.015 | 1.830 | |
| | | TEMP | -4.914 | 1.511 | -0.308 | -6.365 | -4.559 | -0.052 | 0.107 | 1.915 | |
| | | EQEW | 3.824 | 6.562 | -1.902 | -0.846 | -4.326 | -0.053 | 0.250 | -1.867 | |
| | | EQNS | -3.659 | -4.291 | -0.463 | 0.933 | 5.377 | 0.046 | 0.061 | 2.277 | |
| | | EQZ | -1.459 | 1.504 | -0.109 | 0.369 | 2.146 | -0.005 | 0.011 | 0.951 | |
| | | EQT | 0.352 | 0.155 | 0.243 | 0.016 | -0.150 | -0.018 | 0.037 | -0.097 | |
| | | SPKW | -0.240 | 0.042 | 0.193 | -0.019 | 0.016 | -0.041 | 0.021 | 0.066 | |
| | | SPKN | -0.242 | -0.059 | -0.226 | 0.042 | 0.132 | 0.035 | -0.009 | 0.105 | |
| | 5013 | OTHR | -4.216 | -11.815 | 1.058 | 0.493 | 3.584 | 0.007 | -0.030 | 2.092 | |
| | | TEMP | -4.492 | 1.682 | -0.086 | -6.538 | -4.972 | -0.006 | 0.026 | 1.799 | |
| | | EQEW | 5.429 | 10.427 | 0.215 | -1.323 | -6.638 | -0.002 | 0.012 | -2.984 | |
| | | EQNS | -0.845 | 1.502 | -0.434 | 0.377 | 2.323 | -0.013 | 0.130 | 0.940 | |
| | | EQZ | -1.245 | 1.957 | -0.167 | 0.325 | 1.935 | -0.001 | 0.012 | 0.845 | |
| | | EQT | 0.259 | 0.237 | 0.247 | -0.078 | -0.282 | -0.014 | 0.037 | -0.146 | |
| | | SPKW | 0.259 | 0.275 | 0.011 | 0.155 | -0.148 | 0.005 | -0.002 | -0.077 | |
| | | SPKN | -0.678 | -0.176 | -0.094 | -0.153 | 0.170 | -0.007 | 0.012 | 0.192 | |
| | | 5024 | OTHR | -3.969 | -9.719 | 0.725 | 0.668 | 3.119 | -0.008 | 0.012 | 1.841 |
| | | | TEMP | -4.788 | 1.835 | -0.003 | -6.598 | -4.346 | -0.034 | -0.030 | 1.882 |
| | EQEW | | 0.453 | 0.627 | 3.241 | -0.093 | -0.436 | 0.007 | -0.264 | -0.196 | |
| | EQNS | | 2.083 | 7.762 | -0.043 | -0.392 | -1.472 | -0.004 | 0.013 | -0.778 | |
| | EQZ | | -0.986 | 2.190 | -0.014 | 0.309 | 1.777 | -0.007 | -0.003 | 0.773 | |
| | EQT | | 0.016 | 0.008 | 0.419 | -0.009 | -0.021 | -0.013 | 0.008 | -0.007 | |
| | SPKW | | -0.626 | -0.190 | -0.019 | -0.147 | 0.198 | 0.005 | -0.002 | 0.192 | |
| | SPKN | | 0.351 | 0.334 | -0.006 | 0.143 | -0.266 | -0.001 | -0.004 | -0.125 | |
| | 2 RPV Pedestal Mid-Height | 6006 | OTHR | 0.612 | -12.872 | 0.298 | -0.090 | -0.124 | 0.046 | 0.111 | -0.386 |
| | | | TEMP | 0.032 | 1.753 | 0.169 | -6.298 | -4.819 | 0.250 | 0.076 | -1.338 |
| | | | EQEW | -0.307 | 2.620 | -3.688 | 0.070 | 0.312 | -0.267 | 0.010 | -0.094 |
| EQNS | | | 0.421 | -2.493 | -1.016 | -0.148 | -0.141 | 0.015 | 0.118 | 0.098 | |
| EQZ | | | 0.062 | 1.529 | -0.161 | -0.022 | -0.079 | -0.020 | -0.017 | -0.006 | |
| EQT | | | -0.016 | 0.005 | 0.132 | 0.025 | 0.027 | -0.038 | -0.007 | -0.009 | |
| SPKW | | | -0.450 | 0.080 | -0.232 | -0.054 | 0.044 | -0.055 | -0.159 | -0.084 | |
| SPKN | | | -0.183 | 0.071 | 0.166 | -0.016 | -0.010 | 0.041 | 0.124 | -0.042 | |
| 6013 | | OTHR | 0.109 | -11.709 | 1.191 | -0.285 | -0.311 | 0.002 | -0.015 | -0.364 | |
| | | TEMP | -0.090 | 1.491 | -0.205 | -6.540 | -4.716 | -0.049 | -0.028 | -1.484 | |
| | | EQEW | -0.916 | 4.064 | 0.457 | 0.189 | 0.314 | -0.026 | 0.009 | -0.303 | |
| | | EQNS | -0.364 | 1.437 | -1.767 | -0.345 | -0.186 | -0.111 | -0.049 | 0.004 | |
| | | EQZ | 0.066 | 1.672 | -0.252 | 0.007 | -0.047 | -0.008 | 0.010 | -0.040 | |
| | | EQT | -0.032 | -0.006 | 0.321 | 0.014 | 0.040 | -0.039 | 0.001 | -0.016 | |
| | | SPKW | 0.044 | 0.014 | 0.072 | 0.513 | 0.287 | 0.014 | 0.041 | -0.206 | |
| | | SPKN | -0.608 | 0.082 | -0.139 | -0.423 | -0.127 | -0.019 | -0.025 | -0.009 | |
| | | 6024 | OTHR | 0.156 | -6.104 | 0.084 | 0.247 | -0.254 | -0.004 | 0.021 | -0.253 |
| | | | TEMP | -0.282 | 2.013 | 0.068 | -7.565 | -2.982 | -0.333 | 0.009 | -1.347 |
| EQEW | | | -0.203 | 1.547 | 6.461 | 0.032 | 0.048 | 0.415 | 0.220 | 0.041 | |
| EQNS | | | -0.380 | 3.898 | 0.316 | 0.367 | 0.224 | -0.039 | -0.049 | -0.258 | |
| EQZ | | | -0.043 | 1.267 | 0.131 | -0.001 | 0.014 | -0.008 | -0.011 | -0.062 | |
| EQT | | | -0.022 | 0.111 | 0.592 | -0.008 | 0.000 | 0.002 | 0.011 | 0.001 | |
| SPKW | | | -0.606 | 0.083 | 0.037 | -0.450 | -0.108 | -0.003 | 0.024 | -0.028 | |
| SPKN | | | -0.161 | -0.122 | -0.033 | 0.542 | 0.381 | 0.002 | -0.026 | -0.221 | |

OTHR: Loads other than thermal and seismic loads

TEMP: Thermal loads

EQEW: Horizontal seismic loads in the E-W direction

EQNS: Horizontal seismic loads in the N-S direction

EQZ: Vertical seismic loads

EQT: Torsional seismic loads

SPKW: Dynamic soil pressure during a horizontal earthquake in the E-W direction

SPKN: Dynamic soil pressure during a horizontal earthquake in the N-S direction

**Table 3G.1-25
Combined Forces and Moments: RCCV, Selected Load Combination CV-11a (Continued)**

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|--------------------------|-----------------------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 3 RPV Pedestal Top | 6606 | OTHR | 0.672 | -11.114 | 1.790 | 0.534 | 4.773 | 0.233 | -0.007 | -2.046 | |
| | | TEMP | 13.800 | 1.993 | 0.458 | -6.972 | -5.243 | 0.061 | -1.094 | 0.930 | |
| | | EQEW | -1.238 | 0.118 | -2.973 | 0.335 | 1.594 | 0.093 | -0.028 | -0.657 | |
| | | EQNS | -0.120 | -1.156 | -0.164 | -0.406 | -3.016 | -0.196 | 0.727 | 0.863 | |
| | | EQZ | 0.166 | 1.067 | -0.306 | -0.247 | -1.746 | -0.099 | -0.047 | 0.631 | |
| | | EQT | -0.059 | -0.050 | 0.201 | -0.007 | 0.087 | -0.021 | -0.045 | -0.029 | |
| | | SPKW | -0.704 | 0.033 | -0.392 | -0.092 | 0.025 | 0.224 | -0.499 | -0.135 | |
| | | SPKN | -0.339 | 0.062 | 0.323 | 0.044 | 0.014 | -0.210 | 0.435 | -0.110 | |
| | 6613 | OTHR | 0.131 | -10.445 | 0.659 | 0.447 | 5.457 | -0.046 | 0.447 | -2.069 | |
| | | TEMP | 14.040 | 1.756 | -0.439 | -6.980 | -5.204 | 0.051 | 1.161 | 0.871 | |
| | | EQEW | -1.347 | 0.069 | 0.314 | 0.642 | 2.502 | 0.025 | -0.155 | -0.972 | |
| | | EQNS | -1.375 | 1.345 | -1.301 | -0.577 | -1.769 | 0.318 | -0.089 | 0.297 | |
| | | EQZ | 0.176 | 1.114 | -0.128 | -0.210 | -1.696 | 0.113 | 0.019 | 0.609 | |
| | | EQT | -0.001 | -0.104 | 0.278 | 0.051 | 0.156 | -0.040 | -0.042 | -0.050 | |
| | | SPKW | 0.387 | -0.006 | -0.005 | 0.292 | 0.015 | -0.028 | 0.061 | 0.003 | |
| | | SPKN | -1.150 | 0.087 | 0.014 | -0.244 | 0.011 | 0.045 | -0.060 | -0.228 | |
| | 6624 | OTHR | 0.178 | -7.358 | 0.861 | 1.366 | 6.913 | 0.077 | 0.971 | -1.959 | |
| | | TEMP | 14.663 | 2.298 | 0.204 | -6.952 | -5.291 | 0.078 | -1.430 | 1.061 | |
| | | EQEW | -0.190 | 0.065 | 4.374 | -0.010 | 0.231 | -0.176 | 0.137 | -0.087 | |
| | | EQNS | 0.293 | 3.518 | -0.102 | 0.328 | -0.109 | 0.011 | -0.062 | 0.073 | |
| | | EQZ | 0.091 | 1.069 | -0.073 | -0.227 | -1.697 | -0.114 | -0.019 | 0.598 | |
| | | EQT | -0.030 | -0.003 | 0.423 | -0.013 | 0.017 | -0.034 | -0.008 | -0.011 | |
| | | SPKW | -1.363 | 0.123 | 0.037 | -0.280 | -0.015 | -0.035 | 0.045 | -0.233 | |
| | | SPKN | 0.393 | -0.065 | 0.000 | 0.276 | -0.009 | 0.013 | -0.033 | 0.028 | |
| | 4 RCCV Wetwell Bottom | 1806 | OTHR | 1.479 | -1.729 | -0.057 | 0.672 | 4.234 | 0.015 | 0.013 | 1.690 |
| | | | TEMP | 1.751 | -0.007 | -0.297 | -4.421 | -7.805 | 0.062 | 0.058 | -1.566 |
| | | | EQEW | 0.729 | 4.585 | -4.703 | -0.176 | -0.955 | -0.027 | 0.011 | -0.377 |
| EQNS | | | -1.663 | -1.606 | -3.784 | 0.241 | 1.992 | -0.076 | 0.018 | 0.733 | |
| EQZ | | | 0.276 | 3.169 | -0.099 | 0.073 | 0.469 | -0.006 | 0.001 | 0.100 | |
| EQT | | | 0.108 | 0.050 | 0.777 | -0.002 | -0.048 | -0.016 | 0.000 | -0.025 | |
| SPKW | | | -0.433 | 0.096 | 0.283 | -0.005 | 0.013 | 0.055 | 0.007 | 0.053 | |
| SPKN | | | -0.162 | 0.088 | 0.000 | -0.036 | -0.034 | -0.020 | 0.002 | 0.001 | |
| 1813 | | OTHR | 0.962 | -2.233 | 0.343 | 0.718 | 4.514 | 0.012 | -0.015 | 1.913 | |
| | | TEMP | 1.093 | -2.329 | -0.367 | -4.202 | -7.396 | -0.025 | -0.007 | -1.331 | |
| | | EQEW | 1.114 | 5.859 | 0.928 | -0.274 | -1.581 | -0.011 | 0.006 | -0.664 | |
| | | EQNS | -0.371 | 3.027 | -4.441 | 0.119 | 0.882 | -0.034 | 0.019 | 0.352 | |
| | | EQZ | 0.403 | 3.198 | -0.126 | 0.071 | 0.390 | -0.005 | 0.001 | 0.066 | |
| | | EQT | 0.096 | -0.035 | 0.890 | -0.008 | -0.050 | -0.028 | 0.001 | -0.036 | |
| | | SPKW | 0.032 | -0.028 | -0.069 | 0.037 | -0.031 | -0.001 | 0.003 | 0.029 | |
| | | SPKN | -0.468 | 0.064 | 0.168 | -0.033 | 0.031 | 0.000 | -0.006 | 0.050 | |
| 1824 | | OTHR | 0.748 | -2.802 | 0.003 | 0.784 | 4.585 | 0.021 | -0.018 | 1.986 | |
| | | TEMP | 1.981 | -2.824 | 0.082 | -4.322 | -7.438 | 0.022 | -0.082 | -1.354 | |
| | | EQEW | 0.071 | 0.451 | 7.426 | -0.033 | -0.119 | 0.094 | -0.059 | -0.064 | |
| | | EQNS | 0.906 | 6.607 | -0.267 | -0.034 | -0.345 | -0.011 | 0.003 | -0.240 | |
| | | EQZ | 0.327 | 3.634 | 0.042 | 0.074 | 0.449 | 0.000 | 0.002 | 0.092 | |
| | | EQT | 0.002 | -0.002 | 1.125 | -0.003 | -0.005 | -0.013 | -0.004 | -0.003 | |
| | | SPKW | -0.581 | 0.147 | -0.037 | -0.044 | 0.047 | -0.002 | 0.005 | 0.063 | |
| | | SPKN | -0.022 | -0.020 | 0.071 | 0.051 | -0.010 | 0.003 | -0.013 | 0.041 | |

**Table 3G.1-25
Combined Forces and Moments: RCCV, Selected Load Combination CV-11a (Continued)**

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|---------------------------------|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 5 RCCV Wetwell Mid-Height | 2606 | OTHR | 3.049 | -1.507 | -0.188 | -0.173 | -0.626 | -0.014 | 0.008 | -0.298 | |
| | | TEMP | 1.184 | -0.011 | -0.269 | -3.358 | -1.133 | 0.021 | 0.034 | 0.033 | |
| | | EQEW | 0.042 | 3.102 | -4.217 | 0.030 | 0.120 | -0.061 | -0.007 | -0.089 | |
| | | EQNS | -0.421 | -1.104 | -3.924 | -0.087 | -0.098 | -0.120 | -0.018 | 0.181 | |
| | | EQZ | 0.129 | 2.896 | -0.130 | -0.004 | 0.020 | -0.007 | 0.001 | 0.061 | |
| | | EQT | 0.002 | 0.036 | 0.741 | 0.003 | 0.003 | -0.019 | 0.005 | -0.004 | |
| | | SPKW | -0.080 | 0.068 | 0.138 | -0.013 | -0.040 | 0.018 | 0.004 | 0.001 | |
| | | SPKN | -0.084 | 0.034 | -0.014 | -0.017 | 0.001 | -0.018 | -0.003 | -0.002 | |
| | 2613 | OTHR | 2.592 | -2.032 | 0.349 | -0.214 | -0.720 | 0.017 | -0.002 | -0.189 | |
| | | TEMP | -0.038 | -2.791 | -0.063 | -3.081 | -1.119 | 0.008 | -0.077 | 0.390 | |
| | | EQEW | -0.005 | 4.069 | 0.921 | 0.044 | 0.171 | -0.017 | -0.010 | -0.249 | |
| | | EQNS | -0.798 | 2.750 | -4.413 | -0.053 | -0.089 | -0.036 | -0.024 | 0.163 | |
| | | EQZ | 0.199 | 2.967 | -0.138 | 0.020 | 0.040 | -0.003 | 0.000 | 0.040 | |
| | | EQT | 0.102 | -0.088 | 0.859 | 0.011 | 0.023 | -0.025 | -0.002 | -0.011 | |
| | | SPKW | 0.224 | 0.087 | -0.048 | 0.025 | -0.043 | -0.002 | 0.000 | 0.018 | |
| | | SPKN | -0.291 | -0.003 | 0.164 | -0.035 | -0.019 | 0.005 | 0.002 | -0.008 | |
| | 2624 | OTHR | 2.916 | -2.327 | 0.043 | -0.141 | -0.803 | 0.000 | 0.006 | -0.300 | |
| | | TEMP | 1.079 | -3.158 | -0.043 | -3.384 | -1.119 | -0.022 | 0.071 | 0.377 | |
| | | EQEW | 0.046 | 0.198 | 6.829 | 0.008 | 0.044 | 0.103 | 0.036 | -0.013 | |
| | | EQNS | -0.044 | 5.027 | -0.262 | 0.099 | 0.205 | -0.005 | -0.005 | -0.062 | |
| | | EQZ | 0.193 | 3.390 | 0.018 | -0.013 | -0.002 | 0.000 | 0.002 | 0.080 | |
| | | EQT | -0.002 | -0.017 | 0.934 | -0.001 | 0.006 | -0.019 | 0.003 | 0.000 | |
| | | SPKW | -0.284 | 0.016 | -0.021 | -0.043 | -0.029 | -0.005 | 0.004 | -0.020 | |
| | | SPKN | 0.208 | 0.115 | 0.031 | 0.023 | -0.048 | 0.002 | -0.003 | 0.032 | |
| 6 RCCV Wetwell Top | 3406 | OTHR | 1.993 | -1.049 | -0.017 | -0.022 | 0.029 | 0.055 | -0.044 | 0.044 | |
| | | TEMP | 11.624 | 0.596 | 0.226 | -4.154 | -8.398 | -0.221 | 0.439 | 3.322 | |
| | | EQEW | -0.398 | 1.932 | -3.913 | 0.030 | 0.165 | -0.110 | 0.074 | -0.089 | |
| | | EQNS | -0.091 | -0.510 | -3.585 | -0.105 | -0.299 | -0.018 | -0.047 | 0.142 | |
| | | EQZ | 0.195 | 2.546 | -0.179 | -0.076 | -0.463 | 0.034 | -0.071 | 0.157 | |
| | | EQT | 0.052 | -0.005 | 0.713 | -0.006 | -0.021 | -0.024 | -0.003 | 0.008 | |
| | | SPKW | -0.019 | 0.052 | 0.051 | -0.006 | -0.011 | 0.016 | -0.012 | -0.006 | |
| | | SPKN | -0.031 | 0.005 | 0.025 | -0.001 | 0.012 | -0.012 | 0.007 | -0.006 | |
| | | 3413 | OTHR | 1.615 | -1.886 | 0.226 | -0.072 | -0.133 | -0.102 | 0.066 | 0.099 |
| | | | TEMP | 7.954 | -3.660 | -0.047 | -4.357 | -9.124 | -0.396 | 0.519 | 3.323 |
| | | | EQEW | -0.289 | 2.645 | 0.971 | 0.054 | 0.321 | 0.036 | -0.062 | -0.227 |
| | | | EQNS | -0.662 | 2.398 | -4.252 | -0.039 | -0.196 | -0.071 | 0.067 | 0.077 |
| | EQZ | | 0.063 | 2.823 | -0.097 | -0.025 | -0.210 | 0.004 | 0.016 | 0.076 | |
| | EQT | | 0.091 | -0.104 | 0.873 | 0.007 | 0.025 | -0.013 | -0.010 | -0.005 | |
| | 3424 | SPKW | 0.132 | 0.130 | -0.025 | 0.009 | -0.056 | -0.004 | 0.004 | 0.033 | |
| | | SPKN | -0.166 | -0.041 | 0.094 | -0.011 | 0.022 | 0.001 | -0.002 | -0.021 | |
| | | OTHR | 1.691 | -1.711 | 0.068 | 0.051 | 0.080 | 0.024 | -0.001 | 0.046 | |
| | | TEMP | 11.052 | -4.630 | 0.371 | -3.786 | -5.604 | -0.046 | -0.058 | 2.298 | |
| | | EQEW | -0.187 | 0.123 | 5.910 | 0.017 | 0.013 | 0.010 | 0.005 | 0.006 | |
| | | EQNS | -0.518 | 3.812 | -0.168 | 0.065 | 0.270 | 0.045 | -0.033 | -0.081 | |
| | 3424 | EQZ | 0.120 | 3.010 | -0.010 | -0.059 | -0.305 | 0.045 | -0.058 | 0.079 | |
| | | EQT | -0.032 | -0.004 | 0.782 | -0.001 | -0.004 | -0.024 | -0.007 | 0.004 | |
| | | SPKW | -0.147 | -0.044 | -0.004 | -0.005 | 0.046 | -0.004 | 0.002 | -0.031 | |
| | | SPKN | 0.183 | 0.153 | 0.008 | -0.008 | -0.136 | 0.003 | -0.004 | 0.053 | |

Table 3G.1-25
Combined Forces and Moments: RCCV, Selected Load Combination CV-11a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---------------------------------|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 7 RCCV Drywell Bottom | 3606 | OTHR | 1.944 | -0.613 | -0.132 | 0.018 | 0.291 | 0.071 | -0.015 | 0.420 |
| | | TEMP | 8.432 | 0.427 | 0.558 | -5.339 | -8.935 | 0.587 | 0.513 | -1.847 |
| | | EQEW | -0.452 | 1.766 | -3.473 | -0.041 | -0.248 | -0.085 | 0.065 | -0.016 |
| | | EQNS | -0.031 | -0.141 | -3.512 | 0.074 | 0.711 | 0.047 | -0.003 | 0.201 |
| | | EQZ | 0.062 | 2.442 | -0.034 | 0.009 | -0.005 | 0.039 | -0.062 | -0.045 |
| | | EQT | 0.059 | -0.015 | 0.652 | -0.012 | -0.046 | -0.022 | -0.003 | -0.015 |
| | | SPKW | -0.017 | 0.050 | 0.033 | -0.003 | 0.004 | -0.002 | -0.012 | 0.002 |
| | | SPKN | -0.026 | 0.005 | 0.016 | 0.000 | 0.012 | 0.001 | 0.008 | 0.005 |
| | 3613 | OTHR | 1.588 | -1.539 | 0.225 | 0.070 | 0.671 | -0.073 | 0.020 | 0.656 |
| | | TEMP | 4.514 | -4.417 | 0.816 | -4.914 | -6.085 | -0.394 | 0.296 | -0.734 |
| | | EQEW | -0.265 | 2.846 | 1.125 | -0.134 | -0.780 | -0.006 | -0.052 | -0.296 |
| | | EQNS | -0.698 | 2.066 | -3.945 | 0.081 | 0.502 | -0.070 | 0.057 | 0.204 |
| | | EQZ | -0.070 | 2.782 | -0.112 | 0.007 | 0.010 | -0.009 | 0.017 | -0.131 |
| | | EQT | 0.095 | -0.082 | 0.789 | -0.001 | -0.019 | -0.016 | -0.009 | -0.006 |
| | | SPKW | 0.103 | 0.099 | -0.019 | 0.022 | 0.033 | -0.002 | 0.003 | 0.004 |
| | | SPKN | -0.143 | -0.041 | 0.051 | -0.011 | 0.011 | -0.001 | -0.002 | 0.013 |
| | 3624 | OTHR | 1.544 | -1.784 | 0.111 | 0.219 | 1.021 | 0.035 | 0.015 | 0.608 |
| | | TEMP | -3.703 | -6.328 | 0.263 | -1.033 | -3.093 | 0.041 | -0.049 | 0.123 |
| | | EQEW | -0.126 | 0.166 | 5.784 | -0.041 | -0.106 | 0.041 | 0.024 | -0.050 |
| | | EQNS | -0.550 | 3.914 | -0.186 | -0.048 | -0.303 | 0.055 | -0.007 | -0.021 |
| | | EQZ | 0.078 | 3.186 | -0.058 | -0.032 | -0.159 | 0.047 | -0.033 | -0.095 |
| | | EQT | -0.021 | -0.004 | 0.787 | -0.007 | -0.013 | -0.022 | -0.005 | -0.006 |
| | | SPKW | -0.123 | -0.026 | -0.002 | -0.011 | -0.001 | 0.000 | 0.002 | 0.005 |
| | | SPKN | 0.142 | 0.069 | 0.005 | 0.022 | 0.048 | -0.001 | -0.004 | 0.008 |
| 8 RCCV Drywell Mid-Height | 4006 | OTHR | 1.498 | -0.379 | -0.106 | -0.095 | -0.285 | 0.001 | 0.028 | -0.088 |
| | | TEMP | 5.852 | 0.754 | -0.011 | -5.144 | -5.509 | 0.007 | -0.183 | -0.528 |
| | | EQEW | -0.910 | 0.987 | -3.270 | 0.020 | 0.052 | -0.092 | -0.017 | -0.156 |
| | | EQNS | 0.790 | 0.233 | -3.141 | -0.077 | -0.071 | -0.062 | 0.029 | 0.261 |
| | | EQZ | -0.449 | 2.407 | 0.073 | 0.095 | 0.356 | 0.041 | 0.003 | -0.161 |
| | | EQT | 0.019 | -0.053 | 0.620 | -0.001 | -0.016 | -0.024 | 0.000 | -0.007 |
| | | SPKW | -0.013 | 0.044 | 0.005 | -0.003 | 0.001 | 0.010 | -0.001 | -0.001 |
| | | SPKN | -0.014 | 0.006 | 0.039 | 0.001 | -0.004 | -0.006 | 0.001 | 0.002 |
| | 4013 | OTHR | 1.408 | -1.628 | 0.351 | -0.102 | -0.401 | 0.005 | -0.007 | -0.069 |
| | | TEMP | 4.218 | -5.936 | 0.807 | -4.699 | -4.400 | 0.008 | -0.150 | -0.234 |
| | | EQEW | -1.066 | 1.762 | 0.993 | 0.076 | 0.313 | 0.008 | -0.022 | -0.324 |
| | | EQNS | -0.292 | 2.306 | -3.780 | -0.012 | -0.067 | -0.088 | 0.014 | 0.108 |
| | | EQZ | -0.429 | 2.930 | -0.188 | 0.043 | 0.368 | 0.001 | 0.006 | -0.071 |
| | | EQT | 0.077 | -0.117 | 0.773 | -0.003 | -0.022 | -0.006 | -0.001 | 0.008 |
| | | SPKW | 0.058 | 0.139 | -0.017 | 0.011 | 0.005 | -0.002 | 0.000 | 0.014 |
| | | SPKN | -0.064 | -0.052 | 0.039 | -0.010 | -0.009 | -0.001 | 0.000 | -0.003 |
| | 4976 | OTHR | 1.221 | -1.164 | 0.141 | 0.020 | -0.163 | 0.010 | -0.012 | -0.098 |
| | | TEMP | -3.420 | -5.654 | 0.772 | -0.840 | -1.477 | -0.001 | 0.007 | -0.863 |
| | | EQEW | 0.115 | 0.026 | 5.969 | 0.045 | 0.045 | 0.059 | 0.041 | -0.021 |
| | | EQNS | -0.454 | 3.036 | -0.266 | -0.063 | -0.168 | -0.016 | 0.009 | -0.046 |
| | | EQZ | -0.086 | 2.647 | -0.162 | 0.018 | 0.189 | 0.003 | 0.005 | -0.084 |
| | | EQT | 0.030 | -0.017 | 0.833 | 0.005 | 0.002 | -0.016 | 0.006 | -0.001 |
| | | SPKW | -0.050 | -0.035 | 0.003 | -0.004 | 0.006 | -0.002 | 0.000 | -0.009 |
| | | SPKN | 0.067 | 0.077 | -0.003 | 0.007 | -0.007 | 0.002 | -0.001 | 0.019 |

Table 3G.1-25
Combined Forces and Moments: RCCV, Selected Load Combination CV-11a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|--------------------------|------------------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 9 RCCV Drywell Top | 4406 | OTHR | 0.540 | -0.162 | -0.152 | 0.116 | 0.741 | -0.014 | -0.006 | -0.267 | |
| | | TEMP | 3.417 | -0.742 | -1.786 | -4.287 | -4.604 | 0.344 | -0.208 | -0.354 | |
| | | EQEW | -1.432 | 0.273 | -2.870 | 0.144 | 0.700 | -0.008 | 0.016 | -0.292 | |
| | | EQNS | 1.184 | 1.012 | -2.125 | -0.314 | -1.191 | 0.022 | 0.092 | 0.455 | |
| | | EQZ | -0.124 | 2.743 | 0.734 | 0.154 | 1.012 | 0.008 | -0.003 | -0.180 | |
| | | EQT | -0.058 | -0.128 | 0.705 | 0.017 | 0.085 | -0.019 | -0.034 | -0.040 | |
| | | SPKW | -0.005 | 0.045 | 0.000 | -0.001 | 0.004 | 0.006 | 0.009 | -0.001 | |
| | SPKN | -0.010 | 0.008 | 0.051 | -0.001 | -0.009 | -0.004 | -0.005 | 0.000 | | |
| | 4413 | OTHR | 0.153 | -1.736 | 0.327 | 0.090 | 0.901 | 0.036 | 0.008 | -0.394 | |
| | | TEMP | 0.498 | -6.550 | -0.446 | -4.823 | -4.853 | 0.289 | -0.224 | 0.725 | |
| | | EQEW | -1.216 | 0.860 | 0.828 | 0.183 | 1.145 | 0.044 | 0.052 | -0.240 | |
| | | EQNS | 0.714 | 2.598 | -3.377 | -0.009 | -0.368 | -0.034 | -0.042 | 0.072 | |
| | | EQZ | 0.349 | 3.050 | -0.086 | 0.139 | 0.731 | -0.005 | 0.010 | -0.144 | |
| | | EQT | -0.003 | -0.148 | 0.957 | 0.006 | 0.052 | -0.010 | -0.002 | -0.030 | |
| | | SPKW | 0.085 | 0.166 | -0.005 | -0.005 | -0.062 | 0.001 | 0.000 | 0.027 | |
| | | SPKN | -0.051 | -0.051 | 0.033 | -0.001 | 0.016 | 0.000 | 0.000 | -0.013 | |
| | 4424 | OTHR | 0.873 | -0.661 | 0.113 | 0.193 | 0.973 | 0.019 | 0.004 | -0.334 | |
| | | TEMP | -7.055 | -4.082 | 0.940 | -0.023 | 2.580 | -0.017 | -0.012 | -1.978 | |
| | | EQEW | 0.212 | -0.022 | 6.191 | 0.053 | 0.031 | 0.004 | 0.056 | 0.017 | |
| | | EQNS | -0.865 | 2.281 | -0.226 | -0.048 | -0.330 | -0.020 | -0.004 | -0.009 | |
| | | EQZ | -0.042 | 2.067 | -0.135 | 0.054 | 0.448 | -0.003 | 0.000 | -0.085 | |
| | | EQT | 0.048 | -0.016 | 1.133 | 0.008 | 0.006 | -0.013 | -0.009 | 0.001 | |
| | | SPKW | -0.016 | -0.034 | 0.004 | 0.006 | 0.045 | 0.000 | -0.001 | -0.016 | |
| | | SPKN | 0.027 | 0.069 | -0.003 | -0.011 | -0.079 | 0.000 | 0.001 | 0.029 | |
| | 10 Basemat @ Center | 80003 | OTHR | -1.728 | -0.684 | 0.111 | 0.116 | 0.581 | 0.026 | 0.539 | -0.413 |
| | | | TEMP | -3.832 | -4.439 | 0.007 | -4.240 | -4.238 | -0.016 | 0.032 | -0.015 |
| | | | EQEW | 0.003 | 0.113 | 0.970 | 0.137 | 0.241 | -0.184 | 0.020 | 0.540 |
| EQNS | | | 3.586 | 2.842 | -0.331 | -4.691 | -4.176 | 0.064 | 0.477 | 0.092 | |
| EQZ | | | 1.176 | 1.338 | -0.029 | -3.648 | -3.734 | 0.003 | -0.174 | 0.134 | |
| EQT | | | 0.037 | -0.014 | 0.415 | 0.005 | 0.011 | -0.032 | 0.006 | 0.031 | |
| SPKW | | | 0.503 | -1.631 | -0.002 | 0.153 | 0.078 | -0.003 | -0.012 | -0.008 | |
| SPKN | | -1.793 | 0.512 | 0.019 | 0.092 | 0.131 | -0.015 | 0.022 | 0.007 | | |
| 80007 | | OTHR | -1.764 | -0.742 | 0.064 | 0.293 | 0.617 | 0.053 | 0.222 | -0.556 | |
| | | TEMP | -3.849 | -4.408 | 0.035 | -4.214 | -4.235 | -0.013 | 0.025 | -0.019 | |
| | | EQEW | 0.363 | -0.256 | 0.505 | 0.315 | 0.349 | -0.067 | -0.002 | 0.512 | |
| | | EQNS | 3.503 | 2.916 | -0.316 | -4.254 | -4.033 | 0.165 | 0.614 | 0.111 | |
| | | EQZ | 1.185 | 1.348 | -0.024 | -3.657 | -3.736 | 0.001 | 0.023 | 0.216 | |
| | | EQT | 0.062 | -0.063 | 0.349 | 0.016 | 0.016 | -0.025 | 0.009 | 0.028 | |
| | | SPKW | 0.508 | -1.633 | -0.003 | 0.149 | 0.079 | -0.003 | -0.002 | -0.006 | |
| | | SPKN | -1.791 | 0.519 | 0.021 | 0.100 | 0.135 | -0.012 | 0.011 | 0.004 | |
| 80012 | | OTHR | -1.861 | -0.816 | 0.084 | 0.499 | 0.818 | -0.054 | -0.114 | -0.248 | |
| | | TEMP | -3.854 | -4.352 | 0.023 | -4.203 | -4.237 | -0.013 | 0.012 | -0.004 | |
| | | EQEW | -0.098 | 0.116 | 0.355 | 0.055 | 0.059 | 0.106 | -0.005 | 0.558 | |
| | | EQNS | 3.205 | 3.049 | -0.151 | -3.908 | -3.829 | 0.022 | 0.680 | -0.001 | |
| | | EQZ | 1.185 | 1.364 | -0.024 | -3.656 | -3.737 | 0.002 | 0.208 | 0.029 | |
| | | EQT | 0.024 | -0.016 | 0.318 | 0.003 | 0.001 | -0.016 | 0.003 | 0.030 | |
| | | SPKW | 0.516 | -1.630 | 0.001 | 0.143 | 0.078 | -0.003 | 0.001 | -0.002 | |
| | | SPKN | -1.793 | 0.522 | 0.020 | 0.111 | 0.146 | -0.016 | 0.007 | 0.001 | |

Table 3G.1-25
Combined Forces and Moments: RCCV, Selected Load Combination CV-11a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|--------------------------------------|----------------------|--------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|--------|
| 11 Basemat Inside RPV Pedestal | 80206 | OTHR | -1.163 | -0.535 | 0.267 | -4.846 | -4.206 | 1.996 | 2.025 | -1.976 | |
| | | TEMP | -3.802 | -4.758 | 0.110 | -4.600 | -4.678 | 0.084 | 0.016 | -0.101 | |
| | | EQEW | 1.123 | -0.469 | 2.151 | 2.151 | 2.565 | -1.023 | -0.541 | 1.016 | |
| | | EQNS | 4.320 | 2.471 | -1.054 | -6.305 | -4.299 | 0.491 | 0.742 | 0.202 | |
| | | EQZ | 1.149 | 1.282 | -0.043 | -1.685 | -1.928 | -0.649 | -0.747 | 0.658 | |
| | | EQT | 0.104 | -0.077 | 0.574 | -0.151 | 0.217 | -0.100 | 0.111 | 0.160 | |
| | | SPKW | 0.385 | -1.507 | -0.021 | 0.051 | 0.222 | -0.006 | 0.084 | 0.094 | |
| | SPKN | -1.718 | 0.364 | 0.005 | 0.174 | -0.067 | 0.002 | -0.077 | -0.102 | | |
| | 80213 | OTHR | -1.383 | -0.655 | 0.141 | -2.327 | -5.824 | 0.613 | 0.613 | -2.662 | |
| | | TEMP | -3.949 | -4.381 | 0.094 | -4.421 | -4.763 | -0.049 | 0.006 | -0.146 | |
| | | EQEW | 1.929 | -0.848 | 0.482 | 2.692 | 4.698 | 0.061 | 0.096 | 1.708 | |
| | | EQNS | 3.499 | 2.910 | -1.544 | -3.171 | -2.170 | 1.378 | 1.189 | 0.724 | |
| | | EQZ | 1.179 | 1.367 | -0.064 | -2.356 | -1.102 | 0.052 | 0.028 | 1.027 | |
| | | EQT | 0.217 | -0.076 | 0.421 | 0.124 | 0.163 | 0.087 | 0.136 | 0.041 | |
| | | SPKW | 0.312 | -1.636 | -0.043 | -0.034 | 0.008 | 0.016 | -0.002 | 0.005 | |
| | SPKN | -1.592 | 0.519 | 0.012 | 0.279 | 0.202 | -0.018 | -0.006 | -0.006 | | |
| | 80224 | OTHR | -2.170 | -1.459 | -0.007 | -3.168 | -1.785 | -0.801 | -1.803 | -0.775 | |
| | | TEMP | -3.875 | -4.291 | 0.046 | -4.364 | -4.386 | -0.020 | -0.043 | 0.010 | |
| | | EQEW | 0.076 | 0.039 | -1.798 | 0.300 | 0.206 | 0.366 | 0.075 | 0.061 | |
| | | EQNS | 2.510 | 3.600 | -0.146 | 1.629 | -1.229 | 0.129 | 1.970 | 0.063 | |
| | | EQZ | 1.233 | 1.441 | -0.024 | -1.139 | -2.368 | 0.090 | 0.999 | 0.079 | |
| | | EQT | 0.029 | -0.016 | -0.094 | 0.040 | -0.001 | -0.126 | 0.011 | -0.150 | |
| | | SPKW | 0.558 | -1.432 | 0.002 | 0.166 | 0.244 | 0.006 | -0.016 | 0.014 | |
| | SPKN | -1.804 | 0.342 | 0.016 | 0.082 | 0.010 | -0.007 | 0.010 | 0.000 | | |
| | 12 S/P Slab @ RPV | 83306 | OTHR | -0.440 | 2.216 | -0.498 | -0.948 | 1.120 | -0.128 | 4.205 | -0.066 |
| | | | TEMP | -8.430 | 8.012 | 0.027 | -4.417 | -2.896 | 0.015 | -0.248 | 0.001 |
| | | | EQEW | -0.804 | -0.320 | 1.004 | 1.133 | 0.470 | -0.277 | 0.459 | 0.135 |
| | | | EQNS | -0.024 | -1.056 | -1.566 | -2.820 | -1.643 | -0.313 | -1.032 | 0.123 |
| EQZ | | | -0.124 | -0.267 | 0.146 | -1.455 | -0.965 | 0.018 | -0.734 | 0.021 | |
| EQT | | | -0.015 | 0.015 | -0.033 | 0.056 | 0.025 | -0.023 | 0.017 | 0.014 | |
| SPKW | | | -0.450 | -0.624 | 1.118 | -0.045 | -0.038 | 0.007 | -0.032 | 0.005 | |
| SPKN | | -0.194 | -0.406 | -0.948 | -0.019 | -0.016 | 0.004 | -0.008 | -0.004 | | |
| 83313 | | OTHR | 0.211 | 1.881 | -0.873 | -0.861 | 1.231 | -0.158 | 4.241 | 0.058 | |
| | | TEMP | -8.845 | 8.448 | -0.275 | -4.426 | -2.958 | -0.032 | -0.239 | -0.022 | |
| | | EQEW | -1.336 | -0.260 | 0.171 | 1.627 | 0.736 | 0.021 | 0.659 | -0.015 | |
| | | EQNS | -0.431 | -1.505 | 0.783 | -1.652 | -1.076 | -0.449 | -0.591 | 0.167 | |
| | | EQZ | -0.247 | -0.187 | 0.074 | -1.467 | -0.967 | -0.012 | -0.738 | -0.021 | |
| | | EQT | -0.008 | 0.052 | -0.097 | 0.100 | 0.051 | 0.005 | 0.037 | 0.005 | |
| | | SPKW | -0.598 | 0.253 | -0.089 | -0.057 | -0.032 | 0.000 | -0.057 | 0.001 | |
| SPKN | | -0.208 | -0.985 | 0.124 | -0.025 | -0.021 | -0.001 | -0.004 | -0.003 | | |
| 83324 | | OTHR | 2.069 | 2.110 | -0.691 | -0.560 | 1.627 | -0.196 | 4.437 | -0.079 | |
| | | TEMP | -8.617 | 8.870 | 0.723 | -4.216 | -2.783 | 0.001 | -0.123 | 0.042 | |
| | | EQEW | -0.175 | -0.020 | -1.709 | 0.074 | 0.043 | 0.410 | 0.039 | -0.175 | |
| | | EQNS | -0.623 | -0.113 | 0.101 | -0.297 | -0.317 | -0.028 | -0.051 | 0.017 | |
| | | EQZ | -0.232 | -0.288 | -0.002 | -1.473 | -0.971 | 0.018 | -0.742 | 0.020 | |
| | | EQT | -0.007 | -0.012 | -0.225 | 0.007 | 0.004 | 0.029 | 0.002 | -0.011 | |
| | | SPKW | -0.201 | -1.214 | -0.128 | -0.044 | -0.044 | 0.000 | -0.012 | 0.004 | |
| SPKN | | -0.482 | 0.259 | 0.061 | -0.046 | -0.017 | 0.000 | -0.051 | -0.002 | | |

Table 3G.1-25
Combined Forces and Moments: RCCV, Selected Load Combination CV-11a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|-------------------------|-----------------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 13 S/P Slab @ Center | 83406 | OTHR | 0.099 | 2.051 | -0.451 | -6.449 | -1.643 | -0.039 | -0.342 | -0.001 | |
| | | TEMP | -4.716 | 3.300 | -0.435 | -3.598 | -3.189 | -0.006 | -0.274 | 0.009 | |
| | | EQEW | -0.707 | 0.030 | 0.424 | -0.259 | 0.175 | -0.189 | 0.290 | 0.000 | |
| | | EQNS | 0.042 | -1.356 | -1.365 | 0.433 | -0.909 | -0.224 | -0.712 | -0.011 | |
| | | EQZ | -0.143 | -0.260 | 0.105 | 0.552 | -0.468 | 0.003 | -0.366 | 0.000 | |
| | | EQT | -0.012 | 0.060 | 0.007 | 0.004 | 0.009 | -0.018 | 0.012 | 0.001 | |
| | | SPKW | -0.388 | -0.588 | 0.846 | 0.055 | -0.010 | -0.007 | -0.024 | 0.012 | |
| | SPKN | -0.186 | -0.377 | -0.648 | 0.009 | -0.009 | 0.009 | -0.006 | -0.005 | | |
| | 83413 | OTHR | 0.882 | 1.695 | -0.369 | -6.457 | -1.591 | -0.110 | -0.313 | 0.004 | |
| | | TEMP | -5.529 | 3.887 | 0.330 | -3.708 | -3.266 | -0.014 | -0.232 | -0.007 | |
| | | EQEW | -1.249 | -0.033 | 0.148 | -0.337 | 0.283 | 0.028 | 0.418 | 0.001 | |
| | | EQNS | -0.317 | -1.137 | 0.740 | 0.244 | -0.656 | -0.297 | -0.419 | 0.010 | |
| | | EQZ | -0.294 | -0.142 | 0.032 | 0.545 | -0.458 | 0.002 | -0.369 | -0.002 | |
| | | EQT | -0.017 | 0.072 | -0.049 | -0.008 | 0.023 | 0.003 | 0.024 | -0.001 | |
| | | SPKW | -0.916 | 0.099 | -0.048 | 0.119 | 0.017 | 0.001 | -0.042 | 0.000 | |
| | SPKN | -0.003 | -0.766 | 0.028 | -0.010 | -0.017 | -0.004 | -0.004 | 0.001 | | |
| | 83424 | OTHR | 2.021 | 1.723 | -0.299 | -6.502 | -1.385 | -0.092 | -0.242 | 0.004 | |
| | | TEMP | -5.039 | 4.216 | 0.041 | -3.677 | -3.155 | -0.002 | -0.184 | 0.007 | |
| | | EQEW | -0.106 | -0.009 | -0.929 | -0.033 | 0.010 | 0.268 | 0.026 | 0.015 | |
| | | EQNS | -0.869 | -0.164 | 0.069 | 0.039 | -0.327 | -0.018 | -0.075 | 0.000 | |
| | | EQZ | -0.256 | -0.261 | -0.004 | 0.553 | -0.457 | 0.001 | -0.373 | 0.001 | |
| | | EQT | 0.003 | -0.010 | -0.130 | -0.001 | 0.002 | 0.019 | 0.002 | 0.000 | |
| | | SPKW | 0.053 | -0.975 | -0.101 | -0.006 | -0.031 | 0.001 | -0.009 | -0.001 | |
| | SPKN | -0.791 | 0.077 | 0.054 | 0.112 | 0.025 | -0.001 | -0.037 | 0.001 | | |
| | 14 S/P Slab @ RCCV | 83506 | OTHR | 0.578 | 1.946 | -0.305 | 2.778 | -0.491 | -0.033 | -3.874 | -0.003 |
| | | | TEMP | -2.707 | 1.467 | -0.274 | -2.852 | -3.128 | -0.032 | -0.252 | 0.010 |
| | | | EQEW | -0.506 | -0.030 | 0.101 | -1.095 | -0.198 | -0.003 | 0.234 | -0.050 |
| EQNS | | | 0.316 | -1.405 | -1.038 | 2.407 | 0.020 | -0.029 | -0.546 | -0.048 | |
| EQZ | | | -0.144 | -0.236 | 0.096 | 1.146 | -0.010 | 0.006 | -0.102 | -0.002 | |
| EQT | | | -0.030 | 0.096 | 0.021 | -0.029 | -0.007 | -0.006 | 0.009 | -0.002 | |
| SPKW | | | -0.377 | -0.563 | 0.689 | 0.113 | 0.027 | -0.034 | -0.017 | 0.011 | |
| SPKN | | -0.113 | -0.291 | -0.437 | 0.018 | 0.000 | 0.015 | -0.002 | -0.002 | | |
| 83513 | | OTHR | 1.233 | 1.643 | -0.263 | 2.688 | -0.470 | -0.044 | -3.853 | -0.007 | |
| | | TEMP | -3.724 | 1.594 | 0.393 | -3.192 | -3.182 | -0.007 | -0.152 | 0.000 | |
| | | EQEW | -1.070 | -0.066 | 0.138 | -1.520 | -0.265 | 0.009 | 0.331 | 0.005 | |
| | | EQNS | -0.282 | -0.902 | 0.686 | 1.379 | -0.078 | -0.051 | -0.322 | -0.055 | |
| | | EQZ | -0.304 | -0.128 | 0.012 | 1.156 | 0.003 | 0.003 | -0.108 | -0.003 | |
| | | EQT | -0.012 | 0.090 | -0.031 | -0.076 | -0.008 | 0.006 | 0.019 | -0.001 | |
| | | SPKW | -1.040 | -0.083 | -0.027 | 0.241 | 0.072 | 0.001 | -0.034 | 0.000 | |
| SPKN | | 0.093 | -0.574 | -0.045 | -0.011 | -0.008 | -0.005 | 0.000 | -0.001 | | |
| 83524 | | OTHR | 1.905 | 1.595 | -0.243 | 2.502 | -0.400 | -0.034 | -3.803 | -0.008 | |
| | | TEMP | -3.075 | 2.237 | -0.023 | -3.204 | -3.140 | 0.013 | -0.148 | -0.004 | |
| | | EQEW | -0.061 | -0.032 | -0.577 | -0.110 | -0.025 | -0.026 | 0.023 | 0.083 | |
| | | EQNS | -0.923 | -0.264 | 0.036 | 0.211 | -0.213 | 0.002 | -0.048 | -0.004 | |
| | | EQZ | -0.248 | -0.264 | -0.007 | 1.178 | 0.007 | 0.001 | -0.111 | 0.001 | |
| | | EQT | 0.008 | -0.008 | -0.086 | -0.008 | -0.001 | 0.001 | 0.002 | 0.005 | |
| | | SPKW | 0.171 | -0.733 | -0.086 | 0.000 | -0.013 | 0.003 | -0.003 | 0.000 | |
| SPKN | | -0.939 | -0.110 | 0.071 | 0.229 | 0.073 | -0.003 | -0.033 | 0.001 | | |

Table 3G.1-25
Combined Forces and Moments: RCCV, Selected Load Combination CV-11a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|---|-------------------------|-------|--------------|--------------|---------------|---------------|---------------|----------------|-----------|-----------|--------|
| 15 Top slab @ Drywell Head Opening | 98120 | OTHR | 0.698 | 0.780 | 0.572 | -0.038 | -0.023 | -0.058 | -0.008 | 0.000 | |
| | | TEMP | -7.704 | -4.732 | -1.166 | 0.747 | 0.629 | 2.583 | -0.150 | 0.074 | |
| | | EQEW | -1.292 | -1.085 | -0.943 | -0.055 | -0.435 | -0.121 | -0.057 | -0.066 | |
| | | EQNS | 0.071 | 0.072 | 0.030 | -0.046 | -0.076 | -0.034 | -0.040 | -0.019 | |
| | | EQZ | -0.808 | -0.210 | -0.293 | 0.379 | 0.220 | 0.278 | -0.038 | -0.236 | |
| | | EQT | -0.009 | -0.026 | -0.014 | 0.008 | 0.022 | 0.005 | -0.006 | -0.004 | |
| | | SPKW | 0.031 | -0.011 | 0.008 | -0.005 | 0.003 | -0.001 | 0.002 | 0.002 | |
| | | SPKN | -0.031 | -0.002 | -0.012 | 0.002 | -0.003 | -0.001 | -0.001 | 0.001 | |
| | 98135 | OTHR | 0.746 | 0.227 | -0.218 | -0.032 | -0.140 | 0.101 | 0.079 | -0.062 | |
| | | TEMP | -10.062 | -5.610 | 0.556 | 3.094 | -2.008 | -1.221 | 0.306 | -0.222 | |
| | | EQEW | 0.125 | 0.340 | -0.586 | -0.132 | -0.167 | 0.070 | 0.008 | -0.065 | |
| | | EQNS | 0.622 | 0.061 | -0.118 | -0.162 | -0.016 | 0.026 | 0.008 | 0.000 | |
| | | EQZ | -2.236 | -0.182 | 0.197 | 0.527 | -0.240 | -0.066 | 0.082 | -0.299 | |
| | | EQT | 0.038 | 0.018 | -0.022 | -0.001 | 0.001 | -0.007 | -0.009 | 0.003 | |
| | | SPKW | 0.089 | 0.008 | -0.008 | -0.008 | 0.002 | 0.000 | -0.001 | 0.002 | |
| | | SPKN | -0.097 | -0.013 | 0.017 | 0.004 | -0.002 | 0.001 | 0.001 | -0.001 | |
| | 98104 | OTHR | 0.263 | 1.419 | -0.308 | 0.061 | 0.523 | 0.016 | 0.108 | -0.177 | |
| | | TEMP | -5.268 | -2.661 | 0.786 | -1.577 | 3.078 | -1.390 | 0.146 | -0.201 | |
| | | EQEW | 0.417 | 0.603 | -0.632 | -0.056 | -0.513 | 0.012 | 0.016 | -0.418 | |
| | | EQNS | -0.057 | -1.401 | 0.071 | -0.034 | -0.263 | 0.004 | -0.035 | 0.028 | |
| | | EQZ | -0.066 | -0.456 | 0.069 | 0.172 | 1.050 | -0.219 | 0.002 | -0.239 | |
| | | EQT | 0.020 | 0.039 | -0.032 | -0.008 | -0.029 | 0.009 | -0.002 | -0.017 | |
| | | SPKW | -0.001 | -0.056 | 0.002 | -0.003 | 0.007 | 0.000 | -0.002 | 0.000 | |
| | | SPKN | -0.005 | 0.036 | 0.006 | 0.001 | -0.016 | 0.001 | 0.002 | 0.000 | |
| | 16 Top slab @ Center | 98149 | OTHR | 0.689 | 0.927 | -0.056 | 0.002 | -0.029 | -0.068 | 0.058 | 0.124 |
| | | | TEMP | -6.420 | -3.274 | -0.448 | 1.814 | 2.130 | 0.346 | 0.136 | 0.106 |
| | | | EQEW | -1.003 | -0.296 | -0.570 | 0.004 | -0.119 | -0.001 | 0.055 | -0.012 |
| EQNS | | | 0.296 | 0.658 | 0.077 | -0.091 | 0.043 | -0.048 | -0.055 | 0.067 | |
| EQZ | | | -1.174 | 0.156 | -0.372 | 0.527 | 0.371 | -0.031 | 0.043 | 0.191 | |
| EQT | | | 0.033 | -0.037 | 0.002 | 0.002 | 0.005 | -0.008 | -0.005 | -0.013 | |
| SPKW | | | 0.050 | -0.025 | -0.007 | -0.006 | 0.008 | -0.002 | 0.000 | 0.002 | |
| SPKN | | | -0.050 | -0.002 | 0.004 | 0.004 | -0.004 | 0.000 | -0.001 | -0.001 | |
| 98170 | | OTHR | 0.680 | 0.815 | -0.130 | 0.102 | 0.274 | -0.006 | -0.016 | -0.045 | |
| | | TEMP | -6.246 | -3.905 | -0.324 | 2.174 | 3.114 | -0.038 | 0.113 | 0.455 | |
| | | EQEW | -1.062 | 0.055 | -0.748 | -0.033 | 0.008 | -0.035 | 0.007 | -0.003 | |
| | | EQNS | 0.114 | -0.309 | 0.242 | -0.109 | -0.114 | -0.002 | -0.025 | -0.023 | |
| | | EQZ | -1.023 | 0.029 | -0.024 | 0.653 | 0.874 | -0.004 | 0.011 | 0.023 | |
| | | EQT | 0.033 | 0.043 | -0.026 | -0.001 | -0.003 | -0.009 | 0.003 | 0.001 | |
| | | SPKW | 0.050 | -0.009 | 0.001 | -0.003 | 0.011 | 0.001 | 0.000 | 0.002 | |
| | | SPKN | -0.051 | -0.003 | 0.008 | 0.003 | -0.011 | 0.001 | 0.000 | -0.002 | |
| 98109 | | OTHR | 0.517 | 1.104 | -0.050 | 0.570 | 0.705 | 0.003 | 0.062 | -0.133 | |
| | | TEMP | -6.252 | -2.427 | 0.725 | 1.007 | 2.226 | 0.038 | 0.380 | -0.086 | |
| | | EQEW | 0.121 | -0.022 | -0.733 | -0.018 | -0.235 | -0.142 | 0.014 | -0.139 | |
| | | EQNS | 0.015 | -1.309 | -0.036 | -0.221 | -0.377 | -0.030 | -0.060 | 0.070 | |
| | | EQZ | -0.194 | -0.382 | 0.000 | 0.646 | 0.724 | -0.119 | -0.054 | -0.048 | |
| | | EQT | 0.012 | 0.024 | -0.078 | -0.008 | -0.020 | -0.001 | -0.001 | -0.014 | |
| | | SPKW | 0.017 | -0.016 | -0.002 | -0.008 | 0.009 | 0.000 | 0.000 | -0.001 | |
| | | SPKN | -0.028 | 0.011 | 0.007 | 0.006 | -0.017 | -0.001 | 0.000 | 0.002 | |

**Table 3G.1-25
Combined Forces and Moments: RCCV, Selected Load Combination CV-11a (Continued)**

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|-----------------------|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 17 Top slab @ RCCV | 98174 | OTHR | 0.832 | 0.866 | -0.015 | -0.126 | -0.089 | 0.127 | 0.098 | -0.110 |
| | | TEMP | -5.257 | -4.725 | 1.957 | 2.429 | 2.294 | 0.439 | -0.175 | -0.031 |
| | | EQEW | -1.274 | -0.317 | -0.731 | -0.157 | -0.150 | 0.128 | 0.060 | -0.052 |
| | | EQNS | 0.306 | 1.159 | 0.053 | 0.252 | 0.417 | -0.212 | -0.180 | 0.149 |
| | | EQZ | -0.519 | 0.046 | -0.052 | 0.277 | 0.532 | 0.234 | 0.161 | -0.084 |
| | | EQT | 0.054 | -0.063 | 0.001 | -0.026 | -0.069 | 0.005 | 0.013 | -0.026 |
| | | SPKW | 0.045 | -0.016 | -0.016 | -0.005 | 0.020 | -0.002 | -0.001 | 0.004 |
| | | SPKN | -0.044 | -0.015 | 0.009 | 0.005 | -0.011 | -0.001 | -0.001 | -0.003 |
| | 98197 | OTHR | 0.584 | 0.986 | -0.105 | -0.226 | -0.765 | -0.017 | -0.035 | -0.491 |
| | | TEMP | -7.993 | -3.381 | -0.911 | 1.891 | 2.951 | 0.273 | 0.139 | -0.592 |
| | | EQEW | -1.529 | -0.094 | -0.596 | -0.157 | -0.512 | -0.060 | -0.039 | -0.104 |
| | | EQNS | 0.116 | -0.499 | 0.542 | 0.094 | -0.045 | -0.123 | 0.028 | 0.104 |
| | | EQZ | -0.155 | -0.016 | 0.113 | 0.343 | -0.833 | -0.060 | -0.048 | -0.581 |
| | | EQT | 0.030 | 0.070 | -0.039 | -0.013 | -0.013 | 0.004 | -0.003 | -0.005 |
| | | SPKW | 0.062 | -0.027 | 0.006 | 0.006 | 0.007 | 0.002 | 0.001 | 0.001 |
| | | SPKN | -0.047 | 0.006 | 0.007 | 0.003 | -0.007 | 0.001 | 0.000 | 0.001 |
| | 98103 | OTHR | 0.633 | 1.208 | -0.016 | 0.041 | 0.325 | -0.137 | -0.315 | -0.120 |
| | | TEMP | -6.656 | -4.117 | 0.218 | 4.494 | 3.771 | 0.226 | 1.080 | 0.001 |
| | | EQEW | -0.222 | 0.168 | -1.093 | -0.035 | -0.048 | -0.197 | 0.040 | -0.043 |
| | | EQNS | -0.349 | -1.493 | 0.077 | -1.238 | -0.628 | 0.001 | -0.319 | 0.019 |
| | | EQZ | 0.009 | -0.287 | -0.065 | -1.481 | -0.221 | -0.171 | -0.781 | -0.095 |
| | | EQT | -0.020 | 0.037 | -0.202 | 0.003 | 0.003 | -0.009 | 0.009 | 0.006 |
| | | SPKW | 0.019 | -0.001 | 0.002 | -0.002 | 0.013 | 0.000 | 0.004 | -0.001 |
| | | SPKN | -0.032 | 0.001 | 0.000 | -0.016 | -0.027 | 0.000 | -0.009 | 0.001 |

Table 3G.1-26

Combined Forces and Moments: RCCV, Selected Load Combination CV-11b

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|-----------------------------|---------------------------------|------|--------------|-----------|---------------|---------------|---------------|----------------|-----------|-----------|--------|
| 1 RPV Pedestal Bottom | 5006 | OTHR | -3.257 | -10.916 | 0.049 | 0.561 | 3.323 | 0.045 | -0.012 | 1.795 | |
| | | TEMP | -13.947 | 0.161 | -0.486 | -15.740 | -11.087 | -0.102 | 0.226 | 4.880 | |
| | | EQEW | 3.824 | 6.562 | -1.902 | -0.846 | -4.326 | -0.053 | 0.250 | -1.867 | |
| | | EQNS | -3.659 | -4.291 | -0.463 | 0.933 | 5.377 | 0.046 | 0.061 | 2.277 | |
| | | EQZ | -1.459 | 1.504 | -0.109 | 0.369 | 2.146 | -0.005 | 0.011 | 0.951 | |
| | | EQT | 0.352 | 0.155 | 0.243 | 0.016 | -0.150 | -0.018 | 0.037 | -0.097 | |
| | | SPKW | -0.240 | 0.042 | 0.193 | -0.019 | 0.016 | -0.041 | 0.021 | 0.066 | |
| | | SPKN | -0.242 | -0.059 | -0.226 | 0.042 | 0.132 | 0.035 | -0.009 | 0.105 | |
| | 5013 | OTHR | -3.985 | -10.910 | 1.017 | 0.478 | 3.494 | 0.007 | -0.027 | 2.027 | |
| | | TEMP | -13.372 | 0.271 | -0.086 | -16.029 | -11.713 | -0.007 | 0.019 | 4.752 | |
| | | EQEW | 5.429 | 10.427 | 0.215 | -1.323 | -6.638 | -0.002 | 0.012 | -2.984 | |
| | | EQNS | -0.845 | 1.502 | -0.434 | 0.377 | 2.323 | -0.013 | 0.130 | 0.940 | |
| | | EQZ | -1.245 | 1.957 | -0.167 | 0.325 | 1.935 | -0.001 | 0.012 | 0.845 | |
| | | EQT | 0.259 | 0.237 | 0.247 | -0.078 | -0.282 | -0.014 | 0.037 | -0.146 | |
| | | SPKW | 0.259 | 0.275 | 0.011 | 0.155 | -0.148 | 0.005 | -0.002 | -0.077 | |
| | | SPKN | -0.678 | -0.176 | -0.094 | -0.153 | 0.170 | -0.007 | 0.012 | 0.192 | |
| | 5024 | OTHR | -3.647 | -8.758 | 0.720 | 0.647 | 2.974 | -0.007 | 0.011 | 1.745 | |
| | | TEMP | -13.919 | 0.215 | 0.002 | -16.061 | -10.406 | -0.078 | -0.046 | 4.926 | |
| | | EQEW | 0.453 | 0.627 | 3.241 | -0.093 | -0.436 | 0.007 | -0.264 | -0.196 | |
| | | EQNS | 2.083 | 7.762 | -0.043 | -0.392 | -1.472 | -0.004 | 0.013 | -0.778 | |
| | | EQZ | -0.986 | 2.190 | -0.014 | 0.309 | 1.777 | -0.007 | -0.003 | 0.773 | |
| | | EQT | 0.016 | 0.008 | 0.419 | -0.009 | -0.021 | -0.013 | 0.008 | -0.007 | |
| | | SPKW | -0.626 | -0.190 | -0.019 | -0.147 | 0.198 | 0.005 | -0.002 | 0.192 | |
| | | SPKN | 0.351 | 0.334 | -0.006 | 0.143 | -0.266 | -0.001 | -0.004 | -0.125 | |
| | 2 RPV Pedestal Mid-Height | 6006 | OTHR | 0.916 | -12.002 | 0.243 | -0.087 | -0.095 | 0.041 | 0.105 | -0.392 |
| | | | TEMP | -2.483 | 0.613 | 0.460 | -16.186 | -15.497 | 0.425 | 0.153 | -1.652 |
| | | | EQEW | -0.307 | 2.620 | -3.688 | 0.070 | 0.312 | -0.267 | 0.010 | -0.094 |
| EQNS | | | 0.421 | -2.493 | -1.016 | -0.148 | -0.141 | 0.015 | 0.118 | 0.098 | |
| EQZ | | | 0.062 | 1.529 | -0.161 | -0.022 | -0.079 | -0.020 | -0.017 | -0.006 | |
| EQT | | | -0.016 | 0.005 | 0.132 | 0.025 | 0.027 | -0.038 | -0.007 | -0.009 | |
| SPKW | | | -0.450 | 0.080 | -0.232 | -0.054 | 0.044 | -0.055 | -0.159 | -0.084 | |
| SPKN | | | -0.183 | 0.071 | 0.166 | -0.016 | -0.010 | 0.041 | 0.124 | -0.042 | |
| 6013 | | OTHR | 0.420 | -10.816 | 1.129 | -0.277 | -0.278 | 0.000 | -0.011 | -0.374 | |
| | | TEMP | -2.675 | 0.292 | -0.222 | -16.668 | -15.409 | -0.043 | -0.034 | -1.882 | |
| | | EQEW | -0.916 | 4.064 | 0.457 | 0.189 | 0.314 | -0.026 | 0.009 | -0.303 | |
| | | EQNS | -0.364 | 1.437 | -1.767 | -0.345 | -0.186 | -0.111 | -0.049 | 0.004 | |
| | | EQZ | 0.066 | 1.672 | -0.252 | 0.007 | -0.047 | -0.008 | 0.010 | -0.040 | |
| | | EQT | -0.032 | -0.006 | 0.321 | 0.014 | 0.040 | -0.039 | 0.001 | -0.016 | |
| | | SPKW | 0.044 | 0.014 | 0.072 | 0.513 | 0.287 | 0.014 | 0.041 | -0.206 | |
| | | SPKN | -0.608 | 0.082 | -0.139 | -0.423 | -0.127 | -0.019 | -0.025 | -0.009 | |
| 6024 | | OTHR | 0.502 | -5.378 | 0.135 | 0.270 | -0.203 | -0.006 | 0.013 | -0.269 | |
| | | TEMP | -2.798 | 0.648 | 0.087 | -18.667 | -11.882 | -0.682 | 0.031 | -1.562 | |
| | | EQEW | -0.203 | 1.547 | 6.461 | 0.032 | 0.048 | 0.415 | 0.220 | 0.041 | |
| | | EQNS | -0.380 | 3.898 | 0.316 | 0.367 | 0.224 | -0.039 | -0.049 | -0.258 | |
| | | EQZ | -0.043 | 1.267 | 0.131 | -0.001 | 0.014 | -0.008 | -0.011 | -0.062 | |
| | | EQT | -0.022 | 0.111 | 0.592 | -0.008 | 0.000 | 0.002 | 0.011 | 0.001 | |
| | | SPKW | -0.606 | 0.083 | 0.037 | -0.450 | -0.108 | -0.003 | 0.024 | -0.028 | |
| | | SPKN | -0.161 | -0.122 | -0.033 | 0.542 | 0.381 | 0.002 | -0.026 | -0.221 | |

Table 3G.1-26
Combined Forces and Moments: RCCV, Selected Load Combination CV-11b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|--------------------------|-----------------------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 3 RPV Pedestal Top | 6606 | OTHR | 0.868 | -10.324 | 1.683 | 0.427 | 4.064 | 0.209 | -0.019 | -1.787 | |
| | | TEMP | 3.459 | 0.568 | 0.467 | -16.412 | -12.055 | 0.121 | -0.772 | -1.957 | |
| | | EQEW | -1.238 | 0.118 | -2.973 | 0.335 | 1.594 | 0.093 | -0.028 | -0.657 | |
| | | EQNS | -0.120 | -1.156 | -0.164 | -0.406 | -3.016 | -0.196 | 0.727 | 0.863 | |
| | | EQZ | 0.166 | 1.067 | -0.306 | -0.247 | -1.746 | -0.099 | -0.047 | 0.631 | |
| | | EQT | -0.059 | -0.050 | 0.201 | -0.007 | 0.087 | -0.021 | -0.045 | -0.029 | |
| | | SPKW | -0.704 | 0.033 | -0.392 | -0.092 | 0.025 | 0.224 | -0.499 | -0.135 | |
| | SPKN | -0.339 | 0.062 | 0.323 | 0.044 | 0.014 | -0.210 | 0.435 | -0.110 | | |
| | 6613 | OTHR | 0.304 | -9.650 | 0.657 | 0.346 | 4.774 | -0.019 | 0.458 | -1.820 | |
| | | TEMP | 4.014 | 0.624 | -0.376 | -16.392 | -12.231 | -0.024 | 0.838 | -1.943 | |
| | | EQEW | -1.347 | 0.069 | 0.314 | 0.642 | 2.502 | 0.025 | -0.155 | -0.972 | |
| | | EQNS | -1.375 | 1.345 | -1.301 | -0.577 | -1.769 | 0.318 | -0.089 | 0.297 | |
| | | EQZ | 0.176 | 1.114 | -0.128 | -0.210 | -1.696 | 0.113 | 0.019 | 0.609 | |
| | | EQT | -0.001 | -0.104 | 0.278 | 0.051 | 0.156 | -0.040 | -0.042 | -0.050 | |
| | | SPKW | 0.387 | -0.006 | -0.005 | 0.292 | 0.015 | -0.028 | 0.061 | 0.003 | |
| | | SPKN | -1.150 | 0.087 | 0.014 | -0.244 | 0.011 | 0.045 | -0.060 | -0.228 | |
| | 6624 | OTHR | 0.355 | -6.546 | 0.817 | 1.271 | 6.234 | 0.050 | 0.962 | -1.712 | |
| | | TEMP | 4.131 | 0.639 | 0.234 | -16.379 | -12.033 | 0.102 | -1.077 | -1.799 | |
| | | EQEW | -0.190 | 0.065 | 4.374 | -0.010 | 0.231 | -0.176 | 0.137 | -0.087 | |
| | | EQNS | 0.293 | 3.518 | -0.102 | 0.328 | -0.109 | 0.011 | -0.062 | 0.073 | |
| | | EQZ | 0.091 | 1.069 | -0.073 | -0.227 | -1.697 | -0.114 | -0.019 | 0.598 | |
| | | EQT | -0.030 | -0.003 | 0.423 | -0.013 | 0.017 | -0.034 | -0.008 | -0.011 | |
| | | SPKW | -1.363 | 0.123 | 0.037 | -0.280 | -0.015 | -0.035 | 0.045 | -0.233 | |
| | | SPKN | 0.393 | -0.065 | 0.000 | 0.276 | -0.009 | 0.013 | -0.033 | 0.028 | |
| | 4 RCCV Wetwell Bottom | 1806 | OTHR | 1.426 | -1.513 | -0.077 | 0.601 | 3.795 | 0.015 | 0.012 | 1.464 |
| | | | TEMP | -2.089 | -1.627 | -0.394 | -10.252 | -14.421 | 0.073 | 0.070 | -1.432 |
| | | | EQEW | 0.729 | 4.585 | -4.703 | -0.176 | -0.955 | -0.027 | 0.011 | -0.377 |
| EQNS | | | -1.663 | -1.606 | -3.784 | 0.241 | 1.992 | -0.076 | 0.018 | 0.733 | |
| EQZ | | | 0.276 | 3.169 | -0.099 | 0.073 | 0.469 | -0.006 | 0.001 | 0.100 | |
| EQT | | | 0.108 | 0.050 | 0.777 | -0.002 | -0.048 | -0.016 | 0.000 | -0.025 | |
| SPKW | | | -0.433 | 0.096 | 0.283 | -0.005 | 0.013 | 0.055 | 0.007 | 0.053 | |
| SPKN | | | -0.162 | 0.088 | 0.000 | -0.036 | -0.034 | -0.020 | 0.002 | 0.001 | |
| 1813 | | OTHR | 0.897 | -2.056 | 0.292 | 0.643 | 4.075 | 0.012 | -0.015 | 1.685 | |
| | | TEMP | -2.608 | -4.438 | -0.288 | -9.980 | -13.822 | -0.044 | -0.007 | -1.104 | |
| | | EQEW | 1.114 | 5.859 | 0.928 | -0.274 | -1.581 | -0.011 | 0.006 | -0.664 | |
| | | EQNS | -0.371 | 3.027 | -4.441 | 0.119 | 0.882 | -0.034 | 0.019 | 0.352 | |
| | | EQZ | 0.403 | 3.198 | -0.126 | 0.071 | 0.390 | -0.005 | 0.001 | 0.066 | |
| | | EQT | 0.096 | -0.035 | 0.890 | -0.008 | -0.050 | -0.028 | 0.001 | -0.036 | |
| | | SPKW | 0.032 | -0.028 | -0.069 | 0.037 | -0.031 | -0.001 | 0.003 | 0.029 | |
| | | SPKN | -0.468 | 0.064 | 0.168 | -0.033 | 0.031 | 0.000 | -0.006 | 0.050 | |
| 1824 | | OTHR | 0.692 | -2.498 | -0.008 | 0.706 | 4.109 | 0.021 | -0.017 | 1.748 | |
| | | TEMP | -1.725 | -4.483 | 0.172 | -10.129 | -13.767 | 0.031 | -0.103 | -1.054 | |
| | | EQEW | 0.071 | 0.451 | 7.426 | -0.033 | -0.119 | 0.094 | -0.059 | -0.064 | |
| | | EQNS | 0.906 | 6.607 | -0.267 | -0.034 | -0.345 | -0.011 | 0.003 | -0.240 | |
| | | EQZ | 0.327 | 3.634 | 0.042 | 0.074 | 0.449 | 0.000 | 0.002 | 0.092 | |
| | | EQT | 0.002 | -0.002 | 1.125 | -0.003 | -0.005 | -0.013 | -0.004 | -0.003 | |
| | | SPKW | -0.581 | 0.147 | -0.037 | -0.044 | 0.047 | -0.002 | 0.005 | 0.063 | |
| | | SPKN | -0.022 | -0.020 | 0.071 | 0.051 | -0.010 | 0.003 | -0.013 | 0.041 | |

Table 3G.1-26
Combined Forces and Moments: RCCV, Selected Load Combination CV-11b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|---------------------------------|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 5 RCCV Wetwell Mid-Height | 2606 | OTHR | 3.262 | -1.242 | -0.204 | -0.185 | -0.688 | -0.011 | 0.008 | -0.235 | |
| | | TEMP | -4.378 | -2.154 | -0.405 | -9.998 | -7.615 | 0.005 | 0.039 | 0.073 | |
| | | EQEW | 0.042 | 3.102 | -4.217 | 0.030 | 0.120 | -0.061 | -0.007 | -0.089 | |
| | | EQNS | -0.421 | -1.104 | -3.924 | -0.087 | -0.098 | -0.120 | -0.018 | 0.181 | |
| | | EQZ | 0.129 | 2.896 | -0.130 | -0.004 | 0.020 | -0.007 | 0.001 | 0.061 | |
| | | EQT | 0.002 | 0.036 | 0.741 | 0.003 | 0.003 | -0.019 | 0.005 | -0.004 | |
| | | SPKW | -0.080 | 0.068 | 0.138 | -0.013 | -0.040 | 0.018 | 0.004 | 0.001 | |
| | | SPKN | -0.084 | 0.034 | -0.014 | -0.017 | 0.001 | -0.018 | -0.003 | -0.002 | |
| | 2613 | OTHR | 2.771 | -1.844 | 0.312 | -0.230 | -0.777 | 0.014 | -0.002 | -0.137 | |
| | | TEMP | -5.309 | -5.586 | 0.063 | -9.714 | -7.480 | -0.018 | -0.096 | 0.442 | |
| | | EQEW | -0.005 | 4.069 | 0.921 | 0.044 | 0.171 | -0.017 | -0.010 | -0.249 | |
| | | EQNS | -0.798 | 2.750 | -4.413 | -0.053 | -0.089 | -0.036 | -0.024 | 0.163 | |
| | | EQZ | 0.199 | 2.967 | -0.138 | 0.020 | 0.040 | -0.003 | 0.000 | 0.040 | |
| | | EQT | 0.102 | -0.088 | 0.859 | 0.011 | 0.023 | -0.025 | -0.002 | -0.011 | |
| | | SPKW | 0.224 | 0.087 | -0.048 | 0.025 | -0.043 | -0.002 | 0.000 | 0.018 | |
| | | SPKN | -0.291 | -0.003 | 0.164 | -0.035 | -0.019 | 0.005 | 0.002 | -0.008 | |
| | 2624 | OTHR | 3.081 | -2.051 | 0.035 | -0.145 | -0.859 | 0.001 | 0.006 | -0.258 | |
| | | TEMP | -4.767 | -5.072 | -0.072 | -10.108 | -7.790 | -0.038 | 0.082 | 0.381 | |
| | | EQEW | 0.046 | 0.198 | 6.829 | 0.008 | 0.044 | 0.103 | 0.036 | -0.013 | |
| | | EQNS | -0.044 | 5.027 | -0.262 | 0.099 | 0.205 | -0.005 | -0.005 | -0.062 | |
| | | EQZ | 0.193 | 3.390 | 0.018 | -0.013 | -0.002 | 0.000 | 0.002 | 0.080 | |
| | | EQT | -0.002 | -0.017 | 0.934 | -0.001 | 0.006 | -0.019 | 0.003 | 0.000 | |
| | | SPKW | -0.284 | 0.016 | -0.021 | -0.043 | -0.029 | -0.005 | 0.004 | -0.020 | |
| | | SPKN | 0.208 | 0.115 | 0.031 | 0.023 | -0.048 | 0.002 | -0.003 | 0.032 | |
| 6 RCCV Wetwell Top | 3406 | OTHR | 2.368 | -0.738 | -0.033 | -0.022 | 0.040 | 0.036 | -0.024 | 0.008 | |
| | | TEMP | 5.146 | -1.793 | 0.374 | -10.845 | -13.921 | 0.028 | 0.122 | 2.434 | |
| | | EQEW | -0.398 | 1.932 | -3.913 | 0.030 | 0.165 | -0.110 | 0.074 | -0.089 | |
| | | EQNS | -0.091 | -0.510 | -3.585 | -0.105 | -0.299 | -0.018 | -0.047 | 0.142 | |
| | | EQZ | 0.195 | 2.546 | -0.179 | -0.076 | -0.463 | 0.034 | -0.071 | 0.157 | |
| | | EQT | 0.052 | -0.005 | 0.713 | -0.006 | -0.021 | -0.024 | -0.003 | 0.008 | |
| | | SPKW | -0.019 | 0.052 | 0.051 | -0.006 | -0.011 | 0.016 | -0.012 | -0.006 | |
| | | SPKN | -0.031 | 0.005 | 0.025 | -0.001 | 0.012 | -0.012 | 0.007 | -0.006 | |
| | | 3413 | OTHR | 1.937 | -1.695 | 0.218 | -0.081 | -0.106 | -0.087 | 0.055 | 0.053 |
| | | | TEMP | 3.360 | -7.377 | 0.327 | -10.754 | -14.083 | -0.105 | 0.111 | 2.634 |
| | | | EQEW | -0.289 | 2.645 | 0.971 | 0.054 | 0.321 | 0.036 | -0.062 | -0.227 |
| | | | EQNS | -0.662 | 2.398 | -4.252 | -0.039 | -0.196 | -0.071 | 0.067 | 0.077 |
| | EQZ | | 0.063 | 2.823 | -0.097 | -0.025 | -0.210 | 0.004 | 0.016 | 0.076 | |
| | EQT | | 0.091 | -0.104 | 0.873 | 0.007 | 0.025 | -0.013 | -0.010 | -0.005 | |
| | 3424 | SPKW | 0.132 | 0.130 | -0.025 | 0.009 | -0.056 | -0.004 | 0.004 | 0.033 | |
| | | SPKN | -0.166 | -0.041 | 0.094 | -0.011 | 0.022 | 0.001 | -0.002 | -0.021 | |
| | | OTHR | 1.931 | -1.413 | 0.062 | 0.076 | 0.252 | 0.004 | 0.016 | -0.044 | |
| | | TEMP | 3.550 | -6.962 | 0.378 | -10.104 | -10.258 | 0.043 | -0.160 | 1.032 | |
| | | EQEW | -0.187 | 0.123 | 5.910 | 0.017 | 0.013 | 0.010 | 0.005 | 0.006 | |
| | | EQNS | -0.518 | 3.812 | -0.168 | 0.065 | 0.270 | 0.045 | -0.033 | -0.081 | |
| | | EQZ | 0.120 | 3.010 | -0.010 | -0.059 | -0.305 | 0.045 | -0.058 | 0.079 | |
| | | EQT | -0.032 | -0.004 | 0.782 | -0.001 | -0.004 | -0.024 | -0.007 | 0.004 | |
| | | SPKW | -0.147 | -0.044 | -0.004 | -0.005 | 0.046 | -0.004 | 0.002 | -0.031 | |
| | | SPKN | 0.183 | 0.153 | 0.008 | -0.008 | -0.136 | 0.003 | -0.004 | 0.053 | |

Table 3G.1-26
Combined Forces and Moments: RCCV, Selected Load Combination CV-11b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|-----------------------------|---------------------------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 7 RCCV Drywell Bottom | 3606 | OTHR | 2.307 | -0.345 | -0.150 | 0.001 | 0.204 | 0.058 | -0.004 | 0.458 | |
| | | TEMP | 0.855 | -1.873 | -0.034 | -12.684 | -14.715 | 0.245 | 0.161 | -0.543 | |
| | | EQEW | -0.452 | 1.766 | -3.473 | -0.041 | -0.248 | -0.085 | 0.065 | -0.016 | |
| | | EQNS | -0.031 | -0.141 | -3.512 | 0.074 | 0.711 | 0.047 | -0.003 | 0.201 | |
| | | EQZ | 0.062 | 2.442 | -0.034 | 0.009 | -0.005 | 0.039 | -0.062 | -0.045 | |
| | | EQT | 0.059 | -0.015 | 0.652 | -0.012 | -0.046 | -0.022 | -0.003 | -0.015 | |
| | | SPKW | -0.017 | 0.050 | 0.033 | -0.003 | 0.004 | -0.002 | -0.012 | 0.002 | |
| | SPKN | -0.026 | 0.005 | 0.016 | 0.000 | 0.012 | 0.001 | 0.008 | 0.005 | | |
| | 3613 | OTHR | 1.914 | -1.363 | 0.249 | 0.034 | 0.546 | -0.052 | 0.018 | 0.692 | |
| | | TEMP | -1.019 | -8.771 | 1.274 | -12.290 | -13.057 | -0.280 | 0.001 | -0.234 | |
| | | EQEW | -0.265 | 2.846 | 1.125 | -0.134 | -0.780 | -0.006 | -0.052 | -0.296 | |
| | | EQNS | -0.698 | 2.066 | -3.945 | 0.081 | 0.502 | -0.070 | 0.057 | 0.204 | |
| | | EQZ | -0.070 | 2.782 | -0.112 | 0.007 | 0.010 | -0.009 | 0.017 | -0.131 | |
| | | EQT | 0.095 | -0.082 | 0.789 | -0.001 | -0.019 | -0.016 | -0.009 | -0.006 | |
| | | SPKW | 0.103 | 0.099 | -0.019 | 0.022 | 0.033 | -0.002 | 0.003 | 0.004 | |
| | SPKN | -0.143 | -0.041 | 0.051 | -0.011 | 0.011 | -0.001 | -0.002 | 0.013 | | |
| | 3624 | OTHR | 1.814 | -1.444 | 0.092 | 0.193 | 0.906 | 0.014 | 0.022 | 0.641 | |
| | | TEMP | -10.073 | -8.472 | 0.316 | -7.314 | -7.358 | 0.070 | -0.111 | 1.306 | |
| | | EQEW | -0.126 | 0.166 | 5.784 | -0.041 | -0.106 | 0.041 | 0.024 | -0.050 | |
| | | EQNS | -0.550 | 3.914 | -0.186 | -0.048 | -0.303 | 0.055 | -0.007 | -0.021 | |
| | | EQZ | 0.078 | 3.186 | -0.058 | -0.032 | -0.159 | 0.047 | -0.033 | -0.095 | |
| | | EQT | -0.021 | -0.004 | 0.787 | -0.007 | -0.013 | -0.022 | -0.005 | -0.006 | |
| | | SPKW | -0.123 | -0.026 | -0.002 | -0.011 | -0.001 | 0.000 | 0.002 | 0.005 | |
| | SPKN | 0.142 | 0.069 | 0.005 | 0.022 | 0.048 | -0.001 | -0.004 | 0.008 | | |
| | 8 RCCV Drywell Mid-Height | 4006 | OTHR | 1.708 | -0.083 | -0.103 | -0.094 | -0.323 | 0.007 | 0.026 | -0.160 |
| | | | TEMP | 1.877 | -1.562 | -0.442 | -12.483 | -13.207 | 0.139 | -0.296 | -0.380 |
| | | | EQEW | -0.910 | 0.987 | -3.270 | 0.020 | 0.052 | -0.092 | -0.017 | -0.156 |
| EQNS | | | 0.790 | 0.233 | -3.141 | -0.077 | -0.071 | -0.062 | 0.029 | 0.261 | |
| EQZ | | | -0.449 | 2.407 | 0.073 | 0.095 | 0.356 | 0.041 | 0.003 | -0.161 | |
| EQT | | | 0.019 | -0.053 | 0.620 | -0.001 | -0.016 | -0.024 | 0.000 | -0.007 | |
| SPKW | | | -0.013 | 0.044 | 0.005 | -0.003 | 0.001 | 0.010 | -0.001 | -0.001 | |
| SPKN | | -0.014 | 0.006 | 0.039 | 0.001 | -0.004 | -0.006 | 0.001 | 0.002 | | |
| 4013 | | OTHR | 1.611 | -1.516 | 0.377 | -0.124 | -0.443 | 0.004 | -0.008 | -0.151 | |
| | | TEMP | 1.214 | -10.590 | 1.149 | -12.238 | -11.748 | 0.051 | -0.198 | -0.348 | |
| | | EQEW | -1.066 | 1.762 | 0.993 | 0.076 | 0.313 | 0.008 | -0.022 | -0.324 | |
| | | EQNS | -0.292 | 2.306 | -3.780 | -0.012 | -0.067 | -0.088 | 0.014 | 0.108 | |
| | | EQZ | -0.429 | 2.930 | -0.188 | 0.043 | 0.368 | 0.001 | 0.006 | -0.071 | |
| | | EQT | 0.077 | -0.117 | 0.773 | -0.003 | -0.022 | -0.006 | -0.001 | 0.008 | |
| | | SPKW | 0.058 | 0.139 | -0.017 | 0.011 | 0.005 | -0.002 | 0.000 | 0.014 | |
| SPKN | | -0.064 | -0.052 | 0.039 | -0.010 | -0.009 | -0.001 | 0.000 | -0.003 | | |
| 4976 | | OTHR | 1.442 | -0.846 | 0.125 | 0.010 | -0.170 | 0.010 | -0.011 | -0.194 | |
| | | TEMP | -8.101 | -7.344 | 0.924 | -7.622 | -8.430 | 0.004 | 0.035 | -0.545 | |
| | | EQEW | 0.115 | 0.026 | 5.969 | 0.045 | 0.045 | 0.059 | 0.041 | -0.021 | |
| | | EQNS | -0.454 | 3.036 | -0.266 | -0.063 | -0.168 | -0.016 | 0.009 | -0.046 | |
| | | EQZ | -0.086 | 2.647 | -0.162 | 0.018 | 0.189 | 0.003 | 0.005 | -0.084 | |
| | | EQT | 0.030 | -0.017 | 0.833 | 0.005 | 0.002 | -0.016 | 0.006 | -0.001 | |
| | | SPKW | -0.050 | -0.035 | 0.003 | -0.004 | 0.006 | -0.002 | 0.000 | -0.009 | |
| SPKN | | 0.067 | 0.077 | -0.003 | 0.007 | -0.007 | 0.002 | -0.001 | 0.019 | | |

**Table 3G.1-26
Combined Forces and Moments: RCCV, Selected Load Combination CV-11b (Continued)**

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|--------------------------|------------------------|-------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 9 RCCV Drywell Top | 4406 | OTHR | 0.619 | 0.175 | -0.078 | 0.216 | 1.213 | -0.016 | -0.016 | -0.432 | |
| | | TEMP | 0.823 | -3.764 | -3.737 | -11.621 | -12.462 | 0.691 | -0.182 | -0.529 | |
| | | EQEW | -1.432 | 0.273 | -2.870 | 0.144 | 0.700 | -0.008 | 0.016 | -0.292 | |
| | | EQNS | 1.184 | 1.012 | -2.125 | -0.314 | -1.191 | 0.022 | 0.092 | 0.455 | |
| | | EQZ | -0.124 | 2.743 | 0.734 | 0.154 | 1.012 | 0.008 | -0.003 | -0.180 | |
| | | EQT | -0.058 | -0.128 | 0.705 | 0.017 | 0.085 | -0.019 | -0.034 | -0.040 | |
| | | SPKW | -0.005 | 0.045 | 0.000 | -0.001 | 0.004 | 0.006 | 0.009 | -0.001 | |
| | 4413 | SPKN | -0.010 | 0.008 | 0.051 | -0.001 | -0.009 | -0.004 | -0.005 | 0.000 | |
| | | OTHR | 0.121 | -1.684 | 0.335 | 0.163 | 1.400 | 0.040 | 0.009 | -0.564 | |
| | | TEMP | -1.109 | -11.745 | -0.412 | -12.243 | -11.597 | 0.480 | -0.143 | 0.316 | |
| | | EQEW | -1.216 | 0.860 | 0.828 | 0.183 | 1.145 | 0.044 | 0.052 | -0.240 | |
| | | EQNS | 0.714 | 2.598 | -3.377 | -0.009 | -0.368 | -0.034 | -0.042 | 0.072 | |
| | | EQZ | 0.349 | 3.050 | -0.086 | 0.139 | 0.731 | -0.005 | 0.010 | -0.144 | |
| | | EQT | -0.003 | -0.148 | 0.957 | 0.006 | 0.052 | -0.010 | -0.002 | -0.030 | |
| | 4424 | SPKW | 0.085 | 0.166 | -0.005 | -0.005 | -0.062 | 0.001 | 0.000 | 0.027 | |
| | | SPKN | -0.051 | -0.051 | 0.033 | -0.001 | 0.016 | 0.000 | 0.000 | -0.013 | |
| | | OTHR | 0.999 | -0.380 | 0.099 | 0.265 | 1.433 | 0.021 | 0.003 | -0.483 | |
| | | TEMP | -11.976 | -5.333 | 1.168 | -6.791 | -4.544 | -0.050 | -0.027 | -2.329 | |
| | | EQEW | 0.212 | -0.022 | 6.191 | 0.053 | 0.031 | 0.004 | 0.056 | 0.017 | |
| | | EQNS | -0.865 | 2.281 | -0.226 | -0.048 | -0.330 | -0.020 | -0.004 | -0.009 | |
| | | EQZ | -0.042 | 2.067 | -0.135 | 0.054 | 0.448 | -0.003 | 0.000 | -0.085 | |
| | 10 Basemat @ Center | 80003 | EQT | 0.048 | -0.016 | 1.133 | 0.008 | 0.006 | -0.013 | -0.009 | 0.001 |
| | | | SPKW | -0.016 | -0.034 | 0.004 | 0.006 | 0.045 | 0.000 | -0.001 | -0.016 |
| | | | SPKN | 0.027 | 0.069 | -0.003 | -0.011 | -0.079 | 0.000 | 0.001 | 0.029 |
| | | | OTHR | -1.855 | -0.771 | 0.112 | -0.116 | 0.322 | 0.026 | 0.488 | -0.370 |
| | | | TEMP | -1.459 | -2.034 | -0.010 | -4.165 | -4.332 | -0.019 | 0.027 | -0.018 |
| | | | EQEW | 0.003 | 0.113 | 0.970 | 0.137 | 0.241 | -0.184 | 0.020 | 0.540 |
| EQNS | | | 3.586 | 2.842 | -0.331 | -4.691 | -4.176 | 0.064 | 0.477 | 0.092 | |
| EQZ | | | 1.176 | 1.338 | -0.029 | -3.648 | -3.734 | 0.003 | -0.174 | 0.134 | |
| EQT | | | 0.037 | -0.014 | 0.415 | 0.005 | 0.011 | -0.032 | 0.006 | 0.031 | |
| SPKW | | | 0.503 | -1.631 | -0.002 | 0.153 | 0.078 | -0.003 | -0.012 | -0.008 | |
| 80007 | | SPKN | -1.793 | 0.512 | 0.019 | 0.092 | 0.131 | -0.015 | 0.022 | 0.007 | |
| | | OTHR | -1.890 | -0.826 | 0.066 | 0.061 | 0.359 | 0.053 | 0.234 | -0.488 | |
| | | TEMP | -1.464 | -1.995 | 0.022 | -4.146 | -4.332 | -0.017 | 0.015 | -0.025 | |
| | | EQEW | 0.363 | -0.256 | 0.505 | 0.315 | 0.349 | -0.067 | -0.002 | 0.512 | |
| | | EQNS | 3.503 | 2.916 | -0.316 | -4.254 | -4.033 | 0.165 | 0.614 | 0.111 | |
| | | EQZ | 1.185 | 1.348 | -0.024 | -3.657 | -3.736 | 0.001 | 0.023 | 0.216 | |
| | | EQT | 0.062 | -0.063 | 0.349 | 0.016 | 0.016 | -0.025 | 0.009 | 0.028 | |
| | | SPKW | 0.508 | -1.633 | -0.003 | 0.149 | 0.079 | -0.003 | -0.002 | -0.006 | |
| | | SPKN | -1.791 | 0.519 | 0.021 | 0.100 | 0.135 | -0.012 | 0.011 | 0.004 | |
| | | 80012 | OTHR | -1.987 | -0.895 | 0.086 | 0.269 | 0.561 | -0.054 | -0.045 | -0.239 |
| TEMP | | | -1.470 | -1.929 | 0.013 | -4.141 | -4.342 | -0.014 | -0.003 | -0.003 | |
| EQEW | | | -0.098 | 0.116 | 0.355 | 0.055 | 0.059 | 0.106 | -0.005 | 0.558 | |
| EQNS | | | 3.205 | 3.049 | -0.151 | -3.908 | -3.829 | 0.022 | 0.680 | -0.001 | |
| EQZ | | | 1.185 | 1.364 | -0.024 | -3.656 | -3.737 | 0.002 | 0.208 | 0.029 | |
| EQT | | | 0.024 | -0.016 | 0.318 | 0.003 | 0.001 | -0.016 | 0.003 | 0.030 | |
| SPKW | | | 0.516 | -1.630 | 0.001 | 0.143 | 0.078 | -0.003 | 0.001 | -0.002 | |
| SPKN | | | -1.793 | 0.522 | 0.020 | 0.111 | 0.146 | -0.016 | 0.007 | 0.001 | |

**Table 3G.1-26
Combined Forces and Moments: RCCV, Selected Load Combination CV-11b (Continued)**

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|--------------------------------------|----------------------|--------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|--------|
| 11 Basemat Inside RPV Pedestal | 80206 | OTHR | -1.301 | -0.634 | 0.258 | -4.446 | -3.850 | 1.787 | 1.824 | -1.781 | |
| | | TEMP | -1.452 | -2.440 | 0.102 | -4.566 | -4.902 | 0.112 | -0.003 | -0.132 | |
| | | EQEW | 1.123 | -0.469 | 2.151 | 2.151 | 2.565 | -1.023 | -0.541 | 1.016 | |
| | | EQNS | 4.320 | 2.471 | -1.054 | -6.305 | -4.299 | 0.491 | 0.742 | 0.202 | |
| | | EQZ | 1.149 | 1.282 | -0.043 | -1.685 | -1.928 | -0.649 | -0.747 | 0.658 | |
| | | EQT | 0.104 | -0.077 | 0.574 | -0.151 | 0.217 | -0.100 | 0.111 | 0.160 | |
| | | SPKW | 0.385 | -1.507 | -0.021 | 0.051 | 0.222 | -0.006 | 0.084 | 0.094 | |
| | SPKN | -1.718 | 0.364 | 0.005 | 0.174 | -0.067 | 0.002 | -0.077 | -0.102 | | |
| | 80213 | OTHR | -1.511 | -0.742 | 0.135 | -2.126 | -5.197 | 0.636 | 0.628 | -2.368 | |
| | | TEMP | -1.560 | -1.931 | 0.037 | -4.415 | -4.996 | -0.075 | -0.008 | -0.208 | |
| | | EQEW | 1.929 | -0.848 | 0.482 | 2.692 | 4.698 | 0.061 | 0.096 | 1.708 | |
| | | EQNS | 3.499 | 2.910 | -1.544 | -3.171 | -2.170 | 1.378 | 1.189 | 0.724 | |
| | | EQZ | 1.179 | 1.367 | -0.064 | -2.356 | -1.102 | 0.052 | 0.028 | 1.027 | |
| | | EQT | 0.217 | -0.076 | 0.421 | 0.124 | 0.163 | 0.087 | 0.136 | 0.041 | |
| | | SPKW | 0.312 | -1.636 | -0.043 | -0.034 | 0.008 | 0.016 | -0.002 | 0.005 | |
| | SPKN | -1.592 | 0.519 | 0.012 | 0.279 | 0.202 | -0.018 | -0.006 | -0.006 | | |
| | 80224 | OTHR | -2.296 | -1.506 | -0.004 | -2.546 | -1.579 | -0.774 | -1.518 | -0.753 | |
| | | TEMP | -1.413 | -1.845 | 0.033 | -4.392 | -4.556 | -0.029 | -0.087 | 0.015 | |
| | | EQEW | 0.076 | 0.039 | -1.798 | 0.300 | 0.206 | 0.366 | 0.075 | 0.061 | |
| | | EQNS | 2.510 | 3.600 | -0.146 | 1.629 | -1.229 | 0.129 | 1.970 | 0.063 | |
| | | EQZ | 1.233 | 1.441 | -0.024 | -1.139 | -2.368 | 0.090 | 0.999 | 0.079 | |
| | | EQT | 0.029 | -0.016 | -0.094 | 0.040 | -0.001 | -0.126 | 0.011 | -0.150 | |
| | | SPKW | 0.558 | -1.432 | 0.002 | 0.166 | 0.244 | 0.006 | -0.016 | 0.014 | |
| | SPKN | -1.804 | 0.342 | 0.016 | 0.082 | 0.010 | -0.007 | 0.010 | 0.000 | | |
| | 12 S/P Slab @ RPV | 83306 | OTHR | -0.628 | 2.091 | -0.460 | -0.911 | 0.921 | -0.127 | 3.664 | -0.060 |
| | | | TEMP | -9.972 | 1.598 | -0.064 | -9.481 | -8.299 | 0.020 | -0.052 | -0.031 |
| | | | EQEW | -0.804 | -0.320 | 1.004 | 1.133 | 0.470 | -0.277 | 0.459 | 0.135 |
| | | | EQNS | -0.024 | -1.056 | -1.566 | -2.820 | -1.643 | -0.313 | -1.032 | 0.123 |
| EQZ | | | -0.124 | -0.267 | 0.146 | -1.455 | -0.965 | 0.018 | -0.734 | 0.021 | |
| EQT | | | -0.015 | 0.015 | -0.033 | 0.056 | 0.025 | -0.023 | 0.017 | 0.014 | |
| SPKW | | | -0.450 | -0.624 | 1.118 | -0.045 | -0.038 | 0.007 | -0.032 | 0.005 | |
| SPKN | | -0.194 | -0.406 | -0.948 | -0.019 | -0.016 | 0.004 | -0.008 | -0.004 | | |
| 83313 | | OTHR | 0.001 | 1.742 | -0.867 | -0.814 | 1.037 | -0.164 | 3.705 | 0.055 | |
| | | TEMP | -10.412 | 2.279 | 0.020 | -9.487 | -8.358 | -0.018 | -0.032 | 0.009 | |
| | | EQEW | -1.336 | -0.260 | 0.171 | 1.627 | 0.736 | 0.021 | 0.659 | -0.015 | |
| | | EQNS | -0.431 | -1.505 | 0.783 | -1.652 | -1.076 | -0.449 | -0.591 | 0.167 | |
| | | EQZ | -0.247 | -0.187 | 0.074 | -1.467 | -0.967 | -0.012 | -0.738 | -0.021 | |
| | | EQT | -0.008 | 0.052 | -0.097 | 0.100 | 0.051 | 0.005 | 0.037 | 0.005 | |
| | | SPKW | -0.598 | 0.253 | -0.089 | -0.057 | -0.032 | 0.000 | -0.057 | 0.001 | |
| SPKN | | -0.208 | -0.985 | 0.124 | -0.025 | -0.021 | -0.001 | -0.004 | -0.003 | | |
| 83324 | | OTHR | 1.847 | 1.966 | -0.687 | -0.497 | 1.443 | -0.193 | 3.909 | -0.074 | |
| | | TEMP | -10.086 | 2.442 | 0.535 | -9.394 | -8.241 | -0.004 | 0.012 | 0.009 | |
| | | EQEW | -0.175 | -0.020 | -1.709 | 0.074 | 0.043 | 0.410 | 0.039 | -0.175 | |
| | | EQNS | -0.623 | -0.113 | 0.101 | -0.297 | -0.317 | -0.028 | -0.051 | 0.017 | |
| | | EQZ | -0.232 | -0.288 | -0.002 | -1.473 | -0.971 | 0.018 | -0.742 | 0.020 | |
| | | EQT | -0.007 | -0.012 | -0.225 | 0.007 | 0.004 | 0.029 | 0.002 | -0.011 | |
| | | SPKW | -0.201 | -1.214 | -0.128 | -0.044 | -0.044 | 0.000 | -0.012 | 0.004 | |
| SPKN | | -0.482 | 0.259 | 0.061 | -0.046 | -0.017 | 0.000 | -0.051 | -0.002 | | |

Table 3G.1-26
Combined Forces and Moments: RCCV, Selected Load Combination CV-11b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|-------------------------|-----------------------|--------|--------------|--------------|---------------|---------------|---------------|----------------|-----------|-----------|--------|
| 13 S/P Slab @ Center | 83406 | OTHR | -0.086 | 1.914 | -0.422 | -5.651 | -1.475 | -0.038 | -0.326 | 0.000 | |
| | | TEMP | -6.718 | -1.759 | -0.385 | -8.944 | -8.523 | -0.007 | -0.094 | 0.009 | |
| | | EQEW | -0.707 | 0.030 | 0.424 | -0.259 | 0.175 | -0.189 | 0.290 | 0.000 | |
| | | EQNS | 0.042 | -1.356 | -1.365 | 0.433 | -0.909 | -0.224 | -0.712 | -0.011 | |
| | | EQZ | -0.143 | -0.260 | 0.105 | 0.552 | -0.468 | 0.003 | -0.366 | 0.000 | |
| | | EQT | -0.012 | 0.060 | 0.007 | 0.004 | 0.009 | -0.018 | 0.012 | 0.001 | |
| | | SPKW | -0.388 | -0.588 | 0.846 | 0.055 | -0.010 | -0.007 | -0.024 | 0.012 | |
| | SPKN | -0.186 | -0.377 | -0.648 | 0.009 | -0.009 | 0.009 | -0.006 | -0.005 | | |
| | 83413 | OTHR | 0.684 | 1.543 | -0.376 | -5.659 | -1.422 | -0.112 | -0.295 | 0.004 | |
| | | TEMP | -7.659 | -0.903 | 0.493 | -9.069 | -8.607 | -0.009 | -0.043 | -0.004 | |
| | | EQEW | -1.249 | -0.033 | 0.148 | -0.337 | 0.283 | 0.028 | 0.418 | 0.001 | |
| | | EQNS | -0.317 | -1.137 | 0.740 | 0.244 | -0.656 | -0.297 | -0.419 | 0.010 | |
| | | EQZ | -0.294 | -0.142 | 0.032 | 0.545 | -0.458 | 0.002 | -0.369 | -0.002 | |
| | | EQT | -0.017 | 0.072 | -0.049 | -0.008 | 0.023 | 0.003 | 0.024 | -0.001 | |
| | | SPKW | -0.916 | 0.099 | -0.048 | 0.119 | 0.017 | 0.001 | -0.042 | 0.000 | |
| | | SPKN | -0.003 | -0.766 | 0.028 | -0.010 | -0.017 | -0.004 | -0.004 | 0.001 | |
| | 83424 | OTHR | 1.805 | 1.563 | -0.297 | -5.712 | -1.212 | -0.093 | -0.220 | 0.004 | |
| | | TEMP | -6.972 | -0.779 | -0.021 | -9.008 | -8.518 | 0.002 | -0.039 | 0.004 | |
| | | EQEW | -0.106 | -0.009 | -0.929 | -0.033 | 0.010 | 0.268 | 0.026 | 0.015 | |
| | | EQNS | -0.869 | -0.164 | 0.069 | 0.039 | -0.327 | -0.018 | -0.075 | 0.000 | |
| | | EQZ | -0.256 | -0.261 | -0.004 | 0.553 | -0.457 | 0.001 | -0.373 | 0.001 | |
| | | EQT | 0.003 | -0.010 | -0.130 | -0.001 | 0.002 | 0.019 | 0.002 | 0.000 | |
| | | SPKW | 0.053 | -0.975 | -0.101 | -0.006 | -0.031 | 0.001 | -0.009 | -0.001 | |
| | | SPKN | -0.791 | 0.077 | 0.054 | 0.112 | 0.025 | -0.001 | -0.037 | 0.001 | |
| | 14 S/P Slab @ RCCV | 83506 | OTHR | 0.388 | 1.806 | -0.283 | 2.552 | -0.420 | -0.031 | -3.437 | -0.003 |
| | | | TEMP | -5.228 | -3.030 | -0.183 | -8.795 | -8.644 | -0.044 | -0.124 | 0.014 |
| | | | EQEW | -0.506 | -0.030 | 0.101 | -1.095 | -0.198 | -0.003 | 0.234 | -0.050 |
| EQNS | | | 0.316 | -1.405 | -1.038 | 2.407 | 0.020 | -0.029 | -0.546 | -0.048 | |
| EQZ | | | -0.144 | -0.236 | 0.096 | 1.146 | -0.010 | 0.006 | -0.102 | -0.002 | |
| EQT | | | -0.030 | 0.096 | 0.021 | -0.029 | -0.007 | -0.006 | 0.009 | -0.002 | |
| SPKW | | | -0.377 | -0.563 | 0.689 | 0.113 | 0.027 | -0.034 | -0.017 | 0.011 | |
| SPKN | | | -0.113 | -0.291 | -0.437 | 0.018 | 0.000 | 0.015 | -0.002 | -0.002 | |
| 83513 | | | OTHR | 1.044 | 1.490 | -0.279 | 2.456 | -0.404 | -0.044 | -3.413 | -0.007 |
| | | TEMP | -6.407 | -2.664 | 0.563 | -9.202 | -8.697 | -0.010 | 0.002 | 0.004 | |
| | | EQEW | -1.070 | -0.066 | 0.138 | -1.520 | -0.265 | 0.009 | 0.331 | 0.005 | |
| | | EQNS | -0.282 | -0.902 | 0.686 | 1.379 | -0.078 | -0.051 | -0.322 | -0.055 | |
| | | EQZ | -0.304 | -0.128 | 0.012 | 1.156 | 0.003 | 0.003 | -0.108 | -0.003 | |
| | | EQT | -0.012 | 0.090 | -0.031 | -0.076 | -0.008 | 0.006 | 0.019 | -0.001 | |
| | | SPKW | -1.040 | -0.083 | -0.027 | 0.241 | 0.072 | 0.001 | -0.034 | 0.000 | |
| | | SPKN | 0.093 | -0.574 | -0.045 | -0.011 | -0.008 | -0.005 | 0.000 | -0.001 | |
| 83524 | | OTHR | 1.691 | 1.429 | -0.239 | 2.247 | -0.338 | -0.034 | -3.359 | -0.008 | |
| | | TEMP | -5.481 | -2.152 | -0.087 | -9.085 | -8.636 | 0.017 | -0.037 | -0.005 | |
| | | EQEW | -0.061 | -0.032 | -0.577 | -0.110 | -0.025 | -0.026 | 0.023 | 0.083 | |
| | | EQNS | -0.923 | -0.264 | 0.036 | 0.211 | -0.213 | 0.002 | -0.048 | -0.004 | |
| | | EQZ | -0.248 | -0.264 | -0.007 | 1.178 | 0.007 | 0.001 | -0.111 | 0.001 | |
| | | EQT | 0.008 | -0.008 | -0.086 | -0.008 | -0.001 | 0.001 | 0.002 | 0.005 | |
| | | SPKW | 0.171 | -0.733 | -0.086 | 0.000 | -0.013 | 0.003 | -0.003 | 0.000 | |
| | | SPKN | -0.939 | -0.110 | 0.071 | 0.229 | 0.073 | -0.003 | -0.033 | 0.001 | |

Table 3G.1-26
Combined Forces and Moments: RCCV, Selected Load Combination CV-11b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|---|-------------------------|-------|--------------|--------------|---------------|---------------|---------------|----------------|-----------|-----------|--------|
| 15 Top slab @ Drywell Head Opening | 98120 | OTHR | 0.559 | 0.884 | 0.580 | 0.067 | 0.036 | 0.010 | -0.022 | -0.065 | |
| | | TEMP | -12.118 | -11.183 | -5.512 | 6.841 | 6.030 | 5.411 | -0.811 | -0.398 | |
| | | EQEW | -1.292 | -1.085 | -0.943 | -0.055 | -0.435 | -0.121 | -0.057 | -0.066 | |
| | | EQNS | 0.071 | 0.072 | 0.030 | -0.046 | -0.076 | -0.034 | -0.040 | -0.019 | |
| | | EQZ | -0.808 | -0.210 | -0.293 | 0.379 | 0.220 | 0.278 | -0.038 | -0.236 | |
| | | EQT | -0.009 | -0.026 | -0.014 | 0.008 | 0.022 | 0.005 | -0.006 | -0.004 | |
| | | SPKW | 0.031 | -0.011 | 0.008 | -0.005 | 0.003 | -0.001 | 0.002 | 0.002 | |
| | | SPKN | -0.031 | -0.002 | -0.012 | 0.002 | -0.003 | -0.001 | -0.001 | -0.001 | |
| | 98135 | OTHR | 0.244 | 0.225 | -0.222 | 0.113 | -0.223 | 0.099 | 0.113 | -0.149 | |
| | | TEMP | -17.422 | -7.219 | 2.697 | 11.170 | 0.342 | -2.394 | 0.848 | -0.819 | |
| | | EQEW | 0.125 | 0.340 | -0.586 | -0.132 | -0.167 | 0.070 | 0.008 | -0.065 | |
| | | EQNS | 0.622 | 0.061 | -0.118 | -0.162 | -0.016 | 0.026 | 0.008 | 0.000 | |
| | | EQZ | -2.236 | -0.182 | 0.197 | 0.527 | -0.240 | -0.066 | 0.082 | -0.299 | |
| | | EQT | 0.038 | 0.018 | -0.022 | -0.001 | 0.001 | -0.007 | -0.009 | 0.003 | |
| | | SPKW | 0.089 | 0.008 | -0.008 | -0.008 | 0.002 | 0.000 | -0.001 | 0.002 | |
| | | SPKN | -0.097 | -0.013 | 0.017 | 0.004 | -0.002 | 0.001 | 0.001 | -0.001 | |
| | 98104 | OTHR | 0.306 | 1.649 | -0.360 | 0.125 | 0.926 | -0.044 | 0.131 | -0.270 | |
| | | TEMP | -6.925 | -12.999 | 2.994 | 2.265 | 12.026 | -3.290 | 0.606 | -0.472 | |
| | | EQEW | 0.417 | 0.603 | -0.632 | -0.056 | -0.513 | 0.012 | 0.016 | -0.418 | |
| | | EQNS | -0.057 | -1.401 | 0.071 | -0.034 | -0.263 | 0.004 | -0.035 | 0.028 | |
| | | EQZ | -0.066 | -0.456 | 0.069 | 0.172 | 1.050 | -0.219 | 0.002 | -0.239 | |
| | | EQT | 0.020 | 0.039 | -0.032 | -0.008 | -0.029 | 0.009 | -0.002 | -0.017 | |
| | | SPKW | -0.001 | -0.056 | 0.002 | -0.003 | 0.007 | 0.000 | -0.002 | 0.000 | |
| | | SPKN | -0.005 | 0.036 | 0.006 | 0.001 | -0.016 | 0.001 | 0.002 | 0.000 | |
| | 16 Top slab @ Center | 98149 | OTHR | 0.424 | 1.174 | -0.139 | 0.145 | 0.040 | -0.085 | 0.086 | 0.203 |
| | | | TEMP | -11.284 | -4.069 | -0.857 | 4.361 | 5.925 | 0.936 | 0.661 | -1.018 |
| | | | EQEW | -1.003 | -0.296 | -0.570 | 0.004 | -0.119 | -0.001 | 0.055 | -0.012 |
| EQNS | | | 0.296 | 0.658 | 0.077 | -0.091 | 0.043 | -0.048 | -0.055 | 0.067 | |
| EQZ | | | -1.174 | 0.156 | -0.372 | 0.527 | 0.371 | -0.031 | 0.043 | 0.191 | |
| EQT | | | 0.033 | -0.037 | 0.002 | 0.002 | 0.005 | -0.008 | -0.005 | -0.013 | |
| SPKW | | | 0.050 | -0.025 | -0.007 | -0.006 | 0.008 | -0.002 | 0.000 | 0.002 | |
| SPKN | | | -0.050 | -0.002 | 0.004 | 0.004 | -0.004 | 0.000 | -0.001 | -0.001 | |
| 98170 | | OTHR | 0.499 | 0.963 | -0.178 | 0.290 | 0.553 | -0.017 | -0.024 | -0.058 | |
| | | TEMP | -10.473 | -4.943 | 0.330 | 4.246 | 5.164 | -0.051 | 0.133 | 0.663 | |
| | | EQEW | -1.062 | 0.055 | -0.748 | -0.033 | 0.008 | -0.035 | 0.007 | -0.003 | |
| | | EQNS | 0.114 | -0.309 | 0.242 | -0.109 | -0.114 | -0.002 | -0.025 | -0.023 | |
| | | EQZ | -1.023 | 0.029 | -0.024 | 0.653 | 0.874 | -0.004 | 0.011 | 0.023 | |
| | | EQT | 0.033 | 0.043 | -0.026 | -0.001 | -0.003 | -0.009 | 0.003 | 0.001 | |
| | | SPKW | 0.050 | -0.009 | 0.001 | -0.003 | 0.011 | 0.001 | 0.000 | 0.002 | |
| | | SPKN | -0.051 | -0.003 | 0.008 | 0.003 | -0.011 | 0.001 | 0.000 | -0.002 | |
| 98109 | | OTHR | 0.583 | 1.242 | -0.061 | 0.851 | 1.052 | -0.026 | 0.058 | -0.173 | |
| | | TEMP | -6.965 | -3.863 | 0.571 | 8.864 | 11.344 | -0.270 | 0.605 | -0.017 | |
| | | EQEW | 0.121 | -0.022 | -0.733 | -0.018 | -0.235 | -0.142 | 0.014 | -0.139 | |
| | | EQNS | 0.015 | -1.309 | -0.036 | -0.221 | -0.377 | -0.030 | -0.060 | 0.070 | |
| | | EQZ | -0.194 | -0.382 | 0.000 | 0.646 | 0.724 | -0.119 | -0.054 | -0.048 | |
| | | EQT | 0.012 | 0.024 | -0.078 | -0.008 | -0.020 | -0.001 | -0.001 | -0.014 | |
| | | SPKW | 0.017 | -0.016 | -0.002 | -0.008 | 0.009 | 0.000 | 0.000 | -0.001 | |
| | | SPKN | -0.028 | 0.011 | 0.007 | 0.006 | -0.017 | -0.001 | 0.000 | 0.002 | |

**Table 3G.1-26
Combined Forces and Moments: RCCV, Selected Load Combination CV-11b (Continued)**

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|-----------------------|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 17 Top slab @ RCCV | 98174 | OTHR | 0.746 | 1.081 | -0.007 | -0.101 | -0.020 | 0.234 | 0.177 | -0.171 |
| | | TEMP | -8.731 | -7.669 | 2.634 | 5.537 | 4.434 | 0.957 | -0.904 | -0.184 |
| | | EQEW | -1.274 | -0.317 | -0.731 | -0.157 | -0.150 | 0.128 | 0.060 | -0.052 |
| | | EQNS | 0.306 | 1.159 | 0.053 | 0.252 | 0.417 | -0.212 | -0.180 | 0.149 |
| | | EQZ | -0.519 | 0.046 | -0.052 | 0.277 | 0.532 | 0.234 | 0.161 | -0.084 |
| | | EQT | 0.054 | -0.063 | 0.001 | -0.026 | -0.069 | 0.005 | 0.013 | -0.026 |
| | | SPKW | 0.045 | -0.016 | -0.016 | -0.005 | 0.020 | -0.002 | -0.001 | 0.004 |
| | | SPKN | -0.044 | -0.015 | 0.009 | 0.005 | -0.011 | -0.001 | -0.001 | -0.003 |
| | 98197 | OTHR | 0.545 | 1.183 | -0.132 | -0.213 | -1.135 | -0.048 | -0.055 | -0.763 |
| | | TEMP | -12.156 | -5.258 | -1.159 | 4.205 | 6.099 | 0.531 | 0.320 | -0.561 |
| | | EQEW | -1.529 | -0.094 | -0.596 | -0.157 | -0.512 | -0.060 | -0.039 | -0.104 |
| | | EQNS | 0.116 | -0.499 | 0.542 | 0.094 | -0.045 | -0.123 | 0.028 | 0.104 |
| | | EQZ | -0.155 | -0.016 | 0.113 | 0.343 | -0.833 | -0.060 | -0.048 | -0.581 |
| | | EQT | 0.030 | 0.070 | -0.039 | -0.013 | -0.013 | 0.004 | -0.003 | -0.005 |
| | | SPKW | 0.062 | -0.027 | 0.006 | 0.006 | 0.007 | 0.002 | 0.001 | 0.001 |
| | | SPKN | -0.047 | 0.006 | 0.007 | 0.003 | -0.007 | 0.001 | 0.000 | 0.001 |
| | 98103 | OTHR | 0.781 | 1.367 | -0.038 | -0.301 | 0.367 | -0.205 | -0.566 | -0.167 |
| | | TEMP | -6.757 | -8.103 | 0.104 | 13.587 | 13.101 | 0.388 | 1.276 | 0.008 |
| | | EQEW | -0.222 | 0.168 | -1.093 | -0.035 | -0.048 | -0.197 | 0.040 | -0.043 |
| | | EQNS | -0.349 | -1.493 | 0.077 | -1.238 | -0.628 | 0.001 | -0.319 | 0.019 |
| | | EQZ | 0.009 | -0.287 | -0.065 | -1.481 | -0.221 | -0.171 | -0.781 | -0.095 |
| | | EQT | -0.020 | 0.037 | -0.202 | 0.003 | 0.003 | -0.009 | 0.009 | 0.006 |
| | | SPKW | 0.019 | -0.001 | 0.002 | -0.002 | 0.013 | 0.000 | 0.004 | -0.001 |
| | | SPKN | -0.032 | 0.001 | 0.000 | -0.016 | -0.027 | 0.000 | -0.009 | 0.001 |

Table 3G.1-27

Sectional Thicknesses and Rebar Ratios of RCCV Used in the Evaluation

| Location | Element ID | Thickness (m) | Primary Reinforcement | | | | | Shear Tie | |
|---------------------------|----------------------|---------------|-----------------------|--------------------------|-----------|-----------------------------|-----------|-------------|-----------|
| | | | Position | Direction 1 ¹ | | Direction 2 ¹ | | Arrangement | Ratio (%) |
| | | | | Arrangement ² | Ratio (%) | Arrangement ² | Ratio (%) | | |
| 1 RPV Pedestal Bottom | 5006 5013 5024 | 2.4 | Inside | 2-#18@300 | 0.717 | 2-#18@1.8° | 1.007 | #9@1.8°x300 | 1.007 |
| | | | Outside | 3-#18@300 | 1.075 | 3-#18@1.8° | 1.510 | | |
| 2 RPV Pedestal Mid-Height | 6006 6013 6024 | 2.4 | Inside | 2-#18@300 | 0.717 | 2-#18@1.8° | 1.007 | #9@3.6°x600 | 0.252 |
| | | | Outside | 3-#18@300 | 1.075 | 3-#18@1.8° | 1.510 | | |
| 3 RPV Pedestal Top | 6606 6613 6624 | 2.4 | Inside | 2-#18@300 | 0.717 | 2-#18@1.8° | 1.007 | #9@1.8°x300 | 1.007 |
| | | | Outside | 3-#18@300 | 1.075 | 3-#18@1.8° | 1.510 | | |
| 4 RCCV Wetwell Bottom | 1806 1813 1824 | 2.0 | Inside | 2-#18@300 | 0.860 | 3-#18@0.9° | 1.297 | #9@1.2°x300 | 0.540 |
| | | | Outside | 3-#18@300 | 1.290 | 3-#18@0.9° +1-#18@1.8° | 1.513 | | |
| 5 RCCV Wetwell Mid-Height | 2606 2613 2624 | 2.0 | Inside | 2-#18@300 | 0.860 | 2-#18@0.9° | 0.865 | #9@1.2°x600 | 0.270 |
| | | | Outside | 3-#18@300 | 1.290 | 3-#18@0.9° | 1.297 | | |
| 6 RCCV Wetwell Top | 3406 3413 3424 | 2.0 | Inside | 2-#18@300 +1-#18@600 | 1.075 | 2-#18@0.9° | 0.865 | #9@0.9°x300 | 0.721 |
| | | | Outside | 3-#18@300 +1-#18@300 | 1.720 | 3-#18@0.9° +1-#18@0.9° | 1.729 | | |
| 7 RCCV Drywell Bottom | 3606 3613 3624 | 2.0 | Inside | 2-#18@300 | 0.860 | 2-#18@0.9° | 0.865 | #9@1.2°x300 | 0.540 |
| | | | Outside | 3-#18@300 +1-#18@300 | 1.720 | 3-#18@0.9° +1-#18@0.9° | 1.729 | | |
| 8 RCCV Drywell Mid-Height | 4006 4013 4976 | 2.0 | Inside | 2-#18@300 | 0.860 | 2-#18@0.9° | 0.865 | #9@1.2°x600 | 0.270 |
| | | | Outside | 3-#18@300 | 1.290 | 3-#18@0.9° | 1.297 | | |
| 9 RCCV Drywell Top | 4406 4413 | 2.0 | Inside | 2-#18@300 | 0.860 | 2-#18@0.9° | 0.865 | #9@1.2°x300 | 0.540 |
| | | | Outside | 3-#18@300 | 1.290 | 3-#18@0.9° | 1.297 | | |
| | 4424 | 2.0 | Inside | 2-#18@300 | 0.860 | 2-#18@0.9° (+1-#18@1.8°) | 1.081 | #9@1.2°x300 | 0.540 |
| | | | Outside | 3-#18@300 | 1.290 | 3-#18@0.9° | 1.297 | | |

Note *1: RCCV, Pedestal Direction1 : Hoop, Direction2 : Vertical, S/P Slab Direction1 : Radial, Direction2 : Circumferential, Top slab Direction1 : N-S, Direction2 : E-W, Basemat @center Direction1 : N-S, Direction2 : E-W, Basemat Inside RPV Pedestal Direction1 : Top:Radial, Bottom : N-S, Direction2 Top : Circumferential, Bottom : E-W

Note *2: Rebar in parentheses indicates additional bars locally required.

Table 3G.1-27
Sectional Thicknesses and Rebar Ratios of RCCV Used in the Evaluation (Continued)

| Location | Element ID | Thickness (m) | Primary Reinforcement | | | | Shear Tie | | |
|------------------------------------|-------------------------|---------------|-----------------------|-------------|-----------|-------------------------|-----------|--------------|-----------|
| | | | Position | Direction 1 | | Direction 2 | | Arrangement | Ratio (%) |
| | | | | Arrangement | Ratio (%) | Arrangement | Ratio (%) | | |
| 10 Basemat @ Center | 80003 80007 80012 | 4.0 | Top | 3-#9@120 | 0.403 | 3-#9@120 | 0.403 | #9@600x600 | 0.179 |
| | | | Bottom | 5-#11@200 | 0.629 | 5-#11@200 | 0.629 | | |
| 11 Basemat Inside RPV Pedestal | 80206 80213 80224 | 4.0 | Top | 6-#9@1.8° | 0.497 | 2-#9@200 +4-#9@400 | 0.323 | #9@3.6°x400 | 0.414 |
| | | | Bottom | 5-#11@200 | 0.629 | 5-#11@200 | 0.629 | | |
| 12 S/P Slab @ RPV | 83306 83313 83324 | 2.0 | Top | 2-#18@1.8° | 0.913 | 2-#18@300 | 0.860 | #9@1.2°x300 | 1.141 |
| | | | Bottom | 2-#18@1.8° | 0.913 | 2-#18@300 | 0.860 | | |
| 13 S/P Slab @ Center | 83406 83413 83424 | 2.0 | Top | 2-#18@0.9° | 1.264 | 2-#18@300 | 0.860 | #9@1.8°x600 | 0.263 |
| | | | Bottom | 2-#18@0.9° | 1.264 | 2-#18@300 | 0.860 | | |
| 14 S/P Slab @ RCCV | 83506 83513 83524 | 2.0 | Top | 2-#18@0.9° | 0.966 | 2-#18@300 | 0.860 | #9@0.72°x300 | 1.007 |
| | | | Bottom | 2-#18@0.9° | 0.966 | 2-#18@300 | 0.860 | | |
| 15 Top slab @ Drywell Head Opening | 98120 98135 98104 | 2.4 | Top | 3-#14@300 | 0.605 | 3-#14@300 | 0.605 | #9@600x300 | 0.358 |
| | | | Bottom | 3-#14@300 | 0.605 | 3-#14@300 | 0.605 | | |
| 16 Top slab @ Center | 98149 98170 | 2.4 | Top | 3-#14@300 | 0.605 | 3-#14@300 | 0.605 | #9@600x600 | 0.179 |
| | | | Bottom | 3-#14@300 | 0.605 | 3-#14@300 | 0.605 | | |
| | 98109 | 2.4 | Top | 3-#14@300 | 0.605 | 3-#14@300 +1-#14@300 | 0.806 | #9@600x600 | 0.179 |
| | | | Bottom | 3-#14@300 | 0.605 | 3-#14@300 | 0.605 | | |
| 17 Top slab @ RCCV | 98174 | 2.4 | Top | 3-#14@300 | 0.605 | 3-#14@300 | 0.605 | #9@600x600 | 0.179 |
| | | | Bottom | 3-#14@300 | 0.605 | 3-#14@300 | 0.605 | | |
| | 98197 | 2.4 | Top | 3-#14@300 | 0.605 | 3-#14@300 | 0.605 | #9@300x300 | 0.717 |
| | | | Bottom | 3-#14@300 | 0.605 | 3-#14@300 | 0.605 | | |
| | 98103 | 2.4 | Top | 3-#14@300 | 0.605 | 3-#14@300 +1-#14@300 | 0.806 | #9@300x300 | 0.717 |
| | | | Bottom | 3-#14@300 | 0.605 | 3-#14@300 | 0.605 | | |

Note *: RCCV, Pedestal Direction1 : Hoop, Direction2 : Vertical, S/P Slab Direction1 : Radial, Direction2 : Circumferential,
 Top slab Direction1 : N-S, Direction2 : E-W, Basemat @center Direction1 : N-S, Direction2 : E-W,
 Basemat Inside RPV Pedestal Direction1 : Top :Radial, Bottom : N-S, Direction2 Top : Circumferential, Bottom : E-W

Table 3G.1-28

Rebar and Concrete Stresses of RCCV: Selected Load Combination CV-1

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|--|-------------------------|-----------------------|-------------------------|------------------------------------|------------------------|-------------------------|-------------------------|-------------------------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 ¹ | | Direction2 ² | | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 1 RPV Pedestal Bottom | 5006 5013 5024 | -3.5 -3.7 -3.5 | -15.5 -15.5 -15.5 | -1.9 -3.9 -2.3 | -2.4 -3.2 -3.8 | -9.2 -9.3 -9.3 | -20.7 -21.9 -20.4 | 310.2 310.2 310.2 |
| 2 RPV Pedestal Mid-Height | 6006 6013 6024 | -2.4 -2.4 -1.7 | -15.5 -15.5 -15.5 | 29.4 15.1 45.4 | 20.6 19.1 14.1 | -16.7 -16.9 -10.6 | -14.6 -14.4 -11.1 | 310.2 310.2 310.2 |
| 3 RPV Pedestal Top | 6606 6613 6624 | -5.3 -5.2 -5.0 | -15.5 -15.5 -15.5 | 39.0 20.1 45.2 | 6.4 3.5 7.7 | 10.7 4.8 5.0 | -25.9 -27.1 -25.1 | 310.2 310.2 310.2 |
| 4 RCCV Wetwell Bottom | 1806 1813 1824 | -4.4 -4.7 -4.0 | -15.5 -15.5 -15.5 | 24.7 16.9 31.3 | 4.3 2.5 6.1 | 20.1 18.3 9.4 | -16.2 -18.0 -17.3 | 310.2 310.2 310.2 |
| 5 RCCV Wetwell Mid-Height | 2606 2613 2624 | -1.4 -1.7 -1.8 | -15.5 -15.5 -15.5 | 73.1 59.0 73.3 | 55.0 48.8 51.3 | -13.4 -16.2 -11.2 | 2.9 1.7 -3.2 | 310.2 310.2 310.2 |
| 6 RCCV Wetwell Top | 3406 3413 3424 | -0.4 -1.1 -1.1 | -15.5 -15.5 -15.5 | 60.1 47.8 50.9 | 34.3 31.3 24.2 | -1.3 -18.0 -1.5 | -3.3 2.2 -7.0 | 310.2 310.2 310.2 |
| 7 RCCV Drywell Bottom | 3606 3613 3624 | -0.5 -1.0 -1.2 | -15.5 -15.5 -15.5 | 75.4 67.0 66.2 | 34.1 30.3 22.8 | -7.1 -3.6 1.6 | 1.9 -4.1 -8.0 | 310.2 310.2 310.2 |
| 8 RCCV Drywell Mid-Height | 4006 4013 4976 | -0.5 -1.5 -0.5 | -15.5 -15.5 -15.5 | 49.0 47.1 46.8 | 37.0 38.4 29.6 | -10.0 -7.6 -4.3 | 9.1 -0.1 0.2 | 310.2 310.2 310.2 |
| 9 RCCV Drywell Top | 4406 4413 4424 | -4.6 -4.8 -4.9 | -15.5 -15.5 -15.5 | 34.4 11.0 49.0 | 7.0 2.1 12.1 | 68.3 29.9 55.2 | -2.9 -14.9 -9.1 | 310.2 310.2 310.2 |
| 10 Basemat @ Center | 80003 80007 80012 | -1.0 -1.0 -1.1 | -12.4 -12.4 -12.4 | -3.2 -3.2 -3.2 | -6.5 -6.6 -6.7 | 0.3 0.3 0.3 | -4.6 -4.6 -4.6 | 310.2 310.2 310.2 |
| 11 Basemat Inside RPV Pedestal | 80206 80213 80224 | -1.1 -0.9 -1.2 | -12.4 -12.4 -12.4 | -7.0 -5.0 -7.8 | -2.7 -4.8 -2.9 | -2.8 -4.5 -2.7 | -1.6 0.1 -3.0 | 310.2 310.2 310.2 |
| 12 S/P Slab @ RPV | 83306 83313 83324 | -1.7 -2.0 -1.4 | -15.5 -15.5 -15.5 | 26.6 13.5 9.8 | 5.6 2.3 2.3 | 84.5 67.5 83.0 | 8.3 3.5 9.7 | 310.2 310.2 310.2 |
| 13 S/P Slab @ Center | 83406 83413 83424 | -6.2 -5.8 -6.0 | -15.5 -15.5 -15.5 | -7.7 -5.7 -8.3 | 85.3 86.5 82.1 | 14.2 7.0 12.5 | 54.5 40.1 54.8 | 310.2 310.2 310.2 |
| 14 S/P Slab @ RCCV | 83506 83513 83524 | -0.3 -2.4 -0.7 | -15.5 -15.5 -15.5 | 56.5 57.0 51.5 | -21.3 -6.9 -24.7 | 22.6 14.8 26.5 | 31.9 14.3 35.8 | 310.2 310.2 310.2 |
| 15 Top slab @ Drywell Head Opening | 98120 98135 98104 | -0.6 -0.6 -1.6 | -15.5 -15.5 -15.5 | 45.0 3.3 52.7 | 16.8 2.1 14.1 | 55.6 0.9 139.9 | 37.5 25.0 19.7 | 310.2 310.2 310.2 |
| 16 Top slab @ Center | 98149 98170 98109 | -0.4 -1.5 -3.1 | -15.5 -15.5 -15.5 | 30.3 40.9 72.9 | -8.8 5.8 7.7 | 55.2 73.5 81.9 | 41.2 10.1 9.1 | 310.2 310.2 310.2 |
| 17 Top slab @ RCCV | 98174 98197 98103 | -1.0 -2.2 -2.5 | -15.5 -15.5 -15.5 | 20.3 9.7 38.7 | 19.3 27.4 53.2 | 40.8 9.5 55.8 | 38.2 99.2 42.3 | 310.2 310.2 310.2 |

Note: Negative value means compression.

Note *: RCCV, Pedestal Direction1 : Hoop, Direction2 : Vertical, S/P Slab Direction1 : Radial, Direction2 : Circumferential, Top slab Direction1 : N-S, Direction2 : E-W, Basemat @center Direction1 : N-S, Direction2 : E-W, Basemat Inside RPV Pedestal Direction1 : Top :Radial, Bottom : N-S, Direction2 Top : Circumferential, Bottom : E-W

Table 3G.1-29

Rebar and Concrete Stresses of RCCV: Selected Load Combination CV-7a

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|----------------|------------|-----------------------|-----------|------------------------------------|------------|-------------------------|------------|-----------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 ¹ | | Direction2 ² | | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 1 RPV | 5006 | -8.4 | -28.7 | -5.5 | -3.5 | -16.6 | -48.7 | 367.9 |
| Pedestal | 5013 | -8.2 | -28.7 | -8.7 | -5.8 | -14.8 | -47.0 | 367.9 |
| Bottom | 5024 | -7.3 | -28.7 | -7.9 | -7.0 | -10.7 | -40.7 | 367.9 |
| 2 RPV | 6006 | -7.1 | -28.7 | 14.4 | 31.6 | -46.5 | -33.6 | 367.9 |
| Pedestal | 6013 | -6.7 | -28.7 | 6.8 | 28.2 | -43.4 | -25.1 | 367.9 |
| Mid-Height | 6024 | -3.8 | -28.7 | 13.2 | 18.1 | -25.0 | -13.3 | 367.9 |
| 3 RPV | 6606 | -5.3 | -28.7 | -1.9 | 0.4 | -33.2 | -30.9 | 367.9 |
| Pedestal | 6613 | -4.4 | -28.7 | -5.5 | -0.6 | -29.3 | -30.5 | 367.9 |
| Top | 6624 | -9.6 | -28.7 | 2.1 | -7.6 | -54.7 | 10.8 | 367.9 |
| 4 RCCV | 1806 | -10.3 | -29.0 | 79.9 | 24.5 | 111.2 | -20.7 | 369.7 |
| Wetwell | 1813 | -9.5 | -29.0 | 72.5 | 29.6 | 90.8 | -24.0 | 369.7 |
| Bottom | 1824 | -9.0 | -29.0 | 159.7 | 75.0 | 77.9 | -29.3 | 369.7 |
| 5 RCCV | 2606 | -1.0 | -29.1 | 127.1 | 119.4 | -26.0 | 52.7 | 370.2 |
| Wetwell | 2613 | -1.7 | -29.1 | 78.6 | 94.4 | -32.9 | 20.9 | 370.2 |
| Mid-Height | 2624 | -3.1 | -29.1 | 123.8 | 105.2 | -16.1 | 7.3 | 370.2 |
| 6 RCCV | 3406 | -12.1 | -29.1 | 66.6 | 65.1 | -47.7 | 54.6 | 370.2 |
| Wetwell | 3413 | -6.0 | -29.1 | 21.8 | 52.0 | -20.6 | 40.6 | 370.2 |
| Top | 3424 | -10.2 | -29.1 | 213.2 | 136.0 | -82.9 | 67.3 | 370.2 |
| 7 RCCV | 3606 | -9.0 | -28.7 | 96.5 | 118.1 | 72.6 | 46.0 | 367.8 |
| Drywell | 3613 | -2.9 | -28.7 | 83.8 | 107.4 | -35.5 | 50.1 | 367.8 |
| Bottom | 3624 | -2.5 | -27.7 | 84.2 | 6.6 | -14.1 | -13.9 | 360.2 |
| 8 RCCV | 4006 | -2.2 | -28.7 | 29.3 | 117.7 | 3.6 | 62.0 | 367.8 |
| Drywell | 4013 | -1.7 | -28.7 | 41.4 | 111.8 | -13.1 | 41.2 | 367.8 |
| Mid-Height | 4976 | -1.1 | -27.7 | 46.7 | 26.3 | 4.3 | 17.4 | 360.2 |
| 9 RCCV | 4406 | -2.7 | -28.7 | 32.3 | 98.2 | 61.7 | 29.0 | 367.8 |
| Drywell | 4413 | -2.8 | -28.7 | 1.1 | 45.5 | -1.3 | -10.4 | 367.8 |
| Top | 4424 | -5.9 | -27.7 | 41.3 | 7.6 | 87.0 | -5.3 | 360.2 |
| 10 Basemat | 80003 | -3.1 | -23.2 | -17.7 | 13.6 | -15.1 | 22.8 | 370.2 |
| @ Center | 80007 | -3.0 | -23.2 | -17.3 | 11.0 | -15.2 | 21.0 | 370.2 |
| | 80012 | -3.0 | -23.2 | -17.3 | 8.0 | -14.8 | 16.9 | 370.2 |
| 11 Basemat | 80206 | -8.9 | -23.2 | -28.8 | 96.8 | -13.5 | 81.3 | 370.2 |
| Inside | 80213 | -7.1 | -23.2 | -22.2 | 47.9 | -20.3 | 107.9 | 370.2 |
| RPV Pedestal | 80224 | -6.1 | -23.2 | -21.7 | 47.4 | -20.2 | 36.2 | 370.2 |
| 12 S/P Slab | 83306 | -2.7 | -29.0 | -63.2 | 72.5 | 137.7 | 50.7 | 369.8 |
| @ RPV | 83313 | -2.3 | -29.0 | -52.3 | 105.4 | 147.9 | 47.2 | 369.8 |
| | 83324 | -0.4 | -29.0 | -70.4 | 114.2 | 151.0 | 26.8 | 369.8 |
| 13 S/P Slab | 83406 | -19.9 | -29.0 | -30.7 | 236.5 | 35.7 | 210.1 | 369.8 |
| @ Center | 83413 | -19.0 | -29.0 | -26.2 | 240.2 | 16.3 | 162.4 | 369.8 |
| | 83424 | -18.6 | -29.0 | -19.2 | 264.0 | 20.7 | 159.9 | 369.8 |
| 14 S/P Slab | 83506 | -0.8 | -29.0 | 165.8 | -96.1 | 39.1 | 120.3 | 369.8 |
| @ RCCV | 83513 | -7.8 | -29.0 | 158.3 | -20.6 | -18.1 | -2.1 | 369.8 |
| | 83524 | -8.5 | -29.0 | 178.0 | -28.1 | 22.9 | 41.5 | 369.8 |
| 15 Top slab | 98120 | -1.6 | -27.9 | 1.1 | -12.3 | 60.6 | 35.7 | 361.7 |
| @ Drywell Head | 98135 | -2.6 | -27.9 | 1.9 | -15.1 | -6.2 | 7.8 | 361.7 |
| Opening | 98104 | -1.8 | -27.9 | -28.3 | 62.6 | 162.7 | -1.1 | 361.7 |
| 16 Top slab | 98149 | -2.1 | -28.0 | 0.5 | -10.0 | 103.8 | 16.2 | 362.7 |
| @ Center | 98170 | -4.5 | -28.0 | 22.8 | -6.6 | 97.0 | 0.2 | 362.7 |
| | 98109 | -4.4 | -28.0 | 89.0 | 5.3 | 113.3 | 11.3 | 362.7 |
| 17 Top slab | 98174 | -2.8 | -28.0 | 18.0 | -3.4 | 64.9 | 4.3 | 362.7 |
| @ RCCV | 98197 | -1.6 | -28.0 | 24.6 | 22.0 | 10.7 | 80.6 | 362.7 |
| | 98103 | -0.5 | -28.0 | -4.3 | 15.9 | 59.1 | 24.3 | 362.7 |

Note: Negative value means compression.

Note *: RCCV, Pedestal Direction1 : Hoop, Direction2 : Vertical, S/P Slab Direction1 : Radial, Direction2 : Circumferential, Top slab Direction1 : N-S, Direction2 : E-W, Basemat @center Direction1 : N-S, Direction2 : E-W, Basemat Inside RPV Pedestal Direction1 : Top :Radial, Bottom : N-S, Direction2 Top : Circumferential, Bottom : E-W

**Table 3G.1-30
Rebar and Concrete Stresses of RCCV: Selected Load Combination CV-7b**

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|--|-------------------------|-------------------------|-------------------------|------------------------------------|-------------------------|-------------------------|-------------------------|-------------------------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 | | Direction2 | | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 1 RPV Pedestal Bottom | 5006 5013 5024 | -7.2 -7.0 -6.0 | -27.9 -27.9 -27.9 | -28.9 -35.6 -36.7 | -22.6 -28.3 -31.3 | -11.4 -12.3 -7.8 | -38.5 -36.5 -29.5 | 361.6 361.6 361.6 |
| 2 RPV Pedestal Mid-Height | 6006 6013 6024 | -7.1 -7.3 -4.5 | -27.9 -27.9 -27.9 | 60.8 44.4 69.0 | 71.9 74.4 65.9 | -43.4 -47.6 -28.8 | -24.0 -15.6 -5.0 | 361.6 361.6 361.6 |
| 3 RPV Pedestal Top | 6606 6613 6624 | -6.5 -6.4 -3.8 | -27.9 -27.9 -27.9 | 174.6 119.4 251.8 | 129.3 112.7 148.9 | 1.1 -14.3 60.4 | -39.2 -39.0 -84.5 | 361.6 361.6 361.6 |
| 4 RCCV Wetwell Bottom | 1806 1813 1824 | -7.3 -7.2 -6.3 | -28.3 -28.3 -28.3 | 73.3 23.9 35.9 | 29.1 27.6 18.6 | 82.3 63.8 55.5 | -14.8 -19.6 -22.9 | 364.4 364.4 364.4 |
| 5 RCCV Wetwell Mid-Height | 2606 2613 2624 | -1.1 -8.2 -4.8 | -28.2 -28.2 -28.2 | 91.2 47.7 86.1 | 111.0 101.1 96.6 | -46.5 -30.1 -21.1 | 74.6 38.6 29.2 | 363.8 363.8 363.8 |
| 6 RCCV Wetwell Top | 3406 3413 3424 | -5.6 -7.9 -1.3 | -28.2 -28.2 -28.2 | 37.7 36.7 44.6 | 59.1 60.6 42.1 | -24.3 -31.5 -29.4 | 45.0 29.2 16.4 | 363.8 363.8 363.8 |
| 7 RCCV Drywell Bottom | 3606 3613 3624 | -6.1 -5.7 -1.9 | -27.7 -27.7 -26.7 | 17.6 -0.1 78.2 | 132.5 96.5 26.3 | -5.5 -13.6 24.3 | 66.4 17.6 -5.3 | 360.2 360.2 352.9 |
| 8 RCCV Drywell Mid-Height | 4006 4013 4976 | -6.4 -4.6 -1.2 | -27.7 -27.7 -26.7 | 19.4 20.7 50.8 | 165.8 152.6 63.4 | 2.7 -5.6 0.5 | 88.5 58.9 33.5 | 360.2 360.2 352.9 |
| 9 RCCV Drywell Top | 4406 4413 4424 | -5.5 -5.6 -2.7 | -27.7 -27.7 -26.7 | 1.2 -7.4 62.5 | 173.2 62.5 5.6 | 87.4 4.1 64.7 | 87.8 -10.2 5.7 | 360.2 360.2 352.9 |
| 10 Basemat @ Center | 80003 80007 80012 | -2.6 -2.4 -2.5 | -23.2 -23.2 -23.2 | -13.6 -13.0 -12.5 | 20.6 17.8 14.7 | -10.7 -11.3 -10.7 | 33.9 31.5 28.3 | 370.2 370.2 370.2 |
| 11 Basemat Inside RPV Pedestal | 80206 80213 80224 | -7.7 -6.1 -5.1 | -23.2 -23.2 -23.2 | -20.5 -16.4 -16.2 | 82.7 46.2 41.5 | -8.6 -15.3 -13.8 | 96.8 99.5 46.2 | 370.2 370.2 370.2 |
| 12 S/P Slab @ RPV | 83306 83313 83324 | -3.9 -2.7 -7.1 | -28.3 -28.3 -28.3 | -74.5 -83.5 1.0 | 79.6 104.9 98.5 | 126.5 127.7 140.9 | 66.3 69.9 46.0 | 364.4 364.4 364.4 |
| 13 S/P Slab @ Center | 83406 83413 83424 | -18.4 -18.4 -18.1 | -28.3 -28.3 -28.3 | -29.0 -29.5 -22.9 | 211.2 212.9 239.8 | 20.7 21.2 24.0 | 162.7 174.1 165.6 | 364.4 364.4 364.4 |
| 14 S/P Slab @ RCCV | 83506 83513 83524 | -0.7 -0.6 -0.4 | -28.3 -28.3 -28.3 | 105.2 119.2 131.0 | -70.0 -68.8 -45.2 | 29.3 -1.6 12.1 | 126.4 118.0 111.3 | 364.4 364.4 364.4 |
| 15 Top slab @ Drywell Head Opening | 98120 98135 98104 | -7.8 -7.2 -10.0 | -26.2 -26.2 -26.2 | 26.7 12.6 -2.3 | -17.3 -35.0 -4.9 | 41.3 -7.6 170.2 | -6.2 3.0 -10.9 | 349.2 349.2 349.2 |
| 16 Top slab @ Center | 98149 98170 98109 | -4.6 -7.9 -7.9 | -26.6 -26.6 -27.2 | -8.4 44.5 116.4 | -20.1 -12.6 0.7 | 250.5 127.5 146.4 | 30.6 -3.1 6.2 | 352.0 352.0 356.6 |
| 17 Top slab @ RCCV | 98174 98197 98103 | -5.8 -2.5 -2.2 | -26.6 -26.6 -27.2 | 43.8 41.7 16.6 | -9.0 13.9 0.4 | 108.6 14.5 78.7 | 9.7 90.6 5.0 | 352.0 352.0 356.6 |

Note: Negative value means compression.

Note *: RCCV, Pedestal Direction1 : Hoop, Direction2 : Vertical, S/P Slab Direction1 : Radial, Direction2 : Circumferential,
Top slab Direction1 : N-S, Direction2 : E-W, Basemat @center Direction1 : N-S, Direction2 : E-W,
Basemat Inside RPV Pedestal Direction1 : Top :Radial, Bottom : N-S, Direction2 Top : Circumferential, Bottom : E-W

**Table 3G.1-31
Rebar and Concrete Stresses of RCCV: Selected Load Combination CV-11a**

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|--|-------------------------|-------------------------|-------------------------|------------------------------------|-------------------------|--------------------------|-------------------------|-------------------------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 | | Direction2 | | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 1 RPV Pedestal Bottom | 5006 5013 5024 | -15.7 -16.5 -9.3 | -28.7 -28.7 -28.7 | 64.7 44.3 38.1 | 104.8 117.1 37.0 | -46.3 -44.3 52.4 | -82.1 105.4 -54.2 | 367.9 367.9 367.9 |
| 2 RPV Pedestal Mid-Height | 6006 6013 6024 | -8.7 -7.7 -8.3 | -28.7 -28.7 -28.7 | 39.7 20.3 158.6 | 44.2 31.1 117.4 | -53.0 -52.7 94.6 | -38.9 -34.9 101.3 | 367.9 367.9 367.9 |
| 3 RPV Pedestal Top | 6606 6613 6624 | -10.3 -8.1 -14.2 | -28.7 -28.7 -28.7 | -9.6 -17.4 16.2 | 40.6 -8.9 59.0 | -57.3 -46.0 -69.7 | -35.3 -37.9 128.1 | 367.9 367.9 367.9 |
| 4 RCCV Wetwell Bottom | 1806 1813 1824 | -12.9 -12.2 -11.9 | -29.0 -29.0 -29.0 | 251.1 200.6 363.0 | 148.4 127.9 212.6 | 291.1 269.3 292.5 | 128.8 102.4 109.0 | 369.7 369.7 369.7 |
| 5 RCCV Wetwell Mid-Height | 2606 2613 2624 | -7.3 -7.0 -8.8 | -29.1 -29.1 -29.1 | 282.6 217.5 295.3 | 208.2 171.0 203.3 | 206.2 136.7 199.1 | 227.3 187.9 232.0 | 370.2 370.2 370.2 |
| 6 RCCV Wetwell Top | 3406 3413 3424 | -10.8 -10.0 -22.1 | -29.1 -29.1 -29.1 | 201.9 144.9 303.0 | 135.2 113.7 189.2 | 125.8 114.3 -212.3 | 166.4 136.8 236.1 | 370.2 370.2 370.2 |
| 7 RCCV Drywell Bottom | 3606 3613 3624 | -8.8 -8.0 -8.0 | -28.7 -28.7 -27.7 | 272.8 202.0 222.0 | 179.3 166.7 62.6 | 93.4 161.8 130.6 | 177.6 152.2 77.2 | 367.8 367.8 360.2 |
| 8 RCCV Drywell Mid-Height | 4006 4013 4976 | -5.8 -7.0 -8.3 | -28.7 -28.7 -27.7 | 183.8 153.2 233.8 | 212.9 171.2 139.5 | 144.8 95.9 209.6 | 176.4 113.6 183.9 | 367.8 367.8 360.2 |
| 9 RCCV Drywell Top | 4406 4413 4424 | -7.7 -7.2 -8.6 | -28.7 -28.7 -27.7 | 139.8 108.2 250.1 | 195.3 168.0 134.4 | 165.2 145.7 238.1 | 194.0 142.8 133.3 | 367.8 367.8 360.2 |
| 10 Basemat @ Center | 80003 80007 80012 | -6.4 -6.2 -5.5 | -23.2 -23.2 -23.2 | -24.3 -24.5 -23.5 | 96.3 86.6 70.4 | -22.7 -21.0 -20.1 | 133.3 132.8 119.0 | 370.2 370.2 370.2 |
| 11 Basemat Inside RPV Pedestal | 80206 80213 80224 | -14.1 -11.0 -6.3 | -23.2 -23.2 -23.2 | -35.5 -35.0 -32.4 | 250.7 135.7 59.9 | -21.0 -29.7 -25.1 | 250.6 244.9 113.9 | 370.2 370.2 370.2 |
| 12 S/P Slab @ RPV | 83306 83313 83324 | -13.2 -15.7 -11.7 | -29.0 -29.0 -29.0 | 61.6 70.6 -64.3 | 183.9 168.4 164.2 | 227.0 228.7 192.6 | 157.2 102.7 75.3 | 369.8 369.8 369.8 |
| 13 S/P Slab @ Center | 83406 83413 83424 | -20.4 -17.3 -16.3 | -29.0 -29.0 -29.0 | -41.1 -34.6 -25.1 | 209.4 217.8 241.8 | 49.2 34.6 29.1 | 193.5 151.1 149.8 | 369.8 369.8 369.8 |
| 14 S/P Slab @ RCCV | 83506 83513 83524 | -13.9 -11.8 -14.8 | -29.0 -29.0 -29.0 | 250.3 198.3 155.6 | -59.4 -36.4 -58.4 | 55.8 -24.0 -31.8 | 131.8 -9.0 73.1 | 369.8 369.8 369.8 |
| 15 Top slab @ Drywell Head Opening | 98120 98135 98104 | -10.6 -3.5 -5.6 | -27.9 -27.9 -27.9 | 127.9 95.3 -43.1 | -36.6 -26.8 70.6 | 158.5 30.3 191.2 | 82.6 46.8 102.3 | 361.7 361.7 361.7 |
| 16 Top slab @ Center | 98149 98170 98109 | -3.0 -5.1 -4.4 | -28.0 -28.0 -28.0 | 17.9 36.8 110.7 | -13.8 -11.0 11.5 | 111.8 103.8 148.3 | 23.7 6.9 59.1 | 362.7 362.7 362.7 |
| 17 Top slab @ RCCV | 98174 98197 98103 | -3.7 -2.9 -8.1 | -28.0 -28.0 -28.0 | 91.7 63.7 153.1 | 36.0 47.1 36.2 | 119.1 80.2 137.5 | 41.2 89.9 48.4 | 362.7 362.7 362.7 |

Note: Negative value means compression.

Note *: RCCV, Pedestal Direction1 : Hoop, Direction2 : Vertical, S/P Slab Direction1 : Radial, Direction2 : Circumferential,
Top slab Direction1 : N-S, Direction2 : E-W, Basemat @center Direction1 : N-S, Direction2 : E-W,
Basemat Inside RPV Pedestal Direction1 : Top :Radial, Bottom : N-S, Direction2 Top : Circumferential, Bottom : E-W

**Table 3G.1-32
Rebar and Concrete Stresses of RCCV: Selected Load Combination CV-11b**

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|--|-------------------------|-------------------------|-------------------------|------------------------------------|-------------------------|-------------------------|-------------------------|-------------------------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 | | Direction2 | | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 1 RPV Pedestal Bottom | 5006 5013 5024 | -14.4 -15.2 -8.2 | -27.9 -27.9 -27.9 | -40.5 -44.9 -39.0 | -35.5 -41.6 -34.1 | -42.0 -39.1 -31.8 | -72.7 108.6 -44.4 | 361.6 361.6 361.6 |
| 2 RPV Pedestal Mid-Height | 6006 6013 6024 | -9.1 -8.6 -9.3 | -27.9 -27.9 -27.9 | 89.9 67.7 193.2 | 85.1 74.3 167.5 | -52.4 -56.4 80.8 | -31.1 -27.0 145.3 | 361.6 361.6 361.6 |
| 3 RPV Pedestal Top | 6606 6613 6624 | -8.7 -8.9 -7.8 | -27.9 -27.9 -27.9 | 225.5 152.8 294.8 | 178.1 152.7 187.0 | 68.1 -30.0 204.7 | -56.0 -49.8 -84.9 | 361.6 361.6 361.6 |
| 4 RCCV Wetwell Bottom | 1806 1813 1824 | -10.3 -10.6 -9.3 | -28.3 -28.3 -28.3 | 223.6 157.9 272.3 | 149.4 132.9 174.3 | 261.1 238.6 251.0 | 159.6 125.7 118.8 | 364.4 364.4 364.4 |
| 5 RCCV Wetwell Mid-Height | 2606 2613 2624 | -8.9 -7.2 -9.0 | -28.2 -28.2 -28.2 | 235.5 184.8 256.6 | 191.7 173.0 197.4 | 194.5 110.6 162.4 | 254.3 209.2 251.6 | 363.8 363.8 363.8 |
| 6 RCCV Wetwell Top | 3406 3413 3424 | -7.3 -6.7 -7.6 | -28.2 -28.2 -28.2 | 166.0 139.9 179.1 | 120.9 115.9 124.0 | 117.7 79.3 163.5 | 152.9 123.0 144.0 | 363.8 363.8 363.8 |
| 7 RCCV Drywell Bottom | 3606 3613 3624 | -7.2 -7.8 -7.4 | -27.7 -27.7 -26.7 | 133.6 41.4 261.7 | 187.6 165.6 108.0 | 111.6 39.0 201.7 | 172.8 112.9 114.5 | 360.2 360.2 352.9 |
| 8 RCCV Drywell Mid-Height | 4006 4013 4976 | -7.3 -7.5 -8.4 | -27.7 -27.7 -26.7 | 99.9 98.7 232.4 | 252.3 215.7 171.6 | 112.3 75.6 201.6 | 209.3 132.4 196.4 | 360.2 360.2 352.9 |
| 9 RCCV Drywell Top | 4406 4413 4424 | -10.6 -10.9 -8.8 | -27.7 -27.7 -26.7 | 127.2 -35.8 264.0 | 293.8 195.1 136.8 | 171.0 123.9 198.2 | 244.3 150.4 180.0 | 360.2 360.2 352.9 |
| 10 Basemat @ Center | 80003 80007 80012 | -6.5 -6.2 -5.1 | -23.2 -23.2 -23.2 | -23.1 -21.0 -19.5 | 127.2 112.4 83.7 | -19.1 -17.0 -15.5 | 150.0 146.9 127.7 | 370.2 370.2 370.2 |
| 11 Basemat Inside RPV Pedestal | 80206 80213 80224 | -13.2 -10.4 -6.0 | -23.2 -23.2 -23.2 | -30.2 -29.7 -26.8 | 260.6 182.7 75.6 | -17.4 50.9 -20.6 | 271.3 252.4 118.8 | 370.2 370.2 370.2 |
| 12 S/P Slab @ RPV | 83306 83313 83324 | -14.9 -17.1 -14.8 | -28.3 -28.3 -28.3 | -51.0 -67.4 -80.0 | 187.9 162.1 162.5 | 218.3 220.0 187.8 | 167.2 123.8 90.6 | 364.4 364.4 364.4 |
| 13 S/P Slab @ Center | 83406 83413 83424 | -16.8 -16.9 -16.4 | -28.3 -28.3 -28.3 | -37.2 -38.0 -29.1 | 192.3 200.3 230.4 | 26.8 35.3 31.2 | 155.0 155.8 154.1 | 364.4 364.4 364.4 |
| 14 S/P Slab @ RCCV | 83506 83513 83524 | -11.5 -13.2 -11.5 | -28.3 -28.3 -28.3 | 190.5 160.5 120.6 | 66.0 -67.0 -73.6 | 57.1 -34.1 -30.9 | 147.2 111.7 98.9 | 364.4 364.4 364.4 |
| 15 Top slab @ Drywell Head Opening | 98120 98135 98104 | -10.0 -7.7 -10.3 | -26.2 -26.2 -26.2 | 90.8 63.5 50.1 | -20.3 -38.9 5.7 | 114.2 -8.0 187.5 | -9.0 3.7 -23.3 | 349.2 349.2 349.2 |
| 16 Top slab @ Center | 98149 98170 98109 | -5.4 -8.0 -7.5 | -26.6 -26.6 -27.2 | -10.7 74.8 139.1 | -23.2 -17.2 -9.8 | 256.0 127.9 176.2 | 32.6 -9.6 24.2 | 352.0 352.0 356.6 |
| 17 Top slab @ RCCV | 98174 98197 98103 | -6.5 -3.5 -9.7 | -26.6 -26.6 -27.2 | 134.2 81.6 153.1 | -16.2 34.8 -12.0 | 160.2 87.9 145.4 | 24.5 90.4 28.7 | 352.0 352.0 356.6 |

Note: Negative value means compression.

Note *: RCCV, Pedestal Direction1 : Hoop, Direction2 : Vertical, S/P Slab Direction1 : Radial, Direction2 : Circumferential,
Top slab Direction1 : N-S, Direction2 : E-W, Basemat @center Direction1 : N-S, Direction2 : E-W,
Basemat Inside RPV Pedestal Direction1 : Top :Radial, Bottom : N-S, Direction2 Top : Circumferential, Bottom : E-W

Table 3G.1-33
Transverse Shear of RCCV

| Location | Element ID | Load ID | Shear Force Q (MN/m) | d (m) | Shear Stress (MPa) | | | Shear Tie Ratio (%) | |
|------------------------------------|------------|---------|----------------------|-------|--------------------|------|------|---------------------|----------|
| | | | | | vU | vC | vS | required | provided |
| 1 RPV Pedestal Bottom | 5006 | CV-11b | 6.84 | 2.08 | 3.88 | 2.92 | 0.96 | 0.238 | 1.010 |
| | 5013 | CV-11a | 4.96 | 1.94 | 3.01 | 1.66 | 1.36 | 0.332 | 1.010 |
| | 5024 | CV-11a | 5.65 | 1.94 | 3.44 | 1.90 | 1.53 | 0.374 | 1.010 |
| 2 RPV Pedestal Mid-Height | 6006 | CV-7b | 2.04 | 1.94 | 1.24 | 2.67 | 0.00 | 0.000 | 0.252 |
| | 6013 | CV-7b | 3.10 | 1.94 | 1.88 | 2.61 | 0.00 | 0.000 | 0.252 |
| | 6024 | CV-11b | 2.98 | 1.94 | 1.81 | 1.69 | 0.13 | 0.031 | 0.252 |
| 3 RPV Pedestal Top | 6606 | CV-7b | 2.20 | 2.08 | 1.25 | 2.57 | 0.00 | 0.000 | 1.010 |
| | 6613 | CV-7b | 2.27 | 2.07 | 1.29 | 2.49 | 0.00 | 0.000 | 1.010 |
| | 6624 | CV-7b | 2.21 | 2.07 | 1.26 | 2.22 | 0.00 | 0.000 | 1.010 |
| 4 RCCV Wetwell Bottom | 1806 | CV-11a | 1.70 | 1.57 | 1.27 | 0.63 | 0.65 | 0.157 | 0.540 |
| | 1813 | CV-11a | 1.86 | 1.57 | 1.39 | 0.39 | 1.00 | 0.244 | 0.540 |
| | 1824 | CV-11a | 1.50 | 1.57 | 1.12 | 0.27 | 0.86 | 0.209 | 0.540 |
| 5 RCCV Wetwell Mid-Height | 2606 | CV-7a | 0.35 | 1.54 | 0.27 | 1.06 | 0.00 | 0.000 | 0.270 |
| | 2613 | CV-7a | 0.24 | 1.54 | 0.18 | 1.87 | 0.00 | 0.000 | 0.270 |
| | 2624 | CV-7b | 0.24 | 1.54 | 0.18 | 1.04 | 0.00 | 0.000 | 0.270 |
| 6 RCCV Wetwell Top | 3406 | CV-7b | 0.58 | 1.59 | 0.43 | 0.91 | 0.00 | 0.000 | 0.721 |
| | 3413 | CV-1 | 0.04 | 1.66 | 0.02 | 0.02 | 0.00 | 0.000 | 0.721 |
| | 3424 | CV-7a | 0.02 | 1.67 | 0.02 | 0.02 | 0.00 | 0.000 | 0.721 |
| 7 RCCV Drywell Bottom | 3606 | CV-11b | 0.63 | 1.66 | 0.45 | 0.00 | 0.45 | 0.111 | 0.540 |
| | 3613 | CV-7a | 0.63 | 1.59 | 0.46 | 0.96 | 0.00 | 0.000 | 0.540 |
| | 3624 | CV-1 | 0.63 | 1.68 | 0.38 | 1.30 | 0.00 | 0.000 | 0.540 |
| 8 RCCV Drywell Mid-Height | 4006 | CV-11a | 0.62 | 1.59 | 0.46 | 0.06 | 0.40 | 0.098 | 0.270 |
| | 4013 | CV-7b | 0.36 | 1.54 | 0.27 | 1.03 | 0.00 | 0.000 | 0.270 |
| | 4976 | CV-7b | 0.52 | 1.54 | 0.40 | 1.70 | 0.00 | 0.000 | 0.270 |
| 9 RCCV Drywell Top | 4406 | CV-11a | 2.67 | 1.68 | 1.87 | 0.85 | 1.03 | 0.251 | 0.540 |
| | 4413 | CV-1 | 0.78 | 1.68 | 0.47 | 1.11 | 0.00 | 0.000 | 0.540 |
| | 4424 | CV-11b | 0.95 | 1.54 | 0.73 | 0.65 | 0.08 | 0.020 | 0.540 |
| 10 Basemat @ Center | 80003 | CV-7b | 0.57 | 3.50 | 0.19 | 0.97 | 0.00 | 0.000 | 0.179 |
| | 80007 | CV-7a | 0.59 | 3.48 | 0.20 | 1.07 | 0.00 | 0.000 | 0.179 |
| | 80012 | CV-7a | 0.26 | 3.47 | 0.09 | 0.96 | 0.00 | 0.000 | 0.179 |
| 11 Basemat Inside RPV Pedestal | 80206 | CV-11b | 4.29 | 3.49 | 1.45 | 0.84 | 0.61 | 0.148 | 0.414 |
| | 80213 | CV-11a | 4.66 | 3.47 | 1.58 | 1.00 | 0.58 | 0.140 | 0.414 |
| | 80224 | CV-7a | 1.99 | 3.50 | 0.67 | 1.08 | 0.00 | 0.000 | 0.414 |
| 12 S/P Slab @ RPV | 83306 | CV-11a | 5.46 | 1.53 | 4.22 | 2.02 | 2.19 | 0.534 | 1.140 |
| | 83313 | CV-11a | 5.24 | 1.53 | 4.04 | 1.93 | 2.11 | 0.515 | 1.140 |
| | 83324 | CV-11a | 5.14 | 1.53 | 3.96 | 0.89 | 3.07 | 0.747 | 1.140 |
| 13 S/P Slab @ Center | 83406 | CV-1 | 0.03 | 1.76 | 0.02 | 0.02 | 0.00 | 0.000 | 0.263 |
| | 83413 | CV-1 | 0.02 | 1.75 | 0.01 | 0.01 | 0.00 | 0.000 | 0.263 |
| | 83424 | CV-1 | 0.04 | 1.76 | 0.02 | 0.02 | 0.00 | 0.000 | 0.263 |
| 14 S/P Slab @ RCCV | 83506 | CV-7a | 5.08 | 1.53 | 3.92 | 0.89 | 3.02 | 0.736 | 1.010 |
| | 83513 | CV-7a | 5.12 | 1.53 | 3.95 | 0.81 | 3.14 | 0.764 | 1.010 |
| | 83524 | CV-7a | 5.07 | 1.53 | 3.91 | 0.70 | 3.21 | 0.781 | 1.010 |
| 15 Top slab @ Drywell Head Opening | 98120 | CV-1 | 0.14 | 1.95 | 0.07 | 0.07 | 0.00 | 0.000 | 0.358 |
| | 98135 | CV-1 | 0.27 | 1.98 | 0.13 | 0.13 | 0.00 | 0.000 | 0.358 |
| | 98104 | CV-7b | 0.11 | 1.94 | 0.07 | 0.07 | 0.00 | 0.000 | 0.358 |
| 16 Top slab @ Center | 98149 | CV-7a | 0.34 | 1.94 | 0.20 | 0.20 | 0.00 | 0.000 | 0.179 |
| | 98170 | CV-1 | 0.13 | 1.94 | 0.07 | 0.07 | 0.00 | 0.000 | 0.179 |
| | 98109 | CV-1 | 0.22 | 2.00 | 0.11 | 0.11 | 0.00 | 0.000 | 0.179 |
| 17 Top slab @ RCCV | 98174 | CV-7b | 1.12 | 1.94 | 0.68 | 0.85 | 0.00 | 0.000 | 0.179 |
| | 98197 | CV-7b | 1.58 | 2.00 | 0.93 | 0.88 | 0.05 | 0.014 | 0.717 |
| | 98103 | CV-1 | 0.79 | 1.93 | 0.41 | 0.81 | 0.00 | 0.000 | 0.717 |

Table 3G.1-34
Tangential Shear of RCCV

| Location | Element ID | Load ID | Section Forces | | | Thickness T (m) | Rebar Area (cm ² /m) | | rAs/pAs | v _{so} (MPa) | | v _u (MPa) | |
|---------------------------------|------------|---------|-------------------|---------------------|-------------|-----------------------|---------------------------------|-----------------|---------|-----------------------|-----------|----------------------|--|
| | | | Nx / Ny (MN/m) | Nxl / Nyl (MN/m) | V (MN/m) | | Required rAs | Provided pAs | | Calculated | Allowable | Calculated | Allowable 0.4f _c '-v _{so} |
| 1 RPV Pedestal Bottom | 5006 | CV-11a | -1.145 | -8.848 | 1.642 | 2.40 | 213.5 | 431.3 | 0.495 | 0.68 | 4.37 | 0.68 | 12.83 |
| | | CV-11a | -5.817 | -14.908 | 1.730 | 2.40 | 249.8 | 604.8 | 0.413 | 0.72 | 4.37 | 0.72 | 12.80 |
| | 5013 | CV-11a | -1.724 | -9.028 | 0.261 | 2.40 | 198.6 | 431.3 | 0.461 | 0.11 | 4.37 | 0.11 | 13.41 |
| | | CV-11a | -6.251 | -17.407 | 0.743 | 2.40 | 303.7 | 604.8 | 0.502 | 0.31 | 4.37 | 0.31 | 13.21 |
| | 5024 | CV-11a | -1.480 | -3.734 | 4.326 | 2.40 | 115.1 | 431.3 | 0.267 | 1.80 | 4.37 | 1.80 | 11.71 |
| | | CV-11a | -5.953 | -12.404 | -1.003 | 2.40 | 176.4 | 604.8 | 0.292 | 0.42 | 4.37 | 0.42 | 13.10 |
| 2 RPV Pedestal Mid-Height | 6006 | CV-11b | 0.847 | -0.356 | 4.338 | 2.40 | 143.8 | 431.3 | 0.333 | 1.81 | 4.30 | 1.81 | 11.30 |
| | | CV-11a | -5.539 | -11.449 | 3.561 | 2.40 | 175.3 | 604.8 | 0.290 | 1.48 | 4.37 | 1.48 | 12.03 |
| | 6013 | CV-11b | 0.563 | -0.794 | 3.188 | 2.40 | 106.4 | 431.3 | 0.247 | 1.33 | 4.30 | 1.33 | 11.78 |
| | | CV-11a | -5.603 | -11.372 | 1.672 | 2.40 | 160.2 | 604.8 | 0.265 | 0.70 | 4.37 | 0.70 | 12.82 |
| | 6024 | CV-11b | 0.886 | -1.448 | 7.797 | 2.40 | 243.8 | 431.3 | 0.565 | 3.25 | 4.30 | 3.25 | 9.86 |
| | | CV-11a | -4.167 | -5.627 | -6.738 | 2.40 | 125.3 | 604.8 | 0.207 | 2.81 | 4.37 | 2.81 | 10.71 |
| 3 RPV Pedestal Top | 6606 | CV-11b | 0.392 | 0.797 | 4.143 | 2.40 | 127.5 | 431.3 | 0.296 | 1.73 | 4.30 | 1.73 | 11.38 |
| | | CV-11a | -4.702 | -7.410 | 4.129 | 2.40 | 102.7 | 604.8 | 0.170 | 1.72 | 4.37 | 1.72 | 11.80 |
| | 6613 | CV-11b | 0.095 | -2.769 | -0.763 | 2.40 | 82.1 | 431.3 | 0.190 | 0.32 | 4.30 | 0.32 | 12.79 |
| | | CV-11a | -4.874 | -7.353 | 2.387 | 2.40 | 77.7 | 604.8 | 0.128 | 0.99 | 4.37 | 0.99 | 12.52 |
| | 6624 | CV-11b | 0.690 | -1.913 | 5.508 | 2.40 | 180.3 | 431.3 | 0.418 | 2.30 | 4.30 | 2.30 | 10.81 |
| | | CV-11a | -4.607 | -6.690 | 2.969 | 2.40 | 73.7 | 604.8 | 0.122 | 1.24 | 4.37 | 1.24 | 12.28 |
| 4 RCCV Wetwell Bottom | 1806 | CV-11b | 0.226 | 0.505 | 6.903 | 2.00 | 196.1 | 430.0 | 0.456 | 3.45 | 4.33 | 3.45 | 9.84 |
| | | CV-11b | -2.346 | 6.278 | -6.380 | 2.00 | 181.2 | 562.0 | 0.322 | 3.19 | 4.33 | 3.19 | 10.10 |
| | 1813 | CV-11b | 0.018 | 1.689 | 5.664 | 2.00 | 162.7 | 430.0 | 0.378 | 2.83 | 4.33 | 2.83 | 10.46 |
| | | CV-11b | -2.717 | 8.910 | -2.046 | 2.00 | 176.3 | 562.0 | 0.314 | 1.02 | 4.33 | 1.02 | 12.27 |
| | 1824 | CV-11b | 0.411 | -0.798 | -8.356 | 2.00 | 241.6 | 430.0 | 0.562 | 4.18 | 4.33 | 4.18 | 9.11 |
| | | CV-11b | -2.924 | 4.615 | -8.326 | 2.00 | 181.0 | 562.0 | 0.322 | 4.16 | 4.33 | 4.16 | 9.13 |

Note : Top and bottom lines for each element indicate evaluation results for hoop and vertical rebars, respectively.

Nomenclature:

Nx, Ny: axial forces in the hoop and vertical directions due to pressure and dead loads, respectively

Nxl, Nyl: axial forces in the hoop and vertical directions due to lateral loads, respectively

V: tangential shear due to lateral loads

v_{so}: tangential shear stress borne by orthogonal rebars (Refer to Table 3.8-3.)

Table 3G.1-34
Tangential Shear of RCCV (Continued)

| Location | Element ID | Load ID | Section Forces | | | Thickness T (m) | Rebar Area (cm ² /m) | | rAs/pAs | v _{so} (MPa) | | v _u (MPa) | |
|---------------------------------|------------|---------|-------------------|---------------------|-------------|-----------------------|---------------------------------|-----------------|---------|-----------------------|-----------|----------------------|--|
| | | | Nx / Ny (MN/m) | Nxl / Nyl (MN/m) | V (MN/m) | | Required rAs | Provided pAs | | Calculated | Allowable | Calculated | Allowable 0.4f' _c -v _{so} |
| 5 RCCV Wetwell Mid-Height | 2606 | CV-11b | 2.353 | 1.026 | 6.310 | 2.00 | 240.4 | 430.0 | 0.559 | 3.16 | 4.33 | 3.16 | 10.10 |
| | | CV-11b | -1.890 | 4.790 | -6.180 | 2.00 | 162.9 | 433.0 | 0.376 | 3.09 | 4.33 | 3.09 | 10.16 |
| | 2613 | CV-11b | 2.044 | 1.466 | 5.660 | 2.00 | 216.9 | 430.0 | 0.504 | 2.83 | 4.33 | 2.83 | 10.42 |
| | | CV-11b | -2.398 | 5.779 | -4.696 | 2.00 | 138.8 | 433.0 | 0.320 | 2.35 | 4.33 | 2.35 | 10.91 |
| | 2624 | CV-11b | 2.271 | 0.684 | 7.582 | 2.00 | 271.7 | 430.0 | 0.632 | 3.79 | 4.33 | 3.79 | 9.46 |
| | | CV-11b | -2.528 | 3.917 | 7.582 | 2.00 | 165.1 | 433.0 | 0.381 | 3.79 | 4.33 | 3.79 | 9.46 |
| 6 RCCV Wetwell Top | 3406 | CV-11b | 2.226 | 0.816 | 5.686 | 2.00 | 219.1 | 560.0 | 0.391 | 2.84 | 4.33 | 2.84 | 10.41 |
| | | CV-11b | -1.370 | 3.321 | -5.629 | 2.00 | 142.0 | 519.0 | 0.274 | 2.81 | 4.33 | 2.81 | 10.44 |
| | 3413 | CV-11b | 1.883 | 0.351 | 5.309 | 2.00 | 198.0 | 560.0 | 0.354 | 2.65 | 4.33 | 2.65 | 10.60 |
| | | CV-11b | -2.111 | 4.955 | -4.569 | 2.00 | 127.2 | 519.0 | 0.245 | 2.28 | 4.33 | 2.28 | 10.97 |
| | 3424 | CV-11b | 1.665 | 0.060 | 6.741 | 2.00 | 231.0 | 560.0 | 0.413 | 3.37 | 4.33 | 3.37 | 9.88 |
| | | CV-11b | -1.958 | 3.279 | 6.741 | 2.00 | 152.2 | 519.0 | 0.293 | 3.37 | 4.33 | 3.37 | 9.88 |
| 7 RCCV Drywell Bottom | 3606 | CV-11b | 2.198 | -0.230 | -5.400 | 2.00 | 211.1 | 516.0 | 0.409 | 2.70 | 4.29 | 2.70 | 10.32 |
| | | CV-11b | -0.951 | 3.195 | -5.163 | 2.00 | 142.2 | 519.0 | 0.274 | 2.58 | 4.29 | 2.58 | 10.44 |
| | 3613 | CV-11b | 1.927 | 0.501 | 5.021 | 2.00 | 193.6 | 516.0 | 0.375 | 2.51 | 4.29 | 2.51 | 10.51 |
| | | CV-11b | -1.655 | 4.550 | -4.310 | 2.00 | 128.0 | 519.0 | 0.247 | 2.15 | 4.29 | 2.15 | 10.86 |
| | 3624 | CV-11b | 1.701 | -0.134 | 6.469 | 2.00 | 231.5 | 516.0 | 0.449 | 3.23 | 4.21 | 3.23 | 9.31 |
| | | CV-11b | -1.590 | 3.012 | 6.469 | 2.00 | 157.1 | 519.0 | 0.303 | 3.23 | 4.21 | 3.23 | 9.31 |
| 8 RCCV Drywell Mid-Height | 4006 | CV-11b | 1.601 | 0.607 | -5.101 | 2.00 | 187.1 | 430.0 | 0.435 | 2.55 | 4.29 | 2.55 | 10.47 |
| | | CV-11b | -0.585 | 2.603 | -4.989 | 2.00 | 140.0 | 433.0 | 0.323 | 2.49 | 4.29 | 2.49 | 10.52 |
| | 4013 | CV-11b | 1.535 | 0.036 | 4.848 | 2.00 | 177.2 | 430.0 | 0.412 | 2.42 | 4.29 | 2.42 | 10.59 |
| | | CV-11b | -1.731 | 4.253 | -4.236 | 2.00 | 118.6 | 433.0 | 0.274 | 2.12 | 4.29 | 2.12 | 10.90 |
| | 4976 | CV-11b | 1.391 | -0.297 | 6.789 | 2.00 | 232.0 | 430.0 | 0.539 | 3.39 | 4.21 | 3.39 | 9.15 |
| | | CV-11b | -1.073 | 2.620 | 6.789 | 2.00 | 175.8 | 433.0 | 0.406 | 3.39 | 4.21 | 3.39 | 9.15 |
| 9 RCCV Drywell Top | 4406 | CV-11b | 0.496 | 0.825 | -4.612 | 2.00 | 143.8 | 430.0 | 0.334 | 2.31 | 4.29 | 2.31 | 10.71 |
| | | CV-11b | -0.318 | 2.297 | -4.612 | 2.00 | 134.2 | 433.0 | 0.310 | 2.31 | 4.29 | 2.31 | 10.71 |
| | 4413 | CV-11b | 0.126 | -0.659 | 4.494 | 2.00 | 129.6 | 430.0 | 0.301 | 2.25 | 4.29 | 2.25 | 10.77 |
| | | CV-11b | -1.815 | 4.056 | -4.011 | 2.00 | 108.0 | 433.0 | 0.249 | 2.01 | 4.29 | 2.01 | 11.01 |
| | 4424 | CV-11b | 0.845 | -0.223 | 7.140 | 2.00 | 226.3 | 430.0 | 0.526 | 3.57 | 4.21 | 3.57 | 8.98 |
| | | CV-11b | -0.683 | 2.364 | 7.140 | 2.00 | 193.7 | 476.0 | 0.407 | 3.57 | 4.21 | 3.57 | 8.98 |

Table 3G.1-35
Containment Liner Plate Strains (Max)

| Category | Calculated Strain | | | | | Allowable Tension Allowable Compression |
|------------------------------|-------------------|----------|-----------|-----------|----------|--|
| | Cylinder | Pedestal | DW Bottom | WW Bottom | Top Slab | |
| Test | 0.0003 | 0.0004 | 0.0000 | 0.0002 | 0.0002 | 0.002 |
| | -0.0010 | -0.0006 | -0.0001 | -0.0002 | 0.0000 | -0.002 |
| Normal Operation | 0.0004 | 0.0004 | 0.0001 | 0.0004 | 0.0001 | 0.002 |
| | -0.0008 | -0.0010 | -0.0003 | -0.0005 | -0.0005 | -0.002 |
| Severe Environment | 0.0004 | 0.0004 | 0.0001 | 0.0004 | 0.0001 | 0.003 |
| | -0.0008 | -0.0010 | -0.0003 | -0.0005 | -0.0005 | -0.005 |
| Extreme Environment | 0.0005 | 0.0004 | 0.0001 | 0.0004 | 0.0002 | 0.003 |
| | -0.0008 | -0.0010 | -0.0003 | -0.0005 | -0.0005 | -0.005 |
| Abnormal ; LOCA | 0.0005 | 0.0005 | 0.0001 | 0.0004 | 0.0002 | 0.003 |
| | -0.0032 | -0.0028 | -0.0004 | -0.0019 | -0.0017 | -0.005 |
| Abnormal/Extreme Environment | 0.0012 | 0.0007 | 0.0002 | 0.0009 | 0.0004 | 0.003 |
| | -0.0040 | -0.0030 | -0.0006 | -0.0025 | -0.0018 | -0.005 |

**Table 3G.1-35
Containment Liner Plate Strains (Max) (Continued)**

| Category | Calculated Strain | | Allowable Tension Allowable Compression |
|------------------------------|-------------------|----------------------|--|
| | DF Thick PLate | Pedestal Thick Plate | |
| Test | 0.0004 | 0.0001 | 0.002 |
| | -0.0002 | -0.0001 | -0.002 |
| Normal Operation | 0.0001 | 0.0001 | 0.002 |
| | -0.0005 | -0.0006 | -0.002 |
| Severe Environment | 0.0001 | 0.0001 | 0.003 |
| | -0.0005 | -0.0006 | -0.005 |
| Extreme Environment | 0.0002 | 0.0001 | 0.003 |
| | -0.0005 | -0.0006 | -0.005 |
| Abnormal ; LOCA | 0.0004 | 0.0003 | 0.003 |
| | -0.0017 | -0.0020 | -0.005 |
| Abnormal/Extreme Environment | 0.0005 | 0.0004 | 0.003 |
| | -0.0017 | -0.0021 | -0.005 |

**Table 3G.1-36
Drywell Head Elements Stress Summary**

| Service Level | PL | | PL+Pb | | PL+Pb+Q | |
|------------------|-------------------------|------------------------|-------------------------|------------------------|-------------------------|------------------------|
| | Calculated Stress (MPa) | Allowable Stress (MPa) | Calculated Stress (MPa) | Allowable Stress (MPa) | Calculated Stress (MPa) | Allowable Stress (MPa) |
| Test Condition | 77 | 262 | 77 | 262 | - | - |
| Design Condition | 66 | 227 | 66 | 227 | - | - |
| A, B | 66 | 227 | 66 | 227 | 794 *1 | 456 |
| C | 73 | 342 | 73 | 342 | - | - |
| D | 73 | 430 | 73 | 430 | - | - |

*1 Acceptable by meeting all requirements for simplified elastic-plastic analysis stipulated in NE-3228.3 of ASME B&PV Code, Sec.III.

Table 3G.1-37
Diaphragm Floor (D/F) Slab Elements Stress Summary

| Structural Elements | Member Size | Governing Load Combination | Stress or Stress Ratio | Allowable Stress | Acceptance Criteria *2 |
|------------------------------------|--------------------|-----------------------------------|---|--|-------------------------------|
| Top Plate | 25mm | Abnormal Abnormal/Extreme | $\sigma_{\min} = -377\text{MPa}$ $\tau_{\max} = 200\text{MPa}$ | $\sigma = 391\text{MPa}$ $\tau = 243\text{MPa}$ | 1.5S 1.4S |
| Bottom Plate | 25mm | Abnormal Abnormal/Extreme | $\sigma_{\min} = -399\text{MPa}$ $\tau_{\max} = 202\text{MPa}$ | $\sigma = 408\text{MPa}$ $\tau = 253\text{MPa}$ | 1.5S 1.4S |
| Radial Web Plate (Upper Web) | 25mm | Abnormal Normal | $\sigma_{\min} = -336\text{MPa}$ $\tau_{\max} = 150\text{MPa}$ | $\sigma = 391\text{MPa}$ $\tau = 174\text{MPa}$ | 1.5S 1.0S |
| Radial Web Plate (Lower Web) *1 | 25mm | Normal Normal | $\sigma_{\min} = -201\text{MPa}$ $\tau_{\max} = 141\text{MPa}$ | $\sigma = 261\text{MPa}$ $\tau = 181\text{MPa}$ | 1.0S 1.0S |
| Tangential Web Plate*1 | 25mm | Severe Normal | $\sigma_{\min} = -83\text{MPa}$ $\tau_{\max} = 61\text{MPa}$ | $\sigma = 261\text{MPa}$ $\tau = 174\text{MPa}$ | 1.0S 1.0S |
| Bottom Flange*1 | 38mm | Normal Normal | $\sigma_{\min} = -160\text{MPa}$ $\tau_{\max} = 80\text{MPa}$ | $\sigma = 269\text{MPa}$ $\tau = 181\text{MPa}$ | 1.0S 1.0S |

*1 Thermal stress associated with extreme and abnormal load conditions meets deformation limits of AISC N690 Section Q1.5.7.2. The total stress excluding thermal stress satisfies the allowable stress limit in Table Q1.5.7.1 of AISC N690.

*2 S = Allowable stress limit specified in part 1 of AISC N690.

Table 3G.1-38
Diaphragm Floor (D/F) Slab Anchorage Structural Capacity

| Anchor Locations | Governing Load Combination | Design Load (kN) | No. of Anchor Bars Provided | Total Capacity (kN) | Acceptance Criteria *1 |
|-------------------------|-----------------------------------|-------------------------|------------------------------------|----------------------------|-------------------------------|
| Top Plate | Normal (SIT) | 639/deg | 1-#18 @ 0.9 deg | 782/deg | 0.66F _y |
| Bottom Plate | Normal | 153/deg | 1-#18 @ 0.9 deg | 591/deg | 0.5F _y |
| Girder Radial Web Plate | Abnormal/Extreme | 4300 | 5-#18 | 4804 | 0.9F _y |
| Girder Bottom Flange | Abnormal/Extreme | 3320 | 5-#18 | 4804 | 0.9F _y |

*1 F_y = Specified minimum yield stress.

Table 3G.1-39

Vent Wall Structural Elements Stress Summary

| Structural Elements | Member Size | Governing Load Combination | Calculated Stress | Allowable Stress | Acceptance Criteria *1 |
|---------------------|-------------|----------------------------|----------------------------------|--------------------------|------------------------|
| Inner Cylinder | 25mm | Abnormal/Extreme | $\sigma_{\min} = -266\text{MPa}$ | $\sigma = 417\text{MPa}$ | 1.6S |
| | | Abnormal/Extreme | $\tau_{\max} = 133\text{MPa}$ | $\tau = 243\text{MPa}$ | 1.4S |
| Outer Cylinder | 25mm | Abnormal | $\sigma_{\min} = -262\text{MPa}$ | $\sigma = 408\text{MPa}$ | 1.5S |
| | | Abnormal/Extreme | $\tau_{\max} = 152\text{MPa}$ | $\tau = 253\text{MPa}$ | 1.4S |
| Radial Web Plate | 25mm | Abnormal/Extreme | $\sigma_{\min} = -299\text{MPa}$ | $\sigma = 417\text{MPa}$ | 1.6S |
| | | Abnormal/Extreme | $\tau_{\max} = 174\text{MPa}$ | $\tau = 243\text{MPa}$ | 1.4S |

*1 S = Allowable stress limit specified in part 1 of AISC N690.

Table 3G.1-40

Reactor Shield Wall (RSW) Structural Element Stress Summary

| Structural Element | Member Size | Governing Load Combination | Calculated Stress | Allowable | Acceptance Criteria *1 |
|--------------------|-------------|----------------------------|----------------------------------|--------------------------|------------------------|
| RSW | 260mm | Abnormal/Extreme | $\sigma_{\min} = -223\text{MPa}$ | $\sigma = 417\text{MPa}$ | 1.6S |
| Cylindrical Shell | 260mm | Abnormal/Extreme | $\tau_{\max} = 111\text{MPa}$ | $\tau = 243\text{MPa}$ | 1.4S |

*1 S = Allowable stress limit specified in part 1 of AISC N690.

Table 3G.1-41

RPV Support Bracket Structural Elements Stress Summary

| Structural Elements | Member Size | Governing Load Combination | Stress or Stress Ratio | Allowable Stress | Acceptance Criteria *1 *2 |
|---------------------|-------------|----------------------------|----------------------------------|--------------------------|------------------------------|
| Horizontal Plate | 100mm | Abnormal/Extreme | $\sigma_{\max} = 306\text{MPa}$ | $\sigma = 371\text{MPa}$ | 0.7Fu |
| | | Abnormal/Extreme | $\tau_{\max} = 157\text{MPa}$ | $\tau = 243\text{MPa}$ | 1.4S |
| Vertical Plate | 150mm | Abnormal/Extreme | $\sigma_{\min} = -169\text{MPa}$ | $\sigma = 225\text{MPa}$ | 1.6S |
| | | Abnormal/Extreme | $\tau_{\max} = 91\text{MPa}$ | $\tau = 131\text{MPa}$ | 1.4S |

*1 Fu = Specified minimum tensile stress.

*2 S = Allowable stress limit specified in Part 1 of AISC N690.

Table 3G.1-42

Vent Wall and RPV Support Bracket Anchorage Structural Capacity

| Anchor Locations | Governing Load Combination | Design Load (kN) | No. of Anchor Bars Provided | Total Capacity (kN) | Acceptance Criteria*1 |
|---------------------|----------------------------|------------------|-----------------------------|---------------------|-----------------------|
| Vent Wall | Abnormal/Extreme | 1663/deg | 4-#18 @ 1.8deg | 2112/deg | 0.9Fy |
| RPV Support Bracket | Abnormal/Extreme | 45400 | 60-#18 | 57600 | 0.9Fy |

*1 Fy = Specified minimum yield stress.

Table 3G.1-43

Gravity Driven Cooling System (GDSCS) Pool Structural Elements Stress Summary

| Structural Elements | Member Size | Governing Load Combination | Stress or Stress Ratio | Allowable Stress | Acceptance Criteria *2 |
|----------------------|-------------|------------------------------|---|--|------------------------|
| Wall Plate | 16mm | Abnormal Abnormal/Extreme | $\sigma_{\min} = -387\text{MPa}$ $\tau_{\max} = 234\text{MPa}$ | $\sigma = 391\text{MPa}$ $\tau = 243\text{MPa}$ | 1.5S 1.4S |
| Vertical Column | 550x550x25 | Severe Abnormal/Extreme | Ratio = 0.63 $\tau = 108\text{MPa}$ | Ratio = 1.0 $\tau = 243\text{MPa}$ | S 1.4S |
| Vertical Column | 750x750x32 | Severe Abnormal/Extreme | Ratio = 0.91 $\tau = 169\text{MPa}$ | Ratio = 1.0 $\tau = 243\text{MPa}$ | S 1.4S |
| Horizontal Member *1 | 450x450x25 | Severe Severe | Ratio = 0.61 $\tau = 55\text{MPa}$ | Ratio = 1.0 $\tau = 174\text{MPa}$ | S S |
| Bracing Member | 200x200x25 | Abnormal/Extreme Severe | Ratio = 0.78 $\tau = 18\text{MPa}$ | Ratio = 1.0 $\tau = 174\text{MPa}$ | 1.6S S |

*1 Thermal stress associated with extreme and abnormal load conditions meets deformation limits of AISC N690 Section Q1.5.7.2. The total stress excluding thermal stress satisfies the allowable stress limit in Table Q1.5.7.1 of AISC N690.

*2 S = Allowable stress limit specified in Part 1 of AISC N690.

Table 3G.1-44
Gravity Driven Cooling System (GDCS) Pool Anchorage Structural Capacity

| Anchor Locations | Governing Load Combination | Design Load / Anchor Bar (kN) | Capacity / Anchor Bar (kN) | Acceptance Criteria *1 |
|-----------------------------------|----------------------------|-------------------------------|----------------------------|------------------------|
| Bracing Members @ RCCV Wall | Abnormal/Extreme | 613 | 960 | 0.9F _y |
| Horizontal Members @ RCCV Wall | Abnormal/Extreme | 842 | 960 | 0.9F _y |

*1 F_y = Specified minimum yield stress.

Table 3G.1-45

Combined Forces and Moments: RB, Selected Load Combination RB-4

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | OTHR | -2.338 | -3.837 | -0.785 | 0.037 | 0.427 | 0.008 | 0.048 | 0.132 |
| | | TEMP | 3.302 | 3.192 | 0.403 | 0.400 | 1.487 | 0.056 | -0.166 | 0.518 |
| | 20023 | OTHR | -1.564 | -1.510 | -0.465 | 0.040 | -0.314 | 0.034 | -0.016 | -0.171 |
| | | TEMP | -4.222 | -2.622 | 1.119 | -2.956 | -3.848 | 0.045 | -1.060 | -0.836 |
| | 30010 | OTHR | -1.806 | -2.425 | -0.279 | -0.384 | -2.033 | 0.019 | 0.005 | 1.240 |
| | | TEMP | 0.589 | 3.018 | -0.068 | 1.328 | 4.243 | -0.021 | -0.028 | -0.755 |
| | 30020 | OTHR | -1.294 | -1.461 | -0.193 | -0.689 | -0.845 | 0.022 | -0.264 | 0.365 |
| | | TEMP | -0.133 | -1.376 | -0.255 | 0.157 | 1.425 | 0.145 | -0.034 | -0.363 |
| | 40001 | OTHR | -1.002 | -1.708 | 0.283 | -0.418 | -1.300 | -0.265 | 0.134 | 0.768 |
| | | TEMP | -0.207 | -0.899 | -0.037 | 0.221 | 1.578 | -0.095 | 0.154 | -0.406 |
| | 40011 | OTHR | -1.716 | -3.458 | -0.041 | -0.463 | -2.658 | -0.005 | 0.007 | 2.194 |
| | | TEMP | 1.070 | 3.409 | 0.069 | 1.360 | 4.550 | 0.010 | 0.015 | -0.846 |
| 22 Exterior Wall @ EL4.65 ~-6.60m | 22011 | OTHR | -0.233 | -2.976 | 0.712 | -0.007 | 0.045 | 0.009 | -0.025 | 0.091 |
| | | TEMP | 2.396 | 2.929 | -0.220 | -0.084 | -0.025 | 0.038 | 0.021 | 0.216 |
| | 22023 | OTHR | -0.112 | -1.607 | 0.011 | 0.032 | 0.019 | -0.097 | 0.112 | 0.031 |
| | | TEMP | 1.485 | -4.752 | 0.539 | 0.254 | -0.154 | -0.198 | 0.145 | 0.030 |
| | 32010 | OTHR | -0.377 | -1.978 | -0.016 | -0.025 | -0.087 | 0.002 | 0.001 | 0.000 |
| | | TEMP | 15.865 | 7.739 | -0.006 | -3.498 | -3.263 | -0.005 | -0.002 | -0.245 |
| | 32020 | OTHR | -0.046 | -1.838 | -0.024 | -0.099 | -0.078 | -0.021 | -0.039 | 0.020 |
| | | TEMP | 0.372 | 5.212 | 2.952 | -0.762 | -2.361 | -0.499 | 0.919 | 0.136 |
| | 42001 | OTHR | -0.039 | -1.933 | -0.039 | -0.085 | -0.114 | 0.057 | 0.031 | 0.054 |
| | | TEMP | 2.936 | 3.681 | 3.048 | -0.980 | -2.143 | -0.049 | -0.848 | -0.343 |
| | 42011 | OTHR | -0.599 | -2.773 | -0.060 | -0.036 | -0.200 | 0.005 | 0.006 | 0.047 |
| | | TEMP | 14.232 | 5.754 | 0.125 | -3.625 | -3.085 | 0.092 | 0.088 | -0.197 |
| 23 Exterior Wall @ EL22.50 ~-24.60m | 24211 | OTHR | -0.140 | -1.638 | 0.078 | -0.064 | -0.440 | 0.008 | -0.002 | -0.111 |
| | | TEMP | 3.279 | 2.935 | -0.364 | -0.167 | -0.569 | -0.047 | -0.053 | 2.406 |
| | 24224 | OTHR | -0.018 | -0.985 | 0.293 | 0.037 | -0.062 | -0.038 | -0.079 | -0.046 |
| | | TEMP | 0.227 | 5.676 | -4.367 | 0.804 | -0.351 | -0.718 | -0.757 | -0.278 |
| | 34210 | OTHR | -0.009 | -0.821 | 0.044 | -0.002 | -0.042 | -0.002 | 0.004 | 0.010 |
| | | TEMP | 16.993 | 5.968 | -0.582 | -3.644 | -3.497 | 0.038 | -0.015 | -0.213 |
| | 34220 | OTHR | 0.049 | -0.957 | -0.178 | 0.039 | -0.030 | -0.009 | 0.046 | 0.004 |
| | | TEMP | 1.840 | 5.678 | 2.329 | 0.739 | -2.179 | -0.461 | 1.828 | 0.124 |
| | 44201 | OTHR | 0.024 | -1.101 | -0.332 | 0.048 | -0.013 | 0.021 | -0.040 | 0.000 |
| | | TEMP | 1.107 | 6.208 | -0.828 | 0.224 | -2.398 | 0.566 | -2.258 | 0.147 |

OTHR: Loads other than thermal loads

TEMP: Thermal loads

Table 3G.1-46

Combined Forces and Moments: RB, Selected Load Combination RB-8a

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 18 Wall Below RCCV Bottom | 6 | OTHR | -2.585 | -8.230 | -0.231 | 0.308 | 1.462 | -0.008 | 0.004 | 0.600 |
| | | TEMP | 0.931 | -1.122 | -0.745 | 0.243 | 1.608 | -0.041 | 0.046 | 0.242 |
| | 13 | OTHR | -2.289 | -6.898 | -0.039 | -0.072 | -0.145 | 0.012 | -0.007 | 0.069 |
| | | TEMP | 0.411 | -3.019 | -0.612 | 0.436 | 2.455 | 0.002 | 0.013 | 0.527 |
| | 24 | OTHR | -1.736 | -7.576 | -0.429 | -0.268 | -1.541 | -0.003 | 0.009 | -0.555 |
| | | TEMP | 0.330 | -3.256 | 0.153 | 0.473 | 2.598 | -0.007 | 0.001 | 0.588 |
| 19 Wall Below Below RCCV Mid-Height | 806 | OTHR | -1.207 | -7.144 | -0.082 | 0.019 | 0.221 | 0.003 | -0.020 | -0.042 |
| | | TEMP | 1.402 | -1.850 | 0.087 | 0.220 | 1.175 | 0.076 | -0.051 | -0.079 |
| | 813 | OTHR | -1.724 | -6.996 | 0.034 | 0.017 | 0.296 | -0.019 | 0.008 | 0.083 |
| | | TEMP | 0.936 | -3.006 | -0.511 | 0.150 | 1.159 | -0.032 | 0.010 | 0.459 |
| | 824 | OTHR | -2.088 | -7.810 | -0.399 | 0.140 | 0.594 | -0.010 | -0.002 | 0.183 |
| | | TEMP | 0.749 | -3.304 | 0.159 | 0.167 | 1.199 | 0.020 | 0.009 | 0.452 |
| 20 Wall Below RCCV Top | 1606 | OTHR | 1.452 | -6.655 | -0.099 | -0.862 | -4.761 | 0.024 | 0.007 | 1.350 |
| | | TEMP | 10.805 | -2.483 | 0.058 | -0.665 | -3.014 | 0.082 | 0.059 | 2.184 |
| | 1613 | OTHR | 0.961 | -7.055 | 0.202 | -0.842 | -4.690 | -0.003 | -0.020 | 1.372 |
| | | TEMP | 10.442 | -3.559 | -0.426 | -0.713 | -4.000 | -0.009 | -0.013 | 2.514 |
| | 1624 | OTHR | 0.692 | -7.593 | -0.248 | -0.741 | -4.413 | 0.010 | -0.022 | 1.292 |
| | | TEMP | 11.250 | -4.196 | -0.083 | -0.794 | -4.030 | 0.001 | -0.077 | 2.602 |
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | OTHR | -1.852 | -3.292 | -0.679 | 0.133 | 0.750 | 0.016 | 0.035 | 0.239 |
| | | TEMP | 2.705 | 3.066 | 0.389 | 0.368 | 1.368 | 0.053 | -0.156 | 0.466 |
| | 20023 | OTHR | -1.202 | -1.461 | -0.490 | 0.015 | -0.286 | 0.025 | -0.041 | -0.158 |
| | | TEMP | -3.251 | -1.996 | 0.825 | -2.301 | -2.914 | 0.034 | -0.800 | -0.621 |
| | 30010 | OTHR | -1.290 | -2.229 | -0.190 | -0.221 | -1.225 | 0.011 | 0.003 | 0.890 |
| | | TEMP | 0.724 | 2.695 | -0.073 | 1.092 | 3.667 | -0.017 | -0.022 | -0.637 |
| | 30020 | OTHR | -0.964 | -1.562 | -0.227 | -0.546 | -0.762 | 0.020 | -0.158 | 0.324 |
| | | TEMP | -0.071 | -1.233 | -0.217 | 0.074 | 1.116 | 0.124 | -0.017 | -0.276 |
| | 40001 | OTHR | -0.757 | -1.739 | 0.347 | -0.336 | -1.078 | -0.201 | 0.070 | 0.623 |
| | | TEMP | -0.153 | -0.846 | 0.059 | 0.127 | 1.264 | -0.082 | 0.120 | -0.316 |
| | 40011 | OTHR | -1.409 | -3.060 | -0.029 | -0.277 | -1.686 | -0.001 | 0.006 | 1.620 |
| | | TEMP | 0.891 | 3.003 | 0.054 | 1.119 | 3.906 | 0.009 | 0.013 | -0.707 |
| 22 Exterior Wall @ EL4.65 ~-6.60m | 22011 | OTHR | 0.250 | -2.538 | 0.588 | -0.006 | 0.094 | 0.011 | -0.026 | 0.142 |
| | | TEMP | 3.318 | 2.710 | -0.171 | -0.103 | -0.066 | 0.048 | 0.030 | 0.058 |
| | 22023 | OTHR | -0.052 | -1.467 | -0.024 | 0.112 | 0.043 | -0.101 | 0.075 | 0.019 |
| | | TEMP | 1.285 | -3.170 | 0.477 | 0.534 | -0.054 | -0.170 | 0.006 | 0.009 |
| | 32010 | OTHR | 0.216 | -1.777 | 0.022 | -0.020 | 0.013 | 0.008 | 0.000 | -0.096 |
| | | TEMP | 14.112 | 6.168 | -0.023 | -2.775 | -2.672 | 0.003 | -0.007 | -0.020 |
| | 32020 | OTHR | 0.005 | -1.760 | 0.189 | 0.001 | -0.031 | -0.056 | 0.011 | 0.027 |
| | | TEMP | 0.400 | 4.604 | 2.519 | -0.338 | -1.807 | -0.378 | 0.875 | 0.157 |
| | 42001 | OTHR | 0.000 | -1.814 | 0.070 | 0.027 | -0.063 | 0.059 | -0.010 | 0.049 |
| | | TEMP | 2.426 | 3.483 | 2.473 | -0.440 | -1.604 | -0.045 | -0.762 | -0.249 |
| | 42011 | OTHR | -0.123 | -2.264 | -0.022 | -0.042 | -0.111 | -0.004 | 0.005 | -0.055 |
| | | TEMP | 12.516 | 4.854 | 0.184 | -2.941 | -2.613 | 0.072 | 0.080 | 0.063 |
| 23 Exterior Wall @ EL22.50 ~-24.60m | 24211 | OTHR | 0.345 | -1.191 | 0.048 | 0.005 | -0.034 | 0.017 | 0.005 | -0.300 |
| | | TEMP | 3.814 | 3.230 | -0.215 | -0.028 | 0.139 | -0.034 | -0.045 | 1.652 |
| | 24224 | OTHR | -0.003 | -1.187 | 0.105 | 0.018 | -0.029 | -0.010 | -0.041 | -0.042 |
| | | TEMP | 0.397 | 5.311 | -3.629 | 0.850 | -0.366 | -0.448 | -0.780 | -0.397 |
| | 34210 | OTHR | 0.575 | -0.662 | 0.116 | 0.010 | 0.168 | -0.003 | 0.000 | 0.060 |
| | | TEMP | 14.993 | 4.941 | -0.346 | -2.787 | -2.420 | 0.017 | -0.013 | 0.093 |
| | 34220 | OTHR | 0.056 | -1.178 | -0.065 | 0.057 | 0.022 | 0.009 | 0.031 | -0.009 |
| | | TEMP | 1.556 | 5.056 | 1.786 | 0.885 | -1.523 | -0.164 | 1.522 | -0.010 |
| | 44201 | OTHR | 0.037 | -1.274 | -0.135 | 0.059 | 0.021 | 0.011 | -0.034 | -0.006 |
| | | TEMP | 0.989 | 5.532 | -0.249 | 0.541 | -1.740 | 0.350 | -1.832 | 0.050 |

**Table 3G.1-46
Combined Forces and Moments: RB, Selected Load Combination RB-8a (Continued)**

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|-------------------------------|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 24 Basemat @ Wall Below RCCV | 90140 | OTHR | -2.616 | -2.477 | 0.157 | -2.121 | -1.168 | 1.196 | -2.800 | 2.490 |
| | | TEMP | 0.810 | 0.936 | 1.517 | -0.214 | -0.335 | -0.493 | -1.094 | 0.272 |
| | 90182 | OTHR | -1.641 | -2.233 | -0.257 | -0.707 | -1.154 | 0.256 | 0.088 | 1.580 |
| | | TEMP | 2.212 | 0.531 | 0.485 | -0.412 | -3.757 | 0.157 | -0.104 | 2.793 |
| | 90111 | OTHR | -3.798 | -1.449 | -0.006 | -1.461 | -0.524 | -0.304 | 0.951 | 0.299 |
| | | TEMP | 0.599 | 2.397 | -0.039 | -4.358 | -0.699 | 0.073 | 3.051 | 0.135 |
| 25 Slab EL4.65m @ RCCV | 93140 | OTHR | -0.231 | 0.483 | 0.777 | 0.128 | 0.135 | -0.144 | 0.126 | -0.105 |
| | | TEMP | 0.137 | 2.182 | 3.808 | -0.512 | -0.403 | 0.288 | -0.137 | 0.113 |
| | 93182 | OTHR | 0.762 | -0.320 | -0.001 | -0.026 | 0.079 | 0.014 | 0.000 | 0.099 |
| | | TEMP | 3.923 | -3.798 | -1.042 | -0.359 | -1.845 | -0.083 | 0.076 | 1.379 |
| | 93111 | OTHR | -0.013 | 0.686 | -0.124 | 0.059 | -0.031 | -0.003 | 0.073 | -0.005 |
| | | TEMP | -3.346 | 4.625 | -0.234 | -1.884 | -0.337 | -0.050 | 1.257 | 0.001 |
| 26 Slab EL17.5m @ RCCV | 96144 | OTHR | 0.048 | 0.666 | 0.817 | 0.074 | 0.085 | -0.081 | 0.123 | -0.107 |
| | | TEMP | -0.269 | 4.658 | 7.008 | -0.257 | -0.148 | 0.178 | -0.080 | 0.026 |
| | 96186 | OTHR | 1.039 | -0.414 | -0.013 | -0.037 | -0.115 | -0.005 | 0.005 | 0.051 |
| | | TEMP | 6.641 | -4.128 | -1.421 | -0.104 | -0.385 | -0.051 | 0.018 | 0.399 |
| | 96113 | OTHR | -0.606 | 1.711 | -0.140 | -0.201 | -0.033 | -0.011 | 0.320 | 0.041 |
| | | TEMP | -8.012 | 3.448 | -1.490 | -4.673 | -2.833 | -0.192 | 1.013 | -0.053 |
| 27 Slab EL27.0m @ RCCV | 98472 | OTHR | 0.604 | 0.608 | -0.234 | -0.009 | 0.013 | -0.027 | 0.138 | -0.179 |
| | | TEMP | -1.976 | -0.331 | 5.371 | -0.390 | 0.080 | -0.331 | 0.460 | -0.565 |
| | 98514 | OTHR | 0.364 | 0.433 | 0.121 | -0.043 | -0.327 | 0.001 | 0.003 | -0.013 |
| | | TEMP | 0.290 | -2.436 | -1.243 | -0.535 | -0.083 | -0.010 | 0.037 | -0.712 |
| | 98424 | OTHR | 0.269 | 1.265 | -0.162 | -0.102 | 0.003 | -0.203 | -0.318 | -0.070 |
| | | TEMP | -9.771 | -8.139 | -2.242 | 6.366 | 3.591 | 0.270 | -4.372 | -0.664 |
| 28 Pool Girder @ Storage Pool | 123004 | OTHR | 0.747 | 0.952 | 1.149 | 0.049 | 0.211 | -0.055 | 0.055 | 0.155 |
| | | TEMP | -3.222 | -10.346 | 0.042 | 0.420 | 1.524 | -0.253 | -0.188 | 1.420 |
| | 123104 | OTHR | 0.317 | 0.223 | 1.284 | -0.012 | -0.031 | 0.000 | 0.037 | 0.040 |
| | | TEMP | -1.162 | -3.220 | 1.957 | -0.186 | -0.569 | 0.085 | -0.399 | 0.291 |
| 29 Pool Girder @ Cavity | 123012 | OTHR | -0.120 | -0.859 | -0.592 | 0.019 | 0.254 | -0.012 | 0.041 | 0.200 |
| | | TEMP | -1.585 | -0.088 | -0.191 | -0.062 | 0.579 | 0.047 | 0.057 | 0.427 |
| | 123112 | OTHR | 0.525 | -0.503 | -0.569 | 0.003 | -0.024 | -0.027 | 0.002 | 0.006 |
| | | TEMP | -2.307 | -0.056 | -0.067 | -0.143 | -0.117 | -0.095 | -0.040 | 0.096 |
| 30 Pool Girder @ Fuel Pool | 123017 | OTHR | 0.850 | 2.144 | -1.045 | -0.048 | -0.102 | 0.077 | 0.004 | -0.142 |
| | | TEMP | 0.774 | -6.892 | -0.909 | 2.470 | 2.743 | -0.228 | 0.208 | 0.415 |
| | 123117 | OTHR | -0.277 | 0.601 | -0.781 | 0.030 | 0.043 | 0.019 | 0.027 | 0.025 |
| | | TEMP | -0.985 | -2.677 | -0.715 | 2.293 | 1.832 | -0.079 | -0.209 | 0.279 |
| 31 MS Tunnel Wall and Slab | 150122 | OTHR | -0.184 | -0.341 | 0.968 | -0.013 | 0.073 | 0.021 | -0.024 | -0.052 |
| | | TEMP | 2.226 | -0.111 | -0.753 | 3.639 | 3.907 | 0.083 | -0.262 | -0.322 |
| | 96611 | OTHR | -0.094 | 0.552 | -0.069 | 0.070 | -0.127 | -0.087 | -0.200 | 0.008 |
| | | TEMP | -0.174 | 3.068 | -0.248 | -3.645 | -6.606 | -0.247 | 0.700 | 0.064 |
| | 98614 | OTHR | 0.017 | -0.019 | 0.044 | -0.334 | -0.746 | -0.071 | -0.081 | 0.015 |
| | | TEMP | 0.527 | 2.703 | -0.288 | 9.377 | 13.644 | 0.044 | -1.769 | -0.155 |

Table 3G.1-47

Combined Forces and Moments: RB, Selected Load Combination RB-8b

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 18 Wall Below RCCV Bottom | 6 | OTHR | -2.461 | -7.298 | -0.309 | 0.287 | 1.350 | -0.009 | 0.009 | 0.559 |
| | | TEMP | 0.500 | -1.652 | -0.970 | 0.379 | 2.436 | -0.053 | 0.065 | 0.459 |
| | 13 | OTHR | -2.184 | -5.983 | -0.135 | -0.074 | -0.177 | 0.010 | -0.005 | 0.048 |
| | | TEMP | -0.084 | -4.089 | -0.681 | 0.635 | 3.538 | 0.001 | 0.019 | 0.830 |
| | 24 | OTHR | -1.602 | -6.493 | -0.421 | -0.258 | -1.530 | -0.003 | 0.009 | -0.570 |
| | | TEMP | 0.018 | -3.987 | 0.219 | 0.642 | 3.557 | -0.009 | 0.000 | 0.840 |
| 19 Wall Below Below RCCV Mid-Height | 806 | OTHR | -1.141 | -6.158 | -0.157 | 0.016 | 0.200 | 0.000 | -0.021 | -0.045 |
| | | TEMP | 1.716 | -2.753 | 0.114 | 0.305 | 1.594 | 0.082 | -0.064 | -0.104 |
| | 813 | OTHR | -1.662 | -6.039 | -0.073 | 0.010 | 0.275 | -0.017 | 0.009 | 0.073 |
| | | TEMP | 1.264 | -4.042 | -0.538 | 0.199 | 1.585 | -0.036 | 0.005 | 0.613 |
| | 824 | OTHR | -2.009 | -6.663 | -0.392 | 0.142 | 0.569 | -0.009 | -0.002 | 0.184 |
| | | TEMP | 1.020 | -4.014 | 0.230 | 0.220 | 1.644 | 0.029 | 0.013 | 0.560 |
| 20 Wall Below RCCV Top | 1606 | OTHR | 1.409 | -5.592 | -0.135 | -0.759 | -4.186 | 0.024 | 0.007 | 1.196 |
| | | TEMP | 15.254 | -3.694 | 0.085 | -0.865 | -3.919 | 0.106 | 0.072 | 2.988 |
| | 1613 | OTHR | 0.896 | -6.060 | 0.111 | -0.739 | -4.074 | -0.003 | -0.020 | 1.197 |
| | | TEMP | 15.098 | -4.772 | -0.383 | -0.955 | -5.279 | -0.012 | -0.016 | 3.467 |
| | 1624 | OTHR | 0.642 | -6.393 | -0.253 | -0.638 | -3.821 | 0.010 | -0.021 | 1.121 |
| | | TEMP | 15.945 | -5.116 | -0.070 | -1.065 | -5.223 | 0.003 | -0.102 | 3.540 |
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | OTHR | -1.832 | -3.190 | -0.673 | 0.161 | 0.852 | 0.018 | 0.031 | 0.271 |
| | | TEMP | 3.015 | 4.539 | 0.539 | 0.546 | 2.096 | 0.065 | -0.209 | 0.722 |
| | 20023 | OTHR | -1.201 | -1.471 | -0.498 | 0.006 | -0.278 | 0.025 | -0.039 | -0.154 |
| | | TEMP | -3.247 | -1.943 | 0.806 | -2.359 | -2.817 | 0.031 | -0.795 | -0.575 |
| | 30010 | OTHR | -1.254 | -2.205 | -0.193 | -0.186 | -1.052 | 0.010 | 0.002 | 0.854 |
| | | TEMP | 1.001 | 3.822 | -0.190 | 1.305 | 4.878 | -0.022 | -0.029 | -0.906 |
| | 30020 | OTHR | -0.954 | -1.608 | -0.235 | -0.560 | -0.756 | 0.024 | -0.155 | 0.323 |
| | | TEMP | -0.043 | -1.519 | -0.380 | 0.011 | 1.225 | 0.146 | -0.023 | -0.288 |
| | 40001 | OTHR | -0.751 | -1.780 | 0.367 | -0.349 | -1.065 | -0.204 | 0.069 | 0.620 |
| | | TEMP | -0.085 | -1.165 | 0.093 | 0.037 | 1.359 | -0.099 | 0.110 | -0.329 |
| | 40011 | OTHR | -1.411 | -3.021 | -0.028 | -0.240 | -1.501 | 0.001 | 0.006 | 1.582 |
| | | TEMP | 1.348 | 3.854 | 0.063 | 1.290 | 4.897 | 0.012 | 0.016 | -0.910 |
| 22 Exterior Wall @ EL4.65 ~-6.60m | 22011 | OTHR | 0.359 | -2.469 | 0.573 | -0.005 | 0.110 | 0.012 | -0.027 | 0.166 |
| | | TEMP | 4.828 | 4.398 | -0.287 | -0.154 | -0.139 | 0.067 | 0.044 | 0.162 |
| | 22023 | OTHR | -0.041 | -1.450 | -0.006 | 0.144 | 0.051 | -0.108 | 0.066 | 0.017 |
| | | TEMP | 1.518 | -2.692 | 0.328 | 0.990 | 0.017 | -0.183 | -0.173 | 0.000 |
| | 32010 | OTHR | 0.351 | -1.753 | 0.018 | -0.021 | 0.031 | 0.010 | 0.000 | -0.125 |
| | | TEMP | 16.476 | 7.814 | -0.100 | -2.875 | -2.936 | -0.003 | -0.013 | -0.029 |
| | 32020 | OTHR | 0.018 | -1.724 | 0.242 | 0.025 | -0.024 | -0.067 | 0.027 | 0.031 |
| | | TEMP | 0.610 | 4.810 | 2.460 | 0.061 | -1.837 | -0.391 | 1.189 | 0.188 |
| | 42001 | OTHR | 0.015 | -1.768 | 0.090 | 0.058 | -0.056 | 0.063 | -0.021 | 0.052 |
| | | TEMP | 2.708 | 3.726 | 2.529 | 0.074 | -1.559 | -0.037 | -0.972 | -0.233 |
| | 42011 | OTHR | -0.008 | -2.186 | -0.007 | -0.047 | -0.102 | -0.006 | 0.005 | -0.081 |
| | | TEMP | 14.259 | 5.931 | 0.283 | -3.138 | -2.902 | 0.064 | 0.089 | 0.069 |
| 23 Exterior Wall @ EL22.50 ~-24.60m | 24211 | OTHR | 0.455 | -1.111 | 0.044 | 0.020 | 0.053 | 0.019 | 0.007 | -0.339 |
| | | TEMP | 5.628 | 6.168 | -0.121 | 0.036 | 0.461 | -0.032 | -0.057 | 1.532 |
| | 24224 | OTHR | 0.002 | -1.238 | 0.067 | 0.016 | -0.023 | -0.005 | -0.036 | -0.042 |
| | | TEMP | 1.066 | 6.059 | -3.947 | 1.882 | 0.047 | -0.627 | -1.457 | -0.289 |
| | 34210 | OTHR | 0.696 | -0.635 | 0.121 | 0.008 | 0.191 | -0.004 | 0.000 | 0.069 |
| | | TEMP | 21.500 | 5.814 | -0.637 | -2.922 | -2.837 | 0.043 | -0.005 | -0.143 |
| | 34220 | OTHR | 0.055 | -1.225 | -0.049 | 0.058 | 0.032 | 0.016 | 0.028 | -0.013 |
| | | TEMP | 2.573 | 6.295 | 3.703 | 2.522 | -1.254 | -0.604 | 2.464 | 0.060 |
| | 44201 | OTHR | 0.040 | -1.311 | -0.094 | 0.061 | 0.028 | 0.008 | -0.030 | -0.008 |
| | | TEMP | 1.787 | 7.067 | -0.242 | 2.081 | -1.543 | 0.575 | -2.867 | 0.058 |

Table 3G.1-47
Combined Forces and Moments: RB, Selected Load Combination RB-8b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|-------------------------------------|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| 24 Basemat @ Wall Below | 90140 | OTHR | -2.862 | -2.514 | 0.127 | -1.580 | -0.714 | 0.924 | -2.518 | 2.183 |
| | | TEMP | 0.656 | 1.198 | 1.910 | -1.176 | -1.209 | -0.620 | -1.549 | 0.481 |
| | 90182 | OTHR | -1.848 | -2.294 | -0.217 | -0.546 | -0.719 | 0.279 | 0.024 | 1.236 |
| | | TEMP | 2.512 | 0.741 | 0.349 | -1.062 | -5.489 | 0.225 | -0.058 | 3.881 |
| | 90111 | OTHR | -3.843 | -1.594 | -0.010 | -1.109 | -0.398 | -0.265 | 0.594 | 0.273 |
| | | TEMP | 0.765 | 3.129 | -0.048 | -5.573 | -1.340 | 0.131 | 3.888 | 0.160 |
| 25 Slab EL4.65m @ RCCV | 93140 | OTHR | -0.207 | 0.438 | 0.722 | 0.132 | 0.137 | -0.138 | 0.128 | -0.108 |
| | | TEMP | 0.492 | 2.917 | 5.382 | -0.741 | -0.577 | 0.416 | -0.195 | 0.167 |
| | 93182 | OTHR | 0.701 | -0.285 | 0.024 | -0.018 | 0.086 | 0.012 | -0.001 | 0.070 |
| | | TEMP | 5.915 | -4.974 | -1.483 | -0.488 | -2.534 | -0.114 | 0.106 | 1.921 |
| | 93111 | OTHR | 0.005 | 0.607 | -0.115 | 0.066 | -0.023 | -0.003 | 0.050 | -0.005 |
| | | TEMP | -4.283 | 6.565 | -0.433 | -2.488 | -0.436 | -0.068 | 1.677 | 0.002 |
| 26 Slab EL17.5m @ RCCV | 96144 | OTHR | 0.061 | 0.786 | 0.953 | 0.111 | 0.113 | -0.099 | 0.131 | -0.114 |
| | | TEMP | 0.700 | 5.749 | 8.267 | -0.286 | -0.227 | 0.196 | -0.057 | 0.076 |
| | 96186 | OTHR | 1.209 | -0.500 | -0.061 | -0.018 | -0.027 | 0.001 | 0.001 | -0.022 |
| | | TEMP | 9.948 | -4.570 | -2.192 | -0.167 | -0.770 | -0.060 | 0.028 | 0.708 |
| | 96113 | OTHR | -0.749 | 1.860 | -0.206 | -0.017 | 0.009 | 0.004 | 0.169 | 0.028 |
| | | TEMP | -8.874 | 6.067 | -1.617 | -4.618 | -2.819 | -0.231 | 0.824 | -0.088 |
| 27 Slab EL27.0m @ RCCV | 98472 | OTHR | 0.521 | 0.650 | -0.233 | 0.003 | 0.035 | -0.025 | 0.143 | -0.194 |
| | | TEMP | -4.962 | -2.596 | 6.296 | -1.806 | -1.112 | -0.359 | 0.516 | -0.793 |
| | 98514 | OTHR | 0.352 | 0.462 | 0.104 | -0.033 | -0.298 | -0.002 | 0.004 | -0.067 |
| | | TEMP | -2.970 | -2.936 | -1.382 | -1.925 | -1.714 | -0.029 | 0.056 | -0.715 |
| | 98424 | OTHR | 0.276 | 1.415 | -0.202 | -0.298 | 0.006 | -0.240 | -0.290 | -0.056 |
| | | TEMP | -8.160 | -4.306 | -3.504 | 8.110 | 4.330 | 0.601 | -4.475 | -0.830 |
| 28 Pool Girder @ Storage Pool | 123004 | OTHR | 1.040 | 1.803 | 1.811 | 0.049 | 0.223 | -0.077 | 0.075 | 0.152 |
| | | TEMP | -3.773 | -8.910 | 2.443 | -3.192 | -1.409 | -0.451 | -0.296 | 2.590 |
| | 123104 | OTHR | 0.279 | 0.492 | 1.880 | -0.004 | -0.023 | -0.009 | 0.028 | 0.046 |
| | | TEMP | -0.908 | -1.329 | 2.320 | -4.096 | -4.643 | 0.160 | -1.017 | 0.189 |
| 29 Pool Girder @ Cavity | 123012 | OTHR | -0.447 | -1.207 | -0.748 | 0.027 | 0.351 | -0.013 | 0.053 | 0.257 |
| | | TEMP | -1.054 | -0.015 | -0.253 | -3.807 | -2.087 | 0.177 | 0.085 | 1.518 |
| | 123112 | OTHR | 0.736 | -0.715 | -0.728 | 0.005 | -0.010 | -0.038 | 0.002 | 0.008 |
| | | TEMP | 0.270 | 0.204 | -0.469 | -4.115 | -3.707 | -0.173 | -0.004 | -0.028 |
| 30 Pool Girder @ Fuel Pool | 123017 | OTHR | 0.953 | 2.523 | -1.579 | -0.066 | -0.144 | 0.104 | -0.005 | -0.179 |
| | | TEMP | 5.174 | -7.676 | -2.218 | 2.827 | 2.660 | -0.299 | 0.268 | 0.240 |
| | 123117 | OTHR | -0.253 | 0.690 | -1.315 | 0.030 | 0.047 | 0.030 | 0.031 | 0.026 |
| | | TEMP | 1.809 | -2.768 | -0.560 | 2.974 | 1.894 | -0.159 | -0.541 | 0.254 |
| 31 MS Tunnel Wall and Slab | 150122 | OTHR | -0.165 | -0.317 | 0.982 | -0.023 | 0.068 | 0.020 | -0.022 | -0.058 |
| | | TEMP | 2.279 | -0.182 | -0.887 | 3.448 | 3.933 | 0.118 | -0.222 | -0.262 |
| | 96611 | OTHR | -0.127 | 0.596 | -0.083 | 0.040 | -0.167 | -0.089 | -0.189 | 0.009 |
| | | TEMP | -0.295 | 3.728 | -0.322 | -3.550 | -6.604 | -0.232 | 0.690 | 0.063 |
| | 98614 | OTHR | 0.041 | -0.029 | 0.050 | -0.413 | -0.769 | -0.076 | -0.068 | 0.016 |
| | | TEMP | 1.306 | 2.277 | -0.049 | 9.353 | 14.160 | -0.019 | -1.882 | -0.168 |

Table 3G.1-48

Combined Forces and Moments: RB, Selected Load Combination RB-9a

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|---------------------------------|---|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 18 Wall Below RCCV Bottom | 6 | OTHR | -2.277 | -8.129 | -0.186 | 0.176 | 0.701 | -0.006 | 0.002 | 0.363 | |
| | | TEMP | 0.931 | -1.122 | -0.745 | 0.243 | 1.608 | -0.041 | 0.046 | 0.242 | |
| | | EQEW | 4.080 | 9.611 | -4.318 | -0.696 | -3.389 | -0.046 | 0.140 | -1.392 | |
| | | EQNS | -4.226 | -2.828 | -3.149 | 0.950 | 5.629 | 0.027 | 0.006 | 2.014 | |
| | | EQZ | -0.321 | 4.250 | -0.279 | 0.231 | 1.518 | -0.009 | 0.024 | 0.450 | |
| | | EQT | 0.666 | 0.149 | 0.610 | -0.044 | -0.288 | -0.014 | 0.027 | -0.152 | |
| | | SPKW | -0.491 | 0.161 | -0.422 | -0.051 | -0.221 | -0.034 | 0.064 | -0.040 | |
| | | SPKN | -0.386 | -0.001 | 0.016 | 0.009 | 0.091 | 0.009 | -0.016 | 0.064 | |
| | 13 | OTHR | -2.021 | -6.714 | -0.066 | -0.201 | -0.894 | 0.011 | -0.007 | -0.162 | |
| | | TEMP | 0.411 | -3.019 | -0.612 | 0.436 | 2.455 | 0.002 | 0.013 | 0.527 | |
| | | EQEW | 4.939 | 9.278 | 0.447 | -0.384 | -2.349 | -0.019 | 0.036 | -1.176 | |
| | | EQNS | -0.092 | 2.940 | -3.947 | 0.616 | 3.308 | -0.083 | 0.135 | 0.998 | |
| | | EQZ | -0.421 | 3.452 | -0.258 | 0.399 | 2.157 | -0.007 | 0.010 | 0.633 | |
| | | EQT | 0.548 | 0.139 | 0.740 | -0.080 | -0.369 | -0.006 | 0.013 | -0.168 | |
| | | SPKW | 0.171 | 0.101 | 0.078 | -0.066 | -0.733 | -0.008 | 0.009 | -0.359 | |
| | | SPKN | -0.924 | 0.001 | -0.248 | 0.008 | 0.263 | 0.004 | -0.003 | 0.188 | |
| | 24 | OTHR | -1.387 | -7.320 | -0.442 | -0.394 | -2.280 | -0.002 | 0.008 | -0.786 | |
| | | TEMP | 0.330 | -3.256 | 0.153 | 0.473 | 2.598 | -0.007 | 0.001 | 0.588 | |
| | | EQEW | 0.630 | 0.657 | 6.609 | 0.010 | -0.204 | 0.106 | -0.160 | -0.129 | |
| | | EQNS | 2.743 | 8.464 | -0.014 | 0.216 | 1.126 | -0.009 | 0.003 | -0.018 | |
| | | EQZ | -0.417 | 3.860 | 0.100 | 0.425 | 2.253 | -0.005 | 0.002 | 0.637 | |
| | | EQT | 0.075 | 0.011 | 1.005 | 0.002 | -0.029 | -0.003 | 0.005 | -0.017 | |
| | | SPKW | -0.938 | 0.026 | 0.082 | 0.024 | 0.350 | 0.003 | -0.006 | 0.230 | |
| | | SPKN | 0.179 | 0.094 | -0.078 | -0.086 | -0.857 | -0.006 | 0.008 | -0.423 | |
| | 19 Wall Below Below RCCV Mid-Height | 806 | OTHR | -1.203 | -6.985 | -0.069 | 0.014 | 0.182 | -0.004 | -0.019 | -0.052 |
| | | | TEMP | 1.402 | -1.850 | 0.087 | 0.220 | 1.175 | 0.076 | -0.051 | -0.079 |
| | | | EQEW | 0.690 | 7.399 | -5.103 | -0.009 | 0.249 | -0.132 | -0.022 | 0.020 |
| EQNS | | | -2.173 | -2.516 | -3.422 | -0.138 | -0.431 | -0.021 | 0.024 | 0.198 | |
| EQZ | | | -0.054 | 3.702 | -0.048 | -0.019 | -0.024 | 0.019 | -0.004 | 0.065 | |
| EQT | | | 0.313 | 0.075 | 0.573 | 0.023 | 0.068 | -0.031 | -0.006 | -0.004 | |
| SPKW | | | -1.132 | 0.198 | -0.192 | -0.014 | 0.070 | -0.024 | -0.049 | -0.015 | |
| SPKN | | | -0.360 | 0.086 | 0.077 | -0.040 | -0.026 | 0.000 | 0.000 | 0.010 | |
| 813 | | OTHR | -1.727 | -6.723 | -0.008 | 0.002 | 0.242 | -0.021 | 0.008 | 0.037 | |
| | | TEMP | 0.936 | -3.006 | -0.511 | 0.150 | 1.159 | -0.032 | 0.010 | 0.459 | |
| | | EQEW | 1.979 | 8.078 | 0.751 | 0.012 | 0.364 | -0.002 | -0.016 | -0.087 | |
| | | EQNS | -0.413 | 3.201 | -4.445 | -0.018 | -0.076 | 0.039 | -0.051 | 0.288 | |
| | | EQZ | 0.021 | 3.433 | -0.210 | 0.018 | 0.014 | 0.021 | -0.002 | 0.157 | |
| | | EQT | 0.211 | 0.052 | 0.809 | -0.001 | 0.055 | -0.050 | 0.006 | -0.020 | |
| | | SPKW | -0.838 | -0.098 | 0.007 | 0.119 | 0.414 | 0.024 | -0.016 | 0.042 | |
| | | SPKN | -0.761 | 0.184 | -0.138 | -0.077 | -0.142 | -0.003 | 0.013 | -0.003 | |
| 824 | | OTHR | -2.043 | -7.509 | -0.418 | 0.127 | 0.538 | -0.010 | -0.001 | 0.139 | |
| | | TEMP | 0.749 | -3.304 | 0.159 | 0.167 | 1.199 | 0.020 | 0.009 | 0.452 | |
| | | EQEW | 0.194 | 0.650 | 7.276 | 0.037 | 0.064 | 0.059 | 0.069 | 0.036 | |
| | | EQNS | 0.979 | 7.859 | -0.125 | 0.047 | 0.231 | 0.002 | -0.001 | 0.236 | |
| | | EQZ | -0.053 | 3.860 | 0.103 | 0.036 | 0.019 | 0.007 | -0.003 | 0.199 | |
| | | EQT | 0.021 | 0.007 | 1.071 | 0.007 | 0.007 | -0.019 | 0.010 | 0.004 | |
| | | SPKW | -0.931 | 0.329 | 0.017 | -0.093 | -0.178 | -0.001 | -0.001 | -0.007 | |
| | | SPKN | -0.869 | -0.134 | 0.000 | 0.164 | 0.434 | 0.008 | -0.002 | 0.065 | |

OTHR: Loads other than thermal and seismic loads
 TEMP: Thermal loads
 EQEW: Horizontal seismic loads in the E-W direction
 EQNS: Horizontal seismic loads in the N-S direction
 EQZ: Vertical seismic loads
 EQT: Torsional seismic loads
 SPKW: Dynamic soil pressure during a horizontal earthquake in the E-W direction
 SPKN: Dynamic soil pressure during a horizontal earthquake in the N-S direction

Table 3G.1-48
Combined Forces and Moments: RB, Selected Load Combination RB-9a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|------------------------------|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 20 Wall Below RCCV Top | 1606 | OTHR | 0.988 | -6.414 | -0.050 | -0.652 | -3.566 | 0.024 | 0.007 | 1.000 |
| | | TEMP | 10.805 | -2.483 | 0.058 | -0.665 | -3.014 | 0.082 | 0.059 | 2.184 |
| | | EQEW | 0.628 | 5.038 | -5.272 | 0.082 | 0.563 | -0.019 | -0.005 | -0.110 |
| | | EQNS | -1.483 | -1.946 | -3.743 | -0.333 | -1.320 | -0.069 | -0.002 | 0.183 |
| | | EQZ | 0.407 | 3.300 | -0.034 | -0.123 | -0.670 | -0.005 | 0.004 | 0.219 |
| | | EQT | 0.125 | 0.054 | 0.710 | 0.010 | 0.019 | -0.017 | -0.002 | 0.013 |
| | | SPKW | -0.530 | 0.104 | 0.453 | -0.034 | -0.146 | 0.069 | 0.006 | 0.014 |
| | | SPKN | -0.181 | 0.094 | -0.130 | -0.042 | -0.060 | -0.016 | 0.001 | -0.009 |
| | 1613 | OTHR | 0.487 | -6.687 | 0.163 | -0.628 | -3.449 | -0.001 | -0.019 | 0.987 |
| | | TEMP | 10.442 | -3.559 | -0.426 | -0.713 | -4.000 | -0.009 | -0.013 | 2.514 |
| | | EQEW | 1.016 | 6.058 | 0.909 | 0.148 | 0.962 | -0.001 | 0.010 | -0.200 |
| | | EQNS | -0.138 | 3.051 | -4.514 | -0.243 | -1.271 | -0.022 | 0.009 | 0.366 |
| | | EQZ | 0.540 | 3.308 | -0.149 | -0.128 | -0.778 | -0.005 | 0.002 | 0.270 |
| | | EQT | 0.086 | -0.041 | 0.872 | 0.017 | 0.106 | -0.027 | -0.001 | -0.022 |
| | | SPKW | -0.031 | 0.069 | -0.065 | -0.049 | -0.514 | 0.002 | 0.003 | 0.244 |
| | | SPKN | -0.507 | 0.074 | 0.116 | -0.030 | 0.051 | -0.007 | -0.005 | -0.089 |
| | 1624 | OTHR | 0.189 | -7.266 | -0.268 | -0.522 | -3.152 | 0.008 | -0.022 | 0.897 |
| | | TEMP | 11.250 | -4.196 | -0.083 | -0.794 | -4.030 | 0.001 | -0.077 | 2.602 |
| | | EQEW | 0.076 | 0.521 | 7.447 | -0.016 | -0.009 | 0.052 | -0.049 | 0.027 |
| | | EQNS | 0.985 | 6.565 | -0.214 | -0.062 | -0.477 | -0.009 | 0.004 | 0.204 |
| | | EQZ | 0.471 | 3.747 | 0.069 | -0.133 | -0.780 | 0.001 | 0.004 | 0.262 |
| | | EQT | 0.003 | 0.006 | 1.120 | -0.002 | -0.001 | -0.016 | -0.006 | 0.002 |
| | | SPKW | -0.642 | 0.163 | -0.047 | -0.043 | 0.061 | -0.002 | 0.004 | -0.106 |
| | | SPKN | -0.081 | 0.048 | 0.057 | -0.023 | -0.469 | 0.002 | -0.011 | 0.215 |

Table 3G.1-48
Combined Forces and Moments: RB, Selected Load Combination RB-9a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 21 Exterior Wall @ EL-11.50 ~10.50m | 20011 | OTHR | -1.878 | -3.430 | -0.688 | 0.093 | 0.598 | 0.013 | 0.039 | 0.191 |
| | | TEMP | 2.705 | 3.066 | 0.389 | 0.368 | 1.368 | 0.053 | -0.156 | 0.466 |
| | | EQEW | -0.657 | -0.961 | -9.354 | -0.082 | 0.416 | 0.025 | 0.100 | 0.091 |
| | | EQNS | -0.662 | -1.083 | 0.877 | 1.978 | 8.162 | 0.050 | -0.088 | 3.032 |
| | | EQZ | 0.399 | 2.223 | 0.230 | 0.022 | -0.013 | -0.003 | -0.031 | -0.030 |
| | | EQT | 0.045 | 0.000 | 0.742 | 0.044 | 0.150 | -0.010 | 0.016 | 0.051 |
| | | SPKW | -0.940 | 0.122 | 0.125 | 0.019 | 0.107 | -0.005 | -0.002 | 0.047 |
| | | SPKN | 0.198 | 0.046 | -0.209 | -0.099 | -0.402 | 0.004 | 0.000 | -0.193 |
| | 20023 | OTHR | -1.204 | -1.442 | -0.478 | 0.028 | -0.296 | 0.025 | -0.042 | -0.165 |
| | | TEMP | -3.251 | -1.996 | 0.825 | -2.301 | -2.914 | 0.034 | -0.800 | -0.621 |
| | | EQEW | 0.059 | 4.728 | -0.475 | 0.320 | 0.224 | -0.093 | -0.079 | 0.031 |
| | | EQNS | -0.008 | -1.289 | -0.936 | -0.832 | 1.337 | 0.170 | 1.299 | 0.909 |
| | | EQZ | 0.013 | 0.711 | 0.290 | -0.077 | 0.136 | 0.003 | 0.048 | 0.091 |
| | | EQT | -0.071 | -0.099 | 0.316 | 0.150 | -0.095 | -0.040 | -0.281 | -0.111 |
| | | SPKW | -0.619 | -0.161 | 0.146 | -0.075 | -0.036 | 0.004 | 0.016 | 0.014 |
| | | SPKN | 0.085 | 0.082 | -0.115 | -0.003 | -0.002 | 0.005 | 0.015 | -0.017 |
| | 30010 | OTHR | -1.339 | -2.257 | -0.187 | -0.273 | -1.482 | 0.014 | 0.004 | 0.945 |
| | | TEMP | 0.724 | 2.695 | -0.073 | 1.092 | 3.667 | -0.017 | -0.022 | -0.637 |
| | | EQEW | 3.694 | 3.409 | 0.982 | -0.320 | -1.172 | -0.031 | -0.026 | 0.395 |
| | | EQNS | 1.283 | 2.225 | -3.374 | 0.481 | 2.677 | -0.053 | -0.091 | -0.745 |
| | | EQZ | 0.086 | 1.161 | -0.023 | 0.250 | 1.318 | -0.013 | -0.005 | -0.300 |
| | | EQT | 0.623 | -0.159 | 0.842 | -0.074 | -0.293 | -0.013 | -0.017 | 0.102 |
| | | SPKW | -0.102 | -0.362 | 0.000 | -0.054 | -0.444 | -0.009 | -0.009 | 0.538 |
| | | SPKN | -0.755 | 0.135 | -0.073 | 0.018 | 0.168 | 0.006 | 0.006 | -0.068 |
| | 30020 | OTHR | -0.978 | -1.495 | -0.216 | -0.527 | -0.769 | 0.015 | -0.163 | 0.324 |
| | | TEMP | -0.071 | -1.233 | -0.217 | 0.074 | 1.116 | 0.124 | -0.017 | -0.276 |
| | | EQEW | 0.512 | 2.678 | 1.213 | -0.065 | 0.349 | 0.031 | 0.086 | -0.091 |
| | | EQNS | 0.109 | 2.149 | -0.455 | 0.024 | 1.101 | 0.025 | -0.285 | -0.252 |
| | | EQZ | 0.037 | 0.598 | 0.129 | -0.136 | 0.364 | 0.042 | -0.080 | -0.124 |
| | | EQT | 0.111 | -0.186 | 0.205 | -0.040 | -0.050 | 0.005 | 0.118 | -0.005 |
| | | SPKW | -0.077 | -0.160 | -0.125 | -0.069 | -0.255 | 0.115 | -0.007 | 0.145 |
| | | SPKN | -0.231 | -0.074 | 0.067 | -0.289 | 0.022 | -0.037 | -0.108 | -0.046 |
| | 40001 | OTHR | -0.765 | -1.678 | 0.319 | -0.316 | -1.096 | -0.198 | 0.071 | 0.627 |
| | | TEMP | -0.153 | -0.846 | 0.059 | 0.127 | 1.264 | -0.082 | 0.120 | -0.316 |
| | | EQEW | 0.005 | 3.037 | 0.977 | 0.369 | 1.132 | 0.016 | 0.362 | -0.176 |
| | | EQNS | 0.366 | 1.950 | -0.726 | -0.198 | 0.593 | -0.080 | 0.012 | -0.170 |
| | | EQZ | 0.033 | 0.628 | -0.099 | -0.139 | 0.376 | -0.039 | 0.082 | -0.123 |
| | | EQT | -0.020 | 0.049 | 0.302 | 0.129 | 0.031 | 0.017 | 0.064 | 0.042 |
| | | SPKW | -0.237 | -0.076 | -0.075 | -0.240 | 0.040 | 0.034 | 0.086 | -0.041 |
| | | SPKN | -0.097 | -0.190 | 0.116 | -0.103 | -0.367 | -0.143 | -0.008 | 0.163 |
| | 40011 | OTHR | -1.403 | -3.110 | -0.031 | -0.333 | -1.960 | -0.002 | 0.005 | 1.677 |
| | | TEMP | 0.891 | 3.003 | 0.054 | 1.119 | 3.906 | 0.009 | 0.013 | -0.707 |
| | | EQEW | -0.252 | -0.361 | 4.538 | 0.015 | -0.047 | 0.085 | 0.124 | -0.029 |
| | | EQNS | 3.276 | 3.698 | -0.076 | 0.140 | 1.121 | 0.012 | 0.005 | -0.164 |
| | | EQZ | 0.128 | 1.494 | -0.001 | 0.288 | 1.476 | 0.009 | 0.002 | -0.326 |
| | | EQT | -0.021 | -0.014 | 0.917 | 0.006 | 0.005 | -0.006 | -0.007 | -0.010 |
| | | SPKW | -0.539 | 0.209 | 0.000 | 0.020 | 0.248 | -0.002 | -0.003 | -0.104 |
| | | SPKN | -0.224 | -0.417 | -0.024 | -0.053 | -0.519 | 0.004 | 0.004 | 0.587 |

Table 3G.1-48
Combined Forces and Moments: RB, Selected Load Combination RB-9a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 22 Exterior Wall @ EL4.65 ~6.60m | 22011 | OTHR | 0.121 | -2.632 | 0.608 | -0.007 | 0.075 | 0.009 | -0.025 | 0.118 |
| | | TEMP | 3.318 | 2.710 | -0.171 | -0.103 | -0.066 | 0.048 | 0.030 | 0.058 |
| | | EQEW | 0.466 | 3.318 | -6.436 | 0.034 | -0.023 | -0.021 | 0.029 | -0.002 |
| | | EQNS | -0.441 | -7.125 | 2.468 | 0.116 | 0.966 | 0.154 | -0.038 | 0.853 |
| | | EQZ | -0.121 | 1.929 | -0.415 | 0.007 | -0.026 | -0.001 | 0.012 | -0.024 |
| | | EQT | 0.025 | -0.350 | 0.750 | -0.005 | -0.001 | -0.020 | 0.001 | -0.005 |
| | | SPKW | -0.649 | 0.235 | -0.140 | -0.009 | -0.013 | 0.003 | -0.002 | 0.000 |
| | | SPKN | 0.118 | 0.144 | 0.013 | 0.025 | 0.049 | -0.007 | -0.003 | 0.073 |
| | 22023 | OTHR | -0.066 | -1.476 | -0.046 | 0.076 | 0.032 | -0.093 | 0.084 | 0.021 |
| | | TEMP | 1.285 | -3.170 | 0.477 | 0.534 | -0.054 | -0.170 | 0.006 | 0.009 |
| | | EQEW | 0.069 | 4.568 | -3.234 | 0.055 | -0.073 | 0.086 | -0.202 | -0.079 |
| | | EQNS | 0.104 | -4.679 | -0.933 | -0.214 | 0.171 | -0.153 | 0.394 | 0.153 |
| | | EQZ | -0.017 | 0.997 | 0.206 | 0.074 | 0.002 | 0.011 | -0.052 | -0.011 |
| | | EQT | -0.067 | 0.247 | 0.587 | 0.014 | -0.006 | -0.010 | -0.027 | -0.017 |
| | | SPKW | -0.336 | -0.137 | 0.601 | 0.024 | 0.011 | -0.023 | 0.019 | -0.004 |
| | | SPKN | 0.015 | 0.083 | 0.162 | 0.081 | 0.009 | -0.006 | -0.026 | 0.005 |
| | 32010 | OTHR | 0.050 | -1.814 | 0.027 | -0.020 | -0.010 | 0.006 | 0.000 | -0.063 |
| | | TEMP | 14.112 | 6.168 | -0.023 | -2.775 | -2.672 | 0.003 | -0.007 | -0.020 |
| | | EQEW | 0.643 | 3.408 | 0.932 | -0.019 | -0.097 | -0.012 | -0.001 | 0.219 |
| | | EQNS | -0.867 | 1.234 | -3.866 | -0.010 | -0.012 | 0.000 | -0.002 | -0.103 |
| | | EQZ | 0.012 | 1.087 | -0.027 | -0.001 | -0.028 | -0.002 | 0.000 | 0.013 |
| | | EQT | 0.223 | -0.010 | 0.982 | -0.001 | 0.007 | -0.018 | 0.002 | 0.009 |
| | | SPKW | -0.043 | -0.151 | 0.004 | -0.022 | -0.175 | -0.001 | 0.000 | 0.010 |
| | | SPKN | -0.319 | 0.066 | 0.060 | -0.009 | -0.002 | 0.000 | 0.001 | 0.003 |
| | 32020 | OTHR | -0.009 | -1.788 | 0.119 | -0.028 | -0.040 | -0.043 | -0.008 | 0.023 |
| | | TEMP | 0.400 | 4.604 | 2.519 | -0.338 | -1.807 | -0.378 | 0.875 | 0.157 |
| | | EQEW | 0.047 | 2.920 | 2.784 | 0.125 | -0.060 | 0.015 | 0.091 | 0.016 |
| | | EQNS | -0.041 | 3.265 | -1.524 | 0.147 | 0.024 | 0.003 | 0.129 | -0.002 |
| | | EQZ | 0.032 | 1.252 | 0.072 | 0.042 | 0.001 | 0.007 | 0.038 | 0.006 |
| | | EQT | 0.005 | -0.203 | 0.864 | -0.003 | -0.004 | -0.011 | -0.004 | 0.011 |
| | | SPKW | -0.005 | -0.031 | -0.126 | 0.016 | -0.068 | -0.102 | -0.059 | 0.022 |
| | | SPKN | -0.200 | -0.101 | 0.256 | -0.171 | -0.038 | 0.044 | -0.041 | 0.004 |
| | 42001 | OTHR | -0.016 | -1.855 | 0.037 | -0.011 | -0.071 | 0.055 | 0.003 | 0.046 |
| | | TEMP | 2.426 | 3.483 | 2.473 | -0.440 | -1.604 | -0.045 | -0.762 | -0.249 |
| | | EQEW | -0.017 | 2.714 | 2.956 | 0.166 | 0.064 | -0.012 | -0.063 | -0.031 |
| | | EQNS | 0.127 | 3.461 | -1.547 | 0.200 | -0.027 | -0.023 | -0.077 | -0.010 |
| | | EQZ | 0.039 | 1.311 | 0.061 | 0.053 | 0.002 | -0.001 | -0.027 | 0.002 |
| | | EQT | -0.019 | -0.222 | 0.860 | -0.003 | 0.013 | -0.013 | 0.003 | -0.013 |
| | | SPKW | -0.121 | -0.041 | -0.237 | -0.084 | -0.024 | -0.041 | 0.004 | 0.003 |
| | | SPKN | -0.037 | -0.085 | 0.119 | -0.029 | -0.061 | 0.133 | 0.133 | 0.022 |
| | 42011 | OTHR | -0.260 | -2.382 | -0.038 | -0.037 | -0.124 | -0.002 | 0.005 | -0.026 |
| | | TEMP | 12.516 | 4.854 | 0.184 | -2.941 | -2.613 | 0.072 | 0.080 | 0.063 |
| | | EQEW | 0.214 | -0.581 | 5.945 | 0.045 | 0.003 | 0.018 | 0.040 | -0.015 |
| | | EQNS | 0.749 | 3.196 | 0.267 | 0.003 | -0.098 | 0.009 | 0.000 | 0.092 |
| | | EQZ | 0.214 | 1.479 | 0.058 | -0.001 | -0.021 | 0.002 | -0.002 | 0.005 |
| | | EQT | 0.051 | -0.064 | 1.181 | 0.005 | 0.001 | -0.011 | 0.005 | -0.002 |
| | | SPKW | -0.203 | 0.107 | 0.030 | -0.015 | 0.003 | -0.001 | -0.002 | -0.002 |
| | | SPKN | -0.091 | -0.212 | 0.024 | -0.022 | -0.149 | 0.014 | 0.024 | 0.006 |

Table 3G.1-48
Combined Forces and Moments: RB, Selected Load Combination RB-9a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 23 Exterior Wall @ EL22.50 ~24.60m | 24211 | OTHR | 0.185 | -1.298 | 0.054 | -0.017 | -0.161 | 0.014 | 0.003 | -0.236 |
| | | TEMP | 3.814 | 3.230 | -0.215 | -0.028 | 0.139 | -0.034 | -0.045 | 1.652 |
| | | EQEW | -0.114 | 0.162 | -5.394 | -0.003 | 0.026 | 0.015 | 0.004 | 0.008 |
| | | EQNS | -1.174 | -5.369 | 0.191 | -0.170 | -0.660 | -0.042 | -0.003 | 0.840 |
| | | EQZ | 0.087 | 0.973 | -0.055 | 0.074 | 0.507 | -0.011 | 0.000 | 0.135 |
| | | EQT | 0.000 | -0.040 | 0.890 | -0.001 | -0.004 | -0.032 | -0.005 | 0.020 |
| | | SPKW | -0.053 | -0.031 | -0.004 | 0.002 | 0.009 | -0.001 | 0.000 | 0.000 |
| | | SPKN | -0.026 | 0.065 | -0.028 | -0.003 | -0.003 | 0.000 | -0.001 | 0.015 |
| | 24224 | OTHR | -0.011 | -1.086 | 0.160 | 0.018 | -0.043 | -0.019 | -0.050 | -0.047 |
| | | TEMP | 0.397 | 5.311 | -3.629 | 0.850 | -0.366 | -0.448 | -0.780 | -0.397 |
| | | EQEW | 0.259 | 3.913 | -3.713 | -0.231 | -0.100 | -0.022 | 0.227 | -0.045 |
| | | EQNS | -0.282 | -7.465 | 0.532 | 0.695 | 1.033 | -0.289 | 0.178 | 1.126 |
| | | EQZ | 0.039 | 0.762 | -0.252 | -0.010 | 0.046 | 0.050 | 0.040 | 0.028 |
| | | EQT | -0.026 | 0.368 | 0.803 | -0.082 | -0.201 | 0.028 | -0.100 | -0.263 |
| | | SPKW | -0.001 | 0.002 | 0.020 | 0.006 | -0.005 | 0.002 | -0.012 | -0.007 |
| | | SPKN | -0.006 | -0.120 | 0.071 | 0.031 | 0.062 | -0.006 | 0.036 | 0.080 |
| | 34210 | OTHR | 0.385 | -0.705 | 0.108 | 0.007 | 0.100 | -0.003 | 0.002 | 0.041 |
| | | TEMP | 14.993 | 4.941 | -0.346 | -2.787 | -2.420 | 0.017 | -0.013 | 0.093 |
| | | EQEW | -0.199 | 1.096 | 0.772 | 0.064 | 0.354 | -0.010 | -0.002 | 0.139 |
| | | EQNS | -1.211 | 0.237 | -3.509 | -0.031 | -0.189 | -0.011 | 0.011 | -0.088 |
| | | EQZ | 0.013 | 0.514 | -0.045 | -0.006 | -0.005 | 0.001 | -0.003 | -0.011 |
| | | EQT | 0.183 | -0.017 | 1.010 | 0.002 | 0.017 | -0.008 | 0.000 | 0.008 |
| | | SPKW | 0.016 | -0.040 | 0.002 | -0.002 | -0.023 | 0.001 | 0.000 | -0.010 |
| | | SPKN | -0.098 | 0.000 | -0.003 | -0.001 | 0.001 | -0.001 | 0.000 | 0.000 |
| | 34220 | OTHR | 0.056 | -1.100 | -0.095 | 0.054 | 0.006 | 0.003 | 0.034 | -0.005 |
| | | TEMP | 1.556 | 5.056 | 1.786 | 0.885 | -1.523 | -0.164 | 1.522 | -0.010 |
| | | EQEW | -0.162 | 0.839 | 2.354 | 0.119 | 0.142 | 0.026 | 0.026 | -0.022 |
| | | EQNS | -0.048 | 1.855 | -1.261 | 0.007 | 0.010 | -0.003 | 0.014 | -0.006 |
| | | EQZ | -0.042 | 0.660 | 0.115 | -0.034 | 0.017 | 0.007 | -0.029 | -0.002 |
| | | EQT | 0.022 | -0.043 | 0.825 | 0.027 | 0.009 | -0.016 | 0.006 | 0.019 |
| | | SPKW | 0.004 | 0.012 | -0.005 | 0.004 | -0.002 | -0.002 | 0.003 | 0.001 |
| | | SPKN | -0.001 | 0.024 | -0.002 | 0.001 | 0.000 | 0.001 | 0.000 | -0.001 |
| | 44201 | OTHR | 0.030 | -1.212 | -0.195 | 0.053 | 0.009 | 0.013 | -0.038 | -0.004 |
| | | TEMP | 0.989 | 5.532 | -0.249 | 0.541 | -1.740 | 0.350 | -1.832 | 0.050 |
| | | EQEW | 0.145 | 0.808 | 2.848 | 0.066 | 0.009 | 0.059 | -0.076 | 0.024 |
| | | EQNS | -0.107 | 2.171 | -1.075 | 0.032 | 0.040 | -0.008 | 0.012 | -0.013 |
| EQZ | | -0.013 | 0.763 | 0.232 | -0.031 | 0.008 | -0.010 | 0.033 | 0.001 | |
| EQT | | 0.031 | -0.063 | 0.814 | 0.013 | -0.003 | -0.009 | -0.025 | -0.019 | |
| SPKW | | 0.002 | 0.012 | 0.001 | 0.004 | 0.001 | -0.002 | -0.002 | -0.001 | |
| SPKN | | 0.003 | 0.022 | 0.007 | 0.000 | -0.002 | 0.000 | -0.001 | 0.000 | |

Table 3G.1-48
Combined Forces and Moments: RB, Selected Load Combination RB-9a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|-------------------------------|------------------------------|-------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 24 Basemat @ Wall Below | 90140 | OTHR | -2.775 | -2.595 | -0.016 | -2.285 | -1.271 | 1.697 | -2.645 | 2.382 | |
| | | TEMP | 0.810 | 0.936 | 1.517 | -0.214 | -0.335 | -0.493 | -1.094 | 0.272 | |
| | | EQEW | 0.415 | 4.638 | 2.888 | 0.033 | 3.216 | -2.595 | 2.865 | -5.032 | |
| | | EQNS | 0.034 | 1.460 | -2.130 | -6.707 | -0.901 | -0.370 | -2.810 | 1.163 | |
| | | EQZ | -0.060 | 0.480 | 0.263 | 1.419 | 0.971 | -2.078 | 0.964 | -1.107 | |
| | | EQT | 0.965 | -0.447 | 0.984 | 0.658 | 0.012 | -0.229 | 0.294 | 0.106 | |
| | | SPKW | -0.052 | -1.084 | -0.003 | -0.119 | 0.019 | -0.123 | -0.029 | -0.213 | |
| | | SPKN | -1.849 | 0.114 | -0.120 | -0.044 | -0.045 | 0.049 | -0.037 | 0.017 | |
| | 90182 | OTHR | -2.103 | -2.317 | -0.223 | -0.372 | -1.614 | 0.181 | 0.061 | 1.376 | |
| | | TEMP | 2.212 | 0.531 | 0.485 | -0.412 | -3.757 | 0.157 | -0.104 | 2.793 | |
| | | EQEW | 6.054 | 0.571 | 0.309 | 0.153 | -0.445 | -0.242 | -0.046 | -3.502 | |
| | | EQNS | 3.163 | 0.701 | -1.456 | -1.619 | -0.476 | 1.390 | -1.659 | 0.675 | |
| | | EQZ | 0.369 | 0.221 | 0.046 | -0.592 | 1.442 | 0.238 | -0.137 | -0.399 | |
| | | EQT | 1.000 | 0.064 | 0.515 | 0.020 | 0.260 | -0.335 | 0.346 | -0.258 | |
| | | SPKW | 0.120 | -1.176 | -0.143 | -0.170 | -0.632 | -0.021 | 0.026 | -0.440 | |
| | | SPKN | -1.507 | 0.096 | 0.137 | -0.018 | -0.210 | 0.106 | -0.110 | 0.162 | |
| | 90111 | OTHR | -3.876 | -1.729 | 0.008 | -1.955 | -0.228 | -0.380 | 0.736 | 0.289 | |
| | | TEMP | 0.599 | 2.397 | -0.039 | -4.358 | -0.699 | 0.073 | 3.051 | 0.135 | |
| | | EQEW | -0.250 | 0.765 | -0.889 | -0.470 | 0.409 | 1.439 | -0.060 | -2.916 | |
| | | EQNS | 1.027 | 5.920 | -0.258 | 0.380 | -1.228 | 0.393 | -2.033 | -0.131 | |
| | | EQZ | 0.246 | 0.490 | -0.027 | 1.301 | -0.708 | 0.327 | -0.439 | -0.071 | |
| | | EQT | -0.052 | 0.035 | -0.613 | -0.075 | 0.084 | 0.414 | 0.010 | -0.492 | |
| | | SPKW | 0.162 | -1.308 | 0.049 | -0.226 | -0.098 | 0.013 | 0.201 | -0.026 | |
| | | SPKN | -1.233 | 0.065 | -0.048 | -0.638 | -0.141 | 0.024 | -0.484 | 0.020 | |
| | 25 Slab EL4.65m @ RCCV | 93140 | OTHR | -0.268 | 0.369 | 0.667 | 0.109 | 0.120 | -0.121 | 0.125 | -0.104 |
| | | | TEMP | 0.137 | 2.182 | 3.808 | -0.512 | -0.403 | 0.288 | -0.137 | 0.113 |
| | | | EQEW | 0.376 | -0.215 | -0.049 | 0.156 | 0.126 | -0.093 | 0.047 | -0.033 |
| | | | EQNS | -1.560 | 0.330 | -0.338 | -0.361 | -0.226 | 0.156 | -0.082 | 0.108 |
| | | | EQZ | -0.001 | -0.080 | -0.032 | -0.041 | -0.051 | 0.031 | -0.067 | 0.055 |
| | | | EQT | 0.164 | -0.083 | 0.044 | 0.017 | 0.011 | -0.010 | 0.005 | -0.005 |
| SPKW | | | 0.047 | -0.822 | 0.094 | -0.028 | -0.028 | 0.019 | -0.015 | 0.002 | |
| SPKN | | | -0.302 | 0.113 | -0.040 | -0.001 | -0.004 | 0.002 | 0.000 | 0.002 | |
| 93182 | | OTHR | 0.570 | -0.324 | 0.024 | -0.016 | 0.064 | 0.012 | -0.001 | 0.056 | |
| | | TEMP | 3.923 | -3.798 | -1.042 | -0.359 | -1.845 | -0.083 | 0.076 | 1.379 | |
| | | EQEW | 0.013 | -0.083 | -0.165 | 0.085 | 0.479 | 0.017 | -0.023 | -0.425 | |
| | | EQNS | -0.546 | -0.147 | -0.448 | -0.089 | -0.343 | -0.012 | 0.018 | 0.317 | |
| | | EQZ | -0.073 | -0.068 | -0.025 | -0.020 | -0.060 | -0.004 | 0.005 | 0.099 | |
| | | EQT | 0.070 | 0.029 | -0.054 | 0.008 | 0.039 | 0.000 | -0.002 | -0.035 | |
| | | SPKW | -0.143 | -0.871 | -0.027 | -0.030 | -0.155 | -0.009 | 0.008 | 0.161 | |
| | | SPKN | -0.252 | -0.027 | 0.059 | 0.003 | 0.012 | 0.001 | -0.001 | -0.011 | |
| 93111 | | OTHR | -0.033 | 0.501 | -0.094 | 0.045 | -0.021 | -0.003 | 0.041 | -0.004 | |
| | | TEMP | -3.346 | 4.625 | -0.234 | -1.884 | -0.337 | -0.050 | 1.257 | 0.001 | |
| | | EQEW | 0.148 | 0.059 | -0.226 | 0.001 | -0.009 | -0.026 | 0.012 | 0.006 | |
| | | EQNS | -0.088 | -0.093 | 0.017 | 0.067 | -0.003 | 0.007 | -0.042 | 0.002 | |
| | | EQZ | -0.045 | -0.094 | 0.017 | -0.092 | -0.023 | -0.003 | 0.105 | 0.002 | |
| | | EQT | 0.004 | 0.003 | 0.000 | -0.002 | -0.002 | -0.002 | 0.003 | 0.000 | |
| | | SPKW | 0.021 | -0.214 | 0.023 | 0.018 | 0.003 | 0.001 | -0.014 | 0.000 | |
| | | SPKN | -0.906 | -0.142 | 0.121 | -0.154 | -0.028 | -0.007 | 0.135 | -0.001 | |

Table 3G.1-48
Combined Forces and Moments: RB, Selected Load Combination RB-9a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|------------------------------|------------------------------|-------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 26 Slab EL17.5m @ RCCV | 96144 | OTHR | 0.003 | 0.515 | 0.612 | 0.063 | 0.076 | -0.071 | 0.120 | -0.102 | |
| | | TEMP | -0.269 | 4.658 | 7.008 | -0.257 | -0.148 | 0.178 | -0.080 | 0.026 | |
| | | EQEW | -0.105 | -0.246 | -0.165 | 0.139 | 0.119 | -0.090 | 0.046 | -0.017 | |
| | | EQNS | -0.551 | 0.162 | 0.116 | -0.295 | -0.230 | 0.156 | -0.061 | 0.070 | |
| | | EQZ | 0.200 | -0.155 | -0.096 | -0.036 | -0.037 | 0.029 | -0.072 | 0.054 | |
| | | EQT | 0.135 | -0.045 | 0.000 | 0.011 | 0.010 | -0.006 | 0.003 | -0.001 | |
| | | SPKW | 0.019 | -0.035 | 0.000 | -0.004 | -0.004 | 0.002 | -0.002 | 0.000 | |
| | | SPKN | -0.063 | 0.031 | -0.002 | 0.002 | -0.001 | 0.000 | 0.001 | 0.000 | |
| | 96186 | OTHR | 0.783 | -0.306 | 0.015 | -0.030 | -0.101 | -0.004 | 0.003 | 0.038 | |
| | | TEMP | 6.641 | -4.128 | -1.421 | -0.104 | -0.385 | -0.051 | 0.018 | 0.399 | |
| | | EQEW | -0.330 | 0.169 | -0.231 | 0.108 | 0.616 | 0.023 | -0.031 | -0.490 | |
| | | EQNS | -0.608 | -0.144 | 0.033 | -0.075 | -0.342 | -0.012 | 0.027 | 0.274 | |
| | | EQZ | -0.178 | 0.088 | 0.017 | 0.003 | 0.021 | -0.001 | 0.006 | 0.023 | |
| | | EQT | 0.064 | 0.032 | -0.075 | 0.005 | 0.025 | -0.001 | -0.002 | -0.022 | |
| | | SPKW | 0.040 | 0.012 | -0.002 | -0.011 | -0.049 | -0.002 | 0.002 | 0.040 | |
| | | SPKN | -0.077 | -0.028 | 0.030 | 0.001 | 0.004 | 0.001 | 0.000 | -0.003 | |
| | 96113 | OTHR | -0.447 | 1.321 | -0.113 | -0.251 | -0.029 | -0.007 | 0.340 | 0.042 | |
| | | TEMP | -8.012 | 3.448 | -1.490 | -4.673 | -2.833 | -0.192 | 1.013 | -0.053 | |
| | | EQEW | 0.093 | -0.157 | 0.672 | 0.081 | 0.033 | -0.003 | -0.018 | 0.044 | |
| | | EQNS | 0.211 | -1.036 | 0.004 | 0.468 | -0.036 | -0.012 | -0.448 | -0.066 | |
| | | EQZ | 0.138 | -0.325 | 0.062 | 0.169 | -0.011 | -0.009 | -0.171 | -0.016 | |
| | | EQT | 0.010 | -0.006 | 0.231 | 0.008 | 0.008 | 0.007 | 0.003 | 0.011 | |
| | | SPKW | -0.039 | -0.093 | -0.004 | 0.033 | 0.008 | 0.001 | -0.022 | -0.002 | |
| | | SPKN | 0.042 | 0.100 | 0.008 | -0.114 | -0.024 | -0.004 | 0.084 | 0.007 | |
| | 27 Slab EL27.0m @ RCCV | 98472 | OTHR | 0.517 | 0.428 | -0.152 | 0.029 | 0.059 | -0.064 | 0.170 | -0.177 |
| | | | TEMP | -1.976 | -0.331 | 5.371 | -0.390 | 0.080 | -0.331 | 0.460 | -0.565 |
| | | | EQEW | 0.368 | -1.005 | -0.324 | 0.038 | 0.037 | -0.017 | 0.011 | -0.012 |
| | | | EQNS | 1.119 | -0.227 | 0.006 | -0.157 | -0.188 | 0.097 | -0.125 | 0.084 |
| | | | EQZ | -0.147 | 0.039 | -0.075 | -0.116 | -0.166 | 0.128 | -0.206 | 0.148 |
| | | | EQT | -0.089 | 0.058 | 0.007 | 0.014 | 0.016 | -0.011 | 0.014 | -0.007 |
| SPKW | | | 0.037 | -0.008 | -0.012 | -0.004 | -0.007 | 0.003 | -0.006 | 0.003 | |
| SPKN | | | -0.066 | 0.024 | 0.010 | 0.000 | -0.001 | 0.000 | 0.000 | 0.001 | |
| 98514 | | OTHR | 0.261 | 0.335 | 0.118 | -0.024 | -0.215 | 0.007 | 0.002 | -0.043 | |
| | | TEMP | 0.290 | -2.436 | -1.243 | -0.535 | -0.083 | -0.010 | 0.037 | -0.712 | |
| | | EQEW | -0.436 | 0.202 | -0.314 | 0.063 | 0.442 | -0.005 | -0.007 | -0.334 | |
| | | EQNS | -0.235 | -0.151 | -0.159 | -0.073 | -0.260 | 0.002 | 0.008 | 0.265 | |
| | | EQZ | 0.011 | -0.071 | -0.044 | -0.025 | -0.082 | -0.018 | -0.002 | 0.114 | |
| | | EQT | 0.074 | 0.006 | -0.051 | 0.005 | 0.022 | -0.002 | -0.001 | -0.021 | |
| | | SPKW | 0.030 | -0.008 | -0.004 | -0.007 | -0.034 | -0.001 | 0.000 | 0.028 | |
| | | SPKN | -0.025 | -0.007 | 0.021 | 0.000 | -0.001 | 0.001 | 0.000 | 0.000 | |
| 98424 | | OTHR | 0.240 | 1.022 | -0.125 | 0.488 | 0.128 | -0.136 | -0.561 | -0.113 | |
| | | TEMP | -9.771 | -8.139 | -2.242 | 6.366 | 3.591 | 0.270 | -4.372 | -0.664 | |
| | | EQEW | 0.659 | -0.569 | -5.339 | 0.057 | 0.036 | -0.148 | 0.029 | -0.002 | |
| | | EQNS | 0.941 | -1.089 | 0.420 | -1.018 | -0.413 | 0.137 | 1.105 | 0.161 | |
| | | EQZ | -0.029 | -0.290 | 0.019 | -1.420 | -0.331 | -0.030 | 0.841 | 0.152 | |
| | | EQT | 0.057 | -0.034 | -0.745 | 0.023 | 0.019 | 0.018 | -0.014 | 0.006 | |
| | | SPKW | 0.005 | -0.004 | -0.003 | 0.032 | 0.015 | -0.002 | -0.023 | -0.005 | |
| | | SPKN | -0.007 | 0.009 | 0.005 | -0.070 | -0.034 | 0.000 | 0.049 | 0.007 | |

Table 3G.1-48
Combined Forces and Moments: RB, Selected Load Combination RB-9a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|-------------------------------------|------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 28 Pool Girder @ Storage Pool | 123004 | OTHR | 0.279 | -0.884 | 0.232 | 0.051 | 0.136 | -0.028 | 0.035 | 0.105 |
| | | TEMP | -3.222 | -10.346 | 0.042 | 0.420 | 1.524 | -0.253 | -0.188 | 1.420 |
| | | EQEW | -0.043 | -0.854 | -0.200 | 0.285 | 0.713 | -0.142 | 0.099 | 0.614 |
| | | EQNS | 0.507 | 2.822 | -0.383 | -0.070 | -0.008 | 0.034 | -0.041 | -0.012 |
| | | EQZ | 0.536 | 3.574 | 1.280 | -0.034 | 0.052 | -0.025 | 0.001 | 0.018 |
| | | EQT | -0.016 | -0.254 | -0.044 | 0.023 | 0.060 | -0.020 | -0.001 | 0.045 |
| | | SPKW | 0.012 | -0.013 | -0.018 | 0.001 | 0.007 | -0.002 | 0.000 | 0.004 |
| | SPKN | -0.021 | 0.073 | -0.005 | -0.003 | -0.006 | 0.001 | -0.001 | -0.003 | |
| | 123104 | OTHR | 0.492 | -0.409 | 0.554 | 0.001 | -0.021 | 0.009 | 0.033 | 0.025 |
| | | TEMP | -1.162 | -3.220 | 1.957 | -0.186 | -0.569 | 0.085 | -0.399 | 0.291 |
| | | EQEW | 0.031 | -0.354 | 0.429 | 0.149 | -0.068 | -0.025 | 0.014 | 0.077 |
| | | EQNS | -0.578 | 1.180 | -0.739 | -0.090 | -0.008 | -0.001 | -0.034 | 0.011 |
| | | EQZ | -0.664 | 1.245 | 0.734 | -0.024 | -0.002 | -0.018 | -0.017 | 0.015 |
| | | EQT | 0.011 | -0.111 | 0.039 | 0.026 | 0.005 | -0.005 | -0.002 | 0.008 |
| SPKW | | -0.001 | -0.004 | -0.016 | 0.001 | 0.001 | -0.001 | -0.001 | 0.001 | |
| SPKN | -0.025 | 0.025 | -0.018 | -0.002 | 0.000 | 0.001 | 0.000 | -0.001 | | |
| 29 Pool Girder @ Cavity | 123012 | OTHR | 0.306 | -0.346 | -0.278 | -0.001 | 0.069 | -0.007 | 0.021 | 0.076 |
| | | TEMP | -1.585 | -0.088 | -0.191 | -0.062 | 0.579 | 0.047 | 0.057 | 0.427 |
| | | EQEW | -0.584 | -0.011 | 0.262 | 0.082 | 0.217 | -0.021 | 0.002 | 0.186 |
| | | EQNS | 0.042 | -0.086 | 0.277 | -0.025 | 0.009 | -0.004 | 0.026 | 0.045 |
| | | EQZ | -0.913 | -0.581 | -0.368 | 0.034 | 0.265 | -0.003 | 0.016 | 0.151 |
| | | EQT | 0.026 | 0.003 | -0.007 | 0.001 | -0.005 | -0.002 | 0.002 | -0.003 |
| | | SPKW | 0.031 | 0.001 | -0.003 | 0.000 | 0.001 | 0.000 | -0.001 | 0.000 |
| | SPKN | -0.032 | 0.000 | 0.003 | 0.000 | -0.001 | 0.000 | 0.000 | 0.000 | |
| | 123112 | OTHR | 0.282 | -0.207 | -0.237 | -0.002 | -0.029 | -0.008 | 0.006 | 0.001 |
| | | TEMP | -2.307 | -0.056 | -0.067 | -0.143 | -0.117 | -0.095 | -0.040 | 0.096 |
| | | EQEW | -0.677 | -0.004 | 0.368 | 0.091 | -0.015 | -0.016 | -0.088 | -0.009 |
| | | EQNS | -0.554 | -0.088 | 0.245 | -0.113 | -0.026 | -0.013 | 0.039 | 0.003 |
| | | EQZ | 0.119 | -0.337 | -0.426 | 0.010 | 0.031 | -0.027 | -0.013 | 0.012 |
| | | EQT | 0.051 | 0.002 | -0.021 | -0.001 | -0.003 | -0.005 | 0.003 | 0.001 |
| SPKW | | -0.001 | -0.001 | 0.000 | 0.000 | 0.000 | 0.001 | -0.001 | 0.000 | |
| SPKN | -0.013 | 0.001 | -0.002 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | | |
| 30 Pool Girder @ Fuel Pool | 123017 | OTHR | 0.457 | 0.324 | -0.164 | -0.010 | -0.064 | 0.022 | 0.002 | -0.109 |
| | | TEMP | 0.774 | -6.892 | -0.909 | 2.470 | 2.743 | -0.228 | 0.208 | 0.415 |
| | | EQEW | -0.134 | -0.858 | 0.754 | 0.327 | 0.638 | 0.095 | -0.251 | 0.577 |
| | | EQNS | 0.301 | 2.991 | 0.076 | 0.072 | 0.236 | 0.043 | 0.022 | 0.221 |
| | | EQZ | 0.443 | 3.312 | -1.363 | -0.060 | 0.040 | 0.080 | 0.011 | 0.084 |
| | | EQT | -0.005 | -0.005 | -0.041 | -0.014 | -0.083 | -0.023 | -0.001 | -0.054 |
| | | SPKW | 0.015 | -0.001 | 0.018 | 0.002 | 0.009 | 0.003 | 0.000 | 0.007 |
| | SPKN | -0.014 | 0.057 | -0.009 | -0.003 | -0.005 | -0.003 | 0.003 | -0.005 | |
| | 123117 | OTHR | -0.068 | 0.055 | -0.182 | 0.035 | 0.041 | 0.006 | 0.011 | 0.020 |
| | | TEMP | -0.985 | -2.677 | -0.715 | 2.293 | 1.832 | -0.079 | -0.209 | 0.279 |
| | | EQEW | -0.187 | -0.380 | -0.012 | 0.094 | -0.070 | 0.027 | 0.019 | 0.053 |
| | | EQNS | -1.053 | 0.840 | 1.010 | 0.040 | 0.016 | -0.022 | 0.023 | 0.011 |
| | | EQZ | -0.434 | 0.996 | -0.736 | -0.052 | -0.054 | 0.013 | 0.005 | -0.002 |
| | | EQT | 0.066 | 0.034 | -0.012 | -0.017 | -0.005 | -0.009 | -0.008 | -0.007 |
| SPKW | | -0.005 | 0.000 | 0.014 | 0.001 | 0.000 | 0.000 | 0.001 | 0.001 | |
| SPKN | -0.006 | 0.018 | 0.008 | -0.004 | -0.001 | -0.001 | 0.000 | 0.000 | | |

Table 3G.1-48
Combined Forces and Moments: RB, Selected Load Combination RB-9a (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|-------------------------------|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 31 MS Tunnel Wall and Slab | 150122 | OTHR | -0.210 | -0.287 | 0.943 | -0.010 | 0.061 | 0.020 | -0.024 | -0.051 |
| | | TEMP | 2.226 | -0.111 | -0.753 | 3.639 | 3.907 | 0.083 | -0.262 | -0.322 |
| | | EQEW | 0.113 | 0.172 | -0.176 | 0.072 | -0.158 | -0.012 | 0.018 | 0.202 |
| | | EQNS | 0.144 | 0.403 | -0.048 | -0.062 | -0.103 | -0.009 | 0.015 | -0.033 |
| | | EQZ | 0.174 | 0.081 | -0.517 | 0.007 | -0.016 | -0.011 | 0.016 | 0.034 |
| | | EQT | 0.009 | 0.016 | -0.055 | 0.012 | -0.027 | -0.012 | 0.003 | 0.047 |
| | | SPKW | 0.006 | -0.006 | 0.001 | 0.002 | 0.001 | -0.001 | 0.000 | 0.000 |
| | | SPKN | -0.010 | -0.013 | 0.000 | 0.002 | 0.003 | 0.000 | 0.000 | 0.001 |
| | 96611 | OTHR | -0.075 | 0.466 | -0.058 | 0.063 | -0.133 | -0.088 | -0.199 | 0.008 |
| | | TEMP | -0.174 | 3.068 | -0.248 | -3.645 | -6.606 | -0.247 | 0.700 | 0.064 |
| | | EQEW | 0.019 | -0.093 | -0.266 | -0.036 | -0.076 | 0.083 | -0.011 | -0.060 |
| | | EQNS | 0.026 | -0.379 | 0.030 | -0.117 | -0.342 | 0.005 | 0.077 | 0.012 |
| | | EQZ | 0.036 | -0.192 | 0.026 | 0.028 | 0.132 | 0.058 | 0.115 | -0.007 |
| | | EQT | 0.006 | -0.014 | -0.072 | -0.008 | -0.014 | 0.036 | -0.004 | -0.011 |
| | | SPKW | -0.017 | 0.004 | -0.006 | 0.000 | 0.002 | 0.000 | 0.000 | 0.000 |
| | | SPKN | 0.024 | -0.015 | 0.009 | 0.010 | 0.014 | 0.001 | -0.004 | 0.000 |
| | 98614 | OTHR | 0.007 | -0.034 | 0.040 | -0.220 | -0.668 | -0.066 | -0.107 | 0.015 |
| | | TEMP | 0.527 | 2.703 | -0.288 | 9.377 | 13.644 | 0.044 | -1.769 | -0.155 |
| | | EQEW | -0.025 | -0.005 | 0.172 | -0.022 | 0.063 | 0.203 | -0.041 | 0.048 |
| | | EQNS | 0.080 | -0.246 | 0.036 | 0.176 | 0.303 | 0.009 | -0.069 | -0.009 |
| | | EQZ | -0.008 | 0.058 | -0.023 | 0.013 | 0.311 | 0.032 | 0.089 | -0.010 |
| | | EQT | -0.012 | 0.006 | 0.057 | -0.005 | 0.004 | 0.061 | -0.006 | 0.002 |
| | | SPKW | 0.000 | -0.006 | 0.001 | -0.014 | -0.009 | -0.001 | 0.003 | 0.000 |
| | | SPKN | -0.006 | 0.013 | -0.002 | 0.015 | 0.000 | 0.002 | -0.002 | 0.000 |

Table 3G.1-49

Combined Forces and Moments: RB, Selected Load Combination RB-9b

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|---------------------------------|---|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 18 Wall Below RCCV Bottom | 6 | OTHR | -2.195 | -7.507 | -0.237 | 0.162 | 0.627 | -0.007 | 0.005 | 0.335 | |
| | | TEMP | 0.500 | -1.652 | -0.970 | 0.379 | 2.436 | -0.053 | 0.065 | 0.459 | |
| | | EQEW | 4.080 | 9.611 | -4.318 | -0.696 | -3.389 | -0.046 | 0.140 | -1.392 | |
| | | EQNS | -4.226 | -2.828 | -3.149 | 0.950 | 5.629 | 0.027 | 0.006 | 2.014 | |
| | | EQZ | -0.321 | 4.250 | -0.279 | 0.231 | 1.518 | -0.009 | 0.024 | 0.450 | |
| | | EQT | 0.666 | 0.149 | 0.610 | -0.044 | -0.288 | -0.014 | 0.027 | -0.152 | |
| | | SPKW | -0.491 | 0.161 | -0.422 | -0.051 | -0.221 | -0.034 | 0.064 | -0.040 | |
| | SPKN | -0.386 | -0.001 | 0.016 | 0.009 | 0.091 | 0.009 | -0.016 | 0.064 | | |
| | 13 | OTHR | -1.951 | -6.103 | -0.130 | -0.202 | -0.915 | 0.010 | -0.005 | -0.176 | |
| | | TEMP | -0.084 | -4.089 | -0.681 | 0.635 | 3.538 | 0.001 | 0.019 | 0.830 | |
| | | EQEW | 4.939 | 9.278 | 0.447 | -0.384 | -2.349 | -0.019 | 0.036 | -1.176 | |
| | | EQNS | -0.092 | 2.940 | -3.947 | 0.616 | 3.308 | -0.083 | 0.135 | 0.998 | |
| | | EQZ | -0.421 | 3.452 | -0.258 | 0.399 | 2.157 | -0.007 | 0.010 | 0.633 | |
| | | EQT | 0.548 | 0.139 | 0.740 | -0.080 | -0.369 | -0.006 | 0.013 | -0.168 | |
| | | SPKW | 0.171 | 0.101 | 0.078 | -0.066 | -0.733 | -0.008 | 0.009 | -0.359 | |
| | SPKN | -0.924 | 0.001 | -0.248 | 0.008 | 0.263 | 0.004 | -0.003 | 0.188 | | |
| | 24 | OTHR | -1.297 | -6.598 | -0.436 | -0.387 | -2.272 | -0.002 | 0.008 | -0.796 | |
| | | TEMP | 0.018 | -3.987 | 0.219 | 0.642 | 3.557 | -0.009 | 0.000 | 0.840 | |
| | | EQEW | 0.630 | 0.657 | 6.609 | 0.010 | -0.204 | 0.106 | -0.160 | -0.129 | |
| | | EQNS | 2.743 | 8.464 | -0.014 | 0.216 | 1.126 | -0.009 | 0.003 | -0.018 | |
| | | EQZ | -0.417 | 3.860 | 0.100 | 0.425 | 2.253 | -0.005 | 0.002 | 0.637 | |
| | | EQT | 0.075 | 0.011 | 1.005 | 0.002 | -0.029 | -0.003 | 0.005 | -0.017 | |
| | | SPKW | -0.938 | 0.026 | 0.082 | 0.024 | 0.350 | 0.003 | -0.006 | 0.230 | |
| | SPKN | 0.179 | 0.094 | -0.078 | -0.086 | -0.857 | -0.006 | 0.008 | -0.423 | | |
| | 19 Wall Below Below RCCV Mid-Height | 806 | OTHR | -1.160 | -6.328 | -0.119 | 0.012 | 0.167 | -0.006 | -0.020 | -0.054 |
| | | | TEMP | 1.716 | -2.753 | 0.114 | 0.305 | 1.594 | 0.082 | -0.064 | -0.104 |
| | | | EQEW | 0.690 | 7.399 | -5.103 | -0.009 | 0.249 | -0.132 | -0.022 | 0.020 |
| EQNS | | | -2.173 | -2.516 | -3.422 | -0.138 | -0.431 | -0.021 | 0.024 | 0.198 | |
| EQZ | | | -0.054 | 3.702 | -0.048 | -0.019 | -0.024 | 0.019 | -0.004 | 0.065 | |
| EQT | | | 0.313 | 0.075 | 0.573 | 0.023 | 0.068 | -0.031 | -0.006 | -0.004 | |
| SPKW | | | -1.132 | 0.198 | -0.192 | -0.014 | 0.070 | -0.024 | -0.049 | -0.015 | |
| SPKN | | -0.360 | 0.086 | 0.077 | -0.040 | -0.026 | 0.000 | 0.000 | 0.010 | | |
| 813 | | OTHR | -1.685 | -6.085 | -0.079 | -0.002 | 0.228 | -0.020 | 0.008 | 0.030 | |
| | | TEMP | 1.264 | -4.042 | -0.538 | 0.199 | 1.585 | -0.036 | 0.005 | 0.613 | |
| | | EQEW | 1.979 | 8.078 | 0.751 | 0.012 | 0.364 | -0.002 | -0.016 | -0.087 | |
| | | EQNS | -0.413 | 3.201 | -4.445 | -0.018 | -0.076 | 0.039 | -0.051 | 0.288 | |
| | | EQZ | 0.021 | 3.433 | -0.210 | 0.018 | 0.014 | 0.021 | -0.002 | 0.157 | |
| | | EQT | 0.211 | 0.052 | 0.809 | -0.001 | 0.055 | -0.050 | 0.006 | -0.020 | |
| | | SPKW | -0.838 | -0.098 | 0.007 | 0.119 | 0.414 | 0.024 | -0.016 | 0.042 | |
| SPKN | | -0.761 | 0.184 | -0.138 | -0.077 | -0.142 | -0.003 | 0.013 | -0.003 | | |
| 824 | | OTHR | -1.991 | -6.744 | -0.414 | 0.128 | 0.522 | -0.009 | -0.001 | 0.140 | |
| | | TEMP | 1.020 | -4.014 | 0.230 | 0.220 | 1.644 | 0.029 | 0.013 | 0.560 | |
| | | EQEW | 0.194 | 0.650 | 7.276 | 0.037 | 0.064 | 0.059 | 0.069 | 0.036 | |
| | | EQNS | 0.979 | 7.859 | -0.125 | 0.047 | 0.231 | 0.002 | -0.001 | 0.236 | |
| | | EQZ | -0.053 | 3.860 | 0.103 | 0.036 | 0.019 | 0.007 | -0.003 | 0.199 | |
| | | EQT | 0.021 | 0.007 | 1.071 | 0.007 | 0.007 | -0.019 | 0.010 | 0.004 | |
| | | SPKW | -0.931 | 0.329 | 0.017 | -0.093 | -0.178 | -0.001 | -0.001 | -0.007 | |
| SPKN | | -0.869 | -0.134 | 0.000 | 0.164 | 0.434 | 0.008 | -0.002 | 0.065 | | |

Table 3G.1-49
Combined Forces and Moments: RB, Selected Load Combination RB-9b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|------------------------------|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 20 Wall Below RCCV Top | 1606 | OTHR | 0.959 | -5.706 | -0.074 | -0.584 | -3.182 | 0.025 | 0.007 | 0.897 |
| | | TEMP | 15.254 | -3.694 | 0.085 | -0.865 | -3.919 | 0.106 | 0.072 | 2.988 |
| | | EQEW | 0.628 | 5.038 | -5.272 | 0.082 | 0.563 | -0.019 | -0.005 | -0.110 |
| | | EQNS | -1.483 | -1.946 | -3.743 | -0.333 | -1.320 | -0.069 | -0.002 | 0.183 |
| | | EQZ | 0.407 | 3.300 | -0.034 | -0.123 | -0.670 | -0.005 | 0.004 | 0.219 |
| | | EQT | 0.125 | 0.054 | 0.710 | 0.010 | 0.019 | -0.017 | -0.002 | 0.013 |
| | | SPKW | -0.530 | 0.104 | 0.453 | -0.034 | -0.146 | 0.069 | 0.006 | 0.014 |
| | | SPKN | -0.181 | 0.094 | -0.130 | -0.042 | -0.060 | -0.016 | 0.001 | -0.009 |
| | 1613 | OTHR | 0.443 | -6.024 | 0.102 | -0.559 | -3.038 | -0.002 | -0.019 | 0.870 |
| | | TEMP | 15.098 | -4.772 | -0.383 | -0.955 | -5.279 | -0.012 | -0.016 | 3.467 |
| | | EQEW | 1.016 | 6.058 | 0.909 | 0.148 | 0.962 | -0.001 | 0.010 | -0.200 |
| | | EQNS | -0.138 | 3.051 | -4.514 | -0.243 | -1.271 | -0.022 | 0.009 | 0.366 |
| | | EQZ | 0.540 | 3.308 | -0.149 | -0.128 | -0.778 | -0.005 | 0.002 | 0.270 |
| | | EQT | 0.086 | -0.041 | 0.872 | 0.017 | 0.106 | -0.027 | -0.001 | -0.022 |
| | | SPKW | -0.031 | 0.069 | -0.065 | -0.049 | -0.514 | 0.002 | 0.003 | 0.244 |
| | | SPKN | -0.507 | 0.074 | 0.116 | -0.030 | 0.051 | -0.007 | -0.005 | -0.089 |
| | 1624 | OTHR | 0.155 | -6.466 | -0.272 | -0.453 | -2.757 | 0.008 | -0.021 | 0.783 |
| | | TEMP | 15.945 | -5.116 | -0.070 | -1.065 | -5.223 | 0.003 | -0.102 | 3.540 |
| | | EQEW | 0.076 | 0.521 | 7.447 | -0.016 | -0.009 | 0.052 | -0.049 | 0.027 |
| | | EQNS | 0.985 | 6.565 | -0.214 | -0.062 | -0.477 | -0.009 | 0.004 | 0.204 |
| | | EQZ | 0.471 | 3.747 | 0.069 | -0.133 | -0.780 | 0.001 | 0.004 | 0.262 |
| | | EQT | 0.003 | 0.006 | 1.120 | -0.002 | -0.001 | -0.016 | -0.006 | 0.002 |
| | | SPKW | -0.642 | 0.163 | -0.047 | -0.043 | 0.061 | -0.002 | 0.004 | -0.106 |
| | | SPKN | -0.081 | 0.048 | 0.057 | -0.023 | -0.469 | 0.002 | -0.011 | 0.215 |

Table 3G.1-49
Combined Forces and Moments: RB, Selected Load Combination RB-9b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | OTHR | -1.865 | -3.362 | -0.684 | 0.111 | 0.666 | 0.014 | 0.037 | 0.212 |
| | | TEMP | 3.015 | 4.539 | 0.539 | 0.546 | 2.096 | 0.065 | -0.209 | 0.722 |
| | | EQEW | -0.657 | -0.961 | -9.354 | -0.082 | 0.416 | 0.025 | 0.100 | 0.091 |
| | | EQNS | -0.662 | -1.083 | 0.877 | 1.978 | 8.162 | 0.050 | -0.088 | 3.032 |
| | | EQZ | 0.399 | 2.223 | 0.230 | 0.022 | -0.013 | -0.003 | -0.031 | -0.030 |
| | | EQT | 0.045 | 0.000 | 0.742 | 0.044 | 0.150 | -0.010 | 0.016 | 0.051 |
| | | SPKW | -0.940 | 0.122 | 0.125 | 0.019 | 0.107 | -0.005 | -0.002 | 0.047 |
| | | SPKN | 0.198 | 0.046 | -0.209 | -0.099 | -0.402 | 0.004 | 0.000 | -0.193 |
| | 20023 | OTHR | -1.203 | -1.450 | -0.484 | 0.022 | -0.291 | 0.025 | -0.041 | -0.162 |
| | | TEMP | -3.247 | -1.943 | 0.806 | -2.359 | -2.817 | 0.031 | -0.795 | -0.575 |
| | | EQEW | 0.059 | 4.728 | -0.475 | 0.320 | 0.224 | -0.093 | -0.079 | 0.031 |
| | | EQNS | -0.008 | -1.289 | -0.936 | -0.832 | 1.337 | 0.170 | 1.299 | 0.909 |
| | | EQZ | 0.013 | 0.711 | 0.290 | -0.077 | 0.136 | 0.003 | 0.048 | 0.091 |
| | | EQT | -0.071 | -0.099 | 0.316 | 0.150 | -0.095 | -0.040 | -0.281 | -0.111 |
| | | SPKW | -0.619 | -0.161 | 0.146 | -0.075 | -0.036 | 0.004 | 0.016 | 0.014 |
| | | SPKN | 0.085 | 0.082 | -0.115 | -0.003 | -0.002 | 0.005 | 0.015 | -0.017 |
| | 30010 | OTHR | -1.315 | -2.241 | -0.188 | -0.249 | -1.366 | 0.013 | 0.004 | 0.921 |
| | | TEMP | 1.001 | 3.822 | -0.190 | 1.305 | 4.878 | -0.022 | -0.029 | -0.906 |
| | | EQEW | 3.694 | 3.409 | 0.982 | -0.320 | -1.172 | -0.031 | -0.026 | 0.395 |
| | | EQNS | 1.283 | 2.225 | -3.374 | 0.481 | 2.677 | -0.053 | -0.091 | -0.745 |
| | | EQZ | 0.086 | 1.161 | -0.023 | 0.250 | 1.318 | -0.013 | -0.005 | -0.300 |
| | | EQT | 0.623 | -0.159 | 0.842 | -0.074 | -0.293 | -0.013 | -0.017 | 0.102 |
| | | SPKW | -0.102 | -0.362 | 0.000 | -0.054 | -0.444 | -0.009 | -0.009 | 0.538 |
| | | SPKN | -0.755 | 0.135 | -0.073 | 0.018 | 0.168 | 0.006 | 0.006 | -0.068 |
| | 30020 | OTHR | -0.972 | -1.526 | -0.221 | -0.536 | -0.766 | 0.017 | -0.161 | 0.324 |
| | | TEMP | -0.043 | -1.519 | -0.380 | 0.011 | 1.225 | 0.146 | -0.023 | -0.288 |
| | | EQEW | 0.512 | 2.678 | 1.213 | -0.065 | 0.349 | 0.031 | 0.086 | -0.091 |
| | | EQNS | 0.109 | 2.149 | -0.455 | 0.024 | 1.101 | 0.025 | -0.285 | -0.252 |
| | | EQZ | 0.037 | 0.598 | 0.129 | -0.136 | 0.364 | 0.042 | -0.080 | -0.124 |
| | | EQT | 0.111 | -0.186 | 0.205 | -0.040 | -0.050 | 0.005 | 0.118 | -0.005 |
| | | SPKW | -0.077 | -0.160 | -0.125 | -0.069 | -0.255 | 0.115 | -0.007 | 0.145 |
| | | SPKN | -0.231 | -0.074 | 0.067 | -0.289 | 0.022 | -0.037 | -0.108 | -0.046 |
| | 40001 | OTHR | -0.762 | -1.706 | 0.332 | -0.325 | -1.087 | -0.199 | 0.071 | 0.625 |
| | | TEMP | -0.085 | -1.165 | 0.093 | 0.037 | 1.359 | -0.099 | 0.110 | -0.329 |
| | | EQEW | 0.005 | 3.037 | 0.977 | 0.369 | 1.132 | 0.016 | 0.362 | -0.176 |
| | | EQNS | 0.366 | 1.950 | -0.726 | -0.198 | 0.593 | -0.080 | 0.012 | -0.170 |
| | | EQZ | 0.033 | 0.628 | -0.099 | -0.139 | 0.376 | -0.039 | 0.082 | -0.123 |
| | | EQT | -0.020 | 0.049 | 0.302 | 0.129 | 0.031 | 0.017 | 0.064 | 0.042 |
| | | SPKW | -0.237 | -0.076 | -0.075 | -0.240 | 0.040 | 0.034 | 0.086 | -0.041 |
| | | SPKN | -0.097 | -0.190 | 0.116 | -0.103 | -0.367 | -0.143 | -0.008 | 0.163 |
| | 40011 | OTHR | -1.405 | -3.084 | -0.030 | -0.308 | -1.836 | -0.002 | 0.005 | 1.651 |
| | | TEMP | 1.348 | 3.854 | 0.063 | 1.290 | 4.897 | 0.012 | 0.016 | -0.910 |
| | | EQEW | -0.252 | -0.361 | 4.538 | 0.015 | -0.047 | 0.085 | 0.124 | -0.029 |
| | | EQNS | 3.276 | 3.698 | -0.076 | 0.140 | 1.121 | 0.012 | 0.005 | -0.164 |
| | | EQZ | 0.128 | 1.494 | -0.001 | 0.288 | 1.476 | 0.009 | 0.002 | -0.326 |
| | | EQT | -0.021 | -0.014 | 0.917 | 0.006 | 0.005 | -0.006 | -0.007 | -0.010 |
| | | SPKW | -0.539 | 0.209 | 0.000 | 0.020 | 0.248 | -0.002 | -0.003 | -0.104 |
| | | SPKN | -0.224 | -0.417 | -0.024 | -0.053 | -0.519 | 0.004 | 0.004 | 0.587 |

Table 3G.1-49
Combined Forces and Moments: RB, Selected Load Combination RB-9b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 22 Exterior Wall @ EL4.65 ~6.60m | 22011 | OTHR | 0.193 | -2.586 | 0.597 | -0.006 | 0.085 | 0.010 | -0.026 | 0.134 |
| | | TEMP | 4.828 | 4.398 | -0.287 | -0.154 | -0.139 | 0.067 | 0.044 | 0.162 |
| | | EQEW | 0.466 | 3.318 | -6.436 | 0.034 | -0.023 | -0.021 | 0.029 | -0.002 |
| | | EQNS | -0.441 | -7.125 | 2.468 | 0.116 | 0.966 | 0.154 | -0.038 | 0.853 |
| | | EQZ | -0.121 | 1.929 | -0.415 | 0.007 | -0.026 | -0.001 | 0.012 | -0.024 |
| | | EQT | 0.025 | -0.350 | 0.750 | -0.005 | -0.001 | -0.020 | 0.001 | -0.005 |
| | | SPKW | -0.649 | 0.235 | -0.140 | -0.009 | -0.013 | 0.003 | -0.002 | 0.000 |
| | | SPKN | 0.118 | 0.144 | 0.013 | 0.025 | 0.049 | -0.007 | -0.003 | 0.073 |
| | 22023 | OTHR | -0.058 | -1.465 | -0.033 | 0.097 | 0.038 | -0.098 | 0.078 | 0.020 |
| | | TEMP | 1.518 | -2.692 | 0.328 | 0.990 | 0.017 | -0.183 | -0.173 | 0.000 |
| | | EQEW | 0.069 | 4.568 | -3.234 | 0.055 | -0.073 | 0.086 | -0.202 | -0.079 |
| | | EQNS | 0.104 | -4.679 | -0.933 | -0.214 | 0.171 | -0.153 | 0.394 | 0.153 |
| | | EQZ | -0.017 | 0.997 | 0.206 | 0.074 | 0.002 | 0.011 | -0.052 | -0.011 |
| | | EQT | -0.067 | 0.247 | 0.587 | 0.014 | -0.006 | -0.010 | -0.027 | -0.017 |
| | | SPKW | -0.336 | -0.137 | 0.601 | 0.024 | 0.011 | -0.023 | 0.019 | -0.004 |
| | | SPKN | 0.015 | 0.083 | 0.162 | 0.081 | 0.009 | -0.006 | -0.026 | 0.005 |
| | 32010 | OTHR | 0.140 | -1.798 | 0.024 | -0.020 | 0.002 | 0.008 | 0.000 | -0.082 |
| | | TEMP | 16.476 | 7.814 | -0.100 | -2.875 | -2.936 | -0.003 | -0.013 | -0.029 |
| | | EQEW | 0.643 | 3.408 | 0.932 | -0.019 | -0.097 | -0.012 | -0.001 | 0.219 |
| | | EQNS | -0.867 | 1.234 | -3.866 | -0.010 | -0.012 | 0.000 | -0.002 | -0.103 |
| | | EQZ | 0.012 | 1.087 | -0.027 | -0.001 | -0.028 | -0.002 | 0.000 | 0.013 |
| | | EQT | 0.223 | -0.010 | 0.982 | -0.001 | 0.007 | -0.018 | 0.002 | 0.009 |
| | | SPKW | -0.043 | -0.151 | 0.004 | -0.022 | -0.175 | -0.001 | 0.000 | 0.010 |
| | | SPKN | -0.319 | 0.066 | 0.060 | -0.009 | -0.002 | 0.000 | 0.001 | 0.003 |
| | 32020 | OTHR | -0.001 | -1.764 | 0.154 | -0.012 | -0.035 | -0.050 | 0.003 | 0.025 |
| | | TEMP | 0.610 | 4.810 | 2.460 | 0.061 | -1.837 | -0.391 | 1.189 | 0.188 |
| | | EQEW | 0.047 | 2.920 | 2.784 | 0.125 | -0.060 | 0.015 | 0.091 | 0.016 |
| | | EQNS | -0.041 | 3.265 | -1.524 | 0.147 | 0.024 | 0.003 | 0.129 | -0.002 |
| | | EQZ | 0.032 | 1.252 | 0.072 | 0.042 | 0.001 | 0.007 | 0.038 | 0.006 |
| | | EQT | 0.005 | -0.203 | 0.864 | -0.003 | -0.004 | -0.011 | -0.004 | 0.011 |
| | | SPKW | -0.005 | -0.031 | -0.126 | 0.016 | -0.068 | -0.102 | -0.059 | 0.022 |
| | | SPKN | -0.200 | -0.101 | 0.256 | -0.171 | -0.038 | 0.044 | -0.041 | 0.004 |
| | 42001 | OTHR | -0.006 | -1.825 | 0.051 | 0.010 | -0.067 | 0.057 | -0.004 | 0.048 |
| | | TEMP | 2.708 | 3.726 | 2.529 | 0.074 | -1.559 | -0.037 | -0.972 | -0.233 |
| | | EQEW | -0.017 | 2.714 | 2.956 | 0.166 | 0.064 | -0.012 | -0.063 | -0.031 |
| | | EQNS | 0.127 | 3.461 | -1.547 | 0.200 | -0.027 | -0.023 | -0.077 | -0.010 |
| | | EQZ | 0.039 | 1.311 | 0.061 | 0.053 | 0.002 | -0.001 | -0.027 | 0.002 |
| | | EQT | -0.019 | -0.222 | 0.860 | -0.003 | 0.013 | -0.013 | 0.003 | -0.013 |
| | | SPKW | -0.121 | -0.041 | -0.237 | -0.084 | -0.024 | -0.041 | 0.004 | 0.003 |
| | | SPKN | -0.037 | -0.085 | 0.119 | -0.029 | -0.061 | 0.133 | 0.133 | 0.022 |
| | 42011 | OTHR | -0.184 | -2.329 | -0.029 | -0.041 | -0.118 | -0.003 | 0.005 | -0.044 |
| | | TEMP | 14.259 | 5.931 | 0.283 | -3.138 | -2.902 | 0.064 | 0.089 | 0.069 |
| EQEW | | 0.214 | -0.581 | 5.945 | 0.045 | 0.003 | 0.018 | 0.040 | -0.015 | |
| EQNS | | 0.749 | 3.196 | 0.267 | 0.003 | -0.098 | 0.009 | 0.000 | 0.092 | |
| EQZ | | 0.214 | 1.479 | 0.058 | -0.001 | -0.021 | 0.002 | -0.002 | 0.005 | |
| EQT | | 0.051 | -0.064 | 1.181 | 0.005 | 0.001 | -0.011 | 0.005 | -0.002 | |
| SPKW | | -0.203 | 0.107 | 0.030 | -0.015 | 0.003 | -0.001 | -0.002 | -0.002 | |
| SPKN | | -0.091 | -0.212 | 0.024 | -0.022 | -0.149 | 0.014 | 0.024 | 0.006 | |

Table 3G.1-49
Combined Forces and Moments: RB, Selected Load Combination RB-9b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 23 Exterior Wall @ EL22.50 ~24.60m | 24211 | OTHR | 0.259 | -1.245 | 0.051 | -0.007 | -0.103 | 0.015 | 0.004 | -0.262 |
| | | TEMP | 5.628 | 6.168 | -0.121 | 0.036 | 0.461 | -0.032 | -0.057 | 1.532 |
| | | EQEW | -0.114 | 0.162 | -5.394 | -0.003 | 0.026 | 0.015 | 0.004 | 0.008 |
| | | EQNS | -1.174 | -5.369 | 0.191 | -0.170 | -0.660 | -0.042 | -0.003 | 0.840 |
| | | EQZ | 0.087 | 0.973 | -0.055 | 0.074 | 0.507 | -0.011 | 0.000 | 0.135 |
| | | EQT | 0.000 | -0.040 | 0.890 | -0.001 | -0.004 | -0.032 | -0.005 | 0.020 |
| | | SPKW | -0.053 | -0.031 | -0.004 | 0.002 | 0.009 | -0.001 | 0.000 | 0.000 |
| | | SPKN | -0.026 | 0.065 | -0.028 | -0.003 | -0.003 | 0.000 | -0.001 | 0.015 |
| | 24224 | OTHR | -0.007 | -1.121 | 0.135 | 0.016 | -0.039 | -0.015 | -0.046 | -0.047 |
| | | TEMP | 1.066 | 6.059 | -3.947 | 1.882 | 0.047 | -0.627 | -1.457 | -0.289 |
| | | EQEW | 0.259 | 3.913 | -3.713 | -0.231 | -0.100 | -0.022 | 0.227 | -0.045 |
| | | EQNS | -0.282 | -7.465 | 0.532 | 0.695 | 1.033 | -0.289 | 0.178 | 1.126 |
| | | EQZ | 0.039 | 0.762 | -0.252 | -0.010 | 0.046 | 0.050 | 0.040 | 0.028 |
| | | EQT | -0.026 | 0.368 | 0.803 | -0.082 | -0.201 | 0.028 | -0.100 | -0.263 |
| | | SPKW | -0.001 | 0.002 | 0.020 | 0.006 | -0.005 | 0.002 | -0.012 | -0.007 |
| | | SPKN | -0.006 | -0.120 | 0.071 | 0.031 | 0.062 | -0.006 | 0.036 | 0.080 |
| | 34210 | OTHR | 0.465 | -0.687 | 0.111 | 0.005 | 0.115 | -0.003 | 0.001 | 0.047 |
| | | TEMP | 21.500 | 5.814 | -0.637 | -2.922 | -2.837 | 0.043 | -0.005 | -0.143 |
| | | EQEW | -0.199 | 1.096 | 0.772 | 0.064 | 0.354 | -0.010 | -0.002 | 0.139 |
| | | EQNS | -1.211 | 0.237 | -3.509 | -0.031 | -0.189 | -0.011 | 0.011 | -0.088 |
| | | EQZ | 0.013 | 0.514 | -0.045 | -0.006 | -0.005 | 0.001 | -0.003 | -0.011 |
| | | EQT | 0.183 | -0.017 | 1.010 | 0.002 | 0.017 | -0.008 | 0.000 | 0.008 |
| | | SPKW | 0.016 | -0.040 | 0.002 | -0.002 | -0.023 | 0.001 | 0.000 | -0.010 |
| | | SPKN | -0.098 | 0.000 | -0.003 | -0.001 | 0.001 | -0.001 | 0.000 | 0.000 |
| | 34220 | OTHR | 0.055 | -1.132 | -0.085 | 0.054 | 0.013 | 0.007 | 0.032 | -0.008 |
| | | TEMP | 2.573 | 6.295 | 3.703 | 2.522 | -1.254 | -0.604 | 2.464 | 0.060 |
| | | EQEW | -0.162 | 0.839 | 2.354 | 0.119 | 0.142 | 0.026 | 0.026 | -0.022 |
| | | EQNS | -0.048 | 1.855 | -1.261 | 0.007 | 0.010 | -0.003 | 0.014 | -0.006 |
| | | EQZ | -0.042 | 0.660 | 0.115 | -0.034 | 0.017 | 0.007 | -0.029 | -0.002 |
| | | EQT | 0.022 | -0.043 | 0.825 | 0.027 | 0.009 | -0.016 | 0.006 | 0.019 |
| | | SPKW | 0.004 | 0.012 | -0.005 | 0.004 | -0.002 | -0.002 | 0.003 | 0.001 |
| | | SPKN | -0.001 | 0.024 | -0.002 | 0.001 | 0.000 | 0.001 | 0.000 | -0.001 |
| | 44201 | OTHR | 0.032 | -1.237 | -0.167 | 0.055 | 0.014 | 0.011 | -0.035 | -0.005 |
| | | TEMP | 1.787 | 7.067 | -0.242 | 2.081 | -1.543 | 0.575 | -2.867 | 0.058 |
| | | EQEW | 0.145 | 0.808 | 2.848 | 0.066 | 0.009 | 0.059 | -0.076 | 0.024 |
| | | EQNS | -0.107 | 2.171 | -1.075 | 0.032 | 0.040 | -0.008 | 0.012 | -0.013 |
| EQZ | | -0.013 | 0.763 | 0.232 | -0.031 | 0.008 | -0.010 | 0.033 | 0.001 | |
| EQT | | 0.031 | -0.063 | 0.814 | 0.013 | -0.003 | -0.009 | -0.025 | -0.019 | |
| SPKW | | 0.002 | 0.012 | 0.001 | 0.004 | 0.001 | -0.002 | -0.002 | -0.001 | |
| SPKN | | 0.003 | 0.022 | 0.007 | 0.000 | -0.002 | 0.000 | -0.001 | 0.000 | |

Table 3G.1-49
Combined Forces and Moments: RB, Selected Load Combination RB-9b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|-------------------------------|------------------------------|-------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 24 Basemat @ Wall Below | 90140 | OTHR | -2.939 | -2.620 | -0.036 | -1.925 | -0.968 | 1.516 | -2.457 | 2.177 | |
| | | TEMP | 0.656 | 1.198 | 1.910 | -1.176 | -1.209 | -0.620 | -1.549 | 0.481 | |
| | | EQEW | 0.415 | 4.638 | 2.888 | 0.033 | 3.216 | -2.595 | 2.865 | -5.032 | |
| | | EQNS | 0.034 | 1.460 | -2.130 | -6.707 | -0.901 | -0.370 | -2.810 | 1.163 | |
| | | EQZ | -0.060 | 0.480 | 0.263 | 1.419 | 0.971 | -2.078 | 0.964 | -1.107 | |
| | | EQT | 0.965 | -0.447 | 0.984 | 0.658 | 0.012 | -0.229 | 0.294 | 0.106 | |
| | | SPKW | -0.052 | -1.084 | -0.003 | -0.119 | 0.019 | -0.123 | -0.029 | -0.213 | |
| | | SPKN | -1.849 | 0.114 | -0.120 | -0.044 | -0.045 | 0.049 | -0.037 | 0.017 | |
| | 90182 | OTHR | -2.241 | -2.358 | -0.196 | -0.265 | -1.324 | 0.195 | 0.018 | 1.146 | |
| | | TEMP | 2.512 | 0.741 | 0.349 | -1.062 | -5.489 | 0.225 | -0.058 | 3.881 | |
| | | EQEW | 6.054 | 0.571 | 0.309 | 0.153 | -0.445 | -0.242 | -0.046 | -3.502 | |
| | | EQNS | 3.163 | 0.701 | -1.456 | -1.619 | -0.476 | 1.390 | -1.659 | 0.675 | |
| | | EQZ | 0.369 | 0.221 | 0.046 | -0.592 | 1.442 | 0.238 | -0.137 | -0.399 | |
| | | EQT | 1.000 | 0.064 | 0.515 | 0.020 | 0.260 | -0.335 | 0.346 | -0.258 | |
| | | SPKW | 0.120 | -1.176 | -0.143 | -0.170 | -0.632 | -0.021 | 0.026 | -0.440 | |
| | | SPKN | -1.507 | 0.096 | 0.137 | -0.018 | -0.210 | 0.106 | -0.110 | 0.162 | |
| | 90111 | OTHR | -3.906 | -1.826 | 0.005 | -1.720 | -0.144 | -0.354 | 0.499 | 0.271 | |
| | | TEMP | 0.765 | 3.129 | -0.048 | -5.573 | -1.340 | 0.131 | 3.888 | 0.160 | |
| | | EQEW | -0.250 | 0.765 | -0.889 | -0.470 | 0.409 | 1.439 | -0.060 | -2.916 | |
| | | EQNS | 1.027 | 5.920 | -0.258 | 0.380 | -1.228 | 0.393 | -2.033 | -0.131 | |
| | | EQZ | 0.246 | 0.490 | -0.027 | 1.301 | -0.708 | 0.327 | -0.439 | -0.071 | |
| | | EQT | -0.052 | 0.035 | -0.613 | -0.075 | 0.084 | 0.414 | 0.010 | -0.492 | |
| | | SPKW | 0.162 | -1.308 | 0.049 | -0.226 | -0.098 | 0.013 | 0.201 | -0.026 | |
| | | SPKN | -1.233 | 0.065 | -0.048 | -0.638 | -0.141 | 0.024 | -0.484 | 0.020 | |
| | 25 Slab EL4.65m @ RCCV | 93140 | OTHR | -0.251 | 0.339 | 0.631 | 0.112 | 0.122 | -0.118 | 0.127 | -0.106 |
| | | | TEMP | 0.492 | 2.917 | 5.382 | -0.741 | -0.577 | 0.416 | -0.195 | 0.167 |
| | | | EQEW | 0.376 | -0.215 | -0.049 | 0.156 | 0.126 | -0.093 | 0.047 | -0.033 |
| | | | EQNS | -1.560 | 0.330 | -0.338 | -0.361 | -0.226 | 0.156 | -0.082 | 0.108 |
| | | | EQZ | -0.001 | -0.080 | -0.032 | -0.041 | -0.051 | 0.031 | -0.067 | 0.055 |
| | | | EQT | 0.164 | -0.083 | 0.044 | 0.017 | 0.011 | -0.010 | 0.005 | -0.005 |
| SPKW | | | 0.047 | -0.822 | 0.094 | -0.028 | -0.028 | 0.019 | -0.015 | 0.002 | |
| SPKN | | | -0.302 | 0.113 | -0.040 | -0.001 | -0.004 | 0.002 | 0.000 | 0.002 | |
| 93182 | | OTHR | 0.530 | -0.301 | 0.040 | -0.011 | 0.069 | 0.011 | -0.002 | 0.036 | |
| | | TEMP | 5.915 | -4.974 | -1.483 | -0.488 | -2.534 | -0.114 | 0.106 | 1.921 | |
| | | EQEW | 0.013 | -0.083 | -0.165 | 0.085 | 0.479 | 0.017 | -0.023 | -0.425 | |
| | | EQNS | -0.546 | -0.147 | -0.448 | -0.089 | -0.343 | -0.012 | 0.018 | 0.317 | |
| | | EQZ | -0.073 | -0.068 | -0.025 | -0.020 | -0.060 | -0.004 | 0.005 | 0.099 | |
| | | EQT | 0.070 | 0.029 | -0.054 | 0.008 | 0.039 | 0.000 | -0.002 | -0.035 | |
| | | SPKW | -0.143 | -0.871 | -0.027 | -0.030 | -0.155 | -0.009 | 0.008 | 0.161 | |
| | | SPKN | -0.252 | -0.027 | 0.059 | 0.003 | 0.012 | 0.001 | -0.001 | -0.011 | |
| 93111 | | OTHR | -0.021 | 0.449 | -0.089 | 0.049 | -0.016 | -0.003 | 0.026 | -0.004 | |
| | | TEMP | -4.283 | 6.565 | -0.433 | -2.488 | -0.436 | -0.068 | 1.677 | 0.002 | |
| | | EQEW | 0.148 | 0.059 | -0.226 | 0.001 | -0.009 | -0.026 | 0.012 | 0.006 | |
| | | EQNS | -0.088 | -0.093 | 0.017 | 0.067 | -0.003 | 0.007 | -0.042 | 0.002 | |
| | | EQZ | -0.045 | -0.094 | 0.017 | -0.092 | -0.023 | -0.003 | 0.105 | 0.002 | |
| | | EQT | 0.004 | 0.003 | 0.000 | -0.002 | -0.002 | -0.002 | 0.003 | 0.000 | |
| | | SPKW | 0.021 | -0.214 | 0.023 | 0.018 | 0.003 | 0.001 | -0.014 | 0.000 | |
| | | SPKN | -0.906 | -0.142 | 0.121 | -0.154 | -0.028 | -0.007 | 0.135 | -0.001 | |

Table 3G.1-49
Combined Forces and Moments: RB, Selected Load Combination RB-9b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|------------------------------|------------------------------|-------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 26 Slab EL17.5m @ RCCV | 96144 | OTHR | 0.012 | 0.595 | 0.703 | 0.087 | 0.094 | -0.082 | 0.126 | -0.107 | |
| | | TEMP | 0.700 | 5.749 | 8.267 | -0.286 | -0.227 | 0.196 | -0.057 | 0.076 | |
| | | EQEW | -0.105 | -0.246 | -0.165 | 0.139 | 0.119 | -0.090 | 0.046 | -0.017 | |
| | | EQNS | -0.551 | 0.162 | 0.116 | -0.295 | -0.230 | 0.156 | -0.061 | 0.070 | |
| | | EQZ | 0.200 | -0.155 | -0.096 | -0.036 | -0.037 | 0.029 | -0.072 | 0.054 | |
| | | EQT | 0.135 | -0.045 | 0.000 | 0.011 | 0.010 | -0.006 | 0.003 | -0.001 | |
| | | SPKW | 0.019 | -0.035 | 0.000 | -0.004 | -0.004 | 0.002 | -0.002 | 0.000 | |
| | | SPKN | -0.063 | 0.031 | -0.002 | 0.002 | -0.001 | 0.000 | 0.001 | 0.000 | |
| | 96186 | OTHR | 0.896 | -0.363 | -0.017 | -0.018 | -0.042 | 0.000 | 0.001 | -0.011 | |
| | | TEMP | 9.948 | -4.570 | -2.192 | -0.167 | -0.770 | -0.060 | 0.028 | 0.708 | |
| | | EQEW | -0.330 | 0.169 | -0.231 | 0.108 | 0.616 | 0.023 | -0.031 | -0.490 | |
| | | EQNS | -0.608 | -0.144 | 0.033 | -0.075 | -0.342 | -0.012 | 0.027 | 0.274 | |
| | | EQZ | -0.178 | 0.088 | 0.017 | 0.003 | 0.021 | -0.001 | 0.006 | 0.023 | |
| | | EQT | 0.064 | 0.032 | -0.075 | 0.005 | 0.025 | -0.001 | -0.002 | -0.022 | |
| | | SPKW | 0.040 | 0.012 | -0.002 | -0.011 | -0.049 | -0.002 | 0.002 | 0.040 | |
| | | SPKN | -0.077 | -0.028 | 0.030 | 0.001 | 0.004 | 0.001 | 0.000 | -0.003 | |
| | 96113 | OTHR | -0.542 | 1.420 | -0.157 | -0.128 | -0.001 | 0.003 | 0.240 | 0.033 | |
| | | TEMP | -8.874 | 6.067 | -1.617 | -4.618 | -2.819 | -0.231 | 0.824 | -0.088 | |
| | | EQEW | 0.093 | -0.157 | 0.672 | 0.081 | 0.033 | -0.003 | -0.018 | 0.044 | |
| | | EQNS | 0.211 | -1.036 | 0.004 | 0.468 | -0.036 | -0.012 | -0.448 | -0.066 | |
| | | EQZ | 0.138 | -0.325 | 0.062 | 0.169 | -0.011 | -0.009 | -0.171 | -0.016 | |
| | | EQT | 0.010 | -0.006 | 0.231 | 0.008 | 0.008 | 0.007 | 0.003 | 0.011 | |
| | | SPKW | -0.039 | -0.093 | -0.004 | 0.033 | 0.008 | 0.001 | -0.022 | -0.002 | |
| | | SPKN | 0.042 | 0.100 | 0.008 | -0.114 | -0.024 | -0.004 | 0.084 | 0.007 | |
| | 27 Slab EL27.0m @ RCCV | 98472 | OTHR | 0.461 | 0.456 | -0.152 | 0.038 | 0.073 | -0.063 | 0.174 | -0.187 |
| | | | TEMP | -4.962 | -2.596 | 6.296 | -1.806 | -1.112 | -0.359 | 0.516 | -0.793 |
| | | | EQEW | 0.368 | -1.005 | -0.324 | 0.038 | 0.037 | -0.017 | 0.011 | -0.012 |
| | | | EQNS | 1.119 | -0.227 | 0.006 | -0.157 | -0.188 | 0.097 | -0.125 | 0.084 |
| | | | EQZ | -0.147 | 0.039 | -0.075 | -0.116 | -0.166 | 0.128 | -0.206 | 0.148 |
| | | | EQT | -0.089 | 0.058 | 0.007 | 0.014 | 0.016 | -0.011 | 0.014 | -0.007 |
| SPKW | | | 0.037 | -0.008 | -0.012 | -0.004 | -0.007 | 0.003 | -0.006 | 0.003 | |
| SPKN | | | -0.066 | 0.024 | 0.010 | 0.000 | -0.001 | 0.000 | 0.000 | 0.001 | |
| 98514 | | OTHR | 0.253 | 0.354 | 0.106 | -0.017 | -0.196 | 0.006 | 0.003 | -0.079 | |
| | | TEMP | -2.970 | -2.936 | -1.382 | -1.925 | -1.714 | -0.029 | 0.056 | -0.715 | |
| | | EQEW | -0.436 | 0.202 | -0.314 | 0.063 | 0.442 | -0.005 | -0.007 | -0.334 | |
| | | EQNS | -0.235 | -0.151 | -0.159 | -0.073 | -0.260 | 0.002 | 0.008 | 0.265 | |
| | | EQZ | 0.011 | -0.071 | -0.044 | -0.025 | -0.082 | -0.018 | -0.002 | 0.114 | |
| | | EQT | 0.074 | 0.006 | -0.051 | 0.005 | 0.022 | -0.002 | -0.001 | -0.021 | |
| | | SPKW | 0.030 | -0.008 | -0.004 | -0.007 | -0.034 | -0.001 | 0.000 | 0.028 | |
| | | SPKN | -0.025 | -0.007 | 0.021 | 0.000 | -0.001 | 0.001 | 0.000 | 0.000 | |
| 98424 | | OTHR | 0.245 | 1.121 | -0.152 | 0.357 | 0.130 | -0.160 | -0.543 | -0.103 | |
| | | TEMP | -8.160 | -4.306 | -3.504 | 8.110 | 4.330 | 0.601 | -4.475 | -0.830 | |
| | | EQEW | 0.659 | -0.569 | -5.339 | 0.057 | 0.036 | -0.148 | 0.029 | -0.002 | |
| | | EQNS | 0.941 | -1.089 | 0.420 | -1.018 | -0.413 | 0.137 | 1.105 | 0.161 | |
| | | EQZ | -0.029 | -0.290 | 0.019 | -1.420 | -0.331 | -0.030 | 0.841 | 0.152 | |
| | | EQT | 0.057 | -0.034 | -0.745 | 0.023 | 0.019 | 0.018 | -0.014 | 0.006 | |
| | | SPKW | 0.005 | -0.004 | -0.003 | 0.032 | 0.015 | -0.002 | -0.023 | -0.005 | |
| | | SPKN | -0.007 | 0.009 | 0.005 | -0.070 | -0.034 | 0.000 | 0.049 | 0.007 | |

Table 3G.1-49
Combined Forces and Moments: RB, Selected Load Combination RB-9b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|-------------------------------------|------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 28 Pool Girder @ Storage Pool | 123004 | OTHR | 0.475 | -0.317 | 0.673 | 0.051 | 0.144 | -0.042 | 0.048 | 0.102 |
| | | TEMP | -3.773 | -8.910 | 2.443 | -3.192 | -1.409 | -0.451 | -0.296 | 2.590 |
| | | EQEW | -0.043 | -0.854 | -0.200 | 0.285 | 0.713 | -0.142 | 0.099 | 0.614 |
| | | EQNS | 0.507 | 2.822 | -0.383 | -0.070 | -0.008 | 0.034 | -0.041 | -0.012 |
| | | EQZ | 0.536 | 3.574 | 1.280 | -0.034 | 0.052 | -0.025 | 0.001 | 0.018 |
| | | EQT | -0.016 | -0.254 | -0.044 | 0.023 | 0.060 | -0.020 | -0.001 | 0.045 |
| | | SPKW | 0.012 | -0.013 | -0.018 | 0.001 | 0.007 | -0.002 | 0.000 | 0.004 |
| | SPKN | -0.021 | 0.073 | -0.005 | -0.003 | -0.006 | 0.001 | -0.001 | -0.003 | |
| | 123104 | OTHR | 0.467 | -0.230 | 0.951 | 0.006 | -0.015 | 0.003 | 0.026 | 0.029 |
| | | TEMP | -0.908 | -1.329 | 2.320 | -4.096 | -4.643 | 0.160 | -1.017 | 0.189 |
| | | EQEW | 0.031 | -0.354 | 0.429 | 0.149 | -0.068 | -0.025 | 0.014 | 0.077 |
| | | EQNS | -0.578 | 1.180 | -0.739 | -0.090 | -0.008 | -0.001 | -0.034 | 0.011 |
| | | EQZ | -0.664 | 1.245 | 0.734 | -0.024 | -0.002 | -0.018 | -0.017 | 0.015 |
| | | EQT | 0.011 | -0.111 | 0.039 | 0.026 | 0.005 | -0.005 | -0.002 | 0.008 |
| SPKW | | -0.001 | -0.004 | -0.016 | 0.001 | 0.001 | -0.001 | -0.001 | 0.001 | |
| SPKN | -0.025 | 0.025 | -0.018 | -0.002 | 0.000 | 0.001 | 0.000 | -0.001 | | |
| 29 Pool Girder @ Cavity | 123012 | OTHR | 0.089 | -0.578 | -0.382 | 0.005 | 0.134 | -0.008 | 0.029 | 0.114 |
| | | TEMP | -1.054 | -0.015 | -0.253 | -3.807 | -2.087 | 0.177 | 0.085 | 1.518 |
| | | EQEW | -0.584 | -0.011 | 0.262 | 0.082 | 0.217 | -0.021 | 0.002 | 0.186 |
| | | EQNS | 0.042 | -0.086 | 0.277 | -0.025 | 0.009 | -0.004 | 0.026 | 0.045 |
| | | EQZ | -0.913 | -0.581 | -0.368 | 0.034 | 0.265 | -0.003 | 0.016 | 0.151 |
| | | EQT | 0.026 | 0.003 | -0.007 | 0.001 | -0.005 | -0.002 | 0.002 | -0.003 |
| | | SPKW | 0.031 | 0.001 | -0.003 | 0.000 | 0.001 | 0.000 | -0.001 | 0.000 |
| | SPKN | -0.032 | 0.000 | 0.003 | 0.000 | -0.001 | 0.000 | 0.000 | 0.000 | |
| | 123112 | OTHR | 0.422 | -0.348 | -0.343 | 0.000 | -0.020 | -0.016 | 0.006 | 0.002 |
| | | TEMP | 0.270 | 0.204 | -0.469 | -4.115 | -3.707 | -0.173 | -0.004 | -0.028 |
| | | EQEW | -0.677 | -0.004 | 0.368 | 0.091 | -0.015 | -0.016 | -0.088 | -0.009 |
| | | EQNS | -0.554 | -0.088 | 0.245 | -0.113 | -0.026 | -0.013 | 0.039 | 0.003 |
| | | EQZ | 0.119 | -0.337 | -0.426 | 0.010 | 0.031 | -0.027 | -0.013 | 0.012 |
| | | EQT | 0.051 | 0.002 | -0.021 | -0.001 | -0.003 | -0.005 | 0.003 | 0.001 |
| SPKW | | -0.001 | -0.001 | 0.000 | 0.000 | 0.000 | 0.001 | -0.001 | 0.000 | |
| SPKN | -0.013 | 0.001 | -0.002 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | | |
| 30 Pool Girder @ Fuel Pool | 123017 | OTHR | 0.526 | 0.576 | -0.520 | -0.022 | -0.093 | 0.040 | -0.004 | -0.134 |
| | | TEMP | 5.174 | -7.676 | -2.218 | 2.827 | 2.660 | -0.299 | 0.268 | 0.240 |
| | | EQEW | -0.134 | -0.858 | 0.754 | 0.327 | 0.638 | 0.095 | -0.251 | 0.577 |
| | | EQNS | 0.301 | 2.991 | 0.076 | 0.072 | 0.236 | 0.043 | 0.022 | 0.221 |
| | | EQZ | 0.443 | 3.312 | -1.363 | -0.060 | 0.040 | 0.080 | 0.011 | 0.084 |
| | | EQT | -0.005 | -0.005 | -0.041 | -0.014 | -0.083 | -0.023 | -0.001 | -0.054 |
| | | SPKW | 0.015 | -0.001 | 0.018 | 0.002 | 0.009 | 0.003 | 0.000 | 0.007 |
| | SPKN | -0.014 | 0.057 | -0.009 | -0.003 | -0.005 | -0.003 | 0.003 | -0.005 | |
| | 123117 | OTHR | -0.052 | 0.114 | -0.538 | 0.035 | 0.044 | 0.013 | 0.015 | 0.021 |
| | | TEMP | 1.809 | -2.768 | -0.560 | 2.974 | 1.894 | -0.159 | -0.541 | 0.254 |
| | | EQEW | -0.187 | -0.380 | -0.012 | 0.094 | -0.070 | 0.027 | 0.019 | 0.053 |
| | | EQNS | -1.053 | 0.840 | 1.010 | 0.040 | 0.016 | -0.022 | 0.023 | 0.011 |
| | | EQZ | -0.434 | 0.996 | -0.736 | -0.052 | -0.054 | 0.013 | 0.005 | -0.002 |
| | | EQT | 0.066 | 0.034 | -0.012 | -0.017 | -0.005 | -0.009 | -0.008 | -0.007 |
| SPKW | | -0.005 | 0.000 | 0.014 | 0.001 | 0.000 | 0.000 | 0.001 | 0.001 | |
| SPKN | -0.006 | 0.018 | 0.008 | -0.004 | -0.001 | -0.001 | 0.000 | 0.000 | | |

Table 3G.1-49
Combined Forces and Moments: RB, Selected Load Combination RB-9b (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|-------------------------------|------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 31 MS Tunnel Wall and Slab | 150122 | OTHR | -0.198 | -0.271 | 0.952 | -0.017 | 0.058 | 0.019 | -0.023 | -0.054 |
| | | TEMP | 2.279 | -0.182 | -0.887 | 3.448 | 3.933 | 0.118 | -0.222 | -0.262 |
| | | EQEW | 0.113 | 0.172 | -0.176 | 0.072 | -0.158 | -0.012 | 0.018 | 0.202 |
| | | EQNS | 0.144 | 0.403 | -0.048 | -0.062 | -0.103 | -0.009 | 0.015 | -0.033 |
| | | EQZ | 0.174 | 0.081 | -0.517 | 0.007 | -0.016 | -0.011 | 0.016 | 0.034 |
| | | EQT | 0.009 | 0.016 | -0.055 | 0.012 | -0.027 | -0.012 | 0.003 | 0.047 |
| | | SPKW | 0.006 | -0.006 | 0.001 | 0.002 | 0.001 | -0.001 | 0.000 | 0.000 |
| | SPKN | -0.010 | -0.013 | 0.000 | 0.002 | 0.003 | 0.000 | 0.000 | 0.000 | 0.001 |
| | 96611 | OTHR | -0.096 | 0.496 | -0.067 | 0.043 | -0.160 | -0.090 | -0.191 | 0.009 |
| | | TEMP | -0.295 | 3.728 | -0.322 | -3.550 | -6.604 | -0.232 | 0.690 | 0.063 |
| | | EQEW | 0.019 | -0.093 | -0.266 | -0.036 | -0.076 | 0.083 | -0.011 | -0.060 |
| | | EQNS | 0.026 | -0.379 | 0.030 | -0.117 | -0.342 | 0.005 | 0.077 | 0.012 |
| | | EQZ | 0.036 | -0.192 | 0.026 | 0.028 | 0.132 | 0.058 | 0.115 | -0.007 |
| | | EQT | 0.006 | -0.014 | -0.072 | -0.008 | -0.014 | 0.036 | -0.004 | -0.011 |
| | | SPKW | -0.017 | 0.004 | -0.006 | 0.000 | 0.002 | 0.000 | 0.000 | 0.000 |
| | SPKN | 0.024 | -0.015 | 0.009 | 0.010 | 0.014 | 0.001 | -0.004 | 0.000 | |
| | 98614 | OTHR | 0.023 | -0.040 | 0.044 | -0.272 | -0.683 | -0.069 | -0.099 | 0.015 |
| | | TEMP | 1.306 | 2.277 | -0.049 | 9.353 | 14.160 | -0.019 | -1.882 | -0.168 |
| | | EQEW | -0.025 | -0.005 | 0.172 | -0.022 | 0.063 | 0.203 | -0.041 | 0.048 |
| | | EQNS | 0.080 | -0.246 | 0.036 | 0.176 | 0.303 | 0.009 | -0.069 | -0.009 |
| | | EQZ | -0.008 | 0.058 | -0.023 | 0.013 | 0.311 | 0.032 | 0.089 | -0.010 |
| | | EQT | -0.012 | 0.006 | 0.057 | -0.005 | 0.004 | 0.061 | -0.006 | 0.002 |
| | | SPKW | 0.000 | -0.006 | 0.001 | -0.014 | -0.009 | -0.001 | 0.003 | 0.000 |
| | SPKN | -0.006 | 0.013 | -0.002 | 0.015 | 0.000 | 0.002 | -0.002 | 0.000 | |

Table 3G.1-50

Sectional Thicknesses and Rebar Ratios of RB Used in the Evaluation

| Location | Element ID | Thickness (m) | Primary Reinforcement | | | | Shear Tie | | |
|--------------------------------------|----------------------|---------------|-----------------------|---------------------------|-----------|---------------------------|-----------|-------------|-----------|
| | | | Position | Direction 1 ^{*1} | | Direction 2 ^{*1} | | Arrangement | Ratio (%) |
| | | | | Arrangement ^{*2} | Ratio (%) | Arrangement ^{*2} | Ratio (%) | | |
| 18 Wall Below RCCV Bottom | 6 13 24 | 2.0 | Inside | 2-#18@300 | 0.860 | 3-#18@0.9° | 1.297 | #9@0.9°x300 | 0.721 |
| | | | Outside | 3-#18@300 | 1.290 | 3-#18@0.9° +1-#18@0.9° | 1.729 | | |
| 19 Wall Below RCCV Mid-Height | 806 813 824 | 2.0 | Inside | 2-#18@300 | 0.860 | 3-#18@0.9° | 1.297 | #9@1.2°x600 | 0.270 |
| | | | Outside | 3-#18@300 | 1.290 | 3-#18@0.9° | 1.297 | | |
| 20 Wall Below RCCV Top | 1606 1613 1624 | 2.0 | Inside | 2-#18@300 | 0.860 | 3-#18@0.9° | 1.297 | #9@1.2°x300 | 0.540 |
| | | | Outside | 3-#18@300 | 1.290 | 3-#18@0.9° +1-#18@1.8° | 1.513 | | |
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 20023 | 2.0 | Inside | 4-#11@200 +1-#11@400 | 1.132 | 5-#11@200 | 1.258 | #7@400x200 | 0.484 |
| | | | Outside | 4-#11@200 +1-#11@400 | 1.132 | 5-#11@200 | 1.258 | | |
| | 30010 30020 | 2.0 | Inside | 3-#11@200 +1-#11@400 | 0.881 | 4-#11@200 | 1.006 | #6@400x400 | 0.177 |
| | | | Outside | 3-#11@200 +1-#11@400 | 0.881 | 4-#11@200 | 1.006 | | |
| | 40001 40011 | 2.0 | Inside | 3-#11@200 | 0.755 | 3-#11@200 | 0.755 | #6@400x400 | 0.177 |
| | | | Outside | 3-#11@200 | 0.755 | 3-#11@200 | 0.755 | | |
| 22 Exterior Wall @ EL4.65 ~-6.60m | 22011 | 1.5 | Inside | 3-#11@200 +1-#11@400 | 1.174 | 4-#11@200 (+1-#11@200) | 1.677 | #7@400x200 | 0.484 |
| | | | Outside | 3-#11@200 +1-#11@400 | 1.174 | 4-#11@200 (+1-#11@200) | 1.677 | | |
| | 22023 | 1.5 | Inside | 3-#11@200 +1-#11@400 | 1.174 | 4-#11@200 | 1.342 | #7@400x200 | 0.484 |
| | | | Outside | 3-#11@200 +1-#11@400 | 1.174 | 4-#11@200 | 1.342 | | |
| | 32010 | 1.5 | Inside | 3-#11@200 | 1.006 | 3-#11@200 | 1.006 | #6@400x400 | 0.177 |
| | | | Outside | 3-#11@200 (+2-#11@200) | 1.677 | 3-#11@200 (+2-#11@200) | 1.677 | | |
| | 32020 | 1.5 | Inside | 3-#11@200 | 1.006 | 3-#11@200 | 1.006 | #6@400x400 | 0.177 |
| | | | Outside | 3-#11@200 | 1.006 | 3-#11@200 | 1.006 | | |
| | 42001 | 1.5 | Inside | 3-#11@200 | 1.006 | 3-#11@200 | 1.006 | #7@400x400 | 0.242 |
| | | | Outside | 4-#11@200 | 1.342 | 4-#11@200 | 1.342 | | |

Note *1: Wall Below RCCV Direction1 : Hoop, Direction2 : Vertical
 Exterior Wall Direction1 : Horizontal, Direction2 : Vertical
 Slab Direction1 : N-S, Direction2 : E-W
 Pool Girder Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Wall Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Slab Direction1 : N-S, Direction2 : E-W

Note *2: Rebar in parentheses indicates additional bars locally required.

Table 3G.1-50
Sectional Thicknesses and Rebar Ratios of RB Used in the Evaluation (Continued)

| Location | Element ID | Thickness (m) | Primary Reinforcement | | | | | Shear Tie | | |
|------------------------------------|------------------------------|-------------------------|-----------------------|---------------------------|-----------|---------------------------|--------------------|-------------|------------|-------|
| | | | Position | Direction 1 ^{*1} | | Direction 2 ^{*1} | | Arrangement | Ratio (%) | |
| | | | | Arrangement ^{*2} | Ratio (%) | Arrangement ^{*2} | Ratio (%) | | | |
| 22 Exterior Wall @ EL4.65 ~6.60m | 42011 | 1.5 | Inside | 3-#11@200 | 1.006 | 3-#11@200 | 1.006 | #7@400x400 | 0.242 | |
| | | | Outside | 4-#11@200 (+1-#11@200) | 1.677 | 4-#11@200 (+1-#11@200) | 1.677 | | | |
| 23 Exterior Wall @ EL22.50 ~24.60m | 24211 | 1.5 | Inside | 3-#11@200 +1-#11@400 | 1.174 | 4-#11@200 | 1.342 | #7@400x200 | 0.484 | |
| | | | Outside | 3-#11@200 +1-#11@400 | 1.174 | 4-#11@200 | 1.342 | | | |
| | 24224 | 1.5 | Inside | 3-#11@200 +1-#11@400 | 1.174 | 4-#11@200 | 1.342 | #7@200x200 | 0.968 | |
| | | | Outside | 3-#11@200 +1-#11@400 | 1.174 | 4-#11@200 | 1.342 | | | |
| | 34210 | 1.5 | Inside | 3-#11@200 | 1.006 | 3-#11@200 | 1.006 | #6@400x400 | 0.177 | |
| | | | Outside | 3-#11@200 (+2-#11@200) | 1.677 | 3-#11@200 (+2-#11@200) | 1.677 | | | |
| | 34220 | 1.5 | Inside | 3-#11@200 | 1.006 | 3-#11@200 | 1.006 | #6@200x200 | 0.710 | |
| | | | Outside | 3-#11@200 | 1.006 | 3-#11@200 | 1.006 | | | |
| | 44201 | 1.5 | Inside | 3-#11@200 | 1.006 | 3-#11@200 | 1.006 | #7@200x200 | 0.968 | |
| | | | Outside | 4-#11@200 | 1.342 | 4-#11@200 | 1.342 | | | |
| | 24 Basemat @ Wall Below RCCV | 90140 90182 90111 | 4.0 | Top | 6-#9@1.8° | 0.497 | 2-#9@200 +4-#9@400 | 0.323 | #9@200x200 | 1.613 |
| | | | | Bottom | 5-#11@200 | 0.629 | 5-#11@200 | 0.629 | | |
| 25 Slab EL4.65m @ RCCV | 93140 93182 93111 | 1.0 | Top | 2-#11@200 | 1.006 | 2-#11@200 | 1.006 | #5@200x200 | 0.500 | |
| | | | Bottom | PLATE t=16 | - | PLATE t=16 | - | | | |
| 26 Slab EL17.5m @ RCCV | 96144 96186 | 1.0 | Top | 2-#11@200 | 1.006 | 2-#11@200 | 1.006 | #5@200x200 | 0.500 | |
| | | | Bottom | PLATE t=16 | - | PLATE t=16 | - | | | |
| | 96113 | 1.6 | Top | 2-#11@200 | 0.629 | 2-#11@200 | 0.629 | #5@200x200 | 0.500 | |
| | | | Bottom | 3-#11@200 | 0.944 | 3-#11@200 | 0.944 | | | |

Note *1: Wall Below RCCV Direction1 : Hoop, Direction2 : Vertical
 Exterior Wall Direction1 : Horizontal, Direction2 : Vertical
 Slab Direction1 : N-S, Direction2 : E-W
 Pool Girder Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Wall Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Slab Direction1 : N-S, Direction2 : E-W

Note *2: Rebar in parentheses indicates additional bars locally required.

Table 3G.1-50
Sectional Thicknesses and Rebar Ratios of RB Used in the Evaluation (Continued)

| Location | Element ID | Thickness (m) | Primary Reinforcement | | | | Shear Tie | | |
|----------------------------------|------------------|---------------|-----------------------|--------------------------|-----------|--------------------------|-----------|-------------|-----------|
| | | | Position | Direction 1 ¹ | | Direction 2 ¹ | | Arrangement | Ratio (%) |
| | | | | Arrangement ² | Ratio (%) | Arrangement ² | Ratio (%) | | |
| 27 Slab EL27.0m @ RCCV | 98472 98514 | 1.0 | Top | 3-#11@200 | 1.510 | 3-#11@200 | 1.510 | #5@200x200 | 0.500 |
| | | | Bottom | PLATE t=25 | - | PLATE t=25 | - | | |
| | 98424 | 2.4 | Top | 4-#11@200 | 0.839 | 4-#11@200 | 0.839 | #5@200x200 | 0.500 |
| | | | Bottom | 3-#11@200 | 0.629 | 3-#11@200 | 0.629 | | |
| 28 Pool Girder @ Storage Pool | 123004 | 1.6 | Inside | 3-#11@200 | 0.944 | 3-#11@200 (+1#11@200) | 1.258 | #7@200x200 | 0.968 |
| | | | Outside | 3-#11@200 | 0.944 | 3-#11@200 | 0.944 | | |
| | 123104 | 1.6 | Inside | 3-#11@200 | 0.944 | 3-#11@200 | 0.944 | #7@400x200 | 0.484 |
| | | | Outside | 3-#11@200 | 0.944 | 3-#11@200 | 0.944 | | |
| 29 Pool Girder @ Cavity | 123012 123112 | 1.6 | Inside | 3-#11@200 | 0.944 | 2-#11@200 | 0.629 | #7@400x400 | 0.242 |
| | | | Outside | 2-#11@200 | 0.629 | 2-#11@200 | 0.629 | | |
| 30 Pool Girder @ Fuel Pool | 123017 | 1.6 | Inside | 3-#11@200 | 0.944 | 3-#11@200 (+1#11@200) | 1.258 | #7@200x200 | 0.968 |
| | | | Outside | 3-#11@200 | 0.944 | 3-#11@200 | 0.944 | | |
| | 123117 | 1.6 | Inside | 3-#11@200 | 0.944 | 3-#11@200 | 0.944 | #7@400x200 | 0.484 |
| | | | Outside | 3-#11@200 | 0.944 | 3-#11@200 | 0.944 | | |
| 31 MS Tunnel Wall and Slab | 150122 | 1.3 | Inside | 2-#11@200 | 0.774 | 2-#11@200 | 0.774 | #6@400x400 | 0.177 |
| | | | Outside | 2-#11@200 +1-#11@400 | 0.968 | 4-#11@200 +1-#11@400 | 0.968 | | |
| | 96611 | 1.6 | Top | 2-#11@200 | 0.629 | 2-#11@200 | 0.629 | #5@200x200 | 0.500 |
| | | | Bottom | 3-#11@200 | 0.944 | 3-#11@200 | 0.944 | | |
| | 98614 | 2.4 | Top | 4-#11@200 | 0.839 | 4-#11@200 | 0.839 | #5@200x200 | 0.500 |
| | | | Bottom | 3-#11@200 | 0.629 | 3-#11@200 | 0.629 | | |

Note *1: Wall Below RCCV Direction1 : Hoop, Direction2 : Vertical
 Exterior Wall Direction1 : Horizontal, Direction2 : Vertical
 Slab Direction1 : N-S, Direction2 : E-W
 Pool Girder Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Wall Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Slab Direction1 : N-S, Direction2 : E-W

Note *2: Rebar in parentheses indicates additional bars locally required.

Table 3G.1-51

Rebar and Concrete Stresses of RB: Selected Load Combination RB-4

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|---|------------|-----------------------|-----------|------------------------------------|-------|-------------------------|-------|-----------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 [*] | | Direction2 [*] | | |
| | | | | In | Out | In | Out | |
| 21 Exterior Wall @ EL-11.50 ~10.50m | 20011 | -2.2 | -29.3 | 1.7 | 0.7 | 7.2 | -9.7 | 372.2 |
| | 20023 | -6.3 | -29.1 | -30.4 | -1.0 | -20.4 | 16.5 | 370.5 |
| | 30010 | -1.4 | -29.3 | 0.3 | -8.0 | 1.4 | -0.8 | 372.2 |
| | 30020 | -2.1 | -29.3 | -7.6 | 1.5 | -4.3 | -12.1 | 372.2 |
| | 40001 | -1.8 | -29.3 | -4.3 | -1.0 | -5.8 | -9.9 | 372.2 |
| | 40011 | -0.9 | -29.3 | -0.1 | -4.6 | -0.6 | -3.3 | 372.2 |
| 22 Exterior Wall @ EL4.65 ~6.60m | 22011 | -1.0 | -29.3 | 31.1 | 32.9 | 8.6 | 1.5 | 372.2 |
| | 22023 | -3.8 | -29.3 | 13.1 | 5.7 | -27.8 | -23.2 | 372.2 |
| | 32010 | -0.1 | -29.3 | 74.2 | 158.7 | 17.2 | 113.2 | 372.2 |
| | 32020 | -3.5 | -29.3 | 5.6 | 47.2 | -5.1 | 53.7 | 372.2 |
| | 42001 | -3.4 | -29.3 | 7.8 | 34.7 | -10.3 | 29.0 | 372.2 |
| | 42011 | -3.9 | -29.3 | 27.8 | 90.1 | -10.5 | 20.6 | 372.2 |
| 23 Exterior Wall @ EL22.50 ~24.60m | 24211 | -2.0 | -29.3 | 16.4 | 26.2 | -5.3 | 21.1 | 372.2 |
| | 24224 | -2.7 | -29.3 | 24.2 | -0.2 | 6.2 | 16.4 | 372.2 |
| | 34210 | -2.4 | -29.3 | 51.8 | 127.5 | 7.9 | 91.2 | 372.2 |
| | 34220 | -0.8 | -29.3 | 35.5 | 7.4 | -19.8 | 56.1 | 372.2 |
| | 44201 | -0.6 | -29.3 | 44.0 | 34.7 | -4.3 | 69.1 | 372.2 |

Note: Negative value means compression.

Note *: Exterior Wall Direction1 : Horizontal, Direction2 : Vertical

Table 3G.1-52

Rebar and Concrete Stresses of RB: Selected Load Combination RB-8a

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable ² |
|--|------------|-----------------------|-----------|------------------------------------|------------|-------------------------|------------|------------------------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 ¹ | | Direction2 ¹ | | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 18 Wall Below RCCV Bottom | 6 | -7.5 | -29.3 | -1.0 | -1.1 | -11.9 | -41.3 | 372.2 |
| | 13 | -6.8 | -29.3 | -1.3 | -1.8 | -17.5 | -39.0 | 372.2 |
| | 24 | -5.6 | -29.3 | 0.8 | -0.1 | -26.9 | -35.6 | 372.2 |
| 19 Wall Below Below RCCV Mid-Height | 806 | -5.6 | -29.3 | 3.4 | 4.7 | -19.8 | -34.1 | 372.2 |
| | 813 | -6.1 | -29.3 | 1.6 | 2.5 | -22.3 | -37.1 | 372.2 |
| | 824 | -7.1 | -29.3 | 0.9 | 0.8 | -23.7 | -41.8 | 372.2 |
| 20 Wall Below RCCV Top | 1606 | -15.3 | -29.3 | 41.8 | 95.7 | -68.4 | 42.9 | 372.2 |
| | 1613 | -16.7 | -29.3 | 35.6 | 85.7 | -76.6 | 40.7 | 372.2 |
| | 1624 | -16.6 | -29.3 | 35.5 | 81.4 | -80.1 | 30.0 | 372.2 |
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | -2.1 | -29.3 | 3.6 | 0.0 | 9.5 | -8.4 | 372.2 |
| | 20023 | -5.0 | -29.1 | -23.5 | -0.2 | -17.2 | 10.5 | 370.5 |
| | 30010 | -1.1 | -29.3 | 3.0 | -5.0 | 2.4 | -3.4 | 372.2 |
| | 30020 | -1.8 | -29.3 | -5.7 | 2.6 | -5.8 | -10.7 | 372.2 |
| | 40001 | -1.7 | -29.3 | -3.4 | 0.3 | -6.5 | -9.3 | 372.2 |
| | 40011 | -1.3 | -29.3 | 0.4 | -3.9 | 4.6 | -5.9 | 372.2 |
| 22 Exterior Wall @ EL4.65 ~6.60m | 22011 | -0.9 | -29.3 | 49.9 | 51.9 | 12.2 | 2.6 | 372.2 |
| | 22023 | -3.2 | -29.3 | 23.3 | 4.6 | -18.9 | -18.4 | 372.2 |
| | 32010 | -1.1 | -29.3 | 36.4 | 91.9 | -2.5 | 14.0 | 372.2 |
| | 32020 | -3.0 | -29.3 | 8.3 | 31.7 | -6.8 | 40.5 | 372.2 |
| | 42001 | -1.9 | -29.3 | 10.6 | 18.8 | -10.0 | 18.9 | 372.2 |
| | 42011 | -2.4 | -29.3 | 27.9 | 82.8 | -8.5 | 15.7 | 372.2 |
| 23 Exterior Wall @ EL22.50 ~24.60m | 24211 | -0.1 | -29.3 | 46.1 | 46.5 | 19.5 | 15.3 | 372.2 |
| | 24224 | -1.6 | -29.3 | 16.8 | -0.3 | -0.3 | 13.7 | 372.2 |
| | 34210 | -0.1 | -29.3 | 100.1 | 173.4 | 35.0 | 110.2 | 372.2 |
| | 34220 | -0.8 | -29.3 | 35.6 | -7.3 | -12.0 | 42.0 | 372.2 |
| | 44201 | -0.2 | -29.3 | 46.7 | 21.9 | 3.1 | 48.9 | 372.2 |
| 24 Basemat @ Wall Below RCCV | 90140 | -1.8 | -23.5 | -12.1 | 1.5 | -0.3 | -1.0 | 372.2 |
| | 90182 | -1.8 | -23.5 | -9.5 | 2.7 | -1.4 | 7.3 | 372.2 |
| | 90111 | -2.3 | -23.5 | -14.7 | 3.6 | 0.3 | 3.0 | 372.2 |
| 25 Slab EL4.65m @ RCCV | 93140 | -6.7 | -29.3 | 107.4 | 68.5 | 174.9 | 81.2 | 372.2(223.3) |
| | 93182 | -12.8 | -29.3 | 74.7 | 53.9 | -64.1 | 48.3 | 372.2(223.3) |
| | 93111 | -12.3 | -29.3 | -58.7 | 62.0 | 76.0 | 56.4 | 372.2(223.3) |
| 26 Slab EL17.5m @ RCCV | 96144 | -9.3 | -29.3 | 227.5 | 94.2 | 296.0 | 107.9 | 372.2(223.3) |
| | 96186 | -6.7 | -29.3 | 134.8 | 67.4 | -32.3 | -6.3 | 372.2(223.3) |
| | 96113 | -13.5 | -28.8 | -79.9 | 28.9 | 69.0 | 104.0 | 368.2 |
| 27 Slab EL27.0m @ RCCV | 98472 | -8.5 | -29.1 | 118.2 | 29.8 | 167.1 | 25.9 | 370.3(222.2) |
| | 98514 | -3.8 | -29.1 | 7.8 | 36.7 | -9.2 | 13.3 | 370.3(222.2) |
| | 98424 | -9.1 | -28.1 | 18.1 | -46.9 | 9.8 | -30.5 | 363.0 |
| 28 Pool Girder @ Storage Pool | 123004 | -9.0 | -28.4 | -2.7 | -5.9 | -21.1 | -46.3 | 365.0 |
| | 123104 | -4.6 | -28.4 | 45.3 | 69.6 | 17.5 | 51.9 | 365.0 |
| 29 Pool Girder @ Cavity | 123012 | -2.0 | -28.4 | -4.4 | -5.1 | 10.1 | -7.8 | 365.0 |
| | 123112 | -1.7 | -28.4 | -8.0 | -5.9 | -2.2 | 0.1 | 365.0 |
| 30 Pool Girder @ Fuel Pool | 123017 | -9.5 | -29.0 | 103.4 | 29.6 | 49.8 | -25.8 | 369.8 |
| | 123117 | -7.0 | -29.0 | 77.6 | 0.9 | 79.3 | -3.9 | 369.8 |
| 31 MS Tunnel Wall and Slab | 150122 | -10.8 | -29.3 | 159.7 | 2.4 | 130.7 | -18.9 | 372.2 |
| | 96611 | -6.7 | -29.3 | -11.0 | 42.0 | -9.6 | 156.9 | 372.2 |
| | 98614 | -4.4 | -29.3 | 54.4 | -8.9 | 91.6 | -10.3 | 372.2 |

Note: Negative value means compression.

Note *1: Wall Below RCCV Direction1 : Hoop, Direction2 : Vertical
 Exterior Wall Direction1 : Horizontal, Direction2 : Vertical
 Slab Direction1 : N-S, Direction2 : E-W
 Pool Girder Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Wall Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Slab Direction1 : N-S, Direction2 : E-W

Note *2: Value in parentheses indicates the allowable stress of the steel plate.

Table 3G.1-53

Rebar and Concrete Stresses of RB: Selected Load Combination RB-8b

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable ² |
|------------------|------------|-----------------------|-----------|------------------------------------|------------|-------------------------|------------|------------------------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 ¹ | | Direction2 ¹ | | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 18 Wall | 6 | -8.0 | -29.3 | -2.1 | -2.6 | -7.3 | -42.4 | 372.2 |
| Below RCCV | 13 | -8.1 | -29.3 | -2.0 | -3.0 | -12.6 | -44.4 | 372.2 |
| Bottom | 24 | -6.6 | -29.3 | 0.3 | -1.1 | -20.8 | -39.3 | 372.2 |
| 19 Wall Below | 806 | -6.1 | -29.3 | 3.7 | 4.9 | -17.5 | -35.8 | 372.2 |
| Below RCCV | 813 | -6.7 | -29.3 | 2.4 | 4.1 | -20.5 | -39.5 | 372.2 |
| Mid-Height | 824 | -7.4 | -29.3 | 1.7 | 1.7 | -20.4 | -42.6 | 372.2 |
| 20 Wall | 1606 | -15.9 | -29.3 | 61.8 | 108.6 | -70.6 | 47.2 | 372.2 |
| Below RCCV | 1613 | -17.7 | -29.3 | 48.5 | 97.8 | -79.8 | 46.9 | 372.2 |
| Top | 1624 | -17.2 | -29.3 | 47.8 | 94.0 | -81.0 | 37.7 | 372.2 |
| 21 Exterior Wall | 20011 | -2.0 | -29.3 | 7.9 | 0.8 | 15.9 | -6.2 | 372.2 |
| @ EL-11.50 | 20023 | -5.0 | -29.1 | -23.8 | 0.7 | -16.9 | 9.6 | 370.5 |
| ~10.50m | 30010 | -1.3 | -29.3 | 8.4 | -4.2 | 9.6 | -3.0 | 372.2 |
| | 30020 | -2.2 | -29.3 | -6.1 | 4.3 | -6.1 | -12.3 | 372.2 |
| | 40001 | -2.0 | -29.3 | -3.9 | 2.1 | -6.9 | -11.2 | 372.2 |
| | 40011 | -0.9 | -29.3 | 0.8 | -3.0 | 2.5 | -4.3 | 372.2 |
| 22 Exterior Wall | 22011 | -0.8 | -29.3 | 71.5 | 75.6 | 32.6 | 25.2 | 372.2 |
| @ EL4.65 | 22023 | -3.2 | -29.3 | 35.4 | 3.9 | -16.0 | -16.9 | 372.2 |
| ~6.60m | 32010 | -2.6 | -29.3 | 53.6 | 113.2 | 1.5 | 75.8 | 372.2 |
| | 32020 | -3.2 | -29.3 | 9.7 | 21.8 | -8.2 | 39.8 | 372.2 |
| | 42001 | -1.0 | -29.3 | 21.5 | 4.8 | -7.3 | 5.6 | 372.2 |
| | 42011 | -2.7 | -29.3 | 27.1 | 89.8 | -7.2 | 21.3 | 372.2 |
| 23 Exterior Wall | 24211 | 0.0 | -29.3 | 81.9 | 75.8 | 69.2 | 36.3 | 372.2 |
| @ EL22.50 | 24224 | -2.3 | -29.3 | 45.4 | -2.6 | 21.8 | 10.6 | 372.2 |
| ~24.60m | 34210 | -0.1 | -29.3 | 132.0 | 190.1 | 27.9 | 101.3 | 372.2 |
| | 34220 | -2.0 | -29.3 | 66.2 | -28.8 | -7.9 | 44.1 | 372.2 |
| | 44201 | -0.4 | -29.3 | 64.2 | 2.1 | -7.8 | 46.8 | 372.2 |
| 24 Basemat | 90140 | -1.8 | -23.5 | -11.8 | -0.4 | -0.7 | -1.3 | 372.2 |
| @ Wall | 90182 | -1.8 | -23.5 | -9.6 | 2.8 | -1.3 | 8.3 | 372.2 |
| Below RCCV | 90111 | -2.4 | -23.5 | -15.1 | 4.3 | 0.5 | 3.7 | 372.2 |
| 25 Slab | 93140 | -9.6 | -29.3 | 132.1 | 90.2 | 211.5 | 98.6 | 372.2(223.3) |
| EL4.65m | 93182 | -17.5 | -29.3 | 87.1 | 67.9 | -85.8 | 73.1 | 372.2(223.3) |
| @ RCCV | 93111 | -16.3 | -29.3 | -76.7 | 83.8 | 87.3 | 68.8 | 372.2(223.3) |
| 26 Slab | 96144 | -10.0 | -29.3 | 249.9 | 104.3 | 338.1 | 129.5 | 372.2(223.3) |
| EL17.5m | 96186 | -8.7 | -29.3 | 181.1 | 91.1 | -38.4 | 11.1 | 372.2(223.3) |
| @ RCCV | 96113 | -14.5 | -28.8 | -87.8 | 16.0 | 92.3 | 120.1 | 368.2 |
| 27 Slab | 98472 | -10.3 | -27.6 | 10.4 | 60.6 | 64.4 | 44.9 | 359.4(215.6) |
| EL27.0m | 98514 | -13.7 | -27.6 | -20.7 | 70.7 | -20.3 | 74.0 | 359.4(215.6) |
| @ RCCV | 98424 | -11.4 | -28.1 | 72.8 | -55.4 | 90.8 | -8.2 | 363.0 |
| 28 Pool Girder | 123004 | -8.0 | -27.4 | 5.7 | 109.1 | -20.2 | 32.8 | 358.3 |
| @ Storage Pool | 123104 | -13.3 | -27.4 | 34.3 | 249.2 | 20.5 | 257.5 | 358.3 |
| 29 Pool Girder | 123012 | -8.2 | -27.4 | -12.6 | 96.0 | -3.7 | 67.9 | 358.3 |
| @ Cavity | 123112 | -8.4 | -27.4 | 9.7 | 147.7 | -6.0 | 136.8 | 358.3 |
| 30 Pool Girder | 123017 | -9.0 | -29.0 | 169.1 | 55.0 | 101.3 | -7.2 | 369.8 |
| @ Fuel Pool | 123117 | -6.9 | -29.0 | 124.5 | 18.4 | 106.7 | 2.1 | 369.8 |
| 31 MS Tunnel | 150122 | -10.3 | -29.3 | 151.2 | 5.7 | 125.7 | -19.5 | 372.2 |
| Wall and Slab | 96611 | -6.4 | -29.3 | -12.8 | 39.3 | -7.0 | 163.2 | 372.2 |
| | 98614 | -4.8 | -29.3 | 54.1 | -5.6 | 93.7 | -12.9 | 372.2 |

Note: Negative value means compression.

Note *1: Wall Below RCCV Direction1 : Hoop, Direction2 : Vertical
 Exterior Wall Direction1 : Horizontal, Direction2 : Vertical
 Slab Direction1 : N-S, Direction2 : E-W
 Pool Girder Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Wall Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Slab Direction1 : N-S, Direction2 : E-W

Note *2: Value in parentheses indicates the allowable stress of the steel plate.

Table 3G.1-54

Rebar and Concrete Stresses of RB: Selected Load Combination RB-9a

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable ² |
|---|------------|-----------------------|------------|------------------------------------|-------|------------------------|-------------------------|------------------------|
| | | Calculated | Allowable | Calculated | | Allowable ² | | |
| | | | | Direction1 ¹ | | | Direction2 ¹ | |
| In/Top | Out/Bottom | In/Top | Out/Bottom | | | | | |
| 18 Wall Below RCCV Bottom | 6 | -20.4 | -29.3 | 206.2 | 142.3 | 194.2 | 206.3 | 372.2 |
| | 13 | -17.0 | -29.3 | 173.2 | 122.2 | 217.0 | 147.3 | 372.2 |
| | 24 | -12.3 | -29.3 | 189.5 | 96.3 | 124.7 | 65.3 | 372.2 |
| 19 Wall Below Below RCCV Mid-Height | 806 | -10.3 | -29.3 | 162.5 | 97.1 | 163.7 | 113.7 | 372.2 |
| | 813 | -10.7 | -29.3 | 107.5 | 67.7 | 130.6 | 77.3 | 372.2 |
| | 824 | -11.6 | -29.3 | 166.7 | 81.6 | 138.7 | -69.4 | 372.2 |
| 20 Wall Below RCCV Top | 1606 | -20.7 | -29.3 | 185.6 | 214.1 | -89.3 | 290.9 | 372.2 |
| | 1613 | -22.4 | -29.3 | 97.1 | 178.1 | -99.0 | 280.9 | 372.2 |
| | 1624 | -21.2 | -29.3 | 168.7 | 240.1 | -99.1 | 269.8 | 372.2 |
| 21 Exterior Wall @ EL-11.50 ~10.50m | 20011 | -21.9 | -29.3 | 257.5 | 229.6 | 312.0 | 331.6 | 372.2 |
| | 20023 | -8.5 | -29.1 | -29.8 | 62.8 | 57.0 | 125.4 | 370.5 |
| | 30010 | -10.5 | -29.3 | 198.5 | 149.2 | 278.2 | 211.3 | 372.2 |
| | 30020 | -4.4 | -29.3 | -30.5 | 47.1 | 76.1 | 49.8 | 372.2 |
| | 40001 | -5.4 | -29.3 | 47.2 | 55.3 | 118.8 | 76.4 | 372.2 |
| 22 Exterior Wall @ EL4.65 ~6.60m | 22011 | -12.5 | -29.3 | 246.7 | 245.8 | 293.1 | 322.8 | 372.2 |
| | 22023 | -9.7 | -29.3 | 135.7 | 81.9 | 154.2 | 168.8 | 372.2 |
| | 32010 | -11.3 | -29.3 | 275.3 | 310.6 | 221.2 | 285.6 | 372.2 |
| | 32020 | -7.1 | -29.3 | 142.8 | 189.1 | 149.6 | 250.6 | 372.2 |
| | 42001 | -7.7 | -29.3 | 106.8 | 146.8 | 133.1 | 189.4 | 372.2 |
| 23 Exterior Wall @ EL22.50 ~24.60m | 24211 | -8.9 | -29.3 | 242.3 | 245.0 | 279.8 | 246.6 | 372.2 |
| | 24224 | -8.6 | -29.3 | 171.9 | 200.1 | 247.9 | 351.8 | 372.2 |
| | 34210 | -7.9 | -29.3 | 294.9 | 316.5 | 244.0 | 244.6 | 372.2 |
| | 34220 | -4.9 | -29.3 | 152.5 | 119.2 | 137.3 | 190.2 | 372.2 |
| | 44201 | -7.2 | -29.3 | 187.9 | 124.1 | 153.4 | 177.1 | 372.2 |
| 24 Basemat @ Wall Below RCCV | 90140 | -9.6 | -23.5 | 124.5 | 129.9 | 173.6 | 112.1 | 372.2 |
| | 90182 | -14.1 | -23.5 | -116.9 | 139.6 | 196.6 | 108.8 | 372.2 |
| | 90111 | -5.6 | -23.5 | -88.4 | 125.7 | 115.0 | 126.5 | 372.2 |
| 25 Slab EL4.65m @ RCCV | 93140 | -9.3 | -29.3 | 242.4 | 92.4 | 173.3 | 74.5 | 372.2(223.3) |
| | 93182 | -18.3 | -29.3 | 103.6 | 55.8 | -84.5 | 92.7 | 372.2(223.3) |
| | 93111 | -14.6 | -29.3 | -71.7 | 68.5 | 68.3 | 51.0 | 372.2(223.3) |
| 26 Slab EL17.5m @ RCCV | 96144 | -12.0 | -29.3 | 280.7 | 101.6 | 312.0 | 120.4 | 372.2(223.3) |
| | 96186 | -10.5 | -29.3 | 175.5 | 84.3 | -59.5 | -24.8 | 372.2(223.3) |
| | 96113 | -19.9 | -28.8 | -115.9 | 80.2 | 113.0 | 158.9 | 368.2 |
| 27 Slab EL27.0m @ RCCV | 98472 | -11.4 | -29.1 | 159.1 | 41.2 | 223.9 | 38.2 | 370.3(222.2) |
| | 98514 | -7.2 | -29.1 | 38.0 | 44.4 | 31.9 | 24.6 | 370.3(222.2) |
| | 98424 | -14.0 | -28.1 | 229.7 | -63.2 | 201.2 | -33.9 | 363.0 |
| 28 Pool Girder @ Storage Pool | 123004 | -13.1 | -28.4 | -5.4 | -8.4 | -48.0 | -73.4 | 365.0 |
| | 123104 | -5.6 | -28.4 | 73.2 | 76.3 | 38.5 | 74.7 | 365.0 |
| 29 Pool Girder @ Cavity | 123012 | -2.6 | -28.4 | 52.6 | 57.2 | 36.8 | 41.6 | 365.0 |
| | 123112 | -2.3 | -28.4 | 64.7 | 55.7 | 43.6 | 40.9 | 365.0 |
| 30 Pool Girder @ Fuel Pool | 123017 | -12.8 | -29.0 | 181.6 | 53.2 | 232.9 | -61.9 | 369.8 |
| | 123117 | -8.3 | -29.0 | 118.3 | 22.9 | 109.0 | -27.1 | 369.8 |
| 31 MS Tunnel Wall and Slab | 150122 | -16.8 | -29.3 | 230.6 | 3.9 | 215.0 | -29.8 | 372.2 |
| | 96611 | -11.7 | -29.3 | -18.4 | 125.3 | -19.9 | 199.9 | 372.2 |
| | 98614 | -10.6 | -29.3 | 142.2 | -16.6 | 175.1 | -18.1 | 372.2 |

Note: Negative value means compression.

Note *1: Wall Below RCCV Direction1 : Hoop, Direction2 : Vertical
 Exterior Wall Direction1 : Horizontal, Direction2 : Vertical
 Slab Direction1 : N-S, Direction2 : E-W
 Pool Girder Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Wall Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Slab Direction1 : N-S, Direction2 : E-W

Note *2: Value in parentheses indicates the allowable stress of the steel plate.

Table 3G.1-55

Rebar and Concrete Stresses of RB: Selected Load Combination RB-9b

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable ² |
|---|------------|-----------------------|-----------|------------------------------------|------------|------------------------|-------------------------|------------------------|
| | | Calculated | Allowable | Calculated | | Allowable ² | | |
| | | | | Direction1 ¹ | | | Direction2 ¹ | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 18 Wall Below RCCV Bottom | 6 | -21.3 | -29.3 | 225.2 | 146.1 | 217.2 | 206.0 | 372.2 |
| | 13 | -18.4 | -29.3 | 184.7 | 112.1 | 237.0 | 129.0 | 372.2 |
| | 24 | -11.2 | -29.3 | 206.3 | 91.9 | 143.6 | 58.0 | 372.2 |
| 19 Wall Below Below RCCV Mid-Height | 806 | -11.1 | -29.3 | 173.1 | 99.6 | 176.7 | 117.5 | 372.2 |
| | 813 | -11.4 | -29.3 | 114.9 | 69.7 | 143.5 | 79.1 | 372.2 |
| | 824 | -12.1 | -29.3 | 176.3 | 83.0 | 152.3 | -71.4 | 372.2 |
| 20 Wall Below RCCV Top | 1606 | -22.9 | -29.3 | 209.1 | 236.1 | -96.8 | 305.9 | 372.2 |
| | 1613 | -25.0 | -29.3 | 107.5 | 197.3 | -107.3 | 303.2 | 372.2 |
| | 1624 | -23.6 | -29.3 | 183.8 | 265.9 | -106.3 | 294.3 | 372.2 |
| 21 Exterior Wall @ EL-11.50 ~10.50m | 20011 | -22.7 | -29.3 | 272.3 | 229.8 | 335.7 | 331.8 | 372.2 |
| | 20023 | -8.4 | -29.1 | -31.8 | 63.6 | 57.7 | 124.2 | 370.5 |
| | 30010 | -10.8 | -29.3 | 216.5 | 144.7 | 314.6 | 194.5 | 372.2 |
| | 30020 | -4.4 | -29.3 | -36.3 | 49.5 | 75.8 | 47.6 | 372.2 |
| | 40001 | -5.5 | -29.3 | 48.0 | 61.5 | 118.5 | 74.1 | 372.2 |
| 22 Exterior Wall @ EL4.65 ~6.60m | 40011 | -5.7 | -29.3 | 259.1 | 154.6 | 264.6 | 170.2 | 372.2 |
| | 22011 | -12.4 | -29.3 | 272.1 | 273.9 | 311.0 | 344.1 | 372.2 |
| | 22023 | -9.6 | -29.3 | 147.6 | 75.3 | 157.9 | 168.5 | 372.2 |
| | 32010 | -13.3 | -29.3 | 308.0 | 339.9 | 253.0 | 315.6 | 372.2 |
| | 32020 | -7.2 | -29.3 | 162.1 | 179.9 | 156.7 | 247.1 | 372.2 |
| 23 Exterior Wall @ EL22.50 ~24.60m | 42001 | -7.8 | -29.3 | 131.0 | 131.3 | 138.7 | 182.6 | 372.2 |
| | 42011 | -12.6 | -29.3 | 322.3 | 329.4 | 257.5 | 326.1 | 372.2 |
| | 24211 | -8.9 | -29.3 | 278.7 | 275.2 | 328.4 | 265.8 | 372.2 |
| | 24224 | -8.9 | -29.3 | 205.2 | 193.0 | 249.6 | 345.9 | 372.2 |
| | 34210 | -11.1 | -29.3 | 340.6 | 364.6 | 243.6 | 280.7 | 372.2 |
| 24 Basemat @ Wall Below RCCV | 34220 | -8.6 | -29.3 | 179.9 | 78.5 | 121.3 | 155.4 | 372.2 |
| | 44201 | -7.9 | -29.3 | 221.8 | 130.4 | 182.5 | 192.8 | 372.2 |
| | 90140 | -9.6 | -23.5 | 127.4 | 120.5 | 177.9 | 107.5 | 372.2 |
| 25 Slab EL4.65m @ RCCV | 90182 | -12.9 | -23.5 | -77.6 | 136.3 | 193.9 | 125.9 | 372.2 |
| | 90111 | -6.0 | -23.5 | -97.1 | 131.7 | 113.6 | 126.0 | 372.2 |
| | 93140 | -12.2 | -29.3 | 275.9 | 110.1 | 215.1 | 92.7 | 372.2(223.3) |
| 26 Slab EL17.5m @ RCCV | 93182 | -22.8 | -29.3 | 116.7 | 70.4 | -105.8 | 116.7 | 372.2(223.3) |
| | 93111 | -18.6 | -29.3 | -89.8 | 90.6 | 80.9 | 64.3 | 372.2(223.3) |
| | 96144 | -12.6 | -29.3 | 322.2 | 116.8 | 337.7 | 136.8 | 372.2(223.3) |
| 27 Slab EL27.0m @ RCCV | 96186 | -12.8 | -29.3 | 217.7 | 105.3 | -69.3 | 30.3 | 372.2(223.3) |
| | 96113 | -17.4 | -28.8 | -112.6 | 67.7 | 133.2 | 158.0 | 368.2 |
| | 98472 | -13.6 | -27.6 | 50.2 | 91.2 | 114.6 | 71.0 | 359.4(215.6) |
| 28 Pool Girder @ Storage Pool | 98514 | -16.6 | -27.6 | -26.4 | 76.2 | -27.2 | 91.8 | 359.4(215.6) |
| | 98424 | -15.4 | -28.1 | 296.1 | -66.4 | 276.3 | 80.1 | 363.0 |
| | 123004 | -10.5 | -27.4 | 15.5 | 166.0 | -59.1 | 156.0 | 358.3 |
| 29 Pool Girder @ Cavity | 123104 | -14.5 | -27.4 | 43.5 | 248.7 | 28.4 | 263.9 | 358.3 |
| | 123012 | -10.4 | -27.4 | -21.0 | 169.0 | -6.5 | 153.0 | 358.3 |
| 30 Pool Girder @ Fuel Pool | 123112 | -9.6 | -27.4 | 20.9 | 191.0 | -7.8 | 197.1 | 358.3 |
| | 123017 | -12.7 | -29.0 | 246.2 | 97.9 | 261.4 | 110.4 | 369.8 |
| 31 MS Tunnel Wall and Slab | 123117 | -8.0 | -29.0 | 149.2 | 38.1 | 134.6 | -27.6 | 369.8 |
| | 150122 | -15.8 | -29.3 | 216.3 | 8.1 | 201.3 | -30.7 | 372.2 |
| | 96611 | -11.8 | -29.3 | -18.5 | 121.4 | -17.3 | 223.1 | 372.2 |
| | 98614 | -11.5 | -29.3 | 158.7 | -13.7 | 191.6 | -21.0 | 372.2 |

Note: Negative value means compression.
 Note *1: Wall Below RCCV Direction1 : Hoop, Direction2 : Vertical
 Exterior Wall Direction1 : Horizontal, Direction2 : Vertical
 Slab Direction1 : N-S, Direction2 : E-W
 Pool Girder Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Wall Direction1 : Horizontal, Direction2 : Vertical
 MS Tunnel Slab Direction1 : N-S, Direction2 : E-W
 Note *2: Value in parentheses indicates the allowable stress of the steel plate.

Table 3G.1-56
Transverse Shear of RB

| Location | Element ID | Load ID | d (m) | pv (%) | Shear Force (MN/m) | | | | Vu/φVn |
|--|------------|---------|-------|--------|--------------------|------|-------|-------|--------|
| | | | | | Vu | Vc | Vs | φVn | |
| 18 Wall Below RCCV Bottom | 6 | RB-9a | 1.59 | 0.721 | 1.64 | 0.49 | 4.74 | 4.44 | 0.369 |
| | 13 | RB-9a | 1.59 | 0.721 | 1.72 | 1.16 | 4.73 | 5.00 | 0.343 |
| | 24 | RB-8b | 1.57 | 0.721 | 0.27 | 4.25 | 4.68 | 7.60 | 0.036 |
| 19 Wall Below Below RCCV Mid-Height | 806 | RB-8b | 1.57 | 0.270 | 0.16 | 3.89 | 1.75 | 4.80 | 0.034 |
| | 813 | RB-8b | 1.57 | 0.270 | 0.69 | 4.21 | 1.75 | 5.07 | 0.135 |
| | 824 | RB-8b | 1.57 | 0.270 | 0.74 | 4.28 | 1.75 | 5.13 | 0.145 |
| 20 Wall Below RCCV Top | 1606 | RB-9b | 1.57 | 0.540 | 3.97 | 2.38 | 3.50 | 4.99 | 0.796 |
| | 1613 | RB-9b | 1.57 | 0.540 | 4.57 | 2.58 | 3.50 | 5.17 | 0.884 |
| | 1624 | RB-9b | 1.57 | 0.540 | 4.70 | 2.47 | 3.50 | 5.07 | 0.926 |
| 21 Exterior Wall @ EL-11.50 ~-10.50m | 20011 | RB-9b | 1.59 | 0.484 | 3.59 | 1.82 | 3.18 | 4.25 | 0.845 |
| | 20023 | RB-9a | 1.64 | 0.484 | 2.88 | 3.20 | 3.28 | 5.50 | 0.523 |
| | 30010 | RB-9a | 1.65 | 0.177 | 2.03 | 1.46 | 1.21 | 2.27 | 0.898 |
| | 30020 | RB-4 | 1.72 | 0.177 | 0.29 | 3.22 | 1.26 | 3.80 | 0.077 |
| | 40001 | RB-4 | 1.73 | 0.177 | 0.46 | 3.32 | 1.27 | 3.90 | 0.119 |
| | 40011 | RB-9a | 1.72 | 0.177 | 1.89 | 1.38 | 1.26 | 2.24 | 0.845 |
| 22 Exterior Wall @ EL4.65 ~-6.60m | 22011 | RB-9a | 1.19 | 0.484 | 0.64 | 0.00 | 2.38 | 2.02 | 0.316 |
| | 22023 | RB-4 | 1.21 | 0.484 | 0.17 | 2.14 | 2.42 | 3.88 | 0.043 |
| | 32010 | RB-9a | 1.24 | 0.177 | 0.21 | 0.00 | 0.91 | 0.77 | 0.268 |
| | 32020 | RB-9b | 1.26 | 0.177 | 1.24 | 1.18 | 0.92 | 1.78 | 0.698 |
| | 42001 | RB-9b | 1.25 | 0.242 | 0.91 | 0.61 | 1.26 | 1.59 | 0.575 |
| | 42011 | RB-9a | 1.20 | 0.242 | 0.14 | 0.00 | 1.21 | 1.02 | 0.141 |
| 23 Exterior Wall @ EL22.50 ~-24.60m | 24211 | RB-9b | 1.15 | 0.484 | 1.20 | 0.81 | 2.31 | 2.65 | 0.452 |
| | 24224 | RB-9b | 1.19 | 0.968 | 2.20 | 0.29 | 4.64 | 4.19 | 0.526 |
| | 34210 | RB-9a | 1.24 | 0.177 | 0.29 | 0.00 | 0.91 | 0.77 | 0.370 |
| | 34220 | RB-9b | 1.26 | 0.710 | 2.48 | 0.57 | 3.69 | 3.62 | 0.687 |
| | 44201 | RB-9b | 1.26 | 0.968 | 3.02 | 0.76 | 4.89 | 4.80 | 0.630 |
| 24 Basemat @ Wall Below RCCV | 90140 | RB-9b | 3.49 | 1.610 | 12.03 | 5.22 | 12.18 | 14.79 | 0.813 |
| | 90182 | RB-9b | 3.47 | 1.610 | 7.75 | 5.22 | 12.12 | 14.73 | 0.526 |
| | 90111 | RB-9b | 3.49 | 1.610 | 4.77 | 3.03 | 12.16 | 12.92 | 0.369 |
| 25 Slab EL4.65m @ RCCV | 93140 | RB-8a | 1.00 | 0.500 | 0.16 | 2.22 | 2.07 | 3.65 | 0.045 |
| | 93182 | RB-9b | 1.00 | 0.500 | 2.59 | 1.59 | 2.07 | 3.11 | 0.834 |
| | 93111 | RB-9b | 1.00 | 0.500 | 1.84 | 1.52 | 2.07 | 3.05 | 0.603 |
| 26 Slab EL17.5m @ RCCV | 96144 | RB-8b | 1.00 | 0.500 | 0.17 | 2.51 | 2.07 | 3.89 | 0.045 |
| | 96186 | RB-8b | 1.00 | 0.500 | 0.69 | 2.69 | 2.07 | 4.04 | 0.170 |
| | 96113 | RB-8a | 1.34 | 0.500 | 1.22 | 3.50 | 2.76 | 5.32 | 0.229 |
| 27 Slab EL27.0m @ RCCV | 98472 | RB-8a | 0.62 | 0.500 | 0.95 | 1.50 | 1.27 | 2.36 | 0.405 |
| | 98514 | RB-9a | 0.62 | 0.500 | 1.23 | 1.29 | 1.27 | 2.18 | 0.566 |
| | 98424 | RB-9b | 1.95 | 0.500 | 6.24 | 4.82 | 4.04 | 7.53 | 0.829 |
| 28 Pool Girder @ Storage Pool | 123004 | RB-9b | 1.18 | 0.968 | 3.36 | 3.02 | 4.58 | 6.47 | 0.519 |
| | 123104 | RB-8b | 1.21 | 0.484 | 1.02 | 1.43 | 2.43 | 3.28 | 0.310 |
| 29 Pool Girder @ Cavity | 123012 | RB-9b | 1.33 | 0.242 | 1.54 | 1.25 | 1.33 | 2.19 | 0.703 |
| | 123112 | RB-8a | 1.27 | 0.242 | 0.06 | 2.20 | 1.27 | 2.96 | 0.021 |
| 30 Pool Girder @ Fuel Pool | 123017 | RB-9b | 1.24 | 0.968 | 0.54 | 0.61 | 4.84 | 4.64 | 0.117 |
| | 123117 | RB-8a | 1.24 | 0.484 | 0.29 | 1.17 | 2.47 | 3.10 | 0.095 |
| 31 MS Tunnel Wall and Slab | 150122 | RB-8a | 1.08 | 0.177 | 0.17 | 0.20 | 0.79 | 0.84 | 0.206 |
| | 96611 | RB-8a | 1.34 | 0.500 | 0.50 | 1.46 | 2.76 | 3.59 | 0.138 |
| | 98614 | RB-9a | 1.95 | 0.500 | 1.91 | 1.79 | 4.04 | 4.95 | 0.385 |

Table 3G.1-57**Factors of Safety for Foundation Stability**

| Load Combination | Overturning | | Sliding | | Floatation | |
|-----------------------------|--------------------|--------|----------------|--------|-------------------|--------|
| | Required | Actual | Required | Actual | Required | Actual |
| D + H + E' | 1.1 | 344.2 | 1.1 | 1.11 | -- | -- |
| D + F' | -- | -- | -- | -- | 1.1 | 3.48 |

Where,

D = Dead Load

H = Lateral soil pressure

E' = Safe Shutdown Earthquake

F' = Buoyant forces of design basis flood

Table 3G.1-58**Maximum Soil Bearing Stress Involving SSE**

| | Site Condition* | | |
|----------------------|------------------------|--------|------|
| | Soft | Medium | Hard |
| Bearing Stress (MPa) | 2.35 | 5.15 | 5.33 |

* See Table 3A.1-2 for site properties.

Figure 3G.1-1. RB and FB Concrete Outline Plan at EL -11500

Figure 3G.1-2. RB and FB Concrete Outline Plan at EL 4650


Figure 3G.1-3. RB and FB Concrete Outline Plan at EL 17500

Figure 3G.1-4. RB and FB Concrete Outline Plan at EL 27000


Figure 3G.1-5. RB Concrete Outline Plan at EL 34000

Figure 3G.1-6. RB and FB Concrete Outline N-S Section

Figure 3G.1-7. RB and FB Concrete Outline E-W Section



Whole View



Cut View

Figure 3G.1-8. FE Model of RB/FB (Isometric View)




Figure 3G.1-9. FE Model of RB/FB (Foundation Mat)




Figure 3G.1-10. FE Model of RB/FB (RCCV Wall)




Figure 3G.1-11. FE Model of RB/FB (RPV Pedestal)




Figure 3G.1-12. FE Model of RB/FB (Top Slab)




Figure 3G.1-13. FE Model of RB/FB (Suppression Pool Slab)




Figure 3G.1-14. FE Model of RB/FB (External Wall: North Side)

RA RB RC RD RE RF RG




Figure 3G.1-15. FE Model of RB/FB (External Wall: East Side)






Figure 3G.1-16. FE Model of RB/FB (Internal Wall on R7/F1 Column Line)




Whole View




Cut View

Figure 3G.1-17. FE Model of RB/FB (RCCV Internals)



Whole View



Cut View

Figure 3G.1-18. FE Model of RB/FB (RCCV Liner)




Figure 3G.1-19. Soil Pressure at Rest






Figure 3G.1-20. Sections Where Temperature Loads Are Defined




CO Peak Positive Pressure = 186 kPag
 CO Peak Negative Pressure = -186 kPag
 Dynamic Load Factor (DLF) = 2.0

Figure 3G.1-21. Condensation Oscillation (CO) Pressure Loads



CHUG Peak Positive Pressure = 91 kPag
 CHUG Peak Negative Pressure = -66 kPag
 Dynamic Load Factor (DLF) = 2.0

Figure 3G.1-22. Chugging (CHUG) Pressure Loads



SRV Peak Positive Pressure = 152 kPag
 SRV Peak Negative Pressure = -63 kPag
 Dynamic Load Factor (DLF) = 2.0

Figure 3G.1-23. Safety Relief Valve (SRV) Pressure Loads




Figure 3G.1-24. Design Seismic Shears and Moments for RB and FB Walls




Figure 3G.1-25. Design Seismic Shears and Moments for RCCV




Figure 3G.1-26. Design Seismic Shears and Moments for RPV Pedestal and Vent Wall




Figure 3G.1-27. Seismic Lateral Soil Pressure






Figure 3G.1-28. Section Considered for Analysis



Membrane and Shear Forces



Moments

Definition of Element Coordinate System

| Structure | x | y | z |
|--|--------------|-----------------|--------------|
| RCCV Wall RPV Pedestal External Wall | horizontal | vertical | outward |
| Wall in N-S Direction | horizontal | vertical | toward West |
| Wall in E-W Direction | horizontal | vertical | toward South |
| Foundation Mat Floor Slab Top Slab | toward South | toward West | downward |
| Suppression Pool Slab | radial | circumferential | downward |

Figure 3G.1-29. Force and Moment in Shell Element




Figure 3G.1-30. Section Deformation for Dead Load




Figure 3G.1-31. Section Deformation for Drywell Unit Pressure (1 MPa)




Figure 3G.1-32. Section Deformation for Wetwell Unit Pressure (1 MPa)




Figure 3G.1-33. Section Deformation for Temperature Load (Normal Operation: Winter)




Figure 3G.1-34. Section Deformation for Temperature Load (LOCA After 6 min.: Winter)




Figure 3G.1-35. Section Deformation for Temperature Load (LOCA After 72 hr.: Winter)




Figure 3G.1-36. Section Deformation for Seismic Load (Horizontal: North to South)




Figure 3G.1-37. Section Deformation for Seismic Load (Horizontal: East to West)





Figure 3G.1-38. Section Deformation for Seismic Load (Vertical: Upward)



*: Thermal section forces are reduced using the section design calculation program, SSDP-2D, with thermal cracking option selected. However, for the LOCA thermal loads, “thermal ratios” obtained by 3D nonlinear analyses are multiplied to the section forces obtained by linear stress analyses. The section forces from the non-linear analyses can also be used directly. Thermal cracking option of SSDP-2D is not used together with 3D non-linear analyses. (Refer to Subsections 3.8.1.4.1.2 and 3.8.1.4.1.3.)

Figure 3G.1-39. Flow Chart for Structural Analysis and Design




Figure 3G.1-40. Reinforcing Steel of Foundation Mat: Plan







Figure 3G.1-41. Reinforcing Steel of Foundation Mat: Section A-A




RCCV WALL BARS - SECTION



PARTIAL PLAN EL 17500



PARTIAL PLAN EL 12000



PARTIAL PLAN EL 4650



NOTES

1. POSITIONS OF REBARS MAY BE ADJUSTED LOCALLY AS NECESSARY TO AVOID INTERFERENCES WITH EMBEDMENTS.

LEGEND





- (1) TIP END OF REBAR
- : TIP END OF PARTIAL BARS IN THE SAME LAYER
- : W/ TERMINATOR
- (2) Ld : DEVELOPMENT LENGTH

Figure 3G.1-42. Reinforcing Steel of RCCV Wall



LEGEND
 (1) TIP END OF REBAR
 — : W/ TERMINATOR
 (2) Ld : DEVELOPMENT LENGTH

Figure 3G.1-43. Reinforcing Steel of Suppression Pool Slab



| SYMBOLS | SHEAR TIES | SYMBOLS | SHEAR TIES |
|---------|------------|---------|------------|
| | #9@600x600 | | #9@300x300 |
| | #9@300x600 | | |



LEGEND

(1) TIP END OF REBAR


— : W/ TERMINATOR

(2) Ld : DEVELOPMENT LENGTH

Figure 3G.1-44. Reinforcing Steel of Top Slab



PARTIAL PLAN EL -1000



PARTIAL PLAN EL -11500


LEGEND
 (1) TIP END OF REBAR
 : W/ TERMINATOR

Figure 3G.1-45. Reinforcing Steel of RPV Pedestal






Figure 3G.1-46. Reinforcing Steel of IC/PCCS Pool Girder


| RB SEISMIC WALLS REINFORCING SCHEDULE EL-11500 ~ EL34000 | | | | |
|--|-----------|------------------------------|------------------------------|------------------------------|
| ELEVATION | TYPE | OW1 | | |
| | EL 34000 | SECTION | | |
| | VERT BAR | 2-#11 @200 (EF) | | |
| | HORIZ BAR | 2-#11 @200 (EF) | | |
| | SHEAR TIE | #5 @400x400 | | |
| EL 27000 | TYPE | OW1 | OW2 | OW3 |
| | SECTION | | | |
| | VERT BAR | 3-#11@200(OUT) 2-#11@200(IN) | 4-#11@200(OUT) 3-#11@200(IN) | 6-#11@200(OUT) 3-#11@200(IN) |
| | HORIZ BAR | 3-#11@200(OUT) 2-#11@200(IN) | 4-#11@200(OUT) 3-#11@200(IN) | 6-#11@200(OUT) 3-#11@200(IN) |
| | SHEAR TIE | #6 @400x400 | #7 @400x200 | #7 @400x200 |
| EL 17500 EL 4650 | TYPE | OW1 | OW2 | OW3 |
| | SECTION | | | |
| | VERT BAR | 3-#11 @200 (EF) | 4-#11@200(OUT) 3-#11@200(IN) | 4-#11 @200 (EF) |
| | HORIZ BAR | 3-#11 @200 (EF) | 4-#11@200(OUT) 3-#11@200(IN) | 3-#11@200+1-#11@400 (EF) |
| | SHEAR TIE | #6 @400x400 | #7 @400x400 | #7 @400x200 |
| EL -1000 EL -11500 | TYPE | OW1 | OW2 | OW3 |
| | SECTION | | | |
| | VERT BAR | 4-#11 @200 (EF) | 3-#11 @200 (EF) | 5-#11 @200 (EF) |
| | HORIZ BAR | 3-#11@200+1-#11@400 (EF) | 3-#11 @200 (EF) | 4-#11@200+1-#11@400 (EF) |
| | SHEAR TIE | #6 @400x400 | #6 @400x400 | #7 @400x200 |




FLOOR EL 34000



FLOOR EL 27000




FLOOR EL 4650



FLOOR EL -11500

KEY PLAN FOR WALL TYPE

| MS TUNNEL WALL REINFORCING SCHEDULE | | |
|-------------------------------------|-----------|--|
| ELEVATION | TYPE | MW |
| | EL 17500 | SECTION |
| | VERT BAR | 2-#11 @200(IN) 2-#11@200+1-#11@400(OUT) |
| | HORIZ BAR | 2-#11 @200(IN) 2-#11@200+1-#11@400(OUT) |
| | SHEAR TIE | #6 @400x400 |



FLOOR EL 17500

KEY PLAN FOR MS WALL

| SLAB REINFORCING SCHEDULE | | | |
|---------------------------|-----------|-----------------|----------------------|
| ELEVATION | SECTION | REINFORCING | |
| | | EL 27000 | |
| | TOP | 3-#11 @200 (EW) | 4-#11 @200 (EW) |
| | BOTTOM | PLATE t=25 | 3-#11 @200 (EW) |
| | SHEAR TIE | #5 @200x200 | #5 @200x200 |
| EL 17500 | SECTION | | (MS TUNNEL SLAB) |
| | | TOP | 2-#11 @200 (EW) |
| | BOTTOM | PLATE t=16 | 3-#11 @200 (EW) |
| | SHEAR TIE | #5 @200x200 | #5 @200x200 |
| EL 4650 | SECTION | | |
| | | TOP | 2-#11 @200 (EW) |
| | BOTTOM | PLATE t=16 | |
| | SHEAR TIE | #5 @200x200 | |

Figure 3G.1-47. List of RB Wall and Slab Reinforcement




Figure 3G.1-48. Liner Anchor





Figure 3G.1-49. Liner Plate Plans



Note: These are "major" penetrations only.

Figure 3G.1-50. Liner Plate Development Elevation




Figure 3G.1-51. Drywell Head

Figure 3G.1-52. Equipment Hatch

Figure 3G.1-53. Wetwell Hatch

Figure 3G.1-54. Personnel Airlock




Figure 3G.1-55. Diaphragm Floor

D/F SLAB ANCHORS AT TOP PLATE AS SHOWN
D/F SLAB ANCHORS AT BOTTOM PLATE SIMILAR PLAN
(TYPICAL 45° SECTION FROM 157.5' TO 202.5') (1:50)

D/F SLAB ANCHORS AT BEAM BOTTOM FLANGES PLAN (B-B) (1:50)




Figure 3G.1-56. Diaphragm Floor Slab Anchor





Figure 3G.1-58. Reactor Shield Wall



Note : Positions of anchors may be adjusted locally as necessary to avoid interference with rebars.

Figure 3G.1-59. GDCS Pool

3G.2 CONTROL BUILDING

3G.2.1 Objective and Scope

The objective of this subsection is to document the structural design details, inputs and analytical results from the analysis the Control Building (CB) of the standard ESBWR plant. The scope includes the design and analysis of the structure for normal, severe environmental, extreme environmental, and construction loads.

3G.2.2 Conclusions

The following are the major summary conclusions on the design and analysis of the CB.

- Based on the results of finite element analyses performed in accordance with the design conditions identified in Subsection 3G.2.3, stresses in concrete and reinforcement are less than the allowable stresses per the applicable regulations, codes or standards listed in Section 3.8.
- The factors of safety against floatation, sliding, and overturning of the structure under various loading combinations are higher than the required minimum.
- The thickness of the roof slabs and exterior walls are more than the minimum required to preclude penetration, perforation or spalling resulting from impact of design basis tornado missiles.

3G.2.3 Structural Description

The CB houses the essential electrical, control and instrumentation equipment, the control room for the Reactor and Turbine Buildings, and the CB HVAC equipment. Structure below grade in the CB is a Seismic Category I structure that houses control equipment and operation personnel. Structure above grade is a Seismic Category II structure.

The CB is a reinforced concrete box type shear wall structure consisting of walls and slabs and is supported by a foundation mat. Steel framing is composite with concrete slab and used to support the slabs for vertical loads. The CB is a shear wall structure designed to accommodate all seismic loads with its walls and the connected floors. Therefore, frame members such as beams or columns are designed to accommodate deformations of the walls in case of earthquake conditions. The CB is adjacent to but structurally independent of the Reactor Building (see Figures 1.2-2 through 1.2-5 and Figure 1.2-11).

The key dimensions of the CB are summarized in Table 3.8-8. Figures 3G.2-1 through 3G.2-3 show the outline drawings of the CB.

3G.2.4 Analytical Models

3G.2.4.1 Structural Model

The CB is analyzed utilizing the finite element computer program NASTRAN. The finite element model consists of quadrilateral and beam elements. The quadrilateral elements are used to represent the slabs and walls. Beam elements are used to represent columns and beams. The

model is shown in Figures 3G.2-4 to 3G.2-9. The model includes the whole (360°) portion of the CB taking the application of nonaxisymmetrical loads into consideration.

The penthouse structure, which is located above EL 9060 mm, is Seismic Category II, and is not included in the analysis model. The weight of the penthouse is applied as distributed loads in the dead load analysis.

The nodal points are defined by a right hand Cartesian coordinate system X, Y, Z. This system, called the global coordinate system, has its origin located at the north-west corner of the CB at EL 0 mm. The positive X axis is in the south direction; the Y axis is in the east direction; the Z axis is vertical upward. This coordinate system is shown in Figure 3G.2-4.

3G.2.4.2 Foundation Models

The foundation soil is represented by soil springs. The spring constants for rocking and translations are determined based on the following soil parameters which correspond to the Soft Site conditions described in Appendix 3A:

- Shear wave velocity: 300 m/s
- Unit weight: 0.0196 MN/m³ (2.00 t/m³)
- Shear modulus: 180 MN/m² (1.835 x 10⁴ t/m²)
- Poisson's Ratio: 0.478

Soil springs are attached to the bottom of the foundation mat, and the constraints by side soil are not included in the model. The values of the soil springs used in the analysis are shown in Table 3G.2-1. The springs have perfectly elastic stiffness.

These spring values are multiplied by the foundation mat nodal point tributary areas to compute the spring constants assigned to the base slab nodal points.

3G.2.5 Structural Analysis and Design

3G.2.5.1 Site Design Parameters

The key site design parameters are described in Subsection 3G.1.5.1.

3G.2.5.2 Design Loads, Load Combinations, and Material Properties

3G.2.5.2.1 Design Loads

3G.2.5.2.1.1 Dead Load (D) and Live Load (L and Lo)

The weights of structures are evaluated using the following unit weights.

- reinforced concrete: 23.5 kN/m³
- steel: 77.0 kN/m³

Weights of major equipment, miscellaneous structures, piping, and commodities are summarized in Tables 3G.2-2 and 3G.2-3.

Live loads on the CB floor slabs are described in Subsection 3.8.4.3.2.

3G.2.5.2.1.2 Snow Load

The snow load is applied to the roof slab and is taken as shown in Table 3G.1-2. Snow load is reduced to 75% when snow load is combined with seismic loads.

3G.2.5.2.1.3 Lateral Soil Pressure at Rest

The lateral soil pressure at rest is applied to the external walls below grade and is based on soil properties given in Table 3G.1-2. Pressures to be applied to the walls are provided in Figure 3G.2-10.

3G.2.5.2.1.4 Wind Load (W)

Wind load is applied to the roof slab and external walls above grade and is based on basic wind speed given in Table 3G.1-2.

3G.2.5.2.1.5 Tornado Load (W_t)

The tornado load is applied to the roof slab and external walls above grade and its characteristics are given in Table 3G.1-2. The tornado load, W_t , is further defined by the combinations described in Subsection 3G.1.5.2.1.5.

3G.2.5.2.1.6 Thermal Load (T_o and T_a)

Thermal loads for the CB are evaluated for the normal operating conditions and abnormal (LOCA) conditions. Figure 3G.2-11 shows the section location for temperature distributions for various structural elements of the CB, and Table 3G.2-4 shows the magnitude of equivalent linear temperature distribution.

Stress-free temperature is 15.5°C.

3G.2.5.2.1.7 Design Seismic Loads

The design seismic loads are obtained by soil – structure interaction analyses, which are described in Appendix 3A. The seismic loads used for design are as follows:

- Figure 3G.2-12: design seismic shears and moments
- Table 3G.2-5: maximum vertical acceleration

The seismic loads are composed of two perpendicular horizontal and one vertical components. The effects of the three components are combined based on the 100/40/40 method as described in Subsection 3.8.1.3.6.

Seismic lateral soil pressure for wall design is provided in Figure 3G.2-13 using the elastic procedure described in ASCE 4-98 Section 3.5.3.2.

3G.2.5.2.2 Load Combinations and Acceptance Criteria

Table 3.8-15 gives load combinations for the safety-related reinforced concrete structure. Based on previous experience, critical load combinations are selected for the CB design. They are mainly combinations including LOCA loads and seismic loads as shown in Table 3G.2-6. The acceptance criteria for the selected combinations are also included in Table 3G.2-6.

3G.2.5.2.3 Material Properties

Properties of the materials used for the CB design analyses are the same as those for the RB, and they are described in Subsection 3G.1.5.2.3.

3G.2.5.3 Stability Requirements

The stability requirements for the CB foundation are same as those for the RB, and they are described in Subsection 3G.1.5.3.

3G.2.5.4 Structural Design Evaluation

The evaluation of the Seismic Category I structures in the CB is performed using the same procedure as the RB, which is described in Subsection 3G.1.5.4.

The locations of the sections that are selected for evaluation are indicated in Figures 3G.2-5 through 9. They are selected, in principle, from the center and both ends of wall and slab, where it is reasonably expected that the critical stresses appear based on engineering experience and judgment. Tables 3G.2-7 through 3G.2-11 show the forces and moments at the selected sections from NASTRAN analysis. Element forces and moments listed in the tables are defined with relation to the element coordinate system shown in Figure 3G.2-14. Tables 3G.2-12 through 3G.2-14 show the combined forces and moments in accordance with the selected load combinations listed in Table 3G.2-6.

Table 3G.2-15 lists the sectional thicknesses and rebar ratios used in the evaluation. The values are retrieved from the outline drawings shown in Figures 3G.2-1 through 3G.2-3.

Tables 3G.2-16 through 3G.2-21 show the rebar and concrete stresses at these sections for the representative elements. Table 3G.2-22 summarizes evaluation results for transverse shear in accordance with ACI 349, Chapter 11.

3G.2.5.4.1 Shear Walls

The maximum rebar stress of 239.3 MPa is found in the vertical rebar in the wall at EL -7400 due to the load combination CB-9 as shown in Table 3G.2-21. The maximum horizontal rebar stress is found to be 189.1 MPa also in B2F wall due to the load combination CB-9. The maximum transverse shear force is found to be 0.687 MN/m against the shear strength of 1.227 MN/m in the wall at EL -2000.

3G.2.5.4.2 Floor Slabs

The maximum rebar stress of 180.2 MPa is found in the slab at EL 4650 due to the load combination CB-9 as shown in Table 3G.2-20. The maximum transverse shear force is found to be 0.295 MN/m against the shear strength of 0.519 MN/m.

3G.2.5.4.3 Foundation Mat

The maximum rebar stress is found to be 224.5 MPa due to the load combination CB-9 as shown in Table 3G.2-20. The maximum transverse shear force is found to be 1.030 MN/m against the shear strength of 3.969 MN/m.

3G.2.5.5 Foundation Stability

The stabilities of the CB foundation against overturning, sliding and floatation are evaluated. The energy approach is used in calculating the factor of safety against overturning.

The factors of safety against overturning, sliding and floatation are given in Table 3G.2-23. All of these meet the acceptance criteria given in Table 3.8-14.

Maximum soil bearing stress is found to be 256 kPa due to dead plus live loads. Maximum bearing stresses for load combinations involving SSE are shown in Table 3G.2-24 for various site conditions.

3G.2.5.6 Tornado Missile Evaluation

Because the Category I portions of the CB are located below grade as shown in Figure 3G.2-3, only the slab at EL 4650 is required the protection to a tornado missile. The minimum thickness required to prevent penetration and concrete spalling are evaluated. The methods and procedures are shown in Section 3.5.3.1.1. The minimum slab thickness required is less than the minimum 700 mm thickness provided for the CB slab at EL 4650.

**Table 3G.2-1
Soil Spring Constants for the CB Analysis Model**

| Direction of Spring | | Loads | Stiffness (MN/m/m²) |
|----------------------------|-------------|--------------------------|---|
| Horizontal | X-direction | All | 19.650 |
| | Y-direction | All | 20.378 |
| Vertical | | Horizontal Seismic Loads | 79.174 |
| | | Other Loads | 29.177 |

**Table 3G.2-2
Equipment Load of CB**

| Description | Weight | Remarks |
|----------------------|---------------|----------------|
| Division DCIS Room | 216 kN | per one room |
| MCR Display Consoles | 230 kN | |
| Non 1E DCIS Room | 490 kN | per one room |
| HVAC Units | 1079 kN | total |

**Table 3G.2-3
Miscellaneous Structures, Piping, and Commodity Load of CB**

| Elevation (mm) | Area Load |
|-----------------------|-------------------------------|
| 9,060 | 2.4 kN/m ² (50psf) |
| 4,650 | 2.4 kN/m ² (50psf) |
| -2,000 | 2.4 kN/m ² (50psf) |
| -7,400 | 2.4 kN/m ² (50psf) |

Table 3G.2-4

Equivalent Liner Temperature Distributions at Various Sections

| Section [*] 1 | Side ^{*2} | | Equivalent Linear Temperature ^{*3} (°C) | | | |
|---------------------------|--------------------|------|--|-----|------|-------|
| | | | Normal Operation | | DBA | |
| | 1 | 2 | Td | Tg | Td | Tg |
| W1 | MCR | GR | 17.7 | 4.4 | 21.3 | 11.5 |
| W2 | DCIS | GR | 17.7 | 4.4 | 29.2 | 27.4 |
| M1 | DCIS | GR | 18.1 | 5.1 | 31.5 | 32.0 |
| S1 | DCIS | MCR | 21.0 | 0.0 | 40.0 | 12.0 |
| S2 | MCR | DCIS | 21.0 | 0.0 | 40.0 | -10.3 |

Note *1: See Figure 3G.2-11 for the location of sections.

Note *2: MCR: Main Control Room, DCIS: Distributed Control and Information System, GR: Ground

Note *3: Td: Average Temperature,
Tg: Surface Temperature Difference (positive when temperature at Side 1 is higher)

Table 3G.2-5

Maximum Vertical Acceleration

| Walls | | | Slabs | | |
|--------------|-------------|-----------------------------------|--------------|-------------|-----------------------------------|
| Elev. (m) | Node No. | Max. Vertical Acceleration (g) | Elev. (m) | Node No. | Max. Vertical Acceleration (g) |
| 9.06 | 5 | 1.11 | 9.06 | 9101 | 1.01 |
| 4.65 | 4 | 0.92 | | 9102 | 1.51 |
| -2.00 | 3 | 0.62 | | 9103 | 2.89 |
| -7.40 | 2 | 0.47 | | 9104 | 2.93 |
| -10.40 | 1 | 0.47 | | 9105 | 2.62 |

See Figure 3A.7-5 for the node numbers.

Table 3G.2-6
Selected Load Combinations for the CB

| Category | Load Combination | | | | | | | | Acceptance Criteria* ¹ |
|----------------------|--------------------|-----|-----|----------------|----------------|-----|-----|----------------|--------------------------------------|
| | No. * ² | D | L | T _o | T _a | E' | W | W _t | |
| Severe Environmental | CB-3 | 1.4 | 1.7 | | | | 1.7 | | U |
| Tornado | CB-7 | 1.0 | 1.0 | 1.0 | | | | 1.0 | U |
| LOCA + SSE | CB-9 | 1.0 | 1.0 | | 1.0 | 1.0 | | | U |

*1: U = Required section strength based on the strength design method per ACI 349

*2: Based on Table 3.8-15.

Table 3G.2-7

Results of NASTRAN Analysis: Dead Load

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--------------------------|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| Basemat EL-7.4 | 67 | 0.031 | -0.740 | 0.023 | -0.881 | -1.011 | 0.066 | 0.209 | -0.215 |
| | 72 | -0.049 | 0.291 | -0.002 | -0.401 | -0.156 | 0.015 | -0.633 | -0.023 |
| | 115 | -0.761 | -0.256 | 0.261 | -0.246 | -0.157 | -0.302 | -0.058 | -0.584 |
| | 120 | -0.083 | 0.008 | -0.135 | -0.075 | -0.128 | 0.616 | -0.035 | 0.050 |
| Slab B1F EL-2.0 | 567 | -0.007 | 0.691 | -0.047 | -0.050 | -0.018 | -0.003 | -0.063 | 0.016 |
| | 572 | 0.092 | 0.117 | -0.014 | -0.021 | -0.011 | 0.002 | 0.076 | -0.006 |
| | 615 | 0.161 | 0.132 | -0.231 | -0.025 | -0.003 | 0.017 | -0.031 | -0.006 |
| | 620 | 0.034 | 0.037 | 0.045 | -0.014 | -0.017 | -0.019 | 0.021 | 0.025 |
| Slab 1F EL4.65 | 1067 | 0.084 | 0.096 | 0.000 | 0.207 | 0.110 | -0.012 | 0.037 | 0.019 |
| | 1072 | 0.001 | -0.019 | 0.002 | -0.062 | -0.014 | 0.002 | 0.084 | -0.002 |
| | 1115 | 0.249 | 0.063 | 0.093 | -0.018 | -0.174 | -0.022 | -0.001 | 0.159 |
| | 1120 | 0.027 | 0.006 | 0.038 | -0.025 | -0.026 | -0.024 | 0.016 | 0.025 |
| Wall EL-7.4m ~EL-2.0m | 6007 | -0.242 | -0.639 | -0.235 | -0.010 | 0.090 | -0.004 | -0.051 | 0.066 |
| | 4006 | 0.097 | -0.812 | -0.050 | -0.042 | -0.206 | -0.001 | 0.001 | -0.058 |
| | 4010 | 0.068 | -0.142 | -0.052 | 0.012 | -0.071 | -0.005 | -0.031 | -0.041 |
| Wall EL-2.0m ~EL4.65m | 6043 | 0.182 | -1.089 | -0.293 | 0.039 | 0.021 | 0.006 | 0.038 | -0.010 |
| | 4036 | 0.061 | -0.541 | -0.051 | 0.020 | 0.110 | 0.001 | -0.001 | 0.038 |
| | 4040 | -0.010 | -0.248 | 0.107 | -0.002 | 0.022 | 0.011 | 0.014 | 0.016 |

Table 3G.2-8

Results of NASTRAN Analysis: Temperature Load (LOCA: Winter)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--------------------------|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| Basemat EL-7.4 | 67 | -0.659 | -1.669 | 0.174 | 6.545 | 6.107 | -0.153 | 0.371 | -0.144 |
| | 72 | -0.273 | -0.342 | 0.023 | 1.970 | 5.689 | 0.040 | 0.144 | 0.088 |
| | 115 | -1.282 | -0.171 | 0.109 | 6.248 | 2.349 | -0.234 | 0.385 | 0.929 |
| | 120 | -1.011 | -0.921 | -0.608 | 3.338 | 3.354 | 2.200 | 1.174 | 1.295 |
| Slab B1F EL-2.0 | 567 | -0.739 | 0.490 | 0.042 | -0.073 | -0.091 | 0.002 | 0.001 | 0.004 |
| | 572 | 0.311 | -0.838 | -0.057 | -0.006 | -0.062 | 0.003 | -0.035 | 0.000 |
| | 615 | -0.814 | 0.635 | -0.748 | -0.081 | -0.030 | 0.005 | -0.032 | -0.080 |
| | 620 | -0.923 | -0.938 | -1.400 | -0.058 | -0.060 | 0.007 | 0.002 | 0.005 |
| Slab 1F EL4.65 | 1067 | -1.536 | -0.270 | -0.038 | 0.118 | 0.014 | 0.002 | 0.004 | -0.006 |
| | 1072 | -0.482 | -2.085 | -0.085 | 0.418 | 0.170 | 0.014 | -0.137 | 0.006 |
| | 1115 | -0.017 | 0.193 | 0.233 | 0.129 | 0.233 | 0.020 | -0.006 | -0.020 |
| | 1120 | -2.239 | -2.260 | -2.503 | 0.265 | 0.265 | -0.013 | -0.044 | -0.043 |
| Wall EL-7.4m ~EL-2.0m | 6007 | 0.338 | 1.553 | -0.208 | 0.638 | 0.905 | 0.002 | -0.036 | 0.159 |
| | 4006 | 0.710 | -0.086 | 0.026 | -0.707 | -1.171 | -0.001 | -0.001 | -0.221 |
| | 4010 | 1.106 | 0.968 | -0.456 | -0.526 | -0.930 | -0.043 | -0.184 | -0.372 |
| Wall EL-2.0m ~EL4.65m | 6043 | 3.009 | -0.382 | -0.764 | 0.387 | 0.511 | -0.026 | 0.137 | 0.106 |
| | 4036 | 2.363 | 0.048 | -0.085 | -0.282 | -0.293 | 0.002 | 0.031 | 0.030 |
| | 4040 | 1.333 | 0.159 | -0.800 | -0.094 | -0.285 | -0.026 | -0.200 | -0.181 |

Table 3G.2-9

Results of NASTRAN Analysis: Seismic Load (Horizontal: North to South Direction)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--------------------------|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| Basemat EL-7.4 | 67 | -0.116 | -0.109 | 0.139 | -0.407 | -0.294 | -0.209 | 0.656 | -0.020 |
| | 72 | -0.119 | -2.846 | 0.005 | -1.371 | -1.194 | 0.051 | -1.216 | -0.021 |
| | 115 | -0.136 | -0.061 | 1.667 | 0.057 | 0.013 | -1.892 | 0.842 | -0.138 |
| | 120 | 0.085 | -0.610 | 0.083 | -0.594 | -0.251 | 0.475 | 0.063 | -0.698 |
| Slab B1F EL-2.0 | 567 | 0.038 | 0.013 | 0.005 | 0.047 | 0.000 | -0.009 | 0.015 | -0.010 |
| | 572 | 0.087 | 0.101 | 0.000 | -0.001 | -0.006 | 0.000 | -0.005 | 0.002 |
| | 615 | 0.007 | 0.004 | -0.055 | 0.028 | 0.001 | 0.006 | 0.027 | 0.006 |
| | 620 | 0.103 | 0.063 | -0.001 | -0.011 | 0.015 | 0.000 | 0.014 | -0.017 |
| Slab 1F EL4.65 | 1067 | 0.039 | -0.015 | 0.070 | -0.010 | -0.010 | -0.006 | 0.015 | -0.001 |
| | 1072 | 0.264 | 0.496 | -0.036 | -0.008 | -0.016 | 0.001 | -0.009 | 0.001 |
| | 1115 | 0.342 | 0.051 | -0.417 | -0.022 | -0.001 | -0.006 | 0.011 | 0.004 |
| | 1120 | 0.179 | 0.105 | -0.011 | -0.025 | 0.022 | 0.004 | 0.028 | -0.029 |
| Wall EL-7.4m ~EL-2.0m | 6007 | 0.081 | -0.174 | 1.857 | -0.053 | 0.035 | -0.011 | -0.067 | 0.030 |
| | 4006 | -0.737 | -1.756 | -0.067 | 0.000 | -0.018 | -0.001 | 0.004 | -0.002 |
| | 4010 | -0.132 | -0.701 | -0.691 | 0.030 | 0.006 | -0.013 | 0.004 | -0.006 |
| Wall EL-2.0m ~EL4.65m | 6043 | -0.004 | 0.042 | 1.702 | -0.005 | -0.013 | 0.007 | 0.003 | -0.004 |
| | 4036 | 0.066 | -1.078 | -0.091 | -0.004 | -0.007 | -0.001 | -0.002 | -0.006 |
| | 4040 | -0.017 | -0.759 | -0.905 | -0.001 | 0.008 | -0.012 | -0.002 | -0.002 |

Table 3G.2-10

Results of NASTRAN Analysis: Seismic Load (Horizontal: East to West Direction)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--------------------------|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| Basemat EL-7.4 | 67 | -0.129 | 0.236 | -0.377 | -0.415 | -1.265 | -0.065 | -0.480 | 1.724 |
| | 72 | -0.010 | 0.055 | 1.512 | -0.045 | -0.105 | -1.531 | -0.085 | 0.661 |
| | 115 | -2.477 | -0.177 | -0.226 | -0.196 | -0.498 | 0.028 | 0.282 | -0.279 |
| | 120 | -0.611 | 0.212 | 0.150 | -0.182 | -0.471 | 0.001 | -0.801 | 0.150 |
| Slab B1F EL-2.0 | 567 | -0.005 | -0.050 | 0.387 | -0.017 | -0.050 | -0.010 | -0.012 | 0.091 |
| | 572 | 0.004 | 0.003 | 0.238 | 0.001 | 0.000 | -0.001 | -0.001 | -0.001 |
| | 615 | -0.205 | 0.179 | 0.378 | -0.004 | -0.026 | -0.002 | 0.007 | 0.026 |
| | 620 | 0.045 | 0.109 | 0.186 | 0.012 | -0.015 | -0.001 | -0.018 | 0.017 |
| Slab 1F EL4.65 | 1067 | 0.005 | 0.023 | -0.026 | -0.005 | -0.004 | -0.005 | -0.001 | 0.005 |
| | 1072 | 0.002 | 0.006 | -0.308 | 0.002 | 0.000 | -0.007 | -0.001 | -0.005 |
| | 1115 | 0.671 | 0.164 | 0.055 | -0.023 | -0.085 | 0.000 | 0.006 | 0.028 |
| | 1120 | 0.086 | 0.103 | -0.117 | 0.017 | -0.035 | 0.000 | -0.032 | 0.030 |
| Wall EL-7.4m ~EL-2.0m | 6007 | -0.863 | -0.595 | 0.061 | -0.013 | -0.037 | -0.003 | 0.016 | -0.006 |
| | 4006 | 0.048 | -0.094 | 1.505 | -0.005 | -0.012 | 0.011 | 0.006 | -0.005 |
| | 4010 | 0.145 | -0.649 | 0.666 | -0.035 | -0.083 | 0.006 | -0.031 | -0.035 |
| Wall EL-2.0m ~EL4.65m | 6043 | -0.300 | 0.092 | 0.004 | -0.069 | -0.140 | 0.008 | -0.047 | -0.067 |
| | 4036 | 0.015 | -0.040 | 1.400 | 0.000 | 0.000 | -0.003 | -0.006 | 0.000 |
| | 4040 | 0.006 | -0.464 | 0.990 | -0.006 | 0.009 | 0.018 | 0.012 | 0.009 |

Table 3G.2-11

Results of NASTRAN Analysis: Seismic Load (Vertical: Downward Direction)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--------------------------|------------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| Basemat EL-7.4 | 67 | -0.028 | 0.625 | -0.019 | 0.851 | 0.873 | -0.060 | -0.146 | 0.164 |
| | 72 | 0.044 | -0.208 | -0.002 | 0.330 | 0.132 | -0.006 | 0.512 | -0.002 |
| | 115 | 0.642 | 0.224 | -0.231 | 0.229 | 0.142 | 0.259 | 0.054 | 0.520 |
| | 120 | 0.065 | 0.000 | 0.112 | 0.064 | 0.114 | -0.511 | 0.029 | -0.025 |
| Slab B1F EL-2.0 | 567 | 0.002 | -0.598 | 0.039 | 0.043 | 0.013 | 0.002 | 0.045 | -0.012 |
| | 572 | -0.080 | -0.105 | 0.011 | 0.018 | 0.007 | -0.001 | -0.053 | 0.004 |
| | 615 | -0.145 | -0.121 | 0.199 | 0.018 | 0.000 | -0.012 | 0.023 | 0.009 |
| | 620 | -0.032 | -0.034 | -0.043 | 0.009 | 0.011 | 0.013 | -0.013 | -0.016 |
| Slab 1F EL4.65 | 1067 | -0.092 | -0.098 | 0.003 | -0.198 | -0.112 | 0.012 | -0.035 | -0.017 |
| | 1072 | -0.011 | -0.003 | 0.001 | 0.071 | 0.014 | -0.001 | -0.087 | 0.002 |
| | 1115 | -0.235 | -0.072 | -0.092 | 0.018 | 0.174 | 0.022 | 0.001 | -0.155 |
| | 1120 | -0.029 | -0.012 | -0.028 | 0.026 | 0.026 | 0.023 | -0.016 | -0.023 |
| Wall EL-7.4m ~EL-2.0m | 6007 | 0.201 | 0.576 | 0.202 | 0.008 | -0.077 | 0.003 | 0.044 | -0.058 |
| | 4006 | -0.070 | 0.712 | 0.021 | 0.033 | 0.168 | 0.000 | 0.000 | 0.049 |
| | 4010 | -0.055 | 0.136 | 0.053 | -0.010 | 0.060 | 0.004 | 0.025 | 0.035 |
| Wall EL-2.0m ~EL4.65m | 6043 | -0.154 | 1.017 | 0.252 | -0.034 | -0.018 | -0.005 | -0.033 | 0.012 |
| | 4036 | -0.053 | 0.540 | 0.032 | -0.016 | -0.087 | 0.000 | 0.001 | -0.033 |
| | 4040 | 0.009 | 0.251 | -0.083 | 0.001 | -0.017 | -0.007 | -0.011 | -0.013 |

Table 3G.2-12

Combined Forces and Moments: Selected Load Combination CB-3

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---------------------------------|------------|--------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| on Basemat EL-7.4 | 67 | OTHR | -2.301 | -3.420 | 0.064 | -1.171 | -0.629 | 0.026 | 0.313 | -0.308 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 72 | OTHR | -2.543 | -1.869 | -0.021 | 1.226 | 0.218 | -0.005 | -1.028 | -0.074 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 115 | OTHR | -3.203 | -2.274 | 0.134 | -0.211 | 0.512 | -0.108 | -0.039 | -0.855 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 120 | OTHR | -2.020 | -1.840 | 0.035 | 0.618 | 0.398 | 0.098 | -0.299 | -0.179 | |
| | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | |
| on Slab B1F EL-2.0 | 567 | OTHR | -1.006 | -0.224 | -0.007 | -0.081 | -0.027 | -0.005 | -0.109 | 0.025 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 572 | OTHR | -1.189 | -0.493 | 0.044 | -0.058 | -0.021 | 0.003 | 0.139 | -0.009 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 615 | OTHR | -0.475 | -0.501 | -0.300 | -0.037 | -0.022 | 0.024 | -0.042 | 0.010 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 620 | OTHR | -0.590 | -0.432 | 0.756 | -0.030 | -0.037 | -0.028 | 0.036 | 0.047 | |
| | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | |
| on Slab 1F EL4.65 | 1067 | OTHR | -0.219 | 0.023 | 0.004 | 0.342 | 0.211 | -0.020 | 0.058 | 0.027 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 1072 | OTHR | -0.354 | -0.163 | 0.003 | -0.231 | -0.041 | 0.001 | 0.194 | -0.006 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 1115 | OTHR | -0.022 | -0.042 | 0.113 | -0.038 | -0.356 | -0.033 | 0.003 | 0.295 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| 1120 | OTHR | -0.101 | -0.015 | 0.074 | -0.073 | -0.049 | -0.023 | 0.045 | 0.032 | |
| | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | |
| on Wall EL-7.4m ~ EL-2.0m | 6007 | OTHR | -0.973 | -0.978 | -0.238 | 0.069 | 0.143 | 0.047 | 0.085 | 0.335 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 4006 | OTHR | -0.610 | -1.209 | -0.093 | -0.068 | -0.368 | -0.002 | 0.000 | -0.707 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 4010 | OTHR | -0.457 | -0.512 | -0.100 | -0.074 | -0.140 | 0.063 | 0.097 | -0.289 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| on Wall EL-2.0m ~ EL4.65m | 6043 | OTHR | -0.491 | -1.355 | -0.288 | 0.062 | 0.031 | -0.015 | 0.060 | 0.183 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 4036 | OTHR | -0.540 | -0.750 | -0.053 | 0.015 | 0.060 | -0.003 | 0.016 | -0.359 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | 4040 | OTHR | -0.351 | -0.686 | 0.277 | -0.084 | -0.012 | 0.048 | 0.147 | -0.121 |
| | | TEMP | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |

OTHR: Loads other than thermal loads

TEMP: Thermal loads

Table 3G.2-13

Combined Forces and Moments: Selected Load Combination CB-7

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---------------------------------|------------|--------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| on Basemat EL-7.4 | 67 | OTHR | -1.351 | -2.125 | 0.043 | -0.795 | -0.528 | 0.021 | 0.229 | -0.217 |
| | | TEMP | 0.015 | -0.149 | 0.022 | 1.036 | 0.949 | -0.015 | 0.032 | -0.011 |
| | 72 | OTHR | -1.505 | -1.081 | -0.014 | 0.653 | 0.087 | 0.003 | -0.712 | -0.049 |
| | | TEMP | -0.003 | 0.213 | 0.028 | 0.262 | 0.985 | -0.003 | 0.000 | 0.047 |
| | 115 | OTHR | -2.000 | -1.375 | 0.131 | -0.157 | 0.282 | -0.125 | -0.024 | -0.586 |
| | | TEMP | 0.061 | -0.011 | 0.038 | 1.073 | 0.366 | -0.038 | 0.100 | 0.138 |
| 120 | OTHR | -1.200 | -1.085 | 0.000 | 0.349 | 0.216 | 0.156 | -0.179 | -0.099 | |
| | TEMP | -0.182 | -0.166 | 0.058 | 0.528 | 0.535 | 0.222 | 0.248 | 0.273 | |
| on Slab B1F EL-2.0 | 567 | OTHR | -0.593 | -0.028 | -0.011 | -0.054 | -0.019 | -0.003 | -0.074 | 0.017 |
| | | TEMP | -0.177 | 0.047 | 0.001 | -0.003 | -0.004 | 0.000 | -0.001 | 0.001 |
| | 572 | OTHR | -0.686 | -0.272 | 0.024 | -0.036 | -0.014 | 0.002 | 0.094 | -0.006 |
| | | TEMP | 0.061 | -0.255 | -0.021 | 0.004 | 0.001 | 0.001 | -0.003 | 0.000 |
| | 615 | OTHR | -0.257 | -0.274 | -0.209 | -0.026 | -0.014 | 0.017 | -0.030 | 0.006 |
| | | TEMP | -0.289 | 0.062 | -0.091 | -0.003 | 0.002 | 0.000 | -0.005 | -0.010 |
| 620 | OTHR | -0.342 | -0.248 | 0.451 | -0.020 | -0.024 | -0.020 | 0.025 | 0.032 | |
| | TEMP | -0.233 | -0.239 | -0.381 | -0.002 | -0.002 | 0.003 | 0.001 | 0.002 | |
| on Slab 1F EL4.65 | 1067 | OTHR | -0.123 | 0.020 | 0.005 | 0.237 | 0.137 | -0.013 | 0.041 | 0.019 |
| | | TEMP | -0.973 | -0.282 | -0.007 | -0.006 | -0.042 | 0.001 | 0.003 | -0.002 |
| | 1072 | OTHR | -0.204 | -0.092 | 0.000 | -0.139 | -0.027 | 0.002 | 0.123 | -0.004 |
| | | TEMP | -0.249 | -1.407 | -0.041 | 0.172 | 0.020 | 0.007 | -0.074 | 0.003 |
| | 1115 | OTHR | 0.017 | -0.028 | 0.068 | -0.024 | -0.233 | -0.022 | 0.001 | 0.199 |
| | | TEMP | 0.152 | 0.206 | 0.139 | -0.022 | 0.025 | 0.014 | -0.008 | 0.008 |
| 1120 | OTHR | -0.054 | -0.004 | 0.045 | -0.047 | -0.032 | -0.017 | 0.030 | 0.023 | |
| | TEMP | -1.448 | -1.451 | -1.673 | 0.139 | 0.137 | -0.012 | -0.052 | -0.050 | |
| on Wall EL-7.4m ~ EL-2.0m | 6007 | OTHR | -0.608 | -0.664 | -0.158 | 0.039 | 0.098 | 0.027 | 0.042 | 0.207 |
| | | TEMP | 0.149 | 0.206 | -0.006 | 0.104 | 0.142 | 0.000 | -0.006 | 0.029 |
| | 4006 | OTHR | -0.348 | -0.843 | -0.065 | -0.047 | -0.249 | -0.001 | 0.000 | -0.425 |
| | | TEMP | 0.246 | -0.157 | 0.042 | -0.115 | -0.173 | 0.000 | 0.000 | -0.035 |
| | 4010 | OTHR | -0.260 | -0.323 | -0.072 | -0.042 | -0.093 | 0.036 | 0.053 | -0.176 |
| | | TEMP | 0.176 | 0.319 | 0.051 | -0.086 | -0.133 | -0.008 | -0.023 | -0.048 |
| on Wall EL-2.0m ~ EL4.65m | 6043 | OTHR | -0.262 | -0.940 | -0.194 | 0.042 | 0.020 | -0.008 | 0.041 | 0.104 |
| | | TEMP | 0.151 | -0.064 | -0.184 | 0.105 | 0.120 | -0.005 | 0.009 | -0.025 |
| | 4036 | OTHR | -0.306 | -0.518 | -0.041 | 0.012 | 0.053 | -0.001 | 0.010 | -0.206 |
| | | TEMP | 0.001 | -0.325 | -0.014 | -0.102 | -0.100 | 0.001 | 0.001 | 0.064 |
| | 4040 | OTHR | -0.208 | -0.441 | 0.171 | -0.050 | -0.003 | 0.030 | 0.089 | -0.069 |
| | | TEMP | 0.225 | 0.814 | 0.007 | -0.045 | -0.111 | -0.019 | -0.063 | -0.024 |

Table 3G.2-14

Combined Forces and Moments: Selected Load Combination CB-9

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|----------------------|------------|--------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| on Basemat EL-7.4 | 67 | OTHR | -1.347 | -2.147 | 0.041 | -0.859 | -0.553 | 0.029 | 0.217 | -0.220 |
| | | TEMP | -0.659 | -1.669 | 0.174 | 6.545 | 6.107 | -0.153 | 0.371 | -0.144 |
| | | EQEW | 0.129 | -0.236 | 0.377 | 0.415 | 1.265 | 0.065 | 0.480 | -1.724 |
| | | EQNS | -0.116 | -0.109 | 0.139 | -0.407 | -0.294 | -0.209 | 0.656 | -0.020 |
| | | EQZ | -0.028 | 0.625 | -0.019 | 0.851 | 0.873 | -0.060 | -0.146 | 0.164 |
| | | EQT | 0.001 | 0.001 | 0.069 | 0.000 | 0.000 | 0.006 | 0.000 | -0.001 |
| | | SPKW | 0.080 | -1.028 | 0.047 | 0.445 | 0.691 | -0.061 | 0.156 | -0.080 |
| | SPKN | -0.717 | 0.137 | -0.018 | -0.127 | -0.089 | 0.010 | -0.064 | 0.038 | |
| | 72 | OTHR | -1.504 | -1.030 | -0.013 | 0.652 | 0.108 | -0.001 | -0.715 | -0.047 |
| | | TEMP | -0.273 | -0.342 | 0.023 | 1.970 | 5.689 | 0.040 | 0.144 | 0.088 |
| | | EQEW | 0.010 | -0.055 | -1.512 | 0.045 | 0.105 | 1.531 | 0.085 | -0.661 |
| | | EQNS | -0.119 | -2.846 | 0.005 | -1.371 | -1.194 | 0.051 | -1.216 | -0.021 |
| | | EQZ | 0.044 | -0.208 | -0.002 | 0.330 | 0.132 | -0.006 | 0.512 | -0.002 |
| | | EQT | 0.000 | -0.009 | -0.113 | -0.001 | 0.000 | 0.072 | 0.001 | -0.077 |
| | | SPKW | 0.028 | -0.506 | -0.005 | -0.068 | 0.105 | -0.005 | 0.073 | -0.018 |
| | SPKN | -0.702 | -0.139 | -0.018 | 0.923 | 0.205 | 0.005 | -0.116 | -0.014 | |
| | 115 | OTHR | -2.024 | -1.385 | 0.119 | -0.171 | 0.271 | -0.110 | -0.038 | -0.612 |
| | | TEMP | -1.282 | -0.171 | 0.109 | 6.248 | 2.349 | -0.234 | 0.385 | 0.929 |
| | | EQEW | 2.477 | 0.177 | 0.226 | 0.196 | 0.498 | -0.028 | -0.282 | 0.279 |
| | | EQNS | -0.136 | -0.061 | 1.667 | 0.057 | 0.013 | -1.892 | 0.842 | -0.138 |
| | | EQZ | 0.642 | 0.224 | -0.231 | 0.229 | 0.142 | 0.259 | 0.054 | 0.520 |
| | | EQT | 0.014 | 0.000 | 0.128 | 0.013 | 0.006 | -0.054 | 0.089 | 0.001 |
| | | SPKW | -0.121 | -0.455 | -0.054 | 0.126 | 0.449 | 0.062 | -0.038 | 0.015 |
| | SPKN | -0.647 | 0.001 | -0.037 | 0.027 | -0.020 | 0.049 | 0.003 | 0.005 | |
| | 120 | OTHR | -1.204 | -1.078 | -0.004 | 0.352 | 0.210 | 0.169 | -0.184 | -0.094 |
| | | TEMP | -1.011 | -0.921 | -0.608 | 3.338 | 3.354 | 2.200 | 1.174 | 1.295 |
| | | EQEW | 0.611 | -0.212 | -0.150 | 0.182 | 0.471 | -0.001 | 0.801 | -0.150 |
| | | EQNS | 0.085 | -0.610 | 0.083 | -0.594 | -0.251 | 0.475 | 0.063 | -0.698 |
| EQZ | | 0.065 | 0.000 | 0.112 | 0.064 | 0.114 | -0.511 | 0.029 | -0.025 | |
| EQT | | 0.039 | -0.031 | -0.005 | -0.012 | 0.016 | 0.007 | 0.066 | -0.064 | |
| SPKW | | -0.029 | -0.395 | 0.029 | 0.015 | 0.386 | -0.175 | -0.047 | -0.074 | |
| SPKN | -0.412 | -0.025 | 0.001 | 0.411 | 0.030 | -0.085 | -0.062 | -0.016 | | |

OTHR: Loads other than thermal and seismic loads

TEMP: Thermal loads

EQEW: Horizontal seismic loads in the E-W direction

EQNS: Horizontal seismic loads in the N-S direction

EQZ: Vertical seismic loads

EQT: Torsional seismic loads

SPKW: Dynamic soil pressure during a horizontal earthquake in the E-W direction

SPKN: Dynamic soil pressure during a horizontal earthquake in the N-S direction

Table 3G.2-14
Combined Forces and Moments: Selected Load Combination CB-9 (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|-----------------------|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| on Slab B1F EL-2.0 | 567 | OTHR | -0.593 | -0.005 | -0.013 | -0.058 | -0.019 | -0.003 | -0.076 | 0.018 |
| | | TEMP | -0.739 | 0.490 | 0.042 | -0.073 | -0.091 | 0.002 | 0.001 | 0.004 |
| | | EQEW | 0.005 | 0.050 | -0.387 | 0.017 | 0.050 | 0.010 | 0.012 | -0.091 |
| | | EQNS | 0.038 | 0.013 | 0.005 | 0.047 | 0.000 | -0.009 | 0.015 | -0.010 |
| | | EQZ | 0.002 | -0.598 | 0.039 | 0.043 | 0.013 | 0.002 | 0.045 | -0.012 |
| | | EQT | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | | SPKW | 0.117 | -1.155 | 0.044 | 0.003 | 0.000 | 0.001 | 0.000 | -0.005 |
| | | SPKN | -0.949 | 0.119 | -0.005 | 0.001 | 0.000 | 0.000 | 0.001 | 0.001 |
| | 572 | OTHR | -0.682 | -0.268 | 0.023 | -0.038 | -0.014 | 0.002 | 0.096 | -0.006 |
| | | TEMP | 0.311 | -0.838 | -0.057 | -0.006 | -0.062 | 0.003 | -0.035 | 0.000 |
| | | EQEW | -0.004 | -0.003 | -0.238 | -0.001 | 0.000 | 0.001 | 0.001 | 0.001 |
| | | EQNS | 0.087 | 0.101 | 0.000 | -0.001 | -0.006 | 0.000 | -0.005 | 0.002 |
| | | EQZ | -0.080 | -0.105 | 0.011 | 0.018 | 0.007 | -0.001 | -0.053 | 0.004 |
| | | EQT | 0.000 | 0.000 | -0.004 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | | SPKW | 0.004 | -0.465 | 0.005 | -0.008 | -0.002 | 0.000 | 0.003 | 0.000 |
| | | SPKN | -1.112 | -0.205 | 0.044 | 0.032 | 0.005 | 0.000 | -0.013 | 0.000 |
| | 615 | OTHR | -0.249 | -0.271 | -0.220 | -0.027 | -0.013 | 0.017 | -0.031 | 0.004 |
| | | TEMP | -0.814 | 0.635 | -0.748 | -0.081 | -0.030 | 0.005 | -0.032 | -0.080 |
| | | EQEW | 0.205 | -0.179 | -0.378 | 0.004 | 0.026 | 0.002 | -0.007 | -0.026 |
| | | EQNS | 0.007 | 0.004 | -0.055 | 0.028 | 0.001 | 0.006 | 0.027 | 0.006 |
| | | EQZ | -0.145 | -0.121 | 0.199 | 0.018 | 0.000 | -0.012 | 0.023 | 0.009 |
| | | EQT | 0.000 | 0.000 | 0.001 | 0.001 | 0.000 | 0.000 | 0.001 | 0.000 |
| | | SPKW | -0.151 | -0.912 | -0.264 | 0.002 | 0.034 | 0.002 | -0.008 | -0.038 |
| | | SPKN | -0.452 | -0.018 | 0.120 | 0.001 | -0.002 | 0.000 | 0.002 | 0.004 |
| | 620 | OTHR | -0.341 | -0.247 | 0.453 | -0.020 | -0.025 | -0.020 | 0.025 | 0.032 |
| | | TEMP | -0.923 | -0.938 | -1.400 | -0.058 | -0.060 | 0.007 | 0.002 | 0.005 |
| | | EQEW | -0.045 | -0.109 | -0.186 | -0.012 | 0.015 | 0.001 | 0.018 | -0.017 |
| | | EQNS | 0.103 | 0.063 | -0.001 | -0.011 | 0.015 | 0.000 | 0.014 | -0.017 |
| | | EQZ | -0.032 | -0.034 | -0.043 | 0.009 | 0.011 | 0.013 | -0.013 | -0.016 |
| | | EQT | 0.001 | 0.000 | -0.001 | -0.001 | 0.001 | 0.000 | 0.002 | -0.002 |
| | | SPKW | -0.015 | -0.506 | 0.291 | -0.004 | 0.007 | -0.004 | 0.005 | -0.007 |
| | | SPKN | -0.501 | -0.016 | 0.367 | 0.008 | -0.003 | -0.004 | -0.007 | 0.005 |

Table 3G.2-14
Combined Forces and Moments: Selected Load Combination CB-9 (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|----------------------|------------|--------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| on Slab 1F EL4.65 | 1067 | OTHR | -0.112 | 0.034 | 0.002 | 0.238 | 0.145 | -0.014 | 0.040 | 0.019 |
| | | TEMP | -1.536 | -0.270 | -0.038 | 0.118 | 0.014 | 0.002 | 0.004 | -0.006 |
| | | EQEW | -0.005 | -0.023 | 0.026 | 0.005 | 0.004 | 0.005 | 0.001 | -0.005 |
| | | EQNS | 0.039 | -0.015 | 0.070 | -0.010 | -0.010 | -0.006 | 0.015 | -0.001 |
| | | EQZ | -0.092 | -0.098 | 0.003 | -0.198 | -0.112 | 0.012 | -0.035 | -0.017 |
| | | EQT | -0.001 | 0.002 | -0.008 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | | SPKW | 0.089 | -0.671 | 0.041 | -0.018 | 0.042 | 0.000 | -0.004 | 0.004 |
| | | SPKN | -0.630 | 0.076 | -0.008 | 0.011 | 0.008 | -0.001 | 0.000 | 0.000 |
| | 1072 | OTHR | -0.211 | -0.104 | 0.003 | -0.149 | -0.027 | 0.000 | 0.131 | -0.004 |
| | | TEMP | -0.482 | -2.085 | -0.085 | 0.418 | 0.170 | 0.014 | -0.137 | 0.006 |
| | | EQEW | -0.002 | -0.006 | 0.308 | -0.002 | 0.000 | 0.007 | 0.001 | 0.005 |
| | | EQNS | 0.264 | 0.496 | -0.036 | -0.008 | -0.016 | 0.001 | -0.009 | 0.001 |
| | | EQZ | -0.011 | -0.003 | 0.001 | 0.071 | 0.014 | -0.001 | -0.087 | 0.002 |
| | | EQT | 0.001 | 0.001 | -0.010 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | | SPKW | 0.026 | -0.391 | -0.014 | 0.001 | 0.007 | -0.003 | 0.007 | -0.002 |
| | | SPKN | -0.697 | -0.103 | 0.026 | -0.166 | -0.026 | -0.002 | 0.064 | -0.002 |
| | 1115 | OTHR | 0.034 | -0.009 | 0.089 | -0.026 | -0.242 | -0.024 | 0.001 | 0.202 |
| | | TEMP | -0.017 | 0.193 | 0.233 | 0.129 | 0.233 | 0.020 | -0.006 | -0.020 |
| | | EQEW | -0.671 | -0.164 | -0.055 | 0.023 | 0.085 | 0.000 | -0.006 | -0.028 |
| | | EQNS | 0.342 | 0.051 | -0.417 | -0.022 | -0.001 | -0.006 | 0.011 | 0.004 |
| | | EQZ | -0.235 | -0.072 | -0.092 | 0.018 | 0.174 | 0.022 | 0.001 | -0.155 |
| | | EQT | 0.022 | 0.004 | -0.022 | -0.001 | 0.000 | 0.001 | 0.001 | 0.000 |
| | | SPKW | -0.088 | -0.632 | -0.050 | -0.031 | -0.158 | 0.005 | 0.005 | 0.059 |
| | | SPKN | -0.487 | -0.004 | 0.007 | 0.004 | -0.002 | 0.000 | 0.002 | 0.002 |
| | 1120 | OTHR | -0.056 | -0.010 | 0.053 | -0.048 | -0.034 | -0.018 | 0.029 | 0.023 |
| | | TEMP | -2.239 | -2.260 | -2.503 | 0.265 | 0.265 | -0.013 | -0.044 | -0.043 |
| | | EQEW | -0.086 | -0.103 | 0.117 | -0.017 | 0.035 | 0.000 | 0.032 | -0.030 |
| | | EQNS | 0.179 | 0.105 | -0.011 | -0.025 | 0.022 | 0.004 | 0.028 | -0.029 |
| EQZ | | -0.029 | -0.012 | -0.028 | 0.026 | 0.026 | 0.023 | -0.016 | -0.023 | |
| EQT | | 0.005 | -0.005 | -0.004 | -0.002 | 0.002 | 0.000 | 0.003 | -0.003 | |
| SPKW | | 0.007 | -0.303 | 0.124 | 0.014 | -0.048 | 0.020 | -0.027 | 0.039 | |
| SPKN | | -0.302 | 0.005 | 0.135 | -0.050 | 0.013 | 0.022 | 0.040 | -0.028 | |

Table 3G.2-14
Combined Forces and Moments: Selected Load Combination CB-9 (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--------------------------------|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| on Wall EL-7.4m ~EL-2.0m | 6007 | OTHR | -0.617 | -0.695 | -0.193 | 0.039 | 0.101 | 0.027 | 0.041 | 0.209 |
| | | TEMP | 0.338 | 1.553 | -0.208 | 0.638 | 0.905 | 0.002 | -0.036 | 0.159 |
| | | EQEW | 0.863 | 0.595 | -0.061 | 0.013 | 0.037 | 0.003 | -0.016 | 0.006 |
| | | EQNS | 0.081 | -0.174 | 1.857 | -0.053 | 0.035 | -0.011 | -0.067 | 0.030 |
| | | EQZ | 0.201 | 0.576 | 0.202 | 0.008 | -0.077 | 0.003 | 0.044 | -0.058 |
| | | EQT | 0.007 | 0.003 | 0.132 | -0.002 | 0.001 | 0.001 | -0.004 | 0.001 |
| | | SPKW | -0.051 | 0.063 | -0.023 | 0.033 | 0.032 | 0.021 | 0.050 | 0.102 |
| | | SPKN | -0.312 | 0.010 | 0.002 | -0.002 | -0.017 | -0.001 | 0.002 | -0.007 |
| | 4006 | OTHR | -0.338 | -0.855 | -0.063 | -0.048 | -0.254 | -0.001 | 0.000 | -0.426 |
| | | TEMP | 0.710 | -0.086 | 0.026 | -0.707 | -1.171 | -0.001 | -0.001 | -0.221 |
| | | EQEW | -0.048 | 0.094 | -1.505 | 0.005 | 0.012 | -0.011 | -0.006 | 0.005 |
| | | EQNS | -0.737 | -1.756 | -0.067 | 0.000 | -0.018 | -0.001 | 0.004 | -0.002 |
| | | EQZ | -0.070 | 0.712 | 0.021 | 0.033 | 0.168 | 0.000 | 0.000 | 0.049 |
| | | EQT | -0.004 | -0.001 | -0.128 | 0.000 | 0.001 | 0.001 | -0.001 | 0.000 |
| | | SPKW | -0.286 | 0.124 | -0.010 | 0.013 | 0.076 | -0.001 | 0.001 | 0.033 |
| | | SPKN | -0.106 | -0.068 | -0.019 | -0.022 | -0.134 | 0.000 | -0.001 | -0.283 |
| | 4010 | OTHR | -0.255 | -0.326 | -0.065 | -0.042 | -0.096 | 0.036 | 0.052 | -0.178 |
| | | TEMP | 1.106 | 0.968 | -0.456 | -0.526 | -0.930 | -0.043 | -0.184 | -0.372 |
| | | EQEW | -0.145 | 0.649 | -0.666 | 0.035 | 0.083 | -0.006 | 0.031 | 0.035 |
| | | EQNS | -0.132 | -0.701 | -0.691 | 0.030 | 0.006 | -0.013 | 0.004 | -0.006 |
| | | EQZ | -0.055 | 0.136 | 0.053 | -0.010 | 0.060 | 0.004 | 0.025 | 0.035 |
| | | EQT | -0.013 | 0.007 | -0.090 | 0.003 | 0.006 | 0.000 | 0.002 | 0.003 |
| | | SPKW | -0.186 | -0.031 | 0.030 | -0.036 | 0.015 | -0.014 | 0.032 | 0.020 |
| | | SPKN | -0.047 | -0.106 | -0.068 | -0.009 | -0.046 | 0.044 | 0.027 | -0.120 |

Table 3G.2-14
Combined Forces and Moments: Selected Load Combination CB-9 (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--------------------------------|------------|------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|
| on Wall EL-2.0m ~EL4.65m | 6043 | OTHR | -0.255 | -1.003 | -0.234 | 0.043 | 0.023 | -0.008 | 0.042 | 0.106 |
| | | TEMP | 3.009 | -0.382 | -0.764 | 0.387 | 0.511 | -0.026 | 0.137 | 0.106 |
| | | EQEW | 0.300 | -0.092 | -0.004 | 0.069 | 0.140 | -0.008 | 0.047 | 0.067 |
| | | EQNS | -0.004 | 0.042 | 1.702 | -0.005 | -0.013 | 0.007 | 0.003 | -0.004 |
| | | EQZ | -0.154 | 1.017 | 0.252 | -0.034 | -0.018 | -0.005 | -0.033 | 0.012 |
| | | EQT | -0.001 | 0.012 | 0.123 | 0.000 | -0.001 | 0.002 | 0.000 | 0.000 |
| | | SPKW | -0.014 | -0.086 | -0.071 | 0.026 | 0.019 | -0.018 | 0.051 | 0.535 |
| | | SPKN | -0.580 | 0.184 | 0.067 | -0.005 | 0.013 | 0.003 | -0.012 | -0.001 |
| | 4036 | OTHR | -0.308 | -0.541 | -0.039 | 0.012 | 0.056 | -0.001 | 0.009 | -0.204 |
| | | TEMP | 2.363 | 0.048 | -0.085 | -0.282 | -0.293 | 0.002 | 0.031 | 0.030 |
| | | EQEW | -0.015 | 0.040 | -1.400 | 0.000 | 0.000 | 0.003 | 0.006 | 0.000 |
| | | EQNS | 0.066 | -1.078 | -0.091 | -0.004 | -0.007 | -0.001 | -0.002 | -0.006 |
| | | EQZ | -0.053 | 0.540 | 0.032 | -0.016 | -0.087 | 0.000 | 0.001 | -0.033 |
| | | EQT | 0.000 | -0.001 | -0.107 | 0.000 | 0.000 | 0.002 | 0.000 | 0.000 |
| | | SPKW | -0.515 | 0.172 | 0.009 | -0.009 | -0.039 | -0.001 | -0.003 | -0.009 |
| | | SPKN | -0.177 | -0.017 | 0.000 | 0.008 | 0.019 | -0.002 | 0.017 | -0.500 |
| | 4040 | OTHR | -0.208 | -0.447 | 0.187 | -0.050 | -0.003 | 0.030 | 0.089 | -0.068 |
| | | TEMP | 1.333 | 0.159 | -0.800 | -0.094 | -0.285 | -0.026 | -0.200 | -0.181 |
| | | EQEW | -0.006 | 0.464 | -0.990 | 0.006 | -0.009 | -0.018 | -0.012 | -0.009 |
| | | EQNS | -0.017 | -0.759 | -0.905 | -0.001 | 0.008 | -0.012 | -0.002 | -0.002 |
| | | EQZ | 0.009 | 0.251 | -0.083 | 0.001 | -0.017 | -0.007 | -0.011 | -0.013 |
| | | EQT | -0.004 | -0.006 | -0.104 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 |
| | | SPKW | -0.367 | -0.152 | 0.051 | -0.109 | -0.023 | -0.019 | 0.047 | 0.024 |
| | | SPKN | -0.115 | -0.252 | 0.015 | -0.032 | -0.002 | 0.093 | 0.137 | -0.157 |

Table 3G.2-15

Sectional Thicknesses and Rebar Ratios Used in the Evaluation

| Location | Element ID | Thickness (m) | Primary Reinforcement | | | | Shear Tie | | |
|--------------------------|------------------------------|---------------|-----------------------|---|-----------|---|-----------|-------------|-----------|
| | | | Position | N-S Bars (Slab) Horizontal Bars (Wall) | | E-W Bars (Slab) Vertical Bars (Wall) | | Arrangement | Ratio (%) |
| | | | | Arrangement | Ratio (%) | Arrangement | Ratio (%) | | |
| Basemat EL-7.4 | 67 72 115 120 | 3.0 | Top | 1-#11@200 + 1-#11@400 | 0.252 | 1-#11@200 + 1-#11@400 | 0.252 | -- | 0.000 |
| | | | Bottom | 1-#11@200 + 1-#11@400 | 0.252 | 1-#11@200 + 1-#11@400 | 0.252 | | |
| Slab B1F EL-2.0 | 567 572 615 620 | 0.5 | Top | 1-#11@200 | 1.006 | 1-#11@200 | 1.006 | -- | 0.000 |
| | | | Bottom | 1-#11@200 | 1.006 | 1-#11@200 | 1.006 | | |
| Slab 1F EL4.65 | 1067 1072 1115 1120 | 0.7 | Top | 1-#11@200 | 0.719 | 1-#11@200 | 0.719 | -- | 0.000 |
| | | | Bottom | 1-#11@200 | 0.719 | 1-#11@200 | 0.719 | | |
| Wall EL-7.4m ~EL-2.0m | 6007 4006 4010 | 0.9 | Inside | 2-#11@200 | 1.118 | 2-#11@200 | 1.118 | #6@400x200 | 0.355 |
| | | | Outside | 2-#11@200 | 1.118 | 2-#11@200 | 1.118 | | |
| Wall EL-2.0m ~EL4.65m | 6043 4036 4040 | 0.9 | Inside | 2-#11@200 | 1.118 | 2-#11@200 | 1.118 | #6@400x200 | 0.355 |
| | | | Outside | 2-#11@200 | 1.118 | 2-#11@200 | 1.118 | | |

Table 3G.2-16
Rebar and Concrete Stresses (Basemat and Slabs):
Selected Load Combination CB-3

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable | | |
|-----------------------|------------|-----------------------|-----------|------------------------------------|--------|-------------|--------|-----------|-------|-------|
| | | Calculated | Allowable | Calculated | | | | | | |
| | | | | X-direction | | Y-direction | | | | |
| | | | | Top | Bottom | Top | Bottom | | | |
| on Basemat EL-7.4 | 67 | -1.5 | -20.7 | 0.1 | -8.8 | -5.9 | -9.7 | 372.2 | | |
| | 72 | -1.6 | | -10.8 | -0.9 | -3.8 | -3.6 | | | |
| | 115 | -1.2 | | -6.0 | -8.5 | -6.9 | -2.2 | | | |
| | 120 | -1.1 | | -6.8 | -2.2 | -5.2 | -2.6 | | | |
| on Slab B1F EL-2.0 | 567 | -3.6 | -25.9 | -6.8 | -17.6 | 0.8 | -2.4 | | 372.2 | |
| | 572 | -3.4 | | -10.1 | -17.8 | -2.9 | -5.0 | | | |
| | 615 | -3.0 | | 13.0 | -5.3 | 9.1 | -6.4 | | | |
| | 620 | -4.1 | | 57.5 | 7.7 | 65.9 | 3.7 | | | |
| on Slab 1F EL4.65 | 1067 | -9.0 | -25.9 | -10.9 | 114.8 | -4.8 | 83.3 | | | 372.2 |
| | 1072 | -5.2 | | 56.0 | -13.0 | 0.5 | -1.5 | | | |
| | 1115 | -7.3 | | 27.2 | 4.4 | 137.0 | -20.7 | | | |
| | 1120 | -2.5 | | 30.8 | -1.7 | 32.4 | -0.1 | | | |

Note: Negative value means compression.

Table 3G.2-17
Rebar and Concrete Stresses (Walls): Selected Load Combination CB-3

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable | |
|-----------------------------|------------|-----------------------|-----------|------------------------------------|---------|--------------------|---------|-----------|-------|
| | | Calculated | Allowable | Calculated | | | | | |
| | | | | Horizontal direction | | Vertical direction | | | |
| | | | | Inside | Outside | Inside | Outside | | |
| on Wall EL-7.4m ~EL-2.0m | 6007 | -2.3 | -25.9 | -7.0 | -4.4 | -8.9 | -2.6 | 372.2 | |
| | 4006 | -4.3 | | -3.3 | -2.1 | -16.5 | 9.0 | | |
| | 4010 | -2.6 | | -3.9 | 6.0 | -5.7 | 9.6 | | |
| on Wall EL-2.0m ~EL4.65m | 6043 | -1.6 | -25.9 | -3.5 | -0.5 | -9.3 | -8.3 | | 372.2 |
| | 4036 | -1.1 | | -2.8 | -3.1 | -3.2 | -6.0 | | |
| | 4040 | -1.5 | | -3.9 | 0.5 | -4.4 | -4.4 | | |

Note: Negative value means compression.

Table 3G.2-18
Rebar and Concrete Stresses (Basemat and Slabs):
Selected Load Combination CB-7

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable | | |
|-----------------------|------------|-----------------------|-----------|------------------------------------|--------|-------------|--------|-----------|-------|-------|
| | | Calculated | Allowable | Calculated | | | | | | |
| | | | | X-direction | | Y-direction | | | | |
| | | | | Top | Bottom | Top | Bottom | | | |
| on Basemat EL-7.4 | 67 | -1.0 | -23.5 | -3.2 | -1.8 | -7.0 | -3.7 | 372.2 | | |
| | 72 | -1.0 | | -6.7 | -0.5 | -4.2 | 1.0 | | | |
| | 115 | -1.3 | | -7.9 | -1.1 | -5.0 | -0.7 | | | |
| | 120 | -1.0 | | -5.8 | -0.2 | -4.8 | -0.4 | | | |
| on Slab B1F EL-2.0 | 567 | -2.7 | -29.3 | -5.8 | -13.4 | 9.9 | 0.5 | | 372.2 | |
| | 572 | -1.9 | | -4.7 | -9.0 | -4.7 | -6.2 | | | |
| | 615 | -2.5 | | 12.0 | -5.0 | 13.3 | -1.7 | | | |
| | 620 | -2.6 | | 19.1 | -0.7 | 23.5 | -2.7 | | | |
| on Slab 1F EL4.65 | 1067 | -5.5 | -29.3 | -17.4 | 30.6 | -5.7 | 43.8 | | | 372.2 |
| | 1072 | -2.0 | | -3.7 | -0.4 | -12.5 | -14.1 | | | |
| | 1115 | -4.5 | | 38.0 | 7.7 | 89.2 | -12.2 | | | |
| | 1120 | -4.8 | | -5.8 | 22.7 | -9.5 | 27.7 | | | |

Note: Negative value means compression.

Table 3G.2-19
Rebar and Concrete Stresses (Walls): Selected Load Combination CB-7

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|-----------------------------|------------|-----------------------|-----------|------------------------------------|---------|--------------------|---------|-----------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Horizontal direction | | Vertical direction | | |
| | | | | Inside | Outside | Inside | Outside | |
| on Wall EL-7.4m ~EL-2.0m | 6007 | -1.8 | -29.3 | -4.9 | 0.0 | -6.0 | 1.9 | 372.2 |
| | 4006 | -3.9 | | -0.5 | 2.5 | -14.0 | 10.7 | |
| | 4010 | -2.6 | | -1.2 | 16.1 | -1.4 | 22.0 | |
| on Wall EL-2.0m ~EL4.65m | 6043 | -1.9 | | -1.5 | 7.7 | -8.6 | -0.6 | |
| | 4036 | -1.2 | | -2.8 | 0.5 | -6.4 | -4.6 | |
| | 4040 | -0.8 | | 1.3 | 12.3 | 5.2 | 7.6 | |

Note: Negative value means compression.

Table 3G.2-20

Rebar and Concrete Stresses (Basemat and Slabs):

Selected Load Combination CB-9

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|-----------------------|------------|-----------------------|-----------|------------------------------------|--------|-------------|--------|-----------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | X-direction | | Y-direction | | |
| | | | | Top | Bottom | Top | Bottom | |
| on Basemat EL-7.4 | 67 | -5.4 | -23.1 | -15.9 | 23.6 | -34.7 | 36.5 | 368.9 |
| | 72 | -5.0 | | 41.1 | 56.8 | 52.5 | 224.5 | |
| | 115 | -6.0 | | 57.2 | 80.2 | 60.1 | 19.7 | |
| | 120 | -4.1 | | -22.4 | 47.2 | -20.0 | 45.9 | |
| on Slab B1F EL-2.0 | 567 | -8.4 | -28.5 | -23.9 | -40.9 | 73.2 | -17.9 | 366.1 |
| | 572 | -4.7 | | -17.1 | -17.2 | -14.0 | -26.3 | |
| | 615 | -8.2 | | 85.4 | -27.7 | 71.1 | 19.9 | |
| | 620 | -6.7 | | -18.3 | -24.6 | -16.1 | -26.4 | |
| on Slab 1F EL4.65 | 1067 | -13.3 | | -38.2 | 125.8 | -18.6 | 94.7 | |
| | 1072 | -5.4 | | -16.7 | -8.0 | -31.9 | -18.4 | |
| | 1115 | -9.8 | | 104.4 | 33.2 | 180.2 | -35.5 | |
| | 1120 | -8.1 | | -25.6 | 30.6 | -28.9 | 36.2 | |

Note: Negative value means compression.

Table 3G.2-21

Rebar and Concrete Stresses (Walls): Selected Load Combination CB-9

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|-----------------------------|------------|-----------------------|-----------|------------------------------------|---------|--------------------|---------|-----------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Horizontal direction | | Vertical direction | | |
| | | | | Inside | Outside | Inside | Outside | |
| on Wall EL-7.4m ~EL-2.0m | 6007 | -10.8 | -29.0 | 23.1 | 189.1 | 50.8 | 205.6 | 369.6 |
| | 4006 | -15.6 | | 27.0 | 176.3 | -41.6 | 239.3 | |
| | 4010 | -10.5 | | 19.7 | 118.6 | 27.8 | 149.9 | |
| on Wall EL-2.0m ~EL4.65m | 6043 | -9.0 | -29.3 | 38.4 | 147.2 | -27.7 | 135.1 | 372.2 |
| | 4036 | -3.8 | | 48.5 | 108.7 | 52.7 | 121.6 | |
| | 4040 | -4.8 | | 42.7 | 89.6 | 56.2 | 85.9 | |

Note: Negative value means compression.

Table 3G.2-22

Calculation Results for Transverse Shear

| Location | Element ID | Load ID | d (m) | ρ_w (%) | ρ_v (%) | Shear Forces (MN/m) | | | | Vu/ ϕ Vn |
|--------------------------|------------|---------|-------|--------------|--------------|---------------------|-------|-------|-----------|---------------|
| | | | | | | Vu | Vc | Vs | ϕ Vn | |
| Basemat EL-7.4 | 67 | CB-3 | 2.830 | 0.267 | 0.000 | 0.439 | 4.893 | 0.000 | 4.159 | 0.105 |
| | 72 | CB-3 | 2.740 | 0.276 | 0.000 | 1.030 | 4.669 | 0.000 | 3.969 | 0.260 |
| | 115 | CB-3 | 2.780 | 0.272 | 0.000 | 0.856 | 4.687 | 0.000 | 3.984 | 0.215 |
| | 120 | CB-3 | 2.751 | 0.275 | 0.000 | 0.349 | 4.578 | 0.000 | 3.891 | 0.090 |
| B1F EL-2.0 | 567 | CB-3 | 0.363 | 1.393 | 0.000 | 0.112 | 0.774 | 0.000 | 0.658 | 0.170 |
| | 572 | CB-3 | 0.360 | 1.402 | 0.000 | 0.140 | 0.799 | 0.000 | 0.679 | 0.206 |
| | 615 | CB-3 | 0.363 | 1.393 | 0.000 | 0.044 | 0.679 | 0.000 | 0.577 | 0.075 |
| | 620 | CB-3 | 0.392 | 1.290 | 0.000 | 0.059 | 0.329 | 0.000 | 0.280 | 0.210 |
| 1F EL4.65 | 1067 | CB-3 | 0.569 | 0.884 | 0.000 | 0.064 | 0.540 | 0.000 | 0.459 | 0.140 |
| | 1072 | CB-3 | 0.560 | 0.899 | 0.000 | 0.194 | 0.590 | 0.000 | 0.502 | 0.386 |
| | 1115 | CB-3 | 0.610 | 0.825 | 0.000 | 0.295 | 0.611 | 0.000 | 0.519 | 0.569 |
| | 1120 | CB-3 | 0.576 | 0.873 | 0.000 | 0.055 | 0.566 | 0.000 | 0.481 | 0.115 |
| Wall EL-7.4m ~EL-2.0m | 6007 | CB-3 | 0.673 | 1.497 | 0.355 | 0.390 | 0.438 | 0.989 | 1.213 | 0.321 |
| | 4006 | CB-9 | 0.672 | 1.500 | 0.355 | 0.673 | 0.400 | 0.988 | 1.179 | 0.570 |
| | 4010 | CB-9 | 0.672 | 1.499 | 0.355 | 0.566 | 0.472 | 0.988 | 1.241 | 0.456 |
| Wall EL-2.0m ~EL4.65m | 6043 | CB-3 | 0.677 | 1.489 | 0.355 | 0.192 | 1.399 | 0.995 | 2.035 | 0.094 |
| | 4036 | CB-9 | 0.672 | 1.500 | 0.355 | 0.687 | 0.456 | 0.988 | 1.227 | 0.560 |
| | 4040 | CB-3 | 0.696 | 1.449 | 0.355 | 0.191 | 1.325 | 1.023 | 1.996 | 0.096 |

Table 3G.2-23**Factors of Safety for Foundation Stability**

| Load Combination | Overturning | | Sliding | | Floatation | |
|-------------------------|--------------------|--------|----------------|--------|-------------------|--------|
| | Required | Actual | Required | Actual | Required | Actual |
| D + H + E' | 1.1 | 415.6 | 1.1 | 1.54 | -- | -- |
| D + F' | -- | -- | -- | -- | 1.1 | 1.66 |

Where,

D = Dead Load

H = Lateral soil pressure

E' = Safe Shutdown Earthquake

F' = Buoyant forces of design basis flood

Table 3G.2-24**Maximum Soil Bearing Stress Involving SSE**


| | Site Condition* | | |
|-----------------------------|------------------------|--------|------|
| | Soft | Medium | Hard |
| Bearing Stress (MPa) | 1.70 | 1.78 | 1.77 |

* See Table 3A.1-2 for site properties.


Figure 3G.2-1. CB Concrete Outline Plan at EL -7400 and Foundation Reinforcement

Figure 3G.2-2. CB Concrete Outline Plan at EL -2000/4850 and Section Details

Figure 3G.2-3. CB Concrete Outline Plan at EL 9060, Section and Section Detail




Whole View



Cut View

Figure 3G.2-4. FE Model of CB (Isometric View)



: Element selected for evaluation

Figure 3G.2-5. FE Model of CB (Foundation Mat)

| | | | | | | | | | | | | |
|------|------|------|------|------|------|------|------|------|------|------|---------|--|
| (CD) | | | | | (CC) | | (CB) | | | | (CA) | |
| 5013 | 5026 | 5039 | 5052 | 5065 | 5078 | 5091 | 5104 | 5117 | 5130 | 5143 | EL9060 | |
| 4081 | 4082 | 4083 | 4084 | 4085 | 4086 | 4087 | 4088 | 4089 | 4090 | 4643 | | |
| 4513 | 4526 | 4539 | 4552 | 4565 | 4578 | 4591 | 4604 | 4617 | 4630 | 4643 | | |
| 4071 | 4072 | 4073 | 4074 | 4075 | 4076 | 4077 | 4078 | 4079 | 4080 | 4143 | | |
| 4013 | 4026 | 4039 | 4052 | 4065 | 4078 | 4091 | 4104 | 4117 | 4130 | 4143 | | |
| 4061 | 4062 | 4063 | 4064 | 4065 | 4066 | 4067 | 4068 | 4069 | 4070 | 3643 | EL4650 | |
| 3513 | 3526 | 3539 | 3552 | 3565 | 3578 | 3591 | 3604 | 3617 | 3630 | 3643 | | |
| 4051 | 4052 | 4053 | 4054 | 4055 | 4056 | 4057 | 4058 | 4059 | 4060 | 3143 | | |
| 3013 | 3026 | 3039 | 3052 | 3065 | 3078 | 3091 | 3104 | 3117 | 3130 | 3143 | | |
| 4041 | 4042 | 4043 | 4044 | 4045 | 4046 | 4047 | 4048 | 4049 | 4050 | 2643 | | |
| 2513 | 2526 | 2539 | 2552 | 2565 | 2578 | 2591 | 2604 | 2617 | 2630 | 2643 | | |
| 4031 | 4032 | 4033 | 4034 | 4035 | 4036 | 4037 | 4038 | 4039 | 4040 | 2143 | EL-2000 | |
| 2013 | 2026 | 2039 | 2052 | 2065 | 2078 | 2091 | 2104 | 2117 | 2130 | 2143 | | |
| 4021 | 4022 | 4023 | 4024 | 4025 | 4026 | 4027 | 4028 | 4029 | 4030 | 1643 | | |
| 1513 | 1526 | 1539 | 1552 | 1565 | 1578 | 1591 | 1604 | 1617 | 1630 | 1643 | | |
| 4011 | 4012 | 4013 | 4014 | 4015 | 4016 | 4017 | 4018 | 4019 | 4020 | 1143 | | |
| 1013 | 1026 | 1039 | 1052 | 1065 | 1078 | 1091 | 1104 | 1117 | 1130 | 1143 | | |
| 4001 | 4002 | 4003 | 4004 | 4005 | 4006 | 4007 | 4008 | 4009 | 4010 | 643 | EL-7400 | |
| 513 | 526 | 539 | 552 | 565 | 578 | 591 | 604 | 617 | 630 | 643 | | |

: Element selected for evaluation

Figure 3G.2-6. FE Model of CB (External Wall: South Side)

| C1 | | C2 | | | C3 | | C4 | | C5 | | | |
|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|------|
| 5131 | 5132 | 5133 | 5134 | 5135 | 5136 | 5137 | 5138 | 5139 | 5140 | 5141 | 5142 | 5143 |
| 6097 4631 | 6098 4632 | 6099 4633 | 6100 4634 | 6101 4635 | 6102 4636 | 6103 4637 | 6104 4638 | 6105 4639 | 6106 4640 | 6107 4641 | 6108 4642 | 4643 |
| 6085 4131 | 6086 4132 | 6087 4133 | 6088 4134 | 6089 4135 | 4136 | | 6092 4138 | 6093 4139 | 6094 4140 | 6095 4141 | 6096 4142 | 4143 |
| 6073 3631 | 6074 3632 | 6075 3633 | 6076 3634 | 6077 3635 | 6078 3636 | 6079 3637 | 6080 3638 | 6081 3639 | 6082 3640 | 6083 3641 | 6084 3642 | 3643 |
| 6061 3131 | 6062 3132 | 6063 3133 | 6064 3134 | 6065 3135 | 6066 3136 | 6067 3137 | 6068 3138 | 6069 3139 | 6070 3140 | 6071 3141 | 6072 3142 | 3143 |
| 6049 2631 | 6050 2632 | 6051 2633 | 6052 2634 | 6053 2635 | 6054 2636 | 6055 2637 | 6056 2638 | 6057 2639 | 6058 2640 | 6059 2641 | 6060 2642 | 2643 |
| 6037 2131 | 6038 2132 | 6039 2133 | 6040 2134 | 6041 2135 | 6042 2136 | 6043 2137 | 6044 2138 | 6045 2139 | 6046 2140 | 6047 2141 | 6048 2142 | 2143 |
| 6025 1631 | 6026 1632 | 6027 1633 | 6028 1634 | 6029 1635 | 6030 1636 | 6031 1637 | 6032 1638 | 6033 1639 | 6034 1640 | 6035 1641 | 6036 1642 | 1643 |
| 6013 1131 | 6014 1132 | 6015 1133 | 6016 1134 | 6017 1135 | 6018 1136 | 6019 1137 | 6020 1138 | 6021 1139 | 6022 1140 | 6023 1141 | 6024 1142 | 1143 |
| 6001 631 | 6002 632 | 6003 633 | 6004 634 | 6005 635 | 6006 636 | 6007 637 | 6008 638 | 6009 639 | 6010 640 | 6011 641 | 6012 642 | 643 |

EL9060

EL4650

EL-2000

EL-7400

: Element selected for evaluation

Figure 3G.2-7. FE Model of CB (External Wall: East Side)

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|----|----|----|----|
| C1 | | | | | | | | | | | | C2 | | | | | | | | | | | | C3 | | | | | | | | | | | | C4 | | | | | | | | | | | | C5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2131 | 2132 | 2133 | 2134 | 2135 | 2136 | 2137 | 2138 | 2139 | 2140 | 2141 | 2142 | 2143 | 2118 | 2119 | 2120 | 2121 | 2122 | 2123 | 2124 | 2125 | 2126 | 2127 | 2128 | 2129 | 2130 | 2105 | 2106 | 2107 | 2108 | 2109 | 2110 | 2111 | 2112 | 2113 | 2114 | 2115 | 2116 | 2117 | 2092 | 2093 | 2094 | 2095 | 2096 | 2097 | 2098 | 2099 | 2100 | 2101 | 2102 | 2103 | 2104 | 2079 | 2080 | 2081 | 2082 | 2083 | 2084 | 2085 | 2086 | 2087 | 2088 | 2089 | 2090 | 2091 | 2066 | 2067 | 2068 | 2069 | 2070 | 2071 | 2072 | 2073 | 2074 | 2075 | 2076 | 2077 | 2078 | 2053 | 2054 | 2055 | 2056 | 2057 | 2058 | 2059 | 2060 | 2061 | 2062 | 2063 | 2064 | 2065 | 2040 | 2041 | 2042 | 2043 | 2044 | 2045 | 2046 | 2047 | 2048 | 2049 | 2050 | 2051 | 2052 | 2027 | 2028 | 2029 | 2030 | 2031 | 2032 | 2033 | 2034 | 2035 | 2036 | 2037 | 2038 | 2039 | 2014 | 2015 | 2016 | 2017 | 2018 | 2019 | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2001 | 2002 | 2003 | 2004 | 2005 | 2006 | 2007 | 2008 | 2009 | 2010 | 2011 | 2012 | 2013 | CA | CB | CC | CD |
| 609 | 610 | 611 | 612 | 613 | 614 | 615 | 616 | 617 | 618 | 619 | 620 | 597 | 598 | 599 | 600 | 601 | 602 | 603 | 604 | 605 | 606 | 607 | 608 | 585 | 586 | 587 | 588 | 589 | 590 | 591 | 592 | 593 | 594 | 595 | 596 | 573 | 574 | 575 | 576 | 577 | 578 | 579 | 580 | 581 | 582 | 583 | 584 | 561 | 562 | 563 | 564 | 565 | 566 | 567 | 568 | 569 | 570 | 571 | 572 | 549 | 550 | 551 | 552 | 553 | 554 | 555 | 556 | 557 | 558 | 559 | 560 | 537 | 538 | 539 | 540 | 541 | 542 | 543 | 544 | 545 | 546 | 547 | 548 | 525 | 526 | 527 | 528 | 529 | 530 | 531 | 532 | 533 | 534 | 535 | 536 | 513 | 514 | 515 | 516 | | | | | 521 | 522 | 523 | 524 | 501 | 502 | 503 | 504 | 505 | 506 | 507 | 508 | 509 | 510 | 511 | 512 | | | | | | | | | | | | | | | | | | | | | | | | | | | |

: Element selected for evaluation

Figure 3G.2-8. FE Model of CB (Floor Slab: EL -2000)

| | | | | | | | | | | | | |
|------|------|------|------|------|------|------|------|------|------|------|------|------|
| C1 | | C2 | | | | C3 | | C4 | | C5 | | |
| 3631 | 3632 | 3633 | 3634 | 3635 | 3636 | 3637 | 3638 | 3639 | 3640 | 3641 | 3642 | 3643 |
| 1109 | 1110 | 1111 | 1112 | 1113 | 1114 | 1115 | 1116 | 1117 | 1118 | 1119 | 1120 | CA |
| 3618 | 3619 | 3620 | 3621 | 3622 | 3623 | 3624 | 3625 | 3626 | 3627 | 3628 | 3629 | 3630 |
| 1097 | 1098 | 1099 | 1100 | 1101 | 1102 | 1103 | 1104 | 1105 | 1106 | 1107 | 1108 | |
| 3605 | 3606 | 3607 | 3608 | 3609 | 3610 | 3611 | 3612 | 3613 | 3614 | 3615 | 3616 | 3617 |
| 1085 | 1086 | 1087 | 1088 | 1089 | 1090 | 1091 | 1092 | 1093 | 1094 | 1095 | 1096 | |
| 3592 | 3593 | 3594 | 3595 | 3596 | 3597 | 3598 | 3599 | 3600 | 3601 | 3602 | 3603 | 3604 |
| 1073 | 1074 | 1075 | 1076 | 1077 | 1078 | 1079 | 1080 | 1081 | 1082 | 1083 | 1084 | |
| 3579 | 3580 | 3581 | 3582 | 3583 | 3584 | 3585 | 3586 | 3587 | 3588 | 3589 | 3590 | CB |
| 1061 | 1062 | 1063 | 1064 | 1065 | 1066 | 1067 | 1068 | 1069 | 1070 | 1071 | 1072 | |
| 3566 | 3567 | 3568 | 3569 | 3570 | 3571 | 3572 | 3573 | 3574 | 3575 | 3576 | 3577 | 3578 |
| 1049 | 1050 | 1051 | 1052 | 1053 | 1054 | 1055 | 1056 | 1057 | 1058 | 1059 | 1060 | |
| 3553 | 3554 | 3555 | 3556 | 3557 | 3558 | 3559 | 3560 | 3561 | 3562 | 3563 | 3564 | CC |
| 1037 | 1038 | 1039 | 1040 | 1041 | 1042 | 1043 | 1044 | 1045 | 1046 | 1047 | 1048 | |
| 3540 | 3541 | 3542 | 3543 | 3544 | 3545 | 3546 | 3547 | 3548 | 3549 | 3550 | 3551 | 3552 |
| 1025 | 1026 | 1027 | 1028 | 1029 | 1030 | 1031 | 1032 | 1033 | 1034 | 1035 | 1036 | |
| 3527 | 3528 | 3529 | 3530 | 3531 | 3532 | 3533 | 3534 | 3535 | 3536 | 3537 | 3538 | 3539 |
| 1013 | 1014 | 1015 | 1016 | | | | | 1021 | 1022 | 1023 | 1024 | |
| 3514 | 3515 | 3516 | 3517 | 3518 | 3519 | 3520 | 3521 | 3522 | 3523 | 3524 | 3525 | 3526 |
| 1001 | 1002 | 1003 | 1004 | 1005 | 1006 | 1007 | 1008 | 1009 | 1010 | 1011 | 1012 | |
| 3501 | 3502 | 3503 | 3504 | 3505 | 3506 | 3507 | 3508 | 3509 | 3510 | 3511 | 3512 | 3513 |
| | | | | | | | | | | | | CD |


 : Element selected for evaluation

Figure 3G.2-9. FE Model of CB (Floor Slab: EL 4650)




Figure 3G.2-10. Soil Pressure at Rest




Figure 3G.2-11. Sections Where Temperature Loads Are Defined




Figure 3G.2-12. Design Seismic Shears and Moments for CB






Figure 3G.2-13. Seismic Lateral Soil Pressure



Membrane and Shear Forces



Moments

Definition of Element Coordinate System

| Structure | x | y | z |
|------------------------------|--------------|-------------|--------------|
| Wall in N-S Direction | horizontal | vertical | toward West |
| Wall in E-W Direction | horizontal | vertical | toward South |
| Foundation Mat Floor Slab | toward South | toward East | upward |

Figure 3G.2-14. Force and Moment in Shell Element

3G.3 FUEL BUILDING

3G.3.1 Objective and Scope

The objective of this subsection is to document the structural design details, inputs and analytical results from the analysis the Fuel Building (FB) of the standard ESBWR plant. The scope includes the design and analysis of the structure for normal, severe environmental, extreme environmental, and construction loads.

3G.3.2 Conclusions

The following are the major summary conclusions on the design and analysis of the FB.

- Based on the results of finite element analyses performed in accordance with the design conditions identified in Subsection 3G.3.5, stresses in concrete and reinforcement are less than the allowable stresses per the applicable regulations, codes or standards listed in Section 3.8.
- The factors of safety against floatation, sliding, and overturning of the structure under various loading combinations are higher than the required minimum.
- The thickness of the roof slabs and exterior walls are more than the minimum required to preclude penetration, perforation or spalling resulting from impact of design basis tornado missiles.

3G.3.3 Structural Description

The FB is integrated with the RB, sharing a common wall between the RB and the FB and a large common foundation mat (see Section 3.8.4.1.3). The FB houses the spent fuel pool facilities and their supporting system, and HVAC equipment. The FB is a Seismic Category I structure except for the penthouse that covers HVAC equipment. The penthouse is a Seismic Category II structure.

The FB is a reinforced concrete box type shear wall structure consisting of walls and slabs and is supported by a foundation mat. Concrete framing (steel beams can be used partially) is composite with concrete slab and used to support the slabs for vertical loads. The FB is a shear wall structure designed to accommodate all seismic loads with its walls and the connected floors. Therefore, frame members such as beams or columns are designed to accommodate deformations of the walls in case of earthquake conditions.

The key dimensions of the FB are summarized in Table 3.8-8. Figures 3G.1-1 through 3G.1-4 and Figure 3G.1-6 show the outline plans of the FB.

3G.3.4 Analytical Models

Because the FB is integrated with the RB, the finite element model which integrates the RB and FB is used for the stress analysis of the FB. The analysis model is described in Subsection 3G.1.4.1.

3G.3.5 Structural Analysis and Design

3G.3.5.1 Site Design Parameters

The key site design parameters are described in Subsection 3G.1.5.1.

3G.3.5.2 Design Loads, Load Combinations, and Material Properties

3G.3.5.2.1 Design Loads

This section presents only the loads which are applied to the FB directly. Other loads which are applied to the RCCV only but have effects on FB structures because of common foundation mat, like P_a and T_a , are also considered in the FB design.

3G.3.5.2.1.1 Dead Load (D) and Live Load (L and Lo)

The weights of structures are evaluated using the following unit weights.

- reinforced concrete: 23.5 kN/m^3
- steel: 77.0 kN/m^3

Weights of major equipment, miscellaneous structures, piping, and commodities are summarized in Tables 3G.3-1 and 3G.3-2.

Live loads on the FB floor slabs are described in Subsection 3.8.4.3.3.

3G.3.5.2.1.2 Snow Load

The snow load is applied to the roof slab and is taken as shown in Table 3G.1-2. Snow load is reduced to 75% when snow load is combined with seismic loads.

3G.3.5.2.1.3 Lateral Soil Pressure at Rest

The lateral soil pressure at rest is applied to the walls below grade and is based on soil properties given in Table 3G.1-2. Pressures to be applied to the walls are provided in Figure 3G.1-19.

3G.3.5.2.1.4 Wind Load (W)

The wind load is applied to the roof slab and external walls above grade and is based on basic wind speed given in Table 3G.1-2.

3G.3.5.2.1.5 Tornado Load (W_t)

The tornado load is applied to roof slab and external walls above grade and its characteristics are given in Table 3G.1-2. The tornado load, W_t is further defined by the combinations described in Subsection 3G.1.5.2.1.5.

3G.3.5.2.1.6 Thermal Load (T_o)

Thermal loads for the FB are evaluated for the normal operating conditions. Figure 3G.3-1 shows the section location for temperature distributions for various structural elements of the FB, and Table 3G.3-3 shows the magnitude of equivalent linear temperature distribution.

Stress-free temperature is 15.5°C .

3G.3.5.2.1.7 Design Seismic Loads

The design seismic loads applied to the FB are provided in Subsection 3G.1.5.2.1.13.

Seismic lateral soil pressure for the FB is provided in Subsection 3G.1.5.2.1.13.

3G.3.5.2.2 Load Combinations and Acceptance Criteria

Table 3.8-15 gives load combinations for the safety-related reinforced concrete structure. Based on previous experience, critical load combinations are selected for the FB design. They are mainly combinations including LOCA loads and seismic loads as shown in Table 3G.3-4. The acceptance criteria for the selected combinations are also included in Table 3G.3-4.

3G.3.5.2.3 Material Properties

Properties of the materials used for the FB design analyses are same as those for the RB, and they are described in Subsection 3G.1.5.2.3.

3G.3.5.3 Stability Requirements

The stability requirements for the FB foundation are same as those for the RB, and they are described in Subsection 3G.1.5.3.

3G.3.5.4 Structural Design Evaluation

The evaluation of the seismic category I structures in the FB is performed with the same procedure as the RB, which is described in Subsection 3G.1.5.4.

Figure 3G.3-2 shows the location of the sections that are selected for evaluation. They are selected, in principle, from the center and both ends of wall and slab, where it is reasonably expected that the critical stresses appear based on engineering experience and judgment. Tables 3G.3-5 through 3G.3-9 show the forces and moments at the selected sections from NASTRAN analysis. Element forces and moments listed in the tables are defined with relation to the element coordinate system shown in Figure 3G.3-3. Tables 3G.3-10 through 3G.3-12 show the combined forces and moments in accordance with the selected load combinations listed in Table 3G.3-4.

Figures 3G.3-4 and 3G.3-5 present the design drawings used for the evaluation of the FB structural design. Table 3G.3-13 lists the sectional thicknesses and rebar ratios used in the evaluation.

Tables 3G.3-14 through 3G.3-16 show the rebar and concrete stresses at these sections for the representative elements. Table 3G.3-17 summarizes evaluation results for transverse shear in accordance with ACI 349, Chapter 11.

3G.3.5.4.1 Shear Walls and Spent Fuel Pool Walls

The maximum rebar stress of 349.2 MPa is found in the horizontal rebar at Section 3 due to the load combination FB-9 as shown in Table 3G.3-16. The maximum vertical rebar stress is found to be 316.5 MPa at Section 1 for the combination FB-9. The maximum transverse shear force is found to be 4.11 MN/m against the shear strength of 5.91 MN/m at Section 4, Spent Fuel Pool wall.

3G.3.5.4.2 Floor Slabs

The maximum rebar stress of 230.9 MPa is found due to the load combination FB-9 as shown in Table 3G.3-16. The maximum transverse shear force is found to be 0.48 MN/m against the shear strength of 4.37 MN/m.

3G.3.5.4.3 Foundation Mat

The maximum rebar stress is found to be 272.7 MPa due to the load combination FB-9 as shown in Table 3G.3-16. The maximum transverse shear force is found to be 11.20 MN/m against the shear strength of 15.72 MN/m.

3G.3.5.5 *Foundation Stability*

The FB shares the foundation mat with the RB. Evaluation results of the foundation stability are described in Subsection 3G.1.5.5.

3G.3.5.6 *Tornado Missile Evaluation*

The minimum thickness required to prevent penetration and concrete spalling are evaluated. The methods and procedures are shown in Section 3.5.3.1.1. The minimum thickness required is less than the minimum 1000 and 700 mm thickness provided for the FB external walls and slab at EL 22500, respectively.

Table 3G.3-1

Miscellaneous Structures and Commodity in Spent Fuel Pool

| Description | Weight |
|-----------------------------|------------------------|
| Fuel Pool | |
| a. Spent Fuel Storage Racks | 88.7 kN/m ² |
| b. Floor Liner | 1.6 kN/m ² |
| c. Wall Liner | 1.0 kN/m ² |
| d. Water (14.35 m) | 141 kN/m ² |
| Pool Gate | |
| a. Spent Fuel Pool Gate | 70 kN |
| b. Cask Pit Gate | 70 kN |
| Spent Fuel Cask Pool | |
| a. Spent Fuel Cask | 120 kN/m ² |
| b. Floor Liner | 1.6 kN/m ² |
| c. Wall Liner | 1.0 kN/m ² |
| d. Water (14.35 m) | 141 kN/m ² |
| e. Cask Lid | 100 kN |
| f. Cask bearing Plate | 20 kN |
| Fuel Transfer Tube Pool | |
| a. Floor Liner | 1.6 kN/m ² |
| b. Wall Liner | 1.0 kN/m ² |
| c. Water (14.35 m) | 141 kN/m ² |
| d. Transfer Tube Equipment | 160 kN |

Table 3G.3-2**Miscellaneous Structures, Piping, and Commodity Load on FB Floor**

| Elevation (mm) | Area Load |
|----------------|-------------------------------|
| 22,500 | 2.4 kN/m ² (50psf) |
| 4,650 | 2.4 kN/m ² (50psf) |
| -1,000 | 2.4 kN/m ² (50psf) |
| -6,400 | 2.4 kN/m ² (50psf) |
| -11,500 | 2.4 kN/m ² (50psf) |

Table 3G.3-3**Equivalent Liner Temperature Distributions at Various Sections***

| Section ^{*1} | Side ^{*2} | | Equivalent Linear Temperature ^{*3} (°C) | |
|-----------------------|--------------------|----|--|------|
| | | | Normal Operation (Winter) | |
| | 1 | 2 | Td | Tg |
| W1 | FP | RM | 27.0 | 26.0 |
| W2 | FP | RM | 26.6 | 26.7 |
| W3 | FP | GR | 27.8 | 24.5 |
| W4 | FP | GR | 27.8 | 24.5 |

*1: See Figure 3G.3-1 for the location of sections.

*2: FP: Spent Fuel Pool, RM: FB Room, GR: Ground

*3: Td: Average Temperature, Tg: Surface Temperature Difference (positive when temperature at Side 1 is higher)

Table 3G.3-4
Selected Load Combinations for the FB

| Category | Load Combination | | | | | | | | Acceptance Criteria* ¹ |
|------------------------------------|--------------------|------|-----|-------------------------------|----------------|-------------------------------|-----|-----|-----------------------------------|
| | No. * ² | D | L | P _a * ³ | T _o | T _a * ³ | E' | W | |
| Severe Environmental | FB-4 | 1.05 | 1.3 | | 1.3 | | | 1.3 | U |
| LOCA (1.5P _a) 72 hours | FB-8 | 1.0 | 1.0 | 1.5 | | 1.0 | | | U |
| LOCA + SSE 72 hours | FB-9 | 1.0 | 1.0 | 1.0 | | 1.0 | 1.0 | | U |

*1: U = Required section strength based on the strength design method per ACI 349

*2: Based on Table 3.8-15.

*3: P_a and T_a are accident pressure load within the containment and thermal load generated by LOCA, respectively.

P_a and T_a are indirect loads, but their effects are considered in the FB design.

Table 3G.3-5

Results of NASTRAN Analysis: Dead Load

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~-10.50m | 60011 | -0.462 | -1.630 | -0.428 | -0.140 | -1.074 | -0.031 | -0.091 | -0.336 |
| | 60019 | 0.501 | -1.578 | -0.113 | -1.027 | -1.537 | -0.060 | 0.107 | 0.206 |
| | 70001 | -0.014 | -0.199 | 0.064 | 0.618 | -0.037 | 0.087 | -0.196 | 0.114 |
| | 70004 | 0.565 | -0.969 | 0.033 | -0.286 | -0.030 | 0.078 | 0.093 | -0.371 |
| | 110708 | 0.314 | -1.593 | -0.170 | -0.004 | 0.282 | 0.009 | -0.012 | 0.267 |
| 2 Exterior Wall @ EL4.65 ~6.60m | 62011 | 0.086 | -1.006 | 0.122 | 0.041 | 0.134 | 0.006 | 0.010 | 0.050 |
| | 62019 | 0.105 | -0.555 | -0.174 | -0.033 | 0.036 | -0.029 | 0.000 | 0.013 |
| | 72001 | 0.107 | -0.133 | 0.144 | 0.110 | 0.022 | -0.005 | -0.013 | -0.008 |
| | 72004 | 0.150 | -0.398 | 0.255 | -0.038 | 0.007 | 0.000 | -0.017 | 0.013 |
| 3 Exterior Wall @ EL22.50 ~24.60m | 64011 | 0.019 | -0.284 | -0.050 | -0.109 | -0.530 | -0.010 | -0.006 | 0.069 |
| | 64019 | -0.122 | -0.373 | -0.071 | -0.064 | -0.370 | 0.057 | 0.063 | 0.054 |
| | 74001 | -0.017 | -0.047 | 0.108 | 0.048 | -0.046 | -0.045 | -0.020 | -0.029 |
| | 74004 | -0.045 | -0.210 | 0.119 | -0.079 | -0.336 | -0.060 | 0.019 | -0.069 |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 60819 | 0.635 | -1.144 | -0.408 | -1.364 | -0.958 | -0.258 | -0.001 | -0.138 |
| | 70801 | 0.782 | -0.116 | 0.046 | 1.262 | 0.113 | -0.035 | -0.608 | 0.015 |
| | 70804 | 0.636 | -0.662 | 0.163 | -0.645 | -0.464 | 0.053 | -0.118 | 0.075 |
| | 110748 | 0.322 | -0.981 | -0.506 | -0.217 | -0.097 | -0.010 | 0.051 | -0.024 |
| 5 Basemat | 90306 | -1.031 | -0.384 | 0.451 | 0.851 | -0.102 | 0.118 | -0.478 | 1.078 |
| | 90310 | -0.130 | -0.091 | -0.037 | -0.144 | -0.135 | -0.642 | 0.159 | -0.090 |
| | 90410 | -0.418 | -0.846 | 0.472 | -0.686 | 0.137 | 1.346 | 1.276 | -0.027 |
| 5 Basemat @ Spent Fuel Pool | 90486 | 0.101 | -0.132 | 0.036 | 2.387 | 1.876 | 0.183 | -0.075 | 0.164 |
| | 90490 | 0.207 | 0.028 | 0.159 | 0.056 | 0.576 | 0.192 | 1.131 | 0.067 |
| | 90526 | 0.272 | 0.354 | -0.025 | 1.100 | 1.562 | 0.010 | -0.124 | -0.676 |
| 6 Slab EL4.65m | 93306 | 0.125 | 0.007 | 0.045 | 0.037 | 0.008 | 0.005 | 0.030 | -0.100 |
| | 93310 | 0.021 | 0.046 | 0.211 | 0.026 | 0.014 | 0.034 | -0.017 | -0.001 |
| | 93410 | 0.282 | 0.347 | -0.401 | 0.002 | 0.010 | -0.070 | 0.003 | -0.011 |

Table 3G.3-6

Results of NASTRAN Analysis: Temperature Load (Winter)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~-10.50m | 60011 | -1.034 | -0.276 | -0.470 | 0.886 | 0.701 | 0.061 | -0.213 | -0.156 |
| | 60019 | 2.130 | -1.517 | 0.794 | -8.495 | -10.347 | -0.205 | 0.203 | -1.171 |
| | 70001 | 0.665 | 1.233 | -0.737 | -3.570 | -3.154 | 0.152 | 0.567 | 0.226 |
| | 70004 | 1.044 | 0.657 | -0.355 | -2.833 | -2.909 | 0.079 | 0.100 | -0.124 |
| 2 Exterior Wall @ EL4.65 ~-6.60m | 62011 | 5.927 | 1.780 | 0.309 | -1.104 | -1.219 | 0.001 | -0.029 | -0.064 |
| | 62019 | 6.956 | 0.288 | -1.863 | -1.152 | -1.400 | -0.037 | 0.028 | -0.086 |
| | 72001 | 3.754 | -1.871 | 2.422 | -0.553 | -0.895 | 0.030 | -0.600 | 0.207 |
| | 72004 | 6.378 | 0.376 | 2.500 | -1.249 | -1.455 | 0.078 | -0.032 | 0.128 |
| 3 Exterior Wall @ EL22.50 ~-24.60m | 64011 | 4.746 | 0.186 | 0.252 | -0.966 | -0.394 | -0.010 | 0.000 | -0.081 |
| | 64019 | 5.498 | 1.414 | 1.600 | -1.021 | -0.456 | 0.014 | -0.015 | -0.050 |
| | 74001 | 2.909 | -0.796 | -3.432 | -0.753 | -0.461 | 0.131 | -0.303 | 0.097 |
| | 74004 | 4.062 | 0.184 | -3.546 | -0.936 | -0.309 | -0.011 | 0.015 | 0.087 |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 60819 | -2.416 | -2.905 | -0.161 | -6.457 | -6.777 | -0.882 | -0.081 | -0.506 |
| | 70801 | -0.297 | 2.505 | -0.133 | -3.413 | -3.179 | 0.038 | 0.115 | -0.021 |
| | 70804 | -1.329 | 0.117 | 0.288 | -2.912 | -3.121 | 0.212 | 0.007 | 0.047 |
| | 110748 | -1.034 | -1.835 | -0.279 | -1.382 | -1.642 | -0.031 | 0.137 | -0.058 |
| 5 Basemat | 90306 | -0.913 | -0.080 | 0.219 | 1.890 | 0.786 | -0.008 | 0.045 | 0.256 |
| | 90310 | 0.105 | 0.315 | 0.323 | 1.205 | 1.335 | 0.598 | 0.186 | -0.135 |
| | 90410 | -0.147 | -1.226 | 0.653 | 0.548 | 2.081 | 0.464 | 0.252 | -0.198 |
| 5 Basemat @ Spent Fuel Pool | 90486 | -2.543 | -0.964 | 0.092 | -6.708 | -6.839 | 0.557 | 0.292 | 0.029 |
| | 90490 | -1.286 | 2.984 | -0.063 | -12.028 | -8.686 | -0.110 | 1.320 | 1.060 |
| | 90526 | 2.540 | 0.079 | 0.140 | -6.918 | -3.496 | 0.413 | -0.639 | 0.524 |
| 6 Slab EL4.65m | 93306 | -0.743 | -0.035 | -1.631 | -0.052 | 0.030 | -0.015 | 0.079 | -0.027 |
| | 93310 | -2.216 | -2.169 | -3.228 | -0.757 | -0.782 | -0.242 | 0.271 | 0.285 |
| | 93410 | -0.804 | -2.214 | 0.295 | -0.053 | -0.014 | 0.028 | -0.118 | -0.029 |

Table 3G.3-7

Results of NASTRAN Analysis: Seismic Load (Horizontal: North to South Direction)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~-10.50m | 60011 | -5.135 | -4.086 | -0.865 | -0.105 | -1.008 | -0.082 | 0.034 | -0.339 |
| | 60019 | -5.900 | -6.560 | -0.955 | -0.197 | -3.119 | 0.204 | -0.371 | -0.304 |
| | 70001 | -0.169 | -1.548 | -1.870 | 0.188 | -0.964 | 0.056 | -0.590 | 0.222 |
| | 70004 | 1.716 | -5.368 | -4.964 | -1.178 | -2.731 | -0.040 | -0.060 | 0.566 |
| 2 Exterior Wall @ EL4.65 ~6.60m | 110708 | 1.416 | -4.879 | 1.245 | -0.119 | -0.268 | -0.005 | -0.048 | -0.182 |
| | 62011 | 0.921 | -1.364 | -0.345 | 0.048 | 0.175 | 0.002 | -0.018 | 0.033 |
| | 62019 | 0.761 | -1.226 | -2.242 | 0.019 | 0.134 | -0.012 | 0.009 | 0.018 |
| | 72001 | -0.160 | -1.387 | -3.624 | -0.090 | -0.064 | 0.011 | -0.001 | 0.051 |
| 3 Exterior Wall @ EL22.50 ~24.60m | 72004 | -0.274 | -1.755 | -4.201 | -0.033 | -0.035 | -0.003 | 0.016 | 0.007 |
| | 64011 | 3.743 | -0.254 | -0.233 | -0.057 | -0.192 | 0.013 | 0.007 | 0.030 |
| | 64019 | 2.758 | -0.032 | -0.696 | -0.059 | -0.139 | -0.046 | -0.028 | 0.025 |
| | 74001 | 0.085 | -0.152 | -1.111 | 0.036 | 0.049 | -0.049 | 0.041 | -0.012 |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 74004 | -1.414 | -0.263 | -1.644 | 0.036 | 0.028 | -0.033 | 0.014 | 0.010 |
| | 60819 | -0.758 | -4.288 | -2.652 | -0.157 | -0.613 | 0.392 | 0.139 | -0.196 |
| | 70801 | 0.400 | -1.574 | -4.088 | 0.042 | -0.070 | -0.183 | -0.223 | -0.086 |
| | 70804 | 1.104 | -3.154 | -4.888 | -0.691 | -0.169 | -0.213 | 0.013 | 0.171 |
| 5 Basemat | 110748 | 0.513 | -1.335 | 0.892 | 0.012 | 0.081 | -0.101 | -0.050 | 0.016 |
| | 90306 | -1.129 | -1.348 | 5.098 | 2.431 | -0.453 | 4.997 | -4.224 | 3.195 |
| | 90310 | 0.257 | -1.778 | 0.199 | 0.866 | -0.448 | -1.064 | -0.701 | 2.209 |
| 5 Basemat @ Spent Fuel Pool | 90410 | -0.846 | -9.305 | -0.106 | 1.325 | 1.118 | 2.287 | 3.027 | -0.578 |
| | 90486 | -1.781 | -3.137 | -1.736 | 10.401 | 7.567 | -0.576 | -1.304 | 0.304 |
| | 90490 | -1.008 | -8.548 | 0.724 | 0.391 | 3.634 | 0.468 | 5.107 | -0.686 |
| 6 Slab EL4.65m | 90526 | 0.318 | -0.881 | -5.240 | 3.620 | -0.226 | -6.336 | -3.821 | -3.929 |
| | 93306 | 2.092 | 0.406 | -0.866 | 0.344 | -0.454 | -0.007 | -0.050 | 0.040 |
| | 93310 | 0.689 | 0.289 | 0.932 | 0.434 | -0.376 | 0.016 | -0.422 | 0.426 |
| | 93410 | 0.136 | 1.152 | 0.896 | 0.170 | 0.076 | 0.058 | -0.048 | 0.010 |

Table 3G.3-8

Results of NASTRAN Analysis: Seismic Load (Horizontal: East to West Direction)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~-10.50m | 60011 | -0.305 | -0.149 | -5.998 | -0.037 | -0.600 | -0.106 | 0.072 | -0.114 |
| | 60019 | 0.781 | 6.824 | -4.005 | 2.516 | 7.217 | -0.246 | 0.194 | 1.162 |
| | 70001 | 0.578 | 1.593 | -0.568 | -0.290 | 0.836 | -0.133 | -0.050 | -0.353 |
| | 70004 | 1.297 | 7.233 | 0.849 | 0.520 | 1.606 | -0.082 | -0.070 | -0.170 |
| 2 Exterior Wall @ EL4.65 ~-6.60m | 110708 | 0.389 | 4.429 | -0.006 | 0.653 | 1.780 | 0.058 | -0.045 | 0.720 |
| | 62011 | 0.094 | 0.084 | -3.589 | 0.029 | 0.050 | -0.003 | -0.023 | 0.015 |
| | 62019 | -0.276 | 1.277 | -1.922 | 0.018 | 0.013 | 0.002 | -0.003 | 0.005 |
| | 72001 | -0.034 | 1.601 | -0.535 | -0.026 | -0.035 | 0.000 | -0.018 | 0.019 |
| 3 Exterior Wall @ EL22.50 ~-24.60m | 72004 | -0.181 | 1.969 | 0.222 | -0.004 | -0.066 | -0.014 | -0.002 | 0.002 |
| | 64011 | -0.147 | -0.008 | -1.762 | 0.000 | -0.008 | 0.004 | 0.001 | 0.002 |
| | 64019 | -0.507 | 0.073 | -1.155 | -0.005 | 0.000 | -0.011 | -0.001 | 0.001 |
| | 74001 | -0.151 | 0.146 | 0.122 | -0.043 | -0.002 | -0.002 | 0.027 | 0.023 |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 74004 | -0.928 | 0.078 | 0.662 | 0.002 | 0.037 | -0.003 | 0.005 | 0.007 |
| | 60819 | -1.058 | 4.074 | -3.386 | 1.499 | 1.314 | -0.131 | -0.130 | 0.458 |
| | 70801 | -0.630 | 2.169 | -1.057 | -0.695 | -0.071 | 0.010 | 0.381 | -0.041 |
| | 70804 | -0.616 | 4.354 | 0.247 | 0.455 | 0.252 | -0.023 | 0.046 | -0.132 |
| 5 Basemat | 110748 | -0.603 | 1.998 | 0.158 | 0.073 | -0.104 | -0.077 | 0.151 | 0.013 |
| | 90306 | -7.020 | -1.678 | 2.018 | 4.100 | 1.283 | 1.171 | -1.859 | 4.307 |
| | 90310 | -1.063 | -0.549 | 0.488 | -0.168 | 0.634 | -1.187 | 1.745 | -0.066 |
| 5 Basemat @ Spent Fuel Pool | 90410 | 0.042 | 0.193 | 4.874 | -0.356 | -1.677 | 7.604 | -0.004 | -3.773 |
| | 90486 | 2.142 | 2.280 | 0.736 | -10.183 | -10.226 | -0.497 | 0.384 | -1.513 |
| | 90490 | 1.399 | 3.251 | 3.471 | 4.759 | -2.599 | 4.881 | -5.794 | -2.720 |
| 6 Slab EL4.65m | 90526 | 5.409 | 1.105 | 1.445 | -5.714 | -2.644 | 1.608 | 1.465 | 5.248 |
| | 93306 | 1.458 | 0.168 | -0.510 | 0.291 | -0.128 | -0.029 | 0.088 | 0.071 |
| | 93310 | 0.282 | 0.424 | 0.373 | -0.135 | 0.089 | -0.014 | 0.125 | -0.076 |
| | 93410 | -0.178 | 0.457 | 0.267 | 0.080 | -0.058 | 0.102 | -0.181 | -0.004 |

Table 3G.3-9

Results of NASTRAN Analysis: Seismic Load (Vertical: Upward Direction)

| Location | Element ID | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~-10.50m | 60011 | 0.237 | 0.892 | 0.173 | 0.094 | 0.598 | 0.019 | 0.041 | 0.182 |
| | 60019 | -0.011 | 1.002 | 0.045 | 0.418 | 0.643 | 0.024 | -0.043 | -0.161 |
| | 70001 | 0.086 | 0.151 | -0.057 | -0.234 | 0.061 | -0.040 | 0.078 | -0.063 |
| | 70004 | -0.068 | 0.734 | -0.014 | 0.088 | -0.065 | -0.036 | -0.049 | 0.248 |
| 2 Exterior Wall @ EL4.65 ~6.60m | 110708 | -0.073 | 0.890 | 0.252 | 0.007 | -0.104 | -0.013 | 0.020 | -0.145 |
| | 62011 | -0.038 | 0.740 | -0.089 | -0.046 | -0.216 | -0.005 | -0.006 | -0.070 |
| | 62019 | -0.031 | 0.479 | 0.022 | 0.009 | -0.103 | 0.037 | -0.002 | -0.030 |
| | 72001 | -0.037 | 0.168 | -0.046 | -0.060 | -0.013 | 0.001 | 0.001 | 0.001 |
| 3 Exterior Wall @ EL22.50 ~24.60m | 72004 | -0.042 | 0.351 | -0.065 | 0.013 | -0.028 | -0.010 | 0.007 | -0.001 |
| | 64011 | 0.074 | 0.362 | 0.009 | 0.160 | 0.783 | 0.007 | 0.005 | -0.104 |
| | 64019 | 0.115 | 0.434 | 0.063 | 0.096 | 0.554 | -0.074 | -0.088 | -0.081 |
| | 74001 | 0.011 | 0.008 | -0.090 | -0.073 | 0.066 | 0.067 | 0.033 | 0.043 |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 74004 | 0.072 | 0.273 | -0.060 | 0.116 | 0.496 | 0.085 | -0.025 | 0.100 |
| | 60819 | -0.094 | 0.776 | 0.189 | 0.638 | 0.313 | 0.132 | -0.012 | 0.080 |
| | 70801 | -0.101 | 0.231 | -0.025 | -0.577 | -0.059 | 0.022 | 0.280 | -0.005 |
| | 70804 | -0.108 | 0.486 | -0.056 | 0.279 | 0.215 | -0.028 | 0.053 | -0.043 |
| 5 Basemat | 110748 | -0.082 | 0.471 | 0.276 | 0.071 | 0.023 | 0.012 | -0.034 | 0.023 |
| | 90306 | 0.565 | 0.217 | -0.251 | -0.479 | 0.051 | -0.071 | 0.266 | -0.602 |
| | 90310 | 0.074 | 0.046 | 0.020 | 0.081 | 0.071 | 0.351 | -0.091 | 0.056 |
| 5 Basemat @ Spent Fuel Pool | 90410 | 0.227 | 0.457 | -0.215 | 0.383 | -0.074 | -0.688 | -0.700 | -0.044 |
| | 90486 | 0.238 | 0.360 | 0.037 | -1.472 | -1.155 | -0.114 | 0.048 | -0.091 |
| | 90490 | 0.313 | 0.318 | -0.037 | 0.467 | -0.279 | -0.063 | -0.771 | -0.060 |
| 6 Slab EL4.65m | 90526 | 0.280 | 0.287 | 0.065 | -0.581 | -0.217 | 0.031 | 0.106 | 0.572 |
| | 93306 | -0.098 | -0.010 | -0.024 | -0.025 | -0.010 | -0.006 | -0.020 | 0.063 |
| | 93310 | -0.016 | -0.031 | -0.130 | -0.017 | -0.011 | -0.019 | 0.010 | 0.002 |
| | 93410 | -0.230 | -0.215 | 0.188 | -0.048 | -0.010 | 0.037 | 0.019 | 0.007 |

Table 3G.3-10

Combined Forces and Moments: Selected Load Combination FB-4

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|--|---|-------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|--------|
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~-10.50m | 60011 | OTHR | -2.737 | -2.052 | -0.803 | -0.173 | -1.143 | 0.026 | -0.064 | -0.924 | |
| | | TEMP | -1.502 | -0.259 | -0.400 | 1.178 | 1.063 | 0.057 | -0.237 | -0.127 | |
| | 60019 | OTHR | -3.148 | -1.813 | -0.413 | 0.345 | -0.709 | 0.058 | -0.034 | -1.048 | |
| | | TEMP | 2.500 | -1.832 | 1.218 | -10.903 | -13.215 | -0.194 | 0.143 | -1.481 | |
| | 70001 | OTHR | -1.015 | -0.506 | -0.007 | -1.461 | -1.200 | -0.333 | 0.263 | 0.084 | |
| | | TEMP | 0.906 | 1.668 | -1.138 | -4.770 | -4.061 | 0.192 | 0.787 | 0.238 | |
| | 70004 | OTHR | -2.149 | -2.119 | -0.233 | 0.198 | -3.522 | -0.204 | -0.329 | 2.526 | |
| | | TEMP | 1.337 | 0.972 | -0.856 | -3.670 | -3.690 | 0.079 | 0.099 | -0.192 | |
| | 110708 | OTHR | -0.962 | -1.213 | -0.956 | 0.010 | 0.285 | 0.049 | -0.065 | 0.231 | |
| | | TEMP | -3.138 | -2.390 | -0.767 | -1.994 | -2.160 | 0.063 | -0.079 | 0.004 | |
| 2 Exterior Wall @ EL4.65 ~6.60m | 62011 | OTHR | -0.222 | -1.100 | -0.066 | 0.029 | 0.175 | 0.004 | 0.001 | 0.067 | |
| | | TEMP | 7.517 | 2.231 | 0.395 | -1.422 | -1.553 | 0.008 | -0.028 | -0.077 | |
| | 62019 | OTHR | -0.370 | -0.628 | -0.052 | 0.022 | 0.104 | -0.027 | 0.014 | 0.051 | |
| | | TEMP | 9.041 | 0.487 | -2.429 | -1.498 | -1.822 | -0.047 | 0.040 | -0.110 | |
| | 72001 | OTHR | -0.057 | -0.198 | 0.027 | -0.277 | -0.042 | 0.055 | 0.140 | 0.029 | |
| | | TEMP | 4.859 | -1.902 | 3.179 | -0.743 | -1.171 | 0.037 | -0.784 | 0.270 | |
| | 72004 | OTHR | -0.250 | -0.676 | -0.001 | 0.391 | 0.259 | 0.057 | 0.064 | -0.164 | |
| | | TEMP | 8.100 | 0.684 | 3.279 | -1.635 | -1.894 | 0.103 | -0.037 | 0.165 | |
| | 3 Exterior Wall @ EL22.50 ~24.60m | 64011 | OTHR | 0.178 | -0.303 | -0.027 | -0.119 | -0.575 | -0.003 | -0.003 | 0.060 |
| | | | TEMP | 5.733 | 0.223 | 0.232 | -1.265 | -0.551 | -0.017 | -0.001 | -0.097 |
| 64019 | | OTHR | -0.015 | -0.410 | -0.094 | -0.071 | -0.402 | 0.059 | 0.066 | 0.044 | |
| | | TEMP | 6.678 | 1.813 | 1.871 | -1.322 | -0.602 | 0.017 | -0.016 | -0.066 | |
| 74001 | | OTHR | -0.022 | -0.051 | 0.139 | 0.055 | -0.051 | -0.041 | -0.031 | -0.028 | |
| | | TEMP | 3.779 | -0.963 | -4.176 | -1.004 | -0.608 | 0.170 | -0.383 | 0.135 | |
| 74004 | | OTHR | -0.007 | -0.225 | 0.123 | -0.083 | -0.381 | -0.060 | 0.017 | -0.060 | |
| | | TEMP | 5.317 | 0.276 | -4.019 | -1.229 | -0.410 | -0.017 | 0.021 | 0.115 | |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | | 60819 | OTHR | -2.334 | -1.335 | -0.625 | 0.944 | 1.214 | 0.134 | 0.194 | 0.083 |
| | | | TEMP | -3.219 | -3.633 | -0.077 | -8.302 | -8.802 | -0.940 | -0.084 | -0.638 |
| | 70801 | OTHR | -1.608 | -0.652 | 0.059 | -3.966 | -0.351 | -0.356 | 2.343 | -0.304 | |
| | | TEMP | -0.481 | 3.632 | -0.332 | -4.661 | -4.190 | 0.057 | 0.188 | -0.029 | |
| | 70804 | OTHR | -1.403 | -1.206 | 0.000 | 3.050 | 1.858 | -0.305 | 0.375 | 0.172 | |
| | | TEMP | -1.938 | 0.338 | 0.097 | -3.821 | -4.074 | 0.238 | 0.034 | 0.052 | |
| | 110748 | OTHR | -0.691 | -0.518 | -0.330 | -0.109 | -0.094 | -0.059 | 0.084 | -0.057 | |
| | | TEMP | -1.313 | -2.347 | -0.367 | -1.777 | -2.122 | -0.033 | 0.178 | -0.081 | |
| | 5 Basemat | 90306 | OTHR | -4.235 | -3.033 | 0.703 | 0.859 | -0.805 | 0.364 | -0.536 | 1.463 |
| | | | TEMP | -0.634 | -0.066 | 0.499 | 2.237 | 1.085 | 0.227 | -0.205 | 0.263 |
| 90310 | | OTHR | -2.501 | -2.522 | 0.251 | -0.643 | -0.521 | 0.004 | 0.388 | 0.170 | |
| | | TEMP | 0.201 | 0.370 | 0.516 | 1.670 | 1.771 | 0.937 | 0.099 | -0.157 | |
| 90410 | | OTHR | -3.273 | -5.432 | 0.721 | -2.055 | 0.014 | 1.613 | 1.643 | -0.327 | |
| | | TEMP | -0.110 | -1.841 | 0.661 | 0.976 | 2.752 | 0.401 | 0.252 | -0.103 | |
| 5 Basemat @ Spent Fuel Pool | 90486 | OTHR | -3.127 | -5.295 | -0.362 | 1.273 | 0.945 | -0.104 | 0.018 | -0.187 | |
| | | TEMP | -3.174 | -1.293 | -0.171 | -9.075 | -9.112 | 0.593 | 0.295 | 0.057 | |
| | 90490 | OTHR | -3.280 | -4.336 | 0.118 | -2.228 | 0.060 | 0.418 | 1.301 | -0.277 | |
| | | TEMP | -1.627 | 3.605 | -0.276 | -15.412 | -11.258 | -0.420 | 1.596 | 1.460 | |
| | 90526 | OTHR | -4.216 | -6.330 | -0.372 | -0.922 | -8.022 | -0.214 | -0.259 | -2.159 | |
| | | TEMP | 3.507 | 0.114 | -0.219 | -9.167 | -4.524 | 0.050 | -1.095 | 0.770 | |
| 6 Slab EL4.65m | 93306 | OTHR | -0.018 | -0.246 | -0.064 | 0.089 | 0.182 | 0.016 | 0.034 | -0.161 | |
| | | TEMP | -1.177 | -0.080 | -1.177 | -0.072 | 0.022 | -0.025 | 0.087 | -0.034 | |
| | 93310 | OTHR | -0.056 | -0.047 | 0.110 | 0.085 | 0.051 | 0.010 | -0.042 | -0.005 | |
| | | TEMP | -2.822 | -2.799 | -3.622 | -1.004 | -1.005 | -0.292 | 0.367 | 0.361 | |
| | 93410 | OTHR | -0.075 | -0.185 | 0.056 | 0.215 | 0.055 | -0.050 | -0.097 | -0.019 | |
| | | TEMP | -0.879 | -3.076 | 0.337 | -0.163 | -0.033 | 0.012 | -0.109 | -0.035 | |

OTHR: Loads other than thermal loads

TEMP: Thermal loads

Table 3G.3-11

Combined Forces and Moments: Selected Load Combination FB-8

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|--|---------------------------------------|-------|--------------|--------------|---------------|---------------|---------------|----------------|--------------|--------------|--------|
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~-10.50m | 60011 | OTHR | -2.164 | -1.908 | -0.712 | -0.166 | -1.133 | 0.018 | -0.076 | -0.801 | |
| | | TEMP | -1.034 | -0.276 | -0.470 | 0.886 | 0.701 | 0.061 | -0.213 | -0.156 | |
| | 60019 | OTHR | -2.271 | -1.678 | -0.335 | 0.058 | -0.854 | 0.029 | 0.001 | -0.766 | |
| | | TEMP | 2.130 | -1.517 | 0.794 | -8.495 | -10.347 | -0.205 | 0.203 | -1.171 | |
| | 70001 | OTHR | -0.784 | -0.417 | 0.017 | -0.999 | -0.928 | -0.239 | 0.165 | 0.087 | |
| | | TEMP | 0.665 | 1.233 | -0.737 | -3.570 | -3.154 | 0.152 | 0.567 | 0.226 | |
| | 70004 | OTHR | -1.534 | -1.799 | -0.136 | 0.100 | -2.715 | -0.140 | -0.235 | 1.870 | |
| | | TEMP | 1.044 | 0.657 | -0.355 | -2.833 | -2.909 | 0.079 | 0.100 | -0.124 | |
| | 110708 | OTHR | -0.697 | -1.230 | -0.802 | 0.009 | 0.280 | 0.040 | -0.052 | 0.232 | |
| | | TEMP | -2.397 | -1.876 | -0.602 | -1.526 | -1.620 | 0.049 | -0.061 | 0.020 | |
| | 2 Exterior Wall @ EL4.65 ~6.60m | 62011 | OTHR | -0.173 | -1.093 | -0.029 | 0.026 | 0.136 | 0.004 | 0.002 | 0.048 |
| | | | TEMP | 5.927 | 1.780 | 0.309 | -1.104 | -1.219 | 0.001 | -0.029 | -0.064 |
| 62019 | | OTHR | -0.283 | -0.608 | -0.059 | 0.011 | 0.075 | -0.024 | 0.010 | 0.032 | |
| | | TEMP | 6.956 | 0.288 | -1.863 | -1.152 | -1.400 | -0.037 | 0.028 | -0.086 | |
| 72001 | | OTHR | -0.033 | -0.141 | 0.053 | -0.205 | -0.031 | 0.035 | 0.113 | 0.020 | |
| | | TEMP | | | | | | | | | |
| 72004 | | OTHR | -0.180 | -0.584 | 0.045 | 0.304 | 0.196 | 0.039 | 0.046 | -0.113 | |
| | | TEMP | 6.378 | 0.376 | 2.500 | -1.249 | -1.455 | 0.078 | -0.032 | 0.128 | |
| 3 Exterior Wall @ EL22.50 ~24.60m | 64011 | OTHR | -0.039 | -0.321 | -0.021 | -0.119 | -0.592 | -0.004 | -0.003 | 0.077 | |
| | | TEMP | 4.746 | 0.186 | 0.252 | -0.966 | -0.394 | -0.010 | 0.000 | -0.081 | |
| | 64019 | OTHR | -0.153 | -0.423 | -0.134 | -0.070 | -0.416 | 0.055 | 0.066 | 0.057 | |
| | | TEMP | 5.498 | 1.414 | 1.600 | -1.021 | -0.456 | 0.014 | -0.015 | -0.050 | |
| | 74001 | OTHR | -0.034 | -0.041 | 0.165 | 0.044 | -0.056 | -0.035 | -0.028 | -0.028 | |
| | | TEMP | 2.909 | -0.796 | -3.432 | -0.753 | -0.461 | 0.131 | -0.303 | 0.097 | |
| | 74004 | OTHR | -0.079 | -0.238 | 0.193 | -0.084 | -0.398 | -0.054 | 0.014 | -0.080 | |
| | | TEMP | 4.062 | 0.184 | -3.546 | -0.936 | -0.309 | -0.011 | 0.015 | 0.087 | |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 60819 | OTHR | -1.668 | -1.247 | -0.543 | 0.465 | 0.720 | 0.043 | 0.147 | 0.038 | |
| | | TEMP | -2.416 | -2.905 | -0.161 | -6.457 | -6.777 | -0.882 | -0.081 | -0.506 | |
| | 70801 | OTHR | -1.083 | -0.506 | 0.068 | -2.809 | -0.253 | -0.284 | 1.684 | -0.236 | |
| | | TEMP | -0.297 | 2.505 | -0.133 | -3.413 | -3.179 | 0.038 | 0.115 | -0.021 | |
| | 70804 | OTHR | -0.943 | -1.056 | 0.041 | 2.230 | 1.325 | -0.227 | 0.265 | 0.146 | |
| | | TEMP | -1.329 | 0.117 | 0.288 | -2.912 | -3.121 | 0.212 | 0.007 | 0.047 | |
| | 110748 | OTHR | -0.470 | -0.606 | -0.380 | -0.127 | -0.091 | -0.047 | 0.075 | -0.048 | |
| | | TEMP | -1.035 | -1.835 | -0.279 | -1.382 | -1.642 | -0.031 | 0.137 | -0.058 | |
| 5 Basemat | 90306 | OTHR | -3.546 | -2.473 | 0.817 | 0.956 | -0.727 | 0.438 | -0.628 | 1.486 | |
| | | TEMP | -0.913 | -0.080 | 0.219 | 1.890 | 0.787 | -0.008 | 0.045 | 0.256 | |
| | 90310 | OTHR | -1.931 | -2.021 | 0.183 | -0.544 | -0.487 | -0.176 | 0.264 | 0.168 | |
| | | TEMP | 0.105 | 0.315 | 0.323 | 1.205 | 1.335 | 0.598 | 0.186 | -0.135 | |
| | 90410 | OTHR | -2.673 | -4.668 | 0.639 | -1.817 | 0.063 | 1.621 | 1.666 | -0.265 | |
| | | TEMP | -0.147 | -1.227 | 0.653 | 0.548 | 2.081 | 0.464 | 0.252 | -0.198 | |
| 5 Basemat @ Spent Fuel Pool | 90486 | OTHR | -2.448 | -4.241 | -0.247 | 2.405 | 1.861 | -0.039 | -0.002 | -0.065 | |
| | | TEMP | -2.543 | -0.964 | 0.092 | -6.708 | -6.839 | 0.557 | 0.291 | 0.029 | |
| | 90490 | OTHR | -2.563 | -3.765 | 0.135 | -1.916 | 0.389 | 0.344 | 1.602 | -0.187 | |
| | | TEMP | -1.286 | 2.984 | -0.063 | -12.028 | -8.686 | -0.110 | 1.320 | 1.060 | |
| | 90526 | OTHR | -3.206 | -4.874 | -0.524 | -0.126 | -5.834 | -0.409 | -0.421 | -2.176 | |
| | | TEMP | 2.540 | 0.079 | 0.140 | -6.918 | -3.496 | 0.413 | -0.639 | 0.524 | |
| 6 Slab EL4.65m | 93306 | OTHR | 0.000 | -0.199 | -0.125 | 0.078 | 0.143 | 0.013 | 0.034 | -0.144 | |
| | | TEMP | -0.743 | -0.035 | -1.631 | -0.052 | 0.030 | -0.015 | 0.079 | -0.027 | |
| | 93310 | OTHR | -0.052 | -0.037 | 0.082 | 0.072 | 0.042 | 0.013 | -0.038 | -0.006 | |
| | | TEMP | -2.216 | -2.169 | -3.228 | -0.757 | -0.782 | -0.242 | 0.271 | 0.285 | |
| | 93410 | OTHR | -0.039 | -0.083 | -0.026 | 0.160 | 0.042 | -0.052 | -0.072 | -0.017 | |
| | | TEMP | -0.804 | -2.214 | 0.295 | -0.053 | -0.014 | 0.028 | -0.118 | -0.029 | |

Table 3G.3-12

Combined Forces and Moments: Selected Load Combination FB-9

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|--|------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 1 Exterior Wall and Pool Wall @ EL.-11.50 ~-10.50m | 60011 | OTHR | -2.160 | -1.894 | -0.706 | -0.164 | -1.116 | 0.016 | -0.073 | -0.792 |
| | | TEMP | -1.034 | -0.276 | -0.470 | 0.886 | 0.701 | 0.061 | -0.213 | -0.156 |
| | | EQEW | -0.305 | -0.149 | -5.998 | -0.037 | -0.600 | -0.106 | 0.072 | -0.114 |
| | | EQNS | -5.135 | -4.086 | -0.865 | -0.105 | -1.008 | -0.082 | 0.034 | -0.339 |
| | | EQZ | 0.237 | 0.892 | 0.173 | 0.094 | 0.598 | 0.019 | 0.041 | 0.182 |
| | | EQT | -0.003 | -0.070 | 0.879 | -0.004 | 0.029 | -0.007 | 0.020 | 0.005 |
| | | SPKW | -0.784 | -0.020 | 0.008 | 0.009 | 0.019 | 0.006 | -0.004 | -0.018 |
| | | SPKN | -0.181 | -0.001 | 0.246 | -0.098 | -0.142 | 0.026 | 0.037 | -0.249 |
| | 60019 | OTHR | -2.272 | -1.671 | -0.332 | 0.061 | -0.847 | 0.030 | 0.000 | -0.765 |
| | | TEMP | 2.130 | -1.517 | 0.794 | -8.495 | -10.347 | -0.205 | 0.203 | -1.171 |
| | | EQEW | 0.781 | 6.824 | -4.005 | 2.516 | 7.217 | -0.246 | 0.194 | 1.162 |
| | | EQNS | -5.900 | -6.560 | -0.955 | -0.197 | -3.119 | 0.204 | -0.371 | -0.304 |
| | | EQZ | -0.011 | 1.002 | 0.045 | 0.418 | 0.643 | 0.024 | -0.043 | -0.161 |
| | | EQT | 0.531 | -0.081 | 0.815 | -0.345 | -0.370 | -0.051 | 0.134 | -0.072 |
| | | SPKW | -0.630 | 0.366 | -0.119 | -0.346 | 0.711 | 0.048 | 0.016 | 0.295 |
| | | SPKN | -1.040 | -0.613 | -0.054 | 1.762 | -1.406 | 0.075 | -0.219 | -1.474 |
| | 70001 | OTHR | -0.783 | -0.416 | 0.018 | -1.002 | -0.927 | -0.239 | 0.167 | 0.086 |
| | | TEMP | 0.665 | 1.233 | -0.737 | -3.570 | -3.154 | 0.152 | 0.567 | 0.226 |
| | | EQEW | 0.578 | 1.593 | -0.568 | -0.290 | 0.836 | -0.133 | -0.050 | -0.353 |
| | | EQNS | -0.169 | -1.548 | -1.870 | 0.188 | -0.964 | 0.056 | -0.590 | 0.222 |
| | | EQZ | 0.086 | 0.151 | -0.057 | -0.234 | 0.061 | -0.040 | 0.078 | -0.063 |
| | | EQT | 0.010 | 0.138 | 0.371 | -0.003 | -0.068 | 0.000 | 0.156 | 0.053 |
| | | SPKW | -0.193 | -0.205 | 0.255 | -0.628 | -0.708 | -0.228 | -0.094 | 0.000 |
| | | SPKN | 0.004 | 0.061 | -0.351 | -0.680 | 0.198 | 0.059 | 0.332 | -0.163 |
| | 70004 | OTHR | -1.542 | -1.793 | -0.136 | 0.102 | -2.709 | -0.141 | -0.235 | 1.869 |
| | | TEMP | 1.044 | 0.657 | -0.355 | -2.833 | -2.909 | 0.079 | 0.100 | -0.124 |
| | | EQEW | 1.297 | 7.233 | 0.849 | 0.520 | 1.606 | -0.082 | -0.070 | -0.170 |
| | | EQNS | 1.716 | -5.368 | -4.964 | -1.178 | -2.731 | -0.040 | -0.060 | 0.566 |
| | | EQZ | -0.068 | 0.734 | -0.014 | 0.088 | -0.065 | -0.036 | -0.049 | 0.248 |
| | | EQT | -0.483 | 0.015 | 0.818 | 0.163 | 0.191 | 0.001 | -0.011 | -0.045 |
| | | SPKW | -0.692 | -0.689 | 0.187 | 0.209 | -2.329 | -0.137 | -0.211 | 1.384 |
| | | SPKN | -0.567 | 0.371 | -0.102 | 0.016 | 0.508 | -0.046 | -0.041 | -0.201 |
| | 110708 | OTHR | -0.695 | -1.223 | -0.795 | 0.008 | 0.278 | 0.040 | -0.052 | 0.231 |
| | | TEMP | -2.397 | -1.876 | -0.602 | -1.526 | -1.620 | 0.049 | -0.061 | 0.020 |
| | | EQEW | 0.389 | 4.429 | -0.006 | 0.653 | 1.780 | 0.058 | -0.045 | 0.720 |
| | | EQNS | 1.416 | -4.879 | 1.245 | -0.119 | -0.268 | -0.005 | -0.048 | -0.182 |
| EQZ | | -0.073 | 0.890 | 0.252 | 0.007 | -0.104 | -0.013 | 0.020 | -0.145 | |
| EQT | | -0.011 | -0.120 | 0.049 | -0.087 | -0.167 | -0.007 | 0.020 | -0.063 | |
| SPKW | | 0.143 | 0.042 | 0.240 | -0.013 | -0.069 | 0.018 | -0.031 | -0.045 | |
| SPKN | | -1.191 | 0.402 | -1.412 | 0.026 | 0.062 | 0.005 | 0.011 | 0.027 | |

- OTHR: Loads other than thermal and seismic loads
- TEMP: Thermal loads
- EQEW: Horizontal seismic loads in the E-W direction
- EQNS: Horizontal seismic loads in the N-S direction
- EQZ: Vertical seismic loads
- EQT: Torsional seismic loads
- SPKW: Dynamic soil pressure during a horizontal earthquake in the E-W direction
- SPKN: Dynamic soil pressure during a horizontal earthquake in the N-S direction

**Table 3G.3-12
Combined Forces and Moments: Selected Load Combination FB-9 (Continued)**

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---------------------------------------|------------|--------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 2 Exterior Wall @ EL4.65 ~6.60m | 62011 | OTHR | -0.172 | -1.079 | -0.027 | 0.026 | 0.138 | 0.004 | 0.003 | 0.048 |
| | | TEMP | 5.927 | 1.780 | 0.309 | -1.104 | -1.219 | 0.001 | -0.029 | -0.064 |
| | | EQEW | 0.094 | 0.084 | -3.589 | 0.029 | 0.050 | -0.003 | -0.023 | 0.015 |
| | | EQNS | 0.921 | -1.364 | -0.345 | 0.048 | 0.175 | 0.002 | -0.018 | 0.033 |
| | | EQZ | -0.038 | 0.740 | -0.089 | -0.046 | -0.216 | -0.005 | -0.006 | -0.070 |
| | | EQT | -0.087 | 0.010 | 0.456 | -0.005 | -0.009 | -0.004 | 0.003 | -0.002 |
| | | SPKW | -0.451 | 0.118 | -0.111 | 0.008 | 0.003 | 0.004 | -0.001 | 0.000 |
| | | SPKN | 0.234 | -0.069 | -0.044 | -0.046 | -0.006 | -0.020 | -0.008 | -0.009 |
| | 62019 | OTHR | -0.283 | -0.602 | -0.058 | 0.011 | 0.075 | -0.024 | 0.010 | 0.032 |
| | | TEMP | 6.956 | 0.288 | -1.863 | -1.152 | -1.400 | -0.037 | 0.028 | -0.086 |
| | | EQEW | -0.276 | 1.277 | -1.922 | 0.018 | 0.013 | 0.002 | -0.003 | 0.005 |
| | | EQNS | 0.761 | -1.226 | -2.242 | 0.019 | 0.134 | -0.012 | 0.009 | 0.018 |
| | | EQZ | -0.031 | 0.479 | 0.022 | 0.009 | -0.103 | 0.037 | -0.002 | -0.030 |
| | | EQT | -0.083 | -0.034 | 0.491 | -0.004 | -0.008 | -0.004 | -0.001 | -0.002 |
| | | SPKW | -0.456 | 0.110 | 0.287 | -0.037 | -0.040 | 0.004 | 0.012 | -0.002 |
| | | SPKN | 0.008 | -0.149 | -0.236 | 0.196 | 0.216 | 0.017 | -0.013 | 0.054 |
| | 72001 | OTHR | -0.033 | -0.151 | 0.062 | -0.205 | -0.031 | 0.035 | 0.113 | 0.020 |
| | | TEMP | 3.754 | -1.871 | 2.422 | -0.553 | -0.895 | 0.030 | -0.600 | 0.207 |
| | | EQEW | -0.034 | 1.601 | -0.535 | -0.026 | -0.035 | 0.000 | -0.018 | 0.019 |
| | | EQNS | -0.160 | -1.387 | -3.624 | -0.090 | -0.064 | 0.011 | -0.001 | 0.051 |
| | | EQZ | -0.037 | 0.168 | -0.046 | -0.060 | -0.013 | 0.001 | 0.001 | 0.001 |
| | | EQT | 0.047 | -0.061 | 0.574 | 0.018 | 0.011 | -0.004 | 0.003 | -0.009 |
| | | SPKW | 0.024 | -0.152 | 0.213 | -0.245 | -0.013 | 0.042 | 0.170 | 0.002 |
| | | SPKN | -0.585 | -0.117 | -0.684 | -0.223 | -0.066 | -0.011 | 0.011 | 0.019 |
| | 72004 | OTHR | -0.177 | -0.586 | 0.060 | 0.304 | 0.195 | 0.039 | 0.046 | -0.113 |
| | | TEMP | 6.378 | 0.376 | 2.500 | -1.249 | -1.455 | 0.078 | -0.032 | 0.128 |
| | | EQEW | -0.181 | 1.969 | 0.222 | -0.004 | -0.066 | -0.014 | -0.002 | 0.002 |
| | | EQNS | -0.274 | -1.755 | -4.201 | -0.033 | -0.035 | -0.003 | 0.016 | 0.007 |
| | | EQZ | -0.042 | 0.351 | -0.065 | 0.013 | -0.028 | -0.010 | 0.007 | -0.001 |
| | | EQT | 0.123 | 0.026 | 0.583 | 0.010 | 0.011 | 0.000 | -0.002 | -0.002 |
| SPKW | | -0.018 | -0.199 | 0.074 | 0.409 | 0.284 | 0.026 | 0.054 | -0.148 | |
| SPKN | | -0.700 | 0.105 | -0.515 | -0.081 | -0.061 | 0.005 | 0.024 | 0.010 | |

**Table 3G.3-12
Combined Forces and Moments: Selected Load Combination FB-9 (Continued)**

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) |
|---|------------|------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|
| 3 Exterior Wall @ EL22.50 ~24.60m | 64011 | OTHR | -0.001 | -0.318 | -0.023 | -0.119 | -0.590 | -0.004 | -0.003 | 0.077 |
| | | TEMP | 4.746 | 0.186 | 0.252 | -0.966 | -0.394 | -0.010 | 0.000 | -0.081 |
| | | EQEW | -0.147 | -0.008 | -1.762 | 0.000 | -0.008 | 0.004 | 0.001 | 0.002 |
| | | EQNS | 3.743 | -0.254 | -0.233 | -0.057 | -0.192 | 0.013 | 0.007 | 0.030 |
| | | EQZ | 0.074 | 0.362 | 0.009 | 0.160 | 0.783 | 0.007 | 0.005 | -0.104 |
| | | EQT | 0.019 | 0.000 | 0.197 | 0.000 | 0.001 | -0.002 | -0.002 | -0.001 |
| | | SPKW | -0.131 | 0.003 | -0.003 | 0.002 | 0.003 | -0.004 | -0.002 | 0.000 |
| | | SPKN | 0.263 | -0.006 | -0.035 | -0.008 | -0.022 | 0.020 | 0.011 | 0.003 |
| | 64019 | OTHR | -0.129 | -0.416 | -0.121 | -0.070 | -0.414 | 0.054 | 0.065 | 0.057 |
| | | TEMP | 5.498 | 1.414 | 1.600 | -1.021 | -0.456 | 0.014 | -0.015 | -0.050 |
| | | EQEW | -0.507 | 0.073 | -1.155 | -0.005 | 0.000 | -0.011 | -0.001 | 0.001 |
| | | EQNS | 2.758 | -0.032 | -0.696 | -0.059 | -0.139 | -0.046 | -0.028 | 0.025 |
| | | EQZ | 0.115 | 0.434 | 0.063 | 0.096 | 0.554 | -0.074 | -0.088 | -0.081 |
| | | EQT | -0.111 | -0.014 | 0.115 | 0.007 | 0.007 | 0.005 | 0.003 | -0.001 |
| | | SPKW | -0.088 | -0.001 | 0.062 | 0.000 | 0.017 | 0.001 | -0.001 | -0.007 |
| | | SPKN | 0.237 | 0.005 | -0.129 | 0.000 | -0.044 | -0.024 | -0.010 | 0.011 |
| | 74001 | OTHR | -0.030 | -0.042 | 0.155 | 0.045 | -0.056 | -0.035 | -0.029 | -0.028 |
| | | TEMP | 2.909 | -0.796 | -3.432 | -0.753 | -0.461 | 0.131 | -0.303 | 0.097 |
| | | EQEW | -0.151 | 0.146 | 0.122 | -0.043 | -0.002 | -0.002 | 0.027 | 0.023 |
| | | EQNS | 0.085 | -0.152 | -1.111 | 0.036 | 0.049 | -0.049 | 0.041 | -0.012 |
| | | EQZ | 0.011 | 0.008 | -0.090 | -0.073 | 0.066 | 0.067 | 0.033 | 0.043 |
| | | EQT | 0.059 | -0.022 | -0.141 | 0.009 | -0.001 | 0.008 | -0.013 | -0.001 |
| | | SPKW | 0.001 | -0.011 | 0.032 | -0.002 | -0.010 | 0.027 | -0.018 | 0.003 |
| | | SPKN | -0.008 | 0.018 | -0.048 | -0.008 | 0.011 | -0.023 | 0.019 | 0.004 |
| | 74004 | OTHR | -0.059 | -0.238 | 0.174 | -0.084 | -0.396 | -0.054 | 0.014 | -0.079 |
| | | TEMP | 4.062 | 0.184 | -3.546 | -0.936 | -0.309 | -0.011 | 0.015 | 0.087 |
| | | EQEW | -0.928 | 0.078 | 0.662 | 0.002 | 0.037 | -0.003 | 0.005 | 0.007 |
| | | EQNS | -1.414 | -0.263 | -1.644 | 0.036 | 0.028 | -0.033 | 0.014 | 0.010 |
| | | EQZ | 0.072 | 0.273 | -0.060 | 0.116 | 0.496 | 0.085 | -0.025 | 0.100 |
| | | EQT | 0.361 | 0.000 | -0.182 | -0.001 | -0.005 | -0.001 | 0.001 | -0.001 |
| | | SPKW | 0.098 | -0.011 | 0.014 | 0.003 | -0.036 | 0.014 | -0.008 | -0.008 |
| | | SPKN | -0.163 | 0.003 | -0.056 | 0.001 | 0.023 | -0.001 | 0.000 | 0.010 |

Table 3G.3-12
Combined Forces and Moments: Selected Load Combination FB-9 (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|--|------------|-------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|-------|
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 60819 | OTHR | -1.669 | -1.240 | -0.541 | 0.467 | 0.720 | 0.046 | 0.147 | 0.038 | |
| | | TEMP | -2.416 | -2.905 | -0.161 | -6.457 | -6.777 | -0.882 | -0.081 | -0.506 | |
| | | EQEW | -1.058 | 4.074 | -3.386 | 1.499 | 1.314 | -0.131 | -0.130 | 0.458 | |
| | | EQNS | -0.758 | -4.288 | -2.652 | -0.157 | -0.613 | 0.392 | 0.139 | -0.196 | |
| | | EQZ | -0.094 | 0.776 | 0.189 | 0.638 | 0.313 | 0.132 | -0.012 | 0.080 | |
| | | EQT | 0.039 | -0.018 | 0.852 | -0.241 | -0.053 | -0.173 | 0.006 | -0.031 | |
| | | SPKW | -1.557 | 0.342 | -0.035 | -0.975 | -0.163 | 0.150 | 0.201 | 0.123 | |
| | | SPKN | -0.366 | -0.506 | -0.162 | 4.585 | 2.121 | 0.239 | -0.150 | -0.403 | |
| | 70801 | OTHR | -1.085 | -0.507 | 0.076 | -2.811 | -0.254 | -0.284 | 1.684 | -0.236 | |
| | | TEMP | -0.297 | 2.505 | -0.133 | -3.413 | -3.179 | 0.038 | 0.115 | -0.021 | |
| | | EQEW | -0.630 | 2.169 | -1.057 | -0.695 | -0.071 | 0.010 | 0.381 | -0.041 | |
| | | EQNS | 0.400 | -1.574 | -4.088 | 0.042 | -0.070 | -0.183 | -0.223 | -0.086 | |
| | | EQZ | -0.101 | 0.231 | -0.025 | -0.577 | -0.059 | 0.022 | 0.280 | -0.005 | |
| | | EQT | 0.043 | -0.041 | 0.804 | 0.071 | 0.010 | 0.014 | 0.010 | 0.012 | |
| | | SPKW | -0.436 | -0.370 | 0.295 | -2.574 | -0.195 | -0.446 | 1.645 | -0.341 | |
| | | SPKN | -1.752 | -0.185 | -0.222 | -1.291 | -0.267 | 0.199 | 0.186 | 0.091 | |
| | 70804 | OTHR | -0.951 | -1.050 | 0.052 | 2.231 | 1.324 | -0.227 | 0.266 | 0.146 | |
| | | TEMP | -1.329 | 0.117 | 0.288 | -2.912 | -3.121 | 0.212 | 0.007 | 0.047 | |
| | | EQEW | -0.616 | 4.354 | 0.247 | 0.455 | 0.252 | -0.023 | 0.046 | -0.132 | |
| | | EQNS | 1.104 | -3.154 | -4.888 | -0.691 | -0.169 | -0.213 | 0.013 | 0.171 | |
| | | EQZ | -0.108 | 0.486 | -0.056 | 0.279 | 0.215 | -0.028 | 0.053 | -0.043 | |
| | | EQT | 0.028 | -0.034 | 0.807 | 0.108 | 0.000 | 0.013 | -0.006 | -0.011 | |
| | | SPKW | -0.326 | -0.404 | 0.169 | 2.457 | 1.246 | -0.293 | 0.247 | 0.292 | |
| | | SPKN | -1.538 | 0.304 | -0.069 | -0.333 | -0.122 | -0.061 | 0.113 | -0.065 | |
| | 110748 | OTHR | -0.471 | -0.600 | -0.376 | -0.127 | -0.091 | -0.047 | 0.075 | -0.048 | |
| | | TEMP | -1.035 | -1.835 | -0.279 | -1.382 | -1.642 | -0.031 | 0.137 | -0.058 | |
| | | EQEW | -0.603 | 1.998 | 0.158 | 0.073 | -0.104 | -0.077 | 0.151 | 0.013 | |
| | | EQNS | 0.513 | -1.335 | 0.892 | 0.012 | 0.081 | -0.101 | -0.050 | 0.016 | |
| | | EQZ | -0.082 | 0.471 | 0.276 | 0.071 | 0.023 | 0.012 | -0.034 | 0.023 | |
| | | EQT | 0.007 | -0.050 | 0.036 | -0.011 | 0.010 | 0.007 | -0.008 | -0.008 | |
| | | SPKW | 0.132 | 0.148 | 0.257 | 0.048 | 0.020 | 0.007 | 0.014 | -0.010 | |
| | | SPKN | -1.340 | 0.193 | -0.712 | 0.050 | -0.032 | -0.045 | 0.009 | -0.026 | |
| | 5 Basemat | 90306 | OTHR | -3.518 | -2.459 | 0.794 | 0.927 | -0.714 | 0.425 | -0.613 | 1.452 |
| | | | TEMP | -0.913 | -0.080 | 0.219 | 1.890 | 0.787 | -0.008 | 0.045 | 0.256 |
| | | | EQEW | -7.020 | -1.678 | 2.018 | 4.100 | 1.283 | 1.171 | -1.859 | 4.307 |
| | | | EQNS | -1.129 | -1.348 | 5.098 | 2.431 | -0.453 | 4.997 | -4.224 | 3.195 |
| EQZ | | | 0.565 | 0.217 | -0.251 | -0.479 | 0.051 | -0.071 | 0.266 | -0.602 | |
| EQT | | | 0.711 | 0.042 | 0.932 | -0.272 | -0.239 | 0.822 | -0.789 | 0.047 | |
| SPKW | | | -0.153 | -0.741 | -0.097 | -0.210 | -0.732 | 0.016 | 0.107 | 0.132 | |
| SPKN | | | -0.468 | 0.019 | -0.044 | -0.232 | 0.035 | -0.067 | 0.111 | -0.049 | |
| 90310 | | OTHR | -1.932 | -2.011 | 0.186 | -0.537 | -0.478 | -0.161 | 0.268 | 0.159 | |
| | | TEMP | 0.105 | 0.315 | 0.323 | 1.205 | 1.335 | 0.598 | 0.186 | -0.135 | |
| | | EQEW | -1.063 | -0.549 | 0.488 | -0.168 | 0.634 | -1.187 | 1.745 | -0.066 | |
| | | EQNS | 0.257 | -1.778 | 0.199 | 0.866 | -0.448 | -1.064 | -0.701 | 2.209 | |
| | | EQZ | 0.074 | 0.046 | 0.020 | 0.081 | 0.071 | 0.351 | -0.091 | 0.056 | |
| | | EQT | 0.248 | -0.217 | -0.089 | 0.133 | -0.109 | -0.087 | -0.534 | 0.620 | |
| | | SPKW | -0.032 | -0.534 | 0.000 | -0.001 | -0.414 | 0.109 | 0.076 | 0.092 | |
| | | SPKN | -0.518 | -0.108 | -0.067 | -0.511 | -0.059 | 0.022 | 0.035 | 0.203 | |
| 90410 | | OTHR | -2.656 | -4.629 | 0.627 | -1.775 | 0.067 | 1.586 | 1.643 | -0.262 | |
| | | TEMP | -0.147 | -1.227 | 0.653 | 0.548 | 2.081 | 0.464 | 0.252 | -0.198 | |
| | | EQEW | 0.042 | 0.193 | 4.874 | -0.356 | -1.677 | 7.604 | -0.004 | -3.773 | |
| | | EQNS | -0.846 | -9.305 | -0.106 | 1.325 | 1.118 | 2.287 | 3.027 | -0.578 | |
| | | EQZ | 0.227 | 0.457 | -0.215 | 0.383 | -0.074 | -0.688 | -0.700 | -0.044 | |
| | | EQT | -0.011 | -0.048 | -1.046 | 0.064 | 0.167 | -1.141 | 0.067 | 0.978 | |
| | | SPKW | -0.039 | -1.239 | -0.005 | -0.014 | 0.013 | -0.065 | 0.048 | -0.024 | |
| | | SPKN | -0.799 | -0.444 | -0.222 | -1.042 | -0.224 | -0.204 | 0.005 | 0.285 | |

Table 3G.3-12
Combined Forces and Moments: Selected Load Combination FB-9 (Continued)

| Location | Element ID | | Nx (MN/m) | Ny (MN/m) | Nxy (MN/m) | Mx (MNm/m) | My (MNm/m) | Mxy (MNm/m) | Qx (MN/m) | Qy (MN/m) | |
|-----------------------------------|----------------|-------|-----------|-----------|------------|------------|------------|-------------|-----------|-----------|--------|
| 5 Basemat @ Spent Fuel Pool | 90486 | OTHR | -2.443 | -4.237 | -0.259 | 2.310 | 1.791 | -0.038 | -0.010 | -0.065 | |
| | | TEMP | -2.543 | -0.964 | 0.092 | -6.708 | -6.839 | 0.557 | 0.291 | 0.029 | |
| | | EQEW | 2.142 | 2.280 | 0.736 | -10.183 | -10.226 | -0.497 | 0.384 | -1.513 | |
| | | EQNS | -1.781 | -3.137 | -1.736 | 10.401 | 7.567 | -0.576 | -1.304 | 0.304 | |
| | | EQZ | 0.238 | 0.360 | 0.037 | -1.472 | -1.155 | -0.114 | 0.048 | -0.091 | |
| | | EQT | 0.241 | -0.186 | 0.545 | 0.034 | 0.058 | 0.003 | 0.063 | 0.066 | |
| | | SPKW | 0.409 | -1.564 | 0.063 | -0.400 | -0.525 | -0.058 | -0.018 | -0.178 | |
| | | SPKN | -1.949 | 0.191 | -0.489 | -1.030 | -0.405 | -0.229 | 0.188 | 0.048 | |
| | 90490 | OTHR | -2.556 | -3.733 | 0.125 | -1.893 | 0.373 | 0.333 | 1.573 | -0.183 | |
| | | TEMP | -1.286 | 2.984 | -0.063 | -12.028 | -8.686 | -0.110 | 1.320 | 1.060 | |
| | | EQEW | 1.399 | 3.251 | 3.471 | 4.759 | -2.599 | 4.881 | -5.794 | -2.720 | |
| | | EQNS | -1.008 | -8.548 | 0.724 | 0.391 | 3.634 | 0.468 | 5.107 | -0.686 | |
| | | EQZ | 0.313 | 0.318 | -0.037 | 0.467 | -0.279 | -0.063 | -0.771 | -0.060 | |
| | | EQT | -0.017 | 0.643 | -0.941 | -0.476 | -0.201 | -1.073 | 0.096 | 0.897 | |
| | | SPKW | 0.350 | -0.477 | -0.026 | 1.128 | -0.066 | 0.109 | -0.362 | -0.099 | |
| | | SPKN | -2.117 | -0.870 | -0.016 | -4.735 | -0.918 | -0.139 | 0.657 | -0.199 | |
| | 90526 | OTHR | -3.223 | -4.868 | -0.513 | -0.158 | -5.830 | -0.398 | -0.412 | -2.142 | |
| | | TEMP | 2.540 | 0.079 | 0.140 | -6.918 | -3.496 | 0.413 | -0.639 | 0.524 | |
| | | EQEW | 5.409 | 1.105 | 1.445 | -5.714 | -2.644 | 1.608 | 1.465 | 5.248 | |
| | | EQNS | 0.318 | -0.881 | -5.240 | 3.620 | -0.226 | -6.336 | -3.821 | -3.929 | |
| | | EQZ | 0.280 | 0.287 | 0.065 | -0.581 | -0.217 | 0.031 | 0.106 | 0.572 | |
| | | EQT | -0.901 | -0.065 | 1.085 | 0.272 | 0.296 | 1.019 | 0.799 | 0.021 | |
| | | SPKW | -0.666 | -2.016 | 0.234 | -1.004 | -5.108 | 0.230 | 0.130 | -0.816 | |
| | | SPKN | -0.777 | 0.169 | -0.292 | -0.414 | 0.494 | -0.200 | 0.059 | 0.260 | |
| | 6 Slab EL4.65m | 93306 | OTHR | -0.004 | -0.201 | -0.094 | 0.076 | 0.143 | 0.012 | 0.034 | -0.144 |
| | | | TEMP | -0.743 | -0.035 | -1.631 | -0.052 | 0.030 | -0.015 | 0.079 | -0.027 |
| | | | EQEW | 1.458 | 0.168 | -0.510 | 0.291 | -0.128 | -0.029 | 0.088 | 0.071 |
| | | | EQNS | 2.092 | 0.406 | -0.866 | 0.344 | -0.454 | -0.007 | -0.050 | 0.040 |
| | | | EQZ | -0.098 | -0.010 | -0.024 | -0.025 | -0.010 | -0.006 | -0.020 | 0.063 |
| | | | EQT | 0.050 | 0.018 | 0.055 | 0.021 | -0.027 | -0.005 | -0.020 | -0.010 |
| SPKW | | | -0.134 | -0.743 | -0.167 | 0.052 | 0.244 | -0.002 | 0.003 | -0.053 | |
| SPKN | | | -0.311 | -0.002 | 0.109 | 0.010 | -0.010 | 0.010 | -0.010 | -0.004 | |
| 93310 | | OTHR | -0.051 | -0.036 | 0.097 | 0.070 | 0.043 | 0.014 | -0.036 | -0.006 | |
| | | TEMP | -2.216 | -2.169 | -3.228 | -0.757 | -0.782 | -0.242 | 0.271 | 0.285 | |
| | | EQEW | 0.282 | 0.424 | 0.373 | -0.135 | 0.089 | -0.014 | 0.125 | -0.076 | |
| | | EQNS | 0.689 | 0.289 | 0.932 | 0.434 | -0.376 | 0.016 | -0.422 | 0.426 | |
| | | EQZ | -0.016 | -0.031 | -0.130 | -0.017 | -0.011 | -0.019 | 0.010 | 0.002 | |
| | | EQT | 0.054 | -0.001 | 0.148 | 0.071 | -0.050 | 0.006 | -0.067 | 0.058 | |
| | | SPKW | 0.000 | -0.285 | 0.082 | -0.024 | 0.089 | -0.019 | 0.046 | -0.055 | |
| | | SPKN | -0.266 | -0.003 | 0.098 | 0.118 | -0.026 | -0.020 | -0.072 | 0.054 | |
| 93410 | | OTHR | -0.035 | -0.087 | -0.032 | 0.158 | 0.042 | -0.053 | -0.071 | -0.017 | |
| | | TEMP | -0.804 | -2.214 | 0.295 | -0.053 | -0.014 | 0.028 | -0.118 | -0.029 | |
| | | EQEW | -0.178 | 0.457 | 0.267 | 0.080 | -0.058 | 0.102 | -0.181 | -0.004 | |
| | | EQNS | 0.136 | 1.152 | 0.896 | 0.170 | 0.076 | 0.058 | -0.048 | 0.010 | |
| | | EQZ | -0.230 | -0.215 | 0.188 | -0.048 | -0.010 | 0.037 | 0.019 | 0.007 | |
| | | EQT | 0.010 | -0.185 | 0.079 | -0.008 | 0.006 | -0.001 | 0.014 | 0.005 | |
| | | SPKW | 0.006 | -0.596 | 0.230 | -0.005 | 0.003 | -0.005 | -0.002 | 0.000 | |
| | | SPKN | -0.926 | 0.019 | 0.217 | 0.248 | 0.043 | 0.060 | -0.100 | 0.003 | |

Table 3G.3-13

Sectional Thicknesses and Rebar Ratios Used in the Evaluation

| Location | Element ID | Thickness (m) | Primary Reinforcement | | | | Shear Tie | | |
|---|----------------------------------|---------------|-----------------------|-------------|-----------|----------------------|-----------|-------------|-----------|
| | | | Position | Direction 1 | | Direction 2 | | Arrangement | Ratio (%) |
| | | | | Arrangement | Ratio (%) | Arrangement | Ratio (%) | | |
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~-10.50m | 60011 | 2.0 | Inside | 3-#11@200 | 0.755 | 3-#11@200 | 0.755 | #6@400x400 | 0.177 |
| | | | Outside | 3-#11@200 | 0.755 | 3-#11@200 | 0.755 | | |
| | 60019 | 3.6 | Inside | 3-#11@200 | 0.419 | 3-#11@200 +2-#11@200 | 0.699 | #6@400x400 | 0.177 |
| | | | Outside | 3-#11@200 | 0.419 | 3-#11@200 +1-#11@200 | 0.559 | | |
| | 70001 | 2.0 | Inside | 4-#11@200 | 1.006 | 4-#11@200 | 1.006 | #6@400x400 | 0.177 |
| | | | Outside | 4-#11@200 | 1.006 | 4-#11@200 | 1.006 | | |
| | 70004 | 2.0 | Inside | 4-#11@200 | 1.006 | 4-#11@200 | 1.006 | #6@200x200 | 0.710 |
| | | | Outside | 4-#11@200 | 1.006 | 4-#11@200 +1-#11@200 | 1.258 | | |
| | 110708 | 1.5 | Inside | 2-#11@200 | 0.671 | 3-#11@200 +1-#11@200 | 1.342 | #6@400x200 | 0.355 |
| | | | Outside | 2-#11@200 | 0.671 | 3-#11@200 | 1.006 | | |
| 2 Exterior Wall @ EL4.65 ~-6.60m | 62011 62019 72001 72004 | 1.0 | Inside | 2-#11@200 | 1.006 | 2-#11@200 | 1.006 | #5@400x400 | 0.125 |
| | | | Outside | 3-#11@200 | 1.510 | 3-#11@200 | 1.510 | | |
| 3 Exterior Wall @ EL22.50 ~-24.60m | 64011 64019 | 1.0 | Inside | 2-#11@200 | 1.006 | 2-#11@200 | 1.006 | #5@400x400 | 0.125 |
| | | | Outside | 2-#11@200 | 1.006 | 2-#11@200 | 1.006 | | |
| | 74001 74004 | 1.0 | Inside | 2-#11@200 | 1.006 | 2-#11@200 | 1.006 | #5@400x400 | 0.125 |
| | | | Outside | 3-#11@200 | 1.510 | 3-#11@200 | 1.510 | | |

Note *: Exterior Wall, Pool Wall Direction1 : Horizontal, Direction2 : Vertical
 Basemat, Slab Direction1 : N-S, Direction2 : E-W

Table 3G.3-13
Sectional Thicknesses and Rebar Ratios Used in the Evaluation (Continued)

| Location | Element ID | Thickness (m) | Primary Reinforcement | | | | Shear Tie | | |
|--|-------------------------|---------------|-----------------------|--------------------------|-----------|-------------------------|-----------|-------------|-----------|
| | | | Position | Direction 1 [*] | | Direction2 [*] | | Arrangement | Ratio (%) |
| | | | | Arrangement | Ratio (%) | Arrangement | Ratio (%) | | |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 60819 | 3.6 | Inside | 3-#11@200 | 0.419 | 3-#11@200 | 0.419 | #6@400x400 | 0.177 |
| | | | Outside | 3-#11@200 | 0.419 | 3-#11@200 | 0.419 | | |
| | 70801 | 2.0 | Inside | 4-#11@200 | 1.006 | 4-#11@200 | 1.006 | #6@200x200 | 0.710 |
| | | | Outside | 4-#11@200 | 1.006 | 4-#11@200 | 1.006 | | |
| | 70804 | 2.0 | Inside | 4-#11@200 | 1.006 | 4-#11@200 | 1.006 | #6@400x400 | 0.177 |
| | | | Outside | 4-#11@200 | 1.006 | 4-#11@200 | 1.006 | | |
| | 110748 | 1.5 | Inside | 2-#11@200 | 0.671 | 3-#11@200 | 1.006 | #6@400x400 | 0.177 |
| | | | Outside | 2-#11@200 | 0.671 | 3-#11@200 | 1.006 | | |
| 5 Basemat | 90306 90310 90410 | 4.0 | Top | 3-#11@200 | 0.377 | 3-#11@200 | 0.377 | #9@400x200 | 0.807 |
| | | | Bottom | 5-#11@200 | 0.629 | 5-#11@200 | 0.629 | | |
| 5 Basemat @ Spent Fuel Pool | 90486 | 4.0 | Top | 3-#11@200 | 0.377 | 3-#11@200 | 0.377 | #9@400x400 | 0.403 |
| | | | Bottom | 5-#11@200 | 0.629 | 5-#11@200 | 0.629 | | |
| | 90490 90526 | 4.0 | Top | 3-#11@200 | 0.377 | 3-#11@200 | 0.377 | #9@400x200 | 0.807 |
| | | | Bottom | 5-#11@200 | 0.629 | 5-#11@200 | 0.629 | | |
| 6 Slab EL4.65m | 93306 93310 93410 | 1.3 | Top | 2-#11@200 | 0.774 | 2-#11@200 | 0.774 | #5@200x200 | 0.500 |
| | | | Bottom | 2-#11@200 | 0.774 | 2-#11@200 | 0.774 | | |

Note *: Exterior Wall, Pool Wall Direction1 : Horizontal, Direction2 : Vertical
 Basemat, Slab Direction1 : N-S, Direction2 : E-W

Table 3G.3-14

Rebar and Concrete Stresses: Selected Load Combination FB-4

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|---|------------|-----------------------|-----------|------------------------------------|------------|-------------------------|------------|-----------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 ¹ | | Direction2 ² | | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~10.50m | 60011 | -3.4 | -29.3 | -5.6 | -19.5 | -6.9 | -3.9 | 372.2 |
| | 60019 | -3.8 | -29.0 | -6.7 | 5.6 | -20.3 | 30.2 | 370.1 |
| | 70001 | -7.9 | -29.0 | -19.5 | 79.3 | -7.3 | 73.8 | 370.1 |
| | 70004 | -10.3 | -29.0 | -6.2 | 8.1 | -33.7 | 97.4 | 370.1 |
| | 110708 | -7.2 | -29.1 | -24.2 | 36.7 | -16.1 | 20.3 | 370.3 |
| 2 Exterior Wall @ EL4.65 ~6.60m | 62011 | -2.4 | -29.3 | 26.4 | 74.6 | -10.8 | 14.0 | 372.2 |
| | 62019 | -9.2 | -29.3 | 43.9 | 104.0 | -22.0 | 73.8 | 372.2 |
| | 72001 | -9.5 | -29.3 | 21.0 | 115.9 | -19.8 | 80.7 | 372.2 |
| | 72004 | -4.4 | -29.3 | 67.1 | 47.0 | -19.6 | 33.3 | 372.2 |
| 3 Exterior Wall @ EL22.50 ~24.60m | 64011 | -8.0 | -29.3 | 21.6 | 110.0 | -12.8 | 92.6 | 372.2 |
| | 64019 | -7.2 | -29.3 | 35.5 | 135.3 | 6.4 | 101.5 | 372.2 |
| | 74001 | -4.5 | -29.3 | 21.2 | 92.2 | 1.6 | 78.7 | 372.2 |
| | 74004 | -7.7 | -29.3 | 12.8 | 106.6 | 1.2 | 116.3 | 372.2 |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 60819 | -3.8 | -29.0 | -18.8 | 5.4 | -15.6 | 6.1 | 370.1 |
| | 70801 | -13.4 | -29.0 | -43.0 | 141.5 | 7.1 | 68.8 | 370.1 |
| | 70804 | -2.5 | -29.0 | -14.4 | -5.7 | -3.7 | 1.6 | 370.1 |
| | 110748 | -6.4 | -29.1 | -13.0 | 32.0 | -19.1 | 30.7 | 370.3 |
| 5 Basemat | 90306 | -2.1 | -23.5 | -13.9 | -3.9 | -1.5 | -4.8 | 372.2 |
| | 90310 | -0.8 | -23.5 | -4.6 | -4.7 | -2.6 | -1.8 | 372.2 |
| | 90410 | -2.6 | -23.5 | -1.2 | -17.8 | -7.5 | -6.1 | 372.2 |
| 5 Basemat @ Spent Fuel Pool | 90486 | -3.8 | -23.2 | 2.1 | 1.3 | -20.8 | -23.2 | 370.1 |
| | 90490 | -4.8 | -23.2 | 29.6 | 4.5 | -29.7 | -8.1 | 370.1 |
| | 90526 | -5.5 | -23.2 | 7.2 | 20.6 | -7.3 | -36.4 | 370.1 |
| 6 Slab EL4.65m | 93306 | -1.7 | -29.3 | 16.2 | 3.2 | 41.4 | 1.3 | 372.2 |
| | 93310 | -7.5 | -29.3 | -12.3 | 56.0 | -13.3 | 58.3 | 372.2 |
| | 93410 | -2.5 | -29.3 | -1.5 | -3.0 | -15.3 | -15.7 | 372.2 |

Note: Negative value means compression.

Note *: Exterior Wall, Pool Wall Direction1 : Horizontal, Direction2 : Vertical
Basemat, Slab Direction1 : N-S, Direction2 : E-W

Table 3G.3-15

Rebar and Concrete Stresses: Selected Load Combination FB-8

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|---|------------|-----------------------|-----------|------------------------------------|------------|-------------------------|------------|-----------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 ¹ | | Direction2 ² | | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~10.50m | 60011 | -2.6 | -29.3 | -3.9 | -14.6 | -9.0 | -2.0 | 372.2 |
| | 60019 | -3.2 | -29.0 | -4.0 | 4.0 | -17.6 | 23.7 | 370.1 |
| | 70001 | -5.9 | -29.0 | -14.0 | 54.6 | -6.1 | 56.9 | 370.1 |
| | 70004 | -8.0 | -29.0 | -4.2 | 5.4 | -27.2 | 72.1 | 370.1 |
| | 110708 | -5.3 | -29.1 | -17.3 | 28.2 | -14.6 | 10.8 | 370.3 |
| 2 Exterior Wall @ EL4.65 ~6.60m | 62011 | -2.1 | -29.3 | 13.3 | 50.9 | -7.7 | 5.6 | 372.2 |
| | 62019 | -7.8 | -29.3 | 36.5 | 83.6 | -19.2 | 61.0 | 372.2 |
| | 72001 | -7.8 | -29.3 | 14.7 | 88.0 | -18.7 | 57.2 | 372.2 |
| | 72004 | -8.1 | -29.3 | 47.4 | 53.5 | -26.2 | 57.0 | 372.2 |
| 3 Exterior Wall @ EL22.50 ~24.60m | 64011 | -7.6 | -29.3 | 18.4 | 87.1 | -12.9 | 86.0 | 372.2 |
| | 64019 | -6.9 | -29.3 | 22.2 | 100.6 | 8.3 | 81.7 | 372.2 |
| | 74001 | -3.7 | -29.3 | 19.9 | 71.7 | 2.4 | 62.1 | 372.2 |
| | 74004 | -6.1 | -29.3 | 10.7 | 92.6 | 1.4 | 92.7 | 372.2 |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 60819 | -3.1 | -29.0 | -13.8 | 5.2 | -13.6 | 5.1 | 370.1 |
| | 70801 | -9.8 | -29.0 | -29.7 | 105.5 | 5.7 | 57.9 | 370.1 |
| | 70804 | -1.9 | -29.0 | -10.5 | -2.6 | -4.6 | 1.5 | 370.1 |
| | 110748 | -5.4 | -29.1 | -8.4 | 31.9 | -17.1 | 24.5 | 370.3 |
| 5 Basemat | 90306 | -1.9 | -23.5 | -12.9 | -2.7 | -1.4 | -4.3 | 372.2 |
| | 90310 | -0.6 | -23.5 | -3.8 | -3.8 | -1.9 | -1.2 | 372.2 |
| | 90410 | -2.1 | -23.5 | -0.4 | -14.3 | -7.1 | -5.0 | 372.2 |
| 5 Basemat @ Spent Fuel Pool | 90486 | -2.7 | -23.2 | -0.7 | -0.6 | -15.6 | -16.9 | 370.1 |
| | 90490 | -3.8 | -23.2 | 24.5 | 2.3 | -23.7 | -6.2 | 370.1 |
| | 90526 | -4.1 | -23.2 | 3.3 | 13.9 | -5.1 | -27.0 | 370.1 |
| 6 Slab EL4.65m | 93306 | -2.0 | -29.3 | 40.0 | 26.3 | 57.9 | 27.9 | 372.2 |
| | 93310 | -6.0 | -29.3 | -4.7 | 53.8 | -6.3 | 57.1 | 372.2 |
| | 93410 | -1.8 | -29.3 | -0.9 | -4.0 | -10.6 | -11.0 | 372.2 |

Note: Negative value means compression.

Note *: Exterior Wall, Pool Wall Direction1 : Horizontal, Direction2 : Vertical
Basemat, Slab Direction1 : N-S, Direction2 : E-W

Table 3G.3-16

Rebar and Concrete Stresses: Selected Load Combination FB-9

| Location | Element ID | Concrete Stress (MPa) | | Primary Reinforcement Stress (MPa) | | | | Allowable |
|--|------------|-----------------------|-----------|------------------------------------|------------|-------------------------|------------|-----------|
| | | Calculated | Allowable | Calculated | | | | |
| | | | | Direction1 ¹ | | Direction2 ² | | |
| | | | | In/Top | Out/Bottom | In/Top | Out/Bottom | |
| 1 Exterior Wall and Pool Wall @ EL-11.50 ~-10.50m | 60011 | -8.5 | -29.3 | 230.5 | 191.6 | 247.9 | 256.1 | 372.2 |
| | 60019 | -12.6 | -29.0 | 163.1 | 241.5 | 285.3 | 269.3 | 370.1 |
| | 70001 | -12.6 | -29.0 | -26.9 | 205.5 | 34.2 | 158.9 | 370.1 |
| | 70004 | -22.2 | -29.0 | 92.4 | 229.0 | 226.7 | 316.5 | 370.1 |
| | 110708 | -14.1 | -29.1 | 39.8 | 167.7 | 275.8 | 211.0 | 370.3 |
| 2 Exterior Wall @ EL4.65 ~6.60m | 62011 | -10.7 | -29.3 | 175.8 | 292.7 | 134.9 | 293.3 | 372.2 |
| | 62019 | -13.2 | -29.3 | 142.7 | 221.1 | 77.7 | 214.3 | 372.2 |
| | 72001 | -11.8 | -29.3 | 70.9 | 276.7 | 95.1 | 220.2 | 372.2 |
| | 72004 | -14.5 | -29.3 | 203.1 | 238.5 | 191.6 | 272.7 | 372.2 |
| 3 Exterior Wall @ EL22.50 ~24.60m | 64011 | -27.2 | -29.3 | 198.5 | 349.2 | -79.8 | 305.5 | 372.2 |
| | 64019 | -21.8 | -29.3 | 177.6 | 292.2 | -53.9 | 214.4 | 372.2 |
| | 74001 | -7.2 | -29.3 | 109.1 | 118.8 | 73.9 | 98.0 | 372.2 |
| | 74004 | -12.4 | -29.3 | 76.4 | 172.4 | 45.3 | 186.2 | 372.2 |
| 4 Spent Fuel Pool Wall @ EL-5.10 ~-3.30m | 60819 | -5.6 | -29.0 | 85.1 | 103.0 | 252.6 | 170.4 | 370.1 |
| | 70801 | -21.8 | -29.0 | -68.7 | 292.1 | 57.5 | 242.0 | 370.1 |
| | 70804 | -9.8 | -29.0 | 131.1 | 56.7 | 243.6 | 161.7 | 370.1 |
| | 110748 | -7.3 | -29.1 | -18.6 | 87.5 | -32.8 | 154.4 | 370.3 |
| 5 Basemat | 90306 | -9.4 | -23.5 | 167.8 | 64.5 | 250.0 | 272.0 | 372.2 |
| | 90310 | -2.1 | -23.5 | 14.6 | 17.1 | -26.9 | 20.8 | 372.2 |
| | 90410 | -12.4 | -23.5 | 62.6 | 137.0 | 260.0 | 272.7 | 372.2 |
| 5 Basemat @ Spent Fuel Pool | 90486 | -12.2 | -23.2 | 218.5 | 179.0 | 130.5 | 44.4 | 370.1 |
| | 90490 | -9.6 | -23.2 | 90.0 | 224.1 | 267.9 | 165.6 | 370.1 |
| | 90526 | -11.0 | -23.2 | 184.8 | 100.6 | 242.7 | 115.7 | 370.1 |
| 6 Slab EL4.65m | 93306 | -4.4 | -29.3 | 230.9 | 111.5 | 117.9 | 154.7 | 372.2 |
| | 93310 | -8.0 | -29.3 | 79.4 | 86.3 | 51.6 | 112.4 | 372.2 |
| | 93410 | -4.7 | -29.3 | 82.0 | -21.1 | 113.4 | 52.0 | 372.2 |

Note: Negative value means compression.

Note *: Exterior Wall, Pool Wall Direction1 : Horizontal, Direction2 : Vertical
Basemat, Slab Direction1 : N-S, Direction2 : E-W

Table 3G.3-17
Transverse Shear of FB

| Location | Element ID | Load ID | d (m) | pv (%) | Shear Force (MN/m) | | | | Vu/φVn |
|---|------------|---------|-------|--------|--------------------|------|-------|-------|--------|
| | | | | | Vu | Vc | Vs | φVn | |
| 1 Exterior Wall and Pool Wall @ EL-11.50 --10.50m | 60011 | FB-4 | 1.72 | 0.177 | 1.09 | 3.53 | 1.26 | 4.07 | 0.269 |
| | 60019 | FB-9 | 3.35 | 0.177 | 3.14 | 3.08 | 2.45 | 4.70 | 0.669 |
| | 70001 | FB-9 | 1.69 | 0.177 | 1.80 | 1.64 | 1.24 | 2.44 | 0.738 |
| | 70004 | FB-9 | 1.59 | 0.710 | 2.87 | 0.00 | 4.68 | 3.97 | 0.723 |
| | 110708 | FB-9 | 1.11 | 0.355 | 1.14 | 0.07 | 1.64 | 1.45 | 0.782 |
| 2 Exterior Wall @ EL4.65 -6.60m | 62011 | FB-9 | 0.74 | 0.125 | 0.06 | 0.00 | 0.38 | 0.32 | 0.181 |
| | 62019 | FB-4 | 0.72 | 0.125 | 0.06 | 0.69 | 0.37 | 0.90 | 0.062 |
| | 72001 | FB-9 | 0.74 | 0.125 | 0.27 | 0.00 | 0.38 | 0.32 | 0.840 |
| | 72004 | FB-9 | 0.75 | 0.125 | 0.10 | 0.08 | 0.39 | 0.40 | 0.246 |
| 3 Exterior Wall @ EL22.50 -24.60m | 64011 | FB-9 | 0.81 | 0.125 | 0.02 | 0.00 | 0.42 | 0.35 | 0.059 |
| | 64019 | FB-4 | 0.81 | 0.125 | 0.07 | 0.41 | 0.42 | 0.71 | 0.092 |
| | 74001 | FB-4 | 0.72 | 0.125 | 0.11 | 0.68 | 0.37 | 0.89 | 0.125 |
| | 74004 | FB-8 | 0.72 | 0.125 | 0.08 | 0.65 | 0.37 | 0.87 | 0.094 |
| 4 Spent Fuel Pool Wall @ EL-5.10 --3.30m | 60819 | FB-4 | 3.32 | 0.177 | 0.41 | 6.43 | 2.43 | 7.53 | 0.054 |
| | 70801 | FB-9 | 1.69 | 0.710 | 4.11 | 1.99 | 4.97 | 5.91 | 0.696 |
| | 70804 | FB-4 | 1.68 | 0.177 | 0.46 | 3.38 | 1.23 | 3.92 | 0.118 |
| | 110748 | FB-4 | 1.21 | 0.177 | 0.24 | 1.31 | 0.88 | 1.87 | 0.131 |
| 5 Basemat | 90306 | FB-9 | 3.70 | 0.807 | 6.54 | 2.05 | 12.36 | 12.25 | 0.534 |
| | 90310 | FB-4 | 3.69 | 0.807 | 0.47 | 6.07 | 12.32 | 15.63 | 0.030 |
| | 90410 | FB-9 | 3.72 | 0.807 | 3.42 | 2.23 | 12.42 | 12.45 | 0.275 |
| 5 Basemat @ Spent Fuel Pool | 90486 | FB-4 | 3.50 | 0.403 | 0.31 | 6.31 | 5.84 | 10.33 | 0.030 |
| | 90490 | FB-9 | 3.51 | 0.807 | 11.20 | 6.80 | 11.70 | 15.72 | 0.712 |
| | 90526 | FB-9 | 3.48 | 0.807 | 10.82 | 7.20 | 11.61 | 15.98 | 0.677 |
| 6 Slab EL4.65m | 93306 | FB-8 | 1.10 | 0.500 | 0.21 | 0.24 | 2.27 | 2.14 | 0.096 |
| | 93310 | FB-4 | 1.10 | 0.500 | 0.48 | 2.87 | 2.27 | 4.37 | 0.110 |
| | 93410 | FB-4 | 1.10 | 0.500 | 0.21 | 2.06 | 2.27 | 3.68 | 0.058 |

Figure 3G.3-1. Sections Where Temperature Loads Are Defined






Figure 3G.3-2. Section Considered for Analysis



Definition of Element Coordinate System

| Structure | x | y | z |
|------------------------------|--------------|-------------|--------------|
| External Wall | horizontal | vertical | outward |
| Wall in N-S Direction | horizontal | vertical | toward West |
| Wall in E-W Direction | horizontal | vertical | toward South |
| Foundation Mat Floor Slab | toward South | toward West | downward |

Figure 3G.3-3. Force and Moment in Shell Element

Figure 3G.3-4. Reinforcing Steel of Spent Fuel Pool Walls

Figure 3G.3-5. List of FB Wall and Slab Reinforcement

3H. EQUIPMENT QUALIFICATION DESIGN ENVIRONMENTAL CONDITIONS

3H.1 INTRODUCTION

This appendix specifies plant environmental conditions, which envelop the actual environment expected over the plant life, for which safety-related equipment (Section 3.11) are to be designed and qualified. The plant conditions considered in defining the environmental conditions are normal operation including anticipated operational occurrences (AOOs) and test, and accident conditions including post-accident operations. The accident condition considered is a hypothesized single event (not reasonably expected during the course of plant operation) that has the potential to cause severe environmental conditions for safety-related equipment. The specified accident conditions are based on significantly conservative assumptions.

The primary environmental parameters addressed are pressure, temperature, relative humidity, radiation, and chemical conditions. Safety-related equipment is to be designed and qualified for the environmental conditions specified in this appendix. The parameters specified in this appendix do not include margins that may be required to satisfy applicable codes and standards for equipment qualification. The radiation data specified in this appendix is intended to provide a conservative basis for equipment qualification and is not intended to limit or justify personnel access.

3H.2 PLANT ZONES

3H.2.1 Containment Vessel

The containment vessel is divided into a drywell region and a pressure wetwell with an interconnecting vent system. The containment vessel is shown in Figure 6.2-1. The drywell volume is partitioned into an upper drywell and lower drywell by the RPV support skirt and support pedestal. Connecting vents through the pedestal provide a path between upper and lower drywells. Table 3.2-1 identifies the safety-related equipment located within the containment vessel.

For normal operating conditions, the containment vessel is divided into three thermodynamic and four radiation zones to represent the enveloping levels of the environmental conditions. The environmental zones are shown in Figure 3H-1. For accident conditions, zones a-1 and a-2 have the same thermodynamic properties and the entire containment vessel (zones b-1 through b-4) has the same radiation properties.

3H.2.2 Outside Containment Vessel

The reduced amount of safety-related equipment in the ESBWR, permits all of it to be housed within the reactor building. The area outside the containment vessel includes:

- Control Building
- Reactor Building outside containment

The region inside the reactor building surrounding the containment encloses penetrations through the containment, except for those of the main steam tunnel and IC/PCC pools. The control room zone includes the main control room, rooms located in elevation -7400 in control building and

areas adjacent to the control room containing operator facilities. Major equipment zones are shown on the reactor building arrangement drawing (Figure 3H-2).

3H.3 ENVIRONMENTAL CONDITIONS

Table 3H-1 contains a cross listing of the environmental data tables arranged by location and by type of condition.

3H.3.1 Plant Normal Operating Conditions

Tables 3H-2 through 3H-4 define the thermodynamic conditions (pressure, temperature and humidity) for normal operating conditions for areas containing safety-related equipment. Tables 3H-5 through 3H-7 define the radiation environment for the same areas for normal operating conditions. Figures showing equipment location and system configurations are referenced in each table.

3H.3.2 Accident Conditions

Thermodynamic conditions for safety-related equipment in the containment vessel, control room zone, and reactor building are given in Tables 3H-8 through 3H-10 for accident conditions, including post-accident periods. In general, the most severe conditions result from a postulated reactor coolant (steam or water) line break inside the containment. However, conditions were also considered for ruptures occurring in the steam tunnel and breaks in the RWCU/SDC System outside the containment. Tables 3H-11 through 3H-13 specify the radiation environment for accident conditions, including post-accident periods.

3H.3.3 Water Quality

Reactor water quality characteristics for the DBA LOCA are:

- pH = 5.3 to 8.9
- Conductivity $\leq 2.0 \mu\text{S}/\text{cm}$
- $\leq 8 \text{ ppm O}_2, \leq 1 \text{ ppm CO}_2$
- $\leq 1 \text{ ppm}$ dissolved salts available for deposit as dry salts upon evaporation from hot surfaces.
- $\leq 150 \text{ ppb}$ undissolved solids
- $\leq 60 \text{ ppb}$ dissolved H_2 arising from $< 4.0\%$ by volume of H_2O in containment atmosphere.

Water quality characteristics for normal plant operations for auxiliary systems are specified in Chapter 9 and for steam and power conversion systems in Chapter 10.

3H.4 REFERENCES

3H.4-1 10 CFR 50 Appendix J, "Primary Reactor Containment Leakage Testing for Water-Cooled Power Reactors."

3H.4-2 NUREG-1465, "Accident Source Terms for Light-Water Nuclear Power Plants," February 1995.

Table 3H-1
Cross Reference of Plant Environmental Data and Location

| Plant Condition | Location* | | |
|----------------------|--------------------|------------------|-------------------|
| | Containment Vessel | Reactor Building | Control Room Zone |
| Normal Conditions ** | | | |
| (a) Thermodynamic | 3H-2 | 3H-3 | 3H-4 |
| (b) Radiation | 3H-5 | 3H-6 | 3H-7 |
| Accident Conditions | | | |
| (a) Thermodynamic | 3H-8 | 3H-9 | 3H-10 |
| (b) Radiation | 3H-11 | 3H-12 | 3H-13 |

* Specific zones are located on the arrangement drawings, and typical equipment is identified by figure numbers in each table.

** Test and abnormal environments are included with normal operating conditions.

Table 3H-2**Thermodynamic Environment Conditions Inside Containment Vessel for Normal Operating Conditions**

| Plant Zone/Typical Equipment⁽¹⁾ | Pressure⁽²⁾⁽³⁾ (Gauge) kPa (psig) | Temperature⁽³⁾ °C (°F) | Relative Humidity⁽³⁾ % |
|--|---|--|--|
| (a-1) Upper drywell and upper area of lower drywell [Figure 3H-1] | 10.3 (16.0) | 57(135) Ave 65 (150) Max | 50 Nom |
| (a-2) Lower area of lower drywell [Figure 3H-1] | 10.3 (16.0) | 57(135) Max 60(140) Ave | 50 Nom |
| (a-3) Wetwell - pool and gas space [Figure 3H-1] | 4.8(0.7) Nom 9.0(1.3) Max 0 Min | 43(110) Max ⁽⁴⁾ | 100 |

- (1) The containment atmosphere is nitrogen.
- (2) The containment vessel will be pressurized during leak rate tests once per refueling outage in accordance with 10 CFR 50, Appendix J.
- (3) The worst combination of conditions in the table sets the design requirements of equipment.
- (4) The suppression pool water may reach 46°C (115°F) during testing. The maximum abnormal temperature is 49°C (120°F).

Table 3H-3

Thermodynamic Environment Conditions Inside Reactor Building for Normal Operating Conditions

| Plant Zone/Typical Equipment | Pressure⁽¹⁾ (Gauge) kPa (psig) | Temperature⁽²⁾ °C (°F) | Relative Humidity⁽²⁾ % |
|---|--|--|--|
| Hydraulic Control Unit (HCU) Rooms CRD HCUs [Figure 3H-3] | -0 | 40 (104) Max 10 (50) Min | 90 Max 10 Min |
| Control Rod Drive (CRD) Pump Room CRD high pressure makeup line valves [Figure 3H-4] | -0 | 40 (104) Max 10(50) Min | 90 Max 10 Min |
| Standby Liquid Control (SLC) System Room SLC system valves [Figure 3H-5] | -0 | 40 (104) Max 21.1 (70) Min | 60 Max 35 Min |
| Battery Rooms ⁽³⁾ Batteries [Figure 3H-6] | +0 | 25 (77) Nom 29 (85) Max 18 (65) Min | 90 Max 10 Min |
| Electrical Division Rooms DC power system: battery chargers and electrical modules [Figure 3H-7] | +0 | 29 (85) Max 18 (65) Min | 60 Max 35 Min |
| Uninterruptible Power Supply (UPS) AC power system: battery chargers, inverters and electrical modules [Figure 3H-7] | +0 | 29 (85) Max 18 (65) Min | 60 Max 35 Min |
| Reactor Protection System (RPS) [Figure 3H-8] | -0 | 29 (85) Max 18 (65) Min | 60 Max 35 Min |
| Suppression Pool Temperature Monitoring System (SPTMS) [Figure 3H-9] | -0 | 29 (85) Max 18 (65) Min | 60 Max 35 Min |
| Sensors and electrical modules Leak Detection and Isolation System (LD&IS), Process Radiation Monitoring System (PRMS), Containment Inerting Systems (CIS) [Figure 3H-10] | -0 | 29 (85) Max 18 (65) Min | 60 Max 35 Min |
| Electrical modules Neutron Monitoring System (NMS), Essential Distributed Control and Information System (E- DCIS) [Figure 3H-11] | -0 | 29 (85) Max 18 (65) Min | 60 Max 35 Min |

Table 3H-3**Thermodynamic Environment Conditions Inside Reactor Building for Normal Operating Conditions**

| Plant Zone/Typical Equipment | Pressure⁽¹⁾ (Gauge) kPa (psig) | Temperature⁽²⁾ °C (°F) | Relative Humidity⁽²⁾ % |
|--|--|--|--|
| Isolation valves Fuel and Auxiliary Pool Cooling System (FAPCS), RCCWS, High Pressure Nitrogen Supply System (HPNSS), Containment Inerting System (CIS) [Figure 3H-12] | -0 | 40 (104) Max 10 (50) Min | 90 Max 10 Min |
| Reactor Water Cleanup/Shutdown Cooling (RWCU/SDC) Isolation and shutoff valves [Figure 3H-12] | -0 | 40 (104) Max 10 (50) Min | 90 Max 10 Min |
| Main Steam (MS) and Feedwater (FW) Tunnel Main Steamline (MSL) isolation valves MSL drain isolation valves FW isolation valves [Figure 3H-13] | -0 | 57 (135) Max 10 (50) Min | 90 Max 10 Min |
| Isolation Condenser System (ICS) valves outside containment [Figure 3H-14] | -0 | 40 (104) Max 10 (50) Min | 100/Water |

- (1) The indicated positive or negative pressure is maintained. Pressure difference is not maintained.
- (2) Maximum occurs in summer and Minimum in winter. The period for which temperature and humidity reach Max or Min simultaneously is less than 1%. For other times, temperature and humidity are in the middle of Max and Min.
- (3) Hydrogen concentrations are maintained below 2% by volume in battery rooms.

Table 3H-4**Thermodynamic Environment Conditions Inside Control Building for Normal Operating Conditions**

| Plant Zone/Typical Equipment | Pressure* (Gauge) kPa (psig) | Temperature °C (°F) | Relative Humidity % |
|--|---|--------------------------------|------------------------------------|
| Main control room panels [Figure 3H-15] | +0 | 25.6 (78) Max 22.8 (73) Min | 60 Max 25 Min |
| Emergency breathing air system (EBAS) [Figure 3H-16] | +0 | 25.6 (78) Max 22.8 (73) Min | 60 Max 35 Min |
| Safety System Logic and Control (SSLC) [Figure 3H-17] | +0 | 25.6 (78) Max 22.8 (73) Min | 60 Max 25 Min |

* The indicated positive or negative pressure is maintained. Pressure difference is not maintained.

Table 3H-5
Radiation Environment Conditions Inside Containment Vessel for Normal Operating Conditions

| Plant Zone/Typical Equipment | Operating Dose Rate ⁽¹⁾⁽²⁾ | | Integrated Dose ⁽²⁾⁽³⁾ | |
|--|---------------------------------------|----------------------|-----------------------------------|----------|
| | Gamma (R/h) | Beta (R/h) | Gamma (R) | Beta (R) |
| (b-1) Upper drywell [Figure 3H-1] | 2.61 E+1 | Negl. ⁽⁴⁾ | 1.4 E+7 | Negl. |
| (b-2) Upper area of lower drywell [Figure 3H-1] | 2.61 E+1 | Negl. | 1.4 E+7 | Negl. |
| (b-3) Lower area of lower drywell [Figure 3H-1] | 1.98 E+1 | Negl. | 1.0 E+7 | Negl. |
| (b-4) Wetwell - Suppression pool and gas space [Figures 6.2-1 and 3H-1] | < 1.4 | Negl. | 1.7 E+2 | Negl. |

(1) Operating dose rate is at 100% rated power and away from radiation source.

(2) The doses are based on the radiation sources provided in Chapter 12.

(3) Integrated dose means the integrated value over 60 years.

(4) Negl.- Value less than 0.001 mR/h

Table 3H-6
Radiation Environment Conditions Inside Reactor Building for Normal Operating
Conditions

| Plant Zone/Typical Equipment | Operating Dose Rate ⁽¹⁾⁽²⁾ | | Integrated Dose ⁽²⁾⁽³⁾ | |
|---|---------------------------------------|----------------------|-----------------------------------|-------------|
| | Gamma (R/h) | Beta (R/h) | Gamma (R) | Beta (R) |
| HCU Rooms CRD HCUs [Figure 3H-3] | 2.9 E-2 | Negl. ⁽⁴⁾ | 1.2 E+4 | Negl. |
| CRD Pump Room CRD high pressure makeup line valves [Figure 3H-4] | 5.7 E-3 | Negl. | 2.4 E+3 | Negl. |
| SLC System Room SLC system valves [Figure 3H-5] | 1.1 E-3 | Negl. | 4.8 E+2 | Negl. |
| Battery Rooms Batteries [Figure 3H-6] | 6.9 E-4 | Negl. | 2.9 E+2 | Negl. |
| Electrical Division Rooms DC power system: battery chargers and electrical modules [Figure 3H-7] | 6.9 E-4 | Negl. | 2.9 E+2 | Negl. |
| UPS AC power system: battery chargers, inverters and electrical modules [Figure 3H-7] | 6.9 E-4 | Negl. | 2.9 E+2 | Negl. |
| RPS [Figure 3H-8] | 6.9 E-4 | Negl. | 2.9 E+2 | Negl. |
| SPTMS [Figure 3H-9] | 6.9 E-4 | Negl. | 2.9 E+2 | Negl. |
| Sensors and electrical modules LD&IS, PRMS, CIS [Figure 3H-10] | 1.1 E-3 | Negl. | 4.8 E+2 | Negl. |

Table 3H-6
Radiation Environment Conditions Inside Reactor Building for Normal Operating Conditions

| Plant Zone/Typical Equipment | Operating Dose Rate ⁽¹⁾⁽²⁾ | | Integrated Dose ⁽²⁾⁽³⁾ | |
|---|---------------------------------------|------------|-----------------------------------|----------|
| | Gamma (R/h) | Beta (R/h) | Gamma (R) | Beta (R) |
| Electrical modules NMS, E-DCIS [Figure 3H-11] | 6.9 E-4 | Negl. | 2.9 E+2 | Negl. |
| Isolation valves FAPCS, RCCWS, HPNSS, CIS [Figure 3H-12] | 1.15 E-1 | Negl. | 4.9 E+4 | Negl. |
| RWCU/SDC Isolation and shutoff valves [Figure 3H-12] | 1.15 E-1 | Negl. | 4.9 E+4 | Negl. |
| MS and FW Tunnel MSL isolation valve MSL drain isolation valve Feedwater isolation valve [Figure 3H-13] | 1.61 E+1 | Negl. | 6.8 E+6 | Negl. |
| ICS valves outside containment [Figure 3H-14] | 1.13 E-3 | Negl. | 4.8 E+2 | Negl. |

- (1) Operating dose rate is at 100% rated power and away from radiation source.
- (2) The doses are based on the radiation sources provided in Chapter 12.
- (3) Integrated dose means the integrated value over 60 years.
- (4) Negl.- Value less than 0.001 mR/h

Table 3H-7
Radiation Environment Conditions Inside Control Building for Normal Operating Conditions

| Plant Zone/Typical Equipment | Operating Dose Rate ⁽¹⁾⁽²⁾ | | Integrated Dose ⁽²⁾⁽³⁾ | |
|---|---------------------------------------|-----------------------|-----------------------------------|----------|
| | Gamma (R/h) | Beta (R/h) | Gamma (R) | Beta (R) |
| Main control room and SSLC panels [Figure 3H-15 and 3H-17] | 6.9 E-4 | Negl ⁽⁴⁾ . | 2.9 E+2 | Negl. |
| Emergency breathing air system [Figure 3H-16] | 6.9 E-4 | Negl. | 2.9 E+2 | Negl. |

- (1) Operating dose rate is at 100% rated power and away from radiation source.
- (2) The doses are based on the radiation sources provided in Chapter 12.
- (3) Integrated dose means the integrated value over 60 years.
- (4) Negl.- Value less than 0.001 mR/h

Table 3H-8**Thermodynamic Environment Conditions Inside Containment Vessel for Accident Conditions**

| Plant Zone/Typical Equipment | | | | | | |
|-------------------------------------|---|---------------------|------------|------------|-----------|------------|
| (a-1 & a-2) | Upper and lower drywell ⁽¹⁾ [Figure 3H-1] | Time ⁽²⁾ | 500 s. | 1 hr | 72 hrs | 100 days |
| | | Temp. °C (°F) | 171 (340) | 151 (303) | 151 (303) | 57 (135) |
| | | Press. kPa (psig) | 257 (37.3) | 257 (37.3) | 310 (45) | 5.2 (0.75) |
| | | Humidity % | Steam | Steam | Steam | 50 |
| (a-3) | Wetwell [Figure 3H-1] | Time ⁽²⁾ | 500 s | 1 hrs | 72 hrs | 100 days |
| | | Temp. °C (°F) | 43 (109) | 110 (230) | 110 (230) | 43 (110) |
| | | Press. kPa (psig) | 241.3 (35) | 241.3 (35) | 310 (45) | 4.8 (0.7) |
| | | Humidity % | 100 | 100 | 100 | 100 |

Notes:

- (1) For a pipe failure inside the containment vessel, water accumulates in the lower drywell. The amount depends upon the break location.
- (2) Time denotes the time after the occurrence of LOCA. For example 1 hrs means 1 hours after the occurrence of LOCA and 72 hours means the time from 1 hours to 72 hours after LOCA. The specification of conditions 100 days after a LOCA is consistent with previous BWR and ABWR practice.

Table 3H-9

Thermodynamic Environment Conditions Inside Reactor Building for Accident Conditions

| Plant Zone/Typical Equipment | | | |
|--|--|--|--|
| SLC System Room SLC system valves [Figure 3H-5] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 12 h 66 (151) 3.43 (0.49) 100 | 100 days 66 (151) 0 100 |
| Battery Rooms Batteries [Figure 3H-6] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 50 (122) Max 0 90 Max | 50 (122) Max 0 90 Max |
| Electrical Division Rooms DC power system: battery chargers and electrical modules [Figure 3H-7] UPS AC power system: battery chargers, inverters and electrical modules [Figure 3H-7] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 50 (122) Max 0 90 Max 50 (122) Max 0 90 Max | 50 (122) Max 0 90 Max 50 (122) Max 0 90 Max |
| RPS [Figure 3H-8] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 50 (122) Max 0 90 Max | 50 (122) Max 0 90 Max |
| SPTMS [Figure 3H-9] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 50 (122) Max 0 90 Max | 50 (122) Max 0 90 Max |
| Sensors and electrical modules LD&IS, PRMS, CIS [Figure 3H-10] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 12 h 66 (151) 3.43 (0.49) 100 | 100 days 66 (151) 0 100 |
| Electrical modules NMS, E-DCIS [Figure 3H-11] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 12 h 66 (151) 3.43 (0.49) 100 | 100 days 66 (151) 0 100 |

Table 3H-9

Thermodynamic Environment Conditions Inside Reactor Building for Accident Conditions

| Plant Zone/Typical Equipment | | | |
|---|--|--|-------------------------------------|
| Isolation valves FAPCS, RCCWS, HPNSS, CIS [Figure 3H-12] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 12 h 66 (151) 3.43 (0.49) 100 | 100 days 66 (151) 0 100 |
| HCU Rooms CRD HCUs [Figure 3H-3] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 12 h 66 (151) 3.43 (0.49) 100 | 100 days 66 (151) 0 90 Max |
| CRD Pump Room CRD high pressure makeup line valves [Figure 3H-4] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 12 h 66 (151) 3.43 (0.49) 100 | 100 days 66 (151) 0 90 Max |
| RWCU/SDC Isolation and shutoff valves [Figure 3H-12] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 12 h 66 (151) 3.43 (0.49) 100 | 100 days 66 (151) 0 90 Max |
| MS and FW Tunnel MSL isolation valve MSL drain isolation valve Feedwater isolation valve [Figure 3H-13] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 12 h 66 (151) 3.43 (0.49) 100 | 100 days 66 (151) 0 90 Max |
| ICS valves outside containment [Figure 3H-14] | Time * Temp. °C (°F) Press. kPa (psig) Humidity % | 12 h 66 (151) 3.43 (0.49) 100 | 100 days 66 (151) 0 90 Max |

* Time indicates the time after the occurrence of LOCA. The specification of conditions 100 days after a LOCA is consistent with previous BWR and ABWR practice.

Table 3H-10**Thermodynamic Environment Conditions Inside Control Room Zone for Accident Conditions**

| Plant Zone/Typical Equipment | | | |
|---|------------------|---------|----------|
| Control Room Habitability Area Main control room and SSLC panels [Figure 3H-15 and 3H-17] | Time* | 10 days | 100 days |
| | Temp. °C | 30 Max | 30 max |
| | Press. Pa (psig) | 0 | 0 |
| | Humidity | 60 Max | 60 Max |
| Emergency Breathing Air System [Figure 3H-16] | Time* | 10 days | 100 days |
| | Temp. °C | 50 Max | 50 Max |
| | Press. Pa (psig) | 0 | 0 |
| | Humidity | 90 Max | 90 Max |

* Time indicates the time after the occurrence of LOCA. The specification of conditions 100 days after a LOCA is consistent with previous BWR and ABWR practice.

Table 3H-11

Radiation Environment Conditions Inside Containment Vessel for Accident Conditions

| Plant Zone/Typical Equipment | Operating Dose Rate ⁽¹⁾⁽²⁾ | | Integrated Dose ⁽²⁾⁽³⁾ | |
|---|---------------------------------------|---------------|-----------------------------------|-------------|
| | Gamma (R/h) | Beta (R/h) | Gamma (R) | Beta (R) |
| (b-1) Upper drywell [Figure 3H-1] | 2.64 E+7 | 2.64 E+8 | 2.64 E+8 | 2.64 E+9 |
| (b-2) Upper area of lower drywell [Figure 3H-1] | 2.64 E+7 | 2.64 E+8 | 2.64 E+8 | 2.64 E+9 |
| (b-3) Lower area of lower drywell [Figure 3H-1] | 2.64 E+7 | 2.64 E+8 | 2.64 E+8 | 2.64 E+9 |
| (b-4) Wetwell - Suppression pool and gas space [Figures 6.2-1 and 3H-1] | 4.0 E+7 | 5.3 E+8 | 4.0 E+8 | 6.6 E+9 |

- (1) The radiation sources developed in accordance with NUREG-1465 are used.
- (2) The gamma and beta doses are bounding values based upon generic design considerations, and are to be revised and/or verified by the COL applicant based upon the site-specific equipment considerations (exact design, specific location, materials of construction and leakage characteristics).
- (3) Integrated dose is for 6 months.

Table 3H-12

Radiation Environment Inside Reactor Building for Accident Conditions

| Plant Zone/Typical Equipment | Operating Dose Rate ⁽¹⁾⁽²⁾ | | Integrated Dose ⁽²⁾⁽³⁾ | |
|---|---------------------------------------|---------------|-----------------------------------|-------------|
| | Gamma (R/h) | Beta (R/h) | Gamma (R) | Beta (R) |
| HCU Rooms CRD HCUs [Figure 3H-3] | 2.65 E+5 | 1.3 E+7 | 8.0 E+7 | 1.06 E+10 |
| CRD Pump Room CRD high pressure makeup line valves [Figure 3H-4] | 2.65 E+5 | 1.3 E+7 | 8.0 E+7 | 1.06 E+10 |
| SLC System Room SLC system valves [Figure 3H-5] | 1.1 E+1 | 2.6 E+2 | 2.6 E+3 | 4.0 E+4 |
| Battery Rooms Batteries [Figure 3H-6] | 4.0 E0 | 2.6 E+2 | 6.6 E+2 | 6.6 E+4 |
| Electrical Division Rooms DC power system: battery chargers and electrical modules [Figure 3H-7] | 4.0 E0 | 2.6 E+2 | 6.6 E+2 | 6.6 E+4 |
| UPS AC power system: battery chargers, inverters and electrical modules [Figure 3H-7] | 4.0 E0 | 2.6 E+2 | 6.6 E+2 | 6.6 E+4 |
| RPS [Figure 3H-8] | 4.0 E0 | 2.6 E+2 | 6.6 E+2 | 6.6 E+4 |
| SPTMS [Figure 3H-9] | 4.0 E0 | 2.6 E+2 | 6.6 E+2 | 6.6 E+4 |
| Sensors and electrical modules LD&IS, PRMS, CIS [Figure 3H-10] | 1.1 E+1 | 2.6 E+2 | 2.6 E+3 | 4.0 E+4 |
| Electrical modules NMS, E-DCIS [Figure 3H-11] | 4.0 | 2.6 E+2 | 6.6 E+2 | 6.6 E+4 |

Table 3H-12

Radiation Environment Inside Reactor Building for Accident Conditions

| Plant Zone/Typical Equipment | Operating Dose Rate ⁽¹⁾⁽²⁾ | | Integrated Dose ⁽²⁾⁽³⁾ | |
|---|---------------------------------------|---------------|-----------------------------------|-------------|
| | Gamma (R/h) | Beta (R/h) | Gamma (R) | Beta (R) |
| Isolation valves FAPCS, RCCWS, HPNSS, CIS [Figure 3H-12] | 2.6 E+5 | 1.3 E+7 | 8.0 E+7 | 1.0 E+10 |
| RWCU/SDC Isolation and shutoff valves [Figure 3H-12] | 2.6 E+5 | 1.3 E+7 | 8.0 E+7 | 1.0 E+10 |
| MS and FW Tunnel MSL isolation valve MSL drain isolation valve Feedwater isolation valve [Figure 3H-13] | 1.2 E+2 | 9.2 E+2 | 2.6 E+2 | 1.2 E+3 |
| ICS valves outside containment [Figure 3H-14] | 1.1 E+1 | 2.6 E+2 | 2.6 E+3 | 4.0 E+4 |

- (1) The radiation sources developed in accordance with NUREG-1465 are used.
- (2) The gamma and beta doses are bounding values based upon generic design considerations, and are to be revised and/or verified by the COL applicant based upon the site-specific equipment considerations (exact design, specific location, materials of construction and leakage characteristics).
- (3) Integrated dose is for 6 months.

Table 3H-13

Radiation Environment Conditions Inside Control Room Zone for Accident Conditions

| Plant Zone/Typical Equipment | LOCA ⁽¹⁾⁽²⁾ | | Integrated Dose ⁽²⁾⁽³⁾ | |
|--|------------------------|---------------|-----------------------------------|-------------|
| | Gamma (R/h) | Beta (R/h) | Gamma (R) | Beta (R) |
| Sealed Emergency Operating Area Main control room and SSLC panels [Figure 3H-15 and 3H-17] | 4.0 E-2 | 5.0 E-1 | 5.3 E0 | 9.2 E+1 |
| Emergency Breathing Air System [Figure 3H-16] | 4.0 E-2 | 5.0 E-1 | 5.3 E0 | 9.2 E+1 |

- (1) The radiation sources developed in accordance with NUREG-1465 are used.
- (2) The gamma and beta doses are bounding values based upon generic design considerations, and are to be revised and/or verified by the COL applicant based upon the site-specific equipment considerations (exact design, specific location, materials of construction and leakage characteristics).
- (3) Integrated dose is for 6 months.

Figure 3H-1. Environmental Zones in the Containment Vessel

Figure 3H-2. Reactor Building Arrangements

Figure 3H-3. HCU Rooms

Figure 3H-4. CRD Pump Room

Figure 3H-5. SLC System Room

Figure 3H-6. Battery Rooms

Figure 3H-7. Electrical Division Rooms

Figure 3H-8. RPS Arrangement

Figure 3H-9. SPTMS Arrangement

Figure 3H-10. Sensors & Electrical Modules Arrangements For LD&IS, PRMS, CMS

Figure 3H-11. Electrical Modules Arrangements For NMS, E-DCIS

Figure 3H-12. Isolation & Shutoff Valves Arrangements For RWCU/SDC

Figure 3H-13. MS and FW Tunnel Isolation Valve Arrangements

Figure 3H-14. ICS Condenser and Piping Arrangement Outside Containment

Figure 3H-15. Main Control Room Panel Arrangement

Figure 3H-16. Emergency Breathing Air System Arrangement

Figure 3H-17. 1E DCIS Rooms Arrangement

3I. DESIGNATED NEDE-24326-1-P MATERIAL WHICH MAY NOT CHANGE WITHOUT PRIOR NRC APPROVAL

This appendix presents the necessary NEDE-24326-1-P (Reference 3I-1), “General Electric Environmental Qualification Program,” material for *identifying the material, by italics, which shall not be changed without prior NRC approval.* (See Section 3.10.)

3I.1 GENERAL REQUIREMENTS FOR DYNAMIC TESTING

(Paragraph 4.4.2.5.1 of Ref. 3I-1)

- (a) **Mounting** – *Specimens to be tested will be mounted in a manner that adequately simulates the installed configuration or as described in the applicable GE mounting documentation. Mounting will be specified in the Product Performance Qualification Specification (PPQS).*
- (b) **Monitoring** – *Sufficient monitoring equipment will be used to evaluate the performance of the specimen before, during, and after the test. Monitoring product is used to allow determination of applied vibration levels and equipment responses. The location of monitoring sensors shall be specified by the PPQS and will be documented in the test report.*

When required by the PPQS, the response of the product will be measured using accelerometers. When required by the PPQS, the accelerometers shall be located at a sufficient number of locations on the product to define the mode shapes and/or frequencies which would be required to allow dynamic qualification of individual safety-related components and devices, to support analytical extrapolation of test results, or to verify frequency requirements.

- (c) **Exploratory Tests** – *Exploratory vibration tests may be performed on the product to aid in the determination of the test method that will best qualify or determine the dynamic characteristics of the product. If it can be shown that the equipment is not resonant at any frequency within the expected frequency range, it may be considered a rigid body and tested according to methods and procedures discussed in Subsection 4.4.2.5.6 of Reference 3I-1 or analyzed according to the methods of Subsection 4.4.4.1.4.5 of Reference 3I-1.*

If the product contains a single resonance or multiple resonances, one of the methods outlined in Subsection 4.4.2.5.3 of Reference 3I-1 will be used to qualify the product by test.

The exploratory test may be performed in the form of a low-level, continuous sinusoidal sweep at a rate no greater than 2 octave per minute over the frequency range equal to or greater than that to which the equipment is to be qualified. All resonances will be recorded for use in determining the test method to be used or the dynamic characteristics of the equipment. If the configuration of the product is such that critical natural frequencies cannot be ascertained, dynamic qualification will be accomplished by testing by the Response Spectrum method as specified in Paragraph 4.4.2.5.3.6 of Reference 3I-1. An acceptable alternative qualification method is a fragility test as described in Subsection 4.4.2.5.7 of Reference 3I-1.

- (d) **Dynamic Event Aging Tests** – *The dynamic tests simulate the effect of low level earthquake loads combined with Service Level B RBV dynamic loads. The dynamic tests are performed on aged products unless otherwise justified. (See Section 3.10)*

The test sequence to be used will be:

- (1) Vibration aging (if required);
- (2) Low level earthquake loads combined with Service level B RBV dynamic loads; and
- (3) SSE loads combined with Service level D RBV dynamic loads

Because most testing is biaxial rather than triaxial, the above sequence and durations are applied twice with the equipment being rotated 90 degrees on the table between the two tests. (See Section 3.10)

The Test Response Spectra (TRS) will envelop the RRS as specified in 4.2.2.a(6) of Reference 3I-1. (See Section 3.10)

- (e) **Loading** – *Dynamic tests will be performed with the product subjected to nominal operating service conditions. If significant, normal operating loads such as electrical, mechanical, pressure, and thermal will be included. Where normal operating loads cannot be included in the dynamic tests, supplemental analysis will be used to qualify the product for those effects. (See Section 3.10)*

3I.2 PRODUCT AND ASSEMBLY TESTING

(Paragraph 4.4.2.5.2 of Ref. 3I-1)

- (a) *Products will be tested simulating nominal operating conditions. In addition, dynamic coupling between interacting equipment will be considered. See Section 3.10. The product shall be mounted on the shaker table as stated in Paragraph 4.4.2.5.1(a) of Reference 3I-1. If the product is intended to be mounted on a panel, the panel will be included in the test mounting.*

Alternatively, the response at the product mounting location may be measured in the assembly test as specified in Paragraph 4.4.2.5.1(a) of Reference 3I-1. Then the product will be mounted directly to the shaker table, with the dynamic input being that which was determined at the product mounting location.

3I.3 MULTIPLE-FREQUENCY TESTS

(Paragraph 4.4.2.5.3 of Ref. 3I-1)

- (a) **General** – *When the dynamic ground motion has not been strongly filtered, the mounting location retains the broadband characteristics. In this case, multi-frequency testing is applicable to dynamic qualification. (See Section 3.10)*
- (b) **Response Spectrum Test** – *Testing shall be performed by applying artificially generated input excitation to the product, the amplitude of which is controlled in 1/3 octave or narrower bands. The excitation will be controlled to provide a test response spectrum (TRS) which meets or exceeds the required response spectrum (RRS). The peak value of the input excitation equals or exceeds the zero period acceleration (ZPA) of the RRS. (See Section 3.10)*

3I.4 SINGLE- AND MULTI-AXIS TESTS

(Paragraph 4.4.2.5.4 of Ref. 3I-1)

Single-axis tests may be allowed if the tests are designed to conservatively reflect the dynamic event at the equipment mounting locations or if the product being tested can be shown to respond independently in each of the three orthogonal axis or otherwise withstand the dynamic event at its mounting location.

If the preceding considerations do not apply, multi-axis testing will be used. The minimum is biaxial testing with simultaneous inputs in a principal horizontal axis and the vertical axis. Independent random inputs are preferred, and, if used, the test will be performed in two steps with the equipment rotated 90° in the horizontal plane for the second step. If independent random inputs are not used (such as with single frequency tests), four tests would be run; first, with the inputs in phase; second, with one input 180° out of phase; third, with the equipment rotated 90° horizontally and the inputs in phase; and, finally, with the same equipment orientation as in the third step but with one input 180° out of phase. (See Section 3.10)

3I.5 SINGLE FREQUENCY TESTS

(Paragraph 4.4.2.5.6 of Ref. 3I-1)

If it can be shown that the products, as defined in Regulatory Guide 1.92 have no resonances, or only one resonance, or if resonances are widely spaced and do not interact to reduce the fragility level in the frequency range of interest or, if otherwise justified, single frequency tests may be used to fully test the product. (See Section 3.10)

3I.6 DAMPING

(Paragraph 4.4.2.5.7 of Ref. 3I-1)

The product damping value used for dynamic qualification shall be established. See (Reference 3I-1) Section 5 of IEEE-344. (Also see Subsections 3.9.2.2, 3.9.3, and Section 3.10)

3I.7 QUALIFICATION DETERMINATION

(Paragraph 4.4.3.3 of Ref. 3I-1)

In order for equipment to be qualified by reason of operating experience, documented data will be available confirming that the following criteria have been met:

- (a) the product providing the operating experience is identical or justifiably similar to the equipment to be qualified;*
- (b) the product providing the operating experience has operated under service conditions which equal or exceed, in severity, the service conditions and performance requirements for which the product is to be qualified; and*
- (c) the installed product must, in general, be removed from service and subjected to partial type testing to include the dynamic and design basis event environments for which the product is to be qualified. (See Section 3.10)*

3I.8 DYNAMIC QUALIFICATION BY ANALYSIS

(Paragraph 4.4.4.1.4 of Ref. 3I-1)

- (a) The analytical procedures described in this section may be used for dynamic qualification of products.*
- (b) Many factors control the design of a qualification program. Paragraphs 4.2.2.c(3) and 4.2.2.d(1) of Reference 3I-1 provide general guidelines on dynamic analysis techniques. Analytical techniques and modeling assumptions will, when possible, be based on a correlation of the analytical approach with testing or operating experience performed on similar equipment or structures. Analysis may be used as a qualification method for the following conditions:*
 - (1) if maintaining structural integrity is the only required assurance of the safety function (see Section 3.10);*
 - (2) if the response of the equipment is linear or has a simple nonlinear behavior which can be predicted by conservative analytical methods; or*
 - (3) if the product is too large to test.*

3I.9 REQUIRED RESPONSE SPECTRA

(Paragraph 4.4.4.1.4.6.2 of Ref. 3I-1)

- (a) The required response spectra that define the dynamic criteria for the location(s) of the product under consideration are to be given in the PPQS. If the equipment under consideration is attached to the structural system at more than one location, then the dynamic analysis performed takes into consideration the different response spectra at the different support locations. The effect of multiple support attachment points or multiple locations of the particular product can also be accounted for by selecting a single spectrum which will effectively produce the critical maximum responses due to different accelerations existing at different points. (See Section 3.10.) This may be conservatively accomplished by enveloping the response spectra for the different applicable locations.*

Alternatively, actual multi-support excitation effects may be taken into account by performing a multi-support excitation analysis.

3I.10 TIME HISTORY ANALYSIS

(Paragraph 4.4.4.1.4.6.3 of Ref. 3I-1)

Time history analysis will be performed when conditions arise invalidating the response spectrum method of analysis due to nonlinear phenomena, or when generation of in-equipment response spectra or a more exact result is desired. To integrate or differentiate, the analysis will be done by an applicable numerical integration technique. The largest time step used in the analysis will be 1/10 of the period of the highest significant mode of vibration of the equipment. *The dynamic input will be the time history motion at the equipment support location.* (See Section 3.10.) For products supported at several locations, the responses will be determined by simultaneous excitations using appropriate time history input at each support location. The scaled time interval will be varied as per Paragraph 4.4.2.a(6) of Reference 3I-1.

If the product frequency is within the range of the supporting structure, then a time interval will be chosen such that the peak of the response spectrum shall be at the product resonance frequency. The total time interval range will be provided with the time history.

3I.11 REFERENCES

3I-1 GE Nuclear Energy, "General Electric Environmental Qualification Program," NEDE-24326-1-P, Proprietary Document, January 1983.

3J. EVALUATION OF POSTULATED RUPTURES IN HIGH ENERGY PIPES

3J.1 BACKGROUND AND SCOPE

The need for an evaluation of the dynamic effects of fluid dynamic forces resulting from postulated ruptures in high energy piping systems is included by Standard Review Plan (SRP) Sections 3.6.1 and 3.6.2. The criteria for performing this evaluation is defined in Subsections 3.6.1 and 3.6.2, SRP Sections 3.6.1 and 3.6.2 and ANS 58.2.

This Appendix defines an acceptable procedure for performing these evaluations. The procedure is based on use of analytical methodology, computer programs and pipe whip restraints used by GE, but it is intended to be applicable to other computer programs and to pipe whip restraints of alternate design. Applicability of alternate programs will be justified by the Combined Operating License (COL) applicant.

The evaluation is performed in four major steps:

- (1) Identify the location of the postulated rupture and whether the rupture is postulated as circumferential or longitudinal.
- (2) Select the type and location of the pipe whip restraints.
- (3) Perform a complete system dynamic analysis or a simplified dynamic analysis of the ruptured pipe and its pipe whip restraints to determine the total movement of the ruptured pipe, the loads on the pipe, strains in the pipe whip restraint, and the stresses in the penetration pipe.
- (4) Evaluate safety-related equipment that may be impacted by the ruptured pipe or the target of the pipe rupture jet impingement.

The criteria for locations where pipe ruptures must be postulated and the criteria for defining the configuration of the pipe rupture are defined in Subsection 3.6.2. Also defined in Subsection 3.6.2 are:

- the fluid forces acting at the rupture location and in the various segments of the ruptured pipe, and
- the jet impingement effects including jet shape and direction and jet impingement load.

The high energy fluid systems are defined within Subsection 3.6.2.1, and identified in Tables 3.6-3 and 3.6-4. Safety-related systems, components and equipments, or portions thereof, specified in Tables 3.6-1 and 3.6-2, are to be protected from pipe break effects, which would impair their ability to facilitate safe shutdown of the plant.

The information contained in Subsections 3.6.1 and 3.6.2 and in the SRPs and ANS 58.2 is not repeated in this appendix.

3J.2 IDENTIFICATION OF RUPTURE LOCATIONS AND RUPTURE GEOMETRY

3J.2.1 Ruptures in Containment Penetration Area.

Postulation of pipe ruptures in the portion of piping in the containment penetration area is not allowed. This includes the piping between the inner and outer isolation valves. Therefore, examine the final stress analysis of the piping system and confirm that, for piping in containment penetration areas, the design stress and fatigue limits specified within Subsection 3.6.2.1 are not exceeded.

3J.2.2 Ruptures in Areas other than Containment Penetration.

Postulate breaks in Class 1 piping in accordance with Subsection 3.6.2.1.1.

Postulate breaks in Classes 2 and 3 piping in accordance with Subsection 3.6.2.1.1.

Postulate breaks in seismically analyzed non-ASME Class piping in accordance with the above requirements for Classes 2 and 3 piping.

3J.2.3 Determine the Type of Pipe Break

Determine whether the high energy line break is longitudinal or circumferential in accordance with Subsection 3.6.2.1.3.

3J.3 DESIGN AND SELECTION OF PIPE WHIP RESTRAINTS

3J.3.1 Make Preliminary Selection of Pipe Whip Restraint

The load carrying capability of the GE U-Bar pipe whip restraint is determined by the number, size, bend radius and the straight length of the U-bars. The pipe whip restraint must resist the thrust force at the pipe rupture location and the impact force of the pipe. The magnitude of these forces is a function of the pipe size, fluid, and operating pressure.

A preliminary selection of one of the standard GE pipe whip restraints is made by matching the thrust force at the rupture location with a pipe whip restraint capable of resisting this thrust force. This is done by access to the large database contained in the GE REDEP computer file. This file correlates the pipe size and the resulting thrust force at the pipe rupture with the U-bar pipe whip restraints designed to carry the thrust force. REDEP then supplies the force/deflection data for each pipe whip restraint.

3J.3.2 Prepare Simplified Computer Model of Piping-Pipe Whip Restraint System.

Prepare a simplified computer model of piping system as described in Subsection 3J.4.2.1 and as shown in Figure 3J-1 and Figure 3J-2. Critical variables are length of pipe, type of end condition, distance of pipe from structure and location of the pipe whip restraint. Locate the pipe whip restraint as near as practical to the ruptured end of the pipe but establish location to minimize interference to inservice inspection.

3J.3.3 Run Pipe Dynamic Analysis

Run the Pipe Dynamic Analysis (PDA) computer program using the following input.

- The information from the simplified piping model, including pipe length, diameter, wall thickness and pipe whip restraint location.
- Piping information such as pipe material type, stress/strain curve and pipe material mechanical properties.
- Pipe whip restraint properties such as force-deflection data and elastic plastic displacements.
- Force time-history of the thrust at the pipe rupture location.

3J.3.4 Select Pipe Whip Restraint for Pipe Whip Restraint Analysis

PDA provides displacements of pipe and pipe whip restraint, pipe whip U-bar strains, pipe forces and moments at fixed end, time at peak load and lapsed time to achieve steady state using thrust load and pipe characteristics.

Check displacements at the pipe broken end and at the pipe whip restraint and compare loads on the piping and strains of pipe whip restraint U-bars with allowable loads and strains. If not satisfied with output results rerun PDA with different pipe whip restraint parameters.

3J.4 PIPE RUPTURE EVALUATION

3J.4.1 General Approach

There are several analytical approaches, which may be used in analyzing the pipe/pipe whip restraint system for the effects of pipe rupture. This procedure defines two acceptable approaches.

- (1) **Dynamic Time-History Analysis With Simplified Model** - A dynamic time history analysis of a portion of a piping system may be performed in lieu of a complete system analysis when it can be shown to be conservative by test data or by comparison with a more complete system analysis. For example, in those cases where pipe stresses in the containment penetration region need not be calculated, it is acceptable to model only a portion of the piping system as a simple cantilever with a fixed or pinned end or as a beam with both ends fixed or with one end pinned and one end fixed.

When a circumferential break is postulated, the pipe system is modeled as a simple cantilever, the thrust load is applied opposite the fixed (or pinned) end and the pipe whip restraint acts between the fixed (or pinned) end and the thrust load. It is then assumed that deflection of the pipe is in one plane. As the pipe moves a resisting bending moment in the pipe is created and later a restraining force at the pipe whip restraint. Pipe movement stops when the resisting moments about the fixed (or pinned) end exceed the applied thrust moment.

When a longitudinal break is postulated, the pipe system has both ends supported. To analyze this case, two simplifications are made to allow the use of the cantilever model described above. First, an equivalent point mass is assumed to exist at D (Figure 3J-2)

instead of pipe length DE. The inertia characteristics of this mass, as it rotates about point B, are calculated to be identical to those of pipe length DE, as it rotates about point E. Second, an equivalent resisting force is calculated (from the bending moment-angular deflection relationships for end DE) for any deflection for the case of a built-in end. This equivalent force is subtracted from the applied thrust force when calculating the net energy.

See Figure 3J-1 and Figure 3J-2 for the models described above.

- (2) **Dynamic Time-History Analysis with Detailed Piping Model**—In many cases it is necessary to calculate stresses in the ruptured pipe at locations remote from the pipe whip restraint location. For example, the pipe in the containment penetration area must meet the limits of SRP 3.6.2. In these cases it is required that the ruptured piping, the pipe supports, and the pipe whip restraints be modeled in sufficient detail to reflect their dynamic characteristics. A time-history analysis using the fluid forcing functions at the point of rupture and the fluid forcing functions of each pipe segment is performed to determine deflections, strains, loads to structure and equipment and pipe stresses.

3J.4.2 Procedure For Dynamic Time-History Analysis With Simplified Model

3J.4.2.1 Modeling of Piping System

For many piping systems, required information on the response to a postulated pipe rupture can be determined by modeling a portion of the piping system as a cantilever with either a fixed or pinned end. The fixed end model, as shown in Figure 3J-1, is used for piping systems where the stiffness of the piping segment located between A and B is such that the slope of the pipe length, BD, at B, would be approximately zero. The pinned end model, as shown in Figure 3J-1, is used for piping systems where the slope of the pipe length, BD, at B, is much greater than zero. The pinned end model is also used whenever it is not clear that the pipe end is fixed.

A simplified cantilever model may also be used for a postulated longitudinal break in a pipe supported at both ends, as shown in Figure 3J-2. The pipe can have both ends fixed or have pinned end at B and a fixed end at E, as shown in Figure 3J-2. Subsection 3J.4.1(1) discusses the simplification techniques used to allow the use of a cantilever model. A fixed end is used when rotational stiffness of the piping at that location is such that the slope of the pipe at that end is approximately zero. A pinned end is used when the pipe slope at that end is much greater than zero. If it is not clear whether an end is fixed or pinned, the end condition giving more conservative results should be assumed.

The pipe whip restraint is modeled as two components acting in series; the restraint itself and the structure to which the restraint is attached. The restraint and piping behave as determined by an experimentally or analytically determined force-deflection relationship. The structure deflects as a simple linear spring of representative spring constant.

The model must account for the maximum clearance between the restraint and the piping. The clearance is equal to the maximum distance from the pipe during normal operation to the position of the pipe when the pipe whip restraint starts picking up the rupture load. This simplified model is not used if the piping has snubbers or restraints strong enough to affect the pipe movement following a postulated rupture.

3J.4.2.2 Dynamic Analysis of Simplified Piping Model

When the thrust force (as defined in Subsection 3.6.2.2) is applied at the end of the pipe, rotational acceleration would occur about the fixed (or pinned) end. As the pipe moves, the net rotational acceleration would be reduced by the resisting bending moment at the fixed end and by the application of the restraining force at the pipe whip restraint. The kinetic energy would be absorbed by the deflection of the restraint and the bending of the pipe. Movement would continue until equilibrium is reached. The primary acceptance criteria is the pipe whip restraint deflection or strain must not exceed the design strain limit of 50% of the restraint material ultimate uniform strain capacity.

The analysis may be performed by a general purpose computer program with capability for nonlinear time-history analysis such as ANSYS, or by a special purpose computer program especially written for pipe rupture analysis such as the GE computer program, "Pipe Dynamic Analysis".

3J.4.3 Procedure For Dynamic Time-History Analysis Using Detailed Piping Model

3J.4.3.1 Modeling of Piping System

In general, the rules for modeling the ruptured piping system are the same as the modeling rules followed when performing seismic/dynamic analysis of Seismic Category I piping. These rules are outlined in Subsection 3.7.3.3. The piping, pipe supports and pipe whip restraints are modeled in sufficient detail to reflect their dynamic characteristics. Inertia and stiffness effects of the system and gaps between piping and the restraints must be included.

If the snubbers or other seismic restraints are included in the piping model they should be modeled with the same stiffness used in the seismic analysis of the pipe. However, credit for seismic restraints cannot be taken if the applied load exceeds the Level D rating.

The pipe whip restraints are modeled the same as for the simplified model described in Subsection 3J.4.2.1. For piping designed with the GE U-Bar pipe whip restraints, the selected size and dimensions, and the resulting force-deflection and elastic/plastic stiffness is first determined according to the procedure previously defined in Section 3J.3.

3J.4.3.2 Dynamic Analysis using Detail Piping Model

The pipe break nonlinear time-history analysis can be performed by ANSYS or other NRC approved non-linear computer programs. The force time histories acting at the break location and in each of the segments of the ruptured pipe are determined according to the criteria defined in ANS 58.2. The time step used in the analysis must be sufficiently short to obtain convergence of the solution. (GE has shown that for a rupture of the main steam pipe a time step of 0.001 second is adequate for convergence.) The analysis must not stop until the peaks of the dynamic load and the pipe response are over.

The primary acceptance criteria are:

- The piping stresses between the primary containment isolation valves are within the allowable limits specified in Subsection 3.6.2.1.

- The pipe whip restraint loads and displacements due to the postulated break are within the design limits.
- Specified allowable loads on safety-related valves or equipment to which the ruptured piping is attached are not exceeded.

3J.5 JET IMPINGEMENT ON ESSENTIAL PIPING

Postulated pipe ruptures result in a jet of fluid emanating from the rupture point. Safety-related systems and components require protection if they are not designed to withstand the results of the impingement of this jet. Subsection 3.6.2.3.1 provides the criteria and procedure for:

- (1) defining the jet shape and direction;
- (2) defining the jet impingement load, temperature and impingement location; and
- (3) analysis to determine effects of jet impingement on safety-related equipment.

The paragraphs below provide some additional criteria and procedure for the analysis required to determine the effects of jet impingement on piping.

- Jet impingement is a faulted load and the primary stresses it produces in the piping must be combined with the stresses caused by SSE to meet the faulted stress limits for the designated ASME class of piping.
- If a pipe is subjected to more than one jet impingement load, each jet impingement load is applied independently to the piping system and the load which supplies the largest bending moment at each node is used for evaluation.
- A jet impingement load may be characterized as a two part load applied to the piping system—a dynamic portion when the applied force varies with time and a static portion which is considered steady state.

For the dynamic load portion, when static analysis methods are used, apply a dynamic load factor of 2. Snubbers are assumed to be activated. Stresses produced by the dynamic load portion are combined by SRSS with primary stresses produced by SSE.

For the static load portion, snubbers are not activated and stresses are combined with SSE stresses by absolute sum.




Figure 3J-1. Simplified Piping Models




Figure 3J-2. Representation of Pipe With Both Ends Supported With a Longitudinal Break

3K. RESOLUTION OF INTERSYSTEM LOSS OF COOLANT ACCIDENT

3K.1 INTRODUCTION

An Intersystem Loss of Coolant Accident (ISLOCA) is postulated to occur when a series of failures or inadvertent actions occur that allow the high pressure from one system to be applied to the low design pressure of another system, which could potentially rupture the pipe and release coolant from the reactor system pressure boundary. This may also occur within the high and low pressure portions of a single system. Future advanced light water reactor (ALWR) designs like the ESBWR are expected to reduce the possibility of a LOCA outside the containment by designing to the extent practicable all piping systems, major system components (pumps and valves), and subsystems connected to the reactor coolant pressure boundary (RCPB) to an ultimate rupture strength at least equal to the full RCPB pressure. The general Ultimate Rupture Strength (URS) criteria was recommended by the Reference 1 and the NRC Staff recommended specific ultimate rupture strength design characteristics by Reference 2.

3K.2 REGULATORY POSITIONS

In SECY-90-016 and SECY-93-087 (References 3 and 4), the NRC staff resolved the ISLOCA issue for advanced light water reactor plants by requiring that low-pressure piping systems that interface with the reactor coolant pressure boundary be designed to withstand reactor pressure to the extent practicable. However, the staff believes that for those systems that have not been designed to withstand full reactor pressure, evolutionary ALWRs should provide (1) the capability for leak testing the pressure isolation valves, (2) valve position indication that is available in the control room when isolation valve operators are de-energized and (3) high-pressure alarms to warn main control room operators when rising reactor pressure approaches the design pressure of attached low-pressure systems or when both isolation valves are not closed. The staff noted that for some low-pressure systems attached to the RCPB, it may not be practical or necessary to provide a higher system ultimate pressure capability for the entire low-pressure connected system. The staff will evaluate such exceptions on a case-by-case basis during specific design certification reviews.

GE provided a proposed implementation of the issue resolution for the ABWR in Reference 5 and again in Reference 6. The staff in the Civil Engineering and Geosciences Branch of the Division of Engineering completed its evaluation of the Reference 5 proposal. Specifically, as reported by Reference 2 and summarized below, the staff has evaluated the minimum pressure for which low-pressure systems should be designed to ensure reasonable protection against burst failure should the low-pressure system be subjected to full RCPB pressure.

The design pressure for the low-pressure piping systems that interface with the RCPB should be equal to 0.4 times the normal operating RCPB pressure, the minimum wall thickness of low-pressure piping should be no less than that of a standard weight pipe, and that Class 300 valves are adequate. The design is to be in accordance with the ASME Boiler and Pressure Vessel Code, Section III, Subarticle NC/ND-3600. Furthermore, the staff will continue to require periodic surveillance and leak rate testing of the pressure isolation valves via Technical Specifications, as a part of the ISI program.

The periodic surveillance and leak rate testing requirements for high-pressure to low-pressure isolation valves are not applicable to the ESBWR, because, as shown in this appendix, the ESBWR design does not contain a pressure isolation valve between the reactor coolant pressure boundary and a low pressure piping system.

3K.3 BOUNDARY LIMITS OF ULTIMATE RUPTURE STRENGTH

Guidance given by Reference 3 provides provision for applying practical considerations for the extent to which systems are upgraded to the ultimate rupture strength design pressure. The following items form the basis of what constitutes practicality and set forth the test of practicality used to establish the boundary limits of ultimate rupture strength for the ESBWR:

- It is impractical to consider a disruptive open flow path from reactor pressure to a low pressure sink. A key assumption to understanding the establishment of the boundary limits from this practicality basis is that only static pressure conditions are considered. Static conditions are assumed when the valve adjacent to a low pressure sink remains closed. Thus, the dynamic pressurization effects accompanied by violent high flow transients and temperature escalations are precluded that would occur if the full RCPB pressure was connected directly to the low pressure sink. As a consequence, the furthest downstream valve in such a path is assumed closed so that essentially all of the static reactor pressure is contained by the ultimate rupture strength upgraded region.
- It is impractical to design or construct large tank structures to the ultimate rupture strength design pressure that are vented to atmosphere and have a low design pressure.
- It is impractical to design piping systems that are connected to low pressure sink features to the ultimate rupture strength design pressure when the piping is always locked open to a low pressure sink by locked open valves. These piping sections are extensions of the low pressure sink and need no greater design pressure than the low pressure sink to which they are connected.

3K.4 EVALUATION PROCEDURE

The pressures of each system piping boundary on the ESBWR system drawings were reviewed to identify where changes were needed to provide ultimate rupture strength protection. Where low pressure piping interfaces with higher pressure piping connected to piping with reactor coolant at reactor pressure, design pressure values are at least rated to the ultimate rupture strength design pressure. The low pressure piping boundaries were upgraded to ultimate rupture strength pressures and extend to the last closed valve connected to piping interfacing a low pressure sink.

3K.5 SYSTEMS EVALUATED

The following systems, interfacing directly with the RCPB, were evaluated.

- | | |
|--|-------------|
| • Control Rod Drive (CRD) system | Section 4.6 |
| • Standby Liquid Control (SLC) system | Section 9.3 |
| • Reactor Water Cleanup/Shutdown Cooling (RWCU/SDC) system | Section 5.4 |
| • Fuel and Auxiliary Pools Cooling System (FAPCS) | Section 9.1 |

- Nuclear Boiler System (NBS) Section 5.1
- Condensate and Feedwater System (C&FS) Section 10.4

Attachment 3KA contains a system-by-system evaluation of potential reactor pressure application to piping and components, discussing the ultimate rupture strength boundary and listing the upgraded components. For some systems, certain regions of piping and components not upgraded are also listed.

3K.6 PIPING DESIGN PRESSURE FOR ULTIMATE RUPTURE STRENGTH COMPLIANCE

Guidelines for ultimate rupture strength compliance were established by Reference 2, which concluded that for the ESBWR:

- The design pressure for the low-pressure piping systems that interface with the RCPB pressure boundary should be equal to 0.4 times the normal operating RCPB pressure, and
- The minimum wall thickness of the low-pressure piping should be no less than that of a standard weight pipe.

3K.7 APPLICABILITY OF ULTIMATE RUPTURE STRENGTH NON-PIPING COMPONENTS

Reference 2 also provided the NRC Staff's position that:

- (1) The remaining components in the low-pressure systems should also be designed to a design pressure of 0.4 times the normal operating reactor pressure. This is accomplished in DCD by the revised boundary symbols on system design drawings to the design pressure, which includes the piping and components associated with the boundary symbols. A stated parameter (e.g., design pressure) of a boundary symbol on the system design drawing applies to the piping and components that extend away from the boundary symbol, including along any branch line, until another boundary symbol occurs on the drawing. The components include flanges, and pump seals, etc.
- (2) A Class 300 valve is adequate for ensuring the pressure of the low-pressure piping system under full reactor pressure. The rated working pressure for Class 300 valves varies widely depending on material and temperature (ASME/ANSI B16.34).

3K.8 RESULTS

The results of this work are incorporated into the ESBWR system drawings.

3K.9 VALVE MISALIGNMENT DUE TO OPERATOR ERROR

The ESBWR design with the ISLOCA ultimate rupture strength applied for the boundary described by this appendix and its attachment, has extended the increased design pressure (ultimate rupture strength) over the full extent of regions that could potentially experience reactor pressure, so that operator misaligned valves will not expose piping to reactor pressure not designed to the ultimate rupture strength pressure.

3K.10 SUMMARY

Based on the NRC staff's new guidance cited in References 1 through 4, the ESBWR is in full compliance. For ISLOCA considerations, a design pressure of at least the ultimate rupture strength design pressure and pipe having a minimum wall thickness equal to standard grade has been provided as an adequate margin with respect to the full reactor operating pressure, by applying the guidance recommended by Reference 2. This design pressure was applied to the low pressure piping at their boundary symbols on the system drawings, therefore, imposes the requirement on the associated piping, valves, pumps, tanks, instrumentation and other equipment shown between boundary symbols. Notes were added to each ultimate rupture strength upgraded drawing, requiring pipe to have a minimum wall thickness equal to standard grade and requiring valves with a design pressure of at least the ultimate rupture strength design pressure to be a minimum of Class 300.

3K.11 REFERENCES

- 3K-1 USNRC, Dino Scaletti, NRC, to Patrick Marriott, "GE, Identification of New Issues for the General Electric Company Advanced Boiling Water Reactor Review," September 6, 1991.
- 3K-2 Chester Poslusny, NRC, to Patrick Marriott, "GE, Preliminary Evaluation of the Resolution of the Intersystem Loss-of-Coolant Accident (ISLOCA) Issue for the Advanced Boiling Water Reactor (ABWR) - Design Pressure for Low-Pressure Systems," December 2, 1992, Docket No. 52-001.
- 3K-3 James M. Taylor, NRC, to The Commissioners, SECY-90-016, "Evolutionary Light Water Reactor (LWR) Certification Issues and Their Relationship to Current Regulatory Requirements," January 12, 1990.
- 3K-4 James M. Taylor, NRC, to The Commissioners, SECY-93-087, "Policy, Technical, and Licensing Issues Pertaining to Evolutionary and Advanced Light-Water Reactor (ALWR) Designs," April 2, 1993.
- 3K-5 Jack Fox, GE, to Chet Poslusny, NRC, "Proposed Resolution of ISLOCA Issue for ABWR," October 8, 1992.
- 3K-6 Jack Fox, GE, to Chet Poslusny, NRC, "Resolution of Intersystem Loss of Coolant Accident for ABWR," April 30, 1993.

ATTACHMENT 3KA. ULTIMATE RUPTURE STRENGTH SYSTEM BOUNDARY EVALUATION

3KA.1 CONTROL ROD DRIVE SYSTEM

3KA.1.1 System URS Boundary Description

The Control Rod Drive (CRD) system interfaces with the reactor in a manner that makes low pressure piping over pressurization very unlikely. The minimum failure path from the reactor to the low pressure piping has three check valves in series and the second check valve is 12.7 mm in size. This path is from the purge flow channels of the CRD, out through the first check valve in the CRD housing, through the purge supply line that has the second 12.7 mm check valve, and to the pump discharge check valve. An alternate path through the accumulator charging line has additionally the normally closed scram valve, and this path is less likely for failure, therefore not considered. The path from the pump discharge, back through the pump to its suction, and back through the suction lines to the condensate storage tank or the condensate feedwater source is an open path. The open pump suction pipeline is a minimum 100 mm diameter through the pump suction filters in the normal mode of operation, and 200 mm diameter when the suction filter bypass lines are open during the reactor high pressure makeup mode of operation. The CRD pumps run continuously while the reactor is at operating pressure, which prevents reactor pressure from reaching the low pressure piping except for the unlikely case when both CRD pumps have failed. Therefore, an ISLOCA condition from a 12.7 mm diameter source could only occur when three check valves in series fail open at the same time both CRD pumps have failed. The ISLOCA guidelines do not provide credit for this rare condition, so the low pressure piping has been upgraded to the URS design criteria over the entire low pressure piping region of the CRD system. The suction path through the Condensate Storage and Transfer System (CS&TS) to the Condensate Storage Tank (CST) from the CRD interface is an open path whose design pressure was not upgraded to URS design criteria. The piping design of the primary suction path through the Condensate and Feedwater System has not been established, but if a check valve is in the path, the design pressure up to and including the check valve will be the URS design pressure.

The normal key assumption, as stated in the Boundary Limits of URS section above, that the valve adjacent to a low pressure sink remains closed, means that the pump discharge check valve remains closed as a given. However, this valve is in the high pressure piping, which is unique for the CRD system according to this accepted line of reasoning. The low pressure piping would not have to be upgraded because it would not experience the high reactor pressure. However, the low-pressure piping has been designed to the URS design pressure based on the guidance that states “for all interfacing systems and components which do not meet the full URS criteria, justification is required, which must include engineering feasibility; not solely a risk benefit analysis.” Designing the low-pressure piping to the URS design pressure is feasible and was done.

3KA.1.2 Downstream Interfaces

Other systems are listed below that interface with the CRD system and could possibly be exposed to reactor pressure. A description of the interface location and a statement of its applicability to ISLOCA are given.

- RWCU/SDC system at the output of the CRD pump discharge filter units. The RWCU/SDC design pressure exceeds the URS design pressure without upgrade.
- NBS at the output of the CRD pump discharge filter units. The NBS design pressure exceeds the URS design pressure without upgrade.
- CS&TS provides an alternate source of water for the CRD system if the C&FS is not available. Its interfaces with the CRD system are located at pump suction from and system return to the CST. This line cannot be pressurized because of the open communication to the CST, and the CST is vented to atmosphere. There is no source to pressurize the CS&TS line because of closed pump discharge check valves in the CRD URS region.
- C&FS provides a source of water for the CRD pump suction from the turbine building condensate supply. This system is expected to be an open path to a large source similar to CS&TS. Because of the open path, the piping was not considered practical for upgrade to the URS design pressure.
- Process Sampling System (PSS) at the output of the CRD pump discharge filter units. The PSS design pressure exceeds the URS design pressure without upgrade.

3KA.1.3 Low-Pressure Piping Systems and Components Designed to URS Pressure

The following is a listing of low-pressure piping systems and components within CRD that are designed to the minimum URS design pressure of 2.82 MPaG based on the ISLOCA considerations outlined in Appendix 3K.

Pipeline / Component Description (see Figure 4.6-8)

CRD Pump Suction Piping and Associated Components

3KA.2 STANDBY LIQUID CONTROL SYSTEM

3KA.2.1 System URS Boundary Description

The SLC system is a high pressure system which injects enriched sodium pentaborate solution inside the reactor through normally closed squib valves. The leakage path includes two 80 mm check valves in series in addition to a redundant set of normally closed pyrotechnic-type squib valves. The entire SLC system is designed for pressure higher than reactor pressure except the low pressure section from piston pump suction to open mixing drum used for preparation of sodium pentaborate solution. Instrumentation, pressure relief, drain piping and valving are designed to higher than URS design criteria to reduce the level of pressure challenge to these components. The system does not require upgrade to URS design pressure.

3KA.2.2 Downstream interfaces

The SLC system has no further downstream system interfaces that could possibly be exposed to reactor pressure.

3KA.2.3 Low Pressure Piping Systems and Components Designed to URS Pressure

None

3KA.3 REACTOR WATER CLEANUP/SHUTDOWN COOLING SYSTEM

3KA.3.1 System URS Boundary Description

The RWCU/SDC system is a high pressure system that is designed above the URS pressure with the following exception. Low pressure piping connected to the condenser and the liquid waste management system are provided at the downstream of the overboarding line isolation valves. On the upstream side of the isolation valves is provided a pressure reducing control valve that reduces the pressure before the flow enters the low pressure piping.

3KA.3.2 Downstream Interfaces

Other systems are listed below that interface with RWCU/SDC system and could possibly be exposed to reactor pressure. A description of the interface location and a statement of its applicability to ISLOCA are given.

- FAPCS interfacing piping from the reactor well at the upstream of the Train B of RWCU/SDC system non-regenerative heat exchanger has two locked closed isolation valves in series and the piping provides an open free path to reactor well which is an atmospheric pressure pool.
- FAPCS Low Pressure Coolant Injection (LPCI) interfacing piping with Train B of RWCU/SDC system return piping to Feedwater Line A is designed to a pressure that is above the URS pressure.
- CRD system interfacing piping with Train A of RWCU/SDC system return piping to Feedwater Line B is designed to a pressure that is above the URS pressure.

3KA.3.3 Low-Pressure Piping Systems and Components Designed to URS Pressure

The RWCU/SDC system low pressure piping connected at the downstream side of the overboarding line isolation valves is designed to pressure so that the stresses do not exceed the allowable stresses if the piping is subjected to full reactor pressure.

3KA.4 FUEL AND AUXILIARY POOLS COOLING SYSTEM

3KA.4.1 System URS Boundary Description

FAPCS is a low pressure piping system. Its LPCI line is connected to RWCU/SDC system Loop B discharge line, which has an interface with reactor coolant pressure boundary via the Feedwater Loop A discharge line [Figure 9.1-A]. During reactor power operation, an unisolated break outside the reactor coolant pressure boundary could lead to an ISLOCA with the release of reactor coolant from the reactor system pressure boundary. In the FAPCS case, it would require multiple failures before a LOCA could occur, i.e., a break in the FAPCS piping plus failures of the Feedwater line check valves, which maintain the reactor coolant pressure boundary.

3KA.4.2 Downstream Interfaces

The following design features are provided to the interface between the high and low pressure interfaces to prevent an intersystem LOCA from occurring in FAPCS piping:

- Normally closed isolation valves consisting of an air-operated check valve and a motor-operated gate valve are provided on the LPCI line to separate the low pressure FAPCS piping from the high pressure condition in the RWCU/SDC pipe during reactor power operation.
- Valve position lights are provided to the operator in the main control room (MCR) to confirm these isolation valves in the closed positions.
- The isolation valves are provided with a reactor pressure interlock that closes these valves and prevents them from opening whenever a high reactor pressure signal from the NBS is present. Reactor pressure signals ensure high reliability that the isolation valves remain closed.
- The FAPCS LPCI pipe and components between its interface with RWCU/SDC system and the motor-operated gate valve, including the gate valve are Quality Group B components designed to above URS pressure.

3KA.4.3 Low-Pressure Piping Systems and Components Designed to URS Pressure

The low pressure side of LPCI line and the rest of FAPCS piping are not required to be designed to the URS pressure because they are properly protected by the interlock closed isolation valves described above and by a relief valve installed on the LPCI line that protects the line from the overpressure condition, in case of leakage from the RWCU/SDC system side through the isolation valves.

3KA.5 NUCLEAR BOILER SYSTEM

3KA.5.1 System URS Boundary Description

The Main Steam (MS) and Feedwater piping and instrumentation are designed for reactor pressure and do not require upgrading to URS design pressure.

3KA.5.2 Downstream Interfaces

Other systems are listed below that interface with MS and could possibly be exposed to reactor pressure. A description of the interface location and a statement of its applicability to ISLOCA are given.

- The outlet of the CRD pump discharge filter units provide flow to the NBS.
- The CRD design pressure exceeds the URS design pressure without upgrade.
- RWCU/SDC provides high pressure return flow to the Feedwater lines. The RWCU/SDC design pressure exceeds the URS design pressure without upgrade.
- The Isolation Condenser system connects to a piping stub that connects the DPVs to the RPV, and also there are IC vent lines that connect to the main steam lines. The IC design pressure exceeds the URS design pressure without upgrade.

3KA.5.3 Low-Pressure Piping Systems and Components Designed to URS Pressure

None

3KA.6 CONDENSATE AND FEEDWATER SYSTEM

3KA.6.1 System URS Boundary Description

The feedwater subsystem of the C&FS provides high pressure feedwater to the reactor. The feedwater subsystem is designed for high pressure except for the feedwater pump suction and the outlet of the feedwater cleanup valve.

In the feedwater pump, the transition to low pressure occurs from the feedwater pump suction into the direct contact feedwater heater (feedwater tank). The feedwater tank is a low pressure sink. The last closed valve in the path from the reactor is the feedwater pump discharge check valve. The piping to the feedwater pump suction can remain below the URS design pressure because it connects to the low pressure heat sink feedwater tank. The maintenance block valves in the feedwater pump suction lines were upgraded to a LOCK OPEN status.

In the feedwater cleanup control valve, the transition to low pressure occurs from the feedwater cleanup control valve outlet connection into the condenser shell (hotwell). The hotwell is a low pressure sink. The last closed valve in the path from the reactor in the feedwater cleanup control valve is the normally closed block valve. The piping from the feedwater cleanup control valve to the condenser can remain below the URS design pressure because it connects to the low pressure heat sink hotwell.

The Condensate subsystem of the C&FS provides condensate to the feedwater tank, and the condensate subsystem is designed for a pressure higher than the feedwater tank, except for the condensate pump suction. The high pressure design includes the condensate polishing (hollow fiber filters and demineralizers) units and the feedwater bypass valve. The transition to low pressure occurs from the condensate suction into the HP condenser shell (hotwell, which is a low pressure sink). The last closed valve in the path from the feedwater tank is the condensate pump discharge check valve. The piping to the condensate pump suction can remain below the feedwater tank design pressure because it connects the low pressure heat sink hotwell. The maintenance block valves in the condensate pump suction lines were upgraded to a LOCK OPEN status.

3KA.6.2 Downstream Interfaces

None

3KA.6.3 Low-Pressure Piping Systems and Components Designed to URS Pressure

The maintenance block valves in the condensate pump suction lines were upgraded to a LOCK OPEN status.

3L. REACTOR INTERNALS FLOW INDUCED VIBRATION PROGRAM

3L.1 INTRODUCTION

A flow-induced vibration (FIV) testing program of the reactor internal components of the ESBWR prototype plant is to be completed to demonstrate that the ESBWR internals design can safely withstand expected FIV forces for reactor operating conditions up to and including 100% power and core flow. This program includes an initial evaluation phase that has the objective of demonstrating that the reactor internals are not subject to FIV issues that can lead to failures due to material fatigue, or fretting and wear issues. Throughout this part of the program, the emphasis will be placed on demonstrating that the reactor components will safely operate for the design life of the plant. The results of this evaluation are shown in Reference 3L-1. The second phase of the program is focused on preparing and performing the startup test program that demonstrates through instrumentation and inspection that no FIV problems exist. This part of the program meets the requirements of Regulatory Guide 1.20 with the exception of those requirements related to preoperational testing that are not applicable to a natural circulation plant.

3L.2 REACTOR INTERNAL COMPONENTS FIV EVALUATION

The ESBWR reactor internals are part of an evolutionary BWR design, but fundamentally the components and operation of the reactor vessel and internals are very similar to past BWRs. To a large extent the ESBWR design of the components relies heavily on the prior design of internals in operating plants to assure that new vibration issues are not introduced. Also, to assure that the flow of steam or water in the reactor vessel is comparable to prior reactors, efforts were made to maintain traditional spacing and dimensional relationships of components. A unique feature of the ESBWR, with respect to FIV, is the fact that it is a natural circulation plant where no recirculation motors exist that would create pressure pulses from the pump vanes that would travel into the reactor vessel. In previous BWR product lines, the pump vane passing frequency, that is variable with flow, typically has a maximum frequency of 120 Hz at full reactor flow. This source of excitation has caused failures in small components inside BWR reactor vessels. For ESBWR this source of flow excitation does not exist. The design of the ESBWR reactor internals is shown in Figure 5.5-3.

3L.2.1 Evaluation Process – Part 1

The first step in the evaluation process was to establish selection criteria for reactor internal components related to susceptibility to vibration. All reactor internal components were considered as potential candidates for further evaluation. Each component is evaluated against the following selection criteria:

- Is the component critical to safety?
- Is the component of a significantly different or new design compared to earlier BWRs?
- Does the component have a history of FIV-related problems?
- Is the component subjected to significantly different or new flow conditions?

Based on these criteria, the following internal component structures are considered to be candidates for additional evaluation and potential to be instrumented in the startup FIV test program:

- Steam Dryer Bank Hoods and End Plates based on history of past FIV related problems (fatigue cracking between hood and endplate).
- Steam Dryer Skirt based on history of past FIV-related problems (fatigue cracking between skirt and drain channels).
- Steam Dryer Drain Channels based on history of FIV-related problems (fatigue cracking between skirt and drain channels).
- Steam Dryer Support Ring based on history of FIV-related problems (dryer rocking) and the resulting new design features for replacement dryer designs (e.g., strengthened weld joints, castings).
- Chimney partition assembly based on new design features (elongated chimney shell, partition assembly, chimney restraint), potential new flow conditions, difficulty of repair in event of failure, and limited ability to change the design due to dimensional constraints.

- Chimney Head / Steam Separator assembly based on new design (flat head with beam reinforcement and elongated standpipes).
- Shroud /Chimney assembly based on new design features (discrete shroud support members and the chimney connection), potential new flow conditions and difficulty of repair in event of failure.
- Standby Liquid Control (SLC) internal piping based on new design and being critical to safety.

Components that were evaluated but were not considered important for further evaluation were the following components:

- Control Rod Guide Tubes (CRGTs)
- In-Core Monitor Guide Tubes (ICMGTs)
- In-Core Monitor Housings (ICMHs)

For each of these components, the length of the components has decreased from prior BWR product lines due to the plant having shorter fuel. This increases the natural frequency of these components and moves it well beyond the predominated frequency measured at the prototype ABWR plant. Also, the flow conditions in the RPV bottom head region have decreased and the calculated vortex shedding frequencies are well below the natural frequencies of components.

Other components that are not specifically identified as candidates for the instrumentation program are basically proven by past trouble-free BWR experience, and have designs and flow conditions that are similar to prior operating BWR plants.

From this list, the first priority was determined to be the chimney partition assembly. This selection was made since it was a new component where only limited operating experience was available. Also, it is a structure where the geometry of the partitions places limitations on the plate thicknesses, has a long extended length, and is subject to high velocity two-phase steam flow. From this initial selection, a test and analysis program was established and the results are discussed in Subsection 3L.3.3. For this case, testing was required since no prior relevant test data was available for this component.

The steam dryer was established as the second priority. An initial analysis program was started to study the acoustic and flow effects of the ESBWR configuration in comparison to the ABWR steam dryer design. It was determined that the increase in the size of the steam dryer support ring and skirt design, and the increase in steam velocity did not have any adverse effects on the steam dryer structural integrity. At the time of the initial assessment, it was also recognized that the evaluation of BWR operating plant dryer loads was an ongoing program that would need to be ultimately factored into the ESBWR steam dryer design and evaluation effort. The progress of the generic steam dryer program is now at a stage that a meaningful effort can now be planned for the ESBWR steam dryer. The detailed program that is planned is described in Section 3L.4. As a result of the advances in the understanding of dryer vibration and differential pressure loads and steam dryer design improvements, the ESBWR will use a steam dryer design patterned after the replacement steam dryer design developed for BWR operating plants.

The next part of the evaluation phase will be to complete a more quantitative evaluation of the remaining components with the objective of documenting the existing facts regarding the individual components. This part of the evaluation will focus on the following:

- (1) Similarities and differences of the ESBWR component design configurations as compared to prior designs. In most cases the comparison design will be with the ABWR components.
- (2) A review of prior component calculations for the components being evaluated, to establish the mode shapes and natural frequencies. Estimates of the ESBWR component natural frequencies will then be determined based on this data.
- (3) Prior plant startup instrumentation data from the prototype ABWR plant will be reviewed to establish the magnitude and frequency of the measured vibration data, and to review the resulting calculated stress for the components that were instrumented.
- (4) A comparison of the flow paths and characteristics of the ESBWR design will be compared to prior BWR designs where a startup vibration test program was conducted.
- (5) Using the results of the above items, an assessment as to likelihood of FIV issues will be completed and documented in a supplemental report. The objective in some cases will be to conclusively demonstrate that FIV will not be an issue and that safety will not be adversely affected. In other cases, the conclusions may determine that additional evaluation or instrumentation is necessary. For these cases, no FIV issues are anticipated, and the objective is to provide additional supporting information that clearly demonstrates that FIV is not an issue.

3L.2.2 Evaluation Process – Part 2

The next phase of the evaluation program will be to perform additional work to demonstrate the adequacy of components where it was determined that additional evaluations were required, and to do the next steps that are necessary for those components that are planned for instrumentation in the ESBWR startup test program. During this phase, the process as identified in Subsection 3.9.2.3 will be followed to prepare finite element analysis models per the details shown in Subsection 3L.5.5.1, establish correlation functions based on prior instrumentation data, and apply the correlation functions to the model to determine expected stress amplitude. The results of these evaluations will be documented in a supplemental report.

Because most of the reactor internal components are large durable components where there has been no history of FIV issues, no FIV issues are anticipated. Also, because it is still early in the program, there is still the opportunity to make adjustments as necessary in the component designs to make them more resistant to FIV.

3L.3 CHIMNEY PARTITION ASSEMBLY EVALUATION

3L.3.1 Design and Materials

The chimney partition assembly design consists of a bottom ring of the partition assembly that rests on and is bolted and pinned to the bottom flange of the chimney. The top ring of the partition assembly is supported against the inside of the chimney shell. The partitions are a grid of square structures, each of which encompasses 16 fuel assemblies. The partitions are to be fabricated using austenitic stainless steel plate that is full length welded at the junctions of the partitions. The austenitic stainless steel material has a 0.02% maximum carbon content to resist Intergranular Stress Corrosion Cracking (IGSCC). The chimney structure that houses the partition structure is cylindrical and similar to the core shroud. A sketch of the chimney and partition assembly is shown in Figure 3L-2. Because the chimney has structural characteristics similar to the shroud, this component is considered under the generic reactor internals vibration program, and the partition assembly is considered to be the unique component that requires special vibration consideration

3L.3.2 Prior Operating Experience

Prior to the ESBWR design, only one other BWR plant had operating experience with this chimney design. This was the BWR-1 Dodewaard plant, which did not have a vibration instrumentation program. For this plant, the partition size was a square configuration that encompassed four fuel assemblies within the cell, which is $\frac{1}{4}$ the dimension of the ESBWR partitions. Also, the height was approximately $\frac{1}{2}$ the length of the ESBWR design. The partition thickness was 3 mm (0.125 inch) as compared to 9 mm for ESBWR, and the partitions were welded together using intermittent fillet welds as compared to full-length welds for ESBWR. Although the partitions were not instrumented, the plant operated for almost 30 years without any issues related to the chimney structure. Since the design of the ESBWR chimney partitions is more robust, this Dodewaard operational history provides additional assurance that the ESBWR will not have FIV issues.

3L.3.3 Testing and Two-phase Flow Analysis

For the ESBWR, the chimney lattice partition assembly constitutes a structure that needs to have a unique vibration evaluation program as part of the ESBWR reactor internals. In order to assess its capability to maintain structural integrity under plant operating conditions, a flow induced vibration evaluation has been performed in which the fluctuating fluid force acting on the partition plates has been evaluated by a combination of scale tests and two-phase flow analysis.

The test scope comprised both 1/6-scale (100mm × 100mm) and 1/12-scale (50mm × 50mm) air and water two-phase flow testing of a single chimney cell. The superficial velocities of the gas and liquid components of the two-phase flow were adjusted to be consistent with ESBWR values to simulate the actual two-phase flow pattern. Different inlet flow conditions were used to investigate the influence of inlet mixing within the partition to simulate different power conditions. Pressure fluctuation was measured on the inner surface of the partition wall with pressure transducers.

The results of the scale testing were extrapolated by a two-phase flow analysis to determine the characteristics of the pressure fluctuations acting on the partition wall of a full size cell in steam-

water conditions. This extrapolation included the use of a 1/12 and full scale analytical model. The resulting peak-to-peak pressure fluctuation was determined to be 15 kPa at a peak frequency of approximately 2 Hz.

A structural analysis of the chimney and partition design was then conducted using finite element methods. First, an eigenvalue analysis determined that the lowest natural frequency of the chimney structure is approximately 56 Hz. This was sufficiently greater than the predominant frequency of pressure fluctuation determined by testing (2 Hz) that a static analysis of the structure was concluded to be proper. Based on the results of that static analysis, a maximum stress of 41 MPa was calculated near the edge of the partition plate joint. This stress value is bounded by the allowable vibration peak stress amplitude of 68.9 MPa specified in Subsection 3.9.2.3.

3L.4 STEAM DRYER EVALUATION PROGRAM

3L.4.1 Steam Dryer Design and Performance

The ESBWR steam dryer will be designed using modules of dryer vanes enclosed in a housing to make up the steam dryer assembly. The modules or subassemblies of dryer vanes, called dryer units, will be arranged in six parallel rows called banks. The dryer banks will be attached to an upper support ring, which is supported by steam dryer support brackets that are welded attachments to the reactor pressure vessel (RPV). The steam dryer assembly will not physically connect to the shroud head and steam separator assembly and will have no direct connection with the core support or shroud. A cylindrical skirt will attach to the upper support ring and will project downward to form a water seal around the array of steam separators. Normal operating water level will be approximately mid-height on the dryer skirt.

Wet steam from the core will flow upward from the steam separators into an inlet header, horizontally through the dryer vanes, the outlet side perforated plates, vertically in the outlet header and out into the RPV dome. Dry steam will then exit the RPV through the steam outlet nozzles. Moisture (liquid) will be separated from the steam by the vane surface and the hooks attached to the vanes. The captured moisture will flow downward, under the force of gravity, to a collection trough that carries the liquid flow to vertical drain channels. The liquid will flow by gravity through the vertical drain channels to the lower end of the skirt where the flow will then exist below normal water level. Table 3L-1 provides a comparison between major configuration parameters of the ESBWR and an ABWR steam dryer.

During normal refueling outages, the ESBWR steam dryer will be supported from the floor of the equipment pool by the lower support ring that is located at the bottom edge of the skirt. The steam dryer will be installed and removed from the RPV by the reactor building overhead crane. A steam separator and dryer lifting device, which attaches to four steam dryer lifting rod eyes, will be used for lifting the dryer. Guide rods in the RPV will be used to aid dryer installation and removal. Upper and lower guides on the dryer assembly will be used to interface with the guide rods. The ESBWR steam dryer assembly is shown in Figure 3L-2.

3L.4.2 Materials and Fabrication

Current industry practice will be applied to the materials and fabrication of the ESBWR steam dryer. The steam dryer materials are selected to be resistant to corrosion and stress corrosion cracking in the BWR steam/water environment. New industry dryers are currently constructed from wrought 300 series stainless steel and Grade CF3 stainless steel castings. Except for the dryer vane material, the maximum carbon content of the wrought stainless steel will be limited to 0.02% and the maximum hardness of wrought 300 series stainless steel will be limited to Rockwell B92. Fabrication process controls are applied to minimize the degradation of material properties by forming, cold working, etc. Susceptibility to stress corrosion cracking will be avoided by careful control of the solution heat treatment, sensitization testing and testing for intergranular attack (IGA).

3L.4.3 Load Combinations

Design loads for the steam dryer will be based on evaluation of the ASME load combinations provided in Table 3.9-2 except that the load definitions that pertain to the steam dryer are

modified as shown in Table 3L-2. These load combinations consist of dryer deadweight loads, static and fluctuating differential pressure loads (including turbulent and acoustic sources), seismic, thermal, and transient acoustic and fluid impact loads.

3L.4.4 Fluid Loads on the Dryer

During normal operation, the dryer experiences a static differential pressure loading across the dryer plates resulting from the pressure drop of the steam flow across the vane banks. The dryer also experiences fluctuating pressure loads resulting from turbulent flow across the dryer and acoustic sources in the vessel and main steamlines. During transient and accident events, the dryer may also experience acoustic and flow impact loads that result from system actions (e.g., turbine stop valve closure) or from the system response (e.g., the two-phase level swell following a main steamline break).

Of particular interest are the fluctuating pressure loads that act on the dryer during normal operation that has led to fatigue damage in previous dryer designs. Scale model testing has identified the likely sources of fluctuating pressure loading acting on the steam dryer. The results of this testing showed that the fluctuating pressure load frequency spectrum can be divided into four regions based on the postulated source of the loading:

- **0-10 Hz:** The pressure loads in this frequency range are dominated by the fundamental main steamline piping acoustics. The source of these pressure loads is believed to be turbulence in the main steamline or vortex shedding in steam dome.
- **10-30 Hz:** The source of the pressure loads in this frequency range is postulated to be a stationary vortex on the outer hood of the steam dryer adjacent to the vessel outlet nozzles. The frequency characteristics of this pressure loading may be governed by harmonics of the main steamline acoustics.
- **>30 Hz:** The lowest steam plenum acoustic modes are located in this frequency range. The dominant excitation is due to broadband turbulent sources located in main steamlines but the acoustic modes may also be excited by sources in the vessel. The plenum acoustic modes have a very high amplification effect on pressure oscillations in this frequency range. The lower frequency vessel acoustic modes exhibit the most significant response to the turbulent excitation present in the system. Higher frequency vessel acoustics exist but are not significantly excited except as discussed below.
- **120-200 Hz:** Strong narrow band pressure loads in this frequency range are caused by acoustic resonances in safety and relief valve branch lines attached to the main steamlines. Higher frequency steam plenum acoustic modes can be excited if the vessel is acoustically coupled to the branch line. The ESBWR SRV standpipe design is intended to reduce or eliminate acoustic resonances in these branch lines.

The steam dryer acoustic load definition process consists of three primary elements:

- Scale model testing (physical testing using an ESBWR scale model to acquire load definition data, pressure and frequency, monitored by approximately 60 transducers),
- Acoustic finite element modeling of the reactor steam dome region to determine the natural frequencies and mode shapes of the steam volume, and

- A load interpolation algorithm to refine the measured fluctuating load into a fine mesh consistent with the structural finite element model nodalization in order to perform an accurate stress analysis of the dryer.

Flow induced turbulent and acoustic loads for the design of the ESBWR steam dryer will be determined from scale model testing of the dryer design and resultant acoustic modeling performed in the GE scale model testing facility located at the Vallecitos Nuclear Center in Sunol, California. The scale model test apparatus models the outside surface of the steam dryer above the vessel water level, the vessel steam dome region, and the main steamline piping to the turbine inlet, including major branch lines (e.g., SRV standpipes, turbine bypass piping). The testing is performed in ambient air conditions. Because the fluctuating pressure loads are primarily acoustic in nature, the test results are scaled to reactor conditions while preserving an equivalent Mach number between the model and the plant. GE has recently completed a power ascension test program with an instrumented BWR 3 steam dryer. The scale model test has been benchmarked against the plant data acquired from this instrumented dryer and confirms the capability of the GE scale model test methodology to predict the steam dryer acoustic load definitions.

The acoustic finite element modeling models the steam dryer and reactor steam dome cavity. This model is used to predict the acoustic mode shapes of the cavity and provides the framework for the load interpolation algorithm.

The load interpolation algorithm is used to provide a fine mesh load definition for input to the dynamic structural analysis. The algorithm uses the acoustic normal modes of the RPV steam plenum as a basis to describe the domain of interest. The algorithm uses the test measurements taken from the approximately 60 transducer locations on the scale model test and the acoustic finite element model to develop a fine-mesh array of pressure time histories that are consistent with the structural finite element model nodalization.

3L.4.5 Structural Evaluation

A finite element analysis (FEA) will be performed to confirm that the ESBWR steam dryer is structurally acceptable for operation. The FEA will use the scale model test loads as input. The finite element analysis will be performed using a whole dryer analysis model of the ESBWR steam dryer to determine the most highly stressed locations. The FEA consists of time history dynamic analyses for the load combinations identified in Table 3.9-2. If required, locations of high stress identified in the whole dryer analysis will be further evaluated using solid finite element models to more accurately predict stresses at these locations. The analysis will also confirm that the RPV dryer support lugs will accommodate the predicted dryer loads under normal operation and transient and accident conditions. (Also see 3.L.5.5.1.5.)

The structural evaluation of the ESBWR steam dryer design will be presented during the certification phase.

3L.4.6 Instrumentation and Startup Testing

The ESBWR steam dryer will be instrumented with temporary vibration sensors to obtain flow induced vibration data during power operation. The primary function of this vibration measurement program is to confirm the actual pressure loading on the dryer during power operation is consistent with the pressure loading assumed in the structural fatigue evaluation

and to verify that the new steam dryer can adequately withstand flow induced vibration forces for extended period as designed. The detailed objectives are as follows:

- Determine the dryer as-built modal parameters: This will be achieved by impact (hammer) testing the dryer components. The results will yield natural frequencies, mode shapes and damping of the dryer components for the as-built dryer. These results will be used to verify portions of the analytical model of the dryer.
- Confirm the pressure loading: In order to confirm the pressure loading on the dryer due to turbulence, acoustics and other sources, dynamic pressure sensors will be installed on the dryer. These measurements will provide the actual pressure loading on the dryer under various operating conditions.
- Verify the new dryer design: Based on past knowledge gained from different dryers, as well as information gleaned from analysis of the new dryer design, selected areas of the dryer will be instrumented with strain gages and accelerometers to measure vibratory stresses and displacements on the dryer during power operation. The measured strain values will be compared with the allowable values (acceptance criteria) obtained from the analytical model to confirm that the dryer alternating stresses are within allowable limits.

The steam dryer vibration sensors will consist of strain gauges, accelerometers and dynamic pressure sensors, appropriate for the application and environment. A typical list of vibration sensors with their model numbers is provided in Table 3L-3. The selection and total number of sensors will be based on past experience of similar tests conducted on other BWR steam dryers. These sensors will be specifically designed to withstand the reactor environment.

Each of the sensors will be pressure tested in an autoclave prior to assembly and installation on the dryer. An uncertainty analysis will be performed to calculate the expected uncertainty in the measurements.

Prior to initial plant start-up, strain gauges will be resistance spot-welded directly to the dryer surface. Accelerometers will be tack welded to pads that are permanently welded to the dryer surface. Surface mounted pressure sensors will be welded underneath a specially designed dome cover plate to minimize flow disturbances that may affect the measurement. The dome cover plate with the pressure transducer will be welded to an annular pad that is welded permanently to the dryer surface. The sensor conduits will be routed along a mast on the top of the dryer and fed through the RPV instrument nozzle flange to bring the sensor leads out of the pressure boundary. Sensor leads will be routed through the drywell to the data acquisition area outside the primary containment.

Pressure transducers and accelerometers are typically piezoelectric devices, requiring remote charge converters that will be located in junction boxes inside the drywell. The data acquisition system will consist of strain gauges, pressure transducers and accelerometer signal conditioning electronics, a multi-channel data analyzer and a data recorder. The vibration data from all sensors will be recorded on magnetic or optical media for post processing and data archival. The strain gauges, accelerometer and pressure transducers will be field calibrated prior to data collection and analysis. The temporary vibration sensors will be removed after the first outage.

During power ascension, the steam dryer instrumentation (strain gages, accelerometers and dynamic pressure transducers) will be monitored against established limits to assure the

structural integrity of the dryer is maintained. If resonant frequencies are identified and increase above the predetermined criteria, power ascension will stop. The acceptability of the dryer for the measured loading will be evaluated and revised operating limits defined as required.

Future steam dryer inspections will be in accordance with Reference 3L-2, and in accordance with Boiling Water Reactor Vessel Internals Program (BWRVIP) guidance.

3L.5 STARTUP TEST PROGRAM

This section summarizes the program for preparing and performing the startup FIV testing including the methods and analysis that will be performed when the startup test data is available. This section assumes that the initial selection of components identified in Subsection 3L.2.1 will be part of the analysis and instrumentation associated with the startup testing program.

3L.5.1 Component Selections

The components that are selected for instrumentation are determined from the initial evaluation phase as discussed in Subsection 3L.2.1. Many different sensors of four different types are utilized to measure vibration related data on several different reactor internal component structures.

3L.5.2 Sensor Locations

Having determined the components to instrument during the test, sensor locations on those structures are determined based upon the analytically predicted mode shapes for each structure or, in some cases, based upon the location of past FIV-related failures. Strain gages, accelerometers and linear variable differential transformer (LVDT) type relative displacement sensors are used for monitoring vibration levels. Strain gages measure local strain from which local stress can be calculated. Based on knowledge of the natural mode shapes of the structure, peak stresses at other locations on the structure are determined from these data. Accelerometers (with double integration of the output signal) and LVDTs provide measurements of local structural displacement. This information, together with knowledge of the natural mode shapes of the structure, allows the peak stresses to be calculated at other locations. Pressure sensors are also utilized at various locations in the vessel. These are not used to measure structural vibration directly, but rather to measure the pressure variation that is often a forcing function that causes the structural vibration. These pressure sensor data are very useful for determining the source of any excessive vibration amplitudes, if they are to occur during testing. Typical sensor types and potential locations are listed in Table 3L-4.

3L.5.3 Test Conditions

Test conditions are selected early in the FIV test program to consider a variety of steady-state and transient operating conditions that could be expected to occur during the life of the plant.

Reactor pressure vessel (RPV) internals vibration at steady-state conditions is more important than transient conditions for evaluating the structural integrity of components. This is because steady-state normal operating conditions can exist for long periods of time, allowing a very large number of vibration cycles to accumulate. Flow-induced vibration caused by transient operating conditions is far less influential because of the relatively low number of vibration cycles that will occur over the lifetime of the plant. The purpose in including transient test conditions is to confirm that extremely high stresses do not occur during transients. This check is accomplished during the actual startup transient tests by the vibration engineers monitoring the test equipment. Transient stress levels near the allowable limit would be easily and immediately detected by the vibration engineers. No such high stress levels are expected to occur during the ESBWR prototype plant FIV transient tests. Therefore, for the purposes of confirming the structural

capability of the internals, steady-state test conditions are the most important conditions to evaluate.

Total volumetric core flow rate is also an important parameter that affects the vibration magnitude of the internals. Vibration amplitude generally increases as the volumetric flow rate increases.

3L.5.4 Data Reduction Methods

Basically, two types of data reduction are performed: (1) time history analyses and (2) spectrum analyses. In either data reduction method, the measured peak-to-peak (p-p) value of each sensor signal is compared to the allowable p-p value. Even though both time history and spectrum analyses are performed for each selected sensor and test condition, the results from only one data reduction method are used for comparison to the allowable values. The selection of the method is dependent on the analysis method used for data evaluation. The different methods of data evaluation are described in detail in Section 3L.5.5. Briefly, Method I is used for components that have many closely spaced natural vibration modes and utilizes the strain energy weighting method applied to all modes over the frequency range of interest. This method has previously been applied to the In-core Monitor (ICM) housings, shroud, top guide, and steam dryer skirt and support ring. Method II is similar to Method I, except that it is applied to two frequency bands, 0-100 Hz and 100-200 Hz. This method has previously been applied to the steam dryer drain channels and hood. Method III is used for components that have relatively few, distinct dominant natural modes that are matched to the analytical modes. This method has previously been applied to the in-core guide tubes. Table 3L-5 describes the method of data reduction that is applicable to each component.

3L.5.4.1 Time History Analysis

The time history method uses the analyzer's time capture mode of operation. The time capture is performed for a period of several minutes for all the selected sensors and test conditions. The frequency bandwidth for the time capture is chosen to accommodate 0-200 Hz as a minimum for most channels.

For comparison to the allowable vibration amplitude, the measured peak-to-peak (p-p) value over specified bandwidths needs to be obtained for sensors in specific components. The bandwidths used for p-p measurements for various components are shown in Table 3L-5. There are four bandwidths for time history p-p measurement: 0-200 Hz, 0-100 Hz, 100-200 Hz and 0-1600 Hz. The 0-1600 Hz is used only for the accelerometer for the purpose of detecting impacts. The other three bandwidths are used for normal vibrations.

For the 0-200 Hz bandwidth, the maximum p-p values over several minutes of data for selected sensors and test conditions are obtained directly from the time capture. Specification of the bandwidth for time capture (0-200 Hz) automatically results in a low-pass filtered signal.

In order to obtain the maximum p-p in the 0-100 Hz range, the histogram operation is employed on the time capture traces. When the bandwidth (0-100 Hz) is specified in the histogram operation, the signal is automatically low-pass filtered in the specified frequency range. The histogram measurement shows how the amplitude of the input signal is distributed between its maximum and minimum values. The horizontal axis is the amplitude axis and usually the center of the horizontal axis is the zero point with positive and negative amplitudes on either side of the

zero. The vertical axis is the number of counts or the number of times a particular amplitude value occurs in a time-history. From the histogram, the maximum positive and maximum negative values in a time history can be obtained, from which the maximum p-p of the time history can be obtained.

For the 100-200 Hz bandwidth range, the time captured traces are filtered in the 100-200 Hz range and the p-p is obtained over a period of several minutes. The filtered time history between 100 and 200 Hz is scanned to obtain maximum and minimum values to get p-p values.

For the 0-1600 Hz range for accelerometers, the time history signal is examined for the presence of any impacts.

3L.5.4.2 Frequency Analysis

The spectrum shows the signal in the frequency domain. There are several different types of spectra. The linear spectrum is the Fourier transform of the time history signal. The auto power spectrum is the magnitude squared of the linear spectrum, which is computed by multiplying the Fourier transform of the signal by its complex conjugate. This spectrum contains magnitude information only. The spectra generated for ESBWR data reduction are auto power spectra. The spectra for selected sensors and test conditions are obtained from the captured time history described previously.

Signal averaging is used to obtain better statistical properties. It is possible to select the number of averages and the type of averaging. There are three types of averaging:

- Stable (normal)
- Exponential
- Peak Hold

The averaging method used for ESBWR is “Peak Hold”, which compares the current spectral value of each individual frequency during the analysis interval to the last spectral value and holds the larger of the two. The resultant spectrum is a composite spectrum which envelopes the spectrums of all analysis intervals. The parameters used in the spectrum generation are described in Table 3L-6.

In order to obtain greater accuracy on amplitude of the frequency spectrum, a flat top window is selected.

From the spectrum, the dominant frequencies of vibration and their root mean square (RMS) magnitudes can be identified. The frequency is in the horizontal axis and the RMS magnitude is in the vertical axis. The p-p value of vibration at each dominant frequency is obtained by multiplying the RMS value (from the peak hold spectrum) by a factor of 6. This factor is obtained from many years of reactor experience and is a conservative estimate of the p-p value. This p-p value is then used to compute the stress at the sensor location and the maximum stress in the structure.

3L.5.5 Data Evaluation Methods

This section describes the methods used to evaluate the reduced test data for the purpose of determining whether maximum stress levels are below the maximum allowable fatigue stress

limits for the materials. A significant portion of this evaluation lies in the determination of the natural vibration modes of the instrumented components as determined using finite element models. Subsection 3L.5.5.1 describes the finite element models used in this process. Subsection 3L.5.5.2 describes the steps involved in determining the maximum stress amplitudes from the reduced data.

3L.5.5.1 Finite Element Models

Dynamic analytical finite-element models are developed for the following ESBWR prototype plant reactor internal components:

- Chimney Head and Steam Separators
- Shroud and Chimney
- Steam Dryer
- Standby Liquid Control Line

The dynamic analytical finite-element models are used to predict the natural vibration frequency, modal displacement, and modal strain and stress for each of the dominant vibration response modes. Descriptions of the finite-element models are given in the following sections.

3L.5.5.1.1 Chimney Head and Steam Separators

In order to determine the chimney head and steam separator vibration frequencies and mode shapes, an axisymmetric model is developed using the ANSYS computer code (Reference 3L-3) or equivalent qualified program. The detailed model consists of the components that provide structural members within the assembly. Since the separator assembly units are the standard product used on prior BWR product lines, and that operates within the range of the design steam flow rates, detailed modeling is not required. In this model, each nodal point has four degrees of freedom, namely:

- radial displacement;
- tangential displacement;
- vertical displacement; and
- meridian rotation.

3L.5.5.1.2 Shroud and Chimney

In order to determine the shroud vibration frequencies and mode shapes, an axisymmetric shell model is developed using the ANSYS computer code (Reference 3L-3) or equivalent qualified program. The detailed shell model consists of both the reactor pressure vessel (RPV), chimney, chimney support, and shroud such that the hydrodynamic interaction effects between the components are accounted for. In this model, each nodal point has four degrees of freedom, namely:

- radial displacement;
- tangential displacement;

- vertical displacement; and
- meridian rotation.

This shell model is applicable only to the axisymmetric finite element analysis of the shroud and vessel. Responses calculated from this model, other than that of the shroud, shall not be construed as being representative of other reactor components.

The following assumptions are made in generating the axisymmetric shell model:

- (1) Discrete components move in unison for guide tubes, steam separators, standpipes, and control rod drive housings and guide tubes.
- (2) Masses are lumped at the nodal points. Rotational inertias of the masses are neglected.
- (3) Stiffnesses of control rods, control rod drives, steam dryers, and incore housings are neglected.
- (4) Top guide beam and core plate are assumed to have zero rotational stiffness.
- (5) Masses of CRD housings below the vessel are lumped to the bottom head.

Equivalent shells are used to model the mass and stiffness characteristics of the guide tubes, steam separators, and standpipes such that they match the frequencies obtained from a horizontal beam model.

Diagonal hydrodynamic mass terms are selected such that the beam mode frequencies of the shell model agree with those from the beam model.

The RPV, chimney and shroud are modeled as thin shell elements. Discrete components such as guide tubes are modeled as equivalent thin shell elements. The shell element data are defined in terms of thickness, mass density, modulus of elasticity, and Poisson's ratio for the appropriate material and temperature.

The natural frequencies and mode shapes of the shroud shell model are given in terms of two parameters, termed "n" and "m". The "n" parameter refers to the number of circumferential waves, while the "m" parameter refers to the number of axial half-waves. Thus, for beam types of 1 vibration, n=1.

3L.5.5.1.3 Steam Dryer

The design of the steam dryer assembly for the ESBWR prototype plant is somewhat different from the past BWR designs. Specifically, the major differences are in:

- (1) the skirt and support ring diameters;
- (2) the annulus size between the skirt and reactor pressure vessel;
- (3) the flow path between the dryer banks and the vessel head; and
- (4) the design details of the dryer skirt, drain channels and hoods.

In addition, the total steam flow rate of the ESBWR prototype plant is different from past designs. These differences warrant a detailed vibration analysis and test monitoring to assure the adequacy of the new design to withstand the flow-induced vibration.

In the ESBWR prototype plant FIV test program of the dryer assembly, accelerometers and strain gages are located directly on the skirt, drain channels, support ring and hoods. In addition, pressure sensors are used to measure the pressure differentials between the inside and outside of the dryer hood and dryer skirt. The differential pressure fluctuation across the dryer hoods is the primary forcing function causing vibration of the upper part of the dryer structure. The differential pressure fluctuation across the dryer skirt is the primary forcing function causing the vibration of the steam dryer skirt.

A dynamic finite element model of the dryer assembly is developed using the ANSYS computer code (Reference 3L-3). Due to the complicated geometry and the large size of the analytical model, major components may be modeled with coarse meshes such that their dynamic contributions are accounted for in the whole dryer assembly vibration responses. Separate refined dynamic finite element models of the major components are then developed to provide a high resolution of the component's response calculation.

The structural material properties and density for the dryer components at temperature are used in the model. The effect of the water on the dynamic responses is accounted for by using a direct lumped mass input. These added mass inputs include the submerged portions of the dryer skirt, drain channels, and the lower support ring.

Prior analytical models have predicted that the vibration modes are very closely spaced.

3L.5.5.1.4 Standby Liquid Control Lines

In the ESBWR prototype plant reactor, there are two standby liquid control pipes that enter the reactor vessel and are routed to the shroud. To accurately predict the vibration characteristic of the standby liquid control line, a dynamic finite element model of the entire line is developed using the ANSYS computer code. In the model the ends of the line are fixed anchor points since the lines are welded at the vessel nozzle and the shroud attachment points.

3L.5.5.2 Stress Evaluation

Maximum stress amplitude values for evaluation against allowable limits are determined from the test data and finite element models using one of three different evaluation methods. The method used for a particular component depends on the complexity of that component's vibration characteristics. All three methods yield conservatively high predictions of the maximum stress anywhere on the structure. These conservatively high stress predictions are compared against conservatively low acceptance criteria to assure that none of the components is experiencing high stress vibrations that might cause fatigue failures. Table 3L-7 lists the methods that are used for each instrumented component for the ESBWR prototype plant FIV test program.

Method I is used for components that have many closely spaced vibration frequencies and/or closely spaced natural vibration modes distributed over a relatively narrow frequency range. The method utilizes a strain energy weighting method applied to all modes over the entire frequency range. It is applied by determining the maximum peak-to-peak (p-p) amplitude from an unfiltered time history segment. This maximum value is multiplied by a combined shape factor (derived from the strain energy weighting method) and stress concentration factors to yield the maximum stress value that could be expected to be found anywhere on the structure. This value

is then compared against the acceptable fatigue limit stress amplitude for the material [68.9 MPa (10,000 psi)].

Method II is used for components that have many closely spaced vibration frequencies and/or closely spaced natural vibration modes that are unevenly distributed over several frequency ranges. The method is very similar to Method I, except that it is applied over several separate frequency bands. The maximum stress amplitude values for each frequency band are then added together absolutely to yield a conservatively high value for the overall maximum stress amplitude that could be found anywhere on the structure. This value is compared to the same [68.9 MPa (10,000 psi)] limit for the material.

Method III is used for components that have relatively few, distinct dominant natural modes that can be easily identified and matched to the modes predicted by the finite element models. This method utilizes a mode shape factor for each vibration mode that relates the stress at the sensor location to the stress at the maximum stress location for that mode. Appropriate stress concentration factors are also considered in this process. Response spectra are generated from the sensor output, from which the equivalent maximum p-p strain amplitude for each mode can be determined. The mode shape and stress concentration factors are applied mode by mode to determine the maximum stress amplitude associated with each mode. Then the maximum stress amplitudes from each of the modes are added together absolutely to yield a conservatively high maximum overall stress amplitude for the structure. This value is compared to the same [68.9 MPa (10,000 psi)] limits allowed for the material.

All three methods have identical initial steps to obtain mode shape factors for each natural mode. The first five steps for all three methods are as follows (Note: The evaluation method described here relates to strain gages. Similar steps are used for accelerometers used in their displacement mode and for LVDTs.):

- (1) The dynamic finite element model of each instrumented component is used to predict the natural vibration modal displacement, frequency and stress for each vibration response mode. Specifically, the computer model provides the following results for each mode:

ω_i = Natural frequency for vibration mode i

$\{\phi\}_i$ = Mass normalized displacement mode shape for vibration mode i .

(Normalized such that the generalized mass, $\{\phi\}_i^T [M] \{\phi\}_i$, is unity, where $[M]$ is the mass matrix.)

$\{\sigma\}_i$ = Normalized stress distribution for vibration mode i .

(The stress corresponding to the mass normalized mode shape, $\{\phi\}_i$)

The theory and methods for calculation of these parameters may be found in text books on the subject of basic vibration analysis, such as Reference 3L-4.

- (2) For each vibration mode, stress concentration factors are applied at weld locations and regions with high stress gradient. From this information, the maximum stress intensity location and value is determined for each vibration mode.

$\sigma_{i,\max} = \text{Max}\{SCF_i \cdot \sigma_i\}$ considered over the entire structure

where

- SCF_i = Stress concentration factor at some location
 σ_i = Normalized stress intensity at the same location
 $\sigma_{i,max}$ = Normalized maximum stress intensity for mode i

- (3) From the stress distribution of Step 1, a mode shape factor is derived relating the stress at the sensor to the stress at the maximum stress location as determined in Step 2:

$$MSF_i = \frac{\sigma_i(\text{at maximum stress intensity location})}{\sigma_{i,sensor}}$$

where

- MSF_i = Mode shape factor
 $\sigma_{i,sensor}$ = Normalized stress at sensor location for vibration mode i

- (4) The mode shape factor from Step 3 and the maximum allowable stress amplitude for the material [68.9 MPa (10,000 psi)] are used to determine the maximum allowable stress value at the sensor location for each mode.

$$\sigma_{i,sensor,allowed} = \frac{68.9 \text{ MPa}}{(MSF_i) \cdot (SCF_i)}$$

where

- $\sigma_{i,sensor,allowed}$ = Maximum allowed zero to peak stress amplitude at sensor location for vibration mode i (stress amplitude at sensor when maximum stress amplitude in structure is 68.9 MPa)

- (5) The allowable strain for mode i ($\epsilon_{i,allowed}$) is then calculated from this maximum allowed stress amplitude at the sensor location:

$$\epsilon_{i,allowed} = \frac{\sigma_{i,sensor,allowed}}{E}$$

where

- E = Young's modulus [e.g., 1.862 x 10⁵ MPa (27.0 x 10⁶ psi) at 160°C]

This equation is for uniaxial stress components. A similar, but more complex procedure will be used for biaxial stress structures such as the dryer skirt, drain channel and hood.

At this point, Methods I and II diverge from Method III.

3L.5.5.2.1 Methods I and II

The next two steps are identical for Methods I and II.

- (6) A weighting factor is determined by the strain energy method, which begins by obtaining the solution to the following equation based on the expected forcing function:

$$\{U\} = q_1 \{\phi\}_1 + q_2 \{\phi\}_2 + \dots = \sum_{i=1}^N q_i \{\phi\}_i$$

where

$\{U\}$ = A vector representing the displacement response of the structure when subjected to the expected forcing function shape. This displacement response to an input forcing function is calculated from the finite element model on the computer.

$\{\phi\}_i$ = Mass normalized mode shape for vibration mode i . Mode shapes were determined from the modal analysis of the finite element model on the computer. The modes shapes are normalized such that the generalized mass, $\{\phi\}_i^T [M] \{\phi\}_i$, is unity (where $[M]$ is the mass matrix).

q_i = Mode i response, dependent on load distribution. These coefficients are calculated from the previously calculated $\{U\}$ and $\{\phi\}_i$ using formulas derived from the generalized Fourier Theorem.

This is an application of the generalized Fourier Theorem, which establishes that a displacement function such as $\{U\}$ can be represented by a linear sum of the eigenfunctions, $\{\phi\}_i$. The theory and methods for calculation of these coefficients may be found in any good text book on the subject of basic vibration analysis, such as Reference 3L-4.

(7) The strain energy contribution, e_i , for each mode is then calculated:

$$e_i = \frac{1}{2} \cdot q_i^2 \cdot \{\phi\}_i^T \cdot [K] \cdot \{\phi\}_i$$

where

$[K]$ = The structural stiffness matrix (For a more detailed explanation of the theory and calculation methods, see any good vibration analysis textbook, such as Reference 3L-4.)

The next step is similar for both Methods I and II, the only difference being that Method I will include the entire frequency range into one group, while Method II will break into several frequency ranges.

(8) Then the strain energy weighted allowable strain vibration amplitude is calculated over a given frequency range by combining the weighted strain allowable values for each mode as follows:

For

$$\omega_I < \omega_1, \omega_2, \dots, \omega_n \leq \omega_{II}$$

$$\mathcal{E}_{II,allowed} = \frac{e_1 \cdot \mathcal{E}_{1,allowed} + e_2 \cdot \mathcal{E}_{2,allowed} + \dots + e_n \cdot \mathcal{E}_{n,allowed}}{e_1 + e_2 + \dots + e_n}$$

where

$$\varepsilon_{II,allowed} = \text{Allowable strain value between } \omega_I \text{ and } \omega_{II}, \text{ which includes the stress concentration factor, SCF}$$

It should be noted that this step conservatively assumes that the peak stress of each mode occurs at the same physical location on the structure. In reality, the maximum stress locations for different modes may occur at different locations. Since the purpose of this calculation is just to confirm that the maximum stress is less than an acceptable limit, it is quite acceptable to add this conservatism. However, it should be understood that the value calculated is conservatively high, and it is not an accurate prediction of the actual stress amplitude. If a stress calculated in this manner should exceed the limit in a few situations, then a less conservative calculation can be used in those few cases.

The strain value in the above equation is the allowable strain used during the actual execution of the test. It represents the strain level at the sensor location when the maximum stress on the structure is 68.9 MPa (10,000 psi).

Step 9 is the same for both Methods I and II, except that it is applied to each of the multiple frequency ranges associated with Method II; whereas, Method I is only for one frequency range.

- (9) The combined shape factor (CSF) is derived to relate the maximum zero-to-peak strain value measured at the sensor location to the corresponding maximum zero-to-peak stress intensity value on the structure.

$$\sigma_{II,max} = \frac{\varepsilon_{II,measured,max}}{\varepsilon_{II,allowed}} \cdot (68.9 \text{ MPa}) = \varepsilon_{II,measured,max} \cdot CSF$$

where

$$CSF = \frac{(68.9 \text{ MPa})}{\varepsilon_{II,allowed}} = \text{Combined Shape Factor with the SCF included.}$$

$\sigma_{II,max}$ = Maximum zero-to-peak stress value anywhere on the structure for modes within the frequency range of ω_I to ω_{II} .

$\varepsilon_{II,measured,max}$ = Maximum measured zero-to-peak strain (one-half of maximum measured peak-to-peak) from time history of sensor band pass filtered over the frequency range ω_I to ω_{II} .

This is the maximum zero-to-peak stress value anywhere on the structure as determined by Method I. For Method I, this value is compared to 68.9 MPa (10,000 psi) for determination of acceptability. One additional step remains for Method II.

- (10) The maximum stress values for each frequency band are added together absolutely to determine the overall maximum stress on the structure for comparison to the 68.9 MPa (10,000 psi) limit for the material.

$$\sigma_{MAX} = \sigma_{II,max} + \sigma_{III,max} + \dots + \sigma_{N,max}$$

where

σ_{MAX} = Maximum overall zero-to-peak stress anywhere on structure as determined by Method II.

$\sigma_{N,max}$ = Maximum zero-to-peak stress anywhere on structure within the frequency range of ω_{N-1} to ω_N (N-1 frequency ranges total).

σ_{MAX} is compared to the 68.9 MPa (10,000 psi) limit in order to determine acceptability under Method II.

It should be noted that this step conservatively assumes that the peak stress of each mode occurs at the same time. In reality, the maximum stress occurs at different times. Since the purpose of this calculation is just to confirm that the maximum stress is less than an acceptable limit, it is quite acceptable to add this conservatism. However, it should be understood that the value calculated is conservatively high, and it is not an accurate prediction of the actual stress amplitude. If a stress calculated in this manner should exceed the limit in a few situations, then a less conservative calculation can be used in those few cases.

3L.5.5.2.2 Method III

Method III uses the mode shape factor (MSF) from Step 3, the stress concentration factor (SCF) and the measured strain value to determine the maximum stress amplitude anywhere on the structure for each natural mode. Picking up after Step 5 from Section 3L.5.5.2:

- (6) Maximum stress in the structure is calculated from the measured strain value at the sensor location.

$$\sigma_{i,MAX} = \varepsilon_{i,measured,max} \cdot E \cdot MSF_i \cdot SCF_i$$

where

$\sigma_{i,MAX}$ = Maximum zero-to-peak stress anywhere on structure for mode i.

$\varepsilon_{i,measured,max}$ = Maximum zero-to-peak strain for mode i as determined from power spectrum from sensor signal.

E = Young's Modulus

MSF_i = Mode Shape Factor for mode i.

SCF_i = Stress Concentration Factor as applicable for maximum stress location for mode i.

- (7) The maximum stress values for each mode are added together absolutely to determine the overall maximum stress on the structure for comparison to the 68.9 MPa (10,000 psi) limit for the material.

$$\sigma_{MAX} = \sigma_{1,MAX} + \sigma_{2,MAX} + \dots + \sigma_{n,MAX}$$

where

σ_{MAX} = Maximum overall zero-to-peak stress anywhere on structure as determined by Method III.

$\sigma_{i,MAX}$ = Maximum zero-to-peak stress anywhere on structure for mode i (n total dominant modes).

σ_{MAX} is compared to the 68.9 MPa (10,000 psi) limit in order to determine acceptability under Method III.

It should be noted that this step conservatively assumes that the peak stress of each mode occurs at the same physical location on the structure and at the same time. In reality, the maximum stress locations for different modes may occur at different locations and at different times. Since the purpose of this calculation is just to confirm that the maximum stress is less than an acceptable limit, it is quite acceptable to add these conservatisms. However, it should be understood that the value calculated is conservatively high, and it is not an accurate prediction of the actual stress amplitude. If a stress calculated in this manner should exceed the limit in a few situations, then a less conservative calculation can be used in those few cases.

In summary, all three methods involve two significant conservatisms:

- The assumption of the maximum stresses occurring at the same location in a component, and
- The assumption that the maximum stresses for different modes occur at the same time.

Inclusion of these two significant conservatisms results in significantly higher calculated stresses.

3L.6 REFERENCES

- 3L-1 General Electric Company, “ESBWR Reactor Internals Flow Induced Vibration Program – Part 1”, NEDE-33259P, Class III (Proprietary), January 2006, and NEDO-33259, Class I (Non-proprietary), January 2006.
- 3L-2 General Electric Company, “BWR Steam Dryer Integrity”, SIL 644 Revision 1, November 9, 2004.
- 3L-3 *ANSYS Engineering Analysis System User’s Manual*, G.J. DeSalvo and R.W. Gorman, Swanson Analysis Systems, Inc., Houston, PA, Revision 4.4a, May 1989.
- 3L-4 *Elements of Vibration Analysis*, Leonard Meirovitch, McGraw Hill Book Co., 1975.

Table 3L-1

Comparison of Major Steam Dryer Configuration Parameters

| Steam Dryer Configuration Parameter | ESBWR Dryer | ABWR Dryer |
|--|---|--|
| Number of Banks | 6 | 6 |
| Active height (flow area) for vane modules | 1829 mm (65.6 m ²) | 1829 mm (56.6 m ²) |
| Approximate weight | 60,000 Kg | 50,000 Kg |
| Outside diameter of upper support ring | 6920 mm | 6630 mm |
| Overall height | 5700 mm | 5695 mm |
| Length of skirt | 2736 mm | 2731 mm |
| Skirt thickness | 9 mm | 7 mm |
| Cover plate thickness | 25.4 mm | 16 mm |
| Hood thickness | 25.4 mm (outer bank) 12.7 mm (inner banks) | 16 mm (outer bank) 8 mm (inner banks) |
| Upper support ring cross-section | 89 x 242 mm | 89 x 242 mm |
| Average steamline flow velocity | 49.7 m/s | 42.7 m/s |

**Table 3L-2
Specific Steam Dryer Load Definition Legend**

| | |
|------------|---|
| Normal (N) | Normal and/or abnormal loads associated with the system operating conditions, including thermal loads, depending on acceptance criteria. These include deadweight, static differential pressure, and fluctuating pressure loads. |
| TSV | Turbine stop valve closure induced loads in the main steam piping and components integral to or mounted thereon. For the dryer, these include acoustic and flow impact loads. Separate load cases will be evaluated for load components that are separated in time (e.g., acoustic impact and flow impact). |
| LOCA8 | Acoustic impact loads on the dryer due to a postulated steamline break. Separate load cases will be evaluated for load components that are separated in time (e.g., acoustic impact and level swell impact). |
| LOCA9 | Level swell impact loads on the dryer due to a postulated steamline break. Separate load cases will be evaluated for load components that are separated in time (e.g., acoustic impact and level swell impact). |

**Table 3L-3
Typical Vibration Sensors**

| Vibration sensor type | Typical sensor model |
|------------------------------|--|
| Strain gauge | Kyowa Model KHC-10-120-G9 |
| Accelerometer | Vibro-meter Model CA901 |
| Dynamic pressure transducer | Vibro-meter Model CP104 and/or Model CP211 |

Table 3L-4
Typical Sensor Locations and Types

| Equipment Item | Location on Equipment | Sensor Type | Location Basis |
|-----------------------------|--|---|---|
| Steam Dryer Support Ring | On top of dryer support | Accelerometer (Acceleration Mode) | Past experience of dryer rocking. |
| Steam Dryer Skirt | At bottom of dryer | Accelerometer (Displacement Mode) | Modal analysis. |
| Steam Dryer Hood | At edge of dryer bank hood and end plate. | Strain Gage Pressure Transducer | Past experience of cracks at weld & to obtain forcing function data if problem occurs |
| Steam Dryer Drain Channel | At top & bottom, side edge of dryer channels. | Strain Gage | Modal analysis. Past experience of cracks at weld. |
| Steam Dryer Skirt | At top & bottom of dryer skirt. | Strain Gage Pressure Transducer | Modal analysis & to obtain forcing function data if problem occurs |
| Shroud | On the outside diameter | Strain Gage | Modal analysis. |
| Top Guide | On the outside diameter of the top guide mounted to measure tangential & radial relative displacements between top guide and vessel. | Linear Variable Differential Transformer (LVDT) | Past experience to measure shroud motion. |
| Vessel Dome Region | On steam dryer FIV instrument post. | Pressure Transducer | To obtain forcing function data if problem occurs. |
| Vessel Annulus | On the vertical FIV mounting bar in the annulus between the shroud and vessel walls. | Pressure Transducer | To obtain forcing function data if problem occurs. |
| Standby Liquid Control Line | On the joints between the vertical and horizontal runs | Strain Gage | New design |

Table 3L-5

Applicable Data Reduction Method for Comparison to Criteria

| Component | Sensor Type | Applicable Data Reduction Method | | Frequency Bandwidth (Hz) |
|------------------------------|------------------|----------------------------------|--------------|--------------------------|
| | | | | |
| Shroud | Strain Gages | I | Time History | 0-100 |
| Steam Dryer Skirt | Strain Gages | I | Time History | 0-100 |
| Steam Dryer Drain Channels | Strain Gauges | II | Time History | 0-100, 100-200 |
| Steam Dryer Hoods | Strain Gages | II | Time History | 0-100, 100-200 |
| Steam Dryer Support Ring | Accelerometer | Impact | Time History | 0-1600 0-80, 80-200 |
| Top Guide | Displacement | I | Time History | 0-100 |
| Vessel Annulus | Pressure sensors | I | Time History | 0-200 |
| Standby Liquid Control Lines | Strain Gages | I | Time History | 0-200 |

Table 3L-6
Parameters Used in Spectrum Generation

| Parameter | Value |
|----------------------|--------------|
| Bandwidth | 0-200 Hz |
| Time length | 3 minutes |
| No. of Fourier Lines | 400 |
| Resolution | 0.5 Hz |
| Window | Flat Top |
| No. of averages | 90 |
| Overlap | 0% |
| Noise reduction | None |
| Average Type | Peak-hold |
| P-P Value | = RMS x 6 |

Table 3L-7
Data Evaluation Methods to be Used for Each Component

| Internal Component | Data Evaluation Method Used |
|-----------------------------|------------------------------------|
| Shroud and Chimney | I |
| Steam Dryer | I & II |
| Standby Liquid Control Line | I |




Figure 3L-1. Chimney and Partition Assembly




Figure 3L-2. ESBWR Steam Dryer Assembly